# FBISD BP013 KITCHEN RENOVATIONS ES




FORT BEND INDEPENDENT SCHOOL DISTRICT

## ADMINISTRATION

| | |
|---|---|
| DR. MARCELL SMITH | SUPERINTENDENT OF FBISD |
| DR. ANDRIA SCHUR, Ed.D. | CHIEF OF SCHOOLS |

## BOARD OF TRUSTEES

| | |
|---|---|
| KRISTIN K. TASSIN | PRESIDENT |
| RICK GARCIA | VICE PRESIDENT |
| DAVID HAMILTON | SECRETARY |
| ANGIE HANAN | BOARD MEMBER |
| ADAM SCHOOF | BOARD MEMBER |
| DR. SHIRLEY ROSE-GILLIAM | BOARD MEMBER |
| SONYA JONES | BOARD MEMBER |

## PROJECT DESIGN TEAM

PROGRAM MANAGEMENT
FBISD 2023 Bond Team
2323 Texas Parkway
Missouri City, TX 77489
Phone Number: 281-327-5481

ARCHITECT
MWA Architects
11767 Katy Freeway, Suite 430
Houston, Texas 77079
Phone Number: 713-782-8188

FOOD SERVICE
Food Design Professionals
26215 Oak Ridge Drive
The Woodlands, Texas 77380
Phone Number: 281-350-2323

MEP ENGINEERS
Stanton Engineering Group
1300 W. Sam Houston Pkwy South, Suite 121
Houston, Texas 77042
Phone Number: 713-300-9292

STRUCTURAL ENGINEER
Stanley Spurling & Hamilton
3301 Edloe Street, Suite 200
Houston, Texas 77027
Phone Number: 713-776-9433

ISSUED FOR BIDDING AND PERMITTING - JULY 18, 2025

## Sheet List Table

| Sheet Number | Sheet Title |
|---|---|
| **SHARED GENERAL NOTES AND DETAILS** | |
| A.0000 | FBISD BP013 OVERALL COVER SHEET |
| A.000 | OVERALL INDEX SHEET |
| **School: a Austin Pkwy ES** | |
| a-A.000 | COVER AND INDEX |
| a-A00-01 | GENERAL NOTES AND ABBREVIATIONS |
| a-D.101 | DEMO PLANS |
| a-D01-02 | DEMO PLAN PHOTOS |
| a-D01-03 | DEMO PLAN PHOTOS |
| a-ED.100 | LIGHTING DEMOLITION & TEMPORARY KITCHEN |
| A-PD1.01 | PLUMBING DEMOLITION FLOOR PLAN |
| a-A.101 | SITE PLAN |
| a-A.201 | FLOOR PLAN |
| a-TD201 | TECHNOLOGY DEMOLITION FLOOR PLAN |
| a-A.300 | SLAB DIMENSION CONTROL PLAN |
| a-A.301 | KITCHEN PLAN |
| a-A.302 | TEMPORARY KITCHEN LAYOUT |
| a-A.401 | REFLECTED CEILING PLAN |
| a-A.501 | FINISH FLOOR PLAN |
| a-A.502 | PARTITION SCHEDULE |
| a-S1 | KITCHEN PLAN |
| a-S2 | SECTIONS AND TYPICAL DETAILS |
| A-QF1 | FS GENERAL COORDINATION NOTES |
| A-QF1.0 | FS EQUIPMENT PLAN |
| A-QF1.1 | FS FACILITY MODEL |
| A-QF1.2 | FS EQUIPMENT MODEL |
| A-QF1.3 | FS SPECIAL CONDITIONS & MECHANICAL PLAN |
| A-QF1.4 | FS PLUMBING PLAN |
| A-QF1.5 | FS ELECTRICAL PLAN |
| A-QF1.6 | FS CONDENSING UNITS |
| a-QF1.7 | FS WALK-INS |
| a-QF2.0 | FS EQUIPMENT PLAN TEMPORARY SERVING AND MEP |
| a-QF3.1 | FS ELEVATIONS |
| a-QF4.1 | FS SECTIONS AND DETAILS |
| a-QF4.2 | FS DETAILS |
| a-QF4.3 | FS DETAILS |
| a-M1.01 | LEVEL 1 KITCHEN MECHANICAL PLANS |
| a-M2.01 | LEVEL 1 KITCHEN MECHANICAL PLANS |
| a-M2.02 | MECHANICAL DETAILS (CONT.) |
| a-E.000 | ELECTRICAL AND FIRE ALARM SCHEDULES |
| a-E.010 | ELECTRICAL DEVICE DETAILS |
| a-E.011 | ELECTRICAL DETAILS |
| a-E.012 | ELECTRICAL DETAILS |
| a-E.013 | ELECTRICAL KITCHEN DETAILS |
| a-E.060 | LIGHTING SCHEDULES |
| a-E.001 | ELECTRICAL AND FIRE ALARM NOTES |
| a-E.100 | ELECTRICAL PLANS |
| a-E.200 | ELECTRICAL FLOOR PLAN |
| a-E.300 | FIRE ALARM FLOOR PLANS |
| a-E.400 | ELECTRICAL SCHEMATIC |
| a-P0.01 | PLUMBING NOTES AND SCHEDULES |
| a-P0.02 | PLUMBING SCHEDULES AND DETAILS |
| a-P1.01 | PLUMBING FLOOR PLAN |
| a-P1.02 | PLUMBING TEMPORARY KITCHEN PLAN |
| a-T000 | TECHNOLOGY SYMBOLS & LEGEND |
| a-T200 | TECHNOLOGY COMPOSITE FLOOR PLAN |
| a-T201 | TECHNOLOGY NEW-RENOVATION KITCHEN PLAN |
| a-T202 | TECHNOLOGY TEMPORARY KITCHEN PLAN |
| a-T300 | TECHNOLOGY ENLARGED VIEWS |
| a-T400 | TECHNOLOGY TYPICAL DETAILS |
| a-T401 | TECHNOLOGY TYPICAL DETAILS |
| a-T500 | TECHNOLOGY TYPICAL DETAILS |
| a-TN.000 | TECHNOLOGY - INDEX SHEET |
| a-TN-001 | TECHNOLOGY - KITCHEN DEMOLITION |
| a-TN-100 | TECHNOLOGY - OVERALL |
| a-TN-101 | TECHNOLOGY - KITCHEN |
| a-TN-500 | TECHNOLOGY - DETAILS |
| a-TN-600 | TECHNOLOGY - SECURITY DETAILS |
| a-TN-700 | TECHNOLOGY - AV DETAILS |
| **School: b-Burton ES** | |
| b-A.000 | COVER AND INDEX |
| b-TN-000 | TECHNOLOGY - INDEX SHEET |
| b-TN-100 | TECHNOLOGY - OVERALL |
| b-TN-101 | TECHNOLOGY - KITCHEN |
| b-TN-500 | TECHNOLOGY - DETAILS |
| b-TN-600 | TECHNOLOGY - SECURITY DETAILS |
| **School: c-Colony Bend-ES** | |
| c-A.000 | COVER AND INDEX |
| c-TN.000 | TECHNOLOGY - INDEX SHEET |
| c-TN.100 | TECHNOLOGY - OVERALL |
| c-TN-101 | TECHNOLOGY - KITCHEN |
| c-TN-500 | TECHNOLOGY - DETAILS |
| c-TN-600 | TECHNOLOGY - SECURITY DETAILS |
| **School: d-Commonwealth ES** | |
| d-A.000 | COVER AND INDEX |
| d-A00-01 | GENERAL NOTES AND ABBREVIATIONS |
| d-D.101 | DEMO PLAN. DEMO RCP |
| d-A.201 | OVERALL FLOOR PLAN |
| d-A4.01 | CAFETERIA ENLARGED RCP & PLAN |
| d-E.200 | ELECTRICAL FLOOR PLAN AND SCHEDULES |
| d-TN-000 | INDEX SHEET |
| d-TN-100 | TECHNOLOGY - OVERALL |
| d-TN-101 | TECHNOLOGY - KITCHEN |
| d-TN-500 | TECHNOLOGY - DETAILS |
| d-TN-600 | TECHNOLOGY - SECURITY DETAILS |
| **School: e-Cornerstone ES** | |
| e-A.000 | COVER AND INDEX |
| e-A00-01 | GENERAL NOTES AND ABBREVIATIONS |
| e-D.101 | DEMO PLAN PHOTOS |
| e-A.201 | FLOOR PLAN |
| e-A.301 | STUDENT CAFETERIA AND GYM PLAN |
| e-A.501 | FINISH FLOOR PLAN |
| e-A.601 | INTERIOR ELEVATIONS |
| e-S1 | GYMNASIUM PLAN |
| e-S2 | SECTIONS AND TYPICAL DETAILS |
| e-E.200 | ELECTRICAL FLOOR PLAN & SCHEDULES |
| e-TN-000 | TECHNOLOGY - INDEX SHEET |

## Sheet List Table

| Sheet Number | Sheet Title |
|---|---|
| **SHARED GENERAL NOTES AND DETAILS** | |
| e-TN-100 | TECHNOLOGY - OVERALL |
| e-TN-101 | TECHNOLOGY - KITCHEN |
| e-TN-500 | TECHNOLOGY - DETAILS |
| e-TN-600 | TECHNOLOGY - SECURITY DETAILS |
| **School: f-Dulles ES** | |
| f-A.000 | COVER AND INDEX |
| f-A00-01 | GENERAL NOTES AND ABBREVIATIONS |
| f-D.101 | DEMO PLAN |
| f-A.101 | SITE PLAN |
| f-A.201 | OVERALL FLOOR PLAN |
| f-A.301 | KITCHEN FLOOR PLAN |
| f-QF1 | FS GENERAL COORDINATION NOTES |
| f-QF1.0 | FS EQUIPMENT ELECTRICAL PLAN |
| f-E.200 | ELECTRICAL FLOOR PLAN & SCHEDULES |
| f-TN.000 | TECHNOLOGY - INDEX SHEET |
| f-TN-100 | TECHNOLOGY - OVERALL |
| f-TN-101 | TECHNOLOGY - KITCHEN |
| f-TN-500 | TECHNOLOGY - DETAILS |
| f-TN-600 | TECHNOLOGY - SECURITY DETAILS |
| **School: g-Fleming ES** | |
| g-A.000 | COVER AND INDEX |
| g-TN-000 | TECHNOLOGY - INDEX SHEET |
| g-TN-100 | TECHNOLOGY - OVERALL |
| g-TN-101 | TECHNOLOGY - KITCHEN |
| g-TN-500 | TECHNOLOGY - DETAILS |
| g-TN-600 | TECHNOLOGY - SECURITY DETAILS |
| **School: h-GLOVER ES** | |
| h-A.000 | COVER AND INDEX |
| h-TN-000 | TECHNOLOGY - INDEX SHEET |
| h-TN-100 | TECHNOLOGY - OVERALL |
| h-TN-101 | TECHNOLOGY - KITCHEN |
| h-TN-500 | TECHNOLOGY - DETAILS |
| h-TN-600 | TECHNOLOGY - SECURITY DETAILS |
| **School: i-Heritage Rose ES** | |
| i-A.000 | COVER AND INDEX |
| i-A00-01 | GENERAL NOTES AND ABBREVIATIONS |
| i-A.201 | OVERALL FLOOR PLAN |
| i-A.301 | KITCHEN PLAN |
| i-P.101 | FILTER AND NEW WATER SOFTENER |
| **School: j Highlands ES** | |
| j-A.000 | COVER AND INDEX |
| j-A00-01 | GENERAL NOTES AND ABBREVIATIONS |
| j-D.101 | DEMO PLAN |
| j-D.101-2 | DEMO PLAN PHOTOS |
| j-D.101-3 | DEMO PLAN PHOTOS |
| j-ED.100 | ELECTRICAL DEMO AND TEMPORARY PLANS |
| j-PD.101 | PLUMBING DEMOLITION FLOOR PLAN |
| p-TD201 | TECHNOLOGY DEMOLITION FLOOR PLAN |
| j-A.101 | SITE PLAN |
| j-A.200 | SLAB DIMENSION CONTROL PLAN |
| j-A.201 | OVERALL FLOOR PLAN |
| j-A.301 | KITCHEN PLAN |
| j-A.302 | TEMPORARY KITCHEN LAYOUT |
| j-A.401 | REFLECTED CEILING PLAN |
| j-A.501 | FINISH FLOOR PLAN |
| j-A.502 | PARTITION SCHEDULE |
| j-C1.0 | GRADING AND SITE PLAN |
| j-QF1 | FS GENERAL COORDINATION NOTES |
| j-QF1.0 | FS EQUIPMENT PLAN |
| j-QF1.1 | FS FACILITY MODEL |
| j-QF1.2 | FS EQUIPMENT MODEL |
| j-QF1.3 | FS SPECIAL CONDITIONS & MECHANICAL PLAN |
| j-QF1.4 | FS PLUMBING PLAN |
| j-QF1.5 | FS ELECTRICAL PLAN |
| j-QF1.6 | FS CONDENSING UNITS |
| j-QF2.0 | FS TEMPORARY SERVING |
| j-M1.01 | MECHANICAL PLANS |
| M2.01 | LEVEL 1 KITCHEN MECHANICAL PLANS |
| E.000 | ELECTRICAL AND FIRE ALARM SCHEDULES |
| E.001 | ELECTRICAL AND FIRE ALARM NOTES |
| E.010 | ELECTRICAL DEVICE DETAILS |
| E.011 | ELECTRICAL DETAILS |
| E.012 | ELECTRICAL DETAILS |
| E.013 | ELECTRICAL KITCHEN DETAILS |
| E.060 | LIGHTING SCHEDULES |
| j-E100 | LIGHTING FLOOR PLAN |
| j-E200 | ELECTRICAL PLANS |
| j-E300 | FIRE ALARM FLOOR PLANS |
| j-E.400 | ELECTRICAL SCHEMATIC |
| j-P0.01 | PLUMBING NOTES AND SCHEDULES |
| j-P0.02 | PLUMBING SCHEDULES AND DETAILS |
| j-P1.01 | PLUMBING FLOOR PLAN |
| J-P1.02 | PLUMBING TEMPORARY KITCHEN PLAN |
| j-T000 | TECHNOLOGY SYMBOLS & LEGEND |
| j-T200 | TECHNOLOGY COMPOSITE FLOOR |
| j-T201 | TECHNOLOGY NEW_RENOVATION KITCHEN PLan |
| j-T202 | TECHNOLOGY TEMPORARY KITCHEN PLAN |
| j-T300 | TECHNOLOGY ENLARGED VIEWS |
| j-T400 | TECHNOLOGY TYPICAL DETAILS |
| j-T401 | TECHNOLOGY TYPICAL DETAILS |
| j-T500 | TECHNOLOGY TYPICAL LABELING SCHEME |
| j-TN-000 | TECHNOLOGY - INDEX SHEET |
| j-TN-001 | TECHNOLOGY - ELEVATIONS |
| j-TN-100 | TECHNOLOGY - OVERALL |
| j-TN-101 | TECHNOLOGY - KITCHEN |
| j-TN-500 | TECHNOLOGY - DETAILS |
| j-TN-600 | TECHNOLOGY - SECURITY DETAILS |
| J-TN-700 | TECHNOLOGY - AV DETAILS |
| **School: k-Hunters Glen ES** | |
| k-A.000 | COVER AND INDEX |
| k-A00-01 | GENERAL NOTES AND ABBREVIATIONS |
| k-D.101 | DEMO PLAN |
| k-D.101-2 | DEMO PLAN PHOTOS |
| k-D.101-3 | DEMO PLAN PHOTOS |
| k-QF1 | FS DEMO PLAN |

## Sheet List Table

| Sheet Number | Sheet Title |
|---|---|
| **SHARED GENERAL NOTES AND DETAILS** | |
| k-ED.100 | ELECTRICAL DEMOLITION AND TEMPORARY KITCHEN PLAN |
| k-PD1.01 | PLUMBING DEMOLITION FLOOR PLAN |
| k-TD201 | TECHNOLOGY DEMOLITION FLOOR PLAN |
| k-A.101 | SITE PLAN |
| k-A.201 | OVERALL FLOOR PLAN |
| k-A.300 | SLAB DIMENSION CONTROL PLAN |
| k-A.301 | KITCHEN PLAN |
| k-A.302 | TEMPORARY KITCHEN LAYOUT |
| k-A.401 | REFLECTED CEILING PLAN |
| k-A.501 | FINISH FLOOR PLAN |
| k-A.502 | PARTITION SCHEDULE |
| k C1.0 | GRADING AND PAVING PLAN |
| k-QF0.0 | FS GENERAL COORDINATION NOTES |
| k-QF1.0 | FS EQUIPMENT PLAN |
| k-QF1.1 | FS FACILITY MODEL |
| K-QF1.2 | FS EQUIPMENT MODEL |
| k-QF1.3 | FS SPECIAL CONDITIONS & MECHANICAL PLAN |
| k-QF1.4 | FS PLUMBING PLAN |
| k-QF1.5 | FS ELECTRICAL PLAN |
| k-QF1.6 | FS CONDENSING UNITS |
| k-QFS1.7 | FS WALK-INS |
| k-QF2.0 | FS TEMPORARY SERVING |
| k-QF3.1 | FS ELEVATIONS |
| k-QF4.1 | FS SECTIONS AND DETAILS |
| k-QF4.2 | FS DETAILS |
| k-QF4.3 | FS DETAILS |
| k-M1.01 | MECHANICAL PLANS |
| k-M2.01 | KITCHEN MECHANICAL DETAILS |
| k-M2.02 | MECHANICAL DETAILS (CONT.) |
| E.000 | ELECTRICAL AND FIRE ALARM SCHEDULES |
| E.001 | ELECTRICALAND FIRE ALARM NOTES |
| E.010 | ELECTRICAL DEVICE DETAILS |
| E.011 | ELECTRICAL DETAILS |
| E.012 | ELECTRICAL DETAILS |
| E.013 | ELECTRICAL KITCHEN DETAILS |
| E.060 | LIGHTING SCHEDULES |
| k-E.100 | LIGHTING FLOOR PLANS |
| k-E.200 | ELECTRICAL FLOOR PLANS |
| k-E.300 | FIRE ALARM FLOOR PLANS |
| k-E.400 | ELECTRICAL SCHEMATIC |
| k-P1.01 | PLUMBING FLOOR PLAN |
| k-P1.02 | PLUMBING TEMPORARY KITCHEN |
| k-T000 | TECHNOLOGY SYMBOLS & LEGEND |
| k-T200 | TECHNOLOGY COMPOSITE FLOOR |
| k-T201 | TECHNOLOGY NEW_RENOVATION KITCHEN PLAN |
| k-T300 | TECHNOLOGY TEMPORARY KITCHEN PLAN |
| k-T202 | TECHNOLOGY ENLARGED VIEWS |
| k-T400 | TECHNOLOGY TYPICAL DETAILS |
| k-T401 | TECHNOLOGY TYPICAL DETAILS |
| k-T500 | TECHNOLOGY TYPICAL DETAILS |
| k-TN-000 | TECHNOLOGY - INDEX SHEET |
| k-TN-001 | TECHNOLOGY - DEMO |
| k-TN-100 | TECHNOLOGY - OVERALL |
| k-TN-101 | TECHNOLOGY - KITCHEN |
| k-TN-500 | TECHNOLOGY - DETAILS |
| k-TN-600 | TTECHNOLOGY - SECURITY DETAILS |
| k-TN-700 | TECHNOLOGY - AV DETAILS |
| **School: l-Lantern Lane** | |
| l_A0.00 | COVER AND INDEX |
| l-A.101 | Site Plan |
| l-A.201 | Overall Floor Plan |
| l-A.301 | Kitchen Plan |
| l-A.501 | Finish Floor Plan |
| l-TN-000 | TECHNOLOGY - INDEX SHEET |
| l-TN-100 | TECHNOLOGY - OVERALL |
| l-TN-101 | TECHNOLOGY - KITCHEN |
| l-TN-500 | TECHNOLOGY - DETAILS |
| l-TN-600 | TECHNOLOGY - SECURITY DETAILS |
| **School: o-Palmer ES** | |
| o-A.000 | COVER AND INDEX |
| o-A00-01 | GENERAL NOTES AND ABBREVIATIONS |
| o-D.101 | DEMO PLAN |
| o-D.101-2 | DEMO PLAN PHOTOS |
| o-ED.100 | ELECTRICAL DEMOLITION AND TEMP PLANS |
| o-PD1.01 | PLUMBING DEMOLITION FLOOR PLAN |
| o-TD201 | TECHNOLOGY DEMOLITION FLOOR PLAN |
| o-A.101 | SITE PLAN |
| o-A.200 | SLAB DIMENSION CONTROL PLAN |
| o-A.201 | FLOOR PLAN |
| o-A.301 | KITCHEN PLAN |
| o-A.302 | TEMPORARY KITCHEN LAYOUT |
| o-A.401 | REFLECTED CEILING PLAN |
| o-A.501 | FINISH FLOOR PLAN |
| o-A.502 | PARTITION SCHEDULE |
| o-S1 | KITCHEN PLAN |
| o-S2 | SECTIONS AND TYPICAL DETAILS |
| o-QF1 | FS GENERAL COORDINATION NOTES |
| o-QF1.0 | FS EQUIPMENT PLAN |
| o-QF1.1 | FS FACILITY MODEL |
| o-QF1.2 | FS EQUIPMENT MODEL |
| o-QF1.3 | FS SPECIAL CONDITIONS & MECHANICAL PLAN |
| o-QF1.4 | FS PLUMBING PLAN |
| o-QF1.5 | FS ELECTRICAL PLAN |
| o-QF1.6 | FS CONDENSING UNITS |
| o-QF1.7 | FS WALK-INS |
| o-QF2.0 | FS TEMPORARY SERVING |
| o-M1.01 | MECHANICAL PLANS |
| E.000 | ELECTRICAL AND FIRE ALARM SCHEDULES |
| E.001 | ELECTRICAL AND FIRE ALARM NOTES |
| E.010 | ELECTRICAL DEVICE DETAILS |
| E.011 | ELECTRICAL DETAILS |
| E.012 | ELECTRICAL DETAILS |
| E.013 | ELECTRICAL KITCHEN DETAILS |
| E.060 | LIGHTING SCHEDULES |
| o-E.100 | LIGHTING FLOOR PLAN |
| o-E.200 | ELECTRICAL FLOOR PLANS |
| o-E.300 | FIRE ALARM FLOOR PLANS |

## Sheet List Table

| Sheet Number | Sheet Title |
|---|---|
| **SHARED GENERAL NOTES AND DETAILS** | |
| o-E.400 | ELECTRICAL SCHEMATIC |
| o-P1.01 | PLUMBING FLOOR PLAN |
| o-P1.02 | PLUMBING TEMPORARY KITCHEN PLAN |
| o-T000 | TECHNOLOGY SYMBOLS & LEGEND |
| o-T200 | TECHNOLOGY COMPOSITE FLOOR PLAN |
| o-T201 | TECHNOLOGY NEW_RENOVATION KITCHEN PLAN |
| o-T202 | TECHNOLOGY TEMPORARY KITCHEN PLAN |
| o-T300 | TECHNOLOGY ENLARGED VIEWS |
| o-T400 | TECHNOLOGY TYPICAL DETAILS |
| o-T401 | TECHNOLOGY TYPICAL DETAILS |
| o-T500 | TECHNOLOGY TYPICAL DETAILS |
| o-TN-000 | TECHNOLOGY - INDEX SHEET |
| o-TN-001 | TECHNOLOGY - DEMO |
| o-TN-100 | TECHNOLOGY - OVERALL |
| o-TN-101 | TECHNOLOGY - KITCHEN |
| o-TN-500 | TECHNOLOGY - DETAILS |
| o-TN-600 | TTECHNOLOGY - SECURITY DETAILS |
| o-TN-700 | TECHNOLOGY - AV DETAILS |
| **School: p-Pecan Grove ES** | |
| p-A.000 | COVER AND INDEX |
| p-A00-01 | GENERAL NOTES AND ABBREVIATIONS |
| p-D.101 | DEMO PLAN |
| p-D.101-2 | DEMO PLAN PHOTOS |
| p-D.101-3 | DEMO PLAN PHOTOS |
| p-ED.100 | ELECTRICAL DEMOLITION AND TEMP PLANS |
| p-PD1.01 | PLUMBING DEMOLITION FLOOR PLAN |
| p-TD201 | TECHNOLOGY DEMOLITION FLOOR PLAN |
| p-A.101 | SITE PLAN |
| p-A.200 | SLAB DIMENSION CONTROL PLAN |
| p-A.201 | OVERALL FLOOR PLAN |
| p-A.301 | KITCHEN PLAN |
| p-A.302 | TEMPORARY KITCHEN LAYOUT |
| p-A.401 | REFLECTED CEILING PLAN |
| p-A.501 | FINISH FLOOR PLAN |
| p-A.502 | PARTITION SCHEDULE |
| p-S1 | KITCHEN PLAN |
| p-S2 | SECTIONS AND TYPICAL DETAILS |
| p-QF1 | FS GENERAL COORDINATION NOTES |
| p-QF1.0 | FS EQUIPMENT PLAN |
| p-QF1.1 | FS FACILITY MODEL |
| p-QF1.2 | FS EQUIPMENT MODEL |
| p-QF1.3 | FS SPECIAL CONDITIONS & MECHANICAL PLAN |
| p-QF1.4 | FS PLUMBING PLAN |
| p-QF1.5 | FS ELECTRICAL PLAN |
| p-QF1.6 | CONDENSING UNITS |
| p-M1.01 | MECHANICAL PLANS |
| p-M2.01 | KITCHEN MECHANICAL DETAILS |
| E.000 | ELECTRICAL AND FIRE ALARM SCHEDULES |
| E.001 | ELECTRICAL AND FIRE ALARM NOTES |
| E.010 | ELECTRICAL DEVICE DETAILS |
| E.011 | ELECTRICAL DETAILS |
| E.012 | ELECTRICAL DETAILS |
| E.013 | ELECTRICAL KITCHEN DETAILS |
| E.060 | LIGHTING SCHEDULES |
| p-E100 | LIGHTING FLOOR PLAN |
| p-E200 | ELECTRICAL FLOOR PLANS |
| p-E.300 | FIRE ALARM FLOOR PLANS |
| p-E.400 | ELECTRICAL SCHEMATIC |
| p-P0.01 | PLUMBING NOTES AND SCHEDULES |
| p-P0.02 | PLUMBING SCHEDULES AND DETAILS |
| p-P1.01 | PLUMBING FLOOR PLAN |
| p-P1.02 | PLUMBING FLOOR PLAN - TEMPORARY KITCHEN |
| p-T000 | TECHNOLOGY SYMBOLS & LEGEND |
| p-T200 | TECHNOLOGY COMPOSITE FLOOR PLAN |
| p-T201 | TECHNOLOGY NEW_RENOVATION KITCHEN PLAN |
| p-T202 | TECHNOLOGY TEMPORARY KITCHEN PLAN |
| p-T300 | TECHNOLOGY ENLARGED VIEWS |
| p-T400 | TECHNOLOGY TYPICAL DETAILS |
| p-T401 | TECHNOLOGY TYPICAL DETAILS |
| p-T500 | TECHNOLOGY TYPICAL DETAILS |
| p-TN-000 | TECHNOLOGY - INDEX SHEET |
| p-TN-001 | TECHNOLOGY - KITCHEN DEMOLITION |
| p-TN-100 | TECHNOLOGY - OVERALL |
| p-TN-101 | TECHNOLOGY - KITCHEN |
| p-TN-500 | TECHNOLOGY - DETAILS |
| p-TN-600 | TECHNOLOGY - SECURITY DETAILS |
| p-TN-700 | TECHNOLOGY - AV DETAILS |
| **School: q-RIDGEGATE ES** | |
| q-A.000 | COVER AND INDEX |
| q-TN-000 | TECHNOLOGY - INDEX SHEET |
| q-TN-100 | TECHNOLOGY - OVERALL |
| q-TN-101 | TECHNOLOGY - KITCHEN |
| q-TN-500 | TECHNOLOGY - DETAILS |
| q-TN-600 | TECHNOLOGY - SECURITY DETAILS |
| **School: r-RIDGEMONT ES** | |
| r-A.000 | COVER AND INDEX |
| r-TN-000 | TECHNOLOGY - INDEX SHEET |
| r-TN-100 | TECHNOLOGY - OVERALL |
| r-TN-101 | TECHNOLOGY - KITCHEN |
| r-TN-500 | TECHNOLOGY - DETAILS |
| r-TN-600 | TECHNOLOGY - SECURITY DETAILS |
| **School: s-Settlers Way ES** | |
| s-A.000 | COVER AND INDEX |
| s-A00-01 | GENERAL NOTES AND ABBREVIATIONS |
| s-D.101 | DEMO PLAN |
| s-D.101-2 | DEMO PLAN PHOTOS |
| s-D.101-3 | DEMO PLAN PHOTOS |
| s-PD1.01 | PLUMBING DEMOLITION FLOOR PLAN |
| s-ED.100 | ELECTRICAL DEMOLITION AND TEMPORARY PLANS |
| s-TD201 | TECHNOLOGY DEMOLITION FLOOR PLAN |
| s-A.101 | SITE PLAN |
| s-A.200 | SLAB DIMENSION CONTROL PLAN |
| s-A.201 | OVERALL FLOOR PLAN |
| s-A.301 | KITCHEN PLAN |
| s-A.302 | TEMPORARY KITCHEN LAYOUT |
| s-A.401 | REFLECTED CEILING PLAN |

## Sheet List Table

| Sheet Number | Sheet Title |
|---|---|
| **SHARED GENERAL NOTES AND DETAILS** | |
| s-A.501 | FINISH FLOOR PLAN |
| s-A.502 | PARTITION SCHEDULE |
| s-S1 | KITCHEN PLAN |
| s-S2 | SECTIONS AND TYPICAL DETAILS |
| s-QF1 | FS GENERAL COORDINATION NOTES |
| s-QF1.0 | FS EQUIPMENT PLAN |
| s-QF1.1 | FS FACILITY MODEL |
| s-QF1.2 | FS EQUIPMENT MODEL |
| s-QF1.3 | FS SPECIAL CONDITIONS & MECHANICAL PLAN |
| s-QF1.4 | FS PLUMBING PLAN |
| s-QF1.5 | FS ELECTRICAL PLAN |
| s-M1.01 | MECHANICAL PLANS |
| s-M2.01 | KITCHEN DETAILS |
| s-E.000 | ELECTRICAL AND FIRE ALARM SCHEDULES |
| s-E.001 | ELECTRICAL AND FIRE ALARM NOTES |
| s-E.010 | ELECTRICAL DEVICE DETAILS |
| E.011 | ELECTRICAL DETAILS |
| E.012 | ELECTRICAL DETAILS |
| E.013 | ELECTRICAL KITCHEN DETAILS |
| E.060 | LIGHTING SCHEDULES |
| s-E.100 | LIGHTING FLOOR PLANS |
| s-E.200 | ELECTRICAL FLOOR PLANS |
| s-E.300 | FIRE ALARM FLOOR PLANS |
| s-E.400 | ELECTRICAL SCHEMATIC |
| s-P0.01 | PLUMBING NOTES & SCHEDULES |
| s-P0.02 | PLUMBING SCHEDULES & DETAILS |
| s-P1.01 | PLUMBING FLOOR PLAN |
| s-P1.02 | PLUMBING TEMPORARY KITCHEN PLAN |
| s-T000 | TECHNOLOGY SYMBOLS & LEGEND |
| s-T200 | TECHNOLOGY COMPOSITE FLOOR PLAN |
| s-T201 | TECHNOLOGY NEW RENOVATION KITCHEN PLAN |
| s-T202 | TECHNOLOGY TEMPORARY KITCHEN FLOOR PLAN |
| s-T300 | TECHNOLOGY ENLARGED VIEWS |
| s-T400 | TECHNOLOGY TYPICAL DETAILS |
| s-T401 | TECHNOLOGY TYPICAL DETAILS |
| s-T500 | TECHNOLOGY TYPICAL DETAILS |
| s-TN-000 | TECHNOLOGY - INDEX SHEET |
| s-TN-001 | TECHNOLOGY - KITCHEN DEMOLITION |
| s-TN-100 | TECHNOLOGY - OVERALL |
| s-TN-101 | TECHNOLOGY - KITCHEN |
| s-TN-500 | TECHNOLOGY - DETAILS |
| s-TN-600 | TECHNOLOGY - SECURITY DETAILS |
| s-TN-700 | TECHNOLOGY - AV DETAILS |
| **School: t-Sienna Crossing ES** | |
| t-A.000 | COVER AND INDEX |
| t-A00-01 | GENERAL NOTES AND ABBREVIATIONS |
| t-A.201 | FLOOR PLAN |
| t-A.301 | KITCHEN PLAN |
| t-A.401 | REFLECTED CEILING PLAN |
| t-A.501 | FINISH FLOOR PLAN |
| t-E.200 | ELECTRICAL PLAN AND SCHEDULES |
| t-TN-000 | TECHNOLOGY - INDEX SHEET |
| t-TN-100 | TECHNOLOGY - OVERALL |
| t-TN-101 | TECHNOLOGY - KITCHEN |
| t-TN-500 | TECHNOLOGY - DETAILS |
| t-TN-600 | TECHNOLOGY - SECURITY DETAILS |
| **School: u-Sugar Mill ES** | |
| u-A.000 | COVER AND INDEX |
| u-A00-01 | GENERAL NOTES AND ABBREVIATIONS |
| u-A.D.101 | DEMO PLAN |
| u-D.101-2 | REFERENCE PHOTOS FLOOR PLAN |
| u-D.101-3 | DEMO PLAN PHOTOS |
| u-ED.100 | ELECTRICAL DEMO AND TEMP PLANS |
| u-PD1.01 | PLUMBING DEMOLITION FLOOR PLAN |
| u-TD201 | TECHNOLOGY DEMOLITION FLOOR PLAN |
| u-A.101 | SITE PLAN |
| u-A.200 | SLAB DIMENSION CONTROL PLAN |
| u-A.201 | FLOOR PLAN |
| u-A.301 | KITCHEN PLAN |
| u-A.302 | TEMPORARY KITCHEN LAYOUT |
| u-A.401 | REFLECTED CEILING PLAN |
| u-A.501 | FINISH FLOOR PLAN |
| u-A.502 | PARTITION SCHEDULE |
| u-S1 | KITCHEN PLAN |
| u-S2 | SECTIONS AND TYPICAL DETAILS |
| u-C1.0 | GRADING & PAVING PLAN |
| u-QF1 | FS GENERAL COORDINATION NOTES |
| u-QF1.0 | FS EQUIPMENT PLAN |
| u-QF1.1 | FS FACILITY MODEL |
| u-QF1.2 | FS EQUIPMENT MODEL |
| u-QF1.3 | QF SPECIAL CONDITIONS & MECHANICAL PLAN |
| u-QF1.4 | FS PLUMBING PLAN |
| u-QF1.5 | FS ELECTRICAL PLAN |
| u-QF1.6 | FS CONDENSING UNITS |
| u-QF1.7 | FS WALK-INS |
| U-QF2.0 | FS TEMPORARY SERVING |
| u-M1.01 | MECHANICAL PLANS |
| M2.01 | KITCHEN MECHANICAL DETAILS |
| u-M2.02 | MECHANICAL DETAILS |
| E.000 | ELECTRICAL AND FIRE ALARM SCHEDULES |
| E.001 | ELECTRICAL AND FIRE ALARM NOTES |
| E.010 | ELECTRICAL DEVICE DETAILS |
| E.011 | ELECTRICAL DETAILS |
| E.012 | ELECTRICAL DETAILS |
| E.013 | ELECTRICAL KITCHEN DETAILS |
| E.060 | LIGHTING SCHEDULES |
| u-E.100 | LIGHTING FLOOR PLAN |
| u-E.200 | ELECTRICAL FLOOR PLAN |
| u-E.300 | FIRE ALARM FLOOR PLANS |
| u-E.400 | ELECTRICAL SCHEMATIC |
| u-P0.01 | PLUMBING NOTES AND SCHEDULES |
| u-P0.02 | PLUMBING SCHEDULES & DETAILS |
| u-P1.01 | PLUMBING FLOOR PLAN |
| u-P1.02 | PLUMBING FLOOR PLAN - TEMPORARY KITCHEN |
| u-T000 | TECHNOLOGY SYMBOLS & LEGEND |
| u-T200 | TECHNOLOGY COMPOSITE FLOOR PLAN |
| u-T201 | TECHNOLOGY NEW_RENOVATION KITCHEN PLAN |

## Sheet List Table

| Sheet Number | Sheet Title |
|---|---|
| **SHARED GENERAL NOTES AND DETAILS** | |
| u-T202 | TECHNOLOGY TEMPORARY KITCHEN PLAN |
| u-T300 | TECHNOLOGY ENLARGED VIEWS |
| u-T400 | TECHNOLOGY TYPICAL DETAILS |
| u-T401 | TECHNOLOGY TYPICAL DETAILS |
| u-T500 | TECHNOLOGY TYPICAL DETAILS |
| u-TN-000 | TECHNOLOGY - INDEX SHEET |
| u-TN-001 | TECHNOLOGY - KITCHEN DEMOLITION |
| u-TN-100 | TECHNOLOGY - OVERALL |
| u-TN-101 | TECHNOLOGY - KITCHEN |
| u-TN-500 | TECHNOLOGY - DETAILS |
| u-TN-600 | TECHNOLOGY - SECURITY DETAILS |
| u-TN-700 | TECHNOLOGY - AV DETAILS |
| **School: v-Sullivan ES** | |
| v-A.000 | COVER AND INDEX |
| v-A00-01 | GENERAL NOTES AND ABBREVIATIONS |
| v-D.101 | REFERENCE PHOTOS PLAN |
| v-A.101 | SITE PLAN |
| v-A.201 | OVERALL FLOOR PLAN |
| v-A.301 | CAFETERIA PLAN |
| v-A.501 | FINISH FLOOR PLAN |
| v-E.200 | ELECTRICAL FLOOR PLAN & SCHEDULE |
| V-TN-000 | TECHNOLOGY - INDEX SHEET |
| V-TN-100 | TECHNOLOGY - OVERALL |
| V-TN-101 | TECHNOLOGY - KITCHEN |
| V-TN-500 | TECHNOLOGY - DETAILS |
| V-TN-600 | TECHNOLOGY - SECURITY DETAILS |
| **School: w-TOWNEWEST ES** | |
| W-A.000 | COVER AND INDEX |
| w-TN-000 | TECHNOLOGY - INDEX SHEET |
| w-TN-100 | TECHNOLOGY - OVERALL |
| w-TN-101 | TECHNOLOGY - KITCHEN |
| w-TN-501 | TECHNOLOGY - DETAILS |
| w-TN-600 | TECHNOLOGY - SECURITY DETAILS |
| **School: aa-First Colony MS** | |
| aa-A.00 | COVER AND INDEX |
| aa-A.101 | TEMPORARY COOKING LOCATION SITE PLAN |
| aa-E.200 | ELECTRICAL FLOOR PLAN & SCHEDULES |
| **School: bb-Lakeview ES** | |
| bb-A.000 | COVER AND INDEX |
| bb-A.101 | TEMPORARY COOKING LOCATION SITE PLAN |
| bb-E.200 | ELECTRICAL FLOOR PLAN & SCHEDULES |
| **School: cc-Lake Olympia MS** | |
| cc-A.00 | COVER AND INDEX |
| cc-A.101 | TEMPORARY COOKING LOCATION SITE PLAN |
| cc-E.200 | ELECTRICAL FLOOR PLAN & SCHEDULES |
| **School: dd-Marshall HS** | |
| dd-A.000 | COVER AND INDEX |
| dd-A.101 | TEMPORARY COOKING LOCATION SITE PLAN |
| dd-E.200 | ELECTRICAL FLOOR PLAN & SCHEDULES |
| **School: ee-Travis HS** | |
| ee-A.000 | COVER AND INDEX |
| ee-A.101 | TEMPORARY COOKING LOCATION SITE PLAN |
| ee-E.200 | ELECTRICAL FLOOR PLAN & SCHEDULES |
| **School: ff-Dulles HS** | |
| ff-A.000 | COVER AND INDEX |
| ff-A.101 | TEMPORARY COOKING LOCATION SITE PLAN |
| ff-E.200 | ELECTRICAL FLOOR PLAN & SCHEDULES |

ALTERNATE #3:
CORNERSTONE (E)
LEAVING E

# FBISD BP013 KITCHEN RENOVATIONS ES

AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PKWY, MISSOURI CITY, TX 77479

FORT BEND INDEPENDENT SCHOOL DISTRICT

## FORT BEND INDEPENDENT SCHOOL DISTRICT

## ADMINISTRATION

| | |
|---|---|
| DR. MARCELL SMITH | SUPERINTENDENT OF FBISD |
| DR. ANDRIA SCHUR, Ed.D. | CHIEF OF SCHOOLS |

## BOARD OF TRUSTEES

| | |
|---|---|
| KRISTIN K. TASSIN | PRESIDENT |
| RICK GARCIA | VICE PRESIDENT |
| DAVID HAMILTON | SECRETARY |
| ANGIE HANAN | BOARD MEMBER |
| ADAM SCHOOF | BOARD MEMBER |
| DR. SHIRLEY ROSE-GILLIAM | BOARD MEMBER |
| SONYA JONES | BOARD MEMBER |

## PROJECT DESIGN TEAM


PROGRAM MANAGEMENT
FBISD 2023 Bond Team
2323 Texas Parkway
Missouri City, TX 77489
Phone Number: 281-327-5481

ARCHITECT
MWA Architects
11767 Katy Freeway, Suite 430
Houston, Texas 77079
Phone Number: 713-782-8188

FOOD SERVICE
Food Design Professionals
26215 Oak Ridge Drive
The Woodlands, Texas 77380
Phone Number: 281-350-2323

MEP ENGINEERS
Stanton Engineering Group
1300 W. Sam Houston Pkwy South, Suite 121
Houston, Texas 77042
Phone Number: 713-300-9292

STRUCTURAL ENGINEER
Stanley Spurling & Hamilton
3301 Edloe Street, Suite 200
Houston, Texas 77027
Phone Number: 713-776-9433


| Sheet List Table | |
|---|---|
| Sheet Number | Sheet Title |
| School: a Austin Pkwy ES | |
| a-A.000 | COVER AND INDEX |
| a-A00-01 | GENERAL NOTES AND ABBREVIATIONS |
| a-D.101 | DEMO PLANS |
| a-D01-02 | DEMO PLAN PHOTOS |
| a-D01-03 | DEMO PLAN PHOTOS |
| a-ED.100 | LIGHTING DEMOLITION & TEMPORARY KITCHEN |
| A-PD1.01 | PLUMBING DEMOLITION FLOOR PLAN |
| a-A.101 | SITE PLAN |
| a-A.201 | FLOOR PLAN |
| a-TD201 | TECHNOLOGY DEMOLITION FLOOR PLAN |
| a-A.300 | SLAB DIMENSION CONTROL PLAN |
| a-A.301 | KITCHEN PLAN |
| a-A.302 | TEMPORARY KITCHEN LAYOUT |
| a-A.501 | FINISH FLOOR PLAN |
| a-A.401 | REFLECTED CEILING PLAN |
| a-A.502 | PARTITION SCHEDULE |
| a-S1 | KITCHEN PLAN |
| a-S2 | SECTIONS AND TYPICAL DETAILS |
| A-QF1 | FS GENERAL COORDINATION NOTES |
| A-QF1.0 | FS EQUIPMENT PLAN |
| A-QF1.1 | FS FACILITY MODEL |
| A-QF1.2 | FS EQUIPMENT MODEL |
| A-QF1.3 | FS SPECIAL CONDITIONS & MECHANICAL PLAN |
| A-QF1.4 | FS PLUMBING PLAN |
| A-QF1.5 | FS ELECTRICAL PLAN |
| a-QF1.6 | FS CONDENSING UNITS |
| a-QF1.7 | FS WALK-INS |
| a-QF2.0 | FS EQUIPMENT PLAN TEMPORARY SERVING AND MEP |
| a-QF3.1 | FS ELEVATIONS |
| a-QF4.1 | FS SECTIONS AND DETAILS |
| a-QF4.2 | FS DETAILS |
| a-QF4.3 | FS DETAILS |
| a-M1.01 | LEVEL 1 KITCHEN MECHANICAL PLANS |
| a-M2.01 | LEVEL 1 KITCHEN MECHANICAL PLANS |
| a-M2.02 | MECHANICAL DETAILS (CONT.) |
| a-E.000 | ELECTRICAL AND FIRE ALARM SCHEDULES |
| a-E.010 | ELECTRICAL DEVICE DETAILS |
| a-E.011 | ELECTRICAL DETAILS |
| a-E.012 | ELECTRICAL DETAILS |
| a-E.013 | ELECTRICAL KITCHEN DETAILS |
| a-E.060 | LIGHTING SCHEDULES |
| a-E.001 | ELECTRICAL AND FIRE ALARM NOTES |
| a-E.100 | ELECTRICAL PLANS |
| a-E.200 | ELECTRICAL FLOOR PLAN |
| a-E.300 | FIRE ALARM FLOOR PLANS |
| a-E.400 | ELECTRICAL SCHEMATIC |
| a-P0.01 | PLUMBING NOTES AND SCHEDULES |
| A-P0.02 | PLUMBING SCHEDULES AND DETAILS |
| a-P1.01 | PLUMBING FLOOR PLAN |
| a-P1.02 | PLUMBING TEMPORARY KITCHEN PLAN |
| a-T000 | TECHNOLOGY SYMBOLS & LEGEND |
| a-T200 | TECHNOLOGY COMPOSITE FLOOR PLAN |
| a-T201 | TECHNOLOGY NEW-RENOVATION KITCHEN PLAN |
| a-T202 | TECHNOLOGY TEMPORARY KITCHEN PLAN |
| a-T300 | TECHNOLOGY ENLARGED VIEWS |
| a-T400 | TECHNOLOGY TYPICAL DETAILS |
| a-T401 | TECHNOLOGY TYPICAL DETAILS |
| a-T500 | TECHNOLOGY TYPICAL DETAILS |
| a-TN.000 | TECHNOLOGY - INDEX SHEET |
| a-TN-001 | TECHNOLOGY - KITCHEN DEMOLITION |
| a-TN-100 | TECHNOLOGY - OVERALL |
| a-TN-101 | TECHNOLOGY - KITCHEN |
| a-TN-500 | TECHNOLOGY - DETAILS |
| a-TN-600 | TECHNOLOGY - SECURITY DETAILS |
| a-TN-700 | TECHNOLOGY - AV DETAILS |




ISSUED FOR PERMIT AND BIDDING - JULY 18, 2025

a

PART 1 - GENERAL

1.1 GENERAL DEMOLITION NOTES

A. VERIFY EXISTING SITE AND BUILDING CONDITIONS IN FIELD PRIOR TO BIDDING. NOTIFY ARCHITECT OF ANY DISCREPANCIES PRIOR TO BIDDING.

B. CONTRACTOR SHALL COORDINATE WITH OWNER THE SALVAGE OF ITEMS, FURNITURE AND EQUIPMENT INDICATED TO BE REMOVED.

C. CLAIMS FOR ADDITIONAL COST OR TIME DUE TO EXISTING CONDITIONS THAT COULD HAVE BEEN REASONABLY ANTICIPATED DURING A SITE VISIT BY THE CONTRACTOR PRIOR TO BIDDING WILL NOT BE APPROVED.

D. PROTECT EXISTING FINISHES SHOWN TO REMAIN DURING CONSTRUCTION TO PREVENT DAMAGE. REPAIR OR REPLACE DAMAGED MATERIALS AND FINISHES TO MATCH EXISTING AT NO ADDITIONAL COST TO FORT BEND ISD (OWNER).

E. EXISTING AREAS REQUIRING MINOR DEMOLITION OR REPAIR FOR EXECUTION OF WORK SHALL BE REPAIRED TO MATCH EXISTING ADJACENT MATERIALS, UNLESS NOTED OTHERWISE.

F. DO NOT DAMAGE CASEWORK AND EQUIPMENT NOT DESIGNATED TO BE REMOVED OR RELOCATED.EXISTING CASEWORK SHALL REMAIN THE PROPERTY OF THE OWNER.

G. CONTRACTOR TO VERIFY LOCATION OF ELEC. SWITCHES, OUTLETS, GRILLES, CLEAN-OUTS, COVER PLATES, ACCESS DOORS, AND OTHER EQUIPMENT AND DEVICES THAT MAY CONFLICT WITH THE RENOVATION AND NEW CONSTRUCTION OF WALLS, FLOORS, AND CEILINGS PRIOR TO COMMENCEMENT OF WORK. CONTRACTOR SHALL LIKEWISE CONFIRM THAT ELECTRICAL CONDUIT ROUTING SHALL BE CONCEALED WITHIN WALLS. NOTIFY ARCHITECT IF WALL THICKNESS WILL NOT ALLOW FOR CONCEALMENT.

H. REMOVE ANY EXISTING CORNER GUARDS IN THE KITCHEN AREA.

I. PRIOR TO EXECUTION OF DEMOLITION WORK, SCHEDULE A WALK-THROUGH WITH OWNER AND ARCHITECT TO CONFIRM SCOPE OF WORK AND TO REVIEW EXISTING CONDITIONS.

J. EXISTING FLOOR FINISHES AND ACOUSTIC CEILING TILE TO BE REMOVED THROUGHOUT.

K. REFER TO MEP DRAWINGS FOR DEMOLITION AND ALTERATION OF UTILITIES.

L. AT ALL EXISTING WALLS REQUIRING DEMOLITION TO INSTALL NEW PIPING BEHIND SINKS, CUT AND PATCH WALLS AS REQUIRED TO MATCH ADJACENT SURFACE.

M. CLEAN AND PREPARE SUBFLOOR FOR INSTALLATION OF NEW FLOOR FINISH.

N. DEMOLITION ACTIVITIES SHALL BE PERFORMED AS TO PRODUCE MINIMAL DISTURBANCE TO EXISTING FACILITY OCCUPANTS. MINIMIZE EXCESSIVE AND PROLONGED NOISE LEVELS AND DUST.

O. ASBESTOS-CONTAINING MATERIALS. REFER TO SPECIFICATION 02 26 23 FOR ASBESTOS INFORMATION APPLICABLE TO KITCHEN AREAS. FORT BEND ISD HAS RETAINED A SEPARATE ENVIRONMENTAL CONSULTANT FOR THE REMOVAL OF ASBESTOS. GC TO COORDINATE WITH ENVIRONMENTAL CONSULTANT TO CARRY OUT ASBESTOS ABATEMENT FOR ALL AFFECTED KITCHEN AREAS.

1.2 FLOOR PLAN GENERAL NOTES

A. FIELD VERIFY EXISTING CONDITIONS PRIOR TO GENERATING SHOP DRAWINGS AND FABRICATION OF EQUIPMENT.

B. FLOOR FINISH CHANGES SHALL OCCUR AT THE CENTERLINE OF DOORS UNLESS NOTED OTHERWISE. FLOOR FINISH CHANGES SHALL HAVE THRESHOLDS OR REDUCERS STRIPS.

C. DOORS THAT ARE TO BE REPLACED AND INSTALLED IN EXISTING FRAMES SHALL BE MACHINED FOR HARDWARE DIMENSIONS AT EXISTING FRAMES, CONTRACTOR SHALL FIELD VERIFY FRAME CONDITIONS AND DIMENSIONS.

D. CONTRACTOR TO PROVIDE SHEET METAL REINFORCING STRAP AS REQUIRED FOR MOUNTING OF ALL GRAB BARS, CABINETS, MIRRORS, SHELVING, ETC.

E. SAW CUT AND REMOVE EXISTING SLAB AND FLOOR FINISHES AS REQUIRED TO INSTALL NEW PLUMBING LINES, FLOOR DRAINS, PLUMBING FIXTURES, OR ELECTRICAL ITEMS. SPLICE NEW REINFORCING BARS DOWELED INTO EXISTING CONCRETE, AND PROVIDE NEW VAPOR RETARDER AND WATERSTOPS, AND PATCH W/ 3000 PSI CONCRETE AFTER INSTALLATION OF UTILITIES AND FIXTURES. PREPARE CONCRETE TO RECEIVE NEW FINISH.

F. COORDINATE HOUSEKEEPING PAD DIMENSIONS AND LOCATIONS WITH EQUIPMENT TO BE INSTALLED. HOUSEKEEPING PADS SHALL BE A MIN. OF 4" THICK REINF. W/ #3 BARS AT 15" O.C. BOTH WAYS. PROVIDE 1" BY 45-DEGREE CHAMFERED EDGES.

1.3 COMPLETE PERFORMANCE

L. THE CONTRACTOR SHALL FURNISH AND INSTALL ALL ITEMS SPECIFIED HEREIN AND AS INDICATED ON THE DRAWINGS. THE CONTRACTOR SHALL ALSO FURNISH AND INSTALL ALL ITEMS NECESSARY TO MAKE THE SYSTEMS FUNCTION WHICH MAY BE REASONABLY IMPLIED AS ESSENTIAL, WHETHER MENTIONED IN THE CONTRACT DOCUMENTS OR NOT.

M. WORK SHALL BE EXECUTED IN STRICT ACCORDANCE WITH THE BEST PRACTICE OF THE TRADES IN A THOROUGH, SUBSTANTIAL AND WORKMANLIKE MANNER BY COMPETENT WORKMEN.

1.4 SITE FAMILIARIZATION

A. GENERAL: BECOME FAMILIAR WITH THE DRAWINGS AND SPECIFICATIONS, EXAMINE THE PREMISES, AND UNDERSTAND THE CONDITIONS UNDER WHICH THE CONTRACT SHALL BE PERFORMED, PRIOR TO SUBMITTING A BID.

B. SITE: BE INFORMED OF THE SITE CONDITIONS, VERIFY LOCATIONS OF NEW AND EXISTING EQUIPMENT, AND DETERMINE EXACT REQUIREMENTS FOR CONNECTIONS.

C. COORDINATION: TENDER OF A PROPOSAL FOR THIS PROJECT INFERS THAT THE CONTRACTOR HAS VISITED THE SITE AND HAS BECOME FAMILIAR WITH THE DRAWINGS, SPECIFICATIONS, AND SITE CONDITIONS AND HAS INCLUDED IN HIS PROPOSAL ALL WORK NECESSARY TO PROPERLY INSTALL COMPLETE AND FUNCTIONING SYSTEMS ON THE PROJECT. FAILURE TO COMPLY WITH THIS REQUIREMENT SHALL NOT BE CONSIDERED JUSTIFICATION FOR THE OMISSION OR FAULTY INSTALLATION OF ANY WORK COVERED BY THE CONTRACT DOCUMENTS.

1.5 CODES AND STANDARDS

A. GENERAL: ALL WORK SHALL COMPLY WITH THE MOST RECENTLY REVISED VERSIONS OF ALL APPLICABLE LAWS, RULES, REGULATIONS AND ORDINANCES OF ALL FEDERAL, STATE AND LOCAL AUTHORITIES AND APPLICABLE UTILITIES. NONE OF THE TERMS OR PROVISIONS OF THIS SPECIFICATION SHALL BE CONSTRUED AS WAIVING ANY PART OF THE LAWS, RULES, REGULATIONS OR REQUIREMENTS OF THESE AUTHORITIES.

B. CONFLICT: IN THE EVENT OF CONFLICT BETWEEN THE CONTRACT DOCUMENTS AND THE LOCAL ENFORCING AUTHORITY, THE LATTER SHALL RULE. ANY MODIFICATIONS RESULTING THEREFROM SHALL BE MADE WITHOUT ANY ADDITIONAL COST TO THE OWNER OR ARCHITECT. THIS CONTRACTOR SHALL REPORT ANY SUCH MODIFICATIONS TO THE ARCHITECT AND SECURE HIS APPROVAL PRIOR TO PROCEEDING WITH THE WORK.

C. PRECEDENCE: WHERE CONTRACT DOCUMENT REQUIREMENTS EXCEED THE REQUIREMENTS OF THE CODES AND STANDARDS, THE CONTRACT DOCUMENTS SHALL TAKE PRECEDENCE PROVIDED THEY ARE NOT IN CONFLICT WITH THOSE CODES AND STANDARDS.

D. APPROVAL LABELS: ALL ITEMS OF EQUIPMENT AND ALL MATERIALS FOR WHICH APPROVED STANDARDS HAVE BEEN ESTABLISHED BY UNDERWRITERS' LABORATORIES, INC. (UL), FACTORY MUTUAL (FM), CERTIFIED BALLAST MANUFACTURER (CBM), ELECTRICAL TESTING LABORATORY (ETL), NATIONAL MANUFACTURERS ASSOCIATION (NEMA), AMERICAN STANDARD CODES, ASME, AGA, AMCA, ASA, ANSI, ASHRAE, AND ARI SHALL BE SO APPROVED AND SHALL BEAR APPROVAL LABELS ATTESTING TO SAME.

1.6 DRAWINGS AND SPECIFICATIONS

A. DRAWINGS: THE SET OF ORIGINAL DRAWINGS HAS BEEN MODIFIED AND INDICATE APPROXIMATE EXISTING LOCATIONS OF THE FLOOR FINISH ITEMS. ALL ITEMS ARE SHOWN APPROXIMATELY TO SCALE. FIELD VERIFY CONDITIONS.

B. SPECIFICATIONS: THE SPECIFICATIONS ARE INTENDED TO SUPPLEMENT THE DRAWINGS AND IT IS NOT IN THE SCOPE OF THE SPECIFICATIONS TO MENTION ANY PART OF THE WORK THAT THE DRAWINGS ARE COMPETENT TO FULLY EXPLAIN. CONVERSELY, ANY PART OF THE WORK THAT THE SPECIFICATIONS ARE COMPETENT TO FULLY EXPLAIN MAY NOT BE MENTIONED ON THE DRAWINGS. DRAWINGS AND SPECIFICATIONS ARE COMPLIMENTARY/SUPPLEMENTARY DOCUMENTS TO EACH OTHER.

C. DISAGREEMENT: DISAGREEMENT BETWEEN THE DRAWINGS AND SPECIFICATIONS OR WITHIN THE DRAWINGS OR SPECIFICATIONS SHALL BE ESTIMATED AND/OR BID USING THE BETTER QUALITY OR GREATER QUANTITY OF MATERIAL OR INSTALLATION, AND A CLARIFICATION REQUEST FOR INFORMATION SHALL BE MADE TO THE ARCHITECT IN A TIMELY MANNER AFTER THE PROJECT IS UNDER CONTRACT.

1.7 DISCREPANCIES

A. CLARIFICATION: CLARIFICATION OF SIGNIFICANT COST MATTERS SHALL BE OBTAINED BEFORE SUBMITTING A PROPOSAL FOR THE WORK AS TO DISCREPANCIES OR OMISSIONS FROM THE CONTRACT DOCUMENTS OR QUESTIONS AS TO THE INTENT THEREOF.

B. INTERPRETATIONS: SHOULD ANY DOUBT OR QUESTION ARISE RESPECTING THE TRUE MEANING OF DRAWINGS OR SPECIFICATIONS, REFERENCE SHALL BE MADE TO THE ARCHITECT, WHOSE WRITTEN DECISION SHALL BE FINAL AND CONCLUSIVE. NO ALLEGED STATEMENT BY THE ARCHITECT WILL BE ACCEPTED AS AN EXCUSE FOR NON-COMPLIANCE OR INFERIOR WORK.

C. CONTRACTOR AGREEMENT: CONSIDERATION WILL NOT BE GRANTED FOR MISUNDERSTANDING OF THE AMOUNT OF WORK TO BE PERFORMED. TENDER OF A PROPOSAL CONVEYS FULL CONTRACTOR AGREEMENT OF THE ITEMS AND CONDITIONS SPECIFIED, SHOWN, SCHEDULED, OR REQUIRED BY THE NATURE OF THE PROJECT, AND ALL COSTS ARE INCLUDED IN THE PROPOSAL.

1.8 REQUESTS FOR INFORMATION (RFI)

A. GENERAL: SUBMIT ALL CONTRACTOR REQUESTS FOR INFORMATION (RFI) IN WRITING TO THE ARCHITECT FOR RESPONSE. SUBMIT RFI ON A STANDARD FORM THAT HAS A SPACE FOR THE REQUESTED INFORMATION AND THE ARCHITECT'S RESPONSE.

B. SOLUTION PROPOSAL: IN GENERAL, THE CONTRACTOR SHALL PROPOSE SOLUTIONS TO IDENTIFY PROBLEMS FOR REVIEW AND APPROVAL OF THE ARCHITECT. THE RFI SHALL INCLUDE HAND SKETCHES, MARKED DRAWING PRINTS, EQUIPMENT CUTSHEETS, DRAWING AND SPECIFICATION REFERENCES, AND ANY OTHER BACK-UP INFORMATION, ETC., AS REQUIRED TO SUFFICIENTLY EXPLAIN THE PROBLEM AND PROPOSED SOLUTION.

1.9 QUALITY ASSURANCE

A. GENERAL: MATERIALS AND EQUIPMENT SHALL BE NEW, OF BEST GRADE AND QUALITY, AND STANDARD PRODUCTS OF REPUTABLE MANUFACTURERS REGULARLY ENGAGED IN THE PRODUCTION OF SUCH MATERIALS AND EQUIPMENT.

B. WORKMANSHIP: WORK SHALL BE EXECUTED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE BEST PRACTICE OF THE TRADES IN A THOROUGH, SUBSTANTIAL, WORKMANLIKE MANNER BY COMPETENT WORKMEN, PRESENTING A NEAT APPEARANCE WHEN COMPLETED.

C. JUDGMENT: IN ALL CASES, THE ARCHITECT SHALL BE THE SOLE JUDGE OF THE QUALITY AND EQUIVALENCE OF MANUFACTURERS, PRODUCTS, MATERIALS, AND METHODS.

D. MANUFACTURERS/PRODUCTS/MATERIALS/METHODS: MANUFACTURERS, PRODUCTS, MATERIALS, AND METHODS DESCRIBED IN THE VARIOUS SECTIONS OF THE SPECIFICATIONS AND INDICATED ON THE DRAWINGS ARE INTENDED TO ESTABLISH A STANDARD OF QUALITY ONLY. IT IS NOT THE INTENTION OF THE ARCHITECT TO DISCRIMINATE AGAINST ANY MANUFACTURER, PRODUCT, MATERIAL, OR METHOD THAT IS EQUAL TO THE STANDARDS AS INDICATED AND/OR SPECIFIED, NOR IS IT INTENDED TO PRECLUDE OPEN, COMPETITIVE BIDDING. THE FACT THAT A SPECIFIC MANUFACTURER IS LISTED AS AN ACCEPTABLE MANUFACTURER SHALL NOT BE INTERPRETED TO MEAN THAT THE MANUFACTURER'S STANDARD PRODUCT WILL MEET THE REQUIREMENTS OF THE PROJECT DESIGN, SPECIFICATIONS, AND SPACE CONSTRAINTS.

1. WHEREVER A DEFINITE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS SPECIFIED AND THERE IS NOT A STATEMENT THAT ANOTHER MANUFACTURER, PRODUCT, MATERIAL, OR METHOD WILL BE ACCEPTABLE, IT IS THE INTENTION OF THE ARCHITECT THAT THE SPECIFIED MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS THE ONLY ONE THAT SHALL BE USED WITHOUT PRIOR APPROVAL.
2. WHEREVER A DEFINITE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS SPECIFIED AS "NO SUBSTITUTE", IT IS THE INTENTION OF THE ARCHITECT THAT THE LISTED ITEM IS THE ONLY ONE ACCEPTABLE.

E. COORDINATION: WHERE EQUIPMENT IS USED ON THE PROJECT, IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR OR SUBCONTRACTOR INVOLVED TO VERIFY THAT THE EQUIPMENT WILL FIT IN THE SPACE AVAILABLE, INCLUDING ALL REQUIRED CODE AND MAINTENANCE CLEARANCES, AND TO COORDINATE ALL EQUIPMENT REQUIREMENTS AND PROVISIONS WITH THE SYSTEM DESIGN, ALL AFFECTED DIVISIONS, AND ALL OTHER CONTRACTORS. WHERE THE USE OF ALTERNATE OR SUBSTITUTE MATERIALS AFFECTS THE COST OF PROVISIONS MADE BY OTHER CONTRACTORS, THE CONTRACTOR PROVIDING THE ALTERNATE OR SUBSTITUTE SHALL BE RESPONSIBLE FOR THE OTHER CONTRACTOR'S COST ADJUSTMENT. THERE SHALL BE NO ADDITIONAL COST TO THE OWNER OR ARCHITECT DUE TO THE USE OR ACCEPTANCE OF ANY ALTERNATE OR SUBSTITUTE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD.

1.10 PRIOR APPROVAL

A. SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES: THE CONTRACTOR'S SUBMITTAL AND ARCHITECT'S ACCEPTANCE OF SHOP DRAWINGS, PRODUCT DATA, OR SAMPLES THAT RELATE TO CONSTRUCTION ACTIVITIES NOT COMPLYING WITH THE CONTRACT DOCUMENTS DOES NOT CONSTITUTE AN ACCEPTABLE OR VALID REQUEST FOR SUBSTITUTION, NOR DOES IT CONSTITUTE APPROVAL.

1.11 COORDINATION

A. BY SUBMITTING SHOP DRAWINGS ON THE PROJECT, THIS CONTRACTOR IS INDICATING THAT ALL NECESSARY COORDINATION HAS BEEN COMPLETED AND THAT THE SYSTEMS, PRODUCTS AND EQUIPMENT SUBMITTED CAN BE INSTALLED IN THE BUILDING AND WILL OPERATE AS SPECIFIED AND INTENDED, IN FULL COORDINATION WITH ALL OTHER DISCIPLINES.

1.12 SHOP DRAWINGS AND SUBMITTALS

A. GENERAL: AFTER THE CONTRACT IS AWARDED BUT PRIOR TO PROCEEDING WITH THE WORK REQUIRING SHOP DRAWING REVIEW, THE CONTRACTOR SHALL OBTAIN COMPLETE SHOP DRAWINGS AND PRODUCT DATA FROM THE MANUFACTURERS, SUPPLIERS, VENDORS, AND SUB- CONTRACTORS FOR ALL MATERIALS AND EQUIPMENT SPECIFIED HEREIN, AND MAKE FORMAL SUBMISSION TO THE ARCHITECT. A MINIMUM PERIOD OF TWO (2) WEEKS SHOULD BE ALLOWED IN THE CONSTRUCTION SCHEDULE EXCLUSIVE OF TRAVEL TIME FOR THE ARCHITECTS REVIEW.

B. CERTIFICATION: EACH CONTRACTOR RESPONSIBLE FOR THE WORK SHALL REVIEW AND CERTIFY THE SHOP DRAWING, SUBMITTAL AND/OR PRODUCT DATA TO BE IN FULL COMPLIANCE WITH THE REQUIREMENTS OF THE CONTRACT DOCUMENTS.

C. THE ARCHITECTS REVIEW OF SHOP DRAWINGS AND SUBMITTAL DATA SHALL NOT RELIEVE THE CONTRACTOR OF THE RESPONSIBILITY FOR DIMENSIONS OR ERRORS THAT MAY BE CONTAINED THEREIN, OR FOR DEVIATIONS FROM ANY REQUIREMENTS OF THE CONTRACT DOCUMENTS. IT SHALL BE CLEARLY UNDERSTOOD THAT THE ARCHITECTS NOTING SOME ERRORS BUT OVERLOOKING SOME OTHERS DOES NOT GRANT THE CONTRACTOR PERMISSION TO PROCEED IN ERROR. REGARDLESS OF ANY INFORMATION CONTAINED IN THE SHOP DRAWING OR PRODUCT DATA, THE CONTRACT DOCUMENTS SHALL GOVERN THE WORK AND ARE NEITHER WAIVED NOR SUPERSEDED IN ANY WAY BY THE REVIEW OF SHOP DRAWINGS, PRODUCT DATA AND SAMPLES.

1.13 EXECUTION AND COORDINATION OF WORK

A. MANUFACTURER'S RECOMMENDATIONS: WITH EXCEPTIONS AS SPECIFIED AND/OR INDICATED ON THE DRAWINGS OR IN THE SPECIFICATIONS, APPLY, INSTALL, ERECT, USE, CLEAN, AND CONDITION, MANUFACTURED ARTICLES, MATERIALS, AND EQUIPMENT PER MANUFACTURER'S CURRENT PRINTED RECOMMENDATIONS. KEEP COPIES OF SUCH PRINTED RECOMMENDATIONS AT JOB SITE AND MAKE THEM AVAILABLE AS REQUIRED.

1.14 SUPERVISION

A. A COMPETENT SUPERINTENDENT APPROVED BY THE ARCHITECT, SHALL BE KEPT BY THE CONTRACTOR AT THE BUILDING TO RECEIVE INSTRUCTIONS AND TO ACT FOR THE CONTRACTOR. ONCE THE SUPERINTENDENT HAS BEEN APPROVED, NO CHANGE SHALL BE MADE WITHOUT APPROVAL OF ARCHITECT. REPRESENTATIVES OF THE OWNER, ARCHITECT SHALL HAVE THE RIGHT TO OBSERVE THE WORK AT ANY TIME. THE CONTRACTOR SHALL HAVE A REPRESENTATIVE AVAILABLE WHEN HIS WORK IS BEING OBSERVED AND HE SHALL GIVE ASSISTANCE AS MAY BE REQUIRED TO THE ARCHITECT'S REPRESENTATIVE.

B. THE PROJECT SHALL BE CONSTRUCTED BY EMPLOYEES OF THE CONTRACTOR OR BY WORKERS UNDER HIS SUPERVISION. ANY SUBCONTRACTORS EMPLOYED BY THE CONTRACTOR SHALL BE APPROVED BY THE OWNER'S REPRESENTATIVE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL EQUIPMENT, MATERIAL AND WORK PERFORMED BY ANY SUBCONTRACTOR.

1.15 STORAGE AND PROTECTION OF MATERIALS

A. THE CONTRACTOR SHALL PROPERLY STORE ALL MATERIAL AND EQUIPMENT AT THE JOBSITE AND PROTECT IT FROM THE ELEMENTS AND FROM DAMAGE. ANY EQUIPMENT DAMAGED DUE TO IMPROPER PROTECTION SHALL BE REPLACED BY THE CONTRACTOR AT HIS EXPENSE.

B. THE CONTRACTOR SHALL PROTECT THE WORK, EQUIPMENT, AND MATERIAL OF ALL OTHER TRADES FROM DAMAGE BY HIS WORK OR OTHER WORKMEN, AND SHALL MAKE GOOD ALL DAMAGE THUS CAUSED.

C. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL WORK, MATERIALS, AND EQUIPMENT UNTIL FINALLY INSPECTED, TESTED, AND ACCEPTED; PROTECT WORK AGAINST THEFT, INJURY OR DAMAGE; AND CAREFULLY STORE MATERIAL AND EQUIPMENT RECEIVED ON SITE WHICH ARE NOT IMMEDIATELY INSTALLED. CLOSE OPEN ENDS OF WORK WITH TEMPORARY COVERS OR PLUGS DURING CONSTRUCTION TO PREVENT ENTRY OF OBSTRUCTING MATERIAL. THE CONTRACTOR SHALL COVER AND PROTECT IN AN ACCEPTABLE MANNER TO THE OWNER, EXISTING REMAINING EQUIPMENT AND MATERIALS.

D. IF ANY MATERIAL OR EQUIPMENT IS RECEIVED PRIOR TO THE TIME IT IS REQUIRED, THE CONTRACTOR SHALL BE RESPONSIBLE FOR ITS PROPER STORAGE AND PROTECTION UNTIL SUCH TIME AS IT MAY BE REQUIRED. THE CONTRACTOR SHALL PAY FOR ALL COSTS OF DEMURRAGE OR STORAGE.

1.16 DRAYAGE AND HAULING


A. THE CONTRACTOR SHALL KEEP THE JOBSITE FREE FROM THE ACCUMULATION OF TRASH AND CONSTRUCTION DEBRIS, REGARDLESS OF WHICH SUBCONTRACTOR MAY BE RESPONSIBLE.

1.17 CUTTING AND PATCHING


A. WHERE IT BECOMES NECESSARY TO CUT THROUGH ANY WALL, FLOOR OR CEILING TO PERMIT THE INSTALLATION OF ANY WORK, OR TO REPAIR ANY DEFECTS THAT MAY APPEAR, THE CUTTING SHALL BE PERFORMED UNDER THE SUPERVISION OF THE GENERAL CONTRACTOR. INFORM THE OWNER'S REPRESENTATIVE BEFORE ANY WORK COMMENCES. NO STRUCTURAL MEMBER SHALL BE ALTERED WITHOUT THE WRITTEN PERMISSION OF THE ARCHITECT.

B. VERIFICATION: SHOULD A QUESTION ARISE REGARDING THE ACCEPTABLE LEVEL OF NOISE OR VIBRATION IN A PARTICULAR SPACE OR PIECE OF EQUIPMENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING THE SERVICES OF AN APPROVED ACOUSTICAL CONSULTANT TO DETERMINE ACTUAL NOISE/VIBRATION CONDITIONS.


## 01 GENERAL NOTES





## 21 EXTERIOR DOOR SILL
SCALE: 6" = 1'-0" XREF





## 22 DOOR JAMB
SCALE: 6" = 1'-0" XREF





## 23 WINDOW HEAD
SCALE: 6" = 1'-0" XREF





## 24 DOOR WINDOW HEAD
SCALE: 6" = 1'-0" XREF





## 15 WINDOW JAMB AT WALL
SCALE: 6" = 1'-0"





## 16 DOOR HEAD
SCALE: 6" = 1'-0" XREF





## 17 WINDOW SILL
SCALE: 6" = 1'-0" XREF





## 18 DOOR SILL
SCALE: 6" = 1'-0" XREF





## 09 WINDOW CORNER
SCALE: 6" = 1'-0"




## 10 DOOR STRIKE JAMB
SCALE: 6" = 1'-0"




## 11 DOOR HINGE JAMB
SCALE: 6" = 1'-0"





## 12 WINDOW MULLION
SCALE: 6" = 1'-0"


SEQUENCE OF CONSTRUCTION (AS OF 01/27/2025). Schools will be renovated in groups as shown. These groups contain two or three major kitchen renovations and some cafeteria/miscellaneous renovations. This sequencing is critical for FBISD food service to provide the uninterrupted meal services to their schools.

| | |
|---|---|
| GROUPING 1 | AUSTIN PARKWAY ES + SUGAR MILL ES, kitchen renovations. *Plus: COMMON WEALTH ES, CONERSTONE ES misc. renovations.* |
| GROUPING 2 | SETTLERS WAY ES + PALMER ES kitchen renovations. *Plus: SULLIVAN ES, SIENNA CROSSING ES, HERITAGE ROSE ES misc. renovations* |
| GROUPING 3 | HUNTER'S GLEN ES + HIGHLANDS ES + PECAN GROVE ES kitchen renovations. *Plus: RIDGEGATE ES, DULLES ES misc. renovations.* |

## 03 PROJECT SCHEDULE




## 04 EXTERIOR DOOR HEAD JAMB
SCALE: 6" = 1'-0" XREF




## 06 WINDOW JAMB
SCALE: 6" = 1'-0" XREF

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL
REGISTERED ARCHITECT
ROBERT A. WEBB
23613
STATE OF TEXAS
7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

GENERAL NOTES AND ABBREVIATIONS

A00-01


K:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\A00-01 GENERAL NOTES AND ABBREVIATIONS.dwg, Jul 23, 2025, 3:51pm

## GENERAL DEMOLITION NOTES
(NOT ALL NOTES USED ON EACH SHEET)


1. REFER TO SHEET A00-01 FOR DEMOLITION GENERAL NOTES. THESE NOTES APPLY TO ALL SCHOOL KITCHENS.
2. COORDINATE EXTENT OF SAW CUTTING AREAS WITH NEW RECESSED SLAB FOR COOLER/FREEZER LAYOUTS, NEW SERVICE ENTRANCE FLOOR AND EXISTING KITCHEN LAYOUTS THAT REMAIN. SEE STRUCTURAL DRAWINGS AND SLAB DIMENSION CONTROL PLANS FOR ADDITIONAL SCOPE.
3. REMOVE PROTECT AND REINSTALL ALL EXISTING SURFACE MOUNTED FIRE EXTINGUISHERS (TYPES ABC AND K) AT ALL KITCHENS.
4. SAWCUT AND RE-LOCATE EXPOSED CONDUITS AND WIREMOLD TO INSIDE OF WALLS. PATCH AND PAINT. EXCEPTION: WAREWASH AREA BELOW TABLE HEIGHT AND DRY STORAGE ROOMS.
5. CONTRACTOR TO RELOCATE EXISTING KITCHEN EQUIPMENT AND OFFICE FURNITURE TO TEMPORARY KITCHEN LAYOUT AS REQUESTED BY KITCHEN MANAGER. ALSO THAT THE IT EQUIPMENT IS PROTECTED DURING RENOVATIONS. ALL EXISTING EQUIPMENT SHALL BE RETURNED TO OWNER.
6. EXISTING TACKBOARDS TO BE REMOVED BY OWNER.
7. IF PRESENT, EXISTING SAFE IN EACH KITCHEN TO BE TEMPORARILY REMOVED DURING RENOVATION AND REINSTALLED IN KITCHEN AREA.
8. ORIGIN POINT OF EXISTING CEILING GRID SHALL BE IDENTIFIED. NEW CEILING WILL BE INSTALLED (AS MUCH AS POSSIBLE) AT THE SAME ORIGIN POINT SO THAT SPRINKLER SYSTEM PIPING CAN REMAIN UNCHANGED.
9. ABOVE-CEILING INFRASTRUCTURE SHALL REMAIN UNDISTURBED AS MUCH AS IS POSSIBLE. CEILING DEVICES ARE TO BE REMOVED FROM EXISTING GRID/TILE THEN DURING RE-INSTALATION OF CEILING DEVICES SHALL BE LOCATED AS CLOSE TO ORIGINAL LOCATION AS POSSIBLE INTO THE NEW GRID/TILE. PROTECT AND STORE EXISTING INFRASTRUCTURE (CABLING, ELECTRICAL POWER, PIPING) DURING CONSTRUCTION.
10. EXISTING HOOD IN WAREWASH AND (2) HOODS IN PRODUCTION AREA ARE TO BE CLEANED, INSPECTED, SERVICED AND REFURBISHED TO A LIKE NEW CONDITION. THEY ARE TO REMAIN IN PLACE.

## KEYED DEMOLITION NOTES
(NOT ALL NOTES USED ON EACH SHEET)


1. REMOVE EXISTING THINSET SYNTHETIC TERRAZZO FLOOR AND TERRAZZO COVE BASE MATERIAL IF ANY EXISTS THROUGHTOUT KITCHEN AREA. CLEAN AND PREPARE SUBFLOOR TO RECEIVE NEW FLOOR. RE: FINISH PLAN FOR NEW FLOOR FINISH MATERIAL.
2. REMOVE EXISTING QUARRY TILE FLOORING AND BASE. CLEAN AND PREPARE SUBFLOOR TO RECEIVE NEW FLOORING. RE: FINISH SCHEDULE FOR NEW FLOOR FINISH MATERIAL.
3. CEILING DEVICES: REMOVE SMOKE DETECTORS, STROBES, EXIT SIGNAGE, MOTION DETECTORS AND CEILING SPEAKERS. PROTECT AND RE-INSTALL AFTER FINISHES ARE APPLIED.
4. REMOVE EXISTING LOCKERS. PROTECT AND RE-INSTALL AFTER FINISHES APPLIED.
5. REMOVE EXISTING WASHER AND DRYER. VERIFY WITH FBISD FOR RELOCATION TO WAREHOUSE.
6. TEMPORARILY REMOVE EXISTING WALL MOUNTED CLOCK AND STORE FOR REINSTALLATION AFTER WALL RECEIVED NEW FINSH.
7. REMOVE EXISTING WALK-IN COOLER/FREEZER AND CONDENSING UNIT LOCATED IN ADJACENT SPACE. MITIGATE ANY MOLD FOUND.
8. REMOVE EXISTING DOOR AND PROTECT EXISTING FRAME TO REMAIN
9. REMOVE EXISTING DOOR AND FRAME, PROTECT FRAME AND OR DOOR IF IT IS SCHEDULED TO REMAIN.
10. REMOVE PARTIAL EXISTING CMU PARTITION FOR NEW DOOR OPENING
11. INSPECT EXISTING WAREWASH COUNTER DOOR AND S.S. PASS-THRU WINDOW CHUTE. REPAIR REPLACE DAMAGED COMPONENTS. CLEAN, LUBRICATE AND RE-INSTALL.
12. EXISTING CARD READER ACCESS TO REMAIN
13. EXISTING WINDOW TO REMAIN
14. REMOVE EXISTING KITCHEN EQUIPMENT THROUGHOUT KITCHEN INCLUDING WALK-IN COOLER / FREEZER AND CONDENSING UNIT LOCATED IN ADJACENT ROOM OR OUTSIDE OF THE BUILDING. VERIFY WITH OWNER FOR RELOCATION TO WAREHOUSE. SOME EQUIPMENT IS TO BE RE-USED IN TEMPORARY SERVING LINES. SEE ALSO GENERAL DEMOLITION NOTE 6.
15. REMOVE EXISTING FRP AND PREP FOR NEW TILE FINISH.
16. COORDINATE REMOVAL AND STORAGE OF ANY EXISTING FURNITURE ITEMS WITH OWNER . SEE ALSO GENERAL DEMOLITION NOTE 5.
17. REMOVE EXISTING SOAP AND PAPER TOWEL DISPENSER AND RETURN TO OWNER
18. EXISTING WALL MOUNTED ACCESSORIES SIGNS, DISPLAY BOARDS, AND MATS TO BE REMOVED BY FORT BEND ISD (VERIFY EQUIPMENT - IF ANY).
19. REMOVE EXISTING SURFACE MOUNTED FIRE EXTINGUISHER. RE-INSTALL AFTER NEW FINISH APPLIED.
20. REMOVE EXISTING ACOUSTIC CEILING TILE CEILNG SYSTEM AND LIGHT FIXTURES, HVAC DEVICES, SENSORS, ETC. THROUGHTOUT RENOVATED AREAS. PREP FOR NEW SUSPENDED CEILING. EXISTING SPRINKLE SYSTEM TO REMAIN AS-IS UNLESS ROOM CONFIGURATION HAS CHANGED IN NEW DESIGN. PROTECT RECESSED SPRINKLER HEADS AND - RE-INSTALL IN NEW CEILING.
21. REMOVE EXISTING CASEWORK/SHELVING
22. EXISTING CERAMIC WALL TILE TO REMAIN. PROTECT FROM DAMAAGE.
23. REMOVE EXISTING COAT HANGER / ROD / SHELF
24. REMOVE EXISTING PLUMBING FIXTURES IN RESTROOMS. RE: PLUMBING FOR NEW FIXTURES.
25. REMOVE EXISTING UTILITY SINK. RE: PLUMBING FOR NEW PLUMBING FIXTURES.
26. REMOVE EXISTING MOP HOLDER. REPLACE WITH NEW UNIT AS SPECIFIED.
27. REMOVE EXISTING WALL MOUNTED CLEANING SOLUTION DISPENSER (BY FBISD VENDOR)
28. HOOD TO REMAIN - SEE GENERAL DEMOLITION NOTE 10.
29. HOOD TO REMAIN - SEE GENERAL DEMOLITION NOTE 10.
30. REMOVE FLOORING IN THIS AREA FOR NOTE 1.
31. REMOVE CARTIDGE FILTER AND WATER PURTICATION CABNET

## DEMOLITION LEGEND

- EXISTING PARTITION TO REMAIN
- REMOVE EXISTING PARTITION
- EXISTING CMU PARTITION
- REMOVE DOOR AND FRAME TO REMAIN
- REMOVE EXISTING DOOR AND FRAME
- EXISTING PLUMBING FIXTURES (WATER CLOSET, HAND LAVATORY, AND MOP SINK TO BE REMOVED. RE: PLUMBING DRAWINGS.
- EXISTING ACOUSTIC CEILING TILE AND GRID TO BE REMOVED. RE: ELECTRICAL DRAWINGS.
- SPRINKLER HEAD (RECESSED)
- CLOCK
- CEILING MOUNTED SPEAKERS




1 DEMOLITION FLOOR PLAN
SCALE: 1/4" = 1'-0"




2 DEMOLITION REFLECTED CEILING PLAN
SCALE: 1/4" = 1'-0"

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\A-Austin Parkway ES\a-D 101 DEMO PLAN.dwg Jul 23, 2025 - 3:51pm

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL
REGISTERED ARCHITECT
MELISSA A. MARTIN
23651
STATE OF TEXAS
7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

DEMO PLANS

a-D.101



PHOTO D1




PHOTO D2



PHOTO D3




PHOTO D4



PHOTO D5




PHOTO D6



PHOTO D7



PHOTO D8



PHOTO D9




PHOTO D10




PHOTO D11




PHOTO D12




PHOTO D13


PHOTO D14



PHOTO D15



PHOTO D16




PHOTO D17



PHOTO D18



PHOTO D19



PHOTO D20

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL
REGISTERED ARCHITECT
ROBERT A. MAGNUSON
22651
STATE OF TEXAS
7/15/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
DEMO PLAN PHOTOS
a-D01-02

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\A-Austin Parkway ES\a-D01-02 DEMO PLAN PHOTOS.dwg Jul 23, 2025 - 3:51pm




PHOTO D21



PHOTO D22




PHOTO D23




PHOTO D24




PHOTO D25



PHOTO D26




PHOTO D27




PHOTO D28




PHOTO D29




PHOTO D30

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL
REGISTERED ARCHITECT
#29651
STATE OF TEXAS
7/15/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
DEMO PLAN PHOTOS
a-D01-03

F:\2022\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\A-Austin Parkway ES\a-D01-03 DEMO PLAN PHOTOS.dwg Jul 23, 2025 - 3:51pm

## NEW PANEL

## TEMP KITCHEN

### PANEL LTK


150A MCB
208Y/120V, 3ø, 4 WIRE

AVAILABLE FAULT: <10,000A
SCCR & AIC: 10,000A


MOUNTING: SURFACE

| NOTES | EQUIP. NO. | LOAD | DESCRIPTION | WIRE | CB | CKT | A | B | C | CKT | CB | WIRE | DESCRIPTION | LOAD | EQUIP. NO. | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E810 | 2766 | HOT WELLS | 2–12 | 20/2GFI | 1 | ■ | | | 2 | 20/1 | 3–12 | TRANSPORT CART | 1920 | E806 | |
| | | – | – | +12G | – | 3 | | ■ | | 4 | 20/1 | 3–12 | TRANSPORT CART | 1920 | E806 | |
| | E810A | 1643 | HOT WELLS | 2–12 | 20/2GFI | 5 | | | ■ | 6 | 20/1 | 3–12 | TRANSPORT CART | 1920 | E806 | |
| | | – | – | +12G | – | 7 | ■ | | | 8 | 20/1 | 3–12 | TRANSPORT CART | 1920 | E806 | |
| | E810B | 600 | COLD PAN | 3–12 | 20/1GFI | 9 | | ■ | | 10 | 20/1 | 3–12 | 2 REC | 360 | E800A | |
| | E810C | 1200 | BEVERAGE | 3–12 | 20/1GFI | 11 | | | ■ | 12 | 20/1 | 3–12 | 2 REC – DESK | 360 | E800B | |
| | E810C | 1200 | BEVERAGE | 3–12 | 20/1GFI | 13 | ■ | | | 14 | 20/1 | 3–12 | 2 REC | 360 | E800A | |
| | E811 | 180 | CASH REGISTER | 3–12 | 20/1GFI | 15 | | ■ | | 16 | 20/1 | 3–12 | 3 REC | 360 | E800A | |
| | E810B | 600 | COLD PAN | 3–12 | 20/1GFI | 17 | | | ■ | 18 | 20/1 | 3–12 | TEMP. KITCHEN LTS/FAN | 566 | | |
| | E810A | 1643 | HOT WELLS | 2–12 | 20/2GFI | 19 | ■ | | | 20 | 20/1 | | SPARE | | | |
| | | – | – | +12G | – | 21 | | ■ | | 22 | 20/1 | | SPARE | | | |
| | E810 | 2766 | HOT WELLS | 2–12 | 20/2GFI | 23 | | | ■ | 24 | 20/1 | | SPARE | | | |
| | | – | – | +12G | – | 25 | ■ | | | 26 | 20/1 | | SPARE | | | |
| | E808 | 1622 | HEATED CABINET | 2–12 | 20/2 | 27 | | ■ | | 28 | 20/1 | | SPARE | | | |
| | | – | – | +12N+12G | – | 29 | | | ■ | 30 | 20/1 | 3–12 | EXISTING CIRCUIT | 500 | | 3 |
| | E809 | 984 | REFRIGERATOR | 3–12 | 20/1 | 31 | ■ | | | 32 | 20/1 | 3–12 | EXISTING CIRCUIT | 500 | | 3 |
| | E808 | 1622 | HEATED CABINET | 2–12 | 20/2 | 33 | | ■ | | 34 | 15/2 | 2–12 | EXISTING CIRCUIT | 1000 | | 3 |
| | | – | – | +12N+12G | – | 35 | | | ■ | 36 | – | +12N+12G | – | – | | |
| | E809 | 984 | REFRIGERATOR | 3–12 | 20/1 | 37 | ■ | | | 38 | 20/2 | 2–12 | EXISTING CIRCUIT | 1000 | | 3 |
| | | | SPARE | | 20/1 | 39 | | ■ | | 40 | – | +12N+12G | – | – | | |
| | | | SPARE | | 20/1 | 41 | | | ■ | 42 | 50/2 | 2–8 | EXISTING CIRCUIT | 5000 | | 3 |
| | | | SPARE | | 20/1 | 43 | ■ | | | 44 | – | +8N+10G | – | – | | |
| TOTAL LOAD @ 100% = 35498VA | | | | | | TOTAL LOAD @ 100% = 99A | | | | | | | | | | |


1. REF. KITCHEN CONSULTANT'S "FS" DRAWINGS FOR KITCHEN EQUIPMENT NUMBERS.
2. A DEMAND FACTOR PERCENT OF 65% HAS BEEN APPLIED TO THE KITCHEN EQUIPMENT LOAD PURSUANT TO NEC 220–20 AND NEC TABLE 220–20.
3. IDENTIFY ANY CIRCUITS OR PARTIAL CIRCUITS THAT EXTEND BEYOND THE AREA OF RENOVATION. PROVIDE TEMPORARY FEED TO MAINTAIN ALL CIRCUITS SERVING ELEMENTS/SPACES NOT TO BE REMOVED DURING CONSTRUCTION. RECONNECT EXISTING CIRCUITS/DEVICES TO REMAIN TO TEMPORARY KITCHEN PANEL ONCE AVAILABLE USING CB(S) PROVIDED. ALL PARTIAL CIRCUITS SHALL REMAIN AND REMAIN ACTIVE BOTH DURING AND AFTER CONSTRUCTION.




**T1** **TEMPORARY KITCHEN - LIGHTING PLAN**
SCALE: 1/4" = 1'– 0"




**T2** **TEMPORARY KITCHEN - ELECTRICAL PLAN**
SCALE: 1/4" = 1'– 0"




**1** **DEMOLITION FLOOR PLAN**
SCALE: 1/8" = 1'– 0"

## ELECTRICAL KEYED NOTES

GENERAL NOTES:

- CUT WALLS AS REQUIRED TO FLUSH MOUNT NEW DEVICES IN EXISTING WALLS. PATCH/REPAIR WALLS TO MATCH.

DEMOLITION NOTES:

A. EXISTING STANDBY GENERATOR PANEL TO REMAIN.

B. EXISTING KITCHEN PANELS TO BE REPLACED WITH NEW. MODIFY EXISTING WALLS TO MATCH NEW PANEL LAYOUTS AND DIMENSIONS.

C. EXISTING LIGHTING FIXTURES AND CEILING DEVICES TO BE REMOVED THROUGHOUT.

D. EXISTING WALK–IN COOLER/FREEZER AND ASSOCIATED EQUIPMENT TO BE REMOVED.

E. EXISTING WALL ELECTRICAL DEVICES TO BE REMOVED. EXISTING J–BOXES MAY BE REUSED WHERE NEW DEVICES ARE TO BE INSTALLED AT THE SAME LOCATIONS.

F. EXISTING ELECTRICAL DEVICES TO BE REMOVED.

G. NEW 208Y/120V PANEL AND TRANSFORMER FOR TEMPORARY KITCHEN TO BE INSTALLED PRIOR TO DEMOLITION. PANEL AND TRANSFORMER TO BE REMOVED AT END OF KITCHEN RENOVATION AND TURNED OVER TO THE DISTRICT. INSTALL TRANSFORMER ON PREMADE FIBERCRETE PAD AND WAFFLE TYPE VIBRATION ISOLATION PADS. DO NOT PROVIDE A POURED IN PLACE CONCRETE PAD AT THIS LOCATION.

H. PROVIDE RECEPTACLES AND LIGHT FIXTURES FOR TEMPORARY KITCHEN DURING RENOVATION. ALL TEMPORARY DEVICES AND EQUIPMENT TO BE REMOVED AT END OF KITCHEN RENOVATION AND OFFERED TO THE OWNER AS SALVAGE.

I. CONDUITS ROUTED FROM TEMPORARY KITCHEN WALL AND BENEATH SERVING LINE. PROVIDE MULTICHANNEL ROLLOVER CABLE PROTECTOR FOR EXPOSED CONDUITS NOT UNDER THE SERVING LINE. ALL CONDUITS UNDER THE SERVING LINE SHALL BE SECURED TO/ROUTED ON TOP OF UNISTRUT AND NOT DIRECTLY ON THE FLOOR. DO NOT ANCHOR UNISTRUT TO THE EXISTING FLOORING. COORDINATE POWER AND DATA OUTLET LOCATIONS WITH OTHER TRADES.

J. REMOVE EXISTING LIGHT FIXTURES ABOVE NEW KITCHEN EXTENSION. MODIFY EXISTING WIRING TO MAINTAIN REMAINING FIXTURE OPERATION.

K. HARDWIRE KITCHEN EQUIPMENT TO LOCAL ON/OFF SWITCH. TYPICAL.

L. SURFACE MOUNT FIXTURES ON TEMPORARY KITCHEN CEILING. TYPICAL.

M. WIRE TEMPORARY KITCHEN FAN TO LOCAL LIGHTING CIRCUIT AND CONTROLS. FAN SHALL BE ON/OFF WITH LIGHTS.

N. EXISTING EXTERIOR LIGHT FIXTURES TO BE REMOVED.

O. PROVIDE NEW FIRE ALARM DEVICES AS PART OF THE TEMPORARY KITCHEN BUILDOUT.

P. PROVIDE NEW TEMPORARY LIGHT FIXTURES IN THE EXISTING CAFETERIA CEILING ABOVE THE SERVING LINE. COORDINATE LOCATIONS WITH TEMPORARY SERVING LINE AND EXISTING CONDITIONS. CONNECT TO EXISTING LIGHTING CONTROLS/CIRCUIT. ALL TEMPORARY LIGHT FIXTURES SHALL BE REMOVED AT THE END OF KITCHEN RENOVATION AND OFFERED TO THE OWNER AS SALVAGE. PROVIDE REPLACEMENT CEILING TILES.

Q. PROVIDE IN–USE WEATHERPROOF COVER FOR RECEPTACLE.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL DEMO AND TEMP PLANS

a-ED.100


STANTON ENGINEERING GROUP
INFO@STANTON–ENGR.COM (713) 300–6080


TEXAS ENGINEERING FIRM REGISTRATION NO. F–01833 © 2025 ALL RIGHTS RESERVED


1300 W. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77043

## DEMOLITION KEYED NOTES

D1 EXISTING CLEAN OUT SHALL BE REPLACED WITH NEW. CHIP OUT SLAB AROUND CLEANOUT TO REMOVE.

D2 EXISTING FLOOR DRAIN SHALL BE REPLACED WITH NEW, INCLUDING P-TRAP. CHIP OUT SLAB AROUND DRAIN TO REMOVE FLOOR DRAIN AND EXISTING P-TRAP.

D3 CUT AND CAP EXISTING HW/CW FOR FUTURE EXTENSION. DEMOLISH ALL PIPING WITHIN KITCHEN. DEMOLITION SHALL BE DELAYED UNTIL NEW CW MAIN AND HW PIPING LOOP IS INSTALLED IN PARALLEL. CW/HW SERVICE TO THE TEMPORARY KITCHEN SHALL BE UNINTERRUPTED DURING OCCUPIED HOURS. COORDINATE SWITCHOVER FROM EXISTING PIPING TO NEW WITH OCCUPANCY SCHEDULE.

D4 EXISTING FLOOR DRAIN TIED TO GREASE WASTE SYSTEM. DRAIN IS BEING USED FOR TEMPORARY KITCHEN INDIRECT WASTE AND SHALL REMAIN ACTIVE DURING OCCUPIED HOURS. COORDINATE DEMOLITION AND REPLACEMENT WITH TEMPORARY KITCHEN USAGE.


D5 DEMOLISH EXISTING DRAIN A CAP BELOW SLAB.

D6 EXISTING SPACE BEING DEMOLISHED. CAP EXISTING SANITARY MAIN BELOW SLAB AND REMOVE UPSTREAM PIPING. CUT/CHIP OUT SLAB AS REQUIRED AND REPAIR TO MATCH EXISTING.

D7 TEMPORARILY CAP EXISTING SANITARY MAIN BELOW SLAB AND REMOVE UPSTREAM PIPING. CUT/CHIP OUT SLAB AS REQUIRED AND REPAIR TO MATCH EXISTING. PIPING TO BE REPLACED WITH NEW TRUNK AND ADDITIONAL DRAIN BRANCH LINES.

D8 EXISTING CANWASH DRAIN TO REMAIN.

D9 EXISTING CANWASH FAUCET TO REMAIN, ALONG WITH CW CONNECTION FROM ADJACENT MECHANICAL ROOM. DISCONNECT HW IN CEILING PLENUM FOR RECONNECTION TO NEW PIPING LOOP.




# 1 PLUMBING DEMOLITION FLOOR PLAN

SCALE: 1/4" = 1'- 0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL

STATE OF TEXAS
TYLER W. HERRING
106052
LICENSED PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

PLUMBING DEMOLITION FLOOR PLAN

**a-PD1.01**


STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM (713) 300-4080


TEXAS ENG. FIRM REG. NO. F-018332 | © ALL RIGHTS RESERVED



1300 W. SAM HOUSTON PARKWAY S., SUITE 121, HOUSTON, TX 77042

| PHASING CHART FOR ALL SCHOOLS | | |
|---|---|---|
| PHASE 1 | | |
| **SCHOOLS** | **FREEZER START DATE :** | **FREEZER END DATE :** |
| ***AUSTIN PARKWAY ES*** | 11/7/2025 | 5/13/2026 |
| SUGAR MILL ES | | |
| COMMONWEALTH ES | | |
| CONERSTONE ES | | |
| PHASE 2 | | |
| SETTLERS WAY ES | 5/29/2026 | 10/28/2026 |
| PALMER ES | | |
| SULLIVAN ES | | |
| SIENNA CROSSING ES | | |
| HERITAGE ROSE ES | | |
| **PHASE 3** | | |
| HUNTERS GLEN ES | 3/19/2027 | 3/19/2027 |
| PECAN GROVE ES | | |
| HIGHLANDS ES | | |
| DULLES ES | | |

REFER TO SHEET A-A.201 FOR CODE ANALYSIS

2/a-A.101

1/a-A.301 FLOOR PLAN
1/a-D.101 DEMOLITION PLAN




1 SITE PLAN
SCALE: 1" = 30'-0"

SITE PLAN IS ISSUED FOR INFORMATION ONLY. NO WORK IS SHOWN ON THIS PLAN.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL
REGISTERED ARCHITECT
ROY A. WILLIAMS
23451
STATE OF TEXAS
7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

SITE PLAN

a-A.101

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\A-Austin Parkway ES\a-A.101 SITE PLAN.dwg, Jul 23, 2025 - 3:52pm

**ADOPTED CODES W/ AMENDMENTS OF**

**CITY OF SUGAR LAND, TX**

- 2021 INTERNATIONAL BUILDING CODE
- 2021 INTERNATIONAL RESIDENTIAL CODE
- 2021 INTERNATIONAL PLUMBING CODE
- 2021 INTERNATIONAL MECHANICAL CODE
- 2023 NATIONAL ELECTRIC CODE NFPA 70
- 2021 INTERNATIONAL ENERGY CONSERVATION CODE
- 2021 INTERNATIONAL FUEL GAS CODE
- 2021 INTERNATIONAL FIRE CODE

**INTERIOR WALL AND CEILING FINISH REQUIREMENTS BY OCCUPANCY E:**

**NON SPRINKLED**

INTERIOR EXIT STAIRWAYS AND RAMPS AND EXIT PASSAGEWAYS **A**

CORRIDORS AND ENCLOSURE FOR EXIT ACCESS STAIRWAYS AND RAMPS **B**

ROOMS AND ENCLOSED SPACES **C**

**FLOORING SHALL BE CLASS II**

**2021 INTERNATIONAL EXISTING BUILDING CODE**

301.3.1 PRESCRIPTIVE COMPLIANCE METHOD. REPAIRS, ALTERATIONS, ADDITIONS AND CHANGES OF OCCUPANCY COMPLYING WITH CHAPTER FIVE OF THIS CODE IN BUILDINGS COMPLYING WITH THE INTERNATIONAL FIRE CODE SHALL BE CONSIDERED IN COMPLIANCE WITH THE PROVISIONS OF THIS CODE.

302.3 EXISTING MATERIALS. MATERIALS ALREADY IN USE IN A BUILDING IN COMPLIANCE WITH REQUIREMENTS OR APPROVALS IN EFFECT AT THE TIME OF THEIR ERECTION OR INSTALLATION SHALL BE PERMITTED TO REMAIN IN USE UNLESS DETERMINED BY THE BUILDING OFFICIAL TO BE UNSAFE .

302.4 NEW AND REPLACEMENT MATERIALS. EXCEPT AS OTHERWISE REQUIRED OR PERMITTED BY THIS CODE, MATERIALS PERMITTED BY THE APPLICABLE CODE FOR NEW CONSTRUCTION SHALL BE USED. LIKE MATERIALS SHALL BE PERMITTED FOR REPAIRS AND ALTERATIONS, PROVIDED THAT NO UNSAFE CONDITION IS CREATED. HAZARDOUS MATERIALS SHALL NOT BE USED WHERE THE CODE FOR NEW CONSTRUCTION WOULD NOT PERMIT THEIR USE IN BUILDINGS OF SIMILAR OCCUPANCY, PURPOSE AND LOCATION.

**ALTERATION - LEVEL 1** INCLUDE THE REMOVAL AND REPLACEMENT OR THE COVERING OF EXISTING MATERIALS, ELEMENTS, EQUIPMENT, OR FIXTURES USING NEW MATERIALS, ELEMENTS, EQUIPMENT, OR FIXTURES THAT SERVE THE SAME PURPOSE.

**ALTERATION - LEVEL 2** INCLUDE THE ADDITION OR ELIMINATION OF ANY DOOR OR WINDOW, THE RECONFIGURATION OR EXTENSION OF ANY SYSTEM, OR THE INSTALLATION OF ANY ADDITIONAL EQUIPMENT, AND SHALL APPLY WHERE THE WORK IS EQUAL TO OR LESS THAN 50% OF THE BUILDING AREA.


## FIRE RESISTIVE RATINGS

| | |
|---|---|
| EXTERIOR NON-LOAD BEARING WALLS | NON-COMBUSTIBLE |
| STRUCTURAL FRAME: | |
| COLUMNS | 2 HOURS (W6x16 MIN SIZE UL#X722) (4"ø PIPE UL#X751) |
| BEAMS | 1 HOUR (W6x16 MIN SIZE UL#P901) |
| ROOF/CEILING ASSEMBLYS | 1 HOURS |
| TYPICAL | UL# P255 |
| CLERESTORY | UL# P255 |
| CAFETORIUM | UL# P255 |
| MECHANICAL ROOM | UL# P255 |
| PERMANENT PARTITIONS | |
| EXIT/ACCESS CORRIDOR | 1 HOUR UL#U427 |
| OCCUPANCY SEPERATION CMU WALLS | 2 HOURS UL#U906 |

## RESPONSIBILITY MATRIX

| ITEM | | | | CONTRACTOR RESPONSIBLITY | | OWNER RESPONSIBILITY | | NOTES |
|---|---|---|---|---|---|---|---|---|
| **EQUIPMENT** | **MAKE** | **MODEL** | **BASIS OF DESIGN** | FURNISHED | INSTALL | FURNISHED | INSTALL | |
| MARKERBOARD | | | MUST BE MAGNETIC, LOW GLOS, WHITE, NO GREY ALLOWED, 5' X 10' | X | X | | | |
| MOTORIZED FOLDING PARTITION | | | TOP SUPPORTED AND CONTINUOUSLY HINGED, MADE OF 3" THICK STEEL WITH FULL SOUND SEALS. THEY FEATURE AUTOMATIC FLOOR SEALS THAT DEPLOY WHEN POSITIONED. MARKERBOARD FINISHES ARE SUGGESTED FOR CLASSROOM USE. LARGE PARTITIONS SHOULD BE ELECTRONICALLY OPERATED, INTEGRATED WITH THE SCHOOL SYSTEM, AND SUPPORTED FROM THE BOTTOM IN A RECESSED MANNER. | X | X | | | |
| PAPER TOWEL DISPENSER | | | 1 PAPER TOWEL DISPENSER PER SINK | | | X | X | |
| SOAP DISPENSER | | | 1 SOAP DISPENSER PER SINK | | | X | X | |
| COMMERCIAL WASHER | GE | GTW790CPLDG | STAINLESS STEEL, ASTM A666, TYPE 304 WITH NUMBER 4 FINISH. ELECTRIC, 480 VOLTS, 40 LB CAPACITY, MINIMUM EXTRACTOR FORCE 140 G FACTOR. | X | X | | | |
| COMMERCIAL DRYER | GE | GTD75ECPLDG | HEAVY DUTY EMBOSSED STEEL WITH ELECTROSTATICALLY APPLIED BACKED ENAMEL FINISH. | X | X | | | |
| MOP RACK | | | BROOM AND MOP HANGGERS FOR A MINIMUM OF TWELVE (12) HANGERS TO BE PROVIDED IN THE CONTRACT | X | X | | | |
| KITCHEN MENU SYSTEM DEVICE | | | RE: J-QF1.0 SF EQUIPMENT PLAN | X | X | | | REFERED TO IT DRAWINGS |
| LOCKERS | | | 12"W X 15"D, 2 TIER, 60" HIGH. 16 GA. DOOR WITH 20GA. BODY | X | X | | | |
| MIRROR | | | TOP EDGE 74 INCHES (1880 MM) MINIMUM ABOVE THE FINISH FLOOR OR GROUND & BOTTOM EDGE OF THE REFLECTING SURFACE 40 INCHES (1015 MM) MAXIMUM | X | X | | | |
| GRAB BARS | | | AS REQUIRED BY ADA | X | X | | | |
| HOOKS | | | J-HOOKS | X | X | | | |
| TIME CLOCK | KRONOS | | EXISTING UNIT | | X | | | COORDINATE HEIGHT, DATA, POWER AND ROUGH-IN REQUIREMENTS WITH FBISD IT. REMOVE, PROTECT & REINSTALL EXISTITING TIME CLOCK. |
| **KITCHEN OFFICE FURNITURE** | | | | | | | | |
| AUSTIN PARKWAY ES | | | | | | X | X | |
| PECAN GROVE ES | | | | | | X | X | |
| SETTLERS WAY ES | | | | | | X | X | |
| SUGAR MILL ES | | | | | | X | X | |
| HIGHLANDS ES | | | | | | X | X | |
| PALMER ES | | | | | | X | X | |
| HUNTERS GLEN ES | | | | | | X | X | |

# 2 CODE ANALYSIS




1 OVERALL FLOOR PLAN
SCALE: 1/16" = 1'-0"

01
Main Bldg
81,730 SF

1st
80,437 SF

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL
REGISTERED ARCHITECT
ROBERT A. MEYER
22651
STATE OF TEXAS
7/15/2025



ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

OVERALL FLOOR PLAN

a-A.201

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\A-Austin Parkway ES\a-A.201 FLOOR PLAN.dwg Jul 23, 2025 - 3:52pm




1 TECHNOLOGY DEMOLITION FLOOR PLAN
a-TD201 1/4" = 1'-0"

**TECHNOLOGY DEMOLITION PLAN GENERAL NOTES**

1. ALL DATA, VOICE, VIDEO AND SECURITY SYSTEMS SHALL REMAIN OPERATIONAL AT ALL TIMES DURING BUSINESS HOURS UNLESS OTHERWISE NOTED. ANY SYSTEM DOWNTIME SHALL BE SCHEDULED WITH THE ARCHITECT/ENGINEER AND OWNER AT LEAST TEN (10) WORKING DAYS IN ADVANCE. CONTRACTOR SHALL DEVELOP A PHASING PLAN AND SCHEDULE OF ANY REQUIRED SYSTEM DOWNTIME FOR REVIEW AND APPROVAL BY THE ARCHITECT/ENGINEER AND OWNER PRIOR TO ANY CONSTRUCTION ACTIVITIES.
2. OWNER SHALL BE RESPONSIBLE FOR POWER DOWN AND START-UP OF ALL DATA, VOICE, VIDEO AND SECURITY SYSTEMS. CONTRACTOR SHALL COORDINATE WITH THE ARCHITECT/ENGINEER AND OWNER AND PROVIDE A MINIMUM OF TEN (10) WORKING DAYS NOTICE FOR SCHEDULING OF ANY REQUIRED DOWNTIME.
3. ALL EXISTING WIRELESS ACCESS POINTS ARE TO BE REMOVED AND RETURNED TO OWNER. CONTRACTOR SHALL RE-INSTALL ALL EXISTING AND NEW WIRELESS ACCESS POINTS AT COMPLETION OF PROJECT.
4. COORDINATE REMOVAL OF EXISTING CAMERA WITH OWNER/ARCHITECT DURING CONSTRUCTION.

**TECHNOLOGY DEMOLITION PLAN KEYED NOTES**

**NOT ALL KEYED BELOW APPLY TO THIS SHEET**

(1) EXISTING DATA/VOICE/WIRELESS ACCESS POINT OUTLET TO BE REMOVED. CONTRACTOR SHALL REMOVE AND DISPOSE OF ALL 4-PAIR CABLES AND WORKSTATION CONNECTING HARDWARE TERMINATED AT THIS LOCATION. IF LOCATION IS NOT RE-USED, CONTRACTOR SHALL SUPPLY AND INSTALL BLANK COVER. CONTRACTOR IS TO REMOVE EACH CABLE TO BE DEMOLISHED FROM THE PATCH PANEL OR TERMINATION BLOCK IN THE TELECOMMUNICATIONS ROOM. REMOVE THE ENTIRE LENGTH OF THE CABLE AND THE CORRESPONDING MODULAR CONNECTOR, FACEPLATE AND ACCESSORIES. NO ABANDONED CABLING IS TO BE LEFT ABOVE CEILING. CONTRACTOR SHALL INSTALL ALL EXISTING AND NEW WIRELESS ACCESS POINTS AT COMPLETION OF PROJECT.

(2) EXISTING VIDEO SURVEILLANCE CAMERA. CONTRACTOR SHALL REMOVE AND RETURN TO OWNER.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 564070
EXPIRES 12-31-25
RCDD

07/18/2025

MWA ARCHITECTS


ARCHITECTS
AND PLANNING
CONSULTANTS

11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY DEMOLITION FLOOR PLAN

SHEET NO.
a-TD201




1 SLAB DEPRESSION PLAN
SCALE: 1/4" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL
7/15/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

SLAB DIMENSION CONTROL PLAN
a-A.300

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\A-Austin Parkway ES\a-A.200 SLAB DIMENSION CONTROL PLAN.dwg Jul 23, 2025 - 3:52pm

## FLOOR PLAN - GENERAL NOTES

1. REFER TO SHEET FOR GENERAL NOTES. GENERAL NOTES APPLY TO ALL SCHOOL KITCHENS.
2. REFER TO SHEET FOR PARTITION TYPES.
3. EXIXSTING EXPOSED CONDUITS AND DATA CABLING IN WIREMOLD TO BE ROUTED INSIDE WALLS (EXCEPT AT WAREWASH AREA BELOW TABLE HEIGHT AND DRY STORAGE ROOMS). PATCH AND REPAIR AS REQUIRED TO ACHIEVE SMOOTH CLEAN WALL SURFACE.

## PARTITION LEGEND

- EXISTING CMU PARTITION
- NEW CMU SCHEDULED PARTITION
- EXISTING METAL PARTITION
- NEW FRAMED SCHEDULED PARTITION

REFER TO SHEET FOR PARTITION TYPES

## FLOOR PLAN - KEYED NOTES

(NOT ALL NOTES USED ON EACH SHEET)

01 PROVIDE NEW MOP SINK UTILITY SHELF
RE: PLUMBING FOR MOP SINK
RE: SPEC 10 28 00 FOR UTILITY SHELF

02 REMOVE, STORE & REPLACE WALL MOUNTED FIRE EXTINGUISHER

03 PROVIDE NEW WALL MOUNTED FIRE EXTINGUISHER
RE: SPEC SECTIONS 10 44 13

04 PROVIDE NEW LOCKERS
RE: SPEC 10 51 13.

05 PROVIDE WASHER AND DRYER
RE: SPEC 11 45 20

06 REMOVE, PROTECT & REINSTALL WALL MOUNTED CLOCK.

07 PROVIDE CONDENSING UNIT
FOR WALK-IN COOLER/FREEZER
RE: MECHANICAL AND SPEC 11 40 00

08 PROVIDE POWER AND DATA FOR MENU BOARD.
RE: ELECTRICAL, TECHNOLOGY DRAWINGS & FOOD SERVICE.


09 PROVIDE P-LAM SHELVING
REFER TO DETAIL FOR BRACKET SUPPORT

10 FURNITURE & NON FOOD SVE EQUIPMENT RETURN TO OWNER FOR STORAGE

11 INSPECT & SREVICE TOLLING COUNTER DOORS. RETURN TO LIKE NEW CONDITION.

12 COMMERCIAL CLOSED WASHER 40LB CAPACITY.
COMMERCIAL CLOSED DRYER 55LB CAPACITY.
BASIS OF DESIGN: WASHER; SPEED QUEEN SYN040
DRYER; SPEED QUEEN ST055.
REFER TO ELECTRICAL & PLUMBING FOR CONNECTIONS.

## 3 FLOOR PLAN NOTES





## 1 KITCHEN PLAN


SCALE: 1/4"=1'-0"

## 2 DOOR SCHEDULE

DOOR SCHEDULE


| DOOR # | DOOR WIDTH | DOOR HEIGHT | DOOR TYPE | DOOR MATERIAL | DOOR FINISH | FIRE RATING | FRAME THICKNESS | FRAME FINISH | KEY | HARDWARE | DETAILS SILL | DETAILS JAMB | DETAILS HEAD | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| A1 | 3'-0" | X 7'-0" | EXIST | EXIST | EXIST | EXIST | EXIST | EXIST | | EX715V | EXIST | EXIST | EXIST | |
| A3 | 3'-0" | X 7'-0" | HM1 | H.M. | H.M. | NR | | H.M. | | 205 | 21/A00-01 | 04/A00-01 | 04/A00-01 | |
| A4 | 3'-0" | X 7'-0" | SF4 | S.C. WOOD | PLAM | NR | | NAT. ANOD. | | 503S | | 22/A00-01 | 16/A00-01 | |
| A5 | 3'-0" | X 7'-0" | SF4 | S.C. WOOD | PLAM | NR | | NAT. ANOD. | | 341 | | 22/A00-01 | 16/A00-01 | |
| A6 | 3'-0" | X 7'-0" | SF4 | S.C. WOOD | PLAM | NR | | NAT. ANOD. | | 501 | | 22/A00-01 | 16/A00-01 | |
| A7 | 3'-0" | X 7'-0" | SF4 | S.C. WOOD | PLAM | NR | | NAT. ANOD. | | 501H | | 22/A00-01 | 16/A00-01 | |
| A8 | 3'-0" | X 7'-0" | SF4 | S.C. WOOD | PLAM | NR | | NAT. ANOD. | | 501H | | 22/A00-01 | 16/A00-01 | |
| 606E | 3'-0" | X 7'-0" | SF4 | S.C. WOOD | PLAM | NR | | NAT. ANOD. | | 103 | | 22/A00-01 | 16/A00-01 | |
| A9 | 3'-0" | X 7'-0" | SF1 | ALUM/GLASS | ALUM/GLASS | NR | | NAT. ANOD. | | 501AH | 18/A00-01 | 10&11/A00-01 | 23&24/A00-01 | |
| A10 | 3'-0" | X 7'-0" | SF1 | ALUM/GLASS | ALUM/GLASS | NR | | NAT. ANOD. | | 501AH | 18/A00-01 | 10&11/A00-01 | 23&24/A00-01 | |




## 4 MAKERBOARD ELEVATION

SCALE: 1/2"=1'-0"




## 5 LOCKER HOUSEKEEPING PAD

SCALE: 3"=1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL
REGISTERED ARCHITECT
KEITH A. MAYER
22651
STATE OF TEXAS
7/15/2025



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

KITCHEN PLAN

a-A.301

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\A-Austin Parkway ES\a-A.301 KITCHEN PLAN.dwg Jul 30, 2025 - 10:44am




## 3 TEMPORARY LAYOUT SECTION

SCALE: 1"=1'-0"

## TEMPORARY KITCHEN FLOOR PLAN KEYED NOTES 04/a-A.302

01 PROVIDE & INSTALL 555 SF OF RAM BOARD TO PROTECT EXISTING FLOORING. REMOVE AFTER CONSTRUCTION IS COMPLETE. CONTRACTOR MUST REPAIR FLOORING DAMAGED DURING CONSTRUCTION.

02 PROVIDE SCHEDULED PARTITIONS. BUILD PARTITIONS ON TOP OF RAM BOARD. DO NOT ATTACH PARTITIONS TO FLOOR.

03 ATTACH PARTITIONS TO EXISTING WALL. REPAIR WALL TO MATCH EXISTING AFTER CONSTRUCTION IS COMPLETE.

## TEMPORARY KITCHEN RCP KEYED NOTES 03/A-A03-02


04 ALL NEW SCHEDULED PARTITIONS AND CEILINGS FOR TEMPORARY STORAGE LAYOUT TO BE EPOXY PAINTED SW 7014 EIDER WHITE WITH SPECIFIED 4" RUBBER BASE. REMOVE WHEN CONSTRUCTION IS COMPLETED.

05 MOUNT TEMPORARY FLUORESCENT LIGHTS TO TEMPORARY CEILING.

## RCP DEVICE LEGEND


| EXISTING TO REMAIN | NEW | DEMO | |
|---|---|---|---|
| S | S | S | CEILING MOUNTED SPEAKERS |
| | | | SECURITY CAMERA |
| W | W | W | WIRELESS ACCESS POINT |
| | | | CEILING MOUNTED FIRE ALARM AND STROBE |
| | | | SMOKE DETECTOR |
| | | | SPRINKLER HEAD (RECESSED) |
| | | | SPRINKLER HEAD (PENDANT) |
| | | | DRYER VENT |
| | | | EXIT |
| | | | CLOCK |

## 4 KEYED NOTES




## 1 TEMPORARY KITCHEN RCP

1/4"=1'-0"




## 2 TEMPORARY KITCHEN FLOOR PLAN

1/4"=1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL
REGISTERED ARCHITECT
ANN ANDERSON
22651
STATE OF TEXAS
7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

TEMPORARY KITCHEN LAYOUT

a-A.302

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\A-Austin Parkway ES\a-A.302 TEMPORARY KITCHEN LAYOUT.dwg Jul 23, 2025 - 3:53pm

## PAINT COLOR SCHEDULE

UNLESS OTHERWISE INDICATED FIELD COLOR IS PT-1 (SW 7014 EIDER WHITE)

SW 7014 EIDER WHITE (EPOXY PAINT)

## WALL TILE


CERAMIC WALL TILE (WT-1)
REFER TO TILE PATTERN AT SERVING AND RESTROOM
FIELD WALL TILE: DALTILE RITTENHOUSE SQUARE K175 BISCUIT (3X6)

## QUARRY TILE

QUARRY TILE AND BASE - SURE-STEP II QQ30
TILE COLOR SELECTION TO BE APPROVED BY FBISD
EPOXY GROUT COLOR: STERLING SILVER BY LATICRETE


A — PROVIDE ROOM SIGN TO REPLACE EXISTING. SEE LAYOUT FOR TYPE A OR TYPE B SIGN LOCATIONS.


## 2 FLOOR FINISH LEGEND




## 3 ROOM SIGNAGE


SCALE: 6"=1'-0"




## 8 LOCKERS ELEVATION


SCALE: 1/4"=1'-0"




WALL TILE PATTERN - RESTROOM

## 4 WALL TILE PATTERN


SCALE: 1/4"=1'-0"




NEW QUARRY TILE TO EXISTING VCT OR LVT FLOORING TRANSITION OCCURS AT CENTERLINE OF DOOR


## 5 FLOOR TRANSITION - THRESHOLD

SCALE: 3"=1'-0"





## 7 UTILITY ELEVATIONS

SCALE: 1/4"=1'-0"





## 6 RR ELEVATIONS

SCALE: 1/4"=1'-0"





## 9 STOREFRONT ELEVATIONS

SCALE: 1/4"=1'-0"





## 10 MOPSINK ELEVATIONS





## 11 SILL @ KITCHEN/DINING

SCALE: 1:1




## 12 STOREFRONT SECTION

SCALE: 1/2"=1'-0"




## 1 FINISH FLOOR PLAN

SCALE: 1/4" = 1'-0"

ALL FINISHED NOT DENOTED IN DRAWINGS SHALL BE SELECTED DURING THE SUBMITTAL PROCESS

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL

7/15/2025



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

FINISH FLOOR PLAN


a-A.501

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\A-Austin Parkway ES\a-A.501 FINISH FLOOR PLAN.dwg Jul 28, 2025 - 5:29pm




## 2 FOOD SERVICE AREA ELEVATION

SCALE: 3/16" = 1'-0"




## 1 REFLECTED CEILING PLAN

SCALE: 1/4" = 1'-0"

## RCP - GENERAL NOTES

1. CEILING GRID SHALL BE INSTALLED TO MATCH EXISTING GRID'S POINT OF ORIGIN. THIS WILL REDUCE NEED TO RE-LOCATE ABOVE CEILING DUCTS, SPRINKLER PIPING AND OTHER SUPPORT SYSTEMS.
2. REFER TO SHEET A00-01 FOR GENERAL NOTES. GENERAL NOTES APPLY TO ALL SEVEN SCHOOL KITCHEN REMODELS.
3. LIGHTING LEVELS SHOULD BE 50 FC IN PREPARATION AREAS, WARE WASH AND SERVING LINES, OR MEET MINIMUM HEALTH CODE LEVELS, WHICHEVER ITS GREATER. SEE MEP PLANS
4. REPLACE HVAC DEVICES. REPLACE LIGHTING WITH 24"x24" LED LAY IN LIGHT AS SCHEDULED IN ELECTRICAL PLANS.
5. REFER TO MECHANICAL, ELECTRICAL SHEETS FOR DEVICE SCHEDULES.

## RCP - NUMBERED NOTES

01 PROVIDE 30"x30" MIN. ACCESS HATCH IN SOFFIT CENTERED ON MOTOR.

02 AFTER LOWERING THE NEW POWER RETRACTION SYSTEM. REPAIR AND PAINT SOFFITS AND SIDWALLS OF FURR TO MATCH EXISTING.

## NEW RCP LEGEND

PROVIDE NEW VINYL FACED ACOUSTIC CEILING TILE AND GRID AS SPECIFIED (CLEAN ROOM VL NO. 868 BY ARMSTRONG) RE: SPEC 09 51 13 AND MEP DRAWINGS.

DEMOLISH EXISTING CEILING GRID AND ACOUSTIC TILES. SALVAGE OR REPLACE EXISTING DEVICES AND LIGHTS AS PER SCHEDULE AND NOTES.

9'-6" ACOUSTIC CEILING TILE CEILING HEIGHT - MATCH EXISTING.

## MISC. DEVICE LEGEND

| EXISTING TO REMAIN | NEW | DEMO | |
|---|---|---|---|
| (S) | (S) | | CEILING MOUNTED SPEAKERS |
| | | | SECURITY CAMERA |
| (W) | (W) | | WIRELESS ACCESS POINT |
| | | | CEILING MOUNTED FIRE ALARM AND STROBE |
| | | | SMOKE DETECTOR |
| | | | SPRINKLER HEAD (RECESSED) |
| | | | SPRINKLER HEAD (PENDANT) |
| | | | DRYER VENT |
| | | | EXIT |

## RCP HVAC LEGEND

| EXISTING TO REMAIN | NEW | DEMO | |
|---|---|---|---|
| | | | LAY-IN CEILING DIFFUSER |
| | | | LAY-IN CEILING RETURN / FAN |
| | | | HARD CEILNG DIFFUSER |
| | | | HARD CEILNG RETURN / FAN |

## RCP LIGHT LEGEND

| EXISTING TO REMAIN | NEW | DEMO | |
|---|---|---|---|
| | | | 2x2 LAY IN LIGHT FIXTURE |
| | | | 2x4 LAY IN LIGHT FIXTURE |
| | | | 1X4 SURFACE MOUNTED UTILITY LIGHT FIXTURE WITH PROTECTIVE CAGE |

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL

REGISTERED ARCHITECT
ROBERT A. WEBB
22651
STATE OF TEXAS

7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

REFLECTED CEILING PLAN

a-A.401

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\A-Austin Parkway ES\a-A.401 REFLECTED CEILING PLAN.dwg Jul 23, 2025 - 3:54pm

1. AT WALLS THAT TERMINATE ABOVE CEILING, CONTRACTOR MAY CONTINUE METAL STUD FRAMED WALLS TO UNDERSIDE OF METAL DECK AND OMIT DIAGONAL BRACING IF HEIGHT DOES NOT EXCEED LIMITING HEIGHT OF METAL STUD AS INDICATED ON CHART BELOW.

2. PROVIDE INTERMEDIATE BRACING AT ALL PARTITIONS THAT EXCEED LIMITING HEIGHT OF METAL STUDS AS INDICATED ON CHART BELOW.

3. ALL BRACING SHALL BE AT STUD POINTS.


CMU PARTITION NOTES:

1. MATCH EXISTING CMU COURSING.(TYP.):
   BRIARGATE ES (4" CMU STARTER COURSE)
   LAKE OLYMPIA MS (4" CMU STARTER COURSE)
   MISSION BEND ES (8" CMU STARTER COURSE)
   RIDGEMONT ES (8" CMU STARTER COURSE)
   TOWNEWEST ES (8" CMU STARTER COURSE)
2. PROVIDE CMU LINTELS FOR ALL OPENINGS IN INTERIOR CMU PARTITIONS. COORDINATE WITH STRUCTURAL.
3. PROVIDE A 3/4" SPACE BETWEEN TOP OF CMU AND STRUCTURE/DECK FOR POTENTIAL DEFLECTION. SEAL WITH APPROPRIATE CAULK.
4. REFER TO FINISH SCHEDULES FOR CERAMIC TILE LOCATIONS.


GYPSUM WALLBOARD PARTITION NOTES:

1. ALL METAL STUDS PARTITIONS ARE 25 GAUGE METAL STUDS AT 16" O.C. UNLESS OTHERWISE NOTED. IF THE LIMITING HEIGHT FOR A PARTITION TYPE IS EXCEEDED, INCREASE SIZE AND/OR GAUGE OF METAL STUDS AS INDICATED ON "LIMITING HEIGHT OF METAL STUDS" TABLE. NOTIFY THE ARCHITECT PRIOR TO INSTALLATION.


| LIMITING HEIGHT OF METAL STUDS | | | |
|---|---|---|---|
| STUD SIZE | SPACING | 25 GA. | 20 GA. |
| 2-1/2" | 16" | 11'-3" | 12'-10" |
| 3-5/8" | 16" | 14'-4" | 16'-5" |
| 6" | 16" | 19'-9" | 24'-6" |





PARTITION A
SCALE: 1-1/2" = 1'-0"




PARTITION B1
SCALE: 1-1/2" = 1'-0"




PARTITION B2
SCALE: 1-1/2" = 1'-0"




PARTITION B3
SCALE: 1-1/2" = 1'-0"




PARTITION B4
SCALE: 1-1/2" = 1'-0"




PARTITION B5
SCALE: 1-1/2" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |

a

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL


FOR
INTERIM REVIEW
AND NOT INTENDED FOR CONSTRUCTION, BIDDING OR PERMIT PURPOSES.


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 05/23/25

PARTITION SCHEDULE

a-A.502




## GENERAL NOTES

1. ALL CONCRETE SHALL TEST 4000 PSI AT 28 DAYS.
2. ALL CONCRETE REINFORCING BARS SHALL CONFORM TO ASTM A615 GRADE 60.
3. DETAILING AND FABRICATION OF CONCRETE REINFORCEMENT AND ACCESSORIES SHALL BE IN ACCORDANCE WITH ACI-315 LATEST EDITION.
4. LAP ALL CONTINUOUS REINFORCING BARS 50 DIAMETERS AT SPLICES, TEES, AND CORNERS.
5. THE USE OF HEAT TO FACILITATE THE BENDING OF REINFORCING BARS WILL NOT BE PERMITTED.
6. NO ENGINEERING DRAWING MAY BE REPRODUCED FOR USE AS SHOP DRAWINGS.
7. CONTRACTOR SHALL COORDINATE ALL LOCATIONS OF ALL ANCHOR BOLTS AND OPENINGS FOR MECHANICAL, PIPING, AND ELECTRICAL EQUIPMENT WITH THE RESPECTIVE ENGINEERING AND VENDOR DRAWINGS.

## SLAB NOTE

4" CONC. SLAB ON 10 MIL POLY FILM ON 2" MAX. SAND FILL. REINFORCE WITH #3 @ 15"c.c. E.W. IN CENTER OF SLAB.

## SLAB SIDEWALK SLAB NOTE

4" CONC. SLAB ON 2" MAX. SAND FILL. REINF. W/ #3 @ 18"c.c. IN CENTER OF SLAB.

## GEOTECHNICAL NOTE:

ALLOWABLE BEARING CAPACITY IS ASSUMED TO BE 1500 PSF AND SHALL BE CONFIRMED PRIOR TO CONSTRUCTION.

## FOUNDATION PLAN

SCALE: 1/4"=1'-0"

## FIELD VERIFICATION NOTE

1. CONTRACTOR SHALL VERIFY ALL DIMENSIONS PRIOR TO FABRICATION OR CONSTRUCTION.
2. CONTRACTOR SHALL VERIFY AND NOTIFY ENGINEER OF EXISTING CONDITIONS IN NEED OF REVIEW AND POSSIBLE MODIFICATION PRIOR TO FABRICATION.

ISSUE:

| | |
|---|---|
| 03/07/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



KEVIN STANLEY 69701 REGISTERED PROFESSIONAL ENGINEER
*July 17, 2025*



STANLEY SPURLING & HAMILTON, INC.
50 Years
Consulting Engineering Services
T.B.P.E. Registration #F-000175
www.sshinc.net
3301 Edloe Street, Suite 200 Houston, Texas 77027 Tel 713-776-9433
E-MAIL: info@sshinc.net | 0002-0256


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

KITCHEN PLAN

S1




## MIN. REBAR LAP SCHEDULE FOR f'm = 1,500 psi

| BAR SIZE | 6" CMU | 8" CMU | 10" CMU | 12" CMU |
|---|---|---|---|---|
| #3 | 12" | 12" | 12" | 12" |
| #4 | 20" | 15" | 12" | 12" |
| #5 | 32" | 23" | 18" | 15" |
| #6 | 54" | 43" | 34" | 28" |
| #7 | NA | 60" | 46" | 38" |
| #8 | NA | 72" | 71" | 57" |
| #9 | NA | NA | 82" | 74" |

## CONCRETE MASONRY NOTES

1. CONCRETE MASONRY UNITS AND CONSTRUCTION TO BE PER "NATIONAL CONCRETE MASONRY ASSOCIATION" RECOMMENDATIONS (WHERE NOT COVERED BY THE LOCAL BUILDING CODE).
2. ALL MASONRY GROUT TO BE PER TABLE 1 (THIS SHEET); ALL MORTAR PER TABLE 2 (THIS SHEET).
3. FILL CELLS WITH GROUT AT VERTICAL REINFORCEMENT.
4. CAST-IN-ANCHORS EMBEDDED IN CONCRETE MASONRY SHALL EXTEND BEYOND REINFORCING 1" MIN.
5. COMPRESSIVE STRENGTH OF MASONRY SHALL BE 1500 PSI AT 28 DAYS.
6. CMU SHALL BE PLACED IN A RUNNING BOND PATTERN UNLESS SPECIFICALLY NOTED OTHERWISE ON THE PLANS.
7. CONTROL JOINTS SHALL HAVE NO HORIZONTAL REINFORCING THROUGH THE JOINT AND VERTICAL REINFORCING ON BOTH SIDES OF JOINT. CONTROL JOINTS SHALL BE UNGROUTED WITH A BACKER ROD AND SEALANT ON BOTH SIDES OF WALL.
8. BOND BEAMS AND REINFORCING SHALL BE CONTINUOUS AT CONTROL JOINT WITH BACKER ROD AND SEALANT CONTINUOUS WITH JOINT.

## CONCRETE BLOCK LINTEL SCHEDULE

| WALL THICKNESS \ MAXIMUM SPAN | 4'-6" | 9'-0" |
|---|---|---|
| 4" | GROUT; 1 COURSE 1~#4 CONT. | #3 STIRRUPS @ 16" c.c.; GROUT 2 COURSES; 1~#4 CONT. |
| 6" & 8" & 12" | GROUT; 1 COURSE 2~#5 CONT. | #3 STIRRUPS @ 16" c.c.; GROUT 2 COURSES; 2~#5 CONT. TOP & BOT. |

## TABLE 1. GROUT PROPORTIONS BY VOLUME

| TYPE | PARTS BY VOLUME OF PORTLAND CEMENT OR PORTLAND BLAST-FURNACE SLAG CEMENT | PARTS BY VOLUME OF HYDRATED LIME OR LIME PUTTY | AGGREGATE MEASURED IN DAMP, LOOSE CONDITION | |
|---|---|---|---|---|
| | | | FINE | COARSE |
| FINE GROUT (<4" WIDE CAVITY) | 1 | 0 TO 1/10 | 2¼ TO 3 TIMES THE SUM OF THE VOLUMES OF THE CEMENTITIOUS MATERIAL | |
| COARSE GROUT (>4" WIDE CAVITY) | 1 | 0 TO 1/10 | 2¼ TO 3 TIMES THE SUM OF THE VOLUMES OF THE CEMENTITIOUS MATERIAL | 1 TO 2 TIMES THE SUM OF THE VOLUMES OF THE CEMENTITIOUS MATERIAL |

## TABLE 2. MORTAR PROPORTIONS BY VOLUME

| MATERIAL | TYPE | PORTLAND CEMENT OR BLENDED CEMENT | MASONRY CEMENT | HYDRATED LIME OR LIME PUTTY | AGGREGATE RATIO (MEASURE IN DAMP, LOOSE CONDITION) |
|---|---|---|---|---|---|
| CEMENT LIME | S | 1 | .... | OVER ¼ TO ½ | NOT LESS THAN 2¼ & NOT MORE THAN 3 TIMES THE SUM OF THE SEPARATE VOLUMES OF CEMENTITIOUS MATERIALS |
| MASONRY/ CEMENT | S | 1/2 | 1 | .... | |


## NOTE: CONTROL JOINTS SHALL BE LOCATED AT THE FOLLOWING

1. AT ALL CHANGES IN WALL HEIGHT.
2. AT ALL CHANGES IN WALL THICKNESS SUCH AS CHASES, COLUMNS OR PILASTERS.
3. AT (ABOVE) MOVEMENT JOINTS IN FOUNDATIONS AND FLOORS.
4. AT (BELOW) MOVEMENT JOINTS IN ROOFS AND FLOORS THAT BEAR ON A WALL.
5. ADJACENT TO CORNERS OF WALLS OR INTERSECTIONS WITHIN A DISTANCE OF ONE-HALF THE NORMAL CONTROL JOINT SPACING.
6. CONTROL JOINTS SHALL BE SPACED NO MORE THAN 25'-0" APART.
7. DO NOT PLACE CONTROL JOINT ABOVE OR BELOW OPENINGS.
8. CONTRACTOR SHALL PROVIDE A CONTROL JOINT PLAN PRIOR TO FABRICATION OR CONSTRUCTION.

## LOOSE LINTEL SCHEDULE

| SPAN | LINTEL | SPAN | LINTEL |
|---|---|---|---|
| 0' TO 6' | L3½x3½x¼ | 8' TO 9' | L5x3½x5/16 |
| 6' TO 7' | L4x3½"x¼ | 9' TO 10' | L6x3½x5/16 |
| 7' TO 8' | L4x3½x5/16 | 10' TO 12' | L7x4x⅜ |

LOOSE LINTEL MIN. BEARING OF 8".




CONTRACTOR SHALL COVER ALL EXPOSED REBAR DURING CONSTRUCTION.

## TYPICAL ELEVATION OF CONCRETE MASONRY WALL AND NOTES

SCALE: N.T.S.

## TYPICAL REBAR CAP DETAIL

SCALE: N.T.S.

ISSUE:

| | |
|---|---|
| 03/07/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

SECTIONS AND TYPICAL DETAILS

S2




*July 17, 2025*


STANLEY SPURLING & HAMILTON, INC.
Consulting Engineering Services
T.B.P.E. Registration # F-000175
www.sshinc.net
50 Years
3301 Edloe Street, Suite 200 Houston, Texas 77027 Tel 713-776-9433
E-MAIL: info@sshinc.net | 0002-0256

# REFER TO FOODSERVICE DESIGN PROFESSIONALS SPECIFICATIONS AND SUBSEQUENT SHEETS FOR ADDITIONAL COORDINATION INFORMATION

**EXISTING EQUIPMENT NOTES (IF EXISTING EQUIPMENT IS PROVIDED IN THIS PROJECT):**

1. EXISTING EQUIPMENT NOT SCHEDULED FOR RE-USE TO BE RELOCATED BY THE K.E.C. COORDINATE WITH OWNER FOR NEW LOCATION.
2. ALL UTILITIES NOT SCHEDULED FOR RE-USE TO BE CAPPED & COVERED BY REQUIRED DISCIPLINE.
3. K.E.C. TO VERIFY ALL EXISTING UTILITY LOCATIONS & COORDINATE WITH ALL EQUIPMENT AS REQUIRED.

8 EXISTING EQUIPMENT NOTES
NOT TO SCALE

**ARCHITECT TO VERIFY/COORDINATE THE AESTHETIC OPTIONS BELOW (FOOD SERVICE COLOR, MATERIAL, OR SIGNAGE SELECTIONS) IF THESE ITEMS ARE PROVIDED IN THIS PROJECT:**

1. COUNTERTOPS: STONE (STAINLESS STEEL IS PROVIDED UNLESS OTHERWISE SPECIFIED).
2. TRAY SLIDES: CORIAN OR STONE (STAINLESS STEEL IS PROVIDED UNLESS OTHERWISE SPECIFIED).
3. COUNTER FRONTS: CERAMIC TILE, 3 FORM, OR PLASTIC LAMINATE.
4. SNEEZE GUARDS: STONE INSETS.
5. GENERAL COLOR, MATERIAL AND GRAPHIC SELECTIONS:
   - A. DISPLAY AIR SCREEN MERCHANDISERS - COLOR SELECTION: POWDER COAT OR PLASTIC LAMINATE (S/S IS PROVIDED UNLESS OTHERWISE SPECIFIED).
   - B. BAKERY DISPLAY CASES - COLOR SELECTION: POWDER COAT OR PLASTIC LAMINATE (S/S IS PROVIDED UNLESS OTHERWISE SPECIFIED).
   - C. PASS THRU OR REACH IN HOLDING CABINETS - COLOR SELECTION: POWDER COAT (MFG.: TRUE) OR PLASTIC LAMINATE (MFG.: TRAULSEN) (S/S IS PROVIDED UNLESS OTHERWISE SPECIFIED).
   - D. HANGING HEAT LAMPS - TRACK AND FIXTURE COLOR SELECTION.
   - E. HEATED MERCHANDISERS.
   - F. PORTABLE GUIDE RAILS - STANCHION AND BELT COLOR SELECTION.
   - G. POPCORN MACHINE - SIGNAGE SELECTION.
   - H. BOTTLE COOLER - SIGNAGE SELECTION.
   - I. GRAPHICS PACKAGE INFORMATION.
   - J. HOT FOOD WELL COVERS.
6. ARCHITECT TO VERIFY/COORDINATE THE FINISHES BELOW:
   - A. WALLS: CERAMIC TILE, FLAT FRP, OR MOLDED FRP (SMOOTH, IMPERVIOUS, AND EASILY CLEANABLE AS APPROVED BY LOCAL JURISDICTION).
   - B. CEILINGS: REMOVABLE VINYL FACE TILE (SMOOTH, IMPERVIOUS, AND EASILY CLEANABLE AS APPROVED BY LOCAL JURISDICTION).
   - C. FLOORS: TILE, EPOXY, OR RUBBERIZED FLOORING SYSTEM (SMOOTH, IMPERVIOUS, EASILY CLEANABLE AND SLIP RESISTANT AS APPROVED BY LOCAL JURISDICTION) (COORDINATE FLOOR TILE TRANSITION AT SERVING LINES).
   - D. FLOORS: WALK-IN ASSEMBLY - EXTEND KITCHEN FLOOR FLUSH INTO WALK-IN ASSEMBLY WITH COVED BASE.
   - E. FURR DOWNS ABOVE SERVING COUNTERS.

5 ARCHITECTURAL COORDINATION NOTES
NOT TO SCALE

**CRITICAL NOTES:**

1. CONTRACTOR MUST COORDINATE AND VERIFY ALL DIMENSIONS WITH FOOD SERVICE EQUIPMENT SHOP DRAWINGS AND MANUFACTURER'S DATA. DIMENSIONS SHOWN ARE FOR DESIGN AND BIDDING PURPOSES ONLY.
2. WALK-IN ASSEMBLY DOORS MUST BE LEFT OPEN WHILE INTERIOR CONCRETE FLOOR CURES.
3. INSTALL PROTECTIVE COVER ON WALK-IN ASSEMBLY WALL PANELS BEFORE INSTALLING CONCRETE FLOORS AND CURBS.
4. REFER TO GENERAL SPECS - DIVISION 27 TO PROVIDE CONDUIT, DATA, AND INTERCONNECT THE PANIC ALARM INSIDE FREEZER TO THE BUILDING AUTOMATION SYSTEM FOR NOTIFICATION TO DISTRICT PERSONNEL IN THE EVENT OF STAFF ENTRAPMENT.
5. PIPING AND DRAINAGE SYSTEMS (SANITARY AND GREASE-LADEN). SYSTEMS MUST BE CLEANED AND FLUSHED BEFORE THE FINAL CONNECTION WITH FOOD SERVICE EQUIPMENT - CRITICAL (DIV. 22).

7 CRITICAL NOTES
NOT TO SCALE

**DIVISION 26 (ELECTRICAL) IS RESPONSIBLE FOR BUT NOT LIMITED TO:**

1. **DO NOT ROUGH IN FROM FDP DRAWINGS. REFER TO THE KITCHEN EQUIPMENT CONTRACTOR'S DIMENSIONED SHOP DRAWINGS. DIMENSIONS INDICATED ARE TO BE VERIFIED BY KITCHEN EQUIPMENT CONTRACTOR AND ADJUSTED AS REQUIRED BY EQUIPMENT AND FIELD CONDITIONS.**
2. SECTION 11 40 00 TO VERIFY UTILITY REQUIREMENTS OF ANY EXISTING EQUIPMENT.
3. ALL CONNECTIONS SHALL BE MADE FOLLOWING LOCAL CODES AND NATIONAL STANDARDS, EXCEPT WHERE PLANS AND SPECIFICATIONS EXCEED THOSE CODES AND STANDARDS.
4. VERIFY ALL ELECTRICAL REQUIREMENTS WITH ENGINEERING DRAWINGS.
5. ROUGH-IN AND FINAL CONNECTION OF ELECTRICAL SYSTEMS TO FOOD SERVICE EQUIPMENT, WALK-IN ASSEMBLIES, AND BETWEEN COMPONENTS (INCLUDING MATERIALS AND LABOR). ACCESSORIES PROVIDED LOOSE WITH FOOD SERVICE EQUIPMENT BY SECTION 11 40 00 TO BE FIELD INSTALLED BY DIVISION 26.
6. EMPTY EMT CONDUIT WITH PULL-WIRE AND WIDE-SWEEP BENDS FOR REFRIGERANT PIPING TO REMOTE FOOD SERVICE EQUIPMENT REFRIGERATION SYSTEMS.
7. EMPTY EMT CONDUIT WITH PULL-WIRE AND WIDE-SWEEP BENDS FOR INTERCONNECT CABLES BETWEEN LAN AND POS TERMINALS, CHANGE-MAKERS, PRE-CHECK UNITS, PRINTERS, CPUS, ETC. DIVISION 26 TO VERIFY WHERE THE CONDUIT IS TO RUN FOR POS SYSTEM (I.E., MANAGER'S OFFICE OR IDF ROOM).
8. EMPTY EMT CONDUIT WITH PULL-WIRE AND WIDE-SWEEP BENDS FOR FIRE SUPPRESSION SYSTEMS. INTERCONNECT FIRE PROTECTION SYSTEM TO PANEL BOX SHUNT TRIPS AND BUILDING ALARM.
9. WALK-IN LIGHT FIXTURE INSTALLATION (PROVIDED LOOSE BY SECTION 11 40 00) (IF WALK-IN IS PROVIDED IN THIS PROJECT).
10. TABLE LIMIT SWITCH INSTALLATION (PROVIDED LOOSE BY SECTION 11 40 00) (IF DISHMACHINE IS PROVIDED IN THIS PROJECT).
11. ELECTRICAL MATERIALS AND DEVICES (SHUNT-TRIP BREAKERS, SURGE PROTECTORS, LIGHTING CONTROL DEVICES, CONDUIT, WIRE, ETC.).
12. SWITCHES AND STAINLESS STEEL DISCONNECTS AS REQUIRED (PROVIDE, LOCATE, AND INSTALL – TO BE IN AN ACCESSIBLE LOCATION).
13. CHARGING STATIONS FOR FORKLIFTS, PALLET STACKERS, AND PALLET JACKS (SIZE, PROVIDE, LOCATE, AND INSTALL) (IF EQUIPMENT IS PROVIDED IN THIS PROJECT).
14. INTERCONNECTION BETWEEN CONDENSATE FAN AND DISHMACHINE CONTROL PANEL (IF EQUIPMENT IS PROVIDED IN THIS PROJECT).
15. INTERCONNECTION BETWEEN EXHAUST HOOD FANS AND SWITCH (IF EQUIPMENT IS PROVIDED IN THIS PROJECT).
16. INTERCONNECTION BETWEEN EXHAUST HOOD LIGHTS AND SWITCH (IF EQUIPMENT IS PROVIDED IN THIS PROJECT).
17. DOOR HEATERS, LIGHTS, COILS, AND PRESSURE RELIEF PORTS PRE-WIRED TO JUNCTION BOX AT TOP OF WALK-IN ASSEMBLIES (IF EQUIPMENT IS PROVIDED IN THIS PROJECT) PROVIDED BY SECTION 11 40 00. FINAL CONNECTION BY DIV. 26.
18. IF ANY ELECTRICAL ACCESSORIES, FITTINGS, AND CORD/PLUGS ARE PROVIDED LOOSE WITH EQUIPMENT BY 11 40 00, DIV.26 IS TO ATTACH TO EQUIPMENT AND PROVIDE FINAL CONNECTION.
19. PROVIDE WATERPROOF RECEPTACLES IN WET AREAS.
20. ALL ELECTRICAL CONNECTIONS BENEATH EXHAUST HOODS (IF EQUIPMENT IS PROVIDED IN THIS PROJECT) TO EXTEND TO SHUNT TRIP BREAKERS WITH ELECTRICAL PANEL BOX FOR SHUTDOWN DURING FIRE MODE.
21. RECEPTACLES ARE TO BE PRE-WIRED TO THE JUNCTION BOX OR LOAD CENTER FOR FINAL CONNECTION BY DIVISION 26.
22. ALL ELECTRICAL LIGHTING, POWER, AND DISTRIBUTION SYSTEMS.
23. DO NOT INTERCONNECT MORE THAN THREE (3) CONVENIENCE OUTLETS ON ONE (1) BREAKER.
24. OTHER THAN CONVENIENCE OUTLETS, ALL ELECTRICAL CONNECTIONS SHOWN ON FOOD SERVICE PLANS ARE DEDICATED BREAKERS.
25. DOORBELL AT RECEIVING DOOR (PROVIDE AND INSTALL – TO BE AUDIBLE THROUGHOUT KITCHEN, OFFICE, AND DRY STORAGE ROOM).
26. ADEQUATE LIGHTING AT RECEIVING DOOR.
27. PROVIDE AND INSTALL TWO EMERGENCY STROBE BEACONS THAT INTERCONNECT TO PANIC ALARM IN WALK-IN FREEZER. ONE (1) IN KITCHEN ABOVE WALK-IN FREEZER DOOR ONE (1) IN CAFETORIUM (IF WALK-IN IS PROVIDED IN THIS PROJECT). REFER TO GENERAL SPECIFICATIONS FOR ADDITIONAL DETAILS.
28. DEDICATED CIRCUIT FOR HEATED DRAIN LINE CONNECTION IN WALK-IN FREEZER AT EACH COIL (IF WALK-IN IS PROVIDED IN THIS PROJECT).

**NOTE: ELECTRICAL CONNECTIONS INDICATED ARE THOSE REQUIRED FOR THE FOOD SERVICE EQUIPMENT AND THOSE REQUIRED FOR SUPPORT EQUIPMENT FURNISHED BY DIVISION 26. FOR ADDITIONAL REQUIREMENTS, REFER TO THE ELECTRICAL ENGINEER'S DRAWINGS.**

6 ELECTRICAL COORDINATION NOTES
NOT TO SCALE

**DIVISION 22 (PLUMBING) RESPONSIBLE FOR BUT NOT LIMITED TO:**

1. **DO NOT ROUGH-IN FROM FDP DRAWINGS. REFER TO THE KITCHEN EQUIPMENT CONTRACTOR'S DIMENSIONED SHOP DRAWINGS. DIMENSIONS INDICATED ARE TO BE VERIFIED BY KITCHEN EQUIPMENT CONTRACTOR AND ADJUSTED AS REQUIRED BY EQUIPMENT AND/OR FIELD CONDITIONS.**
2. SECTION 11 40 00 TO VERIFY UTILITY REQUIREMENTS OF ANY EXISTING EQUIPMENT.
3. ALL CONNECTIONS SHALL BE MADE IN ACCORDANCE WITH LOCAL CODES AND NATIONAL STANDARDS, EXCEPT WHERE PLANS AND SPECIFICATIONS EXCEED THOSE CODES AND STANDARDS.
4. VERIFY ALL PLUMBING REQUIREMENTS WITH ENGINEERING DRAWINGS.
5. EMPTY PVC CONDUIT WITH WIDE-SWEEP BENDS FOR REFRIGERANT PIPING TO BEVERAGE LINES, CO2 LINES, AND REMOTE FOOD SERVICE EQUIPMENT REFRIGERATION SYSTEMS.
6. ROUGH-IN AND FINAL PLUMBING CONNECTIONS TO FOOD SERVICE EQUIPMENT AND BETWEEN COMPONENTS (INCLUDING MATERIALS AND LABOR). ACCESSORIES PROVIDED LOOSE WITH FOOD SERVICE EQUIPMENT BY SECTION 11 40 00 TO BE FIELD INSTALLED BY DIVISION 22. THIS INCLUDES BUT IS NOT LIMITED TO INSTALLATION OF ALL FAUCETS (WATER FILL FAUCETS, PRE-RINSE FAUCETS, ETC.), HOSES, GAS DISCONNECTS, AND DRAINS FROM EQUIPMENT POINT OF CONNECTION TO BUILDING PLUMBING SYSTEMS. ALL DRAIN LINES ARE PROVIDED AND INSTALLED BY DIV. 22.
7. KITCHEN EQUIPMENT CONTRACTOR IS RESPONSIBLE FOR PROVIDING ALL FAUCETS (WATER FILL FAUCETS, PRE-RINSE FAUCETS, ETC.), DRAIN FITTINGS, MIXING VALVES, CONTROL VALVES, WATER PRESSURE REGULATORS, VACUUM BREAKERS, AND ALL ACCESSORIES FOR EQUIPMENT SPECIFIED UNDER 11 40 00. DIVISION 22 IS RESPONSIBLE FOR INSTALLATION.
8. INDIRECT DRAIN LINE RUNS FROM EQUIPMENT TO NEAREST DRAIN OR FLOOR SINK. LINES TO BE TYPE 'K' COPPER.
9. IF ANY PLUMBING ACCESSORIES OR FITTINGS ARE PROVIDED LOOSE WITH EQUIPMENT BY 11 40 00, DIV. 22 IS TO ATTACH TO EQUIPMENT AND PROVIDE FINAL CONNECTION.
10. GAS SUPPLY SYSTEMS WITH ALL COMPONENTS AND FITTINGS AS REQUIRED FOR A COMPLETE SYSTEM.
11. WATER SUPPLY SYSTEMS WITH ALL COMPONENTS AND FITTINGS AS REQUIRED FOR A COMPLETE SYSTEM.
12. COMPRESSED AIR SYSTEMS WITH ALL COMPONENTS AND FITTINGS AS REQUIRED FOR A COMPLETE SYSTEM (IF REQUIRED FOR THIS PROJECT).
13. PIPING AND DRAINAGE SYSTEMS (SANITARY AND GREASE-LADEN). SYSTEMS MUST BE CLEANED AND FLUSHED BEFORE THE FINAL CONNECTION WITH FOOD SERVICE EQUIPMENT - CRITICAL.
14. FLOOR SINKS (PROVIDE AND INSTALL). FLANGE AND GRATES TO BE FLUSH WITH FINISHED FLOOR.
15. FLOOR DRAINS (PROVIDE AND INSTALL). FLANGE AND GRATES TO BE FLUSH WITH FINISHED FLOOR.
16. TRENCH DRAINS (PROVIDE AND INSTALL). TRENCH LINERS PROVIDED BY 11 40 00. FLANGE AND LINERS TO BE FLUSH WITH FINISHED FLOOR.
17. GREASE TRAPS AS REQUIRED. VERIFY WITH LOCAL CODES TO BYPASS OR PIPE THRU GREASE TRAP AND/OR INTERCEPTOR.
18. P-TRAPS AS REQUIRED (INCLUDING ALL DISPOSERS).
19. INTERCONNECT WATER THRU WATER FILTER (FILTER PROVIDED BY 11 40 00 UNLESS OTHERWISE SPECIFIED) TO EQUIPMENT.
20. GAS QUICK DISCONNECT INSTALLATION (QUICK DISCONNECT PROVIDED BY 11 40 00).
21. SAFETY RESTRAINT CABLE INSTALLATION (SAFETY RESTRAINT CABLE PROVIDED BY 11 40 00).
22. SPECIFIED COUPLINGS AND PIPING TO ALL EQUIPMENT FURNISHED BY 11 40 00.
23. AIR COMPRESSORS (IF REQUIRED FOR THIS PROJECT) (SIZE, PROVIDE, AND INSTALL, UNLESS OTHERWISE SPECIFIED).
24. WATER SOFTENERS (IF REQUIRED FOR THIS PROJECT) (SIZE, PROVIDE, AND INSTALL, UNLESS OTHERWISE SPECIFIED).
25. PRESSURE BOILERS (IF REQUIRED FOR THIS PROJECT) (SIZE, PROVIDE, AND INSTALL, UNLESS OTHERWISE SPECIFIED).
26. HAND SINKS (PROVIDE (UNLESS OTHERWISE SPECIFIED) AND INSTALL). PROVIDE HOT WATER TEMPERING VALVE IF REQUIRED. WATER TEMPERATURE TO BE AT LEAST 100 DEGREES AND FLOW FOR AT LEAST 20 SECONDS.
27. ICE BIN DRAIN INSULATION (IF ICE MACHINE IS PROVIDED IN THIS PROJECT) (PROVIDE AND INSTALL).
28. UNIONS AT DISPOSER SOLENOID VALVES (IF DISPOSER IS PROVIDED IN THIS PROJECT) (PROVIDE AND INSTALL).
29. BACK FLOW PREVENTION AS REQUIRED (PROVIDE AND INSTALL - INCLUDING ALL DISPOSERS). BACK- SIPHONAGE SHALL BE INSTALLED AT ALL FIXTURES AND EQUIPMENT WHERE BACKFLOW AND/OR BACK-SIPHONAGE MAY OCCUR AND WHERE A MINIMUM AIR GAP CANNOT BE PROVIDED BETWEEN THE WATER TO THE FIXTURE OR EQUIPMENT AT ITS FLOOD/LEVEL RIM. VACUUM BREAKERS, WHEN FURNISHED WITH EQUIPMENT, SHALL OVERRIDE THE ABOVE, IF ACCEPTABLE WITH APPLICABLE CODES. DIVISION 22 RESPONSIBLE FOR VERIFYING REQUIREMENT WITH LOCAL CODES.
30. JANITOR SINK WITH FAUCET (PROVIDE AND INSTALL).
31. FREEZE PROOF HYDRANT AT EXTERIOR OF BUILDING BY RECEIVING DOOR (PROVIDE AND INSTALL).
32. REVERSE OSMOSIS SYSTEMS (SIZE, PROVIDE (UNLESS OTHERWISE SPECIFIED), LOCATE AND INSTALL).
33. ALL PIPING WITHIN COUNTER BODY OR UNDER FABRICATED COUNTERS TO BE RUN TO A CONNECTION POINT BELOW COUNTER BODY BY SECTION 11 40 00. FINAL CONNECTION BY DIVISION 22.
34. EXHAUST HOOD CONDENSATE DRAIN CONNECTIONS (IF EXHAUST HOOD IS PROVIDED IN THIS PROJECT) (PROVIDE AND INSTALL).
35. INTERCONNECTION OF 1/2" CW TO PRE-RINSE AND DISPOSERS CONE/BODY INLETS PIPED THROUGH SOLENOID AND VACUUM BREAKER (IF DISPOSER IS PROVIDED IN THIS PROJECT).
36. FIRE SYSTEM PIPING. EXPOSED PIPING TO BE CHROME PLATED.
37. PIPE 1/2" COLD WATER TO SWIRL INLETS AT DISPOSERS (IF DISPOSER IS PROVIDED IN THIS PROJECT).
38. WATER TREATMENT FOR ICE BUILDERS (NON-CHLORINATED WATER WITH A PH LEVEL OF 10 OR HIGHER) AND ANY DRAINS AND OVERFLOWS. PIPING FROM ICE BUILDERS TO TUMBLE CHILLERS BY DIV. 23 (IF ICE BUILDERS AND TUMBLE CHILLERS ARE PROVIDED IN THIS PROJECT).

**NOTE: WATER AND DRAIN CONNECTIONS INDICATED ARE THOSE REQUIRED FOR THE FOOD SERVICE EQUIPMENT AND THOSE REQUIRED FOR SUPPORT EQUIPMENT FURNISHED BY DIVISION 22. FOR ADDITIONAL WATER AND DRAIN REQUIREMENTS REFER TO MECHANICAL DRAWINGS.**

**NOTE: REFER TO ELECTRICAL/MECHANICAL DRAWINGS FOR REQUIREMENTS OF EXHAUST FANS AND MAKE-UP AIR HANDLERS AND LOCATION OF AN INTERLOCK AND START/STOP CONTROLS TO BE LOCATED WITHIN FOOD SERVICE AREA BY DIVISION 26.**

4 PLUMBING COORDINATION NOTES
NOT TO SCALE

**DIVISION 23 (MECHANICAL) RESPONSIBLE FOR BUT NOT LIMITED TO:**

1. **DO NOT ROUGH-IN FROM FDP DRAWINGS. REFER TO THE KITCHEN EQUIPMENT CONTRACTOR'S DIMENSIONED SHOP DRAWINGS. DIMENSIONS INDICATED ARE TO BE VERIFIED BY KITCHEN EQUIPMENT CONTRACTOR AND ADJUSTED AS REQUIRED BY EQUIPMENT AND/OR FIELD CONDITIONS.**
2. SECTION 11 40 00 TO VERIFY UTILITY REQUIREMENTS OF ANY EXISTING EQUIPMENT.
3. ALL CONNECTIONS SHALL BE MADE FOLLOWING LOCAL CODES AND NATIONAL STANDARDS, EXCEPT WHERE PLANS AND SPECIFICATIONS EXCEED THOSE CODES AND STANDARDS.
4. VERIFY ALL MECHANICAL REQUIREMENTS WITH ENGINEERING DRAWINGS.
5. EMPTY EMT CONDUIT WITH PULL-WIRE AND WIDE-SWEEP BENDS FOR REFRIGERANT PIPING TO REMOTE FOOD SERVICE EQUIPMENT REFRIGERATION SYSTEMS.
6. ROUGH-IN AND FINAL CONNECTION OF MECHANICAL SYSTEMS TO FOOD SERVICE EQUIPMENT, WALK-IN ASSEMBLIES, AND BETWEEN COMPONENTS (INCLUDING MATERIALS AND LABOR).
7. TESTING AND BALANCING FOR ROOMS AND EXHAUST HOODS TO BE PERFORMED BY MECHANICAL CONTRACTOR. BALANCE REPORT FOR FOOD SERVICE EXHAUST HOODS TO BE PROVIDED TO FOODSERVICE DESIGN PROFESSIONALS (FDP) IMMEDIATELY UPON COMPLETION (SEND TO HOUSTON.SUBMITTAL@FDP.ORG FOR HOUSTON OFFICE AND DALLAS.SUBMITTAL@FDP.ORG FOR DALLAS OFFICE) AND MUST BE SUBMITTED WITH O&M MANUALS.
8. EXHAUST HOODS, CONDENSATE HOODS, FIRE SUPPRESSION SYSTEMS, CONNECTIONS AND CONTROLS (PROVIDE AND INSTALL – *UNLESS OTHERWISE SPECIFIED*). PROVIDE TEMPERED AIR AT ALL SUPPLY DUCTS.
   - A. IF EXHAUST/CONDENSATE HOODS AND FIRE SUPPRESSION SYSTEMS ARE SPECIFIED UNDER SECTION 11 40 00, DIVISION 23 IS RESPONSIBLE FOR ALL EXHAUST AND CONDENSATE HOOD CONNECTIONS (PROVIDE AND INSTALL).
9. VFD SYSTEM AND CONTROLLERS, WHEN REQUIRED BY CODE (PROVIDE AND INSTALL).
10. PROVIDE AND INSTALL ALL VENTILATION (DIRECT OR INDIRECT), AIR CONDITIONING AND HEATING SYSTEMS (UNLESS OTHERWISE SPECIFIED).
11. COORDINATE SUPPLY AND RETURN DUCTS ABOVE SERVING COUNTERS OR OPEN-AIR REFRIGERATED MERCHANDISERS. NO COLD AIR TO BLOW DIRECTLY ON HOT FOOD COUNTERS.
12. COORDINATE SUPPLY AND RETURN DUCTS AWAY FROM EQUIPMENT WITH TOP MOUNTED REFRIGERATION. NO COLD AIR TO BLOW DIRECTLY ON COMPRESSORS.
13. MECHANICAL CONTRACTOR TO LOCATE TEMPERATURE MONITORS WITHIN RETURN DUCTS.
14. CIRCULATING AIR ABOVE WALK-IN ASSEMBLIES (PROVIDE AND INSTALL).
15. CIRCULATING AIR ABOVE AND IN AIR GAPS AT WAREHOUSE COLD STORAGE ASSEMBLIES (PROVIDE AND INSTALL).
16. WATER CHILLERS AS REQUIRED (IF EQUIPMENT IS PROVIDED IN THIS PROJECT) (PROVIDE, SIZE AND LOCATE).
17. PIPING FROM ICE BUILDERS TO TUMBLE CHILLERS (IF EQUIPMENT IS PROVIDED IN THIS PROJECT) (PROVIDE, SIZE AND LOCATE).

3 MECHANICAL COORDINATION NOTES
NOT TO SCALE

**GENERAL CONTRACTOR RESPONSIBLE FOR BUT NOT LIMITED TO:**

1. ANY WALL PENETRATION REQUIRED FOR FOOD SERVICE EQUIPMENT UTILITIES. ESCUTCHEON PLATES OR S/S SLEEVES TO BE PROVIDED AND INSTALLED AS NEEDED.
2. BULK FREEZER VENTILATION PIPE (IF BULK FREEZER IS PROVIDED IN THIS PROJECT) (PROVIDE AND INSTALL, UNLESS OTHERWISE SPECIFIED).
3. CORE DRILLING FOR GUIDE RAILS (IF GUIDE RAILS ARE PROVIDED IN THIS PROJECT).
4. REFRIGERATION ROOF CURBS / ROOF JACK (IF REFRIGERATION SYSTEM IS PROVIDED IN THIS PROJECT AND LOCATED ON ROOF).
5. INTERIOR BOLLARDS (IF REQUIRED FOR THIS PROJECT) – TO BE EPOXY PAINTED PER LOCAL CODES (PROVIDE AND INSTALL).
6. FURNISH AND INSTALL 3/4" PLYWOOD BLOCKING IN THE WALL FOR MOUNTING EQUIPMENT FURNISHED BY SECTION 11 40 00 AS REQUIRED.
7. WALK-IN DEPRESSIONS (TO BE DEAD LEVEL) AND SAND LEVELING BED (IF WALK-IN IS PROVIDED IN THIS PROJECT AND RECESS IS SHOWN).
8. STRUCTURAL BRACING FOR BULK WALK-IN CEILING PANELS IF REQUIRED.
9. MENU SYSTEM VIDEO MONITORS IN SERVERY (UNLESS OTHERWISE SPECIFIED).
10. STRUCTURAL BRACING FOR MENU SYSTEM VIDEO MONITORS IF REQUIRED.
11. INTERIOR/EXTERIOR REFRIGERATION PENETRATIONS AND SLEEVES AT BUILDING PENETRATIONS.
12. DOORSCOPE VIEWER (PEEPHOLE) WITH WIDE VIEWING ANGLE AT RECEIVING DOOR.
13. CANOPY AT RECEIVING DOOR. COORDINATE HEIGHT WITH THE HEIGHT OF RECEIVING DOOR (8') AND THE MOUNTING HEIGHT OF AIR SCREEN ABOVE THE DOOR.
14. SOAP AND TOWEL DISPENSER PROVIDED BY OWNER. G.C. RESPONSIBLE FOR INSTALLATION.
15. WASHER AND DRYER (PROVIDE AND INSTALL, UNLESS OTHERWISE SPECIFIED).
16. DWARF WALL AT EXPOSED FRONT/ENDS OF CAFETERIA SERVING COUNTERS WITH FINISH AS SELECTED BY ARCHITECT (IF REQUIRED IN THIS PROJECT).

2 GENERAL CONTRACTOR COORDINATION NOTES
NOT TO SCALE

**HEALTH DEPARTMENT REQUIREMENTS (VERIFY WITH LOCAL JURISDICTIONS):**

1. FLOORS: VERIFY WITH DIVISION 9. FLOORS TO BE SMOOTH, IMPERVIOUS, EASILY CLEANABLE AND SLIP RESISTANT.
2. WALLS: VERIFY WITH ARCHITECTURAL DOCUMENTS. WALLS TO BE SMOOTH, IMPERVIOUS, AND EASILY CLEANABLE.
3. CEILING: LAY-IN TILES. CEILING TILES TO BE SMOOTH, IMPERVIOUS, AND EASILY CLEANABLE.
4. EMPLOYEE TOILET: TO BE LOCATED OFF MAIN CORRIDOR AND ADJACENT TO MAIN KITCHEN. RESTROOM MUST HAVE A VESTIBULE AND NOT OPEN TO KITCHEN / PREP AREAS. TOILETS TO BE WELL VENTILATED.
5. LAVATORIES: WALL HUNG LAVATORIES LOCATED WITHIN ALL FUNCTIONAL WORKING AREAS.
6. UTENSIL CLEANING/SANITIZING: ACCOMPLISHED IN UTENSIL WASH AREA WITH (3) 2'-0" x 2'-2" x 15" MINIMUM DEEP SINKS AND WAREWASH MACHINE.
7. MECHANICAL CLEANING/SANITIZING OF TABLEWARE: ACCOMPLISHED BY WAREWASH MACHINE.
8. STOREROOMS: AMPLE DAILY STORAGE PROVIDED IN ENCLOSED STORE ROOMS. STORE ROOMS TO BE VENTILATED AND MAINTAIN PROPER TEMPERATURE.
9. WATER HEATER: LOCATED IN THE MECHANICAL ROOM ADJACENT TO KITCHEN. TO BE SIZED TO PROVIDE AMPLE WATER TO MAINTAIN PROPER WATER TEMPERATURE THROUGHOUT HOURS OF OPERATION.
10. GREASE TRAP: LOCATED AT EXTERIOR OF BUILDING. REFER TO ENGINEER'S DRAWINGS.
11. FOOD SERVICE EQUIPMENT: ALL FLOOR-MOUNTED EQUIPMENT IS TO BE SEALED TO THE FLOOR TO PROVIDE AN EASILY CLEANABLE SURFACE AND PREVENT SEEPAGE. EQUIPMENT NOT MOUNTED TO THE FLOOR IS TO BE WALL MOUNTED ON WALL CARRIERS, OR ELEVATED ON LEGS TO PROVIDE AT LEAST A SIX-INCH CLEARANCE BETWEEN FLOOR AND EQUIPMENT.
12. MOP SINK: LOCATED IN JANITOR CLOSET OFF MAIN KITCHEN CORRIDOR, AND LOCATED IN CLOSE PROXIMITY TO THE SERVERY WAREWASH AREA.
13. EXHAUST HOODS: EXHAUST HOODS PROVIDED OVER COOKING EQUIPMENT WITH LIQUID CHEMICAL ANSUL FIRE EXTINGUISHING SYSTEM.
14. LIGHTING AND PROTECTIVE SHIELDING: RECESSED CEILING-MOUNTED FLUORESCENT LIGHT FIXTURES FITTED WITH CLEAR LEXAN DIFFUSERS.
15. GARBAGE AND REFUSE: CENTRAL TRASH COLLECTION PROVIDED FOR BUILDING LOCATED NEAR RECEIVING AREA ON SMOOTH CONCRETE SURFACE.
16. POISONOUS AND TOXIC MATERIAL STORAGE: LOCATED IN RESPECTIVE JANITOR CLOSETS WITH LOCKING HARDWARE.

1 HEALTH DEPARTMENT COORDINATION NOTES
NOT TO SCALE

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL

FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/18/2025
THIS ITEM IS RELEASED FOR PERMITTING ON THIS DATE AND IS NOT AUTHORIZED FOR CONSTRUCTION
MELISSA MOORE, FCSI NO. 48854119
GPK: 07/18/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

FS GENERAL COORDINATION NOTES

A-QF0.0

| FOOD SERVICE DRAWING INDEX | |
|---|---|
| FDP SHEET NUMBER | FDP SHEET NAME |

| | |
|---|---|
| A-QF0.0 | FS GENERAL COORDINATION NOTES |
| A-QF1.0 | FS EQUIPMENT PLAN |
| A-QF1.1 | FS FACILITY MODEL |
| A-QF1.2 | FS EQUIPMENT MODEL |
| A-QF1.3 | FS SPECIAL CONDITIONS & MECHANICAL PLAN |
| A-QF1.4 | FS PLUMBING PLAN |
| A-QF1.5 | FS ELECTRICAL PLAN |
| A-QF1.6 | FS CONDENSING UNITS |
| A-QF1.7 | FS WALK-INS |
| A-QF2.0 | FS EXISTING EQUIPMENT PLAN |
| A-QF2.1 | FS EQUIPMENT PLAN - TEMPORARY SERVING & MEPS |




1 FOOD SERVICE EQUIPMENT PLAN
1/4" = 1'-0"

| FOOD SERVICE EQUIPMENT SCHEDULE | | | | | |
|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR GENERAL CONTRACTOR & HEALTH DEPARTMENT COORDINATION NOTES | | | | | |
| FDP ITEM | FDP QTY | FDP DESCRIPTION | FDP REMARKS | MANUFACTURER | MODEL |
| 101 | 1 | AIR SCREEN | | MARS | STD248-1UA-OB |
| 102 | 1 | COLD STORAGE ASSEMBLY | | American Panel | |
| 103 | 1 | COLD STORAGE REFRIGERATION SYSTEM | | RDT | ZS1-02Z-CT3-AST |
| 104 | 2 | COLD STORAGE SHELVING | | METRO | METROMAX Q |
| 107 | 1 | DRY STORAGE SHELVING | | METRO | METROMAX Q |
| 108 | 1 | CAN RACK | | NEW AGE | 1250CK |
| 109 | 1 | ICE MACHINE W/ BIN | | MANITOWOC | UYF0310A |
| 110 | 1 | CLOTHES WASHER | | WHIRLPOOL | Residential |
| 110A | 1 | CLOTHES DRYER | | WHIRLPOOL | Residential |
| 111W | 1 | WALL MOUNTED OVERSHELF | | CUSTOM FABRICATED | |
| 122 | 1 | TWO COMPARTMENT SINK WITHOUT DISPOSER | | CUSTOM FABRICATED | |
| 123 | 1 | DISPOSER - 3HP | | SALVAFOR | 300-CA-18-ARSS-LD |
| 124 | 1 | WORKTABLE | | CUSTOM FABRICATED | |
| 125 | 1 | 20 QT. MIXER W/STAND | | HOBART | HL200 |
| 128 | 4 | UTILITY CART | | LAKESIDE | 522 |
| 129 | 2 | WORKTABLE W/S.BAR UT.RACK | | CUSTOM FABRICATED | |
| 138 | 4 | PAN RACK | | CRES COR | 207-UA-13A |
| 139 | 1 | INSUL MOBILE PROOFER | | CRES COR | H-137-WSUA-12D |
| 151 | 2 | FIRE PROTECTION SYSTEM | | ANSUL | R102 |
| 152 | 1 | EXHAUST HOOD | EXISTING | | |
| 153 | 1 | EXHAUST HOOD | EXISTING | | |
| 161 | 2 | CONVECTION OVEN | | BLODGETT | DFG-200 DBL |
| 165 | 1 | TWO BURNER RANGE | | VULCAN | V2B18B |
| 172 | 1 | COMBI OVEN | | RATIONAL | ICP 6-FULL/6-FULL N/G |
| 186 | 2 | PASS-THRU HEATED CABINET-1DR | | TRAULSEN | AHF-132WP |
| 188 | 2 | PASS-THRU REFRIGERATOR-1DR | | TRAULSEN | AHT-132WPUT |
| 201M.1 | 1 | SERVING COUNTER-MODULAR | | COUNTERCRAFT | SCOL-408-MOD |
| 209 | 2 | DROP FRONT MILK COOLER - 8 CASE | | TRAULSEN | RMC34D4 |
| 214 | 2 | CASH REGISTER | OWNER FURNISHED | | |
| 249 | 1 | THREE COMPARTMENT SINK NO DISPOSER | | CUSTOM FABRICATED | |
| 250 | 1 | DISHMACHINE | | HOBART | CL44-BAS |
| 254 | 2 | SOILED & CLEAN DISHTABLE | | CUSTOM FABRICATED | |
| 255 | 2 | MOBILE DRYING RACK | | METRO | PR48VX3 |
| 260 | 6 | HAND SINK | FURNISHED & INSTALLED BY DIV. 22 | | |
| 614 | 1 | FILL FAUCET | | T&S | B-0610 |
| 615 | 2 | MENU MONITOR | BY OWNER | | |
| 800 | 1 | 15 GAL. BRAISING PAN | | GROEN | BPM-15GA |
| 801 | 1 | S/S CORNER GUARDS | LOCATED ON EVERY EXPOSED CORNER THROUGHOUT KITCHEN | CUSTOM FABRICATED | |
| 802 | 1 | WALL BUMPERS | LOCATED ON ALL EXPOSED BUILDING WALLS | PAWLING | MD-1 |
| 803 | 1 | WATER SOFTENER | | HOBART | WA-40 |
| 804 | 6 | S/S SPLASH GUARDS | | CUSTOM FABRICATED | |

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479


SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOON
46854119
PROFESSIONAL MEMBER
Melissa Moon
7/18/2025
THIS ITEM IS DIGITALLY SIGNED AND SEALED BY MELISSA MOON, FCSI NO. 46854119
ON: 07/18/2025


ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS EQUIPMENT PLAN

A-QF1.0

ISOMETRIC VIEWS WITHIN THIS DRAWING ARE NOT TO SCALE AND ARE PROVIDED FOR REFERENCE PURPOSES ONLY. ISOMETRIC VIEWS ARE NOT INTENDED FOR REGULATORY APPROVAL, PERMITTING, NOR CONSTRUCTION. REFER TO FLOOR PLANS AND DETAILS FOR SPECIFIC PROJECT INFORMATION.



1 FS FACILITY MODEL

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL


FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
THE ITEM APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI 48854119 ON 07/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS FACILITY MODEL

A-QF1.1

ISOMETRIC VIEWS WITHIN THIS DRAWING ARE NOT TO SCALE AND ARE PROVIDED FOR REFERENCE PURPOSES ONLY. ISOMETRIC VIEWS ARE NOT INTENDED FOR REGULATORY APPROVAL, PERMITTING, NOR CONSTRUCTION. REFER TO FLOOR PLANS AND DETAILS FOR SPECIFIC PROJECT INFORMATION.



1 FS EQUIPMENT MODEL

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FDP
FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL

FOODSERVICE CONSULTANT
MELISSA MOORE
FCSI
48854119
SOCIETY INTERNATIONAL
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
ITEMS APPEARING ON THIS DOCUMENT ARE AUTHORIZED BY MELISSA MOORE, FCSI NO. 48854119 ON: 07/18/2025

MWA ARCHITECTS


ARCHITECTS
AND PLANNING
CONSULTANTS

11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS EQUIPMENT MODEL


A-QF1.2

| FOOD SERVICE MECHANICAL SCHEDULE | | | | | | |
|---|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR MECHANICAL COORDINATION NOTES | | | | | | |
| FDP NO. | FDP QTY | FDP TYPE | FDP SIZE | FDP LOC | FDP CFM | FDP S.P. |
| M101 | 1 | EXHAUST | 4" X 16" | | 1500 | 0.35" |
| M102 | 1 | EXHAUST | 4" X 16" | | 1500 | 0.35" |
| M103 | 1 | DRYER VEBT | 6" DIA. | | --- | --- |





1 FOOD SERVICE SPECIAL CONDITIONS PLAN
1/4" = 1'-0"

NOTE:
SECTION 11 40 00 TO COORDINATE FINAL LOCATION AND SIZE OF WALL BLOCKING.





5 WALL BLOCKING DETAIL
NOT TO SCALE


NOTE:
SECTION 11 40 00 TO COORDINATE FINAL LOCATION OF ALL TRENCH LINERS WITH EQUIPMENT POUR PATH.




6 TRENCH LINER DETAIL
NOT TO SCALE





3 COLD STORAGE ASSEMBLY ENCLOSURE PANEL DETAIL
NOT TO SCALE




4 COLD STORAGE ASSEMBLY REFRIGERATION SYSTEM GROUND MOUNT 4" PLATFORM DETAIL
NOT TO SCALE

SLAB TO BE MODIFIED AS REQUIRED TO ALLOW FOR A 4 1/2" DEPRESSION SLAB. PROVIDE NEW LEVEL CONCRETE PAD FOR COLD STORAGE ASSEMBLY.




WALL SECTION @ EXTERIOR DOOR

2 COLD STORAGE ASSEMBLY 4 1/2" DEPRESSION DETAIL
NOT TO SCALE

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

# FBISD BP 013 KITCHEN RENOVATIONS
## FORT BEND INDEPENDENT SCHOOL DISTRICT
## AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL

FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
46854119
PROFESSIONAL MEMBER
Melissa Moore
7/18/2025
I HEREBY CERTIFY THAT I PREPARED OR APPROVED THIS DOCUMENT AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF TEXAS.
MELISSA MOORE, FCSI NO. 46854119
ON: 07/18/2025


ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING


FS SPECIAL CONDITIONS & MECHANICAL PLAN

A-QF1.3

## FOOD SERVICE PLUMBING SCHEDULE

REFER TO SHEET QF1 FOR PLUMBING COORDINATION NOTES

| FDP PNO | FDP PSIZE | FDP PCONN | FDP PSERVICE TO | FDP PLOC | FDP PAFF | FDP PREMARKS |
|---|---|---|---|---|---|---|
| P5 | 3/4" | H & C WATER | JANITOR SINK | WALL | 48" | JANITOR SINK BY PLUMBER |
| P6 | 4" | FLOOR DRAIN | JANITOR SINK | FLOOR | VERIFY | JANITOR SINK BY PLUMBER |
| P7 | 3/4" | H & C WATER | HOSE BIBB | WALL | 18" | BTC |
| P10 | VERIFY | FLOOR DRAIN | GENERAL AREA DRAIN | FLOOR | VERIFY | --- |
| P11C | 1/2" | H & C WATER | FAUCET | WALL | 18" | FURNISHED & INSTALLED BY DIV. 22 |
| P11D | 1 1/2" | DIRECT DRAIN | HAND SINK | WALL | 15" | FURNISHED & INSTALLED BY DIV. 22 |
| P12 | VERIFY | FLOOR DRAIN | EQUIP. DRAIN | FLOOR | VERIFY | NO SLOPE |
| P15 | 4" | FLOOR DRAIN | FUNNEL FLOOR DRAIN | FLOOR | 0" | --- |
| P109 | 3/4" | COLD WATER | WATER/ ICE | WALL | 60" | BTC |
| P109A | 12" SQ. | FLOOR SINK | ICE MACHINE | FLOOR | 0" | FULL GRATE |
| P110 | 3/4" | H & C WATER | CLOTHES WASHER | WALL | 48" | BTC; VALVE BOX |
| P110A | 2" | INDIRECT DRAIN | CLOTHES WASHER | WALL | 48" | VALVE BOX |
| P122 | 3/4" | H & C WATER | FAUCET | WALL | 13" | BTC |
| P122A | 12" SQ. | FLOOR SINK | SINK | FLOOR | 0" | 3/4 GRATE |
| P123 | 3/4" | H & C WATER | FAUCET / DISPOSER | WALL | 13" | BTC |
| P123A | 2" | DIRECT DRAIN | DISPOSER | WALL | 10" | BTC |
| P161 | (2)3/4" | NATURAL GAS | CONVECTION OVEN | WALL | 18"/36" | BTC - 60 MBTU/HR EACH |
| P163A | 3/4" | NATURAL GAS | TILT BRAISING PAN | WALL | 18" | BTC - 65 MBTU/HR |
| P163B | 3/4" | H & C WATER | TILT BRAISING PAN | WALL | 36" | BTC |
| P165 | 1" | NATURAL GAS | RANGE | WALL | 18" | BTC - 70 MBTU/HR |
| P172 | (2)3/4" | COLD WATER | COMBI OVEN | WALL | 24"/48" | BTC - INTERCONNECT THRU FILTERS |
| P172A | 3/4" | COLD WATER | COMBI OVEN | WALL | 48" | BTC |
| P172B | 12"SQ. | FLOOR SINK | EQUIPMENT | FLOOR | 0" | 3/4 GRATE |
| P172C | (2)3/4" | NATURAL GAS | COMBI OVEN | WALL | 18"/36" | BTC - 105 MBTU/HR EACH |
| P172D | 3/4" | COLD WATER | COMBI OVEN | WALL | 66" | BTC; INTERCONNECT TO P172 |
| P172E | 3/4" | COLD WATER | COMBI OVEN WATER FILTER | WALL | 66" | BTC |
| P249 | 3/4" | H & C WATER | FAUCET | WALL | 13" | BTC |
| P249A | 12" SQ. | FLOOR SINK | SINK | FLOOR | 0" | THREE QUARTER GRATE |
| P250 | 12" SQ. | FLOOR SINK | BOOSTER / DISHMACHINE | FLOOR | 18" | BTC |
| P250A | 3/4" | HOT WATER | DISHMACHINE | WALL | 18" | EXT. THRU W.FILTER TO BOOSTER / DISH MACHINE - 140DEG.MIN. |
| P250B | 3/4" | COLD WATER | DISHMACHINE | WALL | 18" | BTC |
| P614 | 1/2" | H & C WATER | FILL FAUCET | WALL | 42" | BTC |




1 FOOD SERVICE PLUMBING PLAN
1/4" = 1'-0"

SECTION 11 40 00 TO PROVIDE LOOSE WITH FOOD SERVICE EQUIPMENT. INSTALLATION BY DIV. 22 & 26.


- (A) VACUUM BREAKER
- (B) DISPOSER
- (C) TIME DELAY
- (D) CONTROL PANEL
- (E) SOLENOID VALVE

DIVISION 22 TO PROVIDE AND INSTALL


- (F) 1/2" CW INLET
- (G) FLOW CONTROL
- (H) 1/2" CW
- (I) 2" DRAIN LINE WITH P-TRAP & Y ADAPTOR
- (J) 1-1/2" TAILPIECE
- (K) GATE VALVE
- (L) 1/2" CW SUPPLY
- (M) SHOCK STOP
- (N) RPZ BACK FLOW PREVENTOR

DIVISION 26 TO PROVIDE AND INSTALL


- (O) POWER SUPPLY





6 DISPOSER WITH VACUUM BREAKER DETAIL
NOT TO SCALE





7 EXHAUST HOOD - GAS LINE ROUTING DETAIL
NOT TO SCALE




3 GAS DISCONNECT DETAIL
NOT TO SCALE




5 DRAIN PIPING FASTENER DETAIL
NOT TO SCALE




8 WAREWASH - PERFORATED OVER SHELF DETAIL
NOT TO SCALE

| | | | | | |
|---|---|---|---|---|---|
| ○ | HW | HOT WATER | ☑ | FFD | FUNNEL FLOOR DRAIN |
| ○ | CW | COLD WATER | ◣ | EVC | EXHAUST VENT CONNECTION |
| ○ | HTW | 180 F HOT WATER | ◢ | SVC | SUPPLY VENT CONNECTION |
| ◎ | | CHILLED WATER | ◐ | FR | DIRECT-CONNECTED FLUE RISER |
| ● | W | DIRECT WASTE | ⊕ | PS | PIPE SLEEVE |
| ○ | IW | INDIRECT WASTE | ⊙ | | COMPRESSED AIR |
| ⊙ | | GAS SUPPLY | ♦ | | CO2 |
| ◕ | | STEAM SUPPLY | | AFF | ABOVE FINISHED FLOOR |
| ⊗ | CR | CONDENSATE RETURN | | BTC | BRANCH TO CONN. ON EQUIP |
| ◉ | DR | DRAIN | | DFA | DROP FROM ABOVE |
| □ | FD | FLOOR DRAIN | | CLG | CEILING |
| ▤ | FST | FLOOR SINK 3/4 GRATE | | | |
| ▥ | FSH | FLOOR SINK 3/4 GRATE | | | |

2 PLUMBING SYMBOLS
NOT TO SCALE

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL

FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
THIS ITEM IS APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 48854119 ON: 07/15/2025



ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS PLUMBING PLAN

A-QF1.4

| FOOD SERVICE ELECTRICAL SCHEDULE | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR ELECTRICAL COORDINATION NOTES | | | | | | | | |
| FDP ENO | FDP ECONN | FDP ELOAD | FDP EVOLT | FDP EPH | FDP ESERVICE TO | FDP ELOC | FDP EAFF | FDP EREMARKS |
| E10 | DR | 16.0A | 120 | 1 | CONVENIENCE | WALL | 24" | MOUNT HORIZONTAL |
| E11 | DR | 16.0A | 120 | 1 | CONVENIENCE OUTLET | WALL | 47" | MOUNT HORIZONTAL |
| E15 | JB | --- | --- | -- | FIRE PULL | WALL | 48" | BTC; RECESSED |
| E101 | JB | 5.1A | 120 | 1 | AIR SCREEN | WALL | 82" | BTC; MAGNETIC REED SWITCH ON DOOR JAMB & DOOR |
| E102A | JB | 16.0A | 120 | 1 | DOOR HEATER/LIGHTS | CLG | DFA | BTC |
| E102B | JB | 5.0A | 120 | 1 | TEMP. ALARM | CLG | DFA | BTC |
| E102C | JB | 5.0A | 120 | 1 | PRESSURE RELIEF PORT | CLG | DFA | BTC |
| E102E | JB | 10.0A | 120 | 1 | PANIC ALARM BUTTON | CLG | DFA | BTC-INTERCONNECT TO STROBE LIGHT/HORN ABOVE FREEZER DOOR AND IN CAFETORIUM |
| E103 | JB/DS | 25.0A | 208 | 3 | REFRIGERATION SYSTEM | VERIFY | VERIFY | BTC |
| E103C | JB | 16.0A | 208 | 1 | FREEZER COIL | CLG | DFA | BTC |
| E103D | JB | 10.0A | 120 | 1 | COOLER COIL | CLG | DFA | BTC |
| E103E | JB | --- | --- | --- | DATA CONNECTION | CLG | DFA | BTC; RUN TO NEAREST IDF / MDF ROOM |
| E103F | JB | 16.0A | 120 | 1 | DRAIN LINE HEATER | CLG | DFA | BTC; DEDICATED CIRCUIT |
| E109 | DR | 11.9A | 120 | 1 | ICE MACHINE | WALL | 60" | --- |
| E110 | DR | 16.0A | 120 | 1 | CLOTHES WASHER | WALL | 48" | -- |
| E110A | SR | 30.0A | 208 | 1 | CLOTHES DRYER | WALL | 48" | VERIFY NEMA PLUG RECEPTACLE |
| E123 | JB | 3.0HP | 208 | 3 | DISPOSER | WALL | 24" | BTC; CONNECT THRU C.P. TO DISPOSER |
| E129 | DCR | 16.0A | 120 | 1 | TABLE RECEPTACLE | CLG | 84" | TWISTLOCK PLUG & RECEPTACLE |
| E139A | DCR | 16.6A | 120 | 1 | HEATED CABINET | CEILING | DFA | BTC |
| E151 | JB | 1.0A | 120 | 1 | FIRE PROT. SYSTEM | CLG | DFA | BTC |
| E161 | (2)DR | 6.0A EA. | 120 | 1 | CONVECTION OVEN | WALL | 24"/48" | SHUNT TRIP BREAKER |
| E163 | DR | 5.0A | 120 | 1 | TILT BRAISING PAN | WALL | 24" | SHUNT TRIP BREAKER |
| E172 | (2)JB | 15.0A EA. | 208 | 1 | COMBI OVEN | WALL | 24"/48" | BTC - SHUNT TRIP BREAKER |
| E187 | JB | 15.5A | 120/208 | 1 | HEATED CABINET | WALL | 96" | BTC; MOUNT ON KITCHEN SIDE |
| E188 | JB | 7.2A | 120 | 1 | REFRIGERATOR | WALL | 96" | BTC; MOUNT ON KITCHEN SIDE-OMIT PLUG, UNIT TO BE HARDWIRED |
| E201A | PMR | 28.0A | 208 | 1 | HOT FOOD COUNTER | FLOOR | 4.5" | BTC |
| E201B | PMR | 16.0A | 120 | 1 | COLD FOOD COUNTER | FLR | 4.5" | --- |
| E209 | PMR | 8.0A | 120 | 1 | DROP FRONT MILK COOLER-8 CASE | FLR | 4.5" | --- |
| E214 | PMR | 16.0A | 120 | 1 | CASH REGISTER | FLR | 4.5" | DEDICATED CIRCUIT |

DIVISION 26 TO PROVIDE, COORDINATE, AND INSTALL THE FOLLOWING:
1. AUDIBLE DOORBELL AT RECEIVING DOOR ON EXTERIOR WALL THAT CAN BE HEARD THROUGHOUT THE ENTIRE KITCHEN, OFFICE AND DRY STORAGE ROOM.
2. ADEQUATE LIGHTING AT RECEIVING DOOR.
3. EDWARDS 860 SERIES (OR EQUAL) RED LENS, SURFACE-MOUNTED XENON EMERGENCY STROBE BEACONS. ONE (1) TO BE LOCATED IN THE KITCHEN ABOVE WALK-IN FREEZER DOOR (OR COOLER DOOR WHEN FREEZER IS WITHIN COOLER IN AN 'INLINE' ASSEMBLY), AND ONE (1) TO BE LOCATED IN THE CAFETORIUM (COORDINATE LOCATION WITH OWNERS). PROVIDE CONDUIT, WIRING, AND INTERCONNECT THE ILLUMINATED PUSH BUTTON PANIC ALARM IN THE WALK-IN FREEZER TO BOTH STROBE BEACONS (***CRITICAL***).






DIVISION 27 TO PROVIDE THE FOLLOWING:
1. CONDUIT, DATA, AND INTERCONNECTION FROM THE ILLUMINATED PUSH BUTTON PANIC ALARM INSIDE THE WALK-IN FREEZER TO THE BUILDING AUTOMATION SYSTEM. WHEN ACTIVATED, FACILITY PERSONNEL TO BE NOTIFIED - COORDINATE NOTIFICATION REQUIREMENTS WITH THE OWNER (***CRITICAL***).

NOTE:
(FOR GRAPHICAL REPRESENTATION ONLY)
SECTION 11 40 00 TO VERIFY LOCATION OF REFRIGERATION SYSTEM WITH APPROVED ARCHITECTURAL DRAWINGS.


1 FOOD SERVICE ELECTRICAL PLAN
1/4" = 1'-0"

| FOOD SERVICE ELECTRICAL SCHEDULE | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR ELECTRICAL COORDINATION NOTES | | | | | | | | |
| FDP ENO | FDP ECONN | FDP ELOAD | FDP EVOLT | FDP EPH | FDP ESERVICE TO | FDP ELOC | FDP EAFF | FDP EREMARKS |
| E214A | CS | --- | --- | --- | POS | FLOOR | 6" | BTC; CONDUIT W/DATA LINE TO RUN TO MANAGER'S OFFICE OR IDF ROOM-VERIFY |
| E250 | JB/DS-JB | 51.7A | 480 | 3 | DISHMACHINE | WALL | 66" | BTC; EXTEND FROM JB/DS AT NEAREST WALL |








6 COLD STORAGE ASSEMBLY ENTRAPMENT PANIC ALARM DETAIL
NOT TO SCALE





3 PEDESTAL MOUNTED RECEPTACLE DETAIL
NOT TO SCALE

NOTE:
REFER TO FDP EQUIPMENT PLAN
FOR SPECIFIC COMPONENTS UNDER HOOD.
ALL EQUIPMENT SHOWN HERE FOR GRAPHICAL REPRESENTATION ONLY.




| | |
|---|---|
| A | S/S ENCLOSURE W/AGENT TANK AND NITROGEN CARTRIDGE |
| B | DUCT NOZZLE(S) |
| C | PLENUM NOZZLE(S) |
| D | SURFACE PROTECTION NOZZLE(S) |
| E | FUSIBLE LINK(S) |
| F | (2) WIRES FROM FIRE SYSTEM TO SHUNT TRIP BREAKERS FOR SHUT DOWN OF ELECTRICAL CONNECTIONS LOCATED BENEATH EXHAUST HOOD DURING FIRE MODE |
| G | REMOTE FIRE PULL |
| H | GAS VALVE |
| I | GAS SUPPLY (AS REQUIRED) |

4 FIRE PROTECTION SYSTEM TYPICAL DETAIL
NOT TO SCALE




5 FIRE PROTECTION SYSTEM RECESSED FIRE PULL DETAIL
NOT TO SCALE

| | | | | | |
|---|---|---|---|---|---|
| | SCR | CONDUIT STUB BTC ON RECEPT FURNISH WITH EQUIPMENT | | CC | CONDUIT FOR COMPUTER CABLES |
| • | CS | CONDUIT STUB UP/OUT FOR DIRECT CONNECTION | | BTC | BRANCH TO CONNECTION ON EQUIPMENT |
| | DR | DUPLEX RECEPTACLE | | WPR | WATERPROOF RECEPTACLE (SPRING COVER) |
| | SR | SINGLE PURPOSE RECEPTACLE-1PH | | FPB | FIRE PROTECTION BUZZER |
| | SR | SINGLE PURPOSE RECPTACLE-3PH | | BSC | BEVERAGE SYSTEM CONDUIT |
| | FR | FLUSH FLOOR RECEPTACLE | | DFA | DROP FROM ABOVE |
| | PMR | PEDESTAL MOUNTED RECEPTACLE | | AFF | ABOVE FINISH FLOOR |
| | DCR | DROP CORD RECEPTACLE | | CS/JB | JUNCTION BOX ON PEDESTAL |
| | JB | JUNCTION BOX ON CEILING | | SW | SWITCH |
| | JB | JUNCTION BOX IN WALL | | D | DATA |
| | JB/DS | JUNCTION BOX WITH DISCONNECT BY DIV.26 | | | |

2 ELECTRICAL SYMBOLS
NOT TO SCALE

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479


SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
#8854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
ELECTRONICALLY SIGNED AND SEALED. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SHA AUTHENTICATION CODE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.
MELISSA MOORE, FCSI NO. #8854119
SHA: 8319A35D25


ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS ELECTRICAL PLAN

A-QF1.5

**MODEL NO. ZS1-02Z-CT3-EST OUTDOOR AIR COOLED REFRIGERATION SYSTEM**
**ITEM NO. 103**




NOTE:
- CRANKCASE HEATERS
- FAN CYCLING SWITCHES
- (2) DOOR SENSORS (SHIPPED LOOSE)
- 24" STAND W/ SKIRT (SHIPPED LOOSE)
- REFRIGERANT DETECTION SYSTEM
- CHECK VALVE (SHIPPED LOOSE)
- SHUT OFF VALVE (SHIPPED LOOSE)

RACK WEIGHT: 900 LBS.

## ENGINEERING SUMMARY

**POWER SUPPLY: 208-230/60/3**
**CONNECTED LOAD: 25 AMPS**

**MOPD: 35 AMP**
**MINIMUM CIRCUIT AMPACITY: 28.0**

| | FIXTURES | | | | | | CONDENSING UNIT | | | | | | | | EVAPORATOR COILS | | | | | | | | | | | | REFRIGERANT LINE | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | TEMP °F | | | | COMPRESSOR | | | | | | | | | | FAN MOTORS | | | HEATERS | | | | ACCESSORIES | | | SIZES (IN) | | | | |
| | | | | | | | RATING @ 60 HZ | | | | | | | | | | @ 60 HZ | | | @ 60 HZ | | | | | | | | | | | |
| SYSTEM | ITEM # | DESCRIPTION | FIXT. | SUCT. | REQ'D FIXTURE BTU/H | REFRIG. R. | MODEL NO. | H.P. | RLA | V | PH | BTU CAP @ AMB °F 110 | TYPE | REC. CAP. (lbs) | CONDENSER | ITEM # | MODEL NO. | QTY | RLA | V | PH | RLA | V | PH | DEFR. TYPE | DEFROST CONTROLLER TYPE | CONTROLLER QTY | TSTAT | SOL. VALVE | EXP. V/LV. | SUCT. | SUCT. LINE RISER | LIQUID | LINE RUN (FT) | TYPE | TOTAL SYSTEM LOAD |
| A | 102 | WALK-IN COOLER | 35 | 25 | 8831 | 454A | YS11KAE | | 11.2 | 208 | 3 | 11700 | Z | 14.0 | L1R | - | BEL0095 | 1 | 1.8 | 115 | 1 | | | | O.C. | ECOSMART | 1 | F | F | EF | 5/8 | 5/8 | 3/8 | 100 | M | 11.2 |
| B | 102 | WALK-IN FREEZER | -10 | -20 | 10573 | 454A | YF10KAE | | 13.8 | 208 | 3 | 11050 | Z | 14.0 | L2R | - | BEL0130 | 1 | 1.5 | 208 | 1 | 13.7 | 208 | 1 | ELEC | ECOSMART | 1 | F | F | EF | 7/8 | 7/8 | 3/8 | 100 | M | 13.8 |

ALL EVAPORATOR COILS WILL REQUIRE A HOUSE POWER SUPPLY

c UL us LISTED

NOTE:
IT IS THE INSTALLING CONTRACTORS RESPONSIBILITY TO FOLLOW ALL APPLICABLE CODES AND CURRENT REFRIGERATION INDUSTRY STANDARDS AND PRACTICES WHEN DETERMINING LINE SIZES, AND INSTALLING AND STARTING UP RDT EQUIPMENT.


COMPRESSOR TYPE
Z SCROLL
H HERMETIC
S SEMI-HERMETIC
D DISCUS

DEFROST TYPE
O.C. OFF CYCLE
ELEC ELECTRIC

LINE TYPE
M MAIN - UP TO 100'
B BRANCH - UP TO 50'
T TRUNK - UP TO 200'


EVAPORATOR ACCESSORIES
EF EEV FACTORY EQUIPPED ON EVAP
TF TXV FACTORY EQUIPPED ON EVAP
F FACTORY EQUIPPED ON EVAP
O PROVIDED BY OTHERS
L LOOSE (FIELD INSTALLATION)

## PLANVIEW/ CLEARANCE REQUIREMENTS





NOTE: MINIMUM CLEARANCE REQUIRED FOR PROPER OPERATION
NOTE: ROOF CURB OR GROUND PAD CAN BE SAME SIZE AS OUTDOOR UNIT

## SUCTION LINE VERTICAL RISE DETAIL




- Install trap every transition from horizontal to vertical.
- Insulate suction lines with 3/4" wall Armaflex insulation.
- All joints brazed with minimum 15% silver content brazing rod.
- Install "P" trap on suction line every 15' vertical rise.
- Not to exceed 45' vertically over all.
- *If compressor is above the evaporator, Install inverted trap on top of the rise to prevent oil from seeping down when fixture(s) is turned off.

## EVAPORATOR DETAILS - MODEL BEL




| AIR DEFROST Size | DIMENSIONS A | B | C | D | CONNECTIONS (Inches) Coil Inlet | Suction | Drain | Approx. Net Wt. Lbs. | ELECTRICAL DATA Qty. Motors | EC Motor Fan Amps 115V | 208V |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | Inches | Inches | Inches | Inches | | | | | | | |
| 095 | 45-1/2 | 33-1/4 | - | - | 1/2 OD | 5/8 OD | 3/4 MPT | 51 | 2 | 1.8 | 1.0 |

| ELECTRIC DEFROST | DIMENSIONS A | B | C | D | CONNECTIONS (Inches) Coil Inlet | Suction | Drain | Approx. Net Wt. Lbs. | ELECTRICAL DATA Qty. Motors | EC Motor Fan Amps | Heater Amps as wired for 208-230/60/1 | 208-230/60/3 | 460/60/3 |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Inches | Inches | Inches | Inches | | | | | | | | | |
| 130 | 61-1/2 | 49-1/4 | - | - | 1/2 OD | 7/8 OD | 3/4 MPT | 71 | 3 | 1.5 | 13.7 | 8.5 | 6.8 |

EACH EVAPORATOR COIL:
- EQUIPPED WITH TWO LEAK SENSORS, PRE-MOUNTED AND PRE-WIRED
- SUPPLIED WITH A LIQUID LINE SHUT-OFF VALVE AND SUCTION LINE CHECK VALVE, SHIPPED LOOSE FOR FIELD INSTALL OUTSIDE OF COMPARTMENTS AND NO MORE THAN 10' FROM EVAPORATOR COIL.

## ZS SERIES ENGINEERING SPECIFICATIONS

Multi compressor, outdoor, air cooled. The refrigeration package shall be a pre-engineered and factory-assembled unit, trade name "ZS", as manufactured by Refrigeration Design Technologies, 1808 FM Road 66, P.O. Box 622, Waxahachie, Texas 75168. Phone: (972) 937-3215, Fax: (972) 937-0970.

1. Air-Cooled Refrigeration System
The RDT UL Listed "Air-Cooled" Refrigeration system shall be housed in a weather-protected compact powder coated steel frame. The entire housing shall be brushed stainless steel. The unit shall include an air-cooled aluminum fin copper tube condenser designed to operate at 15 degrees TD. The exterior housing shall feature stainless steel one piece louvers. Lifting points shall be integrated in the framing component. Condenser fan motors shall be mounted within the enclosure. The condenser intake surface shall be protected with stainless steel expanded metal guard to protect against vandalism and hail damage.

Each unit shall be equipped with a ball-bearing fan motor, suction filter, sight glass, liquid filter/drier, liquid line inlet and outlet valve, defrost cycle and high pressure super-hose connections. Each unit shall be equipped with fan cycling controls and/or head pressure regulator where required for low ambient conditions.

Condensing unit shall contain scroll, hermetic, semi-hermetic, and/or discus type compressor(s) assembled to operate with the refrigerant specified for both medium and low temperature applications.

2. Evaporator Coils
A. Evaporator coils shall be direct expansion type fabricated of copper tubes with aluminum fins.
B. All evaporator coils shall be provided with solenoid valve, thermostatic or electronic expansion valve and thermostat.

3. Pre-Piping
All refrigerant lines shall be extended to outside of the housing in a neat and orderly manner. All tubing shall be securely supported and anchored with non-corrosive coated clamps.

All joints must be brazed, not soldered.

All piping and controls shall be factory pressure-tested with dry nitrogen.

4. Control Panel
The package shall have a factory-mounted and pre-wired control panel, with main disconnect (non fused) where required, circuit breakers, contactors wired for single point power connection.

General Information
Contractors shall verify all dimensions onsite and coordinate with other trades.

General contractor shall prepare the platform, curbed openings and weatherproofing the unit after installation.

Refrigeration Contractor
All copper tubing to be refrigerant grade. A.C.R. or type "L".

Brazing should be used for all refrigerant piping. Silver solder or soft solder is not acceptable.

All piping to be pressure tested with nitrogen at 300 psi. After the condensing unit and coil have been connected the balance of the system shall be leak tested with the valves open at 200 psi.

The complete system shall be evacuated with a vacuum pump. Each unit should be charged tested and adjusted to assure operation.

Contractor should provide and install the drain-line heater in freezer. Heater shall be connected by electrical contractor. Seal all penetrations through the walk-in units with foam.

Electrical Contractor
Electrical contractor to provide power for refrigeration package and connect control and defrost system as called for in the wiring diagram.


Electrical contractor to connect drain-line heater in the freezer.

All electrical wiring and installation shall be in accordance with the wiring diagram and local codes. Seal all penetrations through the walk-in units with foam.

Plumbing Contractor
Plumbing contractor to provide copper drain lines for walk-in refrigerator and freezer, pitched 1/4" per foot of run. Trap drain-line outside of refrigerated space to avoid entrance of warm, moist air.


All plumbing installation shall be in accordance with local codes.

## EVAPORATOR MOUNTING DETAIL (TYPICAL)




| COIL MODEL | DISTANCE FROM WALL |
|---|---|
| BEL | 1-1/3"H |
| BEM/BEH | 1/2 " W |


## EVAPORATOR PLACEMENT & CLEARANCE REQUIREMENTS LOW PROFILE EVAPORATOR COILS (I.E. - BEL)




## WIRING DIAGRAM - ECOSMART - AKEA1AE DEMAND DEFROST W/KE2 DOOR SWITCH FOR WALK-IN COOLER WITH ONE COIL 115/60/1

*REFERENCE ENGINEERING SUMMARY FOR COIL AMP DRAW:


| SYS | DESCRIPTION | VOLTAGE |
|---|---|---|
| A | WALK-IN COOLER | 115/1 |




## WIRING DIAGRAM - ECOSMART - AKEB1EE DEMAND DEFROST W/KE2 DOOR SWITCH FOR WALK-IN FREEZER WITH ONE COIL 208-230/60/1

*REFERENCE ENGINEERING SUMMARY FOR COIL AMP DRAW:

| SYS | DESCRIPTION | VOLTAGE |
|---|---|---|
| B | WALK-IN FREEZER | 208/1 |




**APPROVAL STATUS**

THIS DRAWING REPRESENTS OUR UNDERSTANDING OF THE SPECIFICATIONS. PLEASE REVIEW IT CAREFULLY FOR ACCURACY. CLEARLY AND IN DETAIL NOTE CHANGES REQUIRED.

MARK APPROPRIATE BOX, SIGN, AND DATE BELOW.

- ☐ APPROVED FOR FABRICATION NO CHANGES
- ☐ APPROVED FOR FABRICATION WITH CHANGES NOTED
- ☐ REVISE AND RE-SUBMIT DRAWING

BY: _____ DATE: _____

**NOTICE**

THIS DRAWING BEING AN INSTRUMENT OF SERVICE IS AND WILL REMAIN PROPERTY OF REFRIGERATION DESIGN TECHNOLOGIES AND CANNOT BE USED WITHOUT WRITTEN AUTHORIZATION.

| No. | Revision/Issue | Date |
|---|---|---|
| 0 | ORIGINAL ISSUE | 10-02-25 |
| 1 | CHANGES PER NEW FLOOR PLAN | 1-17-25 |
| 2 | CHANGED TO A2L EQUIPMENT | 7-16-25 |


REFRIGERATION DESIGN TECHNOLOGIES
1808 FM Road 66 / P.O. Box 622
Waxahachie, Texas
(800) 736-9518
www.rdtonline.com


Consultant:
Foodservice Design professionals
The Woodlands, TX

Dealer
-
-

**Austin Parkway Elementary School**
**Sugarland, TX**

Project No: 31072
Designed By: A. RODRIGUEZ
Drawn By: A. RODRIGUEZ
Sheet 1.1 of sheets

ISSUE:
12/05/2024 DD PACKAGE
03/11/2025 50% CD PKG.
05/23/2025 90% CD PKG.
07/18/2025 ISSUED FOR BIDDING AND PERMITTING

FOODSERVICE DESIGN PROFESSIONALS


FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479


SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
46854119
PROFESSIONAL MEMBER
Melissa Moore
7/18/2025
THIS ITEM IS RELEASED FOR PERMITTING PURPOSES ONLY
MELISSA MOORE, FCSI NO. 46854119
ON: 07/18/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS CONDENSING UNITS

A-QF1.6








SECTION E – E





SECTION K – K


American Panel's walk-in floor panels with AmeriTuff structural support are designed to withstand uniformly distributed stationary loads of 15,000 lbs. per square foot. American Panel's warranty does not cover damage caused by pallet jacks, forklifts or any other form of heavy-duty rolling traffic. A concrete wearing floor must be installed on top of the AmeriTuff walk-in floor panels for those rolling applications.





COOLER DOOR ELEVATION





TRIM ANGLE
DETAIL #2





TRIM ANGLE
DETAIL #3





DOOR ELECTRICAL CONNECTION




CLOSURE PANEL ABOVE WALK-IN DETAIL #4E




PANEL MOUNTED ELECTRICAL CONNECTION




ROOF SUPPORT ANGLE
SPLIT PARTITION FLOOR & ROOF

| COOLER DOOR | |
|---|---|
| DOOR FRAME KWHr/DAY | 2.424 |

| FREEZER DOOR | |
|---|---|
| DOOR FRAME KWHr/DAY | 4.392 |

| WALK-IN PANEL R-8967 | | |
|---|---|---|
| BUILDING UNITS | R-8967 | 37M2 |
| USA | | |
| SURFACE BURNING CHARACTERISTICS | | |
| MATERIAL DETAILS | "FLAME SPREAD" | "SMOKE DEVELOPED" |
| ALUMINUM PANELS, PAINTED OR UNPAINTED, 5" OR LESS. | 15 | 250 |
| GALVANIZED STEEL OR STAINLESS STEEL PANELS, PAINTED OR UNPAINTED, 5" OR LESS*. | 10 | 400 TO 500 |
| CORE MATERIAL 6" THICK | 20 | 250 |

**AMERICAN PANEL WALK-IN COOLERS AND FREEZERS COMPLY WITH THE 2021 INTERNATIONAL ENERGY CONSERVATION CODE (IECC), SECTION C403.11**

**THIS AMERICAN PANEL WALK-IN WILL BE MANUFACTURED TO UL & NSF REQUIREMENTS. AMERICAN PANEL ACCEPTS NO LIABILITY FOR LOCAL CODE REQUIREMENTS OF WHICH AMERICAN PANEL HAS NOT BEEN MADE AWARE OF IN WRITING PRIOR TO FABRICATION.**

~SPECIFICATIONS~

BOX HEIGHT: FREEZER – 10'-2" OVERALL (9'-6 1/4" INTERIOR)
COOLER – 10'-2" OVERALL (9'-6 1/4" INTERIOR)

CONSTRUCTION: FOAMED IN PLACE
NSF LISTED, STANDARD NO. 7

INSULATION: 4" URETHANE, FINISHED PANEL
UL CLASSIFIED FLAME SPREAD 20
CORE SMOKE DEVELOPED 250

INSTALLATION: INDOOR

FLOOR: (SEE DETAILS)
FREEZER – AMERITUFF STRUCTURAL FLOOR
(1/8" INTEGRAL DIAMOND ALUMINUM TREAD PLATE, 3/4" MARINE PLYWOOD UNDERLAYMENT, FIBERGLASS GRATING SUPPORT)
COOLER – AMERITUFF STRUCTURAL FLOOR W/3/4" DEEP INTERIOR RAMP
(1/8" INTEGRAL DIAMOND ALUMINUM TREAD PLATE, 3/4" MARINE PLYWOOD UNDERLAYMENT, FIBERGLASS GRATING SUPPORT)

DOOR HARDWARE & ACCESSORIES: (EACH DOOR)
SMOOTH POLISHED DOOR HARDWARE
POWER TO BE STUBBED OUT CEILING PANEL
DRY CONTACT LEADS TO BE STUBBED OUT CEILING PANEL IN A SEPARATE STUB OUT
DEADBOLT HANDLE W/KEYED CYLINDER LOCK, PADLOCK PROVISION & QUARTER TURN INSIDE RELEASE (EXTERIOR DOOR ONLY)
1/8" STAINLESS STEEL THRESHOLD COVER PLATE
14 GA STAINLESS STEEL SUB THRESHOLD
FRAME HEATER WIRE
HYDRAULIC DOOR CLOSER
IC+ WALK-IN DOOR CONTROLLER AND ALARM SYSTEM INCLUDING:
INTEGRATED LIGHT SWITCH WITH AUTOMATIC LIGHT OFF AND 3-WAY & 4-WAY CAPABILITY
TEMPERATURE MONITOR AND LOGGER WITH HIGH TEMP. AND LOW TEMP. VISUAL AND AUDIO ALARM
F OR C TEMPERATURE SELECTION
INTEGRATED DRY CONTACT FOR ALARM SIGNALING & POWER FAILURE (1A @ 24VAC, 1A @ 30VDC)
DOOR AND WINDOW HEATER CONTROL (WHEN SO EQUIPPED)
HACCP PREVIEW VIA ONBOARD LCD SCREEN
HACCP DOWNLOAD VIA USB
WIFI CONNECTIVITY (INTERNET ENABLED WIFI NETWORK NEEDED)
BATTERY BACKUP
TEMPERATURE ALARM NOTIFICATION VIA EMAIL &/OR EMAIL TO SMS TEXT MESSAGES
POWER FAILURE NOTIFICATION VIA EMAIL &/OR EMAIL TO SMS TEXT MESSAGES (FOR THIS FEATURE TO WORK THE LOCAL WIFI NETWORK MUST BE POWER PROTECTED AND WORKING AT THE TIME OF POWER FAILURE EVENT)
AUTOMATIC AND ON DEMAND TRANSMISSION OF HACCP DATA VIA EMAIL
ADAPTIVE SETTINGS
MOMENTARY BACK-TO-BACK LIGHT SWITCH W/PILOT
25' AIR TEMPERATURE PROBE
25' SECOND PROBE (EXTENDED) FOR MONITORING THE TEMPERATURE AT A SECOND LOCATION OR FOR MONITORING A SECOND CABINET
DOOR SWITCH TO ENABLE DOOR AJAR ALARM, DOOR AJAR NOTIFICATION VIA EMAIL &/OR EMAIL TO SMS TEXT MESSAGES, AND AUTOMATIC LIGHTS ON WHEN DOOR OPENS
PANIC ALARM WITH ILLUMINATED PANIC BUTTON, ALARM BUZZER WITH LED, & NOTIFICATION VIA EMAIL &/OR EMAIL TO SMS TEXT MESSAGES (1-COOLER, 2-FREEZER)
KASON SCREW-IN VAPOR PROOF LIGHT FIXTURE
W/8.5 WATT SYLVANIA LED BULB & GLOBE
CCI CLEAR VU SWINGING DOOR
3 – KASON #1346 ADJUSTABLE SPRING LOADED HINGES
HEATED VISION WINDOW (14" x 24")
1/8" DIAMOND ALUMINUM TREAD PLATE KICKPLATES @ 36" HIGH S/S & O/S DOOR & FRAME

PANEL MOUNTED ACCESSORIES:
2 – KASON 1826 INTELLO-VENT WITH LIGHTS – FIELD INTERCONNECTION REQUIRED (FOAMED IN PANEL – PER PLAN) (2-COOLER, 2-FREEZER)

ACCESSORIES: (SHIPPED LOOSE)
2 – PCS. TRIM ANGLE – 18 GA STAINLESS STEEL, #3 FINISH
CLOSURE PANEL TO AN EXISTING CEILING (PER PLAN) — VERIFY LENGTH
18 GA STAINLESS STEEL, #3 FINISH
3 – 48" (1810LO) LED LIGHT FIXTURE(S) @ 40W EACH
1/8" DIAMOND ALUMINUM TREAD PLATE WAINSCOT @ 36" HIGH (EXPOSED EXTERIOR ONLY)
2 – BAKELITE LABEL(S) (BLACK) ("FREEZER", "COOLER")
1 – BAKELITE LABEL (YELLOW W/BLACK LETTERING) ("VACUUM PRESSURE RELIEF")
6 MIL POLYETHYLENE VAPOR BARRIER
6 – BELL BOX(ES) & COVER PLATE(S)
2 – DOOR STOP(S)
2 – EDWARDS 860 SERIES STROBE BEACONS
1 – EMERGENCY PRESSURE RELEASE
ROOF SUPPORT ANGLE W/BEAUTY TRIM

METAL FINISHES: INTERIOR & EXTERIOR DOOR & FRAME – 18 GA STAINLESS STEEL, #3 FINISH
INTERIOR WALLS & CEILING – WHITE .040 STUCCO ALUMINUM
EXPOSED EXTERIOR – 20 GA STAINLESS STEEL, #3 FINISH
UNEXPOSED EXTERIOR – 26 GA STUCCO ACRYLUME
EXTERIOR FLOOR & CEILING – 26 GA STUCCO ACRYLUME
INTERIOR FLOOR – AMERITUFF STRUCTURAL FLOOR
(1/8" INTEGRAL DIAMOND ALUMINUM TREAD PLATE, 3/4" AC PLYWOOD UNDERLAYMENT, FIBERGLASS GRATING SUPPORT)

REFRIGERATION: BY OTHERS

NOTE: THE LARGEST DOOR PANEL ON THIS JOB IS 57.5" x 118". CUSTOMER IS TO VERIFY THAT THIS PANEL SIZE WILL NOT CONFLICT WITH ANY JOB SITE RESTRICTIONS.

NOTE: CUSTOMER IS TO VERIFY ALL DIMENSIONS, SECTIONS, DETAILS AND SPECIFICATIONS

NOTE: MAXIMUM LIGHT CIRCUIT LOAD IS 1200W 120VAC TUNGSTEN, 5A 120VAC ELECTRONIC BALLAST. FOR HIGHER LOADS ADDITIONAL LIGHT FIXTURES MUST BE CONTROLLED VIA RELAY (BY OTHERS).

| ELECTRICAL DATA |
|---|
| ⚽ = POINT OF ELECTRICAL CONNECTIONS. |
| WALK-IN DOORS: 115v/1ø – 350w* |
| PANEL MOUNTED ACC: 115v/1ø – 23w (EACH VENT) |

*NOTE: ADD WATTAGE FOR EACH ADDITIONAL LIGHT FIXTURE IN ACCESSORIES.

| INSULATION R-VALUES | | |
|---|---|---|
| PANEL TYPE | COOLER | FREEZER |
| 4" WALLS, ROOFS | R-29 | R-32 |
| 5" WALLS, ROOFS | R-36 | R-40 |
| FLOORS | R-25 | R-28 |
| DOORS | R-32 | |

☐ APPROVED SIGNATURE
☐ APPROVED AS NOTED PRINT NAME
☐ REVISE & RESUBMIT DATE

1) Please verify that door swing and location are correct.
2) If this walk-in is to be installed in a depression, or quarry tile is to be applied to the interior, depression depths or tile thickness must be specified to insure proper door height.
3) All site preparation, floor or slab construction, plumbing, electrical connections (including control wiring) by others.
4) ⚽ Electrical: 115-60-1 required above latch side of each door, through ceiling, to operate frame heater and light.
5) Special note to General Contractor and his Sub Contractor for quarry tile or concrete wearing floors: the sheet metal panel facings may be susceptible to staining due to excessive moisture created by hydration of concrete type materials. Therefore, it is absolutely necessary that each room be properly ventilated. Also note that special precautions must be taken when using muriatic acid due to effects hydrochloric acid fumes have on aluminum and stainless steel.
6) This drawing and information contained herein are the exclusive property of American Panel Corporation. It shall be returned to American Panel Corporation upon demand and shall not be reproduced in whole or part, disclosed to anyone else, or used without the written consent of American Panel Corporation.

ITEM #102 Walk-In Cooler/Freezer

| REV. | DATE | DESCRIPTION | REV. BY | CK'D BY |
|---|---|---|---|---|
| A | 1/23/25 | REVISED SPEC | WS | WQ |

American Panel
AMERICAN PANEL CORPORATION
5800 S.E. 78th St. Ocala, Florida 34472
Ph. (352) 245-7055 Fax (352) 245-0726

CUSTOMER: FOODSERVICE DESIGN PROFESSIONALS
PROJECT: AUSTIN PARKWAY ES–FBISD – FORT BEND, TX
DATE: 10/4/24 | DRAWN BY: LC/TR | P.O.#:
SCALE: 3/8"=1'-0" | PROPOSAL#: PD213242 | JOB#: | SHEET: 1 of 1

ALL DIMENSIONS MUST BE FIELD VERIFIED PRIOR TO FABRICATION AND INSTALLATION

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS


FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
ELECTRONICALLY SIGNED AND SEALED USING AUTHENTICSEAL
MELISSA MOORE, FCSI NO. 48854119
ON: 07/15/2025

ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS WALK-INS

A-QF1.7





1 CC1 ITEM #1 PLAN

SCALE: 1/2" = 1'-0"





4 CC1 ITEM #1 SECTION VIEW

SCALE: 1/2" = 1'-0"





8 CC1 ITEM #1 CONTROL PANEL LAYOUT

SCALE: 1 1/2" = 1'-0"





2 CC1 ITEM #1 FRONT ELEVATION

SCALE: 1/2" = 1'-0"




11 CC1 ITEM #1 3D PERSPECTIVE

SCALE:




3 CC1 ITEM #1 REAR ELEVATION

SCALE: 1/2" = 1'-0"



12 CC1 ITEM #1 3D PERSPECTIVE 2


SCALE:




NOTE: THIS IS NOT A LOAD CENTER, THIS IS A JUNCTION/DISTRIBUTION BLOCK INSIDE THE BREAKER BOX

13 CC1 ELECTRICAL SCHEDULE

CASHIER COUNTER




NOTE: THIS IS NOT A LOAD CENTER, THIS IS A JUNCTION/DISTRIBUTION BLOCK INSIDE THE BREAKER BOX

18 CC1 ELECTRICAL SCHEDULE

HOT FOOD COUNTER #1
(TWO (2) REQUIRED)




NOTE: THIS IS NOT A LOAD CENTER, THIS IS A JUNCTION/DISTRIBUTION BLOCK INSIDE THE BREAKER BOX

16 CC1 ELECTRICAL SCHEDULE

HOT/FROST COUNTER
(TWO (2) REQUIRED)

EQUIPMENT BY OTHERS
COUNTERCRAFT LAYOUTS, MEPS, AND LOAD CENTERS ARE BASED ON SPECIFIED MANUFACTURERS AND MODELS AS OUTLINED IN THE SPECIFICATIONS IN THE CONTRACT DOCUMENTS. COUNTERCRAFT MUST BE NOTIFIED OF ANY CHANGES TO THE CONTRACT DOCUMENTS IN A TIMELY MANNER.

| NO. | REVISIONS PRELIMINARY DWG | DATE | BY |
|---|---|---|---|
| 1 | | 10/18/2024 | MAX |
| 2 | | | |
| 3 | | | |
| 4 | | | |
| 5 | | | |
| 6 | | | |
| 7 | | | |
| 8 | | | |
| 9 | | | |

ANOTHER QUALITY PRODUCT FROM
CounterCraft
7007 STEARNS HOUSTON,TEXAS 77021
(713) 747-3611

Austin Parkway ES FBISD
PROJ.CT
FOOD SERVICE CONSULTANTS
FOODSERVICE DESIGN PROFESSIONALS

PROJECT NO.
AUPES
DATE
10/18/2024
SCALE
As indicated
DRAWN BY
MAX.C
CHECKED BY
E.S
SHEET NO.
CC1
OF SHEET

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS


FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/18/2025
DIGITALLY SIGNING ON THIS DRAWING AUTHORIZED BY MELISSA MOORE, FCSI NO. 48854119 ON: 07/18/2025

MWA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS SERVING COUNTERS

A-QF1.8




2 CC2 LAYOUT

SCALE: 3/4" = 1'-0"

EQUIPMENT BY OTHERS
COUNTERCRAFT LAYOUTS, MEPS, AND LOAD CENTERS ARE BASED ON SPECIFIED MANUFACTURERS AND MODELS AS OUTLINED IN THE SPECIFICATIONS IN THE CONTRACT DOCUMENTS. COUNTERCRAFT MUST BE NOTIFIED OF ANY CHANGES TO THE CONTRACT DOCUMENTS IN A TIMELY MANNER.

| NO. | REVISIONS PRELIMINARY DWG | DATE | BY |
|---|---|---|---|
| 1 | | 10/18/2024 | MAX |
| 2 | | | |
| 3 | | | |
| 4 | | | |
| 5 | | | |
| 6 | | | |
| 7 | | | |
| 8 | | | |
| 9 | | | |

ANOTHER QUALITY PRODUCT FROM
CounterCraft
7007 STEARNS HOUSTON,TEXAS 77021
(713) 747-3611

PROJECT: Austin Parkway ES FBISD
FOODSERVICE CONSULTANT: FOODSERVICE DESIGN PROFESSIONALS

PROJECT NO. AUPES
DATE 10/18/2024
SCALE: 3/4" = 1'-0"
DRAWN BY MAX.C
CHECKED BY E.S
SHEET NO. CC2
OF SHEET

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FDP
FOODSERVICE DESIGN PROFESSIONALS


FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025 PREPARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO 48854119 ON 07/15/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS SERVING COUNTERS

A-QF1.9




1 FOOD SERVICE EQUIPMENT PLAN - DEMO PLAN
1/4" = 1'-0"

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL


FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
FCSI
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/18/2025
THIS ITEM APPEARING ON THIS SHEET WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 48854119 ON: 07/18/2025

ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

FS EXISTING EQUIPMENT PLAN

A-QF2.0




4 FOOD SERVICE ELECTRICAL PLAN - TEMPORARY SERVING
1/4" = 1'-0"

| FOOD SERVICE ELECTRICAL SCHEDULE - TEMPORARY SERVING | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR ELECTRICAL COORDINATION NOTES | | | | | | | | |
| FDP ENO | FDP ECONN | FDP ELOAD | FDP EVOLT | FDP EPH | FDP ESERVICE TO | FDP ELOC | FDP EAFF | FDP EREMARKS |
| E800A | DR | 16.0A | 120 | 1 | CONVENIENCE | WALL | 24" | --- |
| E800B | DR | 16.0A | 120 | 1 | CONVENIENCE | WALL | 24" | DEDICATED CIRCUIT |
| E800C | JB | --- | --- | -- | DATA CONNECTION | WALL | 24" | --- |
| E806 | DR | 16.0A | 120 | 1 | TRANSPORT CABINET | WALL | 24" | --- |
| E808 | JB | 7.8A | 120/208 | 1 | HEATED CABINET | WALL | 96" | BTC; OMIT PLUG, UNIT TO BE HARDWIRED |
| E809 | JB | 8.2A | 120 | 1 | REFRIGERATOR | WALL | 96" | BTC; OMIT PLUG, UNIT TO BE HARDWIRED |
| E810 | CS/SR | 13.3A | 208 | 1 | (4) HOT WELLS | WALL | 24" | EXTEND TO EQUIPMENT - CONFIRM NEMA PLUG |
| E810A | SR | 7.9A | 208 | 1 | (2) HOT WELLS | WALL | 24" | EXTEND TO EQUIPMENT - CONFIRM NEMA PLUG |
| E810B | DR | 5.0A | 120 | 1 | COLD PAN | WALL | 24" | EXTEND TO EQUIPMENT |
| E810C | DR | 10.0A | 120 | 1 | BEVERAGE | WALL | 24" | EXTEND TO EQUIPMENT |
| E811 | DR | 16.0A | 120 | 1 | CASH REGISTER | WALL | 24" | DEDICATED CIRCUIT - EXTEND TO EQUIPMENT |
| E811A | JB | - | --- | 1 | POS | WALL | 24" | BTC |

| | | | | | |
|---|---|---|---|---|---|
| | SCR | CONDUIT STUB BTC ON RECEPT FURNISH WITH EQUIPMENT | | CC | CONDUIT FOR COMPUTER CABLES |
| • | CS | CONDUIT STUB UP/OUT FOR DIRECT CONNECTION | | BTC | BRANCH TO CONNECTION ON EQUIPMENT |
| | DR | DUPLEX RECEPTACLE | | WPR | WATERPROOF RECEPTACLE (SPRING COVER) |
| | SR | SINGLE PURPOSE RECEPTACLE-1PH | | FPB | FIRE PROTECTION BUZZER |
| | SR | SINGLE PURPOSE RECPTACLE-3PH | | BSC | BEVERAGE SYSTEM CONDUIT |
| | FR | FLUSH FLOOR RECEPTACLE | | DFA | DROP FROM ABOVE |
| | PMR | PEDESTAL MOUNTED RECEPTACLE | | AFF | ABOVE FINISH FLOOR |
| | DCR | DROP CORD RECEPTACLE | | CS/JB | JUNCTION BOX ON PEDESTAL |
| | JB | JUNCTION BOX ON CEILING | 1 | SW | SWITCH |
| | JB | JUNCTION BOX IN WALL | | D | DATA |
| | JB/DS | JUNCTION BOX WITH DISCONNECT BY DIV.26 | | | |


5 ELECTRICAL SYMBOLS 1
NOT TO SCALE

| FOOD SERVICE PLUMBING SCHEDULE - TEMPORARY SERVING | | | | | | |
|---|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR PLUMBING COORDINATION NOTES | | | | | | |
| FDP PNO | FDP PSIZE | FDP PCONN | FDP PSERVICE TO | FDP PLOC | FDP PAFF | FDP PREMARKS |
| | | | | | | |
| P11C | 1/2" | H & C WATER | FAUCET | WALL | 18" | FURNISHED & INSTALLED BY DIV. 22 |
| P11D | 1 1/2" | DIRECT DRAIN | HAND SINK | WALL | 15" | FURNISHED & INSTALLED BY DIV. 22 |
| P249 | 3/4" | H & C WATER | FAUCET | WALL | 13" | BTC |


| | | | | | |
|---|---|---|---|---|---|
| | HW | HOT WATER | | FFD | FUNNEL FLOOR DRAIN |
| | CW | COLD WATER | | EVC | EXHAUST VENT CONNECTION |
| | HTW | 180 F HOT WATER | | SVC | SUPPLY VENT CONNECTION |
| | | CHILLED WATER | | FR | DIRECT-CONNECTED FLUE RISER |
| | W | DIRECT WASTE | | PS | PIPE SLEEVE |
| | IW | INDIRECT WASTE | | | COMPRESSED AIR |
| | | GAS SUPPLY | | | CO2 |
| | | STEAM SUPPLY | | AFF | ABOVE FINISHED FLOOR |
| | CR | CONDENSATE RETURN | | BTC | BRANCH TO CONN. ON EQUIP |
| | DR | DRAIN | | DFA | DROP FROM ABOVE |
| | FD | FLOOR DRAIN | | CLG | CEILING |
| | FST | FLOOR SINK 3/4 GRATE | | | |
| | FSH | FLOOR SINK 3/4 GRATE | | | |

3 PLUMBING SYMBOLS 1
NOT TO SCALE

| FOOD SERVICE EQUIPMENT SCHEDULE - TEMPORARY SERVING | | | | | |
|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR GENERAL CONTRACTOR & HEALTH DEPARTMENT COORDINATION NOTES | | | | | |
| FDP ITEM | FDP QTY | FDP DESCRIPTION | FDP REMARKS | MANUFACTURER | MODEL |
| 804 | 2 | S/S SPLASH GUARDS | | CUSTOM FABRICATED | |
| 805 | 1 | THREE COMPARTMENT SINK NO DISPOSER | EXISTING | | |
| 806 | 4 | TRANSPORT CART | EXISTING | | |
| 807 | 2 | HAND SINKS | EXISTING / RELOCATE | | |
| 808 | 2 | REACH IN HEATED CABINET - 1DR | EXISTING | | |
| 809 | 2 | REACH IN REFRIGERATOR - 1DR. | EXISTING | | |
| 810 | 1 | DRY STORAGE SHELVING | EXISTING / RELOCATE | | |
| 811 | 1 | CASH REGISTER | OWNER FURNISHED | | |
| 812 | 1 | SERVING COUNTER | EXISTING / RELOCATE | | |




1 FOOD SERVICE EQUIPMENT PLAN - TEMPORARY SERVING
1/4" = 1'-0"




2 FOOD SERVICE PLUMBING PLAN - TEMPORARY SERVING
1/4" = 1'-0"

62

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL


FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
THIS ITEM IS PREPARING ON THIS DATE AND NOT INTENDED OR AUTHORIZED BY MELISSA MOORE, FCSI NO. 48854119 ON: 07/18/2025

MWA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

FS EQUIPMENT PLAN - TEMPORARY SERVING & MEPS


A-QF2.1




8 ELEVATION @ TRAY DROP
1/2" = 1'-0"




4 ELEVATION @ SETUP AREA B
1/2" = 1'-0"




7 ELEVATION @ UTENSIL WASH
1/2" = 1'-0"




3 ELEVATION @ PRODUCTION LINE A
1/2" = 1'-0"




10 ELEVATION @ HOLDING AREA
1/2" = 1'-0"




6 ELEVATION @ PREP SINK
1/2" = 1'-0"




2 ELEVATION @ PRODUCTION LINE B
1/2" = 1'-0"



9 ELEVATION @ WAREWASH
1/2" = 1'-0"



5 ELEVATION @ SETUP AREA A
1/2" = 1'-0"



1 ELEVATION @ WORKTABLE
1/2" = 1'-0"

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479


SEAL

FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
ELECTRONICALLY SEALED APPEARING ON THIS DOCUMENT IS AUTHORIZED BY MELISSA MOORE, FCSI 48854119 ON 07/18/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS ELEVATIONS


A-QF3.1




## 2 RENO MECHANICAL FLOOR PLAN - KITCHEN AREA

SCALE: 1/8" = 1'-0"

NORTH




## 1 EXIST/DEMO MECHANICAL FLOOR PLAN - KITCHEN AREA

SCALE: 1/8" = 1'-0"

NORTH

## MECHANICAL RENO KEYED NOTES

1. TIE-IN NEW DUCTWORK TO EXISTING DUCTWORK AT WALL PENETRATION.
2. CONNECT NEW AIR DEVICE AND TAP TO EXISTING E/A TRUNK DUCT.
3. EXISTING KITCHEN HOOD AND ASSOCIATED EXHAUST DUCTWORK AND FAN SHALL REMAIN. VERIFY OPERATION AND REPORT ANY DEFICIENCIES TO THE A/E FOR REVIEW.
4. NEW 6" DRYER FLUE VENT DUCT AND TO VENT CAP.
5. TEMP. KITCHEN – CEILING MOUNTED CABINET EXHAUST FAN.
6. TEMP. KITCHEN – 24"X24" SIDE WALL GRILLE. SURFACE MOUNT OPTIONAL. AUXILIARY FRAME: TITUS CT-700.
7. NEW DISH MACHINE: TWO (2) 4"X16" EXHAUST DUCT CONNECTIONS. TRANSITION. PROVIDE NEW CONDENSATE EXHAUST DUCTWORK TO NEW ROOF MOUNTED EXHAUST FAN.
8. NEW ROOF MOUNTED EXHAUST FAN SERVING DISH MACHINE. INSTALL ON EXISTING ROOF OPENING.
9. INLINE FAN INSTALLED ABOVE PLENUM.
10. TEMPORARILY RELOCATE THERMOSTAT (TIED TO CAFTETERIA AHU) TO COLUMN LOCATED OUTSIDE OF TEMPORARY KITCHEN AREA. THERMOSTAT TO BE MOVED BACK TO THE ORIGINAL LOCATION AFTER REMOVAL OF THE TEMPORARY KITCHEN. RELOCATION SHALL BE NON-DESTRUCTIVE, AS TO NOT DAMAGE EXISTING FINISHES WHEN REINSTALLED IN ORIGINAL LOCATION.

## MECHANICAL DEMO KEYED NOTES

1. DEMOLISH EXISTING AIR DEVICE, BRANCH DUCT, DAMPER AND TAP BACK TO TRUNK DUCT. CAP AND SEAL RESULTING OPENING.
2. EXISTING E/A TRUNK DUCT TO REMAIN.
3. EXISTING E/A DUCTWORK AND EXHAUST FAN SERVING KITCHEN HOOD SHALL REMAIN FOR FUTURE USE.
4. DEMOLISH ALL EXISTING AIR DEVICES, DUCTWORK, AND DUCTWORK ACCESSORIES SERVING KITCHEN AREA BACK TO MECH. ROOM WALL PENETRATION.
5. REFURBISH EXISTING KITCHEN HOOD. REFER TO "KITCHEN HOOD REFURBISHMENT NOTES".
6. DEMOLISH EXISTING CONDENSATE HOOD, ASSOCIATED DUCTWORK, AND ROOF EXHAUST FAN.
7. DEMO AND CAP EXISTING DRYER VENT AND FLUE.

## EXHAUST FAN SCHEDULE

| MARK | EF-TK | EF-CF | EF-14 |
|---|---|---|---|
| SERVES | TEMPORARY KITCHEN | COOLER/FREEZER | DISH WASHER |
| TYPE | CEILING CABINET | INLINE FAN | ROOF UPBLAST |
| DRIVE | DIRECT | DIRECT | DIRECT |
| SPEED CONTROL | CONSTANT | CONSTANT | CONSTANT |
| CFM | 1055 | 1000 | 1200 |
| EXT. S.P. (IN. W.G.) | 0.3 | 0.35 | 0.75 |
| IMP. SIZE (IN.) | 8.0 | 13.5 | 14 |
| HORSEPOWER (WATTS) | 1/3 HP | 1/6 HP | 1/4 HP |
| VOLTAGE | 120V/1-PHASE | 120V/1-PHASE | 120V/1-PHASE |
| MANUFACTURER | COOK | COOK | COOK |
| MODEL | GC-862 | 1355QN10D | CUE-140-VG |
| SONES (MAX.) | 15.0 | 15.0 | 15.0 |
| NOTES | 1,2,3,4 | 1,2,3,4 | 1,2,3,4,5,6 |

NOTES

1. STATIC PRESSURE SHOWN IS EXTERNAL TO THE UNIT. MANUFACTURER SHALL ADD DAMPER AND ACCESSORY LOSSES TO THIS VALUE BEFORE SELECTING FAN. FANS SHALL BE CAPABLE OF 120% OF THE SCHEDULED CFM CAPACITY.
2. INTEGRAL DISCONNECT SWITCH.
3. RUBBER IN-SHEAR ISOLATORS.
4. BACKDRAFT DAMPER.
5. BIRD SCREEN AND NEW ROOF CURB
6. REFER TO WRITTEN SPECS FOR ADDITIONAL REQUIREMENTS.

## AIR DEVICE SCHEDULE

| MARK | DESCRIPTION |
|---|---|
| A | CEILING DIFFUSER – 24" X 24" FACE, PATTERN TYPE, STEEL CONSTRUCTION, OBD/RADIATION DAMPER, WHITE FINISH, U.L. LISTED PRICE SCD A1-12" X 12" |
| B | CEILING RETURN GRILLE – 24" X 24" PERFORATED FACE, STEEL CONSTRUCTION, RADIATION DAMPER, WHITE FINISH, U.L. LISTED PRICE PDFR B1-12" X 12" |
| C | CEILING EXHAUST GRILLE – 24" X 24" PERFORATED FACE, STEEL CONST., OBD/RADIATION DAMPER, WHITE FINISH, NECK SIZE SHOWN, U.L. LISTED PRICE PDDR C1-12" X 12" |

NOTES:

1. REFER TO ARCHITECTURAL REFLECTED CEILING PLAN TO VERIFY CEILING TYPES FOR AIR DEVICES.

## KITCHEN HOOD REFURBISHMENT NOTES

HOOD REFURBISHMENT FOR KITCHEN HOODS (QUANTITY 2):

- STEAM WASH AND DEEP CLEAN STAINLESS STEEL HOOD ASSEMBLY, CASING, AND SUPPLY GRILLES WHERE APPLICABLE.
- REPLACE GREASE FILTER RACKS.
- CLEAN EXISTING MAKE-UP AIR AND GREASE EXHAUST DUCT.
- RELAMP EXISTING LIGHT FIXTURES WITH NEW 4000K BULBS LISTED FOR USE IN AN ENCLOSED KITCHEN HOOD FIXTURE.
- COORDINATE WITH DIVISION 11 FOR REPLACEMENT OF ANSUL FIRE SUPPRESSION SYSTEM.
- HOOD ASSEMBLIES SHALL BE CLEANED TO MEET THE STANDARDS ESTABLISHED IN NFPA STANDARD 96.

STANTON ENGINEERING GROUP
INFORMATION@STANTONENGINEERING.COM (713) 300-6056
TEXAS ENG. FIRM REG. NO. F-01833210 © ALL RIGHTS RESERVED
12800 W. SAM HOUSTON PARKWAY N., SUITE 121, HOUSTON, TX 77064

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL

STATE OF TEXAS
TYLER W. HERRING
106052
LICENSED PROFESSIONAL ENGINEER
07.18.2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

LEVEL 1 KITCHEN MECHANICAL PLANS
A-M1.01

## MECHANICAL SYMBOL SCHEDULE

| | |
|---|---|
| CWS | CONDENSER WATER SUPPLY |
| CWR | CONDENSER WATER RETURN |
| CHS | CHILLED WATER SUPPLY |
| CHR | CHILLED WATER RETURN |
| HWS | HEATING WATER SUPPLY |
| HWR | HEATING WATER RETURN |
| RS | REFRIGERANT SUPPLY |
| RR | REFRIGERANT RETURN |
| D | CONDENSATE LINE |
| | PETE'S PLUG |
| | ISOLATION VALVE |
| | ELECTRONIC CONTROL VALVE |
| | BUTTERFLY VALVE |
| | BALL VALVE |
| | UNION OR FLANGE |
| | STRAINER |
| | AUTOMATIC AIR VENT |
| T | LOCAL CONTROL THERMOSTAT |
| T | TEMPERATURE SENSOR |
| H | HUMIDITY SENSOR |
| FD | FIRE DAMPER |
| SD | SMOKE DAMPER |
| FSD | FIRE/SMOKE COMBINATION DAMPER |
| MD | MOTORIZED DAMPER |
| C | CARBON MONOXIDE SENSOR |
| CO2 | CARBON DIOXIDE SENSOR |
| | SUPPLY AIR DIFFUSER |
| | RETURN AIR GRILLE |
| | EXHAUST GRILLE |
| 10 | RETURN AIR OPENING IN WALL |
| VD | VOLUME DAMPERS |
| | DUCT ELEVATION CHANGE |
| | 90° DUCT ELBOW WITH TURNING VANES |
| | FLEXIBLE DUCT |

| | |
|---|---|
| M | DAMPER MOTOR |
| T | TEMPERATURE TRANSMITTER |
| FS | FLOW SWITCH |
| P | DIFFERENTIAL PRESSURE SENSOR |
| SD | DUCT SMOKE DETECTOR |
| PS | STATIC PRESSURE SENSOR |
| PH | STATIC PRESSURE SENSOR HI-LIMIT |
| | ACCESS PANEL |

| | |
|---|---|
| A.P. | ACCESS PANEL |
| AHU | AIR HANDLING UNIT |
| B | BOILER |
| CH | CHILLER |
| CHP | CHILLED WATER PUMP |
| CVT | CONSTANT VOLUME TERMINAL |
| DH | DEHUMIDIFIER |
| E/A | EXHAUST AIR |
| EF | EXHAUST FAN |
| F&B | FACE & BYPASS |
| FF | FLY FAN |
| HDT | HORIZONTAL DRAW THROUGH |
| HWP | HOT WATER PUMP |
| KEF | KITCHEN EXHAUST FAN |
| KSF | KITCHEN SUPPLY FAN |
| O/A | OUTSIDE AIR |
| OBD | OPPOSED-BLADES DAMPER |
| PT | PRE-TREAT |
| R/A | RETURN AIR |
| RAHU | ROOF-MOUNTED AIR HANDLING UNIT |
| S/A | SUPPLY AIR |
| SA | SOUND ATTENUATOR |
| SF | SUPPLY FAN |
| SPD | SPILTER DAMPER |
| SZ | SINGLE ZONE |
| VAV | VARIABLE AIR VOLUME |
| VB | VAV BOX |
| VD | VOLUME DAMPER |
| VDT | VERTICAL DRAW THROUGH |
| VFD | VARIABLE FREQUENCY DRIVE |
| WH | WATER HEATER |
| ⌀ | DESIGNATION FOR "ROUND" |
| ⌀ | DESIGNATION FOR "OVAL" |

## GENERAL MECHANICAL NOTES


1. REFER TO WRITTEN SPECIFICATIONS FOR ADDITIONAL INFORMATION.
2. COORDINATE INSTALLATION OF EQUIPMENT AND PIPING WITH THE ELECTRICAL CONTRACTOR TO INSURE NEC CLEARANCE (42 INCHES) IN FRONT OF ALL ELECTRICAL PANELS. DO NOT INSTALL DUCTWORK OR WATER PIPING OVER THE TOP OF ELECTRICAL PANELS SEE DETAIL 1/M2.01.
3. DUCT SIZES SHOWN ARE NET FREE AIR PASSAGE DIMENSIONS, DUCTS ARE NOT LINED, BUT ARE EXTERNALLY INSULATED. RUNOUTS TO CEILING OUTLETS SHALL BE EXTERNALLY INSULATED GALVANIZED SHEET METAL WITH SPIN-IN V.D. AT TRUNK TAPS, SEE DETAIL 1 & 2/M2.01.
4. REFER TO ARCHITECTURAL REFLECTED CEILING DRAWINGS FOR EXACT LOCATIONS OF CEILING OUTLETS IN RELATION TO OTHER CEILING ENTITIES. OUTLETS MUST BE COMPATIBLE WITH THE CEILING TYPES FOR THE VARIOUS AREAS.
5. IN AREAS WHERE SUPPLY AIR ENTERS CEILING CAVITY THRU RETURN AIR GRILLES AND FREE RETURNS TO AHU'S VIA CEILING CAVITY, PROVIDE RETURN AIR OPENING IN WALL-TO-DECK ABOVE CEILING THAT BLOCK PATH, REFER TO ARCHITECTURAL DRAWINGS. RETURN AIR ELBOWS SHALL BE SIZED AT 1 SQ. FT PER 400 CFM SUPPLY AIR.
6. ARRANGE PIPING CONNECTIONS TO ALL EQUIPMENT TO ALLOW EASY REMOVAL OF EQUIPMENT, SUB-ASSEMBLIES, COILS, FANS, MOTORS, FILTERS, ACCESS PANELS, ETC... PROVIDE UNIONS, FLANGES AND VALVES AT CONNECTIONS. PROVIDE AND INSTALL VICTAULIC JOINTS AT COILS, REF. SPECIFICATIONS. PLACE STOP VALVES ON SYSTEM SIDE OF REMOVABLE PIPE SECTIONS.
7. CONTRACTOR SHALL FIELD MEASURE STRUCTURAL ELEMENTS AND COORDINATE EQUIPMENT, PIPING AND DUCT ROUTING TO FIT EXISTING CONSTRUCTION. PROVIDE OFFSETS, BOOTS FOR ENVELOP OBSTRUCTIONS THAT CANNOT BE AVOIDED. CONSTRUCTION SHALL BE PER SMACNA FIGURE 2-10.

## AIR DEVICE SCHEDULE

| MARK | DESCRIPTION |
|---|---|
| A | CEILING DIFFUSER – 24" X 24" FACE, PATTERN TYPE, STEEL CONSTRUCTION, OBD/RADIATION DAMPER, WHITE FINISH, U.L. LISTED PRICE SCD |
| B | CEILING RETURN GRILLE – 24" X 24" PERFORATED FACE, STEEL CONSTRUCTION, RADIATION DAMPER, WHITE FINISH, U.L. LISTED PRICE PDFR |
| C | CEILING EXHAUST GRILLE – 24" X 24" PERFORATED FACE, STEEL CONST., OBD/RADIATION DAMPER, WHITE FINISH, NECK SIZE SHOWN, U.L. LISTED PRICE PDDR |

NOTES:

1. REFER TO ARCHITECTURAL REFLECTED CEILING PLAN TO VERIFY CEILING TYPES FOR AIR DEVICES.
2. ALL CEILINGS ARE FIRE RATED PER U.L. LISTINGS ON ARCHITECTURAL DRAWINGS. PROVIDE FIRE PROTECTION FOR ALL CEILING DEVICES PER DETAIL 13/M-17 AND SPECIFICATIONS.





### 6 KITCHEN UPBLAST EXHAUST FAN DETAIL

NO SCALE

NOTES

1. ARCHITECTURAL ROOF CURB INSTALLATION REQUIREMENTS SHALL SUPERCEDE THIS DETAIL.
2. INSTALL SHEETMETAL COVERING OVER WOOD BLOCKING IN THE AIRSTREAM OR OPEN TO THE CEILING CAVITY.





### 5 AIR DEVICE DETAIL

NO SCALE

NOTES:

1. RADIATION DAMPER SHALL ONLY BE PROVIDED IN CEILING DEVICES INSTALLED IN RATED CEILING ASSEMBLIES. REFER TO ARCHITECTURAL REFLECTED CEILING PLAN TO DETERMINE WHICH, IF ANY, CEILINGS ARE RATED.
2. REFER TO SPECIFICATIONS OF FOR ADDITIONAL INFORMATION AND REQUIREMENTS.





### 4 EXTERNALLY INSULATED DUCT SUPPORT DETAIL

NO SCALE

NOTES:

1. ROUND MEDIUM PRESSURE DUCT MAY BE SUPPORTED WITH DUCT STRAPS.
2. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.




| TAP SIZE | ROD SIZE | DAMPER THICKNESS |
|---|---|---|
| UP TO 10" | 1/4" | 20 GA |
| OVER 10" | 3/8" | 18 GA |


HARDWARE MANUFACTURERS SHALL BE VENTLOCK, AMERICAN ELGEN, YOUNG AND DURO-DYNE.

### 3 DUCT TAP CONNECTION DETAIL

NO SCALE

NOTES:

1. DELETE CONICAL SECTION IF TOO LARGE FOR THE DUCT.
2. REFER TO SPECIFICATIONS OF FOR ADDITIONAL INFORMATION AND REQUIREMENTS.





### 2 DUCTWORK DETAIL

NO SCALE

NOTES:

1. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.




### 1 MECHANICAL - ELECTRICAL COORDINATION DETAIL

NO SCALE

NOTES:

1. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL


STATE OF TEXAS
TYLER W. HERRING
106052
LICENSED PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

MECHANICAL NOTES AND DETAILS
A-M2.01


STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM | TEXAS ENG. FIRM REG. NO. F-01833 | © 2021 ALL RIGHTS RESERVED
(713) 300-6282 | 1300 W. SAM HOUSTON PARKWAY S., SUITE 121, HOUSTON, TX 77042





## 5 RESIDENTIAL CLOTHES DRYER FLUE VENT

NO SCALE

NOTES:

1. VENT TERMINATION AT WALL FOR STACKABLE WASHER/DRYER SHALL BE AT 60" AFF.
2. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.





## 4 SUPPLY/EXHAUST KITCHEN PLENUM DETAIL

NO SCALE

NOTES:

1. xxxxx





## 3 ROOF EXHAUST FAN AND VENT DETAIL

NO SCALE


NOTES:

1. NO WOOD BLOCKING SHALL BE LEFT EXPOSED IN THE CEILING PLENUM. COVER ALL EXPOSED WOOD WITH 1/2" SHEETROCK OR 20 GAUGE GALVANIZED SHEETMETAL.
2. ROOF VENT WILL NOT HAVE FAN/MOTOR ASSEMBLY, DISCONNECT SWITCH OR OBD.
3. ARCHITECTURAL ROOF CURB INSTALLATION REQUIREMENTS SHALL SUPERCEDE THIS DETAIL WHERE APPLICABLE.
4. ALL FANS SCHEDULED TO BE PROVIDED WITH 140MPH WIND RATING, INCLUDING FACTORY PROVIDED CURB. CURB INSTALLATION SHALL FOLLOW MANUFACTURER'S REQUIREMENTS FOR SECURING TO ROOF AND EQUIPMENT WHERE IT DIFFERS FROM THE DETAIL.
5. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.




## 2 INLINE EXHAUST FAN DETAIL

NO SCALE




## 1 CABINET EXHAUST FAN

NO SCALE

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL

STATE OF TEXAS
TYLER W. HERRING
106052
LICENSED PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

MECHANICAL DETAILS (CONT'D.)

A-M2.02


STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM (713) 300-4080
TEXAS ENG. FIRM REG. NO. F-018337-00 2025 ALL RIGHTS RESERVED
13915 N. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77060

# ELECTRICAL AND LOW VOLTAGE LEGEND AND SYMBOLS

- A — TYPE 'A' LIGHT FIXTURE
- LIGHT FIXTURE WITH EMERGENCY BACKUP
- EXIT SIGN/EXIT SIGN WITH DIRECTIONAL ARROW
- EMERGENCY EGRESS LIGHT FIXTURE
- WALL MOUNTED FIXTURE OR SCONCE
- CEILING DOWNLIGHT OR CYLINDER
- WALL PACK FIXTURE
- INV — LIGHTING INVERTER

- $S^1/S^3/S^4$ — 20A, 277V TOGGLE/3-WAY/4-WAY SWITCH
- $S^2$ — 20A, 277V MOMENTARY 3-POSITION TOGGLE SWITCH
- $S^2$ — 20A, 277V, MOMENTARY 3-POSITION KEY SWITCH
- $S^1/S^3/S^4$ — 20A, 277V MAINTAINED 2-POSITION/3-WAY/4-WAY KEY SWITCH
- $S^{LT}$ — 20A, 277V TOGGLE SWITCH W/ INTEGRAL NIGHT LIGHT
- $S^{MP}$ — MOTOR RATED ON/OFF SWITCH, MP W/ PILOT LIGHT (SWITCH RATING SHALL BE ≥ UPSTREAM OCPD & VOLTAGE)
- DPST $ — DOUBLE POLE SINGLE THROW (DPST) SWITCH WITH RED PILOT LIGHT.
- TDR — TIMER SWITCH

## NETWORK LIGHTING CONTROLS

- MB — MULTIBUTTON LOW VOLTAGE LIGHTING SWITCH PROVIDE NUMBER OF BUTTONS INDICATED IN SINGLE PLATE.
- MD — MULTIPLE DIMMER SWITCHES PROVIDE NUMBER OF SWITCHES INDICATED IN SINGLE PLATE.
- MK — MULTIPLE KEY TYPE SWITCHES PROVIDE NUMBER OF SWITCHES INDICATED IN SINGLE PLATE.
- VSC — WALL SENSOR SWITCH
- $D — 20A, 277V, STANDALONE DIMMER SWITCH (DISPLAY CABINET)
- CSC — 360° CEILING SENSOR
- CSW — 180° CEILING SENSOR
- CSC — CEILING SENSOR
- WSC — WALL MOUNT SENSOR
- PCS — DAYLIGHT PHOTOSENSOR
- RC / RCK — LIGHTING ROOM CONTROLLER/POWER PACK
- ELR — EMERGENCY LIGHTING RELAY/CONTROL UNIT
- PLC — PLUG LOAD CONTROLLER

- 20A, 125V SIMPLEX/DUPLEX/QUAD RECEPTACLE
- GFI — 20A, 125V DUPLEX RECEPTACLE WITH GFCI PROTECTION
- GFI WP — 20A, 125V DUPLEX RECEPTACLE WITH GFCI PROTECTION AND WEATHERPROOF COVER.
- GFI — REMOTE GFCI DEVICE, REF SPECS AND EDF GFI DETAIL.
- USB-A — 20A, 125V DUPLEX/QUAD RECEPTACLE W/ USB-A PORTS PROVIDE 2-5A PORTS PER DEVICE — HUBBELL USB20A5
- IG — 20A, 125V SIMPLEX/DUPLEX/QUAD IG/COMPUTER RECEPTACLE
- GFI IG — 20A, 125V, IG/COMPUTER DUPLEX RECEPTACLE WITH GFCI
- PLUG LOAD CONTROLLED DUPLEX
- NEMA / IEC / CS — NEMA/IEC/CS NUMBERED POWER OUTLET MATCH PROVIDED EQUIPMENT CONNECTION OR CIRCUIT.
- TV IG — 20A, 125V IG DUPLEX RECEPTACLE AT PROJECTOR, TV, OR INTERACTIVE MEDIA LOCATION.
- LOW VOLTAGE OUTLET
- CEILING MOUNTED RECEPTACLE
- CEILING MOUNTED LOW VOLTAGE OUTLET
- SINGLE SERVICE FLOOR BOX WITH DUPLEX/QUAD REC
- SINGLE SERVICE FLOOR BOX WITH DUPLEX/QUAD IG REC
- SINGLE SERVICE LOW VOLTAGE FLOOR BOXES
- MULTI SERVICE FLOOR BOX WITH QUAD/QUAD IG REC
- CR — CORD REEL
- DC — DROP CORD
- EPO — EMERGENCY POWER OFF (EPO) SWITCH
- PB — PUSH BUTTON
- SP — TELEPOWER POLE

- J — J-BOX
- CEILING MOUNTED J-BOX
- CA — J-BOX FOR ACCESS CONTROL DEVICE
- HD — JUNCTION BOX AND FINAL CONNECTION TO HAND DRYER BY DIVISION 26.
- HDWR — JUNCTION BOX AND FINAL CONNECTION TO ELECTRIFIED DOOR HARDWARE BY DIVISION 26.
- HEAT — JUNCTION BOX AND FINAL CONNECTION TO HEAT TRACE EQUIPMENT BY DIVISION 26.
- WC — JUNCTION BOX AND FINAL CONNECTION TO POWERED PLUMBING EQUIPMENT BY DIVISION 26.
- SF — JUNCTION BOX AND FINAL CONNECTION TO SYSTEM FURNITURE BY DIVISION 26.

- CONTACTOR
- NON-FUSED DISCONNECT SWITCH
- NON-FUSED DOUBLE THROW DISCONNECT
- FUSED DISCONNECT SWITCH
- DISCONNECT/CB WITH SHUNT TRIP
- CB — ENCLOSED CIRCUIT BREAKER
- MOTOR STARTER 'VFD' INDICATES VARIABLE FREQUENCY DRIVE MOTOR STARTER
- MOTOR STARTER WITH INTEGRAL DISCONNECT
- MOTOR
- TC — TIME CLOCK

- ELECTRICAL PANELBOARD
- ELECTRICAL METER
- TVSS — TVSS OR SPD
- GANN — GENERATOR REMOTE ANNUNCIATOR

- LOW VOLTAGE CABLING PATHWAY, REF. SPECIFICATIONS

## KITCHEN SYMBOL LEGEND

- LOAD CENTER, BY FOOD SERVICE PROVIDE UNDERGROUND CONDUIT STUBBED UP AT LOAD CENTER LOCATION PER SUBMITTAL SHOP DRAWINGS.
- P — POINT OF SALE EQUIPMENT, BY FOOD SERVICE. PROVIDE UNDERGROUND CONDUIT STUBBED UP POS LOCATION PER SUBMITTAL SHOP DRAWINGS.
- F — REMOTE FIRE PULL, REFERENCE INSTALLATION DETAIL
- B — BELL/BUZZER WITH 120V TO LOW VOLTAGE TRANSFORMER
- D — DROP CORD
- DB — DOORBELL BUTTON
- V — CEILING STROBE FOR ENTRAPMENT ALARM
- V CLR/FRZR — WALL STROBE FOR ENTRAPMENT ALARM

## COORDINATION SYMBOL LEGEND

- DDC — HVAC CONTROL PANEL. REQUIRES POWER AND DATA CONNECTIONS WITHIN CABINET COOR EXACT LOCATION AND REQUIREMENTS WITH CONTROLS CONTRACTOR PRIOR TO ROUGH-IN.
- SD — SMOKE DAMPER
- FSD — FIRE/SMOKE COMBINATION DAMPER
- M / MD — MOTORIZED DAMPER

## SITE PLAN

- UTILITY POLE
- POLE MOUNTED TRANSFORMER BANK
- SITE POLE LIGHT
- UGE — FLUSH IN GRADE ELECTRICAL PULL BOX
- LV UG — FLUSH IN GRADE, LOW VOLTAGE HAND HOLE
- CONCRETE BOLLARD
- (X)PP — POWER POLE
- (X)SP — SERVICE POLE OR RACK
- (X)XP — XFMR POLE
- (X)LVP — LOW VOLTAGE POLE
- (X)TP — TRANSITION POLE
- OHP — OVERHEAD POWER WIRING
- 480V — 480V OVERHEAD POWER WIRING
- UGP — UNDERGROUND PRIMARY ELECTRICAL
- UGS — UNDERGROUND SECONDARY ELECTRICAL
- UGE — UNDERGROUND EMERGENCY ELECTRICAL

## DIVISION 28 LEGENDS

### FIRE ALARM

- F — FIRE ALARM PULL STATION W/ STOPPER II
- F / S — WALL FIRE ALARM AUDIO/VISUAL DEVICE
- WP-S — OUTDOOR WEATHERPROOF FIRE AUDIO/VISUAL DEVICE
- H — WALL FIRE ALARM AUDIO DEVICE
- V — WALL FIRE ALARM VISUAL DEVICE
- H/S — CEILING FIRE ALARM AUDIO/VISUAL DEVICE
- S — CEILING FIRE ALARM AUDIO DEVICE
- V — CEILING FIRE ALARM VISUAL DEVICE
- DUCT SMOKE DETECTOR
- I / S — CEILING SMOKE DETECTOR
- H — CEILING HEAT DETECTOR
- CO — CEILING CARBON MONOXIDE DETECTOR
- S/CO — CEILING COMBINATION SMOKE/CARBON MONOXIDE DETECTOR
- FR — FIRE ALARM RELAY FOR STAGE SOUND RACK OVERRIDE
- BEAM SMOKE DETECTOR
- FANN — FIRE ALARM REMOTE ANNUNCIATOR OR LOCAL OPERATOR'S CONSOLE
- FACP — FIRE ALARM CONTROL PANEL
- FAPS — FIRE ALARM POWER SUPPLY/AMPLIFIER

- G — INDICATES DEVICE WITH PROTECTIVE GUARD
- WG — INDICATES DEVICE WITH WIRE GUARD
- HC — INDICATES DEVICE RATED FOR HAZARDOUS CONDITIONS
- SD — SMOKE DAMPER
- FSD — FIRE/SMOKE COMBINATION DAMPER

## MULTI-SERVICE FLOOR BOX NOTES

FLOOR POWER AND LOW VOLTAGE
PROVIDE HEAVY-DUTY MULTI-GANG FLUSH IN GRADE OR FIRE RATED POKE-THRU OUTLET WITH HEAVY DUTY METAL HINGED COVER WITH CABLE EXIT SLOT.
FLOOR BOX MUST BE RATED FOR INSTALLATION IN GRADE.

FOR EACH FLOOR BOX PROVIDE:
1. PROVIDE:
   - 1.A. ONE QUAD OR TWO DUPLEX RECEPTACLES.
   - 1.B. PROVIDE IG RECEPTACLES WHERE SHOWN.
   - 1.C. POWER CONNECTION TO TABLE (WHERE SHOWN)
2. BLANK STAINLESS STEEL COVER FOR UN-USED GANGS.
3. PROVIDE ONE 3/4"C UNDERGROUND CONDUIT FOR POWER.
4. PROVIDE ONE 1"C UNDERGROUND CONDUIT WITH WATERPROOF INNER DUCT FOR DATA.
5. PROVIDE ONE 1"C UNDERGROUND CONDUIT WITH WATERPROOF INNER DUCT FOR LOW VOLTAGE CABLING
6. PROVIDE DIVIDERS TO MAINTAIN SEPARATION BETWEEN SERVICES.

UNDERGROUND CONDUITS MUST BE WATER TIGHT TO PREVENT MOISTURE ENTERING CONDUITS.
DO NOT COMBINE CONDUIT FOR POWER & LOW VOLTAGE.

REFERENCE FLOOR PLANS AND SPECIFICATIONS FOR QUANTITY OF DATA DROPS AND ADDITIONAL INFORMATION.

COORDINATE WITH ARCHITECT TO PROVIDE COVER/RING TO MATCH FLOOR MATERIAL AND SUBMIT COVER FINISH FOR ARCHITECT TO SELECT PRIOR TO ORDERING.

## GENERAL NOTES / TAGS

| | |
|---|---|
| +18" | INDICATES DEVICES AT +18" AFF |
| +42" | INDICATES DEVICES AT +42" AFF |
| +96" | INDICATES DEVICES AT +96" AFF |
| +12 FT | INDICATES DEVICES AT +12 FT AFF, ETC. |
| * | INDICATES DEVICES ABOVE COUNTER, REF ARCH |
| CLG | INDICATES DEVICES AT CEILING |
| PMR | INDICATES PEDESTAL MOUNTED DEVICE, REF PMR DETAIL |
| TV | INDICATES DEVICES AT TELEVISION/DISPLAY LOCATION |
| M | INDICATES DEVICES AT INTERACTIVE MEDIA LOCATION |
| PROJ | INDICATES DEVICES AT PROJECTOR LOCATION |
| S | INDICATES SURFACE MOUNTED DEVICE |
| IEC | INDICATES IEC POWER OUTLET |
| NEMA | INDICATES NEMA NUMBERED POWER OUTLET |
| GFI | INDICATES GROUND FAULT INTERRUPT (GFI) PROTECTION |
| WP | INDICATES WEATHERPROOF DEVICES |
| WPGFI | INDICATES GFI PROTECTED WEATHERPROOF DEVICE |
| G | INDICATES DEVICE WITH PROTECTIVE GUARD |
| WG | INDICATES DEVICE WITH WIRE GUARD |
| 3R | INDICATES NEMA 3R RATED DEVICE |
| 4XSS | INDICATES NEMA 4XSS RATED DEVICE |
| EM | INDICATES DEVICE ON EM/STANDBY POWER |
| VFD | INDICATES VARIABLE FREQUENCY DRIVE (VFD) |
| E | EXISTING DEVICES TO REMAIN |
| D | EXISTING DEVICES TO BE DEMO/REMOVED |
| R | EXISTING DEVICES TO BE RELOCATED |
| REP | EXISTING DEVICES TO BE REPLACED |
| | (X) = (E) FOR EXISTING |
| | (X) = (D) FOR DEMO |
| | (X) = (R) FOR RELOCATION |
| | (X) = (N) FOR NEW |

- HOMERUN TO CIRCUIT NOTED

1. RECEPTACLES AND DATA OUTLETS SHALL BE MOUNTED AT +18" AFF UNLESS NOTED ON THE DRAWINGS.
2. REF. SPECIFICATIONS FOR MOUNTING HEIGHT OF OTHER DEVICES.
3. ELECTRICAL RECEPTACLES, TELEPHONES, ETC... ARE SHOWN FOR GENERAL LOCATION. HEIGHTS ARE NOTED SO THE ESTIMATOR WILL KNOW WHETHER THEY ARE ABOVE OR BELOW COUNTERS. PRIOR TO INSTALLATION, REVIEW THE ARCHITECTURAL DRAWINGS AND SPECIFICATIONS. IN THE EVENT OF CONFLICT, THE ARCHITECT'S LOCATION WILL GENERALLY PREVAIL BUT SHOULD BE CLARIFIED BY RFI. PROVIDE DEVICES SHOWN ON THE ELECTRICAL DRAWING EVEN IF NOT SHOWN ON ARCHITECTURAL DRAWINGS.
4. COORDINATE POWER AND DATA WITH THE FURNITURE SUPPLIER PRIOR TO ROUGH-IN. AT CASEWORK WITH KNEE SPACE, MOUNT RECEPTACLES AND DATA OUTLETS IN KNEE SPACE. COORDINATE WITH ARCHITECT AND FURNITURE SUPPLIER TO ENSURE THAT PROTECTIVE GROMMETS ARE PROVIDED IN THE COUNTER.
4. ALL DEVICES SHOWN AT THE SAME LOCATION AND ELEVATION SHALL BE GROUPED TOGETHER AND SPACED 2 INCHES BETWEEN BOXES.
5. PROVIDE SS COVER PLATE FOR ALL EMPTY JBOX.
6. ALL NON-LOCKING 125V AND 250V, 15A AND 20A RECEPTACLES SHALL BE TAMPER RESISTANT TYPE.


ISSUE:
12/05/2024 DD PACKAGE
03/11/2025 50% CD PKG.
05/23/2025 90% CD PKG.
07/18/2025 ISSUED FOR BIDDING AND PERMITTING


a

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL

STATE OF TEXAS — GEORGE L. STANTON — 38582 — REGISTERED PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL AND FIRE ALARM SCHEDULES
a-E.000


STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM (713) 305-6266


TEXAS ENG. FIRM REG. NO. F-13932 © 2025 ALL RIGHTS RESERVED


12999 W. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77040

PROVIDE CONDUIT & SLEEVES THRU FIRE WALLS, WALLS AND FLOORS FOR LOW VOLTAGE CABLING WIRING, ETC.

ALL CONDUIT & J-BOXES FOR LOW VOLTAGE CABLING SHALL BE PROVIDED AND INSTALLED BY THE ELECTRICAL CONTRACTOR. ALL LOW VOLTAGE CABLING IN WALLS, EXPOSED AREAS AND ABOVE INACCESSIBLE CEILINGS SHALL REQUIRE CONDUIT AND J-BOXES. REFERENCE SPECIFICATIONS AND TECHNOLOGY DOCUMENTS FOR ADDITIONAL INFORMATION/REQUIREMENTS.

PULL BOXES AND BELOW GRADE CONDUIT FOR LOW VOLTAGE CABLING, WIRING, ETC. BY ELEC CONTRACTOR.

## FIRE ALARM SYSTEM DESCRIPTION AND SEQUENCE OF OPERATION

1. FIRE ALARM SYSTEM SHALL BE DESIGNED TO MEET NFPA REQUIREMENTS AS WELL AS CITY AND NATIONAL BUILDING CODES. PROVIDE COMPLETE FIRE ALARM SYSTEM, DEVICES AND WIRING.
2. INSTALL FIRE ALARM CONTROL PANEL IN RECEPTION AREA. INSTALL REMOTE POWER SUPPLY PANELS IN MECHANICAL/ELECTRICAL ROOMS.
3. FIRE ALARM PANEL, POWER SUPPLIES, DEVICES, ETC. SHALL BE MANUFACTURED BY THE SAME MANUFACTURER AS THE FIRE ALARM CONTROL PANEL.
4. FIRE ALARM REMOTE POWER SUPPLIES AND PANELS SHALL BE LOCATED IN MECHANICAL OR ELECTRICAL ROOMS ONLY. DO NOT LOCATE IN STORAGE ROOMS, DATA CLOSETS OR FINISHED SPACES.
4. PROVIDE AUDIBLE, INTELLIGIBLE AND VISUAL ALARM COVERAGE OF THE AREA OF RENOVATION AS REQUIRED BY CODE.
5. PROVIDE SMOKE DETECTORS AT EACH FIRE ALARM PANEL, REMOTE TRANSPONDER PANEL, BOOSTER PANEL AND REMOTE ANNUNCIATOR PER NFPA 72.
6. IN ADDITION TO THE SPECIFIED FIRE ALARM EQUIPMENT, THE FIRE ALARM CONTRACTOR SHALL PROVIDE
   6.A. SURGE PROTECTORS FOR ALL NEW 120V POWER CONNECTIONS TO FIRE ALARM EQUIPMENT.
   6.B. SURGE PROTECTORS FOR ALL SIGNALING LINE CIRCUITS (SLC), NOTIFICATION CIRCUITS AND INITIATING CIRCUITS CONNECTED TO THE FIRE ALARM CONTROL PANEL WHICH LEAVE THE BUILDING.
7. SHOULD ANY DETECTOR, MONITOR OR PULL STATION ACTIVATE, ALL SPEAKERS SHALL SOUND AND STROBES FLASH. AIR HANDLING EQUIPMENT SHALL BE DEACTIVATED. AN ALARM SIGNAL SHALL BE SENT TO A REMOTE LOCATION VIA AUTOMATIC DIALER. ALSO, DE-ENERGIZE SUPPLY FANS, EXHAUST FANS AND OTHER AIR CIRCULATING DEVICES IF 2000 CFM OR OVER, SERVING THE AREA IN ALARM.
8. ALL LOW VOLTAGE WIRING SHALL BE FPLP RATED WIRE, WITH MINIMUM WIRE SIZE PER SPECIFICATIONS.
   8.A. PLENUM RATED CABLE ABOVE ACCESSIBLE CEILING SHALL BE SUPPORTED BY J-HOOKS, SPACED AT FOUR (4) FEET ON CENTER.
   8.B. INSTALL FIRE ALARM CABLES IN CONDUIT FOR AREAS WITHOUT CEILING OR ABOVE INACCESSIBLE CEILINGS.
   8.C. EXPOSED CONDUIT IN FINISHED SPACES SHALL BE ALLOWED WHERE NO OTHER OPTION EXISTS AND ONLY WITH PRIOR WRITTEN APPROVAL BY THE OWNER. ALL EXPOSED CONDUIT SHALL BE PAINTED TO MATCH.
   8.D. ALL CABLING THROUGH WALLS, FIRE WALLS AND FLOORS SHALL BE INSTALLED IN SLEEVES WITH PROTECTIVE BUSHINGS ON BOTH ENDS.
9. FIRE ALARM SYSTEM SHALL BE MONITORED BY A UL LISTED CENTRAL RECEIVING STATION.
10. INTERLOCK LIGHTING CONTROL PANELS WITH FIRE ALARM SYSTEM TO ENABLE ALL LIGHTING UPON ACTIVATION.
11. REFER TO THE WRITTEN SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.

## FIRE ALARM SYSTEM NOTES

1. GENERAL CONTRACTOR SHALL COORDINATE WITH ELECTRICAL AND FIRE ALARM SUBCONTRACTOR FOR LOCATIONS OF REMOTE POWER SUPPLIES. FIRE ALARM POWER SUPPLIES ARE NOT SHOWN ON THIS DRAWING AND SHALL BE LOCATED BY FIRE ALARM SUBCONTRACTOR IN ORDER TO ACCOMMODATE HIS FIRE ALARM SYSTEM BATTERY AND VOLTAGE DROP CALCULATIONS PER MANUFACTURER'S RECOMMENDATION & NFPA REQUIREMENTS. ELECTRICAL CONTRACTOR SHALL INCLUDE ADDITIONAL DEDICATED 120V CIRCUITS IN BASE BID TO SERVE FIRE ALARM POWER SUPPLIES IN DIFFERENT AREAS. PROVIDE 2–12 +12G, 3/4"C AND SPARE 20A/1P CB(S) IN LOCAL LIFE SAFETY EMERGENCY 120V PANELS TO SERVE FIRE ALARM REMOTE POWER SUPPLIES.
2. FIRE ALARM CONTRACTOR IS RESPONSIBLE FOR DESIGN AND FOR FINAL CORRECT LOCATION OF DEVICES TO RELIEVE NUISANCE ALARMS, SUCH AS INSTALLING A HEAT DETECTOR IN FRONT OF AN OVEN WHICH WILL RELEASE STEAM, THUS POTENTIALLY SETTING OFF THE ALARM. ALSO, THE CONTRACTOR IS RESPONSIBLE FOR DETECTORS REQUIRED BY CODE EVEN IF NOT SHOWN ON DRAWING, LIKE A CLOSET. IF THERE IS UNCERTAINTY, BRING UP DURING THE BID PROCESS AND THEY WILL BE ADDRESSED DURING THE BIDDING PROCESS.
3. FIELD VERIFY ENVIRONMENTAL ISSUES THAT CAN ADVERSELY AFFECT OPERATION OF SMOKE DETECTORS. DO NOT LOCATE NEAR AIR FLOW DEVICES LEADING TO PREMATURE BUILD UP OF DUST CAUSING NUISANCE TROUBLE SIGNALS. DEVICE RELOCATION OR TYPE CHANGE WILL BE COVERED UNDER WARRANTY.

## FIRE ALARM SCOPE OF WORK

1. THERE IS AN EXISTING FIRE ALARM SYSTEM IN EACH BUILDING.
   1.A. TEST THE EXISTING SYSTEM PRIOR TO BEGINNING DEMO. NOTE ANY FAULTS OR TROUBLES AND PROVIDE A WRITTEN REPORT TO THE OWNER.
   1.B. EXPAND THE EXISTING SYSTEM AS REQUIRED TO INTEGRATE THE NEW DEVICES IN THE AREA OF RENOVATION.
2. PROVIDE WIRING AND DEVICES AS INDICATED TO PROVIDE COMPLETE AUDIBLE, INTELLIGIBLE AND VISUAL ALARM COVERAGE OF RENOVATED AREAS AS REQUIRED BY CODE.
   2.A. PROVIDE SMOKE DETECTOR COVERAGE OF ALL STORAGE ROOMS AND ADDTIONALLY AS SHOWN ON THE DRAWINGS.
   2.B. PROVIDE HEAT DETECTOR COVERAGE OF THE KITCHEN, CUSTODIAL ROOMS, AND ADDITIONALLY AS SHOWN ON THE DRAWINGS.
   2.C. PROVIDE DUCT MOUNTED DETECTORS AT EACH NEW AIR HANDLING UNIT SUPPLY AND RETURN CONNECTION EXCEEDING 2000 CFM. IF FREE AIR RETURN, PROVIDE FREE AIR DETECTING COVERAGE OF THE RETURN AIR OPENINGS TO THE MECHANICAL ROOM. ENSURE AIR FLOW CANNOT PREVENT OPERATION OF THE DETECTORS AND PROVIDE ADEQUATE CLEARANCE PER NFPA 72.
   2.D. CONTROL RELAYS SHALL BE LOCATED WITHIN 3 FT OF THE CONTROLLED CIRCUIT OR APPLIANCE.
3. PROVIDE SMOKE DETECTORS AT EACH NEW FIRE ALARM PANEL, REMOTE TRANSPONDER PANEL, BOOSTER PANEL AND REMOTE ANNUNCIATOR PER NFPA 72.
4. PROVIDE LED REMOTE ALARM WITH ENGRAVED STAINLESS STEEL PLATE WHERE DUCT DETECTORS ARE NOT LOCATED IN MECHANICAL ROOM, LOCATED ABOVE CEILINGS OR WHERE MOUNTED TOO HIGH OR VIEW IS BLOCKED BY DUCTWORK IN MECHANICAL ROOM.
   4.A. REMOTE LED LIGHT INDICATOR FOR DUCT SMOKE DETECTORS SHALL BE MOUNTED FLUSH IN CEILING OR MOUNTED IN WALL AT +7FT.
   4.B. STAINLESS STEEL PLATE SHALL BE ENGRAVED WITH THE DUCT SMOKE DETECTOR AS–BUILT IDENTIFICATION NUMBER.
5. REFER TO THE WRITTEN SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.

## SPARES

1. THE FIRE ALARM CONTRACTOR SHALL INCLUDE IN HIS BID THE COST TO PROVIDE AND INSTALL THE ADDITIONAL SPARE PARTS AND ASSOCIATED CABLING PER THE SPECIFICATIONS. SPARES SHALL BE INSTALLED AS INSTRUCTED BY THE OWNER. UNINSTALLED DEVICES SHALL BE DELIVERED TO THE OWNER AS ATTIC STOCK.

## GENERAL RENOVATION AND REMODELING NOTES

1. READ ALL MEP AND ARCH. DRAWINGS TO IDENTIFY AREAS OF RENOVATION AND SCOPE OF WORK.
2. ALL RENOVATION AND DEMOLITION WORK SHALL NOT AFFECT AREAS NOT INCLUDED IN THE AREAS OF WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE CONTINUITY OF ALL SERVICES (POWER, TELEPHONE, FIRE ALARM, DATA, SECURITY, ETC.) IN NON–DEMOLITION/RENOVATION AREAS. ALL SERVICES SHALL BE MAINTAINED AT ALL TIMES.
3. ALL OUTAGES AFFECTING NON–DEMOLITION/RENOVATION AREAS SHALL BE SCHEDULED WITH THE OWNER WITH A MINIMUM 2 WEEKS ADVANCE NOTICE. OUTAGES SHALL BE COORDINATED WITH OTHER TRADES TO MINIMIZE THE QUANTITY AND IMPACT ON BUILDING OPERATION.
4. THIS ELECTRICAL DRAWING ONLY SHOWS SOME EXISTING ELECTRICAL PANELS, DEVICES AND LIGHT FIXTURES IN AREAS OF RENOVATION. ALL OTHER ELECTRICAL EQUIPMENT, WIRING DEVICES, LOW VOLTAGE SYSTEMS, J–BOXES AND CONDUITS SHALL BE LOCATED AND FIELD VERIFIED BY CONTRACTOR.
5. CONTRACTOR SHALL FIELD VERIFY AND MARK UP THE FOLLOWINGS IN AREAS OF RENOVATION:
   5.A. EXISTING DATA, AUDIO, VIDEO, SPEAKERS AND OTHER LOW VOLTAGE OUTLETS AND DEVICES.
   5.B. EXISTING CEILING MOUNTED PROJECTORS.
   5.C. EXISTING SECURITY, CCTV, ACCESS CONTROL DEVICES.
   5.D. EXISTING FIRE ALARM DEVICES.
   5.E. EXISTING WIRELESS ACCESS POINTS AND GRID LABELING.
   5.F. EXISTING LIGHT FIXTURES AND SWITCHES.
   5.G. EXISTING ELECTRICAL DEVICES, J–BOXES, CONDUIT, WIRING, WIRING SUPPORTS, ETC.
   5.H. EXISTING ELECTRICAL SWITCHGEAR.
   5.I. EXISTING CONTROL PANELS AND CONTROL CIRCUITS.
   5.J. EXISTING HANGER WIRE FROM CONC. CEILING.
6. ALL REMOVED DEVICES SHALL BE OFFERED TO THE OWNER AS SALVAGE.
7. ALL EXISTING DEVICES SHALL BE REINSTALLED IN NEW CEILINGS AT SAME LOCATION EXCEPT WHERE SHOWN TO BE NEW.
8. CONDUIT/WIRE NOT TO BE REUSED SHALL BE REMOVED ALL THE WAY BACK TO THE UPSTREAM EQUIPMENT.
   8.A. PROVIDE ADDITIONAL SUPPORTS FOR EXISTING CONDUIT/WIRE TO REMAIN TO MEET CURRENT CODE REQUIREMENTS.
9. ANY MATERIAL THAT HAS SALVAGE VALUE SHALL BE OFFERED TO THE OWNER, AND IF ACCEPTED, DELIVERED TO HIS WAREHOUSE. IF NOT ACCEPTED IT SHALL BE PROPERLY DISPOSED OF WITH THE OTHER CONSTRUCTION DEBRIS.
10. RELOCATE CONDUIT AS NECESSARY TO ALLOW NEW OR MODIFIED CONSTRUCTION. REPAIR EXISTING ELECTRICAL SYSTEMS DAMAGED BY CONSTRUCTION ACTIVITES.
11. WHERE PARTIAL CIRCUITS OR SYSTEMS ARE TO BE REUSED, ENSURE THAT THEY REMAIN ACTIVE. WHERE EXISTING EQUIPMENT IS RELOCATED OR REPLACED WITH NEW, MODIFY, EXTEND AND RELOCATE EXISTING CIRCUIT TO CONNECT TO EQUIPMENT, UNLESS SHOWN TO HAVE NEW CIRCUIT.
12. WHERE AUXILIARY SYSTEMS SUCH AS SECURITY, DATA, SOUND, ETC. INTERFACE WITH EXISTING EQUIPMENT THAT IS REPLACED OR MODIFIED (MECHANICAL, ELECTRICAL OR PLUMBING), DISCONNECT AND RECONNECT THESE SYSTEMS.
13. WHERE NEW CIRCUIT BREAKERS ARE TO BE INSTALLED IN EXISTING PANELS OR SWITCHBOARD, VERIFY THAT THE CIRCUIT BREAKER WILL FIT IN THE ALLOTTED SPACE. PROVIDE NEMA 1 ENCLOSURE ADJACENT TO PANEL & WIRE CONNECT TO BUSSING IF THERE IS INSUFFICIENT SPACE.
14. WHERE PARTIAL CIRCUITS OR SYSTEMS ARE TO BE REUSED, ENSURE THAT THEY REMAIN ACTIVE. WHERE EXISTING EQUIPMENT IS RELOCATED OR REPLACED WITH NEW, MODIFY, EXTEND AND RELOCATE EXISTING CIRCUIT TO CONNECT TO EQUIPMENT, UNLESS SHOWN TO HAVE NEW CIRCUIT.
15. WHEN REPLACING LIGHTS AND CEILINGS, ENSURE THAT EXISTING DATA, TELEVISION AND PA CABLES TO REMAIN CONTINUE TO MEET THE CURRENT STANDARDS. FOR DATA CABLES, THIS IS THE IEEE 802.1. FOR TELEVISION AND PA CABLE, A FOUR INCH DISTANCE IS NEEDED FROM ALL LIGHT FIXTURES. NEW DROP LOCATION SHOULD BE WITHIN THREE FEET OF POWER OUTLET.
16. PAINT NEW AND EXISTING EXPOSED RACEWAY IN AREAS OF RENOVATION TO MATCH FINISHES.
17. ANY DAMAGE TO EXISTING BUILDING, ELECTRICAL EQUIPMENT, WIRING DEVICES, CONDUIT, WIRING, ETC. SHALL BE REPLACED BY THE CONTRACTOR AT NO COST TO THE OWNER. ALL MATERIALS USED FOR THE REPLACEMENT MUST MEET RENOVATION PROJECT STANDARDS.
18. INTERESTED CONTRACTORS MUST VISIT THE SITE PRIOR TO BIDDING TO BECOME FAMILIAR WITH THE PROJECT REQUIREMENTS AND EXISTING CONDITIONS AND SHALL INCLUDE IN THEIR PROPOSALS COSTS TO REPAIR, RELOCATE, MODIFY AND REMOVE EXISTING ELEMENTS AS REQUIRED TO COMPLETE INSTALLATION OF ALL SYSTEMS SHOWN ON THESE DRAWINGS.
19. SEE DRAWINGS FOR ADDITIONAL REQUIREMENTS.

## ELEC REQUIREMENTS FOR BUILDING RENOVATION

1. ELECTRICAL CONTRACTOR SHALL BEGIN FIELD VERIFYING ALL EXISTING BRANCH CIRCUITS FOR EXISTING AREAS TO BE RENOVATED IMMEDIATELY AFTER THE CONTRACT IS ISSUED.
2. ELECTRICAL CONTRACTOR SHALL FIELD VERIFY EXISTING CIRCUITS WITH OWNER'S MAINTENANCE PERSONNEL AFTER NORMAL BUILDING HOURS AS REQUIRED.
3. ELECTRICAL CONTRACTOR SHALL INCLUDE COST RELATED TO FIELD VERIFY EXISTING CIRCUITS IN BASE PROPOSAL.
4. FIND AND RECORD ALL EXISTING DEVICES IN CEILINGS, WALLS AND CASEWORK IN AREAS TO BE RENOVATED. PROVIDE A COPY OF THE FIELD VERIFIED DEVICE DRAWINGS TO OWNER PRIOR TO BEGINNING WORK.
5. ALL EXISTING DEVICES TO REMAIN SHALL BE REINSTALLED IN NEW CEILINGS AND WALLS EXCEPT WHERE INDICATED TO BE REMOVED/RELOCATED/REPLACED.
6. EXISTING DEVICES IN WALLS TO BE FURRED OUT OR RECEIVE NEW SURFACE TREATMENT SHALL REMAIN. EXTEND J-BOX TO NEW WALL SURFACE AND RECONNECT TO EXISTING CIRCUITS. EXTEND WIRING/CABLING FROM NEAREST ACCESSIBLE POINT AS NECESSARY.
7. REINSTALL ALL DEVICES NOT SHOWN TO BE REMOVED.
8. EXISTING LIGHT FIXTURES SHALL REMAIN EXCEPT WHERE SHOWN AS NEW. EXTEND EXIST CONDUIT AND WIRE DOWN TO NEW LIGHT FIXTURES, REFERENCE SPECIFICATIONS FOR ADDITIONAL INFORMATION.
9. ALL EXISTING EXIT SIGNS SHALL BE REINSTALLED AND RECONNECTED TO EXISTING CIRCUITS EXCEPT IN CORRIDORS AND AREAS OF RENOVATION SHOWING NEW.
10. ALL NEW DEVICES IN EXISTING WALLS IN FINISHED SPACES SHALL BE INSTALLED FLUSH MOUNTED, NO EXPOSED CONDUIT OR WIREMOLD ALLOWED. CUT EXISTING WALLS AND PATCH/REPAIR TO MATCH EXISTING AS REQUIRED.
    10.1. DEVICES/CONDUIT IN CUSTODIAL, MECHANICAL AND ELECTRICAL ROOMS MAY BE EXPOSED AND SURFACE MOUNTED.
11. PROVIDE NEW DIRECTORY FOR ALL EXISTING AND NEW PANELS SHOWING FIELD VERIFIED CIRCUITS.
12. ANY FEEDER AND BRANCH CIRCUIT NOT TO BE REUSED SHALL BE REMOVED COMPLETELY UP TO CB IN EXISTING PANEL.
13. ANY CIRCUIT OR PARTIAL CIRCUIT TO BE REUSED SHALL REMAIN ACTIVE.

## GENERAL EQUIPMENT ELECTRICAL NOTE

THE ELECTRICAL DESIGN HAS BEEN COORDINATED FOR SPACE, INSTALLATION AND ELECTRICAL REQUIREMENTS WITH EQUIPMENT THAT IS SCHEDULED BY OTHER DIVISIONS. THE REQUIREMENTS FOR OTHER EQUIPMENT AND MODELS FROM ACCEPTABLE MANUFACTURERS HAVE NOT BEEN VERIFIED OR COORDINATED. THE GENERAL CONTRACTOR SHALL VERIFY THESE REQUIREMENTS PRIOR TO USING OTHER EQUIPMENT IN HIS BID AND INCLUDE ANY ADDITIONAL COSTS FOR INSTALLATION OF THE EQUIPMENT. THIS INCLUDES GENERAL CONSTRUCTION AND MEP COSTS.

ELECTRICAL CONTRACTOR SHALL COORDINATE WITH OWNER/OTHER TRADES FOR EXACT ELECTRICAL REQUIREMENTS OF EQUIPMENT PRIOR TO ORDERING CB(S). FIELD VERIFY EQUIPMENT NAMEPLATE RATINGS AND EQUIPMENT CONNECTION LOCATIONS WITH OTHER TRADES PRIOR TO ROUGH–IN.

TYPICAL OF HVAC EQUIPMENT, SHOP EQUIPMENT, KITCHEN EQUIPMENT, ELECTRIC ROLLUP DOORS, ETC.

## GENERAL ELECTRICAL NOTES

1. REFER TO THE WRITTEN SPECIFICATIONS FOR ADDITIONAL INFORMATION.
2. INSTALL SYSTEMS IN ACCORDANCE WITH THE NATIONAL ELECTRIC CODE.
3. PROVIDE LIGHT FIXTURE FIRE PROTECTION AND CONDUIT FIRE SEALING TO MAINTAIN FIRE RATING OF WALLS AND CEILINGS PER ARCHITECT'S SCHEDULE. REF. SPECIFICATIONS AND ARCH. DRAWINGS FOR ADDITIONAL INFORMATION.
4. ELECTRICAL RECEPTACLES, TELEPHONES, ETC... ARE SHOWN FOR GENERAL LOCATION. HEIGHTS ARE NOTED SO THE ESTIMATOR WILL KNOW WHETHER THEY ARE ABOVE OR BELOW COUNTERS. PRIOR TO INSTALLATION, REVIEW THE ARCHITECTURAL DRAWINGS AND SPECIFICATIONS. IN THE EVENT OF CONFLICT, THE ARCHITECT'S LOCATION WILL GENERALLY PREVAIL BUT SHOULD BE CLARIFIED BY RFI. PROVIDE DEVICES SHOWN ON THE ELECTRICAL DRAWING EVEN IF NOT SHOWN ON ARCHITECTURAL DRAWINGS.
5. COORDINATE POWER AND DATA WITH THE FURNITURE SUPPLIER PRIOR TO ROUGH–IN. AT CASEWORK WITH WIRE SPACE, MOUNT RECEPTACLES AND DATA OUTLETS IN KNEE SPACE. COORDINATE WITH ARCHITECT AND FURNITURE SUPPLIER TO ENSURE THAT PROTECTIVE GROMMETS ARE PROVIDED IN THE COUNTER.
6. DO NOT INSTALL ELECTRICAL PANELS AND TRANSFORMERS UNTIL 1/4" SCALE DRAWINGS SHOWING LOCATION OF THIS EQUIPMENT RELATIVE TO MECHANICAL/PLUMBING EQUIPMENT, DUCTWORK AND PIPING IS SUBMITTED AND APPROVED. NEC CODE CLEARANCE MUST BE MAINTAINED.
7. ELECTRICAL EQUIPMENT HAS BEEN COORDINATED WITH PIPING AND DUCTWORK. DO NOT RELOCATE PANELS WITHOUT PRIOR APPROVAL.
8. ELECTRICAL DEVICES IN FIRE RATED WALLS SHALL BE A MINIMUM OF 24" AWAY FROM DEVICES ON THE OPPOSITE SIDE OF THE WALL TO MAINTAIN FIRE RATING.
9. MINIMUM SIZE CONDUIT FOR POWER SHALL BE 3/4", MIN. SIZE FLEX CONDUIT MAY BE 1/2". MINIMUM SIZE CONDUIT FOR DATA SHALL BE 1"C. DO NOT COMBINE CONDUIT FOR DATA.
10. MAX. LENGTH FOR FLEX CONDUIT SHALL BE 6 FT. ALL FLEX CONDUIT SHALL BE LISTED FOR GROUNDING.
11. LIGHT FIXTURE WHIPS MAY BE MIN. 1/2" FLEX CONDUIT WITH MIN. #12 WIRE. LIGHT FIXTURE WHIPS SHALL BE NO MORE THAN 6 FT LONG.
12. PROVIDE GREEN GROUND WIRE WITH ALL CIRCUITS SIZED PER NEC. BOND GREEN GROUND WIRE TO EACH END OF CONDUIT.
13. GROUND TRANSFORMER SECONDARIES TO BUILDING STEEL AND GROUND ROD. PROVIDE CONDUIT TO PROTECT GROUNDING CONDUCTOR AND BOND EACH END OF CONDUIT TO GROUNDING SYSTEM. MIN. SIZE OF CONDUIT FOR GROUND WIRE SHALL BE 3/4"C.
14. PROVIDE J–BOXES, CONDUIT AND SLEEVES THRU ALL FIRE WALLS FOR DATA, TELEPHONE, SECURITY, FIRE ALARM AND SOUND SYSTEMS WIRINGS, ETC. SEE SPECIFICATIONS.
15. PROVIDE PULL BOXES, JUNCTION BOXES, WIRING TROUGHS AND CABINETS WHEREVER REQUIRED FOR PROPER INSTALLATION OF VARIOUS ELECTRICAL SYSTEMS.
16. WHERE PORTIONS OF INTERIOR RACEWAY SYSTEM ARE EXPOSED TO WIDELY DIFFERENT TEMPERATURES, PROVIDE AIR SEALING PER NEC TO PREVENT CIRCULATION OF AIR FROM WARMER TO A COOLER SECTION.
17. ALL WIRING SHALL BE 600 VOLT, SOFT DRAWN ANNEALED COPPER, 98% CONDUCTIVITY, CONTINUOUS FROM OUTLET TO OUTLET. MINIMUM WIRE SIZE #12. ALL WIRE SHALL BE STRANDED TYPE THHN OR THWN–2 (WET RATED FOR 90° C). ALL WIRES SHALL BE COLOR CODED WITH SAME COLOR CONNECTED TO SAME UNGROUNDED PHASE THROUGHOUT THE INSTALLATION.
18. ALL ELECTRICAL WIRING SHALL BE INSTALLED IN CONDUIT. NO SURFACE MOUNTED WIREMOLD SHALL BE ALLOWED IN FINISHED SPACES. MC CABLE SHALL BE ALLOWED INSIDE EXIST STUD WALLS OR CHASE WALLS.
19. PROVIDE AND INSTALL FINAL CONNECTIONS TO ALL EQUIPMENT PROVIDED BY OTHER TRADES AND/OR FURNISHED BY OWNER INCLUDING ALL NECESSARY CONDUIT, CORDS, PLUGS, WHIPS, HARDWIRING, ETC. IN PARTICULAR CONFIRM CONNECTION REQUIREMENTS WITH DELIVERED EQUIPMENT PRIOR TO ROUGH–IN.
20. ALL MATERIAL MUST BE NEW AND OF GOOD QUALITY AND SHALL BEAR THE STAMP OF APPROVAL OF THE UNDERWRITERS' LABORATORIES, INC. (U.L.).

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL AND FIRE ALARM NOTES

a-E.001


STANTON ENGINEERING GROUP
INFO@STANTON–ENGR.COM (713) 305–6266


TEXAS ENG. FIRM REG. NO. F–018330 | © 2025 ALL RIGHTS RESERVED
12999 W. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77064





SYMBOL: ▽

## 1 TYPICAL DATA OUTLETS

NO SCALE

NOTES:
1. PROVIDE DEEP 4 11/16" X 4 11/16" X 2 1/8", 2-GANG BACK BOX FOR ALL DATA OUTLETS.
   1.A. PROVIDE SINGLE GANG MUDRING FOR DATA OUTLETS WITH 1-4 DROPS.
   1.B. PROVIDE PULL STRING IN ALL LOW VOLTAGE CONDUITS.
2. LOW VOLTAGE CABLING AND DEVICES BY DIVISION 27.
3. REFERENCE TECHNOLOGY DRAWINGS FOR ADDITIONAL INFORMATION.





SYMBOL: ⏀ SYMBOL: ⏁

## 2 TYPICAL POWER & DATA OUTLET DETAIL

NO SCALE

NOTES:
1. LOCATE DEVICES GROUPED TOGETHER AS CLOSELY TOGETHER AS POSSIBLE.
   1.A. USE CADDY TSGB16, RBS16 OR SIMILAR MOUNTING BAR IN SHEETROCK WALLS.




SYMBOL: ⏀ SYMBOL: ⏁ SYMBOL: ⏀USB SYMBOL: ⏀GFI

## 3 TYPICAL ELECTRICAL DEVICES

NO SCALE

NOTES:
1. ALL DEVICES SHALL BE COLOR CODED PER SPECIFICATIONS WITH 302/304 STAINLESS STEEL, STANDARD SIZE, FACEPLATES.
2. ONLY SELECT RECEPTACLES ARE SHOWN HERE. PROVIDE SIMILAR LABELS ON ALL SWITCHES, NEMA POWER OUTLETS, ETC.
3. PROVIDE LABEL WITH RED TEXT READING "EMERGENCY" FOR DEVICES ON GENERATOR FED CIRCUITS.
4. PROVIDE TYPEWRITTEN OR PREMADE CIRCUIT LABELS INDICATING THE ELECTRICAL CIRCUIT ON:
   4.A. INSTALLED WIRING AT EACH SPLICE POINT
   4.B. EACH J-BOX ABOVE CEILING WITH WIRING INSTALLED OR MODIFIED AS PART OF THIS PROJECT.
   4.C. AFFIXED TO THE FRONT OF EACH NEW AND EXISTING DEVICE FACEPLATE IN THE AREA OF RENOVATION.
      CIRCUIT LABEL
      XX-## A. XX = PANEL DESIGNATION
      B. ## = AS-BUILT CIRCUIT DESIGNATION

STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM (713) 360-4090
TEXAS ENGINEERING FIRM REGISTRATION NO. F-01833 © 2025 ALL RIGHTS RESERVED
1300 W. SAM HOUSTON PARKWAY N., SUITE 121, HOUSTON, TX 77043

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL


STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL DEVICE DETAILS


a-E.010




## 10 MECHANICAL - ELECTRICAL COORDINATION DETAIL


NO SCALE

**COORDINATE WITH OTHER TRADES TO ENSURE NO PIPING AND DUCTWORK ABOVE ELECTRICAL EQUIPMENT AS SHOWN. PROVIDE WORKING CLEARANCE IN FRONT OF STARTERS, DISCONNECTS, PANELS, XFMRS AND ADDITIONALLY PER CODE.**




## 11 CONDUIT ROOF PENETRATION DETAIL


NO SCALE




## 12 ROOF AND CANOPY CONDUIT SUPPORT DETAIL

NO SCALE

1. COORDINATE WITH ARCHITECTURAL DRAWINGS, DETAILS, SPECIFICATIONS AND OTHER TRADES.





## 13 CANOPY LIGHT MOUNTING DETAIL TYPE 1

NO SCALE

NOTES:

1. MOUNTING PLATES SHALL BE WELDED TO CANOPY TO MOUNT LIGHT FIXTURES.
2. FOR FIXTURES WITH END CONDUIT ATTACHMENTS ALL CANOPY PENETRATIONS SHALL BE MADE OFF CENTER FROM THE FIXTURE WIRING ENTRY POINT AND SHALL HAVE WEATHERTIGHT SEALING. (SHOWN HERE)
3. CANOPY PENETRATIONS ABOVE FIXTURES SHALL BE PERMITTED ONLY WHERE THE SUPPLIED FIXTURE HAS NO END CONDUIT ATTACHMENTS.
4. CONDUIT SHALL BE SEALED BOTH ABOVE AND BELOW THE CANOPY PENETRATION AND AGAIN AT THE FIXTURE ENTRY POINT TO PREVENT WATER FROM ENTERING THE LIGHTING FIXTURE.
5. CANOPY PENETRATIONS SHALL BE MADE AS CLOSE TO CONDUIT ENTRY PENETRATION POINT AS POSSIBLE AND CONDUIT SHALL BE ROUTED TO MINIMIZE EXPOSED CONDUIT.





## 7 EDF GFI PROTECTION DETAIL

NO SCALE

NOTES:

1. MODIFY EXISTING WALL AS NEEDED TO INSTALL NEW RECEPTACLE AND REMOTE GFI TEST SWITCH. PATCH/REPAIR WALL AS NEEDED TO MATCH EXISTING.
2. WIRE NEW RECEPTACLE DOWNSTREAM OF REMOTE GFI TEST SWITCH.
3. REMOTE GFI TEST SWITCH SHALL BE A DEAD FRONT GFI DEVICE TO BE INSTALLED FLUSH MOUNTED IN WALL WITH EDF SERVED AND PROVIDE GFI PROTECTION FOR THE RECEPTACLE LOCATED WITHIN THE EDF HOUSING.
4. GFI TEST SWITCH SHALL BE READILY ACCESSIBLE PER NEC 210.8.
5. COORDINATE RECEPTACLE LOCATION(S) WITHIN EDF HOUSINGS WITH MANUFACTURER'S INSTALLATION INSTRUCTIONS.





## 8 TRANSFORMER CONNECTION AND GROUNDING DETAIL

NO SCALE


NOTES:

1. INSTALL GROUND ROD ADJACENT TO TRANSFORMER AND SEAL PENETRATION AROUND GROUND ROD.
2. WHERE AN ISOLATED GROUND IS PROVIDED MAKE THE CONNECTION AT THE TRANSFORMER AND RUN DIRECTLY TO THE ISOLATED GROUND BAR IN THE PANELBOARD. DO NOT DEFINE THE ISOLATED GROUND AT THE PANELBOARD.
3. FINAL CONNECTIONS TO TRANSFORMERS SHALL BE MADE IN FLEXIBLE CONDUIT. PROVIDE LIQUID TIGHT CONSTRUCTION AND FITTINGS IN WET, DAMP OR OUTSIDE AREAS EXCEPT WHERE LOCATED IN AIR HANDLING ROOMS. REFERENCE SPECIFICATIONS FOR ADDITIONAL INFORMATION.





## 9 PIGTAIL WIRING DETAIL FOR ELECTRICAL DEVICE

NO SCALE





## 1 CONDUIT/J-BOX DETAIL FOR LIGHT FIXTURES IN LAY-IN CEILING

NO SCALE




## 2 FIXTURE SUPPORT DETAIL

NO SCALE





## 3 TRAPEZE MOUNTED CONDUIT DETAIL

NO SCALE

NOTES:

1. ALL SUPPORT DEVICES SHALL BE UL LISTED AND NEC APPROVED.
2. REFER TO NEC FOR CONDUIT SUPPORT SPACING.





## 4 WALL MOUNTED CONDUITS

NO SCALE

NOTES:

1. ALL SUPPORT DEVICES SHALL BE UL LISTED AND NEC APPROVED.
2. REFER TO NEC FOR CONDUIT SUPPORT SPACING.





## 5 FIREWALL PENETRATION DETAIL

NO SCALE

NOTES:

1. FIRE RATING OF COMPLETED FIREPROOFED ASSEMBLY SHALL BE EQUAL OR EXCEED RATING OF WALL.




## 6 GROUNDING BUSHING WIRING DETAIL

NO SCALE

NOTE:

1. PROVIDE AND INSTALL GROUNDING BUSHINGS FOR DISCONNECT SWITCHES, PANELS AND TRANSFORMERS.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING


ELECTRICAL DETAILS

a-E.011


STANTON ENGINEERING GROUP
INFORMATION-DESIGN
(713) 360-4080
TEXAS ENG. FIRM REG. NO. F-018530 (HP 2021)


ALL RIGHTS RESERVED


12999 W. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77064




## 5 TYPICAL BRANCH CIRCUIT PANEL LABELING DETAIL

NO SCALE

NOTES:

1. LAYOUT OF PANELBOARD, INCLUDING LOCATIONS OF NAMEPLATES, CIRCUIT DIRECTORY, AND OTHER LABELING IS SHOWN FOR REFERENCE ONLY, FIELD LOCATE AS NEEDED BASED ON TRUE EQUIPMENT LAYOUT AND DIMENSIONS.
2. REFERENCE OWNER'S DESIGN GUIDELINES FOR ADDITIONAL LABELING REQUIREMENTS.

(1) PROVIDE LAMACOID NAMEPLATE WITH 5/16" LETTERS SHOWING PANEL NAME, AMPERAGE RATING, VOLTAGE, AND FROM WHERE POWER IS DERIVED. ATTACH WITH MASTIC AND TWO SCREWS. COORDINATE TO GIVE SAME NAME AS PANEL SCHEDULE. IF USED AS MAIN SERVICE PANEL, PROVIDE SHORT CIRCUIT AVAILABLE AND RATING INFORMATION.

(2) PROVIDE PERMANENT ARC FAULT WARNING LABEL.


(3) FOR ALL NEW ELECTRICAL EQUIPMENT, PROVIDE PERMANENTLY AFFIXED LABEL STATING FAULT CURRENT AT THE TIME OF INSTALLATION AND CALCULATION. THE LABEL SHALL BE MINIMUM 2" X 3" IN SIZE, AND INCLUDE THE DATE OF THE CALCULATION. REFERENCE ELECTRICAL DRAWINGS AND EQUIPMENT SHORT CIRCUIT ANALYSIS TABLE. ATTACH WITH MASTIC AND TWO SCREWS.

(4) PROVIDE INFORMATION PER INDUSTRY STANDARDS, BUT SHALL INCLUDE VOLTAGE, PHASE, BUS AMPERAGE, AND SHORT CIRCUIT RATING

(5) FOR EACH CIRCUIT PROVIDE PERMANENT LABEL INDICATING CIRCUIT BREAKER NUMBER, NUMBER SHALL MATCH CIRCUIT DIRECTORY.

(6) CIRCUIT DIRECTORY TO BE COMPLETED AT END OF JOB, TYPEWRITTEN, STATING EQUIPMENT OR ROOMS SERVED BY CIRCUIT. EVEN CIRCUIT ON RIGHT SIDE OF CARD, ODD ON LEFT. PROVIDE LAMINATED DIRECTORY FOR EXTERIOR OR WET LOCATIONS.

(7) PROVIDE PERMANENT LABEL INDICATING COLOR CODING OF PHASE CONDUCTORS BASED ON VOLTAGE USING BUILDING COLOR SCHEME AS IDENTIFIED IN THE OWNER'S DESIGN GUIDELINES.




## 1 TYPICAL DISCONNECT, STARTER, & CONTACTOR LABELING DETAIL

NO SCALE

NOTES:

1. LOCATIONS OF NAMEPLATES SHOWN FOR REFERENCE ONLY, FIELD LOCATE AS NEEDED BASED ON TRUE EQUIPMENT LAYOUT AND DIMENSIONS. REFERENCE OWNER'S DESIGN GUIDELINES FOR ADDITIONAL LABELING REQUIREMENTS.

(1) PROVIDE AN ENGRAVED NAMEPLATE SHOWING LOAD SERVED, EQUIPMENT VOLTAGE, AND CIRCUIT NUMBER MATCHING AS-BUILT CONDITIONS.

(2) PROVIDE AN ENGRAVED NAMEPLATE SHOWING LOADS SERVED, VOLTAGES, AND CIRCUIT NUMBERS MATCHING AS-BUILT CONDITIONS FOR ALL CONTACTOR CIRCUITS. LOADS SERVED SHALL BE "LIGHTING", "FAN", "RECEPTACLES", "PUMP", "WATER HEATER", OR SIMILAR DESCRIPTIVE NOTE.

**DISHWASHER**
**480V, 3PH, 3 WIRE**
**FROM HK-2/4/6**

## 2 DISCONNECT LABELING

NO SCALE

NOTES:

1. PROVIDE LABEL ON EACH DISCONNECT AND FUSED SWITCH.
   1.1. FOR DISCONNECTS AND FUSED SWITCHES REPLACE "PANEL P1NA" WITH THE LOAD SERVED.
   1.2. REFER TO OWNER'S STANDARDS FOR ADDITIONAL LABEL REQUIREMENTS.
2. PROVIDE LABEL ON ELECTRICAL PANEL AND TRANSFORMER.
   2.1. REPLACE "PANEL P1NA" WITH THE PANEL OR TRANSFORMER NAME BEING LABELED.
3. REPLACE "400A FUSED SWITCH" WITH UPSTREAM SOURCE OR CONNECTION.
   3.1. IF FED FROM A XFMR REPLACE "400A FUSED SWITCH" WITH "XFMR XX" WHERE XX IS THE FIELD VERIFIED XFMR NAME.
4. REPLACE VOLTAGE CONFIGURATION TO MATCH THE EQUIPMENT BEING LABELED.
5. REFERENCE FLOOR PLANS FOR EQUIPMENT LOCATIONS.

**⚠ WARNING**
**Arc Flash and Shock Hazard**
**Appropriate PPE Required**


| FLASH PROTECTION | | SHOCK PROTECTION | |
|---|---|---|---|
| Incident Energy at: | 18 in | Shock Risk When Cover is Removed | 480 VAC |
| Min. Arc Rating: | 0.45 cal/cm² | Limited Approach | 42 in |
| Arc Flash Boundary: | 10 in | Restricted Approach | 12 in |
| PPE: Per NFPA 70E 2015 | 1 | Equipment Name: **PANEL HA** Prot Dev: 225/3 CB from Panel DA | |

## 3 TYPICAL ARC FLASH LABEL DETAIL

NO SCALE

NOTES:

1. VALUES AND NAMES SHOWN HERE ARE FOR REFERENCE ONLY, MODIFY TO REFLECT PROJECT'S ARC FLASH STUDY VALUES AND EQUIPMENT NAMES.
2. IF MIN. ARC RATING IS OVER 40CAL/CM² MODIFY "WARNING" TEXT TO READ "DANGER" AND PROVIDE RED SHADING IN LIEU OF ORANGE SHOWN.




## 4 TYPICAL TRANSFORMER LABELING DETAIL

NO SCALE

NOTES:

1. LOCATIONS OF NAMEPLATES SHOWN FOR REFERENCE ONLY, FIELD LOCATE AS NEEDED BASED ON TRUE EQUIPMENT LAYOUT AND DIMENSIONS.

(1) PROVIDE AN ENGRAVED NAMEPLATE SHOWING EQUIPMENT NAME, RATING, VOLTAGE, SOURCE.

STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM | (713) 300-4080
TEXAS ENG. FIRM REG. NO. F-018332 | © 2025 ALL RIGHTS RESERVED
1300 W. SAM HOUSTON PARKWAY S., SUITE 121, HOUSTON, TX 77042

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL




07.18.2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL DETAILS

a-E.012

## KITCHEN AREA ELECTRICAL NOTES

1. REFER TO KITCHEN CONSULTANTS "FS" DRAWINGS FOR ADDITIONAL REQUIREMENTS PARTICULARLY NOTING MOUNTING HEIGHTS OF EQUIPMENT OUTLETS AND JUNCTION BOXES, AND WHETHER SERVICE IS FROM WALL, FLOOR OR OVERHEAD.
2. SOME RECEPTACLES SHALL BE MOUNTED HORIZONTALLY, REFER TO KITCHEN CONSULTANTS "FS" DRAWINGS.
3. FOR DEVICES WITH SERVICE FROM FLOOR, RUN UNDERGROUND CONDUIT FROM DEVICES TO NEAREST COLUMN OR WALL THEN TURN CONDUIT UP AND RUN CONDUIT IN CEILING CAVITY.
4. LIGHT SWITCHES AND RECEPTACLES NOT SERVING A SPECIFIC PIECE OF EQUIPMENT SHALL BE MOUNTED AT ADA HEIGHTS.
5. CONNECTION TYPE SHOWN ON KITCHEN ELECTRICAL FLOOR PLAN IS FOR BIDDING PURPOSES, COORDINATE WITH KITCHEN EQUIPMENT SUPPLIER FOR FINAL CONNECTIONS:
   - 5.A. OBTAIN WIRING INSTRUCTIONS FOR EACH PIECE OF EQUIPMENT FROM EQUIPMENT SUPPLIER PRIOR TO ORDERING WIRING DEVICES AND ROUGH-IN.
   - 5.B. IF EQUIPMENT REQUIRES CORD AND PLUG CONNECTION, CONTRACTOR SHALL PROVIDE NEMA POWER CORD, PLUG, AND RECEPTACLES PER MANUFACTURER'S INSTRUCTION.
   - 5.C. IF EQUIPMENT REQUIRES JUNCTION BOX AND/OR DISCONNECT SWITCH, CONTRACTOR SHALL PROVIDE JUNCTION BOX AND DISCONNECT SWITCH AND CONNECT EQUIPMENT WITH SEALTITE FLEXIBLE CONDUIT.
6. ALL DISCONNECT SWITCHES IN THE KITCHEN AREA SHALL BE NEMA 4XSS STAINLESS STEEL.
7. WHERE PORTIONS OF INTERIOR RACEWAY SYSTEM ARE EXPOSED TO WIDELY DIFFERENT TEMPERATURES, PROVIDE AIR SEALING PER NEC TO PREVENT CIRCULATION OF AIR FROM WARMER TO A COOLER SECTION.
8. FLEXIBLE CONDUIT IN KITCHENS, FOOD PRODUCTION SPLASH ZONES AND WASH DOWN AREAS, FOOD PROCESSING, AND SIMILAR AREAS SHALL BE LIQUID TIGHT CONSTRUCTION INCORPORATING A BACTERIAL GROWTH INHIBITING PVC JACKET THAT MAY BE CLEANED WITHOUT DEGREDATION TO THE JACKET BLEACHING ELEMENTS AND APPROVED FITTINGS FOR WET LOCATION.
   - 8.A. AFC SZ TYPE LFMC OR EQUAL BY KAF-TECH.
9. INTERLOCK KITCHEN EXHAUST HOOD FIRE SYSTEM WITH FIRE ALARM SYSTEM.
10. PROVIDE RELAYS AND INTERLOCK KITCHEN HOOD FANS WITH FIRE ALARM SYSTEM. ACTUATION OF ANY ALARM INITIATING DEVICE SHALL DE-ENERGIZE KITCHEN HOOD FANS.
11. ALL GFI RECEPTACLES IN KITCHEN SHALL BE PASS & SEYMOUR MODEL 2097TRWR-XX TO EXCEED UL943 VOLTAGE SURGE REQUIREMENTS.





### 4 FIRE PROTECTION SYSTEM DETAIL

NO SCALE

NOTES:

1. ANSUL MODEL R-120 FIRE PROTECTION SYSTEM AND TANK(S)
2. ELECTRICAL CONTRACTOR TO FURNISH AND INSTALL POWER DISCONNECT DEVICES FOR ALL EQUIPMENT BELOW THE HOOD, SHUTTING OFF ALL SERVICE, INCLUDING CONTROL VOLTAGE, UPON ACTIVATION OF THE FIRE PROTECTION SYSTEM.
3. MICRO-SWITCH FURNISHED WITH SYSTEM TO BE INTERWIRED TO THE SHUT-OFF DEVICES FOR THE COOKING EQUIPMENT BY THE ELECTRICAL CONTRACTOR.
4. ELECTRICAL CONTRACTOR TO FURNISH AND INSTALL AN OCTAGON SHAPED HANDY BOX FOR THE PULL STATION AT 54" ABOVE THE FLOOR WITH 1/2" CONDUIT FROM THE TOP OF THE BOX TO 6" ABOVE THE CEILING.
5. GAS SHUT-OFF VALVE FURNISHED WITH THE SYSTEM (IF REQUIRED) TO BE INSTALLED IN THE GAS LINE SERVING THE COOKING EQUIPMENT BY THE PLUMBING CONTRACTOR. VERIFY SIZE OF GAS LINE.
6. ALL EXPOSED PIPEWORK TO BE STAINLESS STEEL OR CHROME WHERE EXPOSED.
7. VERIFY LOCATION OF REMOTE MANUAL PULL STATION.
8. UNIT MUST BE PLACED WITHIN EASY ACCESS OF EXIT DOOR.





### 5 KITCHEN HOOD FAN CONTROL SCHEMATIC

NO SCALE

NOTES:

1. THE FANS SHALL BE WIRED SO THAT ONE LOCAL SWITCH TURNS ON ASSOCIATED SUPPLY AND EXHAUST FANS.
2. IF THE FIRE ALARM IS IN ALARM, A FIRE ALARM CONTROL CONTACT SHALL CAUSE THE SUPPLY FAN TO STOP AND THE EXHAUST FAN TO START, EVEN IF THE CONTROL SWITCH IS "OFF".
3. SCHEMATIC IS DIAGRAMMATIC. PROVIDE INTERLOCK WIRING BASED ON EQUIPMENT PROVIDED AND FAN VOLTAGE TO IMPLEMENT THE SEQUENCE SPECIFIED.
4. COORDINATE BETWEEN FIRE ALARM CONTRACTOR, CONTROLS CONTRACTOR AND ELECTRICAL CONTRACTOR TO PROVIDE A COMPLETE INSTALLATION.
5. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.





### 1 GAS VALVE DETAIL

NO SCALE

NOTES:

1. GAS VALVE HOUSINGS ARE NOT SHOWN ON THE ELECTRICAL DRAWING. GC AND ELECTRICAL CONTRACTOR SHALL COORDINATE SIZE AND LOCATION OF GAS VALVE HOUSINGS.
2. SEE FOOD SERVICE CONSULTANT'S DRAWINGS ADDITIONAL INFORMATION AND REQUIREMENTS.
3. PROVIDE MINIMUM 3/4"C AS SHOWN ON THIS DETAIL.





### 2 RECESSED FIRE PULL DETAILS

NO SCALE

NOTES:

1. VERIFY LOCATION OF REMOTE MANUAL PULL STATION.
   - 1.A. MANUAL PULL STATION MUST BE PLACED WITHIN EASY ACCESS OF EXIT DOOR.
   - 1.B. MANUAL PULL STATION MUST BE PLACED NO LESS THAN 4 FEET AWAY FROM KITCHEN HOOD BUT WITHIN A MAXIMUM OF 20 FEET FROM THE KITCHEN HOOD.




### 3 TYPICAL PEDESTAL MOUNTED DEVICE

NO SCALE

NOTES:

1. ALL FACEPLATES SHALL BE STAINLESS STEEL.
2. PEDESTAL BOX PROVIDED BY DIVISION 26.
   - 2.A. A STANDARD DUPLEX INSTALLATION IS SHOWN FOR REFERENCE, PROVIDE SIMILAR INSTALLATION FOR QUAD RECEPTACLES, GFI RECEPTACLES, DATA OUTLETS, NEMA POWER OUTLETS, ETC.
   - 2.B. ALL PEDESTAL BOXES TO BE DOUBLE FACED WITH ONE BLANK FACE FOR FUTURE GROWTH. 2-GANG PEDESTALS WITH ONE BLANK FACE FOR QUAD RECEPTACLE LOCATIONS.
   - 2.C. PEDESTAL BOXES TO BE SIZED BY DIVISION 26 TO PROVIDE SCHEDULED DEVICES ON A SINGLE FACE AND SUFFICIENT DEPTH FOR BACK TO BACK DEVICES ON DOUBLE FACED PEDESTALS.
   - 2.D. BASIS OF DESIGN:
     - 2.D.A. 1-GANG ELECTRICAL DEVICES: LEGRAND LBP2 OR WATER SAVER E400SA-WS
     - 2.D.B. 1-GANG LOW VOLTAGE DEVICES: LEGRAND LBP2 OR WATER SAVER E400SA-WS
     - 2.D.C. 2-GANG ELECTRICAL DEVICES: WATER SAVER E600SA-WS
     - 2.D.D. 2-GANG LOW VOLTAGE DEVICES: WATER SAVER E600SA-WS
3. INSTALLATION REQUIREMENTS:
   - 3.A. STUB UP CONDUIT ABOVE FLOOR TO PEDESTAL BOX CONNECTION LOCATION.
   - 3.B. GROUT GAP BETWEEN FINISHED FLOOR AND BOTTOM OF PEDESTAL BOX.
   - 3.C. PROVIDE TRANSITION PIECE TO CONTINUE FINISHED FLOOR TO BOTTOM EDGE OF SERVICE FITTING AND CONCEAL GROUT. TRANSITION PIECE TO MATCH ARCHITECT'S FINISH SCHEDULE.
   - 3.D. PEDESTAL BOX TO BE INSTALLED SQUARE TO THE FINISHED FLOOR.
4. PROVIDE TYPEWRITTEN OR PREMADE CIRCUIT LABELS ON INSTALLED WIRING AT EACH DEVICE AND SPLICE POINT.
5. PROVIDE TYPEWRITTEN LABEL AFFIXED TO THE FRONT OF EACH DEVICE FACEPLATE INDICATING ELECTRICAL CIRCUIT.

CIRCUIT LABEL

XX-##

A. XX = PANEL DESIGNATION

B. ## = AS-BUILT CIRCUIT DESIGNATION

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL
KITCHEN DETAILS

a-E.013


STANTON ENGINEERING GROUP
INFORMATION@STANTONENGINEERING.COM | (713) 305-4080
TEXAS ENG. FIRM REG. NO. F-018332 | © 2025 ALL RIGHTS RESERVED
12999 W. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77082

LIGHTING SYSTEM FUNCTIONAL TESTING AND DOCUMENTATION NOTES:

1. PRIOR TO PASSING FINAL INSPECTION, THE CONTRACTOR SHALL PERFORM FUNCTIONAL TESTING IN THE PRESENCE OF THE REGISTERED DESIGN PROFESSIONAL, THE OWNER AND/OR THEIR AGENT. THE FUNCTIONAL TESTING SHALL BE AS REQUIRED BY SECTION C408.3.1 OF THE 2021 IECC.
   1.A. THE FUNCTIONAL TESTING SHALL PROVIDE EVIDENCE THAT THE LIGHTING CONTROL SYSTEMS, INCLUDING BOTH HARDWARE AND SOFTWARE, ARE CALIBRATED, ADJUSTED, PROGRAMMED AND IN PROPER WORKING CONDITION IN ACCORDANCE WITH THE CONSTRUCTION DOCUMENTS AND MANUFACTURER'S INSTRUCTIONS.
   1.B. THE FUNCTIONAL TESTING SHALL BE IN ACCORDANCE WITH SECTIONS C408.3.1.1 AND C408.3.1.2 OF THE 2021 IECC FOR THE APPLICABLE CONTROL TYPE.
   1.C. A WRITTEN REPORT SHALL BE GENERATED DOCUMENTING THE FUNCTIONAL TESTING RESULTS IN ACCORDANCE WITH THE 2015 IECC REQUIREMENTS.
2. ALL LIGHTING CONTROLS O&M MANUALS, AS-BUILTS, TESTING REPORTS AND DOCUMENTATION RELATED TO THE LIGHTING CONTROL SYSTEM SHALL BE PROVIDED IN THEIR FINAL AND APPROVED FORM WITHIN 60 DAYS OF THE CERTIFICATE OF OCCUPANCY. ALL DOCUMENTS CERTIFYING THAT THE INSTALLED LIGHTING CONTROLS MEET DOCUMENTED PERFORMANCE CRITERIA OF SECTION C405 OF THE 2021 IECC SHALL BE INCLUDED IN THE O&M MANUALS.
3. ALL DOCUMENTS FROM ITEMS #1 AND #2 ABOVE SHALL BE COMBINED AND PROVIDED TO THE OWNER WITHIN 90 DAYS FROM THE DATE OF RECEIPT OF THE CERTIFICATE OF OCCUPANCY.

# LIGHT FIXTURE SCHEDULE

## EXTERIOR LIGHT FIXTURE SCHEDULE

| | | | |
|---|---|---|---|
| RECESSED 6" DOWNLIGHT WET LOCATION | D5<br>D5Y | 6" DIAMETER RECESSED LED DOWNLIGHT, SPECULAR CLEAR REFLECTOR, MEDIUM (56') BEAM DISTRIBUTION, 1000 LUMENS, 4000K COLOR TEMPERATURE, 120-277V MULTIVOLT INPUT, 1% 0-10V DIMMING DRIVER.<br>LIGHTOLIER 6R-N / C6L-10-9-40-M-Z10-U / C6-R-DL-CC | 9W |
| RECESSED 6" DOWNLIGHT WET LOCATION | D6<br>D6Y | 6" DIAMETER RECESSED LED DOWNLIGHT, SPECULAR CLEAR REFLECTOR, MEDIUM (56') BEAM DISTRIBUTION, 2000 LUMENS, 4000K COLOR TEMPERATURE, 120-277V MULTIVOLT INPUT, 1% 0-10V DIMMING DRIVER.<br>LIGHTOLIER 6R-N / C6L-20-9-40-M-Z10-U / C6-R-DL-CC | 22W |
| SURFACE CANOPY SQUARE LED | WC1<br>WC1X<br>WC1Y | 9" SQUARE SURFACE LED CANOPY LIGHT, 4000K COLOR TEMPERATURE, 3500 LUMENS, 120-277V MULTIVOLT INPUT, DARK BRONZE FINISH.<br>EELP VR7-T-28L-QT-40K (EBLED9W) | 28W |
| EXTERIOR WALL PACK | WP1<br>WP1X<br>WP1Y | 7" WDE WALL MOUNTED LED, 4000K COLOR TEMPERATURE, 5000 LUMENS, TYPE 3 DISTRIBUTION, 120-277 MULTIVOLT INPUT, WET LOCATION, 10KV KA SURGE PROTECTION.<br>REFER TO ARCH FOR MOUNTING HEIGHT.<br>FINISH TO BE SELECTED BY ARCHITECT FROM ALL AVAILABLE FINISHES.<br>GARDCO GEOFORM SMALL GWS-A04-740-UNV-XX FINISH (EM) | 34W |
| EXTERIOR WALL PACK | WP2<br>WP2X<br>WP2Y | 12" WDE WALL MOUNTED LED, 4000K COLOR TEMPERATURE, 8500 LUMENS, TYPE 3 DISTRIBUTION, 120-277 MULTIVOLT INPUT, WET LOCATION. REFER TO ARCH FOR MOUNTING HEIGHT.<br>REFER TO ARCH FOR MOUNTING HEIGHT.<br>FINISH TO BE SELECTED BY ARCHITECT FROM ALL AVAILABLE FINISHES.<br>GARDCO GEOFORM MEDIUM GWM-A11-740-T3M-UNV-XX FINISH (REMOTE EM BATTERY) | 52W |
| EXTERIOR WALL PACK | WP3<br>WP3X<br>WP3Y | 17" WDE WALL MOUNTED LED, 4000K COLOR TEMPERATURE, 12500 LUMENS, TYPE 3 DISTRIBUTION, 120-277 MULTIVOLT INPUT, WET LOCATION. REFER TO ARCH FOR MOUNTING HEIGHT.<br>REFER TO ARCH FOR MOUNTING HEIGHT.<br>FINISH TO BE SELECTED BY ARCHITECT FROM ALL AVAILABLE FINISHES.<br>GARDCO GEOFORM MEDIUM GWM-A14-740-T3M-UNV-XX FINISH (REMOTE EM BATTERY) | 77W |

1. LIGHT FIXTURE CATALOG NUMBERS AND DESCRIPTIONS ARE SCHEDULED FOR ESTABLISHING QUALITY, APPEARANCE AND PERFORMANCE OF THE FIXTURES. EXACT CATALOG NUMBERS DESCRIBING MOUNTING CONDITIONS AND REQUIREMENT RELATED TO TRIM FOR ALL FIXTURES SHALL BE CONFIRMED (BY THE ELECTRICAL CONTRACTOR) WITH THE ROOM FINISH SCHEDULE AND REFLECTED CEILING PLANS ON THE ARCHITECTURAL PLANS PRIOR TO BIDDING AND SUBMITTING LIGHT FIXTURES. PROVIDE DRY WALL KIT AS REQUIRED.
2. ALL 'X', 'Y', AND 'Z' TYPE FIXTURES SHALL HAVE EMERGENCY POWER BACKUP. EMERGENCY POWER SOURCES SHALL MONITOR POWER UPSTREAM OF THE LIGHTING CONTROLS TO SEE IF POWER IS LOST. BATTERY PACKS AND INVERTERS SHALL BE CAPABLE OF POWERING THE DESIGNATED FIXTURE(S) WITH AN OUTPUT OF 1400 LUMENS FOR A MINIMUM OF 90-MINUTES. PROVIDE REMOTE BATTERY PACKS OR INVERTERS AS NECESSARY. EMERGENCY LIGHTS SHALL OPERATE ONLY UPON LOSS OF POWER; ALSO, PROVIDE AND WIRE TEST SWITCH AND LED INDICATOR LIGHT FOR EMERGENCY BATTERY. SEE WIRING INSTRUCTION SUPPLIED BY EMERGENCY BATTERY MANUFACTURER.
   2.A. 'X' TYPE FIXTURES (AX, ETC.) HAVE EMERGENCY GENERATOR POWER LIGHTING TRANSFER DEVICES.
   2.B. 'Y' TYPE FIXTURES (MY, ETC.) HAVE INDIVIDUAL 90-MINUTE EMERGENCY BATTERY POWER.
   2.C. 'Z' TYPE FIXTURES (GTZ, ETC.) HAVE 90-MINUTE INVERTER EMERGENCY BATTERY POWER.
3. PROVIDE BASE COVER FOR ALL LIGHT POLES.
4. ALL EXTERIOR FIXTURES SHALL BE WET RATED WITH COLD WEATHER BALLASTS AND BATTERY PACKS.
5. PROVIDE SPARE FIXTURES AND EMERGENCY DEVICES PER SPECIFICATIONS.
6. WHERE FIXTURE FINISHES ARE INDICATED TO BE SELECTED BY ARCHITECT THE CONTRACTOR SHALL INCLUDE IN THEIR BID ALL AVAILABLE FINISHES. SUBMIT COMPLETE FIXTURE FINISH OPTIONS AS PART OF THE LIGHTING SUBMITTAL PACKAGE.
7. EQUAL BY PHILIPS (CW LIGHTING), COOPER (PUTTERMAN SCHAROK), AND LITHONIA (LESCO) SHALL BE ACCEPTABLE.

## INTERIOR LIGHT FIXTURE SCHEDULE

| APPLICATION | TYPE | DESCRIPTION | WATTS |
|---|---|---|---|
| 1X4 RECESSED LAY-IN CEILING SELECTABLE CCT & LUMENS | A1<br>A1X<br>A1Y | 2X4 RECESSED LED, SMOOTH FROSTED ACRYLIC LENS, EXTRUDED ALUMINUM FRAME, WHITE FINISH, LAY-IN CEILING, 6000 LUMENS, 4000K COLOR TEMPERATURE, 120-347V MULTIVOLT INPUT, 5% 0-10V DIMMING.<br>SET FIELD SELECTABLE SWITCHES TO NEUTRAL WHITE (4000K) AND HIGH (47W).<br>DAYBRITE 2SBP3550L8CS-4-UNJ-DIM | 47W |
| 1X4 RECESSED LAY-IN CEILING SELECTABLE CCT & LUMENS | B1<br>B1X<br>B1Y | 1X4 RECESSED LED, SMOOTH FROSTED ACRYLIC LENS, EXTRUDED ALUMINUM FRAME, WHITE FINISH, LAY-IN CEILING, 4500 LUMENS, 4000K COLOR TEMPERATURE, 120-347V MULTIVOLT INPUT, 5% 0-10V DIMMING.<br>SET FIELD SELECTABLE SWITCHES TO NEUTRAL WHITE (4000K) AND HIGH (36W).<br>DAYBRITE 1SBP3040L8CS-4-UNJ-DIM | 36W |
| 2X2 RECESSED LAY-IN CEILING SELECTABLE CCT & LUMENS | B2<br>B2X<br>B2Y | 2X2 RECESSED LED, SMOOTH FROSTED ACRYLIC LENS, EXTRUDED ALUMINUM FRAME, WHITE FINISH, LAY-IN CEILING, 4250 LUMENS, 4000K COLOR TEMPERATURE, 120-347V MULTIVOLT INPUT, 5% 0-10V DIMMING.<br>SET FIELD SELECTABLE SWITCHES TO NEUTRAL WHITE (4000K) AND HIGH (36W).<br>DAYBRITE 2SBP3040L8CS-2-UNJ-DIM | 39W |
| 4FT STRIP LED MECHANICAL & STORAGE ROOMS | C<br>CX<br>CY | 4 FOOT STRIP LED, STEEL HOUSING, FROSTED ACRYLIC LENS, 4000 LUMENS, 3500K COLOR TEMPERATURE, CHAIN HANGING SET, WIRE GUARD, 120-277V MULTIVOLT INPUT, 0-10V DIMMING DRIVER. PROVIDE CHAIN HANGING SET AND WIREGUARD IN MECHANICAL ROOMS AND AREAS WITHOUT CEILINGS.<br>SET FIELD SELECTABLE SWITCHES TO NEUTRAL WHITE (4000K) AND HIGH (36W).<br>DAYBRITE SDS-4-2448L-8CST-UNV-DIM | 30W |
| RECESSED 6" DOWNLIGHT | D1<br>D1X<br>D1Y | 6" DIAMETER RECESSED LED DOWNLIGHT, MATTE WHITE FINISH, WIDE (76') BEAM DISTRIBUTION, 1000 LUMENS, 4000K COLOR TEMPERATURE, 120-277V MULTIVOLT INPUT, 1% 0-10V DIMMING DRIVER.<br>LIGHTOLIER 6R-N / C6L-10-9-40-W-Z10-U / C6-R-DL-WH | 9W |
| RECESSED 6" DOWNLIGHT | D2<br>D2X<br>D2Y | 6" DIAMETER RECESSED LED DOWNLIGHT, MATTE WHITE FINISH, WIDE (76') BEAM DISTRIBUTION, 2000 LUMENS, 4000K COLOR TEMPERATURE, 120-277V MULTIVOLT INPUT, 1% 0-10V DIMMING DRIVER.<br>LIGHTOLIER 6R-N / C6L-20-9-40-W-Z10-U / C6-R-DL-WH | 22W |
| EXIT SIGN | XB<br>XS<br>XD | DIE CAST ALUMINUM LED EXIT LIGHT, RED LETTERS, MATTE BLACK HOUSING W/ BRUSHED ALUMINUM FACE, UNIVERSAL ARROWS, 120/277 VOLT DUAL INPUT, 90 MINUTE EMERGENCY BATTERY. VERIFY LETTER AND FACE COLOR WITH OWNER/ARCHITECT PRIOR TO ORDERING.<br>XS=SINGLE FACE, XD=DOUBLE FACE, XB=BACK MOUNTED<br>PHILIPS CHLORIDE ER55L-3-R<br>SURELITES CX7-1/2-R<br>LITHONIA LQC-1/2-R-EL N | 5W |
| EXIT SIGN INTEGRAL BATTERY INTEGRAL EM LIGHT BAR | YB<br>YS<br>YD | THERMOPLASTIC LED EXIT LIGHT WITH INTEGRAL EM LIGHT, RED LETTERS, WHITE HOUSING W/ WHITE FACE, UNIVERSAL ARROWS, 120-277 MULTIVOLT INPUT, 90 MINUTE EMERGENCY BATTERY. VERIFY LETTER AND FACE WITH OWNER/ARCHETICT PRIOR TO ORDERING.<br>YS=SINGLE FACE, YD=DOUBLE FACE, YB=BACK MOUNTED<br>SIGNTEX CLP-BB-U-R-W-DG | 5W |
| TWIN HEAD EM LIGHT INTEGRAL BATTERY WET LOCATION | YT1 | TWIN HEAD EM LIGHT, INJECTION-MOLDED THERMOPLASTIC WHITE HOUSING, GASKETED CLEAR POLYCARBONATE COVER, LED LAMPS, 90-MINUTE EMERGENCY BATTERY.<br>CHLORIDE TPU-W-N-LM7-W | 7W |

# LIGHTING CONTROL SEQUENCE OF OPERATIONS

| ROOM TYPE | AUTO ON | MANUAL ON (VACANCY) | AUTO OFF (20 MIN MAX) | PARTIAL OFF AT NORMAL HOURS | AUTO ON AFTER HOURS | AUTO OFF AFTER HOURS (20 MIN MAX) | TIME ON | TIME OFF | ASTRONOMIC OR PHOTOCELL ON/OFF | AUTO STEP CONTROL WITH OFF | AUTO CONTINUOUS DIM WITH OFF | MANUAL BI-LEVEL REDUCTION CONTROL | MANUAL CONTINUOUS DIM CONTROL | MANUAL ON/OFF SWITCH | MANUAL DIMMER SWITCH | DISPLAY, ACCENT, TASK CONTROL | PLUG LOAD CONTROL | SEQUENCE OF OPERATION |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | OCCUPANCY SENSOR | | | | | | TIME SWITCH/SCHEDULING | | | DAYLIGHT CONTROL | | LIGHT REDUCTION | | MANUAL CONTROL | | | | |
| Kitchen/Serving | | | | | | | • | • | | | | • | | • | | | | LOCAL ON/OFF CONTROLS, LOCAL CONTROLS MAY OVERRIDE BUILDING SCHEDULE AND TURN ALL LIGHTS ON FOR MAXIMUM 2HRS. NETWORK LIGHTING CONTROLS ROOM CONTROLLER CONNECTED TO BUILDING CONTROLS; ON/OFF BASED ON BUILDING SCHEDULE, AFTER HOURS ON/OFF BASED ON OCCUPANCY, COORDINATE SCHEDULING WITH OWNER. WHERE ≥150W IN DAYLIGHT AREA, USE CONTINUOUS DIMMING DAYLIGHTING CONTROL. |
| Restrooms | 100% | | 20 MIN | | | | | | | | | | | • | | | | AUTO ON 100%, AUTO OFF BY LOCAL OCCUPANCY SENSOR. LOCAL ON/OFF CONTROLS ONLY, NO FULLY NETWORKED SYSTEM. |
| Custodial rooms | | • | 20 MIN | | | | | | | | | | | • | • | | | MANUAL ON, AUTO OFF BY LOCAL OCCUPANCY SENSOR. LOCAL ON/OFF CONTROLS ONLY, NO FULLY NETWORKED SYSTEM. |
| Storage rooms | 50% | | 20 MIN | | | | | | | | | | | • | • | | | AUTO ON 50%, AUTO OFF BY LOCAL OCCUPANCY SENSOR. LOCAL ON/OFF/DIMMING CONTROLS ONLY, NO FULLY NETWORKED SYSTEM. |
| Private Offices | 50% | | 20 MIN | | | | | | | | | | | • | • | | • | AUTO ON 50%, AUTO OFF BY LOCAL OCCUPANCY SENSOR. LOCAL ON/OFF/DIMMING CONTROLS ONLY, NO FULLY NETWORKED SYSTEM. |
| Corridors | | | | | 100% | 20 MIN | • | • | | | | | | • | | | | LOCAL ON/OFF CONTROLS, LOCAL CONTROLS MAY OVERRIDE BUILDING SCHEDULE AND TURN ALL LIGHTS ON FOR MAXIMUM 2HRS. NETWORK LIGHTING CONTROLS ROOM CONTROLLER CONNECTED TO BUILDING CONTROLS; ON/OFF BASED ON BUILDING SCHEDULE, AFTER HOURS ON/OFF BASED ON OCCUPANCY, COORDINATE SCHEDULING WITH OWNER. WHERE ≥150W IN DAYLIGHT AREA, USE CONTINUOUS DIMMING DAYLIGHTING CONTROL. |
| Electrical Rooms | | | | | | | | | | | | | | • | | | | MANUAL ON/OFF; LOCAL CONTROL DEVICE NOT TIED TO LVLCS. |
| Building Facade/Landscape | | | | | | | • | • | | | | | | | | | | CONNECTED TO BUILDING CONTROLS THROUGH LIGHTING CONTACTOR; ON/OFF BASED ON BUILDING SCHEDULE. |

1. DIMMER SWITCHES SHALL ACTIVATE PRESET ALL ON LIGHTING LEVEL WHEN PRESSED IN THE UP POSITION. LIGHTING LEVELS MAY BE RAISED/LOWERED BY HOLDING THE DIMMER PADDLE. WHEN PRESSED IN THE DOWN POSITION ALL LIGHTS SHALL SMOOTHLY DIM TO OFF.
2. AT LEAST 50 PERCENT OF ALL 125V, 15- AND 20-AMP RECEPTACLES INSTALLED IN ENCLOSED OFFICES, CONFERENCE ROOMS, ROOMS USED PRIMARILY FOR COPY OR PRINT FUNCTIONS, BREAKROOMS, CLASSROOMS AND INDIVIDUAL WORKSTATIONS, INCLUDING THOSE INSTALLED IN MODULAR PARTITIONS AND MODULE OFFICE WORKSTATION SYSTEMS SHALL HAVE PLUG LOAD CONTROL PER IECC 2021 C405.11.

# LIGHTING CONTACTOR SCHEDULE

**CONTACTOR CT1**

| POLE | DESCRIPTION | NORMAL CKT | EM CKT | CONTROL ZONE | CONTACTOR LOCATION | CONTACTOR TYPE |
|---|---|---|---|---|---|---|
| CT1-1 | KITCHEN/SERVING AREA - ZONE 'a' | HK-3 | - | Kitchen-a | CENTRAL PLANT | MAGNETICALLY HELD |
| CT1-2 | SPARE | | | Kitchen-a | CENTRAL PLANT | MAGNETICALLY HELD |
| CT1-3 | SPARE | | | Kitchen-a | CENTRAL PLANT | MAGNETICALLY HELD |

**CONTACTOR CT2**

| | | | | | | |
|---|---|---|---|---|---|---|
| CT2-1 | KITCHEN/SERVING AREA - ZONE 'b' | HK-3 | - | Kitchen-b | CENTRAL PLANT | MAGNETICALLY HELD |
| CT2-2 | SPARE | | | Kitchen-b | CENTRAL PLANT | MAGNETICALLY HELD |
| CT2-3 | SPARE | | | Kitchen-b | CENTRAL PLANT | MAGNETICALLY HELD |

**CONTACTOR CT3**

| | | | | | | |
|---|---|---|---|---|---|---|
| CT3-1 | KITCHEN SOFFIT/CANOPY LTS | HK-5 | - | Exterior | CENTRAL PLANT | MAGNETICALLY HELD |
| CT3-2 | | | | Exterior | CENTRAL PLANT | MAGNETICALLY HELD |
| CT3-3 | | | | Exterior | CENTRAL PLANT | MAGNETICALLY HELD |

1. REFERENCE TYPICAL LIGHTING CONTACTOR WIRING DIAGRAM.
2. EMERGENCY AND NORMAL ZONES WITHIN THE KITCHEN/SERVING SHALL HAVE SEPARATE CONTROLS TO ALLOW FOR LIGHTING REDUCTION CONTROL.
3. LIGHTING CONTACTORS SHALL BE DIN RAIL MOUNTED, MAGNETICALLY HELD TYPE WITH THREE WIRE CONTROL BY THE BAS.
   3.A. PROVIDE CABINET AT EACH LOCATION TO MOUNT ALL CONTACTORS IN A SINGLE ENCLOSURE. ENCLOSURE SIZED BY DIVISION 26.
   3.B. PROVIDE SEPARATE HOA SWITCHES IN THE FRONT COVER OF THE ENCLOSURE WIRED TO CONTROL THE FOLLOWING ZONES SEPARATELY.
      3.B.1. INTERIOR LIGHTING (ALL INTERIOR LIGHTING GROUPS)
      3.B.2. EXTERIOR LIGHTING (ALL EXTERIOR LIGHTING GROUPS)
      3.B.3. HOA SWITCH SHALL PASS THE BAS SIGNALS IN AUTO MODE, DISENGAGE ALL CONTACTORS IN THE OFF POSITION, AND ENGAGE ALL THE CONTACTORS IN THE ON POSITION.
   3.C. SPARE CAPACITY:
      3.C.1. PROVIDE MINIMUM TWO (2) SPARE POLE ON EACH COMBINED TYPE CONTACTOR FOR FUTURE USE.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025


ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING


LIGHTING SCHEDULES

a-E.060


STANTON ENGINEERING GROUP
INFORMATION@STANTON-ENG.COM (713) 300-6080


TEXAS ENGINEERING FIRM REGISTRATION # F-19332 © 2025 ALL RIGHTS RESERVED


12999 W. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77064




**1 LIGHTING RENOVATION PLAN**
SCALE: 1/4" = 1'- 0"

## ELECTRICAL KEYED NOTES

GENERAL NOTES:

- CUT WALLS AS REQUIRED TO FLUSH MOUNT NEW DEVICES IN EXISTING WALLS. PATCH/REPAIR WALLS TO MATCH.

LIGHTING RENOVATION NOTES:

A. KITCHEN LIGHTS TO BE CONTROLLED BY LOCAL MOMENTARY SWITCHES AND BAS. LIGHTING CONTACTOR LOCATIONS SHOWN SCHEMATICALLY ONLY. LOCATE LIGHTING CONTACTOR ENCLOSURE IN THE ADJACENT CENTRAL PLANT SPACE, FIELD VERIFY. REFERENCE LIGHTING CONTROL DETAIL. TYPICAL.
LEFT SWITCH SHALL CONTROL ZONE 'a' NORMAL POWER LIGHTING FIXTURES.
RIGHT SWITCH SHALL CONTROL ZONE 'b' EMERGENCY LIGHTING FIXTURES.

B. PROVIDE PLUG LOAD CONTROLS TIED TO THE LIGHTING IN OFFICE SPACES.

C. WIRE EXIT SIGNS UPSTREAM OF LIGHTING CONTROLS. TYPICAL.

D. EXTERIOR LIGHTS TO BE CONTROLLED BY BAS. LIGHTING CONTACTOR LOCATIONS SHOWN SCHEMATICALLY ONLY. LOCATE LIGHTING CONTACTOR ENCLOSURE IN THE ADJACENT CENTRAL PLANT SPACE, FIELD VERIFY. REFERENCE LIGHTING CONTROL DETAIL. TYPICAL.

E. AFTER REMOVAL OF THE TEMPORARY KITCHEN, PROVIDE NEW EXIT SIGN AT ORIGINAL LOCATION AND RECONNECT TO EXISTING CAFETERIAL LIGHTING CIRCUIT.

F. PATCH/REPAIR EXTERIOR SOFFIT TO ACCOMMODATE NEW SURFACE MOUNTED FIXTURES.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

LIGHTING FLOOR PLANS

a-E.100


STANTON ENGINEERING GROUP
INFORMATION-ENGINEER | TEXAS ENG. FIRM REG. NO.F-21833 (713) 300-9080 | 1300 W. SAM HOUSTON PARKWAY N., SUITE 121, HOUSTON, TX 77043


ALL RIGHTS RESERVED




## 1 ELECTRICAL RENOVATION PLAN

SCALE: 1/4" = 1'- 0"

## ELECTRICAL KEYED NOTES

GENERAL NOTES:

- CUT WALLS AS REQUIRED TO FLUSH MOUNT NEW DEVICES IN EXISTING WALLS. PATCH/REPAIR WALLS TO MATCH.

ELECTRICAL RENOVATION NOTES:

A. CONNECT NEW FREEZER/COOLER AND CONDENSER TO EXISTING STANDBY GENERATOR.

B. PROVIDE ILLUMINATED PUSH BUTTON IN COOLER AND FREEZER. WHEN PRESSED RED STROBE DEVICES IN KITCHEN AND CAFETERIA SHALL ACTIVATE. TYPICAL.

C. PROVIDE HORN/STROBE DEVICE TIED TO PUSH BUTTONS IN FREEZER/COOLER.
(EDWARDS 860 SERIES OR EQUAL).

D. PROVIDE NEW DOORBELL BUTTON AT RECEIVING DOOR. DOORBELL BUTTON SHALL BE THE CLOSEST DEVICE TO THE DOOR FRAME.

E. PROVIDE NEW VIBRATING BUZZER TIED TO DOORBELL BUTTON AT RECEIVING DOOR. BUZZER TO BE WALL MOUNTED JUST BELOW THE CEILING.

F. PROVIDE NEW ELECTRICAL DEVICES MATCHING NEW KITCHEN EQUIPMENT AND ROOM LAYOUTS. REFERENCE FOOD SERVICE DRAWINGS. TYPICAL.

G. PROVIDE ROUGH-IN FOR LOW VOLTAGE DEVICES. REFERENCE TECHNOLOGY DRAWINGS, TYPICAL.

H. POWER AND DATA ROUGH-IN FOR KITCHEN MENU BOARD.

I. POWER AND DATA ROUGH-IN FOR POINT OF SALE (POS) LOCATION.

J. PROVIDE DROP CORD RECEPTACLE WITH HUBBELL KELLEMS LIQUIDTIGHT GRIPS FOR STRAIN RELIEF, TYPICAL OF ALL.

K. PROVIDE J-BOXES AND CONDUIT FOR REMOTE FIRE PULLS, SEE FOOD SERVICE DETAIL DRAWING FOR REQUIREMENTS, TYPICAL

L. WIRE ANSUL SYSTEM TO HOOD EQUIPMENT CONTROL CONTRACTOR. UPON ANSUL SYSTEM ACTIVATION ALL POWER TO EQUIPMENT BENEATH THE HOODS SHALL BE DEACTIVATED. MOUNT CONTACTOR CABINET(S) JUST BELOW THE CEILING.

M. PROVIDE SEPARATE SWITCHES TO TURN ON HOOD LIGHTS AND FANS. WIRE HOOD TEMP SENSOR AHEAD OF HOOD LIGHT SWITCH. USE 120V CIRCUIT TO CONTROL HOOD FANS THROUGH EXISTING STARTER. PROVIDE CONTROLS TRANSFORMER AS REQUIRED TO MATCH STARTER CONTROL INPUT VOLTAGE. TYPICAL.

N. PROVIDE PLUG LOAD CONTROLS TIED TO THE LIGHTING IN OFFICE SPACES.

O. INTERCONNECT DISH MACHINE TO VENT CONTROL. INTERCONNECT TABLE LIMIT SWITCH TO DISHMACHINE.

P. EXISTING MECHANICAL EQUIPMENT TO BE REPLACED. CONNECT TO CIRCUIT AS SHOWN. RECONNECT TO EXISTING STARTER/CONTACTORS, FIELD VERIFY.

Q. SAWCUT FLOOR TO INSTALL NEW PEDESTAL MOUNTED DEVICE BENEATH NEW SERVING LINES, DO NOT REUSE EXISTING STUB UPS OR DEVICES. POUR BACK SLAB AND PROVIDE NEW FINISHES, REFERENCE ARCHITECTURAL.

R. REFERENCE EDF GFI PROTECTION DETAIL FOR INSTALLATION REQUIREMENTS, TYPICAL.

S. WIRE MICRO SWITCH IN DOOR FRAME TO AIR SCREEN. COOR W/ FOOD SERVICE CONTRACTOR PRIOR TO ROUGH-IN. LOCATE LOCAL MOTOR RATED SWITCH ABOVE CEILING ADJACENT TO THE AIR SCREEN.

COOLER/FREEZER NOTES:

1. PROVIDE SEALING FOR CONDUIT IN COOLER AND FREEZER. WHERE PORTIONS OF INTERIOR RACEWAY SYSTEM ARE EXPOSED TO WIDELY DIFFERENT TEMPERATURES, CIRCULATION OF AIR FROM WARMER TO A COLDER SECTION SHALL BE PREVENTED PER N.E.C. ARTICLE 300.7 (A).
2. PROVIDE GROUND-FAULT PROTECTION OF EQUIPMENT FOR ELECTRIC HEAT TRACING AND HEATING PANELS IN THE FREEZER PER N.E.C. ARTICLE 427.22.
3. ELECTRICAL CONTRACTOR SHALL PROVIDE LIQUID TIGHT CONDUIT AND WIRING FOR LIGHT FIXTURES AND LIGHT SWITCHES IN WALK-IN COOLER AND FREEZER, SEE FOODSERVICE CONSULTANT'S DRAWINGS.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL FLOOR PLANS

a-E.200


STANTON ENGINEERING GROUP
INFORMATION@STANTONENGR.COM (713) 300-8206
TEXAS ENG. FIRM REG. NO. F-21833 | 13915 N. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77060

ALL RIGHTS RESERVED




**1** **FIRE ALARM RENOVATION PLAN**
SCALE: 1/4" = 1'- 0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL
ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

FIRE ALARM FLOOR PLANS

a-E.300

STANTON ENGINEERING GROUP
INFORMATION - EMERGENCY (713) 300-6262
TEXAS ENGINEERING FIRM REGISTRATION NO. F-01833 | 1300 W. SAM HOUSTON PARKWAY S., SUITE 121, HOUSTON, TX 77042
ALL RIGHTS RESERVED




## 1 PARTIAL ELECTRICAL RISER

NO SCALE

NOTES:
1. FIELD VERIFY ALL EXISTING ELECTRICAL PANELS AND FEEDERS SHOWN ON DRAWINGS.
2. REF ELECTRICAL FLOOR PLANS FOR PANEL LOCATIONS.
3. ALL OUTAGES SHALL BE SCHEDULED/CONFIRMED IN WRITING WITH THE OWNER A MINIMUM OF TWO WEEKS PRIOR TO ANY OUTAGE.
4. AT THE END OF THE PROJECT PROVIDE A NEW TYPEWRITTEN PANEL SCHEDULE USING BUILDING ROOM NUMBERS FOR ALL PANELS WITH CIRCUITS ADDED, REMOVED, OR MODIFIED AS PART OF THE PROJECT.
5. REFERENCE PANEL SCHEDULES AND SHORT CIRCUIT TABLE FOR AIC AND SCCR VALUES.

## NEW KITCHEN PANEL

**PANEL HK** — 225A MLO, 480Y/277V, 3ϕ, 4 WIRE — AVAILABLE FAULT: 20,250A — SCCR & AIC: 25,000A — MOUNTING: RECESSED — STAINLESS STEEL COVER

| NOTES | EQUIP. NO. | LOAD | DESCRIPTION | WIRE | CB | CKT | A | B | C | CKT | CB | WIRE | DESCRIPTION | LOAD | EQUIP. NO. | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | 325 | KITCHEN ROOM LIGHTS | 3–12 | 20/1 | 1 | | | | 2 | | | SPACE | | | |
| 6 | | 1041 | KITCHEN LIGHTS | 3–12 | 20/1 | 3 | | | | 4 | | | SPACE | | | |
| 7 | | 84 | KITCHEN SOFFIT LIGHTS | 3–12 | 20/1 | 5 | | | | 6 | | | SPACE | | | |
| | | | SPARE | | 20/1 | 7 | | | | 8 | | | SPACE | | | |
| | | | SPARE | | 20/1 | 9 | | | | 10 | | | SPACE | | | |
| | | | SPARE | | 20/1 | 11 | | | | 12 | | | SPACE | | | |
| | | | SPARE | | 20/1 | 13 | | | | 14 | | | SPACE | | | |
| | | | SPARE | | 20/1 | 15 | | | | 16 | | | SPACE | | | |
| | | | SPARE | | 20/1 | 17 | | | | 18 | | | SPACE | | | |
| | | | SPARE | | 20/1 | 19 | | | | 20 | | | SPACE | | | |
| | | | SPARE | | 20/1 | 21 | | | | 22 | | | SPACE | | | |
| | | | SPACE | | | 23 | | | | 24 | | | SPACE | | | |
| | | | SPACE | | | 25 | | | | 26 | | | SPACE | | | |
| | | | SPACE | | | 27 | | | | 28 | | | SPACE | | | |
| | | | SPACE | | | 29 | | | | 30 | | | SPACE | | | |
| | | | SPACE | | | 31 | | | | 32 | | | SPACE | | | |
| | | | SPACE | | | 33 | | | | 34 | | | SPACE | | | |
| | | | SPACE | | | 35 | | | | 36 | | | SPACE | | | |
| | | | SPACE | | | 37 | | | | 38 | 70/3 | 3–6 | DISHMACHINE | 42963 | E250 | |
| | | | SPACE | | | 39 | | | | 40 | – | +8G | – | – | | |
| | | | SPACE | | | 41 | | | | 42 | – | 3/4"C | – | – | | |
| | | TOTAL LOAD ❶ 100% = | | 44413VA | | TOTAL LOAD ❶ 100% = | | | | 53A | | | TOTAL LOAD ❶ 125% = | 67A | | |

## NEW KITCHEN PANEL

**PANEL LK** — 225A MLO, 208Y/120V, 3ϕ, 4 WIRE — AVAILABLE FAULT: <10,000A — SCCR & AIC: 10,000A — MOUNTING: RECESSED — STAINLESS STEEL COVER

| NOTES | EQUIP. NO. | LOAD | DESCRIPTION | WIRE | CB | CKT | A | B | C | CKT | CB | WIRE | DESCRIPTION | LOAD | EQUIP. NO. | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E10 | 640 | 3 REC – RR/STOR/CUST & BELL | 3–12 | 20/1 | 1 | | | | 2 | 20/1 | 3–12 | 2 REC – KITCHEN | 360 | E10 | |
| | E110 | 1920 | WASHING MACHINE | 3–12 | 20/1 | 3 | | | | 4 | 20/1 | 3–12 | 1 REC – KITCHEN | 180 | E10 | |
| | E110A | 5000 | DRYER | 2–10 | 30/2GFI | 5 | | | | 6 | 20/1 | 3–12 | 2 REC – KITCHEN | 360 | E11 | |
| | | – | – | +10N+10G | 3/4"C | 7 | | | | 8 | 20/2 | 2–10 | HEATED CABINET | 3224 | E187 | |
| | | 540 | 3 REC – OFFICE | 3–12 | 20/1 | 9 | | | | 10 | 3/4"C | +10G | – | – | | |
| | E10 | 360 | 2 REC – KITCHEN | 3–12 | 20/1 | 11 | | | | 12 | 20/2 | 2–10 | HEATED CABINET | 3224 | E187 | |
| | E10 | 360 | 2 REC – SERVING LINE | 3–12 | 20/1 | 13 | | | | 14 | 3/4"C | +10G | – | – | | |
| | E10 | 360 | 2 REC – SERVING LINE | 3–12 | 20/1 | 15 | | | | 16 | 20/3 | 3–12 | DISPOSER | 3960 | E123 | |
| | | 1000 | 2 EDF – CAFETERIA | 3–12 | 20/1 | 17 | | | | 18 | – | +12G | ( 3 HP ) | – | | |
| | E615 | 500 | 2 MENU BOARDS | 3–12 | 20/1 | 19 | | | | 20 | – | 3/4"C | – | – | | |
| | E209 | 960 | MILK COOLER | 3–12 | 20/1 | 21 | | | | 22 | 20/1 | 3–12 | AIR SCREEN | 612 | E101 | |
| | E201A | 5824 | HOT FOOD COUNTER | 2–8 | 35/2 | 23 | | | | 24 | 15/1 | 3–12 | EF–CF ( 1/6HP ) | 528 | | |
| | | – | – | +10G | 3/4"C | 25 | | | | 26 | 15/1 | 3–12 | EF–14 ( 1/6HP ) | 528 | | |
| | E201B | 1920 | COLD FOOD COUNTER | 3–12 | 20/1 | 27 | | | | 28 | 20/1 | | SPARE | | | |
| | E214 | 360 | CASH REGISTERS | 3–12 | 20/1 | 29 | | | | 30 | 20/1 | | SPARE | | | |
| | E201B | 1920 | COLD FOOD COUNTER | 3–12 | 20/1 | 31 | | | | 32 | 20/1 | | SPARE | | | |
| | E201A | 5824 | HOT FOOD COUNTER | 2–8 | 35/2 | 33 | | | | 34 | 20/1 | | SPARE | | | |
| | | – | – | +10G | 3/4"C | 35 | | | | 36 | 20/1 | | SPARE | | | |
| | E209 | 960 | MILK COOLER | 3–12 | 20/1 | 37 | | | | 38 | 20/1 | | SPARE | | | |
| | | 360 | 2 REC – CAFETERIA | 3–12 | 20/1 | 39 | | | | 40 | 20/1 | | SPARE | | | |
| | | | SPARE | | 20/1 | 41 | | | | 42 | 20/1 | | SPARE | | | |
| | E153/E153M | 250 | HOOD LTS & SENSOR | 3–12 | 20/1 | 43 | | | | 44 | 20/1GFI | 3–12 | DROP CORD | 180 | E129 | |
| | E153/E153M | 250 | HOOD LTS & SENSOR | 3–12 | 20/1 | 45 | | | | 46 | 20/1GFI | 3–12 | DROP CORD | 180 | E129 | |
| 8 | E161 | 720 | CONVECTION OVEN | 3–12 | 20/1GFI | 47 | | | | 48 | 20/1GFI | 3–12 | MOBILE PROOFER | 1800 | E139A | |
| 8 | E161 | 720 | CONVECTION OVEN | 3–12 | 20/1GFI | 49 | | | | 50 | 20/1GFI | 3–12 | 20QT MIXER | 960 | E125 | |
| 8 | E161 | 720 | CONVECTION OVEN | 3–12 | 20/1GFI | 51 | | | | 52 | 20/1GFI | 3–12 | DROP CORD | 180 | E129 | |
| 8 | E161 | 720 | CONVECTION OVEN | 3–12 | 20/1GFI | 53 | | | | 54 | 20/1GFI | 3–12 | DROP CORD | 180 | E129 | |
| 8 | E163 | 600 | TILT BRAISING PAN | 3–12 | 20/1 | 55 | | | | 56 | | | SPACE | | | |
| 8 | E172 | 3120 | COMBI OVEN | 2–12 | 20/2 | 57 | | | | 58 | 20/1 | 3–12 | EXISTING CIRCUIT | 500 | | 5 |
| | | – | – | +12G | 3/4"C | 59 | | | | 60 | 20/1 | 3–12 | EXISTING CIRCUIT | 500 | | 5 |
| | E172 | 3120 | COMBI OVEN | 2–12 | 20/2 | 61 | | | | 62 | 15/2 | 2–12 | EXISTING CIRCUIT | 1000 | | 5 |
| | | – | – | +12G | 3/4"C | 63 | | | | 64 | – | +12N+12G | – | – | | |
| | | | SPACE | | | 65 | | | | 66 | 20/2 | 2–12 | EXISTING CIRCUIT | 1000 | | 5 |
| | | | SPACE | | | 67 | | | | 68 | – | +12N+12G | – | – | | |
| 9 | | 0 | TEMP LOAD CENTER | 2–6 | 50/2 | 69 | | | | 70 | 30/2 | 2–10 | EXISTING CIRCUIT | 3000 | | 5 |
| | | – | – | +6N+8G | 1"C | 71 | | | | 72 | – | +10N+10G | – | – | | |
| | | TOTAL LOAD ❶ 100% = | | 61484VA | | TOTAL LOAD ❶ 100% = | | | | 171A | | | TOTAL LOAD ❶ 65% = | 111A | | |

## KITCHEN HOOD CONTACTOR SCHEDULE

**HOOD 1**

| POLE | DESCRIPTION | NORMAL CKT | EM CKT | CONTROL ZONE | EQUIPMENT LOCATION | CONTACTOR TYPE |
|---|---|---|---|---|---|---|
| CK1–1 | CONVECTION OVEN | LK–47 | – | HOOD 1 | KITCHEN | ELECTRICALLY HELD – NO |
| CK1–2 | CONVECTION OVEN | LK–49 | – | HOOD 1 | KITCHEN | ELECTRICALLY HELD – NO |
| CK1–3 | CONVECTION OVEN | LK–51 | – | HOOD 1 | KITCHEN | ELECTRICALLY HELD – NO |
| CK1–4 | CONVECTION OVEN | LK–53 | – | HOOD 1 | KITCHEN | ELECTRICALLY HELD – NO |
| CK1–5 | SPARE | | | | | ELECTRICALLY HELD – NO |
| CK1–6 | SPARE | | | | | ELECTRICALLY HELD – NO |
| CK1–7 | SPARE | | | | | ELECTRICALLY HELD – NO |
| CK1–8 | SPARE | | | | | ELECTRICALLY HELD – NO |

**HOOD 2**

| POLE | DESCRIPTION | NORMAL CKT | EM CKT | CONTROL ZONE | EQUIPMENT LOCATION | CONTACTOR TYPE |
|---|---|---|---|---|---|---|
| CK2–1 | TILT BRAISING PAN | LK–55 | – | HOOD 2 | KITCHEN | ELECTRICALLY HELD – NO |
| CK2–2 | COMBI–OVEN | LK–57/59 | – | HOOD 2 | KITCHEN | ELECTRICALLY HELD – NO |
| CK2–3 | ( 2–POLE ) | – | – | – | – | ELECTRICALLY HELD – NO |
| CK2–4 | COMBI–OVEN | LK–61/63 | – | HOOD 2 | KITCHEN | ELECTRICALLY HELD – NO |
| CK2–5 | ( 2–POLE ) | – | – | – | – | ELECTRICALLY HELD – NO |
| CK2–6 | SPARE | | | | | ELECTRICALLY HELD – NO |
| CK2–7 | SPARE | | | | | ELECTRICALLY HELD – NO |
| CK2–8 | SPARE | | | | | ELECTRICALLY HELD – NO |

1. REFERENCE FLOOR PLANS FOR EQUIPMENT LOCATIONS AND ADDITIONAL INFORMATION.
2. EACH KITCHEN HOOD CONTACTOR HALL BE CONTROLLED ON/OFF BY THE APPROPRIATE HOOD ANSUL SYSTEM. WHEN ACTIVATED ALL POWER WITHIN THE COOKING HOOD SHALL BE DE–ENERGIZED.

## EXIST SQUARE D QED SWITCHBOARD — CENTRAL PLANT

**(E)SWBD MDP** — 2000A MCB, 480Y/277V, 3ϕ, 4 WIRE — AVAILABLE FAULT: 37,000A — SCCR & AIC: 100,000A — FREE STANDING

| NOTES | CIRCUIT | DESCRIPTION | CB | FEEDER SIZE | AMPS |
|---|---|---|---|---|---|
| 4 | 1 | NEW PANEL HK | 225/3 | 4–4/0 +4G, 2.5"C | 53A |
| | 2 | EXIST PANEL HE | 400/3 | EXIST FEEDER | |
| | 3 | EXIST DISTRIBUTION PANEL DA | 800/3 | EXIST FEEDER | |
| | 4 | EXIST DISTRIBUTION PANEL DB | 1200/3 | EXIST FEEDER | |
| | 5 | EXIST DISTRIBUTION PANEL R | 800/3 | EXIST FEEDER | |
| 2 | 6 | EXIST PANEL HK | 400/3 | | |
| | 7 | EXIST 180KVAR CAPACITOR | 400/3 | EXIST FEEDER | |
| | 8 | EXIST SPD | 60/3 | EXIST FEEDER | |
| | | | | TOTAL LOAD ❶ 100% = | 53A |
| | | | | TOTAL LOAD ❶ 125% = | 67A |

1. THE EXISTING 2000A FEEDER IS SUFFICIENT FOR THE REVISED LOAD.
2. UPDATE PANEL SCHEDULE AND PROVIDE NEW LAMACOID LABELS TO MATCH REVISED EQUIPMENT DESCRIPTION.

## EXIST SQURE D I-LINE DIST PANELBOARD — CENTRAL PLANT

**(E)DIST. PANEL R** — 800A MLO, 480Y/277V, 3ϕ, 4 WIRE — AVAILABLE FAULT: 37,000A — SCCR & AIC: 65,000A — MOUNTING: SURFACE

| NOTES | CIRCUIT | DESCRIPTION | CB | FEEDER SIZE | AMPS |
|---|---|---|---|---|---|
| | 1 | EXIST CHILLER CH–1 | 250/3 | EXIST FEEDER | 100A |
| | 2 | EXIST SPARE | 200/3 | – | 0A |
| | 3 | EXIST CHILLER CH–2 | 250/3 | EXIST FEEDER | 100A |
| | 4 | EXIST SPARE | 200/3 | – | 0A |
| | 5 | EXIST ATS ASKL | 70/3 | EXIST FEEDER | 38A |
| 4 | 6 | TEMP KITCHEN PANEL LTK | 70/3 | 3–6 +8G, 3/4"C | 40A |
| | | | | TOTAL LOAD ❶ 100% = | 238A |
| | | | | TOTAL LOAD ❶ 125% = | 298A |

1. THE EXISTING 800A FEEDER IS SUFFICIENT FOR THE REVISED LOAD.
2. UPDATE PANEL SCHEDULE AND PROVIDE NEW LAMACOID LABELS TO MATCH REVISED EQUIPMENT DESCRIPTION.

## EXIST EM STANDBY PANELBOARD — CENTRAL PLANT

**(E)PANEL SKL** — 150A MCB, 208Y/120V, 3ϕ, 4 WIRE — AVAILABLE FAULT: <10,000A — SCCR & AIC: 10,000A — MOUNTING: SURFACE

| NOTES | EQUIP. NO. | LOAD | DESCRIPTION | WIRE | CB | CKT | A | B | C | CKT | CB | WIRE | DESCRIPTION | LOAD | EQUIP. NO. | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | 10000 | PANEL SLE | EXIST | 60/3 | 1 | | | | 2 | 40/3 | | REFRIGERATION SYSTEM | | | 2 |
| | | – | – | – | – | 3 | | | | 4 | – | – | – | – | | |
| | | – | – | – | – | 5 | | | | 6 | – | – | – | – | | |
| 2,3 | E103C | 3328 | FREEZER COIL | 2–10 | 20/2 | 7 | | | | 8 | 20/1 | EXIST | HEATER LIGHTS | 1000 | | |
| | | – | – | +10G | – | 9 | | | | 10 | 20/1 | | DOOR HEATER/LTS COOLER | | | 2 |
| 2 | | | COOLER COIL BLOWER | | 20/2 | 11 | | | | 12 | 20/1 | | DOOR HEATER/LTS FREEZER | | | 2 |
| | | – | – | – | – | 13 | | | | 14 | 20/1 | | EXIST SPARE | | | |
| 2 | | | REFRIGERATION SYSTEM | | 60/3 | 15 | | | | 16 | 20/1 | EXIST | GEN BATTERY CHARGER | 500 | | |
| | | – | – | – | – | 17 | | | | 18 | 20/1 | EXIST | GENERATOR POWER | 500 | | |
| | | – | – | – | – | 19 | | | | 20 | 20/1 | | EXIST SPARE | | | |
| 3 | E102B | 600 | COOLER TEMP. ALARM | 3–12 | 20/1 | 21 | | | | 22 | 20/1 | 3–12 | COOLER COIL | 1200 | E103D | 3 |
| 3 | E102C | 600 | COOLER PRESSURE PORT | 3–12 | 20/1 | 23 | | | | 24 | 20/1 | 3–12 | FREEZER TEMP. ALARM | 600 | E102B | 3 |
| 3 | E102E | 120 | PANIC ALARM BUTTONS | 3–12 | 20/1 | 25 | | | | 26 | 20/1 | 3–12 | FREEZER PRESSURE PORT | 600 | E102C | 3 |
| 4 | E188 | 864 | REFRIGERATOR | 3–12 | 20/1 | 27 | | | | 28 | 35/3 | 3–8 | REFRIGERATION SYSTEM | 7344 | E103 | 4 |
| 4 | E188 | 864 | REFRIGERATOR | 3–12 | 20/1 | 29 | | | | 30 | – | +10G | – | – | | |
| 4 | E109 | 1428 | ICE MACHINE | 3–12 | 20/1 | 31 | | | | 32 | – | 3/4"C | – | – | | |
| 4 | E151 | 240 | HOOD ANSUL SYSTEMS | 3–12 | 20/1 | 33 | | | | 34 | 20/1EGF | 3–12 | COOLER DOOR HEATER/LTS | 600 | E102A | 4 |
| | | | SPACE | | | 35 | | | | 36 | 20/1EGF | 3–12 | FREEZER DOOR HEATER/LTS | 600 | E102A | 4 |
| | | | SPACE | | | 37 | | | | 38 | 20/1EGF | 3–12 | FREEZER DRAIN LINE HEATER | 600 | E103F | 4 |
| | | | SPACE | | | 39 | | | | 40 | | | SPACE | | | |
| | | | SPACE | | | 41 | | | | 42 | | | SPACE | | | |
| | | – | MAIN CIRCUIT BREAKER | – | – | 43 | | | | 44 | | | SPACE | | | |
| | | – | – | – | – | 45 | | | | 46 | | | SPACE | | | |
| | | – | – | – | – | 47 | | | | 48 | | | SPACE | | | |
| | | – | – | – | – | 49 | | | | 50 | | | SPACE | | | |
| | | – | – | – | – | 51 | | | | 52 | | | SPACE | | | |
| | | – | – | – | – | 53 | | | | 54 | | | SPACE | | | |
| | | TOTAL LOAD ❶ 100% = | | 31588VA | | TOTAL LOAD ❶ 100% = | | | | 88A | | | TOTAL LOAD ❶ 125% = | 110A | | |

1. THE EXISTING 150A FEEDER IS SUFFICIENT FOR THE REVISED LOAD.
2. UPDATE PANEL SCHEDULE TO MATCH REVISED EQUIPMENT DESCRIPTION.

GENERAL PANEL REQUIREMENTS:
A. REF ELECTRICAL FLOOR PLANS FOR PANEL LOCATIONS.
B. FIELD VERIFY EXISTING CIRCUITS PRIOR TO BEGINNING WORK.
C. ALL OUTAGES SHALL BE SCHEDULED AND CONFIRMED IN WRITING WITH THE OWNER A MINIMUM OF TWO WEEKS PRIOR TO ANY OUTAGE.
D. AT THE END OF THE PROJECT PROVIDE A NEW TYPEWRITTEN PANEL SCHEDULE USING BUILDING ROOM NUMBERS FOR ALL PANELS WITH CIRCUITS ADDED, REMOVED, OR MODIFIED AS PART OF THE PROJECT.

PANEL NOTES:
1. REVISE/REWORK WIRING/CONDUIT AS REQUIRED TO ADD/REMOVE DEVICES FROM EXISTING CIRCUIT.
2. EXISTING CIRCUIT TO BE DEMO.
3. REUSE EXISTING SPARE CB AND WIRE NEW CIRCUIT.
4. PROVIDE NEW CB & WIRE NEW CIRCUIT.
5. IDENTIFY ANY CIRCUITS OR PARTIAL CIRCUITS THAT EXTEND BEYOND THE AREA OF RENOVATION. PROVIDE TEMPORARY FEED TO MAINTAIN ALL CIRCUITS SERVING ELEMENTS/SPACES NOT TO BE REMOVED DURING CONSTRUCTION. RECONNECT EXISTING CIRCUITS/DEVICES TO REMAIN TO TEMPORARY KITCHEN PANEL ONCE AVAILABLE USING CB(S) PROVIDED. ALL PARTIAL CIRCUITS SHALL REMAIN AND REMAIN ACTIVE BOTH DURING AND AFTER CONSTRUCTION.
6. KITCHEN LIGHTS TO BE DUAL ZONES WIRED THROUGH LIGHTING CONTACTORS AND CONTROLLED ON/OFF BY THE BAS AND LOCAL LIGHTING SWITCHES.
7. EXTERIOR LIGHTS TO BE WIRED THROUGH LIGHTING CONTACTOR AND CONTROLLED ON/OFF BY THE BAS.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL SCHEMATIC

a-E.400


STANTON ENGINEERING GROUP
INFORMATION–EXCELLENCE (713) 300–6060
TECHNOLOGY FIRM REG NO.F–2833/2780


©2025 ALL RIGHTS RESERVED


12800 W. SAM HOUSTON PARKWAY S., SUITE 125, HOUSTON, TX 77042

## PLUMBING SYMBOLS LEGEND

| | | | |
|---|---|---|---|
| ——————— | SANITARY WASTE BELOW SLAB | SAN. | SANITARY |
| ——— | SANITARY WASTE ABOVE SLAB | CW | DOMESTIC COLD WATER |
| —— V. —— | VENT PIPING ABOVE SLAB | HW | DOMESTIC HOT WATER |
| — — — — | VENT PIPING | WC | WATER CLOSET |
| —— G —— | GAS PIPING, 4-8oz | UR | URINAL |
| —— G5 —— | GAS PIPING, 5LB | LAV | LAVATORY |
| —·—·— | DOMESTIC COLD WATER PIPING | SK | SINK |
| —·—·—·— | DOMESTIC HOT WATER PIPING | EDF | ELECTRIC DRINKING FOUNTAIN |
| —— D —— | DRAIN/RELIEF VENT PIPING | WH | WALL HYDRANT |
| —⋈— | STOP VALVE | HB | HOSEBIBB |
| 2CO | DOUBLE SAN. CLEANOUT (2-WAY) | CP | HOT WATER CIRCULATOR PUMP |
| CO | SANITARY SEWER CLEANOUT | FD | FLOOR DRAIN |
| WCO | WALL CLEANOUT | FSINK | FLOOR SINK |
| EXIST. | EXISTING | | |
| (R) | REMOVE (DEMOLISH) | | |
| (D) | DEMOLISH (REMOVE) | | |
| (E) | EXISTING – NO WORK | | |

## PLUMBING FIXTURE NOTES

1. ALL FIXTURES SHALL MEET WATER CONSERVATION PERFORMANCE STANDARDS MANDATED BY SENATE BILL 587. ALL FIXTURES SHALL HAVE FLOW RESTRICTION DEVICES (DRINKING FOUNTAINS SHALL BE SELF-CLOSING) TO COMPLY WITH THESE REQUIREMENTS.
2. ALL FIXTURES SHALL HAVE CONTROLS REQUIRING OPERATING FORCE NO GREATER THAN FIVE (5) POUNDS.
3. FOR LAVATORIES AND SINKS, ALL FAUCETS SHALL BE NO–LEAD SOLID BRASS, MEETING ALL REQUIREMENTS OF ANSI/NSF 61, SECTION 9 AND CERTIFIED AS SUCH. ALSO, INSTALL SYMMONS 7–210 MIXING VALVE ON HOT WATER SUPPLY SIDE OF ALL FAUCETS UNLESS HIGH TEMPERATURE LIMIT IS PROVIDED WITH FAUCET. MAXIMUM WATER TEMPERATURE FOR ALL FAUCETS THAT DELIVER HOT OR TEPID WATER SHALL BE 110°F. ALL METERING FAUCETS SHALL HAVE A MINIMUM TEN (10) SECONDS OF WATER FLOW, AND, INSTALL TRUEBRO HANDI LAV–GUARD VANDAL–PROOF INSULATION KITS OVER P–TRAP, SUPPLIES, STOPS AND ALL SHARP EDGES FOR ALL SINKS AND LAVATORIES (TRAP WRAP FROM BROCAR OR PROWRAP FROM McGUIRE SHALL BE ACCEPTABLE).
4. ALL PLUMBING FIXTURES REFERENCED AS "ADA", "TAS" OR "HANDICAP COMPLIANT" SHALL MEET ALL REQUIREMENTS OF THE ADA AND THE TEXAS ACCESSIBILITY STANDARDS. IT SHALL BE THE PLUMBING CONTRACTORS RESPONSIBILITY TO MEET THESE REQUIREMENTS.
5. IN MANY CASES, FIXTURES WITH THE SAME PLUMBING DESIGNATION HAVE DIFFERENT INSTALLATION HEIGHTS – REFERENCE ARCHITECTURAL DRAWINGS FOR ALL INSTALLATION HEIGHTS AND HANDICAP FIXTURE DESIGNATIONS. FIXTURES DESIGNATED AS ADULT HANDICAP SHALL MEET ALL REQUIREMENTS OF THE ADA. FIXTURES DESIGNATED AS CHILD HANDICAP SHALL MEET ALL REQUIREMENTS OF THE TEXAS ACCESSIBILITY STANDARDS FOR THE APPROPRIATE CHILDREN'S AGE GROUP (REF. ARCH. DWGS. AND SPECIFICATIONS).

## PLUMBING MATERIALS

SANITARY WASTE AND VENT

BELOW SLAB/GRADE: SCHEDULE 40, DWV PVC

ABOVE SLAB: STANDARD WEIGHT, CAST IRON, NO–HUB PIPING.

STORM DRAIN PIPING

BELOW SLAB/GRADE: SCHEDULE 40, DWV PVC

ABOVE SLAB, 8" AND UNDER: STANDARD WEIGHT, CAST IRON, NO–HUB PIPING.

ABOVE SLAB, 10" AND ABOVE: SERVICE WEIGHT, CAST IRON, BELL & SPIGOT.

NATURAL GAS

BELOW GRADE (OUTSIDE): YELLOW POLYETHYLENE PIPE WITH COATED STEEL RISER AND TRACER WIRE.

ABOVE SLAB: SCHEDULE 40 BLACK STEEL. PIPING 2.5" AND LARGER SHALL BE WELDED. PIPING 2" AND SMALLER SHALL HAVE SCREWED FITTINGS.

DOMESTIC WATER

INTERIOR: TYPE L COPPER WITH SOLDER TYPE WROUGHT COPPER FITTINGS, MADE UP WITH LEAD–FREE SOLDER.

EXTERIOR: TYPE K COPPER WITH SWEAT FITTINGS AND LEAD–FREE SOLDER. BEYOND 5 FEET FROM BUILDING, SCHEDULE 40 PVC.

## FIRE SPRINKLER SYSTEM NOTES


1. THE EXISTING FIRE SPRINKLER SYSTEM SHALL BE MODIFIED AND/OR EXPANDED TO COVER THE AREA OF RENOVATION IN ENTIRETY. ALL NEW AND REVISED PIPING SHALL BE ENGINEERED AND INSTALLED BY A LICENSED FIRE SPRINKLER CONTRACTOR.
2. REFERENCE THE SPECIFICATIONS, DIVISION 21, FOR MORE INFORMATION.

## GENERAL PLUMBING NOTES

1. SEE ARCHITECTURAL DRAWINGS AND SPECIFICATIONS FOR ADDITIONAL WORK DESCRIPTION. SEE THIS SHEET (P4.00) FOR PLUMBING SYMBOLS LEGEND.
2. COORDINATE PLUMBING SYSTEMS INSTALLATION WITH ARCHITECTURAL, STRUCTURAL, HVAC SYSTEMS, ELECTRICAL SYSTEMS, CONDUITS, ETC.... OFFSET PIPING AS REQUIRED TO PROVIDE A FUNCTIONING SYSTEM WITH ADEQUATE SPACE FOR SERVICING AND REPAIRS.
3. MAKE CONNECTIONS OF NEW PIPE SYSTEMS IN TO EXISTING PIPE SYSTEMS WITH THREADED OR SWEAT JOINTS. PROVIDE ELECTROLYSIS ISOLATING UNIONS AT CONNECTION OF DISSIMILAR MATERIALS. REFERENCE THE SPECIFICATIONS.
4. SITE SERVICES ARE SHOWN FOR REFERENCE ONLY. PLUMBING CONTRACTOR SHALL REFERENCE CIVIL DRAWINGS, INCLUDING LOCATIONS OF SERVICES, SIZES OF PIPES, FLOWLINE ELEVATIONS, ETC..
5. DO NOT INSTALL PLUMBING PIPING OVER ANY ELECTRICAL EQUIPMENT. REFERENCE ELECTRICAL DRAWINGS FOR LOCATIONS OF ELECTRICAL EQUIPMENT AND COORDINATE WITH ELECTRICAL SUBCONTRACTORS ACCORDINGLY. SEE DETAIL 2/MEP1. THIS INCLUDES FIRE SPRINKLER PIPING.
6. ALL PIPES THROUGH WALLS OR FLOORS SHALL BE SLEEVED AND SEALED PER DETAIL 5/P4.02. FIRE CAULK WHERE REQUIRED. THIS INCLUDES ALL WALLS, INTERIOR AND EXTERIOR. THIS INCLUDES FIRE SPRINKLER PIPING.
7. ALL CLEANOUTS SHALL BE CONNECTED TO SANITARY LINES USING WYES AND/OR LONG RADIUS ELLS. SANITARY TEES ARE NOT ACCEPTABLE. 2" MINIMUM SIZE. ALL WALL CLEAN OUTS IN VERTICAL RISERS, OR BANKS OF FIXTURES SHALL BE INSTALLED 4" ABOVE THE FLOOD RIM LEVEL OF THE LOWEST CONNECTED FIXTURE AND A MINIMUM OF 24" AFF.
8. ALL WASTE AND VENT PIPING BELOW SLAB SHALL BE 2" MINIMUM.
9. LOCATE PLUMBING VENTS THROUGH ROOF NOT NEARER THAN SIX (6) FEET AWAY FROM EDGE OF BUILDING AND TEN (10) FEET AWAY FROM ANY FRESH AIR INTAKES. OFFSET VENT PIPING, AS REQUIRED, IN CEILING SPACE BETWEEN CEILING AND ROOF TO MEET THESE REQUIREMENTS. SEE DETAIL 3/P4.02.
10. ALL DOMESTIC WATER PIPING (CW, HW AND HWR) SHALL BE INSULATED PER THE WRITTEN SPECIFICATIONS.
11. TOP OF FLOOR DRAINS IN MECHANICAL, AHU AND BOILER ROOMS SHALL BE SET 1–1/2" BELOW FINISHED FLOOR SURFACE. CONCRETE FLOOR SHALL BE SLOPED TO DRAIN, REFERENCE ARCHITECTURAL DRAWINGS. IN ALL OTHER LOCATIONS, FLOOR DRAINS SHALL BE SET FLUSH WITH FINISHED FLOOR, TAKING INTO ACCOUNT ANY FLOOR SLOPE OR FLOOR FINISH (TILE, TERRAZZO, ETC.) AS SHOWN ON ARCHITECTURAL DRAWINGS.
12. PROVIDE AN ISOLATING VALVE AT EACH WATER TAP OFF HOT AND COLD WATER MAINS TO ALLOW FOR SERVICING. VALVE SHALL BE BALL VALVE IF PIPE SIZE IS 2" OR LESS AND GATE VALVE OR BUTTERFLY VALVE IF LARGER THAN 2". SEE WRITTEN SPECIFICATIONS. VALVES SHALL BE EASILY ACCESSIBLE: PROVIDE 18" X 18", FIRE–RATED, STAINLESS STEEL ACCESS PANELS WITH HINGED, CYLINDER LOCK DOORS WHERE VALVES ARE INSTALLED ABOVE INACCESSIBLE CEILINGS OR IN WALL CHASES (MIFAB MODEL MPFR–SS–C). BALL VALVES AND BUTTERFLY VALVES INSTALLED ABOVE CEILINGS SHALL BE INSTALLED SUCH THAT HANDLE IS ON BOTTOM OF PIPE. ISOLATING WATER VALVES ABOVE CEILINGS SHALL BE INSTALLED NO MORE THAN 24" ABOVE CEILING. VALVES ABOVE INACCESSIBLE CEILINGS SHALL BE INSTALLED WITHIN REASONABLE REACH OF CEILING MOUNTED ACCESS PANEL.
13. WATER HAMMER ARRESTERS SHALL BE INSTALLED IN ADDITION TO AIR CHAMBERS PER THE RISER DIAGRAMS. SEE SPECIFICATIONS.
14. MECHANICALLY CLEAN ALL WASTE LINES WITH ROTARY MACHINE TO PROVE FREE FLOWING, SEE SPECIFICATIONS.
15. PROVIDE VENTED SLEEVE (2 PIPE SIZES LARGER THAN GAS PIPE UNLESS NOTED OTHERWISE) FOR ALL GAS PIPING IN GROUND BELOW PAVING OR SIDEWALKS AND INSIDE BUILDING IN WALLS AND IN UNVENTILATED CEILING SPACES, SEE SPECIFICATIONS.
16. GAS PIPING SHALL BE 1/2" MINIMUM. TAP GAS PIPING ON TOP OR SIDES ONLY. DO NOT INSTALL VALVES IN CEILING PLENUM OR IN ANY INACCESSIBLE LOCATION. ALL GAS VALVES SHALL BE EASILY ACCESSIBLE. REFER TO DETAIL 9/P4.01 FOR TYPICAL GAS CONNECTION INSTALLATION. REFER TO DETAIL 8/P4.02 FOR TYPICAL PRV INSTALLATION.
17. CENTER WALL HYDRANTS IN BRICK PATTERN OF EXTERIOR WALLS, REFERENCE THE ARCHITECTURAL DRAWINGS AND SPECIFICATIONS.
18. ALL REFRIGERATORS WITH ICE MAKERS, COMMERCIAL TYPE COFFEE MAKERS, ICE MAKERS, COFFEE VENDING MACHINES AND OTHER ITEMS REQUIRED BY OTHERS THAT REQUIRE A WATER CONNECTION SHALL HAVE A CW VALVE BOX, "VBOX", INSTALLED TO ALLOW EASY ACCESS AND REMOVAL OF MACHINE. ALSO, INSTALL IN–LINE FILTER IN WATER CONNECTION.
19. REFER TO CIVIL DRAWINGS FOR SITE SANITARY, SITE STORM SEWER, FIRE SERVICE AND DOMESTIC WATER SERVICE. PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR ALL PIPING INSIDE BUILDING TO OUTSIDE LOCATIONS SHOWN ON PLUMBING DRAWINGS. PLUMBING CONTRACTOR SHALL INCLUDE COST OF FINAL TIE–INS TO SITE SERVICES.
20. PER THE DRAWINGS, ALL DRAINS (FLOOR DRAINS, FLOOR SINKS, HUB DRAINS, KITCHEN DRAINS, SHOWER DRAINS, ETC.) SHALL BE VENTED AND TRAP PRIMED – NO EXCEPTIONS. TRAP PRIMING SHALL BE ACCOMPLISHED USING WATER CLOSET FLUSH VALVE TRAP PRIMING DEVICES OR PROSET SYSTEMS TRAP GUARD SEWER GAS EMISSION PROTECTION, AS SHOWN ON DRAWINGS. REFERENCE PLUMBING FLOOR PLANS AND RISER DIAGRAMS.
21. ALL PIPING LOCATED ON ROOF (GAS PIPING) SHALL BE INSTALLED ON ROOF PIPE SUPPORTS PER DETAIL 10/P4.02, 6–FOOT ON CENTER. INSTALL ROOF PIPE JACK PER DETAIL 9/P4.02 FOR ALL PIPING THROUGH ROOF.
22. COORDINATE LOCATIONS OF ALL ROOF DRAINS AND OVERFLOW ROOF DRAINS WITH ARCHITECTURAL DRAWINGS.
23. FOR COMBINATION WASTE AND VENT SYSTEMS (WHERE APPLICABLE ON DRAWINGS), DRAIN P–TRAPS SHALL BE SIZE OF PIPE SHOWN ON DRAWINGS (I.E. TWO PIPE SIZES LARGER THAN DRAIN SIZE). FOR EXAMPLE, A 4" FLOOR DRAIN SHALL HAVE A 6" P–TRAP.
24. FOR ALL PLUMBING FIXTURES, IF COPPER PIPING IS STUBBED THROUGH WALL FOR DRAIN CONNECTION, INSTALL MARVEL FITTING AT DRAIN CONNECTION FOR EASE OF SERVICING AND REPAIRS. COPPER DRAIN PIPING WILL ONLY BE ALLOWED FOR DIRECT/STRAIGHT STUB–OUT OF FIXTURE DRAIN PIPING THROUGH WALL.
25. DO NOT INSTALL ANY PIPING BENEATH CVT OR VAV BOXES. THIS INCLUDES FIRE SPRINKLER PIPING.
26. WHERE UNDERGROUND VENT PIPE SIZE IS NOT NOTATED, VENT SHALL BE 2" DIAMETER.
27. WHERE UNDERGROUND SANITARY PIPE SIZE IS NOT NOTATED, REFER TO THE RISER DIAGRAMS FOR SIZE. NOT BELOW GRADE SANITARY PIPE SHALL BE SMALLER THAN 2". NO SANITARY LINE OR P–TRAP FOR A DRAIN/FIXTURE SHALL BE SMALLER THAN THE FIXTURE CONNECTION SIZE SHOWN ON THE DRAIN/FIXTURE SCHEDULE.
28. WHERE ABOVE GROUND VENT PIPE SIZE IS NOT NOTATED, REFER TO THE RISER DIAGRAMS FOR VENT SIZE.
29. WHERE CW/HW PIPING SIZE TO THE FIXTURE IS NOT SHOWN ON THE FLOOR PLAN, REFER TO THE RISER DIAGRAMS FOR CW/HW PIPE SIZE. NO PIPING TO FIXTURE SHALL BE SMALLER THAN THE FIXTURE CONNECTION SIZE SHOWN ON THE FIXTURE SCHEDULE.
30. TO INSTALL NEW PLUMBING SYSTEMS BELOW EXISTING CONCRETE SLABS, FIRST PLUMBING CONTRACTOR SHALL LAY OUT CUT. THEN, DEMOLITION CONTRACTOR SHALL SAW CUT SLAB TO CONTROL CRACKING AND REMOVE ALL CONCRETE. PLUMBING CONTRACTOR SHALL THEN EXCAVATE FILL TO PROPER SLOPE, INSTALL NEW PIPING SYSTEMS AS REQUIRED, THEN BACKFILL AND COMPACT TO PROPER DENSITY. THE CONCRETE CONTRACTOR SHALL THEN INSTALL NEW SIX (6) MIL POLYETHYLENE VAPOR BARRIER AND SEAL, INSTALL NEW REINFORCING STEEL AND WELD ON TO EXISTING, THEN RE–POUR CONCRETE TO NEW LEVEL. DO NOT CUT THROUGH GRADE BEAMS WITHOUT APPROVAL FROM THE STRUCTURAL ENGINEER. SEE ARCHITECTURAL AND STRUCTURAL DRAWINGS AND SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.
31. ALL ABANDONED FIXTURES, DRAINS AND PIPING (INCLUDING PIPING ABANDONED IN THE PAST) IN AREAS WHERE WORK IS BEING DONE SHALL BE COMPLETELY REMOVED FROM BUILDING (INCLUDING PIPING BELOW SLAB/GRADE – UNLESS SHOWN OTHERWISE ON DRAWINGS). EXISTING WATER PIPING SHALL BE CAPPED AT EXISTING WATER MAIN TAPS AND ALL ABANDONED PIPING REMOVED. ABANDONED VENT PIPING SHALL BE COMPLETELY REMOVED, INCLUDING EXISTING VTR'S NOT RE–USED. PATCH AS REQUIRED. ONLY ACTIVE PIPING, FIXTURES AND DRAINS SHALL REMAIN IN BUILDING WHERE WORK IS BEING DONE.

## GAS PRV SCHEDULE

| MARK | PRV–K |
|---|---|
| LOCATION | MECH. YARD |
| SERVES | KITCHEN |
| GAS LOAD | 585 CFH |
| DISTANCE FROM METER | 150 FT |
| DISTANCE TO LAST OUTLET | 200 FT |
| INLET (SIZE/PRESSURE) | 1" / 5 PSI |
| OUTLET (SIZE/PRESSURE) | 2" / 7–12 IN WC |




## 4 GAS PRESSURE REGULATOR DETAIL (PRV)

NO SCALE

NOTES:
1. GAS REGULATOR SHALL BE ANSI Z21.80 CERTIFIED FOR LINE PRESSURE REGULATION BETWEEN THE SERVICE REGULATOR AND CONNECTED EQUIPMENT.
2. ALL GAS REGULATORS WITH INLET PRESSURE ABOVE 2 PSI SHALL BE EQUIPPED WITH A FACTORY INSTALLED OVERPRESSURE PROTECTION DEVICE, AS PART OF THE ANSI Z21.80 CERTIFICATION.
3. GAS REGULATOR SHALL BE EQUIPPED WITH A VENT LIMITING DEVICE, SIZED IN ACCORDANCE WITH THE REGULATOR OUTLET PRESSURE.
4. ALL REGULATORS INSTALLED OUTDOORS SHALL BE RATED FOR OUTDOOR INSTALLATION.
5. BASIS OF DESIGN IN THE MAXITROL 325–L SERIES OF REGULATORS

## PLUMBING DRAINS, CLEANOUTS AND HYDRANTS


| MARK | MIN. CONNECTION SIZES (IN.) SAN | VENT | CW | HW | DESCRIPTION/SPECIFICATION FOR FIXTURE OR EQUIPMENT |
|---|---|---|---|---|---|
| FD | 4 | 2 | 1/2 | – | TOILET FLOOR DRAIN – TWO–PIECE CAST IRON WITH SEEPAGE FLANGE, REVERSIBLE CLAMPING COLLAR, 1/2" TRAP PRIMER TAP, 6" SQUARE, NICKEL BRONZE HSTRAINER AND SECURITY SCREWS JR SMITH MODEL 2005–03–K06PB–P050–U. |
| FD2 | 4 | 2 | 1/2 | – | EQUIPMENT FLOOR DRAIN – CAST IRON, MEDIUM DEPTH DRAIN WITH FLANGE, CLAMPING DEVICE, SEEPAGE OPENINGS, DUCTILE IRON TRUE–FIT SEDIMENT BUCKET WITH 12" STAINLESS STEEL RIM LESS GRATE, 1/2" TRAP PRIMER TAP ZURN MODEL ZS–540–U–P DRAIN SHALL BE DESIGNED SUCH THAT GRATE CANNOT BE INSTALLED WITHOUT SEDIMENT BUCKET. |
| FD3 | 4 | 2 | 1/2 | – | GRATED MECHANICAL ROOM FLOOR DRAIN – CAST IRON WITH FLANGE, SEEPAGE OPENINGS, 9" HEAVY–DUTY DUCTILE IRON GRATE WITH STAINLESS STEEL VENEER, CLAMPING DEVICE AND 1/2" TRAP PRIMER TAP ZURN MODEL ZS–550–C–P |
| FD4 | 4 | 2 | 1/2 | – | CANWASH FLOOR DRAIN – ALL GALVANIZED CAST IRON, MEDIUM DEPTH DRAIN WITH FLANGE, CLAMPING DEVICE, SEEPAGE OPENINGS, GALVANIZED SUR–SET SEDIMENT BUCKET WITH 12" GALVANIZED DUCTILE IRON RIM AND GRATE, 1/2" TRAP PRIMER TAP ZURN MODEL ZS–540–P–G–HD. DRAIN SHALL BE DESIGNED SUCH THAT GRATE CANNOT BE INSTALLED WITHOUT SEDIMENT BUCKET. |
| FD5 | 4 | 2 | 1/2 | – | KITCHEN FLOOR DRAINS SHALL BE SIMILAR EXCEPT WITH 7" SQUARE, BRONZE GRATE JR SMITH MODEL 2005–03–K07PB–P050–U PROVIDE 4" DIAMETER STAINLESS STEEL FUNNEL WHERE SHOWN ON DRAWINGS. REFERENCE KITCHEN CONNECTION SCHEDULE ON PLUMBING RENOVATION FLOOR PLAN SHEET. |
| FS KITCHEN FS | 4 | 2 | 1/2 | – | FLOOR SINK – CAST IRON, 8" DEEP SUMP, A.R.E. INTERIOR, INTEGRAL FLANGE FOR SUPPORT, CLAMPING DEVICE WHERE VAPOR BARRIER IS INSTALLED BETWEEN SLAB AND CONCRETE BEDDING FOR FLOOR, ALUMINUM SECONDARY DOME STRAINER AND 12" SQUARE HEAVY DUTY STAINLESS STEEL TRACTOR DUTY FRAME WITH 3/4–TRACTOR GRATE AND 1/2" TRAP PRIMER TAP JR SMITH MODEL 3150Y–04–C–13. |
| CO | VARIES | – | – | – | FLOOR CLEANOUT – ADJUSTABLE EXTENSION HOUSING, CAST IRON FERRULE WITH FULL–LINE–SIZE BRASS PLUG (UP TO 4"), 5" DIAMETER STAINLESS STEEL ACCESS COVER WITH VARIABLE–DEPTH FRAME AND TOP SECURING SCREW, ROUND FRAME AND TOP TO BE COMPATIBLE WITH FLOOR TYPE (REFERENCE ARCHITECTURAL DRAWINGS FOR FLOOR TYPES) ZURN MODEL ZS–1400–VP. PROVIDE CARPET FLANGE FOR CARPETED AREAS (CARPET MARKER SHALL NOT BE ACCEPTABLE) AND TERRAZZO RECESS FOR TERRAZZO FLOORS.<br>OUTDOOR CLEANOUT – SAME AS TYPE "CO" EXCEPT WITH HEAVY–DUTY NICKEL BRONZE TOP ZURN MODEL ZN–1400–HD–VP. INSTALL 18" X 18" X 6" THICK CONCRETE PAD AROUND EACH OUTDOOR CLEANOUT. |
| WCO | VARIES | – | – | – | WALL CLEANOUT – CAST IRON FERRULE WITH COUNTERSUNK HEAD (FULL–LINE–SIZE PVC PLUG UP TO 4") AND ROUND, COUNTERSUNK, NICKEL BRONZE ACCESS COVER SHALL BE 8" SQUARE, SURFACE MOUNT, FLUSH INSTALLATION, 16–GAUGE STAINLESS STEEL ACCESS DOOR WITH FLANGED FRAME AND VANDAL–PROOF OPTION MI–FAB MODEL UA–SS–VP. ACID WASTE CLEANOUT (AWCO) SHALL BE SAME EXCEPT ACID WASTE PIPING.<br>INSIDE CABINETWORK WHERE CLEANOUT IS NOT VISIBLE, ACCESS PANEL MAY BE ROUND STAINLESS STEEL TYPE WITH VANDAL–PROOF CENTER SCREW MI–FAB MODEL C1450–RD–3–6. |
| 2CO | 4 | – | – | – | DOUBLE CLEANOUTS – SAME AS OUTDOOR CLEANOUTS. INSTALLED FOR TWO–WAY RODDING. SINGLE CLEANOUT WITH 2–WAY FITTING IS NOT ACCEPTABLE, PROVIDE TWO SEPARATE CLEANOUTS. INSTALL 18" X 18" X 6" THICK CONCRETE PAD AROUND EACH OUTDOOR CLEANOUT. |
| HB | – | – | 3/4 | – | HOSEBIBB – 3/4" HOSE THREAD, INTEGRAL VACUUM BREAKER SPOUT, ROUGH CHROME FINISH WITH REMOVABLE KEYED HANDLE, WALL FLANGE CHICAGO MODEL 952. |
| WH | – | – | 3/4 | – | RESTROOM WALL HYDRANT – NARROW WALL, WARM CLIMATE TYPE HOSE BOX, QUARTER–TURN WHEEL HANDLE, ASSE APPROVED ANTI–SIPHON INTEGRAL VACUUM BREAKER AND DUAL CHECK VALVE, 3/4" STRAIGHT INLET HOSE CONNECTION, CAST STAINLESS STEEL HYDRANT BOX. FLUSH MOUNTED 16–GAUGE STAINLESS STEEL FRAME AND 180° DROP DOWN DOOR WITH KEY LOCK AND WALL CLAMP JR SMITH MODEL 5518 |
| WH2 | – | – | 3/4 | – | EXTERIOR WALL HYDRANT – NON–FREEZE HOSE BOX, QUARTER–TURN WHEEL HANDLE, ASSE APPROVED ANTI–SIPHON INTEGRAL VACUUM BREAKER AND DUAL CHECK VALVE, 3/4" STRAIGHT INLET HOSE CONNECTION, CAST STAINLESS STEEL HYDRANT BOX, FLUSH MOUNTED 16–GAUGE STAINLESS STEEL FRAME AND 180° DROP DOWN DOOR WITH KEY LOCK AND WALL CLAMP JR SMITH MODEL 5519 |
| WH3 | – | – | 3/4 | 3/4 | CANWASH WALL HYDRANT – NON–FREEZE HOSE BOX WITH STRAIGHT INLET CONNECTION, HOT AND COLD MIXING, REMOVABLE KEYED HANDLE, ASSE APPROVED ANTI–SIPHON INTEGRAL BACKFLOW PREVENTER WITH 3/4" HOSE CONNECTION, HEAVY DUTY BRASS CASING, POLISHED BRONZE HYDRANT BOX WITH HINGED COVER, "WATER" CAST ON COVER, DRIP LIP AND WALL CLAMP J.R. SMITH MODEL 5560–QT–WC–H–W–PB. |
| WBOX | 2 | 2 | 3/4 | 3/4 | CLOTHES WASHER DRAIN/VALVE BOX – HEAVY–GAUGE GALVANIZED STEEL CONSTRUCTION, RECESSED IN WALL VALVE AND DRAIN CONNECTIONS, WATTS DUO–CLOZ VALVE GUY GRAY MODEL WB–200. |

## PLUMBING FIXTURES AND EQUIPMENT

| MARK | MIN. CONNECTION SIZES (IN.) SAN | VENT | CW | HW | DESCRIPTION/SPECIFICATION |
|---|---|---|---|---|---|
| WC | 4 | 2 | 1 | – | WATER CLOSET – WALL MOUNTED, WHITE VITREOUS CHINA, SIPHON JET ACTION, 1.28 GPF, ELONGATED BOWL, TOP SPUD, ADA/TAS COMPLIANT, AMERICAN STANDARD AFWALL: SLOAN ROYAL 111–1.28 FLUSH VALVE WITH VANDAL–PROOF FREE–SPINNING TOP CAP, 1.28 GPF, VANDAL–PROOF STOP AND ADA/TAS COMPLIANT LEVER ACTUATOR WITH LEVER INSTALLED ON LEFT SIDE (FOR FIXTURES DESIGNATED AS "HANDICAP"). INSTALL LEVER ON "WIDE–SIDE" OF TOILET STALL); BEMIS 1655–SS/C EXTRA HEAVY DUTY, WHITE, OPEN FRONT SEAT LESS COVER WITH SELF–SUSTAINING, STAINLESS STEEL CHECK HINGE; AND, FLOOR MOUNTED CARRIER. |
| LV | 1–1/4 | 1–1/4 | 1/2 | 1/2 | LAVATORY GOOSENECK FAUCET – WALL HUNG, WHITE VITREOUS CHINA, FRONT OVERFLOW, SELF–DRAINING DECK AREA, 21" X 18", ADA/TAS COMPLIANT AMERICAN STANDARD LUCERNE 0355.012; DECK MOUNTED FAUCET, 4" CENTERS, FIXED, CHROME PLATED, 5.25" GOOSENECK SPOUT, PRESSURE COMPENSATING LAMINAR FLOW NON–AERATING 0.5 GPM OUTLET, 4" WRISTBLADE HANDLES, BUILDABLE COMPRESSION CARTRIDGES, CHICAGO 895–317GN2AE72ABCP; CHROME PLATED, 17–GAUGE CAST BRASS GRID DRAIN WITH WHEELCHAIR OFFSET FITTING; CHROME PLATED, 17–GAUGE CAST BRASS P–TRAP WITH CLEANOUT PLUG; CHROME PLATED, CAST BRASS, LOOSE KEY ANGLE STOP WITH CHROME PLATED COPPER RISER; TRUEBRO HANDI LAV–GUARD VANDAL–PROOF, WHITE INSULATION KITS; AND, FLOOR MOUNTED, CONCEALED ARMS CARRIER. PROVIDE ASSE 1070 LISTED MIXING VALVE, LEONARD 170–LF OR EQUAL (MUST BE CAPABLE OF ADJUSTMENT ABOVE 130°F). |
| LV2 | 1–1/4 | 1–1/4 | 1/2 | 1/2 | LAVATORY – WALL HUNG, WHITE VITREOUS CHINA, FRONT OVERFLOW, SELF–DRAINING DECK AREA, 21" X 18", ADA/TAS COMPLIANT AMERICAN STANDARD LUCERNE 0355.012; CHROME PLATED, ALL CAST BRASS CONSTRUCTION, ADA/TAS COMPLIANT, VANDAL–PROOF FAUCET WITH 4" WRIST BLADE HANDLES, COMPRESSION STYLE CARTRIDGES, CHROME DECK PLATE, VANDAL–PROOF AERATOR, COPPER SUPPLIES AND CERTIFIED FOR MEETING ALL REQUIREMENTS OF NSF 61 SECTION 9 CHICAGO MARATHON MODEL 802–E70–317ABCP; CHROME PLATED, 17–GAUGE CAST BRASS GRID DRAIN WITH WHEELCHAIR OFFSET FITTING; CHROME PLATED, 17–GAUGE CAST BRASS P–TRAP WITH CLEANOUT PLUG; CHROME PLATED, CAST BRASS, LOOSE KEY ANGLE STOP WITH CHROME PLATED COPPER RISER; TRUEBRO HANDI LAV–GUARD VANDAL–PROOF, WHITE INSULATION KITS; AND, FLOOR MOUNTED, CONCEALED ARMS CARRIER. PROVIDE ASSE 1070 LISTED MIXING VALVE, LEONARD 170–LF OR EQUAL (MUST BE CAPABLE OF ADJUSTMENT ABOVE 130°F). |
| EDF | 1–1/2 | 1–1/2 | 1/2 | – | BI–LEVEL ELECTRIC DRINKING FOUNTAINS WITH BOTTLE FILLER – WALL MOUNTED, ALL STAINLESS STEEL, ADA AND TAS COMPLIANT FOR ALL AGES, 8 GPH AT ARI STANDARDS, 2–STREAM ALL METAL BUBBLER FITTING WITH VANDAL–RESISTANT KIT AND FRONT PUSH BUTTON ACTUATION, PUSH BUTTON ACTIVATED BOTTLE FILLER WITH 1.1GPM FILL RATE AND ANTI–MICROBIAL COATING, INTEGRAL WATER FILTER, LEAD–FREE (CERTIFIED FOR MEETING ALL REQUIREMENTS OF NSF 61 SECTION 9), REFRIGERANT HFC–134a, MAINTENANCE ACCESS PANEL, HALSEY–TAYLOR MODEL HTHBHVR8BL; CHROME PLATED, 17–GAUGE CAST BRASS P–TRAP WITH CLEANOUT PLUG; CHROME PLATED, CAST BRASS, LOOSE KEY ANGLE STOP WITH CHROME PLATED COPPER RISER; FLOOR MOUNTED CHAIR CARRIER; AND, STAINLESS STEEL ADA APRON FOR LOCATIONS REQUIRED BY ADA OR TAS. |
| MB | 3 | 2 | 3/4 | 3/4 | MOP BASIN – 24" X 24" X 12" DEEP TERRAZZO, TWO (2) STAINLESS STEEL SPLASH CATCHER PANELS, 8" DROP FRONT WITH STAINLESS STEEL CAP, CAST BRASS DRAIN WITH STAINLESS STEEL STRAINER – STERN WILLIAMS HILOW MODEL HI–1800–BP; FAUCET SHALL BE POLISHED CHROME PLATED SERVICE SINK TYPE WITH VACUUM BREAKER, INTEGRAL SUPPLY CHECK STOPS, SPOUT WITH PAIL HOOK, HOSE END AND TOP BRACE CHICAGO MODEL 897–CCF (INSTALL BACKING/BRACING INSIDE WALL TO SUPPORT FAUCET AND TOP BRACE). |
| LP–1 | 3 | 2 | 3/4 | 3/4 | LAVATORY PUMP – FACTORY BUILT, LIFT PUMP FOR GRAY WATER WASTE, TOP ACCESS TO INTERNAL 1/6HP PUMP AND FLOAT SWITCH, 1.5" TOP AND SIDE INLETS, 1.5" TOP OUTLET, INTEGRAL CHECK VALVE AT BOTTOM INLET CONNECTIONS, 9FT POWER CORD WITH GROUNDED PLUG;<br>LIBERTY PUMPS MODEL 406 |

## KITCHEN PLUMBING CONNECTION SCHEDULE


| MARK | DESCRIPTION |
|---|---|
| P5 | 3/4" CW AND 3/4" HW – IN WALL, 36" AFF, TO MOP BASIN ("MB") FAUCET. REFERENCE PLUMBING FIXTURE SCHEDULE. |
| P6 | 3" DRAIN IN FLOOR FOR MOP BASIN ("MB") DRAIN. REFERENCE PLUMBING FIXTURE SCHEDULE. |
| P7 | 3/4" CW AND 3/4" HW – IN WALL, 18" AFF, TO HOSE BIBB. |
| P10 | FLOOR DRAIN – 3" OUTLET; FLUSH WITH FLOOR; TWO–PIECE CAST IRON WITH SEEPAGE FLANGE, REVERSIBLE CLAMPING COLLAR, 7" SQUARE HEAVY–DUTY POLISHED BRONZE GRATE, 1/2" TRAP PRIMER TAP, AND TRAP SEAL DEVICE (MODEL 2692) JR SMITH MODEL 2005–03–K07PB–P050–U. |
| P11C | 1/2" CW AND 1/2" HW – IN WALL, FOR HAND LAVATORY WITH FOOT CONTROLS ("LV"). REFERENCE PLUMBING FIXTURE SCHEDULE. |
| P11D | 2" DRAIN – IN WALL, FOR HAND LAVATORY WITH FOOT CONTROLS ("LV"). REFERENCE PLUMBING FIXTURE SCHEDULE. |
| P12 | FLOOR SINK – 4" OUTLET; FLUSH WITH FLOOR; CAST IRON, 8" DEEP SUMP, A.R.E. INTERIOR, INTEGRAL FLANGE FOR SUPPORT, CLAMPING DEVICE WHERE VAPOR BARRIER IS INSTALLED BETWEEN SLAB AND CONCRETE BEDDING FOR FLOOR, ALUMINUM SECONDARY DOME STRAINER AND 12" SQUARE HEAVY D




## 13 FLUSH VALVE TRAP PRIMING TUBE DETAIL

NO SCALE


MI-FAB MODEL MI-702-MOD FLUSH VALVE TRAP PRIMER, OR EQUAL




## 13 GAS PIPING WALL-TO-ROOF TRANSITION DETAIL

NO SCALE

| TANKLESS WATER HEATER SCHED. | | |
|---|---|---|
| MARK | IEWH-1 | |
| SERVES | LAVATORY | |
| LOCATION | BELOW COUNTER | |
| HEATER KW | 1.8 KW | |
| TEMP RISE (@ 0.5 GPM) | 25°F | |
| VOLTAGE/PHASE | 120V/1PH | |
| EEMAX MODEL | SPEX1812T | |





## 11 TANKLESS WATER HEATER

NO SCALE

NOTES:

1. LOCATION OF VALVE AND PIPING SHALL NOT INTERFERE WITH ANY ADA/HANDICAP KNEE-SPACE CLEARANCE REQUIREMENTS.
2. ALL PIPING SHALL BE CHROME PLATED CAST BRASS AND SHALL BE INSULATED BY TRUEBRO HANDI LAV-GUARD INSULATION KITS. INSULATION KITS SHALL COVER P-TRAP, MIXING VALVE, WATER STOPS, PIPING AND ALL SHARP EDGES (ONLY WHERE CABINETWORK KNEESPACE SCREEN NOT PROVIDED).
3. ALL CW AND HW CONNECTIONS SHALL HAVE COMPRESSION TYPE FITTINGS.
4. FURNISH & INSTALL 0.5-GPM AERATOR ON FAUCET COMPATIBLE WITH TANKLESS EWH REQUIREMENTS.
5. WATER HEATER SHALL HAVE INTEGRAL ASSE-1070 COMPLIANT TEMPERED MIXING VALVE.





## 10 ELECTRONIC TRAP PRIMING MANIFOLD DETAIL (TP)

NO SCALE

NOTES:


1. REFERENCE SCHEDULE ON SHEET P3.00




## 8 SAMPLE TEST WELL DETAIL (STW)

NO SCALE

NOTES:





## 14 GAS PIPING ROOF SUPPORT DETAIL

NO SCALE

NOTES:


1. GAS PIPING SUPPORT SHALL BE PORTABLE PIPE HANGERS, INC. MODEL PP10-R. PIPING SHALL BE INSTALLED 12" ABOVE FINISHED ROOF. PROVIDE 18" X 18" CAREY TREAD-TYPE MATERIAL BENEATH EACH PIPE SUPPORT.
2. FIELD LOCATE ROOF STRUCTURAL SUPPORTS AND PLACE BASE OF PIPE SUPPORT OVER ROOF SUPPORTS ONLY. PROVIDE BASE OF ADEQUATE LENGTH TO SPAN ROOF JOIST TO PREVENT SUPPORTS SETTING ON ROOF DECK ONLY.
3. INSTALL SIX (6) FOOT-ON-CENTERS.
4. PIPE SUPPORT MANUFACTURER'S REPRESENTATIVE SHALL PERSONALLY INSPECT INSTALLATIONS OF PIPE SUPPORTS AND MAKE CORRECTIONS AND HEIGHT ADJUSTMENTS TO INSTALLATIONS, AS REQUIRED, DURING INSPECTION.




## 9 ROOF PIPE JACK DETAIL


NO SCALE

NOTE: COORDINATE WITH ARCHITECTURAL DRAWINGS, DETAILS AND SPECIFICATIONS.




## 7 TYPICAL GAS CONNECTION


NO SCALE




## 6 HOT WATER BALANCING STATION


NO SCALE

PROVIDE AT EACH JUNCTION OF BRANCH HOT WATER RETURN LOOPS TO MAIN CIRCULATING HOT WATER LINE, SEE PLUMBING PLANS.




## 5 WALL PENETRATION DETAIL


NO SCALE




## 4 PVC-TO-CAST IRON INSTALLATION DETAIL

NO SCALE


MISSION TRANSITION COUPLING DESIGNED AND CERTIFIED FOR THIS SPECIFIC APPLICATION SHALL BE ACCEPTABLE IN LIEU OF HUSKY COUPLING IN THIS DETAIL.




## 3 ROOF VENT DETAIL

NO SCALE

COORDINATE WITH ARCHITECTURAL DRAWINGS AND SPECIFICATIONS.





## 2 MIXING VALVE DETAIL

NO SCALE

NOTES

1. UNDERCOUNTER MIXING VALVE SHALL BE MOUNTED ON WALL IN FIXTURE KNEE-SPACE. LOCATION OF VALVE AND PIPING SHALL NOT INTERFERE WITH ANY ADA/HANDICAP KNEE-SPACE CLEARANCE REQUIREMENTS.
2. ALL PIPING SHALL BE CHROME PLATED CAST BRASS AND SHALL BE INSULATED BY TRUEBRO HANDI LAV-GUARD INSULATION KITS. INSULATION KITS SHALL COVER P-TRAP, MIXING VALVE, WATER STOPS, PIPING AND ALL SHARP EDGES (ONLY WHERE CABINETWORK KNEESPACE SCREEN NOT PROVIDED).
3. ALL CW AND HW CONNECTIONS SHALL HAVE COMPRESSION TYPE FITTINGS.
4. FOR ABOVE CEILING INSTALLATION, VALVE SHALL BE INSTALLED IN AN EASILY/READILY ACCESSIBLE LOCATION. SEE KITCHEN PLUMBING CONNECTION SCHEDULE FOR REQUIRED KITCHEN LOCATIONS.
5. LAVATORY MIXING VALVES SHALL HAVE AN OUTPUT ADJUSTMENT RANGE UP TO OR ABOVE 130°F.
   SINK MIXING VALVES SHALL HAVE AN OUTPUT ADJUSTMENT RANGE UP TO OR ABOVE 140°F.




## 1 MECHANICAL - ELECTRICAL COORDINATION DETAIL

NO SCALE

DO NOT INSTALL ANY PIPING BENEATH CVT BOXES. DO NOT INSTALL ANY PIPING (EXCEPT FIRE SPRINKLER PIPING AND OTHER PIPES SHOWN SPECIFICALLY ON THE PLUMBING FLOOR PLANS) OVER COMPUTER CLASSROOMS, BOOKROOMS, IDF/MDF/SERVER ROOMS OR OTHER ROOMS NOTED ON THE PLUMBING FLOOR PLANS.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL

STATE OF TEXAS
INTERIM REVIEW
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

PLUMBING SCHEDULES & DETAILS


a-P0.02

PRELIMINARY
NOT FOR CONSTRUCTION OR BIDDING PURPOSES


STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM (713) 300-9080
TEXAS ENGINEERING FIRM REG. NO. F-18153-00


©2025 ALL RIGHTS RESERVED


12300 W. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77064




**RENOVATION KEYED NOTES**

P1 NEW CLEAN OUT IN PLACE OF EXISTING. TIE BACK INTO EXISTING SANITARY BELOW SLAB AND REPAIR SLAB TO MATCH EXISTING.

P2 NEW FLOOR DRAIN IN PLACE OF EXISTING WITH NEW, INCLUDING P-TRAP. TIE BACK INTO EXISTING SANITARY BELOW SLAB AND REPAIR SLAB TO MATCH EXISTING.

**1 PLUMBING RENOVATION FLOOR PLAN**

SCALE: 1/4" = 1'- 0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT

AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL

STATE OF TEXAS
TYLER W. HERRING
106052
LICENSED PROFESSIONAL ENGINEER
07.18.2025



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

PLUMBING FLOOR PLAN

**a-P1.01**


STANTON ENGINEERING GROUP
INFORMATION@STANTONENG.COM (713) 300-6080 | TEXAS ENG. FIRM REG. NO. F-018537-0 | ©2025 ALL RIGHTS RESERVED
12800 N. SAM HOUSTON PARKWAY E., SUITE 125, HOUSTON, TX 77060





## 2 PLUMBING TEMPORARY KITCHEN PLAN - POST DEMO

SCALE: 1/4" = 1'-0"

NOTES:

1. AFTER DEMOLITION OF EXISTING KITCHEN AND DURING CONSTRUCTION OF NEW KITCHEN, EXISTING TEMPORARY KITCHEN SHALL REMAIN ACTIVE.
2. ALL SANITARY, CW AND HW CONNECTIONS SHALL REMAIN ACTIVE DURING ALL TIMES WHEN TEMPORARY KITCHEN IS ACTIVE.
3. UPON COMPLETION OF NEW KITCHEN, EXISTING TEMPORARY KITCHEN SHALL BE DEMOLISHED AND ALL TEMPORARILY UTILITIES SHALL BE REMOVED AND TEMPORARY WATER TAPS CAPPED AT MAIN LINE TAP.
4. ALL DEMOLISHED LAVATORIES AND FAUCETS SHALL BE PERMITTED TO BE RELOCATED ACROSS TEMPORARY KITCHENS WITHIN THE PROJECT BASED ON AVAILABILITY/PROJECT PHASING SCHEDULE. AT THE END OF THE PROJECT, REMOVE FIXTURES AND OFFER TO OWNER AS SALVAGE. IF NOT ACCEPTED, ALL FIXTURES SHALL BE DISPOSED OF BY THE CONTRACTOR.

NORTH




## 1 PLUMBING TEMPORARY KITCHEN PLAN - PRE DEMO

SCALE: 1/4" = 1'-0"

NOTES:

1. BEFORE DEMOLITION OF THE EXISTING KITCHEN BEGINS, INSTALL ALL NEW PLUMBING FIXTURES AND UTILITIES FOR TEMPORARY KITCHEN.

NORTH

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
4400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL




MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

PLUMBING FLOOR PLAN - TEMP KITCHEN

**a-P1.02**

STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM (713) 300-6060
TEXAS ENG. FIRM REG. NO. F-018332 | © 2025 ALL RIGHTS RESERVED
1300 W. SAM HOUSTON PARKWAY S., SUITE 121, HOUSTON, TX 77042

# TECHNOLOGY SYMBOLS & LEGEND

## VOICE SYMBOLS

| | |
|---|---|
| | SINGLE VOICE OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| X | VOICE OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |
| | SINGLE VOICE OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED. |
| X | VOICE OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED, X = NUMBER OF CABLE TERMINATIONS PER LOCATION AS INDICATED. |
| | POWER/COMMUNICATIONS POLE WITH A SINGLE VOICE OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| X | POWER/COMMUNICATIONS POLE WITH X = NUMBER OF VOICE OUTLETS, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| | SINGLE VOICE OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE-THRU AS SPECIFIED. |
| X | VOICE OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE -THRU AS SPECIFIED WITH X = NUMBER OF VOICE TERMINATIONS PER LOCATION. |
| W | SINGLE VOICE OUTLET FOR WALL-MOUNTED PHONE, CABLE TYPE AS SPECIFIED, MOUNTED +52-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

## DATA SYMBOLS

| | |
|---|---|
| | SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| X | DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |
| | SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED. |
| X | DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED, X = NUMBER OF CABLE TERMINATIONS PER LOCATION AS INDICATED. |
| | POWER/COMMUNICATIONS POLE WITH A SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| X | POWER/COMMUNICATIONS POLE WITH X = NUMBER OF DATA OUTLETS, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| | SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE-THRU AS SPECIFIED. |
| X | DATA OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE -THRU AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |
| W | SINGLE DATA OUTLET FOR WALL-MOUNTED IP PHONE, CABLE TYPE AS SPECIFIED, MOUNTED +52-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| X | DATA CABLE FOR COMPUTER ON WHEELS, CABLE TYPE AS SPECIFIED MOUNTED + 18-INCHES A.F.F UNLESS OTHERWISE NOTED. X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |
| X | DATA CABLE FOR CEILING MOUNTED WIRELESS ACCESS POINT, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A GREEN ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. |
| X | DATA CABLE FOR CEILING MOUNTED VIDEO SURVEILLANCE CAMERA, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A ORANGE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. REFER TO SECURITY DRAWINGS PRIOR TO INSTALLATION. |
| | DATA CABLE FOR CEILING MOUNTED PROJECTOR, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A BLUE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. REFER TO AUDIO/VISUAL DRAWINGS PRIOR TO INSTALLATION. |
| X | DATA CABLE FOR CEILING MOUNTED AUDIO/VISUAL EQUIPMENT ENCLOSURE, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A BLUE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. REFER TO AUDIO/VISUAL DRAWINGS PRIOR TO INSTALLATION. |
| X | DATA CABLE FOR WALL MOUNTED PROJECTOR, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A BLUE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. REFER TO AUDIO/VISUAL DRAWINGS PRIOR TO INSTALLATION. |

## DATA SYMBOLS, CONT.

| | |
|---|---|
| X CAME | DATA CABLE FOR EXTERIOR WALL MOUNTED VIDEO SURVEILLANCE CAMERA, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A ORANGE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW, REFER TO SECURITY DRAWINGS PRIOR TO INSTALLATION. |
| X CAMW | DATA CABLE FOR INTERIOR WALL MOUNTED SURVEILLANCE CAMERA, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A ORANGE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. |
| X CAME | DATA CABLE FOR EXTERIOR WALL MOUNTED SURVEILLANCE CAMERA, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A ORANGE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. |
| X WAPW | DATA CABLE FOR INTERIOR WALL MOUNTED WIRELESS ACCESS POINT, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A GREEN ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. |
| X WAPE | DATA CABLE FOR EXTERIOR WALL MOUNTED WIRELESS ACCESS POINT, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A GREEN ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

## CABLE PLANT & RISER DIAGRAM

| | |
|---|---|
| | MAINTENANCE HOLE, SIZE & TYPE AS SPECIFIED. |
| | PULLBOX, SIZE AND TYPE AS SPECIFIED. |
| UGC | DIRECT BURIED COMMUNICATIONS, CABLE TYPE AS SPECIFIED. |
| AER | AERIAL COMMUNICATIONS, CABLE TYPE AS SPECIFIED. |
| | CONDUIT, SIZE AND TYPE AS SPECIFIED. |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

## VOICE/DATA SYMBOLS

| | |
|---|---|
| | SINGLE VOICE & SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| X Y | VOICE & DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. X = NUMBER OF VOICE TERMINATIONS , Y = NUMBER OF DATA TERMINATIONS PER LOCATION. |
| | SINGLE VOICE & SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED. |
| X Y | VOICE & DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED, X = NUMBER OF VOICE OUTLETS AND Y = NUMBER OF DATA OUTLETS PER LOCATION AS INDICATED. |
| | POWER/COMMUNICATIONS POLE WITH A SINGLE VOICE OUTLET AND SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| X Y | POWER/COMMUNICATIONS POLE WITH X = NUMBER OF VOICE TERMINATIONS, Y = NUMBER OF DATA TERMINATIONS, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| | SINGLE VOICE OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE-THRU AS SPECIFIED. |
| X Y | VOICE OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE -THRU AS SPECIFIED WITH X = NUMBER OF VOICE TERMINATIONS, Y = NUMBER OF DATA TERMINATIONS PER LOCATION. |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

## FIBER OPTIC SYMBOLS

| | |
|---|---|
| | SINGLE FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| X | FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |
| | SINGLE FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED. |
| X | FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED, X = NUMBER OF CABLE TERMINATIONS PER LOCATION AS INDICATED. |
| | POWER/COMMUNICATIONS POLE WITH A SINGLE FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| X | POWER/COMMUNICATIONS POLE WITH X = NUMBER OF FIBER OPTIC OUTLETS, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| | SINGLE FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE-THRU AS SPECIFIED. |
| X | FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE -THRU AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

## ROUGH-IN & MISC. SYMBOLS

| | |
|---|---|
| | ROUGH-IN LOCATION, INFRASTRUCTURE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| | ROUGH-IN LOCATION, INFRASTRUCTURE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED. |
| | POWER POLE WITH ROUGH-IN LOCATION, INFRASTRUCTURE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| | ROUGH-IN LOCATION, TERMINATED IN FLOOR BOX/POKE-THRU AS SPECIFIED. |
| WAP | WIRELESS ACCESS POINT. EQUIPMENT AS SPECIFIED. |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

## GENERAL SYMBOLS

| | |
|---|---|
| # SHEET DRAWING TITLE SCALE: SCALE | DRAWING TITLE CALLOUT, # = DETAIL NUMBER. |
| # SHEET | DETAIL CALLOUT, # = DETAIL NUMBER. |
| # SHEET | SECTION CALLOUT, # = DETAIL NUMBER. |
| SHEET # | ELEVATION CALLOUT, # = DETAIL NUMBER. |
| # | KEYED NOTE, # = KEYED NOTE NUMBER. |
| # | REVISION TRIANGLE, # = REVISION NUMBER (PER SHEET). |
| TR (IDF XXX) | INDICATES TELECOMMUNICATIONS REGION |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

## ABBREVIATIONS

| | |
|---|---|
| A.F.F. | ABOVE FINISHED FLOOR |
| A.F.G. | ABOVE FINISHED GRADE |
| AER | AERIAL |
| DEMARC | DEMARCATION POINT |
| EMT | ELECTRIC METALLIC TUBE |
| F.O.C. | FIBER OPTIC CABLE |
| GIP | GALVANIZED IRON PIPE |
| HE | PAINTERCOM HEAD-END |
| IMC | INTERMEDIATE METAL CONDUIT |
| ISP | INSIDE CABLE PLANT |
| IDF | INTERMEDIATE DISTRIBUTION FRAME |
| MDF | MAIN DISTRIBUTION FRAME |
| MH | MAINTENANCE HOLE |
| MM | MULTIMODE |
| OSP | OUTSIDE CABLE PLANT |
| PB | PULLBOX |
| PR | PAIR |
| PVC | POLYVINYL CHLORIDE |
| RSC | RIGID STEEL CONDUIT |
| SM | SINGLE MODE |
| SP | SERVICE PROVIDER |
| STP | SHIELDED TWISTED PAIR |
| TB | TERMINAL BLOCK |
| TR | TELECOMMUNICATION REGION |
| UGC | UNDERGROUND COMMUNICATION |
| UON | UNLESS OTHERWISE NOTED |
| UTP | UNSHIELDED TWISTED PAIR |

## NOTES

1. CONTRACTOR SHALL REVIEW DRAWINGS AND SPECIFICATIONS THAT MAKE UP THE CONTRACT DOCUMENTS AND COMPLETE ALL WORK INCLUDED THEREIN.
2. SCALE OF TECHNOLOGY DRAWINGS IS PROVIDED FOR REFERENCE ONLY. CONTRACTOR SHALL BE RESPONSIBLE FOR PROPER CABLE LENGTHS, SIZE OF PATHWAYS, DIMENSIONS, ETC.
3. TECHNOLOGY DRAWINGS SHALL BE USED TO COMPLEMENT THE WRITTEN SPECIFICATIONS.
4. ANY DISCREPANCY OR CONFLICT WITHIN OR BETWEEN THE DRAWINGS AND SPECIFICATIONS SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT/DESIGN CONSULTANT'S. DISCREPANCIES OR CONFLICTS NOT BROUGHT TO THE ATTENTION OF THE ARCHITECT/DESIGN CONSULTANT AND SUBSEQUENTLY CLARIFIED DURING THE BIDDING OF THE PROJECT WILL BE DEEMED TO HAVE BEEN BID OR PROPOSED IN THE MORE COSTLY OR DIFFICULT MANNER, AND THE BETTER QUALITY OR GREATER QUANTITY OF WORK SHALL BE PROVIDED BY THE CONTRACTOR IN ACCORDANCE WITH THE ARCHITECT'S/DESIGN CONSULTANT'S INTERPRETATION.

## INDEX OF DRAWINGS


a-T000 TECHNOLOGY SYMBOLS & LEGEND
a-TD201 TECHNOLOGY DEMOLITION FLOOR PLAN
a-T200 TECHNOLOGY COMPOSITE FLOOR PLAN
a-T201 TECHNOLOGY NEW/RENOVATION KITCHEN PLAN
a-T202 TECHNOLOGY TEMPORARY KITCHEN PLAN
a-T300 TECHNOLOGY ENLARGED VIEWS
a-T400 TECHNOLOGY TYPICAL DETAILS
a-T401 TECHNOLOGY TYPICAL DETAILS
a-T500 TECHNOLOGY TYPICAL DETAILS


ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 564970
EXPIRES 12-31-25
RCDD


07/18/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY SYMBOLS & LEGEND

SHEET NO.
a-T000




1 a-T200 TECHNOLOGY COMPOSITE FLOOR PLAN
1/16" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD


07/18/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY COMPOSITE FLOOR PLAN

SHEET NO.
a-T200




1 TECHNOLOGY NEW/RENOVATION KITCHEN PLAN
a-T201 1/4" = 1'-0"

**TECHNOLOGY FLOOR PLANS GENRAL NOTES:**

1. THE TECHNOLOGY REGION / WIRING BOUNDARIES ARE IDENTIFIED ON THE OVERALL SHEETS ONLY AND NOT ON THE ENLARGED SHEETS. CONTRACTOR SHALL REFER TO THE OVERALL SHEETS FOR ALL TECHNOLOGY REGIONS / WIRING BOUNDARIES.
2. ALL CONDUIT PATHWAYS, ROUGH-INS, BACKBOXES, FLOOR BOXES, CONDUIT SLEEVES, ETC. INDICATED ON THE TECHNOLOGY DRAWINGS ARE TO BE PROVIDED AND INSTALLED BY DIVISION 26.
3. ALL POWER INDICATED ON THE TECHNOLOGY DRAWINGS IS TO BE PROVIDED AND INSTALLED BY DIVISION 26.
4. CONTRACTOR SHALL RESTORE ALL PENETRATIONS PROVIDED THROUGH FIRE RATED WALLS/STRUCTURES FOR TECHNOLOGY CABLING BACK TO THE ORIGINAL RATING.
5. CONTRACTOR SHALL RESTORE ALL PENETRATIONS PROVIDED THROUGH NON-RATED WALLS/STRUCTURES FOR TECHNOLOGY CABLING FOR SOUND TO REDUCE NOISE TRAVELING THROUGH PENETRATIONS.
6. TECHNOLOGY CABLING SHALL BE ROUTED IN SEPARATE PATHWAYS IN J-HOOKS, CONDUITS, CONDUIT SLEEVES, CORES, ETC. THROUGHOUT THE ENTIRE PATHWAY. DIFFERENT MEDIA TYPES (DATA, VIDEO, SECURITY, ETC.) SHALL NOT SHARE THE SAME J-HOOK, CONDUIT, CONDUIT SLEEVE, CORE, ETC.
7. UNLESS NOTED OTHERWISE, ALL CONDUITS FOR TECHNOLOGY DEVICES SHALL ROUTE FROM THE DEVICE LOCATION AND TERMINATE ABOVE AN ACCESSIBLE CEILING (AN OPEN CEILING OR CLOUD TYPE CEILING IS NOT CONSIDERED AN ACCESSIBLE CEILING) IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF A MAIN CORRIDOR OR NEAREST MDF/IDF. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF / IDF ROOM TO MINIMIZE THE CABLE LENGTH ENSURING CABLE LENGTH DOES NOT EXCEED 275 FEET.
8. UNLESS NOTED OTHERWISE ALL CONDUITS SHALL BE HOMERUN FROM THE DEVICE LOCATION AND NO DAISY CHAINING OF DEVICES/ ROUGH-INS SHALL BE ALLOWED.
9. CONDUIT SEGMENTS SHALL BE NO MORE THAN 100-FEET IN LENGTH WITH NO MORE THAN THE EQUIVALENT OF (2) 90 DEGREE BENDS BETWEEN PULLING POINTS.
10. CONDUITS SHALL MAINTAIN A BEND RADIUS OF 6 TIMES THE DIAMETER OF THE CONDUIT FOR CONDUITS 2-INCHES OR SMALLER AND 10 TIMES THE DIAMETER OF THE CONDUIT FOR CONDUITS GREATER THAN 2-INCHES.
11. ALL CONDUITS SHALL HAVE A PULL STRING INSTALLED FOR PULLING OF CABLE. CLEARLY LABEL AS "PULL STRING" INDICATING OPPOSITE END LOCATION.
12. ALL SPARE CONDUITS OR CONDUITS FILLED WITH LESS THAN THE MAXIMUM ALLOWED FILL RATIO SHALL HAVE A PULL STRING INSTALLED AND LEFT FOR FUTURE PULLING OF CABLE. CLEARLY LABEL AS "PULL STRING" INDICATING OPPOSITE END LOCATION.
13. EQUIPMENT NOT RELATED TO THE SUPPORT OF THE TELECOMMUNICATIONS ROOM (E.G., PIPING, DUCTWORK, PNEUMATIC TUBING) SHALL NOT BE INSTALLED IN, PASS THROUGH, OR ENTER THE TELECOMMUNICATIONS ROOM.
14. ALL CONDUITS FOR TECHNOLOGY DEVICES SHALL ROUTE FROM THE DEVICE LOCATION AND TERMINATE ABOVE A LAY-IN TYPE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE A LAY- IN TYPE CEILING TO PREVENT THE CABLES FROM BEING EXPOSED, THE CONDUIT SHALL ROUTE TO THE NEAREST LAY-IN TYPE CEILING OFF A MAIN CORRIDOR OR NEAREST MDF/IDF. THE CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE MAIN CORRIDOR OR NEAREST MDF/IDF TO MINIMIZE THE CABLE LENGTH ENSURING THE CABLE LENGTH DOES NOT EXCEED 275 FEET. CONDUIT, CONNECTIONS, J-BOXES, SUSPENSION, ANCHORAGES, AND OTHER CONDUIT COMPONENTS EXPOSED TO VIEW IN PUBLIC SPACES SHALL BE ROUTED AND INSTALLED CAREFULLY TO MINIMIZE VISUAL IMPACT AND SHALL BE FULLY PAINTED TO MATCH UNLESS NOTED OTHERWISE.
15. CONDUIT(S) INSTALLED IN-SLAB OR UNDER-SLAB TO FLOOR BOXES, POKE-THURS, AND TO WORKAREA OUTLETS, ETC. SHALL BE INSTALLED WITH WET RATED CABLE(S).
16. NO GRID WIRE SHALL BE UTILIZED FOR SUPPORTS ONLY USE SOLID SUPPORTS (CLIPS, ALL-THREAD, ANCHORS, ETC.).

**TECHNOLOGY PLAN KEYED NOTES**

**NOT ALL KEYED BELOW APPLY TO THIS SHEET**

1. DATA CABLE FOR CONTRACTOR FURNISHED / CONTRACTOR INSTALLED MENU BOARD. REFERENCE ARCHITECTURAL AND FOOD SERVICE DRAWINGS FOR MOUNTING HEIGHT AND ADDITIONAL INFORMATION. BUILDING POWER ADJACENT TO DATA RECEPTACLE IS REQUIRED.
2. INDOOR / OUTDOOR RATED DATA CABLE FOR POINT OF SALE LOCATION. PROVIDE (1) 1-INCH CONDUIT FOR DATA TO THE WALL BEHIND POINT OF SALE LOCATION AND UP WALL TO ABOVE ACCESSIBLE CEILING. CONDUITS SHALL TERMINATE INSIDE A DOUBLE GANG BOX THAT IS SECURED TO THE POINT OF SALE LOCATION. REFER TO FOOD SERVICE / KITCHEN DRAWINGS FOR EXACT LOCATION AND CONDUIT ROUGH-IN REQUIREMENTS.
3. DATA CABLE FOR TEMPERATURE MONITORING OF FREEZER COOLER. REFER TO FOOD SERVICE / KITCHEN DRAWINGS FOR EXACT LOCATION AND CONDUIT ROUGH-IN REQUIREMENTS AND TERMINATION POINT AND CONNECTIVITY NEEDS IN FREEZER / COOLER CONTROL UNIT.
4. DATA CABLE FOR TEMPORARY POINT OF SALES CASH REGISTER. COORDINATE WITH OWNER, ARCHITECT, AND CONSULTANT FOR ROUTING OF CABLES TO POINT OF SALE CASH REGISTER PRIOR TO INSTALLATION

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 564070
EXPIRES12-31-25
RCDD


07/18/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY NEW/RENOVATION KITCHEN PLAN

SHEET NO.
a-T201




1 a-T202 TECHNOLOGY TEMPORARY KITCHEN FLOOR PLAN
1/4" = 1'-0"

**TECHNOLOGY FLOOR PLANS GENRAL NOTES:**

1. THE TECHNOLOGY REGION / WIRING BOUNDARIES ARE IDENTIFIED ON THE OVERALL SHEETS ONLY AND NOT ON THE ENLARGED SHEETS. CONTRACTOR SHALL REFER TO THE OVERALL SHEETS FOR ALL TECHNOLOGY REGIONS / WIRING BOUNDARIES.
2. ALL CONDUIT PATHWAYS, ROUGH-INS, BACKBOXES, FLOOR BOXES, CONDUIT SLEEVES, ETC. INDICATED ON THE TECHNOLOGY DRAWINGS ARE TO BE PROVIDED AND INSTALLED BY DIVISION 26.
3. ALL POWER INDICATED ON THE TECHNOLOGY DRAWINGS IS TO BE PROVIDED AND INSTALLED BY DIVISION 26.
4. CONTRACTOR SHALL RESTORE ALL PENETRATIONS PROVIDED THROUGH FIRE RATED WALLS/STRUCTURES FOR TECHNOLOGY CABLING BACK TO THE ORIGINAL RATING.
5. CONTRACTOR SHALL RESTORE ALL PENETRATIONS PROVIDED THROUGH NON-RATED WALLS/STRUCTURES FOR TECHNOLOGY CABLING FOR SOUND TO REDUCE NOISE TRAVELING THROUGH PENETRATIONS.
6. TECHNOLOGY CABLING SHALL BE ROUTED IN SEPARATE PATHWAYS IN J-HOOKS, CONDUITS, CONDUIT SLEEVES, CORES, ETC. THROUGHOUT THE ENTIRE PATHWAY. DIFFERENT MEDIA TYPES (DATA, VIDEO, SECURITY, ETC.) SHALL NOT SHARE THE SAME J-HOOK, CONDUIT, CONDUIT SLEEVE, CORE, ETC.
7. UNLESS NOTED OTHERWISE, ALL CONDUITS FOR TECHNOLOGY DEVICES SHALL ROUTE FROM THE DEVICE LOCATION AND TERMINATE ABOVE AN ACCESSIBLE CEILING (AN OPEN CEILING OR CLOUD TYPE CEILING IS NOT CONSIDERED AN ACCESSIBLE CEILING) IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF A MAIN CORRIDOR OR NEAREST MDF/IDF. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF / IDF ROOM TO MINIMIZE THE CABLE LENGTH ENSURING CABLE LENGTH DOES NOT EXCEED 275 FEET.
8. UNLESS NOTED OTHERWISE ALL CONDUITS SHALL BE HOMERUN FROM THE DEVICE LOCATION AND NO DAISY CHAINING OF DEVICES/ ROUGH-INS SHALL BE ALLOWED.
9. CONDUIT SEGMENTS SHALL BE NO MORE THAN 100-FEET IN LENGTH WITH NO MORE THAN THE EQUIVALENT OF (2) 90 DEGREE BENDS BETWEEN PULLING POINTS.
10. CONDUITS SHALL MAINTAIN A BEND RADIUS OF 6 TIMES THE DIAMETER OF THE CONDUIT FOR CONDUITS 2-INCHES OR SMALLER AND 10 TIMES THE DIAMETER OF THE CONDUIT FOR CONDUITS GREATER THAN 2-INCHES.
11. ALL CONDUITS SHALL HAVE A PULL STRING INSTALLED FOR PULLING OF CABLE. CLEARLY LABEL AS "PULL STRING" INDICATING OPPOSITE END LOCATION.
12. ALL SPARE CONDUITS OR CONDUITS FILLED WITH LESS THAN THE MAXIMUM ALLOWED FILL RATIO SHALL HAVE A PULL STRING INSTALLED AND LEFT FOR FUTURE PULLING OF CABLE. CLEARLY LABEL AS "PULL STRING" INDICATING OPPOSITE END LOCATION.
13. EQUIPMENT NOT RELATED TO THE SUPPORT OF THE TELECOMMUNICATIONS ROOM (E.G., PIPING, DUCTWORK, PNEUMATIC TUBING) SHALL NOT BE INSTALLED IN, PASS THROUGH, OR ENTER THE TELECOMMUNICATIONS ROOM.
14. ALL CONDUITS FOR TECHNOLOGY DEVICES SHALL ROUTE FROM THE DEVICE LOCATION AND TERMINATE ABOVE A LAY-IN TYPE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE A LAY- IN TYPE CEILING TO PREVENT THE CABLES FROM BEING EXPOSED, THE CONDUIT SHALL ROUTE TO THE NEAREST LAY-IN TYPE CEILING OFF A MAIN CORRIDOR OR NEAREST MDF/IDF. THE CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE MAIN CORRIDOR OR NEAREST MDF/IDF TO MINIMIZE THE CABLE LENGTH ENSURING THE CABLE LENGTH DOES NOT EXCEED 275 FEET. CONDUIT, CONNECTIONS, J-BOXES, SUSPENSION, ANCHORAGES, AND OTHER CONDUIT COMPONENTS EXPOSED TO VIEW IN PUBLIC SPACES SHALL BE ROUTED AND INSTALLED CAREFULLY TO MINIMIZE VISUAL IMPACT AND SHALL BE FULLY PAINTED TO MATCH UNLESS NOTED OTHERWISE.
15. CONDUIT(S) INSTALLED IN-SLAB OR UNDER-SLAB TO FLOOR BOXES, POKE-THURS, AND TO WORKAREA OUTLETS, ETC. SHALL BE INSTALLED WITH WET RATED CABLE(S).
16. NO GRID WIRE SHALL BE UTILIZED FOR SUPPORTS ONLY USE SOLID SUPPORTS (CLIPS, ALL-THREAD, ANCHORS, ETC.).

**TECHNOLOGY PLAN KEYED NOTES**

**NOT ALL KEYED BELOW APPLY TO THIS SHEET**

1. DATA CABLE FOR CONTRACTOR FURNISHED / CONTRACTOR INSTALLED MENU BOARD. REFERENCE ARCHITECTURAL AND FOOD SERVICE DRAWINGS FOR MOUNTING HEIGHT AND ADDITIONAL INFORMATION. BUILDING POWER ADJACENT TO DATA RECEPTACLE IS REQUIRED.
2. INDOOR / OUTDOOR RATED DATA CABLE FOR POINT OF SALE LOCATION. PROVIDE (1) 1-INCH CONDUIT FOR DATA TO THE WALL BEHIND POINT OF SALE LOCATION AND UP WALL TO ABOVE ACCESSIBLE CEILING. CONDUITS SHALL TERMINATE INSIDE A DOUBLE GANG BOX THAT IS SECURED TO THE POINT OF SALE LOCATION. REFER TO FOOD SERVICE / KITCHEN DRAWINGS FOR EXACT LOCATION AND CONDUIT ROUGH-IN REQUIREMENTS.
3. DATA CABLE FOR TEMPERATURE MONITORING OF FREEZER COOLER. REFER TO FOOD SERVICE / KITCHEN DRAWINGS FOR EXACT LOCATION AND CONDUIT ROUGH-IN REQUIREMENTS AND TERMINATION POINT AND CONNECTIVITY NEEDS IN FREEZER / COOLER CONTROL UNIT.
4. DATA CABLE FOR TEMPORARY POINT OF SALES CASH REGISTER. COORDINATE WITH OWNER, ARCHITECT, AND CONSULTANT FOR ROUTING OF CABLES TO POINT OF SALE CASH REGISTER PRIOR TO INSTALLATION

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 10-31-25
RCDD

07/18/2025

MWA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING


TECHNOLOGY TEMPORARY KITCHEN PLAN

SHEET NO.
a-T202

NOTE TO CONTRACTOR:

UNLESS OTHERWISE NOTED, LOW VOLTAGE CABLING SHALL BE INSTALLED WITHIN 6-INCHES OF THE CEILING AND ACCESSIBLE BY A TECHNICIAN ON A STANDARD A-FRAME LADDER.

CONTRACTOR SHALL MAINTAIN AT LEAST 6-INCHES OF SEPRATION BETWEEN CABLING BUNDLES AND MECHANICAL DUCTWORKS, EQUIPMENT, PIPIING OR OTHER SYSTEMS IN THE CEILING PLENUM.





KEYED NOTES:

1. J-HOOK WITH RETAINER CLIP ABOVE ACCESSIBLE CEILING (BY DIV 27).
2. DATA CABLE ABOVE ACCESSIBLE CEILING (BY DIV 27).
3. A/V CABLE ABOVE ACCESSIBLE CEILING (BY DIV 27).
4. SECURITY CABLE ABOVE ACCESSIBLE CEILING (BY DIV 28).
5. SPARE J-HOOK (BY DIV 27).

## 1 T400 TYPICAL J-HOOK CABLE PATHWAY

SCALE: N.T.S.





KEYED NOTES:

1. SCHEDULED FLOOR OR DECK.
2. CONDUIT SLEEVE (BY DIV 26).
3. NYLON BUSHING (BY DIV 26).

## 2 T400 TYPICAL CONDUIT SLEEVE THROUGH FLOOR OR DECK DETAIL

SCALE: N.T.S.





KEYED NOTES:

1. SCHEDULED WALL.
2. SCHEDULED CEILING.
3. CONDUIT SLEEVE (BY DIV 26).
4. NYLON BUSHING (BY DIV 26).

## 3 T400 TYPICAL CONDUIT SLEEVE GOING THROUGH WALL

SCALE: N.T.S.





KEYED NOTES:

1. SCHEDULED WALL.
2. SCHEDULED CEILING.
3. SCHEDULED DECK ABOVE.
4. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX WITH DOUBLE GANG PLASTER RING (BY DIV 26).
5. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH. (BY DIV 26).

## 4 T400 TYPICAL TECHNOLOGY CONDUIT ROUGH-IN

SCALE: N.T.S.





KEYED NOTES:

1. SCHEDULED STUD.
2. SCHEDULED WALL.
3. J-HOOK WITH RETAINER CLIP ABOVE ACCESSIBLE CEILING (BY DIV 27).
4. DATA CABLE ABOVE ACCESSIBLE CEILING (BY DIV 27).
5. 20 FOOT SERVICE LOOP ABOVE ACCESSIBLE CEILING NEATLY COILED AND SECURED TO J-HOOK (BY DIV 27).
6. SURFACE MOUNT BOX ABOVE ACCESSIBLE CEILING SECURED TO BUILDING STRUCTURE (BY DIV 27).
7. DATA INSERT (BY DIV 27).

## 5 T400 TYPICAL ABOVE CEILING SINGLE DATA OUTLET (WALL MOUNTED)

SCALE: N.T.S.





KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH PHONE STUDS (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. CABLE AS SPECIFIED (BY DIV 27).

## 6 T400 TYPICAL WALL PHONE OUTLET CONFIGURATION

SCALE: N.T.S.





KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH DESIGNATION IN WINDOW (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. CABLE AS SPECIFIED (BY DIV 27).
7. ELECTRICAL RECEPTACLE, GANG BOX AND CONDUIT SHOWN FOR REFERENCE ONLY (REFER TO DIV 26).

## 7 T400 TYPICAL DUAL DATA OUTLET CONFIGURATION

SCALE: N.T.S.





KEYED NOTES:

1. 4 11/16-INCH X 4 11/16-INCH X 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. DOUBLE GANG PLASTER RING (BY DIV 26).
4. SURFACE MOUNT BOX INSIDE THE 4 11/16-INCH X 4 11/16-INCH X 2 1/8-INCH DOUBLE GANG BOX (BY DIV 27).
5. RJ-45 INSERT (BY DIV 27).

## 8 T400 TYPICAL WALL-MOUNTED WIRELESS ACCESS POINT

SCALE: N.T.S.




KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH DESIGNATION IN WINDOW (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. BLANK INSERT (BY DIV 27).
7. CABLE AS SPECIFIED (BY DIV 27).
8. ELECTRICAL RECEPTACLE, GANG BOX AND CONDUIT SHOWN FOR REFERENCE ONLY (REFER TO DIV 26).

## 9 T400 TYPICAL THREE DATA OUTLET CONFIGURATION

SCALE: N.T.S.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 554370
EXPIRES 12-31-25
RCDD


07/18/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY TYPICAL DETAILS

SHEET NO.
a-T400





KEYED NOTES:

1. ALL THREAD TO BUILDING STRUCTURE (BY DIV. 27)
2. SCHEDULING CEILING
3. IN-PLENUM CEILING BRACKET PN 49223-CBC ATTACHED TO ALL THREAD (BY DIV. 27)
4. SURFACE MOUNT BOX ABOVE ACCESSIBLE CEILING SECURED TO BRACKET (BY DIV. 27)
5. DATA CABLE (BY DIV. 27)
6. DATA INSERT (BY DIV. 27)

## 1 / T401 TYPICAL ABOVE CEILING DATA OUTLET

SCALE: N.T.S.





KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH DESIGNATION IN WINDOW (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. CABLE AS SPECIFIED (BY DIV 27).
7. ELECTRICAL RECEPTACLE, GANG BOX AND CONDUIT SHOWN FOR REFERENCE ONLY (REFER TO DIV 26). ELECTRICAL RECEPTACLE TO BE INSTALLED AT 36" A.F.F AND ADJACENT TO COW / SECONDARY TEACHING OUTLET LOCATION.

## 2 / T401 TYPICAL COW / SECONDARY TEACHER'S DATA OUTLET CONFIGURATION

SCALE: N.T.S.





KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH DESIGNATION IN WINDOW (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. BLANK INSERT (BY DIV 27).
7. CABLE AS SPECIFIED (BY DIV 27).
8. ELECTRICAL RECEPTACLE, GANG BOX AND CONDUIT SHOWN FOR REFERENCE ONLY (REFER TO DIV 26).

## 3 / T401 TYPICAL THREE DATA OUTLET CONFIGURATION

SCALE: N.T.S.




KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH DESIGNATION IN WINDOW (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. CABLE AS SPECIFIED (BY DIV 27).
7. ELECTRICAL RECEPTACLE, GANG BOX AND CONDUIT SHOWN FOR REFERENCE ONLY (REFER TO DIV 26).

## 4 / T401 TYPICAL FOUR DATA OUTLET CONFIGURATION


SCALE: N.T.S.

| TBB/GE CONDUCTOR SIZING | |
|---|---|
| LENGTH IN LINEAR M (FT) | SIZE (AWG) |
| LESS THAN 4 (13) | 6 |
| 4 - 6 (14-20) | 4 |
| 6 - 8 (21 - 26) | 3 |
| 8 - 10 (27 - 33) | 2 |
| 10 - 13 (34 - 41) | 1 |
| 13 - 16 (42 - 52) | 1/0 |
| 16 - 20 (53 - 66) | 2/0 |
| 20 - 26 (67 - 84) | 3/0 |
| 26 - 32 (85 - 105) | 4/0 |
| 32 - 38 (106 - 125) | 250 kcmil |
| 38 - 46 (126 - 150) | 300 kcmil |
| 46 - 53 (151 - 175) | 350 kcmil |
| 53 - 76 (176 - 250) | 500 kcmil |
| 76 - 91 (251 - 300) | 600 kcmil |
| GREATER THAN 91 (301) | 750 kcmil |

ROUTE THE TBB TO EACH TGB IN AS STRAIGHT A PATH AS POSSIBLE. THE TBB SHOULD BE INSTALLED AS A CONTINUOUS CONDUCTOR, AVOIDING SPLICES WHERE POSSIBLE.

## 5 / T401 TBB CONDUCTOR SIZING

SCALE: N.T.S.





1. TELECOMMUNICATIONS MAIN GROUNDING BUS BAR (PBB)(BY DIV. 27)
2. TELECOMMUNICATIONS GROUNDING BUS BAR (SBB)(BY DIV 27)
3. TELECOMMUNICATIONS BONDING CONDUCTOR (TBC). REFER TO CONDUCTOR SIZING CHART FOR EXACT SIZE REQUIREMENTS (BY DIV 27)
4. CONNECT TO GROUNDED BUILDING STEEL WHEN EXPOSED IN ROOM.
5. TELECOMMUNICATIONS BONDING BACKBONE (TBB). REFER TO CONDUCTOR SIZING CHART FOR EXACT SIZE REQUIREMENTS (BY DIV 26)
6. TELECOMMUNICATIONS BONDING CONDUCTOR (TBC). BY ELECTRICAL CONTRACTOR.REFER TO CONDUCTOR SIZING CHART FOR EXACT SIZE REQUIREMENTS.
7. GROUNDING EQUALIZER CONDUCTOR (GEC)(BY DIV 26)
8. BOUND WITH GROUDING COLLARS TO EACH CONTINUOUS CONDUIT THAT ENTERS THE TELECOM ROOM. (BY DIV 26).
9. BOND TO EACH ACCESS CONTROL PANEL AND OTHER SECURITY PANELS IN HE TELECOM ROOM. (BY DIV 27)

## 6 / T401 TYPICAL GROUNDING DIAGRAM

SCALE: N.T.S.

System No. W-L-3218
F Ratings - 1, 2, 3 and 4 Hr (See Items 1 and 3)
T Ratings - 3/4 and 1 Hr (See Item 3)
L Rating At Ambient - Less Than 1, 1, 3, 4 or 7 CFM (See Item 3)
L Rating At 400 F - Less Than 1, 2 or 3 CFM (See Item 3)




Section A-A

1. Wall Assembly - The 1, 2, 3 or 4 hr fire-rated gypsum board/stud wall assembly shall be constructed of the materials and in the manner described within the individual U300, U400 or V400 Series Wall and Partition Designs in the UL Fire Resistance Directory and shall incorporate the following construction features:
   A. Studs - Wall framing shall consist of either wood studs or steel channel studs. Wood studs to consist of nom 2 by 4 in. (51 by 102 mm) lumber spaced max 16 in. (406 mm) OC. Steel studs to be min 3-1/2 in. (89 mm) wide and spaced max 24 in. (610 mm) OC.
   B. Gypsum Board* - Thickness, type, number of layers and fasteners as specified in the individual Wall and Partition Design. Opening in gypsum board to be max 1/4 in. (6 mm) larger then width and height dimensions of firestop device(s).

   The hourly F Rating of the firestop system is dependent upon the hourly rating of the wall in which it is installed.
2. Firestop Device* - One, two, three, four or seven firestop device modules ganged together. Each firestop device module consists of a 3 by 3 by 10-1/2 in. (76 by 76 by 267 mm) long galv steel tube with an intumescent material lining. Firestop device modules to be installed in accordance with the accompanying installation instructions. The space between the firestop device module(s) and the periphery of the opening shall be min 0 in. ( 0 mm, point contact) to max 1/8 in. (3.2 mm). In round openings, the space between the firestop device and the periphery of the opening shall be min 0 in. (point contact) to max 1/2 in. (13 mm). Firestop device module(s) secured in place by means of steel wall plates installed with gasketing material supplied with product. Steel wall plates installed on both sides of wall and secured to each device by means of steel set screws provided with device. Each four- and seven-gang steel wall plate shall be fastened to the studs with steel screws sized to extend through the gypsum board layers and penetrate 1/2 in. (13 mm) into the framing member. Each firestop device module is to be installed with ends projecting an equal distance beyond each surface of the wall assembly.

   As an alternate, the four- and seven-gang steel wall plates may be installed directly against the studs for walls having 16 and 24 in. (406 and 610 mm) center-to-center stud spacing, respectively, prior to installation of the gypsum board layers. The steel wall plates shall be secured to the stud by means of steel screws. After installation of the steel wall plates and firestop device modules, the gypsum board shall be installed as specified in the individual U300 or U400 Design with a maximum 1/8 in. (3.2 mm) gap between the firestop device module and the cutout in the gypsum board. Gap between the firestop device module and the cutout in the gypsum board may be filled with gypsum joint compound or fill material (Item 4).

   SPECIFIED TECHNOLOGIES INC - EZ PATH Series 33 Fire Rated Pathway

2A. Firestop Device* - Extension Module - (Optional, Not Shown) - Module attached to ends of 3 by 3 by 10-1/2 in. (76 by 76 by 267 mm) long firestop device (Item 3) to increase its length to facilitate installation in thicker walls. Each module consists of a 3 by 3 by 6 in. (76 by 76 by 152 mm) long galv steel tube with an intumescent material lining. Extension module to be installed in accordance with the accompanying installation instructions. When module is used, firestop device (Item 2) and extension module(s) secured in place by means of steel wall plates installed with gasketing material supplied with product. Steel wall plates installed on both sides of wall and secured to each device or extension module(s) by means of steel set screws provided with wall plates. Firestop device and extension module(s) assembly to be installed with ends projecting an equal distance beyond each surface of the wall assembly.

   SPECIFIED TECHNOLOGIES INC - EZ PATH Extension

3. Cables - Within the loading area for each firestop device module, the cables may represent a 0 to 100 percent visual fill. Cable fill to be distributed at a uniform height across the width of the firestop device module. Cables to be rigidly supported on both sides of the wall assembly. Any combination of the following types of cables may be used:
   A. Max 400 pair No. 24 AWG (or smaller) copper conductor telecommunication cable with polyvinyl chloride (PVC) jacketing and insulation.
   B. Max 350 kcmil single copper conductor power cable with XLPE jacket and insulation
   C. Max 7/C No. 12 AWG copper conductor control cable with PVC or XLPE jacket and insulation.
   D. Max 3/C No. 10 AWG metal clad or armored cable with steel or aluminum jacket.
   E. Max 3/C No. 8 AWG NM cable (Romex) with PVC insulation and jacket.
   F. Max four pair No. 22 AWG (or smaller) copper conductor data cable with PVC or plenum rated jacketing and insulation.
   G. Max RG/U coaxial cable with fluorinated ethylene insulation and jacketing.
   H. Fiber optic cable with PVC or polyethylene (PE) jacket and insulation having a max diam of 5/8 in. (16 mm).
   I. Optical Fiber Raceway+ - Max 1-1/2 in. (38 mm) diam (or smaller) optical fiber raceway ("innerduct") formed of either PVC or polyvinylidene fluoride (PVDF) with optical fiber cable fill. Raceways installed in accordance with the National Electrical Code (NFPA 70).

   When the hourly rating of the wall assembly is 1 hr, the T Rating is 3/4 hr. When the hourly fire rating of the wall assembly is greater than 1 hr, the T Rating is 3/4 hr when Item 3A, 3B, 3C, 3D or 3E is used. Otherwise the T Rating is 1 hr. When Item 3A, 3B, 3C, 3D or 3E is used, the maximum F Rating is 2 hr. When max 200 pair No. 24 AWG telecommunication cable is used or when Item 3F, 3G, 3H or 3I is used, the maximum F Rating is 4 hr.

   The L Rating for each empty firestop device module is less than 1 cfm at ambient and at 400F. When Item 3A is used, the L Rating for each firestop device module with 100 percent visual fill is 4 cfm at ambient and 3 cfm at 400F. When Item 3F is used, the L Rating for each firestop device module with 100 percent visual fill is 1.3 cfm at ambient and 1 cfm at 400F. When Item 3G or 3H is used, the L Rating for each firestop device module with 100 percent visual fill is 7 cfm at ambient and 2 cfm at 400F.
4. Fill, Void or Cavity Material* - Sealant or Putty - (Not Shown) - As an alternate to gypsum joint compound, the gap between the firestop device module and the cutout in the gypsum board may be sealed with fill material on each side of the wall assembly when four- and seven-gang steel wall plates are installed directly against the wood or steel studs.

   SPECIFIED TECHNOLOGIES INC - SpecSeal Series SSS Sealant, SpecSeal LCI Sealant, SpecSeal Putty

   *Bearing the UL Classification Mark

## 7 / T401 TYPICAL STI EZ-PATH SLEEVE DETAIL

SCALE: N.T.S.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL

DISTRIBUTION DESIGNER
REGISTERED COMMUNICATIONS
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD


07/18/2025



MVA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY TYPICAL DETAILS

SHEET NO.
a-T401













1 T500 TYPICAL HORIZONTAL DATA CABLE LABELING SCHEME

SCALE: N.T.S.






2 T500 TYPICAL FIBER BACKBONE LABELING SCHEME

SCALE: N.T.S.




3 T500 TYPICAL COPPER BACKBONE LABELING SCHEME

SCALE: N.T.S.




4 T500 ABOVE ASSESSIBLE CEILING LABELING SCHEME

SCALE: N.T.S.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
AUSTIN PARKWAY ELEMENTARY SCHOOL
400 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL

BICSI REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD

07/18/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY TYPICAL DETAILS

SHEET NO.
a-T500

## AUDIO/VISUAL MULTIMEDIA LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| A## V## | WALL AV ROUGH-IN DETAIL |
| A## V## | CEILING AV ROUGH-IN DETAIL |
| A## V## | FLOOR AV ROUGH-IN DETAIL |
| IWB IWB | INTERACTIVE WHITE BOARD - WALL - CEILING |
| PJ PJ | MULTIMEDIA PROJECTOR |
| FP# FP# | MULTIMEDIA FLAT PANEL DISPLAY |
| S S | LOUDSPEAKER, WALL MOUNTED AND CEILING MOUNTED RESPECTIVELY - # INDICATES TYPE |
| CP# | CONTROL PANEL |
| TP# | TOUCH PANEL |
| M | MICROPHONE, CEILING MOUNTED - # INDICATES TYPE |
| VC | VOLUME CONTROL |
| WB | WALL BOX ENCLOSURE |
| D1 A1 | D1 = DIGITAL SINGLE SIDED CLOCK / A1 = ANALOG SINGLE SIDED CLOCK |
| D2 A2 | D2 = DIGITAL DOUBLE SIDED CLOCK / A2 = ANALOG DOUBLE SIDED CLOCK |
| ENC | CEILING AV ENCLOSURE |
| C C | PRESENTATION CAMERA - CEILING - WALL MOUNTED |

## PREMISE SECURITY LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| CR | CARD READER |
| CR M | CARD READER MULLION |
| KP | INTRUSION DETECTION KEYPAD |
| IC | INTERCOM (1 DATA CABLE) |
| IC MS | INTERCOM MASTER STATION (1 DATA CABLE) |
| PB | PANIC/DURESS BUTTON |
| LD | LOCK DOWN BUTTON |
| MD | MOTION DETECTOR |
| GB | ACCOUSTICAL GLASS BREAK SENSOR |
| BM | BIOMETRIC READER |
| RX | REQUEST TO EXIT - SURFACE PIR |
| KS | KEY SWITCH |
| LA | LOCAL ALARM SOUNDER |
| RG | RED/GREEN INDICATOR LIGHT |
| DB | DOORBELL |
| DH | MAGNETIC DOOR HOLD |
| DR | DOOR RELEASE |
| RX | REQUEST TO EXIT - INTEGRAL TO DOOR HARDWARE |
| DC | DOOR CONTACT / MONITOR |
| ES EL EH | ELECTRIFIED STRIKE - ELECTRIFIED LATCH - ELECTRIFIED HARDWARE (REFER TO SCHEDULES) |
| C C | STANDARD IP SURVEILLANCE CAMERA, (1) CABLE |
| C C | 180° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° FISHEYE LENS CAMERA |
| IR | IR ILLUMINATOR |

## STRUCTURED CABLING LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF DATA CABLE(S)/JACK(S) |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) |
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| W | WALL MOUNT PHONE (1 CABLE/JACK) |
| W | WALL MOUNT PHONE, SURFACE MOUNT (1 CABLE/JACK) |
| # | FLOOR MOUNTED OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| #/# | FLOOR MOUNTED OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| # | CEILING MOUNTED DATA OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) |
| AP# | CEILING MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| AP# | WALL MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| | CABLING SLEEVE(S) |
| | TYPICAL LADDER RACK |
| | TYPICAL CABLE TRAY, BASKET STYLE |

## GENERAL ANNOTATION LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| MER | MAIN EQUIPMENT ROOM |
| TR | TELECOMMUNICATION ROOM |
| MDF | MAIN DISTRIBUTION FRAME |
| IDF | INTERMEDIATE DISTRIBUTION FRAME |
| ETR | EXISTING TO REMAIN |
| PBO | PROVIDED BY OTHERS |
| AFF | ABOVE FINISHED FLOOR |
| AFG | ABOVE FINISHED GRADE |
| AC | ABOVE COUNTER |
| EC | ELECTRICAL CONTRACTOR |
| PSC | PREMISE SECURITY CONTRACTOR |
| SCC | STRUCTURAL CABLING CONTRACTOR |
| AVC | AV/MULTIMEDIA CONTRACTOR |
| UNO | UNLESS NOTED OTHERWISE |
| ACS | ACCESS CONTROL SYSTEM |
| VSS | VIDEO SURVEILLANCE SYSTEM |

## TECHNOLOGY - GENERAL NOTES

1. EACH KEYNOTE MAY NOT BE UTILIZED ON EVERY SHEET.
2. ALL CONDUIT MEASUREMENTS REFER TO STANDARD CONDUIT TRADE SIZES.
3. ALL CABLES SHALL BE CONCEALED.
4. EACH CONTRACTOR SHALL PROVIDE AND INSTALL ALL NECESSARY SLEEVES, WHETHER OR NOT SPECIFICALLY NOTED ON PROJECT DRAWINGS. ALL SLEEVES SHALL BE 2" UNLESS NOTED OTHERWISE ON THE DRAWINGS. CABLE FILL PERCENTAGE SHALL COMPLY WITH NEC.
5. DEVICE LOCATIONS ARE APPROXIMATE. CONTRACTOR SHALL REVIEW CONDITIONS AND COORDINATE WITH OTHER TRADES AS NECESSARY FOR EXACT PLACEMENT.

## TECHNOLOGY SYMBOLS LEGEND

NOT ALL SYMBOLS ARE USED

- A## — AV WALL ROUGH-IN WITH DATA
- # — KEYNOTE
- C — Proposed Camera Direction — SURVEILLANCE CAMERA
- T#-## — Camera Schedule Number (Floor #-Camera #) — Camera (N)ew, (E)xisting Rough-in, (D)emo
- C — Proposed Camera Direction — #-## PTZ — PTZ CAMERA
- C — Proposed Camera Direction — #-## — FIXED SURVEILLANCE CAMERA
- C — 360°/MULTI-SENSOR FIXED SURVEILLANCE CAMERA OR FISHEYE LENS CAMERA
- ##° — Approximate view of lens
- Lens View Angle
- C — 360°/MULTI-SENSOR FIXED SURVEILLANCE CAMERA OR FISHEYE LENS CAMERA
- #mm — Lens size
- C M — MICROPHONE WITH AUDIO LINKED TO CAMERA
- C CR — CARD READER LINKED TO CAMERA
- SYMBOL TAG — CR # — (#) = DIFFERENT TYPES OF CARD READERS: M = MULLION; W = WIRELESS (Proprietary); WI = Wi-Fi (802.11); POE = POWER OVER ETHERNET
- SYMBOL TAG — KP # — (#) = DIFFERENT TYPES OF CARD READERS: TS = TOUCHSCREEN; PU = PUSH BUTTON
- # / #### — TOP = DETAIL NUMBER; DETAIL REFERENCE; BOTTOM = SHEET NUMBER
- NORTH ARROW
- # / #### — SHEET NUMBER; SECTION MARKER; DETAIL NUMBER
- DIRECTION OF ELEVATION; # / #### — ELEVATION MARKER; SHEET NUMBER; DETAIL NUMBER
- DIRECTION OF ELEVATION; SHEET NUMBER; # / #### — DIRECTION OF ELEVATION; DETAIL NUMBER
- BAR IS ONE INCH ON ORIGINAL DRAWING. IF NOT ONE INCH ON THIS DRAWING ADJUST SCALES ACCORDINGLY

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Austin Parkway Elementary School
4400 Austin Pkwy, Sugar Land, TX 77479

SEAL

BICSI REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256587
EXPIRES 12-31-27


07-18-25

MVA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY - TITLE SHEET

a-TN000




1 AUSTIN PARKWAY - DEMO PLAN
SCALE: 3/16" = 1'-0"

**DEMO KEYNOTES**

1. REMOVE, AND PROTECT DURING CONSTRUCTION, INSTALL IN EXISTING LOCATION AFTER NEW ACT GRID IS IN PLACE.
2. DEVICES IN ACT ARE TO BE REMOVED AND PROTECTED DURING CONSTRUCTION AND REINSTALLED IN THE SAME LOCATION AFTER THE NEW CEILING GRID IS IN PLACE. DECIVES INCLUDE: SPEAKERS, ACCESS POINTS AND INTRUSION MOTION DETECTORS.
3. EXISTING CARD READER, DOOR CONTACT, & REX (REQUEST TO EXIT) TO BE DEMOLISHED, REMOVE DEVICES AND PROTECT WIREING.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Austin Parkway Elementary School
4400 Austin Pkwy, Sugar Land, TX 77479

SEAL

Registered Communications Distribution Designer
Bicsi
Brian C Porter
BICSI ID # 256657
EXPIRES 12-31-27
RCDD

07-18-25

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING


TECHNOLOGY - Austin Parkway ES - DEMO

a-TN.001

TRUENORTH A PMY COMPANY

## TECHNOLOGY KEYNOTES

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.




1 BACKGROUND A (AUSTIN PARKWAY) OVERALL
SCALE: 1" = 20'-0"

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Austin Parkway Elementary School
4400 Austin Pkwy, Sugar Land, TX 77479

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256557
EXPIRES 12-31-27

07-18-25

MVA ARCHITECTS


ARCHITECTS
AND PLANNING
CONSULTANTS

11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING
AND
PERMITTING

TECHNOLOGY - Austin Parkway ES - OVERALL

a-TN.100




1 AUSTIN PARKWAY - KITCHEN PLAN
SCALE: 3/16" = 1'-0"

**TECHNOLOGY KEYNOTES**

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.

TRUENORTH A PWY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Austin Parkway Elementary School
4400 Austin Pkwy, Sugar Land, TX 77479

SEAL

Bicsi
Brian C Porter
BICSI ID # 256557
EXPIRES 12-31-27
07-18-25

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY - Austin Parkway ES - KITCHEN


a-TN.101

**GENERAL NOTE**


1. FACE PLATE DETAIL FOR OUTLET CONFIGURATION PURPOSES ONLY. CONTRACTOR TO SELECT TYPE OF FACE PLATE TO MATCH CONNECTIVITY HARDWARE, FLOOR BOX AND/OR MODULAR FURNITURE OPENING.





1 DATA ROUGH-IN DETAILS
SCALE: NS




2 TYPICAL CABLING SLEEVE
SCALE: NTS





3 PANDUIT J-HOOK DETAIL
SCALE: NTS





4 LABELING & CABLING SCHEMES
SCALE: NTS





5 CABLE PATHWAY CROSS SECTION
SCALE: NTS




6 DROPPED CEILING MOUNTING DETAIL
SCALE: NS




7 I-JOIST MOUNTING DETAIL
SCALE: NS




8 BAR JOIST MOUNTING DETAIL
SCALE: NS

| CAMERA TYPE | MANUFACTURER | MODEL NUMBER | GENERAL DESCRIPTION |
|---|---|---|---|
| C1 | iPro | WV-S8574L | 4x4K (33MP) EXTERIOR MULTI-SENSOR - PARKING LOTS, STADIUM |
| C2 | iPro | WV-S8544L | 4x4MP (16MP) EXTERIOR MULTI-SENSOR - BUILDING PERIMETER |
| C3 | iPro | WV-S25500-V3LN | 5MP EXTERIOR VANDAL DOME |
| C4 | iPro | WV-S22500-V3L | 5MP INTERIOR VANDAL DOME - CORR., COMMON, SPED |
| C5 | iPro | WV-S4156A | 5MP 360 (FISHEYE) - STAIRWELLS |

9 CAMERA SCHEDULE
SCALE: NTS

| Symbol | Purpose | Size | Mount | Backbox | Notes |
|---|---|---|---|---|---|
| FP1 | Digital Signage/Menu Boards | +49" | Ceiling Pole | N/A | Data and Power Outlets on ceiling |

10 DISPLAY SCHEDULE
SCALE: NTS

TRUENORTH
A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Austin Parkway Elementary School
4400 Austin Pkwy, Sugar Land, TX 77479

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256557
EXPIRES 12-31-27
RCDD

07-18-25


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY - Austin Parkway ES - DETAILS


a-TN.500

GENERAL NOTES:


1. REFER TO SECURITY SCHEDULE AND WRITTEN SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
2. ALL MOUNTING DETAILS ARE REFERENCE FOR ALL FIXED DOME, 180°, 360°, PTZ, AND "BULLET/BOX" CAMERAS.





1 TYPICAL CAMERA INSTALLATION SECTION DETAIL
SCALE: NS




6 WALL MOUNTED CAMERA DETAIL
SCALE: NS




4 TILE BRIDGE DETAIL
SCALE: NS





5 CEILING MOUNTED CAMERA DETAIL
SCALE: NS


ACCESS CONROL DETAILS AND GENERAL NOTES:

1. CONDUIT ROUGH-IN IS A GUIDE FOR WHAT WILL BE REQUIRED FOR EACH DOOR. AS DOOR COMPONENTS CHANGE, EXACT CONDUIT LOCATION WILL ALSO NEED TO BE ADJUSTED.


2. PROTECT EXISTING-TO-REMAIN ACCESS CONTROL DEVICES AND CABLE THROUGHOUT RENOVATION WORK. IF CABLE AND/OR DEVICES ARE DAMAGED, SECURITY CONTRACTOR TO REPLACE WITH NEW.




1 ACCESS CONTROL - WIRING DETAIL - EXIT DEVICE W/ BUILT-IN REX
SCALE: NTS




2 ACCESS CONTROL - STEEL/HOLLOW METAL DOOR.
SCALE: NTS




KP PB LD

3 ROUGH-IN DETAILS: KP, PB, LD
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Austin Parkway Elementary School
4400 Austin Pkwy, Sugar Land, TX 77479

SEAL


REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 384683
EXPIRES 12-31-27
07-18-25


MVA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY - Austin Parkway ES - SECURITY DETAILS

a-TN.600




6 CEILING MOUNT DISPLAY - A/V ROUGH-IN DETAIL
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

a

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Austin Parkway Elementary School
4400 Austin Pkwy, Sugar Land, TX 77479

SEAL




07-18-25

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY - Austin Parkway ES - AV DETAILS

a-TN.700

# FBISD BP013 KITCHEN RENOVATIONS ES

| Sheet List Table | |
|---|---|
| Sheet Number | Sheet Title |
| School: b-Burton ES | |
| b-A-000 | COVER AND INDEX |
| b-TN-000 | TECHNOLOGY - INDEX SHEET |
| b-TN-100 | TECHNOLOGY - OVERALL |
| b-TN-101 | TECHNOLOGY - KITCHEN |
| b-TN-500 | TECHNOLOGY - DETAILS |
| b-TN-600 | TECHNOLOGY - SECURITY DETAILS |




FORT BEND INDEPENDENT SCHOOL DISTRICT

WALTER MOSES BURTON ELEMENTARY SCHOOL
1625 HUNTER GREEN LANE, FRESNO, TX 77545

## ADMINISTRATION

| | |
|---|---|
| DR. MARCELL SMITH | SUPERINTENDENT OF FBISD |
| DR. ANDRIA SCHUR, Ed.D. | CHIEF OF SCHOOLS |

## BOARD OF TRUSTEES

| | |
|---|---|
| KRISTIN K. TASSIN | PRESIDENT |
| RICK GARCIA | VICE PRESIDENT |
| DAVID HAMILTON | SECRETARY |
| ANGIE HANAN | BOARD MEMBER |
| ADAM SCHOOF | BOARD MEMBER |
| DR. SHIRLEY ROSE-GILLIAM | BOARD MEMBER |
| SONYA JONES | BOARD MEMBER |

## PROJECT DESIGN TEAM

PROGRAM MANAGEMENT
FBISD 2023 Bond Team
2323 Texas Parkway
Missouri City, TX 77489
Phone Number: 281-327-5481

ARCHITECT
MWA Architects
11767 Katy Freeway, Suite 430
Houston, Texas 77079
Phone Number: 713-782-8188

FOOD SERVICE
Food Design Professionals
26215 Oak Ridge Drive
The Woodlands, Texas 77380
Phone Number: 281-350-2323

MEP ENGINEERS
Stanton Engineering Group
1300 W. Sam Houston Pkwy South, Suite 121
Houston, Texas 77042
Phone Number: 713-300-9292

STRUCTURAL ENGINEER
Stanley Spurling & Hamilton
3301 Edloe Street, Suite 200
Houston, Texas 77027
Phone Number: 713-776-9433

ISSUED FOR PERMIT AND BIDDING - JULY 18, 2025

b

## AUDIO/VISUAL MULTIMEDIA LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| A## V## | WALL AV ROUGH-IN DETAIL |
| A## V## | CEILING AV ROUGH-IN DETAIL |
| A## V## | FLOOR AV ROUGH-IN DETAIL |
| IWB IWB | INTERACTIVE WHITE BOARD - WALL - CEILING |
| PJ PJ | MULTIMEDIA PROJECTOR |
| FP# FP# | MULTIMEDIA FLAT PANEL DISPLAY |
| S S | LOUDSPEAKER, WALL MOUNTED AND CEILING MOUNTED RESPECTIVELY - # INDICATES TYPE |
| CP# | CONTROL PANEL |
| TP# | TOUCH PANEL |
| M | MICROPHONE, CEILING MOUNTED - # INDICATES TYPE |
| VC | VOLUME CONTROL |
| WB | WALL BOX ENCLOSURE |
| D1 A1 | D1 = DIGITAL SINGLE SIDED CLOCK / A1 = ANALOG SINGLE SIDED CLOCK |
| D2 A2 | D2 = DIGITAL DOUBLE SIDED CLOCK / A2 = ANALOG DOUBLE SIDED CLOCK |
| ENC | CEILING AV ENCLOSURE |
| C C | PRESENTATION CAMERA - CEILING - WALL MOUNTED |

## PREMISE SECURITY LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| CR | CARD READER |
| CR M | CARD READER MULLION |
| KP | INTRUSION DETECTION KEYPAD |
| IC | INTERCOM (1 DATA CABLE) |
| IC MS | INTERCOM MASTER STATION (1 DATA CABLE) |
| PB | PANIC/DURESS BUTTON |
| LD | LOCK DOWN BUTTON |
| MD | MOTION DETECTOR |
| GB | ACCOUSTICAL GLASS BREAK SENSOR |
| BM | BIOMETRIC READER |
| RX | REQUEST TO EXIT - SURFACE PIR |
| KS | KEY SWITCH |
| LA | LOCAL ALARM SOUNDER |
| RG | RED/GREEN INDICATOR LIGHT |
| DB | DOORBELL |
| DH | MAGNETIC DOOR HOLD |
| DR | DOOR RELEASE |
| RX | REQUEST TO EXIT - INTEGRAL TO DOOR HARDWARE |
| DC | DOOR CONTACT / MONITOR |
| ES EL EH | ELECTRIFIED STRIKE - ELECTRIFIED LATCH - ELECTRIFIED HARDWARE (REFER TO SCHEDULES) |
| C C | STANDARD IP SURVEILLANCE CAMERA, (1) CABLE |
| C C C | 180° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° FISHEYE LENS CAMERA |
| IR | IR ILLUMINATOR |

## STRUCTURED CABLING LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF DATA CABLE(S)/JACK(S) |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) |
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| W | WALL MOUNT PHONE (1 CABLE/JACK) |
| W | WALL MOUNT PHONE, SURFACE MOUNT (1 CABLE/JACK) |
| # | FLOOR MOUNTED OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| #/# | FLOOR MOUNTED OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| # | CEILING MOUNTED DATA OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) |
| AP# | CEILING MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| AP# | WALL MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| | CABLING SLEEVE(S) |
| | TYPICAL LADDER RACK |
| | TYPICAL CABLE TRAY, BASKET STYLE |

## GENERAL ANNOTATION LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| MER | MAIN EQUIPMENT ROOM |
| TR | TELECOMMUNICATION ROOM |
| MDF | MAIN DISTRIBUTION FRAME |
| IDF | INTERMEDIATE DISTRIBUTION FRAME |
| ETR | EXISTING TO REMAIN |
| PBO | PROVIDED BY OTHERS |
| AFF | ABOVE FINISHED FLOOR |
| AFG | ABOVE FINISHED GRADE |
| AC | ABOVE COUNTER |
| EC | ELECTRICAL CONTRACTOR |
| PSC | PREMISE SECURITY CONTRACTOR |
| SCC | STRUCTURAL CABLING CONTRACTOR |
| AVC | AV/MULTIMEDIA CONTRACTOR |
| UNO | UNLESS NOTED OTHERWISE |
| ACS | ACCESS CONTROL SYSTEM |
| VSS | VIDEO SURVEILLANCE SYSTEM |

## TECHNOLOGY - GENERAL NOTES

1. EACH KEYNOTE MAY NOT BE UTILIZED ON EVERY SHEET.
2. ALL CONDUIT MEASUREMENTS REFER TO STANDARD CONDUIT TRADE SIZES.
3. ALL CABLES SHALL BE CONCEALED.
4. EACH CONTRACTOR SHALL PROVIDE AND INSTALL ALL NECESSARY SLEEVES, WHETHER OR NOT SPECIFICALLY NOTED ON PROJECT DRAWINGS. ALL SLEEVES SHALL BE 2" UNLESS NOTED OTHERWISE ON THE DRAWINGS. CABLE FILL PERCENTAGE SHALL COMPLY WITH NEC.
5. DEVICE LOCATIONS ARE APPROXIMATE. CONTRACTOR SHALL REVIEW CONDITIONS AND COORDINATE WITH OTHER TRADES AS NECESSARY FOR EXACT PLACEMENT.

## TECHNOLOGY SYMBOLS LEGEND

NOT ALL SYMBOLS ARE USED

- AV WALL ROUGH-IN WITH DATA
- KEYNOTE
- Proposed Camera Direction
  SURVEILLANCE CAMERA
  Camera Schedule Number (Floor #-Camera #)
  Camera (N)ew, (E)xisting Rough-in, (D)emo
- Proposed Camera Direction
  PTZ CAMERA
  PTZ
- Proposed Camera Direction
  FIXED SURVEILLANCE CAMERA
- 360°/MULTI-SENSOR FIXED SURVEILLANCE CAMERA OR FISHEYE LENS CAMERA
- Approximate view of lens
  Lens View Angle
  360°/MULTI-SENSOR FIXED SURVEILLANCE CAMERA OR FISHEYE LENS CAMERA
  Lens size
- MICROPHONE WITH AUDIO LINKED TO CAMERA
- CARD READER LINKED TO CAMERA
- SYMBOL TAG — (#) = DIFFERENT TYPES OF CARD READERS:
  M = MULLION
  W = WIRELESS (Proprietary)
  Wi = Wi-Fi (802.11)
  POE = POWER OVER ETHERNET
- SYMBOL TAG — (#) = DIFFERENT TYPES OF CARD READERS:
  TS = TOUCHSCREEN
  PU = PUSH BUTTON
- TOP = DETAIL NUMBER
  DETAIL REFERENCE
  BOTTOM = SHEET NUMBER
- NORTH ARROW
- SHEET NUMBER
  SECTION MARKER
  DETAIL NUMBER
- DIRECTION OF ELEVATION
  ELEVATION MARKER
  SHEET NUMBER
  DETAIL NUMBER
- DIRECTION OF ELEVATION
  SHEET NUMBER
  DIRECTION OF ELEVATION
  DETAIL NUMBER
- BAR IS ONE INCH ON ORIGINAL DRAWING. IF NOT ONE INCH ON THIS DRAWING ADJUST SCALES ACCORDINGLY

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

b

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Burton Elementary School
1625 Hunter Green Ln, Fresno, TX 77545

SEAL




07-18-25

MVA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY - TITLE SHEET

b-TN000

## TECHNOLOGY KEYNOTES

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.




1 BURTON (OVERALL)
SCALE: 1" = 20'-0"

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

b

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Burton Elementary School
1625 Hunter Green Ln, Fresno, TX 77545

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256557
EXPIRES 12-31-27

07-18-25


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY - Burton ES - OVERALL

b-TN.100

**TECHNOLOGY KEYNOTES**

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.




1 BURTON - REFLECTED CEILING PLAN
SCALE: 3/16" = 1'-0"

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

b

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Burton Elementary School
1625 Hunter Green Ln, Fresno, TX 77545

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256557
EXPIRES 12-31-27

07-18-25


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY - Burton ES - KITCHEN


b-TN.101

**GENERAL NOTE**


1. FACE PLATE DETAIL FOR OUTLET CONFIGURATION PURPOSES ONLY. CONTRACTOR TO SELECT TYPE OF FACE PLATE TO MATCH CONNECTIVITY HARDWARE, FLOOR BOX AND/OR MODULAR FURNITURE OPENING.





1 DATA ROUGH-IN DETAILS
SCALE: NS





2 TYPICAL CABLING SLEEVE
SCALE: NTS





3 PANDUIT J-HOOK DETAIL
SCALE: NTS





4 LABELING & CABLING SCHEMES
SCALE: NTS





5 CABLE PATHWAY CROSS SECTION
SCALE: NTS




6 DROPPED CEILING MOUNTING DETAIL
SCALE: NS




7 I-JOIST MOUNTING DETAIL
SCALE: NS




8 BAR JOIST MOUNTING DETAIL
SCALE: NS

| CAMERA TYPE | MANUFACTURER | MODEL NUMBER | GENERAL DESCRIPTION |
|---|---|---|---|
| C1 | iPro | WV-S8574L | 4x4K (33MP) EXTERIOR MULTI-SENSOR - PARKING LOTS, STADIUM |
| C2 | iPro | WV-S8544L | 4x4MP (16MP) EXTERIOR MULTI-SENSOR - BUILDING PERIMETER |
| C3 | iPro | WV-S25500-V3LN | 5MP EXTERIOR VANDAL DOME |
| C4 | iPro | WV-S22500-V3L | 5MP INTERIOR VANDAL DOME - CORR., COMMON, SPED |
| C5 | iPro | WV-S4156A | 5MP 360 (FISHEYE) - STAIRWELLS |

9 CAMERA SCHEDULE
SCALE: NTS

| Symbol | Purpose | Size | Mount | Backbox | Notes |
|---|---|---|---|---|---|
| FP1 | Digital Signage/Menu Boards | +49" | Ceiling Pole | N/A | Data and Power Outlets on ceiling |

10 DISPLAY SCHEDULE
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

b

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Burton Elementary School
1625 Hunter Green Ln, Fresno, TX 77545

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 384683
EXPIRES 12-31-27
SCOT

07-18-25



MVA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - DETAILS


b-TN.500

GENERAL NOTES:


1. REFER TO SECURITY SCHEDULE AND WRITTEN SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
2. ALL MOUNTING DETAILS ARE REFERENCE FOR ALL FIXED DOME, 180°, 360°, PTZ, AND "BULLET/BOX" CAMERAS.





1 TYPICAL CAMERA INSTALLATION SECTION DETAIL
SCALE: NS




6 WALL MOUNTED CAMERA DETAIL
SCALE: NS




4 TILE BRIDGE DETAIL
SCALE: NS





5 CEILING MOUNTED CAMERA DETAIL
SCALE: NS


ACCESS CONROL DETAILS AND GENERAL NOTES:

1. CONDUIT ROUGH-IN IS A GUIDE FOR WHAT WILL BE REQUIRED FOR EACH DOOR. AS DOOR COMPONENTS CHANGE, EXACT CONDUIT LOCATION WILL ALSO NEED TO BE ADJUSTED.


2. PROTECT EXISTING-TO-REMAIN ACCESS CONTROL DEVICES AND CABLE THROUGHOUT RENOVATION WORK. IF CABLE AND/OR DEVICES ARE DAMAGED, SECURITY CONTRACTOR TO REPLACE WITH NEW.




1 ACCESS CONTROL - WIRING DETAIL - EXIT DEVICE W/ BUILT-IN REX
SCALE: NTS




2 ACCESS CONTROL - STEEL/HOLLOW METAL DOOR.
SCALE: NTS




KP PB LD

3 ROUGH-IN DETAILS: KP, PB, LD
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

b

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Burton Elementary School
1625 Hunter Green Ln, Fresno, TX 77545

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 3564687
EXPIRES 12-31-27

07-18-25


MVA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING
AND
PERMITTING

TECHNOLOGY - SECURITY DETAILS

b-TN.600

# FBISD BP013 KITCHEN RENOVATIONS ES

| Sheet List Table | |
|---|---|
| Sheet Number | Sheet Title |
| School: c-Colony Bend-ES | |
| c-A.000 | COVER AND INDEX |
| c-TN.000 | TECHNOLOGY - INDEX SHEET |
| c-TN.100 | TECHNOLOGY - OVERALL |
| c-TN-101 | TECHNOLOGY - KITCHEN |
| c-TN-500 | TECHNOLOGY - DETAILS |
| c-TN-600 | TECHNOLOGY - SECURITY DETAILS |




FORT BEND INDEPENDENT SCHOOL DISTRICT

WALTER MOSES BURTON ELEMENTARY SCHOOL
1625 HUNTER GREEN LANE, FRESNO, TX 77545

## ADMINISTRATION

| | |
|---|---|
| DR. MARCELL SMITH | SUPERINTENDENT OF FBISD |
| DR. ANDRIA SCHUR, Ed.D. | CHIEF OF SCHOOLS |

## BOARD OF TRUSTEES

| | |
|---|---|
| KRISTIN K. TASSIN | PRESIDENT |
| RICK GARCIA | VICE PRESIDENT |
| DAVID HAMILTON | SECRETARY |
| ANGIE HANAN | BOARD MEMBER |
| ADAM SCHOOF | BOARD MEMBER |
| DR. SHIRLEY ROSE-GILLIAM | BOARD MEMBER |
| SONYA JONES | BOARD MEMBER |

## PROJECT DESIGN TEAM

PROGRAM MANAGEMENT
FBISD 2023 Bond Team
2323 Texas Parkway
Missouri City, TX 77489
Phone Number: 281-327-5481

ARCHITECT
MWA Architects
11767 Katy Freeway, Suite 430
Houston, Texas 77079
Phone Number: 713-782-8188

FOOD SERVICE
Food Design Professionals
26215 Oak Ridge Drive
The Woodlands, Texas 77380
Phone Number: 281-350-2323

MEP ENGINEERS
Stanton Engineering Group
1300 W. Sam Houston Pkwy South, Suite 121
Houston, Texas 77042
Phone Number: 713-300-9292

STRUCTURAL ENGINEER
Stanley Spurling & Hamilton
3301 Edloe Street, Suite 200
Houston, Texas 77027
Phone Number: 713-776-9433

ISSUED FOR PERMIT AND BIDDING - JULY 18, 2025

C

## AUDIO/VISUAL MULTIMEDIA LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| A## V## | WALL AV ROUGH-IN DETAIL |
| A## V## | CEILING AV ROUGH-IN DETAIL |
| A## V## | FLOOR AV ROUGH-IN DETAIL |
| IWB IWB | INTERACTIVE WHITE BOARD - WALL - CEILING |
| PJ PJ | MULTIMEDIA PROJECTOR |
| FP# FP# | MULTIMEDIA FLAT PANEL DISPLAY |
| S S | LOUDSPEAKER, WALL MOUNTED AND CEILING MOUNTED RESPECTIVELY - # INDICATES TYPE |
| CP# | CONTROL PANEL |
| TP# | TOUCH PANEL |
| M | MICROPHONE, CEILING MOUNTED - # INDICATES TYPE |
| VC | VOLUME CONTROL |
| WB | WALL BOX ENCLOSURE |
| D1 A1 | D1 = DIGITAL SINGLE SIDED CLOCK / A1 = ANALOG SINGLE SIDED CLOCK |
| D2 A2 | D2 = DIGITAL DOUBLE SIDED CLOCK / A2 = ANALOG DOUBLE SIDED CLOCK |
| ENC | CEILING AV ENCLOSURE |
| C C | PRESENTATION CAMERA - CEILING - WALL MOUNTED |

## PREMISE SECURITY LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| CR | CARD READER |
| CR M | CARD READER MULLION |
| KP | INTRUSION DETECTION KEYPAD |
| IC | INTERCOM (1 DATA CABLE) |
| IC MS | INTERCOM MASTER STATION (1 DATA CABLE) |
| PB | PANIC/DURESS BUTTON |
| LD | LOCK DOWN BUTTON |
| MD | MOTION DETECTOR |
| GB | ACCOUSTICAL GLASS BREAK SENSOR |
| BM | BIOMETRIC READER |
| RX | REQUEST TO EXIT - SURFACE PIR |
| KS | KEY SWITCH |
| LA | LOCAL ALARM SOUNDER |
| RG | RED/GREEN INDICATOR LIGHT |
| DB | DOORBELL |
| DH | MAGNETIC DOOR HOLD |
| DR | DOOR RELEASE |
| RX | REQUEST TO EXIT - INTEGRAL TO DOOR HARDWARE |
| DC | DOOR CONTACT / MONITOR |
| ES EL EH | ELECTRIFIED STRIKE - ELECTRIFIED LATCH - ELECTRIFIED HARDWARE (REFER TO SCHEDULES) |
| C C | STANDARD IP SURVEILLANCE CAMERA, (1) CABLE |
| C C C | 180° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° FISHEYE LENS CAMERA |
| IR | IR ILLUMINATOR |

## STRUCTURED CABLING LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF DATA CABLE(S)/JACK(S) |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) |
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| W | WALL MOUNT PHONE (1 CABLE/JACK) |
| W | WALL MOUNT PHONE, SURFACE MOUNT (1 CABLE/JACK) |
| # | FLOOR MOUNTED OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| #/# | FLOOR MOUNTED OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| # | CEILING MOUNTED DATA OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) |
| AP# | CEILING MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| AP# | WALL MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| | CABLING SLEEVE(S) |
| | TYPICAL LADDER RACK |
| | TYPICAL CABLE TRAY, BASKET STYLE |

## GENERAL ANNOTATION LEGEND


| SYMBOL | DESCRIPTION |
|---|---|
| MER | MAIN EQUIPMENT ROOM |
| TR | TELECOMMUNICATION ROOM |
| MDF | MAIN DISTRIBUTION FRAME |
| IDF | INTERMEDIATE DISTRIBUTION FRAME |
| ETR | EXISTING TO REMAIN |
| PBO | PROVIDED BY OTHERS |
| AFF | ABOVE FINISHED FLOOR |
| AFG | ABOVE FINISHED GRADE |
| AC | ABOVE COUNTER |
| EC | ELECTRICAL CONTRACTOR |
| PSC | PREMISE SECURITY CONTRACTOR |
| SCC | STRUCTURAL CABLING CONTRACTOR |
| AVC | AV/MULTIMEDIA CONTRACTOR |
| UNO | UNLESS NOTED OTHERWISE |
| ACS | ACCESS CONTROL SYSTEM |
| VSS | VIDEO SURVEILLANCE SYSTEM |

## TECHNOLOGY - GENERAL NOTES

1. EACH KEYNOTE MAY NOT BE UTILIZED ON EVERY SHEET.
2. ALL CONDUIT MEASUREMENTS REFER TO STANDARD CONDUIT TRADE SIZES.
3. ALL CABLES SHALL BE CONCEALED.
4. EACH CONTRACTOR SHALL PROVIDE AND INSTALL ALL NECESSARY SLEEVES, WHETHER OR NOT SPECIFICALLY NOTED ON PROJECT DRAWINGS. ALL SLEEVES SHALL BE 2" UNLESS NOTED OTHERWISE ON THE DRAWINGS. CABLE FILL PERCENTAGE SHALL COMPLY WITH NEC.
5. DEVICE LOCATIONS ARE APPROXIMATE. CONTRACTOR SHALL REVIEW CONDITIONS AND COORDINATE WITH OTHER TRADES AS NECESSARY FOR EXACT PLACEMENT.

## TECHNOLOGY SYMBOLS LEGEND

NOT ALL SYMBOLS ARE USED




TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

C

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Colony Bend Elementary School
2720 Planters St, Sugar Land, TX 77479

SEAL




07-18-25

MVA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY - TITLE SHEET

c-TN000

## TECHNOLOGY KEYNOTES

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.







1 COLONY BEND (OVERALL)
SCALE: 1" = 20'-0"

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

C

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Colony Bend Elementary School
2720 Planters St, Sugar Land, TX 77479

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Perez
BICSI ID # 295857
EXPIRES 12-31-27
07-18-25



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Colony Bend ES - OVERALL

c-TN.100

## TECHNOLOGY KEYNOTES

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.




1 COLONY BEND - KITCHEN PLAN
SCALE: 3/16" = 1'-0"

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

C

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Colony Bend Elementary School
2720 Planters St, Sugar Land, TX 77479

SEAL

BICSI REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Pena
BICSI ID # 295857
EXPIRES 12-31-27

07-18-25


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Colony Bend ES - KITCHEN

c-TN.101

**GENERAL NOTE**


1. FACE PLATE DETAIL FOR OUTLET CONFIGURATION PURPOSES ONLY. CONTRACTOR TO SELECT TYPE OF FACE PLATE TO MATCH CONNECTIVITY HARDWARE, FLOOR BOX AND/OR MODULAR FURNITURE OPENING.









1 DATA ROUGH-IN DETAILS
SCALE: NS





2 TYPICAL CABLING SLEEVE
SCALE: NTS





3 PANDUIT J-HOOK DETAIL
SCALE: NTS





4 LABELING & CABLING SCHEMES
SCALE: NTS





5 CABLE PATHWAY CROSS SECTION
SCALE: NTS




6 DROPPED CEILING MOUNTING DETAIL
SCALE: NS




7 I-JOIST MOUNTING DETAIL
SCALE: NS




8 BAR JOIST MOUNTING DETAIL
SCALE: NS

| CAMERA TYPE | MANUFACTURER | MODEL NUMBER | GENERAL DESCRIPTION |
|---|---|---|---|
| C1 | iPro | WV-S8574L | 4x4K (33MP) EXTERIOR MULTI-SENSOR - PARKING LOTS, STADIUM |
| C2 | iPro | WV-S8544L | 4x4MP (16MP) EXTERIOR MULTI-SENSOR - BUILDING PERIMETER |
| C3 | iPro | WV-S25500-V3LN | 5MP EXTERIOR VANDAL DOME |
| C4 | iPro | WV-S22500-V3L | 5MP INTERIOR VANDAL DOME - CORR., COMMON, SPED |
| C5 | iPro | WV-S4156A | 5MP 360 (FISHEYE) - STAIRWELLS |

9 CAMERA SCHEDULE
SCALE: NTS

| Symbol | Purpose | Size | Mount | Backbox | Notes |
|---|---|---|---|---|---|
| FP1 | Digital Signage/Menu Boards | +49" | Ceiling Pole | N/A | Data and Power Outlets on ceiling |

10 DISPLAY SCHEDULE
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

C

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Colony Bend Elementary School
2720 Planters St, Sugar Land, TX 77479

SEAL

BICSI REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256557
EXPIRES 12-31-27

07-18-25



MVA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Colony Bend ES - DETAILS


c-TN.500

GENERAL NOTES:


1. REFER TO SECURITY SCHEDULE AND WRITTEN SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
2. ALL MOUNTING DETAILS ARE REFERENCE FOR ALL FIXED DOME, 180°, 360°, PTZ, AND "BULLET/BOX" CAMERAS.





1 TYPICAL CAMERA INSTALLATION SECTION DETAIL
SCALE: NS




6 WALL MOUNTED CAMERA DETAIL
SCALE: NS




4 TILE BRIDGE DETAIL
SCALE: NS





5 CEILING MOUNTED CAMERA DETAIL
SCALE: NS


ACCESS CONROL DETAILS AND GENERAL NOTES:

1. CONDUIT ROUGH-IN IS A GUIDE FOR WHAT WILL BE REQUIRED FOR EACH DOOR. AS DOOR COMPONENTS CHANGE, EXACT CONDUIT LOCATION WILL ALSO NEED TO BE ADJUSTED.


2. PROTECT EXISTING-TO-REMAIN ACCESS CONTROL DEVICES AND CABLE THROUGHOUT RENOVATION WORK. IF CABLE AND/OR DEVICES ARE DAMAGED, SECURITY CONTRACTOR TO REPLACE WITH NEW.




1 ACCESS CONTROL - WIRING DETAIL - EXIT DEVICE W/ BUILT-IN REX
SCALE: NTS




2 ACCESS CONTROL - STEEL/HOLLOW METAL DOOR.
SCALE: NTS




KP PB LD

3 ROUGH-IN DETAILS: KP, PB, LD
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

C

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Colony Bend Elementary School
2720 Planters St, Sugar Land, TX 77479

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256657
EXPIRES 12-31-27
BCCD

07-18-25


MVA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING
AND
PERMITTING
TECHNOLOGY - Colony Bend
ES - SECURITY DETAILS

c-TN.600

# FBISD BP013 KITCHEN RENOVATIONS ES

## COMMONWEALTH ELEMENTARY SCHOOL
4909 COMMONWEALTH BLVD, SUGAR LAND, TX 77479

| Sheet List Table | |
|---|---|
| Sheet Number | Sheet Title |
| School: d-Commonwealth ES | |
| d-A.000 | COVER AND INDEX |
| d-A00-01 | GENERAL NOTES AND ABBREVIATIONS |
| d-D.101 | DEMO PLAN, DEMO RCP |
| d-A.201 | OVERALL FLOOR PLAN |
| d-A4.01 | CAFETERIA ENLARGED RCP & PLAN |
| d-E.200 | ELECTRICAL FLOOR PLAN AND SCHEDULES |
| d-TN-000 | INDEX SHEET |
| d-TN-100 | TECHNOLOGY - OVERALL |
| d-TN-101 | TECHNOLOGY - KITCHEN |
| d-TN-500 | TECHNOLOGY - DETAILS |
| d-TN-600 | TECHNOLOGY - SECURITY DETAILS |




ISSUED FOR BIDDING AND PERMITTING - JULY 18, 2025

FORT BEND INDEPENDENT SCHOOL DISTRICT

## ADMINISTRATION

| | |
|---|---|
| DR. MARCELL SMITH | SUPERINTENDENT OF FBISD |
| DR. ANDRIA SCHUR, Ed.D. | CHIEF OF SCHOOLS |

## BOARD OF TRUSTEES

| | |
|---|---|
| KRISTIN K. TASSIN | PRESIDENT |
| RICK GARCIA | VICE PRESIDENT |
| DAVID HAMILTON | SECRETARY |
| ANGIE HANAN | BOARD MEMBER |
| ADAM SCHOOF | BOARD MEMBER |
| DR. SHIRLEY ROSE-GILLIAM | BOARD MEMBER |
| SONYA JONES | BOARD MEMBER |

## PROJECT DESIGN TEAM


PROGRAM MANAGEMENT
FBISD 2023 Bond Team
2323 Texas Parkway
Missouri City, TX 77489
Phone Number: 281-327-5481

ARCHITECT
MWA Architects
11767 Katy Freeway, Suite 430
Houston, Texas 77079
Phone Number: 713-782-8188

FOOD SERVICE
Food Design Professionals
26215 Oak Ridge Drive
The Woodlands, Texas 77380
Phone Number: 281-350-2323

MEP ENGINEERS
Stanton Engineering Group
1300 W. Sam Houston Pkwy South, Suite 121
Houston, Texas 77042
Phone Number: 713-300-9292

STRUCTURAL ENGINEER
Stanley Spurling & Hamilton
3301 Edloe Street, Suite 200
Houston, Texas 77027
Phone Number: 713-776-9433


d

PART 1 - GENERAL

1.1 GENERAL DEMOLITION NOTES

A. VERIFY EXISTING SITE AND BUILDING CONDITIONS IN FIELD PRIOR TO BIDDING. NOTIFY ARCHITECT OF ANY DISCREPANCIES PRIOR TO BIDDING.

B. CONTRACTOR SHALL COORDINATE WITH OWNER THE SALVAGE OF ITEMS, FURNITURE AND EQUIPMENT INDICATED TO BE REMOVED.

C. CLAIMS FOR ADDITIONAL COST OR TIME DUE TO EXISTING CONDITIONS THAT COULD HAVE BEEN REASONABLY ANTICIPATED DURING A SITE VISIT BY THE CONTRACTOR PRIOR TO BIDDING WILL NOT BE APPROVED.

D. PROTECT EXISTING FINISHES SHOWN TO REMAIN DURING CONSTRUCTION TO PREVENT DAMAGE. REPAIR OR REPLACE DAMAGED MATERIALS AND FINISHES TO MATCH EXISTING AT NO ADDITIONAL COST TO FORT BEND ISD (OWNER).

E. EXISTING AREAS REQUIRING MINOR DEMOLITION OR REPAIR FOR EXECUTION OF WORK SHALL BE REPAIRED TO MATCH EXISTING ADJACENT MATERIALS, UNLESS NOTED OTHERWISE.

F. DO NOT DAMAGE CASEWORK AND EQUIPMENT NOT DESIGNATED TO BE REMOVED OR RELOCATED.EXISTING CASEWORK SHALL REMAIN THE PROPERTY OF THE OWNER.

G. CONTRACTOR TO VERIFY LOCATION OF ELEC. SWITCHES, OUTLETS, GRILLES, CLEAN-OUTS, COVER PLATES, ACCESS DOORS, AND OTHER EQUIPMENT AND DEVICES THAT MAY CONFLICT WITH THE RENOVATION AND NEW CONSTRUCTION OF WALLS, FLOORS, AND CEILINGS PRIOR TO COMMENCEMENT OF WORK. CONTRACTOR SHALL LIKEWISE CONFIRM THAT ELECTRICAL CONDUIT ROUTING SHALL BE CONCEALED WITHIN WALLS. NOTIFY ARCHITECT IF WALL THICKNESS WILL NOT ALLOW FOR CONCEALMENT.

H. REMOVE ANY EXISTING CORNER GUARDS IN THE KITCHEN AREA.

I. PRIOR TO EXECUTION OF DEMOLITION WORK, SCHEDULE A WALK-THROUGH WITH OWNER AND ARCHITECT TO CONFIRM SCOPE OF WORK AND TO REVIEW EXISTING CONDITIONS.

J. EXISTING FLOOR FINISHES AND ACOUSTIC CEILING TILE TO BE REMOVED THROUGHOUT.

K. REFER TO MEP DRAWINGS FOR DEMOLITION AND ALTERATION OF UTILITIES.

L. AT ALL EXISTING WALLS REQUIRING DEMOLITION TO INSTALL NEW PIPING BEHIND SINKS, CUT AND PATCH WALLS AS REQUIRED TO MATCH ADJACENT SURFACE.

M. CLEAN AND PREPARE SUBFLOOR FOR INSTALLATION OF NEW FLOOR FINISH.

N. DEMOLITION ACTIVITIES SHALL BE PERFORMED AS TO PRODUCE MINIMAL DISTURBANCE TO EXISTING FACILITY OCCUPANTS. MINIMIZE EXCESSIVE AND PROLONGED NOISE LEVELS AND DUST.

O. ASBESTOS-CONTAINING MATERIALS. REFER TO SPECIFICATION 02 26 23 FOR ASBESTOS INFORMATION APPLICABLE TO KITCHEN AREAS. FORT BEND ISD HAS RETAINED A SEPARATE ENVIRONMENTAL CONSULTANT FOR THE REMOVAL OF ASBESTOS. GC TO COORDINATE WITH ENVIRONMENTAL CONSULTANT TO CARRY OUT ASBESTOS ABATEMENT FOR ALL AFFECTED KITCHEN AREAS.

1.2 FLOOR PLAN GENERAL NOTES

A. FIELD VERIFY EXISTING CONDITIONS PRIOR TO GENERATING SHOP DRAWINGS AND FABRICATION OF EQUIPMENT.
B. FLOOR FINISH CHANGES SHALL OCCUR AT THE CENTERLINE OF DOORS UNLESS NOTED OTHERWISE, FLOOR FINISH CHANGES SHALL HAVE THRESHOLDS OR REDUCERS STRIPS.
C. DOORS THAT ARE TO BE REPLACED AND INSTALLED IN EXISTING FRAMES SHALL BE MACHINED FOR HARDWARE DIMENSIONS AT EXISTING FRAMES, CONTRACTOR SHALL FIELD VERIFY FRAME CONDITIONS AND DIMENSIONS.
D. CONTRACTOR TO PROVIDE SHEET METAL REINFORCING STRAP AS REQUIRED FOR MOUNTING OF ALL GRAB BARS, CABINETS, MIRRORS, SHELVING, ETC.
E. SAW CUT AND REMOVE EXISTING SLAB AND FLOOR FINISHES AS REQUIRED TO INSTALL NEW PLUMBING LINES, FLOOR DRAINS, PLUMBING FIXTURES, OR ELECTRICAL ITEMS. SPLICE NEW REINFORCING BARS DOWELED INTO EXISTING CONCRETE, AND PROVIDE NEW VAPOR RETARDER AND WATERSTOPS, AND PATCH W/ 3000 PSI CONCRETE AFTER INSTALLATION OF UTILITIES AND FIXTURES. PREPARE CONCRETE TO RECEIVE NEW FINISH.
F. COORDINATE HOUSEKEEPING PAD DIMENSIONS AND LOCATIONS WITH EQUIPMENT TO BE INSTALLED. HOUSEKEEPING PADS SHALL BE A MIN. OF 4" THICK REINF. W/ #3 BARS AT 15" O.C. BOTH WAYS. PROVIDE 1" BY 45-DEGREE CHAMFERED EDGES.

1.3 COMPLETE PERFORMANCE

L. THE CONTRACTOR SHALL FURNISH AND INSTALL ALL ITEMS SPECIFIED HEREIN AND AS INDICATED ON THE DRAWINGS. THE CONTRACTOR SHALL ALSO FURNISH AND INSTALL ALL ITEMS NECESSARY TO MAKE THE SYSTEMS FUNCTION WHICH MAY BE REASONABLY IMPLIED AS ESSENTIAL, WHETHER MENTIONED IN THE CONTRACT DOCUMENTS OR NOT.

M. WORK SHALL BE EXECUTED IN STRICT ACCORDANCE WITH THE BEST PRACTICE OF THE TRADES IN A THOROUGH, SUBSTANTIAL AND WORKMANLIKE MANNER BY COMPETENT WORKMEN.

1.4 SITE FAMILIARIZATION

A. GENERAL: BECOME FAMILIAR WITH THE DRAWINGS AND SPECIFICATIONS, EXAMINE THE PREMISES, AND UNDERSTAND THE CONDITIONS UNDER WHICH THE CONTRACT SHALL BE PERFORMED, PRIOR TO SUBMITTING A BID.

B. SITE: BE INFORMED OF THE SITE CONDITIONS, VERIFY LOCATIONS OF NEW AND EXISTING EQUIPMENT, AND DETERMINE EXACT REQUIREMENTS FOR CONNECTIONS.

C. COORDINATION: TENDER OF A PROPOSAL FOR THIS PROJECT INFERS THAT THE CONTRACTOR HAS VISITED THE SITE AND HAS BECOME FAMILIAR WITH THE DRAWINGS, SPECIFICATIONS, AND SITE CONDITIONS AND HAS INCLUDED IN HIS PROPOSAL, ALL WORK NECESSARY TO PROPERLY INSTALL COMPLETE AND FUNCTIONING SYSTEMS ON THE PROJECT. FAILURE TO COMPLY WITH THIS REQUIREMENT SHALL NOT BE CONSIDERED JUSTIFICATION FOR THE OMISSION OR FAULTY INSTALLATION OF ANY WORK COVERED BY THE CONTRACT DOCUMENTS.

1.5 CODES AND STANDARDS

A. GENERAL: ALL WORK SHALL COMPLY WITH THE MOST RECENTLY REVISED VERSIONS OF ALL APPLICABLE LAWS, RULES, REGULATIONS AND ORDINANCES OF ALL FEDERAL, STATE AND LOCAL AUTHORITIES AND APPLICABLE UTILITIES. NONE OF THE TERMS OR PROVISIONS OF THIS SPECIFICATION SHALL BE CONSTRUED AS WAIVING ANY PART OF THE LAWS, RULES, REGULATIONS OR REQUIREMENTS OF THESE AUTHORITIES.

B. CONFLICT: IN THE EVENT OF CONFLICT BETWEEN THE CONTRACT DOCUMENTS AND THE LOCAL ENFORCING AUTHORITY, THE LATTER SHALL RULE. ANY MODIFICATIONS RESULTING THEREFROM SHALL BE MADE WITHOUT ANY ADDITIONAL COST TO THE OWNER OR ARCHITECT. THIS CONTRACTOR SHALL REPORT ANY SUCH MODIFICATIONS TO THE ARCHITECT AND SECURE HIS APPROVAL PRIOR TO PROCEEDING WITH THE WORK.

C. PRECEDENCE: WHERE CONTRACT DOCUMENT REQUIREMENTS EXCEED THE REQUIREMENTS OF THE CODES AND STANDARDS, THE CONTRACT DOCUMENTS SHALL TAKE PRECEDENCE PROVIDED THEY ARE NOT IN CONFLICT WITH THOSE CODES AND STANDARDS.

D. APPROVAL LABELS: ALL ITEMS OF EQUIPMENT AND ALL MATERIALS FOR WHICH APPROVED STANDARDS HAVE BEEN ESTABLISHED BY UNDERWRITERS' LABORATORIES, INC. (UL), FACTORY MUTUAL (FM), CERTIFIED BALLAST MANUFACTURER (CBM), ELECTRICAL TESTING LABORATORY (ETL), NATIONAL MANUFACTURERS ASSOCIATION (NEMA), AMERICAN STANDARD CODES, ASME, AGA, AMCA, ASA, ANSI, ASHRAE, AND ARI SHALL BE SO APPROVED AND SHALL BEAR APPROVAL LABELS ATTESTING TO SAME.

1.6 DRAWINGS AND SPECIFICATIONS

A. DRAWINGS: THE SET OF ORIGINAL DRAWINGS HAS BEEN MODIFIED AND INDICATE APPROXIMATE EXISTING LOCATIONS OF THE FLOOR FINISH ITEMS. ALL ITEMS ARE SHOWN APPROXIMATELY TO SCALE. FIELD VERIFY CONDITIONS.

B. SPECIFICATIONS: THE SPECIFICATIONS ARE INTENDED TO SUPPLEMENT THE DRAWINGS AND IT IS NOT IN THE SCOPE OF THE SPECIFICATIONS TO MENTION ANY PART OF THE WORK THAT THE DRAWINGS ARE COMPETENT TO FULLY EXPLAIN. CONVERSELY, ANY PART OF THE WORK THAT THE SPECIFICATIONS ARE COMPETENT TO FULLY EXPLAIN MAY NOT BE MENTIONED ON THE DRAWINGS. DRAWINGS AND SPECIFICATIONS ARE COMPLIMENTARY/SUPPLEMENTARY DOCUMENTS TO EACH OTHER.

C. DISAGREEMENT: DISAGREEMENT BETWEEN THE DRAWINGS AND SPECIFICATIONS OR WITHIN THE DRAWINGS OR SPECIFICATIONS SHALL BE ESTIMATED AND/OR BID USING THE BETTER QUALITY OR GREATER QUANTITY OF MATERIAL OR INSTALLATION, AND A CLARIFICATION REQUEST FOR INFORMATION SHALL BE MADE TO THE ARCHITECT IN A TIMELY MANNER AFTER THE PROJECT IS UNDER CONTRACT.

1.7 DISCREPANCIES

A. CLARIFICATION: CLARIFICATION OF SIGNIFICANT COST MATTERS SHALL BE OBTAINED BEFORE SUBMITTING A PROPOSAL FOR THE WORK AS TO DISCREPANCIES OR OMISSIONS FROM THE CONTRACT DOCUMENTS OR QUESTIONS AS TO THE INTENT THEREOF.

B. INTERPRETATIONS: SHOULD ANY DOUBT OR QUESTION ARISE RESPECTING THE TRUE MEANING OF DRAWINGS OR SPECIFICATIONS, REFERENCE SHALL BE MADE TO THE ARCHITECT, WHOSE WRITTEN DECISION SHALL BE FINAL AND CONCLUSIVE. NO ALLEGED STATEMENT BY THE ARCHITECT WILL BE ACCEPTED AS AN EXCUSE FOR NON-COMPLIANCE OR INFERIOR WORK.

C. CONTRACTOR AGREEMENT: CONSIDERATION WILL NOT BE GRANTED FOR MISUNDERSTANDING OF THE AMOUNT OF WORK TO BE PERFORMED. TENDER OF A PROPOSAL CONVEYS FULL CONTRACTOR AGREEMENT OF THE ITEMS AND CONDITIONS SPECIFIED, SHOWN, SCHEDULED, OR REQUIRED BY THE NATURE OF THE PROJECT, AND ALL COSTS ARE INCLUDED IN THE PROPOSAL.

1.8 REQUESTS FOR INFORMATION (RFI)

A. GENERAL: SUBMIT ALL CONTRACTOR REQUESTS FOR INFORMATION (RFI) IN WRITING TO THE ARCHITECT FOR RESPONSE. SUBMIT RFI ON A STANDARD FORM THAT HAS A SPACE FOR THE REQUESTED INFORMATION AND THE ARCHITECT'S RESPONSE.
B. SOLUTION PROPOSAL: IN GENERAL, THE CONTRACTOR SHALL PROPOSE SOLUTIONS TO IDENTIFY PROBLEMS FOR REVIEW AND APPROVAL OF THE ARCHITECT. THE RFI SHALL INCLUDE HAND SKETCHES, MARKED DRAWING PRINTS, EQUIPMENT CUTSHEETS, DRAWING AND SPECIFICATION REFERENCES, AND ANY OTHER BACK-UP INFORMATION, ETC., AS REQUIRED TO SUFFICIENTLY EXPLAIN THE PROBLEM AND PROPOSED SOLUTION.

1.9 QUALITY ASSURANCE

A. GENERAL: MATERIALS AND EQUIPMENT SHALL BE NEW, OF BEST GRADE AND QUALITY, AND STANDARD PRODUCTS OF REPUTABLE MANUFACTURERS REGULARLY ENGAGED IN THE PRODUCTION OF SUCH MATERIALS AND EQUIPMENT.
B. WORKMANSHIP: WORK SHALL BE EXECUTED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE BEST PRACTICE OF THE TRADES IN A THOROUGH, SUBSTANTIAL, WORKMANLIKE MANNER BY COMPETENT WORKMEN, PRESENTING A NEAT APPEARANCE WHEN COMPLETED.
C. JUDGMENT: IN ALL CASES, THE ARCHITECT SHALL BE THE SOLE JUDGE OF THE QUALITY AND EQUIVALENCE OF MANUFACTURERS, PRODUCTS, MATERIALS, AND METHODS.
D. MANUFACTURERS/PRODUCTS/MATERIALS/METHODS: MANUFACTURERS, PRODUCTS, MATERIALS, AND METHODS DESCRIBED IN THE VARIOUS SECTIONS OF THE SPECIFICATIONS AND INDICATED ON THE DRAWINGS ARE INTENDED TO ESTABLISH A STANDARD OF QUALITY ONLY, IT IS NOT THE INTENTION OF THE ARCHITECT TO DISCRIMINATE AGAINST ANY MANUFACTURER, PRODUCT, MATERIAL, OR METHOD THAT IS EQUAL TO THE STANDARDS AS INDICATED AND/OR SPECIFIED, NOR IS IT INTENDED TO PRECLUDE OPEN, COMPETITIVE BIDDING. THE FACT THAT A SPECIFIC MANUFACTURER IS LISTED AS AN ACCEPTABLE MANUFACTURER SHALL NOT BE INTERPRETED TO MEAN THAT THE MANUFACTURER'S STANDARD PRODUCT WILL MEET THE REQUIREMENTS OF THE PROJECT DESIGN, SPECIFICATIONS, AND SPACE CONSTRAINTS.
    1. WHEREVER A DEFINITE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS SPECIFIED AND THERE IS NOT A STATEMENT THAT ANOTHER MANUFACTURER, PRODUCT, MATERIAL, OR METHOD WILL BE ACCEPTABLE, IT IS THE INTENTION OF THE ARCHITECT THAT THE SPECIFIED MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS THE ONLY ONE THAT SHALL BE USED WITHOUT PRIOR APPROVAL.
    2. WHEREVER A DEFINITE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS SPECIFIED AS "NO SUBSTITUTE", IT IS THE INTENTION OF THE ARCHITECT THAT THE LISTED ITEM IS THE ONLY ONE ACCEPTABLE.
E. COORDINATION: WHERE EQUIPMENT IS USED ON THE PROJECT, IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR OR SUBCONTRACTOR INVOLVED TO VERIFY THAT THE EQUIPMENT WILL FIT IN THE SPACE AVAILABLE, INCLUDING ALL REQUIRED CODE AND MAINTENANCE CLEARANCES, AND TO COORDINATE ALL EQUIPMENT REQUIREMENTS AND PROVISIONS WITH THE SYSTEM DESIGN, ALL AFFECTED DIVISIONS, AND ALL OTHER CONTRACTORS. WHERE THE USE OF ALTERNATE OR SUBSTITUTE MATERIALS AFFECTS THE COST OF PROVISIONS MADE BY OTHER CONTRACTORS, THE CONTRACTOR PROVIDING THE ALTERNATE OR SUBSTITUTE SHALL BE RESPONSIBLE FOR THE OTHER CONTRACTOR'S COST ADJUSTMENT. THERE SHALL BE NO ADDITIONAL COST TO THE OWNER OR ARCHITECT DUE TO THE USE OR ACCEPTANCE OF ANY ALTERNATE OR SUBSTITUTE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD.

1.10 PRIOR APPROVAL

A. SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES: THE CONTRACTOR'S SUBMITTAL AND ARCHITECT'S ACCEPTANCE OF SHOP DRAWINGS, PRODUCT DATA, OR SAMPLES THAT RELATE TO CONSTRUCTION ACTIVITIES NOT COMPLYING WITH THE CONTRACT DOCUMENTS DOES NOT CONSTITUTE AN ACCEPTABLE OR VALID REQUEST FOR SUBSTITUTION, NOR DOES IT CONSTITUTE APPROVAL.

1.11 COORDINATION

A. BY SUBMITTING SHOP DRAWINGS ON THE PROJECT, THIS CONTRACTOR IS INDICATING THAT ALL NECESSARY COORDINATION HAS BEEN COMPLETED AND THAT THE SYSTEMS, PRODUCTS AND EQUIPMENT SUBMITTED CAN BE INSTALLED IN THE BUILDING AND WILL OPERATE AS SPECIFIED AND INTENDED, IN FULL COORDINATION WITH ALL OTHER DISCIPLINES.

1.12 SHOP DRAWINGS AND SUBMITTALS

A. GENERAL: AFTER THE CONTRACT IS AWARDED BUT PRIOR TO PROCEEDING WITH THE WORK REQUIRING SHOP DRAWING REVIEW, THE CONTRACTOR SHALL OBTAIN COMPLETE SHOP DRAWINGS AND PRODUCT DATA FROM THE MANUFACTURERS, SUPPLIERS, VENDORS, AND SUB- CONTRACTORS FOR ALL MATERIALS AND EQUIPMENT SPECIFIED HEREIN, AND MAKE FORMAL SUBMISSION TO THE ARCHITECT, A MINIMUM PERIOD OF TWO (2) WEEKS SHOULD BE ALLOWED IN THE CONSTRUCTION SCHEDULE EXCLUSIVE OF TRAVEL TIME FOR THE ARCHITECTS REVIEW.
B. CERTIFICATION: EACH CONTRACTOR RESPONSIBLE FOR THE WORK SHALL REVIEW AND CERTIFY THE SHOP DRAWING, SUBMITTAL AND/OR PRODUCT DATA TO BE IN FULL COMPLIANCE WITH THE REQUIREMENTS OF THE CONTRACT DOCUMENTS.
C. THE ARCHITECTS REVIEW OF SHOP DRAWINGS AND SUBMITTAL DATA SHALL NOT RELIEVE THE CONTRACTOR OF THE RESPONSIBILITY FOR DIMENSIONS OR ERRORS THAT MAY BE CONTAINED THEREIN, OR FOR DEVIATIONS FROM ANY REQUIREMENTS OF THE CONTRACT DOCUMENTS. IT SHALL BE CLEARLY UNDERSTOOD THAT THE ARCHITECTS NOTING SOME ERRORS BUT OVERLOOKING SOME OTHERS DOES NOT GRANT THE CONTRACTOR PERMISSION TO PROCEED IN ERROR. REGARDLESS OF ANY INFORMATION CONTAINED IN THE SHOP DRAWING OR PRODUCT DATA, THE CONTRACT DOCUMENTS SHALL GOVERN THE WORK AND ARE NEITHER WAIVED NOR SUPERSEDED IN ANY WAY BY THE REVIEW OF SHOP DRAWINGS, PRODUCT DATA AND SAMPLES.

1.13 EXECUTION AND COORDINATION OF WORK

A. MANUFACTURER'S RECOMMENDATIONS: WITH EXCEPTIONS AS SPECIFIED AND/OR INDICATED ON THE DRAWINGS OR IN THE SPECIFICATIONS, APPLY, INSTALL, ERECT, USE, CLEAN, AND CONDITION, MANUFACTURED ARTICLES, MATERIALS, AND EQUIPMENT PER MANUFACTURER'S CURRENT PRINTED RECOMMENDATIONS. KEEP COPIES OF SUCH PRINTED RECOMMENDATIONS AT JOB SITE AND MAKE THEM AVAILABLE AS REQUIRED.

1.14 SUPERVISION

A. A COMPETENT SUPERINTENDENT APPROVED BY THE ARCHITECT, SHALL BE KEPT BY THE CONTRACTOR AT THE BUILDING TO RECEIVE INSTRUCTIONS AND TO ACT FOR THE CONTRACTOR. ONCE THE SUPERINTENDENT HAS BEEN APPROVED, NO CHANGE SHALL BE MADE WITHOUT APPROVAL OF ARCHITECT, REPRESENTATIVES OF THE OWNER, ARCHITECT SHALL HAVE THE RIGHT TO OBSERVE THE WORK AT ANY TIME. THE CONTRACTOR SHALL HAVE A REPRESENTATIVE AVAILABLE WHEN HIS WORK IS BEING OBSERVED AND HE SHALL GIVE ASSISTANCE AS MAY BE REQUIRED TO THE ARCHITECT'S REPRESENTATIVE.

B. THE PROJECT SHALL BE CONSTRUCTED BY EMPLOYEES OF THE CONTRACTOR OR BY WORKERS UNDER HIS SUPERVISION. ANY SUBCONTRACTORS EMPLOYED BY THE CONTRACTOR SHALL BE APPROVED BY THE OWNER'S REPRESENTATIVE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL EQUIPMENT, MATERIAL AND WORK PERFORMED BY ANY SUBCONTRACTOR.

1.15 STORAGE AND PROTECTION OF MATERIALS

A. THE CONTRACTOR SHALL PROPERLY STORE ALL MATERIAL AND EQUIPMENT AT THE JOBSITE AND PROTECT IT FROM THE ELEMENTS AND FROM DAMAGE. ANY EQUIPMENT DAMAGED DUE TO IMPROPER PROTECTION SHALL BE REPLACED BY THE CONTRACTOR AT HIS EXPENSE.

B. THE CONTRACTOR SHALL PROTECT THE WORK, EQUIPMENT, AND MATERIAL OF ALL OTHER TRADES FROM DAMAGE BY HIS WORK OR OTHER WORKMEN, AND SHALL MAKE GOOD ALL DAMAGE THUS CAUSED.

C. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL WORK, MATERIALS, AND EQUIPMENT UNTIL FINALLY INSPECTED, TESTED, AND ACCEPTED. PROTECT WORK AGAINST THEFT, INJURY OR DAMAGE. AND CAREFULLY STORE MATERIAL AND EQUIPMENT RECEIVED ON SITE WHICH ARE NOT IMMEDIATELY INSTALLED, CLOSE OPEN ENDS OF WORK WITH TEMPORARY COVERS OR PLUGS DURING CONSTRUCTION TO PREVENT ENTRY OF OBSTRUCTING MATERIAL. THE CONTRACTOR SHALL COVER AND PROTECT IN AN ACCEPTABLE MANNER TO THE OWNER, EXISTING REMAINING EQUIPMENT AND MATERIALS.

D. IF ANY MATERIAL OR EQUIPMENT IS RECEIVED PRIOR TO THE TIME IT IS REQUIRED, THE CONTRACTOR SHALL BE RESPONSIBLE FOR ITS PROPER STORAGE AND PROTECTION UNTIL SUCH TIME AS IT MAY BE REQUIRED. THE CONTRACTOR SHALL PAY FOR ALL COSTS OF DEMURRAGE OR STORAGE.

1.16 DRAYAGE AND HAULING

A. THE CONTRACTOR SHALL KEEP THE JOBSITE FREE FROM THE ACCUMULATION OF TRASH AND CONSTRUCTION DEBRIS, REGARDLESS OF WHICH SUBCONTRACTOR MAY BE RESPONSIBLE.

1.17 CUTTING AND PATCHING

A. WHERE IT BECOMES NECESSARY TO CUT THROUGH ANY WALL, FLOOR OR CEILING TO PERMIT THE INSTALLATION OF ANY WORK, OR TO REPAIR ANY DEFECTS THAT MAY APPEAR, THE CUTTING SHALL BE PERFORMED UNDER THE SUPERVISION OF THE GENERAL CONTRACTOR. INFORM THE OWNER'S REPRESENTATIVE BEFORE ANY WORK COMMENCES. NO STRUCTURAL MEMBER SHALL BE ALTERED WITHOUT THE WRITTEN PERMISSION OF THE ARCHITECT.

B. VERIFICATION: SHOULD A QUESTION ARISE REGARDING THE ACCEPTABLE LEVEL OF NOISE OR VIBRATION IN A PARTICULAR SPACE OR PIECE OF EQUIPMENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING THE SERVICES OF AN APPROVED ACOUSTICAL CONSULTANT TO DETERMINE ACTUAL NOISE/VIBRATION CONDITIONS.

## 01 GENERAL NOTES

SEQUENCE OF CONSTRUCTION (AS OF 01/27/2025) Schools will be renovated in groups as shown. These groups contain two or three major kitchen renovations and some cafeteria/miscellaneous renovations. This sequencing is critical for FBISD food service to provide the uninterrupted meal services to their schools.

| | |
|---|---|
| GROUPING 1 | AUSTIN PARKWAY ES + SUGAR MILL ES, kitchen renovations. *Plus: COMMON WEALTH ES, CONERSTONE ES misc. renovations.* |
| GROUPING 2 | SETTLERS WAY ES + PALMER ES kitchen renovations. *Plus: SULLIVAN ES, SIENNA CROSSING ES, HERITAGE ROSE ES misc. renovations* |
| GROUPING 3 | HUNTER'S GLEN ES + HIGHLANDS ES + PECAN GROVE ES kitchen renovations. *Plus: RIDGEGATE ES, DULLES ES misc. renovations.* |

## 03 PROJECT SCHEDULE

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

d

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
COMMONWEALTH ELEMENTARY SCHOOL
4909 COMMONWEALTH BLVD
SUGAR LAND, TX 77479

SEAL

REGISTERED ARCHITECT
ROSS ALEXANDER
#29651
STATE OF TEXAS


7/15/2025


ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING


GENERAL NOTES AND ABBREVIATIONS

A00-01




## 2 DEMO REFLECTED CEILING PLAN

SCALE: 1/8" = 1'-0"




## 1 DEMO PLAN

SCALE: 1/8" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

d

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
COMMONWEALTH ELEMENTARY SCHOOL
4909 COMMONWEALTH BLVD
SUGAR LAND, TX 77479

SEAL

7/15/2025

ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

DEMO PLAN, DEMO RCP

d-D.101

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\D-Commonwealth ES\DEMO PLAN, DEMO RCP .dwg Jul 23, 2025 - 11:25am

## Project Information

PROJECT: COMMONWEALTH ELEMENTARY SCHOOL
LOCATION: 4909 COMMONWEALTH BLVD
SUGAR LAND, TX 77479

REVISED SCOPE OF WORK: REPLACE CEILING TILE IN GYMNASIUM AND CAFETERIA AREAS, REPLACE DAMAGED MOVEABLE PARTITION PANELS. SCOPE REVISION DATED 08/20/24

## City of Sugar Land Adopted Building Codes

2021 INTERNATIONAL BUILDING CODE (AS AMENDED)
2021 INTERNATIONAL FIRE CODE (AS AMENDED)
2021 INTERNATIONAL MECHANICAL CODE (AS AMENDED)
2021 INTERNATIONAL PLUMBING CODE (AS AMENDED)
2021 INTERNATIONAL FUEL GAS CODE (AS AMENDED)
2023 NATIONAL ELECTRICAL CODE *PER STATE OF TEXAS ADOPTION. (AS AMENDED)
2021 INTERNATIONAL ENERGY CONSERVATION CODE
2021 EXISTING BUILDING CODE (AS AMENDED)

* ALTHOUGH THE CITY OF SUGARLAND HAS ADOPTED THE 2021 NATIONAL ELECTRIC CODE, THE STATE OF TEXAS HAS ADOPTED THE 2023 NATIONAL ELECTRICA CODE, THEREFORE THE CITY ENFORCES CODE COMPLIANCE WITH THIS NEWER CODE.

## Chapter 3 - Use and Occupancy Classification

GROUP E (EDUCATIONAL - IBC 2021 SECTION 305)
EXISTING ELEMENTARY SCHOOL, FULLY SPRINKLERED BUILDING, PER 302.1

## Chapter 5 - General Building Heights and Area

ALLOWABLE BUILDING HEIGHT:
TWO STORIES W/ 55 FT MAX. HEIGHT FOR GROUP E
(AS ALLOWED BY TABLE 504.3)

EXISTING BUILDING HEIGHT PROVIDED:
HEIGHT TO HIGHEST ROOF: 36'-0"

INCIDENTAL USE SEPARATION:
SEPARATIONS REQUIRED: INCIDENTAL USE AREAS, AS PER TABLE 509.4, STORAGE ROOMS OVER 100 S.F. ARE REQUIRED TO BE ONE HOUR RATED OR HAVE AUTOMATIC FIRE EXTINGUISHING SYSTEM.

INCIDENTAL USE ROOM AREAS PROVIDED WITH EXISTING AUTOMATIC SPRINKLER SYSTEM.

TOTAL EXISTING BUILDING AREA IS 80,729 SF.

## Chapter 6 - Construction Type Fire Resistance Ratings

EXISTING CONSTRUCTION: TYPE IIB

TABLES 601 AND 602

| BUILDING ELEMENTS | REQUIRED (FOR TYPE IIB) | PROVIDED |
|---|---|---|
| STRUCTURAL FRAME (TABLE 601) | NO RATING | NO RATING |
| EXTERIOR BEARING WALLS (TABLE 601) | NO RATING | NO RATING |
| INTERIOR BEARING WALLS (TABLE 601) | NO RATING | NO RATING |
| EXTERIOR NON-BEARING WALLS (TABLE 602) | NO RATING | NO RATING (WALLS GREATER THAN 30' FROM PROPERTY LINE) |
| INTERIOR NON-BEARING WALLS (TABLE 601) | NO RATING | NO RATING |
| FLOOR CONSTRUCTION (TABLE 601) | NO RATING | NO RATING |
| ROOF CONSTRUCTION (TABLE 601) | NO RATING | NO RATING |

## Chapter 9 - Fire Protection Systems

AUTOMATIC SPRINKLER SYSTEM: EXISTING SPRINKLER SYSTEM PROVIDED THROUGHOUT.

## Chapter 29 - Plumbing


Fixture Count per Table 2902.1
Occupant Load Basis:

12 Occupants

| | Total Fixtures REQUIRED | Total Fixtures PROVIDED |
|---|---|---|
| Unisex: | | |
| W.C. | 1 per 50 | 1 |
| lavatories | 1 per 50 | 1 |
| Drinking Fountains | 1 per 100 | 2 |

# 2 CODE ANALYSIS

| PHASING CHART FOR ALL SCHOOLS | | |
|---|---|---|
| PHASE 1 | | |
| **SCHOOLS** | **FREEZER START DATE :** | **FREEZER END DATE :** |
| AUSTIN PARKWAY ES | 11/7/2025 | 5/13/2026 |
| SUGAR MILL ES | | |
| ***COMMONWEALTH ES*** | | |
| CONERSTONE ES | | |
| PHASE 2 | | |
| SETTLERS WAY ES | 5/29/2026 | 10/28/2026 |
| PALMER ES | | |
| SULLIVAN ES | | |
| SIENNA CROSSING ES | | |
| HERITAGE ROSE ES | | |
| **PHASE 3** | | |
| HUNTERS GLEN ES | 3/19/2027 | 3/19/2027 |
| PECAN GROVE ES | | |
| HIGHLANDS ES | | |
| DULLES ES | | |




# 1 OVERALL FLOOR PLAN

SCALE: 1/16" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

d

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
COMMONWEALTH ELEMENTARY SCHOOL
4909 COMMONWEALTH BLVD
SUGAR LAND, TX 77479

SEAL

7/15/2025



ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING


OVERALL FLOOR PLAN

d-A.201


F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\D-Commonwealth ES\d-A 201 FLOOR PLAN.dwg Jul 23, 2025 - 11:25am





4 CAFETERIA SIDE OF WALL (NEW CONSTRUCTION)
SCALE: 3/16" = 1'-0"





5 GYM SIDE OF WALL (NEW CONSTRUCTION)
SCALE: 3/16" = 1'-0"




3 SECTION AT FOLDING PARTITION
SCALE: 1"=1'-0"




1 FLOOR PLAN
SCALE: 1/8"=1'-0"




2 REFLECTED CEILING PLAN
SCALE: 1/8"=1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

d

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
COMMONWEALTH ELEMENTARY SCHOOL
4909 COMMONWEALTH BLVD
SUGAR LAND, TX 77479


SEAL
REGISTERED ARCHITECT
22651
STATE OF TEXAS
7/15/2025

MWA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

CAFETERIA
ENLARGED RCP &
PLAN
D-A4.01

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\d-A4.01.dwg, Jul 23, 2025 - 11:26am




## 2 OVERALL FLOOR PLAN

SCALE: 1" = 50'- 0"

## SYMBOL LEGEND


| | |
|---|---|
| | SIMPLEX/DUPLEX/QUAD – 5361/2 REC |
| GFI | DUPLEX W/ GFCI PROTECTION–P&S 2097 |
| | J–BOX |
| | CEILING MOUNTED J–BOX |
| | MOTOR |
| | HEAVY DUTY, NON–FUSED DISCONNECT. MIN RATING OF CIRCUIT OCPD/VOLTAGE. |
| | ELECTRICAL PANEL |
| | HOMERUN TO CIRCUIT NOTED |
| E | EXISTING DEVICES TO REMAIN |
| R | EXISTING DEVICES TO BE RELOCATED |
| D | EXISTING DEVICES TO BE DEMO/REMOVED |
| REP | EXISTING DEVICES TO BE REPLACED |
| S | INDICATES SURFACE MOUNTED |
| SR | INDICATES SURFACE RACEWAY |
| * | INDICATES ABOVE COUNTER DEVICE |
| + | INDICATES DEVICE AT +30–60" |
| ++ | INDICATES DEVICE AT +80–96" |
| CLG | INDICATES DEVICES MOUNTED IN CEILING |
| WP | INDICATES WEATHERPROOF COVER |
| 3R | INDICATES 3R RATED DEVICE |
| (E)LA–X | CONNECT(ED) TO EXIST CIRCUIT LA–X |
| (D)LA–X | DEMO PORTION OF EXIST CIRCUIT LA–X |
| (N)LA–X | CONNECT(ED) TO NEW CIRCUIT LA–X |

GENERAL ELECTRICAL NOTES:

1. INSTALL SYSTEM IN ACCORDANCE WITH THE NATIONAL ELECTRIC CODE AS ADOPTED BY THE LOCAL AUTHORITY HAVING JURISDICTION INCLUDING ALL AMENDMENTS.
2. PROVIDE CONDUIT FOR ALL DEVICES INSTALLED IN WALLS.
   - 2.A. 3/4"C FOR POWER AND 1"C FOR LOW VOLTAGE/DATA UNLESS NOTED OTHERWISE.
   - 2.B. PROVIDE PROTECTIVE BUSHING ON END OF ALL LOW VOLTAGE CONDUITS.
   - 2.C. ALL ELECTRICAL HOMERUNS SHALL BE IN CONDUIT, MIN 3/4"C.
   - 2.D. USE INSULATED THROAT FITTINGS FOR CONNECTIONS TO HOUSINGS, BOXES, ENCLOSURES, ETC.
   - 2.E. MAX LENGTH FOR FLEX CONDUIT SHALL BE 6FT AND MIN. SIZE SHALL BE 1/2". ALL FLEX CONDUIT SHALL BE LISTED FOR GROUNDING.
3. CONDUIT TYPES:
   - 3.A. INSIDE BUILDINGS: GALVANIZED STEEL EMT.
     - 3.A.A. ALL LOW VOLTAGE CABLING SHALL BE INSTALLED IN CONDUIT IN EXPOSED CEILING AREAS. ROUTE TO NEAREST ACCESSIBLE CEILING WITH CONTINUOUS PATHWAYS TO LOW VOLTAGE SOURCE/DEVICE.
     - 3.A.B. ALL LOW VOLTAGE CABLING SHALL BE INSTALLED IN CONDUIT ABOVE INACCESSIBLE CEILINGS. ROUTE TO NEAREST ACCESSIBLE CEILING WITH CONTINUOUS PATHWAYS TO LOW VOLTAGE SOURCE/DEVICE.
   - 3.B. NO MC CABLE SHALL BE ALLOWED.
   - 3.C. PROVIDE FLEXIBLE CONNECTIONS TO MOTORS, PUMPS, TRANSFORMERS, OR SIMILAR EQUIPMENT.
4. PROVIDE GALVANIZED STEEL, ONE–PIECE CONSTRUCTION, OUTLET BOXES IN ALL CASES SUITABLE FOR INTENDED USE.
   - 4.A. BOXES OUTSIDE SHALL BE STEEL, NEMA 3 TYPE.
   - 4.B. PROVIDE CEILING BRACKET TO SUPPORT CEILING MOUNTED DEVICES FROM CEILING TEES.
5. 20 AMP, SINGLE PHASE BRANCH CIRCUITS SERVING LIGHTING AND GENERAL RECEPTACLES MAY BE GROUPED IN A SINGLE RACEWAY PROVIDED A NEUTRAL CONDUCTOR IS INSTALLED FOR EACH CIRCUIT REQUIRING A NEUTRAL.
   - 5.A. DO NOT INSTALL MORE THAN FOUR CURRENT CARRYING CONDUCTORS IN A CONDUIT EXCEPT SIX #12 OR #10 CURRENT CARRYING CONDUCTORS MAY BE INSTALLED IN 3/4" OR LARGER CONDUIT FOR 20A CIRCUITS.
   - 5.B. DO NOT INSTALL 480/277 VOLT CONDUCTORS IN THE SAME CONDUIT WITH 240/208/120 VOLT CONDUCTORS.
   - 5.C. DO NOT COMBINE NEUTRALS. PROVIDE DEDICATED NEUTRALS FOR EACH BRANCH CIRCUIT.
   - 5.D. MULTIPLE DEVICES ON A CIRCUIT SUCH AS RECEPTACLES SHALL BE WIRED WITH A PIGTAIL SO THE DEVICE DOES NOT PROVIDE THE CONTINUITY PATH. FEED THROUGH CONNECTIONS FOR GFCI RECEPTACLES SHALL NOT BE USED FOR PROTECTION OF DOWNSTREAM DEVICES.
6. PROVIDE GREEN GROUND WIRE WITH ALL CIRCUITS SIZED PER NEC. BOND GREEN GROUND WIRE TO EACH END OF CONDUIT.
7. PROVIDE J–BOXES, CONDUIT AND SLEEVES THRU ALL FIRE WALLS FOR DATA, TELEPHONE, SECURITY, FIRE ALARM, SOUND SYSTEM, LOW VOLTAGE WIRING, ETC. PROVIDE PROTECTIVE BUSHINGS ON ENDS OF ALL LOW VOLTAGE CONDUITS.
8. PROVIDE PULL BOXES, JUNCTION BOXES, WIRING TROUGHS AND CABINETS WHEREVER REQUIRED FOR PROPER INSTALLATION OF VARIOUS ELECTRICAL SYSTEMS. ALL JUNCTION/PULL BOXES INSTALLED ABOVE ACCESSIBLE CEILINGS SHALL BE MOUNTED SO THAT THE ACCESS PANEL IS NO HIGHER THAN 18" ABOVE THE CEILING.
9. PROVIDE CIRCUIT LABELS IN PERMANENT MARKER ON ALL NEW AND EXISTING J–BOX COVERS UTILIZED IN THE AREA OF RENOVATION.
10. PROVIDE CIRCUIT LABEL ON ALL ABOVE CEILING J–BOXES, EQUIPMENT, ETC. IDENTIFYING THE CIRCUITS CONTAINED/CONNECTED.
11. ALL WIRING SHALL BE 600 VOLT, SOFT DRAWN ANNEALED COPPER, 98% CONDUCTIVITY, CONTINUOUS FROM OUTLET TO OUTLET. MINIMUM WIRE SIZE #12.
    - 11.A. TYPICAL BUILDING WIRE SHALL BE STRANDED TYPE THHN, THWN–2 (WET RATED FOR 90°C), OR XHHW–2. MINIMUM WIRE SIZE SHALL BE #12.
    - 11.B. ALL BUILDING WIRE SHALL BE COLOR CODED WITH THE SAME COLOR CONNECTED TO THE SAME UNGROUNDED PHASE THROUGHOUT THE INSTALLATION MATCHING THE EXISTING BUILDING COLOR CODE SCHEME.
12. WHERE PORTIONS OF INTERIOR RACEWAY SYSTEM ARE EXPOSED TO WIDELY DIFFERENT TEMPERATURES, PROVIDE AIR SEAL PER NEC TO PREVENT CIRCULATION OF AIR FROM WARMER TO COOLER SECTIONS.
13. DRAWINGS, SCHEDULES, NOTES, AND DETAILS ARE INTENDED TO BE COMPLIMENTARY. ANY WORK DESCRIBED IN ANY OF THEM, WILL BE WORK REQUIRED UNDER THIS CONTRACT. WHERE THERE IS A CONFLICT BETWEEN DIFFERENT PORTIONS OF THE DESIGN DOCUMENTS IT SHALL BE CLARIFIED BY RFI. BARRING CLARIFICATION PRIOR TO BIDDING THE MOST EXPENSIVE OPTION SHALL BE INCLUDED AND CLARIFICATION SHALL BE MADE DURING CONSTRUCTION.
14. SHOULD ANY WORK REQUIRED BY THE DRAWINGS AND SPECIFICATIONS BE IN VIOLATION OF ANY FEDERAL, STATE, COUNTY OR CITY LAWS, ORDINANCE OR REGULATION, THOSE LAWS AND REGULATIONS SHALL PREVAIL, AND SHALL BE COMPLIED WITH BY THE CONTRACTOR AS A PART OF THIS WORK WITH NO EXTRA COMPENSATION.
15. ALL MATERIAL MUST BE NEW AND OF GOOD QUALITY AND SHALL BEAR THE STAMP OF APPROVAL OF THE UNDERWRITERS' LABORATORIES, INC. (U.L.).

GENERAL RENOVATION AND REMODELING NOTES:

1. THESE ELECTRICAL DRAWINGS ONLY SHOW SOME EXISTING ELECTRICAL PANELS, DEVICES AND LIGHT FIXTURES IN AREAS OF RENOVATION. ALL OTHER ELECTRICAL EQUIPMENT, WIRING DEVICES, LOW VOLTAGE SYSTEMS, J–BOXES AND CONDUITS SHALL BE LOCATED AND FIELD VERIFIED BY CONTRACTOR.
2. ALL REMOVED DEVICES SHALL BE OFFERED TO THE OWNER AS SALVAGE.
3. RELOCATE CONDUIT AS NECESSARY TO ALLOW NEW OR MODIFIED CONSTRUCTION. RESUPPORT EXISTING CABLING/CONDUIT TO REMAIN TO MEET CURRENTLY ADOPTED CODE REQUIREMENTS. REMOVE ALL ABANDONED CONDUIT AND WIRE. REPAIR EXISTING ELECTRICAL SYSTEMS DAMAGED BY CONSTRUCTION ACTIVITIES.
4. ANY DAMAGE TO EXISTING BUILDING, ELECTRICAL EQUIPMENT, WIRING DEVICES, CONDUIT, WIRING, ETC. SHALL BE REPLACED BY THE CONTRACTOR AT NO COST TO THE OWNER. ALL MATERIALS USED FOR THE REPLACEMENT MUST MEET RENOVATION PROJECT STANDARDS.
5. ELECTRICAL CONTRACTOR SHALL BEGIN FIELD VERIFYING ALL EXISTING BRANCH CIRCUITS FOR EXISTING AREAS TO BE RENOVATED IMMEDIATELY AFTER THE CONTRACT IS ISSUED.
6. ELECTRICAL CONTRACTOR SHALL FIELD VERIFY EXISTING CIRCUITS WITH OWNER'S MAINTENANCE PERSONNEL AFTER NORMAL BUILDING HOURS AS REQUIRED.
7. ANY CIRCUIT OR PARTIAL CIRCUIT TO REMAIN OR BE REUSED SHALL REMAIN ACTIVE.
8. ELECTRICAL CONTRACTOR SHALL INCLUDE COST RELATED TO FIELD VERIFY EXISTING CIRCUITS IN BASE PROPOSAL.
9. FIND AND RECORD ALL EXISTING DEVICES IN CEILINGS, WALLS AND CASEWORK IN AREAS TO BE RENOVATED. PROVIDE A COPY OF THE FIELD VERIFIED DEVICE DRAWINGS TO OWNER PRIOR TO BEGINNING WORK.
10. AT THE END OF THE PROJECT PROVIDE A NEW TYPEWRITTEN AS–BUILT PANEL SCHEDULE FOR ALL PANELS WITH CIRCUITS ADDED, REMOVED, OR MODIFIED AS PART OF THE PROJECT USING BUILDING ROOM NUMBERS.




## 3 PARTIAL ELECTRICAL RISER - COMMONWEALTH ES

NO SCALE

NOTES:

1. FIELD VERIFY ALL EXISTING ELECTRICAL PANELS AND FEEDERS SHOWN ON DRAWINGS.
2. REF ELECTRICAL FLOOR PLANS FOR PANEL LOCATIONS.
3. ALL OUTAGES SHALL BE SCHEDULED/CONFIRMED IN WRITING WITH THE OWNER A MINIMUM OF TWO WEEKS PRIOR TO ANY OUTAGE.
4. AT THE END OF THE PROJECT PROVIDE A NEW TYPEWRITTEN PANEL SCHEDULE USING BUILDING ROOM NUMBERS FOR ALL PANELS WITH CIRCUITS ADDED, REMOVED, OR MODIFIED AS PART OF THE PROJECT.
5. REFERENCE PANEL SCHEDULES AND SHORT CIRCUIT TABLE FOR AIC AND SCCR VALUES.

### MECH X164

**(E)PANEL H8** — 1025A MCB, 480Y/277V, 3ø, 4 WIRE — AVAILABLE FAULT: <14,000A — SCCR & AIC: 14,000A — MOUNTING: SURFACE

| NOTES | LOAD | DESCRIPTION | WIRE | CB | CKT | A | B | C | CKT | CB | WIRE | DESCRIPTION | LOAD | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | 540 | EXIST CIRCUIT | EXIST | 20/1 | 1 | | | | 2 | 15/3 | EXIST | AHU–1 | 6316 | |
| | 540 | EXIST CIRCUIT | EXIST | 20/1 | 3 | | | | 4 | – | – | ( 5 HP ) | – | |
| | 540 | EXIST CIRCUIT | EXIST | 20/1 | 5 | | | | 6 | – | – | – | – | |
| | 14498 | TRANSFORMER T8 | EXIST | 50/3 | 7 | | | | 8 | 15/3 | EXIST | OAHU–1 | 2493 | |
| | – | ( 30KVA, PANEL L8 ) | – | – | 9 | | | | 10 | – | – | ( 1.5 HP ) | – | |
| | – | – | – | – | 11 | | | | 12 | – | – | – | – | |
| | | SPACE | | | 13 | | | | 14 | | | SPACE | | |
| | | SPACE | | | 15 | | | | 16 | | | SPACE | | |
| | | SPACE | | | 17 | | | | 18 | | | SPACE | | |
| | | SPACE | | | 19 | | | | 20 | | | SPACE | | |
| | | SPACE | | | 21 | | | | 22 | | | SPACE | | |
| | | SPACE | | | 23 | | | | 24 | | | SPACE | | |
| | | SPACE | | | 25 | | | | 26 | | | SPACE | | |
| | | SPACE | | | 27 | | | | 28 | | | SPACE | | |
| | | SPACE | | | 29 | | | | 30 | | | SPACE | | |
| | | SPACE | | | 31 | | | | 32 | | | SPACE | | |
| | | SPACE | | | 33 | | | | 34 | | | SPACE | | |
| | | SPACE | | | 35 | | | | 36 | | | SPACE | | |
| | | SPACE | | | 37 | | | | 38 | | | SPACE | | |
| | | SPACE | | | 39 | | | | 40 | | | SPACE | | |
| | | SPACE | | | 41 | | | | 42 | | | SPACE | | |
| | TOTAL LOAD @ 100% = | 24927VA | | | TOTAL LOAD @ 100% = | | | | 30A | | | TOTAL LOAD @ 125% = | 37A | |


1. THE EXISTING 125A FEEDER IS SUFFICIENT FOR THE REVISED LOAD.

### MECH X164

**(E)PANEL L8** — 100A MCB, 208Y/120V, 3ø, 4 WIRE — AVAILABLE FAULT: <10,000A — SCCR & AIC: 10,000A — MOUNTING: SURFACE

| NOTES | LOAD | DESCRIPTION | WIRE | CB | CKT | A | B | C | CKT | CB | WIRE | DESCRIPTION | LOAD | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | 540 | RECEPTACLES | EXIST | 20/1 | 1 | | | | 2 | 20/1 | EXIST | RECEPTACLES | 540 | |
| | 720 | COMPUTER RECEPTACLES | EXIST | 20/1 | 3 | | | | 4 | 20/1 | EXIST | RECEPTACLES | 540 | |
| | 900 | RECEPTACLES | EXIST | 20/1 | 5 | | | | 6 | 20/1 | EXIST | COMPUTER RECEPTACLES | 720 | |
| | 720 | GYM OFFICE RECEPTACLES | EXIST | 20/1 | 7 | | | | 8 | 20/1 | EXIST | COMPUTER RECEPTACLES | 540 | |
| | 1080 | GYM RECEPTACLES | EXIST | 20/1 | 9 | | | | 10 | 20/1 | EXIST | COMPUTER RECEPTACLES | 360 | |
| | 500 | EDF | EXIST | 20/1 | 11 | | | | 12 | 20/1 | EXIST | COMPUTER RECEPTACLES | 360 | |
| | 500 | EDF | EXIST | 20/1 | 13 | | | | 14 | 20/1 | EXIST | COMPUTER RECEPTACLES | 540 | |
| | | EXIST SPARE | | 20/1 | 15 | | | | 16 | 20/1 | EXIST | RECEPTACLES | 900 | |
| | | EXIST SPARE | | 20/1 | 17 | | | | 18 | 20/1 | EXIST | RECEPTACLES 602 | 900 | |
| | 250 | EMS | EXIST | 20/1 | 19 | | | | 20 | 20/1 | EXIST | EF–1F | 260 | |
| | | EXIST SPARE | | 20/1 | 21 | | | | 22 | 20/1 | EXIST | DOOR HOLDER | 800 | |
| | | EXIST SPARE | | 20/1 | 23 | | | | 24 | 20/1 | EXIST | FIRE/SMOKE DAMPERS | 300 | |
| | | EXIST SPARE | | 20/1 | 25 | | | | 26 | 20/1 | EXIST | FIRE/SMOKE DAMPERS | 300 | |
| | | EXIST SPARE | | 20/1 | 27 | | | | 28 | 20/1 | EXIST | EXIST CIRCUIT | 500 | |
| | | EXIST SPARE | | 20/1 | 29 | | | | 30 | | | SPACE | | |
| | | SPACE | | | 31 | | | | 32 | | | SPACE | | |
| | | SPACE | | | 33 | | | | 34 | | | SPACE | | |
| | | SPACE | | | 35 | | | | 36 | | | SPACE | | |
| | | SPACE | | | 37 | | | | 38 | 15/3 | 3–12 | MOTORIZED PARTITION – CAFE | 1728 | 2 |
| | | SPACE | | | 39 | | | | 40 | – | +12G | – | – | |
| | | SPACE | | | 41 | | | | 42 | – | 3/4"C | – | – | |
| | TOTAL LOAD @ 100% = | 14498VA | | | TOTAL LOAD @ 100% = | | | | 40A | | | TOTAL LOAD @ 125% = | 50A | |

1. THE EXISTING 100A FEEDER IS SUFFICIENT FOR THE REVISED LOAD.
2. PROVIDE NEW CIRCUIT BREAKER IN EXISTING SPACE AND WIRE CIRCUIT AS SHOWN.




## 1 ELECTRICAL RENOVATION PLAN

SCALE: 1/8" = 1'- 0"

STANTON ENGINEERING GROUP
INFO@STANTON–ENG.COM (713) 305–4080 | TEXAS ENG. FIRM REG. NO. F–018332 | © 2025 ALL RIGHTS RESERVED | 1300 W. SAM HOUSTON PARKWAY S., SUITE 175, HOUSTON, TX 77042

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

d

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
COMMONWEALTH ELEMENTARY SCHOOL
4909 COMMONWEALTH BLVD
SUGAR LAND, TX 77479

SEAL




07.18.2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL FLOOR PLAN & SCHEDULES

d-E.200

## AUDIO/VISUAL MULTIMEDIA LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| A## V## | WALL AV ROUGH-IN DETAIL |
| A## V## | CEILING AV ROUGH-IN DETAIL |
| A## V## | FLOOR AV ROUGH-IN DETAIL |
| IWB IWB | INTERACTIVE WHITE BOARD - WALL - CEILING |
| PJ PJ | MULTIMEDIA PROJECTOR |
| FP# FP# | MULTIMEDIA FLAT PANEL DISPLAY |
| S S | LOUDSPEAKER, WALL MOUNTED AND CEILING MOUNTED RESPECTIVELY - # INDICATES TYPE |
| CP# | CONTROL PANEL |
| TP# | TOUCH PANEL |
| M | MICROPHONE, CEILING MOUNTED - # INDICATES TYPE |
| VC | VOLUME CONTROL |
| WB | WALL BOX ENCLOSURE |
| D1 A1 | D1 = DIGITAL SINGLE SIDED CLOCK / A1 = ANALOG SINGLE SIDED CLOCK |
| D2 A2 | D2 = DIGITAL DOUBLE SIDED CLOCK / A2 = ANALOG DOUBLE SIDED CLOCK |
| ENC | CEILING AV ENCLOSURE |
| C C | PRESENTATION CAMERA - CEILING - WALL MOUNTED |

## PREMISE SECURITY LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| CR | CARD READER |
| CR M | CARD READER MULLION |
| KP | INTRUSION DETECTION KEYPAD |
| IC | INTERCOM (1 DATA CABLE) |
| IC MS | INTERCOM MASTER STATION (1 DATA CABLE) |
| PB | PANIC/DURESS BUTTON |
| LD | LOCK DOWN BUTTON |
| MD | MOTION DETECTOR |
| GB | ACCOUSTICAL GLASS BREAK SENSOR |
| BM | BIOMETRIC READER |
| RX | REQUEST TO EXIT - SURFACE PIR |
| KS | KEY SWITCH |
| LA | LOCAL ALARM SOUNDER |
| RG | RED/GREEN INDICATOR LIGHT |
| DB | DOORBELL |
| DH | MAGNETIC DOOR HOLD |
| DR | DOOR RELEASE |
| RX | REQUEST TO EXIT - INTEGRAL TO DOOR HARDWARE |
| DC | DOOR CONTACT / MONITOR |
| ES EL EH | ELECTRIFIED STRIKE - ELECTRIFIED LATCH - ELECTRIFIED HARDWARE (REFER TO SCHEDULES) |
| C C | STANDARD IP SURVEILLANCE CAMERA, (1) CABLE |
| C C | 180° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° FISHEYE LENS CAMERA |
| IR | IR ILLUMINATOR |

## STRUCTURED CABLING LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF DATA CABLE(S)/JACK(S) |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) |
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| W | WALL MOUNT PHONE (1 CABLE/JACK) |
| W | WALL MOUNT PHONE, SURFACE MOUNT (1 CABLE/JACK) |
| # | FLOOR MOUNTED OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| #/# | FLOOR MOUNTED OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| # | CEILING MOUNTED DATA OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) |
| AP# | CEILING MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| AP# | WALL MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| | CABLING SLEEVE(S) |
| | TYPICAL LADDER RACK |
| | TYPICAL CABLE TRAY, BASKET STYLE |

## GENERAL ANNOTATION LEGEND


| SYMBOL | DESCRIPTION |
|---|---|
| MER | MAIN EQUIPMENT ROOM |
| TR | TELECOMMUNICATION ROOM |
| MDF | MAIN DISTRIBUTION FRAME |
| IDF | INTERMEDIATE DISTRIBUTION FRAME |
| ETR | EXISTING TO REMAIN |
| PBO | PROVIDED BY OTHERS |
| AFF | ABOVE FINISHED FLOOR |
| AFG | ABOVE FINISHED GRADE |
| AC | ABOVE COUNTER |
| EC | ELECTRICAL CONTRACTOR |
| PSC | PREMISE SECURITY CONTRACTOR |
| SCC | STRUCTURAL CABLING CONTRACTOR |
| AVC | AV/MULTIMEDIA CONTRACTOR |
| UNO | UNLESS NOTED OTHERWISE |
| ACS | ACCESS CONTROL SYSTEM |
| VSS | VIDEO SURVEILLANCE SYSTEM |

## TECHNOLOGY - GENERAL NOTES

1. EACH KEYNOTE MAY NOT BE UTILIZED ON EVERY SHEET.
2. ALL CONDUIT MEASUREMENTS REFER TO STANDARD CONDUIT TRADE SIZES.
3. ALL CABLES SHALL BE CONCEALED.
4. EACH CONTRACTOR SHALL PROVIDE AND INSTALL ALL NECESSARY SLEEVES, WHETHER OR NOT SPECIFICALLY NOTED ON PROJECT DRAWINGS. ALL SLEEVES SHALL BE 2" UNLESS NOTED OTHERWISE ON THE DRAWINGS. CABLE FILL PERCENTAGE SHALL COMPLY WITH NEC.
5. DEVICE LOCATIONS ARE APPROXIMATE. CONTRACTOR SHALL REVIEW CONDITIONS AND COORDINATE WITH OTHER TRADES AS NECESSARY FOR EXACT PLACEMENT.

## TECHNOLOGY SYMBOLS LEGEND

NOT ALL SYMBOLS ARE USED




TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

d

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Commonwealth Elementary School
4909 Commonwealth Blvd, Sugar Land, TX 77479

SEAL

BICSI REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256587
EXPIRES 12-31-27

07-18-25


MVA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY - TITLE SHEET

d-TN000

**DEMO KEYNOTES**

1. REMOVE, AND PROTECT DURING CONSTRUCTION, INSTALL IN EXISTING LOCATION AFTER NEW ACT GRID IS IN PLACE.
2. DEVICES IN ACT ARE TO BE REMOVED AND PROTECTED DURING CONSTRUCTION AND REINSTALLED IN THE SAME LOCATION AFTER THE NEW CEILING GRID IS IN PLACE. DECIVES INCLUDE: SPEAKERS, ACCESS POINTS AND INTRUSION MOTION DETECTORS.
3. EXISTING CARD READER, DOOR CONTACT, & REX (REQUEST TO EXIT) TO BE DEMOLISHED, REMOVE DEVICES AND PROTECT WIREING.




1 BACKGROUND D (COMMONWEALTH ES)
SCALE: 1" = 20'-0"

TRUENORTH A PMT COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

d

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Commonwealth Elementary School
4909 Commonwealth Blvd, Sugar Land, TX 77479

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256857
EXPIRES 12-31-27

07-18-25


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Commonwealth ES - OVERALL

d-TN.100

## TECHNOLOGY KEYNOTES

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.




2 COMMONWEALTH - REFLECTED CEILING PLAN
SCALE: 3/16" = 1'-0"

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

d

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Commonwealth Elementary School
4909 Commonwealth Blvd. Sugar Land, TX 77479

SEAL




07-18-25


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Commonwealth ES - KITCHEN


d-TN.101

**GENERAL NOTE**


1. FACE PLATE DETAIL FOR OUTLET CONFIGURATION PURPOSES ONLY. CONTRACTOR TO SELECT TYPE OF FACE PLATE TO MATCH CONNECTIVITY HARDWARE, FLOOR BOX AND/OR MODULAR FURNITURE OPENING.





1 DATA ROUGH-IN DETAILS
SCALE: NS





2 TYPICAL CABLING SLEEVE
SCALE: NTS





3 PANDUIT J-HOOK DETAIL
SCALE: NTS





4 LABELING & CABLING SCHEMES
SCALE: NTS





5 CABLE PATHWAY CROSS SECTION
SCALE: NTS




6 DROPPED CEILING MOUNTING DETAIL
SCALE: NS




7 I-JOIST MOUNTING DETAIL
SCALE: NS




8 BAR JOIST MOUNTING DETAIL
SCALE: NS

| CAMERA TYPE | MANUFACTURER | MODEL NUMBER | GENERAL DESCRIPTION |
|---|---|---|---|
| C1 | iPro | WV-S8574L | 4x4K (33MP) EXTERIOR MULTI-SENSOR - PARKING LOTS, STADIUM |
| C2 | iPro | WV-S8544L | 4x4MP (16MP) EXTERIOR MULTI-SENSOR - BUILDING PERIMETER |
| C3 | iPro | WV-S25500-V3LN | 5MP EXTERIOR VANDAL DOME |
| C4 | iPro | WV-S22500-V3L | 5MP INTERIOR VANDAL DOME - CORR., COMMON, SPED |
| C5 | iPro | WV-S4156A | 5MP 360 (FISHEYE) - STAIRWELLS |

9 CAMERA SCHEDULE
SCALE: NTS

| Symbol | Purpose | Size | Mount | Backbox | Notes |
|---|---|---|---|---|---|
| FP1 | Digital Signage/Menu Boards | +49" | Ceiling Pole | N/A | Data and Power Outlets on ceiling |

10 DISPLAY SCHEDULE
SCALE: NTS

TRUENORTH
A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

d

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Commonwealth Elementary School
4909 Commonwealth Blvd, Sugar Land, TX 77479

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256687
EXPIRES 12-31-27

07-18-25


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY - Commonwealth ES - DETAILS


d-TN.500

GENERAL NOTES:


1. REFER TO SECURITY SCHEDULE AND WRITTEN SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
2. ALL MOUNTING DETAILS ARE REFERENCE FOR ALL FIXED DOME, 180°, 360°, PTZ, AND "BULLET/BOX" CAMERAS.





1 TYPICAL CAMERA INSTALLATION SECTION DETAIL
SCALE: NS




6 WALL MOUNTED CAMERA DETAIL
SCALE: NS




4 TILE BRIDGE DETAIL
SCALE: NS





5 CEILING MOUNTED CAMERA DETAIL
SCALE: NS


ACCESS CONROL DETAILS AND GENERAL NOTES:

1. CONDUIT ROUGH-IN IS A GUIDE FOR WHAT WILL BE REQUIRED FOR EACH DOOR. AS DOOR COMPONENTS CHANGE, EXACT CONDUIT LOCATION WILL ALSO NEED TO BE ADJUSTED.


2. PROTECT EXISTING-TO-REMAIN ACCESS CONTROL DEVICES AND CABLE THROUGHOUT RENOVATION WORK. IF CABLE AND/OR DEVICES ARE DAMAGED, SECURITY CONTRACTOR TO REPLACE WITH NEW.




1 ACCESS CONTROL - WIRING DETAIL - EXIT DEVICE W/ BUILT-IN REX
SCALE: NTS




2 ACCESS CONTROL - STEEL/HOLLOW METAL DOOR.
SCALE: NTS




KP PB LD

3 ROUGH-IN DETAILS: KP, PB, LD
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

d

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Commonwealth Elementary School
4909 Commonwealth Blvd, Sugar Land, TX 77479

SEAL




07-18-25


MVA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING
AND
PERMITTING

TECHNOLOGY -
Commonwealth ES -
SECURITY DETAILS

d-TN.600

# FBISD BP013 KITCHEN RENOVATIONS ES

## CORNERSTONE ELEMENTARY SCHOOL
1800 CHANTHAM AVE, SUGAR LAND, TX 77479

FORT BEND INDEPENDENT SCHOOL DISTRICT 2023 BOND

| Sheet List Table | |
|---|---|
| Sheet Number | Sheet Title |
| School: e-Cornerstone ES | |
| e-A.000 | COVER AND INDEX |
| e-A00-01 | GENERAL NOTES AND ABBREVIATIONS |
| e-D.101 | DEMO PLAN PHOTOS |
| e-A.201 | FLOOR PLAN |
| e-A.301 | STUDENT CAFETERIA AND GYM PLAN |
| e-A.501 | FINISH FLOOR PLAN |
| e-A.601 | INTERIOR ELEVATIONS |
| e-S1 | GYMNASIUM PLAN |
| e-S2 | SECTIONS AND TYPICAL DETAILS |
| e-E.000 | ELECTRICAL AND FIRE ALARM SCHEDULES |
| e-E.001 | ELECTRICAL AND FIRE ALARM NOTES |
| e-E.200 | ELECTRICAL FLOOR PLAN & SCHEDULES |
| e-TN-000 | TECHNOLOGY - INDEX SHEET |
| e-TN-100 | TECHNOLOGY - OVERALL |
| e-TN-101 | TECHNOLOGY - KITCHEN |
| e-TN-500 | TECHNOLOGY - DETAILS |
| e-TN-600 | TECHNOLOGY - SECURITY DETAILS |




ISSUED FOR BIDDING AND PERMITTING - JULY 18, 2025

FORT BEND INDEPENDENT SCHOOL DISTRICT

## ADMINISTRATION

| | |
|---|---|
| DR. MARCELL SMITH | SUPERINTENDENT OF FBISD |
| DR. ANDRIA SCHUR, Ed.D. | CHIEF OF SCHOOLS |

## BOARD OF TRUSTEES

| | |
|---|---|
| KRISTIN K. TASSIN | PRESIDENT |
| RICK GARCIA | VICE PRESIDENT |
| DAVID HAMILTON | SECRETARY |
| ANGIE HANAN | BOARD MEMBER |
| ADAM SCHOOF | BOARD MEMBER |
| DR. SHIRLEY ROSE-GILLIAM | BOARD MEMBER |
| SONYA JONES | BOARD MEMBER |

## PROJECT DESIGN TEAM

PROGRAM MANAGEMENT
FBISD 2023 Bond Team
2323 Texas Parkway
Missouri City, TX 77489
Phone Number: 281-327-5481

ARCHITECT
MWA Architects
11767 Katy Freeway, Suite 430
Houston, Texas 77079
Phone Number: 713-782-8188

FOOD SERVICE
Food Design Professionals
26215 Oak Ridge Drive
The Woodlands, Texas 77380
Phone Number: 281-350-2323

MEP ENGINEERS
Stanton Engineering Group
1300 W. Sam Houston Pkwy South, Suite 121
Houston, Texas 77042
Phone Number: 713-300-9292

STRUCTURAL ENGINEER
Stanley Spurling & Hamilton
3301 Edloe Street, Suite 200
Houston, Texas 77027
Phone Number: 713-776-9433

PART 1 - GENERAL

1.1 GENERAL DEMOLITION NOTES

A. VERIFY EXISTING SITE AND BUILDING CONDITIONS IN FIELD PRIOR TO BIDDING. NOTIFY ARCHITECT OF ANY DISCREPANCIES PRIOR TO BIDDING.

B. CONTRACTOR SHALL COORDINATE WITH OWNER THE SALVAGE OF ITEMS, FURNITURE AND EQUIPMENT INDICATED TO BE REMOVED.

C. CLAIMS FOR ADDITIONAL COST OR TIME DUE TO EXISTING CONDITIONS THAT COULD HAVE BEEN REASONABLY ANTICIPATED DURING A SITE VISIT BY THE CONTRACTOR PRIOR TO BIDDING WILL NOT BE APPROVED.

D. PROTECT EXISTING FINISHES SHOWN TO REMAIN DURING CONSTRUCTION TO PREVENT DAMAGE. REPAIR OR REPLACE DAMAGED MATERIALS AND FINISHES TO MATCH EXISTING AT NO ADDITIONAL COST TO FORT BEND ISD (OWNER).

E. EXISTING AREAS REQUIRING MINOR DEMOLITION OR REPAIR FOR EXECUTION OF WORK SHALL BE REPAIRED TO MATCH EXISTING ADJACENT MATERIALS, UNLESS NOTED OTHERWISE.

F. DO NOT DAMAGE CASEWORK AND EQUIPMENT NOT DESIGNATED TO BE REMOVED OR RELOCATED.EXISTING CASEWORK SHALL REMAIN THE PROPERTY OF THE OWNER.

G. CONTRACTOR TO VERIFY LOCATION OF ELEC. SWITCHES, OUTLETS, GRILLES, CLEAN-OUTS, COVER PLATES, ACCESS DOORS, AND OTHER EQUIPMENT AND DEVICES THAT MAY CONFLICT WITH THE RENOVATION AND NEW CONSTRUCTION OF WALLS, FLOORS, AND CEILINGS PRIOR TO COMMENCEMENT OF WORK. CONTRACTOR SHALL LIKEWISE CONFIRM THAT ELECTRICAL CONDUIT ROUTING SHALL BE CONCEALED WITHIN WALLS. NOTIFY ARCHITECT IF WALL THICKNESS WILL NOT ALLOW FOR CONCEALMENT.

H. REMOVE ANY EXISTING CORNER GUARDS IN THE KITCHEN AREA.

I. PRIOR TO EXECUTION OF DEMOLITION WORK, SCHEDULE A WALK-THROUGH WITH OWNER AND ARCHITECT TO CONFIRM SCOPE OF WORK AND TO REVIEW EXISTING CONDITIONS.

J. EXISTING FLOOR FINISHES AND ACOUSTIC CEILING TILE TO BE REMOVED THROUGHOUT.

K. REFER TO MEP DRAWINGS FOR DEMOLITION AND ALTERATION OF UTILITIES.

L. AT ALL EXISTING WALLS REQUIRING DEMOLITION TO INSTALL NEW PIPING BEHIND SINKS, CUT AND PATCH WALLS AS REQUIRED TO MATCH ADJACENT SURFACE.

M. CLEAN AND PREPARE SUBFLOOR FOR INSTALLATION OF NEW FLOOR FINISH.

N. DEMOLITION ACTIVITIES SHALL BE PERFORMED AS TO PRODUCE MINIMAL DISTURBANCE TO EXISTING FACILITY OCCUPANTS. MINIMIZE EXCESSIVE AND PROLONGED NOISE LEVELS AND DUST.

O. ASBESTOS-CONTAINING MATERIALS. REFER TO SPECIFICATION 02 26 23 FOR ASBESTOS INFORMATION APPLICABLE TO KITCHEN AREAS. FORT BEND ISD HAS RETAINED A SEPARATE ENVIRONMENTAL CONSULTANT FOR THE REMOVAL OF ASBESTOS. GC TO COORDINATE WITH ENVIRONMENTAL CONSULTANT TO CARRY OUT ASBESTOS ABATEMENT FOR ALL AFFECTED KITCHEN AREAS.

1.2 FLOOR PLAN GENERAL NOTES

A. FIELD VERIFY EXISTING CONDITIONS PRIOR TO GENERATING SHOP DRAWINGS AND FABRICATION OF EQUIPMENT.
B. FLOOR FINISH CHANGES SHALL OCCUR AT THE CENTERLINE OF DOORS UNLESS NOTED OTHERWISE. FLOOR FINISH CHANGES SHALL HAVE THRESHOLDS OR REDUCERS STRIPS.
C. DOORS THAT ARE TO BE REPLACED AND INSTALLED IN EXISTING FRAMES SHALL BE MACHINED FOR HARDWARE DIMENSIONS AT EXISTING FRAMES, CONTRACTOR SHALL FIELD VERIFY FRAME CONDITIONS AND DIMENSIONS.
D. CONTRACTOR TO PROVIDE SHEET METAL REINFORCING STRAP AS REQUIRED FOR MOUNTING OF ALL GRAB BARS, CABINETS, MIRRORS, SHELVING, ETC.
E. SAW CUT AND REMOVE EXISTING SLAB AND FLOOR FINISHES AS REQUIRED TO INSTALL NEW PLUMBING LINES, FLOOR DRAINS, PLUMBING FIXTURES, OR ELECTRICAL ITEMS. SPLICE NEW REINFORCING BARS DOWELED INTO EXISTING CONCRETE, AND PROVIDE NEW VAPOR RETARDER AND WATERSTOPS, AND PATCH W/ 3000 PSI CONCRETE AFTER INSTALLATION OF UTILITIES AND FIXTURES. PREPARE CONCRETE TO RECEIVE NEW FINISH.
F. COORDINATE HOUSEKEEPING PAD DIMENSIONS AND LOCATIONS WITH EQUIPMENT TO BE INSTALLED. HOUSEKEEPING PADS SHALL BE A MIN. OF 4" THICK REINF. W/ #3 BARS AT 15" O.C. BOTH WAYS. PROVIDE 1" BY 45-DEGREE CHAMFERED EDGES.

1.3 COMPLETE PERFORMANCE

L. THE CONTRACTOR SHALL FURNISH AND INSTALL ALL ITEMS SPECIFIED HEREIN AND AS INDICATED ON THE DRAWINGS. THE CONTRACTOR SHALL ALSO FURNISH AND INSTALL ALL ITEMS NECESSARY TO MAKE THE SYSTEMS FUNCTION WHICH MAY BE REASONABLY IMPLIED AS ESSENTIAL, WHETHER MENTIONED IN THE CONTRACT DOCUMENTS OR NOT.

M. WORK SHALL BE EXECUTED IN STRICT ACCORDANCE WITH THE BEST PRACTICE OF THE TRADES IN A THOROUGH, SUBSTANTIAL AND WORKMANLIKE MANNER BY COMPETENT WORKMEN.

1.4 SITE FAMILIARIZATION

A. GENERAL: BECOME FAMILIAR WITH THE DRAWINGS AND SPECIFICATIONS, EXAMINE THE PREMISES, AND UNDERSTAND THE CONDITIONS UNDER WHICH THE CONTRACT SHALL BE PERFORMED, PRIOR TO SUBMITTING A BID.

B. SITE: BE INFORMED OF THE SITE CONDITIONS, VERIFY LOCATIONS OF NEW AND EXISTING EQUIPMENT, AND DETERMINE EXACT REQUIREMENTS FOR CONNECTIONS.

C. COORDINATION: TENDER OF A PROPOSAL FOR THIS PROJECT INFERS THAT THE CONTRACTOR HAS VISITED THE SITE AND HAS BECOME FAMILIAR WITH THE DRAWINGS, SPECIFICATIONS, AND SITE CONDITIONS AND HAS INCLUDED IN HIS PROPOSAL ALL WORK NECESSARY TO PROPERLY INSTALL COMPLETE AND FUNCTIONING SYSTEMS ON THE PROJECT. FAILURE TO COMPLY WITH THIS REQUIREMENT SHALL NOT BE CONSIDERED JUSTIFICATION FOR THE OMISSION OR FAULTY INSTALLATION OF ANY WORK COVERED BY THE CONTRACT DOCUMENTS.

1.5 CODES AND STANDARDS

A. GENERAL: ALL WORK SHALL COMPLY WITH THE MOST RECENTLY REVISED VERSIONS OF ALL APPLICABLE LAWS, RULES, REGULATIONS AND ORDINANCES OF ALL FEDERAL, STATE AND LOCAL AUTHORITIES AND APPLICABLE UTILITIES. NONE OF THE TERMS OR PROVISIONS OF THIS SPECIFICATION SHALL BE CONSTRUED AS WAIVING ANY PART OF THE LAWS, RULES, REGULATIONS OR REQUIREMENTS OF THESE AUTHORITIES.

B. CONFLICT: IN THE EVENT OF CONFLICT BETWEEN THE CONTRACT DOCUMENTS AND THE LOCAL ENFORCING AUTHORITY, THE LATTER SHALL RULE. ANY MODIFICATIONS RESULTING THEREFROM SHALL BE MADE WITHOUT ANY ADDITIONAL COST TO THE OWNER OR ARCHITECT. THIS CONTRACTOR SHALL REPORT ANY SUCH MODIFICATIONS TO THE ARCHITECT AND SECURE HIS APPROVAL PRIOR TO PROCEEDING WITH THE WORK.

C. PRECEDENCE: WHERE CONTRACT DOCUMENT REQUIREMENTS EXCEED THE REQUIREMENTS OF THE CODES AND STANDARDS, THE CONTRACT DOCUMENTS SHALL TAKE PRECEDENCE PROVIDED THEY ARE NOT IN CONFLICT WITH THOSE CODES AND STANDARDS.

D. APPROVAL LABELS: ALL ITEMS OF EQUIPMENT AND ALL MATERIALS FOR WHICH APPROVED STANDARDS HAVE BEEN ESTABLISHED BY UNDERWRITERS' LABORATORIES, INC. (UL), FACTORY MUTUAL (FM), CERTIFIED BALLAST MANUFACTURER (CBM), ELECTRICAL TESTING LABORATORY (ETL), NATIONAL MANUFACTURERS ASSOCIATION (NEMA), AMERICAN STANDARD CODES, ASME, AGA, AMCA, ASA, ANSI, ASHRAE, AND ARI SHALL BE SO APPROVED AND SHALL BEAR APPROVAL LABELS ATTESTING TO SAME.

1.6 DRAWINGS AND SPECIFICATIONS

A. DRAWINGS: THE SET OF ORIGINAL DRAWINGS HAS BEEN MODIFIED AND INDICATE APPROXIMATE EXISTING LOCATIONS OF THE FLOOR FINISH ITEMS. ALL ITEMS ARE SHOWN APPROXIMATELY TO SCALE. FIELD VERIFY CONDITIONS.

B. SPECIFICATIONS: THE SPECIFICATIONS ARE INTENDED TO SUPPLEMENT THE DRAWINGS AND IT IS NOT IN THE SCOPE OF THE SPECIFICATIONS TO MENTION ANY PART OF THE WORK THAT THE DRAWINGS ARE COMPETENT TO FULLY EXPLAIN. CONVERSELY, ANY PART OF THE WORK THAT THE SPECIFICATIONS ARE COMPETENT TO FULLY EXPLAIN MAY NOT BE MENTIONED ON THE DRAWINGS. DRAWINGS AND SPECIFICATIONS ARE COMPLIMENTARY/SUPPLEMENTARY DOCUMENTS TO EACH OTHER.

C. DISAGREEMENT: DISAGREEMENT BETWEEN THE DRAWINGS AND SPECIFICATIONS OR WITHIN THE DRAWINGS OR SPECIFICATIONS SHALL BE ESTIMATED AND/OR BID USING THE BETTER QUALITY OR GREATER QUANTITY OF MATERIAL OR INSTALLATION, AND A CLARIFICATION REQUEST FOR INFORMATION SHALL BE MADE TO THE ARCHITECT IN A TIMELY MANNER AFTER THE PROJECT IS UNDER CONTRACT.

1.7 DISCREPANCIES

A. CLARIFICATION: CLARIFICATION OF SIGNIFICANT COST MATTERS SHALL BE OBTAINED BEFORE SUBMITTING A PROPOSAL FOR THE WORK AS TO DISCREPANCIES OR OMISSIONS FROM THE CONTRACT DOCUMENTS OR QUESTIONS AS TO THE INTENT THEREOF.

B. INTERPRETATIONS: SHOULD ANY DOUBT OR QUESTION ARISE RESPECTING THE TRUE MEANING OF DRAWINGS OR SPECIFICATIONS, REFERENCE SHALL BE MADE TO THE ARCHITECT, WHOSE WRITTEN DECISION SHALL BE FINAL AND CONCLUSIVE. NO ALLEGED STATEMENT BY THE ARCHITECT WILL BE ACCEPTED AS AN EXCUSE FOR NON-COMPLIANCE OR INFERIOR WORK.

C. CONTRACTOR AGREEMENT: CONSIDERATION WILL NOT BE GRANTED FOR MISUNDERSTANDING OF THE AMOUNT OF WORK TO BE PERFORMED. TENDER OF A PROPOSAL CONVEYS FULL CONTRACTOR AGREEMENT OF THE ITEMS AND CONDITIONS SPECIFIED, SHOWN, SCHEDULED, OR REQUIRED BY THE NATURE OF THE PROJECT, AND ALL COSTS ARE INCLUDED IN THE PROPOSAL.

1.8 REQUESTS FOR INFORMATION (RFI)

A. GENERAL: SUBMIT ALL CONTRACTOR REQUESTS FOR INFORMATION (RFI) IN WRITING TO THE ARCHITECT FOR RESPONSE. SUBMIT RFI ON A STANDARD FORM THAT HAS A SPACE FOR THE REQUESTED INFORMATION AND THE ARCHITECT'S RESPONSE.
B. SOLUTION PROPOSAL: IN GENERAL, THE CONTRACTOR SHALL PROPOSE SOLUTIONS TO IDENTIFY PROBLEMS FOR REVIEW AND APPROVAL OF THE ARCHITECT. THE RFI SHALL INCLUDE HAND SKETCHES, MARKED DRAWING PRINTS, EQUIPMENT CUTSHEETS, DRAWING AND SPECIFICATION REFERENCES, AND ANY OTHER BACK-UP INFORMATION, ETC., AS REQUIRED TO SUFFICIENTLY EXPLAIN THE PROBLEM AND PROPOSED SOLUTION.

1.9 QUALITY ASSURANCE

A. GENERAL: MATERIALS AND EQUIPMENT SHALL BE NEW, OF BEST GRADE AND QUALITY, AND STANDARD PRODUCTS OF REPUTABLE MANUFACTURERS REGULARLY ENGAGED IN THE PRODUCTION OF SUCH MATERIALS AND EQUIPMENT.
B. WORKMANSHIP: WORK SHALL BE EXECUTED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE BEST PRACTICE OF THE TRADES IN A THOROUGH, SUBSTANTIAL, WORKMANLIKE MANNER BY COMPETENT WORKMEN, PRESENTING A NEAT APPEARANCE WHEN COMPLETED.
C. JUDGMENT: IN ALL CASES, THE ARCHITECT SHALL BE THE SOLE JUDGE OF THE QUALITY AND EQUIVALENCE OF MANUFACTURERS, PRODUCTS, MATERIALS, AND METHODS.
D. MANUFACTURERS/PRODUCTS/MATERIALS/METHODS: MANUFACTURERS, PRODUCTS, MATERIALS, AND METHODS DESCRIBED IN THE VARIOUS SECTIONS OF THE SPECIFICATIONS AND INDICATED ON THE DRAWINGS ARE INTENDED TO ESTABLISH A STANDARD OF QUALITY ONLY, IT IS NOT THE INTENTION OF THE ARCHITECT TO DISCRIMINATE AGAINST ANY MANUFACTURER, PRODUCT, MATERIAL, OR METHOD THAT IS EQUAL TO THE STANDARDS AS INDICATED AND/OR SPECIFIED, NOR IS IT INTENDED TO PRECLUDE OPEN, COMPETITIVE BIDDING. THE FACT THAT A SPECIFIC MANUFACTURER IS LISTED AS AN ACCEPTABLE MANUFACTURER SHALL NOT BE INTERPRETED TO MEAN THAT THE MANUFACTURER'S STANDARD PRODUCT WILL MEET THE REQUIREMENTS OF THE PROJECT DESIGN, SPECIFICATIONS, AND SPACE CONSTRAINTS.
   1. WHEREVER A DEFINITE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS SPECIFIED AND THERE IS NOT A STATEMENT THAT ANOTHER MANUFACTURER, PRODUCT, MATERIAL, OR METHOD WILL BE ACCEPTABLE, IT IS THE INTENTION OF THE ARCHITECT THAT THE SPECIFIED MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS THE ONLY ONE THAT SHALL BE USED WITHOUT PRIOR APPROVAL.
   2. WHEREVER A DEFINITE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS SPECIFIED AS "NO SUBSTITUTE", IT IS THE INTENTION OF THE ARCHITECT THAT THE LISTED ITEM IS THE ONLY ONE ACCEPTABLE.
E. COORDINATION: WHERE EQUIPMENT IS USED ON THE PROJECT, IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR OR SUBCONTRACTOR INVOLVED TO VERIFY THAT THE EQUIPMENT WILL FIT IN THE SPACE AVAILABLE, INCLUDING ALL REQUIRED CODE AND MAINTENANCE CLEARANCES, AND TO COORDINATE ALL EQUIPMENT REQUIREMENTS AND PROVISIONS WITH THE SYSTEM DESIGN, ALL AFFECTED DIVISIONS, AND ALL OTHER CONTRACTORS. WHERE THE USE OF ALTERNATE OR SUBSTITUTE MATERIALS AFFECTS THE COST OF PROVISIONS MADE BY OTHER CONTRACTORS, THE CONTRACTOR PROVIDING THE ALTERNATE OR SUBSTITUTE SHALL BE RESPONSIBLE FOR THE OTHER CONTRACTOR'S COST ADJUSTMENT. THERE SHALL BE NO ADDITIONAL COST TO THE OWNER OR ARCHITECT DUE TO THE USE OR ACCEPTANCE OF ANY ALTERNATE OR SUBSTITUTE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD.

1.10 PRIOR APPROVAL

A. SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES: THE CONTRACTOR'S SUBMITTAL AND ARCHITECT'S ACCEPTANCE OF SHOP DRAWINGS, PRODUCT DATA, OR SAMPLES THAT RELATE TO CONSTRUCTION ACTIVITIES NOT COMPLYING WITH THE CONTRACT DOCUMENTS DOES NOT CONSTITUTE AN ACCEPTABLE OR VALID REQUEST FOR SUBSTITUTION, NOR DOES IT CONSTITUTE APPROVAL.

1.11 COORDINATION

A. BY SUBMITTING SHOP DRAWINGS ON THE PROJECT, THIS CONTRACTOR IS INDICATING THAT ALL NECESSARY COORDINATION HAS BEEN COMPLETED AND THAT THE SYSTEMS, PRODUCTS AND EQUIPMENT SUBMITTED CAN BE INSTALLED IN THE BUILDING AND WILL OPERATE AS SPECIFIED AND INTENDED, IN FULL COORDINATION WITH ALL OTHER DISCIPLINES.

1.12 SHOP DRAWINGS AND SUBMITTALS

A. GENERAL: AFTER THE CONTRACT IS AWARDED BUT PRIOR TO PROCEEDING WITH THE WORK REQUIRING SHOP DRAWING REVIEW, THE CONTRACTOR SHALL OBTAIN COMPLETE SHOP DRAWINGS AND PRODUCT DATA FROM THE MANUFACTURERS, SUPPLIERS, VENDORS, AND SUB- CONTRACTORS FOR ALL MATERIALS AND EQUIPMENT SPECIFIED HEREIN, AND MAKE FORMAL SUBMISSION TO THE ARCHITECT. A MINIMUM PERIOD OF TWO (2) WEEKS SHOULD BE ALLOWED IN THE CONSTRUCTION SCHEDULE EXCLUSIVE OF TRAVEL TIME FOR THE ARCHITECTS REVIEW.
B. CERTIFICATION: EACH CONTRACTOR RESPONSIBLE FOR THE WORK SHALL REVIEW AND CERTIFY THE SHOP DRAWING, SUBMITTAL AND/OR PRODUCT DATA TO BE IN FULL COMPLIANCE WITH THE REQUIREMENTS OF THE CONTRACT DOCUMENTS.
C. THE ARCHITECTS REVIEW OF SHOP DRAWINGS AND SUBMITTAL DATA SHALL NOT RELIEVE THE CONTRACTOR OF THE RESPONSIBILITY FOR DIMENSIONS OR ERRORS THAT MAY BE CONTAINED THEREIN, OR FOR DEVIATIONS FROM ANY REQUIREMENTS OF THE CONTRACT DOCUMENTS. IT SHALL BE CLEARLY UNDERSTOOD THAT THE ARCHITECTS NOTING SOME ERRORS BUT OVERLOOKING SOME OTHERS DOES NOT GRANT THE CONTRACTOR PERMISSION TO PROCEED IN ERROR. REGARDLESS OF ANY INFORMATION CONTAINED IN THE SHOP DRAWING OR PRODUCT DATA, THE CONTRACT DOCUMENTS SHALL GOVERN THE WORK AND ARE NEITHER WAIVED NOR SUPERSEDED IN ANY WAY BY THE REVIEW OF SHOP DRAWINGS, PRODUCT DATA AND SAMPLES.

1.13 EXECUTION AND COORDINATION OF WORK

A. MANUFACTURER'S RECOMMENDATIONS: WITH EXCEPTIONS AS SPECIFIED AND/OR INDICATED ON THE DRAWINGS OR IN THE SPECIFICATIONS, APPLY, INSTALL, ERECT, USE, CLEAN, AND CONDITION, MANUFACTURED ARTICLES, MATERIALS, AND EQUIPMENT PER MANUFACTURER'S CURRENT PRINTED RECOMMENDATIONS. KEEP COPIES OF SUCH PRINTED RECOMMENDATIONS AT JOB SITE AND MAKE THEM AVAILABLE AS REQUIRED.

1.14 SUPERVISION

A. A COMPETENT SUPERINTENDENT APPROVED BY THE ARCHITECT, SHALL BE KEPT BY THE CONTRACTOR AT THE BUILDING TO RECEIVE INSTRUCTIONS AND TO ACT FOR THE CONTRACTOR. ONCE THE SUPERINTENDENT HAS BEEN APPROVED, NO CHANGE SHALL BE MADE WITHOUT APPROVAL OF ARCHITECT, REPRESENTATIVES OF THE OWNER, ARCHITECT SHALL HAVE THE RIGHT TO OBSERVE THE WORK AT ANY TIME. THE CONTRACTOR SHALL HAVE A REPRESENTATIVE AVAILABLE WHEN HIS WORK IS BEING OBSERVED AND HE SHALL GIVE ASSISTANCE AS MAY BE REQUIRED TO THE ARCHITECT'S REPRESENTATIVE.
B. THE PROJECT SHALL BE CONSTRUCTED BY EMPLOYEES OF THE CONTRACTOR OR BY WORKERS UNDER HIS SUPERVISION. ANY SUBCONTRACTORS EMPLOYED BY THE CONTRACTOR SHALL BE APPROVED BY THE OWNER'S REPRESENTATIVE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL EQUIPMENT, MATERIAL AND WORK PERFORMED BY ANY SUBCONTRACTOR.

1.15 STORAGE AND PROTECTION OF MATERIALS

A. THE CONTRACTOR SHALL PROPERLY STORE ALL MATERIAL AND EQUIPMENT AT THE JOBSITE AND PROTECT IT FROM THE ELEMENTS AND FROM DAMAGE. ANY EQUIPMENT DAMAGED DUE TO IMPROPER PROTECTION SHALL BE REPLACED BY THE CONTRACTOR AT HIS EXPENSE.
B. THE CONTRACTOR SHALL PROTECT THE WORK, EQUIPMENT, AND MATERIAL OF ALL OTHER TRADES FROM DAMAGE BY HIS WORK OR OTHER WORKMEN, AND SHALL MAKE GOOD ALL DAMAGE THUS CAUSED.
C. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL WORK, MATERIALS, AND EQUIPMENT UNTIL FINALLY INSPECTED, TESTED, AND ACCEPTED; PROTECT WORK AGAINST THEFT, INJURY OR DAMAGE; AND CAREFULLY STORE MATERIAL AND EQUIPMENT RECEIVED ON SITE WHICH ARE NOT IMMEDIATELY INSTALLED, CLOSE OPEN ENDS OF WORK WITH TEMPORARY COVERS OR PLUGS DURING CONSTRUCTION TO PREVENT ENTRY OF OBSTRUCTING MATERIAL. THE CONTRACTOR SHALL COVER AND PROTECT IN AN ACCEPTABLE MANNER TO THE OWNER, EXISTING REMAINING EQUIPMENT AND MATERIALS.
D. IF ANY MATERIAL OR EQUIPMENT IS RECEIVED PRIOR TO THE TIME IT IS REQUIRED, THE CONTRACTOR SHALL BE RESPONSIBLE FOR ITS PROPER STORAGE AND PROTECTION UNTIL SUCH TIME AS IT MAY BE REQUIRED. THE CONTRACTOR SHALL PAY FOR ALL COSTS OF DEMURRAGE OR STORAGE.

1.16 DRAYAGE AND HAULING

A. THE CONTRACTOR SHALL KEEP THE JOBSITE FREE FROM THE ACCUMULATION OF TRASH AND CONSTRUCTION DEBRIS, REGARDLESS OF WHICH SUBCONTRACTOR MAY BE RESPONSIBLE.

1.17 CUTTING AND PATCHING

A. WHERE IT BECOMES NECESSARY TO CUT THROUGH ANY WALL, FLOOR OR CEILING TO PERMIT THE INSTALLATION OF ANY WORK, OR TO REPAIR ANY DEFECTS THAT MAY APPEAR, THE CUTTING SHALL BE PERFORMED UNDER THE SUPERVISION OF THE GENERAL CONTRACTOR. INFORM THE OWNER'S REPRESENTATIVE BEFORE ANY WORK COMMENCES. NO STRUCTURAL MEMBER SHALL BE ALTERED WITHOUT THE WRITTEN PERMISSION OF THE ARCHITECT.
B. VERIFICATION: SHOULD A QUESTION ARISE REGARDING THE ACCEPTABLE LEVEL OF NOISE OR VIBRATION IN A PARTICULAR SPACE OR PIECE OF EQUIPMENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING THE SERVICES OF AN APPROVED ACOUSTICAL CONSULTANT TO DETERMINE ACTUAL NOISE/VIBRATION CONDITIONS.

## 01 GENERAL NOTES

SEQUENCE OF CONSTRUCTION (AS OF 01/27/2025): Schools will be renovated in groups as shown. These groups contain two or three major kitchen renovations and some cafeteria/miscellaneous renovations. This sequencing is critical for FBISD food service to provide the uninterrupted meal services to their schools.

| | |
|---|---|
| GROUPING 1 | AUSTIN PARKWAY ES + SUGAR MILL ES, kitchen renovations. *Plus: COMMON WEALTH ES, CONERSTONE ES misc. renovations.* |
| GROUPING 2 | SETTLERS WAY ES + PALMER ES kitchen renovations. *Plus: SULLIVAN ES, SIENNA CROSSING ES, HERITAGE ROSE ES misc. renovations* |
| GROUPING 3 | HUNTER'S GLEN ES + HIGHLANDS ES + PECAN GROVE ES kitchen renovations. *Plus: RIDGEGATE ES, DULLES ES misc. renovations.* |

## 03 PROJECT SCHEDULE

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
CORNERSTONE ELEMENTARY SCHOOL
1800 CHATHAM AVE.
SUGAR LAND, TX 77479

SEAL

7/15/2025


ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

GENERAL NOTES AND ABBREVIATIONS

A00-01

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\A00-01 GENERAL NOTES AND ABBREVIATIONS.dwg Jul 23, 2025 - 4:03pm




PHOTO D1



PHOTO D2



PHOTO D3



PHOTO D4



PHOTO D5



PHOTO D6




PHOTO D7




PHOTO D8


PHOTO D9




PHOTO D10

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

e

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
CORNERSTONE ELEMENTARY SCHOOL
1800 CHATHAM AVE.
SUGAR LAND, TX 77479

SEAL
REGISTERED ARCHITECT
ROBERT A. MAGNER
#26511
STATE OF TEXAS
7/15/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
DEMO PLAN PHOTOS
e-D.101-2

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\E-Cornerstone ES\e-D.101 DEMO PLAN PHOTOS.dwg, Jul 23, 2025 - 4:03pm

2015 INTERNATIONAL EXISTING BUILDING CODE

301.1.1 PRESCRIPTIVE COMPLIANCE METHOD. REPAIRS, ALTERATIONS, ADDITIONS AND CHANGES OF OCCUPANCY COMPLYING WITH CHAPTER FOUR OF THIS CODE IN BUILDINGS COMPLYING WITH THE INTERNATIONAL FIRE CODE SHALL BE CONSIDERED IN COMPLIANCE WITH THE PROVISIONS OF THIS CODE.

401.2.1 EXISTING MATERIALS. MATERIALS ALREADY IN USE IN A BUILDING IN COMPLIANCE WITH REQUIREMENTS OR APPROVALS IN EFFECT AT THE TIME OF THEIR ERECTION OR INSTALLATION SHALL BE PERMITTED TO REMAIN IN USE UNLESS DETERMINED BY THE BUILDING OFFICIAL TO BE UNSAFE PER SECTION 115.

401.2.2 NEW AND REPLACEMENT MATERIALS. EXCEPT AS OTHERWISE REQUIRED OR PERMITTED BY THIS CODE, MATERIALS PERMITTED BY THE APPLICABLE CODE FOR NEW CONSTRUCTION SHALL BE USED. LIKE MATERIALS SHALL BE PERMITTED FOR REPAIRS AND ALTERATIONS, PROVIDED NO HAZARD TO LIFE, HEALTH OR PROPERTY IS CREATED. HAZARDOUS MATERIALS SHALL NOT BE USED WHERE THE CODE FOR NEW CONSTRUCTION WOULD NOT PERMIT THEIR USE IN BUILDINGS OF SIMILAR OCCUPANCY, PURPOSE AND LOCATION.

Area increase due to frontage and fire sprinkler protection TYPE IIB

$$A_a = [A_t + (NS \times I_f)] \times Sa$$

ALLOWABLE BUILDING AREA ONE STORY = 58,000 + (14,500 x 1.5) x 1 = 79,750 SF

ONE SINGLE STORY 100,643 SF.

# 2 CODE ANALYSIS

## Project Information

PROJECT: CORNERSTONE ELEMENTARY SCHOOL
LOCATION: 1800 CHATHAM AVE
SUGAR LAND, TX 77479

SCOPE OF WORK: SECURITY CAMERAS OVER SERVING LINES.
RENOVATE, RECONFIGURE, AND EXPAND EXISTING CAFETERIA.

## City of Sugar Land Adopted Building Code

2015 INTERNATIONAL BUILDING CODE (AS AMENDED)
2015 INTERNATIONAL FIRE CODE (AS AMENDED)
2015 INTERNATIONAL MECHANICAL CODE (AS AMENDED)
2015 INTERNATIONAL PLUMBING CODE (AS AMENDED)
2014 NATIONAL ELECTRICAL CODE (AS AMENDED)
2015 INTERNATIONAL ENERGY CONSERVATION CODE

## Chapter 3 - Use and Occupancy Classification

GROUP E (EDUCATIONAL - IBC 2015 SECTION 305)
EXISTING FULLY SPRINKLERED BUILDING

## Chapter 5 - General Building Heights and Area

ALLOWABLE BUILDING HEIGHT:
TWO STORIES W/ 55 FT MAX. HEIGHT FOR GROUP E
(AS ALLOWED BY TABLE 503)

EXISTING BUILDING HEIGHT PROVIDED:
HEIGHT TO ROOF: 15'-0"

INCIDENTAL USE SEPARATION:
SEPARATIONS REQUIRED: INCIDENTAL USE AREAS, AS PER TABLE 509.4, STORAGE ROOMS OVER 100 S.F. ARE REQUIRED TO BE ONE HOUR RATED OR HAVE AUTOMATIC FIRE EXTINGUISHING SYSTEM.

INCIDENTAL USE ROOM AREAS PROVIDED WITH EXISTING AUTOMATIC SPRINKLER SYSTEM.

TOTAL EXISTING BUILDING AREA IS 100,643 SF.

## Chapter 6 - Construction Type Fire Resistance Ratings

EXISTING CONSTRUCTION: TYPE IIB

TABLES 601 AND 602

| BUILDING ELEMENTS | REQUIRED (FOR TYPE IIB) | PROVIDED |
|---|---|---|
| STRUCTURAL FRAME (TABLE 601) | NO RATING | NO RATING |
| EXTERIOR BEARING WALLS (TABLE 601) | NO RATING | NO RATING |
| INTERIOR BEARING WALLS (TABLE 601) | NO RATING | NO RATING |
| EXTERIOR NON-BEARING WALLS (TABLE 602) | NO RATING | NO RATING (WALLS GREATER THAN *30'* FROM PROPERTY LINE) |
| INTERIOR NON-BEARING WALLS (TABLE 601) | NO RATING | NO RATING |
| FLOOR CONSTRUCTION (TABLE 601) | NO RATING | NO RATING |
| ROOF CONSTRUCTION (TABLE 601) | NO RATING | NO RATING |


## Chapter 9 - Fire Protection Systems

AUTOMATIC SPRINKLER SYSTEM: EXISTING SPRINKLER SYSTEM PROVIDED THROUGHOUT.

## Chapter 29 - Plumbing

| Fixture Count per Table 2902.1 | | |
|---|---|---|
| Occupant Load Basis: | | |
| | | |
| 12 Occupants | | |
| | | |
| | Total Fixtures REQUIRED | Total Fixtures PROVIDED |
| Unisex: | | |
| W.C. | 1 per 50 | 1 |
| lavatories | 1 per 50 | 1 |
| | | |
| Drinking Fountains | 1 per 100 | 2 |
| | | |

| PHASING CHART FOR ALL SCHOOLS | | |
|---|---|---|
| | PHASE 1 | |
| **SCHOOLS** | **FREEZER START DATE :** | **FREEZER END DATE :** |
| AUSTIN PARKWAY ES | 11/7/2025 | 5/13/2026 |
| SUGAR MILL ES | | |
| COMMONWEALTH ES | | |
| ***CONERSTONE ES*** | | |
| | PHASE 2 | |
| SETTLERS WAY ES | 5/29/2026 | 10/28/2026 |
| PALMER ES | | |
| SULLIVAN ES | | |
| SIENNA CROSSING ES | | |
| HERITAGE ROSE ES | | |
| | **PHASE 3** | |
| HUNTERS GLEN ES | 3/19/2027 | 3/19/2027 |
| PECAN GROVE ES | | |
| HIGHLANDS ES | | |
| DULLES ES | | |




1 OVERALL FLOOR PLAN
SCALE: 1/16" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

e

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
CORNERSTONE ELEMENTARY SCHOOL
1800 CHATHAM AVE
SUGAR LAND, TX 77479

SEAL
REGISTERED ARCHITECT
#2651
STATE OF TEXAS
7/15/2025



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

OVERALL FLOOR PLAN


e-A.201

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\E-Cornerstone ES\e-A.201 FLOOR PLAN.dwg Jul 23, 2025 - 4:04pm




## 1 PLAN STUDENT DINING AND GYM

SCALE: 1/4" = 1'-0"




## 3 SECTION AT FOLDING PARTITION

SCALE: 1-1/2" = 1'-0"

## FLOOR PLAN - GENERAL NOTES

1. REFER TO SHEET FOR GENERAL NOTES. GENERAL NOTES APPLY TO ALL SCHOOL KITCHENS.
2. REFER TO SHEET FOR PARTITION TYPES.
3. EXIXSTING EXPOSED CONDUITS AND DATA CABLING IN WIREMOLD TO BE ROUTED INSIDE WALLS (EXCEPT AT WAREWASH AREA BELOW TABLE HEIGHT AND DRY STORAGE ROOMS). PATCH AND REPAIR AS REQUIRED TO ACHIEVE SMOOTH CLEAN WALL SURFACE.

## 2 FLOOR PLAN NOTES

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

e

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT

CORNERSTONE ELEMENTARY SCHOOL
1800 CHATHAM AVE
SUGAR LAND, TX 77479

SEAL
REGISTERED ARCHITECT
22651
STATE OF TEXAS
7/15/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

KITCHEN FLOOR PLAN

e-A.301

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\E-Cornerstone ES\e-A.301 STUDENT CAFETERIA AND GYM PLAN.dwg Jul 23, 2025 - 4:04pm

## PAINT COLOR SCHEDULE

UNLESS OTHERWISE INDICATED FIELD COLOR IS PT-1 (SW 7014 EIDER WHITE)


SW 7014 EIDER WHITE (EPOXY PAINT)

### WALL TILE


CERAMIC WALL TILE (WT-1)
REFER TO TILE PATTERN AT SERVING AND RESTROOM
FIELD WALL TILE: DALTILE RITTENHOUSE SQUARE K175 BISCUIT (3X6)

A — PROVIDE ROOM SIGN TO REPLACE EXISTING. SEE LAYOUT FOR TYPE A OR TYPE B SIGN LOCATIONS.

JOHNSONITE DURCOVE RB-1 BURNT UMBER - 6"





TYPE A
ROOM SIGNAGE - FIXED NAMES




TYPE B
KITCHEN RESTROOM SIGNAGE

## PAINT COLOR SCHEDULE





WALL TILE PATTERN - RESTROOM

## 2 FLOOR FINISH LEGEND

## 3 ROOM SIGNAGE

## 4 WALL TILE PATTERN




1 FINISH FLOOR PLAN
SCALE: 1/4" = 1'-0"

## NEW FLOOR LEGEND

NEW LVT : TARKETT - EVENT ABSTRACT/ MELANGE - 18 X 18
(1,941 SF)

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

e

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
CORNERSTONE ELEMENTARY SCHOOL
1800 CHATHAM AVE
SUGAR LAND, TX 77479

SEAL

REGISTERED ARCHITECT
MICHAEL K. MARTIN
#26511
STATE OF TEXAS

7/15/2025



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

FINISH FLOOR PLAN

e-A.501


F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\E-Cornerstone ES\e-A.501 FINISH FLOOR PLAN.dwg Jul 23, 2025 - 4:04pm





## 5 NEW CONTROL JOINT
3"=1'-0"

NUMBERED DEMOLITION NOTES - CORNERSTONE

1. REMOVE 12" CMU WALL BETWEEN CONTROL JOINTS.
2. IF NEEDED FOR WORKING SPACE, CAREFULLY REMOVE CIRCULAR DUCTS, STORE AND PROTECT. RE-INSTALL DUCT AND DIFFUSERS, CLEAN AND RE-PAINT TO MATCH EXISTING.
3. PROTECT FLOOR FINISH ON BOTH SIDES OF WALL FROM DAMAGE BY INSTALLING MIN. 3/4" T&G PLYWOOD (STURDI-FLOOR) OR EQ. FOR A DISTANCE OF 10' OUTWARD FROM WALL. PLYWOOD SHALL BE UNTREASED AND BE PLACED ON NONSTAINING TEMPORARY FLOOR PROTECTION "RAM-BOARD".
4. SALVAGE, STORE AND PROTECT EXISTING ACOUSTIC PANELS. CLEAN AND RE-INSTALL ON NEW WALL FACE. USE PANELS FROM NEWLY RELOCATED BASKETBALL GOAL ON OPPOSITE SIDE OF GYM TO REPLACE THE GAPS LEFT IN THIS RUN OF PANELS.
5. RELOCATE EXISTING BASKETBALL GOAL TO OPPOSITE WALL. COORDINATE WITH PRINCIPAL AND COACH.
6. PHOTOGRAPH BOTH SIDES OF THIS WALL BEFORE WORK BEGINS. RESTORE NEW WALL TO LIKE CONDITIONS INCUDING SIGNAGE, ACCESSORIES, SECURITY ITEMS, POWER AND SWITCHES.
7. SALVAGE, STORE AND PROTECT EXISTING WALL PADS/PROTECTIVE PANELS. CLEAN AND REMOUNT BELOW RELOCATED BASKETBALL GOAL ON OPPOSITE WALL.
8. PROTECT EXISTING SECURITY DEVICE.
9. PROTECT EXISTING SECURITY FIRE EXTINGUISHER CABINET, DUPLEX RECEPTACLE AND KEYED SWITCHES
10. SOURCE, MATCH AND REPLACE BASE ON BOTH SIDES OF WALL.
11. SALVAGE MARKER BOARD. CLEAN AND RE-MOUNT AT COACH'S DIRECTION.
12. SALVAGE PAPER SIGNS. DELIVER TO COACH AND RE-MOUNT AT COACH'S DIRECTION.
13. EXISTING CONDUIT, LIGHTING, PLUMBING TO REMAIN IN PLACE.
14. RELOCATE EXISTING DUPLEX RECEPTACLE
15. GYP. BD. FURR OFF FACE OF CMU WALL IS BE REMOVED DURING DEMOLITION AND RE-BUILT BETWEEN TWO REMAINING SECTIONS OF CMU WALL WITH COLD FORMED METAL FRAMING SYSTEM. SPRINKLER PIPING INSIDE TO BE PROTECTED.
16. NEW MOVEABLE PARTITION AND SUPPORT BEAM.
17. MANUFACTURER STANDARD VINYL WALCOVERING FINISH, COLOR TO BE DECIDED.
18. GYPSUM BOARD WALL FINISH ON CFMF FRAMING SYSTEM





## 4 DEMOLITION (FROM GYM SIDE OF WALL)
SCALE: 1/4" = 1'-0"





## 6 SECTION THRU MOVEABLE PARTITION
3/4"=1'-0"

## 7 TEMPORARY CONTRUCTION WALL
3/4"=1'-0"




## 3 GYM SIDE OF WALL (NEW CONSTRUCTION)
SCALE: 1/4" = 1'-0"




## 2 CAFETERIA SIDE OF WALL (NEW CONSTRUCTION)
SCALE: 1/4" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

e

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
CORNERSTONE ELEMENTARY SCHOOL
1800 CHATHAM AVE
SUGAR LAND, TX 77479

SEAL
REGISTERED ARCHITECT
ROBERT A. MEYER
STATE OF TEXAS
23651
7/15/2025



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

INTERIOR ELEVATIONS

e-A.601

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\INTERIOR ELEVATIONS.dwg Jul 23, 2025 - 4:04pm




FOUNDATION PLAN
SCALE: 3/16"=1'-0"

**FIELD VERIFICATION NOTE**

1. CONTRACTOR SHALL VERIFY ALL DIMENSIONS PRIOR TO FABRICATION OR CONSTRUCTION.
2. CONTRACTOR SHALL VERIFY AND NOTIFY ENGINEER OF EXISTING CONDITIONS IN NEED OF REVIEW AND POSSIBLE MODIFICATION PRIOR TO FABRICATION.

**WORK SEQUENCE**

1. DEMO PORTIONS OF CMU WALL TO ALLOW FOUNDATION INSTALLATION.
2. INSTALL FOUNDATION.
3. INSTALL COLUMN/STRONG-BACKS.
4. INSTALL CHANNEL HEADERS.
5. DEMO ONE COURSE CMU BELOW HEADER AND INSTALL TEMPORARY POSTS.
6. INSTALL HEADER PLATE.
7. INSTALL KICKERS.
8. DEMO REMAINDER OF CMU.
9. INSTALL PARTITION.

**GENERAL NOTES**


1. ALL CONCRETE SHALL TEST 4000 PSI AT 28 DAYS.
2. ALL CONCRETE REINFORCING BARS SHALL CONFORM TO ASTM A615 GRADE 60.
3. DETAILING AND FABRICATION OF CONCRETE REINFORCEMENT AND ACCESSORIES SHALL BE IN ACCORDANCE WITH ACI-315 LATEST EDITION.
4. LAP ALL CONTINUOUS REINFORCING BARS 50 DIAMETERS AT SPLICES, TEES, AND CORNERS.
5. THE USE OF HEAT TO FACILITATE THE BENDING OF REINFORCING BARS WILL NOT BE PERMITTED.
6. NO ENGINEERING DRAWING MAY BE REPRODUCED FOR USE AS SHOP DRAWINGS.
7. CONTRACTOR SHALL COORDINATE ALL LOCATIONS OF ALL ANCHOR BOLTS AND OPENINGS FOR MECHANICAL, PIPING, AND ELECTRICAL EQUIPMENT WITH THE RESPECTIVE ENGINEERING AND VENDOR DRAWINGS.

**SLAB NOTE**

4" CONC. SLAB ON 10 MIL POLY FILM ON 2" MAX. SAND FILL. REINFORCE WITH #3 @ 15"c.c. E.W. IN CENTER OF SLAB. FOR SUBGRADE PREPARATION REFER TO GEOTECHNICAL INVESTIGATION BY PARADIGM CONSULTANTS, INC. REPORT NUMBER 24-1071, DATED DEC. 2024.

**SLAB SIDEWALK SLAB NOTE**

4" CONC. SLAB ON 2" MAX. SAND FILL. REINF. W/ #3 @ 18"c.c. IN CENTER OF SLAB.




FRAMING PLAN
SCALE: 3/16"=1'-0"

KEN STANLEY 69701 REGISTERED PROFESSIONAL ENGINEER
*July 17, 2025*

STANLEY SPURLING & HAMILTON, INC.
Consulting Engineering Services
T.B.P.E. Registration # F-000175
www.sshinc.net
50 Years
3301 Edloe Street, Suite 200 Houston, Texas 77027 Tel 713-776-9433
E-MAIL: info@sshinc.net
0002-0256

ISSUE:

| | |
|---|---|
| 03/07/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |


FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
CORNERSTONE ELEMENTARY SCHOOL
1800 CHATHAM AVE
SUGAR LAND, TX 77479

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

KITCHEN PLAN


S1





1 SECTION
SCALE: 3/4"=1'-0"




2 SECTION
SCALE: 3/4"=1'-0"





3 SECTION
SCALE: 3/4"=1'-0"




CONTRACTOR SHALL COVER ALL EXPOSED REBAR DURING CONSTRUCTION.

TYPICAL REBAR CAP DETAIL
SCALE: N.T.S.




| FTG. SCHEDULE TYP. U.N.O. | | |
|---|---|---|
| SIZE | VERT. | TIES |
| 18 | 5~#5 | #3 @ 12"c.c. |

TYPICAL FOOTING DETAIL (U.N.O.)
SCALE: N.T.S.

ISSUE:

| | |
|---|---|
| 03/07/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
CORNERSTONE ELEMENTARY SCHOOL
1800 CHATHAM AVE
SUGAR LAND, TX 77479


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079






*July 17, 2025*


STANLEY SPURLING & HAMILTON, INC.
Consulting Engineering Services
T.B.P.E. Registration # F-000175
www.sshinc.net
50 Years
3301 Edloe Street, Suite 200 Houston, Texas 77027 Tel 713-776-9433
E-MAIL: info@sshinc.net
0002-0256


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

SECTIONS AND TYPICAL DETAILS

S2




## 2 OVERALL FLOOR PLAN

SCALE: 1" = 30'- 0"

## SYMBOL LEGEND


| | |
|---|---|
| ①①①① | SIMPLEX/DUPLEX/QUAD – 5361/2 REC |
| GFI | DUPLEX W/ GFCI PROTECTION–P&S 2097 |
| J | J–BOX |
| | CEILING MOUNTED J–BOX |
| M | MOTOR |
| | HEAVY DUTY, NON–FUSED DISCONNECT. MIN RATING OF CIRCUIT OCPD/VOLTAGE. |
| | ELECTRICAL PANEL |
| | HOMERUN TO CIRCUIT NOTED |
| E | EXISTING DEVICES TO REMAIN |
| R | EXISTING DEVICES TO BE RELOCATED |
| D | EXISTING DEVICES TO BE DEMO/REMOVED |
| REP | EXISTING DEVICES TO BE REPLACED |
| S | INDICATES SURFACE MOUNTED |
| SR | INDICATES SURFACE RACEWAY |
| * | INDICATES ABOVE COUNTER DEVICE |
| + | INDICATES DEVICE AT +30–60" |
| ++ | INDICATES DEVICE AT +80–96" |
| CLG | INDICATES DEVICES MOUNTED IN CEILING |
| WP | INDICATES WEATHERPROOF COVER |
| 3R | INDICATES 3R RATED DEVICE |
| (E)LA–X | CONNECT(ED) TO EXIST CIRCUIT LA–X |
| (D)LA–X | DEMO PORTION OF EXIST CIRCUIT LA–X |
| (N)LA–X | CONNECT(ED) TO NEW CIRCUIT LA–X |

GENERAL ELECTRICAL NOTES:

1. INSTALL SYSTEM IN ACCORDANCE WITH THE NATIONAL ELECTRIC CODE AS ADOPTED BY THE LOCAL AUTHORITY HAVING JURISDICTION INCLUDING ALL AMENDMENTS.
2. PROVIDE CONDUIT FOR ALL DEVICES INSTALLED IN WALLS.
   - 2.A. 3/4"C FOR POWER AND 1"C FOR LOW VOLTAGE/DATA UNLESS NOTED OTHERWISE.
   - 2.B. PROVIDE PROTECTIVE BUSHING ON END OF ALL LOW VOLTAGE CONDUITS.
   - 2.C. ALL ELECTRICAL HOMERUNS SHALL BE IN CONDUIT, MIN 3/4"C.
   - 2.D. USE INSULATED THROAT FITTINGS FOR CONNECTIONS TO HOUSINGS, BOXES, ENCLOSURES, ETC.
   - 2.E. MAX LENGTH FOR FLEX CONDUIT SHALL BE 6FT AND MIN. SIZE SHALL BE 1/2". ALL FLEX CONDUIT SHALL BE LISTED FOR GROUNDING.
3. CONDUIT TYPES:
   - 3.A. INSIDE BUILDINGS: GALVANIZED STEEL EMT.
     - 3.A.A. ALL LOW VOLTAGE CABLING SHALL BE INSTALLED IN CONDUIT IN EXPOSED CEILING AREAS. ROUTE TO NEAREST ACCESSIBLE CEILING WITH CONTINUOUS PATHWAYS TO LOW VOLTAGE SOURCE/DEVICE.
     - 3.A.B. ALL LOW VOLTAGE CABLING SHALL BE INSTALLED IN CONDUIT ABOVE INACCESSIBLE CEILINGS. ROUTE TO NEAREST ACCESSIBLE CEILING WITH CONTINUOUS PATHWAYS TO LOW VOLTAGE SOURCE/DEVICE.
   - 3.B. NO MC CABLE SHALL BE ALLOWED.
   - 3.C. PROVIDE FLEXIBLE CONNECTIONS TO MOTORS, PUMPS, TRANSFORMERS, OR SIMILAR EQUIPMENT.
4. PROVIDE GALVANIZED STEEL, ONE–PIECE CONSTRUCTION, OUTLET BOXES IN ALL CASES SUITABLE FOR INTENDED USE.
   - 4.A. BOXES OUTSIDE SHALL BE STEEL NEMA 3 TYPE.
   - 4.B. PROVIDE CEILING BRACKET TO SUPPORT CEILING MOUNTED DEVICES FROM CEILING TEES.
5. 20 AMP, SINGLE PHASE BRANCH CIRCUITS SERVING LIGHTING AND GENERAL RECEPTACLES MAY BE GROUPED IN A SINGLE RACEWAY PROVIDED A NEUTRAL CONDUCTOR IS INSTALLED FOR EACH CIRCUIT REQUIRING A NEUTRAL.
   - 5.A. DO NOT INSTALL MORE THAN FOUR CURRENT CARRYING CONDUCTORS IN A CONDUIT EXCEPT SIX #12 OR #10 CURRENT CARRYING CONDUCTORS MAY BE INSTALLED IN 3/4" OR LARGER CONDUIT FOR 20A CIRCUITS.
   - 5.B. DO NOT INSTALL 480/277 VOLT CONDUCTORS IN THE SAME CONDUIT WITH 240/208/120 VOLT CONDUCTORS.
   - 5.C. DO NOT COMBINE NEUTRALS. PROVIDE DEDICATED NEUTRALS FOR EACH BRANCH CIRCUIT.
   - 5.D. MULTIPLE DEVICES ON A CIRCUIT SUCH AS RECEPTACLES SHALL BE WIRED WITH A PIGTAIL SO THE DEVICE DOES NOT PROVIDE THE CONTINUITY PATH. FEED THROUGH CONNECTIONS FOR GFCI RECEPTACLES SHALL NOT BE USED FOR PROTECTION OF DOWNSTREAM DEVICES.
6. PROVIDE GREEN GROUND WIRE WITH ALL CIRCUITS SIZED PER NEC. BOND GREEN GROUND WIRE TO EACH END OF CONDUIT.
7. PROVIDE J–BOXES, CONDUIT AND DEVICES THRU ALL FIRE WALLS FOR DATA, TELEPHONE, SECURITY, FIRE ALARM, SOUND SYSTEM, LOW VOLTAGE WIRING, ETC. PROVIDE PROTECTIVE BUSHINGS ON ENDS OF ALL LOW VOLTAGE CONDUITS.
8. PROVIDE PULL BOXES, JUNCTION BOXES, WIRING TROUGHS AND CABINETS WHEREVER REQUIRED FOR PROPER INSTALLATION OF VARIOUS ELECTRICAL SYSTEMS. ALL JUNCTION/PULL BOXES INSTALLED ABOVE ACCESSIBLE CEILINGS SHALL BE MOUNTED SO THAT THE ACCESS PANEL IS NO HIGHER THAN 18" ABOVE THE CEILING.
9. PROVIDE CIRCUIT LABELS IN PERMANENT MARKER ON ALL NEW AND EXISTING J–BOX COVERS UTILIZED IN THE AREA OF RENOVATION.
10. PROVIDE CIRCUIT LABEL ON ALL ABOVE CEILING J–BOXES, EQUIPMENT, ETC. IDENTIFYING THE CIRCUITS CONTAINED/CONNECTED.
11. ALL WIRING SHALL BE 600 VOLT, SOFT DRAWN ANNEALED COPPER, 98% CONDUCTIVITY, CONTINUOUS FROM OUTLET TO OUTLET. MINIMUM WIRE SIZE #12.
    - 11.A. TYPICAL BUILDING WIRE SHALL BE STRANDED TYPE THHN, THWN–2 (WET RATED FOR 90°C), OR XHHW–2. MINIMUM WIRE SIZE SHALL BE #12.
    - 11.B. ALL BUILDING WIRE SHALL BE COLOR CODED WITH THE SAME COLOR CONNECTED TO THE SAME UNGROUNDED PHASE THROUGHOUT THE INSTALLATION MATCHING THE EXISTING BUILDING COLOR CODE SCHEME.
12. WHERE PORTIONS OF INTERIOR RACEWAY SYSTEM ARE EXPOSED TO WIDELY DIFFERENT TEMPERATURES, PROVIDE AIR SEAL PER NEC TO PREVENT CIRCULATION OF AIR FROM WARMER TO COOLER SECTIONS.
13. DRAWINGS, SCHEDULES, NOTES, AND DETAILS ARE INTENDED TO BE COMPLIMENTARY. ANY WORK DESCRIBED IN ANY OF THEM, WILL BE WORK REQUIRED UNDER THIS CONTRACT. WHERE THERE IS A CONFLICT BETWEEN DIFFERENT PORTIONS OF THE DESIGN DOCUMENTS IT SHALL BE CLARIFIED BY RFI. BARRING CLARIFICATION PRIOR TO BIDDING THE MOST EXPENSIVE OPTION SHALL BE INCLUDED AND CLARIFICATION SHALL BE MADE DURING CONSTRUCTION.
14. SHOULD ANY WORK REQUIRED BY THE DRAWINGS AND SPECIFICATIONS BE IN VIOLATION OF ANY FEDERAL, STATE, COUNTY OR CITY LAWS, ORDINANCE OR REGULATION, THOSE LAWS AND REGULATIONS SHALL PREVAIL, AND SHALL BE COMPLIED WITH BY THE CONTRACTOR AS A PART OF THIS WORK WITH NO EXTRA COMPENSATION.
15. ALL MATERIAL MUST BE NEW AND OF GOOD QUALITY AND SHALL BEAR THE STAMP OF APPROVAL OF THE UNDERWRITERS' LABORATORIES, INC. (U.L.).

GENERAL RENOVATION AND REMODELING NOTES:

1. THESE ELECTRICAL DRAWINGS ONLY SHOW SOME EXISTING ELECTRICAL PANELS, DEVICES AND LIGHT FIXTURES IN AREAS OF RENOVATION. ALL OTHER ELECTRICAL EQUIPMENT, WIRING DEVICES, LOW VOLTAGE SYSTEMS, J–BOXES AND CONDUITS SHALL BE LOCATED AND FIELD VERIFIED BY CONTRACTOR.
2. ALL REMOVED DEVICES SHALL BE OFFERED TO THE OWNER AS SALVAGE.
3. RELOCATE CONDUIT AS NECESSARY TO ALLOW NEW OR MODIFIED CONSTRUCTION. RESUPPORT EXISTING CABLING/CONDUIT TO REMAIN TO MEET CURRENTLY ADOPTED CODE REQUIREMENTS. REMOVE ALL ABANDONED CONDUIT AND WIRE. REPAIR EXISTING ELECTRICAL SYSTEMS DAMAGED BY CONSTRUCTION ACTIVITIES.
4. ANY DAMAGE TO EXISTING BUILDING, ELECTRICAL EQUIPMENT, WIRING DEVICES, CONDUIT, WIRING, ETC. SHALL BE REPLACED BY THE CONTRACTOR AT NO COST TO THE OWNER. ALL MATERIALS USED FOR THE REPLACEMENT MUST MEET RENOVATION PROJECT STANDARDS.
5. ELECTRICAL CONTRACTOR SHALL BEGIN FIELD VERIFYING ALL EXISTING BRANCH CIRCUITS FOR EXISTING AREAS TO BE RENOVATED IMMEDIATELY AFTER THE CONTRACT IS ISSUED.
6. ELECTRICAL CONTRACTOR SHALL FIELD VERIFY EXISTING CIRCUITS WITH OWNER'S MAINTENANCE PERSONNEL AFTER NORMAL BUILDING HOURS AS REQUIRED.
7. ANY CIRCUIT OR PARTIAL CIRCUIT TO REMAIN OR BE REUSED SHALL REMAIN ACTIVE.
8. ELECTRICAL CONTRACTOR SHALL INCLUDE COST RELATED TO FIELD VERIFY EXISTING CIRCUITS IN BASE PROPOSAL.
9. FIND AND RECORD ALL EXISTING DEVICES IN CEILINGS, WALLS AND CASEWORK IN AREAS TO BE RENOVATED. PROVIDE A COPY OF THE FIELD VERIFIED DEVICE DRAWINGS TO OWNER PRIOR TO BEGINNING WORK.
10. AT THE END OF THE PROJECT PROVIDE A NEW TYPEWRITTEN AS–BUILT PANEL SCHEDULE FOR ALL PANELS WITH CIRCUITS ADDED, REMOVED, OR MODIFIED AS PART OF THE PROJECT USING BUILDING ROOM NUMBERS.





## 3 PARTIAL ELECTRICAL RISER - CORNERSTONE ELEMENTARY

NO SCALE

NOTES:

1. FIELD VERIFY ALL EXISTING ELECTRICAL PANELS AND FEEDERS SHOWN ON DRAWINGS.
2. REF ELECTRICAL FLOOR PLANS FOR PANEL LOCATIONS.
3. ALL OUTAGES SHALL BE SCHEDULED/CONFIRMED IN WRITING WITH THE OWNER A MINIMUM OF TWO WEEKS PRIOR TO ANY OUTAGE.
4. AT THE END OF THE PROJECT PROVIDE A NEW TYPEWRITTEN PANEL SCHEDULE USING BUILDING ROOM NUMBERS FOR ALL PANELS WITH CIRCUITS ADDED, REMOVED, OR MODIFIED AS PART OF THE PROJECT.
5. REFERENCE PANEL SCHEDULES AND SHORT CIRCUIT TABLE FOR AIC AND SCCR VALUES.




## 1 ELECTRICAL RENOVATION PLAN

SCALE: 1/8" = 1'- 0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

e

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
CORNERSTONE ELEMENTARY SCHOOL
1800 CHATHAM AVE
SUGAR LAND, TX 77479

SEAL




07.18.2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL FLOOR PLAN & SCHEDULES

e-E.200

STANTON ENGINEERING GROUP
INFORMATION@STANTONEG.COM (713) 305–6082
TEXAS ENG. FIRM REG. NO. F–018332 © 2025 ALL RIGHTS RESERVED
12800 W. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77064

## AUDIO/VISUAL MULTIMEDIA LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| A## V## | WALL AV ROUGH-IN DETAIL |
| A## V## | CEILING AV ROUGH-IN DETAIL |
| A## V## | FLOOR AV ROUGH-IN DETAIL |
| IWB IWB | INTERACTIVE WHITE BOARD - WALL - CEILING |
| PJ PJ | MULTIMEDIA PROJECTOR |
| FP# FP# | MULTIMEDIA FLAT PANEL DISPLAY |
| S S | LOUDSPEAKER, WALL MOUNTED AND CEILING MOUNTED RESPECTIVELY - # INDICATES TYPE |
| CP# | CONTROL PANEL |
| TP# | TOUCH PANEL |
| M | MICROPHONE, CEILING MOUNTED - # INDICATES TYPE |
| VC | VOLUME CONTROL |
| WB | WALL BOX ENCLOSURE |
| D1 A1 | D1 = DIGITAL SINGLE SIDED CLOCK / A1 = ANALOG SINGLE SIDED CLOCK |
| D2 A2 | D2 = DIGITAL DOUBLE SIDED CLOCK / A2 = ANALOG DOUBLE SIDED CLOCK |
| ENC | CEILING AV ENCLOSURE |
| C C | PRESENTATION CAMERA - CEILING - WALL MOUNTED |

## PREMISE SECURITY LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| CR | CARD READER |
| CR M | CARD READER MULLION |
| KP | INTRUSION DETECTION KEYPAD |
| IC | INTERCOM (1 DATA CABLE) |
| IC MS | INTERCOM MASTER STATION (1 DATA CABLE) |
| PB | PANIC/DURESS BUTTON |
| LD | LOCK DOWN BUTTON |
| MD | MOTION DETECTOR |
| GB | ACCOUSTICAL GLASS BREAK SENSOR |
| BM | BIOMETRIC READER |
| RX | REQUEST TO EXIT - SURFACE PIR |
| KS | KEY SWITCH |
| LA | LOCAL ALARM SOUNDER |
| RG | RED/GREEN INDICATOR LIGHT |
| DB | DOORBELL |
| DH | MAGNETIC DOOR HOLD |
| DR | DOOR RELEASE |
| RX | REQUEST TO EXIT - INTEGRAL TO DOOR HARDWARE |
| DC | DOOR CONTACT / MONITOR |
| ES EL EH | ELECTRIFIED STRIKE - ELECTRIFIED LATCH - ELECTRIFIED HARDWARE (REFER TO SCHEDULES) |
| C C | STANDARD IP SURVEILLANCE CAMERA, (1) CABLE |
| C C C | 180° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° FISHEYE LENS CAMERA |
| IR | IR ILLUMINATOR |

## STRUCTURED CABLING LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF DATA CABLE(S)/JACK(S) |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) |
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| W | WALL MOUNT PHONE (1 CABLE/JACK) |
| W | WALL MOUNT PHONE, SURFACE MOUNT (1 CABLE/JACK) |
| # | FLOOR MOUNTED OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| #/# | FLOOR MOUNTED OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| # | CEILING MOUNTED DATA OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) |
| AP# | CEILING MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| AP# | WALL MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| | CABLING SLEEVE(S) |
| | TYPICAL LADDER RACK |
| | TYPICAL CABLE TRAY, BASKET STYLE |

## GENERAL ANNOTATION LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| MER | MAIN EQUIPMENT ROOM |
| TR | TELECOMMUNICATION ROOM |
| MDF | MAIN DISTRIBUTION FRAME |
| IDF | INTERMEDIATE DISTRIBUTION FRAME |
| ETR | EXISTING TO REMAIN |
| PBO | PROVIDED BY OTHERS |
| AFF | ABOVE FINISHED FLOOR |
| AFG | ABOVE FINISHED GRADE |
| AC | ABOVE COUNTER |
| EC | ELECTRICAL CONTRACTOR |
| PSC | PREMISE SECURITY CONTRACTOR |
| SCC | STRUCTURAL CABLING CONTRACTOR |
| AVC | AV/MULTIMEDIA CONTRACTOR |
| UNO | UNLESS NOTED OTHERWISE |
| ACS | ACCESS CONTROL SYSTEM |
| VSS | VIDEO SURVEILLANCE SYSTEM |

## TECHNOLOGY - GENERAL NOTES

1. EACH KEYNOTE MAY NOT BE UTILIZED ON EVERY SHEET.
2. ALL CONDUIT MEASUREMENTS REFER TO STANDARD CONDUIT TRADE SIZES.
3. ALL CABLES SHALL BE CONCEALED.
4. EACH CONTRACTOR SHALL PROVIDE AND INSTALL ALL NECESSARY SLEEVES, WHETHER OR NOT SPECIFICALLY NOTED ON PROJECT DRAWINGS. ALL SLEEVES SHALL BE 2" UNLESS NOTED OTHERWISE ON THE DRAWINGS. CABLE FILL PERCENTAGE SHALL COMPLY WITH NEC.
5. DEVICE LOCATIONS ARE APPROXIMATE. CONTRACTOR SHALL REVIEW CONDITIONS AND COORDINATE WITH OTHER TRADES AS NECESSARY FOR EXACT PLACEMENT.

## TECHNOLOGY SYMBOLS LEGEND

NOT ALL SYMBOLS ARE USED

- AV WALL ROUGH-IN WITH DATA
- KEYNOTE
- Proposed Camera Direction
  SURVEILLANCE CAMERA
  Camera Schedule Number (Floor #-Camera #)
  Camera (N)ew, (E)xisting Rough-in, (D)emo
- Proposed Camera Direction
  PTZ CAMERA
  PTZ
- Proposed Camera Direction
  FIXED SURVEILLANCE CAMERA
- 360°/MULTI-SENSOR FIXED SURVEILLANCE CAMERA OR FISHEYE LENS CAMERA
- Approximate view of lens
  Lens View Angle
  360°/MULTI-SENSOR FIXED SURVEILLANCE CAMERA OR FISHEYE LENS CAMERA
  Lens size
- MICROPHONE WITH AUDIO LINKED TO CAMERA
- CARD READER LINKED TO CAMERA
- SYMBOL TAG
  (#) = DIFFERENT TYPES OF CARD READERS:
  M = MULLION
  W = WIRELESS (Proprietary)
  Wi = Wi-Fi (802.11)
  POE = POWER OVER ETHERNET
- SYMBOL TAG
  (#) = DIFFERENT TYPES OF CARD READERS:
  TS = TOUCHSCREEN
  PU = PUSH BUTTON
- TOP = DETAIL NUMBER
  DETAIL REFERENCE
  BOTTOM = SHEET NUMBER
- NORTH ARROW
- SHEET NUMBER
  SECTION MARKER
  DETAIL NUMBER
- DIRECTION OF ELEVATION
  ELEVATION MARKER
  SHEET NUMBER
  DETAIL NUMBER
- DIRECTION OF ELEVATION
  SHEET NUMBER
  DIRECTION OF ELEVATION
  DETAIL NUMBER
- BAR IS ONE INCH ON ORIGINAL DRAWING. IF NOT ONE INCH ON THIS DRAWING ADJUST SCALES ACCORDINGLY

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

e

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Cornerstone Elementary School
1600 Chatham Ave, Sugar Land, TX 77479

SEAL

BICSI CERTIFIED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 258657
EXPIRES 10-31-27
NCCDD

07-18-25


MVA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY - TITLE SHEET

e-TN000

## TECHNOLOGY KEYNOTES

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.




1 CORNERSTONE - OVERALL
SCALE: 1" = 20'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

e

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Cornerstone Elementary School
1800 Chatham Ave, Sugar Land, TX 77479

SEAL




07-18-25


MWA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING
AND
PERMITTING

TECHNOLOGY - Cornerstone
ES - OVERALL

e-TN.100

TRUENORTH A PWY COMPANY




2 CORNERSTONE - REFLECTED CEILING PLAN
SCALE: 3/16" = 1'-0"

**TECHNOLOGY KEYNOTES**

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

e

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Cornerstone Elementary School
1800 Chatham Ave, Sugar Land, TX 77479

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 254657
EXPIRES 12-31-27
RCDD
07-18-25


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Cornerstone ES - KITCHEN


e-TN.101

**GENERAL NOTE**


1. FACE PLATE DETAIL FOR OUTLET CONFIGURATION PURPOSES ONLY. CONTRACTOR TO SELECT TYPE OF FACE PLATE TO MATCH CONNECTIVITY HARDWARE, FLOOR BOX AND/OR MODULAR FURNITURE OPENING.





1 DATA ROUGH-IN DETAILS
SCALE: NS




2 TYPICAL CABLING SLEEVE
SCALE: NTS




3 PANDUIT J-HOOK DETAIL
SCALE: NTS




4 LABELING & CABLING SCHEMES
SCALE: NTS




5 CABLE PATHWAY CROSS SECTION
SCALE: NTS




6 DROPPED CEILING MOUNTING DETAIL
SCALE: NS




7 I-JOIST MOUNTING DETAIL
SCALE: NS




8 BAR JOIST MOUNTING DETAIL
SCALE: NS

| CAMERA TYPE | MANUFACTURER | MODEL NUMBER | GENERAL DESCRIPTION |
|---|---|---|---|
| C1 | iPro | WV-S8574L | 4x4K (33MP) EXTERIOR MULTI-SENSOR - PARKING LOTS, STADIUM |
| C2 | iPro | WV-S8544L | 4x4MP (16MP) EXTERIOR MULTI-SENSOR - BUILDING PERIMETER |
| C3 | iPro | WV-S25500-V3LN | 5MP EXTERIOR VANDAL DOME |
| C4 | iPro | WV-S22500-V3L | 5MP INTERIOR VANDAL DOME - CORR., COMMON, SPED |
| C5 | iPro | WV-S4156A | 5MP 360 (FISHEYE) - STAIRWELLS |

9 CAMERA SCHEDULE
SCALE: NTS

| Symbol | Purpose | Size | Mount | Backbox | Notes |
|---|---|---|---|---|---|
| FP1 | Digital Signage/Menu Boards | +49" | Ceiling Pole | N/A | Data and Power Outlets on ceiling |

10 DISPLAY SCHEDULE
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

e

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Cornerstone Elementary School
1800 Chatham Ave, Sugar Land, TX 77479

SEAL

BICSI REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256557
EXPIRES 12-31-27

07-18-25


MVA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Cornerstone ES - OVERALL - DETAILS


e-TN.500

GENERAL NOTES:


1. REFER TO SECURITY SCHEDULE AND WRITTEN SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
2. ALL MOUNTING DETAILS ARE REFERENCE FOR ALL FIXED DOME, 180°, 360°, PTZ, AND "BULLET/BOX" CAMERAS.





1 TYPICAL CAMERA INSTALLATION SECTION DETAIL
SCALE: NS




6 WALL MOUNTED CAMERA DETAIL
SCALE: NS




4 TILE BRIDGE DETAIL
SCALE: NS





5 CEILING MOUNTED CAMERA DETAIL
SCALE: NS


ACCESS CONROL DETAILS AND GENERAL NOTES:

1. CONDUIT ROUGH-IN IS A GUIDE FOR WHAT WILL BE REQUIRED FOR EACH DOOR. AS DOOR COMPONENTS CHANGE, EXACT CONDUIT LOCATION WILL ALSO NEED TO BE ADJUSTED.


2. PROTECT EXISTING-TO-REMAIN ACCESS CONTROL DEVICES AND CABLE THROUGHOUT RENOVATION WORK. IF CABLE AND/OR DEVICES ARE DAMAGED, SECURITY CONTRACTOR TO REPLACE WITH NEW.




1 ACCESS CONTROL - WIRING DETAIL - EXIT DEVICE W/ BUILT-IN REX
SCALE: NTS




2 ACCESS CONTROL - STEEL/HOLLOW METAL DOOR.
SCALE: NTS




KP PB LD

3 ROUGH-IN DETAILS: KP, PB, LD
SCALE: NTS

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

e

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Cornerstone Elementary School
1800 Chatham Ave, Sugar Land, TX 77479

SEAL




07-18-25

MVA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Cornerstone ES - SECURITY DETAILS

e-TN.600

TRUENORTH A PMY COMPANY

# FBISD BP013 KITCHEN RENOVATIONS ES

DULLES ELEMENTARY SCHOOL
630 DULLES AVE, SUGAR LAND, TX 77478

FORT BEND INDEPENDENT SCHOOL DISTRICT

| Sheet List Table | |
|---|---|
| Sheet Number | Sheet Title |
| School: f-Dulles ES | |
| f-A.000 | COVER AND INDEX |
| f-A00-01 | GENERAL NOTES AND ABBREVIATIONS |
| f-D.101 | DEMO PLAN |
| f-A.101 | SITE PLAN |
| f-A.201 | OVERALL FLOOR PLAN |
| f-A.301 | KITCHEN FLOOR PLAN |
| f-QF1 | FS GENERAL COORDINATION NOTES |
| f-QF1.0 | FS EQUIPMENT ELECTRICAL PLAN |
| f-E.200 | ELECTRICAL FLOOR PLAN & SCHEDULES |
| f-TN.000 | TECHNOLOGY - INDEX SHEET |
| f-TN-100 | TECHNOLOGY - OVERALL |
| f-TN-101 | TECHNOLOGY - KITCHEN |
| f-TN-500 | TECHNOLOGY - DETAILS |
| f-TN-600 | TECHNOLOGY - SECURITY DETAILS |




ISSUED FOR BIDDING AND PERMITTING - JULY 18, 2025

## ADMINISTRATION

| | |
|---|---|
| DR. MARCELL SMITH | SUPERINTENDENT OF FBISD |
| DR. ANDRIA SCHUR, Ed.D. | CHIEF OF SCHOOLS |

## BOARD OF TRUSTEES

| | |
|---|---|
| KRISTIN K. TASSIN | PRESIDENT |
| RICK GARCIA | VICE PRESIDENT |
| DAVID HAMILTON | SECRETARY |
| ANGIE HANAN | BOARD MEMBER |
| ADAM SCHOOF | BOARD MEMBER |
| DR. SHIRLEY ROSE-GILLIAM | BOARD MEMBER |
| SONYA JONES | BOARD MEMBER |

## PROJECT DESIGN TEAM

PROGRAM MANAGEMENT
FBISD 2023 Bond Team
2323 Texas Parkway
Missouri City, TX 77489
Phone Number: 281-327-5481

ARCHITECT
MWA Architects
11767 Katy Freeway, Suite 430
Houston, Texas 77079
Phone Number: 713-782-8188

FOOD SERVICE
Food Design Professionals
26215 Oak Ridge Drive
The Woodlands, Texas 77380
Phone Number: 281-350-2323

MEP ENGINEERS
Stanton Engineering Group
1300 W. Sam Houston Pkwy South, Suite 121
Houston, Texas 77042
Phone Number: 713-300-9292

STRUCTURAL ENGINEER
Stanley Spurling & Hamilton
3301 Edloe Street, Suite 200
Houston, Texas 77027
Phone Number: 713-776-9433

PART 1 - GENERAL

1.1 GENERAL DEMOLITION NOTES

A. VERIFY EXISTING SITE AND BUILDING CONDITIONS IN FIELD PRIOR TO BIDDING. NOTIFY ARCHITECT OF ANY DISCREPANCIES PRIOR TO BIDDING.

B. CONTRACTOR SHALL COORDINATE WITH OWNER THE SALVAGE OF ITEMS, FURNITURE AND EQUIPMENT INDICATED TO BE REMOVED.

C. CLAIMS FOR ADDITIONAL COST OR TIME DUE TO EXISTING CONDITIONS THAT COULD HAVE BEEN REASONABLY ANTICIPATED DURING A SITE VISIT BY THE CONTRACTOR PRIOR TO BIDDING WILL NOT BE APPROVED.

D. PROTECT EXISTING FINISHES SHOWN TO REMAIN DURING CONSTRUCTION TO PREVENT DAMAGE. REPAIR OR REPLACE DAMAGED MATERIALS AND FINISHES TO MATCH EXISTING AT NO ADDITIONAL COST TO FORT BEND ISD (OWNER).

E. EXISTING AREAS REQUIRING MINOR DEMOLITION OR REPAIR FOR EXECUTION OF WORK SHALL BE REPAIRED TO MATCH EXISTING ADJACENT MATERIALS, UNLESS NOTED OTHERWISE.

F. DO NOT DAMAGE CASEWORK AND EQUIPMENT NOT DESIGNATED TO BE REMOVED OR RELOCATED.EXISTING CASEWORK SHALL REMAIN THE PROPERTY OF THE OWNER.

G. CONTRACTOR TO VERIFY LOCATION OF ELEC. SWITCHES, OUTLETS, GRILLES, CLEAN-OUTS, COVER PLATES, ACCESS DOORS, AND OTHER EQUIPMENT AND DEVICES THAT MAY CONFLICT WITH THE RENOVATION AND NEW CONSTRUCTION OF WALLS, FLOORS, AND CEILINGS PRIOR TO COMMENCEMENT OF WORK. CONTRACTOR SHALL LIKEWISE CONFIRM THAT ELECTRICAL CONDUIT ROUTING SHALL BE CONCEALED WITHIN WALLS. NOTIFY ARCHITECT IF WALL THICKNESS WILL NOT ALLOW FOR CONCEALMENT.

H. REMOVE ANY EXISTING CORNER GUARDS IN THE KITCHEN AREA.

I. PRIOR TO EXECUTION OF DEMOLITION WORK, SCHEDULE A WALK-THROUGH WITH OWNER AND ARCHITECT TO CONFIRM SCOPE OF WORK AND TO REVIEW EXISTING CONDITIONS.

J. EXISTING FLOOR FINISHES AND ACOUSTIC CEILING TILE TO BE REMOVED THROUGHOUT.

K. REFER TO MEP DRAWINGS FOR DEMOLITION AND ALTERATION OF UTILITIES.

L. AT ALL EXISTING WALLS REQUIRING DEMOLITION TO INSTALL NEW PIPING BEHIND SINKS, CUT AND PATCH WALLS AS REQUIRED TO MATCH ADJACENT SURFACE.

M. CLEAN AND PREPARE SUBFLOOR FOR INSTALLATION OF NEW FLOOR FINISH.

N. DEMOLITION ACTIVITIES SHALL BE PERFORMED AS TO PRODUCE MINIMAL DISTURBANCE TO EXISTING FACILITY OCCUPANTS. MINIMIZE EXCESSIVE AND PROLONGED NOISE LEVELS AND DUST.

O. ASBESTOS-CONTAINING MATERIALS. REFER TO SPECIFICATION 02 26 23 FOR ASBESTOS INFORMATION APPLICABLE TO KITCHEN AREAS. FORT BEND ISD HAS RETAINED A SEPARATE ENVIRONMENTAL CONSULTANT FOR THE REMOVAL OF ASBESTOS. GC TO COORDINATE WITH ENVIRONMENTAL CONSULTANT TO CARRY OUT ASBESTOS ABATEMENT FOR ALL AFFECTED KITCHEN AREAS.

1.2 FLOOR PLAN GENERAL NOTES

A. FIELD VERIFY EXISTING CONDITIONS PRIOR TO GENERATING SHOP DRAWINGS AND FABRICATION OF EQUIPMENT.
B. FLOOR FINISH CHANGES SHALL OCCUR AT THE CENTERLINE OF DOORS UNLESS NOTED OTHERWISE. FLOOR FINISH CHANGES SHALL HAVE THRESHOLDS OR REDUCERS STRIPS.
C. DOORS THAT ARE TO BE REPLACED AND INSTALLED IN EXISTING FRAMES SHALL BE MACHINED FOR HARDWARE DIMENSIONS AT EXISTING FRAMES, CONTRACTOR SHALL FIELD VERIFY FRAME CONDITIONS AND DIMENSIONS.
D. CONTRACTOR TO PROVIDE SHEET METAL REINFORCING STRAP AS REQUIRED FOR MOUNTING OF ALL GRAB BARS, CABINETS, MIRRORS, SHELVING, ETC.
E. SAW CUT AND REMOVE EXISTING SLAB AND FLOOR FINISHES AS REQUIRED TO INSTALL NEW PLUMBING LINES, FLOOR DRAINS, PLUMBING FIXTURES, OR ELECTRICAL ITEMS. SPLICE NEW REINFORCING BARS DOWELED INTO EXISTING CONCRETE, AND PROVIDE NEW VAPOR RETARDER AND WATERSTOPS, AND PATCH W/ 3000 PSI CONCRETE AFTER INSTALLATION OF UTILITIES AND FIXTURES. PREPARE CONCRETE TO RECEIVE NEW FINISH.
F. COORDINATE HOUSEKEEPING PAD DIMENSIONS AND LOCATIONS WITH EQUIPMENT TO BE INSTALLED. HOUSEKEEPING PADS SHALL BE A MIN. OF 4" THICK REINF. W/ #3 BARS AT 15" O.C. BOTH WAYS. PROVIDE 1" BY 45-DEGREE CHAMFERED EDGES.

1.3 COMPLETE PERFORMANCE

L. THE CONTRACTOR SHALL FURNISH AND INSTALL ALL ITEMS SPECIFIED HEREIN AND AS INDICATED ON THE DRAWINGS. THE CONTRACTOR SHALL ALSO FURNISH AND INSTALL ALL ITEMS NECESSARY TO MAKE THE SYSTEMS FUNCTION WHICH MAY BE REASONABLY IMPLIED AS ESSENTIAL, WHETHER MENTIONED IN THE CONTRACT DOCUMENTS OR NOT.

M. WORK SHALL BE EXECUTED IN STRICT ACCORDANCE WITH THE BEST PRACTICE OF THE TRADES IN A THOROUGH, SUBSTANTIAL AND WORKMANLIKE MANNER BY COMPETENT WORKMEN.

1.4 SITE FAMILIARIZATION

A. GENERAL: BECOME FAMILIAR WITH THE DRAWINGS AND SPECIFICATIONS, EXAMINE THE PREMISES, AND UNDERSTAND THE CONDITIONS UNDER WHICH THE CONTRACT SHALL BE PERFORMED, PRIOR TO SUBMITTING A BID.

B. SITE: BE INFORMED OF THE SITE CONDITIONS, VERIFY LOCATIONS OF NEW AND EXISTING EQUIPMENT, AND DETERMINE EXACT REQUIREMENTS FOR CONNECTIONS.

C. COORDINATION: TENDER OF A PROPOSAL FOR THIS PROJECT INFERS THAT THE CONTRACTOR HAS VISITED THE SITE AND HAS BECOME FAMILIAR WITH THE DRAWINGS, SPECIFICATIONS, AND SITE CONDITIONS AND HAS INCLUDED IN HIS PROPOSAL ALL WORK NECESSARY TO PROPERLY INSTALL COMPLETE AND FUNCTIONING SYSTEMS ON THE PROJECT. FAILURE TO COMPLY WITH THIS REQUIREMENT SHALL NOT BE CONSIDERED JUSTIFICATION FOR THE OMISSION OR FAULTY INSTALLATION OF ANY WORK COVERED BY THE CONTRACT DOCUMENTS.

1.5 CODES AND STANDARDS

A. GENERAL: ALL WORK SHALL COMPLY WITH THE MOST RECENTLY REVISED VERSIONS OF ALL APPLICABLE LAWS, RULES, REGULATIONS AND ORDINANCES OF ALL FEDERAL, STATE AND LOCAL AUTHORITIES AND APPLICABLE UTILITIES. NONE OF THE TERMS OR PROVISIONS OF THIS SPECIFICATION SHALL BE CONSTRUED AS WAIVING ANY PART OF THE LAWS, RULES, REGULATIONS OR REQUIREMENTS OF THESE AUTHORITIES.

B. CONFLICT: IN THE EVENT OF CONFLICT BETWEEN THE CONTRACT DOCUMENTS AND THE LOCAL ENFORCING AUTHORITY, THE LATTER SHALL RULE. ANY MODIFICATIONS RESULTING THEREFROM SHALL BE MADE WITHOUT ANY ADDITIONAL COST TO THE OWNER OR ARCHITECT. THIS CONTRACTOR SHALL REPORT ANY SUCH MODIFICATIONS TO THE ARCHITECT AND SECURE HIS APPROVAL PRIOR TO PROCEEDING WITH THE WORK.

C. PRECEDENCE: WHERE CONTRACT DOCUMENT REQUIREMENTS EXCEED THE REQUIREMENTS OF THE CODES AND STANDARDS, THE CONTRACT DOCUMENTS SHALL TAKE PRECEDENCE PROVIDED THEY ARE NOT IN CONFLICT WITH THOSE CODES AND STANDARDS.

D. APPROVAL LABELS: ALL ITEMS OF EQUIPMENT AND ALL MATERIALS FOR WHICH APPROVED STANDARDS HAVE BEEN ESTABLISHED BY UNDERWRITERS' LABORATORIES, INC. (UL), FACTORY MUTUAL (FM), CERTIFIED BALLAST MANUFACTURER (CBM), ELECTRICAL TESTING LABORATORY (ETL), NATIONAL MANUFACTURERS ASSOCIATION (NEMA), AMERICAN STANDARD CODES, ASME, AGA, AMCA, ASA, ANSI, ASHRAE, AND ARI SHALL BE SO APPROVED AND SHALL BEAR APPROVAL LABELS ATTESTING TO SAME.

1.6 DRAWINGS AND SPECIFICATIONS

A. DRAWINGS: THE SET OF ORIGINAL DRAWINGS HAS BEEN MODIFIED AND INDICATE APPROXIMATE EXISTING LOCATIONS OF THE FLOOR FINISH ITEMS. ALL ITEMS ARE SHOWN APPROXIMATELY TO SCALE. FIELD VERIFY CONDITIONS.

B. SPECIFICATIONS: THE SPECIFICATIONS ARE INTENDED TO SUPPLEMENT THE DRAWINGS AND IT IS NOT IN THE SCOPE OF THE SPECIFICATIONS TO MENTION ANY PART OF THE WORK THAT THE DRAWINGS ARE COMPETENT TO FULLY EXPLAIN. CONVERSELY, ANY PART OF THE WORK THAT THE SPECIFICATIONS ARE COMPETENT TO FULLY EXPLAIN MAY NOT BE MENTIONED ON THE DRAWINGS. DRAWINGS AND SPECIFICATIONS ARE COMPLIMENTARY/SUPPLEMENTARY DOCUMENTS TO EACH OTHER.

C. DISAGREEMENT: DISAGREEMENT BETWEEN THE DRAWINGS AND SPECIFICATIONS OR WITHIN THE DRAWINGS OR SPECIFICATIONS SHALL BE ESTIMATED AND/OR BID USING THE BETTER QUALITY OR GREATER QUANTITY OF MATERIAL OR INSTALLATION, AND A CLARIFICATION REQUEST FOR INFORMATION SHALL BE MADE TO THE ARCHITECT IN A TIMELY MANNER AFTER THE PROJECT IS UNDER CONTRACT.

1.7 DISCREPANCIES

A. CLARIFICATION: CLARIFICATION OF SIGNIFICANT COST MATTERS SHALL BE OBTAINED BEFORE SUBMITTING A PROPOSAL FOR THE WORK AS TO DISCREPANCIES OR OMISSIONS FROM THE CONTRACT DOCUMENTS OR QUESTIONS AS TO THE INTENT THEREOF.

B. INTERPRETATIONS: SHOULD ANY DOUBT OR QUESTION ARISE RESPECTING THE TRUE MEANING OF DRAWINGS OR SPECIFICATIONS, REFERENCE SHALL BE MADE TO THE ARCHITECT, WHOSE WRITTEN DECISION SHALL BE FINAL AND CONCLUSIVE. NO ALLEGED STATEMENT BY THE ARCHITECT WILL BE ACCEPTED AS AN EXCUSE FOR NON-COMPLIANCE OR INFERIOR WORK.

C. CONTRACTOR AGREEMENT: CONSIDERATION WILL NOT BE GRANTED FOR MISUNDERSTANDING OF THE AMOUNT OF WORK TO BE PERFORMED. TENDER OF A PROPOSAL CONVEYS FULL CONTRACTOR AGREEMENT OF THE ITEMS AND CONDITIONS SPECIFIED, SHOWN, SCHEDULED, OR REQUIRED BY THE NATURE OF THE PROJECT, AND ALL COSTS ARE INCLUDED IN THE PROPOSAL.

1.8 REQUESTS FOR INFORMATION (RFI)

A. GENERAL: SUBMIT ALL CONTRACTOR REQUESTS FOR INFORMATION (RFI) IN WRITING TO THE ARCHITECT FOR RESPONSE. SUBMIT RFI ON A STANDARD FORM THAT HAS A SPACE FOR THE REQUESTED INFORMATION AND THE ARCHITECT'S RESPONSE.
B. SOLUTION PROPOSAL: IN GENERAL, THE CONTRACTOR SHALL PROPOSE SOLUTIONS TO IDENTIFY PROBLEMS FOR REVIEW AND APPROVAL OF THE ARCHITECT. THE RFI SHALL INCLUDE HAND SKETCHES, MARKED DRAWING PRINTS, EQUIPMENT CUTSHEETS, DRAWING AND SPECIFICATION REFERENCES, AND ANY OTHER BACK-UP INFORMATION, ETC., AS REQUIRED TO SUFFICIENTLY EXPLAIN THE PROBLEM AND PROPOSED SOLUTION.

1.9 QUALITY ASSURANCE

A. GENERAL: MATERIALS AND EQUIPMENT SHALL BE NEW, OF BEST GRADE AND QUALITY, AND STANDARD PRODUCTS OF REPUTABLE MANUFACTURERS REGULARLY ENGAGED IN THE PRODUCTION OF SUCH MATERIALS AND EQUIPMENT.
B. WORKMANSHIP: WORK SHALL BE EXECUTED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE BEST PRACTICE OF THE TRADES IN A THOROUGH, SUBSTANTIAL, WORKMANLIKE MANNER BY COMPETENT WORKMEN, PRESENTING A NEAT APPEARANCE WHEN COMPLETED.
C. JUDGMENT: IN ALL CASES, THE ARCHITECT SHALL BE THE SOLE JUDGE OF THE QUALITY AND EQUIVALENCE OF MANUFACTURERS, PRODUCTS, MATERIALS, AND METHODS.
D. MANUFACTURERS/PRODUCTS/MATERIALS/METHODS: MANUFACTURERS, PRODUCTS, MATERIALS, AND METHODS DESCRIBED IN THE VARIOUS SECTIONS OF THE SPECIFICATIONS AND INDICATED ON THE DRAWINGS ARE INTENDED TO ESTABLISH A STANDARD OF QUALITY ONLY. IT IS NOT THE INTENTION OF THE ARCHITECT TO DISCRIMINATE AGAINST ANY MANUFACTURER, PRODUCT, MATERIAL, OR METHOD THAT IS EQUAL TO THE STANDARDS AS INDICATED AND/OR SPECIFIED, NOR IS IT INTENDED TO PRECLUDE OPEN, COMPETITIVE BIDDING. THE FACT THAT A SPECIFIC MANUFACTURER IS LISTED AS AN ACCEPTABLE MANUFACTURER SHALL NOT BE INTERPRETED TO MEAN THAT THE MANUFACTURER'S STANDARD PRODUCT WILL MEET THE REQUIREMENTS OF THE PROJECT DESIGN, SPECIFICATIONS, AND SPACE CONSTRAINTS.
    1. WHEREVER A DEFINITE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS SPECIFIED AND THERE IS NOT A STATEMENT THAT ANOTHER MANUFACTURER, PRODUCT, MATERIAL, OR METHOD WILL BE ACCEPTABLE, IT IS THE INTENTION OF THE ARCHITECT THAT THE SPECIFIED MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS THE ONLY ONE THAT SHALL BE USED WITHOUT PRIOR APPROVAL.
    2. WHEREVER A DEFINITE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS SPECIFIED AS "NO SUBSTITUTE", IT IS THE INTENTION OF THE ARCHITECT THAT THE LISTED ITEM IS THE ONLY ONE ACCEPTABLE.
E. COORDINATION: WHERE EQUIPMENT IS USED ON THE PROJECT, IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR OR SUBCONTRACTOR INVOLVED TO VERIFY THAT THE EQUIPMENT WILL FIT IN THE SPACE AVAILABLE, INCLUDING ALL REQUIRED CODE AND MAINTENANCE CLEARANCES, AND TO COORDINATE ALL EQUIPMENT REQUIREMENTS AND PROVISIONS WITH THE SYSTEM DESIGN, ALL AFFECTED DIVISIONS, AND ALL OTHER CONTRACTORS. WHERE THE USE OF ALTERNATE OR SUBSTITUTE MATERIALS AFFECTS THE COST OF PROVISIONS MADE BY OTHER CONTRACTORS, THE CONTRACTOR PROVIDING THE ALTERNATE OR SUBSTITUTE SHALL BE RESPONSIBLE FOR THE OTHER CONTRACTOR'S COST ADJUSTMENT. THERE SHALL BE NO ADDITIONAL COST TO THE OWNER OR ARCHITECT DUE TO THE USE OR ACCEPTANCE OF ANY ALTERNATE OR SUBSTITUTE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD.

1.10 PRIOR APPROVAL

A. SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES: THE CONTRACTOR'S SUBMITTAL AND ARCHITECT'S ACCEPTANCE OF SHOP DRAWINGS, PRODUCT DATA, OR SAMPLES THAT RELATE TO CONSTRUCTION ACTIVITIES NOT COMPLYING WITH THE CONTRACT DOCUMENTS DOES NOT CONSTITUTE AN ACCEPTABLE OR VALID REQUEST FOR SUBSTITUTION, NOR DOES IT CONSTITUTE APPROVAL.

1.11 COORDINATION

A. BY SUBMITTING SHOP DRAWINGS ON THE PROJECT, THIS CONTRACTOR IS INDICATING THAT ALL NECESSARY COORDINATION HAS BEEN COMPLETED AND THAT THE SYSTEMS, PRODUCTS AND EQUIPMENT SUBMITTED CAN BE INSTALLED IN THE BUILDING AND WILL OPERATE AS SPECIFIED AND INTENDED, IN FULL COORDINATION WITH ALL OTHER DISCIPLINES.

1.12 SHOP DRAWINGS AND SUBMITTALS

A. GENERAL: AFTER THE CONTRACT IS AWARDED BUT PRIOR TO PROCEEDING WITH THE WORK REQUIRING SHOP DRAWING REVIEW, THE CONTRACTOR SHALL OBTAIN COMPLETE SHOP DRAWINGS AND PRODUCT DATA FROM THE MANUFACTURERS, SUPPLIERS, VENDORS, AND SUB- CONTRACTORS FOR ALL MATERIALS AND EQUIPMENT SPECIFIED HEREIN, AND MAKE FORMAL SUBMISSION TO THE ARCHITECT. A MINIMUM PERIOD OF TWO (2) WEEKS SHOULD BE ALLOWED IN THE CONSTRUCTION SCHEDULE EXCLUSIVE OF TRAVEL TIME FOR THE ARCHITECTS REVIEW.

B. CERTIFICATION: EACH CONTRACTOR RESPONSIBLE FOR THE WORK SHALL REVIEW AND CERTIFY THE SHOP DRAWING, SUBMITTAL AND/OR PRODUCT DATA TO BE IN FULL COMPLIANCE WITH THE REQUIREMENTS OF THE CONTRACT DOCUMENTS.

C. THE ARCHITECTS REVIEW OF SHOP DRAWINGS AND SUBMITTAL DATA SHALL NOT RELIEVE THE CONTRACTOR OF THE RESPONSIBILITY FOR DIMENSIONS OR ERRORS THAT MAY BE CONTAINED THEREIN, OR FOR DEVIATIONS FROM ANY REQUIREMENTS OF THE CONTRACT DOCUMENTS. IT SHALL BE CLEARLY UNDERSTOOD THAT THE ARCHITECTS NOTING SOME ERRORS BUT OVERLOOKING SOME OTHERS DOES NOT GRANT THE CONTRACTOR PERMISSION TO PROCEED IN ERROR. REGARDLESS OF ANY INFORMATION CONTAINED IN THE SHOP DRAWING OR PRODUCT DATA, THE CONTRACT DOCUMENTS SHALL GOVERN THE WORK AND ARE NEITHER WAIVED NOR SUPERSEDED IN ANY WAY BY THE REVIEW OF SHOP DRAWINGS, PRODUCT DATA AND SAMPLES.

1.13 EXECUTION AND COORDINATION OF WORK

A. MANUFACTURER'S RECOMMENDATIONS: WITH EXCEPTIONS AS SPECIFIED AND/OR INDICATED ON THE DRAWINGS OR IN THE SPECIFICATIONS, APPLY, INSTALL, ERECT, USE, CLEAN, AND CONDITION, MANUFACTURED ARTICLES, MATERIALS, AND EQUIPMENT PER MANUFACTURER'S CURRENT PRINTED RECOMMENDATIONS. KEEP COPIES OF SUCH PRINTED RECOMMENDATIONS AT JOB SITE AND MAKE THEM AVAILABLE AS REQUIRED.

1.14 SUPERVISION

A. A COMPETENT SUPERINTENDENT APPROVED BY THE ARCHITECT, SHALL BE KEPT BY THE CONTRACTOR AT THE BUILDING TO RECEIVE INSTRUCTIONS AND TO ACT FOR THE CONTRACTOR. ONCE THE SUPERINTENDENT HAS BEEN APPROVED, NO CHANGE SHALL BE MADE WITHOUT APPROVAL OF ARCHITECT. REPRESENTATIVES OF THE OWNER, ARCHITECT SHALL HAVE THE RIGHT TO OBSERVE THE WORK AT ANY TIME. THE CONTRACTOR SHALL HAVE A REPRESENTATIVE AVAILABLE WHEN HIS WORK IS BEING OBSERVED AND HE SHALL GIVE ASSISTANCE AS MAY BE REQUIRED TO THE ARCHITECT'S REPRESENTATIVE.

B. THE PROJECT SHALL BE CONSTRUCTED BY EMPLOYEES OF THE CONTRACTOR OR BY WORKERS UNDER HIS SUPERVISION. ANY SUBCONTRACTORS EMPLOYED BY THE CONTRACTOR SHALL BE APPROVED BY THE OWNER'S REPRESENTATIVE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL EQUIPMENT, MATERIAL AND WORK PERFORMED BY ANY SUBCONTRACTOR.

1.15 STORAGE AND PROTECTION OF MATERIALS

A. THE CONTRACTOR SHALL PROPERLY STORE ALL MATERIAL AND EQUIPMENT AT THE JOBSITE AND PROTECT IT FROM THE ELEMENTS AND FROM DAMAGE. ANY EQUIPMENT DAMAGED DUE TO IMPROPER PROTECTION SHALL BE REPLACED BY THE CONTRACTOR AT HIS EXPENSE.

B. THE CONTRACTOR SHALL PROTECT THE WORK, EQUIPMENT, AND MATERIAL OF ALL OTHER TRADES FROM DAMAGE BY HIS WORK OR OTHER WORKMEN, AND SHALL MAKE GOOD ALL DAMAGE THUS CAUSED.

C. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL WORK, MATERIALS, AND EQUIPMENT UNTIL FINALLY INSPECTED, TESTED, AND ACCEPTED. PROTECT WORK AGAINST THEFT, INJURY OR DAMAGE; AND CAREFULLY STORE MATERIAL AND EQUIPMENT RECEIVED ON SITE WHICH ARE NOT IMMEDIATELY INSTALLED. CLOSE OPEN ENDS OF WORK WITH TEMPORARY COVERS OR PLUGS DURING CONSTRUCTION TO PREVENT ENTRY OF OBSTRUCTING MATERIAL. THE CONTRACTOR SHALL COVER AND PROTECT IN AN ACCEPTABLE MANNER TO THE OWNER, EXISTING REMAINING EQUIPMENT AND MATERIALS.

D. IF ANY MATERIAL OR EQUIPMENT IS RECEIVED PRIOR TO THE TIME IT IS REQUIRED, THE CONTRACTOR SHALL BE RESPONSIBLE FOR ITS PROPER STORAGE AND PROTECTION UNTIL SUCH TIME AS IT MAY BE REQUIRED. THE CONTRACTOR SHALL PAY FOR ALL COSTS OF DEMURRAGE OR STORAGE.

1.16 DRAYAGE AND HAULING

A. THE CONTRACTOR SHALL KEEP THE JOBSITE FREE FROM THE ACCUMULATION OF TRASH AND CONSTRUCTION DEBRIS, REGARDLESS OF WHICH SUBCONTRACTOR MAY BE RESPONSIBLE.

1.17 CUTTING AND PATCHING

A. WHERE IT BECOMES NECESSARY TO CUT THROUGH ANY WALL, FLOOR OR CEILING TO PERMIT THE INSTALLATION OF ANY WORK, OR TO REPAIR ANY DEFECTS THAT MAY APPEAR, THE CUTTING SHALL BE PERFORMED UNDER THE SUPERVISION OF THE GENERAL CONTRACTOR. INFORM THE OWNER'S REPRESENTATIVE BEFORE ANY WORK COMMENCES. NO STRUCTURAL MEMBER SHALL BE ALTERED WITHOUT THE WRITTEN PERMISSION OF THE ARCHITECT.

B. VERIFICATION: SHOULD A QUESTION ARISE REGARDING THE ACCEPTABLE LEVEL OF NOISE OR VIBRATION IN A PARTICULAR SPACE OR PIECE OF EQUIPMENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING THE SERVICES OF AN APPROVED ACOUSTICAL CONSULTANT TO DETERMINE ACTUAL NOISE/VIBRATION CONDITIONS.

01 GENERAL NOTES

| | |
|---|---|
| SEQUENCE OF CONSTRUCTION (AS OF 01/27/2025) Schools will be renovated in groups as shown. These groups contain two or three major kitchen renovations and some cafeteria/miscellaneous renovations. This sequencing is critical for FBISD food service to provide the uninterrupted meal services to their schools. | |
| GROUPING 1 | AUSTIN PARKWAY ES + SUGAR MILL ES, kitchen renovations. *Plus: COMMON WEALTH ES, CONERSTONE ES misc. renovations.* |
| GROUPING 2 | SETTLERS WAY ES + PALMER ES kitchen renovations. *Plus: SULLIVAN ES, SIENNA CROSSING ES, HERITAGE ROSE ES misc. renovations* |
| GROUPING 3 | HUNTER'S GLEN ES + HIGHLANDS ES + PECAN GROVE ES kitchen renovations. *Plus: RIDGEGATE ES, DULLES ES misc. renovations.* |

03 PROJECT SCHEDULE

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
DULLES ELEMENTARY SCHOOL
630 DULLES AVENUE
SUGAR LAND, TX 77478

SEAL

REGISTERED ARCHITECT
MICHAEL WILLIAM ANDERSON
22651
STATE OF TEXAS


7/15/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

GENERAL NOTES AND ABBREVIATIONS

A00-01




1 DEMOLITION FLOOR PLAN
SCALE: 1/4" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
DULLES ELEMENTARY SCHOOL
630 DULLES AVENUE
SUGAR LAND, TX 77478

SEAL
REGISTERED ARCHITECT
ROBERT E. WILLIAMS
22651
STATE OF TEXAS
7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING


DEMO PLAN

f-D.101

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\f-Dulles ES\f-D.101 DEMO PLAN.dwg, Jul 23, 2025 - 1:33pm

| PHASING CHART FOR ALL SCHOOLS | | |
|---|---|---|
| PHASE 1 | | |
| **SCHOOLS** | **FREEZER START DATE :** | **FREEZER END DATE :** |
| ***AUSTIN PARKWAY ES*** | 11/7/2025 | 5/13/2026 |
| SUGAR MILL ES | | |
| COMMONWEALTH ES | | |
| CONERSTONE ES | | |
| PHASE 2 | | |
| SETTLERS WAY ES | 5/29/2026 | 10/28/2026 |
| PALMER ES | | |
| SULLIVAN ES | | |
| SIENNA CROSSING ES | | |
| HERITAGE ROSE ES | | |
| **PHASE 3** | | |
| HUNTERS GLEN ES | 3/19/2027 | 3/19/2027 |
| PECAN GROVE ES | | |
| HIGHLANDS ES | | |
| DULLES ES | | |

REFER TO SHEET D-A02-01 FOR CODE ANALYSIS




1 SITE PLAN
SCALE: 1" = 30'-0"

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\f-Dulles ES\f-A 101 SITE PLAN.dwg Jul 23, 2025 - 1:34pm

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT

DULLES ELEMENTARY SCHOOL
630 DULLES AVENUE
SUGAR LAND, TX 77478

SEAL
REGISTERED ARCHITECT
22651
STATE OF TEXAS
7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

SITE PLAN

f-A.101

# 2 CODE ANALYSIS

SCOPE OF WORK: ALL SCOPE FALLS UNDER A LEVEL 2 ALTERATION PER SECTION 603.1 OF THE INTERNATIONAL EXISTING BUILDING CODE AS FOLLOWS:

ADD (1) REACH-IN FREEZER AND (1) REACH-IN REFRIGERATOR AND UTILTIES FOR EACH. THIS PROVIDES STORAGE FOR CEP PROGRAM.

**ADOPTED CODES: CITY OF MISSOURI CITY AND SUGAR LAND, TX**

- 2021 INTERNATIONAL BUILDING CODE
- 2021 INTERNATIONAL RESIDENTIAL CODE
- 2021 INTERNATIONAL PLUMBING CODE
- 2021 INTERNATIONAL MECHANICAL CODE
- 2023 NATIONAL ELECTRIC CODE NFPA 70
- 2021 INTERNATIONAL ENERGY CONSERVATION CODE
- 2021 INTERNATIONAL FUEL GAS CODE
- 2021 INTERNATIONAL FIRE CODE

**INTERIOR WALL AND CEILING FINISH REQUIREMENTS BY OCCUPANCY:**

**SPRINKLERED**

| | |
|---|---|
| INTERIOR EXIT STAIRWAYS AND RAMPS AND EXIT PASSAGEWAYS | **B** |
| CORRIDORS AND ENCLOSURE FOR EXIT ACCESS STAIRWAYS AND RAMPS | **C** |
| ROOMS AND ENCLOSED SPACES | **C** |

**FLOORING SHALL BE CLASS II**

**2021 INTERNATIONAL EXISTING BUILDING CODE**

301.3.1 PRESCRIPTIVE COMPLIANCE METHOD. REPAIRS, ALTERATIONS, ADDITIONS AND CHANGES OF OCCUPANCY COMPLYING WITH CHAPTER FIVE OF THIS CODE IN BUILDINGS COMPLYING WITH THE INTERNATIONAL FIRE CODE SHALL BE CONSIDERED IN COMPLIANCE WITH THE PROVISIONS OF THIS CODE.

302.3 EXISTING MATERIALS. MATERIALS ALREADY IN USE IN A BUILDING IN COMPLIANCE WITH REQUIREMENTS OR APPROVALS IN EFFECT AT THE TIME OF THEIR ERECTION OR INSTALLATION SHALL BE PERMITTED TO REMAIN IN USE UNLESS DETERMINED BY THE BUILDING OFFICIAL TO BE UNSAFE .

302.4 NEW AND REPLACEMENT MATERIALS. EXCEPT AS OTHERWISE REQUIRED OR PERMITTED BY THIS CODE, MATERIALS PERMITTED BY THE APPLICABLE CODE FOR NEW CONSTRUCTION SHALL BE USED. LIKE MATERIALS SHALL BE PERMITTED FOR REPAIRS AND ALTERATIONS, PROVIDED THAT NO UNSAFE CONDITION IS CREATED. HAZARDOUS MATERIALS SHALL NOT BE USED WHERE THE CODE FOR NEW CONSTRUCTION WOULD NOT PERMIT THEIR USE IN BUILDINGS OF SIMILAR OCCUPANCY, PURPOSE AND LOCATION.

**ALTERATION - LEVEL 1** INCLUDE THE REMOVAL AND REPLACEMENT OR THE COVERING OF EXISTING MATERIALS, ELEMENTS, EQUIPMENT, OR FIXTURES USING NEW MATERIALS, ELEMENTS, EQUIPMENT, OR FIXTURES THAT SERVE THE SAME PURPOSE.

**ALTERATION - LEVEL 2** INCLUDE THE ADDITION OR ELIMINATION OF ANY DOOR OR WINDOW, THE RECONFIGURATION OR EXTENSION OF ANY SYSTEM, OR THE INSTALLATION OF ANY ADDITIONAL EQUIPMENT, AND SHALL APPLY WHERE THE WORK IS EQUAL TO OR LESS THAN 50% OF THE BUILDING AREA.

THIS BUILDING'S CONSTRUCTION IS TYPE IIB.


THIS BUILDING'S OCCUPANCY IS E.

THIS BUILDING'S IS SPRINKLERED.

THERE WILL NOT BE ANY MODIFACATIONS TO THE HOOD SYSTEMS IN THE KITCHENS BEYOND REPLACEMENT OF MOTOR FOR LIKE KIND IF NEEDED.

THE BUILDING WILL NOT HAVE ADDITIONAL SQUARE FOOTAGE AS PART OF THE WORK.

NEW CONSTRUCTION ELEMENTS, COMPONENTS, SYSTEMS AND SPACES SHALL COMPLY WITH THE REQUIREMENTS OF THE INTERNATIONAL BUILDING CODES




# 1 OVERALL FLOOR PLAN

SCALE: 1/16" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

f

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT

DULLES ELEMENTARY SCHOOL
630 DULLES AVENUE
SUGAR LAND, TX 77478

SEAL

REGISTERED ARCHITECT
MICHAEL ANDERSON
#22651
STATE OF TEXAS

7/15/2025


MWA ARCHITECTS

ARCHITECTS AND PLANNING CONSULTANTS


11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

OVERALL FLOOR PLAN

f-A.201

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\F-Dulles ES\f-A.201 FLOOR PLAN.dwg Jul 23, 2025 - 1:34pm




1 KITCHEN FLOOR PLAN
SCALE: 1/4" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

f

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
DULLES ELEMENTARY SCHOOL
630 DULLES AVENUE
SUGAR LAND, TX 77478

SEAL
REGISTERED ARCHITECT
ROBERT L. WILLIAMS
22651
STATE OF TEXAS
7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

KITCHEN
FLOOR PLAN

f-A.301

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\f-Dulles ES\f-A.301 KITCHEN FLOOR PLAN.dwg Jul 23, 2025 - 1:34pm

# REFER TO FOODSERVICE DESIGN PROFESSIONALS SPECIFICATIONS AND SUBSEQUENT SHEETS FOR ADDITIONAL COORDINATION INFORMATION

**EXISTING EQUIPMENT NOTES (IF EXISTING EQUIPMENT IS PROVIDED IN THIS PROJECT):**

1. EXISTING EQUIPMENT NOT SCHEDULED FOR RE-USE TO BE RELOCATED BY THE K.E.C. COORDINATE WITH OWNER FOR NEW LOCATION.
2. ALL UTILITIES NOT SCHEDULED FOR RE-USE TO BE CAPPED & COVERED BY REQUIRED DISCIPLINE.
3. K.E.C. TO VERIFY ALL EXISTING UTILITY LOCATIONS & COORDINATE WITH ALL EQUIPMENT AS REQUIRED.

8 EXISTING EQUIPMENT NOTES
NOT TO SCALE

**ARCHITECT TO VERIFY/COORDINATE THE AESTHETIC OPTIONS BELOW (FOOD SERVICE COLOR, MATERIAL, OR SIGNAGE SELECTIONS) IF THESE ITEMS ARE PROVIDED IN THIS PROJECT:**

1. COUNTERTOPS: STONE (STAINLESS STEEL IS PROVIDED UNLESS OTHERWISE SPECIFIED).
2. TRAY SLIDES: CORIAN OR STONE (STAINLESS STEEL IS PROVIDED UNLESS OTHERWISE SPECIFIED).
3. COUNTER FRONTS: CERAMIC TILE, 3 FORM, OR PLASTIC LAMINATE.
4. SNEEZE GUARDS: STONE INSETS.
5. GENERAL COLOR, MATERIAL AND GRAPHIC SELECTIONS:
   - A. DISPLAY AIR SCREEN MERCHANDISERS - COLOR SELECTION: POWDER COAT OR PLASTIC LAMINATE (S/S IS PROVIDED UNLESS OTHERWISE SPECIFIED).
   - B. BAKERY DISPLAY CASES - COLOR SELECTION: POWDER COAT OR PLASTIC LAMINATE (S/S IS PROVIDED UNLESS OTHERWISE SPECIFIED).
   - C. PASS THRU OR REACH IN HOLDING CABINETS - COLOR SELECTION: POWDER COAT (MFG.: TRUE) OR PLASTIC LAMINATE (MFG.: TRAULSEN) (S/S IS PROVIDED UNLESS OTHERWISE SPECIFIED).
   - D. HANGING HEAT LAMPS - TRACK AND FIXTURE COLOR SELECTION.
   - E. HEATED MERCHANDISERS.
   - F. PORTABLE GUIDE RAILS - STANCHION AND BELT COLOR SELECTION.
   - G. POPCORN MACHINE - SIGNAGE SELECTION.
   - H. BOTTLE COOLER - SIGNAGE SELECTION.
   - I. GRAPHICS PACKAGE INFORMATION.
   - J. HOT FOOD WELL COVERS.
6. ARCHITECT TO VERIFY/COORDINATE THE FINISHES BELOW:
   - A. WALLS: CERAMIC TILE, FLAT FRP, OR MOLDED FRP (SMOOTH, IMPERVIOUS, AND EASILY CLEANABLE AS APPROVED BY LOCAL JURISDICTION).
   - B. CEILINGS: REMOVABLE VINYL FACE TILE (SMOOTH, IMPERVIOUS, AND EASILY CLEANABLE AS APPROVED BY LOCAL JURISDICTION).
   - C. FLOORS: TILE, EPOXY, OR RUBBERIZED FLOORING SYSTEM (SMOOTH, IMPERVIOUS, EASILY CLEANABLE AND SLIP RESISTANT AS APPROVED BY LOCAL JURISDICTION) (COORDINATE FLOOR TILE TRANSITION AT SERVING LINES).
   - D. FLOORS: WALK-IN ASSEMBLY - EXTEND KITCHEN FLOOR FLUSH INTO WALK-IN ASSEMBLY WITH COVED BASE.
   - E. FURR DOWNS ABOVE SERVING COUNTERS.

ARCHITECTURAL COORDINATION NOTES
5 NOT TO SCALE

**CRITICAL NOTES:**

1. CONTRACTOR MUST COORDINATE AND VERIFY ALL DIMENSIONS WITH FOOD SERVICE EQUIPMENT SHOP DRAWINGS AND MANUFACTURER'S DATA. DIMENSIONS SHOWN ARE FOR DESIGN AND BIDDING PURPOSES ONLY.
2. WALK-IN ASSEMBLY DOORS MUST BE LEFT OPEN WHILE INTERIOR CONCRETE FLOOR CURES.
3. INSTALL PROTECTIVE COVER ON WALK-IN ASSEMBLY WALL PANELS BEFORE INSTALLING CONCRETE FLOORS AND CURBS.
4. REFER TO GENERAL SPECS - DIVISION 27 TO PROVIDE CONDUIT, DATA, AND INTERCONNECT THE PANIC ALARM INSIDE FREEZER TO THE BUILDING AUTOMATION SYSTEM FOR NOTIFICATION TO DISTRICT PERSONNEL IN THE EVENT OF STAFF ENTRAPMENT.
5. PIPING AND DRAINAGE SYSTEMS (SANITARY AND GREASE-LADEN). SYSTEMS MUST BE CLEANED AND FLUSHED BEFORE THE FINAL CONNECTION WITH FOOD SERVICE EQUIPMENT - CRITICAL (DIV. 22).

7 CRITICAL NOTES
NOT TO SCALE

**DIVISION 26 (ELECTRICAL) IS RESPONSIBLE FOR BUT NOT LIMITED TO:**

1. **DO NOT ROUGH IN FROM FDP DRAWINGS. REFER TO THE KITCHEN EQUIPMENT CONTRACTOR'S DIMENSIONED SHOP DRAWINGS. DIMENSIONS INDICATED ARE TO BE VERIFIED BY KITCHEN EQUIPMENT CONTRACTOR AND ADJUSTED AS REQUIRED BY EQUIPMENT AND FIELD CONDITIONS.**
2. SECTION 11 40 00 TO VERIFY UTILITY REQUIREMENTS OF ANY EXISTING EQUIPMENT.
3. ALL CONNECTIONS SHALL BE MADE FOLLOWING LOCAL CODES AND NATIONAL STANDARDS, EXCEPT WHERE PLANS AND SPECIFICATIONS EXCEED THOSE CODES AND STANDARDS.
4. VERIFY ALL ELECTRICAL REQUIREMENTS WITH ENGINEERING DRAWINGS.
5. ROUGH-IN AND FINAL CONNECTION OF ELECTRICAL SYSTEMS TO FOOD SERVICE EQUIPMENT, WALK-IN ASSEMBLIES, AND BETWEEN COMPONENTS (INCLUDING MATERIALS AND LABOR). ACCESSORIES PROVIDED LOOSE WITH FOOD SERVICE EQUIPMENT BY SECTION 11 40 00 TO BE FIELD INSTALLED BY DIVISION 26.
6. EMPTY EMT CONDUIT WITH PULL-WIRE AND WIDE-SWEEP BENDS FOR REFRIGERANT PIPING TO REMOTE FOOD SERVICE EQUIPMENT REFRIGERATION SYSTEMS.
7. EMPTY EMT CONDUIT WITH PULL-WIRE AND WIDE-SWEEP BENDS FOR INTERCONNECT CABLES BETWEEN LAN AND POS TERMINALS, CHANGE-MAKERS, PRE-CHECK UNITS, PRINTERS, CPUS, ETC. DIVISION 26 TO VERIFY WHERE THE CONDUIT IS TO RUN FOR POS SYSTEM (I.E., MANAGER'S OFFICE OR IDF ROOM).
8. EMPTY EMT CONDUIT WITH PULL-WIRE AND WIDE-SWEEP BENDS FOR FIRE SUPPRESSION SYSTEMS. INTERCONNECT FIRE PROTECTION SYSTEM TO PANEL BOX SHUNT TRIPS AND BUILDING ALARM.
9. WALK-IN LIGHT FIXTURE INSTALLATION (PROVIDED LOOSE BY SECTION 11 40 00) (IF WALK-IN IS PROVIDED IN THIS PROJECT).
10. TABLE LIMIT SWITCH INSTALLATION (PROVIDED LOOSE BY SECTION 11 40 00) (IF DISHMACHINE IS PROVIDED IN THIS PROJECT).
11. ELECTRICAL MATERIALS AND DEVICES (SHUNT-TRIP BREAKERS, SURGE PROTECTORS, LIGHTING CONTROL DEVICES, CONDUIT, WIRE, ETC.).
12. SWITCHES AND STAINLESS STEEL DISCONNECTS AS REQUIRED (PROVIDE, LOCATE, AND INSTALL – TO BE IN AN ACCESSIBLE LOCATION).
13. CHARGING STATIONS FOR FORKLIFTS, PALLET STACKERS, AND PALLET JACKS (SIZE, PROVIDE, LOCATE, AND INSTALL) (IF EQUIPMENT IS PROVIDED IN THIS PROJECT).
14. INTERCONNECTION BETWEEN CONDENSATE FAN AND DISHMACHINE CONTROL PANEL (IF EQUIPMENT IS PROVIDED IN THIS PROJECT).
15. INTERCONNECTION BETWEEN EXHAUST HOOD FANS AND SWITCH (IF EQUIPMENT IS PROVIDED IN THIS PROJECT).
16. INTERCONNECTION BETWEEN EXHAUST HOOD LIGHTS AND SWITCH (IF EQUIPMENT IS PROVIDED IN THIS PROJECT).
17. DOOR HEATERS, LIGHTS, COILS, AND PRESSURE RELIEF PORTS PRE-WIRED TO JUNCTION BOX AT TOP OF WALK-IN ASSEMBLIES (IF EQUIPMENT IS PROVIDED IN THIS PROJECT) PROVIDED BY SECTION 11 40 00. FINAL CONNECTION BY DIV. 26.
18. IF ANY ELECTRICAL ACCESSORIES, FITTINGS, AND CORD/PLUGS ARE PROVIDED LOOSE WITH EQUIPMENT BY 11 40 00, DIV.26 IS TO ATTACH TO EQUIPMENT AND PROVIDE FINAL CONNECTION.
19. PROVIDE WATERPROOF RECEPTACLES IN WET AREAS.
20. ALL ELECTRICAL CONNECTIONS BENEATH EXHAUST HOODS (IF EQUIPMENT IS PROVIDED IN THIS PROJECT) TO EXTEND TO SHUNT TRIP BREAKERS WITH ELECTRICAL PANEL BOX FOR SHUTDOWN DURING FIRE MODE.
21. RECEPTACLES ARE TO BE PRE-WIRED TO THE JUNCTION BOX OR LOAD CENTER FOR FINAL CONNECTION BY DIVISION 26.
22. ALL ELECTRICAL LIGHTING, POWER, AND DISTRIBUTION SYSTEMS.
23. DO NOT INTERCONNECT MORE THAN THREE (3) CONVENIENCE OUTLETS ON ONE (1) BREAKER.
24. OTHER THAN CONVENIENCE OUTLETS, ALL ELECTRICAL CONNECTIONS SHOWN ON FOOD SERVICE PLANS ARE DEDICATED BREAKERS.
25. DOORBELL AT RECEIVING DOOR (PROVIDE AND INSTALL – TO BE AUDIBLE THROUGHOUT KITCHEN, OFFICE, AND DRY STORAGE ROOM).
26. ADEQUATE LIGHTING AT RECEIVING DOOR.
27. PROVIDE AND INSTALL TWO EMERGENCY STROBE BEACONS THAT INTERCONNECT TO PANIC ALARM IN WALK-IN FREEZER. ONE (1) IN KITCHEN ABOVE WALK-IN FREEZER DOOR ONE (1) IN CAFETORIUM (IF WALK-IN IS PROVIDED IN THIS PROJECT). REFER TO GENERAL SPECIFICATIONS FOR ADDITIONAL DETAILS.
28. DEDICATED CIRCUIT FOR HEATED DRAIN LINE CONNECTION IN WALK-IN FREEZER AT EACH COIL (IF WALK-IN IS PROVIDED IN THIS PROJECT).

**NOTE: ELECTRICAL CONNECTIONS INDICATED ARE THOSE REQUIRED FOR THE FOOD SERVICE EQUIPMENT AND THOSE REQUIRED FOR SUPPORT EQUIPMENT FURNISHED BY DIVISION 26. FOR ADDITIONAL REQUIREMENTS, REFER TO THE ELECTRICAL ENGINEER'S DRAWINGS.**

6 ELECTRICAL COORDINATION NOTES1
NOT TO SCALE

**DIVISION 22 (PLUMBING) RESPONSIBLE FOR BUT NOT LIMITED TO:**

1. **DO NOT ROUGH-IN FROM FDP DRAWINGS. REFER TO THE KITCHEN EQUIPMENT CONTRACTOR'S DIMENSIONED SHOP DRAWINGS. DIMENSIONS INDICATED ARE TO BE VERIFIED BY KITCHEN EQUIPMENT CONTRACTOR AND ADJUSTED AS REQUIRED BY EQUIPMENT AND/OR FIELD CONDITIONS.**
2. SECTION 11 40 00 TO VERIFY UTILITY REQUIREMENTS OF ANY EXISTING EQUIPMENT.
3. ALL CONNECTIONS SHALL BE MADE IN ACCORDANCE WITH LOCAL CODES AND NATIONAL STANDARDS, EXCEPT WHERE PLANS AND SPECIFICATIONS EXCEED THOSE CODES AND STANDARDS.
4. VERIFY ALL PLUMBING REQUIREMENTS WITH ENGINEERING DRAWINGS.
5. EMPTY PVC CONDUIT WITH WIDE-SWEEP BENDS FOR REFRIGERANT PIPING TO BEVERAGE LINES, CO2 LINES, AND REMOTE FOOD SERVICE EQUIPMENT REFRIGERATION SYSTEMS.
6. ROUGH-IN AND FINAL PLUMBING CONNECTIONS TO FOOD SERVICE EQUIPMENT AND BETWEEN COMPONENTS (INCLUDING MATERIALS AND LABOR). ACCESSORIES PROVIDED LOOSE WITH FOOD SERVICE EQUIPMENT BY SECTION 11 40 00 TO BE FIELD INSTALLED BY DIVISION 22. THIS INCLUDES BUT IS NOT LIMITED TO INSTALLATION OF ALL FAUCETS (WATER FILL FAUCETS, PRE-RINSE FAUCETS, ETC.), HOSES, GAS DISCONNECTS, AND DRAINS FROM EQUIPMENT POINT OF CONNECTION TO BUILDING PLUMBING SYSTEMS. ALL DRAIN LINES ARE PROVIDED AND INSTALLED BY DIV. 22.
7. KITCHEN EQUIPMENT CONTRACTOR IS RESPONSIBLE FOR PROVIDING ALL FAUCETS (WATER FILL FAUCETS, PRE-RINSE FAUCETS, ETC.), DRAIN FITTINGS, MIXING VALVES, CONTROL VALVES, WATER PRESSURE REGULATORS, VACUUM BREAKERS, AND ALL ACCESSORIES FOR EQUIPMENT SPECIFIED UNDER 11 40 00. DIVISION 22 IS RESPONSIBLE FOR INSTALLATION.
8. INDIRECT DRAIN LINE RUNS FROM EQUIPMENT TO NEAREST DRAIN OR FLOOR SINK. LINES TO BE TYPE 'K' COPPER.
9. IF ANY PLUMBING ACCESSORIES OR FITTINGS ARE PROVIDED LOOSE WITH EQUIPMENT BY 11 40 00, DIV. 22 IS TO ATTACH TO EQUIPMENT AND PROVIDE FINAL CONNECTION.
10. GAS SUPPLY SYSTEMS WITH ALL COMPONENTS AND FITTINGS AS REQUIRED FOR A COMPLETE SYSTEM.
11. WATER SUPPLY SYSTEMS WITH ALL COMPONENTS AND FITTINGS AS REQUIRED FOR A COMPLETE SYSTEM.
12. COMPRESSED AIR SYSTEMS WITH ALL COMPONENTS AND FITTINGS AS REQUIRED FOR A COMPLETE SYSTEM (IF REQUIRED FOR THIS PROJECT).
13. PIPING AND DRAINAGE SYSTEMS (SANITARY AND GREASE-LADEN). SYSTEMS MUST BE CLEANED AND FLUSHED BEFORE THE FINAL CONNECTION WITH FOOD SERVICE EQUIPMENT - CRITICAL.
14. FLOOR SINKS (PROVIDE AND INSTALL). FLANGE AND GRATES TO BE FLUSH WITH FINISHED FLOOR.
15. FLOOR DRAINS (PROVIDE AND INSTALL). FLANGE AND GRATES TO BE FLUSH WITH FINISHED FLOOR.
16. TRENCH DRAINS (PROVIDE AND INSTALL). TRENCH LINERS PROVIDED BY 11 40 00. FLANGE AND LINERS TO BE FLUSH WITH FINISHED FLOOR.
17. GREASE TRAPS AS REQUIRED. VERIFY WITH LOCAL CODES TO BYPASS OR PIPE THRU GREASE TRAP AND/OR INTERCEPTOR.
18. P-TRAPS AS REQUIRED (INCLUDING ALL DISPOSERS).
19. INTERCONNECT WATER THRU WATER FILTER (FILTER PROVIDED BY 11 40 00 UNLESS OTHERWISE SPECIFIED) TO EQUIPMENT.
20. GAS QUICK DISCONNECT INSTALLATION (QUICK DISCONNECT PROVIDED BY 11 40 00).
21. SAFETY RESTRAINT CABLE INSTALLATION (SAFETY RESTRAINT CABLE PROVIDED BY 11 40 00).
22. SPECIFIED COUPLINGS AND PIPING TO ALL EQUIPMENT FURNISHED BY 11 40 00.
23. AIR COMPRESSORS (IF REQUIRED FOR THIS PROJECT) (SIZE, PROVIDE, AND INSTALL, UNLESS OTHERWISE SPECIFIED).
24. WATER SOFTENERS (IF REQUIRED FOR THIS PROJECT) (SIZE, PROVIDE, AND INSTALL, UNLESS OTHERWISE SPECIFIED).
25. PRESSURE BOILERS (IF REQUIRED FOR THIS PROJECT) (SIZE, PROVIDE, AND INSTALL, UNLESS OTHERWISE SPECIFIED).
26. HAND SINKS (PROVIDE (UNLESS OTHERWISE SPECIFIED) AND INSTALL). PROVIDE HOT WATER TEMPERING VALVE IF REQUIRED. WATER TEMPERATURE TO BE AT LEAST 100 DEGREES AND FLOW FOR AT LEAST 20 SECONDS.
27. ICE BIN DRAIN INSULATION (IF ICE MACHINE IS PROVIDED IN THIS PROJECT) (PROVIDE AND INSTALL).
28. UNIONS AT DISPOSER SOLENOID VALVES (IF DISPOSER IS PROVIDED IN THIS PROJECT) (PROVIDE AND INSTALL).
29. BACK FLOW PREVENTION AS REQUIRED (PROVIDE AND INSTALL - INCLUDING ALL DISPOSERS). BACK- SIPHONAGE SHALL BE INSTALLED AT ALL FIXTURES AND EQUIPMENT WHERE BACKFLOW AND/OR BACK-SIPHONAGE MAY OCCUR AND WHERE A MINIMUM AIR GAP CANNOT BE PROVIDED BETWEEN THE WATER TO THE FIXTURE OR EQUIPMENT AT ITS FLOOD/LEVEL RIM. VACUUM BREAKERS, WHEN FURNISHED WITH EQUIPMENT, SHALL OVERRIDE THE ABOVE, IF ACCEPTABLE WITH APPLICABLE CODES. DIVISION 22 RESPONSIBLE FOR VERIFYING REQUIREMENT WITH LOCAL CODES.
30. JANITOR SINK WITH FAUCET (PROVIDE AND INSTALL).
31. FREEZE PROOF HYDRANT AT EXTERIOR OF BUILDING BY RECEIVING DOOR (PROVIDE AND INSTALL).
32. REVERSE OSMOSIS SYSTEMS (SIZE, PROVIDE (UNLESS OTHERWISE SPECIFIED), LOCATE AND INSTALL).
33. ALL PIPING WITHIN COUNTER BODY OR UNDER FABRICATED COUNTERS TO BE RUN TO A CONNECTION POINT BELOW COUNTER BODY BY SECTION 11 40 00. FINAL CONNECTION BY DIVISION 22.
34. EXHAUST HOOD CONDENSATE DRAIN CONNECTIONS (IF EXHAUST HOOD IS PROVIDED IN THIS PROJECT) (PROVIDE AND INSTALL).
35. INTERCONNECTION OF 1/2" CW TO PRE-RINSE AND DISPOSERS CONE/BODY INLETS PIPED THROUGH SOLENOID AND VACUUM BREAKER (IF DISPOSER IS PROVIDED IN THIS PROJECT).
36. FIRE SYSTEM PIPING. EXPOSED PIPING TO BE CHROME PLATED.
37. PIPE 1/2" COLD WATER TO SWIRL INLETS AT DISPOSERS (IF DISPOSER IS PROVIDED IN THIS PROJECT).
38. WATER TREATMENT FOR ICE BUILDERS (NON-CHLORINATED WATER WITH A PH LEVEL OF 10 OR HIGHER) AND ANY DRAINS AND OVERFLOWS. PIPING FROM ICE BUILDERS TO TUMBLE CHILLERS BY DIV. 23 (IF ICE BUILDERS AND TUMBLE CHILLERS ARE PROVIDED IN THIS PROJECT).

**NOTE: WATER AND DRAIN CONNECTIONS INDICATED ARE THOSE REQUIRED FOR THE FOOD SERVICE EQUIPMENT AND THOSE REQUIRED FOR SUPPORT EQUIPMENT FURNISHED BY DIVISION 22. FOR ADDITIONAL WATER AND DRAIN REQUIREMENTS REFER TO MECHANICAL DRAWINGS.**

**NOTE: REFER TO ELECTRICAL/MECHANICAL DRAWINGS FOR REQUIREMENTS OF EXHAUST FANS AND MAKE-UP AIR HANDLERS AND LOCATION OF AN INTERLOCK AND START/STOP CONTROLS TO BE LOCATED WITHIN FOOD SERVICE AREA BY DIVISION 26.**

4 PLUMBING COORDINATION NOTES1
NOT TO SCALE

**DIVISION 23 (MECHANICAL) RESPONSIBLE FOR BUT NOT LIMITED TO:**

1. **DO NOT ROUGH-IN FROM FDP DRAWINGS. REFER TO THE KITCHEN EQUIPMENT CONTRACTOR'S DIMENSIONED SHOP DRAWINGS. DIMENSIONS INDICATED ARE TO BE VERIFIED BY KITCHEN EQUIPMENT CONTRACTOR AND ADJUSTED AS REQUIRED BY EQUIPMENT AND/OR FIELD CONDITIONS.**
2. SECTION 11 40 00 TO VERIFY UTILITY REQUIREMENTS OF ANY EXISTING EQUIPMENT.
3. ALL CONNECTIONS SHALL BE MADE FOLLOWING LOCAL CODES AND NATIONAL STANDARDS, EXCEPT WHERE PLANS AND SPECIFICATIONS EXCEED THOSE CODES AND STANDARDS.
4. VERIFY ALL MECHANICAL REQUIREMENTS WITH ENGINEERING DRAWINGS.
5. EMPTY EMT CONDUIT WITH PULL-WIRE AND WIDE-SWEEP BENDS FOR REFRIGERANT PIPING TO REMOTE FOOD SERVICE EQUIPMENT REFRIGERATION SYSTEMS.
6. ROUGH-IN AND FINAL CONNECTION OF MECHANICAL SYSTEMS TO FOOD SERVICE EQUIPMENT, WALK-IN ASSEMBLIES, AND BETWEEN COMPONENTS (INCLUDING MATERIALS AND LABOR).
7. TESTING AND BALANCING FOR ROOMS AND EXHAUST HOODS TO BE PERFORMED BY MECHANICAL CONTRACTOR. BALANCE REPORT FOR FOOD SERVICE EXHAUST HOODS TO BE PROVIDED TO FOODSERVICE DESIGN PROFESSIONALS (FDP) IMMEDIATELY UPON COMPLETION (SEND TO HOUSTON.SUBMITTAL@FDP.ORG FOR HOUSTON OFFICE AND DALLAS.SUBMITTAL@FDP.ORG FOR DALLAS OFFICE) AND MUST BE SUBMITTED WITH O&M MANUALS.
8. EXHAUST HOODS, CONDENSATE HOODS, FIRE SUPPRESSION SYSTEMS, CONNECTIONS AND CONTROLS (PROVIDE AND INSTALL – *UNLESS OTHERWISE SPECIFIED*). PROVIDE TEMPERED AIR AT ALL SUPPLY DUCTS.
   - A. IF EXHAUST/CONDENSATE HOODS AND FIRE SUPPRESSION SYSTEMS ARE SPECIFIED UNDER SECTION 11 40 00, DIVISION 23 IS RESPONSIBLE FOR ALL EXHAUST AND CONDENSATE HOOD CONNECTIONS (PROVIDE AND INSTALL).
9. VFD SYSTEM AND CONTROLLERS, WHEN REQUIRED BY CODE (PROVIDE AND INSTALL).
10. PROVIDE AND INSTALL ALL VENTILATION (DIRECT OR INDIRECT), AIR CONDITIONING AND HEATING SYSTEMS (UNLESS OTHERWISE SPECIFIED).
11. COORDINATE SUPPLY AND RETURN DUCTS ABOVE SERVING COUNTERS OR OPEN-AIR REFRIGERATED MERCHANDISERS. NO COLD AIR TO BLOW DIRECTLY ON HOT FOOD COUNTERS.
12. COORDINATE SUPPLY AND RETURN DUCTS AWAY FROM EQUIPMENT WITH TOP MOUNTED REFRIGERATION. NO COLD AIR TO BLOW DIRECTLY ON COMPRESSORS.
13. MECHANICAL CONTRACTOR TO LOCATE TEMPERATURE MONITORS WITHIN RETURN DUCTS.
14. CIRCULATING AIR ABOVE WALK-IN ASSEMBLIES (PROVIDE AND INSTALL).
15. CIRCULATING AIR ABOVE AND IN AIR GAPS AT WAREHOUSE COLD STORAGE ASSEMBLIES (PROVIDE AND INSTALL).
16. WATER CHILLERS AS REQUIRED (IF EQUIPMENT IS PROVIDED IN THIS PROJECT) (PROVIDE, SIZE AND LOCATE).
17. PIPING FROM ICE BUILDERS TO TUMBLE CHILLERS (IF EQUIPMENT IS PROVIDED IN THIS PROJECT) (PROVIDE, SIZE AND LOCATE).

3 MECHANICAL COORDINATION NOTES
NOT TO SCALE

**GENERAL CONTRACTOR RESPONSIBLE FOR BUT NOT LIMITED TO:**

1. ANY WALL PENETRATION REQUIRED FOR FOOD SERVICE EQUIPMENT UTILITIES. ESCUTCHEON PLATES OR S/S SLEEVES TO BE PROVIDED AND INSTALLED AS NEEDED.
2. BULK FREEZER VENTILATION PIPE (IF BULK FREEZER IS PROVIDED IN THIS PROJECT) (PROVIDE AND INSTALL, UNLESS OTHERWISE SPECIFIED).
3. CORE DRILLING FOR GUIDE RAILS (IF GUIDE RAILS ARE PROVIDED IN THIS PROJECT).
4. REFRIGERATION ROOF CURBS / ROOF JACK (IF REFRIGERATION SYSTEM IS PROVIDED IN THIS PROJECT AND LOCATED ON ROOF).
5. INTERIOR BOLLARDS (IF REQUIRED FOR THIS PROJECT) – TO BE EPOXY PAINTED PER LOCAL CODES (PROVIDE AND INSTALL).
6. FURNISH AND INSTALL 3/4" PLYWOOD BLOCKING IN THE WALL FOR MOUNTING EQUIPMENT FURNISHED BY SECTION 11 40 00 AS REQUIRED.
7. WALK-IN DEPRESSIONS (TO BE DEAD LEVEL) AND SAND LEVELING BED (IF WALK-IN IS PROVIDED IN THIS PROJECT AND RECESS IS SHOWN).
8. STRUCTURAL BRACING FOR BULK WALK-IN CEILING PANELS IF REQUIRED.
9. MENU SYSTEM VIDEO MONITORS IN SERVERY (UNLESS OTHERWISE SPECIFIED).
10. STRUCTURAL BRACING FOR MENU SYSTEM VIDEO MONITORS IF REQUIRED.
11. INTERIOR/EXTERIOR REFRIGERATION PENETRATIONS AND SLEEVES AT BUILDING PENETRATIONS.
12. DOORSCOPE VIEWER (PEEPHOLE) WITH WIDE VIEWING ANGLE AT RECEIVING DOOR.
13. CANOPY AT RECEIVING DOOR. COORDINATE HEIGHT WITH THE HEIGHT OF RECEIVING DOOR (8') AND THE MOUNTING HEIGHT OF AIR SCREEN ABOVE THE DOOR.
14. SOAP AND TOWEL DISPENSER PROVIDED BY OWNER. G.C. RESPONSIBLE FOR INSTALLATION.
15. WASHER AND DRYER (PROVIDE AND INSTALL, UNLESS OTHERWISE SPECIFIED).
16. DWARF WALL AT EXPOSED FRONT/ENDS OF CAFETERIA SERVING COUNTERS WITH FINISH AS SELECTED BY ARCHITECT (IF REQUIRED IN THIS PROJECT).

GENERAL CONTRACTOR COORDINATION NOTES
2 NOT TO SCALE

**HEALTH DEPARTMENT REQUIREMENTS (VERIFY WITH LOCAL JURISDICTIONS):**

1. FLOORS: VERIFY WITH DIVISION 9. FLOORS TO BE SMOOTH, IMPERVIOUS, EASILY CLEANABLE AND SLIP RESISTANT.
2. WALLS: VERIFY WITH ARCHITECTURAL DOCUMENTS. WALLS TO BE SMOOTH, IMPERVIOUS, AND EASILY CLEANABLE.
3. CEILING: LAY-IN TILES. CEILING TILES TO BE SMOOTH, IMPERVIOUS, AND EASILY CLEANABLE.
4. EMPLOYEE TOILET: TO BE LOCATED OFF MAIN CORRIDOR AND ADJACENT TO MAIN KITCHEN. RESTROOM MUST HAVE A VESTIBULE AND NOT OPEN TO KITCHEN / PREP AREAS. TOILETS TO BE WELL VENTILATED.
5. LAVATORIES: WALL HUNG LAVATORIES LOCATED WITHIN ALL FUNCTIONAL WORKING AREAS.
6. UTENSIL CLEANING/SANITIZING: ACCOMPLISHED IN UTENSIL WASH AREA WITH (3) 2'-0" x 2'-2" x 15" MINIMUM DEEP SINKS AND WAREWASH MACHINE.
7. MECHANICAL CLEANING/SANITIZING OF TABLEWARE: ACCOMPLISHED BY WAREWASH MACHINE.
8. STOREROOMS: AMPLE DAILY STORAGE PROVIDED IN ENCLOSED STORE ROOMS. STORE ROOMS TO BE VENTILATED AND MAINTAIN PROPER TEMPERATURE.
9. WATER HEATER: LOCATED IN THE MECHANICAL ROOM ADJACENT TO KITCHEN. TO BE SIZED TO PROVIDE AMPLE WATER TO MAINTAIN PROPER WATER TEMPERATURE THROUGHOUT HOURS OF OPERATION.
10. GREASE TRAP: LOCATED AT EXTERIOR OF BUILDING. REFER TO ENGINEER'S DRAWINGS.
11. FOOD SERVICE EQUIPMENT: ALL FLOOR-MOUNTED EQUIPMENT IS TO BE SEALED TO THE FLOOR TO PROVIDE AN EASILY CLEANABLE SURFACE AND PREVENT SEEPAGE. EQUIPMENT NOT MOUNTED TO THE FLOOR IS TO BE WALL MOUNTED ON WALL CARRIERS, OR ELEVATED ON LEGS TO PROVIDE AT LEAST A SIX-INCH CLEARANCE BETWEEN FLOOR AND EQUIPMENT.
12. MOP SINK: LOCATED IN JANITOR CLOSET OFF MAIN KITCHEN CORRIDOR, AND LOCATED IN CLOSE PROXIMITY TO THE SERVERY WAREWASH AREA.
13. EXHAUST HOODS: EXHAUST HOODS PROVIDED OVER COOKING EQUIPMENT WITH LIQUID CHEMICAL ANSUL FIRE EXTINGUISHING SYSTEM.
14. LIGHTING AND PROTECTIVE SHIELDING: RECESSED CEILING-MOUNTED FLUORESCENT LIGHT FIXTURES FITTED WITH CLEAR LEXAN DIFFUSERS.
15. GARBAGE AND REFUSE: CENTRAL TRASH COLLECTION PROVIDED FOR BUILDING LOCATED NEAR RECEIVING AREA ON SMOOTH CONCRETE SURFACE.
16. POISONOUS AND TOXIC MATERIAL STORAGE: LOCATED IN RESPECTIVE JANITOR CLOSETS WITH LOCKING HARDWARE.

HEALTH DEPARTMENT COORDINATION NOTES
1 NOT TO SCALE

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
DULLES ELEMENTARY SCHOOL
630 DULLES AVE. SUGAR LAND, TX 77478


SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL FCSI 48854119 PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
ELECTRONICALLY APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 48854119 ON: 07/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

FS GENERAL COORDINATION NOTES

F-QF0.0





1 FOODSERVICE EXISTING EQUIPMENT PLAN
1/4" = 1'-0"




2 FOODSERVICE EQUIPMENT PLAN
1/4" = 1'-0"

| FOODSERVICE EQUIPMENT SCHEDULE | | | |
|---|---|---|---|
| FDP ITEM | QTY | FDP DESCRIPTION | FDP REMARKS |
| 193 | 1 | REACH-IN REFRIGERATOR-2DR | |
| 195 | 1 | REACH-IN FREEZER - 2DR | |




4 FOODSERVICE ELECTRICAL CONNECTION PLAN
1/4" = 1'-0"

| FOODSERVICE ELECTRICAL SCHEDULE | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| FDP ENO | FDP ECONN | FDP ELOAD | FDP EVOLT | FDP EPH | FDP ESERVICE TO | FDP ELOC | FDP EAFF | FDP EREMARKS |
| | | | | | | | | |
| E193 | JB | 8.2A | 120 | 1 | REFRIGERATOR | WALL | 96" | BTC; OMIT PLUG, UNIT TO BE HARDWIRED |
| E195 | JB | 14.9A | 120 | 1 | FREEZER | WALL | 96" | BTC; OMIT PLUG, UNIT TO BE HARDWIRED |

| | | | | | |
|---|---|---|---|---|---|
| | SCR | CONDUIT STUB BTC ON RECEPT FURNISH WITH EQUIPMENT | CC | CC | CONDUIT FOR COMPUTER CABLES |
| | CS | CONDUIT STUB UP/OUT FOR DIRECT CONNECTION | | BTC | BRANCH TO CONNECTION ON EQUIPMENT |
| | DR | 20 AMP DUPLEX RECEPTACLE (MOUNT HORIZONTAL) | | WPR | 20 AMP WEATHERPROOF RECEPTACLE (SPRING COVER) |
| | SR | SINGLE PURPOSE RECEPTACLE | | FPB | FIRE PROTECTION BUZZER |
| | SR | SINGLE PURPOSE RECPT. 208V 1PH | | BSC | BEVERAGE SYSTEM CONDUIT |
| | FR | FLUSH FLOOR RECEPTACLE | | DFA | DROP FROM ABOVE |
| | PMR | PEDESTAL MOUNTED RECPTACLE | | AFF | ABOVE FINISH FLOOR |
| | DCR | DROP CORD RECEPTACLE | | CS/JB | JUNCTION BOX ON PEDSTAL |
| | JB | JUNCTION BOX ON CEILING | | DS | DISCONNECT SWITCH |
| | JB | JUNCTION BOX IN WALL | | | |
| | JB/DS | JUNCTION BOX WITH DISCONNECT BY DIV.26 | | JB/DS | CONDUIT STUB-UP WITH DISCONNECTI BY DIV.26 |

3 ELECTRICAL SYMBOLS
NONE

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
DULLES ELEMENTARY SCHOOL
630 DULLES AVE. SUGAR LAND, TX 77478

SEAL


FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
7/18/2025
THIS DOCUMENT APPEARING ON THIS SHEET WAS AUTHORIZED BY MELISSA MOORE, FCSI NO: 48854119 ON: 07/18/2025

MWA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING


FS EQUIPMENT / ELECTRICAL PLAN

F-QF1.0




## 2 OVERALL FLOOR PLAN

SCALE: 1" = 50'- 0"




## 3 PARTIAL ELECTRICAL RISER - DULLES ELEMENTARY

NO SCALE

NOTES:

1. FIELD VERIFY ALL EXISTING ELECTRICAL PANELS AND FEEDERS SHOWN ON DRAWINGS.
2. REF ELECTRICAL FLOOR PLANS FOR PANEL LOCATIONS.
3. ALL OUTAGES SHALL BE SCHEDULED/CONFIRMED IN WRITING WITH THE OWNER A MINIMUM OF TWO WEEKS PRIOR TO ANY OUTAGE.
4. AT THE END OF THE PROJECT PROVIDE A NEW TYPEWRITTEN PANEL SCHEDULE USING BUILDING ROOM NUMBERS FOR ALL PANELS WITH CIRCUITS ADDED, REMOVED, OR MODIFIED AS PART OF THE PROJECT.
5. REFERENCE PANEL SCHEDULES AND SHORT CIRCUIT TABLE FOR AIC AND SCCR VALUES.

## SYMBOL LEGEND


| | |
|---|---|
| ①/②/④: | SIMPLEX/DUPLEX/QUAD – 5361/2 REC |
| GFI | DUPLEX W/ GFCI PROTECTION–P&S 2097 |
| J | J–BOX |
| | CEILING MOUNTED J–BOX |
| M | MOTOR |
| | HEAVY DUTY, NON–FUSED DISCONNECT. MIN RATING OF CIRCUIT OCPD/VOLTAGE. |
| | ELECTRICAL PANEL |
| | HOMERUN TO CIRCUIT NOTED |
| E | EXISTING DEVICES TO REMAIN |
| R | EXISTING DEVICES TO BE RELOCATED |
| D | EXISTING DEVICES TO BE DEMO/REMOVED |
| RCP | EXISTING DEVICES TO BE REPLACED |
| S | INDICATES SURFACE MOUNTED |
| SR | INDICATES SURFACE RACEWAY |
| + | INDICATES ABOVE COUNTER DEVICE |
| + | INDICATES DEVICE AT +30–60" |
| ++ | INDICATES DEVICE AT +80–96" |
| CLG | INDICATES DEVICES MOUNTED IN CEILING |
| WP | INDICATES WEATHERPROOF COVER |
| 3R | INDICATES 3R RATED DEVICE |
| (C)LA–X | CONNECT(ED) TO EXIST CIRCUIT LA–X |
| (D)LA–X | DEMO PORTION OF EXIST CIRCUIT LA–X |
| (N)LA–X | CONNECT(ED) TO NEW CIRCUIT LA–X |

GENERAL ELECTRICAL NOTES:

1. INSTALL SYSTEM IN ACCORDANCE WITH THE NATIONAL ELECTRC CODE AS ADOPTED BY THE LOCAL AUTHORITY HAVING JURISDICTION INCLUDING ALL AMENDMENTS.
2. PROVIDE CONDUIT FOR ALL DEVICES INSTALLED IN WALLS.
   - 2.A. 3/4"C FOR POWER AND 1"C FOR LOW VOLTAGE/DATA UNLESS NOTED OTHERWISE.
   - 2.B. PROVIDE PROTECTIVE BUSHING ON END OF ALL LOW VOLTAGE CONDUITS.
   - 2.C. ALL ELECTRICAL HOMERUNS SHALL BE IN CONDUIT, MIN 3/4"C.
   - 2.D. USE INSULATED THROAT FITTINGS FOR CONNECTIONS TO HOUSINGS, BOXES, ENCLOSURES, ETC.
   - 2.E. MAX LENGTH FOR FLEX CONDUIT SHALL BE 6FT AND MIN. SIZE SHALL BE 1/2". ALL FLEX CONDUIT SHALL BE LISTED FOR GROUNDING.
3. CONDUIT TYPES:
   - 3.A. INSIDE BUILDINGS: GALVANIZED STEEL EMT.
     - 3.A.A. ALL LOW VOLTAGE CABLING SHALL BE INSTALLED IN CONDUIT IN EXPOSED CEILING AREAS. ROUTE TO NEAREST ACCESSIBLE CEILING WITH CONTINUOUS PATHWAYS TO LOW VOLTAGE SOURCE/DEVICE.
     - 3.A.B. ALL LOW VOLTAGE CABLING SHALL BE INSTALLED IN CONDUIT ABOVE INACCESSIBLE CEILINGS. ROUTE TO NEAREST ACCESSIBLE CEILING WITH CONTINUOUS PATHWAYS TO LOW VOLTAGE SOURCE/DEVICE.
   - 3.B. NO MC CABLE SHALL BE ALLOWED.
   - 3.C. PROVIDE FLEXIBLE CONNECTIONS TO MOTORS, PUMPS, TRANSFORMERS, OR SIMILAR EQUIPMENT.
4. PROVIDE GALVANIZED STEEL, ONE–PIECE CONSTRUCTION, OUTLET BOXES IN ALL CASES SUITABLE FOR INTENDED USE.
   - 4.A. BOXES OUTSIDE SHALL BE STEEL NEMA 3 TYPE
   - 4.B. PROVIDE CEILING BRACKET TO SUPPORT CEILING MOUNTED DEVICES FROM CEILING TEES.
5. 20 AMP, SINGLE PHASE BRANCH CIRCUITS SERVING LIGHTING AND GENERAL RECEPTACLES MAY BE GROUPED IN A SINGLE RACEWAY PROVIDED A NEUTRAL CONDUCTOR IS INSTALLED FOR EACH CIRCUIT REQUIRING A NEUTRAL.
   - 5.A. DO NOT INSTALL MORE THAN FOUR CURRENT CARRYING CONDUCTORS IN A CONDUIT EXCEPT SIX #12 OR #10 CURRENT CARRYING CONDUCTORS MAY BE INSTALLED IN 3/4" OR LARGER CONDUIT FOR 20A CIRCUITS.
   - 5.B. DO NOT INSTALL 480/277 VOLT CONDUCTORS IN THE SAME CONDUIT WITH 240/208/120 VOLT CONDUCTORS.
   - 5.C. DO NOT COMBINE NEUTRALS. PROVIDE DEDICATED NEUTRALS FOR EACH BRANCH CIRCUIT.
   - 5.D. MULTIPLE DEVICES ON A CIRCUIT SUCH AS RECEPTACLES SHALL BE WIRED WITH A PIGTAIL SO THE DEVICE DOES NOT PROVIDE THE CONTINUITY PATH. FEED THROUGH CONNECTIONS FOR GFCI RECEPTACLES SHALL NOT BE USED FOR PROTECTION OF DOWNSTREAM DEVICES.
6. PROVIDE GREEN GROUND WIRE WITH ALL CIRCUITS SIZED PER NEC. BOND GREEN GROUND WIRE TO EACH END OF CONDUIT.
7. PROVIDE J–BOXES, CONDUIT AND SLEEVES THRU ALL FIRE WALLS FOR DATA, TELEPHONE, SECURITY, FIRE ALARM, SOUND SYSTEM, LOW VOLTAGE WIRING, ETC. PROVIDE PROTECTIVE BUSHINGS ON ENDS OF ALL LOW VOLTAGE CONDUITS.
8. PROVIDE PULL BOXES, JUNCTION BOXES, WIRING TROUGHS AND CABINETS WHEREVER REQUIRED FOR PROPER INSTALLATION OF VARIOUS ELECTRICAL SYSTEMS. ALL JUNCTION/PULL BOXES INSTALLED ABOVE ACCESSIBLE CEILINGS SHALL BE MOUNTED SO THAT THE ACCESS PANEL IS NO HIGHER THAN 18" ABOVE THE CEILING.
9. PROVIDE CIRCUIT LABELS IN PERMANENT MARKER ON ALL NEW AND EXISTING J–BOX COVERS UTILIZED IN THE AREA OF RENOVATION.
10. PROVIDE CIRCUIT LABEL ON ALL ABOVE CEILING J–BOXES, EQUIPMENT, ETC. IDENTIFYING THE CIRCUITS CONTAINED/CONNECTED.
11. ALL WIRING SHALL BE 600 VOLT, SOFT DRAWN ANNEALED COPPER, 98% CONDUCTIVITY, CONTINUOUS FROM OUTLET TO OUTLET. MINIMUM WIRE SIZE #12.
    - 11.A. TYPICAL BUILDING WIRE SHALL BE STRANDED TYPE THHN, THWN–2 (WET RATED FOR 90°C), OR XHHW–2. MINIMUM WIRE SIZE SHALL BE #12.
    - 11.B. ALL BUILDING WIRE SHALL BE COLOR CODED WITH THE SAME COLOR CONNECTED TO THE SAME UNGROUNDED PHASE THROUGHOUT THE INSTALLATION MATCHING THE EXISTING BUILDING COLOR CODE SCHEME.
12. WHERE PORTIONS OF INTERIOR RACEWAY SYSTEM ARE EXPOSED TO WIDELY DIFFERENT TEMPERATURES, PROVIDE AIR SEAL PER NEC TO PREVENT CIRCULATION OF AIR FROM WARMER TO COOLER SECTIONS.
13. DRAWINGS, SCHEDULES, NOTES, AND DETAILS ARE INTENDED TO BE COMPLIMENTARY. ANY WORK DESCRIBED IN ANY OF THEM, WILL BE WORK REQUIRED UNDER THIS CONTRACT. WHERE THERE IS A CONFLICT BETWEEN DIFFERENT PORTIONS OF THE DESIGN DOCUMENTS IT SHALL BE CLARIFIED BY RFI. BARRING CLARIFICATION PRIOR TO BIDDING THE MOST EXPENSIVE OPTION SHALL BE INCLUDED AND CLARIFICATION SHALL BE MADE DURING CONSTRUCTION.
14. SHOULD ANY WORK REQUIRED BY THE DRAWINGS AND SPECIFICATIONS BE IN VIOLATION OF ANY FEDERAL, STATE, COUNTY OR CITY LAWS, ORDINANCE OR REGULATION, THOSE LAWS AND REGULATIONS SHALL PREVAIL, AND SHALL BE COMPLIED WITH BY THE CONTRACTOR AS A PART OF THIS WORK WITH NO EXTRA COMPENSATION.
15. ALL MATERIAL MUST BE NEW AND OF GOOD QUALITY AND SHALL BEAR THE STAMP OF APPROVAL OF THE UNDERWRITERS' LABORATORIES, INC. (U.L.).

GENERAL RENOVATION AND REMODELING NOTES:

1. THESE ELECTRICAL DRAWINGS ONLY SHOW SOME EXISTING ELECTRICAL PANELS, DEVICES AND LIGHT FIXTURES IN AREAS OF RENOVATION. ALL OTHER ELECTRICAL EQUIPMENT, WIRING DEVICES, LOW VOLTAGE SYSTEMS, J–BOXES AND CONDUITS SHALL BE LOCATED AND FIELD VERIFIED BY CONTRACTOR.
2. ALL REMOVED DEVICES SHALL BE OFFERED TO THE OWNER AS SALVAGE.
3. RELOCATE CONDUIT AS NECESSARY TO ALLOW NEW OR MODIFIED CONSTRUCTION. RESUPPORT EXISTING CABLING/CONDUIT TO REMAIN TO MEET CURRENTLY ADOPTED CODE REQUIREMENTS. REMOVE ALL ABANDONED CONDUIT AND WIRE. REPAIR EXISTING ELECTRICAL SYSTEMS DAMAGED BY CONSTRUCTION ACTIVITIES.
4. ANY DAMAGE TO EXISTING BUILDING, ELECTRICAL EQUIPMENT, WIRING DEVICES, CONDUIT, WIRING, ETC. SHALL BE REPLACED BY THE CONTRACTOR AT NO COST TO THE OWNER. ALL MATERIALS USED FOR THE REPLACEMENT MUST MEET RENOVATION PROJECT STANDARDS.
5. ELECTRICAL CONTRACTOR SHALL BEGIN FIELD VERIFYING ALL EXISTING BRANCH CIRCUITS FOR EXISTING AREAS TO BE RENOVATED IMMEDIATELY AFTER THE CONTRACT IS ISSUED.
6. ELECTRICAL CONTRACTOR SHALL FIELD VERIFY EXISTING CIRCUITS WITH OWNER'S MAINTENANCE PERSONNEL AFTER NORMAL BUILDING HOURS AS REQUIRED.
7. ANY CIRCUIT OR PARTIAL CIRCUIT TO REMAIN OR BE REUSED SHALL REMAIN ACTIVE.
8. ELECTRICAL CONTRACTOR SHALL INCLUDE COST RELATED TO FIELD VERIFY EXISTING CIRCUITS IN BASE PROPOSAL.
9. FIND AND RECORD ALL EXISTING DEVICES IN CEILINGS, WALLS AND CASEWORK IN AREAS TO BE RENOVATED. PROVIDE A COPY OF THE FIELD VERIFIED DEVICE DRAWINGS TO OWNER PRIOR TO BEGINNING WORK.
10. AT THE END OF THE PROJECT PROVIDE A NEW TYPEWRITTEN AS–BUILT PANEL SCHEDULE FOR ALL PANELS WITH CIRCUITS ADDED, REMOVED, OR MODIFIED AS PART OF THE PROJECT USING BUILDING ROOM NUMBERS.




## 1 ELECTRICAL RENOVATION PLAN

SCALE: 1/4" = 1'– 0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
DULLES ELEMENTARY SCHOOL
630 DULLES AVENUE
SUGAR LAND, TX 77478

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
LICENSED
PROFESSIONAL ENGINEER
07.18.2025

ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL FLOOR PLAN & SCHEDULES

f-E.200

STANTON ENGINEERING GROUP
INFORMATION@SEGI.COM (713) 300–6060 | TEXAS ENG. FIRM REG. NO. F–01853/01 | 1300 W. SAM HOUSTON PKWY.N., SUITE 125, HOUSTON, TX 77043
2025 ALL RIGHTS RESERVED

## AUDIO/VISUAL MULTIMEDIA LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| A## V## | WALL AV ROUGH-IN DETAIL |
| A## V## | CEILING AV ROUGH-IN DETAIL |
| A## V## | FLOOR AV ROUGH-IN DETAIL |
| IWB IWB | INTERACTIVE WHITE BOARD - WALL - CEILING |
| PJ PJ | MULTIMEDIA PROJECTOR |
| FP# FP# | MULTIMEDIA FLAT PANEL DISPLAY |
| S S | LOUDSPEAKER, WALL MOUNTED AND CEILING MOUNTED RESPECTIVELY - # INDICATES TYPE |
| CP# | CONTROL PANEL |
| TP# | TOUCH PANEL |
| M | MICROPHONE, CEILING MOUNTED - # INDICATES TYPE |
| VC | VOLUME CONTROL |
| WB | WALL BOX ENCLOSURE |
| D1 A1 | D1 = DIGITAL SINGLE SIDED CLOCK / A1 = ANALOG SINGLE SIDED CLOCK |
| D2 A2 | D2 = DIGITAL DOUBLE SIDED CLOCK / A2 = ANALOG DOUBLE SIDED CLOCK |
| ENC | CEILING AV ENCLOSURE |
| C C | PRESENTATION CAMERA - CEILING - WALL MOUNTED |

## PREMISE SECURITY LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| CR | CARD READER |
| CR M | CARD READER MULLION |
| KP | INTRUSION DETECTION KEYPAD |
| IC | INTERCOM (1 DATA CABLE) |
| IC MS | INTERCOM MASTER STATION (1 DATA CABLE) |
| PB | PANIC/DURESS BUTTON |
| LD | LOCK DOWN BUTTON |
| MD | MOTION DETECTOR |
| GB | ACCOUSTICAL GLASS BREAK SENSOR |
| BM | BIOMETRIC READER |
| RX | REQUEST TO EXIT - SURFACE PIR |
| KS | KEY SWITCH |
| LA | LOCAL ALARM SOUNDER |
| RG | RED/GREEN INDICATOR LIGHT |
| DB | DOORBELL |
| DH | MAGNETIC DOOR HOLD |
| DR | DOOR RELEASE |
| RX | REQUEST TO EXIT - INTEGRAL TO DOOR HARDWARE |
| DC | DOOR CONTACT / MONITOR |
| ES EL EH | ELECTRIFIED STRIKE - ELECTRIFIED LATCH - ELECTRIFIED HARDWARE (REFER TO SCHEDULES) |
| C C | STANDARD IP SURVEILLANCE CAMERA, (1) CABLE |
| C C C | 180° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° FISHEYE LENS CAMERA |
| IR | IR ILLUMINATOR |

## STRUCTURED CABLING LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF DATA CABLE(S)/JACK(S) |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) |
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| W | WALL MOUNT PHONE (1 CABLE/JACK) |
| W | WALL MOUNT PHONE, SURFACE MOUNT (1 CABLE/JACK) |
| # | FLOOR MOUNTED OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| #/# | FLOOR MOUNTED OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| # | CEILING MOUNTED DATA OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) |
| AP# | CEILING MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| AP# | WALL MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| | CABLING SLEEVE(S) |
| | TYPICAL LADDER RACK |
| | TYPICAL CABLE TRAY, BASKET STYLE |

## GENERAL ANNOTATION LEGEND


| SYMBOL | DESCRIPTION |
|---|---|
| MER | MAIN EQUIPMENT ROOM |
| TR | TELECOMMUNICATION ROOM |
| MDF | MAIN DISTRIBUTION FRAME |
| IDF | INTERMEDIATE DISTRIBUTION FRAME |
| ETR | EXISTING TO REMAIN |
| PBO | PROVIDED BY OTHERS |
| AFF | ABOVE FINISHED FLOOR |
| AFG | ABOVE FINISHED GRADE |
| AC | ABOVE COUNTER |
| EC | ELECTRICAL CONTRACTOR |
| PSC | PREMISE SECURITY CONTRACTOR |
| SCC | STRUCTURAL CABLING CONTRACTOR |
| AVC | AV/MULTIMEDIA CONTRACTOR |
| UNO | UNLESS NOTED OTHERWISE |
| ACS | ACCESS CONTROL SYSTEM |
| VSS | VIDEO SURVEILLANCE SYSTEM |

## TECHNOLOGY - GENERAL NOTES

1. EACH KEYNOTE MAY NOT BE UTILIZED ON EVERY SHEET.
2. ALL CONDUIT MEASUREMENTS REFER TO STANDARD CONDUIT TRADE SIZES.
3. ALL CABLES SHALL BE CONCEALED.
4. EACH CONTRACTOR SHALL PROVIDE AND INSTALL ALL NECESSARY SLEEVES, WHETHER OR NOT SPECIFICALLY NOTED ON PROJECT DRAWINGS. ALL SLEEVES SHALL BE 2" UNLESS NOTED OTHERWISE ON THE DRAWINGS. CABLE FILL PERCENTAGE SHALL COMPLY WITH NEC.
5. DEVICE LOCATIONS ARE APPROXIMATE. CONTRACTOR SHALL REVIEW CONDITIONS AND COORDINATE WITH OTHER TRADES AS NECESSARY FOR EXACT PLACEMENT.

## TECHNOLOGY SYMBOLS LEGEND

NOT ALL SYMBOLS ARE USED




TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

f

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Dulles Elementary School
630 Dulles Ave, Sugar Land, TX 77478

SEAL




07-18-25


MVA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY - TITLE SHEET

f-TN000

## TECHNOLOGY KEYNOTES

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.




1 BACKGROUND F (DULLES ES)
SCALE: 1" = 20'-0"

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

f

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Dulles Elementary School
630 Dulles Ave, Sugar Land, TX 77478

SEAL

BICSI REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256657
EXPIRES 12-31-27
RCDD


07-18-25

MVA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY - Dulles ES - OVERALL

f-TN.100




1 DULLES - KITCHEN PLAN
SCALE: 3/16" = 1'-0"

**TECHNOLOGY KEYNOTES**

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

f

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Dulles Elementary School
630 Dulles Ave, Sugar Land, TX 77478

SEAL

BICSI REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256657
EXPIRES 12-31-27
RCDD

07-18-25

MVA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING
AND
PERMITTING


TECHNOLOGY - Dulles ES - KITCHEN

f-TN.101


TRUENORTH
A PMY COMPANY

**GENERAL NOTE**


1. FACE PLATE DETAIL FOR OUTLET CONFIGURATION PURPOSES ONLY. CONTRACTOR TO SELECT TYPE OF FACE PLATE TO MATCH CONNECTIVITY HARDWARE, FLOOR BOX AND/OR MODULAR FURNITURE OPENING.





1 DATA ROUGH-IN DETAILS
SCALE: NS




2 TYPICAL CABLING SLEEVE
SCALE: NTS




3 PANDUIT J-HOOK DETAIL
SCALE: NTS




4 LABELING & CABLING SCHEMES
SCALE: NTS




5 CABLE PATHWAY CROSS SECTION
SCALE: NTS




6 DROPPED CEILING MOUNTING DETAIL
SCALE: NS




7 I-JOIST MOUNTING DETAIL
SCALE: NS




8 BAR JOIST MOUNTING DETAIL
SCALE: NS

| CAMERA TYPE | MANUFACTURER | MODEL NUMBER | GENERAL DESCRIPTION |
|---|---|---|---|
| C1 | iPro | WV-S8574L | 4x4K (33MP) EXTERIOR MULTI-SENSOR - PARKING LOTS, STADIUM |
| C2 | iPro | WV-S8544L | 4x4MP (16MP) EXTERIOR MULTI-SENSOR - BUILDING PERIMETER |
| C3 | iPro | WV-S25500-V3LN | 5MP EXTERIOR VANDAL DOME |
| C4 | iPro | WV-S22500-V3L | 5MP INTERIOR VANDAL DOME - CORR., COMMON, SPED |
| C5 | iPro | WV-S4156A | 5MP 360 (FISHEYE) - STAIRWELLS |

9 CAMERA SCHEDULE
SCALE: NTS

| Symbol | Purpose | Size | Mount | Backbox | Notes |
|---|---|---|---|---|---|
| FP1 | Digital Signage/Menu Boards | +49" | Ceiling Pole | N/A | Data and Power Outlets on ceiling |

10 DISPLAY SCHEDULE
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

f

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Dulles Elementary School
630 Dulles Ave, Sugar Land, TX 77478

SEAL




07-18-25



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Dulles ES - DETAILS


f-TN.500

GENERAL NOTES:


1. REFER TO SECURITY SCHEDULE AND WRITTEN SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
2. ALL MOUNTING DETAILS ARE REFERENCE FOR ALL FIXED DOME, 180°, 360°, PTZ, AND "BULLET/BOX" CAMERAS.





1 TYPICAL CAMERA INSTALLATION SECTION DETAIL
SCALE: NS




6 WALL MOUNTED CAMERA DETAIL
SCALE: NS




4 TILE BRIDGE DETAIL
SCALE: NS





5 CEILING MOUNTED CAMERA DETAIL
SCALE: NS


ACCESS CONROL DETAILS AND GENERAL NOTES:

1. CONDUIT ROUGH-IN IS A GUIDE FOR WHAT WILL BE REQUIRED FOR EACH DOOR. AS DOOR COMPONENTS CHANGE, EXACT CONDUIT LOCATION WILL ALSO NEED TO BE ADJUSTED.


2. PROTECT EXISTING-TO-REMAIN ACCESS CONTROL DEVICES AND CABLE THROUGHOUT RENOVATION WORK. IF CABLE AND/OR DEVICES ARE DAMAGED, SECURITY CONTRACTOR TO REPLACE WITH NEW.




1 ACCESS CONTROL - WIRING DETAIL - EXIT DEVICE W/ BUILT-IN REX
SCALE: NTS




2 ACCESS CONTROL - STEEL/HOLLOW METAL DOOR.
SCALE: NTS




KP PB LD

3 ROUGH-IN DETAILS: KP, PB, LD
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

f

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Dulles Elementary School
630 Dulles Ave, Sugar Land, TX 77478

SEAL




07-18-25


MVA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING
AND
PERMITTING

TECHNOLOGY - Dulles ES - SECURITY DETAILS

f-TN.600

# FBISD BP013 KITCHEN RENOVATIONS ES

| Sheet List Table | |
|---|---|
| Sheet Number | Sheet Title |
| School: g-Fleming ES | |
| g-A-000 | COVER AND INDEX |
| g-TN-000 | TECHNOLOGY - INDEX SHEET |
| g-TN-100 | TECHNOLOGY - OVERALL |
| g-TN-101 | TECHNOLOGY - KITCHEN |
| g-TN-500 | TECHNOLOGY - DETAILS |
| g-TN-600 | TECHNOLOGY - SECURITY DETAILS |




FORT BEND INDEPENDENT SCHOOL DISTRICT

ARIZONA FLEMING ELEMENTARY SCHOOL
14850 BISSONNET STREET, HOUSTON, TX 77083

## ADMINISTRATION

| | |
|---|---|
| DR. MARCELL SMITH | SUPERINTENDENT OF FBISD |
| DR. ANDRIA SCHUR, Ed.D. | CHIEF OF SCHOOLS |

## BOARD OF TRUSTEES

| | |
|---|---|
| KRISTIN K. TASSIN | PRESIDENT |
| RICK GARCIA | VICE PRESIDENT |
| DAVID HAMILTON | SECRETARY |
| ANGIE HANAN | BOARD MEMBER |
| ADAM SCHOOF | BOARD MEMBER |
| DR. SHIRLEY ROSE-GILLIAM | BOARD MEMBER |
| SONYA JONES | BOARD MEMBER |

## PROJECT DESIGN TEAM


PROGRAM MANAGEMENT
FBISD 2023 Bond Team
2323 Texas Parkway
Missouri City, TX 77489
Phone Number: 281-327-5481

ARCHITECT
MWA Architects
11767 Katy Freeway, Suite 430
Houston, Texas 77079
Phone Number: 713-782-8188

FOOD SERVICE
Food Design Professionals
26215 Oak Ridge Drive
The Woodlands, Texas 77380
Phone Number: 281-350-2323

MEP ENGINEERS
Stanton Engineering Group
1300 W. Sam Houston Pkwy South, Suite 121
Houston, Texas 77042
Phone Number: 713-300-9292

STRUCTURAL ENGINEER
Stanley Spurling & Hamilton
3301 Edloe Street, Suite 200
Houston, Texas 77027
Phone Number: 713-776-9433


ISSUED FOR PERMIT AND BIDDING - JULY 18, 2025

g

## AUDIO/VISUAL MULTIMEDIA LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| A## V## | WALL AV ROUGH-IN DETAIL |
| A## V## | CEILING AV ROUGH-IN DETAIL |
| A## V## | FLOOR AV ROUGH-IN DETAIL |
| IWB IWB | INTERACTIVE WHITE BOARD - WALL - CEILING |
| PJ PJ | MULTIMEDIA PROJECTOR |
| FP# FP# | MULTIMEDIA FLAT PANEL DISPLAY |
| S S | LOUDSPEAKER, WALL MOUNTED AND CEILING MOUNTED RESPECTIVELY - # INDICATES TYPE |
| CP# | CONTROL PANEL |
| TP# | TOUCH PANEL |
| M | MICROPHONE, CEILING MOUNTED - # INDICATES TYPE |
| VC | VOLUME CONTROL |
| WB | WALL BOX ENCLOSURE |
| D1 A1 | D1 = DIGITAL SINGLE SIDED CLOCK / A1 = ANALOG SINGLE SIDED CLOCK |
| D2 A2 | D2 = DIGITAL DOUBLE SIDED CLOCK / A2 = ANALOG DOUBLE SIDED CLOCK |
| ENC | CEILING AV ENCLOSURE |
| C C | PRESENTATION CAMERA - CEILING - WALL MOUNTED |

## PREMISE SECURITY LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| CR | CARD READER |
| CR M | CARD READER MULLION |
| KP | INTRUSION DETECTION KEYPAD |
| IC | INTERCOM (1 DATA CABLE) |
| IC MS | INTERCOM MASTER STATION (1 DATA CABLE) |
| PB | PANIC/DURESS BUTTON |
| LD | LOCK DOWN BUTTON |
| MD | MOTION DETECTOR |
| GB | ACCOUSTICAL GLASS BREAK SENSOR |
| BM | BIOMETRIC READER |
| RX | REQUEST TO EXIT - SURFACE PIR |
| KS | KEY SWITCH |
| LA | LOCAL ALARM SOUNDER |
| RG | RED/GREEN INDICATOR LIGHT |
| DB | DOORBELL |
| DH | MAGNETIC DOOR HOLD |
| DR | DOOR RELEASE |
| RX | REQUEST TO EXIT - INTEGRAL TO DOOR HARDWARE |
| DC | DOOR CONTACT / MONITOR |
| ES EL EH | ELECTRIFIED STRIKE - ELECTRIFIED LATCH - ELECTRIFIED HARDWARE (REFER TO SCHEDULES) |
| C C | STANDARD IP SURVEILLANCE CAMERA, (1) CABLE |
| C C C | 180° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° FISHEYE LENS CAMERA |
| IR | IR ILLUMINATOR |

## STRUCTURED CABLING LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF DATA CABLE(S)/JACK(S) |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) |
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| W | WALL MOUNT PHONE (1 CABLE/JACK) |
| W | WALL MOUNT PHONE, SURFACE MOUNT (1 CABLE/JACK) |
| # | FLOOR MOUNTED OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| #/# | FLOOR MOUNTED OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| # | CEILING MOUNTED DATA OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) |
| AP# | CEILING MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| AP# | WALL MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| | CABLING SLEEVE(S) |
| | TYPICAL LADDER RACK |
| | TYPICAL CABLE TRAY, BASKET STYLE |

## GENERAL ANNOTATION LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| MER | MAIN EQUIPMENT ROOM |
| TR | TELECOMMUNICATION ROOM |
| MDF | MAIN DISTRIBUTION FRAME |
| IDF | INTERMEDIATE DISTRIBUTION FRAME |
| ETR | EXISTING TO REMAIN |
| PBO | PROVIDED BY OTHERS |
| AFF | ABOVE FINISHED FLOOR |
| AFG | ABOVE FINISHED GRADE |
| AC | ABOVE COUNTER |
| EC | ELECTRICAL CONTRACTOR |
| PSC | PREMISE SECURITY CONTRACTOR |
| SCC | STRUCTURAL CABLING CONTRACTOR |
| AVC | AV/MULTIMEDIA CONTRACTOR |
| UNO | UNLESS NOTED OTHERWISE |
| ACS | ACCESS CONTROL SYSTEM |
| VSS | VIDEO SURVEILLANCE SYSTEM |

## TECHNOLOGY - GENERAL NOTES

1. EACH KEYNOTE MAY NOT BE UTILIZED ON EVERY SHEET.
2. ALL CONDUIT MEASUREMENTS REFER TO STANDARD CONDUIT TRADE SIZES.
3. ALL CABLES SHALL BE CONCEALED.
4. EACH CONTRACTOR SHALL PROVIDE AND INSTALL ALL NECESSARY SLEEVES, WHETHER OR NOT SPECIFICALLY NOTED ON PROJECT DRAWINGS. ALL SLEEVES SHALL BE 2" UNLESS NOTED OTHERWISE ON THE DRAWINGS. CABLE FILL PERCENTAGE SHALL COMPLY WITH NEC.
5. DEVICE LOCATIONS ARE APPROXIMATE. CONTRACTOR SHALL REVIEW CONDITIONS AND COORDINATE WITH OTHER TRADES AS NECESSARY FOR EXACT PLACEMENT.

## TECHNOLOGY SYMBOLS LEGEND

NOT ALL SYMBOLS ARE USED

- AV WALL ROUGH-IN WITH DATA
- KEYNOTE
- Proposed Camera Direction SURVEILLANCE CAMERA
- Camera Schedule Number (Floor #-Camera #) Camera (N)ew, (E)xisting Rough-in, (D)emo
- Proposed Camera Direction PTZ CAMERA
- Proposed Camera Direction FIXED SURVEILLANCE CAMERA
- 360°/MULTI-SENSOR FIXED SURVEILLANCE CAMERA OR FISHEYE LENS CAMERA
- Approximate view of lens
- Lens View Angle
- 360°/MULTI-SENSOR FIXED SURVEILLANCE CAMERA OR FISHEYE LENS CAMERA
- Lens size
- MICROPHONE WITH AUDIO LINKED TO CAMERA
- CARD READER LINKED TO CAMERA
- SYMBOL TAG — (#) = DIFFERENT TYPES OF CARD READERS: M = MULLION; W = WIRELESS (Proprietary); Wi = Wi-Fi (802.11); POE = POWER OVER ETHERNET
- SYMBOL TAG — (#) = DIFFERENT TYPES OF CARD READERS: TS = TOUCHSCREEN; PU = PUSH BUTTON
- TOP = DETAIL NUMBER; DETAIL REFERENCE; BOTTOM = SHEET NUMBER
- NORTH ARROW
- SHEET NUMBER; SECTION MARKER; DETAIL NUMBER
- DIRECTION OF ELEVATION; ELEVATION MARKER; SHEET NUMBER; DETAIL NUMBER
- DIRECTION OF ELEVATION; SHEET NUMBER; DIRECTION OF ELEVATION; DETAIL NUMBER
- BAR IS ONE INCH ON ORIGINAL DRAWING. IF NOT ONE INCH ON THIS DRAWING ADJUST SCALES ACCORDINGLY

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

g

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Fleming Elementary School
630 Dulles Ave, Sugar Land, TX 77478

SEAL

BICSI CERTIFIED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 258557
EXPIRES 10-31-27
RCDD

07-18-25


MVA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY - TITLE SHEET

g-TN000

## TECHNOLOGY KEYNOTES

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.




1 BACKGROUND G (FLEMING ES)
SCALE: 1" = 20'-0"

TRUENORTH A PMT COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

g

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Fleming Elementary School
630 Dulles Ave, Sugar Land, TX 77478

SEAL

Bicsi
Brian C Porter
BICSI ID # 256557
EXPIRES 12-31-27
REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER

07-18-25

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY - Fleming ES - OVERALL

g-TN.100

## TECHNOLOGY KEYNOTES

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.




1 FLEMING - KITCHEN PLAN
SCALE: 3/16" = 1'-0"

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

g

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Fleming Elementary School
630 Dulles Ave, Sugar Land, TX 77478

SEAL

BICSI REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256557
EXPIRES 12-31-27

07-18-25


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Fleming ES - KITCHEN


g-TN.101

**GENERAL NOTE**


1. FACE PLATE DETAIL FOR OUTLET CONFIGURATION PURPOSES ONLY. CONTRACTOR TO SELECT TYPE OF FACE PLATE TO MATCH CONNECTIVITY HARDWARE, FLOOR BOX AND/OR MODULAR FURNITURE OPENING.





## 1 DATA ROUGH-IN DETAILS
SCALE: NS





## 2 TYPICAL CABLING SLEEVE
SCALE: NTS





## 3 PANDUIT J-HOOK DETAIL
SCALE: NTS





## 4 LABELING & CABLING SCHEMES
SCALE: NTS





## 5 CABLE PATHWAY CROSS SECTION
SCALE: NTS




## 6 DROPPED CEILING MOUNTING DETAIL
SCALE: NS




## 7 I-JOIST MOUNTING DETAIL
SCALE: NS




## 8 BAR JOIST MOUNTING DETAIL
SCALE: NS

| CAMERA TYPE | MANUFACTURER | MODEL NUMBER | GENERAL DESCRIPTION |
|---|---|---|---|
| C1 | iPro | WV-S8574L | 4x4K (33MP) EXTERIOR MULTI-SENSOR - PARKING LOTS, STADIUM |
| C2 | iPro | WV-S8544L | 4x4MP (16MP) EXTERIOR MULTI-SENSOR - BUILDING PERIMETER |
| C3 | iPro | WV-S25500-V3LN | 5MP EXTERIOR VANDAL DOME |
| C4 | iPro | WV-S22500-V3L | 5MP INTERIOR VANDAL DOME - CORR., COMMON, SPED |
| C5 | iPro | WV-S4156A | 5MP 360 (FISHEYE) - STAIRWELLS |

## 9 CAMERA SCHEDULE
SCALE: NTS

| Symbol | Purpose | Size | Mount | Backbox | Notes |
|---|---|---|---|---|---|
| FP1 | Digital Signage/Menu Boards | +49" | Ceiling Pole | N/A | Data and Power Outlets on ceiling |

## 10 DISPLAY SCHEDULE
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

g

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Fleming Elementary School
630 Dulles Ave, Sugar Land, TX 77478

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256557
EXPIRES 12-31-27
RCDD

07-18-25



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Fleming ES - DETAILS


g-TN.500

GENERAL NOTES:


1. REFER TO SECURITY SCHEDULE AND WRITTEN SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
2. ALL MOUNTING DETAILS ARE REFERENCE FOR ALL FIXED DOME, 180°, 360°, PTZ, AND "BULLET/BOX" CAMERAS.





1 TYPICAL CAMERA INSTALLATION SECTION DETAIL
SCALE: NS




6 WALL MOUNTED CAMERA DETAIL
SCALE: NS




4 TILE BRIDGE DETAIL
SCALE: NS





5 CEILING MOUNTED CAMERA DETAIL
SCALE: NS


ACCESS CONROL DETAILS AND GENERAL NOTES:

1. CONDUIT ROUGH-IN IS A GUIDE FOR WHAT WILL BE REQUIRED FOR EACH DOOR. AS DOOR COMPONENTS CHANGE, EXACT CONDUIT LOCATION WILL ALSO NEED TO BE ADJUSTED.


2. PROTECT EXISTING-TO-REMAIN ACCESS CONTROL DEVICES AND CABLE THROUGHOUT RENOVATION WORK. IF CABLE AND/OR DEVICES ARE DAMAGED, SECURITY CONTRACTOR TO REPLACE WITH NEW.




1 ACCESS CONTROL - WIRING DETAIL - EXIT DEVICE W/ BUILT-IN REX
SCALE: NTS




2 ACCESS CONTROL - STEEL/HOLLOW METAL DOOR.
SCALE: NTS




KP PB LD

3 ROUGH-IN DETAILS: KP, PB, LD
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

g

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Fleming Elementary School
630 Dulles Ave, Sugar Land, TX 77478

SEAL




07-18-25


MVA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING
AND
PERMITTING
TECHNOLOGY - Fleming ES - SECURITY DETAILS

g-TN.600

# FBISD BP013 KITCHEN RENOVATIONS ES

| Sheet List Table | |
|---|---|
| Sheet Number | Sheet Title |
| School: h-GLOVER ES | |
| h-A-000 | COVER AND INDEX |
| h-TN-000 | TECHNOLOGY - INDEX SHEET |
| h-TN-100 | TECHNOLOGY - OVERALL |
| h-TN-101 | TECHNOLOGY - KITCHEN |
| h-TN-500 | TECHNOLOGY - DETAILS |
| h-TN-600 | TECHNOLOGY - SECURITY DETAILS |




FORT BEND INDEPENDENT SCHOOL DISTRICT

EDGAR GLOVER JR ELEMENTARY SCHOOL
1510 COLUMBIA BLUE DRIVE, MISSOURI CITY, TX 77489

## ADMINISTRATION

| | |
|---|---|
| DR. MARCELL SMITH | SUPERINTENDENT OF FBISD |
| DR. ANDRIA SCHUR, Ed.D. | CHIEF OF SCHOOLS |

## BOARD OF TRUSTEES

| | |
|---|---|
| KRISTIN K. TASSIN | PRESIDENT |
| RICK GARCIA | VICE PRESIDENT |
| DAVID HAMILTON | SECRETARY |
| ANGIE HANAN | BOARD MEMBER |
| ADAM SCHOOF | BOARD MEMBER |
| DR. SHIRLEY ROSE-GILLIAM | BOARD MEMBER |
| SONYA JONES | BOARD MEMBER |

## PROJECT DESIGN TEAM

PROGRAM MANAGEMENT
FBISD 2023 Bond Team
2323 Texas Parkway
Missouri City, TX 77489
Phone Number: 281-327-5481

ARCHITECT
MWA Architects
11767 Katy Freeway, Suite 430
Houston, Texas 77079
Phone Number: 713-782-8188

FOOD SERVICE
Food Design Professionals
26215 Oak Ridge Drive
The Woodlands, Texas 77380
Phone Number: 281-350-2323

MEP ENGINEERS
Stanton Engineering Group
1300 W. Sam Houston Pkwy South, Suite 121
Houston, Texas 77042
Phone Number: 713-300-9292

STRUCTURAL ENGINEER
Stanley Spurling & Hamilton
3301 Edloe Street, Suite 200
Houston, Texas 77027
Phone Number: 713-776-9433

ISSUED FOR BIDDING AND PERMITTING - JULY 18, 2025

h

## AUDIO/VISUAL MULTIMEDIA LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| A## V## | WALL AV ROUGH-IN DETAIL |
| A## V## | CEILING AV ROUGH-IN DETAIL |
| A## V## | FLOOR AV ROUGH-IN DETAIL |
| IWB IWB | INTERACTIVE WHITE BOARD - WALL - CEILING |
| PJ PJ | MULTIMEDIA PROJECTOR |
| FP# FP# | MULTIMEDIA FLAT PANEL DISPLAY |
| S S | LOUDSPEAKER, WALL MOUNTED AND CEILING MOUNTED RESPECTIVELY - # INDICATES TYPE |
| CP# | CONTROL PANEL |
| TP# | TOUCH PANEL |
| M | MICROPHONE, CEILING MOUNTED - # INDICATES TYPE |
| VC | VOLUME CONTROL |
| WB | WALL BOX ENCLOSURE |
| D1 A1 | D1 = DIGITAL SINGLE SIDED CLOCK / A1 = ANALOG SINGLE SIDED CLOCK |
| D2 A2 | D2 = DIGITAL DOUBLE SIDED CLOCK / A2 = ANALOG DOUBLE SIDED CLOCK |
| ENC | CEILING AV ENCLOSURE |
| C C | PRESENTATION CAMERA - CEILING - WALL MOUNTED |

## PREMISE SECURITY LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| CR | CARD READER |
| CR M | CARD READER MULLION |
| KP | INTRUSION DETECTION KEYPAD |
| IC | INTERCOM (1 DATA CABLE) |
| IC MS | INTERCOM MASTER STATION (1 DATA CABLE) |
| PB | PANIC/DURESS BUTTON |
| LD | LOCK DOWN BUTTON |
| MD | MOTION DETECTOR |
| GB | ACCOUSTICAL GLASS BREAK SENSOR |
| BM | BIOMETRIC READER |
| RX | REQUEST TO EXIT - SURFACE PIR |
| KS | KEY SWITCH |
| LA | LOCAL ALARM SOUNDER |
| RG | RED/GREEN INDICATOR LIGHT |
| DB | DOORBELL |
| DH | MAGNETIC DOOR HOLD |
| DR | DOOR RELEASE |
| RX | REQUEST TO EXIT - INTEGRAL TO DOOR HARDWARE |
| DC | DOOR CONTACT / MONITOR |
| ES EL EH | ELECTRIFIED STRIKE - ELECTRIFIED LATCH - ELECTRIFIED HARDWARE (REFER TO SCHEDULES) |
| C C | STANDARD IP SURVEILLANCE CAMERA, (1) CABLE |
| C C C | 180° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° FISHEYE LENS CAMERA |
| IR | IR ILLUMINATOR |

## STRUCTURED CABLING LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF DATA CABLE(S)/JACK(S) |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) |
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| W | WALL MOUNT PHONE (1 CABLE/JACK) |
| W | WALL MOUNT PHONE, SURFACE MOUNT (1 CABLE/JACK) |
| # | FLOOR MOUNTED OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| #/# | FLOOR MOUNTED OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| # | CEILING MOUNTED DATA OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) |
| AP# | CEILING MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| AP# | WALL MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| | CABLING SLEEVE(S) |
| | TYPICAL LADDER RACK |
| | TYPICAL CABLE TRAY, BASKET STYLE |

## GENERAL ANNOTATION LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| MER | MAIN EQUIPMENT ROOM |
| TR | TELECOMMUNICATION ROOM |
| MDF | MAIN DISTRIBUTION FRAME |
| IDF | INTERMEDIATE DISTRIBUTION FRAME |
| ETR | EXISTING TO REMAIN |
| PBO | PROVIDED BY OTHERS |
| AFF | ABOVE FINISHED FLOOR |
| AFG | ABOVE FINISHED GRADE |
| AC | ABOVE COUNTER |
| EC | ELECTRICAL CONTRACTOR |
| PSC | PREMISE SECURITY CONTRACTOR |
| SCC | STRUCTURAL CABLING CONTRACTOR |
| AVC | AV/MULTIMEDIA CONTRACTOR |
| UNO | UNLESS NOTED OTHERWISE |
| ACS | ACCESS CONTROL SYSTEM |
| VSS | VIDEO SURVEILLANCE SYSTEM |

## TECHNOLOGY - GENERAL NOTES

1. EACH KEYNOTE MAY NOT BE UTILIZED ON EVERY SHEET.
2. ALL CONDUIT MEASUREMENTS REFER TO STANDARD CONDUIT TRADE SIZES.
3. ALL CABLES SHALL BE CONCEALED.
4. EACH CONTRACTOR SHALL PROVIDE AND INSTALL ALL NECESSARY SLEEVES, WHETHER OR NOT SPECIFICALLY NOTED ON PROJECT DRAWINGS. ALL SLEEVES SHALL BE 2" UNLESS NOTED OTHERWISE ON THE DRAWINGS. CABLE FILL PERCENTAGE SHALL COMPLY WITH NEC.
5. DEVICE LOCATIONS ARE APPROXIMATE. CONTRACTOR SHALL REVIEW CONDITIONS AND COORDINATE WITH OTHER TRADES AS NECESSARY FOR EXACT PLACEMENT.

## TECHNOLOGY SYMBOLS LEGEND

NOT ALL SYMBOLS ARE USED

- AV WALL ROUGH-IN WITH DATA
- KEYNOTE
- Proposed Camera Direction SURVEILLANCE CAMERA
- Camera Schedule Number (Floor #-Camera #) Camera (N)ew, (E)xisting Rough-in, (D)emo
- Proposed Camera Direction PTZ CAMERA
- Proposed Camera Direction FIXED SURVEILLANCE CAMERA
- 360°/MULTI-SENSOR FIXED SURVEILLANCE CAMERA OR FISHEYE LENS CAMERA
- Approximate view of lens
- Lens View Angle
- Lens size
- MICROPHONE WITH AUDIO LINKED TO CAMERA
- CARD READER LINKED TO CAMERA
- SYMBOL TAG — (#) = DIFFERENT TYPES OF CARD READERS: M = MULLION, W = WIRELESS (Proprietary), Wi = Wi-Fi (802.11), POE = POWER OVER ETHERNET
- SYMBOL TAG — (#) = DIFFERENT TYPES OF CARD READERS: TS = TOUCHSCREEN, PU = PUSH BUTTON
- TOP = DETAIL NUMBER; DETAIL REFERENCE; BOTTOM = SHEET NUMBER
- NORTH ARROW
- SHEET NUMBER; SECTION MARKER; DETAIL NUMBER
- DIRECTION OF ELEVATION; ELEVATION MARKER; SHEET NUMBER; DETAIL NUMBER
- DIRECTION OF ELEVATION; SHEET NUMBER; DIRECTION OF ELEVATION; DETAIL NUMBER
- BAR IS ONE INCH ON ORIGINAL DRAWING. IF NOT ONE INCH ON THIS DRAWING ADJUST SCALES ACCORDINGLY

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

h

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Glover Elementary School
1510 Columbia Blue Dr, Missouri City, TX 77489

SEAL

BICSI REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 258557
EXPIRES 10-31-27
RCDD


07-18-25


MVA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY - TITLE SHEET

h-TN000




1 BACKGROUND H (GLOVER ES)
SCALE: 1" = 20'-0"

**TECHNOLOGY KEYNOTES**

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.

TRUENORTH A PWY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

h

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Glover Elementary School
1510 Columbia Blue Dr, Missouri City, TX 77489

SEAL




07-18-25

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Glover ES - OVERALL

h-TN.100

## TECHNOLOGY KEYNOTES

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.




2 GLOVER - KITCHEN PLAN
SCALE: 3/16" = 1'-0"

TRUENORTH A PMT COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

h

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Glover Elementary School
1510 Columbia Blue Dr, Missouri City, TX 77489

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256857
EXPIRES 12-31-27

07-18-25

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY - Glover ES - KITCHEN


h-TN.101

**GENERAL NOTE**


1. FACE PLATE DETAIL FOR OUTLET CONFIGURATION PURPOSES ONLY. CONTRACTOR TO SELECT TYPE OF FACE PLATE TO MATCH CONNECTIVITY HARDWARE, FLOOR BOX AND/OR MODULAR FURNITURE OPENING.





1 DATA ROUGH-IN DETAILS
SCALE: NS




2 TYPICAL CABLING SLEEVE
SCALE: NTS





3 PANDUIT J-HOOK DETAIL
SCALE: NTS





4 LABELING & CABLING SCHEMES
SCALE: NTS





5 CABLE PATHWAY CROSS SECTION
SCALE: NTS




6 DROPPED CEILING MOUNTING DETAIL
SCALE: NS




7 I-JOIST MOUNTING DETAIL
SCALE: NS




8 BAR JOIST MOUNTING DETAIL
SCALE: NS

| CAMERA TYPE | MANUFACTURER | MODEL NUMBER | GENERAL DESCRIPTION |
|---|---|---|---|
| C1 | iPro | WV-S8574L | 4x4K (33MP) EXTERIOR MULTI-SENSOR - PARKING LOTS, STADIUM |
| C2 | iPro | WV-S8544L | 4x4MP (16MP) EXTERIOR MULTI-SENSOR - BUILDING PERIMETER |
| C3 | iPro | WV-S25500-V3LN | 5MP EXTERIOR VANDAL DOME |
| C4 | iPro | WV-S22500-V3L | 5MP INTERIOR VANDAL DOME - CORR., COMMON, SPED |
| C5 | iPro | WV-S4156A | 5MP 360 (FISHEYE) - STAIRWELLS |

9 CAMERA SCHEDULE
SCALE: NTS

| Symbol | Purpose | Size | Mount | Backbox | Notes |
|---|---|---|---|---|---|
| FP1 | Digital Signage/Menu Boards | +49" | Ceiling Pole | N/A | Data and Power Outlets on ceiling |

10 DISPLAY SCHEDULE
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

h

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Glover Elementary School
1510 Columbia Blue Dr, Missouri City, TX 77489

SEAL





07-18-25


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Glover ES - DETAILS
h-TN.500

GENERAL NOTES:


1. REFER TO SECURITY SCHEDULE AND WRITTEN SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
2. ALL MOUNTING DETAILS ARE REFERENCE FOR ALL FIXED DOME, 180°, 360°, PTZ, AND "BULLET/BOX" CAMERAS.





1 TYPICAL CAMERA INSTALLATION SECTION DETAIL
SCALE: NS




6 WALL MOUNTED CAMERA DETAIL
SCALE: NS




4 TILE BRIDGE DETAIL
SCALE: NS





5 CEILING MOUNTED CAMERA DETAIL
SCALE: NS


ACCESS CONROL DETAILS AND GENERAL NOTES:

1. CONDUIT ROUGH-IN IS A GUIDE FOR WHAT WILL BE REQUIRED FOR EACH DOOR. AS DOOR COMPONENTS CHANGE, EXACT CONDUIT LOCATION WILL ALSO NEED TO BE ADJUSTED.


2. PROTECT EXISTING-TO-REMAIN ACCESS CONTROL DEVICES AND CABLE THROUGHOUT RENOVATION WORK. IF CABLE AND/OR DEVICES ARE DAMAGED, SECURITY CONTRACTOR TO REPLACE WITH NEW.




1 ACCESS CONTROL - WIRING DETAIL - EXIT DEVICE W/ BUILT-IN REX
SCALE: NTS




2 ACCESS CONTROL - STEEL/HOLLOW METAL DOOR.
SCALE: NTS




KP PB LD

3 ROUGH-IN DETAILS: KP, PB, LD
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

h

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Glover Elementary School
1510 Columbia Blue Dr, Missouri City, TX 77489

SEAL




07-18-25

MVA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING
AND
PERMITTING

TECHNOLOGY - Glover ES - SECURITY DETAILS

h-TN.600

# FBISD BP013 KITCHEN RENOVATIONS ES

HERITAGE ROSE ELEMENTARY SCHOOL
636 GLENDALE LAKES DR, ROSHARON, TX 77583

FORT BEND INDEPENDENT SCHOOL DISTRICT

FORT BEND INDEPENDENT SCHOOL DISTRICT

## ADMINISTRATION

| | |
|---|---|
| DR. MARCELL SMITH | SUPERINTENDENT OF FBISD |
| DR. ANDRIA SCHUR, Ed.D. | CHIEF OF SCHOOLS |

## BOARD OF TRUSTEES

| | |
|---|---|
| KRISTIN K. TASSIN | PRESIDENT |
| RICK GARCIA | VICE PRESIDENT |
| DAVID HAMILTON | SECRETARY |
| ANGIE HANAN | BOARD MEMBER |
| ADAM SCHOOF | BOARD MEMBER |
| DR. SHIRLEY ROSE-GILLIAM | BOARD MEMBER |
| SONYA JONES | BOARD MEMBER |

## PROJECT DESIGN TEAM


PROGRAM MANAGEMENT
FBISD 2023 Bond Team
2323 Texas Parkway
Missouri City, TX 77489
Phone Number: 281-327-5481

ARCHITECT
MWA Architects
11767 Katy Freeway, Suite 430
Houston, Texas 77079
Phone Number: 713-782-8188

FOOD SERVICE
Food Design Professionals
26215 Oak Ridge Drive
The Woodlands, Texas 77380
Phone Number: 281-350-2323

MEP ENGINEERS
Stanton Engineering Group
1300 W. Sam Houston Pkwy South, Suite 121
Houston, Texas 77042
Phone Number: 713-300-9292

STRUCTURAL ENGINEER
Stanley Spurling & Hamilton
3301 Edloe Street, Suite 200
Houston, Texas 77027
Phone Number: 713-776-9433


| Sheet List Table | |
|---|---|
| Sheet Number | Sheet Title |
| School: I-Heritage Rose ES | |
| I-A.000 | COVER AND INDEX |
| I-A00-01 | GENERAL NOTES AND ABBREVIATIONS |
| I-A.201 | OVERALL FLOOR PLAN |
| I-A.301 | KITCHEN PLAN |
| I-P.101 | FILTER AND NEW WATER SOFTENER |

REGISTERED ARCHITECT
MICHAEL A. MCGUIRE
22651
STATE OF TEXAS

18 July 2025

ISSUED FOR BIDDING AND PERMITTING - JULY 18, 2025

PART 1 - GENERAL

1.1 GENERAL DEMOLITION NOTES

A. VERIFY EXISTING SITE AND BUILDING CONDITIONS IN FIELD PRIOR TO BIDDING. NOTIFY ARCHITECT OF ANY DISCREPANCIES PRIOR TO BIDDING.

B. CONTRACTOR SHALL COORDINATE WITH OWNER THE SALVAGE OF ITEMS, FURNITURE AND EQUIPMENT INDICATED TO BE REMOVED.

C. CLAIMS FOR ADDITIONAL COST OR TIME DUE TO EXISTING CONDITIONS THAT COULD HAVE BEEN REASONABLY ANTICIPATED DURING A SITE VISIT BY THE CONTRACTOR PRIOR TO BIDDING WILL NOT BE APPROVED.

D. PROTECT EXISTING FINISHES SHOWN TO REMAIN DURING CONSTRUCTION TO PREVENT DAMAGE. REPAIR OR REPLACE DAMAGED MATERIALS AND FINISHES TO MATCH EXISTING AT NO ADDITIONAL COST TO FORT BEND ISD (OWNER).

E. EXISTING AREAS REQUIRING MINOR DEMOLITION OR REPAIR FOR EXECUTION OF WORK SHALL BE REPAIRED TO MATCH EXISTING ADJACENT MATERIALS, UNLESS NOTED OTHERWISE.

F. DO NOT DAMAGE CASEWORK AND EQUIPMENT NOT DESIGNATED TO BE REMOVED OR RELOCATED.EXISTING CASEWORK SHALL REMAIN THE PROPERTY OF THE OWNER.

G. CONTRACTOR TO VERIFY LOCATION OF ELEC. SWITCHES, OUTLETS, GRILLES, CLEAN-OUTS, COVER PLATES, ACCESS DOORS, AND OTHER EQUIPMENT AND DEVICES THAT MAY CONFLICT WITH THE RENOVATION AND NEW CONSTRUCTION OF WALLS, FLOORS, AND CEILINGS PRIOR TO COMMENCEMENT OF WORK. CONTRACTOR SHALL LIKEWISE CONFIRM THAT ELECTRICAL CONDUIT ROUTING SHALL BE CONCEALED WITHIN WALLS. NOTIFY ARCHITECT IF WALL THICKNESS WILL NOT ALLOW FOR CONCEALMENT.

H. REMOVE ANY EXISTING CORNER GUARDS IN THE KITCHEN AREA.

I. PRIOR TO EXECUTION OF DEMOLITION WORK, SCHEDULE A WALK-THROUGH WITH OWNER AND ARCHITECT TO CONFIRM SCOPE OF WORK AND TO REVIEW EXISTING CONDITIONS.

J. EXISTING FLOOR FINISHES AND ACOUSTIC CEILING TILE TO BE REMOVED THROUGHOUT.

K. REFER TO MEP DRAWINGS FOR DEMOLITION AND ALTERATION OF UTILITIES.

L. AT ALL EXISTING WALLS REQUIRING DEMOLITION TO INSTALL NEW PIPING BEHIND SINKS, CUT AND PATCH WALLS AS REQUIRED TO MATCH ADJACENT SURFACE.

M. CLEAN AND PREPARE SUBFLOOR FOR INSTALLATION OF NEW FLOOR FINISH.

N. DEMOLITION ACTIVITIES SHALL BE PERFORMED AS TO PRODUCE MINIMAL DISTURBANCE TO EXISTING FACILITY OCCUPANTS. MINIMIZE EXCESSIVE AND PROLONGED NOISE LEVELS AND DUST.

O. ASBESTOS-CONTAINING MATERIALS. REFER TO SPECIFICATION 02 26 23 FOR ASBESTOS INFORMATION APPLICABLE TO KITCHEN AREAS. FORT BEND ISD HAS RETAINED A SEPARATE ENVIRONMENTAL CONSULTANT FOR THE REMOVAL OF ASBESTOS. GC TO COORDINATE WITH ENVIRONMENTAL CONSULTANT TO CARRY OUT ASBESTOS ABATEMENT FOR ALL AFFECTED KITCHEN AREAS.

1.2 FLOOR PLAN GENERAL NOTES

A. FIELD VERIFY EXISTING CONDITIONS PRIOR TO GENERATING SHOP DRAWINGS AND FABRICATION OF EQUIPMENT.
B. FLOOR FINISH CHANGES SHALL OCCUR AT THE CENTERLINE OF DOORS UNLESS NOTED OTHERWISE. FLOOR FINISH CHANGES SHALL HAVE THRESHOLDS OR REDUCERS STRIPS.
C. DOORS THAT ARE TO BE REPLACED AND INSTALLED IN EXISTING FRAMES SHALL BE MACHINED FOR HARDWARE DIMENSIONS AT EXISTING FRAMES, CONTRACTOR SHALL FIELD VERIFY FRAME CONDITIONS AND DIMENSIONS.
D. CONTRACTOR TO PROVIDE SHEET METAL REINFORCING STRAP AS REQUIRED FOR MOUNTING OF ALL GRAB BARS, CABINETS, MIRRORS, SHELVING, ETC.
E. SAW CUT AND REMOVE EXISTING SLAB AND FLOOR FINISHES AS REQUIRED TO INSTALL NEW PLUMBING LINES, FLOOR DRAINS, PLUMBING FIXTURES, OR ELECTRICAL ITEMS. SPLICE NEW REINFORCING BARS DOWELED INTO EXISTING CONCRETE, AND PROVIDE NEW VAPOR RETARDER AND WATERSTOPS, AND PATCH W/ 3000 PSI CONCRETE AFTER INSTALLATION OF UTILITIES AND FIXTURES. PREPARE CONCRETE TO RECEIVE NEW FINISH.
F. COORDINATE HOUSEKEEPING PAD DIMENSIONS AND LOCATIONS WITH EQUIPMENT TO BE INSTALLED. HOUSEKEEPING PADS SHALL BE A MIN. OF 4" THICK REINF. W/ #3 BARS AT 15" O.C. BOTH WAYS. PROVIDE 1" BY 45-DEGREE CHAMFERED EDGES.

1.3 COMPLETE PERFORMANCE

L. THE CONTRACTOR SHALL FURNISH AND INSTALL ALL ITEMS SPECIFIED HEREIN AND AS INDICATED ON THE DRAWINGS. THE CONTRACTOR SHALL ALSO FURNISH AND INSTALL ALL ITEMS NECESSARY TO MAKE THE SYSTEMS FUNCTION WHICH MAY BE REASONABLY IMPLIED AS ESSENTIAL, WHETHER MENTIONED IN THE CONTRACT DOCUMENTS OR NOT.

M. WORK SHALL BE EXECUTED IN STRICT ACCORDANCE WITH THE BEST PRACTICE OF THE TRADES IN A THOROUGH, SUBSTANTIAL AND WORKMANLIKE MANNER BY COMPETENT WORKMEN.

1.4 SITE FAMILIARIZATION

A. GENERAL: BECOME FAMILIAR WITH THE DRAWINGS AND SPECIFICATIONS, EXAMINE THE PREMISES, AND UNDERSTAND THE CONDITIONS UNDER WHICH THE CONTRACT SHALL BE PERFORMED, PRIOR TO SUBMITTING A BID.

B. SITE: BE INFORMED OF THE SITE CONDITIONS, VERIFY LOCATIONS OF NEW AND EXISTING EQUIPMENT, AND DETERMINE EXACT REQUIREMENTS FOR CONNECTIONS.

C. COORDINATION: TENDER OF A PROPOSAL FOR THIS PROJECT INFERS THAT THE CONTRACTOR HAS VISITED THE SITE AND HAS BECOME FAMILIAR WITH THE DRAWINGS, SPECIFICATIONS, AND SITE CONDITIONS AND HAS INCLUDED IN HIS PROPOSAL ALL WORK NECESSARY TO PROPERLY INSTALL COMPLETE AND FUNCTIONING SYSTEMS ON THE PROJECT. FAILURE TO COMPLY WITH THIS REQUIREMENT SHALL NOT BE CONSIDERED JUSTIFICATION FOR THE OMISSION OR FAULTY INSTALLATION OF ANY WORK COVERED BY THE CONTRACT DOCUMENTS.

1.5 CODES AND STANDARDS

A. GENERAL: ALL WORK SHALL COMPLY WITH THE MOST RECENTLY REVISED VERSIONS OF ALL APPLICABLE LAWS, RULES, REGULATIONS AND ORDINANCES OF ALL FEDERAL, STATE AND LOCAL AUTHORITIES AND APPLICABLE UTILITIES. NONE OF THE TERMS OR PROVISIONS OF THIS SPECIFICATION SHALL BE CONSTRUED AS WAIVING ANY PART OF THE LAWS, RULES, REGULATIONS OR REQUIREMENTS OF THESE AUTHORITIES.

B. CONFLICT: IN THE EVENT OF CONFLICT BETWEEN THE CONTRACT DOCUMENTS AND THE LOCAL ENFORCING AUTHORITY, THE LATTER SHALL RULE. ANY MODIFICATIONS RESULTING THEREFROM SHALL BE MADE WITHOUT ANY ADDITIONAL COST TO THE OWNER OR ARCHITECT. THIS CONTRACTOR SHALL REPORT ANY SUCH MODIFICATIONS TO THE ARCHITECT AND SECURE HIS APPROVAL PRIOR TO PROCEEDING WITH THE WORK.

C. PRECEDENCE: WHERE CONTRACT DOCUMENT REQUIREMENTS EXCEED THE REQUIREMENTS OF THE CODES AND STANDARDS, THE CONTRACT DOCUMENTS SHALL TAKE PRECEDENCE PROVIDED THEY ARE NOT IN CONFLICT WITH THOSE CODES AND STANDARDS.

D. APPROVAL LABELS: ALL ITEMS OF EQUIPMENT AND ALL MATERIALS FOR WHICH APPROVED STANDARDS HAVE BEEN ESTABLISHED BY UNDERWRITERS' LABORATORIES, INC. (UL), FACTORY MUTUAL (FM), CERTIFIED BALLAST MANUFACTURER (CBM), ELECTRICAL TESTING LABORATORY (ETL), NATIONAL MANUFACTURERS ASSOCIATION (NEMA), AMERICAN STANDARD CODES, ASME, AGA, AMCA, ASA, ANSI, ASHRAE, AND ARI SHALL BE SO APPROVED AND SHALL BEAR APPROVAL LABELS ATTESTING TO SAME.

1.6 DRAWINGS AND SPECIFICATIONS

A. DRAWINGS: THE SET OF ORIGINAL DRAWINGS HAS BEEN MODIFIED AND INDICATE APPROXIMATE EXISTING LOCATIONS OF THE FLOOR FINISH ITEMS. ALL ITEMS ARE SHOWN APPROXIMATELY TO SCALE. FIELD VERIFY CONDITIONS.

B. SPECIFICATIONS: THE SPECIFICATIONS ARE INTENDED TO SUPPLEMENT THE DRAWINGS AND IT IS NOT IN THE SCOPE OF THE SPECIFICATIONS TO MENTION ANY PART OF THE WORK THAT THE DRAWINGS ARE COMPETENT TO FULLY EXPLAIN. CONVERSELY, ANY PART OF THE WORK THAT THE SPECIFICATIONS ARE COMPETENT TO FULLY EXPLAIN MAY NOT BE MENTIONED ON THE DRAWINGS. DRAWINGS AND SPECIFICATIONS ARE COMPLIMENTARY/SUPPLEMENTARY DOCUMENTS TO EACH OTHER.

C. DISAGREEMENT: DISAGREEMENT BETWEEN THE DRAWINGS AND SPECIFICATIONS OR WITHIN THE DRAWINGS OR SPECIFICATIONS SHALL BE ESTIMATED AND/OR BID USING THE BETTER QUALITY OR GREATER QUANTITY OF MATERIAL OR INSTALLATION, AND A CLARIFICATION REQUEST FOR INFORMATION SHALL BE MADE TO THE ARCHITECT IN A TIMELY MANNER AFTER THE PROJECT IS UNDER CONTRACT.

1.7 DISCREPANCIES

A. CLARIFICATION: CLARIFICATION OF SIGNIFICANT COST MATTERS SHALL BE OBTAINED BEFORE SUBMITTING A PROPOSAL FOR THE WORK AS TO DISCREPANCIES OR OMISSIONS FROM THE CONTRACT DOCUMENTS OR QUESTIONS AS TO THE INTENT THEREOF.

B. INTERPRETATIONS: SHOULD ANY DOUBT OR QUESTION ARISE RESPECTING THE TRUE MEANING OF DRAWINGS OR SPECIFICATIONS, REFERENCE SHALL BE MADE TO THE ARCHITECT, WHOSE WRITTEN DECISION SHALL BE FINAL AND CONCLUSIVE. NO ALLEGED STATEMENT BY THE ARCHITECT WILL BE ACCEPTED AS AN EXCUSE FOR NON-COMPLIANCE OR INFERIOR WORK.

C. CONTRACTOR AGREEMENT: CONSIDERATION WILL NOT BE GRANTED FOR MISUNDERSTANDING OF THE AMOUNT OF WORK TO BE PERFORMED. TENDER OF A PROPOSAL CONVEYS FULL CONTRACTOR AGREEMENT OF THE ITEMS AND CONDITIONS SPECIFIED, SHOWN, SCHEDULED, OR REQUIRED BY THE NATURE OF THE PROJECT, AND ALL COSTS ARE INCLUDED IN THE PROPOSAL.

1.8 REQUESTS FOR INFORMATION (RFI)

A. GENERAL: SUBMIT ALL CONTRACTOR REQUESTS FOR INFORMATION (RFI) IN WRITING TO THE ARCHITECT FOR RESPONSE. SUBMIT RFI ON A STANDARD FORM THAT HAS A SPACE FOR THE REQUESTED INFORMATION AND THE ARCHITECT'S RESPONSE.
B. SOLUTION PROPOSAL: IN GENERAL, THE CONTRACTOR SHALL PROPOSE SOLUTIONS TO IDENTIFY PROBLEMS FOR REVIEW AND APPROVAL OF THE ARCHITECT. THE RFI SHALL INCLUDE HAND SKETCHES, MARKED DRAWING PRINTS, EQUIPMENT CUTSHEETS, DRAWING AND SPECIFICATION REFERENCES, AND ANY OTHER BACK-UP INFORMATION, ETC., AS REQUIRED TO SUFFICIENTLY EXPLAIN THE PROBLEM AND PROPOSED SOLUTION.

1.9 QUALITY ASSURANCE

A. GENERAL: MATERIALS AND EQUIPMENT SHALL BE NEW, OF BEST GRADE AND QUALITY, AND STANDARD PRODUCTS OF REPUTABLE MANUFACTURERS REGULARLY ENGAGED IN THE PRODUCTION OF SUCH MATERIALS AND EQUIPMENT.
B. WORKMANSHIP: WORK SHALL BE EXECUTED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE BEST PRACTICE OF THE TRADES IN A THOROUGH, SUBSTANTIAL, WORKMANLIKE MANNER BY COMPETENT WORKMEN, PRESENTING A NEAT APPEARANCE WHEN COMPLETED.
C. JUDGMENT: IN ALL CASES, THE ARCHITECT SHALL BE THE SOLE JUDGE OF THE QUALITY AND EQUIVALENCE OF MANUFACTURERS, PRODUCTS, MATERIALS, AND METHODS.
D. MANUFACTURERS/PRODUCTS/MATERIALS/METHODS: MANUFACTURERS, PRODUCTS, MATERIALS, AND METHODS DESCRIBED IN THE VARIOUS SECTIONS OF THE SPECIFICATIONS AND INDICATED ON THE DRAWINGS ARE INTENDED TO ESTABLISH A STANDARD OF QUALITY ONLY. IT IS NOT THE INTENTION OF THE ARCHITECT TO DISCRIMINATE AGAINST ANY MANUFACTURER, PRODUCT, MATERIAL, OR METHOD THAT IS EQUAL TO THE STANDARDS AS INDICATED AND/OR SPECIFIED, NOR IS IT INTENDED TO PRECLUDE OPEN, COMPETITIVE BIDDING. THE FACT THAT A SPECIFIC MANUFACTURER IS LISTED AS AN ACCEPTABLE MANUFACTURER SHALL NOT BE INTERPRETED TO MEAN THAT THE MANUFACTURER'S STANDARD PRODUCT WILL MEET THE REQUIREMENTS OF THE PROJECT DESIGN, SPECIFICATIONS, AND SPACE CONSTRAINTS.
    1. WHEREVER A DEFINITE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS SPECIFIED AND THERE IS NOT A STATEMENT THAT ANOTHER MANUFACTURER, PRODUCT, MATERIAL, OR METHOD WILL BE ACCEPTABLE, IT IS THE INTENTION OF THE ARCHITECT THAT THE SPECIFIED MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS THE ONLY ONE THAT SHALL BE USED WITHOUT PRIOR APPROVAL.
    2. WHEREVER A DEFINITE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS SPECIFIED AS "NO SUBSTITUTE", IT IS THE INTENTION OF THE ARCHITECT THAT THE LISTED ITEM IS THE ONLY ONE ACCEPTABLE.
E. COORDINATION: WHERE EQUIPMENT IS USED ON THE PROJECT, IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR OR SUBCONTRACTOR INVOLVED TO VERIFY THAT THE EQUIPMENT WILL FIT IN THE SPACE AVAILABLE, INCLUDING ALL REQUIRED CODE AND MAINTENANCE CLEARANCES, AND TO COORDINATE ALL EQUIPMENT REQUIREMENTS AND PROVISIONS WITH THE SYSTEM DESIGN, ALL AFFECTED DIVISIONS, AND ALL OTHER CONTRACTORS. WHERE THE USE OF ALTERNATE OR SUBSTITUTE MATERIALS AFFECTS THE COST OF PROVISIONS MADE BY OTHER CONTRACTORS, THE CONTRACTOR PROVIDING THE ALTERNATE OR SUBSTITUTE SHALL BE RESPONSIBLE FOR THE OTHER CONTRACTOR'S COST ADJUSTMENT. THERE SHALL BE NO ADDITIONAL COST TO THE OWNER OR ARCHITECT DUE TO THE USE OR ACCEPTANCE OF ANY ALTERNATE OR SUBSTITUTE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD.

1.10 PRIOR APPROVAL

A. SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES: THE CONTRACTOR'S SUBMITTAL AND ARCHITECT'S ACCEPTANCE OF SHOP DRAWINGS, PRODUCT DATA, OR SAMPLES THAT RELATE TO CONSTRUCTION ACTIVITIES NOT COMPLYING WITH THE CONTRACT DOCUMENTS DOES NOT CONSTITUTE AN ACCEPTABLE OR VALID REQUEST FOR SUBSTITUTION, NOR DOES IT CONSTITUTE APPROVAL.

1.11 COORDINATION

A. BY SUBMITTING SHOP DRAWINGS ON THE PROJECT, THIS CONTRACTOR IS INDICATING THAT ALL NECESSARY COORDINATION HAS BEEN COMPLETED AND THAT THE SYSTEMS, PRODUCTS AND EQUIPMENT SUBMITTED CAN BE INSTALLED IN THE BUILDING AND WILL OPERATE AS SPECIFIED AND INTENDED, IN FULL COORDINATION WITH ALL OTHER DISCIPLINES.

1.12 SHOP DRAWINGS AND SUBMITTALS

A. GENERAL: AFTER THE CONTRACT IS AWARDED BUT PRIOR TO PROCEEDING WITH THE WORK REQUIRING SHOP DRAWING REVIEW, THE CONTRACTOR SHALL OBTAIN COMPLETE SHOP DRAWINGS AND PRODUCT DATA FROM THE MANUFACTURERS, SUPPLIERS, VENDORS, AND SUB- CONTRACTORS FOR ALL MATERIALS AND EQUIPMENT SPECIFIED HEREIN, AND MAKE FORMAL SUBMISSION TO THE ARCHITECT. A MINIMUM PERIOD OF TWO (2) WEEKS SHOULD BE ALLOWED IN THE CONSTRUCTION SCHEDULE EXCLUSIVE OF TRAVEL TIME FOR THE ARCHITECTS REVIEW.

B. CERTIFICATION: EACH CONTRACTOR RESPONSIBLE FOR THE WORK SHALL REVIEW AND CERTIFY THE SHOP DRAWING, SUBMITTAL AND/OR PRODUCT DATA TO BE IN FULL COMPLIANCE WITH THE REQUIREMENTS OF THE CONTRACT DOCUMENTS.

C. THE ARCHITECTS REVIEW OF SHOP DRAWINGS AND SUBMITTAL DATA SHALL NOT RELIEVE THE CONTRACTOR OF THE RESPONSIBILITY FOR DIMENSIONS OR ERRORS THAT MAY BE CONTAINED THEREIN, OR FOR DEVIATIONS FROM ANY REQUIREMENTS OF THE CONTRACT DOCUMENTS. IT SHALL BE CLEARLY UNDERSTOOD THAT THE ARCHITECTS NOTING SOME ERRORS BUT OVERLOOKING SOME OTHERS DOES NOT GRANT THE CONTRACTOR PERMISSION TO PROCEED IN ERROR. REGARDLESS OF ANY INFORMATION CONTAINED IN THE SHOP DRAWING OR PRODUCT DATA, THE CONTRACT DOCUMENTS SHALL GOVERN THE WORK AND ARE NEITHER WAIVED NOR SUPERSEDED IN ANY WAY BY THE REVIEW OF SHOP DRAWINGS, PRODUCT DATA AND SAMPLES.

1.13 EXECUTION AND COORDINATION OF WORK

A. MANUFACTURER'S RECOMMENDATIONS: WITH EXCEPTIONS AS SPECIFIED AND/OR INDICATED ON THE DRAWINGS OR IN THE SPECIFICATIONS, APPLY, INSTALL, ERECT, USE, CLEAN, AND CONDITION, MANUFACTURED ARTICLES, MATERIALS, AND EQUIPMENT PER MANUFACTURER'S CURRENT PRINTED RECOMMENDATIONS. KEEP COPIES OF SUCH PRINTED RECOMMENDATIONS AT JOB SITE AND MAKE THEM AVAILABLE AS REQUIRED.

1.14 SUPERVISION

A. A COMPETENT SUPERINTENDENT APPROVED BY THE ARCHITECT, SHALL BE KEPT BY THE CONTRACTOR AT THE BUILDING TO RECEIVE INSTRUCTIONS AND TO ACT FOR THE CONTRACTOR. ONCE THE SUPERINTENDENT HAS BEEN APPROVED, NO CHANGE SHALL BE MADE WITHOUT APPROVAL OF ARCHITECT. REPRESENTATIVES OF THE OWNER, ARCHITECT SHALL HAVE THE RIGHT TO OBSERVE THE WORK AT ANY TIME. THE CONTRACTOR SHALL HAVE A REPRESENTATIVE AVAILABLE WHEN HIS WORK IS BEING OBSERVED AND HE SHALL GIVE ASSISTANCE AS MAY BE REQUIRED TO THE ARCHITECT'S REPRESENTATIVE.

B. THE PROJECT SHALL BE CONSTRUCTED BY EMPLOYEES OF THE CONTRACTOR OR BY WORKERS UNDER HIS SUPERVISION. ANY SUBCONTRACTORS EMPLOYED BY THE CONTRACTOR SHALL BE APPROVED BY THE OWNER'S REPRESENTATIVE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL EQUIPMENT, MATERIAL AND WORK PERFORMED BY ANY SUBCONTRACTOR.

1.15 STORAGE AND PROTECTION OF MATERIALS

A. THE CONTRACTOR SHALL PROPERLY STORE ALL MATERIAL AND EQUIPMENT AT THE JOBSITE AND PROTECT IT FROM THE ELEMENTS AND FROM DAMAGE. ANY EQUIPMENT DAMAGED DUE TO IMPROPER PROTECTION SHALL BE REPLACED BY THE CONTRACTOR AT HIS EXPENSE.

B. THE CONTRACTOR SHALL PROTECT THE WORK, EQUIPMENT, AND MATERIAL OF ALL OTHER TRADES FROM DAMAGE BY HIS WORK OR OTHER WORKMEN, AND SHALL MAKE GOOD ALL DAMAGE THUS CAUSED.

C. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL WORK, MATERIALS, AND EQUIPMENT UNTIL FINALLY INSPECTED, TESTED, AND ACCEPTED; PROTECT WORK AGAINST THEFT, INJURY OR DAMAGE; AND CAREFULLY STORE MATERIAL AND EQUIPMENT RECEIVED ON SITE WHICH ARE NOT IMMEDIATELY INSTALLED. CLOSE OPEN ENDS OF WORK WITH TEMPORARY COVERS OR PLUGS DURING CONSTRUCTION TO PREVENT ENTRY OF OBSTRUCTING MATERIAL. THE CONTRACTOR SHALL COVER AND PROTECT IN AN ACCEPTABLE MANNER TO THE OWNER, EXISTING REMAINING EQUIPMENT AND MATERIALS.

D. IF ANY MATERIAL OR EQUIPMENT IS RECEIVED PRIOR TO THE TIME IT IS REQUIRED, THE CONTRACTOR SHALL BE RESPONSIBLE FOR ITS PROPER STORAGE AND PROTECTION UNTIL SUCH TIME AS IT MAY BE REQUIRED. THE CONTRACTOR SHALL PAY FOR ALL COSTS OF DEMURRAGE OR STORAGE.

1.16 DRAYAGE AND HAULING

A. THE CONTRACTOR SHALL KEEP THE JOBSITE FREE FROM THE ACCUMULATION OF TRASH AND CONSTRUCTION DEBRIS, REGARDLESS OF WHICH SUBCONTRACTOR MAY BE RESPONSIBLE.

1.17 CUTTING AND PATCHING

A. WHERE IT BECOMES NECESSARY TO CUT THROUGH ANY WALL, FLOOR OR CEILING TO PERMIT THE INSTALLATION OF ANY WORK, OR TO REPAIR ANY DEFECTS THAT MAY APPEAR, THE CUTTING SHALL BE PERFORMED UNDER THE SUPERVISION OF THE GENERAL CONTRACTOR. INFORM THE OWNER'S REPRESENTATIVE BEFORE ANY WORK COMMENCES. NO STRUCTURAL MEMBER SHALL BE ALTERED WITHOUT THE WRITTEN PERMISSION OF THE ARCHITECT.

B. VERIFICATION: SHOULD A QUESTION ARISE REGARDING THE ACCEPTABLE LEVEL OF NOISE OR VIBRATION IN A PARTICULAR SPACE OR PIECE OF EQUIPMENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING THE SERVICES OF AN APPROVED ACOUSTICAL CONSULTANT TO DETERMINE ACTUAL NOISE/VIBRATION CONDITIONS.

## 01 GENERAL NOTES

## 03 PROJECT SCHEDULE

SEQUENCE OF CONSTRUCTION (AS OF 01/27/2025). Schools will be renovated in groups as shown. These groups contain two or three major kitchen renovations and some cafeteria/miscellaneous renovations. This sequencing is critical for FBISD food service to provide the uninterrupted meal services to their schools.

| | |
|---|---|
| GROUPING 1 | AUSTIN PARKWAY ES + SUGAR MILL ES, kitchen renovations. *Plus: COMMON WEALTH ES, CONERSTONE ES misc. renovations.* |
| GROUPING 2 | SETTLERS WAY ES + PALMER ES kitchen renovations. *Plus: SULLIVAN ES, SIENNA CROSSING ES, HERITAGE ROSE ES misc. renovations* |
| GROUPING 3 | HUNTER'S GLEN ES + HIGHLANDS ES + PECAN GROVE ES kitchen renovations. *Plus: RIDGEGATE ES, DULLES ES misc. renovations.* |

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HERITAGE ROSE ELEMENTARY SCHOOL
636 GLENDALE LAKES DRIVE
ROSHARON, TX 77583

SEAL

7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

GENERAL NOTES AND ABBREVIATIONS

A00-01


F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\A00-01 GENERAL NOTES AND ABBREVIATIONS.dwg Jul 23, 2025 - 1:50pm


## Project Information

PROJECT: HERITAGE ROSE ELEMENTARY SCHOOL
LOCATION: 636 GLENDALE LAKES DRIVE
ROSHARON, TX 77583

SCOPE OF WORK: PROVIDE AND INSTALL REVERSE OSMOSIS FOR KITCHEM APPLIANCES.

| PHASING CHART FOR ALL SCHOOLS | | |
|---|---|---|
| PHASE 1 | | |
| **SCHOOLS** | **FREEZER START DATE :** | **FREEZER END DATE :** |
| AUSTIN PARKWAY ES | 11/7/2025 | 5/13/2026 |
| SUGAR MILL ES | | |
| COMMONWEALTH ES | | |
| CONERSTONE ES | | |
| PHASE 2 | | |
| SETTLERS WAY ES | 5/29/2026 | 10/28/2026 |
| PALMER ES | | |
| SULLIVAN ES | | |
| SIENNA CROSSING ES | | |
| ***HERITAGE ROSE ES*** | | |
| **PHASE 3** | | |
| HUNTERS GLEN ES | 3/19/2027 | 3/19/2027 |
| PECAN GROVE ES | | |
| HIGHLANDS ES | | |
| DULLES ES | | |


1
1/A.301
LOCATION OF NEW R.O. UNIT
MECH M818 1,006 SF
MECH M816 457 SF
ELEC E314 209 SF
STO B11 96 SF
STO B10A 108 SF
2,455 S.F.
(13 OCC.
@ 200 S.F.)
KITCHEN / SERVING B150 2,715 SF
CIRC B18 229 SF
CUST B12 369 SF
RR B102 43 SF
STO B10B 348 SF
STO B100 195 SF
RR B078 43 SF
STO B809 266 SF
RR B07A 43 SF
STUDENT DINING B07 4,591 SF
PE STO B802 172 SF
RR B32 172 SF
GYM B04 4,657 SF
CIRC A02 3,254 SF
PE STO B29 108 SF
STO B28 123 SF
STAGE B06 933 SF
PE STO B28 234 SF
CIRC B23 414 SF
MUSIC B02 1,088 SF
STO B18 93 SF
OFFICE B09A 222 SF
OFFICE B18 106 SF
RR B096 172 SF
RR B094 171 SF
OFFICE B03A 130 SF
RR B14 39 SF
RR B15 39 SF
STO B09 158 SF
EXTENDED DAY B03 2,241 SF
STO B03B 55 SF
ART B01 946 SF
ART B00 945 SF
CLASSROOM 801 703 SF
CLASSROOM 802 704 SF
CLASSROOM 803 701 SF
CLASSROOM 804 701 SF
CLASSROOM 805 703 SF
CLASSROOM 806 703 SF
CLASSROOM 807 703 SF
CLASSROOM 808 703 SF
CLASSROOM 809 704 SF
CLASSROOM 810 703 SF
CLASSROOM 811 805 SF
CLASSROOM 503 801 SF
CLASSROOM 504 801 SF
CLASSROOM 505 807 SF
CLASSROOM 506 806 SF
CLASSROOM 507 804 SF
CIRC A31 1,007 SF
CIRC A26 1,007 SF
CIRC A27 1,048 SF
CIRC E26 1,019 SF
CIRC E34 1,157 SF
CIRC E33 2,741 SF
CIRC E32 351 SF
CIRC B36 885 SF
CIRC D11 981 SF
CIRC B45 1,007 SF
CIRC F23 86 SF
CIRC D21 174 SF
CIRC E37 1,027 SF
CLASSROOM 698 SF
CLASSROOM 699 SF
CLASSROOM 798 SF
CLASSROOM 702 SF
CLASSROOM 704 SF
CLASSROOM 703 SF
CLASSROOM 701 SF
CLASSROOM 702 SF
CLASSROOM 707 798 SF
CLASSROOM 708 813 SF
CLASSROOM 709 810 SF
CLASSROOM 710 824 SF
CLASSROOM 711 811 SF
CLASSROOM 712 809 SF
CLASSROOM 713 811 SF
CLASSROOM 714 811 SF
CLASSROOM 715 811 SF
CLASSROOM 716 811 SF
CLASSROOM 717 811 SF
CLASSROOM 718 811 SF
CLASSROOM 719 811 SF
CLASSROOM 720 811 SF
CLASSROOM 721 811 SF
CLASSROOM 722 811 SF
CLASSROOM 723 811 SF
CLASSROOM 724 811 SF
CLASSROOM 725 811 SF
CLASSROOM 726 811 SF
CLASSROOM 727 811 SF
CLASSROOM 728 811 SF
CLASSROOM 729 811 SF
CLASSROOM 730 811 SF
CLASSROOM 731 811 SF
CLASSROOM 732 811 SF
CLASSROOM 733 811 SF
CLASSROOM 734 811 SF
CLASSROOM 735 811 SF
CLASSROOM 736 811 SF
CLASSROOM 737 811 SF
CLASSROOM 738 811 SF
CLASSROOM 739 811 SF
CLASSROOM 740 811 SF
CLASSROOM 741 811 SF
CLASSROOM 742 811 SF
CLASSROOM 743 811 SF
CLASSROOM 744 811 SF
CLASSROOM 745 811 SF
CLASSROOM 746 811 SF
CLASSROOM 747 811 SF
CLASSROOM 748 811 SF
CLASSROOM 749 811 SF
CLASSROOM 750 811 SF
CLASSROOM 751 811 SF
CLASSROOM 752 811 SF
CLASSROOM 753 811 SF
CLASSROOM 754 811 SF
CLASSROOM 755 811 SF
CLASSROOM 756 811 SF
CLASSROOM 757 811 SF
CLASSROOM 758 811 SF
CLASSROOM 759 811 SF
CLASSROOM 760 811 SF
CLASSROOM 761 811 SF
CLASSROOM 762 811 SF
CLASSROOM 763 811 SF
CLASSROOM 764 811 SF
CLASSROOM 765 811 SF
CLASSROOM 766 811 SF
CLASSROOM 767 811 SF
CLASSROOM 768 811 SF
CLASSROOM 769 811 SF
CLASSROOM 770 811 SF
CLASSROOM 771 811 SF
CLASSROOM 772 811 SF
CLASSROOM 773 811 SF
CLASSROOM 774 811 SF
CLASSROOM 775 811 SF
CLASSROOM 776 811 SF
CLASSROOM 777 811 SF
CLASSROOM 778 811 SF
CLASSROOM 779 811 SF
CLASSROOM 780 811 SF
CLASSROOM 781 811 SF
CLASSROOM 782 811 SF
CLASSROOM 783 811 SF
CLASSROOM 784 811 SF
CLASSROOM 785 811 SF
CLASSROOM 786 811 SF
CLASSROOM 787 811 SF
CLASSROOM 788 811 SF
CLASSROOM 789 811 SF
CLASSROOM 790 811 SF
CLASSROOM 791 811 SF
CLASSROOM 792 811 SF
CLASSROOM 793 811 SF
CLASSROOM 794 811 SF
CLASSROOM 795 811 SF
CLASSROOM 796 811 SF
CLASSROOM 797 811 SF
CLASSROOM 798 811 SF
CLASSROOM 799 811 SF
CLASSROOM 800 811 SF
CLASSROOM 801 811 SF
CLASSROOM 802 811 SF
CLASSROOM 803 811 SF
CLASSROOM 804 811 SF
CLASSROOM 805 811 SF
CLASSROOM 806 811 SF
CLASSROOM 807 811 SF
CLASSROOM 808 811 SF
CLASSROOM 809 811 SF
CLASSROOM 810 811 SF
CLASSROOM 811 811 SF
CLASSROOM 812 811 SF
CLASSROOM 813 811 SF
CLASSROOM 814 811 SF
CLASSROOM 815 811 SF
CLASSROOM 816 811 SF
CLASSROOM 817 811 SF
CLASSROOM 818 811 SF
CLASSROOM 819 811 SF
CLASSROOM 820 811 SF
CLASSROOM 821 811 SF
CLASSROOM 822 811 SF
CLASSROOM 823 811 SF
CLASSROOM 824 811 SF
CLASSROOM 825 811 SF
CLASSROOM 826 811 SF
CLASSROOM 827 811 SF
CLASSROOM 828 811 SF
CLASSROOM 829 811 SF
CLASSROOM 830 811 SF
CLASSROOM 831 811 SF
CLASSROOM 832 811 SF
CLASSROOM 833 811 SF
CLASSROOM 834 811 SF
CLASSROOM 835 811 SF
CLASSROOM 836 811 SF
CLASSROOM 837 811 SF
CLASSROOM 838 811 SF
CLASSROOM 839 811 SF
CLASSROOM 840 811 SF
CLASSROOM 841 811 SF
CLASSROOM 842 811 SF
CLASSROOM 843 811 SF
CLASSROOM 844 811 SF
CLASSROOM 845 811 SF
CLASSROOM 846 811 SF
CLASSROOM 847 811 SF
CLASSROOM 848 811 SF
CLASSROOM 849 811 SF
CLASSROOM 850 811 SF
CLASSROOM 851 811 SF
CLASSROOM 852 811 SF
CLASSROOM 853 811 SF
CLASSROOM 854 811 SF
CLASSROOM 855 811 SF
CLASSROOM 856 811 SF
CLASSROOM 857 811 SF
CLASSROOM 858 811 SF
CLASSROOM 859 811 SF
CLASSROOM 860 811 SF
CLASSROOM 861 811 SF
CLASSROOM 862 811 SF
CLASSROOM 863 811 SF
CLASSROOM 864 811 SF
CLASSROOM 865 811 SF
CLASSROOM 866 811 SF
CLASSROOM 867 811 SF
CLASSROOM 868 811 SF
CLASSROOM 869 811 SF
CLASSROOM 870 811 SF
CLASSROOM 871 811 SF
CLASSROOM 872 811 SF
CLASSROOM 873 811 SF
CLASSROOM 874 811 SF
CLASSROOM 875 811 SF
CLASSROOM 876 811 SF
CLASSROOM 877 811 SF
CLASSROOM 878 811 SF
CLASSROOM 879 811 SF
CLASSROOM 880 811 SF
CLASSROOM 881 811 SF
CLASSROOM 882 811 SF
CLASSROOM 883 811 SF
CLASSROOM 884 811 SF
CLASSROOM 885 811 SF
CLASSROOM 886 811 SF
CLASSROOM 887 811 SF
CLASSROOM 888 811 SF
CLASSROOM 889 811 SF
CLASSROOM 890 811 SF
CLASSROOM 891 811 SF
CLASSROOM 892 811 SF
CLASSROOM 893 811 SF
CLASSROOM 894 811 SF
CLASSROOM 895 811 SF
CLASSROOM 896 811 SF
CLASSROOM 897 811 SF
CLASSROOM 898 811 SF
CLASSROOM 899 811 SF
CLASSROOM 900 811 SF
CLASSROOM 901 811 SF
CLASSROOM 902 811 SF
CLASSROOM 903 811 SF
CLASSROOM 904 811 SF
CLASSROOM 905 811 SF
CLASSROOM 906 811 SF
CLASSROOM 907 811 SF
CLASSROOM 908 811 SF
CLASSROOM 909 811 SF
CLASSROOM 910 811 SF
CLASSROOM 911 811 SF
CLASSROOM 912 811 SF
CLASSROOM 913 811 SF
CLASSROOM 914 811 SF
CLASSROOM 915 811 SF
CLASSROOM 916 811 SF
CLASSROOM 917 811 SF
CLASSROOM 918 811 SF
CLASSROOM 919 811 SF
CLASSROOM 920 811 SF
CLASSROOM 921 811 SF
CLASSROOM 922 811 SF
CLASSROOM 923 811 SF
CLASSROOM 924 811 SF
CLASSROOM 925 811 SF
CLASSROOM 926 811 SF
CLASSROOM 927 811 SF
CLASSROOM 928 811 SF
CLASSROOM 929 811 SF
CLASSROOM 930 811 SF
CLASSROOM 931 811 SF
CLASSROOM 932 811 SF
CLASSROOM 933 811 SF
CLASSROOM 934 811 SF
CLASSROOM 935 811 SF
CLASSROOM 936 811 SF
CLASSROOM 937 811 SF
CLASSROOM 938 811 SF
CLASSROOM 939 811 SF
CLASSROOM 940 811 SF
CLASSROOM 941 811 SF
CLASSROOM 942 811 SF
CLASSROOM 943 811 SF
CLASSROOM 944 811 SF
CLASSROOM 945 811 SF
CLASSROOM 946 811 SF
CLASSROOM 947 811 SF
CLASSROOM 948 811 SF
CLASSROOM 949 811 SF
CLASSROOM 950 811 SF
CLASSROOM 951 811 SF
CLASSROOM 952 811 SF
CLASSROOM 953 811 SF
CLASSROOM 954 811 SF
CLASSROOM 955 811 SF
CLASSROOM 956 811 SF
CLASSROOM 957 811 SF
CLASSROOM 958 811 SF
CLASSROOM 959 811 SF
CLASSROOM 960 811 SF
CLASSROOM 961 811 SF
CLASSROOM 962 811 SF
CLASSROOM 963 811 SF
CLASSROOM 964 811 SF
CLASSROOM 965 811 SF
CLASSROOM 966 811 SF
CLASSROOM 967 811 SF
CLASSROOM 968 811 SF
CLASSROOM 969 811 SF
CLASSROOM 970 811 SF
CLASSROOM 971 811 SF
CLASSROOM 972 811 SF
CLASSROOM 973 811 SF
CLASSROOM 974 811 SF
CLASSROOM 975 811 SF
CLASSROOM 976 811 SF
CLASSROOM 977 811 SF
CLASSROOM 978 811 SF
CLASSROOM 979 811 SF
CLASSROOM 980 811 SF
CLASSROOM 981 811 SF
CLASSROOM 982 811 SF
CLASSROOM 983 811 SF
CLASSROOM 984 811 SF
CLASSROOM 985 811 SF
CLASSROOM 986 811 SF
CLASSROOM 987 811 SF
CLASSROOM 988 811 SF
CLASSROOM 989 811 SF
CLASSROOM 990 811 SF
CLASSROOM 991 811 SF
CLASSROOM 992 811 SF
CLASSROOM 993 811 SF
CLASSROOM 994 811 SF
CLASSROOM 995 811 SF
CLASSROOM 996 811 SF
CLASSROOM 997 811 SF
CLASSROOM 998 811 SF
CLASSROOM 999 811 SF
CLASSROOM 1000 811 SF
CLASSROOM 1001 811 SF
CLASSROOM 1002 811 SF
CLASSROOM 1003 811 SF
CLASSROOM 1004 811 SF
CLASSROOM 1005 811 SF
CLASSROOM 1006 811 SF
CLASSROOM 1007 811 SF
CLASSROOM 1008 811 SF
CLASSROOM 1009 811 SF
CLASSROOM 1010 811 SF
CLASSROOM 1011 811 SF
CLASSROOM 1012 811 SF
CLASSROOM 1013 811 SF
CLASSROOM 1014 811 SF
CLASSROOM 1015 811 SF
CLASSROOM 1016 811 SF
CLASSROOM 1017 811 SF
CLASSROOM 1018 811 SF
CLASSROOM 1019 811 SF
CLASSROOM 1020 811 SF
CLASSROOM 1021 811 SF
CLASSROOM 1022 811 SF
CLASSROOM 1023 811 SF
CLASSROOM 1024 811 SF
CLASSROOM 1025 811 SF
CLASSROOM 1026 811 SF
CLASSROOM 1027 811 SF
CLASSROOM 1028 811 SF
CLASSROOM 1029 811 SF
CLASSROOM 1030 811 SF
CLASSROOM 1031 811 SF
CLASSROOM 1032 811 SF
CLASSROOM 1033 811 SF
CLASSROOM 1034 811 SF
CLASSROOM 1035 811 SF
CLASSROOM 1036 811 SF
CLASSROOM 1037 811 SF
CLASSROOM 1038 811 SF
CLASSROOM 1039 811 SF
CLASSROOM 1040 811 SF
CLASSROOM 1041 811 SF
CLASSROOM 1042 811 SF
CLASSROOM 1043 811 SF
CLASSROOM 1044 811 SF
CLASSROOM 1045 811 SF
CLASSROOM 1046 811 SF
CLASSROOM 1047 811 SF
CLASSROOM 1048 811 SF
CLASSROOM 1049 811 SF
CLASSROOM 1050 811 SF
CLASSROOM 1051 811 SF
CLASSROOM 1052 811 SF
CLASSROOM 1053 811 SF
CLASSROOM 1054 811 SF
CLASSROOM 1055 811 SF
CLASSROOM 1056 811 SF
CLASSROOM 1057 811 SF
CLASSROOM 1058 811 SF
CLASSROOM 1059 811 SF
CLASSROOM 1060 811 SF
CLASSROOM 1061 811 SF
CLASSROOM 1062 811 SF
CLASSROOM 1063 811 SF
CLASSROOM 1064 811 SF
CLASSROOM 1065 811 SF
CLASSROOM 1066 811 SF
CLASSROOM 1067 811 SF
CLASSROOM 1068 811 SF
CLASSROOM 1069 811 SF
CLASSROOM 1070 811 SF
CLASSROOM 1071 811 SF
CLASSROOM 1072 811 SF
CLASSROOM 1073 811 SF
CLASSROOM 1074 811 SF
CLASSROOM 1075 811 SF
CLASSROOM 1076 811 SF
CLASSROOM 1077 811 SF
CLASSROOM 1078 811 SF
CLASSROOM 1079 811 SF
CLASSROOM 1080 811 SF
CLASSROOM 1081 811 SF
CLASSROOM 1082 811 SF
CLASSROOM 1083 811 SF
CLASSROOM 1084 811 SF
CLASSROOM 1085 811 SF
CLASSROOM 1086 811 SF
CLASSROOM 1087 811 SF
CLASSROOM 1088 811 SF
CLASSROOM 1089 811 SF
CLASSROOM 1090 811 SF
CLASSROOM 1091 811 SF
CLASSROOM 1092 811 SF
CLASSROOM 1093 811 SF
CLASSROOM 1094 811 SF
CLASSROOM 1095 811 SF
CLASSROOM 1096 811 SF
CLASSROOM 1097 811 SF
CLASSROOM 1098 811 SF
CLASSROOM 1099 811 SF
CLASSROOM 1100 811 SF
CLASSROOM 1101 811 SF
CLASSROOM 1102 811 SF
CLASSROOM 1103 811 SF
CLASSROOM 1104 811 SF
CLASSROOM 1105 811 SF
CLASSROOM 1106 811 SF
CLASSROOM 1107 811 SF
CLASSROOM 1108 811 SF
CLASSROOM 1109 811 SF
CLASSROOM 1110 811 SF
CLASSROOM 1111 811 SF
CLASSROOM 1112 811 SF
CLASSROOM 1113 811 SF
CLASSROOM 1114 811 SF
CLASSROOM 1115 811 SF
CLASSROOM 1116 811 SF
CLASSROOM 1117 811 SF
CLASSROOM 1118 811 SF
CLASSROOM 1119 811 SF
CLASSROOM 1120 811 SF
CLASSROOM 1121 811 SF
CLASSROOM 1122 811 SF
CLASSROOM 1123 811 SF
CLASSROOM 1124 811 SF
CLASSROOM 1125 811 SF
CLASSROOM 1126 811 SF
CLASSROOM 1127 811 SF
CLASSROOM 1128 811 SF
CLASSROOM 1129 811 SF
CLASSROOM 1130 811 SF
CLASSROOM 1131 811 SF
CLASSROOM 1132 811 SF
CLASSROOM 1133 811 SF
CLASSROOM 1134 811 SF
CLASSROOM 1135 811 SF
CLASSROOM 1136 811 SF
CLASSROOM 1137 811 SF
CLASSROOM 1138 811 SF
CLASSROOM 1139 811 SF
CLASSROOM 1140 811 SF
CLASSROOM 1141 811 SF
CLASSROOM 1142 811 SF
CLASSROOM 1143 811 SF
CLASSROOM 1144 811 SF
CLASSROOM 1145 811 SF
CLASSROOM 1146 811 SF
CLASSROOM 1147 811 SF
CLASSROOM 1148 811 SF
CLASSROOM 1149 811 SF
CLASSROOM 1150 811 SF
CLASSROOM 1151 811 SF
CLASSROOM 1152 811 SF
CLASSROOM 1153 811 SF
CLASSROOM 1154 811 SF
CLASSROOM 1155 811 SF
CLASSROOM 1156 811 SF
CLASSROOM 1157 811 SF
CLASSROOM 1158 811 SF
CLASSROOM 1159 811 SF
CLASSROOM 1160 811 SF
CLASSROOM 1161 811 SF
CLASSROOM 1162 811 SF
CLASSROOM 1163 811 SF
CLASSROOM 1164 811 SF
CLASSROOM 1165 811 SF
CLASSROOM 1166 811 SF
CLASSROOM 1167 811 SF
CLASSROOM 1168 811 SF
CLASSROOM 1169 811 SF
CLASSROOM 1170 811 SF
CLASSROOM 1171 811 SF
CLASSROOM 1172 811 SF
CLASSROOM 1173 811 SF
CLASSROOM 1174 811 SF
CLASSROOM 1175 811 SF
CLASSROOM 1176 811 SF
CLASSROOM 1177 811 SF
CLASSROOM 1178 811 SF
CLASSROOM 1179 811 SF
CLASSROOM 1180 811 SF
CLASSROOM 1181 811 SF
CLASSROOM 1182 811 SF
CLASSROOM 1183 811 SF
CLASSROOM 1184 811 SF
CLASSROOM 1185 811 SF
CLASSROOM 1186 811 SF
CLASSROOM 1187 811 SF
CLASSROOM 1188 811 SF
CLASSROOM 1189 811 SF
CLASSROOM 1190 811 SF
CLASSROOM 1191 811 SF
CLASSROOM 1192 811 SF
CLASSROOM 1193 811 SF
CLASSROOM 1194 811 SF
CLASSROOM 1195 811 SF
CLASSROOM 1196 811 SF
CLASSROOM 1197 811 SF
CLASSROOM 1198 811 SF
CLASSROOM 1199 811 SF
CLASSROOM 1200 811 SF
CLASSROOM 1201 811 SF
CLASSROOM 1202 811 SF
CLASSROOM 1203 811 SF
CLASSROOM 1204 811 SF
CLASSROOM 1205 811 SF
CLASSROOM 1206 811 SF
CLASSROOM 1207 811 SF
CLASSROOM 1208 811 SF
CLASSROOM 1209 811 SF
CLASSROOM 1210 811 SF
CLASSROOM 1211 811 SF
CLASSROOM 1212 811 SF
CLASSROOM 1213 811 SF
CLASSROOM 1214 811 SF
CLASSROOM 1215 811 SF
CLASSROOM 1216 811 SF
CLASSROOM 1217 811 SF
CLASSROOM 1218 811 SF
CLASSROOM 1219 811 SF
CLASSROOM 1220 811 SF
CLASSROOM 1221 811 SF
CLASSROOM 1222 811 SF
CLASSROOM 1223 811 SF
CLASSROOM 1224 811 SF
CLASSROOM 1225 811 SF
CLASSROOM 1226 811 SF
CLASSROOM 1227 811 SF
CLASSROOM 1228 811 SF
CLASSROOM 1229 811 SF
CLASSROOM 1230 811 SF
CLASSROOM 1231 811 SF
CLASSROOM 1232 811 SF
CLASSROOM 1233 811 SF
CLASSROOM 1234 811 SF
CLASSROOM 1235 811 SF
CLASSROOM 1236 811 SF
CLASSROOM 1237 811 SF
CLASSROOM 1238 811 SF
CLASSROOM 1239 811 SF
CLASSROOM 1240 811 SF
CLASSROOM 1241 811 SF
CLASSROOM 1242 811 SF
CLASSROOM 1243 811 SF
CLASSROOM 1244 811 SF
CLASSROOM 1245 811 SF
CLASSROOM 1246 811 SF
CLASSROOM 1247 811 SF
CLASSROOM 1248 811 SF
CLASSROOM 1249 811 SF
CLASSROOM 1250 811 SF
CLASSROOM 1251 811 SF
CLASSROOM 1252 811 SF
CLASSROOM 1253 811 SF
CLASSROOM 1254 811 SF
CLASSROOM 1255 811 SF
CLASSROOM 1256 811 SF
CLASSROOM 1257 811 SF
CLASSROOM 1258 811 SF
CLASSROOM 1259 811 SF
CLASSROOM 1260 811 SF
CLASSROOM 1261 811 SF
CLASSROOM 1262 811 SF
CLASSROOM 1263 811 SF
CLASSROOM 1264 811 SF
CLASSROOM 1265 811 SF
CLASSROOM 1266 811 SF
CLASSROOM 1267 811 SF
CLASSROOM 1268 811 SF
CLASSROOM 1269 811 SF
CLASSROOM 1270 811 SF
CLASSROOM 1271 811 SF
CLASSROOM 1272 811 SF
CLASSROOM 1273 811 SF
CLASSROOM 1274 811 SF
CLASSROOM 1275 811 SF
CLASSROOM 1276 811 SF
CLASSROOM 1277 811 SF
CLASSROOM 1278 811 SF
CLASSROOM 1279 811 SF
CLASSROOM 1280 811 SF
CLASSROOM 1281 811 SF
CLASSROOM 1282 811 SF
CLASSROOM 1283 811 SF
CLASSROOM 1284 811 SF
CLASSROOM 1285 811 SF
CLASSROOM 1286 811 SF
CLASSROOM 1287 811 SF
CLASSROOM 1288 811 SF
CLASSROOM 1289 811 SF
CLASSROOM 1290 811 SF
CLASSROOM 1291 811 SF
CLASSROOM 1292 811 SF
CLASSROOM 1293 811 SF
CLASSROOM 1294 811 SF
CLASSROOM 1295 811 SF
CLASSROOM 1296 811 SF
CLASSROOM 1297 811 SF
CLASSROOM 1298 811 SF
CLASSROOM 1299 811 SF
CLASSROOM 1300 811 SF
CLASSROOM 1301 811 SF
CLASSROOM 1302 811 SF
CLASSROOM 1303 811 SF
CLASSROOM 1304 811 SF
CLASSROOM 1305 811 SF
CLASSROOM 1306 811 SF
CLASSROOM 1307 811 SF
CLASSROOM 1308 811 SF
CLASSROOM 1309 811 SF
CLASSROOM 1310 811 SF
CLASSROOM 1311 811 SF
CLASSROOM 1312 811 SF
CLASSROOM 1313 811 SF
CLASSROOM 1314 811 SF
CLASSROOM 1315 811 SF
CLASSROOM 1316 811 SF
CLASSROOM 1317 811 SF
CLASSROOM 1318 811 SF
CLASSROOM 1319 811 SF
CLASSROOM 1320 811 SF
CLASSROOM 1321 811 SF
CLASSROOM 1322 811 SF
CLASSROOM 1323 811 SF
CLASSROOM 1324 811 SF
CLASSROOM 1325 811 SF
CLASSROOM 1326 811 SF
CLASSROOM 1327 811 SF
CLASSROOM 1328 811 SF
CLASSROOM 1329 811 SF
CLASSROOM 1330 811 SF
CLASSROOM 1331 811 SF
CLASSROOM 1332 811 SF
CLASSROOM 1333 811 SF
CLASSROOM 1334 811 SF
CLASSROOM 1335 811 SF
CLASSROOM 1336 811 SF
CLASSROOM 1337 811 SF
CLASSROOM 1338 811 SF
CLASSROOM 1339 811 SF
CLASSROOM 1340 811 SF
CLASSROOM 1341 811 SF
CLASSROOM 1342 811 SF
CLASSROOM 1343 811 SF
CLASSROOM 1344 811 SF
CLASSROOM 1345 811 SF
CLASSROOM 1346 811 SF
CLASSROOM 1347 811 SF
CLASSROOM 1348 811 SF
CLASSROOM 1349 811 SF
CLASSROOM 1350 811 SF
CLASSROOM 1351 811 SF
CLASSROOM 1352 811 SF
CLASSROOM 1353 811 SF
CLASSROOM 1354 811 SF
CLASSROOM 1355 811 SF
CLASSROOM 1356 811 SF
CLASSROOM 1357 811 SF
CLASSROOM 1358 811 SF
CLASSROOM 1359 811 SF
CLASSROOM 1360 811 SF
CLASSROOM 1361 811 SF
CLASSROOM 1362 811 SF
CLASSROOM 1363 811 SF
CLASSROOM 1364 811 SF
CLASSROOM 1365 811 SF
CLASSROOM 1366 811 SF
CLASSROOM 1367 811 SF
CLASSROOM 1368 811 SF
CLASSROOM 1369 811 SF
CLASSROOM 1370 811 SF
CLASSROOM 1371 811 SF
CLASSROOM 1372 811 SF
CLASSROOM 1373 811 SF
CLASSROOM 1374 811 SF
CLASSROOM 1375 811 SF
CLASSROOM 1376 811 SF
CLASSROOM 1377 811 SF
CLASSROOM 1378 811 SF
CLASSROOM 1379 811 SF
CLASSROOM 1380 811 SF
CLASSROOM 1381 811 SF
CLASSROOM 1382 811 SF
CLASSROOM 1383 811 SF
CLASSROOM 1384 811 SF
CLASSROOM 1385 811 SF
CLASSROOM 1386 811 SF
CLASSROOM 1387 811 SF
CLASSROOM 1388 811 SF
CLASSROOM 1389 811 SF
CLASSROOM 1390 811 SF
CLASSROOM 1391 811 SF
CLASSROOM 1392 811 SF
CLASSROOM 1393 811 SF
CLASSROOM 1394 811 SF
CLASSROOM 1395 811 SF
CLASSROOM 1396 811 SF
CLASSROOM 1397 811 SF
CLASSROOM 1398 811 SF
CLASSROOM 1399 811 SF
CLASSROOM 1400 811 SF
CLASSROOM 1401 811 SF
CLASSROOM 1402 811 SF
CLASSROOM 1403 811 SF
CLASSROOM 1404 811 SF
CLASSROOM 1405 811 SF
CLASSROOM 1406 811 SF
CLASSROOM 1407 811 SF
CLASSROOM 1408 811 SF
CLASSROOM 1409 811 SF
CLASSROOM 1410 811 SF
CLASSROOM 1411 811 SF
CLASSROOM 1412 811 SF
CLASSROOM 1413 811 SF
CLASSROOM 1414 811 SF
CLASSROOM 1415 811 SF
CLASSROOM 1416 811 SF
CLASSROOM 1417 811 SF
CLASSROOM 1418 811 SF
CLASSROOM 1419 811 SF
CLASSROOM 1420 811 SF
CLASSROOM 1421 811 SF
CLASSROOM 1422 811 SF
CLASSROOM 1423 811 SF
CLASSROOM 1424 811 SF
CLASSROOM 1425 811 SF
CLASSROOM 1426 811 SF
CLASSROOM 1427 811 SF
CLASSROOM 1428 811 SF
CLASSROOM 1429 811 SF
CLASSROOM 1430 811 SF
CLASSROOM 1431 811 SF
CLASSROOM 1432 811 SF
CLASSROOM 1433 811 SF
CLASSROOM 1434 811 SF
CLASSROOM 1435 811 SF
CLASSROOM 1436 811 SF
CLASSROOM 1437 811 SF
CLASSROOM 1438 811 SF
CLASSROOM 1439 811 SF
CLASSROOM 1440 811 SF
CLASSROOM 1441 811 SF
CLASSROOM 1442 811 SF
CLASSROOM 1443 811 SF
CLASSROOM 1444 811 SF
CLASSROOM 1445 811 SF
CLASSROOM 1446 811 SF
CLASSROOM 1447 811 SF
CLASSROOM 1448 811 SF
CLASSROOM 1449 811 SF
CLASSROOM 1450 811 SF
CLASSROOM 1451 811 SF
CLASSROOM 1452 811 SF
CLASSROOM 1453 811 SF
CLASSROOM 1454 811 SF
CLASSROOM 1455 811 SF
CLASSROOM 1456 811 SF
CLASSROOM 1457 811 SF
CLASSROOM 1458 811 SF
CLASSROOM 1459 811 SF
CLASSROOM 1460 811 SF
CLASSROOM 1461 811 SF
CLASSROOM 1462 811 SF
CLASSROOM 1463 811 SF
CLASSROOM 1464 811 SF
CLASSROOM 1465 811 SF
CLASSROOM 1466 811 SF
CLASSROOM 1467 811 SF
CLASSROOM 1468 811 SF
CLASSROOM 1469 811 SF
CLASSROOM 1470 811 SF
CLASSROOM 1471 811 SF
CLASSROOM 1472 811 SF
CLASSROOM 1473 811 SF
CLASSROOM 1474 811 SF
CLASSROOM 1475 811 SF
CLASSROOM 1476 811 SF
CLASSROOM 1477 811 SF
CLASSROOM 1478 811 SF
CLASSROOM 1479 811 SF
CLASSROOM 1480 811 SF
CLASSROOM 1481 811 SF
CLASSROOM 1482 811 SF
CLASSROOM 1483 811 SF
CLASSROOM 1484 811 SF
CLASSROOM 1485 811 SF
CLASSROOM 1486 811 SF
CLASSROOM 1487 811 SF
CLASSROOM 1488 811 SF
CLASSROOM 1489 811 SF
CLASSROOM 1490 811 SF
CLASSROOM 1491 811 SF
CLASSROOM 1492 811 SF
CLASSROOM 1493 811 SF
CLASSROOM 1494 811 SF
CLASSROOM 1495 811 SF
CLASSROOM 1496 811 SF
CLASSROOM 1497 811 SF
CLASSROOM 1498 811 SF
CLASSROOM 1499 811 SF
CLASSROOM 1500 811 SF
CLASSROOM 1501 811 SF
CLASSROOM 1502 811 SF
CLASSROOM 1503 811 SF
CLASSROOM 1504 811 SF
CLASSROOM 1505 811 SF
CLASSROOM 1506 811 SF
CLASSROOM 1507 811 SF
CLASSROOM 1508 811 SF
CLASSROOM 1509 811 SF
CLASSROOM 1510 811 SF
CLASSROOM 1511 811 SF
CLASSROOM 1512 811 SF
CLASSROOM 1513 811 SF
CLASSROOM 1514 811 SF
CLASSROOM 1515 811 SF
CLASSROOM 1516 811 SF
CLASSROOM 1517 811 SF
CLASSROOM 1518 811 SF
CLASSROOM 1519 811 SF
CLASSROOM 1520 811 SF
CLASSROOM 1521 811 SF
CLASSROOM 1522 811 SF
CLASSROOM 1523 811 SF
CLASSROOM 1524 811 SF
CLASSROOM 1525 811 SF
CLASSROOM 1526 811 SF
CLASSROOM 1527 811 SF
CLASSROOM 1528 811 SF
CLASSROOM 1529 811 SF
CLASSROOM 1530 811 SF
CLASSROOM 1531 811 SF
CLASSROOM 1532 811 SF
CLASSROOM 1533 811 SF
CLASSROOM 1534 811 SF
CLASSROOM 1535 811 SF
CLASSROOM 1536 811 SF
CLASSROOM 1537 811 SF
CLASSROOM 1538 811 SF
CLASSROOM 1539 811 SF
CLASSROOM 1540 811 SF
CLASSROOM 1541 811 SF
CLASSROOM 1542 811 SF
CLASSROOM 1543 811 SF
CLASSROOM 1544 811 SF
CLASSROOM 1545 811 SF
CLASSROOM 1546 811 SF
CLASSROOM 1547 811 SF
CLASSROOM 1548 811 SF
CLASSROOM 1549 811 SF
CLASSROOM 1550 811 SF
CLASSROOM 1551 811 SF
CLASSROOM 1552 811 SF
CLASSROOM 1553 811 SF
CLASSROOM 1554 811 SF
CLASSROOM 1555 811 SF
CLASSROOM 1556 811 SF
CLASSROOM 1557 811 SF
CLASSROOM 1558 811 SF
CLASSROOM 1559 811 SF
CLASSROOM 1560 811 SF
CLASSROOM 1561 811 SF
CLASSROOM 1562 811 SF
CLASSROOM 1563 811 SF
CLASSROOM 1564 811 SF
CLASSROOM 1565 811 SF
CLASSROOM 1566 811 SF
CLASSROOM 1567 811 SF
CLASSROOM 1568 811 SF
CLASSROOM 1569 811 SF
CLASSROOM 1570 811 SF
CLASSROOM 1571 811 SF
CLASSROOM 1572 811 SF
CLASSROOM 1573 811 SF
CLASSROOM 1574 811 SF
CLASSROOM 1575 811 SF
CLASSROOM 1576 811 SF
CLASSROOM 1577 811 SF
CLASSROOM 1578 811 SF
CLASSROOM 1579 811 SF
CLASSROOM 1580 811 SF
CLASSROOM 1581 811 SF
CLASSROOM 1582 811 SF
CLASSROOM 1583 811 SF
CLASSROOM 1584 811 SF
CLASSROOM 1585 811 SF
CLASSROOM 1586 811 SF
CLASSROOM 1587 811 SF
CLASSROOM 1588 811 SF
CLASSROOM 1589 811 SF
CLASSROOM 1590 811 SF
CLASSROOM 1591 811 SF
CLASSROOM 1592 811 SF
CLASSROOM 1593 811 SF
CLASSROOM 1594 811 SF
CLASSROOM 1595 811 SF
CLASSROOM 1596 811 SF
CLASSROOM 1597 811 SF
CLASSROOM 1598 811 SF
CLASSROOM 1599 811 SF
CLASSROOM 1600 811 SF
CLASSROOM 1601 811 SF
CLASSROOM 1602 811 SF
CLASSROOM 1603 811 SF
CLASSROOM 1604 811 SF
CLASSROOM 1605 811 SF
CLASSROOM 1606 811 SF
CLASSROOM 1607 811 SF
CLASSROOM 1608 811 SF
CLASSROOM 1609 811 SF
CLASSROOM 1610 811 SF
CLASSROOM 1611 811 SF
CLASSROOM 1612 811 SF
CLASSROOM 1613 811 SF
CLASSROOM 1614 811 SF
CLASSROOM 1615 811 SF
CLASSROOM 1616 811 SF
CLASSROOM 1617 811 SF
CLASSROOM 1618 811 SF
CLASSROOM 1619 811 SF
CLASSROOM 1620 811 SF
CLASSROOM 1621 811 SF
CLASSROOM 1622 811 SF
CLASSROOM 1623 811 SF
CLASSROOM 1624 811 SF
CLASSROOM 1625 811 SF
CLASSROOM 1626 811 SF




1 KITCHEN PLAN
SCALE: 1/4" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

i

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT

SEAL

REGISTERED ARCHITECT
MICHAEL K. WILLIAMS
22651
STATE OF TEXAS

7/15/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

KITCHEN PLAN

i-A.301

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\i-Heritage Rose ES\i-A 301 KITCHEN PLAN.dwg Jul 23, 2025 - 1:59pm

## PLUMBING SYMBOLS LEGEND

| | | | |
|---|---|---|---|
| ---------- | SANITARY WASTE BELOW SLAB | SAN. | SANITARY |
| ———— | SANITARY WASTE ABOVE SLAB | CW | DOMESTIC COLD WATER |
| —— V —— | VENT PIPING ABOVE SLAB | HW | DOMESTIC HOT WATER |
| - - - - - - | VENT PIPING | WC | WATER CLOSET |
| —— G —— | GAS PIPING, 4–8oz | UR | URINAL |
| —— G5 —— | GAS PIPING, 5LB | LAV | LAVATORY |
| —·—·—·— | DOMESTIC COLD WATER PIPING | SK | SINK |
| —·—·—·— | DOMESTIC HOT WATER PIPING | EDF | ELECTRIC DRINKING FOUNTAIN |
| —— D —— | DRAIN/RELIEF VENT PIPING | WH | WALL HYDRANT |
| ——⋈—— | STOP VALVE | HB | HOSEBIBB |
| 2CO | DOUBLE SAN. CLEANOUT (2–WAY) | CP | HOT WATER CIRCULATOR PUMP |
| CO | SANITARY SEWER CLEANOUT | FD | FLOOR DRAIN |
| WCO | WALL CLEANOUT | FSINK | FLOOR SINK |
| EXIST. | EXISTING | | |
| (R) | REMOVE (DEMOLISH) | | |
| (D) | DEMOLISH (REMOVE) | | |
| (E) | EXISTING – NO WORK | | |

## PLUMBING FIXTURE NOTES

1. ALL FIXTURES SHALL MEET WATER CONSERVATION PERFORMANCE STANDARDS MANDATED BY SENATE BILL 587. ALL FIXTURES SHALL HAVE FLOW RESTRICTION DEVICES (DRINKING FOUNTAINS SHALL BE SELF–CLOSING) TO COMPLY WITH THESE REQUIREMENTS.
2. ALL FIXTURES SHALL HAVE CONTROLS REQUIRING OPERATING FORCE NO GREATER THAN FIVE (5) POUNDS.
3. FOR LAVATORIES AND SINKS, ALL FAUCETS SHALL BE NO–LEAD SOLID BRASS, MEETING ALL REQUIREMENTS OF ANSI/NSF 61, SECTION 9 AND CERTIFIED AS SUCH. ALSO, INSTALL SYMMONS 7–210 MIXING VALVE ON HOT WATER SUPPLY SIDE OF ALL FAUCETS UNLESS HIGH TEMPERATURE LIMIT IS PROVIDED WITH FAUCET. MAXIMUM WATER TEMPERATURE FOR ALL FAUCETS THAT DELIVER HOT OR TEPID WATER SHALL BE 110°F. ALL METERING FAUCETS SHALL HAVE A MINIMUM TEN (10) SECONDS OF WATER FLOW. AND, INSTALL TRUEBRO HANDI LAV–GUARD VANDAL–PROOF INSULATION KITS OVER P–TRAP, SUPPLIES, STOPS AND ALL SHARP EDGES FOR ALL SINKS AND LAVATORIES (TRAP WRAP FROM BRODAR OR PROWRAP FROM McGUIRE SHALL BE ACCEPTABLE).
4. ALL PLUMBING FIXTURES REFERENCED AS "ADA", "TAS" OR "HANDICAP COMPLIANT" SHALL MEET ALL REQUIREMENTS OF THE ADA AND THE TEXAS ACCESSIBILITY STANDARDS. IT SHALL BE THE PLUMBING CONTRACTORS RESPONSIBILITY TO MEET THESE REQUIREMENTS.
5. IN MANY CASES, FIXTURES WITH THE SAME PLUMBING DESIGNATION HAVE DIFFERENT INSTALLATION HEIGHTS – REFERENCE ARCHITECTURAL DRAWINGS FOR ALL INSTALLATION HEIGHTS AND HANDICAP FIXTURE DESIGNATIONS. FIXTURES DESIGNATED AS ADULT HANDICAP SHALL MEET ALL REQUIREMENTS OF THE ADA. FIXTURES DESIGNATED AS CHILD HANDICAP SHALL MEET ALL REQUIREMENTS OF THE TEXAS ACCESSIBILITY STANDARDS FOR THE APPROPRIATE CHILDREN'S AGE GROUP (REF. ARCH. DWGS. AND SPECIFICATIONS).

## PLUMBING MATERIALS

SANITARY WASTE AND VENT

BELOW SLAB/GRADE: SCHEDULE 40, DWV PVC

ABOVE SLAB: STANDARD WEIGHT, CAST IRON, NO–HUB PIPING.


DOMESTIC WATER

INTERIOR: TYPE L COPPER WITH SOLDER TYPE WROUGHT COPPER FITTINGS, MADE UP WITH LEAD–FREE SOLDER.

EXTERIOR: TYPE K COPPER WITH SWEAT FITTINGS AND LEAD–FREE SOLDER. BEYOND 5 FEET FROM BUILDING, SCHEDULE 40 PVC.

## GENERAL PLUMBING NOTES

1. SEE ARCHITECTURAL DRAWINGS AND SPECIFICATIONS FOR ADDITIONAL WORK DESCRIPTION. SEE THIS SHEET (P4.00) FOR PLUMBING SYMBOLS LEGEND.
2. COORDINATE PLUMBING SYSTEMS INSTALLATION WITH ARCHITECTURAL, STRUCTURAL, HVAC SYSTEMS, ELECTRICAL SYSTEMS, CONDUITS, ETC.... OFFSET PIPING AS REQUIRED TO PROVIDE A FUNCTIONING SYSTEM WITH ADEQUATE SPACE FOR SERVICING AND REPAIRS.
3. MAKE CONNECTIONS OF NEW PIPE SYSTEMS IN TO EXISTING PIPE SYSTEMS WITH THREADED OR SWEAT JOINTS. PROVIDE ELECTROLYSIS ISOLATING UNIONS AT CONNECTION OF DISSIMILAR MATERIALS. REFERENCE THE SPECIFICATIONS.
4. SITE SERVICES ARE SHOWN FOR REFERENCE ONLY. PLUMBING CONTRACTOR SHALL REFERENCE CIVIL DRAWINGS, INCLUDING LOCATIONS OF SERVICES, SIZES OF PIPES, FLOWLINE ELEVATIONS, ETC..
5. DO NOT INSTALL PLUMBING PIPING OVER ANY ELECTRICAL EQUIPMENT. REFERENCE ELECTRICAL DRAWINGS FOR LOCATIONS OF ELECTRICAL EQUIPMENT AND COORDINATE WITH ELECTRICAL SUBCONTRACTORS ACCORDINGLY. SEE DETAIL 2/MEP1. THIS INCLUDES FIRE SPRINKLER PIPING.
6. ALL PIPES THROUGH WALLS OR FLOORS SHALL BE SLEEVED AND SEALED PER DETAIL 5/P4.02. FIRE CAULK WHERE REQUIRED. THIS INCLUDES ALL WALLS, INTERIOR AND EXTERIOR. THIS INCLUDES FIRE SPRINKLER PIPING.
7. ALL CLEANOUTS SHALL BE CONNECTED TO SANITARY LINES USING WYES AND/OR LONG RADIUS ELLS. SANITARY TEES ARE NOT ACCEPTABLE. 2" MINIMUM SIZE. ALL WALL CLEAN OUTS IN VERTICAL RISERS, OR BANKS OF FIXTURES SHALL BE INSTALLED 4" ABOVE THE FLOOD RIM LEVEL OF THE LOWEST CONNECTED FIXTURE AND A MINIMUM OF 24" AFF.
8. ALL WASTE AND VENT PIPING BELOW SLAB SHALL BE 2" MINIMUM.
9. LOCATE PLUMBING VENTS THROUGH ROOF NOT NEARER THAN SIX (6) FEET AWAY FROM EDGE OF BUILDING AND TEN (10) FEET AWAY FROM ANY FRESH AIR INTAKES. OFFSET VENT PIPING, AS REQUIRED, IN CEILING SPACE BETWEEN CEILING AND ROOF TO MEET THESE REQUIREMENTS. SEE DETAIL 3/P4.02.
10. ALL DOMESTIC WATER PIPING (CW, HW AND HWR) SHALL BE INSULATED PER THE WRITTEN SPECIFICATIONS.
11. TOP OF FLOOR DRAINS IN MECHANICAL, AHU AND BOILER ROOMS SHALL BE SET 1–1/2" BELOW FINISHED FLOOR SURFACE. CONCRETE FLOOR SHALL BE SLOPED TO DRAIN, REFERENCE ARCHITECTURAL DRAWINGS. IN ALL OTHER LOCATIONS, FLOOR DRAINS SHALL BE SET FLUSH WITH FINISHED FLOOR, TAKING INTO ACCOUNT ANY FLOOR SLOPE OR FLOOR FINISH (TILE, TERRAZZO, ETC.) AS SHOWN ON ARCHITECTURAL DRAWINGS.
12. PROVIDE AN ISOLATING VALVE AT EACH WATER TAP OFF HOT AND COLD WATER MAINS TO ALLOW FOR SERVICING. VALVE SHALL BE BALL VALVE IF PIPE SIZE IS 2" OR LESS AND GATE VALVE OR BUTTERFLY VALVE IF LARGER THAN 2". SEE WRITTEN SPECIFICATIONS. VALVES SHALL BE EASILY ACCESSIBLE: PROVIDE 18" X 18", FIRE–RATED, STAINLESS STEEL ACCESS PANELS WITH HINGED, CYLINDER LOCK DOORS WHERE VALVES ARE INSTALLED ABOVE INACCESSIBLE CEILINGS OR IN WALL CHASES (MIFAB MODEL MPFR–SS–C). BALL VALVES AND BUTTERFLY VALVES INSTALLED ABOVE CEILINGS SHALL BE INSTALLED SUCH THAT HANDLE IS ON BOTTOM OF PIPE. ISOLATING WATER VALVES ABOVE CEILINGS SHALL BE INSTALLED NO MORE THAN 24" ABOVE CEILING. VALVES ABOVE INACCESSIBLE CEILINGS SHALL BE INSTALLED WITHIN REASONABLE REACH OF CEILING MOUNTED ACCESS PANEL.
13. WATER HAMMER ARRESTERS SHALL BE INSTALLED IN ADDITION TO AIR CHAMBERS PER THE RISER DIAGRAMS. SEE SPECIFICATIONS.
14. MECHANICALLY CLEAN ALL WASTE LINES WITH ROTARY MACHINE TO PROVE FREE FLOWING, SEE SPECIFICATIONS.
15. PROVIDE VENTED SLEEVE (2 PIPE SIZES LARGER THAN GAS PIPE UNLESS NOTED OTHERWISE) FOR ALL GAS PIPING IN GROUND BELOW PAVING OR SIDEWALKS AND INSIDE BUILDING IN WALLS AND IN UNVENTILATED CEILING SPACES, SEE SPECIFICATIONS.
16. GAS PIPING SHALL BE 1/2" MINIMUM. TAP GAS PIPING ON TOP OR SIDES ONLY. DO NOT INSTALL VALVES IN CEILING PLENUM OR IN ANY INACCESSIBLE LOCATION. ALL GAS VALVES SHALL BE EASILY ACCESSIBLE. REFER TO DETAIL 9/P4.01 FOR TYPICAL GAS CONNECTION INSTALLATION. REFER TO DETAIL 8/P4.02 FOR TYPICAL PRV INSTALLATION.
17. CENTER WALL HYDRANTS IN BRICK PATTERN OF EXTERIOR WALLS, REFERENCE THE ARCHITECTURAL DRAWINGS AND SPECIFICATIONS.
18. ALL REFRIGERATORS WITH ICE MAKERS, COMMERCIAL TYPE COFFEE MAKERS, ICE MAKERS, COFFEE VENDING MACHINES AND OTHER ITEMS PROVIDED BY OTHERS THAT REQUIRE A WATER CONNECTION SHALL HAVE A CW VALVE BOX, "VBOX", INSTALLED TO ALLOW EASY ACCESS AND REMOVAL OF MACHINE. ALSO, INSTALL IN–LINE FILTER IN WATER CONNECTION.
19. REFER TO CIVIL DRAWINGS FOR SITE SANITARY, SITE STORM SEWER, FIRE SERVICE AND DOMESTIC WATER SERVICE. PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR ALL PIPING INSIDE BUILDING TO OUTSIDE LOCATIONS SHOWN ON PLUMBING DRAWINGS. PLUMBING CONTRACTOR SHALL INCLUDE COST OF FINAL TIE–INS TO SITE SERVICES.
20. PER THE DRAWINGS, ALL DRAINS (FLOOR DRAINS, FLOOR SINKS, HUB DRAINS, KITCHEN DRAINS, SHOWER DRAINS, ETC.) SHALL BE VENTED AND TRAP PRIMED – NO EXCEPTIONS. TRAP PRIMING SHALL BE ACCOMPLISHED USING WATER CLOSET FLUSH VALVE TRAP PRIMING DEVICES OR PROSET SYSTEMS TRAP GUARD SEWER GAS EMISSION PROTECTION, AS SHOWN ON DRAWINGS. REFERENCE PLUMBING FLOOR PLANS AND RISER DIAGRAMS.
21. ALL PIPING LOCATED ON ROOF (GAS PIPING) SHALL BE INSTALLED ON ROOF PIPE SUPPORTS PER DETAIL 10/P4.02, 6–FOOT ON CENTER. INSTALL ROOF PIPE JACK PER DETAIL 9/P4.02 FOR ALL PIPING THROUGH ROOF.
22. COORDINATE LOCATIONS OF ALL ROOF DRAINS AND OVERFLOW ROOF DRAINS WITH ARCHITECTURAL DRAWINGS.
23. FOR COMBINATION WASTE AND VENT SYSTEMS (WHERE APPLICABLE ON DRAWINGS), DRAIN P–TRAPS SHALL BE SIZE OF PIPE SHOWN ON DRAWINGS (I.E. TWO PIPE SIZES LARGER THAN DRAIN SIZE). FOR EXAMPLE, A 4" FLOOR DRAIN SHALL HAVE A 8" P–TRAP.
24. FOR ALL PLUMBING FIXTURES, IF COPPER PIPING IS STUBBED THROUGH WALL FOR DRAIN CONNECTION, INSTALL MARVEL FITTING AT DRAIN CONNECTION FOR EASE OF SERVICING AND REPAIRS. COPPER DRAIN PIPING WILL ONLY BE ALLOWED FOR DIRECT/STRAIGHT STUB–OUT OF FIXTURE DRAIN PIPING THROUGH WALL.
25. DO NOT INSTALL ANY PIPING BENEATH CVT OR VAV BOXES. THIS INCLUDES FIRE SPRINKLER PIPING.
26. WHERE UNDERGROUND VENT PIPE SIZE IS NOT NOTATED, VENT SHALL BE 2" DIAMETER.
27. WHERE UNDERGROUND SANITARY PIPE SIZE IS NOT NOTATED, REFER TO THE RISER DIAGRAMS FOR SIZE. NOT BELOW GRADE SANITARY PIPE SHALL BE SMALLER THAN 2". NO SANITARY LINE OR P–TRAP FOR A DRAIN/FIXTURE SHALL BE SMALLER THAN THE FIXTURE CONNECTION SIZE SHOWN ON THE DRAIN/FIXTURE SCHEDULE.
28. WHERE ABOVE GROUND VENT PIPE SIZE IS NOT NOTATED, REFER TO THE RISER DIAGRAMS FOR VENT SIZE.
29. WHERE CW/HW PIPING SIZE TO THE FIXTURE IS NOT SHOWN ON THE FLOOR PLAN, REFER TO THE RISER DIAGRAMS FOR CW/HW PIPE SIZE. NO PIPING TO FIXTURE SHALL BE SMALLER THAN THE FIXTURE CONNECTION SIZE SHOWN ON THE FIXTURE SCHEDULE.
30. TO INSTALL NEW PLUMBING SYSTEMS BELOW EXISTING CONCRETE SLABS, FIRST PLUMBING CONTRACTOR SHALL LAY OUT CUT. THEN, DEMOLITION CONTRACTOR SHALL SAW CUT SLAB TO CONTROL CRACKING AND REMOVE ALL CONCRETE. PLUMBING CONTRACTOR SHALL THEN EXCAVATE FILL TO PROPER SLOPE, INSTALL NEW PIPING SYSTEMS AS REQUIRED, THEN BACKFILL AND COMPACT TO PROPER DENSITY. THE CONCRETE CONTRACTOR SHALL THEN INSTALL NEW SIX (6) MIL POLYETHYLENE VAPOR BARRIER AND SEAL, INSTALL NEW REINFORCING STEEL AND WELD ON TO EXISTING, THEN RE–POUR CONCRETE TO NEW LEVEL. DO NOT CUT THROUGH GRADE BEAMS WITHOUT APPROVAL FROM THE STRUCTURAL ENGINEER. SEE ARCHITECTURAL AND STRUCTURAL DRAWINGS AND SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.
31. ALL ABANDONED FIXTURES, DRAINS AND PIPING (INCLUDING PIPING ABANDONED IN THE PAST) IN AREAS WHERE WORK IS BEING DONE SHALL BE COMPLETELY REMOVED FROM BUILDING (INCLUDING PIPING BELOW SLAB/GRADE – UNLESS SHOWN OTHERWISE ON DRAWINGS). EXISTING WATER PIPING SHALL BE CAPPED AT EXISTING WATER MAIN TAPS AND ALL ABANDONED PIPING REMOVED. ABANDONED VENT PIPING SHALL BE COMPLETELY REMOVED, INCLUDING EXISTING VTR's NOT RE–USED. PATCH AS REQUIRED. ONLY ACTIVE PIPING, FIXTURES AND DRAINS SHALL REMAIN IN BUILDING WHERE WORK IS BEING DONE.




## WATER SOFTENER SCHEDULE

| | |
|---|---|
| CONSTANT FLOW RATE PER TANK: | 39 GPM @ 15 PSI |
| PEAK FLOW RATE PER TANK: | 51 GPM @ 25 PSI |
| EXCHANGE CAPACITY PER TANK: | 60,000 GRAINS |
| SOFTENER TANK SIZE (1 TANK): | 14" DIA. X 65" TALL |
| BRINE TANK SIZE: | 18" DIA. X 40" TALL |
| BASIS OF DESIGN: | WATERTECH WTS–F90 2 |
| REFERENCE SPECIFICATIONS FOR ACCEPTABLE MANUFACTUERS | |

## WATER FILTER SCHEDULE

| | |
|---|---|
| FILTER HOUSING CONNECTION SIZE | 2" INLET/OUTLET |
| HOUSING CONSTRUCTION | GLASS REINFORCED PP |
| OVERALL DIMENSIONS | 12" DIA. X 40" TALL |
| FILTER TYPE | PLEATED, 20 MICRON |
| MAXIMUM FILTER FLOW RATE | 150 GPM |
| BASIS OF DESIGN: | WATTS BBH–150 WITH BBC–150–P20 CARTRIGE |
| REFERENCE SPECIFICATIONS FOR ACCEPTABLE MANUFACTUERS | |

## 2 WATER SOFTENING SYSTEM SCHEMATIC

NO SCALE

SEE WRITTEN SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.

PLUMBING KEYED NOTES:

1 NEW SEDIMENT FILTER WITH ISOLATION VALVES ON INLET AND OUTLET AND FULL LINE SIZE BYPASS VALVE.


2 NEW WATER SOFTENER MINERAL TANK, IN PLACE OF EXISTING ON EXISTING CONCRETE PAD.

3 NEW WATER SOFTENER BRINE TANK WITH CONTROLLER IN PLACE OF EXISTING ON EXISTING CONCRETE PAD. EXTEND NEW 2" CW TO INLET/OUTLET CONNECTIONS WITH ISOLATION VALVES AND FULL LINE SIZE BY PASS VALVE.

4 NEW 2" CW, REROUTED FROM EXISTING. DEMOLISH ALL ABANDONED EXISTING PIPING.

5 NEW 2" CW, REROUTED FROM EXISTING AND TIED BACK TO CW FEED TO EXISTING GAS WATER HEATER.

6 EXISTING 2" HW FEED TO KITCHEN, SHOW FOR REFERENCE ONLY.




## 1 PLUMBING RENOVATION FLOOR PLAN

SCALE: 1/4" = 1'– 0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL

STATE OF TEXAS
TYLER W. HERRING
106052
LICENSED PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

PLUMBING FLOOR PLAN

i-P1.01


STANTON ENGINEERING GROUP
INFO@STANTON–ENG.COM (713) 300–6080


TEXAS ENG. FIRM REG. NO. F–018537 © 2025 ALL RIGHTS RESERVED


12999 W. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77065

# FBISD BP013 KITCHEN RENOVATIONS ES

## HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DR, SUGAR LAND, TX 77478

FORT BEND INDEPENDENT SCHOOL DISTRICT 2023 BOND

## FORT BEND INDEPENDENT SCHOOL DISTRICT

### ADMINISTRATION

| | |
|---|---|
| DR. MARCELL SMITH | SUPERINTENDENT OF FBISD |
| DR. ANDRIA SCHUR, Ed.D. | CHIEF OF SCHOOLS |

### BOARD OF TRUSTEES

| | |
|---|---|
| KRISTIN K. TASSIN | PRESIDENT |
| RICK GARCIA | VICE PRESIDENT |
| DAVID HAMILTON | SECRETARY |
| ANGIE HANAN | BOARD MEMBER |
| ADAM SCHOOF | BOARD MEMBER |
| DR. SHIRLEY ROSE-GILLIAM | BOARD MEMBER |
| SONYA JONES | BOARD MEMBER |

### PROJECT DESIGN TEAM


**PROGRAM MANAGEMENT**
FBISD 2023 Bond Team
2323 Texas Parkway
Missouri City, TX 77489
Phone Number: 281-327-5481

**ARCHITECT**
MWA Architects
11767 Katy Freeway, Suite 430
Houston, Texas 77079
Phone Number: 713-782-8188

**FOOD SERVICE**
Food Design Professionals
26215 Oak Ridge Drive
The Woodlands, Texas 77380
Phone Number: 281-350-2323

**MEP ENGINEERS**
Stanton Engineering Group
1300 W. Sam Houston Pkwy South, Suite 121
Houston, Texas 77042
Phone Number: 713-300-9292

**STRUCTURAL ENGINEER**
Stanley Spurling & Hamilton
3301 Edloe Street, Suite 200
Houston, Texas 77027
Phone Number: 713-776-9433


| Sheet List Table | |
|---|---|
| Sheet Number | Sheet Title |
| School: j Highlands ES | |
| j-A.000 | COVER AND INDEX |
| j-A00-01 | GENERAL NOTES AND ABBREVIATIONS |
| j-D.101 | DEMO PLAN |
| j-D.101-2 | DEMO PLAN PHOTOS |
| j-D.101-3 | DEMO PLAN PHOTOS |
| j-ED.100 | ELECTRICAL DEMO AND TEMPORARY PLANS |
| j-PD.101 | PLUMBING DEMOLITION FLOOR PLAN |
| p-TD201 | TECHNOLOGY DEMOLITION FLOOR PLAN |
| j-A.101 | SITE PLAN |
| j-A.200 | SLAB DIMENSION CONTROL PLAN |
| j-A.201 | OVERALL FLOOR PLAN |
| j-A.301 | KITCHEN PLAN |
| j-A.302 | TEMPORARY KITCHEN LAYOUT |
| j-A.401 | REFLECTED CEILING PLAN |
| j-A.501 | FINISH FLOOR PLAN |
| j-A.502 | PARTITION SCHEDULE |
| j-C1.0 | GRADING AND SITE PLAN |
| j-QF1 | FS GENERAL COORDINATION NOTES |
| j-QF1.0 | FS EQUIPMENT PLAN |
| j-QF1.1 | FS FACILITY MODEL |
| j-QF1.2 | FS EQUIPMENT MODEL |
| j-QF1.3 | FS SPECIAL CONDITIONS & MECHANICAL PLAN |
| j-QF1.4 | FS PLUMBING PLAN |
| j-QF1.5 | FS ELECTRICAL PLAN |
| j-QF1.6 | FS CONDENSING UNITS |
| j-QF2.0 | FS TEMPORARY SERVING |
| j-M1.01 | MECHANICAL PLANS |
| M2.01 | LEVEL 1 KITCHEN MECHANICAL PLANS |
| E.000 | ELECTRICAL AND FIRE ALARM SCHEDULES |
| E.001 | ELECTRICAL AND FIRE ALARM NOTES |
| E.010 | ELECTRICAL DEVICE DETAILS |
| E.011 | ELECTRICAL DETAILS |
| E.012 | ELECTRICAL DETAILS |
| E.013 | ELECTRICAL KITCHEN DETAILS |
| E.060 | LIGHTING SCHEDULES |
| j-E100 | LIGHTING FLOOR PLAN |
| j-E200 | ELECTRICAL PLANS |
| j-E300 | FIRE ALARM FLOOR PLANS |
| j-E 400 | ELECTRICAL SCHEMATIC |
| j-P0.01 | PLUMBING NOTES AND SCHEDULES |
| j-P0.02 | PLUMBING SCHEDULES AND DETAILS |
| j-P1.01 | PLUMBING FLOOR PLAN |
| J-P1.02 | PLUMBING TEMPORARY KITCHEN PLAN |
| j-T000 | TECHNOLOGY SYMBOLS & LEGEND |
| j-T200 | TECHNOLOGY COMPOSITE FLOOR |
| j-T201 | TECHNOLOGY NEW_RENOVATION KITCHEN PLan |
| j-T202 | TECHNOLOGY TEMPORARY KITCHEN PLAN |
| j-T300 | TECHNOLOGY ENLARGED VIEWS |
| j-T400 | TECHNOLOGY TYPICAL DETAILS |
| j-T401 | TECHNOLOGY TYPICAL DETAILS |
| j-T500 | TECHNOLOGY TYPICAL LABELING SCHEME |
| j-TN-000 | TECHNOLOGY - INDEX SHEET |
| j-TN-001 | TECHNOLOGY - ELEVATIONS |
| j-TN-100 | TECHNOLOGY - OVERALL |
| j-TN-101 | TECHNOLOGY - KITCHEN |
| j-TN-500 | TECHNOLOGY - DETAILS |
| j-TN-600 | TECHNOLOGY - SECURITY DETAILS |
| J-TN-700 | TECHNOLOGY - AV DETAILS |

REGISTERED ARCHITECT MIKE MAGUIRE 22651 STATE OF TEXAS

18 July 2025

ISSUED FOR PERMIT AND BIDDING - JULY 18, 2025

j

PART 1 - GENERAL

1.1 GENERAL DEMOLITION NOTES

A. VERIFY EXISTING SITE AND BUILDING CONDITIONS IN FIELD PRIOR TO BIDDING. NOTIFY ARCHITECT OF ANY DISCREPANCIES PRIOR TO BIDDING.

B. CONTRACTOR SHALL COORDINATE WITH OWNER THE SALVAGE OF ITEMS, FURNITURE AND EQUIPMENT INDICATED TO BE REMOVED.

C. CLAIMS FOR ADDITIONAL COST OR TIME DUE TO EXISTING CONDITIONS THAT COULD HAVE BEEN REASONABLY ANTICIPATED DURING A SITE VISIT BY THE CONTRACTOR PRIOR TO BIDDING WILL NOT BE APPROVED.

D. PROTECT EXISTING FINISHES SHOWN TO REMAIN DURING CONSTRUCTION TO PREVENT DAMAGE. REPAIR OR REPLACE DAMAGED MATERIALS AND FINISHES TO MATCH EXISTING AT NO ADDITIONAL COST TO FORT BEND ISD (OWNER).

E. EXISTING AREAS REQUIRING MINOR DEMOLITION OR REPAIR FOR EXECUTION OF WORK SHALL BE REPAIRED TO MATCH EXISTING ADJACENT MATERIALS, UNLESS NOTED OTHERWISE.

F. DO NOT DAMAGE CASEWORK AND EQUIPMENT NOT DESIGNATED TO BE REMOVED OR RELOCATED.EXISTING CASEWORK SHALL REMAIN THE PROPERTY OF THE OWNER.

G. CONTRACTOR TO VERIFY LOCATION OF ELEC. SWITCHES, OUTLETS, GRILLES, CLEAN-OUTS, COVER PLATES, ACCESS DOORS, AND OTHER EQUIPMENT AND DEVICES THAT MAY CONFLICT WITH THE RENOVATION AND NEW CONSTRUCTION OF WALLS, FLOORS, AND CEILINGS PRIOR TO COMMENCEMENT OF WORK. CONTRACTOR SHALL LIKEWISE CONFIRM THAT ELECTRICAL CONDUIT ROUTING SHALL BE CONCEALED WITHIN WALLS. NOTIFY ARCHITECT IF WALL THICKNESS WILL NOT ALLOW FOR CONCEALMENT.

H. REMOVE ANY EXISTING CORNER GUARDS IN THE KITCHEN AREA.

I. PRIOR TO EXECUTION OF DEMOLITION WORK, SCHEDULE A WALK-THROUGH WITH OWNER AND ARCHITECT TO CONFIRM SCOPE OF WORK AND TO REVIEW EXISTING CONDITIONS.

J. EXISTING FLOOR FINISHES AND ACOUSTIC CEILING TILE TO BE REMOVED THROUGHOUT.

K. REFER TO MEP DRAWINGS FOR DEMOLITION AND ALTERATION OF UTILITIES.

L. AT ALL EXISTING WALLS REQUIRING DEMOLITION TO INSTALL NEW PIPING BEHIND SINKS, CUT AND PATCH WALLS AS REQUIRED TO MATCH ADJACENT SURFACE.

M. CLEAN AND PREPARE SUBFLOOR FOR INSTALLATION OF NEW FLOOR FINISH.

N. DEMOLITION ACTIVITIES SHALL BE PERFORMED AS TO PRODUCE MINIMAL DISTURBANCE TO EXISTING FACILITY OCCUPANTS. MINIMIZE EXCESSIVE AND PROLONGED NOISE LEVELS AND DUST.

O. ASBESTOS-CONTAINING MATERIALS. REFER TO SPECIFICATION 02 26 23 FOR ASBESTOS INFORMATION APPLICABLE TO KITCHEN AREAS. FORT BEND ISD HAS RETAINED A SEPARATE ENVIRONMENTAL CONSULTANT FOR THE REMOVAL OF ASBESTOS. GC TO COORDINATE WITH ENVIRONMENTAL CONSULTANT TO CARRY OUT ASBESTOS ABATEMENT FOR ALL AFFECTED KITCHEN AREAS.

1.2 FLOOR PLAN GENERAL NOTES

A. FIELD VERIFY EXISTING CONDITIONS PRIOR TO GENERATING SHOP DRAWINGS AND FABRICATION OF EQUIPMENT.

B. FLOOR FINISH CHANGES SHALL OCCUR AT THE CENTERLINE OF DOORS UNLESS NOTED OTHERWISE. FLOOR FINISH CHANGES SHALL HAVE THRESHOLDS OR REDUCERS STRIPS.

C. DOORS THAT ARE TO BE REPLACED AND INSTALLED IN EXISTING FRAMES SHALL BE MACHINED FOR HARDWARE DIMENSIONS AT EXISTING FRAMES, CONTRACTOR SHALL FIELD VERIFY FRAME CONDITIONS AND DIMENSIONS.

D. CONTRACTOR TO PROVIDE SHEET METAL REINFORCING STRAP AS REQUIRED FOR MOUNTING OF ALL GRAB BARS, CABINETS, MIRRORS, SHELVING, ETC.

E. SAW CUT AND REMOVE EXISTING SLAB AND FLOOR FINISHES AS REQUIRED TO INSTALL NEW PLUMBING LINES, FLOOR DRAINS, PLUMBING FIXTURES, OR ELECTRICAL ITEMS. SPLICE NEW REINFORCING BARS DOWELED INTO EXISTING CONCRETE, AND PROVIDE NEW VAPOR RETARDER AND WATERSTOPS, AND PATCH W/ 3000 PSI CONCRETE AFTER INSTALLATION OF UTILITIES AND FIXTURES. PREPARE CONCRETE TO RECEIVE NEW FINISH.

F. COORDINATE HOUSEKEEPING PAD DIMENSIONS AND LOCATIONS WITH EQUIPMENT TO BE INSTALLED. HOUSEKEEPING PADS SHALL BE A MIN. OF 4" THICK REINF. W/ #3 BARS AT 15" O.C. BOTH WAYS. PROVIDE 1" BY 45-DEGREE CHAMFERED EDGES.

1.3 COMPLETE PERFORMANCE

L. THE CONTRACTOR SHALL FURNISH AND INSTALL ALL ITEMS SPECIFIED HEREIN AND AS INDICATED ON THE DRAWINGS. THE CONTRACTOR SHALL ALSO FURNISH AND INSTALL ALL ITEMS NECESSARY TO MAKE THE SYSTEMS FUNCTION WHICH MAY BE REASONABLY IMPLIED AS ESSENTIAL, WHETHER MENTIONED IN THE CONTRACT DOCUMENTS OR NOT.

M. WORK SHALL BE EXECUTED IN STRICT ACCORDANCE WITH THE BEST PRACTICE OF THE TRADES IN A THOROUGH, SUBSTANTIAL AND WORKMANLIKE MANNER BY COMPETENT WORKMEN.

1.4 SITE FAMILIARIZATION

A. GENERAL: BECOME FAMILIAR WITH THE DRAWINGS AND SPECIFICATIONS, EXAMINE THE PREMISES, AND UNDERSTAND THE CONDITIONS UNDER WHICH THE CONTRACT SHALL BE PERFORMED, PRIOR TO SUBMITTING A BID.

B. SITE: BE INFORMED OF THE SITE CONDITIONS, VERIFY LOCATIONS OF NEW AND EXISTING EQUIPMENT, AND DETERMINE EXACT REQUIREMENTS FOR CONNECTIONS.

C. COORDINATION: TENDER OF A PROPOSAL FOR THIS PROJECT INFERS THAT THE CONTRACTOR HAS VISITED THE SITE AND HAS BECOME FAMILIAR WITH THE DRAWINGS, SPECIFICATIONS, AND SITE CONDITIONS AND HAS INCLUDED IN HIS PROPOSAL ALL WORK NECESSARY TO PROPERLY INSTALL COMPLETE AND FUNCTIONING SYSTEMS ON THE PROJECT. FAILURE TO COMPLY WITH THIS REQUIREMENT SHALL NOT BE CONSIDERED JUSTIFICATION FOR THE OMISSION OR FAULTY INSTALLATION OF ANY WORK COVERED BY THE CONTRACT DOCUMENTS.

1.5 CODES AND STANDARDS

A. GENERAL: ALL WORK SHALL COMPLY WITH THE MOST RECENTLY REVISED VERSIONS OF ALL APPLICABLE LAWS, RULES, REGULATIONS AND ORDINANCES OF ALL FEDERAL, STATE AND LOCAL AUTHORITIES AND APPLICABLE UTILITIES. NONE OF THE TERMS OR PROVISIONS OF THIS SPECIFICATION SHALL BE CONSTRUED AS WAIVING ANY PART OF THE LAWS, RULES, REGULATIONS OR REQUIREMENTS OF THESE AUTHORITIES.

B. CONFLICT: IN THE EVENT OF CONFLICT BETWEEN THE CONTRACT DOCUMENTS AND THE LOCAL ENFORCING AUTHORITY, THE LATTER SHALL RULE. ANY MODIFICATIONS RESULTING THEREFROM SHALL BE MADE WITHOUT ANY ADDITIONAL COST TO THE OWNER OR ARCHITECT. THIS CONTRACTOR SHALL REPORT ANY SUCH MODIFICATIONS TO THE ARCHITECT AND SECURE HIS APPROVAL PRIOR TO PROCEEDING WITH THE WORK.

C. PRECEDENCE: WHERE CONTRACT DOCUMENT REQUIREMENTS EXCEED THE REQUIREMENTS OF THE CODES AND STANDARDS, THE CONTRACT DOCUMENTS SHALL TAKE PRECEDENCE PROVIDED THEY ARE NOT IN CONFLICT WITH THOSE CODES AND STANDARDS.

D. APPROVAL LABELS: ALL ITEMS OF EQUIPMENT AND ALL MATERIALS FOR WHICH APPROVED STANDARDS HAVE BEEN ESTABLISHED BY UNDERWRITERS' LABORATORIES. INC. (UL), FACTORY MUTUAL (FM), CERTIFIED BALLAST MANUFACTURER (CBM), ELECTRICAL TESTING LABORATORY (ETL), NATIONAL MANUFACTURERS ASSOCIATION (NEMA), AMERICAN STANDARD CODES, ASME, AGA, AMCA, ASA, ANSI, ASHRAE, AND ARI SHALL BE SO APPROVED AND SHALL BEAR APPROVAL LABELS ATTESTING TO SAME.

1.6 DRAWINGS AND SPECIFICATIONS

A. DRAWINGS: THE SET OF ORIGINAL DRAWINGS HAS BEEN MODIFIED AND INDICATE APPROXIMATE EXISTING LOCATIONS OF THE FLOOR FINISH ITEMS. ALL ITEMS ARE SHOWN APPROXIMATELY TO SCALE. FIELD VERIFY CONDITIONS.

B. SPECIFICATIONS: THE SPECIFICATIONS ARE INTENDED TO SUPPLEMENT THE DRAWINGS AND IT IS NOT IN THE SCOPE OF THE SPECIFICATIONS TO MENTION ANY PART OF THE WORK THAT THE DRAWINGS ARE COMPETENT TO FULLY EXPLAIN. CONVERSELY, ANY PART OF THE WORK THAT THE SPECIFICATIONS ARE COMPETENT TO FULLY EXPLAIN MAY NOT BE MENTIONED ON THE DRAWINGS. DRAWINGS AND SPECIFICATIONS ARE COMPLIMENTARY/SUPPLEMENTARY DOCUMENTS TO EACH OTHER.

C. DISAGREEMENT: DISAGREEMENT BETWEEN THE DRAWINGS AND SPECIFICATIONS OR WITHIN THE DRAWINGS OR SPECIFICATIONS SHALL BE ESTIMATED AND/OR BID USING THE BETTER QUALITY OR GREATER QUANTITY OF MATERIAL OR INSTALLATION, AND A CLARIFICATION REQUEST FOR INFORMATION SHALL BE MADE TO THE ARCHITECT IN A TIMELY MANNER AFTER THE PROJECT IS UNDER CONTRACT.

1.7 DISCREPANCIES

A. CLARIFICATION: CLARIFICATION OF SIGNIFICANT COST MATTERS SHALL BE OBTAINED BEFORE SUBMITTING A PROPOSAL FOR THE WORK AS TO DISCREPANCIES OR OMISSIONS FROM THE CONTRACT DOCUMENTS OR QUESTIONS AS TO THE INTENT THEREOF.

B. INTERPRETATIONS: SHOULD ANY DOUBT OR QUESTION ARISE RESPECTING THE TRUE MEANING OF DRAWINGS OR SPECIFICATIONS, REFERENCE SHALL BE MADE TO THE ARCHITECT, WHOSE WRITTEN DECISION SHALL BE FINAL AND CONCLUSIVE. NO ALLEGED STATEMENT BY THE ARCHITECT WILL BE ACCEPTED AS AN EXCUSE FOR NON-COMPLIANCE OR INFERIOR WORK.

C. CONTRACTOR AGREEMENT: CONSIDERATION WILL NOT BE GRANTED FOR MISUNDERSTANDING OF THE AMOUNT OF WORK TO BE PERFORMED. TENDER OF A PROPOSAL CONVEYS FULL CONTRACTOR AGREEMENT OF THE ITEMS AND CONDITIONS SPECIFIED, SHOWN, SCHEDULED, OR REQUIRED BY THE NATURE OF THE PROJECT, AND ALL COSTS ARE INCLUDED IN THE PROPOSAL.

1.8 REQUESTS FOR INFORMATION (RFI)

A. GENERAL: SUBMIT ALL CONTRACTOR REQUESTS FOR INFORMATION (RFI) IN WRITING TO THE ARCHITECT FOR RESPONSE. SUBMIT RFI ON A STANDARD FORM THAT HAS A SPACE FOR THE REQUESTED INFORMATION AND THE ARCHITECT'S RESPONSE.

B. SOLUTION PROPOSAL: IN GENERAL, THE CONTRACTOR SHALL PROPOSE SOLUTIONS TO IDENTIFY PROBLEMS FOR REVIEW AND APPROVAL OF THE ARCHITECT. THE RFI SHALL INCLUDE HAND SKETCHES, MARKED DRAWING PRINTS, EQUIPMENT CUTSHEETS, DRAWING AND SPECIFICATION REFERENCES, AND ANY OTHER BACK-UP INFORMATION, ETC., AS REQUIRED TO SUFFICIENTLY EXPLAIN THE PROBLEM AND PROPOSED SOLUTION.

1.9 QUALITY ASSURANCE

A. GENERAL: MATERIALS AND EQUIPMENT SHALL BE NEW, OF BEST GRADE AND QUALITY, AND STANDARD PRODUCTS OF REPUTABLE MANUFACTURERS REGULARLY ENGAGED IN THE PRODUCTION OF SUCH MATERIALS AND EQUIPMENT.

B. WORKMANSHIP: WORK SHALL BE EXECUTED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE BEST PRACTICE OF THE TRADES IN A THOROUGH, SUBSTANTIAL, WORKMANLIKE MANNER BY COMPETENT WORKMEN, PRESENTING A NEAT APPEARANCE WHEN COMPLETED.

C. JUDGMENT: IN ALL CASES, THE ARCHITECT SHALL BE THE SOLE JUDGE OF THE QUALITY AND EQUIVALENCE OF MANUFACTURERS, PRODUCTS, MATERIALS, AND METHODS.

D. MANUFACTURERS/PRODUCTS/MATERIALS/METHODS: MANUFACTURERS, PRODUCTS, MATERIALS, AND METHODS DESCRIBED IN THE VARIOUS SECTIONS OF THE SPECIFICATIONS AND INDICATED ON THE DRAWINGS ARE INTENDED TO ESTABLISH A STANDARD OF QUALITY ONLY. IT IS NOT THE INTENTION OF THE ARCHITECT TO DISCRIMINATE AGAINST ANY MANUFACTURER, PRODUCT, MATERIAL, OR METHOD THAT IS EQUAL TO THE STANDARDS AS INDICATED AND/OR SPECIFIED, NOR IS IT INTENDED TO PRECLUDE OPEN, COMPETITIVE BIDDING. THE FACT THAT A SPECIFIC MANUFACTURER IS LISTED AS AN ACCEPTABLE MANUFACTURER SHALL NOT BE INTERPRETED TO MEAN THAT THE MANUFACTURER'S STANDARD PRODUCT WILL MEET THE REQUIREMENTS OF THE PROJECT DESIGN, SPECIFICATIONS, AND SPACE CONSTRAINTS.

1. WHEREVER A DEFINITE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS SPECIFIED AND THERE IS NOT A STATEMENT THAT ANOTHER MANUFACTURER, PRODUCT, MATERIAL, OR METHOD WILL BE ACCEPTABLE, IT IS THE INTENTION OF THE ARCHITECT THAT THE SPECIFIED MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS THE ONLY ONE THAT SHALL BE USED WITHOUT PRIOR APPROVAL.
2. WHEREVER A DEFINITE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS SPECIFIED AS "NO SUBSTITUTE", IT IS THE INTENTION OF THE ARCHITECT THAT THE LISTED ITEM IS THE ONLY ONE ACCEPTABLE.

E. COORDINATION: WHERE EQUIPMENT IS USED ON THE PROJECT, IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR OR SUBCONTRACTOR INVOLVED TO VERIFY THAT THE EQUIPMENT WILL FIT IN THE SPACE AVAILABLE, INCLUDING ALL REQUIRED CODE AND MAINTENANCE CLEARANCES, AND TO COORDINATE ALL EQUIPMENT REQUIREMENTS AND PROVISIONS WITH THE SYSTEM DESIGN, ALL AFFECTED DIVISIONS, AND ALL OTHER CONTRACTORS. WHERE THE USE OF ALTERNATE OR SUBSTITUTE MATERIALS AFFECTS THE COST OF PROVISIONS MADE BY OTHER CONTRACTORS, THE CONTRACTOR PROVIDING THE ALTERNATE OR SUBSTITUTE SHALL BE RESPONSIBLE FOR THE OTHER CONTRACTOR'S COST ADJUSTMENT. THERE SHALL BE NO ADDITIONAL COST TO THE OWNER OR ARCHITECT DUE TO THE USE OR ACCEPTANCE OF ANY ALTERNATE OR SUBSTITUTE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD.

1.10 PRIOR APPROVAL

A. SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES: THE CONTRACTOR'S SUBMITTAL AND ARCHITECT'S ACCEPTANCE OF SHOP DRAWINGS, PRODUCT DATA, OR SAMPLES THAT RELATE TO CONSTRUCTION ACTIVITIES NOT COMPLYING WITH THE CONTRACT DOCUMENTS DOES NOT CONSTITUTE AN ACCEPTABLE OR VALID REQUEST FOR SUBSTITUTION, NOR DOES IT CONSTITUTE APPROVAL.

1.11 COORDINATION

A. BY SUBMITTING SHOP DRAWINGS ON THE PROJECT, THIS CONTRACTOR IS INDICATING THAT ALL NECESSARY COORDINATION HAS BEEN COMPLETED AND THAT THE SYSTEMS, PRODUCTS AND EQUIPMENT SUBMITTED CAN BE INSTALLED IN THE BUILDING AND WILL OPERATE AS SPECIFIED AND INTENDED, IN FULL COORDINATION WITH ALL OTHER DISCIPLINES.

1.12 SHOP DRAWINGS AND SUBMITTALS

A. GENERAL: AFTER THE CONTRACT IS AWARDED BUT PRIOR TO PROCEEDING WITH THE WORK REQUIRING SHOP DRAWING REVIEW, THE CONTRACTOR SHALL OBTAIN COMPLETE SHOP DRAWINGS AND PRODUCT DATA FROM THE MANUFACTURERS, SUPPLIERS, VENDORS, AND SUB- CONTRACTORS FOR ALL MATERIALS AND EQUIPMENT SPECIFIED HEREIN, AND MAKE FORMAL SUBMISSION TO THE ARCHITECT. A MINIMUM PERIOD OF TWO (2) WEEKS SHOULD BE ALLOWED IN THE CONSTRUCTION SCHEDULE EXCLUSIVE OF TRAVEL TIME FOR THE ARCHITECTS REVIEW.

B. CERTIFICATION: EACH CONTRACTOR RESPONSIBLE FOR THE WORK SHALL REVIEW AND CERTIFY THE SHOP DRAWING, SUBMITTAL AND/OR PRODUCT DATA TO BE IN FULL COMPLIANCE WITH THE REQUIREMENTS OF THE CONTRACT DOCUMENTS.

C. THE ARCHITECTS REVIEW OF SHOP DRAWINGS AND SUBMITTAL DATA SHALL NOT RELIEVE THE CONTRACTOR OF THE RESPONSIBILITY FOR DIMENSIONS OR ERRORS THAT MAY BE CONTAINED THEREIN, OR FOR DEVIATIONS FROM ANY REQUIREMENTS OF THE CONTRACT DOCUMENTS. IT SHALL BE CLEARLY UNDERSTOOD THAT THE ARCHITECTS NOTING SOME ERRORS BUT OVERLOOKING SOME OTHERS DOES NOT GRANT THE CONTRACTOR PERMISSION TO PROCEED IN ERROR. REGARDLESS OF ANY INFORMATION CONTAINED IN THE SHOP DRAWING OR PRODUCT DATA, THE CONTRACT DOCUMENTS SHALL GOVERN THE WORK AND ARE NEITHER WAIVED NOR SUPERSEDED IN ANY WAY BY THE REVIEW OF SHOP DRAWINGS, PRODUCT DATA AND SAMPLES.

1.13 EXECUTION AND COORDINATION OF WORK

A. MANUFACTURER'S RECOMMENDATIONS: WITH EXCEPTIONS AS SPECIFIED AND/OR INDICATED ON THE DRAWINGS OR IN THE SPECIFICATIONS, APPLY, INSTALL, ERECT, USE, CLEAN, AND CONDITION, MANUFACTURED ARTICLES, MATERIALS, AND EQUIPMENT PER MANUFACTURER'S CURRENT PRINTED RECOMMENDATIONS. KEEP COPIES OF SUCH PRINTED RECOMMENDATIONS AT JOB SITE AND MAKE THEM AVAILABLE AS REQUIRED.

1.14 SUPERVISION

A. A COMPETENT SUPERINTENDENT APPROVED BY THE ARCHITECT, SHALL BE KEPT BY THE CONTRACTOR AT THE BUILDING TO RECEIVE INSTRUCTIONS AND TO ACT FOR THE CONTRACTOR. ONCE THE SUPERINTENDENT HAS BEEN APPROVED, NO CHANGE SHALL BE MADE WITHOUT APPROVAL OF ARCHITECT. REPRESENTATIVES OF THE OWNER, ARCHITECT SHALL HAVE THE RIGHT TO OBSERVE THE WORK AT ANY TIME. THE CONTRACTOR SHALL HAVE A REPRESENTATIVE AVAILABLE WHEN HIS WORK IS BEING OBSERVED AND HE SHALL GIVE ASSISTANCE AS MAY BE REQUIRED TO THE ARCHITECT'S REPRESENTATIVE.

B. THE PROJECT SHALL BE CONSTRUCTED BY EMPLOYEES OF THE CONTRACTOR OR BY WORKERS UNDER HIS SUPERVISION. ANY SUBCONTRACTORS EMPLOYED BY THE CONTRACTOR SHALL BE APPROVED BY THE OWNER'S REPRESENTATIVE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL EQUIPMENT, MATERIAL AND WORK PERFORMED BY ANY SUBCONTRACTOR.

1.15 STORAGE AND PROTECTION OF MATERIALS

A. THE CONTRACTOR SHALL PROPERLY STORE ALL MATERIAL AND EQUIPMENT AT THE JOBSITE AND PROTECT IT FROM THE ELEMENTS AND FROM DAMAGE. ANY EQUIPMENT DAMAGED DUE TO IMPROPER PROTECTION SHALL BE REPLACED BY THE CONTRACTOR AT HIS EXPENSE.

B. THE CONTRACTOR SHALL PROTECT THE WORK, EQUIPMENT, AND MATERIAL OF ALL OTHER TRADES FROM DAMAGE BY HIS WORK OR OTHER WORKMEN, AND SHALL MAKE GOOD ALL DAMAGE THUS CAUSED.

C. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL WORK, MATERIALS, AND EQUIPMENT UNTIL FINALLY INSPECTED, TESTED, AND ACCEPTED. PROTECT WORK AGAINST THEFT, INJURY OR DAMAGE. AND CAREFULLY STORE MATERIAL AND EQUIPMENT RECEIVED ON SITE WHICH ARE NOT IMMEDIATELY INSTALLED. CLOSE OPEN ENDS OF WORK WITH TEMPORARY COVERS OR PLUGS DURING CONSTRUCTION TO PREVENT ENTRY OF OBSTRUCTING MATERIAL. THE CONTRACTOR SHALL COVER AND PROTECT IN AN ACCEPTABLE MANNER TO THE OWNER, EXISTING REMAINING EQUIPMENT AND MATERIALS.

D. IF ANY MATERIAL OR EQUIPMENT IS RECEIVED PRIOR TO THE TIME IT IS REQUIRED, THE CONTRACTOR SHALL BE RESPONSIBLE FOR ITS PROPER STORAGE AND PROTECTION UNTIL SUCH TIME AS IT MAY BE REQUIRED. THE CONTRACTOR SHALL PAY FOR ALL COSTS OF DEMURRAGE OR STORAGE.

1.16 DRAYAGE AND HAULING


A. THE CONTRACTOR SHALL KEEP THE JOBSITE FREE FROM THE ACCUMULATION OF TRASH AND CONSTRUCTION DEBRIS, REGARDLESS OF WHICH SUBCONTRACTOR MAY BE RESPONSIBLE.

1.17 CUTTING AND PATCHING


A. WHERE IT BECOMES NECESSARY TO CUT THROUGH ANY WALL, FLOOR OR CEILING TO PERMIT THE INSTALLATION OF ANY WORK, OR TO REPAIR ANY DEFECTS THAT MAY APPEAR, THE CUTTING SHALL BE PERFORMED UNDER THE SUPERVISION OF THE GENERAL CONTRACTOR. INFORM THE OWNER'S REPRESENTATIVE BEFORE ANY WORK COMMENCES. NO STRUCTURAL MEMBER SHALL BE ALTERED WITHOUT THE WRITTEN PERMISSION OF THE ARCHITECT.

B. VERIFICATION: SHOULD A QUESTION ARISE REGARDING THE ACCEPTABLE LEVEL OF NOISE OR VIBRATION IN A PARTICULAR SPACE OR PIECE OF EQUIPMENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING THE SERVICES OF AN APPROVED ACOUSTICAL CONSULTANT TO DETERMINE ACTUAL NOISE/VIBRATION CONDITIONS.


## 01 GENERAL NOTES





## 21 EXTERIOR DOOR SILL
SCALE: 6" = 1'-0" XREF





## 22 DOOR JAMB
SCALE: 6" = 1'-0" XREF





## 23 WINDOW HEAD
SCALE: 6" = 1'-0" XREF





## 24 DOOR WINDOW HEAD
SCALE: 6" = 1'-0" XREF




## 15 WINDOW JAMB AT WALL
SCALE: 6" = 1'-0"





## 16 DOOR HEAD
SCALE: 6" = 1'-0" XREF





## 17 WINDOW SILL
SCALE: 6" = 1'-0" XREF





## 18 DOOR SILL
SCALE: 6" = 1'-0" XREF




## 09 WINDOW CORNER
SCALE: 6" = 1'-0"




## 10 DOOR STRIKE JAMB
SCALE: 6" = 1'-0"




## 11 DOOR HINGE JAMB
SCALE: 6" = 1'-0"





## 12 WINDOW MULLION
SCALE: 6" = 1'-0"


SEQUENCE OF CONSTRUCTION (AS OF 01/27/2025) Schools will be renovated in groups as shown. These groups contain two or three major kitchen renovations and some cafeteria/miscellaneous renovations. This sequencing is critical for FBISD food service to provide the uninterrupted meal services to their schools.

| | |
|---|---|
| GROUPING 1 | AUSTIN PARKWAY ES + SUGAR MILL ES, kitchen renovations. *Plus: COMMON WEALTH ES, CONERSTONE ES misc. renovations.* |
| GROUPING 2 | SETTLERS WAY ES + PALMER ES kitchen renovations. *Plus: SULLIVAN ES, SIENNA CROSSING ES, HERITAGE ROSE ES misc. renovations* |
| GROUPING 3 | HUNTER'S GLEN ES + HIGHLANDS ES + PECAN GROVE ES kitchen renovations. *Plus: RIDGEGATE ES, DULLES ES misc. renovations.* |

## 03 PROJECT SCHEDULE




## 04 EXTERIOR DOOR HEAD JAMB
SCALE: 6" = 1'-0" XREF




## 06 WINDOW JAMB
SCALE: 6" = 1'-0" XREF

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT

SEAL
REGISTERED ARCHITECT
ROBERT ALEXANDER
22651
STATE OF TEXAS
7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

GENERAL NOTES AND ABBREVIATIONS

A00-01

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\A00-01 GENERAL NOTES AND ABBREVIATIONS.dwg Jul 23, 2025 - 1:53pm

## GENERAL DEMOLITION NOTES
(NOT ALL NOTES USED ON EACH SHEET)

1. REFER TO SHEET A00-01 FOR DEMOLITION GENERAL NOTES. THESE NOTES APPLY TO ALL SCHOOL KITCHENS.
2. COORDINATE EXTENT OF SAW CUTTING AREAS WITH NEW RECESSED SLAB FOR COOLER/FREEZER LAYOUTS, NEW SERVICE ENTRANCE FLOOR AND EXISTING KITCHEN LAYOUTS THAT REMAIN. SEE STRUCTURAL DRAWINGS AND SLAB DIMENSION CONTROL PLANS FOR ADDITIONAL SCOPE.
3. REMOVE PROTECT AND REINSTALL ALL EXISTING SURFACE MOUNTED FIRE EXTINGUISHERS (TYPES ABC AND K) AT ALL KITCHENS.
4. SAWCUT AND RE-LOCATE EXPOSED CONDUITS AND WIREMOLD TO INSIDE OF WALLS. PATCH AND PAINT. EXCEPTION: WAREWASH AREA BELOW TABLE HEIGHT AND DRY STORAGE ROOMS.
5. CONTRACTOR TO RELOCATE EXISTING KITCHEN EQUIPMENT AND OFFICE FURNITURE TO TEMPORARY KITCHEN LAYOUT AS REQUESTED BY KITCHEN MANAGER. ALSO THAT THE IT EQUIPMENT IS PROTECTED DURING RENOVATIONS. ALL EXISTING EQUIPMENT SHALL BE RETURNED TO OWNER.
6. EXISTING TACKBOARDS TO BE REMOVED BY OWNER.
7. IF PRESENT, EXISTING SAFE IN EACH KITCHEN TO BE TEMPORARILY REMOVED DURING RENOVATION AND REINSTALLED IN KITCHEN AREA.
8. ORIGIN POINT OF EXISTING CEILING GRID SHALL BE IDENTIFIED. NEW CEILING WILL BE INSTALLED (AS MUCH AS POSSIBLE) AT THE SAME ORIGIN POINT SO THAT SPRINKLER SYSTEM PIPING CAN REMAIN UNCHANGED.
9. ABOVE-CEILING INFRASTRUCTURE SHALL REMAIN UNDISTURBED AS MUCH AS IS POSSIBLE. CEILING DEVICES ARE TO BE REMOVED FROM EXISTING GRID/TILE THEN DURING RE-INSTALATION OF CEILING DEVICES SHALL BE LOCATED AS CLOSE TO ORIGINAL LOCATION AS POSSIBLE INTO THE NEW GRID/TILE. PROTECT AND STORE EXISTING INFRASTRUCTURE (CABLING, ELECTRICAL POWER, PIPING) DURING CONSTRUCTION.
10. EXISTING HOOD IN WAREWASH AND (2) HOODS IN PRODUCTION AREA ARE TO BE CLEANED, INSPECTED, SERVICED AND REFURBISHED TO A LIKE NEW CONDITION. THEY ARE TO REMAIN IN PLACE.


## KEYED DEMOLITION NOTES
(NOT ALL NOTES USED ON EACH SHEET)

1. REMOVE EXISTING THINSET SYNTHETIC TERRAZZO FLOOR AND TERRAZZO COVE BASE MATERIAL IF ANY EXISTS THROUGHTOUT KITCHEN AREA. CLEAN AND PREPARE SUBFLOOR TO RECEIVE NEW FLOOR. RE: FINISH PLAN FOR NEW FLOOR FINISH MATERIAL.
2. REMOVE EXISTING QUARRY TILE FLOORING AND BASE. CLEAN AND PREPARE SUBFLOOR TO RECEIVE NEW FLOORING. RE: FINISH SCHEDULE FOR NEW FLOOR FINISH MATERIAL.
3. CEILING DEVICES: REMOVE SMOKE DETECTORS, STROBES, EXIT SIGNAGE, MOTION DETECTORS AND CEILING SPEAKERS. PROTECT AND RE-INSTALL AFTER FINISHES ARE APPLIED.
4. REMOVE EXISTING LOCKERS. PROTECT AND RE-INSTALL AFTER FINISHES APPLIED.
5. REMOVE EXISTING WASHER AND DRYER. VERIFY WITH FBISD FOR RELOCATION TO WAREHOUSE.
6. TEMPORARILY REMOVE EXISTING WALL MOUNTED CLOCK AND STORE FOR REINSTALLATION AFTER WALL RECEIVED NEW FINSH.
7. REMOVE EXISTING WALK-IN COOLER/FREEZER AND CONDENSING UNIT LOCATED IN ADJACENT SPACE. MITIGATE ANY MOLD FOUND.
8. REMOVE EXISTING DOOR AND PROTECT EXISTING FRAME TO REMAIN
9. REMOVE EXISTING DOOR AND FRAME, PROTECT FRAME AND OR DOOR IF IT IS SCHEDULED TO REMAIN.
10. REMOVE PARTIAL EXISTING CMU PARTITION FOR NEW DOOR OPENING
11. INSPECT EXISTING WAREWASH COUNTER DOOR AND S.S. PASS-THRU WINDOW CHUTE. REPAIR REPLACE DAMAGED COMPONENTS. CLEAN, LUBRICATE AND RE-INSTALL.
12. EXISTING CARD READER ACCESS TO REMAIN
13. EXISTING WINDOW TO REMAIN
14. REMOVE EXISTING KITCHEN EQUIPMENT THROUGHOUT KITCHEN INCLUDING WALK-IN COOLER / FREEZER AND CONDENSING UNIT LOCATED IN ADJACENT ROOM OR OUTSIDE OF THE BUILDING. VERIFY WITH OWNER FOR RELOCATION TO WAREHOUSE. SOME EQUIPMENT IS TO BE RE-USED IN TEMPORARY SERVING LINES. SEE ALSO GENERAL DEMOLITION NOTE 6.
15. REMOVE EXISTING FRP AND PREP FOR NEW TILE FINISH.
16. COORDINATE REMOVAL AND STORAGE OF ANY EXISTING FURNITURE ITEMS WITH OWNER . SEE ALSO GENERAL DEMOLITION NOTE 5.
17. REMOVE EXISTING SOAP AND PAPER TOWEL DISPENSER AND RETURN TO OWNER
18. EXISTING WALL MOUNTED ACCESSORIES SIGNS, DISPLAY BOARDS, AND MATS TO BE REMOVED BY FORT BEND ISD (VERIFY EQUIPMENT - IF ANY).
19. REMOVE EXISTING SURFACE MOUNTED FIRE EXTINGUISHER. RE-INSTALL AFTER NEW FINISH APPLIED.
20. REMOVE EXISTING ACOUSTIC CEILING TILE CEILNG SYSTEM AND LIGHT FIXTURES, HVAC DEVICES, SENSORS, ETC. THROUGHTOUT RENOVATED AREAS. PREP FOR NEW SUSPENDED CEILING. EXISTING SPRINKLE SYSTEM TO REMAIN AS-IS UNLESS ROOM CONFIGURATION HAS CHANGED IN NEW DESIGN. PROTECT RECESSED SPRINKLER HEADS AND - RE-INSTALL IN NEW CEILING.
21. REMOVE EXISTING CASEWORK/SHELVING
22. EXISTING CERAMIC WALL TILE TO REMAIN. PROTECT FROM DAMAAGE.
23. REMOVE EXISTING COAT HANGER / ROD / SHELF
24. REMOVE EXISTING PLUMBING FIXTURES IN RESTROOMS. RE: PLUMBING FOR NEW FIXTURES.
25. REMOVE EXISTING UTILITY SINK. RE: PLUMBING FOR NEW PLUMBING FIXTURES.
26. REMOVE EXISTING MOP HOLDER. REPLACE WITH NEW UNIT AS SPECIFIED.
27. REMOVE EXISTING WALL MOUNTED CLEANING SOLUTION DISPENSER (BY FBISD VENDOR)
28. HOOD TO REMAIN - SEE GENERAL DEMOLITION NOTE 10.
29. HOOD TO REMAIN - SEE GENERAL DEMOLITION NOTE 10.
30. REMOVE FLOORING IN THIS AREA FOR NOTE 1.
31. REMOVE CARTIDGE FILTER AND WATER PURTICATION CABNET


## DEMOLITION LEGEND

- EXISTING PARTITION TO REMAIN
- REMOVE EXISTING PARTITION
- EXISTING CMU PARTITION
- REMOVE DOOR AND FRAME TO REMAIN
- REMOVE EXISTING DOOR AND FRAME
- EXISTING PLUMBING FIXTURES (WATER CLOSET, HAND LAVATORY, AND MOP SINK TO BE REMOVED. RE: PLUMBING DRAWINGS.
- EXISTING ACOUSTIC CEILING TILE AND GRID TO BE REMOVED. RE: ELECTRICAL DRAWINGS.
- SPRINKLER HEAD (RECESSED)
- CLOCK
- CEILING MOUNTED SPEAKERS

# 3 DEMOLITION NOTES




## 1 DEMOLITION FLOOR PLAN
SCALE: 1/4" = 1'-0"




## 2 DEMOLITION REFLECTED CEILING PLAN
SCALE: 1/4" = 1'-0"

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\J-Highlands ES\j-D 101 DEMO PLAN.dwg Jul 23, 2025 - 1:53pm

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

j

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL
REGISTERED ARCHITECT
KEITH A. MAHAFFEY
22651
STATE OF TEXAS
7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

DEMO PLAN

j-D.101


PHOTO D1




PHOTO D2




PHOTO D3



PHOTO D4




PHOTO D5




PHOTO D6




PHOTO D7




PHOTO D8



PHOTO D9


PHOTO D10




PHOTO D11




PHOTO D12



PHOTO D13




PHOTO D14



PHOTO D15



PHOTO D16




PHOTO D17




PHOTO D18



PHOTO D19



PHOTO D20

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

j

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DR,
SUGAR LAND, TX 77478

SEAL
REGISTERED ARCHITECT
MARK A. MADDEN
22651
STATE OF TEXAS
7/15/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
DEMO PLAN PHOTOS
j-D.101-2

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\J-Highlands ES\j-D.101-2 DEMO PLAN PHOTOS.dwg Jul 23, 2025 - 1:54pm





**PHOTO D21**




**PHOTO D22**





**PHOTO D23**




**PHOTO D24**




**PHOTO D25**




**PHOTO D26**




**PHOTO D27**





**PHOTO D28**





**PHOTO D29**





**PHOTO D30**

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

j

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DR,
SUGAR LAND, TX 77478

SEAL

REGISTERED ARCHITECT
KIRK A. MOORE
22851
STATE OF TEXAS

7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

DEMO PLAN PHOTOS

j-D.101-3


F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\J-Highlands ES\j-D.101-3 DEMO PLAN PHOTOS.dwg Jul 23, 2025 - 1:54pm

## NEW PANEL — TEMP KITCHEN


**PANEL LTK** — 150A MCB, 208Y/120V, 3ϕ, 4 WIRE — AVAILABLE FAULT: <10,000A — SCCR & AIC: 10,000A — MOUNTING: SURFACE

| NOTES | EQUIP. NO. | LOAD | DESCRIPTION | WIRE | CB | CKT | A | B | C | CKT | CB | WIRE | DESCRIPTION | LOAD | EQUIP. NO. | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E810 | 2766 | HOT WELLS | 2–12 | 20/2GFI | 1 | ■ | | | 2 | 20/1 | 3–12 | TRANSPORT CART | 1920 | E806 | |
| | – | – | – | +12G | – | 3 | | ■ | | 4 | 20/1 | 3–12 | TRANSPORT CART | 1920 | E806 | |
| | E810A | 1643 | HOT WELLS | 2–12 | 20/2GFI | 5 | | | ■ | 6 | 20/1 | 3–12 | TRANSPORT CART | 1920 | E806 | |
| | – | – | – | +12G | – | 7 | ■ | | | 8 | 20/1 | 3–12 | TRANSPORT CART | 1920 | E806 | |
| | E810B | 600 | COLD PAN | 3–12 | 20/1GFI | 9 | | ■ | | 10 | 20/1 | 3–12 | 2 REC | 360 | E800A | |
| | E810C | 1200 | BEVERAGE | 3–12 | 20/1GFI | 11 | | | ■ | 12 | 20/1 | 3–12 | 2 REC – DESK | 360 | E800B | |
| | E810C | 1200 | BEVERAGE | 3–12 | 20/1GFI | 13 | ■ | | | 14 | 20/1 | 3–12 | 2 REC | 360 | E800A | |
| | E811 | 180 | CASH REGISTER | 3–12 | 20/1GFI | 15 | | ■ | | 16 | 20/1 | 3–12 | 3 REC | 360 | E800A | |
| | E810B | 600 | COLD PAN | 3–12 | 20/1GFI | 17 | | | ■ | 18 | 20/1 | 3–12 | TEMP. KITCHEN LTS/FAN | 566 | | |
| | E810A | 1643 | HOT WELLS | 2–12 | 20/2GFI | 19 | ■ | | | 20 | 20/1 | | SPARE | | | |
| | – | – | – | +12G | – | 21 | | ■ | | 22 | 20/1 | | SPARE | | | |
| | E810 | 2766 | HOT WELLS | 2–12 | 20/2GFI | 23 | | | ■ | 24 | 20/1 | | SPARE | | | |
| | – | – | – | +12G | – | 25 | ■ | | | 26 | 20/1 | | SPARE | | | |
| | E808 | 1622 | HEATED CABINET | 2–12 | 20/2 | 27 | | ■ | | 28 | 20/1 | | SPARE | | | |
| | – | – | – | +12N+12G | – | 29 | | | ■ | 30 | 20/1 | 3–12 | EXISTING CIRCUIT | 500 | | 3 |
| | E809 | 984 | REFRIGERATOR | 3–12 | 20/1 | 31 | ■ | | | 32 | 20/1 | 3–12 | EXISTING CIRCUIT | 500 | | 3 |
| | E808 | 1622 | HEATED CABINET | 2–12 | 20/2 | 33 | | ■ | | 34 | 15/2 | 2–12 | EXISTING CIRCUIT | 1000 | | 3 |
| | – | – | – | +12N+12G | – | 35 | | | ■ | 36 | – | +12N+12G | – | – | | |
| | E809 | 984 | REFRIGERATOR | 3–12 | 20/1 | 37 | ■ | | | 38 | 20/2 | 2–12 | EXISTING CIRCUIT | 1000 | | 3 |
| | | | SPARE | | 20/1 | 39 | | ■ | | 40 | – | +12N+12G | – | – | | |
| | | | SPARE | | 20/1 | 41 | | | ■ | 42 | 50/2 | 2–8 | EXISTING CIRCUIT | 5000 | | 3 |
| | | | SPARE | | 20/1 | 43 | ■ | | | 44 | – | +8N+10G | – | – | | |
| | TOTAL LOAD @ 100% = | | 35498VA | | | TOTAL LOAD @ 100% = | | | | 99A | | | | | | |

1. REF. KITCHEN CONSULTANT'S "FCS" DRAWINGS FOR KITCHEN EQUIPMENT NUMBERS.
2. A DEMAND FACTOR PERCENT OF 65% HAS BEEN APPLIED TO THE KITCHEN EQUIPMENT LOAD PURSUANT TO NEC 220–20 AND NEC TABLE 220–20.
3. IDENTIFY ANY CIRCUITS OR PARTIAL CIRCUITS THAT EXTEND BEYOND THE AREA OF RENOVATION. PROVIDE TEMPORARY FEED TO MAINTAIN ALL CIRCUITS SERVING ELEMENTS/SPACES NOT TO BE REMOVED DURING CONSTRUCTION. RECONNECT EXISTING CIRCUITS/DEVICES TO REMAIN TO TEMPORARY KITCHEN PANEL ONCE AVAILABLE USING CB(S) PROVIDED. ALL PARTIAL CIRCUITS SHALL REMAIN AND REMAIN ACTIVE BOTH DURING AND AFTER CONSTRUCTION.




**T1** **TEMPORARY KITCHEN - LIGHTING PLAN**
SCALE: 1/4" = 1'– 0"




**T2** **TEMPORARY KITCHEN - ELECTRICAL PLAN**
SCALE: 1/4" = 1'– 0"

## ELECTRICAL KEYED NOTES

GENERAL NOTES:

- CUT WALLS AS REQUIRED TO FLUSH MOUNT NEW DEVICES IN EXISTING WALLS. PATCH/REPAIR WALLS TO MATCH.

DEMOLITION NOTES:

A. EXISTING STANDBY GENERATOR PANEL TO REMAIN.

B. EXISTING KITCHEN PANELS TO BE REPLACED WITH NEW. MODIFY EXISTING WALLS TO MATCH NEW PANEL LAYOUTS AND DIMENSIONS.

C. EXISTING LIGHTING FIXTURES AND CEILING DEVICES TO BE REMOVED THROUGHOUT.

D. EXISTING WALK–IN COOLER/FREEZER AND ASSOCIATED EQUIPMENT TO BE REMOVED.

E. EXISTING WALL ELECTRICAL DEVICES TO BE REMOVED. EXISTING J–BOXES MAY BE REUSED WHERE NEW DEVICES ARE TO BE INSTALLED AT THE SAME LOCATIONS.

F. EXISTING ELECTRICAL DEVICES TO BE REMOVED.

G. NEW 208Y/120V PANEL AND TRANSFORMER FOR TEMPORARY KITCHEN TO BE INSTALLED PRIOR TO DEMOLITION. PANEL AND TRANSFORMER TO BE REMOVED AT END OF KITCHEN RENOVATION AND TURNED OVER TO THE DISTRICT. INSTALL TRANSFORMER ON PREMADE FIBERCRETE PAD AND WAFFLE TYPE VIBRATION ISOLATION PADS. DO NOT PROVIDE A POURED IN PLACE CONCRETE PAD AT THIS LOCATION.

H. PROVIDE RECEPTACLES AND LIGHT FIXTURES FOR TEMPORARY KITCHEN DURING RENOVATION. ALL TEMPORARY DEVICES AND EQUIPMENT TO BE REMOVED AT END OF KITCHEN RENOVATION AND OFFERED TO THE OWNER AS SALVAGE.

I. CONDUITS ROUTED FROM TEMPORARY KITCHEN WALL AND BENEATH SERVING LINE. PROVIDE MULTICHANNEL ROLLOVER CABLE PROTECTOR FOR EXPOSED CONDUITS NOT UNDER THE SERVING LINE. ALL CONDUITS UNDER THE SERVING LINE SHALL BE SECURED TO/ROUTED ON TOP OF UNISTRUT AND NOT DIRECTLY ON THE FLOOR. DO NOT ANCHOR UNISTRUT TO THE EXISTING FLOORING. COORDINATE POWER AND DATA OUTLET LOCATIONS WITH OTHER TRADES.

J. REMOVE EXISTING LIGHT FIXTURES ABOVE NEW KITCHEN EXTENSION. MODIFY EXISTING WIRING TO MAINTAIN REMAINING FIXTURE OPERATION.

K. HARDWIRE KITCHEN EQUIPMENT TO LOCAL ON/OFF SWITCH. TYPICAL.

L. SURFACE MOUNT FIXTURES ON TEMPORARY KITCHEN CEILING. TYPICAL.


M. WIRE TEMPORARY KITCHEN FAN TO LOCAL LIGHTING CIRCUIT AND CONTROLS. FAN SHALL BE ON/OFF WITH LIGHTS.

N. EXISTING EXTERIOR LIGHT FIXTURES TO BE REMOVED.

O. PROVIDE NEW FIRE ALARM DEVICES AS PART OF THE TEMPORARY KITCHEN BUILDOUT.

P. PROVIDE NEW TEMPORARY LIGHT FIXTURES IN THE EXISTING CAFETERIA CEILING ABOVE THE SERVING LINE. COORDINATE LOCATIONS WITH TEMPORARY SERVING LINE AND EXISTING CONDITIONS. CONNECT TO EXISTING LIGHTING CONTROLS/CIRCUIT. ALL TEMPORARY LIGHT FIXTURES SHALL BE REMOVED AT THE END OF KITCHEN RENOVATION AND OFFERED TO THE OWNER AS SALVAGE. PROVIDE REPLACEMENT CEILING TILES.

Q. PROVIDE IN–USE WEATHERPROOF COVER FOR RECEPTACLE.




**1** **DEMOLITION FLOOR PLAN**
SCALE: 1/8" = 1'– 0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL

STATE OF TEXAS — GEORGE L. STANTON — 38582 — REGISTERED PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL DEMO AND TEMP PLANS

j-ED.100


STANTON ENGINEERING GROUP
INFO@STANTON–ENG.COM (713) 300–6080 | TEXAS ENG. FIRM REG. NO. F–018332 | 1300 W. SAM HOUSTON PARKWAY S., SUITE 121, HOUSTON, TX 77042


© 2021 ALL RIGHTS RESERVED

## DEMOLITION KEYED NOTES

D1 EXISTING CLEAN OUT SHALL BE REPLACED WITH NEW. CHIP OUT SLAB AROUND CLEANOUT TO REMOVE.

D2 EXISTING FLOOR DRAIN SHALL BE REPLACED WITH NEW, INCLUDING P-TRAP. CHIP OUT SLAB AROUND DRAIN TO REMOVE FLOOR DRAIN AND EXISTING P-TRAP.

D3 CUT AND CAP EXISTING HW/CW FOR FUTURE EXTENSION. DEMOLISH ALL PIPING WITHIN KITCHEN. DEMOLITION SHALL BE DELAYED UNTIL NEW CW MAIN AND HW PIPING LOOP IS INSTALLED IN PARALLEL. CW/HW SERVICE TO THE TEMPORARY KITCHEN SHALL BE UNINTERRUPTED DURING OCCUPIED HOURS. COORDINATE SWITCHOVER FROM EXISTING PIPING TO NEW WITH OCCUPANCY SCHEDULE.


D4 EXISTING FLOOR DRAIN TIED TO GREASE WASTE SYSTEM. DRAIN IS BEING USED FOR TEMPORARY KITCHEN INDIRECT WASTE AND SHALL REMAIN ACTIVE DURING OCCUPIED HOURS. COORDINATE DEMOLITION AND REPLACEMENT WITH TEMPORARY KITCHEN USAGE.

D5 DEMOLISH EXISTING DRAIN A CAP BELOW SLAB.

D6 EXISTING SPACE BEING DEMOLISHED. CAP EXISTING SANITARY MAIN BELOW SLAB AND REMOVE UPSTREAM PIPING. CUT/CHIP OUT SLAB AS REQUIRED AND REPAIR TO MATCH EXISTING.

D7 TEMPORARILY CAP EXISTING SANITARY MAIN BELOW SLAB AND REMOVE UPSTREAM PIPING. CUT/CHIP OUT SLAB AS REQUIRED AND REPAIR TO MATCH EXISTING. PIPING TO BE REPLACED WITH NEW TRUNK AND ADDITIONAL DRAIN BRANCH LINES.

D8 CUT AND CAP EXISTING SANITARY MAIN BELOW GRADE FOR EXTENSION IN RENOVATION PHASE. ALL UPSTREAM PIPING SHALL BE ABANDONED IN PLACE. CAP ANY OPEN ENDS BEFORE BURIAL.




**1 PLUMBING DEMOLITION FLOOR PLAN**

SCALE: 1/4" = 1'- 0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL






MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

PLUMBING DEMOLITION FLOOR PLAN

**j-PD1.01**


STANTON ENGINEERING GROUP
TEXAS ENGINEERING FIRM REG. NO. F-12344 © 2025 ALL RIGHTS RESERVED
INFORMATION PLEASE! (713) 300-60360 | 13999 W. SAM HOUSTON PARKWAY S., SUITE 125, HOUSTON, TX 77072




1 j-TD201 TECHNOLOGY DEMOLITION FLOOR PLAN
1/4" = 1'-0"

**TECHNOLOGY DEMOLITION PLAN GENERAL NOTES**

1. ALL DATA, VOICE, VIDEO AND SECURITY SYSTEMS SHALL REMAIN OPERATIONAL AT ALL TIMES DURING BUSINESS HOURS UNLESS OTHERWISE NOTED. ANY SYSTEM DOWNTIME SHALL BE SCHEDULED WITH THE ARCHITECT/ENGINEER AND OWNER AT LEAST TEN (10) WORKING DAYS IN ADVANCE. CONTRACTOR SHALL DEVELOP A PHASING PLAN AND SCHEDULE OF ANY REQUIRED SYSTEM DOWNTIME FOR REVIEW AND APPROVAL BY THE ARCHITECT/ENGINEER AND OWNER PRIOR TO ANY CONSTRUCTION ACTIVITIES.
2. OWNER SHALL BE RESPONSIBLE FOR POWER DOWN AND START-UP OF ALL DATA, VOICE, VIDEO AND SECURITY SYSTEMS. CONTRACTOR SHALL COORDINATE WITH THE ARCHITECT/ENGINEER AND OWNER AND PROVIDE A MINIMUM OF TEN (10) WORKING DAYS NOTICE FOR SCHEDULING OF ANY REQUIRED DOWNTIME.
3. ALL EXISTING WIRELESS ACCESS POINTS ARE TO BE REMOVED AND RETURNED TO OWNER. CONTRACTOR SHALL RE-INSTALL ALL EXISTING AND NEW WIRELESS ACCESS POINTS AT COMPLETION OF PROJECT.
4. COORDINATE REMOVAL OF EXISTING CAMERA WITH OWNER/ARCHITECT DURING CONSTRUCTION.

**TECHNOLOGY DEMOLITION PLAN KEYED NOTES**

**NOT ALL KEYED BELOW APPLY TO THIS SHEET**

(1) EXISTING DATA/VOICE/WIRELESS ACCESS POINT OUTLET TO BE REMOVED. CONTRACTOR SHALL REMOVE AND DISPOSE OF ALL 4-PAIR CABLES AND WORKSTATION CONNECTING HARDWARE TERMINATED AT THIS LOCATION. IF LOCATION IS NOT RE-USED, CONTRACTOR SHALL SUPPLY AND INSTALL BLANK COVER. CONTRACTOR IS TO REMOVE EACH CABLE TO BE DEMOLISHED FROM THE PATCH PANEL OR TERMINATION BLOCK IN THE TELECOMMUNICATIONS ROOM. REMOVE THE ENTIRE LENGTH OF THE CABLE AND THE CORRESPONDING MODULAR CONNECTOR, FACEPLATE AND ACCESSORIES. NO ABANDONED CABLING IS TO BE LEFT ABOVE CEILING. CONTRACTOR SHALL INSTALL ALL EXISTING AND NEW WIRELESS ACCESS POINTS AT COMPLETION OF PROJECT.

(2) EXISTING VIDEO SURVEILLANCE CAMERA. CONTRACTOR SHALL REMOVE AND RETURN TO OWNER.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

J

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD


07/18/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY DEMOLITION FLOOR PLAN


SHEET NO.
j-TD201




10 CANOPY DETAILS
3/4" = 1'-0"





11 CANOPY PLAN
3/4" = 1'-0"





12 CANOPY SECTION
3/4" = 1'-0"

NUMBERED NOTES: FOR 2/J-A.101

1. COOLER RENTAL UNIT; APPROX. 8' X 10' BASIS OF DESIGN: MODEL DT810 BY POLAR LEASING REFRIGERATION RENTAL.
2. INCLUDE OPTIONAL DIAMOND TREAD RAMP SUITABLE FOR WHEELED TRAFFIC
3. LOCATION SHOWN IS SUBJECT TO OWNER APPROX. LOCATION MUST NOT BLOCK DELIVERIES TO REAR DOOR, MUST BE WITH 10' OF AREA DRAIN, AND WITHIN 100' OF ELECTRICAL POWER.
4. CONTRACTOR SHALL SCAN PAVING FOR BURIED UTILITIES BEFOR CUTTING CONC.




1 SITE PLAN
SCALE: 1" = 30'-0"




2 ENLARGED SITE PLAN
SCALE: 1/8" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

j

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT

HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL
REGISTERED ARCHITECT
MICHAEL K. ANDERSON
#26511
STATE OF TEXAS
7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

SITE PLAN

j-A.101

F:\2022\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\J-Highlands ES\j-A.101 SITE PLAN.dwg Jul 23, 2025 - 1:54pm




# 1 SLAB DEPRESSION PLAN

SCALE: 1/4" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

j

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL
REGISTERED ARCHITECT
STATE OF TEXAS
23051
7/15/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

SLAB SIMENSION CONTROL PLAN

j-A.200

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\J-Highlands ES\j-A.200 SLAB DIMENSION CONTROL PLAN.dwg Jul 23, 2025 - 1:55pm

## RESPONSIBILITY MATRIX

| ITEM | | | | CONTRACTOR RESPONSIBILITY | | OWNER RESPONSIBILITY | | NOTES |
|---|---|---|---|---|---|---|---|---|
| **EQUIPMENT** | **MAKE** | **MODEL** | **BASIS OF DESIGN** | FURNISHED | INSTALL | FURNISHED | INSTALL | |
| MARKERBOARD | | | MUST BE MAGNETIC; LOW GLOS, WHITE. NO GREY ALLOWED. 5' X 10' | X | X | | | |
| MOTORIZED FOLDING PARTITION | | | TOP SUPPORTED AND CONTINUOUSLY HINGED. MADE OF 3" THICK STEEL WITH FULL SOUND SEALS. THEY FEATURE AUTOMATIC FLOOR SEALS THAT DEPLOY WHEN POSITIONED. MARKERBOARD FINISHES ARE SUGGESTED FOR CLASSROOM USE. LARGE PARTITIONS SHOULD BE ELECTRONICALLY OPERATED, INTEGRATED WITH THE SCHOOL SYSTEM, AND SUPPORTED FROM THE BOTTOM IN A RECESSED MANNER. | X | X | | | |
| PAPER TOWEL DISPENSER | | | 1 PAPER TOWEL DISPENSER PER SINK | | X | X | | |
| SOAP DISPENSER | | | 1 SOAP DISPENSER PER SINK | | X | X | | |
| COMMERCIAL WASHER | GE | GTW750CPLDG | STAINLESS STEEL; ASTM A666, TYPE 304 WITH NUMBER 4 FINISH. ELECTRIC, 480 VOLTS, 40 LB CAPACITY, MINIMUM EXTRACTOR FORCE 140 G FACTOR. | X | X | | | |
| COMMERCIAL DRYER | GE | GTD75ECPLDG | HEAVY DUTY EMBOSSED STEEL WITH ELECTROSTATICALLY APPLIED BACKED ENAMEL FINISH. | X | X | | | |
| MOP RACK | | | BROOM AND MOP HANGGERS FOR A MINIMUM OF TWELVE (12) HANGERS TO BE PROVIDED IN THE CONTRACT | X | X | | | |
| KITCHEN MENU SYSTEM DEVICE | | | RE: J-QP1.0 SF EQUIPMENT PLAN | X | X | | | REFERED TO IT DRAWINGS |
| LOCKERS | | | 12"W X 15"D, 2 TIER, 60" HIGH. 16 GA. DOOR WITH 20GA. BODY | X | X | | | |
| MIRROR | | | TOP EDGE 74 INCHES (1880 MM) MINIMUM ABOVE THE FINISH FLOOR OR GROUND & BOTTOM EDGE OF THE REFLECTING SURFACE 40 INCHES (1015 MM) MAXIMUM | X | X | | | |
| GRAB BARS | | | AS REQUIRED BY ADA | X | X | | | |
| HOOKS | | | J-HOOKS | X | X | | | |
| TIME CLOCK | KRONOS | | EXISTING UNIT | | X | | | COORDINATE HEIGHT, DATA, POWER AND ROUGH-IN REQUIREMENTS WITH FBISD IT. REMOVE, PROTECT & REINSTALL EXISTITNG TIME CLOCK. |
| **KITCHEN OFFICE FURNITURE** | | | | | | | | |
| AUSTIN PARKWAY ES | | | | | | X | X | |
| PECAN GROVE ES | | | | | | X | X | |
| SETTLERS WAY ES | | | | | | X | X | |
| SUGAR MILL ES | | | | | | X | X | |
| HIGHLANDS ES | | | | | | X | X | |
| PALMER ES | | | | | | X | X | |
| HUNTERS GLEN ES | | | | | | X | X | |

# 2 CODE ANALYSIS

SCOPE OF WORK: KITCHEN REPLACEMENT OF FLOOR, WALL, AND CEILING FINISHES, AS WELL AS, REPLACEMENT OF KITCHEN EQUIPMENT. BACK DOOR DELIVERY AREA UPGRADE.

**ADOPTED CODES: CITY OF SUGAR LAND, TX**

- 2021 INTERNATIONAL BUILDING CODE
- 2021 INTERNATIONAL RESIDENTIAL CODE
- 2021 INTERNATIONAL PLUMBING CODE
- 2021 INTERNATIONAL MECHANICAL CODE
- 2023 NATIONAL ELECTRIC CODE NFPA 70
- 2021 INTERNATIONAL ENERGY CONSERVATION CODE
- 2021 INTERNATIONAL FUEL GAS CODE
- 2021 INTERNATIONAL FIRE CODE

**INTERIOR WALL AND CEILING FINISH REQUIREMENTS BY OCCUPANCY:**

**SPRINKLED**

INTERIOR EXIT STAIRWAYS AND RAMPS AND EXIT PASSAGEWAYS **B**

CORRIDORS AND ENCLOSURE FOR EXIT ACCESS STAIRWAYS AND RAMPS **C**

ROOMS AND ENCLOSED SPACES **C**

**FLOORING SHALL BE CLASS II**

**2021 INTERNATIONAL EXISTING BUILDING CODE**

301.3.1 PRESCRIPTIVE COMPLIANCE METHOD. REPAIRS, ALTERATIONS, ADDITIONS AND CHANGES OF OCCUPANCY COMPLYING WITH CHAPTER FIVE OF THIS CODE IN BUILDINGS COMPLYING WITH THE INTERNATIONAL FIRE CODE SHALL BE CONSIDERED IN COMPLIANCE WITH THE PROVISIONS OF THIS CODE.

302.3 EXISTING MATERIALS. MATERIALS ALREADY IN USE IN A BUILDING IN COMPLIANCE WITH REQUIREMENTS OR APPROVALS IN EFFECT AT THE TIME OF THEIR ERECTION OR INSTALLATION SHALL BE PERMITTED TO REMAIN IN USE UNLESS DETERMINED BY THE BUILDING OFFICIAL TO BE UNSAFE .

302.4 NEW AND REPLACEMENT MATERIALS. EXCEPT AS OTHERWISE REQUIRED OR PERMITTED BY THIS CODE, MATERIALS PERMITTED BY THE APPLICABLE CODE FOR NEW CONSTRUCTION SHALL BE USED. LIKE MATERIALS SHALL BE PERMITTED FOR REPAIRS AND ALTERATIONS, PROVIDED THAT NO UNSAFE CONDITION IS CREATED. HAZARDOUS MATERIALS SHALL NOT BE USED WHERE THE CODE FOR NEW CONSTRUCTION WOULD NOT PERMIT THEIR USE IN BUILDINGS OF SIMILAR OCCUPANCY, PURPOSE AND LOCATION.

**ALTERATION - LEVEL 1** INCLUDE THE REMOVAL AND REPLACEMENT OR THE COVERING OF EXISTING MATERIALS, ELEMENTS, EQUIPMENT, OR FIXTURES USING NEW MATERIALS, ELEMENTS, EQUIPMENT, OR FIXTURES THAT SERVE THE SAME PURPOSE.

**ALTERATION - LEVEL 2** INCLUDE THE ADDITION OR ELIMINATION OF ANY DOOR OR WINDOW, THE RECONFIGURATION OR EXTENSION OF ANY SYSTEM, OR THE INSTALLATION OF ANY ADDITIONAL EQUIPMENT, AND SHALL APPLY WHERE THE WORK IS EQUAL TO OR LESS THAN 50% OF THE BUILDING AREA.

THIS BUILDING'S CONSTRUCTION IS TYPE IIB.


THIS BUILDING'S OCCUPANCY IS E.

THIS BUILDING'S IS SPRINKLED.

THERE WILL NOT BE ANY MODIFICATIONS TO THE HOOD SYSTEMS IN THE KITCHENS BEYOND REPLACEMENT OF MOTOR FOR LIKE KIND IF NEEDED.

THE BUILDING WILL NOT HAVE ADDITIONAL SQUARE FOOTAGE AS PART OF THE WORK.

NEW CONSTRUCTION ELEMENTS, COMPONENTS, SYSTEMS AND SPACES SHALL COMPLY WITH THE REQUIREMENTS OF THE INTERNATIONAL BUILDING CODES




1 OVERALL FLOOR PLAN
SCALE: 1/16" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

j

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL
REGISTERED ARCHITECT
#22651
STATE OF TEXAS
7/15/2025


MWA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING


OVERALL
FLOOR PLAN

j-A.201

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\J-Highlands ES\j-A.201 FLOOR PLAN.dwg, Jul 23, 2025 - 1:55pm

# DOOR SCHEDULE

| DOOR # | DOOR WIDTH | DOOR HEIGHT | DOOR TYPE | DOOR MATERIAL | DOOR FINISH | FIRE RATING | FRAME THICKNESS | FRAME FINISH | KEY | HARDWARE | DETAILS | | | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | | SILL | JAMB | HEAD | |
| A005 | 3'-0" | X 7'-0" | SF4 | SOLID CORE | P LAM | NR | 4 1/2" | ANOD AL | | 103 | | 22/A00-01 | 16/A00-01 | |
| A006 | 3'-6" | X 7'-0" | SF4 | SOLID CORE | P LAM | NR | 4 1/2" | ANOD AL | | 501 | | 22/A00-01 | 16/A00-01 | |
| A007 | 3'-0" | X 7'-0" | SF4 | SOLID CORE | P LAM | NR | 4 1/2" | ANOD AL | | 341 | | 22/A00-01 | 16/A00-01 | |
| A008 | 3'-0" | X 7'-0" | SF4 | SOLID CORE | P LAM | NR | 4 1/2" | ANOD AL | | 501C | | 22/A00-01 | 16/A00-01 | |
| A012 | 4'-0" | X 7'-0" | HM1 | H.M. | PAINT | NR | 6" | PAINT HM | | 715V | 21/A00-01 | 04/A00-01 | 04/A00-01 | |
| 109A | 3'-0" | X 7'-0" | SF4 | SOLID CORE | P LAM | NR | 4 1/2" | ANOD AL | | 501H | | 22/A00-01 | 16/A00-01 | |
| 109B | 3'-0" | X 7'-0" | SF1 | ALUM/GLASS | ANOD AL | NR | 4 1/2" | ANOD AL | | C201AH | 18/A00-01 | 10&11/A00-01 | 23&24/A00-01 | CARD READER, CLOSER, BUZZER |
| 109C | 3'-0" | X 7'-0" | SF1 | ALUM/GLASS | ANOD AL | NR | 4 1/2" | ANOD AL | | C201AH | 18/A00-01 | 10&11/A00-01 | 23&24/A00-01 | CARD READER, CLOSER, BUZZER |
| 109D | 3'-0" | X 7'-0" | SF4 | SOLID CORE | P LAM | NR | 4 1/2" | ANOD AL | | 501H | | 22/A00-01 | 16/A00-01 | |




## 2 DOOR SCHEDULE

## FLOOR PLAN - GENERAL NOTES

1. REFER TO SHEET FOR GENERAL NOTES. GENERAL NOTES APPLY TO ALL SCHOOL KITCHENS.
2. REFER TO SHEET FOR PARTITION TYPES.
3. EXIXSTING EXPOSED CONDUITS AND DATA CABLING IN WIREMOLD TO BE ROUTED INSIDE WALLS (EXCEPT AT WAREWASH AREA BELOW TABLE HEIGHT AND DRY STORAGE ROOMS). PATCH AND REPAIR AS REQUIRED TO ACHIEVE SMOOTH CLEAN WALL SURFACE.

## PARTITION LEGEND

- EXISTING CMU PARTITION
- NEW CMU SCHEDULED PARTITION
- EXISTING METAL PARTITION
- NEW FRAMED SCHEDULED PARTITION

REFER TO SHEET FOR PARTITION TYPES

## FLOOR PLAN - KEYED NOTES

(NOT ALL NOTES USED ON EACH SHEET)

01 PROVIDE NEW MOP SINK UTILITY SHELF
RE: PLUMBING FOR MOP SINK
RE: SPEC 10 28 00 FOR UTILITY SHELF

02 REMOVE, STORE & REPLACE WALL MOUNTED FIRE EXTINGUISHER

03 PROVIDE NEW WALL MOUNTED FIRE EXTINGUISHER
RE: SPEC SECTIONS 10 44 13

04 PROVIDE NEW LOCKERS
RE: SPEC 10 51 13.

05 PROVIDE WASHER AND DRYER
RE: SPEC 11 45 20

06 REMOVE, PROTECT & REINSTALL WALL MOUNTED CLOCK.

07 PROVIDE CONDENSING UNIT
FOR WALK-IN COOLER/FREEZER
RE: MECHANICAL AND SPEC 11 40 00

08 PROVIDE POWER AND DATA FOR MENU BOARD.
RE: ELECTRICAL, TECHNOLOGY DRAWINGS & FOOD SERVICE.


09 PROVIDE P-LAM SHELVING
REFER TO DETAIL FOR BRACKET SUPPORT

10 FURNITURE & NON FOOD SVE EQUIPMENT RETURN TO OWNER FOR STORAGE.

11 INSPECT & SREVICE TOLLING COUNTER DOORS. RETURN TO LIKE NEW CONDITION.


12 COMMERCIAL CLOSED WASHER 40LB CAPACITY.
COMMERCIAL CLOSED DRYER 55LB CAPACITY.
BASIS OF DESIGN: WASHER; SPEED QUEEN SYN040
DRYER; SPEED QUEEN ST055.
REFER TO ELECTRICAL & PLUMBING FOR CONNECTIONS.


## 3 FLOOR PLAN NOTES





## 1 KITCHEN PLAN

SCALE: 1/4" = 1'-0"






## 4 MAKERBOARD ELEVATION

SCALE: 1/2"=1'-0"




## 5 RAMP @ REAR DOOR

SCALE: 3/16"=1'-0"




## A

SCALE: 1/2"=1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

j

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL
REGISTERED ARCHITECT
KIM A. HAMMOND
42651
STATE OF TEXAS
7/15/2025



ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

KITCHEN PLAN

j-A.301

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\J-Highlands ES\j-A.301 KITCHEN PLAN.dwg Jul 30, 2025 - 9:59am




## TEMPORARY KITCHEN FLOOR PLAN KEYED NOTES 05/A-A03-02

01 PROVIDE & INSTALL 555 SF OF RAM BOARD TO PROTECT EXISTING FLOORING. REMOVE AFTER CONSTRUCTION IS COMPLETE. CONTRACTOR MUST REPAIR FLOORING DAMAGED DURING CONSTRUCTION.

02 PROVIDE SCHEDULED PARTITIONS. BUILD PARTITIONS ON TOP OF RAM BOARD. DO NOT ATTACH PARTITIONS TO FLOOR.

03 ATTACH PARTITIONS TO EXISTING WALL. REPAIR WALL TO MATCH EXISTING AFTER CONSTRUCTION IS COMPLETE.


## TEMPORARY KITCHEN RCP KEYED NOTES 03/A-A03-02

04 ALL NEW SCHEDULED PARTITIONS AND CEILINGS FOR TEMPORARY STORAGE LAYOUT TO BE EPOXY PAINTED SW 7014 EIDER WHITE WITH SPECIFIED 4" RUBBER BASE. REMOVE WHEN CONSTRUCTION IS COMPLETED.


05 MOUNT TEMPORARY FLUORESCENT LIGHTS TO TEMPORARY CEILING.

## 3 TEMPORARY LAYOUT SECTION
SCALE: 1"=1' 0"

## 4 KEYED NOTES
SCALE: 1/4"=1'0"




## 1 TEMPORARY KITCHEN RCP
SCALE: 1/4" = 1'-0"




## 2 TEMPORARY KITCHEN FLOOR PLAN
SCALE: 1/4" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

j

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL
REGISTERED ARCHITECT
ROBERT M. WILLIAMS
23051
STATE OF TEXAS
7/15/2025


MWA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

TEMPORARY
KITCHEN
LAYOUT
j-A.302

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\J-Highlands ES\j-A.302 TEMPORARY KITCHEN LAYOUT.dwg Jul 23, 2025 - 1:35pm

## RCP - GENERAL NOTES

1. CEILING GRID SHALL BE INSTALLED TO MATCH EXISTING GRID'S POINT OF O THIS WILL REDUCE NEED TO RE-LOCATE ABOVE CEILING DUCTS, SPRINKLER AND OTHER SUPPORT SYSTEMS.
2. REFER TO SHEET A00-01 FOR GENERAL NOTES. GENERAL NOTES APPLY TO SEVEN SCHOOL KITCHEN REMODELS.
3. LIGHTING LEVELS SHOULD BE 50 FC IN PREPARATION AREAS, WARE WASH A SERVING LINES, OR MEET MINIMUM HEALTH CODE LEVELS, WHICHEVER ITS SEE MEP PLANS
4. REPLACE HVAC DEVICES. REPLACE LIGHTING WITH 24"x24" LED LAY IN LIGH SCHEDULED IN ELECTRICAL PLANS.
5. REFER TO MECHANICAL, ELECTRICAL SHEETS FOR DEVICE SCHEDULES.


## RCP - NUMBERED NOTES

01 PROVIDE 30"x30" MIN. ACCESS HATCH IN SOFFIT CENTERED ON MOTOR.


02 AFTER LOWERING THE NEW POWER RETRACTION SYSTEM. REPAIR AND PAINT SOFFITS AND SIDWALLS OF FURR TO MATCH EXISTING.

## RCP DEVICE LEGEND

| EXISTING TO REMAIN | NEW | DEMO | |
|---|---|---|---|
| S | S | S | CEILING MOUNTED SPEAKERS |
| | | | SECURITY CAMERA |
| W | W | W | WIRELESS ACCESS POINT |
| 901-33 | 901-33 | 901-33 | CEILING MOUNTED FIRE ALARM AND STROBE |
| | | | SMOKE DETECTOR |
| | | | SPRINKLER HEAD (RECESSED) |
| | | | SPRINKLER HEAD (PENDANT) |
| | | | DRYER VENT |
| | | | EXIT |
| | | | DOOR |




2 FOOD SERVICE AREA ELEVATION
SCALE: 3/16" = 1'-0"




1 REFLECTED CEILING PLAN
SCALE: 1/4" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

j

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL
REGISTERED ARCHITECT
ROY A. MARTINEZ
22651
STATE OF TEXAS
7/15/2025



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING


REFLECTED CEILING PLAN

j-A.401


F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\J-Highlands ES\j-A.401 REFLECTED CEILING PLAN.dwg Jul 23, 2025 - 1:56pm





## 3 LOCKER HOUSEKEEPING PAD
SCALE: 3"=1'-0"




## 4 MOPSINK ELEVATIONS
SCALE: 1/4"=1'-0"




## TYPE A
ROOM SIGNAGE - FIXED NAMES




## TYPE B
KITCHEN RESTROOM SIGNAGE

## 7 ROOM SIGNAGE
SCALE: 6"=1'-0"

### PAINT COLOR SCHEDULE
UNLESS OTHERWISE INDICATED FIELD COLOR IS PT-1 (SW 7014 EIDER WHITE)


SW 7014 EIDER WHITE (EPOXY PAINT)

### WALL TILE
CERAMIC WALL TILE (WT-1)
REFER TO TILE PATTERN AT SERVING AND RESTROOM
FIELD WALL TILE: DALTILE RITTENHOUSE SQUARE K175 BISCUIT (3X6)


### QUARRY TILE
QUARRY TILE AND BASE - SURE-STEP II OQ30
TILE COLOR SELECTION TO BE APPROVED BY FBISD
EPOXY GROUT COLOR: STERLING SILVER BY LATICRETE

A — PROVIDE ROOM SIGN TO REPLACE EXISTING. SEE LAYOUT FOR TYPE A OR TYPE B SIGN LOCATIONS.

## 2 FLOOR FINISH LEGEND





## 5 FLOOR TRANSITION - THRESHOLD
SCALE: 3"=1'-0"





## 1 FINISH FLOOR PLAN
SCALE: 1/4" = 1'-0"


ALL FINISHED NOT DENOTED IN DRAWINGS SHALL BE SELECTED DURING THE SUBMITTAL PROCESS





## 8 RR ELEVATIONS
SCALE: 1/4"=1'-0"





## 6 WALL TILE PATTERN
SCALE: 1/4"=1'-0"




## 9 UTILITY ELEVATIONS
SCALE: 1/4"=1'-0"




## 10 STOREFRONT ELEVATIONS
SCALE: 1/4"=1'-0"




## 11 STOREFRONT SECTION
SCALE: 1/2"=1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

j

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL
REGISTERED ARCHITECT
MIR ALI KAZMI
32651
STATE OF TEXAS
7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

FINISH FLOOR PLAN

j-A.501

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\J-Highlands ES\j-A 501 FINISH FLOOR PLAN.dwg Jul 28, 2025 - 5:32pm

1. AT WALLS THAT TERMINATE ABOVE CEILING, CONTRACTOR MAY CONTINUE METAL STUD FRAMED WALLS TO UNDERSIDE OF METAL DECK AND OMIT DIAGONAL BRACING IF HEIGHT DOES NOT EXCEED LIMITING HEIGHT OF METAL STUD AS INDICATED ON CHART BELOW.

2. PROVIDE INTERMEDIATE BRACING AT ALL PARTITIONS THAT EXCEED LIMITING HEIGHT OF METAL STUDS AS INDICATED ON CHART BELOW.

3. ALL BRACING SHALL BE AT STUD POINTS.


CMU PARTITION NOTES:

1. MATCH EXISTING CMU COURSING (TYP.):
   BRIARGATE ES (4" CMU STARTER COURSE)
   LAKE OLYMPIA MS (4" CMU STARTER COURSE)
   MISSION BEND ES (8" CMU STARTER COURSE)
   RIDGEMONT ES (8" CMU STARTER COURSE)
   TOWNEWEST ES (8" CMU STARTER COURSE)
2. PROVIDE CMU LINTELS FOR ALL OPENINGS IN INTERIOR CMU PARTITIONS. COORDINATE WITH STRUCTURAL.
3. PROVIDE A 3/4" SPACE BETWEEN TOP OF CMU AND STRUCTURE/DECK FOR POTENTIAL DEFLECTION. SEAL WITH APPROPRIATE CAULK.
4. REFER TO FINISH SCHEDULES FOR CERAMIC TILE LOCATIONS.


GYPSUM WALLBOARD PARTITION NOTES:

1. ALL METAL STUDS PARTITIONS ARE 25 GAUGE METAL STUDS AT 16" O.C. UNLESS OTHERWISE NOTED. IF THE LIMITING HEIGHT FOR A PARTITION TYPE IS EXCEEDED, INCREASE SIZE AND/OR GAUGE OF METAL STUDS AS INDICATED ON "LIMITING HEIGHT OF METAL STUDS" TABLE. NOTIFY THE ARCHITECT PRIOR TO INSTALLATION.


| LIMITING HEIGHT OF METAL STUDS | | | |
|---|---|---|---|
| STUD SIZE | SPACING | 25 GA. | 20 GA. |
| 2-1/2" | 16" | 11'-3" | 12'-10" |
| 3-5/8" | 16" | 14'-4" | 16'-5" |
| 6" | 16" | 19'-9" | 24'-6" |





PARTITION A
SCALE: 1-1/2" = 1'-0"




PARTITION B1
SCALE: 1-1/2" = 1'-0"




PARTITION B2
SCALE: 1-1/2" = 1'-0"




PARTITION B3
SCALE: 1-1/2" = 1'-0"




PARTITION B4
SCALE: 1-1/2" = 1'-0"




PARTITION B5
SCALE: 1-1/2" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |

j

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL

FOR
INTERIM REVIEW
AND NOT INTENDED FOR CONSTRUCTION, BIDDING OR PERMIT PURPOSES.


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 05/23/25

PARTITION SCHEDULE

j-A.502

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\j-A.502 PARTITION SCHEDULE.dwg, Jul 23, 2025, 1:56pm

# REFER TO FOODSERVICE DESIGN PROFESSIONALS SPECIFICATIONS AND SUBSEQUENT SHEETS FOR ADDITIONAL COORDINATION INFORMATION

**EXISTING EQUIPMENT NOTES (IF EXISTING EQUIPMENT IS PROVIDED IN THIS PROJECT):**

1. EXISTING EQUIPMENT NOT SCHEDULED FOR RE-USE TO BE RELOCATED BY THE K.E.C. COORDINATE WITH OWNER FOR NEW LOCATION.
2. ALL UTILITIES NOT SCHEDULED FOR RE-USE TO BE CAPPED & COVERED BY REQUIRED DISCIPLINE.
3. K.E.C. TO VERIFY ALL EXISTING UTILITY LOCATIONS & COORDINATE WITH ALL EQUIPMENT AS REQUIRED.

8 EXISTING EQUIPMENT NOTES
NOT TO SCALE

**ARCHITECT TO VERIFY/COORDINATE THE AESTHETIC OPTIONS BELOW (FOOD SERVICE COLOR, MATERIAL, OR SIGNAGE SELECTIONS) IF THESE ITEMS ARE PROVIDED IN THIS PROJECT:**

1. COUNTERTOPS: STONE (STAINLESS STEEL IS PROVIDED UNLESS OTHERWISE SPECIFIED).
2. TRAY SLIDES: CORIAN OR STONE (STAINLESS STEEL IS PROVIDED UNLESS OTHERWISE SPECIFIED).
3. COUNTER FRONTS: CERAMIC TILE, 3 FORM, OR PLASTIC LAMINATE.
4. SNEEZE GUARDS: STONE INSETS.
5. GENERAL COLOR, MATERIAL AND GRAPHIC SELECTIONS:
   - A. DISPLAY AIR SCREEN MERCHANDISERS - COLOR SELECTION: POWDER COAT OR PLASTIC LAMINATE (S/S IS PROVIDED UNLESS OTHERWISE SPECIFIED).
   - B. BAKERY DISPLAY CASES - COLOR SELECTION: POWDER COAT OR PLASTIC LAMINATE (S/S IS PROVIDED UNLESS OTHERWISE SPECIFIED).
   - C. PASS THRU OR REACH IN HOLDING CABINETS - COLOR SELECTION: POWDER COAT (MFG.: TRUE) OR PLASTIC LAMINATE (MFG.: TRAULSEN) (S/S IS PROVIDED UNLESS OTHERWISE SPECIFIED).
   - D. HANGING HEAT LAMPS - TRACK AND FIXTURE COLOR SELECTION.
   - E. HEATED MERCHANDISERS.
   - F. PORTABLE GUIDE RAILS - STANCHION AND BELT COLOR SELECTION.
   - G. POPCORN MACHINE - SIGNAGE SELECTION.
   - H. BOTTLE COOLER - SIGNAGE SELECTION.
   - I. GRAPHICS PACKAGE INFORMATION.
   - J. HOT FOOD WELL COVERS.
6. ARCHITECT TO VERIFY/COORDINATE THE FINISHES BELOW:
   - A. WALLS: CERAMIC TILE, FLAT FRP, OR MOLDED FRP (SMOOTH, IMPERVIOUS, AND EASILY CLEANABLE AS APPROVED BY LOCAL JURISDICTION).
   - B. CEILINGS: REMOVABLE VINYL FACE TILE (SMOOTH, IMPERVIOUS, AND EASILY CLEANABLE AS APPROVED BY LOCAL JURISDICTION).
   - C. FLOORS: TILE, EPOXY, OR RUBBERIZED FLOORING SYSTEM (SMOOTH, IMPERVIOUS, EASILY CLEANABLE AND SLIP RESISTANT AS APPROVED BY LOCAL JURISDICTION) (COORDINATE FLOOR TILE TRANSITION AT SERVING LINES).
   - D. FLOORS: WALK-IN ASSEMBLY - EXTEND KITCHEN FLOOR FLUSH INTO WALK-IN ASSEMBLY WITH COVED BASE.
   - E. FURR DOWNS ABOVE SERVING COUNTERS.

5 ARCHITECTURAL COORDINATION NOTES
NOT TO SCALE

**CRITICAL NOTES:**

1. CONTRACTOR MUST COORDINATE AND VERIFY ALL DIMENSIONS WITH FOOD SERVICE EQUIPMENT SHOP DRAWINGS AND MANUFACTURER'S DATA. DIMENSIONS SHOWN ARE FOR DESIGN AND BIDDING PURPOSES ONLY.
2. WALK-IN ASSEMBLY DOORS MUST BE LEFT OPEN WHILE INTERIOR CONCRETE FLOOR CURES.
3. INSTALL PROTECTIVE COVER ON WALK-IN ASSEMBLY WALL PANELS BEFORE INSTALLING CONCRETE FLOORS AND CURBS.
4. REFER TO GENERAL SPECS - DIVISION 27 TO PROVIDE CONDUIT, DATA, AND INTERCONNECT THE PANIC ALARM INSIDE FREEZER TO THE BUILDING AUTOMATION SYSTEM FOR NOTIFICATION TO DISTRICT PERSONNEL IN THE EVENT OF STAFF ENTRAPMENT.
5. PIPING AND DRAINAGE SYSTEMS (SANITARY AND GREASE-LADEN). SYSTEMS MUST BE CLEANED AND FLUSHED BEFORE THE FINAL CONNECTION WITH FOOD SERVICE EQUIPMENT - CRITICAL (DIV. 22).

7 CRITICAL NOTES
NOT TO SCALE

**DIVISION 26 (ELECTRICAL) IS RESPONSIBLE FOR BUT NOT LIMITED TO:**

1. **DO NOT ROUGH IN FROM FDP DRAWINGS. REFER TO THE KITCHEN EQUIPMENT CONTRACTOR'S DIMENSIONED SHOP DRAWINGS. DIMENSIONS INDICATED ARE TO BE VERIFIED BY KITCHEN EQUIPMENT CONTRACTOR AND ADJUSTED AS REQUIRED BY EQUIPMENT AND FIELD CONDITIONS.**
2. SECTION 11 40 00 TO VERIFY UTILITY REQUIREMENTS OF ANY EXISTING EQUIPMENT.
3. ALL CONNECTIONS SHALL BE MADE FOLLOWING LOCAL CODES AND NATIONAL STANDARDS, EXCEPT WHERE PLANS AND SPECIFICATIONS EXCEED THOSE CODES AND STANDARDS.
4. VERIFY ALL ELECTRICAL REQUIREMENTS WITH ENGINEERING DRAWINGS.
5. ROUGH-IN AND FINAL CONNECTION OF ELECTRICAL SYSTEMS TO FOOD SERVICE EQUIPMENT, WALK-IN ASSEMBLIES, AND BETWEEN COMPONENTS (INCLUDING MATERIALS AND LABOR). ACCESSORIES PROVIDED LOOSE WITH FOOD SERVICE EQUIPMENT BY SECTION 11 40 00 TO BE FIELD INSTALLED BY DIVISION 26.
6. EMPTY EMT CONDUIT WITH PULL-WIRE AND WIDE-SWEEP BENDS FOR REFRIGERANT PIPING TO REMOTE FOOD SERVICE EQUIPMENT REFRIGERATION SYSTEMS.
7. EMPTY EMT CONDUIT WITH PULL-WIRE AND WIDE-SWEEP BENDS FOR INTERCONNECT CABLES BETWEEN LAN AND POS TERMINALS, CHANGE-MAKERS, PRE-CHECK UNITS, PRINTERS, CPUS, ETC. DIVISION 26 TO VERIFY WHERE THE CONDUIT IS TO RUN FOR POS SYSTEM (I.E., MANAGER'S OFFICE OR IDF ROOM).
8. EMPTY EMT CONDUIT WITH PULL-WIRE AND WIDE-SWEEP BENDS FOR FIRE SUPPRESSION SYSTEMS. INTERCONNECT FIRE PROTECTION SYSTEM TO PANEL BOX SHUNT TRIPS AND BUILDING ALARM.
9. WALK-IN LIGHT FIXTURE INSTALLATION (PROVIDED LOOSE BY SECTION 11 40 00) (IF WALK-IN IS PROVIDED IN THIS PROJECT).
10. TABLE LIMIT SWITCH INSTALLATION (PROVIDED LOOSE BY SECTION 11 40 00) (IF DISHMACHINE IS PROVIDED IN THIS PROJECT).
11. ELECTRICAL MATERIALS AND DEVICES (SHUNT-TRIP BREAKERS, SURGE PROTECTORS, LIGHTING CONTROL DEVICES, CONDUIT, WIRE, ETC.).
12. SWITCHES AND STAINLESS STEEL DISCONNECTS AS REQUIRED (PROVIDE, LOCATE, AND INSTALL – TO BE IN AN ACCESSIBLE LOCATION).
13. CHARGING STATIONS FOR FORKLIFTS, PALLET STACKERS, AND PALLET JACKS (SIZE, PROVIDE, LOCATE, AND INSTALL) (IF EQUIPMENT IS PROVIDED IN THIS PROJECT).
14. INTERCONNECTION BETWEEN CONDENSATE FAN AND DISHMACHINE CONTROL PANEL (IF EQUIPMENT IS PROVIDED IN THIS PROJECT).
15. INTERCONNECTION BETWEEN EXHAUST HOOD FANS AND SWITCH (IF EQUIPMENT IS PROVIDED IN THIS PROJECT).
16. INTERCONNECTION BETWEEN EXHAUST HOOD LIGHTS AND SWITCH (IF EQUIPMENT IS PROVIDED IN THIS PROJECT).
17. DOOR HEATERS, LIGHTS, COILS, AND PRESSURE RELIEF PORTS PRE-WIRED TO JUNCTION BOX AT TOP OF WALK-IN ASSEMBLIES (IF EQUIPMENT IS PROVIDED IN THIS PROJECT) PROVIDED BY SECTION 11 40 00. FINAL CONNECTION BY DIV. 26.
18. IF ANY ELECTRICAL ACCESSORIES, FITTINGS, AND CORD/PLUGS ARE PROVIDED LOOSE WITH EQUIPMENT BY 11 40 00, DIV.26 IS TO ATTACH TO EQUIPMENT AND PROVIDE FINAL CONNECTION.
19. PROVIDE WATERPROOF RECEPTACLES IN WET AREAS.
20. ALL ELECTRICAL CONNECTIONS BENEATH EXHAUST HOODS (IF EQUIPMENT IS PROVIDED IN THIS PROJECT) TO EXTEND TO SHUNT TRIP BREAKERS WITH ELECTRICAL PANEL BOX FOR SHUTDOWN DURING FIRE MODE.
21. RECEPTACLES ARE TO BE PRE-WIRED TO THE JUNCTION BOX OR LOAD CENTER FOR FINAL CONNECTION BY DIVISION 26.
22. ALL ELECTRICAL LIGHTING, POWER, AND DISTRIBUTION SYSTEMS.
23. DO NOT INTERCONNECT MORE THAN THREE (3) CONVENIENCE OUTLETS ON ONE (1) BREAKER.
24. OTHER THAN CONVENIENCE OUTLETS, ALL ELECTRICAL CONNECTIONS SHOWN ON FOOD SERVICE PLANS ARE DEDICATED BREAKERS.
25. DOORBELL AT RECEIVING DOOR (PROVIDE AND INSTALL – TO BE AUDIBLE THROUGHOUT KITCHEN, OFFICE, AND DRY STORAGE ROOM).
26. ADEQUATE LIGHTING AT RECEIVING DOOR.
27. PROVIDE AND INSTALL TWO EMERGENCY STROBE BEACONS THAT INTERCONNECT TO PANIC ALARM IN WALK-IN FREEZER. ONE (1) IN KITCHEN ABOVE WALK-IN FREEZER DOOR ONE (1) IN CAFETORIUM (IF WALK-IN IS PROVIDED IN THIS PROJECT). REFER TO GENERAL SPECIFICATIONS FOR ADDITIONAL DETAILS.
28. DEDICATED CIRCUIT FOR HEATED DRAIN LINE CONNECTION IN WALK-IN FREEZER AT EACH COIL (IF WALK-IN IS PROVIDED IN THIS PROJECT).

**NOTE: ELECTRICAL CONNECTIONS INDICATED ARE THOSE REQUIRED FOR THE FOOD SERVICE EQUIPMENT AND THOSE REQUIRED FOR SUPPORT EQUIPMENT FURNISHED BY DIVISION 26. FOR ADDITIONAL REQUIREMENTS, REFER TO THE ELECTRICAL ENGINEER'S DRAWINGS.**

6 ELECTRICAL COORDINATION NOTES
NOT TO SCALE

**DIVISION 22 (PLUMBING) RESPONSIBLE FOR BUT NOT LIMITED TO:**

1. **DO NOT ROUGH-IN FROM FDP DRAWINGS. REFER TO THE KITCHEN EQUIPMENT CONTRACTOR'S DIMENSIONED SHOP DRAWINGS. DIMENSIONS INDICATED ARE TO BE VERIFIED BY KITCHEN EQUIPMENT CONTRACTOR AND ADJUSTED AS REQUIRED BY EQUIPMENT AND/OR FIELD CONDITIONS.**
2. SECTION 11 40 00 TO VERIFY UTILITY REQUIREMENTS OF ANY EXISTING EQUIPMENT.
3. ALL CONNECTIONS SHALL BE MADE IN ACCORDANCE WITH LOCAL CODES AND NATIONAL STANDARDS, EXCEPT WHERE PLANS AND SPECIFICATIONS EXCEED THOSE CODES AND STANDARDS.
4. VERIFY ALL PLUMBING REQUIREMENTS WITH ENGINEERING DRAWINGS.
5. EMPTY PVC CONDUIT WITH WIDE-SWEEP BENDS FOR REFRIGERANT PIPING TO BEVERAGE LINES, CO2 LINES, AND REMOTE FOOD SERVICE EQUIPMENT REFRIGERATION SYSTEMS.
6. ROUGH-IN AND FINAL PLUMBING CONNECTIONS TO FOOD SERVICE EQUIPMENT AND BETWEEN COMPONENTS (INCLUDING MATERIALS AND LABOR). ACCESSORIES PROVIDED LOOSE WITH FOOD SERVICE EQUIPMENT BY SECTION 11 40 00 TO BE FIELD INSTALLED BY DIVISION 22. THIS INCLUDES BUT IS NOT LIMITED TO INSTALLATION OF ALL FAUCETS (WATER FILL FAUCETS, PRE-RINSE FAUCETS, ETC.), HOSES, GAS DISCONNECTS, AND DRAINS FROM EQUIPMENT POINT OF CONNECTION TO BUILDING PLUMBING SYSTEMS. ALL DRAIN LINES ARE PROVIDED AND INSTALLED BY DIV. 22.
7. KITCHEN EQUIPMENT CONTRACTOR IS RESPONSIBLE FOR PROVIDING ALL FAUCETS (WATER FILL FAUCETS, PRE-RINSE FAUCETS, ETC.), DRAIN FITTINGS, MIXING VALVES, CONTROL VALVES, WATER PRESSURE REGULATORS, VACUUM BREAKERS, AND ALL ACCESSORIES FOR EQUIPMENT SPECIFIED UNDER 11 40 00. DIVISION 22 IS RESPONSIBLE FOR INSTALLATION.
8. INDIRECT DRAIN LINE RUNS FROM EQUIPMENT TO NEAREST DRAIN OR FLOOR SINK. LINES TO BE TYPE 'K' COPPER.
9. IF ANY PLUMBING ACCESSORIES OR FITTINGS ARE PROVIDED LOOSE WITH EQUIPMENT BY 11 40 00, DIV. 22 IS TO ATTACH TO EQUIPMENT AND PROVIDE FINAL CONNECTION.
10. GAS SUPPLY SYSTEMS WITH ALL COMPONENTS AND FITTINGS AS REQUIRED FOR A COMPLETE SYSTEM.
11. WATER SUPPLY SYSTEMS WITH ALL COMPONENTS AND FITTINGS AS REQUIRED FOR A COMPLETE SYSTEM.
12. COMPRESSED AIR SYSTEMS WITH ALL COMPONENTS AND FITTINGS AS REQUIRED FOR A COMPLETE SYSTEM (IF REQUIRED FOR THIS PROJECT).
13. PIPING AND DRAINAGE SYSTEMS (SANITARY AND GREASE-LADEN). SYSTEMS MUST BE CLEANED AND FLUSHED BEFORE THE FINAL CONNECTION WITH FOOD SERVICE EQUIPMENT - CRITICAL.
14. FLOOR SINKS (PROVIDE AND INSTALL). FLANGE AND GRATES TO BE FLUSH WITH FINISHED FLOOR.
15. FLOOR DRAINS (PROVIDE AND INSTALL). FLANGE AND GRATES TO BE FLUSH WITH FINISHED FLOOR.
16. TRENCH DRAINS (PROVIDE AND INSTALL). TRENCH LINERS PROVIDED BY 11 40 00. FLANGE AND LINERS TO BE FLUSH WITH FINISHED FLOOR.
17. GREASE TRAPS AS REQUIRED. VERIFY WITH LOCAL CODES TO BYPASS OR PIPE THRU GREASE TRAP AND/OR INTERCEPTOR.
18. P-TRAPS AS REQUIRED (INCLUDING ALL DISPOSERS).
19. INTERCONNECT WATER THRU WATER FILTER (FILTER PROVIDED BY 11 40 00 UNLESS OTHERWISE SPECIFIED) TO EQUIPMENT.
20. GAS QUICK DISCONNECT INSTALLATION (QUICK DISCONNECT PROVIDED BY 11 40 00).
21. SAFETY RESTRAINT CABLE INSTALLATION (SAFETY RESTRAINT CABLE PROVIDED BY 11 40 00).
22. SPECIFIED COUPLINGS AND PIPING TO ALL EQUIPMENT FURNISHED BY 11 40 00.
23. AIR COMPRESSORS (IF REQUIRED FOR THIS PROJECT) (SIZE, PROVIDE, AND INSTALL, UNLESS OTHERWISE SPECIFIED).
24. WATER SOFTENERS (IF REQUIRED FOR THIS PROJECT) (SIZE, PROVIDE, AND INSTALL, UNLESS OTHERWISE SPECIFIED).
25. PRESSURE BOILERS (IF REQUIRED FOR THIS PROJECT) (SIZE, PROVIDE, AND INSTALL, UNLESS OTHERWISE SPECIFIED).
26. HAND SINKS (PROVIDE (UNLESS OTHERWISE SPECIFIED) AND INSTALL). PROVIDE HOT WATER TEMPERING VALVE IF REQUIRED. WATER TEMPERATURE TO BE AT LEAST 100 DEGREES AND FLOW FOR AT LEAST 20 SECONDS.
27. ICE BIN DRAIN INSULATION (IF ICE MACHINE IS PROVIDED IN THIS PROJECT) (PROVIDE AND INSTALL).
28. UNIONS AT DISPOSER SOLENOID VALVES (IF DISPOSER IS PROVIDED IN THIS PROJECT) (PROVIDE AND INSTALL).
29. BACK FLOW PREVENTION AS REQUIRED (PROVIDE AND INSTALL - INCLUDING ALL DISPOSERS). BACK- SIPHONAGE SHALL BE INSTALLED AT ALL FIXTURES AND EQUIPMENT WHERE BACKFLOW AND/OR BACK-SIPHONAGE MAY OCCUR AND WHERE A MINIMUM AIR GAP CANNOT BE PROVIDED BETWEEN THE WATER TO THE FIXTURE OR EQUIPMENT AT ITS FLOOD/LEVEL RIM. VACUUM BREAKERS, WHEN FURNISHED WITH EQUIPMENT, SHALL OVERRIDE THE ABOVE, IF ACCEPTABLE WITH APPLICABLE CODES. DIVISION 22 RESPONSIBLE FOR VERIFYING REQUIREMENT WITH LOCAL CODES.
30. JANITOR SINK WITH FAUCET (PROVIDE AND INSTALL).
31. FREEZE PROOF HYDRANT AT EXTERIOR OF BUILDING BY RECEIVING DOOR (PROVIDE AND INSTALL).
32. REVERSE OSMOSIS SYSTEMS (SIZE, PROVIDE (UNLESS OTHERWISE SPECIFIED), LOCATE AND INSTALL).
33. ALL PIPING WITHIN COUNTER BODY OR UNDER FABRICATED COUNTERS TO BE RUN TO A CONNECTION POINT BELOW COUNTER BODY BY SECTION 11 40 00. FINAL CONNECTION BY DIVISION 22.
34. EXHAUST HOOD CONDENSATE DRAIN CONNECTIONS (IF EXHAUST HOOD IS PROVIDED IN THIS PROJECT) (PROVIDE AND INSTALL).
35. INTERCONNECTION OF 1/2" CW TO PRE-RINSE AND DISPOSERS CONE/BODY INLETS PIPED THROUGH SOLENOID AND VACUUM BREAKER (IF DISPOSER IS PROVIDED IN THIS PROJECT).
36. FIRE SYSTEM PIPING. EXPOSED PIPING TO BE CHROME PLATED.
37. PIPE 1/2" COLD WATER TO SWIRL INLETS AT DISPOSERS (IF DISPOSER IS PROVIDED IN THIS PROJECT).
38. WATER TREATMENT FOR ICE BUILDERS (NON-CHLORINATED WATER WITH A PH LEVEL OF 10 OR HIGHER) AND ANY DRAINS AND OVERFLOWS. PIPING FROM ICE BUILDERS TO TUMBLE CHILLERS BY DIV. 23 (IF ICE BUILDERS AND TUMBLE CHILLERS ARE PROVIDED IN THIS PROJECT).

**NOTE: WATER AND DRAIN CONNECTIONS INDICATED ARE THOSE REQUIRED FOR THE FOOD SERVICE EQUIPMENT AND THOSE REQUIRED FOR SUPPORT EQUIPMENT FURNISHED BY DIVISION 22. FOR ADDITIONAL WATER AND DRAIN REQUIREMENTS REFER TO MECHANICAL DRAWINGS.**

**NOTE: REFER TO ELECTRICAL/MECHANICAL DRAWINGS FOR REQUIREMENTS OF EXHAUST FANS AND MAKE-UP AIR HANDLERS AND LOCATION OF AN INTERLOCK AND START/STOP CONTROLS TO BE LOCATED WITHIN FOOD SERVICE AREA BY DIVISION 26.**

4 PLUMBING COORDINATION NOTES
NOT TO SCALE

**DIVISION 23 (MECHANICAL) RESPONSIBLE FOR BUT NOT LIMITED TO:**

1. **DO NOT ROUGH-IN FROM FDP DRAWINGS. REFER TO THE KITCHEN EQUIPMENT CONTRACTOR'S DIMENSIONED SHOP DRAWINGS. DIMENSIONS INDICATED ARE TO BE VERIFIED BY KITCHEN EQUIPMENT CONTRACTOR AND ADJUSTED AS REQUIRED BY EQUIPMENT AND/OR FIELD CONDITIONS.**
2. SECTION 11 40 00 TO VERIFY UTILITY REQUIREMENTS OF ANY EXISTING EQUIPMENT.
3. ALL CONNECTIONS SHALL BE MADE FOLLOWING LOCAL CODES AND NATIONAL STANDARDS, EXCEPT WHERE PLANS AND SPECIFICATIONS EXCEED THOSE CODES AND STANDARDS.
4. VERIFY ALL MECHANICAL REQUIREMENTS WITH ENGINEERING DRAWINGS.
5. EMPTY EMT CONDUIT WITH PULL-WIRE AND WIDE-SWEEP BENDS FOR REFRIGERANT PIPING TO REMOTE FOOD SERVICE EQUIPMENT REFRIGERATION SYSTEMS.
6. ROUGH-IN AND FINAL CONNECTION OF MECHANICAL SYSTEMS TO FOOD SERVICE EQUIPMENT, WALK-IN ASSEMBLIES, AND BETWEEN COMPONENTS (INCLUDING MATERIALS AND LABOR).
7. TESTING AND BALANCING FOR ROOMS AND EXHAUST HOODS TO BE PERFORMED BY MECHANICAL CONTRACTOR. BALANCE REPORT FOR FOOD SERVICE EXHAUST HOODS TO BE PROVIDED TO FOODSERVICE DESIGN PROFESSIONALS (FDP) IMMEDIATELY UPON COMPLETION (SEND TO HOUSTON.SUBMITTAL@FDP.ORG FOR HOUSTON OFFICE AND DALLAS.SUBMITTAL@FDP.ORG FOR DALLAS OFFICE) AND MUST BE SUBMITTED WITH O&M MANUALS.
8. EXHAUST HOODS, CONDENSATE HOODS, FIRE SUPPRESSION SYSTEMS, CONNECTIONS AND CONTROLS (PROVIDE AND INSTALL – *UNLESS OTHERWISE SPECIFIED*). PROVIDE TEMPERED AIR AT ALL SUPPLY DUCTS.
   - A. IF EXHAUST/CONDENSATE HOODS AND FIRE SUPPRESSION SYSTEMS ARE SPECIFIED UNDER SECTION 11 40 00, DIVISION 23 IS RESPONSIBLE FOR ALL EXHAUST AND CONDENSATE HOOD CONNECTIONS (PROVIDE AND INSTALL).
9. VFD SYSTEM AND CONTROLLERS, WHEN REQUIRED BY CODE (PROVIDE AND INSTALL).
10. PROVIDE AND INSTALL ALL VENTILATION (DIRECT OR INDIRECT), AIR CONDITIONING AND HEATING SYSTEMS (UNLESS OTHERWISE SPECIFIED).
11. COORDINATE SUPPLY AND RETURN DUCTS ABOVE SERVING COUNTERS OR OPEN-AIR REFRIGERATED MERCHANDISERS. NO COLD AIR TO BLOW DIRECTLY ON HOT FOOD COUNTERS.
12. COORDINATE SUPPLY AND RETURN DUCTS AWAY FROM EQUIPMENT WITH TOP MOUNTED REFRIGERATION. NO COLD AIR TO BLOW DIRECTLY ON COMPRESSORS.
13. MECHANICAL CONTRACTOR TO LOCATE TEMPERATURE MONITORS WITHIN RETURN DUCTS.
14. CIRCULATING AIR ABOVE WALK-IN ASSEMBLIES (PROVIDE AND INSTALL).
15. CIRCULATING AIR ABOVE AND IN AIR GAPS AT WAREHOUSE COLD STORAGE ASSEMBLIES (PROVIDE AND INSTALL).
16. WATER CHILLERS AS REQUIRED (IF EQUIPMENT IS PROVIDED IN THIS PROJECT) (PROVIDE, SIZE AND LOCATE).
17. PIPING FROM ICE BUILDERS TO TUMBLE CHILLERS (IF EQUIPMENT IS PROVIDED IN THIS PROJECT) (PROVIDE, SIZE AND LOCATE).

3 MECHANICAL COORDINATION NOTES
NOT TO SCALE

**GENERAL CONTRACTOR RESPONSIBLE FOR BUT NOT LIMITED TO:**

1. ANY WALL PENETRATION REQUIRED FOR FOOD SERVICE EQUIPMENT UTILITIES. ESCUTCHEON PLATES OR S/S SLEEVES TO BE PROVIDED AND INSTALLED AS NEEDED.
2. BULK FREEZER VENTILATION PIPE (IF BULK FREEZER IS PROVIDED IN THIS PROJECT) (PROVIDE AND INSTALL, UNLESS OTHERWISE SPECIFIED).
3. CORE DRILLING FOR GUIDE RAILS (IF GUIDE RAILS ARE PROVIDED IN THIS PROJECT).
4. REFRIGERATION ROOF CURBS / ROOF JACK (IF REFRIGERATION SYSTEM IS PROVIDED IN THIS PROJECT AND LOCATED ON ROOF).
5. INTERIOR BOLLARDS (IF REQUIRED FOR THIS PROJECT) – TO BE EPOXY PAINTED PER LOCAL CODES (PROVIDE AND INSTALL).
6. FURNISH AND INSTALL 3/4" PLYWOOD BLOCKING IN THE WALL FOR MOUNTING EQUIPMENT FURNISHED BY SECTION 11 40 00 AS REQUIRED.
7. WALK-IN DEPRESSIONS (TO BE DEAD LEVEL) AND SAND LEVELING BED (IF WALK-IN IS PROVIDED IN THIS PROJECT AND RECESS IS SHOWN).
8. STRUCTURAL BRACING FOR BULK WALK-IN CEILING PANELS IF REQUIRED.
9. MENU SYSTEM VIDEO MONITORS IN SERVERY (UNLESS OTHERWISE SPECIFIED).
10. STRUCTURAL BRACING FOR MENU SYSTEM VIDEO MONITORS IF REQUIRED.
11. INTERIOR/EXTERIOR REFRIGERATION PENETRATIONS AND SLEEVES AT BUILDING PENETRATIONS.
12. DOORSCOPE VIEWER (PEEPHOLE) WITH WIDE VIEWING ANGLE AT RECEIVING DOOR.
13. CANOPY AT RECEIVING DOOR. COORDINATE HEIGHT WITH THE HEIGHT OF RECEIVING DOOR (8') AND THE MOUNTING HEIGHT OF AIR SCREEN ABOVE THE DOOR.
14. SOAP AND TOWEL DISPENSER PROVIDED BY OWNER. G.C. RESPONSIBLE FOR INSTALLATION.
15. WASHER AND DRYER (PROVIDE AND INSTALL, UNLESS OTHERWISE SPECIFIED).
16. DWARF WALL AT EXPOSED FRONT/ENDS OF CAFETERIA SERVING COUNTERS WITH FINISH AS SELECTED BY ARCHITECT (IF REQUIRED IN THIS PROJECT).

2 GENERAL CONTRACTOR COORDINATION NOTES
NOT TO SCALE

**HEALTH DEPARTMENT REQUIREMENTS (VERIFY WITH LOCAL JURISDICTIONS):**

1. FLOORS: VERIFY WITH DIVISION 9. FLOORS TO BE SMOOTH, IMPERVIOUS, EASILY CLEANABLE AND SLIP RESISTANT.
2. WALLS: VERIFY WITH ARCHITECTURAL DOCUMENTS. WALLS TO BE SMOOTH, IMPERVIOUS, AND EASILY CLEANABLE.
3. CEILING: LAY-IN TILES. CEILING TILES TO BE SMOOTH, IMPERVIOUS, AND EASILY CLEANABLE.
4. EMPLOYEE TOILET: TO BE LOCATED OFF MAIN CORRIDOR AND ADJACENT TO MAIN KITCHEN. RESTROOM MUST HAVE A VESTIBULE AND NOT OPEN TO KITCHEN / PREP AREAS. TOILETS TO BE WELL VENTILATED.
5. LAVATORIES: WALL HUNG LAVATORIES LOCATED WITHIN ALL FUNCTIONAL WORKING AREAS.
6. UTENSIL CLEANING/SANITIZING: ACCOMPLISHED IN UTENSIL WASH AREA WITH (3) 2'-0" x 2'-2" x 15" MINIMUM DEEP SINKS AND WAREWASH MACHINE.
7. MECHANICAL CLEANING/SANITIZING OF TABLEWARE: ACCOMPLISHED BY WAREWASH MACHINE.
8. STOREROOMS: AMPLE DAILY STORAGE PROVIDED IN ENCLOSED STORE ROOMS. STORE ROOMS TO BE VENTILATED AND MAINTAIN PROPER TEMPERATURE.
9. WATER HEATER: LOCATED IN THE MECHANICAL ROOM ADJACENT TO KITCHEN. TO BE SIZED TO PROVIDE AMPLE WATER TO MAINTAIN PROPER WATER TEMPERATURE THROUGHOUT HOURS OF OPERATION.
10. GREASE TRAP: LOCATED AT EXTERIOR OF BUILDING. REFER TO ENGINEER'S DRAWINGS.
11. FOOD SERVICE EQUIPMENT: ALL FLOOR-MOUNTED EQUIPMENT IS TO BE SEALED TO THE FLOOR TO PROVIDE AN EASILY CLEANABLE SURFACE AND PREVENT SEEPAGE. EQUIPMENT NOT MOUNTED TO THE FLOOR IS TO BE WALL MOUNTED ON WALL CARRIERS, OR ELEVATED ON LEGS TO PROVIDE AT LEAST A SIX-INCH CLEARANCE BETWEEN FLOOR AND EQUIPMENT.
12. MOP SINK: LOCATED IN JANITOR CLOSET OFF MAIN KITCHEN CORRIDOR, AND LOCATED IN CLOSE PROXIMITY TO THE SERVERY WAREWASH AREA.
13. EXHAUST HOODS: EXHAUST HOODS PROVIDED OVER COOKING EQUIPMENT WITH LIQUID CHEMICAL ANSUL FIRE EXTINGUISHING SYSTEM.
14. LIGHTING AND PROTECTIVE SHIELDING: RECESSED CEILING-MOUNTED FLUORESCENT LIGHT FIXTURES FITTED WITH CLEAR LEXAN DIFFUSERS.
15. GARBAGE AND REFUSE: CENTRAL TRASH COLLECTION PROVIDED FOR BUILDING LOCATED NEAR RECEIVING AREA ON SMOOTH CONCRETE SURFACE.
16. POISONOUS AND TOXIC MATERIAL STORAGE: LOCATED IN RESPECTIVE JANITOR CLOSETS WITH LOCKING HARDWARE.

1 HEALTH DEPARTMENT COORDINATION NOTES
NOT TO SCALE

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
THE ITEMS APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 48854119 ON 07/15/2025



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

FS GENERAL COORDINATION NOTES

J-QF0.0

| FOOD SERVICE DRAWING INDEX | |
|---|---|
| FDP SHEET NUMBER | FDP SHEET NAME |
| J-QF0.0 | FS GENERAL COORDINATION NOTES |
| J-QF1.0 | FS EQUIPMENT PLAN |
| J-QF1.1 | FS FACILITY MODEL |
| J-QF1.2 | FS EQUIPMENT MODEL |
| J-QF1.3 | FS SPECIAL CONDITIONS & MECHANICAL PLAN |
| J-QF1.4 | FS PLUMBING PLAN |
| J-QF1.5 | FS ELECTRICAL PLAN |
| J-QF1.6 | FS CONDENSING UNITS |
| J-QF1.7 | FS WALK-INS |
| J-QF1.8 | FS SERVING COUNTERS |
| J-QF1.9 | FS SERVING COUNTERS |
| J-QF2.0 | FS DEMO PLAN |
| J-QF2.1 | FS TEMPORARY SERVING |
| J-QF3.1 | FS ELEVATIONS |
| J-QF4.1 | FS SECTIONS & DETAILS |
| J-QF4.2 | FS DETAILS |
| J-QF4.3 | FS DETAILS |




1 FOOD SERVICE EQUIPMENT PLAN
1/4" = 1'-0"

| FOOD SERVICE EQUIPMENT SCHEDULE | | | | | |
|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR GENERAL CONTRACTOR & HEALTH DEPARTMENT COORDINATION NOTES | | | | | |
| FDP ITEM | FDP QTY | FDP DESCRIPTION | FDP REMARKS | MANUFACTURER | MODEL |
| 101 | 1 | AIR SCREEN | | MARS | STD248-1UA-OB |
| 102 | 1 | COLD STORAGE ASSEMBLY | | AMERICAN PANEL | |
| 103.1 | 1 | COLD STORAGE REFRIGERATION SYSTEM | | RDT | ZS1-02Z-CT3-AST |
| 104 | 2 | COLD STORAGE SHELVING | | METRO | METROMAX Q |
| 107 | 1 | DRY STORAGE SHELVING | | METRO | METROMAX Q |
| 108 | 1 | CAN RACK | | NEW AGE | 1250CK |
| 109 | 1 | ICE MACHINE W/ BIN | | MANITOWOC | UYF0310A |
| 110 | 1 | CLOTHES WASHER | | WHIRLPOOL | RESIDENTIAL |
| 110A | 1 | CLOTHES DRYER | | WHIRLPOOL | RESIDENTIAL |
| 111W | 1 | WALL MOUNTED OVERSHELF | | CUSTOM FABRICATED | |
| 122 | 1 | TWO COMPARTMENT SINK WITHOUT DISPOSER | | CUSTOM FABRICATED | |
| 123 | 1 | DISPOSER - 3HP | | SALAVHOR | 300-CA-18-ARSS-LD |
| 125 | 1 | 20 QT. MIXER W/STAND | | CUSTOM FABRICATED | |
| 128 | 4 | UTILITY CART | | LAKESIDE | 522 |
| 129 | 3 | WORKTABLE W/S.BAR UT.RACK | | CUSTOM FABRICATED | |
| 138 | 4 | PAN RACK | | CRES COR | 207-UA-13A |
| 139 | 1 | INSUL MOBILE PROOFER | | CRES COR | H-137-WSUA-12D |
| 151 | 2 | FIRE PROTECTION SYSTEM | | ANSUL | R102 |
| 152 | 1 | EXHAUST HOOD | EXISTING | | |
| 153 | 1 | EXHAUST HOOD | EXISTING | | |
| 161 | 2 | CONVECTION OVEN | | BLODGETT | 200-DFG DBL |
| 165 | 1 | TWO BURNER RANGE | | VULCAN | V2B18B |
| 172 | 1 | COMBI OVEN | | RATIONAL | ICP 6-FULL/6-FULL N/G |
| 186 | 2 | PASS-THRU HEATED CABINET-1DR | | TRAULSEN | AHF132WP |
| 188 | 2 | PASS-THRU REFRIGERATOR-1DR | | TRAULSEN | AHT132WPUT |
| 201M.1 | 1 | SERVING COUNTER-MODULAR | | COUNTERCRAFT | SCOL-408-MOD |
| 209 | 2 | DROP FRONT MILK COOLER - 8 CASE | | TRAULSEN | RMC34D4 |
| 214 | 2 | CASH REGISTER | OWNER FURNISHED | | |
| 249 | 1 | THREE COMPARTMENT SINK NO DISPOSER | | CUSTOM FABRICATED | |
| 250 | 1 | DISHMACHINE | | HOBART | CL44-BAS |
| 254 | 2 | SOILED & CLEAN DISHTABLE | | CUSTOM FABRICATED | |
| 255 | 2 | MOBILE DRYING RACK | | METRO | PR48VX3 |
| 260 | 4 | HAND SINK | FURNISHED & INSTALLED BY DIV. 22 | | |
| 614 | 1 | FILL FAUCET | | T&S | B-0610 |
| 615 | 2 | MENU MONITOR | BY OWNER | | |
| 800 | 1 | 15 GAL. BRAISING PAN | | GROEN | BPM-15GA |
| 801 | 1 | S/S CORNER GUARDS | LOCATED ON EVERY EXPOSED CORNER THROUGHOUT KITCHEN | CUSTOM FABRICATED | |
| 802 | 1 | WALL BUMPERS | LOCATED ON ALL EXPOSED BUILDING WALLS | PAWLING | MD-1 |
| 803 | 1 | WATER SOFTENER | | HOBART | WS-40 |
| 804 | 1 | S/S SPLASH GUARDS | | CUSTOM FABRICATED | |

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL

FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
ELECTRONICALLY APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO: 48854119 ON: 07/15/2025



ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

FS EQUIPMENT PLAN

J-QF1.0

ISOMETRIC VIEWS WITHIN THIS DRAWING ARE NOT TO SCALE AND ARE PROVIDED FOR REFERENCE PURPOSES ONLY. ISOMETRIC VIEWS ARE NOT INTENDED FOR REGULATORY APPROVAL, PERMITTING, NOR CONSTRUCTION. REFER TO FLOOR PLANS AND DETAILS FOR SPECIFIC PROJECT INFORMATION.



1 FS FACILITY MODEL

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL

FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
THIS ITEM BEARING ON THIS SHEET WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 48854119 ON: 07/15/2025



ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

FS FACILITY MODEL

J-QF1.1

ISOMETRIC VIEWS WITHIN THIS DRAWING ARE NOT TO SCALE AND ARE PROVIDED FOR REFERENCE PURPOSES ONLY. ISOMETRIC VIEWS ARE NOT INTENDED FOR REGULATORY APPROVAL, PERMITTING, NOR CONSTRUCTION. REFER TO FLOOR PLANS AND DETAILS FOR SPECIFIC PROJECT INFORMATION.



1 FS EQUIPMENT MODEL

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL

FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
RELEASE FOR PERMITTING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 48854119 ON: 07/15/2025



ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

FS EQUIPMENT MODEL


J-QF1.2

| FOOD SERVICE MECHANICAL SCHEDULE | | | | | | |
|---|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR MECHANICAL COORDINATION NOTES | | | | | | |
| FDP NO. | FDP QTY | FDP TYPE | FDP SIZE | FDP LOC | FDP CFM | FDP S.P. |
| M101 | 1 | EXHAUST | 4" X 16" | | 400 | 0.30" |
| M102 | 1 | EXHAUST | 4" X 16" | | 800 | 0.30" |
| M103 | 1 | DRYER VENT | 6" DIA. | | --- | --- |





1 FOOD SERVICE SPECIAL CONDITIONS PLAN
1/4" = 1'-0"

NOTE:
SECTION 11 40 00 TO COORDINATE FINAL LOCATION AND SIZE OF WALL BLOCKING.





5 WALL BLOCKING DETAIL
NOT TO SCALE


NOTE:
SECTION 11 40 00 TO COORDINATE FINAL LOCATION OF ALL TRENCH LINERS WITH EQUIPMENT POUR PATH.




6 TRENCH LINER DETAIL
NOT TO SCALE





3 COLD STORAGE ASSEMBLY ENCLOSURE PANEL DETAIL
NOT TO SCALE




COLD STORAGE ASSEMBLY REFRIGERATION SYSTEM GROUND MOUNT 4" PLATFORM DETAIL
4 NOT TO SCALE

SLAB TO BE MODIFIED AS REQUIRED TO ALLOW FOR A 4 1/2" DEPRESSION SLAB. PROVIDE NEW LEVEL CONCRETE PAD FOR COLD STORAGE ASSEMBLY.




WALL SECTION @ EXTERIOR DOOR

2 COLD STORAGE ASSEMBLY 4 1/2" DEPRESSION DETAIL
NOT TO SCALE

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FDP
FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
THIS ITEM IS APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 48854119 ON: 07/18/2025


ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

FS SPECIAL CONDITIONS & MECHANICAL PLAN

J-QF1.3

| FOOD SERVICE PLUMBING SCHEDULE | | | | | | |
|---|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR PLUMBING COORDINATION NOTES | | | | | | |
| FDP PNO | FDP PSIZE | FDP PCONN | FDP PSERVICE TO | FDP PLOC | FDP PAFF | FDP PREMARKS |
| P5 | 3/4" | H & C WATER | JANITOR SINK | WALL | 48" | JANITOR SINK BY PLUMBER |
| P6 | 4" | FLOOR DRAIN | JANITOR SINK | FLOOR | VERIFY | JANITOR SINK BY PLUMBER |
| P7 | 3/4" | H & C WATER | HOSE BIBB | WALL | 18" | BTC |
| P10 | VERIFY | FLOOR DRAIN | GENERAL AREA DRAIN | FLOOR | VERIFY | --- |
| P11C | 1/2" | H & C WATER | FAUCET | WALL | 18" | FURNISHED & INSTALLED BY DIV. 22 |
| P11D | 1 1/2" | DIRECT DRAIN | HAND SINK | WALL | 15" | FURNISHED & INSTALLED BY DIV. 22 |
| P12 | VERIFY | FLOOR DRAIN | EQUIP. DRAIN | FLOOR | VERIFY | NO SLOPE |
| P15 | 4" | FLOOR DRAIN | FUNNEL FLOOR DRAIN | FLOOR | 0" | --- |
| P109 | 3/4" | COLD WATER | WATER/ ICE | WALL | 60" | BTC |
| P109A | 12" SQ. | FLOOR SINK | ICE MACHINE | FLOOR | 0" | FULL GRATE |
| P110 | 3/4" | H & C WATER | CLOTHES WASHER | WALL | 48" | BTC; VALVE BOX |
| P110A | 2" | INDIRECT DRAIN | CLOTHES WASHER | WALL | 48" | VALVE BOX |
| P122 | 3/4" | H & C WATER | FAUCET | WALL | 13" | BTC |
| P122A | 12" SQ. | FLOOR SINK | SINK | FLOOR | 0" | 3/4 GRATE |
| P123 | 3/4" | H & C WATER | FAUCET / DISPOSER | WALL | 13" | BTC |
| P123A | 2" | DIRECT DRAIN | DISPOSER | WALL | 10" | BTC |
| P161 | (2)3/4" | NATURAL GAS | CONVECTION OVEN | WALL | 18"/36" | BTC - 60 MBTU/HR EACH |
| P163A | 3/4" | NATURAL GAS | TILT BRAISING PAN | WALL | 18" | BTC - 65 MBTU/HR |
| P163B | 3/4" | H & C WATER | TILT BRAISING PAN | WALL | 36" | BTC |
| P165 | 1" | NATURAL GAS | RANGE | WALL | 18" | BTC - 70 MBTU/HR |
| P172 | (2)3/4" | COLD WATER | COMBI OVEN | WALL | 24"/48" | BTC - INTERCONNECT THRU FILTERS |
| P172A | 3/4" | COLD WATER | COMBI OVEN | WALL | 48" | BTC |
| P172B | 12"SQ. | FLOOR SINK | EQUIPMENT | FLOOR | 0" | 3/4 GRATE |
| P172C | (2)3/4" | NATURAL GAS | COMBI OVEN | WALL | 18"/36" | BTC - 105 MBTU/HR EACH |
| P172D | 3/4" | COLD WATER | COMBI OVEN | WALL | 66" | BTC; INTERCONNECT TO P172 |
| P172E | 3/4" | COLD WATER | COMBI OVEN WATER FILTER | WALL | 66" | BTC |
| P249 | 3/4" | H & C WATER | FAUCET | WALL | 13" | BTC |
| P249A | 12" SQ. | FLOOR SINK | SINK | FLOOR | 0" | THREE QUARTER GRATE |
| P250 | 12" SQ. | FLOOR SINK | BOOSTER / DISHMACHINE | FLOOR | 18" | BTC |
| P250A | 3/4" | HOT WATER | DISHMACHINE | WALL | 18" | EXT. THRU W.FILTER TO BOOSTER / DISH MACHINE - 140DEG.MIN. |
| P250B | 3/4" | COLD WATER | DISHMACHINE | WALL | 18" | BTC |
| P614 | 1/2" | H & C WATER | FILL FAUCET | WALL | 42" | BTC |
| P800 | 12" SQ. | FLOOR SINK | EQUIPMENT | FLOOR | 0" | 3/4 GRATE |




1 FOOD SERVICE PLUMBING PLAN
1/4" = 1'-0"

SECTION 11 40 00 TO PROVIDE LOOSE WITH FOOD SERVICE EQUIPMENT. INSTALLATION BY DIV. 22 & 26.


- (A) VACUUM BREAKER
- (B) DISPOSER
- (C) TIME DELAY
- (D) CONTROL PANEL
- (E) SOLENOID VALVE

DIVISION 22 TO PROVIDE AND INSTALL


- (F) 1/2" CW INLET
- (G) FLOW CONTROL
- (H) 1/2" CW
- (I) 2" DRAIN LINE WITH P-TRAP & Y ADAPTOR
- (J) 1-1/2" TAILPIECE
- (K) GATE VALVE
- (L) 1/2" CW SUPPLY
- (M) SHOCK STOP
- (N) RPZ BACK FLOW PREVENTOR

DIVISION 26 TO PROVIDE AND INSTALL


- (O) POWER SUPPLY





6 DISPOSER WITH VACUUM BREAKER DETAIL
NOT TO SCALE





7 EXHAUST HOOD - GAS LINE ROUTING DETAIL
NOT TO SCALE




3 GAS DISCONNECT DETAIL
NOT TO SCALE




5 DRAIN PIPING FASTENER DETAIL
NOT TO SCALE




8 WAREWASH - PERFORATED OVER SHELF DETAIL
NOT TO SCALE

| | | | | | |
|---|---|---|---|---|---|
| ○ | HW | HOT WATER | ⊡ | FFD | FUNNEL FLOOR DRAIN |
| ○ | CW | COLD WATER | ◣ | EVC | EXHAUST VENT CONNECTION |
| ○ | HTW | 180 F HOT WATER | ⋈ | SVC | SUPPLY VENT CONNECTION |
| ◎ | | CHILLED WATER | ◔ | FR | DIRECT-CONNECTED FLUE RISER |
| ● | W | DIRECT WASTE | ◍ | PS | PIPE SLEEVE |
| ○ | IW | INDIRECT WASTE | ⊙ | | COMPRESSED AIR |
| ⊙ | | GAS SUPPLY | ♦ | | CO2 |
| ◕ | | STEAM SUPPLY | | AFF | ABOVE FINISHED FLOOR |
| ⊗ | CR | CONDENSATE RETURN | | BTC | BRANCH TO CONN. ON EQUIP |
| ◉ | DR | DRAIN | | DFA | DROP FROM ABOVE |
| □ | FD | FLOOR DRAIN | | CLG | CEILING |
| ▟ | FST | FLOOR SINK 3/4 GRATE | | | |
| ▟ | FSH | FLOOR SINK 3/4 GRATE | | | |

2 PLUMBING SYMBOLS
NOT TO SCALE

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FDP
FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
THIS ITEM IS ELECTRONICALLY SIGNED AND SEALED BY MELISSA MOORE, FCSI NO: 48854119 ON: 07/15/2025


ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

FS PLUMBING PLAN


J-QF1.4

| FOOD SERVICE ELECTRICAL SCHEDULE | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR ELECTRICAL COORDINATION NOTES | | | | | | | | |
| FDP ENO | FDP ECONN | FDP ELOAD | FDP EVOLT | FDP EPH | FDP ESERVICE TO | FDP ELOC | FDP EAFF | FDP EREMARKS |
| E10 | DR | 16.0A | 120 | 1 | CONVENIENCE | WALL | 24" | MOUNT HORIZONTAL |
| E13 | WPR | 16.0A | 120 | 1 | CONVENIENCE | WALL | 24" | MOUNT HORIZONTAL |
| E15 | JB | --- | --- | --- | FIRE PROT. SYSTEM | WALL | 48" | RECESSED EMPTY CONDUIT FOR FIRE PULL |
| E101 | JB | 5.1A | 120 | 1 | AIR SCREEN | WALL | 82" | BTC; MAGNETIC REED SWITCH ON DOOR JAMB & DOOR |
| E102A | JB | 16.0A | 120 | 1 | DOOR HEATER/LIGHTS | CLG | DFA | BTC |
| E102B | JB | 5.0A | 120 | 1 | TEMP. ALARM | CLG | DFA | BTC |
| E102C | JB | 5.0A | 120 | 1 | PRESSURE RELIEF PORT | CLG | DFA | BTC |
| E102E | JB | 10.0A | 120 | 1 | PANIC ALARM BUTTON | CLG | DFA | BTC-INTERCONNECT TO STROBE LIGHT/HORN ABOVE FREEZER DOOR AND IN CAFETORIUM |
| E103 | JB/DS | 38.4A | 208 | 3 | REFRIGERATION SYSTEM | VERIFY | VERIFY | BTC - WEATHERPROOF DISCONNECT SWITCH |
| E103C | JB | 13.7A | 208 | 1 | FREEZER COIL | CLG | DFA | BTC |
| E103D | JB | 1.8A | 120 | 1 | COOLER COIL | CLG | DFA | BTC |
| E103E | JB | --- | --- | --- | DATA CONNECTION | CLG | DFA | BTC; RUN TO NEAREST IDF / MDF ROOM |
| E103F | JB | 16.0A | 120 | 1 | DRAIN LINE HEATER | CLG | DFA | BTC; DEDICATED CIRCUIT |
| E109 | DR | 11.9A | 120 | 1 | ICE MACHINE | WALL | 60" | --- |
| E110 | DR | 16.0A | 120 | 1 | CLOTHES WASHER | WALL | 48" | -- |
| E110A | SR | 30.0A | 208 | 1 | CLOTHES DRYER | WALL | 48" | VERIFY NEMA PLUG RECEPTACLE |
| E123 | JB | 3.0HP | 208 | 3 | DISPOSER | WALL | 24" | BTC; CONNECT THRU C.P. TO DISPOSER |


| FOOD SERVICE ELECTRICAL SCHEDULE | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR ELECTRICAL COORDINATION NOTES | | | | | | | | |
| FDP ENO | FDP ECONN | FDP ELOAD | FDP EVOLT | FDP EPH | FDP ESERVICE TO | FDP ELOC | FDP EAFF | FDP EREMARKS |
| E129 | DCR | 16.0A | 120 | 1 | TABLE RECEPTACLE | CLG | 84" | TWISTLOCK PLUG & RECEPTACLE |
| E139 | DCR | 15.0A | 120 | 1 | INSUL. MOBILE PROOFER | CEILING | DFA | -- |
| E151 | JB | 1.0A | 120 | 1 | FIRE PROT. SYSTEM | CLG | DFA | BTC |
| E161 | (2)DR | 6.0A EA. | 120 | 1 | CONVECTION OVEN | WALL | 24"/48" | SHUNT TRIP BREAKER |
| E163 | DR | 5.0A | 120 | 1 | TILT BRAISING PAN | WALL | 24" | SHUNT TRIP BREAKER |
| E172 | (2)JB | 15.0A EA. | 208 | 1 | COMBI OVEN | WALL | 24"/48" | BTC; RE: NOTE #4- SHUNT TRIP BREAKER |
| E187 | JB | 15.5A | 120/208 | 1 | HEATED CABINET | WALL | 96" | BTC; MOUNT ON KITCHEN SIDE |
| E188 | JB | 7.2A | 120 | 1 | REFRIGERATOR | WALL | 96" | BTC; MOUNT ON KITCHEN SIDE-OMIT PLUG, UNIT TO BE HARDWIRED |
| E201A | PMR | 28.0A | 208 | 1 | HOT FOOD COUNTER | FLOOR | 4.5" | BTC |
| E201B | PMR | 16.0A | 120 | 1 | COLD FOOD COUNTER | FLR | 4.5" | --- |
| E209 | PMR | 8.0A | 120 | 1 | DROP FRONT MILK COOLER-8 CASE | FLR | 4.5" | --- |
| E214 | PMR | 16.0A | 120 | 1 | CASH REGISTER | FLR | 4.5" | DEDICATED CIRCUIT |
| E214A | CS | --- | --- | --- | POS | FLOOR | 6" | BTC; CONDUIT W/DATA LINE TO RUN TO MANAGER'S OFFICE OR IDF ROOM-VERIFY |
| E250 | JB/DS-JB | 51.7A | 480 | 3 | DISHMACHINE | WALL | 66" | BTC; EXTEND FROM JB/DS AT NEAREST WALL |
| E615 | DR | 5.0A | 120 | 1 | VIDEO / DATA SYSTEM | CLG | VERIFY | PROVIDE DCO AT VIDEO LOCATION |
| E615A | JB | --- | --- | --- | VIDEO / DATA SYSTEM | CLG | VERIFY | PROVIDE JB AT DATA LOCATION |





1 FOOD SERVICE ELECTRICAL PLAN
1/4" = 1'-0"





6 COLD STORAGE ASSEMBLY ENTRAPMENT PANIC ALARM DETAIL
NOT TO SCALE





3 PEDESTAL MOUNTED RECEPTACLE DETAIL
NOT TO SCALE




4 FIRE PROTECTION SYSTEM TYPICAL DETAIL
NOT TO SCALE




5 FIRE PROTECTION SYSTEM RECESSED FIRE PULL DETAIL
NOT TO SCALE

| | | | | | |
|---|---|---|---|---|---|
| | SCR | CONDUIT STUB BTC ON RECEPT FURNISH WITH EQUIPMENT | | CC | CONDUIT FOR COMPUTER CABLES |
| • | CS | CONDUIT STUB UP/OUT FOR DIRECT CONNECTION | | BTC | BRANCH TO CONNECTION ON EQUIPMENT |
| | DR | DUPLEX RECEPTACLE | | WPR | WATERPROOF RECEPTACLE (SPRING COVER) |
| | SR | SINGLE PURPOSE RECEPTACLE-1PH | | FPB | FIRE PROTECTION BUZZER |
| | SR | SINGLE PURPOSE RECPTACLE-3PH | | BSC | BEVERAGE SYSTEM CONDUIT |
| | FR | FLUSH FLOOR RECEPTACLE | | DFA | DROP FROM ABOVE |
| | PMR | PEDESTAL MOUNTED RECEPTACLE | | AFF | ABOVE FINISH FLOOR |
| | DCR | DROP CORD RECEPTACLE | | CS/JB | JUNCTION BOX ON PEDESTAL |
| | JB | JUNCTION BOX ON CEILING | | SW | SWITCH |
| | JB | JUNCTION BOX IN WALL | | D | DATA |
| | JB/DS | JUNCTION BOX WITH DISCONNECT BY DIV.26 | | | |

2 ELECTRICAL SYMBOLS
NOT TO SCALE

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
DOCUMENT ADMINISTRATIVELY AUTHORIZED BY MELISSA MOORE, FCSI NO. 48854119 ON: 07/15/2025



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

FS ELECTRICAL PLAN

J-QF1.5

**MODEL NO. ZS1-02Z-CT3-EST OUTDOOR AIR COOLED REFRIGERATION SYSTEM**
**ITEM NO. 103**




NOTE:
- CRANKCASE HEATERS
- FAN CYCLING SWITCH
- COATED CONDENSERS
- HEADMASTER CONTROLS
- (2) DOOR SENSORS (SHIPPED LOOSE)

RACK WEIGHT: 775 LBS.

# ENGINEERING SUMMARY

**POWER SUPPLY: 208-230/60/3**
**CONNECTED LOAD: 38.4 AMPS**

**MOPD: 65 AMP**
**MINIMUM CIRCUIT AMPACITY: 44.4**

| SYSTEM | FIXTURES: ITEM # | DESCRIPTION | TEMP °F: FIXT. | TEMP °F: SUCT. | REQ'D FIXTURE BTU/H | REFRIG. R- | CONDENSING UNIT: COMPRESSOR: MODEL NO. | RATING @ 60 HZ: RLA | V | PH | BTU CAP @ AMB °F: 110 | TYPE | REC. CAP. (lbs) | CONDENSER | EVAPORATOR COILS: ITEM # | MODEL NO. | QTY | FAN MOTORS @ 60 HZ: RLA | V | PH | HEATERS @ 60 HZ: RLA | V | PH | DEFR. TYPE | DEFROST CONTROLLER TYPE | CONTROLLER QTY | ACCESSORIES: TSTAT | SOL. VALVE | EXP. V.LV. | CHECK V.LV. | SHUT-OFF V.LV. | REFRIGERANT LINE SIZES (IN): SUCT. | SUCT. LINE RISER | LIQUID | LINE RUN (FT) | TYPE | TOTAL SYSTEM LOAD |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| A | 102 | W/I COOLER | 35 | 25 | 16420 | 454A | YS17KSE | 10.6 | 208 | 3 | 20000 | Z | 14.0 | L1R | 103 | BEL0155 | 1 | 2.7 | 115 | 1 | | | | O.C. | ECOSMART | 1 | F | F | EF | L | L | 7/8 | 7/8 | 3/8 | 100 | M | 10.6 |
| B | 102 | W/I FREEZER | -10 | -20 | 16521 | 454A | YF19KAE | 27.8 | 208 | 3 | 20600 | Z | 44.0 | L5R | 103 | BEL0170 | 1 | 2.0 | 208 | 1 | 18.3 | 208 | 1 | ELEC | ECOSMART | 1 | F | F | EF | L | L | 1-1/8 | 1-1/8 | 3/8 | 100 | M | 27.8 |

ALL EVAPORATOR COILS WILL REQUIRE A HOUSE POWER SUPPLY

c UL us LISTED

NOTE:
IT IS THE INSTALLING CONTRACTORS RESPONSIBILITY TO FOLLOW ALL APPLICABLE CODES AND CURRENT REFRIGERATION INDUSTRY STANDARDS AND PRACTICES WHEN DETERMINING LINE SIZES, AND INSTALLING AND STARTING UP RDT EQUIPMENT.


COMPRESSOR TYPE
Z SCROLL
H HERMETIC
S SEMI-HERMETIC
D DISCUS

DEFROST TYPE
O.C. OFF CYCLE
ELEC ELECTRIC

LINE TYPE
M MAIN - UP TO 100'
B BRANCH - UP TO 50'
T TRUNK - UP TO 200'

EVAPORATOR ACCESSORIES
EF EEV FACTORY EQUIPPED ON EVAP
TF TXV FACTORY EQUIPPED ON EVAP
F FACTORY EQUIPPED ON EVAP
O PROVIDED BY OTHERS
L LOOSE (FIELD INSTALLATION)


## PLANVIEW/ CLEARANCE REQUIREMENTS




NOTE: MINIMUM CLEARANCE REQUIRED FOR PROPER OPERATION


NOTE: ROOF CURB OR GROUND PAD CAN BE SAME SIZE AS OUTDOOR UNIT

## SUCTION LINE VERTICAL RISE DETAIL




- Install trap every transition from horizontal to vertical.
- Insulate suction lines with 3/4" wall Armaflex insulation.
- All joints brazed with minimum 15% silver content brazing rod.
- Install "P" trap on suction line every 15' vertical rise.
- Not to exceed 45' vertically over all.
- *If compressor is above the evaporator, Install inverted trap on top of the rise to prevent oil from seeping down when fixture(s) is turned off.

## EVAPORATOR DETAILS - MODEL BEL




| AIR DEFROST Size | DIMENSIONS A | B | C | D | CONNECTIONS (Inches) Coil Inlet | Suction | Drain | Approx. Net Wt. lbs. | ELECTRICAL DATA Qty. Motors | EC Motor Fan Amps 115V | 208V |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | Inches | Inches | Inches | Inches | | | | | | | |
| 155 | 61-1/2 | 49-3/4 | - | - | 1/2 OD | 7/8 OD | 3/4 MPT | 67 | 3 | 2.7 | 1.5 |

| ELECTRIC DEFROST | DIMENSIONS A | B | C | D | CONNECTIONS (Inches) Coil Inlet | Suction | Drain | Approx. Net Wt. lbs. | ELECTRICAL DATA Qty. Motors | EC Motor Fan Amps | Heater Amps as wired for 208-230/60/1 | 208-230/60/3 | 460/60/3 |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Inches | Inches | Inches | Inches | | | | | | | | | |
| 170 | 77-1/2 | 65-1/4 | - | - | 1/2 OD | 7/8 OD | 3/4 MPT | 91 | 4 | 2.0 | 18.3 | 11.4 | 9.1 |

EACH EVAPORATOR COIL:
- EQUIPPED WITH TWO LEAK SENSORS, PRE-MOUNTED AND PRE-WIRED
- SUPPLIED WITH A LIQUID LINE SHUT-OFF VALVE AND SUCTION LINE CHECK VALVE, SHIPPED LOOSE FOR FIELD INSTALL OUTSIDE OF COMPARTMENTS AND NO MORE THAN 10' FROM EVAPORATOR COIL.

## ZS SERIES ENGINEERING SPECIFICATIONS

Multi compressor, outdoor, air cooled. The refrigeration package shall be a pre-engineered and factory-assembled unit, trade name "ZS", as manufactured by Refrigeration Design Technologies, 1808 FM Road 66, P.O. Box 622, Waxahachie, Texas 75168. Phone: (972) 937-3215; Fax: (972) 937-0970.

1. Air-Cooled Refrigeration System
The RDT UL Listed "Air-Cooled" Refrigeration system shall be housed in a weather-protected compact powder coated steel frame. The entire housing shall be brushed stainless steel. The unit shall include an air-cooled aluminum fin copper tube condenser designed to operate at 15 degrees TD. The exterior housing shall feature stainless steel one piece louvers. Lifting points shall be integrated in the framing component. Condenser fan motors shall be mounted within the enclosure. The condenser intake surface shall be protected with stainless steel expanded metal guard to protect against vandalism and hail damage.

Each unit shall be equipped with a ball-bearing fan motor, suction filter, sight glass, liquid filter/drier, liquid line inlet and outlet valve, defrost cycle and high pressure super-hose connections. Each unit shall be equipped with fan cycling controls and/or head pressure regulator where required for low ambient conditions.

Condensing unit shall contain scroll, hermetic, semi-hermetic, and/or discus type compressor(s) assembled to operate with the refrigerant specified for both medium and low temperature applications.

2. Evaporator Coils
A. Evaporator coils shall be direct expansion type fabricated of copper tubes with aluminum fins.
B. All evaporator coils shall be provided with solenoid valve, thermostatic or electronic expansion valve and thermostat.

3. Pre-Piping
All refrigerant lines shall be extended to outside of the housing in a neat and orderly manner. All tubing shall be securely supported and anchored with non-corrosive coated clamps.

All joints must be brazed, not soldered.

All piping and controls shall be factory pressure-tested with dry nitrogen.

4. Control Panel
The package shall have a factory-mounted and pre-wired control panel, with main disconnect (non fused) where required, circuit breakers, contactors wired for single point power connection.

General Information
Contractors shall verify all dimensions onsite and coordinate with other trades.

General contractor shall prepare the platform, curbed openings and weatherproofing the unit after installation.

Refrigeration Contractor
All copper tubing to be refrigerant grade. A.C.R. or type "L".

Brazing should be used for all refrigerant piping. Silver solder or soft solder is not acceptable.

All piping to be pressure tested with nitrogen at 300 psi. After the condensing unit and coil have been connected the balance of the system shall be leak tested with the valves open at 200 psi.

The complete system shall be evacuated with a vacuum pump. Each unit should be charged tested and adjusted to assure operation.

Contractor should provide and install the drain-line heater in freezer. Heater shall be connected by electrical contractor. Seal all penetrations through the walk-in units with foam.

Electrical Contractor
Electrical contractor to provide power for refrigeration package and connect control and defrost system as called for in the wiring diagram.


Electrical contractor to connect drain-line heater in the freezer.

All electrical wiring and installation shall be in accordance with the wiring diagram and local codes. Seal all penetrations through the walk-in units with foam.

Plumbing Contractor
Plumbing contractor to provide copper drain lines for walk-in refrigerator and freezer, pitched 1/4" per foot of run. Trap drain-line outside of refrigerated space to avoid entrance of warm, moist air.


All plumbing installation shall be in accordance with local codes.

## EVAPORATOR MOUNTING DETAIL (TYPICAL)




| COIL MODEL | DISTANCE FROM WALL |
|---|---|
| BEL | 1-1/3"H |
| BEM/BEH | 1/2 " W |


## EVAPORATOR PLACEMENT & CLEARANCE REQUIREMENTS LOW PROFILE EVAPORATOR COILS (I.E. - BEL)




## WIRING DIAGRAM - ECOSMART - AKEA1AE DEMAND DEFROST W/KE2 DOOR SWITCH FOR WALK-IN COOLER WITH ONE COIL 115/60/1

*REFERENCE ENGINEERING SUMMARY FOR COIL AMP DRAW:

| ITEM | DESCRIPTION | VOLTAGE |
|---|---|---|
| 103 | W/I COOLER | 115/1 |





FACTORY WIRING ———
FIELD WIRING - - - - -

## WIRING DIAGRAM - ECOSMART - AKEB1EE DEMAND DEFROST W/KE2 DOOR SWITCH FOR WALK-IN FREEZER WITH ONE COIL 208-230/60/1

*REFERENCE ENGINEERING SUMMARY FOR COIL AMP DRAW:

| ITEM | DESCRIPTION | VOLTAGE |
|---|---|---|
| 103 | W/I FREEZER | 208/1 |




FACTORY WIRING ———
FIELD WIRING - - - - -

**APPROVAL STATUS**

THIS DRAWING REPRESENTS OUR UNDERSTANDING OF THE SPECIFICATIONS. PLEASE REVIEW IT CAREFULLY FOR ACCURACY. CLEARLY AND IN DETAIL NOTE CHANGES REQUIRED.

MARK APPROPRIATE BOX, SIGN, AND DATE BELOW.

☐ APPROVED FOR FABRICATION NO CHANGES
☐ APPROVED FOR FABRICATION WITH CHANGES NOTED
☐ REVISE AND RE-SUBMIT DRAWING

BY: _____ DATE: _____

**NOTICE**

THIS DRAWING BEING AN INSTRUMENT OF SERVICE IS AND WILL REMAIN PROPERTY OF REFRIGERATION DESIGN TECHNOLOGIES AND CANNOT BE USED WITHOUT WRITTEN AUTHORIZATION.

| No. | Revision/Issue | Date |
|---|---|---|
| 0 | ORIGINAL ISSUE | 3/31/22 |
| 1 | CHANGES PER NEW MOUNTING LOCATION AND CONDENSER REQUIREMENTS | 1/27/25 |
| 2 | A2L COMPLIANT | 7/16/25 |


REFRIGERATION DESIGN TECHNOLOGIES
1808 FM Road 66 / P.O. Box 622
Waxahachie, Texas
(800) 736-9518
www.rdtonline.com


Consultant:
Foodservice Design Professionals
The Woodlands, TX

Dealer
-
-

**Highland Hills Elementary School**
**San Antonio, TX**

Project No: 27251
Designed By: L. Aguirre
Drawn By: L. Aguirre

Sheet 1.1 of sheets

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478


SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
FCSI 48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
ITEMS APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 48854119 ON: 07/15/2025



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING


FS CONDENSING UNITS

J-QF1.6






COOLER DOOR ELEVATION




DOOR ELECTRICAL CONNECTION




TRIM ANGLE
DETAIL #3




PANEL MOUNTED ELECTRICAL CONNECTION

~SPECIFICATIONS~

BOX HEIGHT: FREEZER – 10'-2" OVERALL (7'-6 1/4" INTERIOR)
COOLER – 10'-2" OVERALL (7'-6 1/4" INTERIOR)

CONSTRUCTION: FOAMED IN PLACE
NSF LISTED, STANDARD NO. 7

INSULATION: 4" URETHANE, FINISHED PANEL
UL CLASSIFIED FLAME SPREAD 20
CORE SMOKE DEVELOPED 250

INSTALLATION: INDOOR

FLOOR: (SEE DETAILS)
FREEZER – STANDARD W/AMERITUFF STRUCTURAL FLOOR
(1/8" INTEGRAL DIAMOND ALUMINUM TREAD PLATE,
3/4" MARINE PLYWOOD UNDERLAYMENT, FIBERGLASS GRATING SUPPORT)
COOLER – STANDARD W/36" DEEP INTERIOR RAMP & AMERITUFF STRUCTURAL FLOOR
(1/8" INTEGRAL DIAMOND ALUMINUM TREAD PLATE,
3/4" MARINE PLYWOOD UNDERLAYMENT, FIBERGLASS GRATING SUPPORT)

DOOR HARDWARE & ACCESSORIES: (EACH DOOR)
SMOOTH POLISHED DOOR HARDWARE
POWER TO BE STUBBED OUT CEILING PANEL
DRY CONTACT LEADS TO BE STUBBED OUT CEILING PANEL IN A SEPARATE STUB OUT
DEADBOLT HANDLE W/KEYED CYLINDER LOCK, PADLOCK
PROVISION & QUARTER TURN INSIDE RELEASE (EXTERIOR DOOR ONLY)
1/8" STAINLESS STEEL THRESHOLD COVER PLATE
14 GA STAINLESS STEEL SUB THRESHOLD
FRAME HEATER WIRE
HYDRAULIC DOOR CLOSER
IC+ WALK-IN DOOR CONTROLLER AND ALARM SYSTEM INCLUDING:
INTEGRATED LIGHT SWITCH WITH AUTOMATIC LIGHT OFF AND 3-WAY & 4-WAY CAPABILITY
TEMPERATURE MONITOR AND LOGGER WITH HIGH TEMP. AND LOW TEMP. VISUAL AND AUDIO ALARM
F OR C TEMPERATURE SELECTION
INTEGRATED DRY CONTACT FOR ALARM SIGNALING & POWER FAILURE (1A @ 24VAC, 1A @ 30VDC)
DOOR AND WINDOW HEATER CONTROL (WHEN SO EQUIPPED)
HACCP PREVIEW VIA ONBOARD LCD SCREEN
HACCP DOWNLOAD VIA USB
WIFI CONNECTIVITY (INTERNET ENABLED WIFI NETWORK NEEDED)
BATTERY BACKUP
TEMPERATURE ALARM NOTIFICATION VIA EMAIL &/OR EMAIL TO SMS TEXT MESSAGES
POWER FAILURE NOTIFICATION VIA EMAIL &/OR EMAIL TO SMS TEXT MESSAGES
(FOR THIS FEATURE TO WORK THE LOCAL WIFI NETWORK MUST BE
POWER PROTECTED AND WORKING AT THE TIME OF POWER FAILURE EVENT)
AUTOMATIC AND ON DEMAND TRANSMISSION OF HACCP DATA VIA EMAIL
ADAPTIVE SETTINGS
MOMENTARY BACK-TO-BACK LIGHT SWITCH W/PILOT
25' AIR TEMPERATURE PROBE
25' SECOND PROBE (EXTENDED) FOR MONITORING THE TEMPERATURE AT
A SECOND LOCATION OR FOR MONITORING A SECOND CABINET
DOOR SWITCH TO ENABLE DOOR AJAR ALARM, DOOR AJAR NOTIFICATION VIA EMAIL &/OR
EMAIL TO SMS TEXT MESSAGES, AND AUTOMATIC LIGHTS ON WHEN DOOR OPENS
PANIC ALARM WITH ILLUMINATED PANIC BUTTON, ALARM BUZZER WITH LED,
& NOTIFICATION VIA EMAIL &/OR EMAIL TO SMS TEXT MESSAGES (1-COOLER, 2-FREEZER)
KASON SCREW-IN VAPOR PROOF LIGHT FIXTURE
W/8.5 WATT SYLVANIA LED BULB & GLOBE
CCI CLEAR VU SWINGING DOOR
3 – KASON #1346 ADJUSTABLE SPRING LOADED HINGES
HEATED VISION WINDOW (14" x 24")
1/8" DIAMOND ALUMINUM TREAD PLATE KICKPLATES @ 36" HIGH I/S & O/S DOOR & FRAME
KASON 1826 INTELLO-VENT WITH LIGHTS (FREEZER DOOR ONLY) – FIELD INTERCONNECTION REQUIRED

PANEL MOUNTED ACCESSORIES:
1 – KASON 1826 INTELLO-VENT WITH LIGHTS – FIELD INTERCONNECTION REQUIRED
(FOAMED IN PANEL – PER PLAN) (COOLER ONLY)

ACCESSORIES: (SHIPPED LOOSE)
2 – PCS. TRIM ANGLE – 18 GA STAINLESS STEEL, #3 FINISH
CLOSURE PANEL TO AN EXISTING CEILING (PER PLAN) — **VERIFY LENGTH**
18 GA STAINLESS STEEL, #3 FINISH
2 – 48" (1810LC) LED LIGHT FIXTURE(S) @ 40W EACH (LIGHTS TO BE INSTALLED PERPENDICULAR TO COILS)
1/8" DIAMOND ALUMINUM TREAD PLATE WAINSCOT @ 36" HIGH (EXPOSED EXTERIOR ONLY)
1 – 1/8" DIAMOND ALUMINUM TREAD PLATE CORNER GUARD(S) @ 36" HIGH
ALUMINUM COVED BASE MOLDING (COMPLETE INTERIOR ONLY)
ROOF SUPPORT ANGLE W/SEALITY TRIM
2 – BAKELITE LABEL(S) (BLACK) ("FREEZER", "COOLER")
1 – BAKELITE LABEL (YELLOW W/BLACK LETTERING) ("VACUUM PRESSURE RELIEF")
6 MIL POLYETHYLENE VAPOR BARRIER
5 – BELL BOX(ES) & COVER PLATE(S)
2 – DOOR STOP(S)
2 – EDWARDS 860 SERIES STROBE BEACONS
1 – EMERGENCY PRESSURE RELEASE

METAL FINISHES: INTERIOR & EXTERIOR DOOR & FRAME – 18 GA STAINLESS STEEL, #3 FINISH
INTERIOR WALLS & CEILING – WHITE .040 STUCCO ALUMINUM
EXPOSED EXTERIOR – 20 GA STAINLESS STEEL, #3 FINISH
UNEXPOSED EXTERIOR – 26 GA STUCCO ACRYLUME
EXTERIOR FLOOR – 26 GA STUCCO ACRYLUME
EXTERIOR ROOF – 26 GA STUCCO ACRYLUME
INTERIOR FLOOR – AMERITUFF STRUCTURAL FLOOR
(1/8" INTEGRAL DIAMOND ALUMINUM TREAD PLATE,
3/4" MARINE PLYWOOD UNDERLAYMENT, FIBERGLASS GRATING SUPPORT)

REFRIGERATION: BY OTHERS

NOTE: THE LARGEST DOOR PANEL ON THIS JOB IS 57.5" x 114.5".
NOTE: THE LARGEST ROOF/FLOOR PANEL ON THIS JOB IS 46.5" x 129".
CUSTOMER IS TO VERIFY THAT THIS PANEL SIZE WILL NOT CONFLICT WITH ANY JOB SITE RESTRICTIONS.


NOTE: CUSTOMER IS TO VERIFY ALL DIMENSIONS, SECTIONS, DETAILS AND SPECIFICATIONS.

NOTE: MAXIMUM LIGHT CIRCUIT LOAD IS 1200W 120VAC TUNGSTEN, 5A 120VAC ELECTRONIC BALLAST. FOR HIGHER LOADS ADDITIONAL LIGHT FIXTURES MUST BE CONTROLLED VIA RELAY (BY OTHERS).


| ELECTRICAL DATA |
|---|
| ⏚ = POINT OF ELECTRICAL CONNECTIONS. |
| WALK-IN DOORS: 115v/1ø – 350w* |
| PANEL MOUNTED ACC: 115v/1ø – 23w (EACH VENT) |

*NOTE: ADD WATTAGE FOR EACH ADDITIONAL LIGHT FIXTURE IN ACCESSORIES.


**ITEM #102 WALK-IN COOLER/FREEZER**





SECTION E – E





SECTION K – K




TRIM ANGLE
DETAIL #2




CLOSURE PANEL ABOVE WALK-IN DETAIL #4E




DETAIL "A" WAINSCOT AT INTERIOR CORNER

American Panel's walk-in floor panels with AmeriTuff structural support are designed to withstand uniformly distributed stationary loads of 15,000 lbs. per square foot. American Panel's warranty does not cover damage caused by pallet jacks, forklifts or any other form of heavy-duty rolling traffic. A concrete wearing floor must be installed on top of the AmeriTuff walk-in floor panels for those rolling applications.

| INSULATION R-VALUES | | |
|---|---|---|
| PANEL TYPE | COOLER | FREEZER |
| 4" WALLS, ROOFS | R-29 | R-32 |
| 5" WALLS, ROOFS | R-36 | R-40 |
| FLOORS | R-25 | R-28 |
| DOORS | R-32 | |

| COOLER DOOR | |
|---|---|
| DOOR FRAME KWHr/DAY | 2.424 |

| FREEZER DOOR | |
|---|---|
| DOOR FRAME KWHr/DAY | 4.392 |

| WALK-IN PANEL R-8967 | | |
|---|---|---|
| BUILDING UNITS | R-8967 | 37M2 |
| **USA** | | |
| SURFACE BURNING CHARACTERISTICS | | |
| MATERIAL DETAILS | "FLAME SPREAD" | "SMOKE DEVELOPED" |
| ALUMINUM PANELS, PAINTED OR UNPAINTED, 5" OR LESS | 15 | 350 |
| "GALVANIZED STEEL OR STAINLESS STEEL PANELS, PAINTED OR UNPAINTED, 5" OR LESS" | 10 | 400 TO 500 |
| CORE MATERIAL, 6" THICK | 20 | 250 |

AMERICAN PANEL WALK-IN COOLERS AND FREEZERS COMPLY WITH THE 2021 INTERNATIONAL ENERGY CONSERVATION CODE (IECC), SECTION C403.11

THIS AMERICAN PANEL WALK-IN WILL BE MANUFACTURED TO UL & NSF REQUIREMENTS. AMERICAN PANEL ACCEPTS NO LIABILITY FOR LOCAL CODE REQUIREMENTS OF WHICH AMERICAN PANEL HAS NOT BEEN MADE AWARE OF IN WRITING PRIOR TO FABRICATION.

1) Please verify that door swing and location are correct.

2) If this walk-in is to be installed in a depression, or quarry tile is to be applied to the interior, depression depths or tile thickness must be specified to insure proper door height.

3) All site preparation, floor or slab construction, plumbing, electrical connections (including control wiring) by others.

4) ⏚ Electrical: 115-60-1 required above latch side of each door, through ceiling, to operate frame heater and light.

5) Special note to General Contractor and his Sub Contractor for quarry tile or concrete wearing floors: the sheet metal panel facings may be susceptible to staining due to excessive moisture created by hydration of concrete type materials. Therefore, it is absolutely necessary that each room be properly ventilated. Also note that special precautions must be taken when using muriatic acid due to effects hydrochloric acid fumes have on aluminum and stainless steel.

6) This drawing and information contained herein are the exclusive property of American Panel Corporation. It shall be returned to American Panel Corporation upon demand and shall not be reproduced in whole or part, disclosed to anyone else, or used without the written consent of American Panel Corporation.

☐ APPROVED
☐ APPROVED AS NOTED
☐ REVISE & RESUBMIT
SIGNATURE _____
PRINT NAME _____
DATE _____

| REV. | DATE | DESCRIPTION | REV. BY | CHK'D BY |
|---|---|---|---|---|
| A | 1/22/25 | REVISED LAYOUT, SPECS; ADDED DETAIL | DH | WQ |

American Panel — AMERICAN PANEL CORPORATION
5800 S.E. 78th St. Ocala, Florida 34472
Ph. (352) 245-7055 Fax (352) 245-0726

CUSTOMER: FOODSERVICE DESIGN PROFESSIONALS
PROJECT: HIGHLAND ES-FBISD – FORT BEND, TX
DATE: 10/7/24 | DRAWN BY: LC/TR | P.O.#:
SCALE: 3/8"=1'-0" | PROPOSAL#: PD213252 | JOB#: | SHEET: 1 of 1

ALL DIMENSIONS MUST BE FIELD VERIFIED PRIOR TO FABRICATION AND INSTALLATION

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FDP
FOODSERVICE DESIGN PROFESSIONALS

# FBISD BP 013 KITCHEN RENOVATIONS
## FORT BEND INDEPENDENT SCHOOL DISTRICT
## HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478


SEAL
CONSERVICE CONSULTANTS
MELISSA MOORE
FCSI
488584119
SOCIETY INTERNATIONAL
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
THIS DOCUMENT APPEARING ON THIS SHEET WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 488584119 ON: 07/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

FS WALK-INS


J-QF1.7




## 3 MECHANICAL ROOF FLOOR PLAN

SCALE: 1/8" = 1'-0"


NORTH




## 2 RENO MECHANICAL FLOOR PLAN - KITCHEN AREA

SCALE: 1/8" = 1'-0"

NORTH




## 1 DEMO MECHANICAL FLOOR PLAN - KITCHEN AREA

SCALE: 1/8" = 1'-0"

NORTH

## AIR DEVICE SCHEDULE

| MARK | DESCRIPTION |
|---|---|
| A | CEILING DIFFUSER – 24" X 24" FACE, PATTERN TYPE, STEEL CONSTRUCTION, OBD/RADIATION DAMPER, WHITE FINISH, U.L. LISTED PRICE SCD A1–12" X 12" |
| B | CEILING RETURN GRILLE – 24" X 24" PERFORATED FACE, STEEL CONSTRUCTION, RADIATION DAMPER, WHITE FINISH, U.L. LISTED PRICE PDFR B1–12" X 12" |
| C | CEILING EXHAUST GRILLE – 24" X 24" PERFORATED FACE, STEEL CONST., OBD/RADIATION DAMPER, WHITE FINISH, NECK SIZE SHOWN, U.L. LISTED PRICE PDDR C1–12" X 12" |

NOTES:

1. REFER TO ARCHITECTURAL REFLECTED CEILING PLAN TO VERIFY CEILING TYPES FOR AIR DEVICES.

## KITCHEN HOOD REFURBISHMENT NOTES

HOOD REFURBISHMENT FOR KITCHEN HOODS (QUANTITY 2):

- STEAM WASH AND DEEP CLEAN STAINLESS STEEL HOOD ASSEMBLY, CASING, AND SUPPLY GRILLES WHERE APPLICABLE.
- REPLACE GREASE FILTER RACKS.
- CLEAN EXISTING MAKE-UP AIR AND GREASE EXHAUST DUCT.
- RELAMP EXISTING LIGHT FIXTURES WITH NEW 4000K BULBS LISTED FOR USE IN AN ENCLOSED KITCHEN HOOD FIXTURE.
- COORDINATE WITH DIVISION 11 FOR REPLACEMENT OF ANSUL FIRE SUPPRESSION SYSTEM.
- HOOD ASSEMBLIES SHALL BE CLEANED TO MEET THE STANDARDS ESTABLISHED IN NFPA STANDARD 96.

## KITCHEN HOOD EXHAUST & MAKE-UP AIR UNIT SCHEDULE

| MARK | ESF-1,2 |
|---|---|
| SERVES | KITCHEN HOOD-1 & 2 |
| **SUPPLY SECTION** | |
| TYPE | INDIRECT GAS-FIRED MAKE-UP AIR UNIT |
| DRIVE | DIRECT |
| SPEED CONTROL | VFD |
| SUPPLY CFM | 2250 |
| EXT. S.P. (IN. W.G.) | 0.375 |
| HORSEPOWER (WATTS) | 1-1/2 HP |
| VOLTAGE | 480V/3-PHASE |
| UNIT MCA | 4.6 A |
| UNIT MOCP | 15 A |
| HEATING MEDIUM | NATURAL GAS |
| INPUT/OUTPUT (MBH) | 150.0/121.5 |
| TURNDOWN RATIO | 4:1 |
| MANUFACTURER | GREENHECK |
| MODEL | IGX-P109-H12-MF-E |
| **EXHAUST SECTION** | |
| TYPE | UPBLAST BELT DRIVE CENTRIFUGAL |
| EXHAUST CFM | 3600 |
| EXT. S.P. (IN. W.G.) | 0.75 |
| HORSEPOWER (WATTS) | 1-1/2 HP |
| VOLTAGE | 480V/3-PHASE |
| UNIT MCA | 3.75 A |
| UNIT MOCP | 15 A |
| MANUFACTURER | GREENHECK |
| EXHAUST FAN MODEL | CUBE-200-15 |

NOTES

1. EXHAUST FAN: PROVIDE FAN WITH PRE-FABRICATED ROOF CURB ADAPTER, VENTED CURB EXTENSION, HINGING KIT, HEAT BAFFLE, DRAIN CONNECTION, GREASE TRAP, AND DISCONNECT SWITCH. FANS SHALL BE UL LISTED FOR USE WITH TYPE 1 GREASE HOOD.
2. EXHAUST FAN: PROVIDE NEW MOTOR STARTER, SIZED FOR EXHAUST FAN MOTOR AND INSTALLED IN PLACE OF EXISTING. REFERENCE THE SPECIFICATIONS FOR STARTER REQUIREMENTS. COORDINATE WITH DIV.25 FOR RE-TERMINATION OF PERMISSIVE ON/OFF CONTROL. COORDINATE WITH DIV.26 FOR RE-TERMINATION OF LOCAL HOOD SWITCH INTERLOCK FOR START/STOP CONTROL.
3. SUPPLY FAN/FURNACE: FLUE GAS FROM HEATING COIL SHALL BE POWER VENTED.
4. SUPPLY FAN/FURNACE: WEATHERHOOD WITH ALUMINUM MESH.
5. SUPPLY FAN/FURNACE: 5 YEAR HEAT EXCHANGER WARRANTY.
6. SUPPLY FAN/FURNACE CONTROLS: INTEGRAL HEATER CONTROLS WITH BAS INTERLOCK FOR PERMISSIVE ON/OFF AND LOCAL SWITCH INTERLOCK FOR CONTROL FROM KITCHEN HOOD SWITCH. FURNACE CONTROLS SHALL BE PROGRAMMED FOR 64°F LAT, WITH A LOCKOUT FOR O/A TEMPERATURES ABOVE THE LAT SETPOINT. COORDINATE WITH DIV.25 AND DIV.26 FOR CONTROLS AND SWITCH INTERLOCKS.
7. TWO POINT POWER CONNECTION: ONE FOR EXHAUST FAN AND ONE FOR INTAKE/SUPPLY FAN.
8. INTERLOCK FAN(S) WITH ASSOCIATED COOKING HOOD
9. INTERLOCK FAN WITH SWITCH ON KITCHEN HOOD.
10. UNIT TO BE PROVIDED WITH GALVANIZED STEEL FAN PACK EXTENSION/COMBINATION CURB.
11. REFER TO WRITTEN SPECS FOR ADDITIONAL REQUIREMENTS.

## MECHANICAL RENO KEYED NOTES

1. TIE-IN NEW DUCTWORK TO EXISTING DUCTWORK AT WALL PENETRATION.
2. CONNECT NEW AIR DEVICE AND TAP TO EXISTING E/A TRUNK DUCT.
3. REWORK EXISTING EXHAUST AND SUPPLY DUCTWORK FROM EXISTING KITCHEN HOOD UP TO FAN, AS REQUIRED, WITH NEW TRANSITIONS AND SUPPLY AIR DUCTWORK OFFSETS TO MATE WITH NEW FAN CURB.
4. EXISTING ELECTRIC DUCT HEATER TO BE RETAINED FOR RE-INSTALLATION IN RENOVATION PHASE.
5. NEW DRYER VENT DUCT AND VENT CAP.
6. TEMP. KITCHEN – CEILING MOUNTED CABINET EXHAUST FAN.
7. TEMP. KITCHEN – 24"X24" SIDE WALL GRILLE. SURFACE MOUNT OPTIONAL. AUXILIARY FRAME. TITUS CT-700.
8. RECONFIGURE DUCTWORK TO CONNECT TO NEW DISHMACHINE HOOD OUTLETS. REF. KITCHEN CONSULTANT DRAWINGS FOR EXACT DIMENSIONS OF DUCT CONNECTIONS.
9. CONDENSATE EXHAUST DUCT UP THROUGH ROOF TO NEW EXHAUST FAN SET ON NEW ROOF CURB. REUSE EXISTING ROOF PENETRATION.

## MECHANICAL DEMO KEYED NOTES

1. DEMOLISH EXISTING AIR DEVICE, BRANCH DUCT, DAMPER AND TAP BACK TO TRUNK DUCT. CAP AND SEAL RESULTING OPENING.
2. EXISTING E/A TRUNK DUCT TO REMAIN.
3. DISCONNECT EXISTING S/A AND E/A DUCTWORK SERVING KITCHEN HOODS FROM FAN ASSEMBLY ON ROOF. DEMOLISH SUPPLY AND EXHAUST FAN PLENUM ASSEMBLY SERVING KITCHEN HOODS, ALONG WITH CURB. NEW CURB TO BE PROVIDED AND INSTALLED AS PART OF RENOVATION.
4. DEMOLISH ALL EXISTING AIR DEVICES, DUCTWORK, AND DUCTWORK ACCESSORIES SERVING KITCHEN AREA BACK TO MECH. ROOM WALL PENETRATION.
5. EXISTING ELECTRIC DUCT HEATER TO BE RETAINED FOR RE-INSTALLATION IN RENOVATION PHASE.
6. REFURBISH EXISTING KITCHEN HOOD. REFER TO "KITCHEN HOOD REFURBISHMENT NOTES".
7. DEMOLISH AND REPLACE EXISTING DRYER EXHAUST DUCT AND FLUE VENT CAP.
8. DEMOLISH EXISTING CONDENSATE HOOD, ASSOCIATED DUCTWORK, AND ROOF EXHAUST FAN.

## EXHAUST FAN SCHEDULE

| MARK | EF-TK | EF-CF | EF-14 |
|---|---|---|---|
| SERVES | TEMPORARY KITCHEN | COOLER/FREEZER | DISH WASHER |
| TYPE | CEILING CABINET | INLINE FAN | ROOF UPBLAST |
| DRIVE | DIRECT | DIRECT | DIRECT |
| SPEED CONTROL | INTEGRAL SPEED CONTROLLER | CONSTANT | CONSTANT |
| CFM | 1055 | 1000 | 1200 |
| EXT. S.P. (IN. W.G.) | 0.3 | 0.35 | 0.60 |
| IMP. SIZE (IN.) | 8.0 | 13.5 | |
| HORSEPOWER (WATTS) | 1/3 HP | 1/6 HP | 1/6 HP |
| VOLTAGE | 120V/1-PHASE | 120V/1-PHASE | 120V/1-PHASE |
| MANUFACTURER | COOK | COOK | COOK |
| MODEL | GC-862 | 1355QN10D | CUE-140-VG |
| SONES (MAX.) | 15.0 | 15.0 | 15.0 |
| NOTES | 1 THRU 4 | 1 THRU 4 | 1 THRU 4 |

NOTES

1. STATIC PRESSURE SHOWN IS EXTERNAL TO THE UNIT. MANUFACTURER SHALL ADD DAMPER AND ACCESSORY LOSSES TO THIS VALUE BEFORE SELECTING FAN. FANS SHALL BE CAPABLE OF 120% OF THE SCHEDULED CFM CAPACITY.
2. INTEGRAL DISCONNECT SWITCH.
3. RUBBER IN-SHEAR ISOLATORS.
4. REFER TO WRITTEN SPECS FOR ADDITIONAL REQUIREMENTS.


ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL

STATE OF TEXAS
TYLER W. HERRING
106052
LICENSED PROFESSIONAL ENGINEER
07.18.2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

KITCHEN AREA MECHANICAL PLANS
J-M1.01

STANTON ENGINEERING GROUP
INFORMATION@STANTON-ENG.COM | (713) 300-4080
TEXAS ENG. FIRM REG. NO. F-8183 | © 2025 ALL RIGHTS RESERVED
13915 N. SAM HOUSTON PARKWAY S., SUITE 175, HOUSTON, TX 77060

## MECHANICAL SYMBOL SCHEDULE

| | |
|---|---|
| CWS | CONDENSER WATER SUPPLY |
| CWR | CONDENSER WATER RETURN |
| CHS | CHILLED WATER SUPPLY |
| CHR | CHILLED WATER RETURN |
| HWS | HEATING WATER SUPPLY |
| HWR | HEATING WATER RETURN |
| RS | REFRIGERANT SUPPLY |
| RR | REFRIGERANT RETURN |
| D | CONDENSATE LINE |
| | PETE'S PLUG |
| | ISOLATION VALVE |
| | ELECTRONIC CONTROL VALVE |
| | BUTTERFLY VALVE |
| | BALL VALVE |
| | UNION OR FLANGE |
| | STRAINER |
| | AUTOMATIC AIR VENT |
| T | LOCAL CONTROL THERMOSTAT |
| T | TEMPERATURE SENSOR |
| H | HUMIDITY SENSOR |
| FD | FIRE DAMPER |
| SD | SMOKE DAMPER |
| FSD | FIRE/SMOKE COMBINATION DAMPER |
| MD | MOTORIZED DAMPER |
| C | CARBON MONOXIDE SENSOR |
| CO2 | CARBON DIOXIDE SENSOR |
| | SUPPLY AIR DIFFUSER |
| | RETURN AIR GRILLE |
| | EXHAUST GRILLE |
| RA | RETURN AIR OPENING IN WALL |
| VD | VOLUME DAMPERS |
| | DUCT ELEVATION CHANGE |
| | 90° DUCT ELBOW WITH TURNING VANES |
| | FLEXIBLE DUCT |
| M | DAMPER MOTOR |
| T | TEMPERATURE TRANSMITTER |
| FS | FLOW SWITCH |
| P | DIFFERENTIAL PRESSURE SENSOR |
| SD | DUCT SMOKE DETECTOR |
| PS | STATIC PRESSURE SENSOR |
| PH | STATIC PRESSURE SENSOR HI-LIMIT |
| AP | ACCESS PANEL |

| | |
|---|---|
| A.P. | ACCESS PANEL |
| AHU | AIR HANDLING UNIT |
| B | BOILER |
| CH | CHILLER |
| CHP | CHILLED WATER PUMP |
| CVT | CONSTANT VOLUME TERMINAL |
| DH | DEHUMIDIFIER |
| E/A | EXHAUST AIR |
| EF | EXHAUST FAN |
| F&B | FACE & BYPASS |
| FF | FLY FAN |
| HDT | HORIZONTAL DRAW THROUGH |
| HWP | HOT WATER PUMP |
| KEF | KITCHEN EXHAUST FAN |
| KSF | KITCHEN SUPPLY FAN |
| O/A | OUTSIDE AIR |
| OBD | OPPOSED-BLADES DAMPER |
| PT | PRE-TREAT |
| R/A | RETURN AIR |
| RAHU | ROOF-MOUNTED AIR HANDLING UNIT |
| S/A | SUPPLY AIR |
| SA | SOUND ATTENUATOR |
| SF | SUPPLY FAN |
| SPD | SPILTER DAMPER |
| SZ | SINGLE ZONE |
| VAV | VARIABLE AIR VOLUME |
| VB | VAV BOX |
| VD | VOLUME DAMPER |
| VDT | VERTICAL DRAW THROUGH |
| VFD | VARIABLE FREQUENCY DRIVE |
| WH | WATER HEATER |
| ⌀ | DESIGNATION FOR "ROUND" |
| ⌀ | DESIGNATION FOR "OVAL" |

## GENERAL MECHANICAL NOTES


1. REFER TO WRITTEN SPECIFICATIONS FOR ADDITIONAL INFORMATION.
2. COORDINATE INSTALLATION OF EQUIPMENT AND PIPING WITH THE ELECTRICAL CONTRACTOR TO INSURE NEC CLEARANCE (42 INCHES) IN FRONT OF ALL ELECTRICAL PANELS. DO NOT INSTALL DUCTWORK OR WATER PIPING OVER THE TOP OF ELECTRICAL PANELS SEE DETAIL 1/M2.01.
3. DUCT SIZES SHOWN ARE NET FREE AIR PASSAGE DIMENSIONS, DUCTS ARE NOT LINED, BUT ARE EXTERNALLY INSULATED. RUNOUTS TO CEILING OUTLETS SHALL BE EXTERNALLY INSULATED GALVANIZED SHEET METAL WITH SPIN-IN V.D. AT TRUNK TAPS, SEE DETAIL 1 & 2/M2.01.
4. REFER TO ARCHITECTURAL REFLECTED CEILING DRAWINGS FOR EXACT LOCATIONS OF CEILING OUTLETS IN RELATION TO OTHER CEILING ENTITIES. OUTLETS MUST BE COMPATIBLE WITH THE CEILING TYPES FOR THE VARIOUS AREAS.
5. IN AREAS WHERE SUPPLY AIR ENTERS CEILING CAVITY THRU RETURN AIR GRILLES AND FREE RETURNS TO AHU'S VIA CEILING CAVITY, PROVIDE RETURN AIR OPENING IN WALL-TO-DECK ABOVE CEILING THAT BLOCK PATH, REFER TO ARCHITECTURAL DRAWINGS. RETURN AIR ELBOWS SHALL BE SIZED AT 1 SQ. FT PER 400 CFM SUPPLY AIR.
6. ARRANGE PIPING CONNECTIONS TO ALL EQUIPMENT TO ALLOW EASY REMOVAL OF EQUIPMENT, SUB-ASSEMBLIES, COILS, FANS, MOTORS, FILTERS, ACCESS PANELS, ETC... PROVIDE UNIONS, FLANGES AND VALVES AT CONNECTIONS. PROVIDE AND INSTALL VICTAULIC JOINTS AT COILS, REF. SPECIFICATIONS. PLACE STOP VALVES ON SYSTEM SIDE OF REMOVABLE PIPE SECTIONS.
7. CONTRACTOR SHALL FIELD MEASURE STRUCTURAL ELEMENTS AND COORDINATE EQUIPMENT, PIPING AND DUCT ROUTING TO FIT EXISTING CONSTRUCTION. PROVIDE OFFSETS, BOOTS FOR ENVELOP OBSTRUCTIONS THAT CANNOT BE AVOIDED. CONSTRUCTION SHALL BE PER SMACNA FIGURE 2-10.

## AIR DEVICE SCHEDULE

| MARK | DESCRIPTION |
|---|---|
| A | CEILING DIFFUSER – 24" X 24" FACE, PATTERN TYPE, STEEL CONSTRUCTION, OBD/RADIATION DAMPER, WHITE FINISH, U.L. LISTED PRICE SCD |
| B | CEILING RETURN GRILLE – 24" X 24" PERFORATED FACE, STEEL CONSTRUCTION, RADIATION DAMPER, WHITE FINISH, U.L. LISTED PRICE PDFR |
| C | CEILING EXHAUST GRILLE – 24" X 24" PERFORATED FACE, STEEL CONST., OBD/RADIATION DAMPER, WHITE FINISH, NECK SIZE SHOWN, U.L. LISTED PRICE PDDR |

NOTES:

1. REFER TO ARCHITECTURAL REFLECTED CEILING PLAN TO VERIFY CEILING TYPES FOR AIR DEVICES.
2. ALL CEILINGS ARE FIRE RATED PER U.L. LISTINGS ON ARCHITECTURAL DRAWINGS. PROVIDE FIRE PROTECTION FOR ALL CEILING DEVICES PER DETAIL 13/M-17 AND SPECIFICATIONS.





### 6 KITCHEN UPBLAST EXHAUST FAN DETAIL

NO SCALE

NOTES

1. ARCHITECTURAL ROOF CURB INSTALLATION REQUIREMENTS SHALL SUPERCEDE THIS DETAIL.
2. INSTALL SHEETMETAL COVERING OVER WOOD BLOCKING IN THE AIRSTREAM OR OPEN TO THE CEILING CAVITY.





### 5 AIR DEVICE DETAIL

NO SCALE

NOTES:

1. RADIATION DAMPER SHALL ONLY BE PROVIDED IN CEILING DEVICES INSTALLED IN RATED CEILING ASSEMBLIES. REFER TO ARCHITECTURAL REFLECTED CEILING PLAN TO DETERMINE WHICH, IF ANY, CEILINGS ARE RATED.
2. REFER TO SPECIFICATIONS OF FOR ADDITIONAL INFORMATION AND REQUIREMENTS.





### 4 EXTERNALLY INSULATED DUCT SUPPORT DETAIL

NO SCALE

NOTES:

1. ROUND MEDIUM PRESSURE DUCT MAY BE SUPPORTED WITH DUCT STRAPS.
2. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.




| TAP SIZE | ROD SIZE | DAMPER THICKNESS |
|---|---|---|
| UP TO 10" | 1/4" | 20 GA |
| OVER 10" | 3/8" | 18 GA |


HARDWARE MANUFACTURERS SHALL BE VENTLOCK, AMERICAN ELGEN, YOUNG AND DURO-DYNE.

### 3 DUCT TAP CONNECTION DETAIL

NO SCALE

NOTES:

1. DELETE CONICAL SECTION IF TOO LARGE FOR THE DUCT.
2. REFER TO SPECIFICATIONS OF FOR ADDITIONAL INFORMATION AND REQUIREMENTS.





### 2 DUCTWORK DETAIL

NO SCALE

NOTES:

1. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.




### 1 MECHANICAL - ELECTRICAL COORDINATION DETAIL

NO SCALE

NOTES:

1. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL


STATE OF TEXAS
TYLER W. HERRING
106052
LICENSED PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

MECHANICAL NOTES AND DETAILS
J-M2.01


STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM | TEXAS ENGINEERING FIRM REG. NO. F-01833 | (713) 300-6282 | 1300 W. SAM HOUSTON PARKWAY S., SUITE 121, HOUSTON, TX 77042
© 2021 ALL RIGHTS RESERVED





## 5 RESIDENTIAL CLOTHES DRYER FLUE VENT

NO SCALE

NOTES:

1. VENT TERMINATION AT WALL FOR STACKABLE WASHER/DRYER SHALL BE AT 60" AFF.
2. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.





## 4 SUPPLY/EXHAUST KITCHEN PLENUM DETAIL

NO SCALE

NOTES:

1. xxxxx





## 3 ROOF EXHAUST FAN AND VENT DETAIL

NO SCALE


NOTES:

1. NO WOOD BLOCKING SHALL BE LEFT EXPOSED IN THE CEILING PLENUM. COVER ALL EXPOSED WOOD WITH 1/2" SHEETROCK OR 20 GAUGE GALVANIZED SHEETMETAL.
2. ROOF VENT WILL NOT HAVE FAN/MOTOR ASSEMBLY, DISCONNECT SWITCH OR OBD.
3. ARCHITECTURAL ROOF CURB INSTALLATION REQUIREMENTS SHALL SUPERCEDE THIS DETAIL WHERE APPLICABLE.
4. ALL FANS SCHEDULED TO BE PROVIDED WITH 140MPH WIND RATING, INCLUDING FACTORY PROVIDED CURB. CURB INSTALLATION SHALL FOLLOW MANUFACTURER'S REQUIREMENTS FOR SECURING TO ROOF AND EQUIPMENT WHERE IT DIFFERS FROM THE DETAIL.
5. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.




## 2 INLINE EXHAUST FAN DETAIL

NO SCALE




## 1 CABINET EXHAUST FAN

NO SCALE

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL




ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

MECHANICAL DETAILS (CONT'D.)

J-M2.02

STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM (713) 300-4080
TEXAS ENG. FIRM REG. NO. F-018337-00 2025 ALL RIGHTS RESERVED
13999 W. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77040

# ELECTRICAL AND LOW VOLTAGE LEGEND AND SYMBOLS

- A — TYPE 'A' LIGHT FIXTURE
- LIGHT FIXTURE WITH EMERGENCY BACKUP
- EXIT SIGN/EXIT SIGN WITH DIRECTIONAL ARROW
- EMERGENCY EGRESS LIGHT FIXTURE
- WALL MOUNTED FIXTURE OR SCONCE
- CEILING DOWNLIGHT OR CYLINDER
- WALL PACK FIXTURE
- INV — LIGHTING INVERTER

- 20A, 277V TOGGLE/3-WAY/4-WAY SWITCH
- 20A, 277V MOMENTARY 3-POSITION TOGGLE SWITCH
- 20A, 277V, MOMENTARY 3-POSITION KEY SWITCH
- 20A, 277V MAINTAINED 2-POSITION/3-WAY/4-WAY KEY SWITCH
- 20A, 277V TOGGLE SWITCH W/ INTEGRAL NIGHT LIGHT
- MOTOR RATED ON/OFF SWITCH, MP W/ PILOT LIGHT (SWITCH RATING SHALL BE ≥ UPSTREAM OCPD & VOLTAGE)
- DPST — DOUBLE POLE SINGLE THROW (DPST) SWITCH WITH RED PILOT LIGHT.
- TDM — TIMER SWITCH

## NETWORK LIGHTING CONTROLS

- MULTIBUTTON LOW VOLTAGE LIGHTING SWITCH PROVIDE NUMBER OF BUTTONS INDICATED IN SINGLE PLATE.
- MULTIPLE DIMMER SWITCHES PROVIDE NUMBER OF SWITCHES INDICATED IN SINGLE PLATE.
- MULTIPLE KEY TYPE SWITCHES PROVIDE NUMBER OF SWITCHES INDICATED IN SINGLE PLATE.
- VSC — WALL SENSOR SWITCH
- 20A, 277V, STANDALONE DIMMER SWITCH (DISPLAY CABINET)
- OC — 360° CEILING SENSOR
- OW — 180° CEILING SENSOR
- OC — CEILING SENSOR
- DC — WALL MOUNT SENSOR
- PC — DAYLIGHT PHOTOSENSOR
- RC / RCK — LIGHTING ROOM CONTROLLER/POWER PACK
- ELR — EMERGENCY LIGHTING RELAY/CONTROL UNIT
- PLC — PLUG LOAD CONTROLLER

- 20A, 125V SIMPLEX/DUPLEX/QUAD RECEPTACLE
- GFI — 20A, 125V DUPLEX RECEPTACLE WITH GFCI PROTECTION
- GFI WP — 20A, 125V DUPLEX RECEPTACLE WITH GFCI PROTECTION AND WEATHERPROOF COVER.
- GFI — REMOTE GFCI DEVICE, REF SPECS AND EDF GFI DETAIL.
- 20A, 125V DUPLEX/QUAD RECEPTACLE W/ USB-A PORTS PROVIDE 2-5A PORTS PER DEVICE — HUBBELL USB20A5
- 20A, 125V SIMPLEX/DUPLEX/QUAD IG/COMPUTER RECEPTACLE
- GFI — 20A, 125V, IG/COMPUTER DUPLEX RECEPTACLE WITH GFCI
- PLUG LOAD CONTROLLED DUPLEX
- NEMA/IEC/CS — NEMA/IEC/CS NUMBERED POWER OUTLET MATCH PROVIDED EQUIPMENT CONNECTION OR CIRCUIT.
- 20A, 125V IG DUPLEX RECEPTACLE AT PROJECTOR, TV, OR INTERACTIVE MEDIA LOCATION.
- LOW VOLTAGE OUTLET
- CEILING MOUNTED RECEPTACLE
- CEILING MOUNTED LOW VOLTAGE OUTLET
- SINGLE SERVICE FLOOR BOX WITH DUPLEX/QUAD REC
- SINGLE SERVICE FLOOR BOX WITH DUPLEX/QUAD IG REC
- SINGLE SERVICE LOW VOLTAGE FLOOR BOXES
- MULTI SERVICE FLOOR BOX WITH QUAD/QUAD IG REC
- CR — CORD REEL
- DC — DROP CORD
- EPO — EMERGENCY POWER OFF (EPO) SWITCH
- PB — PUSH BUTTON
- SP — TELEPOWER POLE

- J — J-BOX
- CEILING MOUNTED J-BOX
- CA — J-BOX FOR ACCESS CONTROL DEVICE
- HD — JUNCTION BOX AND FINAL CONNECTION TO HAND DRYER BY DIVISION 26.
- HDWR — JUNCTION BOX AND FINAL CONNECTION TO ELECTRIFIED DOOR HARDWARE BY DIVISION 26.
- HEAT — JUNCTION BOX AND FINAL CONNECTION TO HEAT TRACE EQUIPMENT BY DIVISION 26.
- WC — JUNCTION BOX AND FINAL CONNECTION TO POWERED PLUMBING EQUIPMENT BY DIVISION 26.
- SF — JUNCTION BOX AND FINAL CONNECTION TO SYSTEM FURNITURE BY DIVISION 26.

- CONTACTOR
- NON-FUSED DISCONNECT SWITCH
- NON-FUSED DOUBLE THROW DISCONNECT
- FUSED DISCONNECT SWITCH
- DISCONNECT/CB WITH SHUNT TRIP
- CB — ENCLOSED CIRCUIT BREAKER
- MOTOR STARTER 'VFD' INDICATES VARIABLE FREQUENCY DRIVE MOTOR STARTER
- MOTOR STARTER WITH INTEGRAL DISCONNECT
- MOTOR
- TC — TIME CLOCK

- ELECTRICAL PANELBOARD
- ELECTRICAL METER
- SPD — TVSS OR SPD
- GANN — GENERATOR REMOTE ANNUNCIATOR

- LOW VOLTAGE CABLING PATHWAY, REF. SPECIFICATIONS

## KITCHEN SYMBOL LEGEND

- LOAD CENTER, BY FOOD SERVICE PROVIDE UNDERGROUND CONDUIT STUBBED UP AT LOAD CENTER LOCATION PER SUBMITTAL SHOP DRAWINGS.
- P — POINT OF SALE EQUIPMENT, BY FOOD SERVICE. PROVIDE UNDERGROUND CONDUIT STUBBED UP POS LOCATION PER SUBMITTAL SHOP DRAWINGS.
- F — REMOTE FIRE PULL, REFERENCE INSTALLATION DETAIL
- B — BELL/BUZZER WITH 120V TO LOW VOLTAGE TRANSFORMER
- D — DROP CORD
- DB — DOORBELL BUTTON
- V — CEILING STROBE FOR ENTRAPMENT ALARM
- V — CLR/FRZR — WALL STROBE FOR ENTRAPMENT ALARM

## COORDINATION SYMBOL LEGEND

- DDC — HVAC CONTROL PANEL. REQUIRES POWER AND DATA CONNECTIONS WITHIN CABINET COOR EXACT LOCATION AND REQUIREMENTS WITH CONTROLS CONTRACTOR PRIOR TO ROUGH-IN.
- SD — SMOKE DAMPER
- FD — FIRE/SMOKE COMBINATION DAMPER
- M / MD — MOTORIZED DAMPER

## SITE PLAN

- UTILITY POLE
- POLE MOUNTED TRANSFORMER BANK
- SITE POLE LIGHT
- UGE — FLUSH IN GRADE ELECTRICAL PULL BOX
- LV UG — FLUSH IN GRADE, LOW VOLTAGE HAND HOLE
- CONCRETE BOLLARD
- (X)PP — POWER POLE
- (X)SP — SERVICE POLE OR RACK
- (X)XP — XFMR POLE
- (X)LVP — LOW VOLTAGE POLE
- (X)TP — TRANSITION POLE
- OHP — OVERHEAD POWER WIRING
- 480V — 480V OVERHEAD POWER WIRING
- UGP — UNDERGROUND PRIMARY ELECTRICAL
- UGS — UNDERGROUND SECONDARY ELECTRICAL
- UGE — UNDERGROUND EMERGENCY ELECTRICAL

## DIVISION 28 LEGENDS

### FIRE ALARM

- F — FIRE ALARM PULL STATION W/ STOPPER II
- F / S — WALL FIRE ALARM AUDIO/VISUAL DEVICE
- WP — OUTDOOR WEATHERPROOF FIRE AUDIO/VISUAL DEVICE
- H — WALL FIRE ALARM AUDIO DEVICE
- V — WALL FIRE ALARM VISUAL DEVICE
- H / S — CEILING FIRE ALARM AUDIO/VISUAL DEVICE
- H — CEILING FIRE ALARM AUDIO DEVICE
- V — CEILING FIRE ALARM VISUAL DEVICE
- DH / DV — DUCT SMOKE DETECTOR
- I / S — CEILING SMOKE DETECTOR
- H — CEILING HEAT DETECTOR
- CO — CEILING CARBON MONOXIDE DETECTOR
- S / CO — CEILING COMBINATION SMOKE/CARBON MONOXIDE DETECTOR
- FR — FIRE ALARM RELAY FOR STAGE SOUND RACK OVERRIDE
- BD — BEAM SMOKE DETECTOR
- FANN — FIRE ALARM REMOTE ANNUNCIATOR OR LOCAL OPERATOR'S CONSOLE
- FACP — FIRE ALARM CONTROL PANEL
- FAPS — FIRE ALARM POWER SUPPLY/AMPLIFIER

- G — INDICATES DEVICE WITH PROTECTIVE GUARD
- WG — INDICATES DEVICE WITH WIRE GUARD
- HC — INDICATES DEVICE RATED FOR HAZARDOUS CONDITIONS
- SD — SMOKE DAMPER
- FD — FIRE/SMOKE COMBINATION DAMPER

## MULTI-SERVICE FLOOR BOX NOTES

FLOOR POWER AND LOW VOLTAGE

PROVIDE HEAVY-DUTY MULTI-GANG FLUSH IN GRADE OR FIRE RATED POKE-THRU OUTLET WITH HEAVY DUTY METAL HINGED COVER WITH CABLE EXIT SLOT.
FLOOR BOX MUST BE RATED FOR INSTALLATION IN GRADE.

FOR EACH FLOOR BOX PROVIDE:
1. PROVIDE:
   - 1.A. ONE QUAD OR TWO DUPLEX RECEPTACLES.
   - 1.B. PROVIDE IG RECEPTACLES WHERE SHOWN.
   - 1.C. POWER CONNECTION TO TABLE (WHERE SHOWN)
2. BLANK STAINLESS STEEL COVER FOR UN-USED GANGS.
3. PROVIDE ONE 3/4"C UNDERGROUND CONDUIT FOR POWER.
4. PROVIDE ONE 1"C UNDERGROUND CONDUIT WITH WATERPROOF INNER DUCT FOR DATA.
5. PROVIDE ONE 1"C UNDERGROUND CONDUIT WITH WATERPROOF INNER DUCT FOR LOW VOLTAGE CABLING
6. PROVIDE DIVIDERS TO MAINTAIN SEPARATION BETWEEN SERVICES.

UNDERGROUND CONDUITS MUST BE WATER TIGHT TO PREVENT MOISTURE ENTERING CONDUITS.
DO NOT COMBINE CONDUIT FOR POWER & LOW VOLTAGE.

REFERENCE FLOOR PLANS AND SPECIFICATIONS FOR QUANTITY OF DATA DROPS AND ADDITIONAL INFORMATION.

COORDINATE WITH ARCHITECT TO PROVIDE COVER/RING TO MATCH FLOOR MATERIAL AND SUBMIT COVER FINISH FOR ARCHITECT TO SELECT PRIOR TO ORDERING.

## GENERAL NOTES / TAGS

| | |
|---|---|
| +18" | INDICATES DEVICES AT +18" AFF |
| +42" | INDICATES DEVICES AT +42" AFF |
| +96" | INDICATES DEVICES AT +96" AFF |
| +12 FT | INDICATES DEVICES AT +12 FT AFF, ETC. |
| * | INDICATES DEVICES ABOVE COUNTER, REF ARCH |
| CLG | INDICATES DEVICES AT CEILING |
| PMR | INDICATES PEDESTAL MOUNTED DEVICE, REF PMR DETAIL |
| TV | INDICATES DEVICES AT TELEVISION/DISPLAY LOCATION |
| IM | INDICATES DEVICES AT INTERACTIVE MEDIA LOCATION |
| PROJ | INDICATES DEVICES AT PROJECTOR LOCATION |
| S | INDICATES SURFACE MOUNTED DEVICE |
| IEC | INDICATES IEC POWER OUTLET |
| NEMA | INDICATES NEMA NUMBERED POWER OUTLET |
| GFI | INDICATES GROUND FAULT INTERRUPT (GFI) PROTECTION |
| WP | INDICATES WEATHERPROOF DEVICES |
| GFI WP | INDICATES GFI PROTECTED WEATHERPROOF DEVICE |
| G | INDICATES DEVICE WITH PROTECTIVE GUARD |
| WG | INDICATES DEVICE WITH WIRE GUARD |
| 3R | INDICATES NEMA 3R RATED DEVICE |
| 4XSS | INDICATES NEMA 4XSS RATED DEVICE |
| EM | INDICATES DEVICE ON EM/STANDBY POWER |
| VFD | INDICATES VARIABLE FREQUENCY DRIVE (VFD) |
| E | EXISTING DEVICES TO REMAIN |
| D | EXISTING DEVICES TO BE DEMO/REMOVED |
| R | EXISTING DEVICES TO BE RELOCATED |
| REP | EXISTING DEVICES TO BE REPLACED |
| | (X) = (E) FOR EXISTING |
| | (X) = (D) FOR DEMO |
| | (X) = (R) FOR RELOCATION |
| | (X) = (N) FOR NEW |

- HOMERUN TO CIRCUIT NOTED

1. RECEPTACLES AND DATA OUTLETS SHALL BE MOUNTED AT +18" AFF UNLESS NOTED ON THE DRAWINGS.
2. REF. SPECIFICATIONS FOR MOUNTING HEIGHT OF OTHER DEVICES.
3. ELECTRICAL RECEPTACLES, TELEPHONES, ETC... ARE SHOWN FOR GENERAL LOCATION. HEIGHTS ARE NOTED SO THE ESTIMATOR WILL KNOW WHETHER THEY ARE ABOVE OR BELOW COUNTERS. PRIOR TO INSTALLATION, REVIEW THE ARCHITECTURAL DRAWINGS AND SPECIFICATIONS. IN THE EVENT OF CONFLICT, THE ARCHITECT'S LOCATION WILL GENERALLY PREVAIL BUT SHOULD BE CLARIFIED BY RFI. PROVIDE DEVICES SHOWN ON THE ELECTRICAL DRAWING EVEN IF NOT SHOWN ON ARCHITECTURAL DRAWINGS.
4. COORDINATE POWER AND DATA WITH THE FURNITURE SUPPLIER PRIOR TO ROUGH-IN. AT CASEWORK WITH KNEE SPACE, MOUNT RECEPTACLES AND DATA OUTLETS IN KNEE SPACE. COORDINATE WITH ARCHITECT AND FURNITURE SUPPLIER TO ENSURE THAT PROTECTIVE GROMMETS ARE PROVIDED IN THE COUNTER.
4. ALL DEVICES SHOWN AT THE SAME LOCATION AND ELEVATION SHALL BE GROUPED TOGETHER AND SPACED 2 INCHES BETWEEN BOXES.
5. PROVIDE SS COVER PLATE FOR ALL EMPTY JBOX.
6. ALL NON-LOCKING 125V AND 250V, 15A AND 20A RECEPTACLES SHALL BE TAMPER RESISTANT TYPE.

STANTON ENGINEERING GROUP
INFORMATION: (713)-360-6080 | TEXAS ENG. FIRM REG NO. F-01853 (c) 2025 ALL RIGHTS RESERVED
12999 W. SAM HOUSTON PKWY NORTH, SUITE 725, HOUSTON, TX 77064

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

j

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL

STATE OF TEXAS — GEORGE L. STANTON — 38582 — REGISTERED PROFESSIONAL ENGINEER
07.18.2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL AND FIRE ALARM SCHEDULES
j-E.000

PROVIDE CONDUIT & SLEEVES THRU FIRE WALLS, WALLS AND FLOORS FOR LOW VOLTAGE CABLING WIRING, ETC.

ALL CONDUIT & J-BOXES FOR LOW VOLTAGE CABLING SHALL BE PROVIDED AND INSTALLED BY THE ELECTRICAL CONTRACTOR. ALL LOW VOLTAGE CABLING IN WALLS, EXPOSED AREAS AND ABOVE INACCESSIBLE CEILINGS SHALL REQUIRE CONDUIT AND J-BOXES. REFERENCE SPECIFICATIONS AND TECHNOLOGY DOCUMENTS FOR ADDITIONAL INFORMATION/REQUIREMENTS.

PULL BOXES AND BELOW GRADE CONDUIT FOR LOW VOLTAGE CABLING, WIRING, ETC. BY ELEC CONTRACTOR.

## FIRE ALARM SYSTEM DESCRIPTION AND SEQUENCE OF OPERATION

1. FIRE ALARM SYSTEM SHALL BE DESIGNED TO MEET NFPA REQUIREMENTS AS WELL AS CITY AND NATIONAL BUILDING CODES. PROVIDE COMPLETE FIRE ALARM SYSTEM, DEVICES AND WIRING.
2. INSTALL FIRE ALARM CONTROL PANEL IN RECEPTION AREA. INSTALL REMOTE POWER SUPPLY PANELS IN MECHANICAL/ELECTRICAL ROOMS.
3. FIRE ALARM PANEL, POWER SUPPLIES, DEVICES, ETC. SHALL BE MANUFACTURED BY THE SAME MANUFACTURER AS THE FIRE ALARM CONTROL PANEL.
4. FIRE ALARM REMOTE POWER SUPPLIES AND PANELS SHALL BE LOCATED IN MECHANICAL OR ELECTRICAL ROOMS ONLY. DO NOT LOCATE IN STORAGE ROOMS, DATA CLOSETS OR FINISHED SPACES.
4. PROVIDE AUDIBLE, INTELLIGIBLE AND VISUAL ALARM COVERAGE OF THE AREA OF RENOVATION AS REQUIRED BY CODE.
5. PROVIDE SMOKE DETECTORS AT EACH FIRE ALARM PANEL, REMOTE TRANSPONDER PANEL, BOOSTER PANEL AND REMOTE ANNUNCIATOR PER NFPA 72.
6. IN ADDITION TO THE SPECIFIED FIRE ALARM EQUIPMENT, THE FIRE ALARM CONTRACTOR SHALL PROVIDE
   6.A. SURGE PROTECTORS FOR ALL NEW 120V POWER CONNECTIONS TO FIRE ALARM EQUIPMENT.
   6.B. SURGE PROTECTORS FOR ALL SIGNALING LINE CIRCUITS (SLC), NOTIFICATION CIRCUITS AND INITIATING CIRCUITS CONNECTED TO THE FIRE ALARM CONTROL PANEL WHICH LEAVE THE BUILDING.
7. SHOULD ANY DETECTOR, MONITOR OR PULL STATION ACTIVATE, ALL SPEAKERS SHALL SOUND AND STROBES FLASH. AIR HANDLING EQUIPMENT SHALL BE DEACTIVATED. AN ALARM SIGNAL SHALL BE SENT TO A REMOTE LOCATION VIA AUTOMATIC DIALER. ALSO, DE-ENERGIZE SUPPLY FANS, EXHAUST FANS AND OTHER AIR CIRCULATING DEVICES IF 2000 CFM OR OVER, SERVING THE AREA IN ALARM.
8. ALL LOW VOLTAGE WIRING SHALL BE FPLP RATED WIRE, WITH MINIMUM WIRE SIZE PER SPECIFICATIONS.
   8.A. PLENUM RATED CABLE ABOVE ACCESSIBLE CEILING SHALL BE SUPPORTED BY J-HOOKS, SPACED AT FOUR (4) FEET ON CENTER.
   8.B. INSTALL FIRE ALARM CABLES IN CONDUIT FOR AREAS WITHOUT CEILING OR ABOVE INACCESSIBLE CEILINGS.
   8.C. EXPOSED CONDUIT IN FINISHED SPACES SHALL BE ALLOWED WHERE NO OTHER OPTION EXISTS AND ONLY WITH PRIOR WRITTEN APPROVAL BY THE OWNER. ALL EXPOSED CONDUIT SHALL BE PAINTED TO MATCH.
   8.D. ALL CABLING THROUGH WALLS, FIRE WALLS AND FLOORS SHALL BE INSTALLED IN SLEEVES WITH PROTECTIVE BUSHINGS ON BOTH ENDS.
9. FIRE ALARM SYSTEM SHALL BE MONITORED BY A UL LISTED CENTRAL RECEIVING STATION.
10. INTERLOCK LIGHTING CONTROL PANELS WITH FIRE ALARM SYSTEM TO ENABLE ALL LIGHTING UPON ACTIVATION.
11. REFER TO THE WRITTEN SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.

## FIRE ALARM SYSTEM NOTES

1. GENERAL CONTRACTOR SHALL COORDINATE WITH ELECTRICAL AND FIRE ALARM SUBCONTRACTOR FOR LOCATIONS OF REMOTE POWER SUPPLIES. FIRE ALARM POWER SUPPLIES ARE NOT SHOWN ON THIS DRAWING AND SHALL BE LOCATED BY FIRE ALARM SUBCONTRACTOR IN ORDER TO ACCOMMODATE HIS FIRE ALARM SYSTEM BATTERY AND VOLTAGE DROP CALCULATIONS PER MANUFACTURER'S RECOMMENDATION & NFPA REQUIREMENTS. ELECTRICAL CONTRACTOR SHALL INCLUDE ADDITIONAL DEDICATED 120V CIRCUITS IN BASE BID TO SERVE FIRE ALARM POWER SUPPLIES IN DIFFERENT AREAS. PROVIDE 2–12 +12G, 3/4"C AND SPARE 20A/1P CB(S) IN LOCAL LIFE SAFETY EMERGENCY 120V PANELS TO SERVE FIRE ALARM REMOTE POWER SUPPLIES.
2. FIRE ALARM CONTRACTOR IS RESPONSIBLE FOR DESIGN AND FOR FINAL CORRECT LOCATION OF DEVICES TO RELIEVE NUISANCE ALARMS, SUCH AS INSTALLING A HEAT DETECTOR IN FRONT OF AN OVEN WHICH WILL RELEASE STEAM, THUS POTENTIALLY SETTING OFF THE ALARM. ALSO, THE CONTRACTOR IS RESPONSIBLE FOR DETECTORS REQUIRED BY CODE EVEN IF NOT SHOWN ON DRAWING, LIKE A CLOSET. IF THERE IS UNCERTAINTY, BRING UP DURING THE BID PROCESS AND THEY WILL BE ADDRESSED DURING THE BIDDING PROCESS.
3. FIELD VERIFY ENVIRONMENTAL ISSUES THAT CAN ADVERSELY AFFECT OPERATION OF SMOKE DETECTORS. DO NOT LOCATE NEAR AIR FLOW DEVICES LEADING TO PREMATURE BUILD UP OF DUST CAUSING NUISANCE TROUBLE SIGNALS. DEVICE RELOCATION OR TYPE CHANGE WILL BE COVERED UNDER WARRANTY.

## FIRE ALARM SCOPE OF WORK

1. THERE IS AN EXISTING FIRE ALARM SYSTEM IN EACH BUILDING.
   1.A. TEST THE EXISTING SYSTEM PRIOR TO BEGINNING DEMO. NOTE ANY FAULTS OR TROUBLES AND PROVIDE A WRITTEN REPORT TO THE OWNER.
   1.B. EXPAND THE EXISTING SYSTEM AS REQUIRED TO INTEGRATE THE NEW DEVICES IN THE AREA OF RENOVATION.
2. PROVIDE WIRING AND DEVICES AS INDICATED TO PROVIDE COMPLETE AUDIBLE, INTELLIGIBLE AND VISUAL ALARM COVERAGE OF RENOVATED AREAS AS REQUIRED BY CODE.
   2.A. PROVIDE SMOKE DETECTOR COVERAGE OF ALL STORAGE ROOMS AND ADDITIONALLY AS SHOWN ON THE DRAWINGS.
   2.B. PROVIDE HEAT DETECTOR COVERAGE OF THE KITCHEN, CUSTODIAL ROOMS, AND ADDITIONALLY AS SHOWN ON THE DRAWINGS.
   2.C. PROVIDE DUCT MOUNTED DETECTORS AT EACH NEW AIR HANDLING UNIT SUPPLY AND RETURN CONNECTION EXCEEDING 2000 CFM. IF FREE AIR RETURN, PROVIDE FREE AIR DETECTING COVERAGE OF THE RETURN AIR OPENINGS TO THE MECHANICAL ROOM. ENSURE AIR FLOW CANNOT PREVENT OPERATION OF THE DETECTORS AND PROVIDE ADEQUATE CLEARANCE PER NFPA 72.
   2.D. CONTROL RELAYS SHALL BE LOCATED WITHIN 3 FT OF THE CONTROLLED CIRCUIT OR APPLIANCE.
3. PROVIDE SMOKE DETECTORS AT EACH NEW FIRE ALARM PANEL, REMOTE TRANSPONDER PANEL, BOOSTER PANEL AND REMOTE ANNUNCIATOR PER NFPA 72.
4. PROVIDE LED REMOTE ALARM WITH ENGRAVED STAINLESS STEEL PLATE WHERE DUCT DETECTORS ARE NOT LOCATED IN MECHANICAL ROOM, LOCATED ABOVE CEILINGS OR WHERE MOUNTED TOO HIGH OR VIEW IS BLOCKED BY DUCTWORK IN MECHANICAL ROOM.
   4.A. REMOTE LED LIGHT INDICATOR FOR DUCT SMOKE DETECTORS SHALL BE MOUNTED FLUSH IN CEILING OR MOUNTED IN WALL AT +7FT.
   4.B. STAINLESS STEEL PLATE SHALL BE ENGRAVED WITH THE DUCT SMOKE DETECTOR AS–BUILT IDENTIFICATION NUMBER.
5. REFER TO THE WRITTEN SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.

## SPARES

1. THE FIRE ALARM CONTRACTOR SHALL INCLUDE IN HIS BID THE COST TO PROVIDE AND INSTALL THE ADDITIONAL SPARE PARTS AND ASSOCIATED CABLING PER THE SPECIFICATIONS. SPARES SHALL BE INSTALLED AS INSTRUCTED BY THE OWNER. UNINSTALLED DEVICES SHALL BE DELIVERED TO THE OWNER AS ATTIC STOCK.

## GENERAL RENOVATION AND REMODELING NOTES

1. READ ALL MEP AND ARCH. DRAWINGS TO IDENTIFY AREAS OF RENOVATION AND SCOPE OF WORK.
2. ALL RENOVATION AND DEMOLITION WORK SHALL NOT AFFECT AREAS NOT INCLUDED IN THE AREAS OF WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE CONTINUITY OF ALL SERVICES (POWER, TELEPHONE, FIRE ALARM, DATA, SECURITY, ETC.) IN NON–DEMOLITION/RENOVATION AREAS. ALL SERVICES SHALL BE MAINTAINED AT ALL TIMES.
3. ALL OUTAGES AFFECTING NON–DEMOLITION/RENOVATION AREAS SHALL BE SCHEDULED WITH THE OWNER WITH A MINIMUM 2 WEEKS ADVANCE NOTICE. OUTAGES SHALL BE COORDINATED WITH OTHER TRADES TO MINIMIZE THE QUANTITY AND IMPACT ON BUILDING OPERATION.
4. THIS ELECTRICAL DRAWING ONLY SHOWS SOME EXISTING ELECTRICAL PANELS, DEVICES AND LIGHT FIXTURES IN AREAS OF RENOVATION. ALL OTHER ELECTRICAL EQUIPMENT, WIRING DEVICES, LOW VOLTAGE SYSTEMS, J–BOXES AND CONDUITS SHALL BE LOCATED AND FIELD VERIFIED BY CONTRACTOR.
5. CONTRACTOR SHALL FIELD VERIFY AND MARK UP THE FOLLOWINGS IN AREAS OF RENOVATION:
   5.A. EXISTING DATA, AUDIO, VIDEO, SPEAKERS AND OTHER LOW VOLTAGE OUTLETS AND DEVICES.
   5.B. EXISTING CEILING MOUNTED PROJECTORS.
   5.C. EXISTING SECURITY, CCTV, ACCESS CONTROL DEVICES.
   5.D. EXISTING FIRE ALARM DEVICES.
   5.E. EXISTING WIRELESS ACCESS POINTS AND GRID LABELING.
   5.F. EXISTING LIGHT FIXTURES AND SWITCHES.
   5.G. EXISTING ELECTRICAL DEVICES, J–BOXES, CONDUIT, WIRING, WIRING SUPPORTS, ETC.
   5.H. EXISTING ELECTRICAL SWITCHGEAR.
   5.I. EXISTING CONTROL PANELS AND CONTROL CIRCUITS.
   5.J. EXISTING HANGER WIRE FROM CONC. CEILING.
6. ALL REMOVED DEVICES SHALL BE OFFERED TO THE OWNER AS SALVAGE.
7. ALL EXISTING DEVICES SHALL BE REINSTALLED IN NEW CEILINGS AT SAME LOCATION EXCEPT WHERE SHOWN TO BE NEW.
8. CONDUIT/WIRE NOT TO BE REUSED SHALL BE REMOVED ALL THE WAY BACK TO THE UPSTREAM EQUIPMENT.
   8.A. PROVIDE ADDITIONAL SUPPORTS FOR EXISTING CONDUIT/WIRE TO REMAIN TO MEET CURRENT CODE REQUIREMENTS.
9. ANY MATERIAL THAT HAS SALVAGE VALUE SHALL BE OFFERED TO THE OWNER, AND IF ACCEPTED, DELIVERED TO HIS WAREHOUSE. IF NOT ACCEPTED IT SHALL BE PROPERLY DISPOSED OF WITH THE OTHER CONSTRUCTION DEBRIS.
10. RELOCATE CONDUIT AS NECESSARY TO ALLOW NEW OR MODIFIED CONSTRUCTION. REPAIR EXISTING ELECTRICAL SYSTEMS DAMAGED BY CONSTRUCTION ACTIVITES.
11. WHERE PARTIAL CIRCUITS OR SYSTEMS ARE TO BE REUSED, ENSURE THAT THEY REMAIN ACTIVE. WHERE EXISTING EQUIPMENT IS RELOCATED OR REPLACED WITH NEW, MODIFY, EXTEND AND RELOCATE EXISTING CIRCUIT TO CONNECT TO EQUIPMENT, UNLESS SHOWN TO HAVE NEW CIRCUIT.
12. WHERE AUXILIARY SYSTEMS SUCH AS SECURITY, DATA, SOUND, ETC. INTERFACE WITH EXISTING EQUIPMENT THAT IS REPLACED OR MODIFIED (MECHANICAL, ELECTRICAL OR PLUMBING), DISCONNECT AND RECONNECT THESE SYSTEMS.
13. WHERE NEW CIRCUIT BREAKERS ARE TO BE INSTALLED IN EXISTING PANELS OR SWITCHBOARD, VERIFY THAT THE CIRCUIT BREAKER WILL FIT IN THE ALLOTTED SPACE. PROVIDE NEMA 1 ENCLOSURE ADJACENT TO PANEL & WIRE CONNECT TO BUSSING IF THERE IS INSUFFICIENT SPACE.
14. WHERE PARTIAL CIRCUITS OR SYSTEMS ARE TO BE REUSED, ENSURE THAT THEY REMAIN ACTIVE. WHERE EXISTING EQUIPMENT IS RELOCATED OR REPLACED WITH NEW, MODIFY, EXTEND AND RELOCATE EXISTING CIRCUIT TO CONNECT TO EQUIPMENT, UNLESS SHOWN TO HAVE NEW CIRCUIT.
15. WHEN REPLACING LIGHTS AND CEILINGS, ENSURE THAT EXISTING DATA, TELEVISION AND PA CABLES TO REMAIN CONTINUE TO MEET THE CURRENT STANDARDS. FOR DATA CABLES, THIS IS THE IEEE 802.1. FOR TELEVISION AND PA CABLE, A FOUR INCH DISTANCE IS NEEDED FROM ALL LIGHT FIXTURES. NEW DROP LOCATION SHOULD BE WITHIN THREE FEET OF POWER OUTLET.
16. PAINT NEW AND EXISTING EXPOSED RACEWAY IN AREAS OF RENOVATION TO MATCH FINISHES.
17. ANY DAMAGE TO EXISTING BUILDING, ELECTRICAL EQUIPMENT, WIRING DEVICES, CONDUIT, WIRING, ETC. SHALL BE REPLACED BY THE CONTRACTOR AT NO COST TO THE OWNER. ALL MATERIALS USED FOR THE REPLACEMENT MUST MEET RENOVATION PROJECT STANDARDS.
18. INTERESTED CONTRACTORS MUST VISIT THE SITE PRIOR TO BIDDING TO BECOME FAMILIAR WITH THE PROJECT REQUIREMENTS AND EXISTING CONDITIONS AND SHALL INCLUDE IN THEIR PROPOSALS COSTS TO REPAIR, RELOCATE, MODIFY AND REMOVE EXISTING ELEMENTS AS REQUIRED TO COMPLETE INSTALLATION OF ALL SYSTEMS SHOWN ON THESE DRAWINGS.
19. SEE DRAWINGS FOR ADDITIONAL REQUIREMENTS.

## ELEC REQUIREMENTS FOR BUILDING RENOVATION

1. ELECTRICAL CONTRACTOR SHALL BEGIN FIELD VERIFYING ALL EXISTING BRANCH CIRCUITS FOR EXISTING AREAS TO BE RENOVATED IMMEDIATELY AFTER THE CONTRACT IS ISSUED.
2. ELECTRICAL CONTRACTOR SHALL FIELD VERIFY EXISTING CIRCUITS WITH OWNER'S MAINTENANCE PERSONNEL AFTER NORMAL BUILDING HOURS AS REQUIRED.
3. ELECTRICAL CONTRACTOR SHALL INCLUDE COST RELATED TO FIELD VERIFY EXISTING CIRCUITS IN BASE PROPOSAL.
4. FIND AND RECORD ALL EXISTING DEVICES IN CEILINGS, WALLS AND CASEWORK IN AREAS TO BE RENOVATED. PROVIDE A COPY OF THE FIELD VERIFIED DEVICE DRAWINGS TO OWNER PRIOR TO BEGINNING WORK.
5. ALL EXISTING DEVICES TO REMAIN SHALL BE REINSTALLED IN NEW CEILINGS AND WALLS EXCEPT WHERE INDICATED TO BE REMOVED/RELOCATED/REPLACED.
6. EXISTING DEVICES IN WALLS TO BE FURRED OUT OR RECEIVE NEW SURFACE TREATMENT SHALL REMAIN. EXTEND JBOX TO NEW WALL SURFACE AND RECONNECT TO EXISTING CIRCUITS. EXTEND WIRING/CABLING FROM NEAREST ACCESSIBLE POINT AS NECESSARY.
7. REINSTALL ALL DEVICES NOT SHOWN TO BE REMOVED.
8. EXISTING LIGHT FIXTURES SHALL REMAIN EXCEPT WHERE SHOWN AS NEW. EXTEND EXIST CONDUIT AND WIRE DOWN TO NEW LIGHT FIXTURES, REFERENCE SPECIFICATIONS FOR ADDITIONAL INFORMATION.
9. ALL EXISTING EXIT SIGNS SHALL BE REINSTALLED AND RECONNECTED TO EXISTING CIRCUITS EXCEPT IN CORRIDORS AND AREAS OF RENOVATION SHOWING NEW.
10. ALL NEW DEVICES IN EXISTING WALLS IN FINISHED SPACES SHALL BE INSTALLED FLUSH MOUNTED, NO EXPOSED CONDUIT OR WIREMOLD ALLOWED. CUT EXISTING WALLS AND PATCH/REPAIR TO MATCH EXISTING AS REQUIRED.
    10.1. DEVICES/CONDUIT IN CUSTODIAL, MECHANICAL AND ELECTRICAL ROOMS MAY BE EXPOSED AND SURFACE MOUNTED.
11. PROVIDE NEW DIRECTORY FOR ALL EXISTING AND NEW PANELS SHOWING FIELD VERIFIED CIRCUITS.
12. ANY FEEDER AND BRANCH CIRCUIT NOT TO BE REUSED SHALL BE REMOVED COMPLETELY UP TO CB IN EXISTING PANEL.
13. ANY CIRCUIT OR PARTIAL CIRCUIT TO BE REUSED SHALL REMAIN ACTIVE.

## GENERAL EQUIPMENT ELECTRICAL NOTE

THE ELECTRICAL DESIGN HAS BEEN COORDINATED FOR SPACE, INSTALLATION AND ELECTRICAL REQUIREMENTS WITH EQUIPMENT THAT IS SCHEDULED BY OTHER DIVISIONS. THE REQUIREMENTS FOR OTHER EQUIPMENT AND MODELS FROM ACCEPTABLE MANUFACTURERS HAVE NOT BEEN VERIFIED OR COORDINATED. THE GENERAL CONTRACTOR SHALL VERIFY THESE REQUIREMENTS PRIOR TO USING OTHER EQUIPMENT IN HIS BID AND INCLUDE ANY ADDITIONAL COSTS FOR INSTALLATION OF THE EQUIPMENT. THIS INCLUDES GENERAL CONSTRUCTION AND MEP COSTS.

ELECTRICAL CONTRACTOR SHALL COORDINATE WITH OWNER/OTHER TRADES FOR EXACT ELECTRICAL REQUIREMENTS OF EQUIPMENT PRIOR TO ORDERING CB(S). FIELD VERIFY EQUIPMENT NAMEPLATE RATINGS AND EQUIPMENT CONNECTION LOCATIONS WITH OTHER TRADES PRIOR TO ROUGH–IN.

TYPICAL OF HVAC EQUIPMENT, SHOP EQUIPMENT, KITCHEN EQUIPMENT, ELECTRIC ROLLUP DOORS, ETC.

## GENERAL ELECTRICAL NOTES

1. REFER TO THE WRITTEN SPECIFICATIONS FOR ADDITIONAL INFORMATION.
2. INSTALL SYSTEMS IN ACCORDANCE WITH THE NATIONAL ELECTRIC CODE.
3. PROVIDE LIGHT FIXTURE FIRE PROTECTION AND CONDUIT FIRE SEALING TO MAINTAIN FIRE RATING OF WALLS AND CEILINGS PER ARCHITECT'S SCHEDULE. REF. SPECIFICATIONS AND ARCH. DRAWINGS FOR ADDITIONAL INFORMATION.
4. ELECTRICAL RECEPTACLES, TELEPHONES, ETC... ARE SHOWN FOR GENERAL LOCATION. HEIGHTS ARE NOTED SO THE ESTIMATOR WILL KNOW WHETHER THEY ARE ABOVE OR BELOW COUNTERS. PRIOR TO INSTALLATION, REVIEW THE ARCHITECTURAL DRAWINGS AND SPECIFICATIONS. IN THE EVENT OF CONFLICT, THE ARCHITECT'S LOCATION WILL GENERALLY PREVAIL BUT SHOULD BE CLARIFIED BY RFI. PROVIDE DEVICES SHOWN ON THE ELECTRICAL DRAWING EVEN IF NOT SHOWN ON ARCHITECTURAL DRAWINGS.
5. COORDINATE POWER AND DATA WITH THE FURNITURE SUPPLIER PRIOR TO ROUGH–IN. AT CASEWORK WITH WIRE SPACE, MOUNT RECEPTACLES AND DATA OUTLETS IN KNEE SPACE. COORDINATE WITH ARCHITECT AND FURNITURE SUPPLIER TO ENSURE THAT PROTECTIVE GROMMETS ARE PROVIDED IN THE COUNTER.
6. DO NOT INSTALL ELECTRICAL PANELS AND TRANSFORMERS UNTIL 1/4" SCALE DRAWINGS SHOWING LOCATION OF THIS EQUIPMENT RELATIVE TO MECHANICAL/PLUMBING EQUIPMENT, DUCTWORK AND PIPING IS SUBMITTED AND APPROVED. NEC CODE CLEARANCE MUST BE MAINTAINED.
7. ELECTRICAL EQUIPMENT HAS BEEN COORDINATED WITH PIPING AND DUCTWORK. DO NOT RELOCATE PANELS WITHOUT PRIOR APPROVAL.
8. ELECTRICAL DEVICES IN FIRE RATED WALLS SHALL BE A MINIMUM OF 24" AWAY FROM DEVICES ON THE OPPOSITE SIDE OF THE WALL TO MAINTAIN FIRE RATING.
9. MINIMUM SIZE CONDUIT FOR POWER SHALL BE 3/4", MIN. SIZE FLEX CONDUIT MAY BE 1/2". MINIMUM SIZE CONDUIT FOR DATA SHALL BE 1"C. DO NOT COMBINE CONDUIT FOR DATA.
10. MAX. LENGTH FOR FLEX CONDUIT SHALL BE 6 FT. ALL FLEX CONDUIT SHALL BE LISTED FOR GROUNDING.
11. LIGHT FIXTURE WHIPS MAY BE MIN. 1/2" FLEX CONDUIT WITH MIN. #12 WIRE. LIGHT FIXTURE WHIPS SHALL BE NO MORE THAN 6 FT LONG.
12. PROVIDE GREEN GROUND WIRE WITH ALL CIRCUITS SIZED PER NEC. BOND GREEN GROUND WIRE TO EACH END OF CONDUIT.
13. GROUND TRANSFORMER SECONDARIES TO BUILDING STEEL AND GROUND ROD. PROVIDE CONDUIT TO PROTECT GROUNDING CONDUCTOR AND BOND EACH END OF CONDUIT TO GROUNDING SYSTEM. MIN. SIZE OF CONDUIT FOR GROUND WIRE SHALL BE 3/4"C.
14. PROVIDE J–BOXES, CONDUIT AND SLEEVES THRU ALL FIRE WALLS FOR DATA, TELEPHONE, SECURITY, FIRE ALARM AND SOUND SYSTEMS WIRINGS, ETC. SEE SPECIFICATIONS.
15. PROVIDE PULL BOXES, JUNCTION BOXES, WIRING TROUGHS AND CABINETS WHEREVER REQUIRED FOR PROPER INSTALLATION OF VARIOUS ELECTRICAL SYSTEMS.
16. WHERE PORTIONS OF INTERIOR RACEWAY SYSTEM ARE EXPOSED TO WIDELY DIFFERENT TEMPERATURES, PROVIDE AIR SEALING PER NEC TO PREVENT CIRCULATION OF AIR FROM WARMER TO A COOLER SECTION.
17. ALL WIRING SHALL BE 600 VOLT, SOFT DRAWN ANNEALED COPPER, 98% CONDUCTIVITY, CONTINUOUS FROM OUTLET TO OUTLET. MINIMUM WIRE SIZE #12. ALL WIRE SHALL BE STRANDED TYPE THHN OR THWN–2 (WET RATED FOR 90° C). ALL WIRES SHALL BE COLOR CODED WITH SAME COLOR CONNECTED TO SAME UNGROUNDED PHASE THROUGHOUT THE INSTALLATION.
18. ALL ELECTRICAL WIRING SHALL BE INSTALLED IN CONDUIT. NO SURFACE MOUNTED WIREMOLD SHALL BE ALLOWED IN FINISHED SPACES. MC CABLE SHALL BE ALLOWED INSIDE EXIST STUD WALLS OR CHASE WALLS.
19. PROVIDE AND INSTALL FINAL CONNECTIONS TO ALL EQUIPMENT PROVIDED BY OTHER TRADES AND/OR FURNISHED BY OWNER INCLUDING ALL NECESSARY CONDUIT, CORDS, PLUGS, WHIPS, HARDWIRING, ETC. IN PARTICULAR CONFIRM CONNECTION REQUIREMENTS WITH DELIVERED EQUIPMENT PRIOR TO ROUGH–IN.
20. ALL MATERIAL MUST BE NEW AND OF GOOD QUALITY AND SHALL BEAR THE STAMP OF APPROVAL OF THE UNDERWRITERS' LABORATORIES, INC. (U.L.).

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025


ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING


ELECTRICAL AND FIRE ALARM NOTES

j-E.001


STANTON ENGINEERING GROUP
INFO@STANTON–ENGR.COM (713) 305–6280


TEXAS ENG. FIRM REG. NO. F–21833 © 2025 ALL RIGHTS RESERVED


12999 W. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77043





SYMBOL: ▽

## 1 TYPICAL DATA OUTLETS

NO SCALE

NOTES:
1. PROVIDE DEEP 4 11/16" X 4 11/16" X 2 1/8", 2-GANG BACK BOX FOR ALL DATA OUTLETS.
   1.A. PROVIDE SINGLE GANG MUDRING FOR DATA OUTLETS WITH 1-4 DROPS.
   1.B. PROVIDE PULL STRING IN ALL LOW VOLTAGE CONDUITS.
2. LOW VOLTAGE CABLING AND DEVICES BY DIVISION 27.
3. REFERENCE TECHNOLOGY DRAWINGS FOR ADDITIONAL INFORMATION.





SYMBOL: ⏀ SYMBOL: ⏁

## 2 TYPICAL POWER & DATA OUTLET DETAIL

NO SCALE

NOTES:
1. LOCATE DEVICES GROUPED TOGETHER AS CLOSELY TOGETHER AS POSSIBLE.
   1.A. USE CADDY TSGB16, RBS16 OR SIMILAR MOUNTING BAR IN SHEETROCK WALLS.




SYMBOL: ⏀ SYMBOL: ⏁ SYMBOL: ⏀USB SYMBOL: ⏀GFI

## 3 TYPICAL ELECTRICAL DEVICES

NO SCALE

NOTES:
1. ALL DEVICES SHALL BE COLOR CODED PER SPECIFICATIONS WITH 302/304 STAINLESS STEEL, STANDARD SIZE, FACEPLATES.
2. ONLY SELECT RECEPTACLES ARE SHOWN HERE. PROVIDE SIMILAR LABELS ON ALL SWITCHES, NEMA POWER OUTLETS, ETC.
3. PROVIDE LABEL WITH RED TEXT READING "EMERGENCY" FOR DEVICES ON GENERATOR FED CIRCUITS.
4. PROVIDE TYPEWRITTEN OR PREMADE CIRCUIT LABELS INDICATING THE ELECTRICAL CIRCUIT ON:
   4.A. INSTALLED WIRING AT EACH SPLICE POINT
   4.B. EACH J-BOX ABOVE CEILING WITH WIRING INSTALLED OR MODIFIED AS PART OF THIS PROJECT.
   4.C. AFFIXED TO THE FRONT OF EACH NEW AND EXISTING DEVICE FACEPLATE IN THE AREA OF RENOVATION.
        CIRCUIT LABEL
        XX-## A. XX = PANEL DESIGNATION
        B. ## = AS-BUILT CIRCUIT DESIGNATION

STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM (713) 360-4090
TEXAS ENGINEERING FIRM REGISTRATION NO. F-018332 | 2025 ALL RIGHTS RESERVED
1300 W. SAM HOUSTON PARKWAY N., SUITE 121, HOUSTON, TX 77043

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

j

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL


STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED PROFESSIONAL ENGINEER
07.18.2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL DEVICE DETAILS


j-E.010




## 10 MECHANICAL - ELECTRICAL COORDINATION DETAIL

NO SCALE

**COORDINATE WITH OTHER TRADES TO ENSURE NO PIPING AND DUCTWORK ABOVE ELECTRICAL EQUIPMENT AS SHOWN. PROVIDE WORKING CLEARANCE IN FRONT OF STARTERS, DISCONNECTS, PANELS, XFMRS AND ADDITIONALLY PER CODE.**




## 11 CONDUIT ROOF PENETRATION DETAIL


NO SCALE




## 12 ROOF AND CANOPY CONDUIT SUPPORT DETAIL

NO SCALE

1. COORDINATE WITH ARCHITECTURAL DRAWINGS, DETAILS, SPECIFICATIONS AND OTHER TRADES.





## 13 CANOPY LIGHT MOUNTING DETAIL TYPE 1

NO SCALE

NOTES:

1. MOUNTING PLATES SHALL BE WELDED TO CANOPY TO MOUNT LIGHT FIXTURES.
2. FOR FIXTURES WITH END CONDUIT ATTACHMENTS ALL CANOPY PENETRATIONS SHALL BE MADE OFF CENTER FROM THE FIXTURE WIRING ENTRY POINT AND SHALL HAVE WEATHERTIGHT SEALING. (SHOWN HERE)
3. CANOPY PENETRATIONS ABOVE FIXTURES SHALL BE PERMITTED ONLY WHERE THE SUPPLIED FIXTURE HAS NO END CONDUIT ATTACHMENTS.
4. CONDUIT SHALL BE SEALED BOTH ABOVE AND BELOW THE CANOPY PENETRATION AND AGAIN AT THE FIXTURE ENTRY POINT TO PREVENT WATER FROM ENTERING THE LIGHTING FIXTURE.
5. CANOPY PENETRATIONS SHALL BE MADE AS CLOSE TO CONDUIT ENTRY PENETRATION POINT AS POSSIBLE AND CONDUIT SHALL BE ROUTED TO MINIMIZE EXPOSED CONDUIT.





## 7 EDF GFI PROTECTION DETAIL

NO SCALE

NOTES:

1. MODIFY EXISTING WALL AS NEEDED TO INSTALL NEW RECEPTACLE AND REMOTE GFI TEST SWITCH. PATCH/REPAIR WALL AS NEEDED TO MATCH EXISTING.
2. WIRE NEW RECEPTACLE DOWNSTREAM OF REMOTE GFI TEST SWITCH.
3. REMOTE GFI TEST SWITCH SHALL BE A DEAD FRONT GFI DEVICE TO BE INSTALLED FLUSH MOUNTED IN WALL WITH EDF SERVED AND PROVIDE GFI PROTECTION FOR THE RECEPTACLE LOCATED WITHIN THE EDF HOUSING.
4. GFI TEST SWITCH SHALL BE READILY ACCESSIBLE PER NEC 210.8.
5. COORDINATE RECEPTACLE LOCATION(S) WITHIN EDF HOUSINGS WITH MANUFACTURER'S INSTALLATION INSTRUCTIONS.





## 8 TRANSFORMER CONNECTION AND GROUNDING DETAIL

NO SCALE


NOTES:

1. INSTALL GROUND ROD ADJACENT TO TRANSFORMER AND SEAL PENETRATION AROUND GROUND ROD.
2. WHERE AN ISOLATED GROUND IS PROVIDED MAKE THE CONNECTION AT THE TRANSFORMER AND RUN DIRECTLY TO THE ISOLATED GROUND BAR IN THE PANELBOARD. DO NOT DEFINE THE ISOLATED GROUND AT THE PANELBOARD.
3. FINAL CONNECTIONS TO TRANSFORMERS SHALL BE MADE IN FLEXIBLE CONDUIT. PROVIDE LIQUID TIGHT CONSTRUCTION AND FITTINGS IN WET, DAMP OR OUTSIDE AREAS EXCEPT WHERE LOCATED IN AIR HANDLING ROOMS. REFERENCE SPECIFICATIONS FOR ADDITIONAL INFORMATION.





## 9 PIGTAIL WIRING DETAIL FOR ELECTRICAL DEVICE

NO SCALE





## 1 CONDUIT/J-BOX DETAIL FOR LIGHT FIXTURES IN LAY-IN CEILING

NO SCALE




## 2 FIXTURE SUPPORT DETAIL

NO SCALE





## 3 TRAPEZE MOUNTED CONDUIT DETAIL

NO SCALE

NOTES:

1. ALL SUPPORT DEVICES SHALL BE UL LISTED AND NEC APPROVED.
2. REFER TO NEC FOR CONDUIT SUPPORT SPACING.





## 4 WALL MOUNTED CONDUITS

NO SCALE

NOTES:

1. ALL SUPPORT DEVICES SHALL BE UL LISTED AND NEC APPROVED.
2. REFER TO NEC FOR CONDUIT SUPPORT SPACING.





## 5 FIREWALL PENETRATION DETAIL

NO SCALE

NOTES:

1. FIRE RATING OF COMPLETED FIREPROOFED ASSEMBLY SHALL BE EQUAL OR EXCEED RATING OF WALL.




## 6 GROUNDING BUSHING WIRING DETAIL

NO SCALE

NOTE:

1. PROVIDE AND INSTALL GROUNDING BUSHINGS FOR DISCONNECT SWITCHES, PANELS AND TRANSFORMERS.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

j

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL DETAILS

j-E.011

STANTON ENGINEERING GROUP
INFORMATION-DESIGN
(713) 360-4080
TEXAS ENG. FIRM REG. NO. F-018537 © 2025 ALL RIGHTS RESERVED
12800 W. I-10 FRONTAGE RD, SUITE 125, HOUSTON, TX 77065




## 5 TYPICAL BRANCH CIRCUIT PANEL LABELING DETAIL

NO SCALE

NOTES:

1. LAYOUT OF PANELBOARD, INCLUDING LOCATIONS OF NAMEPLATES, CIRCUIT DIRECTORY, AND OTHER LABELING IS SHOWN FOR REFERENCE ONLY, FIELD LOCATE AS NEEDED BASED ON TRUE EQUIPMENT LAYOUT AND DIMENSIONS.
2. REFERENCE OWNER'S DESIGN GUIDELINES FOR ADDITIONAL LABELING REQUIREMENTS.

(1) PROVIDE LAMACOID NAMEPLATE WITH 5/16" LETTERS SHOWING PANEL NAME, AMPERAGE RATING, VOLTAGE, AND FROM WHERE POWER IS DERIVED. ATTACH WITH MASTIC AND TWO SCREWS. COORDINATE TO GIVE SAME NAME AS PANEL SCHEDULE. IF USED AS MAIN SERVICE PANEL, PROVIDE SHORT CIRCUIT AVAILABLE AND RATING INFORMATION.

(2) PROVIDE PERMANENT ARC FAULT WARNING LABEL.


(3) FOR ALL NEW ELECTRICAL EQUIPMENT, PROVIDE PERMANENTLY AFFIXED LABEL STATING FAULT CURRENT AT THE TIME OF INSTALLATION AND CALCULATION. THE LABEL SHALL BE MINIMUM 2" X 3" IN SIZE, AND INCLUDE THE DATE OF THE CALCULATION. REFERENCE ELECTRICAL DRAWINGS AND EQUIPMENT SHORT CIRCUIT ANALYSIS TABLE. ATTACH WITH MASTIC AND TWO SCREWS.

(4) PROVIDE INFORMATION PER INDUSTRY STANDARDS, BUT SHALL INCLUDE VOLTAGE, PHASE, BUS AMPERAGE, AND SHORT CIRCUIT RATING

(5) FOR EACH CIRCUIT PROVIDE PERMANENT LABEL INDICATING CIRCUIT BREAKER NUMBER, NUMBER SHALL MATCH CIRCUIT DIRECTORY.

(6) CIRCUIT DIRECTORY TO BE COMPLETED AT END OF JOB, TYPEWRITTEN, STATING EQUIPMENT OR ROOMS SERVED BY CIRCUIT. EVEN CIRCUIT ON RIGHT SIDE OF CARD, ODD ON LEFT. PROVIDE LAMINATED DIRECTORY FOR EXTERIOR OR WET LOCATIONS.

(7) PROVIDE PERMANENT LABEL INDICATING COLOR CODING OF PHASE CONDUCTORS BASED ON VOLTAGE USING BUILDING COLOR SCHEME AS IDENTIFIED IN THE OWNER'S DESIGN GUIDELINES.




## 1 TYPICAL DISCONNECT, STARTER, & CONTACTOR LABELING DETAIL

NO SCALE

NOTES:

1. LOCATIONS OF NAMEPLATES SHOWN FOR REFERENCE ONLY, FIELD LOCATE AS NEEDED BASED ON TRUE EQUIPMENT LAYOUT AND DIMENSIONS. REFERENCE OWNER'S DESIGN GUIDELINES FOR ADDITIONAL LABELING REQUIREMENTS.

(1) PROVIDE AN ENGRAVED NAMEPLATE SHOWING LOAD SERVED, EQUIPMENT VOLTAGE, AND CIRCUIT NUMBER MATCHING AS-BUILT CONDITIONS.

(2) PROVIDE AN ENGRAVED NAMEPLATE SHOWING LOADS SERVED, VOLTAGES, AND CIRCUIT NUMBERS MATCHING AS-BUILT CONDITIONS FOR ALL CONTACTOR CIRCUITS. LOADS SERVED SHALL BE "LIGHTING", "FAN", "RECEPTACLES", "PUMP", "WATER HEATER", OR SIMILAR DESCRIPTIVE NOTE.

**DISHWASHER**
**480V, 3PH, 3 WIRE**
**FROM HK-2/4/6**

## 2 DISCONNECT LABELING

NO SCALE

NOTES:

1. PROVIDE LABEL ON EACH DISCONNECT AND FUSED SWITCH.
   1.1. FOR DISCONNECTS AND FUSED SWITCHES REPLACE "PANEL P1NA" WITH THE LOAD SERVED.
   1.2. REFER TO OWNER'S STANDARDS FOR ADDITIONAL LABEL REQUIREMENTS.
2. PROVIDE LABEL ON ELECTRICAL PANEL AND TRANSFORMER.
   2.1. REPLACE "PANEL P1NA" WITH THE PANEL OR TRANSFORMER NAME BEING LABELED.
3. REPLACE "400A FUSED SWITCH" WITH UPSTREAM SOURCE OR CONNECTION.
   3.1. IF FED FROM A XFMR REPLACE "400A FUSED SWITCH" WITH "XFMR XX" WHERE XX IS THE FIELD VERIFIED XFMR NAME.
4. REPLACE VOLTAGE CONFIGURATION TO MATCH THE EQUIPMENT BEING LABELED.
5. REFERENCE FLOOR PLANS FOR EQUIPMENT LOCATIONS.

**⚠ WARNING**

**Arc Flash and Shock Hazard**
**Appropriate PPE Required**


| FLASH PROTECTION | | SHOCK PROTECTION | |
|---|---|---|---|
| Incident Energy at: | 18 in | Shock Risk When Cover is Removed | 480 VAC |
| Min. Arc Rating: | 0.45 cal/cm² | Limited Approach | 42 in |
| Arc Flash Boundary: | 10 in | Restricted Approach | 12 in |
| PPE: Per NFPA 70E 2015 | 1 | Equipment Name: **PANEL HA** Prot Dev: 225/3 CB from Panel DA | |

## 3 TYPICAL ARC FLASH LABEL DETAIL

NO SCALE

NOTES:

1. VALUES AND NAMES SHOWN HERE ARE FOR REFERENCE ONLY, MODIFY TO REFLECT PROJECT'S ARC FLASH STUDY VALUES AND EQUIPMENT NAMES.
2. IF MIN. ARC RATING IS OVER 40CAL/CM² MODIFY "WARNING" TEXT TO READ "DANGER" AND PROVIDE RED SHADING IN LIEU OF ORANGE SHOWN.




## 4 TYPICAL TRANSFORMER LABELING DETAIL

NO SCALE

NOTES:

1. LOCATIONS OF NAMEPLATES SHOWN FOR REFERENCE ONLY, FIELD LOCATE AS NEEDED BASED ON TRUE EQUIPMENT LAYOUT AND DIMENSIONS.

(1) PROVIDE AN ENGRAVED NAMEPLATE SHOWING EQUIPMENT NAME, RATING, VOLTAGE, SOURCE.

STANTON ENGINEERING GROUP
INFORMATION@STANTONENGINEERING.COM | (713) 360-6080
TEXAS ENG. FIRM REG. NO. F-018537-0 | 2025 ALL RIGHTS RESERVED
12800 W. I-10 KATY FREEWAY, SUITE 725, HOUSTON, TX 77065

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

j

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER

07.18.2025

MWA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL
DETAILS

j-E.012

## KITCHEN AREA ELECTRICAL NOTES

1. REFER TO KITCHEN CONSULTANTS "FS" DRAWINGS FOR ADDITIONAL REQUIREMENTS PARTICULARLY NOTING MOUNTING HEIGHTS OF EQUIPMENT OUTLETS AND JUNCTION BOXES, AND WHETHER SERVICE IS FROM WALL, FLOOR OR OVERHEAD.
2. SOME RECEPTACLES SHALL BE MOUNTED HORIZONTALLY, REFER TO KITCHEN CONSULTANTS "FS" DRAWINGS.
3. FOR DEVICES WITH SERVICE FROM FLOOR, RUN UNDERGROUND CONDUIT FROM DEVICES TO NEAREST COLUMN OR WALL THEN TURN CONDUIT UP AND RUN CONDUIT IN CEILING CAVITY.
4. LIGHT SWITCHES AND RECEPTACLES NOT SERVING A SPECIFIC PIECE OF EQUIPMENT SHALL BE MOUNTED AT ADA HEIGHTS.
5. CONNECTION TYPE SHOWN ON KITCHEN ELECTRICAL FLOOR PLAN IS FOR BIDDING PURPOSES, COORDINATE WITH KITCHEN EQUIPMENT SUPPLIER FOR FINAL CONNECTIONS:
   - 5.A. OBTAIN WIRING INSTRUCTIONS FOR EACH PIECE OF EQUIPMENT FROM EQUIPMENT SUPPLIER PRIOR TO ORDERING WIRING DEVICES AND ROUGH-IN.
   - 5.B. IF EQUIPMENT REQUIRES CORD AND PLUG CONNECTION, CONTRACTOR SHALL PROVIDE NEMA POWER CORD, PLUG, AND RECEPTACLES PER MANUFACTURER'S INSTRUCTION.
   - 5.C. IF EQUIPMENT REQUIRES JUNCTION BOX AND/OR DISCONNECT SWITCH, CONTRACTOR SHALL PROVIDE JUNCTION BOX AND DISCONNECT SWITCH AND CONNECT EQUIPMENT WITH SEALTITE FLEXIBLE CONDUIT.
6. ALL DISCONNECT SWITCHES IN THE KITCHEN AREA SHALL BE NEMA 4XSS STAINLESS STEEL.
7. WHERE PORTIONS OF INTERIOR RACEWAY SYSTEM ARE EXPOSED TO WIDELY DIFFERENT TEMPERATURES, PROVIDE AIR SEALING PER NEC TO PREVENT CIRCULATION OF AIR FROM WARMER TO A COOLER SECTION.
8. FLEXIBLE CONDUIT IN KITCHENS, FOOD PRODUCTION SPLASH ZONES AND WASH DOWN AREAS, FOOD PROCESSING, AND SIMILAR AREAS SHALL BE LIQUID TIGHT CONSTRUCTION INCORPORATING A BACTERIAL GROWTH INHIBITING PVC JACKET THAT MAY BE CLEANED WITHOUT DEGREDATION TO THE JACKET BLEACHING ELEMENTS AND APPROVED FITTINGS FOR WET LOCATION.
   - 8.A. AFC SZ TYPE LFMC OR EQUAL BY KAF-TECH.
9. INTERLOCK KITCHEN EXHAUST HOOD FIRE SYSTEM WITH FIRE ALARM SYSTEM.
10. PROVIDE RELAYS AND INTERLOCK KITCHEN HOOD FANS WITH FIRE ALARM SYSTEM. ACTUATION OF ANY ALARM INITIATING DEVICE SHALL DE-ENERGIZE KITCHEN HOOD FANS.
11. ALL GFI RECEPTACLES IN KITCHEN SHALL BE PASS & SEYMOUR MODEL 2097TRWR-XX TO EXCEED UL943 VOLTAGE SURGE REQUIREMENTS.





## 4 FIRE PROTECTION SYSTEM DETAIL

NO SCALE

NOTES:

1. ANSUL MODEL R-120 FIRE PROTECTION SYSTEM AND TANK(S)
2. ELECTRICAL CONTRACTOR TO FURNISH AND INSTALL POWER DISCONNECT DEVICES FOR ALL EQUIPMENT BELOW THE HOOD, SHUTTING OFF ALL SERVICE, INCLUDING CONTROL VOLTAGE, UPON ACTIVATION OF THE FIRE PROTECTION SYSTEM.
3. MICRO-SWITCH FURNISHED WITH SYSTEM TO BE INTERWIRED TO THE SHUT-OFF DEVICES FOR THE COOKING EQUIPMENT BY THE ELECTRICAL CONTRACTOR.
4. ELECTRICAL CONTRACTOR TO FURNISH AND INSTALL AN OCTAGON SHAPED HANDY BOX FOR THE PULL STATION AT 54" ABOVE THE FLOOR WITH 1/2" CONDUIT FROM THE TOP OF THE BOX TO 6" ABOVE THE CEILING.
5. GAS SHUT-OFF VALVE FURNISHED WITH THE SYSTEM (IF REQUIRED) TO BE INSTALLED IN THE GAS LINE SERVING THE COOKING EQUIPMENT BY THE PLUMBING CONTRACTOR. VERIFY SIZE OF GAS LINE.
6. ALL EXPOSED PIPEWORK TO BE STAINLESS STEEL OR CHROME WHERE EXPOSED.
7. VERIFY LOCATION OF REMOTE MANUAL PULL STATION.
8. UNIT MUST BE PLACED WITHIN EASY ACCESS OF EXIT DOOR.





## 5 KITCHEN HOOD FAN CONTROL SCHEMATIC

NO SCALE

NOTES:

1. THE FANS SHALL BE WIRED SO THAT ONE LOCAL SWITCH TURNS ON ASSOCIATED SUPPLY AND EXHAUST FANS.
2. IF THE FIRE ALARM IS IN ALARM, A FIRE ALARM CONTROL CONTACT SHALL CAUSE THE SUPPLY FAN TO STOP AND THE EXHAUST FAN TO START, EVEN IF THE CONTROL SWITCH IS "OFF".
3. SCHEMATIC IS DIAGRAMMATIC. PROVIDE INTERLOCK WIRING BASED ON EQUIPMENT PROVIDED AND FAN VOLTAGE TO IMPLEMENT THE SEQUENCE SPECIFIED.
4. COORDINATE BETWEEN FIRE ALARM CONTRACTOR, CONTROLS CONTRACTOR AND ELECTRICAL CONTRACTOR TO PROVIDE A COMPLETE INSTALLATION.
5. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.





## 1 GAS VALVE DETAIL

NO SCALE

NOTES:

1. GAS VALVE HOUSINGS ARE NOT SHOWN ON THE ELECTRICAL DRAWING. GC AND ELECTRICAL CONTRACTOR SHALL COORDINATE SIZE AND LOCATION OF GAS VALVE HOUSINGS.
2. SEE FOOD SERVICE CONSULTANT'S DRAWINGS ADDITIONAL INFORMATION AND REQUIREMENTS.
3. PROVIDE MINIMUM 3/4"C AS SHOWN ON THIS DETAIL.





## 2 RECESSED FIRE PULL DETAILS

NO SCALE

NOTES:

1. VERIFY LOCATION OF REMOTE MANUAL PULL STATION.
   - 1.A. MANUAL PULL STATION MUST BE PLACED WITHIN EASY ACCESS OF EXIT DOOR.
   - 1.B. MANUAL PULL STATION MUST BE PLACED NO LESS THAN 4 FEET AWAY FROM KITCHEN HOOD BUT WITHIN A MAXIMUM OF 20 FEET FROM THE KITCHEN HOOD.




## 3 TYPICAL PEDESTAL MOUNTED DEVICE

NO SCALE

NOTES:

1. ALL FACEPLATES SHALL BE STAINLESS STEEL.
2. PEDESTAL BOX PROVIDED BY DIVISION 26.
   - 2.A. A STANDARD DUPLEX INSTALLATION IS SHOWN FOR REFERENCE, PROVIDE SIMILAR INSTALLATION FOR QUAD RECEPTACLES, GFI RECEPTACLES, DATA OUTLETS, NEMA POWER OUTLETS, ETC.
   - 2.B. ALL PEDESTAL BOXES TO BE DOUBLE FACED WITH ONE BLANK FACE FOR FUTURE GROWTH. 2-GANG PEDESTALS WITH ONE BLANK FACE FOR QUAD RECEPTACLE LOCATIONS.
   - 2.C. PEDESTAL BOXES TO BE SIZED BY DIVISION 26 TO PROVIDE SCHEDULED DEVICES ON A SINGLE FACE AND SUFFICIENT DEPTH FOR BACK TO BACK DEVICES ON DOUBLE FACED PEDESTALS.
   - 2.D. BASIS OF DESIGN:
     - 2.D.A. 1-GANG ELECTRICAL DEVICES: LEGRAND LBP2 OR WATER SAVER E400SA-WS
     - 2.D.B. 1-GANG LOW VOLTAGE DEVICES: LEGRAND LBP2 OR WATER SAVER E400SA-WS
     - 2.D.C. 2-GANG ELECTRICAL DEVICES: WATER SAVER E600SA-WS
     - 2.D.D. 2-GANG LOW VOLTAGE DEVICES: WATER SAVER E600SA-WS
3. INSTALLATION REQUIREMENTS:
   - 3.A. STUB UP CONDUIT ABOVE FLOOR TO PEDESTAL BOX CONNECTION LOCATION.
   - 3.B. GROUT GAP BETWEEN FINISHED FLOOR AND BOTTOM OF PEDESTAL BOX.
   - 3.C. PROVIDE TRANSITION PIECE TO CONTINUE FINISHED FLOOR TO BOTTOM EDGE OF SERVICE FITTING AND CONCEAL GROUT. TRANSITION PIECE TO MATCH ARCHITECT'S FINISH SCHEDULE.
   - 3.D. PEDESTAL BOX TO BE INSTALLED SQUARE TO THE FINISHED FLOOR.
4. PROVIDE TYPEWRITTEN OR PREMADE CIRCUIT LABELS ON INSTALLED WIRING AT EACH DEVICE AND SPLICE POINT.
5. PROVIDE TYPEWRITTEN LABEL AFFIXED TO THE FRONT OF EACH DEVICE FACEPLATE INDICATING ELECTRICAL CIRCUIT.

CIRCUIT LABEL

XX-##

- A. XX = PANEL DESIGNATION
- B. ## = AS-BUILT CIRCUIT DESIGNATION

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

j

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER

07.18.2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL
KITCHEN DETAILS

j-E.013

STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM | (713) 305-4080
TEXAS ENG. FIRM REG NO. F-018332 | © 2025 ALL RIGHTS RESERVED
13999 W. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77040

LIGHTING SYSTEM FUNCTIONAL TESTING AND DOCUMENTATION NOTES:

1. PRIOR TO PASSING FINAL INSPECTION, THE CONTRACTOR SHALL PERFORM FUNCTIONAL TESTING IN THE PRESENCE OF THE REGISTERED DESIGN PROFESSIONAL, THE OWNER AND/OR THEIR AGENT. THE FUNCTIONAL TESTING SHALL BE AS REQUIRED BY SECTION C408.3.1 OF THE 2021 IECC.
   1.A. THE FUNCTIONAL TESTING SHALL PROVIDE EVIDENCE THAT THE LIGHTING CONTROL SYSTEMS, INCLUDING BOTH HARDWARE AND SOFTWARE, ARE CALIBRATED, ADJUSTED, PROGRAMMED AND IN PROPER WORKING CONDITION IN ACCORDANCE WITH THE CONSTRUCTION DOCUMENTS AND MANUFACTURER'S INSTRUCTIONS.
   1.B. THE FUNCTIONAL TESTING SHALL BE IN ACCORDANCE WITH SECTIONS C408.3.1.1 AND C408.3.1.2 OF THE 2021 IECC FOR THE APPLICABLE CONTROL TYPE.
   1.C. A WRITTEN REPORT SHALL BE GENERATED DOCUMENTING THE FUNCTIONAL TESTING RESULTS IN ACCORDANCE WITH THE 2015 IECC REQUIREMENTS.
2. ALL LIGHTING CONTROLS O&M MANUALS, AS-BUILTS, TESTING REPORTS AND DOCUMENTATION RELATED TO THE LIGHTING CONTROL SYSTEM SHALL BE PROVIDED IN THEIR FINAL AND APPROVED FORM WITHIN 60 DAYS OF THE CERTIFICATE OF OCCUPANCY. ALL DOCUMENTS CERTIFYING THAT THE INSTALLED LIGHTING CONTROLS MEET DOCUMENTED PERFORMANCE CRITERIA OF SECTION C405 OF THE 2021 IECC SHALL BE INCLUDED IN THE O&M MANUALS.
3. ALL DOCUMENTS FROM ITEMS #1 AND #2 ABOVE SHALL BE COMBINED AND PROVIDED TO THE OWNER WITHIN 90 DAYS FROM THE DATE OF RECEIPT OF THE CERTIFICATE OF OCCUPANCY.

# LIGHT FIXTURE SCHEDULE

## EXTERIOR LIGHT FIXTURE SCHEDULE

| | | | |
|---|---|---|---|
| RECESSED 6" DOWNLIGHT WET LOCATION | D5<br>D5Y | 6" DIAMETER RECESSED LED DOWNLIGHT, SPECULAR CLEAR REFLECTOR, MEDIUM (56') BEAM DISTRIBUTION, 1000 LUMENS, 4000K COLOR TEMPERATURE, 120-277V MULTIVOLT INPUT, 1% 0-10V DIMMING DRIVER.<br>LIGHTOLIER 6R-N / C6L-10-9-40-M-Z10-U / C6-R-DL-CC | 9W |
| RECESSED 6" DOWNLIGHT WET LOCATION | D6<br>D6Y | 6" DIAMETER RECESSED LED DOWNLIGHT, SPECULAR CLEAR REFLECTOR, MEDIUM (56') BEAM DISTRIBUTION, 2000 LUMENS, 4000K COLOR TEMPERATURE, 120-277V MULTIVOLT INPUT, 1% 0-10V DIMMING DRIVER.<br>LIGHTOLIER 6R-N / C6L-20-9-40-M-Z10-U / C6-R-DL-CC | 22W |
| SURFACE CANOPY SQUARE LED | WC1<br>WC1X<br>WC1Y | 9" SQUARE SURFACE LED CANOPY LIGHT, 4000K COLOR TEMPERATURE, 3500 LUMENS, 120-277V MULTIVOLT INPUT, DARK BRONZE FINISH.<br>EELP VR7-T-28L-QT-40K (EBLED9W) | 28W |
| EXTERIOR WALL PACK | WP1<br>WP1X<br>WP1Y | 7" WDE WALL MOUNTED LED, 4000K COLOR TEMPERATURE, 5000 LUMENS, TYPE 3 DISTRIBUTION, 120-277 MULTIVOLT INPUT, WET LOCATION, 10KV KA SURGE PROTECTION.<br>REFER TO ARCH FOR MOUNTING HEIGHT.<br>FINISH TO BE SELECTED BY ARCHITECT FROM ALL AVAILABLE FINISHES.<br>GARDCO GEOFORM SMALL GWS-A04-740-UNV-XX FINISH (EM) | 34W |
| EXTERIOR WALL PACK | WP2<br>WP2X<br>WP2Y | 12" WDE WALL MOUNTED LED, 4000K COLOR TEMPERATURE, 8500 LUMENS, TYPE 3 DISTRIBUTION, 120-277 MULTIVOLT INPUT, WET LOCATION. REFER TO ARCH FOR MOUNTING HEIGHT.<br>REFER TO ARCH FOR MOUNTING HEIGHT.<br>FINISH TO BE SELECTED BY ARCHITECT FROM ALL AVAILABLE FINISHES.<br>GARDCO GEOFORM MEDIUM GWM-A11-740-T3M-UNV-XX FINISH (REMOTE EM BATTERY) | 52W |
| EXTERIOR WALL PACK | WP3<br>WP3X<br>WP3Y | 17" WDE WALL MOUNTED LED, 4000K COLOR TEMPERATURE, 12500 LUMENS, TYPE 3 DISTRIBUTION, 120-277 MULTIVOLT INPUT, WET LOCATION. REFER TO ARCH FOR MOUNTING HEIGHT.<br>REFER TO ARCH FOR MOUNTING HEIGHT.<br>FINISH TO BE SELECTED BY ARCHITECT FROM ALL AVAILABLE FINISHES.<br>GARDCO GEOFORM MEDIUM GWM-A14-740-T3M-UNV-XX FINISH (REMOTE EM BATTERY) | 77W |

1. LIGHT FIXTURE CATALOG NUMBERS AND DESCRIPTIONS ARE SCHEDULED FOR ESTABLISHING QUALITY, APPEARANCE AND PERFORMANCE OF THE FIXTURES. EXACT CATALOG NUMBERS DESCRIBING MOUNTING CONDITIONS AND REQUIREMENT RELATED TO TRIM FOR ALL FIXTURES SHALL BE CONFIRMED (BY THE ELECTRICAL CONTRACTOR) WITH THE ROOM FINISH SCHEDULE AND REFLECTED CEILING PLANS ON THE ARCHITECTURAL PLANS PRIOR TO BIDDING AND SUBMITTING LIGHT FIXTURES. PROVIDE DRY WALL KIT AS REQUIRED.
2. ALL 'X', 'Y', AND 'Z' TYPE FIXTURES SHALL HAVE EMERGENCY POWER BACKUP. EMERGENCY POWER SOURCES SHALL MONITOR POWER UPSTREAM OF THE LIGHTING CONTROLS TO SEE IF POWER IS LOST. BATTERY PACKS AND INVERTERS SHALL BE CAPABLE OF POWERING THE DESIGNATED FIXTURE(S) WITH AN OUTPUT OF 1400 LUMENS FOR A MINIMUM OF 90-MINUTES. PROVIDE REMOTE BATTERY PACKS OR INVERTERS AS NECESSARY. EMERGENCY LIGHTS SHALL OPERATE ONLY UPON LOSS OF POWER; ALSO, PROVIDE AND WIRE TEST SWITCH AND LED INDICATOR LIGHT FOR EMERGENCY BATTERY. SEE WIRING INSTRUCTION SUPPLIED BY EMERGENCY BATTERY MANUFACTURER.
   2.A. 'X' TYPE FIXTURES (AX, ETC.) HAVE EMERGENCY GENERATOR POWER LIGHTING TRANSFER DEVICES.
   2.B. 'Y' TYPE FIXTURES (MY, ETC.) HAVE INDIVIDUAL 90-MINUTE EMERGENCY BATTERY POWER.
   2.C. 'Z' TYPE FIXTURES (GTZ, ETC.) HAVE 90-MINUTE INVERTER EMERGENCY BATTERY POWER.
3. PROVIDE BASE COVER FOR ALL LIGHT POLES.
4. ALL EXTERIOR FIXTURES SHALL BE WET RATED WITH COLD WEATHER BALLASTS AND BATTERY PACKS.
5. PROVIDE SPARE FIXTURES AND EMERGENCY DEVICES PER SPECIFICATIONS.
6. WHERE FIXTURE FINISHES ARE INDICATED TO BE SELECTED BY ARCHITECT THE CONTRACTOR SHALL INCLUDE IN THEIR BID ALL AVAILABLE FINISHES. SUBMIT COMPLETE FIXTURE FINISH OPTIONS AS PART OF THE LIGHTING SUBMITTAL PACKAGE.
7. EQUAL BY PHILIPS (CW LIGHTING), COOPER (PUTTERMAN SCHAROK), AND LITHONIA (LESCO) SHALL BE ACCEPTABLE.

## INTERIOR LIGHT FIXTURE SCHEDULE

| APPLICATION | TYPE | DESCRIPTION | WATTS |
|---|---|---|---|
| 1X4 RECESSED LAY-IN CEILING SELECTABLE CCT & LUMENS | A1<br>A1X<br>A1Y | 2X4 RECESSED LED, SMOOTH FROSTED ACRYLIC LENS, EXTRUDED ALUMINUM FRAME, WHITE FINISH, LAY-IN CEILING, 6000 LUMENS, 4000K COLOR TEMPERATURE, 120-347V MULTIVOLT INPUT, 5% 0-10V DIMMING.<br>SET FIELD SELECTABLE SWITCHES TO NEUTRAL WHITE (4000K) AND HIGH (47W).<br>DAYBRITE 2SBP3550L8CS-4-UNJ-DIM | 47W |
| 1X4 RECESSED LAY-IN CEILING SELECTABLE CCT & LUMENS | B1<br>B1X<br>B1Y | 1X4 RECESSED LED, SMOOTH FROSTED ACRYLIC LENS, EXTRUDED ALUMINUM FRAME, WHITE FINISH, LAY-IN CEILING, 4500 LUMENS, 4000K COLOR TEMPERATURE, 120-347V MULTIVOLT INPUT, 5% 0-10V DIMMING.<br>SET FIELD SELECTABLE SWITCHES TO NEUTRAL WHITE (4000K) AND HIGH (36W).<br>DAYBRITE 1SBP3040L8CS-4-UNJ-DIM | 36W |
| 2X2 RECESSED LAY-IN CEILING SELECTABLE CCT & LUMENS | B2<br>B2X<br>B2Y | 2X2 RECESSED LED, SMOOTH FROSTED ACRYLIC LENS, EXTRUDED ALUMINUM FRAME, WHITE FINISH, LAY-IN CEILING, 4250 LUMENS, 4000K COLOR TEMPERATURE, 120-347V MULTIVOLT INPUT, 5% 0-10V DIMMING.<br>SET FIELD SELECTABLE SWITCHES TO NEUTRAL WHITE (4000K) AND HIGH (36W).<br>DAYBRITE 2SBP3040L8CS-2-UNJ-DIM | 39W |
| 4FT STRIP LED MECHANICAL & STORAGE ROOMS | C<br>CX<br>CY | 4 FOOT STRIP LED, STEEL HOUSING, FROSTED ACRYLIC LENS, 4000 LUMENS, 3500K COLOR TEMPERATURE, CHAIN HANGING SET, WIRE GUARD, 120-277V MULTIVOLT INPUT, 0-10V DIMMING DRIVER. PROVIDE CHAIN HANGING SET AND WIREGUARD IN MECHANICAL ROOMS AND AREAS WITHOUT CEILINGS.<br>SET FIELD SELECTABLE SWITCHES TO NEUTRAL WHITE (4000K) AND HIGH (36W).<br>DAYBRITE SDS-4-2448L-8CST-UNV-DIM | 30W |
| RECESSED 6" DOWNLIGHT | D1<br>D1X<br>D1Y | 6" DIAMETER RECESSED LED DOWNLIGHT, MATTE WHITE FINISH, WIDE (76') BEAM DISTRIBUTION, 1000 LUMENS, 4000K COLOR TEMPERATURE, 120-277V MULTIVOLT INPUT, 1% 0-10V DIMMING DRIVER.<br>LIGHTOLIER 6R-N / C6L-10-9-40-W-Z10-U / C6-R-DL-WH | 9W |
| RECESSED 6" DOWNLIGHT | D2<br>D2X<br>D2Y | 6" DIAMETER RECESSED LED DOWNLIGHT, MATTE WHITE FINISH, WIDE (76') BEAM DISTRIBUTION, 2000 LUMENS, 4000K COLOR TEMPERATURE, 120-277V MULTIVOLT INPUT, 1% 0-10V DIMMING DRIVER.<br>LIGHTOLIER 6R-N / C6L-20-9-40-W-Z10-U / C6-R-DL-WH | 22W |
| EXIT SIGN | XB<br>XS<br>XD | DIE CAST ALUMINUM LED EXIT LIGHT, RED LETTERS, MATTE BLACK HOUSING W/ BRUSHED ALUMINUM FACE, UNIVERSAL ARROWS, 120/277 VOLT DUAL INPUT, 90 MINUTE EMERGENCY BATTERY.<br>VERIFY LETTER AND FACE COLOR WITH OWNER/ARCHITECT PRIOR TO ORDERING.<br>XS=SINGLE FACE, XD=DOUBLE FACE, XB=BACK MOUNTED<br>PHILIPS CHLORIDE ER55L-3-R<br>SURELITES CX7-1/2-R<br>LITHONIA LQC-1/2-R-EL N | 5W |
| EXIT SIGN INTEGRAL BATTERY INTEGRAL EM LIGHT BAR | YB<br>YS<br>YD | THERMOPLASTIC LED EXIT LIGHT WITH INTEGRAL EM LIGHT, RED LETTERS, WHITE HOUSING W/ WHITE FACE, UNIVERSAL ARROWS, 120-277 MULTIVOLT INPUT, 90 MINUTE EMERGENCY BATTERY. VERIFY LETTER AND FACE WITH OWNER/ARCHETICT PRIOR TO ORDERING.<br>YS=SINGLE FACE, YD=DOUBLE FACE, YB=BACK MOUNTED<br>SIGNTEX CLP-BB-U-R-W-DG | 5W |
| TWIN HEAD EM LIGHT INTEGRAL BATTERY WET LOCATION | YT1 | TWIN HEAD EM LIGHT, INJECTION-MOLDED THERMOPLASTIC WHITE HOUSING, GASKETED CLEAR POLYCARBONATE COVER, LED LAMPS, 90-MINUTE EMERGENCY BATTERY.<br>CHLORIDE TPU-W-N-LM7-W | 7W |

# LIGHTING CONTROL SEQUENCE OF OPERATIONS

| ROOM TYPE | AUTO ON | MANUAL ON (VACANCY) | AUTO OFF (20 MIN MAX) | PARTIAL OFF AT NORMAL HOURS | AUTO ON AFTER HOURS | AUTO OFF AFTER HOURS (20 MIN MAX) | TIME ON | TIME OFF | ASTRONOMIC OR PHOTOCELL ON/OFF | AUTO STEP CONTROL WITH OFF | AUTO CONTINUOUS DIM WITH OFF | MANUAL BI-LEVEL REDUCTION CONTROL | MANUAL CONTINUOUS DIM CONTROL | MANUAL ON/OFF SWITCH | MANUAL DIMMER SWITCH | DISPLAY, ACCENT, TASK CONTROL | PLUG LOAD CONTROL | SEQUENCE OF OPERATION |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | OCCUPANCY SENSOR | | | | | | TIME SWITCH/SCHEDULING | | | DAYLIGHT CONTROL | | LIGHT REDUCTION | | MANUAL CONTROL | | | | |
| Kitchen/Serving | | | | | | | • | • | | | | • | | • | | | | LOCAL ON/OFF CONTROLS. LOCAL CONTROLS MAY OVERRIDE BUILDING SCHEDULE AND TURN ALL LIGHTS ON FOR MAXIMUM 2HRS. NETWORK LIGHTING CONTROLS ROOM CONTROLLER CONNECTED TO BUILDING CONTROLS; ON/OFF BASED ON BUILDING SCHEDULE, AFTER HOURS ON/OFF BASED ON OCCUPANCY, COORDINATE SCHEDULING WITH OWNER. WHERE ≥150W IN DAYLIGHT AREA, USE CONTINUOUS DIMMING DAYLIGHTING CONTROL. |
| Restrooms | 100% | | 20 MIN | | | | | | | | | | | • | | | | AUTO ON 100%, AUTO OFF BY LOCAL OCCUPANCY SENSOR. LOCAL ON/OFF CONTROLS ONLY, NO FULLY NETWORKED SYSTEM. |
| Custodial rooms | | • | 20 MIN | | | | | | | | | | | • | • | | | MANUAL ON, AUTO OFF BY LOCAL OCCUPANCY SENSOR. LOCAL ON/OFF CONTROLS ONLY, NO FULLY NETWORKED SYSTEM. |
| Storage rooms | 50% | | 20 MIN | | | | | | | | | | | • | • | | | AUTO ON 50%, AUTO OFF BY LOCAL OCCUPANCY SENSOR. LOCAL ON/OFF/DIMMING CONTROLS ONLY, NO FULLY NETWORKED SYSTEM. |
| Private Offices | 50% | | 20 MIN | | | | | | | | | | | • | • | | • | AUTO ON 50%, AUTO OFF BY LOCAL OCCUPANCY SENSOR. LOCAL ON/OFF/DIMMING CONTROLS ONLY, NO FULLY NETWORKED SYSTEM. |
| Corridors | | | | | 100% | 20 MIN | • | • | | | | | | • | | | | LOCAL ON/OFF CONTROLS. LOCAL CONTROLS MAY OVERRIDE BUILDING SCHEDULE AND TURN ALL LIGHTS ON FOR MAXIMUM 2HRS. NETWORK LIGHTING CONTROLS ROOM CONTROLLER CONNECTED TO BUILDING CONTROLS; ON/OFF BASED ON BUILDING SCHEDULE, AFTER HOURS ON/OFF BASED ON OCCUPANCY, COORDINATE SCHEDULING WITH OWNER. WHERE ≥150W IN DAYLIGHT AREA, USE CONTINUOUS DIMMING DAYLIGHTING CONTROL. |
| Electrical Rooms | | | | | | | | | | | | | | • | | | | MANUAL ON/OFF; LOCAL CONTROL DEVICE NOT TIED TO LVLCS. |
| Building Facade/Landscape | | | | | | | • | • | | | | | | | | | | CONNECTED TO BUILDING CONTROLS THROUGH LIGHTING CONTACTOR; ON/OFF BASED ON BUILDING SCHEDULE. |

1. DIMMER SWITCHES SHALL ACTIVATE PRESET ALL ON LIGHTING LEVEL WHEN PRESSED IN THE UP POSITION. LIGHTING LEVELS MAY BE RAISED/LOWERED BY HOLDING THE DIMMER PADDLE. WHEN PRESSED IN THE DOWN POSITION ALL LIGHTS SHALL SMOOTHLY DIM TO OFF.
2. AT LEAST 50 PERCENT OF ALL 125V, 15- AND 20-AMP RECEPTACLES INSTALLED IN ENCLOSED OFFICES, CONFERENCE ROOMS, ROOMS USED PRIMARILY FOR COPY OR PRINT FUNCTIONS, BREAKROOMS, CLASSROOMS AND INDIVIDUAL WORKSTATIONS, INCLUDING THOSE INSTALLED IN MODULAR PARTITIONS AND MODULE OFFICE WORKSTATION SYSTEMS SHALL HAVE PLUG LOAD CONTROL PER IECC 2021 C405.11.

# LIGHTING CONTACTOR SCHEDULE

| POLE | DESCRIPTION | NORMAL CKT | EM CKT | CONTROL ZONE | CONTACTOR LOCATION | CONTACTOR TYPE |
|---|---|---|---|---|---|---|
| **CONTACTOR CT1** | | | | | | |
| CT1-1 | KITCHEN/SERVING AREA - ZONE 'a' | HK-3 | - | Kitchen-a | CENTRAL PLANT | MAGNETICALLY HELD |
| CT1-2 | SPARE | | | Kitchen-a | CENTRAL PLANT | MAGNETICALLY HELD |
| CT1-3 | SPARE | | | Kitchen-a | CENTRAL PLANT | MAGNETICALLY HELD |
| **CONTACTOR CT2** | | | | | | |
| CT2-1 | KITCHEN/SERVING AREA - ZONE 'b' | HK-3 | - | Kitchen-b | CENTRAL PLANT | MAGNETICALLY HELD |
| CT2-2 | SPARE | | | Kitchen-b | CENTRAL PLANT | MAGNETICALLY HELD |
| CT2-3 | SPARE | | | Kitchen-b | CENTRAL PLANT | MAGNETICALLY HELD |
| **CONTACTOR CT3** | | | | | | |
| CT3-1 | KITCHEN SOFFIT/CANOPY LTS | HK-5 | - | Exterior | CENTRAL PLANT | MAGNETICALLY HELD |
| CT3-2 | | | | Exterior | CENTRAL PLANT | MAGNETICALLY HELD |
| CT3-3 | | | | Exterior | CENTRAL PLANT | MAGNETICALLY HELD |

1. REFERENCE TYPICAL LIGHTING CONTACTOR WIRING DIAGRAM.
2. EMERGENCY AND NORMAL ZONES WITHIN THE KITCHEN/SERVING SHALL HAVE SEPARATE CONTROLS TO ALLOW FOR LIGHTING REDUCTION CONTROL.
3. LIGHTING CONTACTORS SHALL BE DIN RAIL MOUNTED, MAGNETICALLY HELD TYPE WITH THREE WIRE CONTROL BY THE BAS.
   3.A. PROVIDE CABINET AT EACH LOCATION TO MOUNT ALL CONTACTORS IN A SINGLE ENCLOSURE. ENCLOSURE SIZED BY DIVISION 26.
   3.B. PROVIDE SEPARATE HOA SWITCHES IN THE FRONT COVER OF THE ENCLOSURE WIRED TO CONTROL THE FOLLOWING ZONES SEPARATELY.
      3.B.1. INTERIOR LIGHTING (ALL INTERIOR LIGHTING GROUPS)
      3.B.2. EXTERIOR LIGHTING (ALL EXTERIOR LIGHTING GROUPS)
      3.B.3. HOA SWITCH SHALL PASS THE BAS SIGNALS IN AUTO MODE, DISENGAGE ALL CONTACTORS IN THE OFF POSITION, AND ENGAGE ALL THE CONTACTORS IN THE ON POSITION.
   3.C. SPARE CAPACITY:
      3.C.1. PROVIDE MINIMUM TWO (2) SPARE POLE ON EACH COMBINED TYPE CONTACTOR FOR FUTURE USE.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

LIGHTING SCHEDULES

j-E.060


STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM | C*(713) 360-4080 | TEXAS ENG. FIRM REG. NO. F-01853 | 10810 W. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77064



© 2025 ALL RIGHTS RESERVED

## NEW PANEL — TEMP KITCHEN


**PANEL LTK** — 150A MCB, 208Y/120V, 3ϕ, 4 WIRE — AVAILABLE FAULT: <10,000A — SCCR & AIC: 10,000A — MOUNTING: SURFACE

| NOTES | EQUIP. NO. | LOAD | DESCRIPTION | WIRE | CB | CKT | A | B | C | CKT | CB | WIRE | DESCRIPTION | LOAD | EQUIP. NO. | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E810 | 2766 | HOT WELLS | 2–12 | 20/2GFI | 1 | ■ | | | 2 | 20/1 | 3–12 | TRANSPORT CART | 1920 | E806 | |
| | – | – | – | +12G | – | 3 | | ■ | | 4 | 20/1 | 3–12 | TRANSPORT CART | 1920 | E806 | |
| | E810A | 1643 | HOT WELLS | 2–12 | 20/2GFI | 5 | | | ■ | 6 | 20/1 | 3–12 | TRANSPORT CART | 1920 | E806 | |
| | – | – | – | +12G | – | 7 | ■ | | | 8 | 20/1 | 3–12 | TRANSPORT CART | 1920 | E806 | |
| | E810B | 600 | COLD PAN | 3–12 | 20/1GFI | 9 | | ■ | | 10 | 20/1 | 3–12 | 2 REC | 360 | E800A | |
| | E810C | 1200 | BEVERAGE | 3–12 | 20/1GFI | 11 | | | ■ | 12 | 20/1 | 3–12 | 2 REC – DESK | 360 | E800B | |
| | E810C | 1200 | BEVERAGE | 3–12 | 20/1GFI | 13 | ■ | | | 14 | 20/1 | 3–12 | 2 REC | 360 | E800A | |
| | E811 | 180 | CASH REGISTER | 3–12 | 20/1GFI | 15 | | ■ | | 16 | 20/1 | 3–12 | 3 REC | 360 | E800A | |
| | E810B | 600 | COLD PAN | 3–12 | 20/1GFI | 17 | | | ■ | 18 | 20/1 | 3–12 | TEMP. KITCHEN LTS/FAN | 566 | | |
| | E810A | 1643 | HOT WELLS | 2–12 | 20/2GFI | 19 | ■ | | | 20 | 20/1 | | SPARE | | | |
| | – | – | – | +12G | – | 21 | | ■ | | 22 | 20/1 | | SPARE | | | |
| | E810 | 2766 | HOT WELLS | 2–12 | 20/2GFI | 23 | | | ■ | 24 | 20/1 | | SPARE | | | |
| | – | – | – | +12G | – | 25 | ■ | | | 26 | 20/1 | | SPARE | | | |
| | E808 | 1622 | HEATED CABINET | 2–12 | 20/2 | 27 | | ■ | | 28 | 20/1 | | SPARE | | | |
| | – | – | – | +12N+12G | – | 29 | | | ■ | 30 | 20/1 | 3–12 | EXISTING CIRCUIT | 500 | | 3 |
| | E809 | 984 | REFRIGERATOR | 3–12 | 20/1 | 31 | ■ | | | 32 | 20/1 | 3–12 | EXISTING CIRCUIT | 500 | | 3 |
| | E808 | 1622 | HEATED CABINET | 2–12 | 20/2 | 33 | | ■ | | 34 | 15/2 | 2–12 | EXISTING CIRCUIT | 1000 | | 3 |
| | – | – | – | +12N+12G | – | 35 | | | ■ | 36 | – | +12N+12G | – | – | | |
| | E809 | 984 | REFRIGERATOR | 3–12 | 20/1 | 37 | ■ | | | 38 | 20/2 | 2–12 | EXISTING CIRCUIT | 1000 | | 3 |
| | | | SPARE | | 20/1 | 39 | | ■ | | 40 | – | +12N+12G | – | – | | |
| | | | SPARE | | 20/1 | 41 | | | ■ | 42 | 50/2 | 2–8 | EXISTING CIRCUIT | 5000 | | 3 |
| | | | SPARE | | 20/1 | 43 | ■ | | | 44 | – | +8N+10G | – | – | | |
| | TOTAL LOAD @ 100% = | | 35498VA | | | TOTAL LOAD @ 100% = | | | | 99A | | | | | | |

1. REF. KITCHEN CONSULTANT'S "FCS" DRAWINGS FOR KITCHEN EQUIPMENT NUMBERS.
2. A DEMAND FACTOR PERCENT OF 65% HAS BEEN APPLIED TO THE KITCHEN EQUIPMENT LOAD PURSUANT TO NEC 220–20 AND NEC TABLE 220–20.
3. IDENTIFY ANY CIRCUITS OR PARTIAL CIRCUITS THAT EXTEND BEYOND THE AREA OF RENOVATION. PROVIDE TEMPORARY FEED TO MAINTAIN ALL CIRCUITS SERVING ELEMENTS/SPACES NOT TO BE REMOVED DURING CONSTRUCTION. RECONNECT EXISTING CIRCUITS/DEVICES TO REMAIN TO TEMPORARY KITCHEN PANEL ONCE AVAILABLE USING CB(S) PROVIDED. ALL PARTIAL CIRCUITS SHALL REMAIN AND REMAIN ACTIVE BOTH DURING AND AFTER CONSTRUCTION.




**T1** **TEMPORARY KITCHEN - LIGHTING PLAN**
SCALE: 1/4" = 1'– 0"




**T2** **TEMPORARY KITCHEN - ELECTRICAL PLAN**
SCALE: 1/4" = 1'– 0"

## ELECTRICAL KEYED NOTES

GENERAL NOTES:

- CUT WALLS AS REQUIRED TO FLUSH MOUNT NEW DEVICES IN EXISTING WALLS. PATCH/REPAIR WALLS TO MATCH.

DEMOLITION NOTES:

A. EXISTING STANDBY GENERATOR PANEL TO REMAIN.

B. EXISTING KITCHEN PANELS TO BE REPLACED WITH NEW. MODIFY EXISTING WALLS TO MATCH NEW PANEL LAYOUTS AND DIMENSIONS.

C. EXISTING LIGHTING FIXTURES AND CEILING DEVICES TO BE REMOVED THROUGHOUT.

D. EXISTING WALK–IN COOLER/FREEZER AND ASSOCIATED EQUIPMENT TO BE REMOVED.

E. EXISTING WALL ELECTRICAL DEVICES TO BE REMOVED. EXISTING J–BOXES MAY BE REUSED WHERE NEW DEVICES ARE TO BE INSTALLED AT THE SAME LOCATIONS.

F. EXISTING ELECTRICAL DEVICES TO BE REMOVED.

G. NEW 208Y/120V PANEL AND TRANSFORMER FOR TEMPORARY KITCHEN TO BE INSTALLED PRIOR TO DEMOLITION. PANEL AND TRANSFORMER TO BE REMOVED AT END OF KITCHEN RENOVATION AND TURNED OVER TO THE DISTRICT. INSTALL TRANSFORMER ON PREMADE FIBERCRETE PAD AND WAFFLE TYPE VIBRATION ISOLATION PADS. DO NOT PROVIDE A POURED IN PLACE CONCRETE PAD AT THIS LOCATION.

H. PROVIDE RECEPTACLES AND LIGHT FIXTURES FOR TEMPORARY KITCHEN DURING RENOVATION. ALL TEMPORARY DEVICES AND EQUIPMENT TO BE REMOVED AT END OF KITCHEN RENOVATION AND OFFERED TO THE OWNER AS SALVAGE.

I. CONDUITS ROUTED FROM TEMPORARY KITCHEN WALL AND BENEATH SERVING LINE. PROVIDE MULTICHANNEL ROLLOVER CABLE PROTECTOR FOR EXPOSED CONDUITS NOT UNDER THE SERVING LINE. ALL CONDUITS UNDER THE SERVING LINE SHALL BE SECURED TO/ROUTED ON TOP OF UNISTRUT AND NOT DIRECTLY ON THE FLOOR. DO NOT ANCHOR UNISTRUT TO THE EXISTING FLOORING. COORDINATE POWER AND DATA OUTLET LOCATIONS WITH OTHER TRADES.

J. REMOVE EXISTING LIGHT FIXTURES ABOVE NEW KITCHEN EXTENSION. MODIFY EXISTING WIRING TO MAINTAIN REMAINING FIXTURE OPERATION.

K. HARDWIRE KITCHEN EQUIPMENT TO LOCAL ON/OFF SWITCH. TYPICAL.

L. SURFACE MOUNT FIXTURES ON TEMPORARY KITCHEN CEILING. TYPICAL.


M. WIRE TEMPORARY KITCHEN FAN TO LOCAL LIGHTING CIRCUIT AND CONTROLS. FAN SHALL BE ON/OFF WITH LIGHTS.

N. EXISTING EXTERIOR LIGHT FIXTURES TO BE REMOVED.

O. PROVIDE NEW FIRE ALARM DEVICES AS PART OF THE TEMPORARY KITCHEN BUILDOUT.

P. PROVIDE NEW TEMPORARY LIGHT FIXTURES IN THE EXISTING CAFETERIA CEILING ABOVE THE SERVING LINE. COORDINATE LOCATIONS WITH TEMPORARY SERVING LINE AND EXISTING CONDITIONS. CONNECT TO EXISTING LIGHTING CONTROLS/CIRCUIT. ALL TEMPORARY LIGHT FIXTURES SHALL BE REMOVED AT THE END OF KITCHEN RENOVATION AND OFFERED TO THE OWNER AS SALVAGE. PROVIDE REPLACEMENT CEILING TILES.

Q. PROVIDE IN–USE WEATHERPROOF COVER FOR RECEPTACLE.




**1** **DEMOLITION FLOOR PLAN**
SCALE: 1/8" = 1'– 0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL

STATE OF TEXAS — GEORGE L. STANTON — 38582 — REGISTERED PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL DEMO AND TEMP PLANS

j-ED.100


STANTON ENGINEERING GROUP
INFO@STANTON–ENG.COM (713) 300–6080 | TEXAS ENG. FIRM REG. NO. F–018332 | 1300 W. SAM HOUSTON PARKWAY S., SUITE 121, HOUSTON, TX 77042


© 2021 ALL RIGHTS RESERVED

## ELECTRICAL KEYED NOTES

GENERAL NOTES:

- CUT WALLS AS REQUIRED TO FLUSH MOUNT NEW DEVICES IN EXISTING WALLS. PATCH/REPAIR WALLS TO MATCH.

LIGHTING RENOVATION NOTES:

A. KITCHEN LIGHTS TO BE CONTROLLED BY LOCAL MOMENTARY SWITCHES AND BAS. LIGHTING CONTACTOR LOCATIONS SHOWN SCHEMATICALLY ONLY. LOCATE LIGHTING CONTACTOR ENCLOSURE IN THE ADJACENT CENTRAL PLANT SPACE, FIELD VERIFY. REFERENCE LIGHTING CONTROL DETAIL. TYPICAL.
   LEFT SWITCH SHALL CONTROL ZONE 'a' NORMAL POWER LIGHTING FIXTURES.
   RIGHT SWITCH SHALL CONTROL ZONE 'b' EMERGENCY LIGHTING FIXTURES.


B. PROVIDE PLUG LOAD CONTROLS TIED TO THE LIGHTING IN OFFICE SPACES.

C. WIRE EXIT SIGNS UPSTREAM OF LIGHTING CONTROLS. TYPICAL.

D. EXTERIOR LIGHTS TO BE CONTROLLED BY BAS. LIGHTING CONTACTOR LOCATIONS SHOWN SCHEMATICALLY ONLY. LOCATE LIGHTING CONTACTOR ENCLOSURE IN THE ADJACENT CENTRAL PLANT SPACE, FIELD VERIFY. REFERENCE LIGHTING CONTROL DETAIL. TYPICAL.

E. AFTER REMOVAL OF THE TEMPORARY KITCHEN, PROVIDE NEW EXIT SIGN AT ORIGINAL LOCATION AND RECONNECT TO EXISTING CAFETERIAL LIGHTING CIRCUIT.

F. PATCH/REPAIR EXTERIOR SOFFIT TO ACCOMMODATE NEW SURFACE MOUNTED FIXTURES.




**1 LIGHTING RENOVATION PLAN**
SCALE: 1/4" = 1'- 0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING


LIGHTING FLOOR PLANS

j-E.100


STANTON ENGINEERING GROUP
INFORMATION-TECHNOLOGY (713) 300-60360


TEXAS ENGINEERING FIRM REG. NO.F-12343 © 2025 ALL RIGHTS RESERVED


12000 W. SAM HOUSTON PARKWAY N., SUITE 725, HOUSTON, TX 77043




## 1 ELECTRICAL RENOVATION PLAN

SCALE: 1/4" = 1'- 0"

## ELECTRICAL KEYED NOTES

GENERAL NOTES:

- CUT WALLS AS REQUIRED TO FLUSH MOUNT NEW DEVICES IN EXISTING WALLS. PATCH/REPAIR WALLS TO MATCH.

ELECTRICAL RENOVATION NOTES:

A. CONNECT NEW FREEZER/COOLER AND CONDENSER TO EXISTING STANDBY GENERATOR.

B. PROVIDE ILLUMINATED PUSH BUTTON IN COOLER AND FREEZER. WHEN PRESSED RED STROBE DEVICES IN KITCHEN AND CAFETERIA SHALL ACTIVATE. TYPICAL.

C. PROVIDE HORN/STROBE DEVICE TIED TO PUSH BUTTONS IN FREEZER/COOLER.
(EDWARDS 860 SERIES OR EQUAL).

D. PROVIDE NEW DOORBELL BUTTON AT RECEIVING DOOR. DOORBELL BUTTON SHALL BE THE CLOSEST DEVICE TO THE DOOR FRAME.

E. PROVIDE NEW VIBRATING BUZZER TIED TO DOORBELL BUTTON AT RECEIVING DOOR. BUZZER TO BE WALL MOUNTED JUST BELOW THE CEILING.

F. PROVIDE NEW ELECTRICAL DEVICES MATCHING NEW KITCHEN EQUIPMENT AND ROOM LAYOUTS. REFERENCE FOOD SERVICE DRAWINGS. TYPICAL.

G. PROVIDE ROUGH-IN FOR LOW VOLTAGE DEVICES. REFERENCE TECHNOLOGY DRAWINGS, TYPICAL.

H. POWER AND DATA ROUGH-IN FOR KITCHEN MENU BOARD.

I. POWER AND DATA ROUGH-IN FOR POINT OF SALE (POS) LOCATION.

J. PROVIDE DROP CORD RECEPTACLE WITH HUBBELL KELLEMS LIQUIDTIGHT GRIPS FOR STRAIN RELIEF, TYPICAL OF ALL.

K. PROVIDE J-BOXES AND CONDUIT FOR REMOTE FIRE PULLS, SEE FOOD SERVICE DETAIL DRAWING FOR REQUIREMENTS, TYPICAL

L. WIRE ANSUL SYSTEM TO HOOD EQUIPMENT CONTROL CONTRACTOR. UPON ANSUL SYSTEM ACTIVATION ALL POWER TO EQUIPMENT BENEATH THE HOODS SHALL BE DEACTIVATED. MOUNT CONTACTOR CABINET(S) JUST BELOW THE CEILING.

M. PROVIDE SEPARATE SWITCHES TO TURN ON HOOD LIGHTS AND FANS. WIRE HOOD TEMP SENSOR AHEAD OF HOOD LIGHT SWITCH. USE 120V CIRCUIT TO CONTROL HOOD FANS THROUGH EXISTING STARTER. PROVIDE CONTROLS TRANSFORMER AS REQUIRED TO MATCH STARTER CONTROL INPUT VOLTAGE. TYPICAL.

N. PROVIDE PLUG LOAD CONTROLS TIED TO THE LIGHTING IN OFFICE SPACES.

O. INTERCONNECT DISH MACHINE TO VENT CONTROL. INTERCONNECT TABLE LIMIT SWITCH TO DISHMACHINE.

P. EXISTING MECHANICAL EQUIPMENT TO BE REPLACED. CONNECT TO CIRCUIT AS SHOWN. RECONNECT TO EXISTING STARTER/CONTACTORS, FIELD VERIFY.

Q. SAWCUT FLOOR TO INSTALL NEW PEDESTAL MOUNTED DEVICE BENEATH NEW SERVING LINES, DO NOT REUSE EXISTING STUB UPS OR DEVICES. POUR BACK SLAB AND PROVIDE NEW FINISHES, REFERENCE ARCHITECTURAL.

R. REFERENCE EDF GFI PROTECTION DETAIL FOR INSTALLATION REQUIREMENTS, TYPICAL.

S. WIRE MICRO SWITCH IN DOOR FRAME TO AIR SCREEN. COOR W/ FOOD SERVICE CONTRACTOR PRIOR TO ROUGH-IN. LOCATE LOCAL MOTOR RATED SWITCH ABOVE CEILING ADJACENT TO THE AIR SCREEN.

COOLER/FREEZER NOTES:

1. PROVIDE SEALING FOR CONDUIT IN COOLER AND FREEZER. WHERE PORTIONS OF INTERIOR RACEWAY SYSTEM ARE EXPOSED TO WIDELY DIFFERENT TEMPERATURES, CIRCULATION OF AIR FROM WARMER TO A COLDER SECTION SHALL BE PREVENTED PER N.E.C. ARTICLE 300.7 (A).
2. PROVIDE GROUND-FAULT PROTECTION OF EQUIPMENT FOR ELECTRIC HEAT TRACING AND HEATING PANELS IN THE FREEZER PER N.E.C. ARTICLE 427.22.
3. ELECTRICAL CONTRACTOR SHALL PROVIDE LIQUID TIGHT CONDUIT AND WIRING FOR LIGHT FIXTURES AND LIGHT SWITCHES IN WALK-IN COOLER AND FREEZER, SEE FOODSERVICE CONSULTANT'S DRAWINGS.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

j

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
LICENSED
PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL FLOOR PLANS

j-E.200

STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM (713) 300-4080 | TEXAS ENG. FIRM REG. NO. F-01853-01
© 2025 ALL RIGHTS RESERVED
1200 N. SAM HOUSTON PARKWAY E., SUITE 121, HOUSTON, TX 77060




**1 FIRE ALARM RENOVATION PLAN**
SCALE: 1/4" = 1'- 0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL




07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

FIRE ALARM FLOOR PLANS

j-E.300

STANTON ENGINEERING GROUP
INFORMATION@STANTONENGINEERING.COM | (713) 300-6060
TEXAS ENG. FIRM REG. NO. F-21853 | 10200 W. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77064
ALL RIGHTS RESERVED




## 1 PARTIAL ELECTRICAL RISER

NO SCALE

NOTES:
1. FIELD VERIFY ALL EXISTING ELECTRICAL PANELS AND FEEDERS SHOWN ON DRAWINGS.
2. REF ELECTRICAL FLOOR PLANS FOR PANEL LOCATIONS.
3. ALL OUTAGES SHALL BE SCHEDULED/CONFIRMED IN WRITING WITH THE OWNER A MINIMUM OF TWO WEEKS PRIOR TO ANY OUTAGE.
4. AT THE END OF THE PROJECT PROVIDE A NEW TYPEWRITTEN PANEL SCHEDULE USING BUILDING ROOM NUMBERS FOR ALL PANELS WITH CIRCUITS ADDED, REMOVED, OR MODIFIED AS PART OF THE PROJECT.
5. REFERENCE PANEL SCHEDULES AND SHORT CIRCUIT TABLE FOR AIC AND SCCR VALUES.

### NEW KITCHEN PANEL — KITCHEN

**PANEL HK** — 225A MLO, 480Y/277V, 3ϕ, 4 WIRE — AVAILABLE FAULT: 20,250A — SCCR & AIC: 25,000A — MOUNTING: RECESSED — STAINLESS STEEL COVER

| NOTES | EQUIP. NO. | LOAD | DESCRIPTION | WIRE | CB | CKT | A | B | C | CKT | CB | WIRE | DESCRIPTION | LOAD | EQUIP. NO. | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 6 | | 376 | KITCHEN ROOM LIGHTS | 3–12 | 20/1 | 1 | | | | 2 | 15/3 | 3–12 | ESF–1 | 4986 | | |
| 7 | | 1095 | KITCHEN LIGHTS | 3–12 | 20/1 | 3 | | | | 4 | – | +12G | ( 1.5HP / 1.5HP ) | – | | |
| | | 84 | KITCHEN SOFFIT LIGHTS | 3–12 | 20/1 | 5 | | | | 6 | – | 3/4"C | – | – | | |
| | | | SPARE | | 20/1 | 7 | | | | 8 | 15/3 | 3–12 | ESF–2 | 4986 | | |
| | | | SPARE | | 20/1 | 9 | | | | 10 | – | +12G | ( 1.5HP / 1.5HP ) | – | | |
| | | | SPARE | | 20/1 | 11 | | | | 12 | – | 3/4"C | – | – | | |
| | | | SPARE | | 20/1 | 13 | | | | 14 | | | SPACE | | | |
| | | | SPARE | | 20/1 | 15 | | | | 16 | | | SPACE | | | |
| | | | SPARE | | 20/1 | 17 | | | | 18 | | | SPACE | | | |
| | | | SPARE | | 20/1 | 19 | | | | 20 | | | SPACE | | | |
| | | | SPARE | | 20/1 | 21 | | | | 22 | | | SPACE | | | |
| | | | SPACE | | | 23 | | | | 24 | | | SPACE | | | |
| | | | SPACE | | | 25 | | | | 26 | | | SPACE | | | |
| | | | SPACE | | | 27 | | | | 28 | | | SPACE | | | |
| | | | SPACE | | | 29 | | | | 30 | | | SPACE | | | |
| | | | SPACE | | | 31 | | | | 32 | | | SPACE | | | |
| | | | SPACE | | | 33 | | | | 34 | | | SPACE | | | |
| | | | SPACE | | | 35 | | | | 36 | | | SPACE | | | |
| | | | SPACE | | | 37 | | | | 38 | 70/3 | 3–6 | DISHMACHINE | 42963 | E250 | |
| | | | SPACE | | | 39 | | | | 40 | – | +8G | – | – | | |
| | | | SPACE | | | 41 | | | | 42 | – | 3/4"C | – | – | | |
| | | TOTAL LOAD ❶ 100% = | 54490VA | | | | TOTAL LOAD ❶ 100% = | | | | 66A | | | TOTAL LOAD ❶ 125% = | 82A | | |

### NEW KITCHEN PANEL — KITCHEN

**PANEL LK** — 225A MLO, 208Y/120V, 3ϕ, 4 WIRE — AVAILABLE FAULT: <10,000A — SCCR & AIC: 10,000A — MOUNTING: RECESSED — STAINLESS STEEL COVER

| NOTES | EQUIP. NO. | LOAD | DESCRIPTION | WIRE | CB | CKT | A | B | C | CKT | CB | WIRE | DESCRIPTION | LOAD | EQUIP. NO. | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E10 | 640 | 3 REC – RR/STOR/CUST & BELL | 3–12 | 20/1 | 1 | | | | 2 | 20/1 | 3–12 | 1 REC – KITCHEN | 180 | E10 | |
| | E110 | 1920 | WASHING MACHINE | 3–12 | 20/1 | 3 | | | | 4 | 20/1 | 3–12 | 1 REC – KITCHEN | 180 | E10 | |
| | E110A | 5000 | DRYER | 2–10 | 30/2GFI | 5 | | | | 6 | 20/1 | 3–12 | 1 REC – KITCHEN | 180 | E10 | |
| | E151 | – | – | +10N+10G | 3/4"C | 7 | | | | 8 | 20/2 | 2–10 | HEATED CABINET | 3224 | E187 | |
| | | 540 | 3 REC – OFFICE | 3–12 | 20/1 | 9 | | | | 10 | 3/4"C | +10G | – | – | | |
| | E10 | 540 | 3 REC – KITCHEN | 3–12 | 20/1 | 11 | | | | 12 | 20/2 | 2–10 | HEATED CABINET | 3224 | E187 | |
| | E10 | 360 | 2 REC – SERVING LINE | 3–12 | 20/1 | 13 | | | | 14 | 3/4"C | +10G | – | – | | |
| | E10 | 360 | 2 REC – SERVING LINE | 3–12 | 20/1 | 15 | | | | 16 | 20/3 | 3–12 | DISPOSER | 3960 | E123 | |
| | | 1000 | 2 EDF – CAFETERIA | 3–12 | 20/1 | 17 | | | | 18 | – | +12G | ( 3 HP ) | – | | |
| | E615 | 500 | 2 MENU BOARDS | 3–12 | 20/1 | 19 | | | | 20 | – | 3/4"C | – | – | | |
| | E209 | 960 | MILK COOLER | 3–12 | 20/1 | 21 | | | | 22 | 20/1 | 3–12 | AIR SCREEN | 612 | E101 | |
| | E201A | 5824 | HOT FOOD COUNTER | 2–8 | 35/2 | 23 | | | | 24 | 15/1 | 3–12 | EF–CF ( 1/6HP ) | 528 | | |
| | | – | – | +10G | 3/4"C | 25 | | | | 26 | 15/1 | 3–12 | EF–14 ( 1/6HP ) | 528 | | |
| | E201B | 1920 | COLD FOOD COUNTER | 3–12 | 20/1 | 27 | | | | 28 | 20/1 | 3–12 | EF–2 ( 1/6HP ) | 528 | | |
| | E214 | 360 | CASH REGISTERS | 3–12 | 20/1 | 29 | | | | 30 | 20/1 | | SPARE | | | |
| | E201B | 1920 | COLD FOOD COUNTER | 3–12 | 20/1 | 31 | | | | 32 | 20/1 | | SPARE | | | |
| | E201A | 5824 | HOT FOOD COUNTER | 2–8 | 35/2 | 33 | | | | 34 | 20/1 | | SPARE | | | |
| | | – | – | +10G | 3/4"C | 35 | | | | 36 | 20/1 | | SPARE | | | |
| | E209 | 960 | MILK COOLER | 3–12 | 20/1 | 37 | | | | 38 | 20/1 | | SPARE | | | |
| | | 360 | 2 REC – CAFETERIA | 3–12 | 20/1 | 39 | | | | 40 | 20/1 | | SPARE | | | |
| | | | SPARE | | 20/1 | 41 | | | | 42 | 20/1 | | SPARE | | | |
| | E153/E153M | 250 | HOOD LTS & SENSOR | 3–12 | 20/1 | 43 | | | | 44 | 20/1GFI | 3–12 | DROP CORD | 180 | E129 | |
| | E153/E153M | 250 | HOOD LTS & SENSOR | 3–12 | 20/1 | 45 | | | | 46 | 20/1GFI | 3–12 | DROP CORD | 180 | E129 | |
| 8 | E161 | 720 | CONVECTION OVEN | 3–12 | 20/1GFI | 47 | | | | 48 | 20/1GFI | 3–12 | MOBILE PROOFER | 1800 | E139A | |
| 8 | E161 | 720 | CONVECTION OVEN | 3–12 | 20/1GFI | 49 | | | | 50 | 20/1GFI | 3–12 | 20QT MIXER | 960 | E125 | |
| 8 | E161 | 720 | CONVECTION OVEN | 3–12 | 20/1GFI | 51 | | | | 52 | 20/1GFI | 3–12 | DROP CORD | 180 | E129 | |
| 8 | E161 | 720 | CONVECTION OVEN | 3–12 | 20/1GFI | 53 | | | | 54 | 20/1GFI | 3–12 | DROP CORD | 180 | E129 | |
| 8 | E163 | 600 | TILT BRAISING PAN | 3–12 | 20/1 | 55 | | | | 56 | 20/1GFI | 3–12 | DROP CORD | 180 | E129 | |
| 8 | E172 | 3120 | COMBI OVEN | 2–12 | 20/2 | 57 | | | | 58 | 20/1GFI | 3–12 | DROP CORD | 180 | E129 | |
| | | – | – | +12G | 3/4"C | 59 | | | | 60 | 20/1 | 3–12 | EXISTING CIRCUIT | 500 | | 5 |
| 8 | E172 | 3120 | COMBI OVEN | 2–12 | 20/2 | 61 | | | | 62 | 20/2 | 2–12 | EXISTING CIRCUIT | 1000 | | 5 |
| | | – | – | +12G | 3/4"C | 63 | | | | 64 | – | +12N+12G | – | – | | 5 |
| | | 250 | EXISTING CIRCUIT | 3–12 | 20/1 | 65 | | | | 66 | 20/2 | 2–12 | EXISTING CIRCUIT | 1000 | | 5 |
| 9 | | 0 | TEMP LOAD CENTER | 4–3 | 100/3 | 67 | | | | 68 | – | +12N+12G | – | – | | 5 |
| | | – | – | +8G | – | 69 | | | | 70 | 30/2 | 2–10 | EXISTING CIRCUIT | 3000 | | 5 |
| | | – | – | 1.25"C | – | 71 | | | | 72 | – | +10N+10G | – | – | | |
| | | TOTAL LOAD ❶ 100% = | 61942VA | | | | TOTAL LOAD ❶ 100% = | | | | 172A | | | TOTAL LOAD ❶ 65% = | 112A | | |

### KITCHEN HOOD CONTACTOR SCHEDULE

**HOOD 1**

| POLE | DESCRIPTION | NORMAL CKT | EM CKT | CONTROL ZONE | EQUIPMENT LOCATION | CONTACTOR TYPE |
|---|---|---|---|---|---|---|
| CK1–1 | CONVECTION OVEN | LK–47 | – | HOOD 1 | KITCHEN | ELECTRICALLY HELD – NO |
| CK1–2 | CONVECTION OVEN | LK–49 | – | HOOD 1 | KITCHEN | ELECTRICALLY HELD – NO |
| CK1–3 | CONVECTION OVEN | LK–51 | – | HOOD 1 | KITCHEN | ELECTRICALLY HELD – NO |
| CK1–4 | CONVECTION OVEN | LK–53 | – | HOOD 1 | KITCHEN | ELECTRICALLY HELD – NO |
| CK1–5 | SPARE | | | | | ELECTRICALLY HELD – NO |
| CK1–6 | SPARE | | | | | ELECTRICALLY HELD – NO |
| CK1–7 | SPARE | | | | | ELECTRICALLY HELD – NO |
| CK1–8 | SPARE | | | | | ELECTRICALLY HELD – NO |

**HOOD 2**

| POLE | DESCRIPTION | NORMAL CKT | EM CKT | CONTROL ZONE | EQUIPMENT LOCATION | CONTACTOR TYPE |
|---|---|---|---|---|---|---|
| CK2–1 | TILT BRAISING PAN | LK–55 | – | HOOD 2 | KITCHEN | ELECTRICALLY HELD – NO |
| CK2–2 | COMBI–OVEN | LK–57/59 | – | HOOD 2 | KITCHEN | ELECTRICALLY HELD – NO |
| CK2–3 | ( 2–POLE ) | – | – | – | – | ELECTRICALLY HELD – NO |
| CK2–4 | COMBI–OVEN | LK–61/63 | – | HOOD 2 | KITCHEN | ELECTRICALLY HELD – NO |
| CK2–5 | ( 2–POLE ) | – | – | – | – | ELECTRICALLY HELD – NO |
| CK2–6 | SPARE | | | | | ELECTRICALLY HELD – NO |
| CK2–7 | SPARE | | | | | ELECTRICALLY HELD – NO |
| CK2–8 | SPARE | | | | | ELECTRICALLY HELD – NO |

1. REFERENCE FLOOR PLANS FOR EQUIPMENT LOCATIONS AND ADDITIONAL INFORMATION.
2. EACH KITCHEN HOOD CONTACTOR HALL BE CONTROLLED ON/OFF BY THE APPROPRIATE HOOD ANSUL SYSTEM. WHEN ACTIVATED ALL POWER WITHIN THE COOKING HOOD SHALL BE DE–ENERGIZED.

### EXIST SQUARE D QED SWITCHBOARD — CENTRAL PLANT

**(E)SWBD MSB** — 2000A MCB, 480Y/277V, 3ϕ, 4 WIRE — AVAILABLE FAULT: 37,000A — SCCR & AIC: 100,000A — FREE STANDING

| NOTES | CIRCUIT | DESCRIPTION | CB | FEEDER SIZE | AMPS |
|---|---|---|---|---|---|
| | 1 | EXTENDED DAY PANEL H | 150/3 | EXIST FEEDER | |
| | 2 | EXIST ATS | 250/3 | EXIST FEEDER | 7A |
| 2 | 3 | EXIST PANEL HK | 400/3 | EXIST FEEDER | |
| 4 | 4 | NEW PANEL HK | 225/3 | 4–4/0 +4G, 2.5"C | 53A |
| | 5 | EXIST DISTRIBUTION PANEL DA | 400/3 | EXIST FEEDER | 275A |
| | 6 | EXIST SPACE | 400/3PS | – | |
| | 7 | EXIST DISTRIBUTION PANEL DB | 400/3 | EXIST FEEDER | |
| | 8 | EXIST DISTRIBUTION PANEL DC | 400/3 | EXIST FEEDER | |
| | 9 | EXIST DISTRIBUTION PANEL AC | 800/3 | EXIST FEEDER | |
| | | | | TOTAL LOAD ❶ 100% = | 336A |
| | | | | TOTAL LOAD ❶ 125% = | 419A |

1. THE EXISTING 2000A FEEDER IS SUFFICIENT FOR THE REVISED LOAD.
2. UPDATE PANEL SCHEDULE TO MATCH REVISED EQUIPMENT DESCRIPTION.

### EXIST GE NHB PANELBOARD — STORAGE ROOM

**(E)PANEL DA** — 400A MLO, 480Y/277V, 3ϕ, 4 WIRE — AVAILABLE FAULT: 27,000A — SCCR & AIC: 35,000A — MOUNTING: SURFACE

| NOTES | LOAD | DESCRIPTION | WIRE | CB | CKT | A | B | C | CKT | CB | WIRE | DESCRIPTION | LOAD | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | SPACE | | | 1 | | | | 2 | 70/3 | 3–6 | TEMP KITCHEN PANEL LTK | 37918 | 4 |
| | | SPACE | | | 3 | | | | 4 | – | +8G | – | – | |
| | | SPACE | | | 5 | | | | 6 | – | 3/4"C | – | – | |
| | | SPACE | | | 7 | | | | 8 | | | SPACE | | |
| | | SPACE | | | 9 | | | | 10 | | | SPACE | | |
| 2 | | KITCHEN LIGHTS | EXIST | 20/1 | 11 | | | | 12 | | | SPACE | | |
| 1 | 3100 | LIGHTS CAFETORIUM | EXIST | 20/1 | 13 | | | | 14 | | | SPACE | | |
| 1 | 3370 | LIGHTS CAFETORIUM | EXIST | 20/1 | 15 | | | | 16 | 20/1 | EXIST | OUTSIDE LIGHTS | 1000 | |
| 1 | 2300 | LIGHTS CAFETORIUM RMS | EXIST | 20/1 | 17 | | | | 18 | 20/1 | EXIST | EWH–2 IN MECH 404 | 3000 | |
| | 9150 | AHU #2 | EXIST | 20/3 | 19 | | | | 20 | 60/3 | EXIST | DUCT HEATER 2 | 39000 | |
| | – | – | – | – | 21 | | | | 22 | – | – | ( STAGE ) | – | |
| | – | – | – | – | 23 | | | | 24 | – | – | – | – | |
| | 130000 | PANEL PA | EXIST | 225/3 | 25 | | | | 26 | – | – | – | – | |
| | – | ( SUBFEED BREAKER ) | – | – | 27 | | | | 28 | – | – | – | – | |
| | – | – | – | – | 29 | | | | 30 | – | – | – | – | |
| | | TOTAL LOAD ❶ 100% = 228838VA | | | | TOTAL LOAD ❶ 100% = | | | | 275A | | TOTAL LOAD ❶ 125% = | 344A | |

1. THE EXISTING 400A FEEDER IS SUFFICIENT FOR THE REVISED LOAD.
2. UPDATE PANEL SCHEDULE TO MATCH REVISED EQUIPMENT DESCRIPTION.

### EXIST EM STANDBY PANELBOARD — STORAGE ROOM

**(E)PANEL EL** — 125A MCB, 208Y/120V, 3ϕ, 4 WIRE — AVAILABLE FAULT: <10,000A — SCCR & AIC: 10,000A — MOUNTING: SURFACE

| NOTES | EQUIP. NO. | LOAD | DESCRIPTION | WIRE | CB | CKT | A | B | C | CKT | CB | WIRE | DESCRIPTION | LOAD | EQUIP. NO. | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | 500 | GENERATOR REMOTE | EXIST | 20/1 | 1 | | | | 2 | 20/1 | EXIST | MDF RM SEC | 500 | | |
| | | 500 | GENERATOR BATTERY | EXIST | 20/1 | 3 | | | | 4 | 20/2 | EXIST | MDF RM SERVER 220 | 2000 | | |
| | | 500 | GENERATOR CONTROL | EXIST | 20/1 | 5 | | | | 6 | – | – | – | – | | |
| | | 500 | GENERATOR HEATER | EXIST | 20/1 | 7 | | | | 8 | 20/2 | EXIST | MDF RM SERVER 220 | 2000 | | |
| | | 500 | RM S125 PA SYSTEM | EXIST | 20/1 | 9 | | | | 10 | – | – | – | – | | |
| | | 500 | RM S125 FA | EXIST | 20/1 | 11 | | | | 12 | 20/1 | | EXIST SPARE | | | |
| | | | EXIST SPARE | | 20/1 | 13 | | | | 14 | 20/1 | | EXIST SPARE | | | |
| | | | EXIST SPARE | | 20/1 | 15 | | | | 16 | 20/1 | | EXIST SPARE | | | |
| 4 | E188 | 864 | REFRIGERATOR | 3–12 | 20/1 | 17 | | | | 18 | 20/1 | | EXIST SPARE | | | |
| 4 | E188 | 864 | REFRIGERATOR | 3–12 | 20/1 | 19 | | | | 20 | 20/1 | | EXIST SPARE | | | |
| 4 | E109 | 1428 | ICE MACHINE | 3–12 | 20/1 | 21 | | | | 22 | 20/1 | | EXIST SPARE | | | |
| 4 | E151 | 240 | HOOD ANSUL SYSTEMS | 3–12 | 20/1 | 23 | | | | 24 | 25/3 | 3–10 | REFRIGERATION SYSTEM | 6192 | E103 | 4 |
| 4 | E102B | 600 | COOLER TEMP. ALARM | 3–12 | 20/1 | 25 | | | | 26 | – | +10G | – | – | | |
| 4 | E102C | 600 | COOLER PRESSURE PORT | 3–12 | 20/1 | 27 | | | | 28 | – | 3/4"C | – | – | | |
| 4 | E102E | 120 | PANIC ALARM BUTTONS | 3–12 | 20/1 | 29 | | | | 30 | 20/1EGF | 3–12 | COOLER DOOR HEATER/LTS | 600 | E102A | 4 |
| 4 | E103D | 216 | COOLER COIL | 3–12 | 20/1 | 31 | | | | 32 | 20/1EGF | 3–12 | FREEZER DOOR HEATER/LTS | 600 | E102A | 4 |
| 4 | E102B | 600 | FREEZER TEMP. ALARM | 3–12 | 20/1 | 33 | | | | 34 | 20/1EGF | 3–12 | FREEZER DRAIN LINE HEATER | 600 | E103F | 4 |
| 4 | E102C | 600 | FREEZER PRESSURE PORT | 3–12 | 20/1 | 35 | | | | 36 | | | SPACE | | | |
| 4 | E103C | 1893 | FREEZER COIL | 2–10 | 20/2 | 37 | | | | 38 | 30/3 | EXIST | SPD | 50 | | |
| | | – | – | +10G | – | 39 | | | | 40 | – | – | – | – | | |
| | | | SPACE | | | 41 | | | | 42 | – | – | – | – | | |
| | | TOTAL LOAD ❶ 100% = | 23567VA | | | | TOTAL LOAD ❶ 100% = | | | | 65A | | | TOTAL LOAD ❶ 125% = | 82A | |

1. THE EXISTING 125A FEEDER IS SUFFICIENT FOR THE REVISED LOAD.
2. UPDATE PANEL SCHEDULE TO MATCH REVISED EQUIPMENT DESCRIPTION.

GENERAL PANEL REQUIREMENTS:
A. REF ELECTRICAL FLOOR PLANS FOR PANEL LOCATIONS.
B. FIELD VERIFY EXISTING CIRCUITS PRIOR TO BEGINNING WORK.
C. ALL OUTAGES SHALL BE SCHEDULED AND CONFIRMED IN WRITING WITH THE OWNER A MINIMUM OF TWO WEEKS PRIOR TO ANY OUTAGE.
D. AT THE END OF THE PROJECT PROVIDE A NEW TYPEWRITTEN PANEL SCHEDULE USING BUILDING ROOM NUMBERS FOR ALL PANELS WITH CIRCUITS ADDED, REMOVED, OR MODIFIED AS PART OF THE PROJECT.

PANEL NOTES:
1. REVISE/REWORK WIRING/CONDUIT AS REQUIRED TO ADD/REMOVE DEVICES FROM EXISTING CIRCUIT.
2. EXISTING CIRCUIT TO BE DEMO.
3. REUSE EXISTING SPARE CB AND WIRE NEW CIRCUIT.
4. PROVIDE NEW CB & WIRE NEW CIRCUIT.
5. IDENTIFY ANY CIRCUITS OR PARTIAL CIRCUITS THAT EXTEND BEYOND THE AREA OF RENOVATION. PROVIDE TEMPORARY FEED TO MAINTAIN ALL CIRCUITS SERVING ELEMENTS/SPACES NOT TO BE REMOVED DURING CONSTRUCTION. RECONNECT EXISTING CIRCUITS/DEVICES TO REMAIN TO TEMPORARY KITCHEN PANEL ONCE AVAILABLE USING CB(S) PROVIDED. ALL PARTIAL CIRCUITS SHALL REMAIN AND REMAIN ACTIVE BOTH DURING AND AFTER CONSTRUCTION.
6. KITCHEN LIGHTS TO BE DUAL ZONES WIRED THROUGH LIGHTING CONTACTORS AND CONTROLLED ON/OFF BY THE BAS AND LOCAL LIGHTING SWITCHES.
7. EXTERIOR LIGHTS TO BE WIRED THROUGH LIGHTING CONTACTOR AND CONTROLLED ON/OFF BY THE BAS.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

j

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL

STATE OF TEXAS — GEORGE L. STANTON — 38582 — REGISTERED PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL SCHEMATIC

j-E.400


STANTON ENGINEERING GROUP
INFORMATION–EXCELLENCE | TEXAS ENG. FIRM REG. NO. F–2833 (713) 300–6080 | 1300 W. SAM HOUSTON PARKWAY S., SUITE 125, HOUSTON, TX 77042


©2025 ALL RIGHTS RESERVED

## PLUMBING SYMBOLS LEGEND

| | | | |
|---|---|---|---|
| ——— | SANITARY WASTE BELOW SLAB | SAN. | SANITARY |
| ——— | SANITARY WASTE ABOVE SLAB | CW | DOMESTIC COLD WATER |
| —— V. —— | VENT PIPING ABOVE SLAB | HW | DOMESTIC HOT WATER |
| — — — — | VENT PIPING | WC | WATER CLOSET |
| —— G —— | GAS PIPING, 4–8oz | UR | URINAL |
| —— GS —— | GAS PIPING, 5LB | LAV | LAVATORY |
| —·—·— | DOMESTIC COLD WATER PIPING | SK | SINK |
| —·—·—·— | DOMESTIC HOT WATER PIPING | EDF | ELECTRIC DRINKING FOUNTAIN |
| —— D —— | DRAIN/RELIEF VENT PIPING | WH | WALL HYDRANT |
| —⋈— | STOP VALVE | HB | HOSEBIBB |
| 2CO | DOUBLE SAN. CLEANOUT (2–WAY) | CP | HOT WATER CIRCULATOR PUMP |
| CO | SANITARY SEWER CLEANOUT | FD | FLOOR DRAIN |
| WCO | WALL CLEANOUT | FSINK | FLOOR SINK |
| EXIST. | EXISTING | | |
| (R) | REMOVE (DEMOLISH) | | |
| (D) | DEMOLISH (REMOVE) | | |
| (E) | EXISTING – NO WORK | | |

## PLUMBING FIXTURE NOTES

1. ALL FIXTURES SHALL MEET WATER CONSERVATION PERFORMANCE STANDARDS MANDATED BY SENATE BILL 587. ALL FIXTURES SHALL HAVE FLOW RESTRICTION DEVICES (DRINKING FOUNTAINS SHALL BE SELF–CLOSING) TO COMPLY WITH THESE REQUIREMENTS.
2. ALL FIXTURES SHALL HAVE CONTROLS REQUIRING OPERATING FORCE NO GREATER THAN FIVE (5) POUNDS.
3. FOR LAVATORIES AND SINKS, ALL FAUCETS SHALL BE NO–LEAD SOLID BRASS, MEETING ALL REQUIREMENTS OF ANSI/NSF 61, SECTION 9 AND CERTIFIED AS SUCH. ALSO, INSTALL SYMMONS 7–210 MIXING VALVE ON HOT WATER SUPPLY SIDE OF ALL FAUCETS UNLESS HIGH TEMPERATURE LIMIT IS PROVIDED WITH FAUCET. MAXIMUM WATER TEMPERATURE FOR ALL FAUCETS THAT DELIVER HOT OR TEPID WATER SHALL BE 110°F. ALL METERING FAUCETS SHALL HAVE A MINIMUM TEN (10) SECONDS OF WATER FLOW, AND, INSTALL TRUEBRO HANDI LAV–GUARD VANDAL–PROOF INSULATION KITS OVER P–TRAP, SUPPLIES, STOPS AND ALL SHARP EDGES FOR ALL SINKS AND LAVATORIES (TRAP WRAP FROM BROCAR OR PROWRAP FROM McGUIRE SHALL BE ACCEPTABLE).
4. ALL PLUMBING FIXTURES REFERENCED AS "ADA", "TAS" OR "HANDICAP COMPLIANT" SHALL MEET ALL REQUIREMENTS OF THE ADA AND THE TEXAS ACCESSIBILITY STANDARDS. IT SHALL BE THE PLUMBING CONTRACTORS RESPONSIBILITY TO MEET THESE REQUIREMENTS.
5. IN MANY CASES, FIXTURES WITH THE SAME PLUMBING DESIGNATION HAVE DIFFERENT INSTALLATION HEIGHTS – REFERENCE ARCHITECTURAL DRAWINGS FOR ALL INSTALLATION HEIGHTS AND HANDICAP FIXTURE DESIGNATIONS. FIXTURES DESIGNATED AS ADULT HANDICAP SHALL MEET ALL REQUIREMENTS OF THE ADA. FIXTURES DESIGNATED AS CHILD HANDICAP SHALL MEET ALL REQUIREMENTS OF THE TEXAS ACCESSIBILITY STANDARDS FOR THE APPROPRIATE CHILDREN'S AGE GROUP (REF. ARCH. DWGS. AND SPECIFICATIONS).

## PLUMBING MATERIALS

SANITARY WASTE AND VENT

BELOW SLAB/GRADE: SCHEDULE 40, DWV PVC

ABOVE SLAB: STANDARD WEIGHT, CAST IRON, NO–HUB PIPING.

STORM DRAIN PIPING

BELOW SLAB/GRADE: SCHEDULE 40, DWV PVC

ABOVE SLAB, 8" AND UNDER: STANDARD WEIGHT, CAST IRON, NO–HUB PIPING.

ABOVE SLAB, 10" AND ABOVE: SERVICE WEIGHT, CAST IRON, BELL & SPIGOT.

NATURAL GAS

BELOW GRADE (OUTSIDE): YELLOW POLYETHYLENE PIPE WITH COATED STEEL RISER AND TRACER WIRE.

ABOVE SLAB: SCHEDULE 40 BLACK STEEL. PIPING 2.5" AND LARGER SHALL BE WELDED. PIPING 2" AND SMALLER SHALL HAVE SCREWED FITTINGS.

DOMESTIC WATER

INTERIOR: TYPE L COPPER WITH SOLDER TYPE WROUGHT COPPER FITTINGS, MADE UP WITH LEAD–FREE SOLDER.

EXTERIOR: TYPE K COPPER WITH SWEAT FITTINGS AND LEAD–FREE SOLDER. BEYOND 5 FEET FROM BUILDING, SCHEDULE 40 PVC.

## FIRE SPRINKLER SYSTEM NOTES


1. THE EXISTING FIRE SPRINKLER SYSTEM SHALL BE MODIFIED AND/OR EXPANDED TO COVER THE AREA OF RENOVATION IN ENTIRETY. ALL NEW AND REVISED PIPING SHALL BE ENGINEERED AND INSTALLED BY A LICENSED FIRE SPRINKLER CONTRACTOR.
2. REFERENCE THE SPECIFICATIONS, DIVISION 21, FOR MORE INFORMATION.

## GENERAL PLUMBING NOTES

1. SEE ARCHITECTURAL DRAWINGS AND SPECIFICATIONS FOR ADDITIONAL WORK DESCRIPTION. SEE THIS SHEET (P4.00) FOR PLUMBING SYMBOLS LEGEND.
2. COORDINATE PLUMBING SYSTEMS INSTALLATION WITH ARCHITECTURAL, STRUCTURAL, HVAC SYSTEMS, ELECTRICAL SYSTEMS, CONDUITS, ETC.... OFFSET PIPING AS REQUIRED TO PROVIDE A FUNCTIONING SYSTEM WITH ADEQUATE SPACE FOR SERVICING AND REPAIRS.
3. MAKE CONNECTIONS OF NEW PIPE SYSTEMS IN TO EXISTING PIPE SYSTEMS WITH THREADED OR SWEAT JOINTS. PROVIDE ELECTROLYSIS ISOLATING UNIONS AS CONNECTION OF DISSIMILAR MATERIALS. REFERENCE THE SPECIFICATIONS.
4. SITE SERVICES ARE SHOWN FOR REFERENCE ONLY. PLUMBING CONTRACTOR SHALL REFERENCE CIVIL DRAWINGS, INCLUDING LOCATIONS OF SERVICES, SIZES OF PIPES, FLOWLINE ELEVATIONS, ETC..
5. DO NOT INSTALL PLUMBING PIPING OVER ANY ELECTRICAL EQUIPMENT. REFERENCE ELECTRICAL DRAWINGS FOR LOCATIONS OF ELECTRICAL EQUIPMENT AND COORDINATE WITH ELECTRICAL SUBCONTRACTORS ACCORDINGLY. SEE DETAIL 2/M6P1. THIS INCLUDES FIRE SPRINKLER PIPING.
6. ALL PIPES THROUGH WALLS OR FLOORS SHALL BE SLEEVED AND SEALED PER DETAIL 5/P4.02. FIRE CAULK WHERE REQUIRED. THIS INCLUDES ALL WALLS, INTERIOR AND EXTERIOR. THIS INCLUDES FIRE SPRINKLER PIPING.
7. ALL CLEANOUTS SHALL BE CONNECTED TO SANITARY LINES USING WYES AND/OR LONG RADIUS ELLS. SANITARY TEES ARE NOT ACCEPTABLE. 2" MINIMUM SIZE. ALL WALL CLEAN OUTS IN VERTICAL RISERS, OR BANKS OF FIXTURES SHALL BE INSTALLED 4" ABOVE THE FLOOD RIM LEVEL OF THE LOWEST CONNECTED FIXTURE AND A MINIMUM OF 24" AFF.
8. ALL WASTE AND VENT PIPING BELOW SLAB SHALL BE 2" MINIMUM.
9. LOCATE PLUMBING VENTS THROUGH ROOF NOT NEARER THAN SIX (6) FEET AWAY FROM EDGE OF BUILDING AND TEN (10) FEET AWAY FROM ANY FRESH AIR INTAKES. OFFSET VENT PIPING, AS REQUIRED, IN CEILING SPACE BETWEEN CEILING AND ROOF TO MEET THESE REQUIREMENTS. SEE DETAIL 3/P4.02.
10. ALL DOMESTIC WATER PIPING (CW, HW AND HWR) SHALL BE INSULATED PER THE WRITTEN SPECIFICATIONS.
11. TOP OF FLOOR DRAINS IN MECHANICAL, AHU AND BOILER ROOMS SHALL BE SET 1–1/2" BELOW FINISHED FLOOR SURFACE. CONCRETE FLOOR SHALL BE SLOPED TO DRAIN, REFERENCE ARCHITECTURAL DRAWINGS. IN ALL OTHER LOCATIONS, FLOOR DRAINS SHALL BE SET FLUSH WITH FINISHED FLOOR, TAKING INTO ACCOUNT ANY FLOOR SLOPE OR FLOOR FINISH (TILE, TERRAZZO, ETC.) AS SHOWN ON ARCHITECTURAL DRAWINGS.
12. PROVIDE AN ISOLATING VALVE AT EACH WATER TAP OFF HOT AND COLD WATER MAINS TO ALLOW FOR SERVICING. VALVE SHALL BE BALL VALVE IF PIPE SIZE IS 2" OR LESS AND GATE VALVE OR BUTTERFLY VALVE IF LARGER THAN 2". SEE WRITTEN SPECIFICATIONS. VALVES SHALL BE EASILY ACCESSIBLE. PROVIDE 18" X 18", FIRE–RATED, STAINLESS STEEL ACCESS PANELS WITH NON–CORROSIVE CYLINDER LOCK DOORS WHERE VALVES ARE INSTALLED ABOVE INACCESSIBLE CEILINGS OR IN WALL CHASES (MIFAB MODEL MPFR–SS–C). BALL VALVES AND BUTTERFLY VALVES INSTALLED ABOVE CEILINGS SHALL BE INSTALLED SUCH THAT HANDLE IS ON BOTTOM OF PIPE. ISOLATING WATER VALVES ABOVE CEILINGS SHALL BE INSTALLED NO MORE THAN 24" ABOVE CEILING. VALVES ABOVE INACCESSIBLE CEILINGS SHALL BE INSTALLED WITHIN REASONABLE REACH OF CEILING MOUNTED ACCESS PANEL.
13. WATER HAMMER ARRESTERS SHALL BE INSTALLED IN ADDITION TO AIR CHAMBERS PER THE RISER DIAGRAMS. SEE SPECIFICATIONS.
14. MECHANICALLY CLEAN ALL WASTE LINES WITH ROTARY MACHINE TO PROVE FREE FLOWING, SEE SPECIFICATIONS.
15. PROVIDE VENTED SLEEVE (2 PIPE SIZES LARGER THAN GAS PIPE UNLESS NOTED OTHERWISE) FOR ALL GAS PIPING IN GROUND BELOW PAVING OR SIDEWALKS AND INSIDE BUILDING IN WALLS AND IN UNVENTILATED CEILING SPACES, SEE SPECIFICATIONS.
16. GAS PIPING SHALL BE 1/2" MINIMUM. TAP GAS PIPING ON TOP OR SIDES ONLY. DO NOT INSTALL VALVES IN CEILING PLENUM OR IN ANY INACCESSIBLE LOCATION. ALL GAS VALVES SHALL BE EASILY ACCESSIBLE. REFER TO DETAIL 9/P4.01 FOR TYPICAL GAS CONNECTION INSTALLATION. REFER TO DETAIL 8/P4.02 FOR TYPICAL PRV INSTALLATION.
17. CENTER WALL HYDRANTS IN BRICK PATTERN OF EXTERIOR WALLS, REFERENCE THE ARCHITECTURAL DRAWINGS AND SPECIFICATIONS.
18. ALL REFRIGERATORS WITH ICE MAKERS, COMMERCIAL TYPE COFFEE MAKERS, ICE MAKERS, COFFEE VENDING MACHINES AND OTHER ITEMS PROVIDED BY OTHERS THAT REQUIRE A WATER CONNECTION SHALL HAVE A CW VALVE BOX, "VBOX", INSTALLED TO ALLOW EASY ACCESS AND REMOVAL OF MACHINE. ALSO, INSTALL IN–LINE FILTER IN WATER CONNECTION.
19. REFER TO CIVIL DRAWINGS FOR SITE SANITARY, SITE STORM SEWER, FIRE SERVICE AND DOMESTIC WATER SERVICE. PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR ALL PIPING INSIDE BUILDING TO OUTSIDE LOCATIONS SHOWN ON PLUMBING DRAWINGS. PLUMBING CONTRACTOR SHALL INCLUDE COST OF FINAL TIE–INS TO SITE SERVICES.
20. PER THE DRAWINGS, ALL DRAINS (FLOOR DRAINS, FLOOR SINKS, HUB DRAINS, KITCHEN DRAINS, SHOWER DRAINS, ETC.) SHALL BE VENTED AND TRAP PRIMED – NO EXCEPTIONS. TRAP PRIMING SHALL BE ACCOMPLISHED USING WATER CLOSET FLUSH VALVE TRAP PRIMING DEVICES OR PROSET SYSTEMS TRAP GUARD SEWER GAS EMISSION PROTECTION, AS SHOWN ON DRAWINGS. REFERENCE PLUMBING FLOOR PLANS AND RISER DIAGRAMS.
21. ALL PIPING LOCATED ON ROOF (GAS PIPING) SHALL BE INSTALLED ON ROOF PIPE SUPPORTS PER DETAIL 10/P4.02, 6–FOOT ON CENTER. INSTALL ROOF PIPE JACK PER DETAIL 9/P4.02 FOR ALL PIPING THROUGH ROOF.
22. COORDINATE LOCATIONS OF ALL ROOF DRAINS AND OVERFLOW ROOF DRAINS WITH ARCHITECTURAL DRAWINGS.
23. FOR COMBINATION WASTE AND VENT SYSTEMS (WHERE APPLICABLE ON DRAWINGS), DRAIN P–TRAPS SHALL BE SIZE OF PIPE SHOWN ON DRAWINGS (I.E. TWO PIPE SIZES LARGER THAN DRAIN SIZE). FOR EXAMPLE, A 4" FLOOR DRAIN SHALL HAVE A 6" P–TRAP.
24. FOR ALL PLUMBING FIXTURES, IF COPPER PIPING IS STUBBED THROUGH WALL FOR DRAIN CONNECTION, INSTALL MARWEL FITTING AT DRAIN CONNECTION FOR EASE OF SERVICING AND REPAIRS. COPPER DRAIN PIPING WILL ONLY BE ALLOWED FOR DIRECT/STRAIGHT STUB–OUT OF FIXTURE DRAIN PIPING THROUGH WALL.
25. DO NOT INSTALL ANY PIPING BENEATH CVT OR VAV BOXES. THIS INCLUDES FIRE SPRINKLER PIPING.
26. WHERE UNDERGROUND VENT PIPE SIZE IS NOT NOTATED, VENT SHALL BE 2" DIAMETER.
27. WHERE UNDERGROUND SANITARY PIPE SIZE IS NOT NOTATED, REFER TO THE RISER DIAGRAMS FOR SIZE. NOT BELOW GRADE SANITARY PIPE SHALL BE SMALLER THAN 2". NO SANITARY LINE OR P–TRAP FOR A DRAIN/FIXTURE SHALL BE SMALLER THAN THE FIXTURE CONNECTION SIZE SHOWN ON THE DRAIN/FIXTURE SCHEDULE.
28. WHERE ABOVE GROUND VENT PIPE SIZE IS NOT NOTATED, REFER TO THE RISER DIAGRAMS FOR VENT SIZE.
29. WHERE CW/HW PIPING SIZE TO THE FIXTURE IS NOT SHOWN ON THE FLOOR PLAN, REFER TO THE RISER DIAGRAMS FOR CW/HW PIPE SIZE. NO PIPING TO FIXTURE SHALL BE SMALLER THAN THE FIXTURE CONNECTION SIZE SHOWN ON THE FIXTURE SCHEDULE.
30. TO INSTALL NEW PLUMBING SYSTEMS BELOW EXISTING CONCRETE SLABS, FIRST PLUMBING CONTRACTOR SHALL LAY OUT CUT. THEN, DEMOLITION CONTRACTOR SHALL SAW CUT SLAB TO CONTROL CRACKING AND REMOVE ALL CONCRETE. PLUMBING CONTRACTOR SHALL THEN EXCAVATE FILL TO PROPER SLOPE, INSTALL NEW PIPING SYSTEMS AS REQUIRED, THEN BACKFILL AND COMPACT TO PROPER DENSITY. THE CONCRETE CONTRACTOR SHALL THEN INSTALL NEW SIX (6) MIL POLYETHYLENE VAPOR BARRIER AND SEAL, INSTALL NEW REINFORCING STEEL AND WELD ON TO EXISTING, THEN RE–POUR CONCRETE TO NEW LEVEL. DO NOT CUT THROUGH GRADE BEAMS WITHOUT APPROVAL FROM THE STRUCTURAL ENGINEER. SEE ARCHITECTURAL AND STRUCTURAL DRAWINGS AND SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.
31. ALL ABANDONED FIXTURES, DRAINS AND PIPING (INCLUDING PIPING ABANDONED IN THE PAST) IN AREAS WHERE WORK IS BEING DONE SHALL BE COMPLETELY REMOVED FROM BUILDING (INCLUDING PIPING BELOW SLAB/GRADE – UNLESS SHOWN OTHERWISE ON DRAWINGS). EXISTING WATER PIPING SHALL BE CAPPED AT EXISTING WATER MAIN TAPS AND ALL ABANDONED PIPING REMOVED. ABANDONED VENT PIPING SHALL BE COMPLETELY REMOVED, INCLUDING EXISTING VTR'S NOT RE–USED. PATCH AS REQUIRED. ONLY ACTIVE PIPING, FIXTURES AND DRAINS SHALL REMAIN IN BUILDING WHERE WORK IS BEING DONE.

## GAS PRV SCHEDULE

| MARK | PRV–K |
|---|---|
| LOCATION | MECH. YARD |
| SERVES | KITCHEN |
| GAS LOAD | 585 CFH |
| DISTANCE FROM METER | 150 FT |
| DISTANCE TO LAST OUTLET | 200 FT |
| INLET (SIZE/PRESSURE) | 1" / 5 PSI |
| OUTLET (SIZE/PRESSURE) | 2" / 7–12 IN WC |




### 4 GAS PRESSURE REGULATOR DETAIL (PRV)

NO SCALE

NOTES:
1. GAS REGULATOR SHALL BE ANSI Z21.80 CERTIFIED FOR LINE PRESSURE REGULATION BETWEEN THE SERVICE REGULATOR AND CONNECTED EQUIPMENT.
2. ALL GAS REGULATORS WITH INLET PRESSURE ABOVE 2 PSI SHALL BE EQUIPPED WITH A FACTORY INSTALLED OVERPRESSURE PROTECTION DEVICE, AS PART OF THE ANSI Z21.80 CERTIFICATION.
3. GAS REGULATOR SHALL BE EQUIPPED WITH A VENT LIMITING DEVICE, SIZED IN ACCORDANCE WITH THE REGULATOR OUTLET PRESSURE.
4. ALL REGULATORS INSTALLED OUTDOORS SHALL BE RATED FOR OUTDOOR INSTALLATION.
5. BASIS OF DESIGN IN THE MAXITROL 325–L SERIES OF REGULATORS

## PLUMBING DRAINS, CLEANOUTS AND HYDRANTS


| MARK | MIN. CONNECTION SIZES (IN.) SAN | VENT | CW | HW | DESCRIPTION/SPECIFICATION FOR FIXTURE OR EQUIPMENT |
|---|---|---|---|---|---|
| FD | 4 | 2 | 1/2 | – | TOILET FLOOR DRAIN – TWO–PIECE CAST IRON WITH SEEPAGE FLANGE, REVERSIBLE CLAMPING COLLAR, 1/2" TRAP PRIMER TAP, 6" SQUARE, NICKEL BRONZE HSTRAINER AND SECURITY SCREWS JR SMITH MODEL 2005–03–K06PB–P050–U. |
| FD2 | 4 | 2 | 1/2 | – | EQUIPMENT FLOOR DRAIN – CAST IRON, MEDIUM DEPTH DRAIN WITH FLANGE, CLAMPING DEVICE, SEEPAGE OPENINGS, DUCTILE IRON TRUE–FIT SEDIMENT BUCKET WITH 12" STAINLESS STEEL RIM LESS GRATE, 1/2" TRAP PRIMER TAP ZURN MODEL ZS–540–U–S DRAIN SHALL BE DESIGNED SUCH THAT GRATE CANNOT BE INSTALLED WITHOUT SEDIMENT BUCKET. |
| FD3 | 4 | 2 | 1/2 | – | GRATED MECHANICAL ROOM FLOOR DRAIN – CAST IRON WITH FLANGE, SEEPAGE OPENINGS, 9" HEAVY–DUTY DUCTILE IRON GRATE WITH STAINLESS STEEL VENEER, CLAMPING DEVICE AND 1/2" TRAP PRIMER TAP ZURN MODEL ZS–550–C–P |
| FD4 | 4 | 2 | 1/2 | – | CANWASH FLOOR DRAIN – ALL GALVANIZED CAST IRON, MEDIUM DEPTH DRAIN WITH FLANGE, CLAMPING DEVICE, SEEPAGE OPENINGS, GALVANIZED SUR–SET SEDIMENT BUCKET WITH 12" GALVANIZED DUCTILE IRON RIM AND GRATE, 1/2" TRAP PRIMER TAP ZURN MODEL ZS–540–P–G–HD. DRAIN SHALL BE DESIGNED SUCH THAT GRATE CANNOT BE INSTALLED WITHOUT SEDIMENT BUCKET. |
| FD5 | 4 | 2 | 1/2 | – | KITCHEN FLOOR DRAINS SHALL BE SIMILAR EXCEPT WITH 7" SQUARE, BRONZE GRATE JR SMITH MODEL 2005–03–K07PB–P050–U. PROVIDE 4" DIAMETER STAINLESS STEEL FUNNEL WHERE SHOWN ON DRAWINGS. REFERENCE KITCHEN CONNECTION SCHEDULE ON PLUMBING RENOVATION FLOOR PLAN SHEET. |
| FS KITCHEN FS | 4 | 2 | 1/2 | – | FLOOR SINK – CAST IRON, 8" DEEP SUMP, A.R.E. INTERIOR, INTEGRAL FLANGE FOR SUPPORT, CLAMPING DEVICE WHERE VAPOR BARRIER IS INSTALLED BETWEEN SLAB AND CONCRETE BEDDING FOR FLOOR, ALUMINUM SECONDARY DOME STRAINER AND 12" SQUARE HEAVY DUTY STAINLESS STEEL TRACTOR DUTY FRAME WITH 3/4–TRACTOR GRATE AND 1/2" TRAP PRIMER TAP JR SMITH MODEL 3150Y–04–C–13. |
| CO | VARIES | – | – | – | FLOOR CLEANOUT – ADJUSTABLE EXTENSION HOUSING, CAST IRON FERRULE WITH FULL–LINE–SIZE BRASS PLUG (UP TO 4"), 5" DIAMETER STAINLESS STEEL ACCESS COVER WITH VANDAL–PROOF SECURITY SCREWS, EXCEPTIONAL FRAME AND TOP SIZE COMPATIBLE WITH FLOOR TYPE (REFERENCE ARCHITECTURAL DRAWINGS FOR FLOOR TYPES) ZURN MODEL ZS–1400–VP. PROVIDE CARPET FRAME FOR CARPETED AREAS (CARPET MARKER SHALL NOT BE ACCEPTABLE) AND TERRAZZO RECESS FOR TERRAZZO FLOORS.<br>OUTDOOR CLEANOUT – SAME AS TYPE "CO" EXCEPT WITH HEAVY–DUTY NICKEL BRONZE TOP ZURN MODEL ZN–1400–HD–VP. INSTALL 18" X 18" X 6" THICK CONCRETE PAD AROUND EACH OUTDOOR CLEANOUT. |
| WCO | VARIES | – | – | – | WALL CLEANOUT – CAST IRON FERRULE WITH COUNTERSUNK HEAD (FULL–LINE–SIZE PVC PLUG UP TO 4") MI–FAB MODEL CM–SD. ACCESS COVER SHALL BE 8" SQUARE, SURFACE MOUNT, FLUSH INSTALLATION, 16–GAUGE STAINLESS STEEL ACCESS DOOR WITH FLANGED FRAME AND VANDAL–PROOF OPTION MI–FAB MODEL UA–SS–VP. ACID WASTE CLEANOUT (AWCO) SHALL BE SAME EXCEPT ACID WASTE PIPING.<br>INSIDE CABINETWORK WHERE CLEANOUT IS NOT VISIBLE, ACCESS PANEL MAY BE ROUND STAINLESS STEEL TYPE WITH VANDAL–PROOF CENTER SCREW MI–FAB MODEL C1450–RD–3–6. |
| 2CO | 4 | – | – | – | DOUBLE CLEANOUTS – SAME AS OUTDOOR CLEANOUTS. INSTALLED FOR TWO–WAY RODDING. SINGLE CLEANOUT WITH 2–WAY FITTING IS NOT ACCEPTABLE, PROVIDE TWO SEPARATE CLEANOUTS. INSTALL 18" X 18" X 6" THICK CONCRETE PAD AROUND EACH OUTDOOR CLEANOUT. |
| HB | – | – | 3/4 | – | HOSEBIBB – 3/4" HOSE THREAD, INTEGRAL VACUUM BREAKER SPOUT, ROUGH CHROME FINISH WITH REMOVABLE KEYED HANDLE, WALL FLANGE CHICAGO MODEL 952. |
| WH | – | – | 3/4 | – | RESTROOM WALL HYDRANT – NARROW WALL, WARM CLIMATE TYPE HOSE BOX, QUARTER–TURN WHEEL HANDLE, ASSE APPROVED ANTI–SIPHON INTEGRAL VACUUM BREAKER AND DUAL CHECK VALVE, 3/4" STRAIGHT INLET HOSE CONNECTION, CAST STAINLESS STEEL HYDRANT BOX. FLUSH MOUNTED 16–GAUGE STAINLESS STEEL FRAME AND 180° DROP DOWN DOOR WITH KEY LOCK AND WALL CLAMP JR SMITH MODEL 5518 |
| WH2 | – | – | 3/4 | – | EXTERIOR WALL HYDRANT – NON–FREEZE HOSE BOX, QUARTER–TURN WHEEL HANDLE, ASSE APPROVED ANTI–SIPHON INTEGRAL VACUUM BREAKER AND DUAL CHECK VALVE, 3/4" STRAIGHT INLET HOSE CONNECTION, CAST STAINLESS STEEL HYDRANT BOX, FLUSH MOUNTED 16–GAUGE STAINLESS STEEL FRAME AND 180° DROP DOWN DOOR WITH KEY LOCK AND WALL CLAMP JR SMITH MODEL 5519 |
| WH3 | – | – | 3/4 | 3/4 | CANWASH WALL HYDRANT – NON–FREEZE HOSE BOX WITH STRAIGHT INLET CONNECTION, HOT AND COLD MIXING, REMOVABLE KEYED HANDLE, ASSE APPROVED ANTI–SIPHON INTEGRAL BACKFLOW PREVENTER WITH 3/4" HOSE CONNECTION, HEAVY DUTY BRASS CASING, POLISHED BRONZE HYDRANT BOX WITH HINGED COVER, "WATER" CAST ON COVER, DRIP LIP AND WALL CLAMP J.R. SMITH MODEL 5560–QT–WC–H–W–PB. |
| WBOX | 2 | 2 | 3/4 | 3/4 | CLOTHES WASHER DRAIN/VALVE BOX – HEAVY–GAUGE GALVANIZED STEEL CONSTRUCTION, RECESSED IN WALL VALVE AND DRAIN CONNECTIONS, WATTS DUO–CLOZ VALVE GUY GRAY MODEL WB–200. |

## PLUMBING FIXTURES AND EQUIPMENT

| MARK | MIN. CONNECTION SIZES (IN.) SAN | VENT | CW | HW | DESCRIPTION/SPECIFICATION |
|---|---|---|---|---|---|
| WC | 4 | 2 | 1 | – | WATER CLOSET – WALL MOUNTED, WHITE VITREOUS CHINA, SIPHON JET ACTION, 1.28 GPF, ELONGATED BOWL, TOP SPUD, ADA/TAS COMPLIANT, AMERICAN STANDARD AFWALL: SLOAN ROYAL 111–1.28 FLUSH VALVE WITH VANDAL–PROOF FREE–SPINNING TOP CAP, 1.28 GPF, VANDAL–PROOF STOP AND ADA/TAS COMPLIANT LEVER ACTUATOR WITH LEVER INSTALLED ON LEFT SIDE (FOR FIXTURES DESIGNATED AS "HANDICAP"). INSTALL LEVER ON "WIDE–SIDE" OF TOILET STALL): BEMIS 1655–SS/C EXTRA HEAVY DUTY, WHITE, OPEN FRONT SEAT LESS COVER WITH SELF–SUSTAINING, STAINLESS STEEL CHECK HINGE; AND, FLOOR MOUNTED CARRIER. |
| LV | 1–1/4 | 1–1/4 | 1/2 | 1/2 | LAVATORY GOOSENECK FAUCET – WALL HUNG, WHITE VITREOUS CHINA, FRONT OVERFLOW, SELF–DRAINING DECK AREA, 21" X 18", ADA/TAS COMPLIANT AMERICAN STANDARD LUCERNE 0355.012; DECK MOUNTED FAUCET, 4" CENTERS, FIXED, CHROME PLATED, 5.25" GOOSENECK SPOUT, PRESSURE COMPENSATING LAMINAR FLOW NON–AERATING 0.5 GPM OUTLET, 4" WRISTBLADE HANDLES, ASSEMBLY/BUILDABLE CARTRIDGES, CHICAGO 895–317GN2AE72ABCP; CHROME PLATED, 17–GAUGE CAST BRASS GRID DRAIN WITH WHEELCHAIR OFFSET FITTING; CHROME PLATED, 17–GAUGE CAST BRASS P–TRAP WITH CLEANOUT PLUG; CHROME PLATED, CAST BRASS, LOOSE KEY ANGLE STOP WITH CHROME PLATED COPPER RISER; TRUEBRO HANDI LAV–GUARD VANDAL–PROOF, WHITE INSULATION KITS; AND, FLOOR MOUNTED, CONCEALED ARMS CARRIER. PROVIDE ASSE 1070 LISTED MIXING VALVE, LEONARD 170–LF OR EQUAL (MUST BE CAPABLE OF ADJUSTMENT ABOVE 130°F). |
| LV2 | 1–1/4 | 1–1/4 | 1/2 | 1/2 | LAVATORY – WALL HUNG, WHITE VITREOUS CHINA, FRONT OVERFLOW, SELF–DRAINING DECK AREA, 21" X 18", ADA/TAS COMPLIANT AMERICAN STANDARD LUCERNE 0355.012; CHROME PLATED, ALL CAST BRASS CONSTRUCTION, ADA/TAS COMPLIANT, VANDAL–PROOF FAUCET WITH 4" WRIST BLADE HANDLES, COMPRESSION STYLE CARTRIDGES, CHROME DECK PLATE, VANDAL–PROOF AERATOR, COPPER SUPPLIES AND CERTIFIED FOR MEETING ALL REQUIREMENTS OF NSF 61 SECTION 9 CHICAGO MARATHON MODEL 802–E70–317ABCP; CHROME PLATED, 17–GAUGE CAST BRASS GRID DRAIN WITH WHEELCHAIR OFFSET FITTING; CHROME PLATED, 17–GAUGE CAST BRASS P–TRAP WITH CLEANOUT PLUG; CHROME PLATED, CAST BRASS, LOOSE KEY ANGLE STOP WITH CHROME PLATED COPPER RISER; TRUEBRO HANDI LAV–GUARD VANDAL–PROOF, WHITE INSULATION KITS; AND, FLOOR MOUNTED, CONCEALED ARMS CARRIER. PROVIDE ASSE 1070 LISTED MIXING VALVE, LEONARD 170–LF OR EQUAL (MUST BE CAPABLE OF ADJUSTMENT ABOVE 130°F). |
| EDF | 1–1/2 | 1–1/2 | 1/2 | – | BI–LEVEL ELECTRIC DRINKING FOUNTAINS WITH BOTTLE FILLER – WALL MOUNTED, ALL STAINLESS STEEL, ADA AND TAS COMPLIANT FOR ALL AGES, 8 GPH AT ARI STANDARDS, 2–STREAM ALL METAL BUBBLER FITTING WITH VANDAL–RESISTANT KIT AND FRONT PUSH BUTTON ACTUATION, PUSH BUTTON ACTUATED BOTTLE FILLER WITH 1.1GPM FILL AND ANTI–MICROBIAL COATING, INTEGRAL WATER FILTER, LEAD–FREE (CERTIFIED FOR MEETING ALL REQUIREMENTS OF NSF 61 SECTION 9), REFRIGERANT HFC–134a, MAINTENANCE ACCESS PANEL, HALSEY–TAYLOR MODEL HTHBHVR8BL; CHROME PLATED, 17–GAUGE CAST BRASS P–TRAP WITH CLEANOUT PLUG; CHROME PLATED, CAST BRASS, LOOSE KEY ANGLE STOP WITH CHROME PLATED COPPER RISER; FLOOR MOUNTED CHAIR CARRIER; AND, STAINLESS STEEL ADA APRON FOR LOCATIONS REQUIRED BY ADA OR TAS. |
| MB | 3 | 2 | 3/4 | 3/4 | MOP BASIN – 24" X 24" X 12" DEEP TERRAZZO, TWO (2) STAINLESS STEEL SPLASH CATCHER PANELS, 6" DROP FRONT WITH STAINLESS STEEL CAP, CAST BRASS DRAIN WITH STAINLESS STEEL STRAINER STERN WILLIAMS HILOW MODEL HI–1800–BP; FAUCET SHALL BE POLISHED CHROME PLATED SERVICE SINK TYPE WITH VACUUM BREAKER, INTEGRAL SUPPLY CHECK STOPS, SPOUT WITH PAIL HOOK, HOSE END AND TOP BRACE CHICAGO MODEL 897–CCF (INSTALL BACKING/BRACING INSIDE WALL TO SUPPORT FAUCET AND TOP BRACE). |
| LP–1 | 3 | 2 | 3/4 | 3/4 | LAVATORY PUMP – FACTORY BUILT, LIFT PUMP FOR GRAY WATER WASTE, TOP ACCESS TO INTERNAL 1/5HP PUMP AND FLOAT SWITCH, 1.5" TOP AND SIDE INLETS, 1.5" TOP OUTLET, INTEGRAL CHECK VALVE AT BOTTOM INLET CONNECTIONS, 9FT POWER CORD WITH GROUNDED PLUG;<br>LIBERTY PUMPS MODEL 406 |

## KITCHEN PLUMBING CONNECTION SCHEDULE


| MARK | DESCRIPTION |
|---|---|
| P5 | 3/4" CW AND 3/4" HW – IN WALL, 36" AFF, TO MOP BASIN ("MB") FAUCET. REFERENCE PLUMBING FIXTURE SCHEDULE. |
| P6 | 3" DRAIN IN FLOOR FOR MOP BASIN ("MB") DRAIN. REFERENCE PLUMBING FIXTURE SCHEDULE. |
| P7 | 3/4" CW AND 3/4" HW – IN WALL, 18" AFF, TO HOSE BIBB. |
| P10 | FLOOR DRAIN – 3" OUTLET; FLUSH WITH FLOOR; TWO–PIECE CAST IRON WITH SEEPAGE FLANGE, REVERSIBLE CLAMPING COLLAR, 7" SQUARE HEAVY–DUTY POLISHED BRONZE GRATE, 1/2" TRAP PRIMER TAP, AND TRAP SEAL DEVICE (MODEL 2692) JR SMITH MODEL 2005–03–K07PB–P050–U. |
| P11C | 1/2" CW AND 1/2" HW – IN WALL, FOR HAND LAVATORY WITH FOOT CONTROLS ("LV"). REFERENCE PLUMBING FIXTURE SCHEDULE. |
| P11D | 2" DRAIN – IN WALL, FOR HAND LAVATORY WITH FOOT CONTROLS ("LV"). REFERENCE PLUMBING FIXTURE SCHEDULE. |
| P12 | FLOOR SINK – 4" OUTLET; FLUSH WITH FLOOR; CAST IRON, 8" DEEP SUMP, A.R.E. INTERIOR, INTEGRAL FLANGE FOR SUPPORT, CLAMPING DEVICE WHERE VAPOR BARRIER IS INSTALLED BETWEEN SLAB AND CONCRETE BEDDING FOR FLOOR, ALUMINUM SECONDARY DOME STRAINER AND 12" SQUARE HEAVY DUTY NICKEL BRONZE FR




## 13 FLUSH VALVE TRAP PRIMING TUBE DETAIL

NO SCALE


MI-FAB MODEL MI-702-MOD FLUSH VALVE TRAP PRIMER, OR EQUAL




## 13 GAS PIPING WALL-TO-ROOF TRANSITION DETAIL

NO SCALE

| TANKLESS WATER HEATER SCHED. | | |
|---|---|---|
| MARK | IEWH-1 | |
| SERVES | LAVATORY | |
| LOCATION | BELOW COUNTER | |
| HEATER KW | 1.8 KW | |
| TEMP RISE (@ 0.5 GPM) | 25°F | |
| VOLTAGE/PHASE | 120V/1PH | |
| EEMAX MODEL | SPEX1812T | |





## 11 TANKLESS WATER HEATER

NO SCALE

NOTES:

1. LOCATION OF VALVE AND PIPING SHALL NOT INTERFERE WITH ANY ADA/HANDICAP KNEE-SPACE CLEARANCE REQUIREMENTS.
2. ALL PIPING SHALL BE CHROME PLATED CAST BRASS AND SHALL BE INSULATED BY TRUEBRO HANDI LAV-GUARD INSULATION KITS. INSULATION KITS SHALL COVER P-TRAP, MIXING VALVE, WATER STOPS, PIPING AND ALL SHARP EDGES (ONLY WHERE CABINETWORK KNEESPACE SCREEN NOT PROVIDED).
3. ALL CW AND HW CONNECTIONS SHALL HAVE COMPRESSION TYPE FITTINGS.
4. FURNISH & INSTALL 0.5-GPM AERATOR ON FAUCET COMPATIBLE WITH TANKLESS EWH REQUIREMENTS.
5. WATER HEATER SHALL HAVE INTEGRAL ASSE-1070 COMPLIANT TEMPERED MIXING VALVE.





## 10 ELECTRONIC TRAP PRIMING MANIFOLD DETAIL (TP)

NO SCALE

NOTES:

1. REFERENCE SCHEDULE ON SHEET P3.00





## 14 GAS PIPING ROOF SUPPORT DETAIL

NO SCALE

NOTES:


1. GAS PIPING SUPPORT SHALL BE PORTABLE PIPE HANGERS, INC. MODEL PP10-R. PIPING SHALL BE INSTALLED 12" ABOVE FINISHED ROOF. PROVIDE 18" X 18" CAREY TREAD-TYPE MATERIAL BENEATH EACH PIPE SUPPORT.
2. FIELD LOCATE ROOF STRUCTURAL SUPPORTS AND PLACE BASE OF PIPE SUPPORT OVER ROOF SUPPORTS ONLY. PROVIDE BASE OF ADEQUATE LENGTH TO SPAN ROOF JOIST TO PREVENT SUPPORTS SETTING ON ROOF DECK ONLY.
3. INSTALL SIX (6) FOOT-ON-CENTERS.
4. PIPE SUPPORT MANUFACTURER'S REPRESENTATIVE SHALL PERSONALLY INSPECT INSTALLATIONS OF PIPE SUPPORTS AND MAKE CORRECTIONS AND HEIGHT ADJUSTMENTS TO INSTALLATIONS, AS REQUIRED, DURING INSPECTION.




## 9 ROOF PIPE JACK DETAIL

NO SCALE


NOTE: COORDINATE WITH ARCHITECTURAL DRAWINGS, DETAILS AND SPECIFICATIONS.




## 8 SAMPLE TEST WELL DETAIL (STW)


NO SCALE

NOTES:




## 7 TYPICAL GAS CONNECTION


NO SCALE




## 6 HOT WATER BALANCING STATION


NO SCALE

PROVIDE AT EACH JUNCTION OF BRANCH HOT WATER RETURN LOOPS TO MAIN CIRCULATING HOT WATER LINE, SEE PLUMBING PLANS.




## 5 WALL PENETRATION DETAIL


NO SCALE




## 4 PVC-TO-CAST IRON INSTALLATION DETAIL

NO SCALE


MISSION TRANSITION COUPLING DESIGNED AND CERTIFIED FOR THIS SPECIFIC APPLICATION SHALL BE ACCEPTABLE IN LIEU OF HUSKY COUPLING IN THIS DETAIL.




## 3 ROOF VENT DETAIL

NO SCALE

COORDINATE WITH ARCHITECTURAL DRAWINGS AND SPECIFICATIONS.





## 2 MIXING VALVE DETAIL

NO SCALE

NOTES

1. UNDERCOUNTER MIXING VALVE SHALL BE MOUNTED ON WALL IN FIXTURE KNEE-SPACE. LOCATION OF VALVE AND PIPING SHALL NOT INTERFERE WITH ANY ADA/HANDICAP KNEE-SPACE CLEARANCE REQUIREMENTS.
2. ALL PIPING SHALL BE CHROME PLATED CAST BRASS AND SHALL BE INSULATED BY TRUEBRO HANDI LAV-GUARD INSULATION KITS. INSULATION KITS SHALL COVER P-TRAP, MIXING VALVE, WATER STOPS, PIPING AND ALL SHARP EDGES (ONLY WHERE CABINETWORK KNEESPACE SCREEN NOT PROVIDED).
3. ALL CW AND HW CONNECTIONS SHALL HAVE COMPRESSION TYPE FITTINGS.
4. FOR ABOVE CEILING INSTALLATION, VALVE SHALL BE INSTALLED IN AN EASILY/READILY ACCESSIBLE LOCATION. SEE KITCHEN PLUMBING CONNECTION SCHEDULE FOR REQUIRED KITCHEN LOCATIONS.
5. LAVATORY MIXING VALVES SHALL HAVE AN OUTPUT ADJUSTMENT RANGE UP TO OR ABOVE 130°F.
   SINK MIXING VALVES SHALL HAVE AN OUTPUT ADJUSTMENT RANGE UP TO OR ABOVE 140°F.




## 1 MECHANICAL - ELECTRICAL COORDINATION DETAIL

NO SCALE

DO NOT INSTALL ANY PIPING BENEATH CVT BOXES. DO NOT INSTALL ANY PIPING (EXCEPT FIRE SPRINKLER PIPING AND OTHER PIPES SHOWN SPECIFICALLY ON THE PLUMBING FLOOR PLANS) OVER COMPUTER CLASSROOMS, BOOKROOMS, IDF/MDF/SERVER ROOMS OR OTHER ROOMS NOTED ON THE PLUMBING FLOOR PLANS.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

j

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL

STATE OF TEXAS
INTERIM REVIEW
THOMAS J. STANTON
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

PLUMBING SCHEDULES & DETAILS

**j-P0.02**

PRELIMINARY
NOT FOR CONSTRUCTION OR BIDDING PURPOSES


STANTON ENGINEERING GROUP
INFORMATION@STANTONEG.COM (713) 300-9080
TEXAS ENGINEERING FIRM REG. NO. F-018332 | 1300 W. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77043

©2025 ALL RIGHTS RESERVED

# TECHNOLOGY SYMBOLS & LEGEND

## VOICE SYMBOLS

| | |
|---|---|
| ▼ | SINGLE VOICE OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| ▼X | VOICE OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |
| ▼ | SINGLE VOICE OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED. |
| ▼X | VOICE OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED, X = NUMBER OF CABLE TERMINATIONS PER LOCATION AS INDICATED. |
| ▼ | POWER/COMMUNICATIONS POLE WITH A SINGLE VOICE OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| ▼X | POWER/COMMUNICATIONS POLE WITH X = NUMBER OF VOICE OUTLETS, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| ▣▼ | SINGLE VOICE OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE-THRU AS SPECIFIED. |
| X ▣▼ | VOICE OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE -THRU AS SPECIFIED WITH X = NUMBER OF VOICE TERMINATIONS PER LOCATION. |
| W ▼ | SINGLE VOICE OUTLET FOR WALL-MOUNTED PHONE, CABLE TYPE AS SPECIFIED, MOUNTED +52-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

## DATA SYMBOLS

| | |
|---|---|
| ▽ | SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| X ▽ | DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |
| ▽ | SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED. |
| X ▽ | DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED, X = NUMBER OF CABLE TERMINATIONS PER LOCATION AS INDICATED. |
| ▽ | POWER/COMMUNICATIONS POLE WITH A SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| X ▽ | POWER/COMMUNICATIONS POLE WITH X = NUMBER OF DATA OUTLETS, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| ▣ | SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE-THRU AS SPECIFIED. |
| X ▣ | DATA OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE -THRU AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |
| W ▽ | SINGLE DATA OUTLET FOR WALL-MOUNTED IP PHONE, CABLE TYPE AS SPECIFIED, MOUNTED +52-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| X ▽ | DATA CABLE FOR COMPUTER ON WHEELS, CABLE TYPE AS SPECIFIED MOUNTED + 18-INCHES A.F.F UNLESS OTHERWISE NOTED. X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |
| X | DATA CABLE FOR CEILING MOUNTED WIRELESS ACCESS POINT, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A GREEN ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. |
| X | DATA CABLE FOR CEILING MOUNTED VIDEO SURVEILLANCE CAMERA, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A ORANGE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. REFER TO SECURITY DRAWINGS PRIOR TO INSTALLATION. |
| | DATA CABLE FOR CEILING MOUNTED PROJECTOR, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A BLUE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. REFER TO AUDIO/VISUAL DRAWINGS PRIOR TO INSTALLATION. |
| X | DATA CABLE FOR CEILING MOUNTED AUDIO/VISUAL EQUIPMENT ENCLOSURE, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A BLUE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. REFER TO AUDIO/VISUAL DRAWINGS PRIOR TO INSTALLATION. |
| X ▽ | DATA CABLE FOR WALL MOUNTED PROJECTOR, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A BLUE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. REFER TO AUDIO/VISUAL DRAWINGS PRIOR TO INSTALLATION. |

## DATA SYMBOLS, CONT.

| | |
|---|---|
| X CAME | DATA CABLE FOR EXTERIOR WALL MOUNTED VIDEO SURVEILLANCE CAMERA, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A ORANGE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW, REFER TO SECURITY DRAWINGS PRIOR TO INSTALLATION. |
| X CAMW | DATA CABLE FOR INTERIOR WALL MOUNTED SURVEILLANCE CAMERA, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A ORANGE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. |
| X CAME | DATA CABLE FOR EXTERIOR WALL MOUNTED SURVEILLANCE CAMERA, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A ORANGE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. |
| X WAPW | DATA CABLE FOR INTERIOR WALL MOUNTED WIRELESS ACCESS POINT, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A GREEN ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. |
| X WAPE | DATA CABLE FOR EXTERIOR WALL MOUNTED WIRELESS ACCESS POINT, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A GREEN ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

## CABLE PLANT & RISER DIAGRAM

| | |
|---|---|
| ◯ | MAINTENANCE HOLE, SIZE & TYPE AS SPECIFIED. |
| □ | PULLBOX, SIZE AND TYPE AS SPECIFIED. |
| UGC | DIRECT BURIED COMMUNICATIONS, CABLE TYPE AS SPECIFIED. |
| AER | AERIAL COMMUNICATIONS, CABLE TYPE AS SPECIFIED. |
| | CONDUIT, SIZE AND TYPE AS SPECIFIED. |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

## VOICE/DATA SYMBOLS

| | |
|---|---|
| ▼ | SINGLE VOICE & SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| X Y ▼ | VOICE & DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. X = NUMBER OF VOICE TERMINATIONS , Y = NUMBER OF DATA TERMINATIONS PER LOCATION. |
| ▼ | SINGLE VOICE & SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED. |
| X Y ▼ | VOICE & DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED, X = NUMBER OF VOICE OUTLETS AND Y = NUMBER OF DATA OUTLETS PER LOCATION AS INDICATED. |
| ▼ | POWER/COMMUNICATIONS POLE WITH A SINGLE VOICE OUTLET AND SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| X Y ▼ | POWER/COMMUNICATIONS POLE WITH X = NUMBER OF VOICE TERMINATIONS, Y = NUMBER OF DATA TERMINATIONS, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| ▣▼ | SINGLE VOICE OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE-THRU AS SPECIFIED. |
| X Y ▣▼ | VOICE OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE -THRU AS SPECIFIED WITH X = NUMBER OF VOICE TERMINATIONS, Y = NUMBER OF DATA TERMINATIONS PER LOCATION. |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

## FIBER OPTIC SYMBOLS

| | |
|---|---|
| ▽ | SINGLE FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| X ▽ | FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |
| ▽ | SINGLE FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED. |
| X ▽ | FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED, X = NUMBER OF CABLE TERMINATIONS PER LOCATION AS INDICATED. |
| ▽ | POWER/COMMUNICATIONS POLE WITH A SINGLE FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| X ▽ | POWER/COMMUNICATIONS POLE WITH X = NUMBER OF FIBER OPTIC OUTLETS, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| ▣ | SINGLE FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE-THRU AS SPECIFIED. |
| X ▣ | FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE -THRU AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

## ROUGH-IN & MISC. SYMBOLS

| | |
|---|---|
| R ▽ | ROUGH-IN LOCATION, INFRASTRUCTURE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| R ▽ | ROUGH-IN LOCATION, INFRASTRUCTURE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED. |
| R ▽ | POWER POLE WITH ROUGH-IN LOCATION, INFRASTRUCTURE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| R ▣ | ROUGH-IN LOCATION, TERMINATED IN FLOOR BOX/POKE-THRU AS SPECIFIED. |
| WAP | WIRELESS ACCESS POINT. EQUIPMENT AS SPECIFIED. |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

## GENERAL SYMBOLS

| | |
|---|---|
| # SHEET DRAWING TITLE SCALE: SCALE | DRAWING TITLE CALLOUT, # = DETAIL NUMBER. |
| # SHEET | DETAIL CALLOUT, # = DETAIL NUMBER. |
| # SHEET | SECTION CALLOUT, # = DETAIL NUMBER. |
| SHEET # | ELEVATION CALLOUT, # = DETAIL NUMBER. |
| # | KEYED NOTE, # = KEYED NOTE NUMBER. |
| # | REVISION TRIANGLE, # = REVISION NUMBER (PER SHEET). |
| TR (IDF XXX) | INDICATES TELECOMMUNICATIONS REGION |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

## ABBREVIATIONS

| | |
|---|---|
| A.F.F. | ABOVE FINISHED FLOOR |
| A.F.G. | ABOVE FINISHED GRADE |
| AER | AERIAL |
| DEMARC | DEMARCATION POINT |
| EMT | ELECTRIC METALLIC TUBE |
| F.O.C. | FIBER OPTIC CABLE |
| GIP | GALVANIZED IRON PIPE |
| HE | PAINTERCOM HEAD-END |
| IMC | INTERMEDIATE METAL CONDUIT |
| ISP | INSIDE CABLE PLANT |
| IDF | INTERMEDIATE DISTRIBUTION FRAME |
| MDF | MAIN DISTRIBUTION FRAME |
| MH | MAINTENANCE HOLE |
| MM | MULTIMODE |
| OSP | OUTSIDE CABLE PLANT |
| PB | PULLBOX |
| PR | PAIR |
| PVC | POLYVINYL CHLORIDE |
| RSC | RIGID STEEL CONDUIT |
| SM | SINGLE MODE |
| SP | SERVICE PROVIDER |
| STP | SHIELDED TWISTED PAIR |
| TB | TERMINAL BLOCK |
| TR | TELECOMMUNICATION REGION |
| UGC | UNDERGROUND COMMUNICATION |
| UON | UNLESS OTHERWISE NOTED |
| UTP | UNSHIELDED TWISTED PAIR |

## NOTES

1. CONTRACTOR SHALL REVIEW DRAWINGS AND SPECIFICATIONS THAT MAKE UP THE CONTRACT DOCUMENTS AND COMPLETE ALL WORK INCLUDED THEREIN.
2. SCALE OF TECHNOLOGY DRAWINGS IS PROVIDED FOR REFERENCE ONLY. CONTRACTOR SHALL BE RESPONSIBLE FOR PROPER CABLE LENGTHS, SIZE OF PATHWAYS, DIMENSIONS, ETC.
3. TECHNOLOGY DRAWINGS SHALL BE USED TO COMPLEMENT THE WRITTEN SPECIFICATIONS.
4. ANY DISCREPANCY OR CONFLICT WITHIN OR BETWEEN THE DRAWINGS AND SPECIFICATIONS SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT/DESIGN CONSULTANT'S. DISCREPANCIES OR CONFLICTS NOT BROUGHT TO THE ATTENTION OF THE ARCHITECT/DESIGN CONSULTANT AND SUBSEQUENTLY CLARIFIED DURING THE BIDDING OF THE PROJECT WILL BE DEEMED TO HAVE BEEN BID OR PROPOSED IN THE MORE COSTLY OR DIFFICULT MANNER, AND THE BETTER QUALITY OR GREATER QUANTITY OF WORK SHALL BE PROVIDED BY THE CONTRACTOR IN ACCORDANCE WITH THE ARCHITECT'S/DESIGN CONSULTANT'S INTERPRETATION.

## INDEX OF DRAWINGS


| | |
|---|---|
| j-T000 | TECHNOLOGY SYMBOLS & LEGEND |
| j-TD201 | TECHNOLOGY DEMOLITION FLOOR PLAN |
| j-T200 | TECHNOLOGY COMPOSITE FLOOR PLAN |
| j-T201 | TECHNOLOGY NEW/RENOVATION KITCHEN PLAN |
| j-T202 | TECHNOLOGY TEMPORARY KITCHEN FLOOR PLAN |
| j-T300 | TECHNOLOGY ENLARGED VIEWS |
| j-T400 | TECHNOLOGY TYPICAL DETAILS |
| j-T401 | TECHNOLOGY TYPICAL DETAILS |
| j-T500 | TECHNOLOGY TYPICAL LABELING SCHEME |


ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD


07/18/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY SYMBOLS & LEGEND

SHEET NO.
j-T000




1 TECHNOLOGY COMPOSITE FLOOR PLAN
j-T200 1/16" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

J

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzales Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD


07/18/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY COMPOSITE FLOOR PLAN

SHEET NO.
j-T200




1 j-T201 TECHNOLOGY NEW/RENOVATION KITCHEN PLAN
1/4" = 1'-0"

**TECHNOLOGY FLOOR PLANS GENRAL NOTES:**

1. THE TECHNOLOGY REGION / WIRING BOUNDARIES ARE IDENTIFIED ON THE OVERALL SHEETS ONLY AND NOT ON THE ENLARGED SHEETS. CONTRACTOR SHALL REFER TO THE OVERALL SHEETS FOR ALL TECHNOLOGY REGIONS / WIRING BOUNDARIES.
2. ALL CONDUIT PATHWAYS, ROUGH-INS, BACKBOXES, FLOOR BOXES, CONDUIT SLEEVES, ETC. INDICATED ON THE TECHNOLOGY DRAWINGS ARE TO BE PROVIDED AND INSTALLED BY DIVISION 26.
3. ALL POWER INDICATED ON THE TECHNOLOGY DRAWINGS IS TO BE PROVIDED AND INSTALLED BY DIVISION 26.
4. CONTRACTOR SHALL RESTORE ALL PENETRATIONS PROVIDED THROUGH FIRE RATED WALLS/STRUCTURES FOR TECHNOLOGY CABLING BACK TO THE ORIGINAL RATING.
5. CONTRACTOR SHALL RESTORE ALL PENETRATIONS PROVIDED THROUGH NON-RATED WALLS/STRUCTURES FOR TECHNOLOGY CABLING FOR SOUND TO REDUCE NOISE TRAVELING THROUGH PENETRATIONS.
6. TECHNOLOGY CABLING SHALL BE ROUTED IN SEPARATE PATHWAYS IN J-HOOKS, CONDUITS, CONDUIT SLEEVES, CORES, ETC. THROUGHOUT THE ENTIRE PATHWAY. DIFFERENT MEDIA TYPES (DATA, VIDEO, SECURITY, ETC.) SHALL NOT SHARE THE SAME J-HOOK, CONDUIT, CONDUIT SLEEVE, CORE, ETC.
7. UNLESS NOTED OTHERWISE, ALL CONDUITS FOR TECHNOLOGY DEVICES SHALL ROUTE FROM THE DEVICE LOCATION AND TERMINATE ABOVE AN ACCESSIBLE CEILING (AN OPEN CEILING OR CLOUD TYPE CEILING IS NOT CONSIDERED AN ACCESSIBLE CEILING) IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF A MAIN CORRIDOR OR NEAREST MDF/IDF. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF / IDF ROOM TO MINIMIZE THE CABLE LENGTH ENSURING CABLE LENGTH DOES NOT EXCEED 275 FEET.
8. UNLESS NOTED OTHERWISE ALL CONDUITS SHALL BE HOMERUN FROM THE DEVICE LOCATION AND NO DAISY CHAINING OF DEVICES/ ROUGH-INS SHALL BE ALLOWED.
9. CONDUIT SEGMENTS SHALL BE NO MORE THAN 100-FEET IN LENGTH WITH NO MORE THAN THE EQUIVALENT OF (2) 90 DEGREE BENDS BETWEEN PULLING POINTS.
10. CONDUITS SHALL MAINTAIN A BEND RADIUS OF 6 TIMES THE DIAMETER OF THE CONDUIT FOR CONDUITS 2-INCHES OR SMALLER AND 10 TIMES THE DIAMETER OF THE CONDUIT FOR CONDUITS GREATER THAN 2-INCHES.
11. ALL CONDUITS SHALL HAVE A PULL STRING INSTALLED FOR PULLING OF CABLE. CLEARLY LABEL AS "PULL STRING" INDICATING OPPOSITE END LOCATION.
12. ALL SPARE CONDUITS OR CONDUITS FILLED WITH LESS THAN THE MAXIMUM ALLOWED FILL RATIO SHALL HAVE A PULL STRING INSTALLED AND LEFT FOR FUTURE PULLING OF CABLE. CLEARLY LABEL AS "PULL STRING" INDICATING OPPOSITE END LOCATION.
13. EQUIPMENT NOT RELATED TO THE SUPPORT OF THE TELECOMMUNICATIONS ROOM (E.G., PIPING, DUCTWORK, PNEUMATIC TUBING) SHALL NOT BE INSTALLED IN, PASS THROUGH, OR ENTER THE TELECOMMUNICATIONS ROOM.
14. ALL CONDUITS FOR TECHNOLOGY DEVICES SHALL ROUTE FROM THE DEVICE LOCATION AND TERMINATE ABOVE A LAY-IN TYPE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE A LAY- IN TYPE CEILING TO PREVENT THE CABLES FROM BEING EXPOSED, THE CONDUIT SHALL ROUTE TO THE NEAREST LAY-IN TYPE CEILING OFF A MAIN CORRIDOR OR NEAREST MDF/IDF. THE CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE MAIN CORRIDOR OR NEAREST MDF/IDF TO MINIMIZE THE CABLE LENGTH ENSURING THE CABLE LENGTH DOES NOT EXCEED 275 FEET. CONDUIT, CONNECTIONS, J-BOXES, SUSPENSION, ANCHORAGES, AND OTHER CONDUIT COMPONENTS EXPOSED TO VIEW IN PUBLIC SPACES SHALL BE ROUTED AND INSTALLED CAREFULLY TO MINIMIZE VISUAL IMPACT AND SHALL BE FULLY PAINTED TO MATCH UNLESS NOTED OTHERWISE.
15. CONDUIT(S) INSTALLED IN-SLAB OR UNDER-SLAB TO FLOOR BOXES, POKE-THURS, AND TO WORKAREA OUTLETS, ETC. SHALL BE INSTALLED WITH WET RATED CABLE(S).
16. NO GRID WIRE SHALL BE UTILIZED FOR SUPPORTS ONLY USE SOLID SUPPORTS (CLIPS, ALL-THREAD, ANCHORS, ETC.).

**TECHNOLOGY PLAN KEYED NOTES**

**NOT ALL KEYED BELOW APPLY TO THIS SHEET**

1. DATA CABLE FOR CONTRACTOR FURNISHED / CONTRACTOR INSTALLED MENU BOARD. REFERENCE ARCHITECTURAL AND FOOD SERVICE DRAWINGS FOR MOUNTING HEIGHT AND ADDITIONAL INFORMATION. BUILDING POWER ADJACENT TO DATA RECEPTACLE IS REQUIRED.
2. INDOOR / OUTDOOR RATED DATA CABLE FOR POINT OF SALE LOCATION. PROVIDE (1) 1-INCH CONDUIT FOR DATA TO THE WALL BEHIND POINT OF SALE LOCATION AND UP WALL TO ABOVE ACCESSIBLE CEILING. CONDUITS SHALL TERMINATE INSIDE A DOUBLE GANG BOX THAT IS SECURED TO THE POINT OF SALE LOCATION. REFER TO FOOD SERVICE / KITCHEN DRAWINGS FOR EXACT LOCATION AND CONDUIT ROUGH-IN REQUIREMENTS.
3. DATA CABLE FOR TEMPERATURE MONITORING OF FREEZER COOLER. REFER TO FOOD SERVICE / KITCHEN DRAWINGS FOR EXACT LOCATION AND CONDUIT ROUGH-IN REQUIREMENTS AND TERMINATION POINT AND CONNECTIVITY NEEDS IN FREEZER / COOLER CONTROL UNIT.
4. DATA CABLE FOR TEMPORARY POINT OF SALES CASH REGISTER. COORDINATE WITH OWNER, ARCHITECT, AND CONSULTANT FOR ROUTING OF CABLES TO POINT OF SALE CASH REGISTER PRIOR TO INSTALLATION

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD


07/18/2025

ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY NEW/RENOVATION KITCHEN PLAN

SHEET NO.
j-T201




1 j-T202 TECHNOLOGY TEMPORARY KITCHEN FLOOR PLAN
1/4" = 1'-0"

**TECHNOLOGY FLOOR PLANS GENRAL NOTES:**

1. THE TECHNOLOGY REGION / WIRING BOUNDARIES ARE IDENTIFIED ON THE OVERALL SHEETS ONLY AND NOT ON THE ENLARGED SHEETS. CONTRACTOR SHALL REFER TO THE OVERALL SHEETS FOR ALL TECHNOLOGY REGIONS / WIRING BOUNDARIES.
2. ALL CONDUIT PATHWAYS, ROUGH-INS, BACKBOXES, FLOOR BOXES, CONDUIT SLEEVES, ETC. INDICATED ON THE TECHNOLOGY DRAWINGS ARE TO BE PROVIDED AND INSTALLED BY DIVISION 26.
3. ALL POWER INDICATED ON THE TECHNOLOGY DRAWINGS IS TO BE PROVIDED AND INSTALLED BY DIVISION 26.
4. CONTRACTOR SHALL RESTORE ALL PENETRATIONS PROVIDED THROUGH FIRE RATED WALLS/STRUCTURES FOR TECHNOLOGY CABLING BACK TO THE ORIGINAL RATING.
5. CONTRACTOR SHALL RESTORE ALL PENETRATIONS PROVIDED THROUGH NON-RATED WALLS/STRUCTURES FOR TECHNOLOGY CABLING FOR SOUND TO REDUCE NOISE TRAVELING THROUGH PENETRATIONS.
6. TECHNOLOGY CABLING SHALL BE ROUTED IN SEPARATE PATHWAYS IN J-HOOKS, CONDUITS, CONDUIT SLEEVES, CORES, ETC. THROUGHOUT THE ENTIRE PATHWAY. DIFFERENT MEDIA TYPES (DATA, VIDEO, SECURITY, ETC.) SHALL NOT SHARE THE SAME J-HOOK, CONDUIT, CONDUIT SLEEVE, CORE, ETC.
7. UNLESS NOTED OTHERWISE, ALL CONDUITS FOR TECHNOLOGY DEVICES SHALL ROUTE FROM THE DEVICE LOCATION AND TERMINATE ABOVE AN ACCESSIBLE CEILING (AN OPEN CEILING OR CLOUD TYPE CEILING IS NOT CONSIDERED AN ACCESSIBLE CEILING) IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF A MAIN CORRIDOR OR NEAREST MDF/IDF. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF / IDF ROOM TO MINIMIZE THE CABLE LENGTH ENSURING CABLE LENGTH DOES NOT EXCEED 275 FEET.
8. UNLESS NOTED OTHERWISE ALL CONDUITS SHALL BE HOMERUN FROM THE DEVICE LOCATION AND NO DAISY CHAINING OF DEVICES/ ROUGH-INS SHALL BE ALLOWED.
9. CONDUIT SEGMENTS SHALL BE NO MORE THAN 100-FEET IN LENGTH WITH NO MORE THAN THE EQUIVALENT OF (2) 90 DEGREE BENDS BETWEEN PULLING POINTS.
10. CONDUITS SHALL MAINTAIN A BEND RADIUS OF 6 TIMES THE DIAMETER OF THE CONDUIT FOR CONDUITS 2-INCHES OR SMALLER AND 10 TIMES THE DIAMETER OF THE CONDUIT FOR CONDUITS GREATER THAN 2-INCHES.
11. ALL CONDUITS SHALL HAVE A PULL STRING INSTALLED FOR PULLING OF CABLE. CLEARLY LABEL AS "PULL STRING" INDICATING OPPOSITE END LOCATION.
12. ALL SPARE CONDUITS OR CONDUITS FILLED WITH LESS THAN THE MAXIMUM ALLOWED FILL RATIO SHALL HAVE A PULL STRING INSTALLED AND LEFT FOR FUTURE PULLING OF CABLE. CLEARLY LABEL AS "PULL STRING" INDICATING OPPOSITE END LOCATION.
13. EQUIPMENT NOT RELATED TO THE SUPPORT OF THE TELECOMMUNICATIONS ROOM (E.G., PIPING, DUCTWORK, PNEUMATIC TUBING) SHALL NOT BE INSTALLED IN, PASS THROUGH, OR ENTER THE TELECOMMUNICATIONS ROOM.
14. ALL CONDUITS FOR TECHNOLOGY DEVICES SHALL ROUTE FROM THE DEVICE LOCATION AND TERMINATE ABOVE A LAY-IN TYPE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE A LAY- IN TYPE CEILING TO PREVENT THE CABLES FROM BEING EXPOSED, THE CONDUIT SHALL ROUTE TO THE NEAREST LAY-IN TYPE CEILING OFF A MAIN CORRIDOR OR NEAREST MDF/IDF. THE CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE MAIN CORRIDOR OR NEAREST MDF/IDF TO MINIMIZE THE CABLE LENGTH ENSURING THE CABLE LENGTH DOES NOT EXCEED 275 FEET. CONDUIT, CONNECTIONS, J-BOXES, SUSPENSION, ANCHORAGES, AND OTHER CONDUIT COMPONENTS EXPOSED TO VIEW IN PUBLIC SPACES SHALL BE ROUTED AND INSTALLED CAREFULLY TO MINIMIZE VISUAL IMPACT AND SHALL BE FULLY PAINTED TO MATCH UNLESS NOTED OTHERWISE.
15. CONDUIT(S) INSTALLED IN-SLAB OR UNDER-SLAB TO FLOOR BOXES, POKE-THURS, AND TO WORKAREA OUTLETS, ETC. SHALL BE INSTALLED WITH WET RATED CABLE(S).
16. NO GRID WIRE SHALL BE UTILIZED FOR SUPPORTS ONLY USE SOLID SUPPORTS (CLIPS, ALL-THREAD, ANCHORS, ETC.).

**TECHNOLOGY PLAN KEYED NOTES**

**NOT ALL KEYED BELOW APPLY TO THIS SHEET**

1. DATA CABLE FOR CONTRACTOR FURNISHED / CONTRACTOR INSTALLED MENU BOARD. REFERENCE ARCHITECTURAL AND FOOD SERVICE DRAWINGS FOR MOUNTING HEIGHT AND ADDITIONAL INFORMATION. BUILDING POWER ADJACENT TO DATA RECEPTACLE IS REQUIRED.
2. INDOOR / OUTDOOR RATED DATA CABLE FOR POINT OF SALE LOCATION. PROVIDE (1) 1-INCH CONDUIT FOR DATA TO THE WALL BEHIND POINT OF SALE LOCATION AND UP WALL TO ABOVE ACCESSIBLE CEILING. CONDUITS SHALL TERMINATE INSIDE A DOUBLE GANG BOX THAT IS SECURED TO THE POINT OF SALE LOCATION. REFER TO FOOD SERVICE / KITCHEN DRAWINGS FOR EXACT LOCATION AND CONDUIT ROUGH-IN REQUIREMENTS.
3. DATA CABLE FOR TEMPERATURE MONITORING OF FREEZER COOLER. REFER TO FOOD SERVICE / KITCHEN DRAWINGS FOR EXACT LOCATION AND CONDUIT ROUGH-IN REQUIREMENTS AND TERMINATION POINT AND CONNECTIVITY NEEDS IN FREEZER / COOLER CONTROL UNIT.
4. DATA CABLE FOR TEMPORARY POINT OF SALES CASH REGISTER. COORDINATE WITH OWNER, ARCHITECT, AND CONSULTANT FOR ROUTING OF CABLES TO POINT OF SALE CASH REGISTER PRIOR TO INSTALLATION

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzales Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD


07/18/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING


TECHNOLOGY TEMPORARY KITCHEN FLOOR PLAN

SHEET NO.
j-T202




UTILIZE THIS PANEL FOR NEW CABLING

1 j-T300 HIGHLANDS ES EXISTING RACK - TOP PORTION
N.T.S




UTILIZE THIS PANEL FOR NEW CABLING

2 j-T300 HIGHLANDS ES EXISTING RACK - BOTTOM PORTION
N.T.S

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

J

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD

07/18/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING


TECHNOLOGY ENLARGED VIEWS

SHEET NO.
j-T300

NOTE TO CONTRACTOR:

UNLESS OTHERWISE NOTED, LOW VOLTAGE CABLING SHALL BE INSTALLED WITHIN 6-INCHES OF THE CEILING AND ACCESSIBLE BY A TECHNICIAN ON A STANDARD A-FRAME LADDER.

CONTRACTOR SHALL MAINTAIN AT LEAST 6-INCHES OF SEPRATION BETWEEN CABLING BUNDLES AND MECHANICAL DUCTWORKS, EQUIPMENT, PIPIING OR OTHER SYSTEMS IN THE CEILING PLENUM.





KEYED NOTES:

1. J-HOOK WITH RETAINER CLIP ABOVE ACCESSIBLE CEILING (BY DIV 27).
2. DATA CABLE ABOVE ACCESSIBLE CEILING (BY DIV 27).
3. A/V CABLE ABOVE ACCESSIBLE CEILING (BY DIV 27).
4. SECURITY CABLE ABOVE ACCESSIBLE CEILING (BY DIV 28).
5. SPARE J-HOOK (BY DIV 27).

## 1 / T400 TYPICAL J-HOOK CABLE PATHWAY

SCALE: N.T.S.





KEYED NOTES:

1. SCHEDULED FLOOR OR DECK.
2. CONDUIT SLEEVE (BY DIV 26).
3. NYLON BUSHING (BY DIV 26).

## 2 / T400 TYPICAL CONDUIT SLEEVE THROUGH FLOOR OR DECK DETAIL

SCALE: N.T.S.





KEYED NOTES:

1. SCHEDULED WALL.
2. SCHEDULED CEILING.
3. CONDUIT SLEEVE (BY DIV 26).
4. NYLON BUSHING (BY DIV 26).

## 3 / T400 TYPICAL CONDUIT SLEEVE GOING THROUGH WALL

SCALE: N.T.S.





KEYED NOTES:

1. SCHEDULED WALL.
2. SCHEDULED CEILING.
3. SCHEDULED DECK ABOVE.
4. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX WITH DOUBLE GANG PLASTER RING (BY DIV 26).
5. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH. (BY DIV 26).

## 4 / T400 TYPICAL TECHNOLOGY CONDUIT ROUGH-IN

SCALE: N.T.S.





KEYED NOTES:

1. SCHEDULED STUD.
2. SCHEDULED WALL.
3. J-HOOK WITH RETAINER CLIP ABOVE ACCESSIBLE CEILING (BY DIV 27).
4. DATA CABLE ABOVE ACCESSIBLE CEILING (BY DIV 27).
5. 20 FOOT SERVICE LOOP ABOVE ACCESSIBLE CEILING NEATLY COILED AND SECURED TO J-HOOK (BY DIV 27).
6. SURFACE MOUNT BOX ABOVE ACCESSIBLE CEILING SECURED TO BUILDING STRUCTURE (BY DIV 27).
7. DATA INSERT (BY DIV 27).

## 5 / T400 TYPICAL ABOVE CEILING SINGLE DATA OUTLET (WALL MOUNTED)

SCALE: N.T.S.





KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH PHONE STUDS (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. CABLE AS SPECIFIED (BY DIV 27).

## 6 / T400 TYPICAL WALL PHONE OUTLET CONFIGURATION

SCALE: N.T.S.





KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH DESIGNATION IN WINDOW (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. CABLE AS SPECIFIED (BY DIV 27).
7. ELECTRICAL RECEPTACLE, GANG BOX AND CONDUIT SHOWN FOR REFERENCE ONLY (REFER TO DIV 26).

## 7 / T400 TYPICAL DUAL DATA OUTLET CONFIGURATION

SCALE: N.T.S.





KEYED NOTES:

1. 4 11/16-INCH X 4 11/16-INCH X 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. DOUBLE GANG PLASTER RING (BY DIV 26).
4. SURFACE MOUNT BOX INSIDE THE 4 11/16-INCH X 4 11/16-INCH X 2 1/8-INCH DOUBLE GANG BOX (BY DIV 27).
5. RJ-45 INSERT (BY DIV 27).

## 8 / T400 TYPICAL WALL-MOUNTED WIRELESS ACCESS POINT

SCALE: N.T.S.




KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH DESIGNATION IN WINDOW (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. BLANK INSERT (BY DIV 27).
7. CABLE AS SPECIFIED (BY DIV 27).
8. ELECTRICAL RECEPTACLE, GANG BOX AND CONDUIT SHOWN FOR REFERENCE ONLY (REFER TO DIV 26).

## 9 / T400 TYPICAL THREE DATA OUTLET CONFIGURATION

SCALE: N.T.S.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

J

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzales Jr
BICSI ID # 364970
EXPIRES12-31-25
RCDD


07/18/2025


MVA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY TYPICAL DETAILS

SHEET NO.
j-T400





KEYED NOTES:

1. ALL THREAD TO BUILDING STRUCTURE (BY DIV. 27)
2. SCHEDULING CEILING
3. IN-PLENUM CEILING BRACKET PN 49223-CBC ATTACHED TO ALL THREAD (BY DIV. 27)
4. SURFACE MOUNT BOX ABOVE ACCESSIBLE CEILING SECURED TO BRACKET (BY DIV. 27)
5. DATA CABLE (BY DIV. 27)
6. DATA INSERT (BY DIV. 27)

1 / T401 TYPICAL ABOVE CEILING DATA OUTLET

SCALE: N.T.S.





KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH DESIGNATION IN WINDOW (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. CABLE AS SPECIFIED (BY DIV 27).
7. ELECTRICAL RECEPTACLE, GANG BOX AND CONDUIT SHOWN FOR REFERENCE ONLY (REFER TO DIV 26). ELECTRICAL RECEPTACLE TO BE INSTALLED AT 36" A.F.F. AND ADJACENT TO COW / SECONDARY TEACHING OUTLET LOCATION.

2 / T401 TYPICAL COW / SECONDARY TEACHER'S DATA OUTLET CONFIGURATION

SCALE: N.T.S.





KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH DESIGNATION IN WINDOW (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. BLANK INSERT (BY DIV 27).
7. CABLE AS SPECIFIED (BY DIV 27).
8. ELECTRICAL RECEPTACLE, GANG BOX AND CONDUIT SHOWN FOR REFERENCE ONLY (REFER TO DIV 26).

3 / T401 TYPICAL THREE DATA OUTLET CONFIGURATION

SCALE: N.T.S.




KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH DESIGNATION IN WINDOW (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. CABLE AS SPECIFIED (BY DIV 27).
7. ELECTRICAL RECEPTACLE, GANG BOX AND CONDUIT SHOWN FOR REFERENCE ONLY (REFER TO DIV 26).

4 / T401 TYPICAL FOUR DATA OUTLET CONFIGURATION


SCALE: N.T.S.

| TBB/GE CONDUCTOR SIZING | |
|---|---|
| LENGTH IN LINEAR M (FT) | SIZE (AWG) |
| LESS THAN 4 (13) | 6 |
| 4 - 6 (14-20) | 4 |
| 6 - 8 (21 - 26) | 3 |
| 8 - 10 (27 - 33) | 2 |
| 10 - 13 (34 - 41) | 1 |
| 13 - 16 (42 - 52) | 1/0 |
| 16 - 20 (53 - 66) | 2/0 |
| 20 - 26 (67 - 84) | 3/0 |
| 26 - 32 (85 - 105) | 4/0 |
| 32 - 38 (106 - 125) | 250 kcmil |
| 38 - 46 (126 - 150) | 300 kcmil |
| 46 - 53 (151 - 175) | 350 kcmil |
| 53 - 76 (176 - 250) | 500 kcmil |
| 76 - 91 (251 - 300) | 600 kcmil |
| GREATER THAN 91 (301) | 750 kcmil |

ROUTE THE TBB TO EACH TGB IN AS STRAIGHT A PATH AS POSSIBLE. THE TBB SHOULD BE INSTALLED AS A CONTINUOUS CONDUCTOR, AVOIDING SPLICES WHERE POSSIBLE.

5 / T401 TBB CONDUCTOR SIZING

SCALE: N.T.S.





1. TELECOMMUNICATIONS MAIN GROUNDING BUS BAR (PBB)(BY DIV. 27)
2. TELECOMMUNICATIONS GROUNDING BUS BAR (SBB)(BY DIV 27)
3. TELECOMMUNICATIONS BONDING CONDUCTOR (TBC). REFER TO CONDUCTOR SIZING CHART FOR EXACT SIZE REQUIREMENTS (BY DIV 27)
4. CONNECT TO GROUNDED BUILDING STEEL WHEN EXPOSED IN ROOM.
5. TELECOMMUNICATIONS BONDING BACKBONE (TBB). REFER TO CONDUCTOR SIZING CHART FOR EXACT SIZE REQUIREMENTS (BY DIV 26)
6. TELECOMMUNICATIONS BONDING CONDUCTOR (TBC). BY ELECTRICAL CONTRACTOR.REFER TO CONDUCTOR SIZING CHART FOR EXACT SIZE REQUIREMENTS.
7. GROUNDING EQUALIZER CONDUCTOR (GEC)(BY DIV 26)
8. BOUND WITH GROUDING COLLARS TO EACH CONTINUOUS CONDUIT THAT ENTERS THE TELECOM ROOM. (BY DIV 26).
9. BOND TO EACH ACCESS CONTROL PANEL AND OTHER SECURITY PANELS IN HE TELECOM ROOM. (BY DIV 27)

6 / T401 TYPICAL GROUNDING DIAGRAM

SCALE: N.T.S.

System No. W-L-3218
F Ratings - 1, 2, 3 and 4 Hr (See Items 1 and 3)
T Ratings - 3/4 and 1 Hr (See Item 3)
L Rating At Ambient - Less Than 1, 1.3, 4 or 7 CFM (See Item 3)
L Rating At 400 F - Less Than 1, 2 or 3 CFM (See Item 3)




Section A-A

1. Wall Assembly - The 1, 2, 3 or 4 hr fire-rated gypsum board/stud wall assembly shall be constructed of the materials and in the manner described within the individual U300, U400 or V400 Series Wall and Partition Designs in the UL Fire Resistance Directory and shall incorporate the following construction features:
   A. Studs - Wall framing shall consist of either wood studs or steel channel studs. Wood studs to consist of nom 2 by 4 in. (51 by 102 mm) lumber spaced max 16 in. (406 mm) OC. Steel studs to be min 3-1/2 in. (89 mm) wide and spaced max 24 in. (610 mm) OC.
   B. Gypsum Board* - Thickness, type, number of layers and fasteners as specified in the individual Wall and Partition Design. Opening in gypsum board to be max 1/4 in. (6 mm) larger then width and height dimensions of firestop device(s).

   The hourly F Rating of the firestop system is dependent upon the hourly rating of the wall in which it is installed.
2. Firestop Device* - One, two, three, four or seven firestop device modules ganged together. Each firestop device module consists of a 3 by 3 by 10-1/2 in. (76 by 76 by 267 mm) long galv steel tube with an intumescent material lining. Firestop device modules to be installed in accordance with the accompanying installation instructions. The space between the firestop device module(s) and the periphery of the opening shall be min 0 in. ( 0 mm, point contact) to max 1/8 in. (3.2 mm). In round openings, the space between the firestop device and the periphery of the opening shall be min 0 in. (point contact) to max 1/2 in. (13 mm). Firestop device module(s) secured in place by means of steel wall plates installed with gasketing material supplied with product. Steel wall plates installed on both sides of wall and secured to each device by means of steel set screws provided with device. Each four- and seven-gang steel wall plate shall be fastened to the studs with steel screws sized to extend through the gypsum board layers and penetrate 1/2 in. (13 mm) into the framing member. Each firestop device module is to be installed with ends projecting an equal distance beyond each surface of the wall assembly.

   As an alternate, the four- and seven-gang steel wall plates may be installed directly against the studs for walls having 16 and 24 in. (406 and 610 mm) center-to-center stud spacing, respectively, prior to installation of the gypsum board layers. The steel wall plates shall be secured to the stud by means of steel screws. After installation of the steel wall plates and firestop device modules, the gypsum board shall be installed as specified in the individual U300 or U400 Design with a maximum 1/8 in. (3.2 mm) gap between the firestop device module and the cutout in the gypsum board. Gap between the firestop device module and the cutout in the gypsum board may be filled with gypsum joint compound or fill material (Item 4).

   SPECIFIED TECHNOLOGIES INC - EZ PATH Series 33 Fire Rated Pathway

2A. Firestop Device* - Extension Module - (Optional, Not Shown) - Module attached to ends of 3 by 3 by 10-1/2 in. (76 by 76 by 267 mm) long firestop device (Item 3) to increase its length to facilitate installation in thicker walls. Each module consists of a 3 by 3 by 6 in. (76 by 76 by 152 mm) long galv steel tube with an intumescent material lining. Extension module to be installed in accordance with the accompanying installation instructions. When module is used, firestop device (Item 2) and extension module(s) secured in place by means of steel wall plates installed with gasketing material supplied with product. Steel wall plates installed on both sides of wall and secured to each device or extension module(s) by means of steel set screws provided with wall plates. Firestop device and extension module(s) assembly to be installed with ends projecting an equal distance beyond each surface of the wall assembly.

   SPECIFIED TECHNOLOGIES INC - EZ PATH Extension

3. Cables - Within the loading area for each firestop device module, the cables may represent a 0 to 100 percent visual fill. Cable fill to be distributed at a uniform height across the width of the firestop device module. Cables to be rigidly supported on both sides of the wall assembly. Any combination of the following types of cables may be used:
   A. Max 400 pair No. 24 AWG (or smaller) copper conductor telecommunication cable with polyvinyl chloride (PVC) jacketing and insulation.
   B. Max 350 kcmil single copper conductor power cable with XLPE jacket and insulation
   C. Max 7/C No. 12 AWG copper conductor control cable with PVC or XLPE jacket and insulation.
   D. Max 3/C No. 10 AWG metal clad or armored cable with steel or aluminum jacket.
   E. Max 3/C No. 8 AWG NM cable (Romex) with PVC insulation and jacket.
   F. Max four pair No. 22 AWG (or smaller) copper conductor data cable with PVC or plenum rated jacketing and insulation.
   G. Max RG/U coaxial cable with fluorinated ethylene insulation and jacketing.
   H. Fiber optic cable with PVC or polyethylene (PE) jacket and insulation having a max diam of 5/8 in. (16 mm).
   I. Optical Fiber Raceway+ - Max 1-1/2 in. (38 mm) diam (or smaller) optical fiber raceway ("innerduct") formed of either PVC or polyvinylidene fluoride (PVDF) with optical fiber cable fill. Raceways installed in accordance with the National Electrical Code (NFPA 70).

   When the hourly rating of the wall assembly is 1 hr, the T Rating is 3/4 hr. When the hourly fire rating of the wall assembly is greater than 1 hr, the T Rating is 3/4 hr when Item 3A, 3B, 3C, 3D or 3E is used. Otherwise the T Rating is 1 hr. When Item 3A, 3B, 3C, 3D or 3E is used, the maximum F Rating is 2 hr. When max 200 pair No. 24 AWG telecommunication cable is used or when Item 3F, 3G, 3H or 3I is used, the maximum F Rating is 4 hr.

   The L Rating for each empty firestop device module is less than 1 cfm at ambient and at 400F. When Item 3A is used, the L Rating for each firestop device module with 100 percent visual fill is 4 cfm at ambient and 3 cfm at 400F. When Item 3F is used, the L Rating for each firestop device module with 100 percent visual fill is 1.3 cfm at ambient and 1 cfm at 400F. When Item 3G or 3H is used, the L Rating for each firestop device module with 100 percent visual fill is 7 cfm at ambient and 2 cfm at 400F.
4. Fill, Void or Cavity Material* - Sealant or Putty - (Not Shown) - As an alternate to gypsum joint compound, the gap between the firestop device module and the cutout in the gypsum board may be sealed with fill material on each side of the wall assembly when four- and seven-gang steel wall plates are installed directly against the wood or steel studs.

   SPECIFIED TECHNOLOGIES INC - SpecSeal Series SSS Sealant, SpecSeal LCI Sealant, SpecSeal Putty

   *Bearing the UL Classification Mark

7 / T401 TYPICAL STI EZ-PATH SLEEVE DETAIL

SCALE: N.T.S.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

J

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD


07/18/2025



ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY TYPICAL DETAILS

SHEET NO.
j-T401













1 T500 TYPICAL HORIZONTAL DATA CABLE LABELING SCHEME

SCALE: N.T.S.






2 T500 TYPICAL FIBER BACKBONE LABELING SCHEME

SCALE: N.T.S.




3 T500 TYPICAL COPPER BACKBONE LABELING SCHEME

SCALE: N.T.S.




4 T500 ABOVE ASSESSIBLE CEILING LABELING SCHEME

SCALE: N.T.S.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

J

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HIGHLANDS ELEMENTARY SCHOOL
2022 COLONIST PARK DRIVE
SUGAR LAND, TX 77478

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD

07/18/2025

MWA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY TYPICAL LABELING SCHEME

SHEET NO.
j-T500

## AUDIO/VISUAL MULTIMEDIA LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| A## V## | WALL AV ROUGH-IN DETAIL |
| A## V## | CEILING AV ROUGH-IN DETAIL |
| A## V## | FLOOR AV ROUGH-IN DETAIL |
| IWB IWB | INTERACTIVE WHITE BOARD - WALL - CEILING |
| PJ PJ | MULTIMEDIA PROJECTOR |
| FP# FP# | MULTIMEDIA FLAT PANEL DISPLAY |
| S S | LOUDSPEAKER, WALL MOUNTED AND CEILING MOUNTED RESPECTIVELY - # INDICATES TYPE |
| CP# | CONTROL PANEL |
| TP# | TOUCH PANEL |
| M | MICROPHONE, CEILING MOUNTED - # INDICATES TYPE |
| VC | VOLUME CONTROL |
| WB | WALL BOX ENCLOSURE |
| D1 A1 | D1 = DIGITAL SINGLE SIDED CLOCK / A1 = ANALOG SINGLE SIDED CLOCK |
| D2 A2 | D2 = DIGITAL DOUBLE SIDED CLOCK / A2 = ANALOG DOUBLE SIDED CLOCK |
| ENC | CEILING AV ENCLOSURE |
| C C | PRESENTATION CAMERA - CEILING - WALL MOUNTED |

## PREMISE SECURITY LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| CR | CARD READER |
| CR M | CARD READER MULLION |
| KP | INTRUSION DETECTION KEYPAD |
| IC | INTERCOM (1 DATA CABLE) |
| IC MS | INTERCOM MASTER STATION (1 DATA CABLE) |
| PB | PANIC/DURESS BUTTON |
| LD | LOCK DOWN BUTTON |
| MD | MOTION DETECTOR |
| GB | ACCOUSTICAL GLASS BREAK SENSOR |
| BM | BIOMETRIC READER |
| RX | REQUEST TO EXIT - SURFACE PIR |
| KS | KEY SWITCH |
| LA | LOCAL ALARM SOUNDER |
| RG | RED/GREEN INDICATOR LIGHT |
| DB | DOORBELL |
| DH | MAGNETIC DOOR HOLD |
| DR | DOOR RELEASE |
| RX | REQUEST TO EXIT - INTEGRAL TO DOOR HARDWARE |
| DC | DOOR CONTACT / MONITOR |
| ES EL EH | ELECTRIFIED STRIKE - ELECTRIFIED LATCH - ELECTRIFIED HARDWARE (REFER TO SCHEDULES) |
| C C | STANDARD IP SURVEILLANCE CAMERA, (1) CABLE |
| C C C | 180° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° FISHEYE LENS CAMERA |
| IR | IR ILLUMINATOR |

## STRUCTURED CABLING LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF DATA CABLE(S)/JACK(S) |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) |
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| W | WALL MOUNT PHONE (1 CABLE/JACK) |
| W | WALL MOUNT PHONE, SURFACE MOUNT (1 CABLE/JACK) |
| # | FLOOR MOUNTED OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| #/# | FLOOR MOUNTED OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| # | CEILING MOUNTED DATA OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) |
| AP# | CEILING MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| AP# | WALL MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| | CABLING SLEEVE(S) |
| | TYPICAL LADDER RACK |
| | TYPICAL CABLE TRAY, BASKET STYLE |

## GENERAL ANNOTATION LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| MER | MAIN EQUIPMENT ROOM |
| TR | TELECOMMUNICATION ROOM |
| MDF | MAIN DISTRIBUTION FRAME |
| IDF | INTERMEDIATE DISTRIBUTION FRAME |
| ETR | EXISTING TO REMAIN |
| PBO | PROVIDED BY OTHERS |
| AFF | ABOVE FINISHED FLOOR |
| AFG | ABOVE FINISHED GRADE |
| AC | ABOVE COUNTER |
| EC | ELECTRICAL CONTRACTOR |
| PSC | PREMISE SECURITY CONTRACTOR |
| SCC | STRUCTURAL CABLING CONTRACTOR |
| AVC | AV/MULTIMEDIA CONTRACTOR |
| UNO | UNLESS NOTED OTHERWISE |
| ACS | ACCESS CONTROL SYSTEM |
| VSS | VIDEO SURVEILLANCE SYSTEM |

## TECHNOLOGY - GENERAL NOTES

1. EACH KEYNOTE MAY NOT BE UTILIZED ON EVERY SHEET.
2. ALL CONDUIT MEASUREMENTS REFER TO STANDARD CONDUIT TRADE SIZES.
3. ALL CABLES SHALL BE CONCEALED.
4. EACH CONTRACTOR SHALL PROVIDE AND INSTALL ALL NECESSARY SLEEVES, WHETHER OR NOT SPECIFICALLY NOTED ON PROJECT DRAWINGS. ALL SLEEVES SHALL BE 2" UNLESS NOTED OTHERWISE ON THE DRAWINGS. CABLE FILL PERCENTAGE SHALL COMPLY WITH NEC.
5. DEVICE LOCATIONS ARE APPROXIMATE. CONTRACTOR SHALL REVIEW CONDITIONS AND COORDINATE WITH OTHER TRADES AS NECESSARY FOR EXACT PLACEMENT.

## TECHNOLOGY SYMBOLS LEGEND

NOT ALL SYMBOLS ARE USED

- AV WALL ROUGH-IN WITH DATA
- KEYNOTE
- Proposed Camera Direction
  SURVEILLANCE CAMERA
  Camera Schedule Number (Floor #-Camera #)
  Camera (N)ew, (E)xisting Rough-in, (D)emo
- Proposed Camera Direction
  PTZ CAMERA
  PTZ
- Proposed Camera Direction
  FIXED SURVEILLANCE CAMERA
- 360°/MULTI-SENSOR FIXED SURVEILLANCE CAMERA OR FISHEYE LENS CAMERA
- Approximate view of lens
  Lens View Angle
  360°/MULTI-SENSOR FIXED SURVEILLANCE CAMERA OR FISHEYE LENS CAMERA
  Lens size
- MICROPHONE WITH AUDIO LINKED TO CAMERA
- CARD READER LINKED TO CAMERA
- SYMBOL TAG
  (#) = DIFFERENT TYPES OF CARD READERS:
  M = MULLION
  W = WIRELESS (Proprietary)
  Wi = Wi-Fi (802.11)
  POE = POWER OVER ETHERNET
- SYMBOL TAG
  (#) = DIFFERENT TYPES OF CARD READERS:
  TS = TOUCHSCREEN
  PU = PUSH BUTTON
- TOP = DETAIL NUMBER
  DETAIL REFERENCE
  BOTTOM = SHEET NUMBER
- NORTH ARROW
- SHEET NUMBER
  SECTION MARKER
  DETAIL NUMBER
- DIRECTION OF ELEVATION
  ELEVATION MARKER
  SHEET NUMBER
  DETAIL NUMBER
- DIRECTION OF ELEVATION
  SHEET NUMBER
  DIRECTION OF ELEVATION
  DETAIL NUMBER
- BAR IS ONE INCH ON ORIGINAL DRAWING. IF NOT ONE INCH ON THIS DRAWING ADJUST SCALES ACCORDINGLY

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

j

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Highlands Elementary School
2022 Colonist Park Dr, Sugar Land, TX 77478

SEAL

BICSI REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 258557
EXPIRES 10-31-27
RCDD

07-18-25

MVA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY - TITLE SHEET

j-TN000

**DEMO KEYNOTES**

1. REMOVE, AND PROTECT DURING CONSTRUCTION, INSTALL IN EXISTING LOCATION AFTER NEW ACT GRID IS IN PLACE.
2. DEVICES IN ACT ARE TO BE REMOVED AND PROTECTED DURING CONSTRUCTION AND REINSTALLED IN THE SAME LOCATION AFTER THE NEW CEILING GRID IS IN PLACE. DECIVES INCLUDE: SPEAKERS, ACCESS POINTS AND INTRUSION MOTION DETECTORS.
3. EXISTING CARD READER, DOOR CONTACT, & REX (REQUEST TO EXIT) TO BE DEMOLISHED, REMOVE DEVICES AND PROTECT WIREING.




1 HIGHLAND - DEMO PLAN
SCALE: 3/16" = 1'-0"

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

j

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Highlands Elementary School
2022 Colonist Park Dr, Sugar Land, TX 77478


SEAL

BICSI REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256557
EXPIRES 12-31-27
07-18-25


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - HIGHLAND ES - DEMO

j-TN.001




1 BACKGROUND 1 (HIGHLAND)
SCALE: 1" = 20'-0"

## TECHNOLOGY KEYNOTES

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

j

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Highlands Elementary School
2022 Colonist Park Dr, Sugar Land, TX 77478

SEAL




07-18-25

MWA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING
AND
PERMITTING


TECHNOLOGY - HIGHLAND ES - OVERALL

j-TN.100

TRUENORTH A PMY COMPANY

## TECHNOLOGY KEYNOTES

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.




1 HIGHLAND - KITCHEN PLAN
SCALE: 3/16" = 1'-0"

TRUENORTH A PWY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

j

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Highlands Elementary School
2022 Colonist Park Dr, Sugar Land, TX 77478

SEAL

BICSI REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256557
EXPIRES 12-31-27

07-18-25


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - HIGHLAND ES - KITCHEN


j-TN.101

**GENERAL NOTE**


1. FACE PLATE DETAIL FOR OUTLET CONFIGURATION PURPOSES ONLY. CONTRACTOR TO SELECT TYPE OF FACE PLATE TO MATCH CONNECTIVITY HARDWARE, FLOOR BOX AND/OR MODULAR FURNITURE OPENING.





## 1 DATA ROUGH-IN DETAILS
SCALE: NS





## 2 TYPICAL CABLING SLEEVE
SCALE: NTS





## 3 PANDUIT J-HOOK DETAIL
SCALE: NTS





## 4 LABELING & CABLING SCHEMES
SCALE: NTS





## 5 CABLE PATHWAY CROSS SECTION
SCALE: NTS




## 6 DROPPED CEILING MOUNTING DETAIL
SCALE: NS




## 7 I-JOIST MOUNTING DETAIL
SCALE: NS




## 8 BAR JOIST MOUNTING DETAIL
SCALE: NS

| CAMERA TYPE | MANUFACTURER | MODEL NUMBER | GENERAL DESCRIPTION |
|---|---|---|---|
| C1 | iPro | WV-S8574L | 4x4K (33MP) EXTERIOR MULTI-SENSOR - PARKING LOTS, STADIUM |
| C2 | iPro | WV-S8544L | 4x4MP (16MP) EXTERIOR MULTI-SENSOR - BUILDING PERIMETER |
| C3 | iPro | WV-S25500-V3LN | 5MP EXTERIOR VANDAL DOME |
| C4 | iPro | WV-S22500-V3L | 5MP INTERIOR VANDAL DOME - CORR., COMMON, SPED |
| C5 | iPro | WV-S4156A | 5MP 360 (FISHEYE) - STAIRWELLS |

## 9 CAMERA SCHEDULE
SCALE: NTS

| Symbol | Purpose | Size | Mount | Backbox | Notes |
|---|---|---|---|---|---|
| FP1 | Digital Signage/Menu Boards | +49" | Ceiling Pole | N/A | Data and Power Outlets on ceiling |

## 10 DISPLAY SCHEDULE
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

j

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Highlands Elementary School
2022 Colonist Park Dr, Sugar Land, TX 77478

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256687
EXPIRES 12-31-27


07-18-25

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - HIGHLAND ES - DETAILS
j-TN.500

GENERAL NOTES:


1. REFER TO SECURITY SCHEDULE AND WRITTEN SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
2. ALL MOUNTING DETAILS ARE REFERENCE FOR ALL FIXED DOME, 180°, 360°, PTZ, AND "BULLET/BOX" CAMERAS.





1 TYPICAL CAMERA INSTALLATION SECTION DETAIL
SCALE: NS




6 WALL MOUNTED CAMERA DETAIL
SCALE: NS




4 TILE BRIDGE DETAIL
SCALE: NS





5 CEILING MOUNTED CAMERA DETAIL
SCALE: NS


ACCESS CONROL DETAILS AND GENERAL NOTES:

1. CONDUIT ROUGH-IN IS A GUIDE FOR WHAT WILL BE REQUIRED FOR EACH DOOR. AS DOOR COMPONENTS CHANGE, EXACT CONDUIT LOCATION WILL ALSO NEED TO BE ADJUSTED.


2. PROTECT EXISTING-TO-REMAIN ACCESS CONTROL DEVICES AND CABLE THROUGHOUT RENOVATION WORK. IF CABLE AND/OR DEVICES ARE DAMAGED, SECURITY CONTRACTOR TO REPLACE WITH NEW.




1 ACCESS CONTROL - WIRING DETAIL - EXIT DEVICE W/ BUILT-IN REX
SCALE: NTS




2 ACCESS CONTROL - STEEL/HOLLOW METAL DOOR.
SCALE: NTS




KP PB LD

3 ROUGH-IN DETAILS: KP, PB, LD
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

j

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Highlands Elementary School
2022 Colonist Park Dr, Sugar Land, TX 77478

SEAL





07-18-25


MVA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING
AND
PERMITTING

TECHNOLOGY - HIGHLAND ES - SECURITY DETAILS

j-TN.600




6 CEILING MOUNT DISPLAY - A/V ROUGH-IN DETAIL
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

j

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Highlands Elementary School
2022 Colonist Park Dr, Sugar Land, TX 77478

SEAL

BICSI REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256657
EXPIRES 12-31-27
RCDD

07-18-25

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - HIGHLAND ES - AV DETAILS
j-TN.700

# FBISD BP013 KITCHEN RENOVATIONS ES

## HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD, MISSOURI CITY, TX 77489

FORT BEND INDEPENDENT SCHOOL DISTRICT

## FORT BEND INDEPENDENT SCHOOL DISTRICT

### ADMINISTRATION

| | |
|---|---|
| DR. MARCELL SMITH | SUPERINTENDENT OF FBISD |
| DR. ANDRIA SCHUR, Ed.D. | CHIEF OF SCHOOLS |

### BOARD OF TRUSTEES

| | |
|---|---|
| KRISTIN K. TASSIN | PRESIDENT |
| RICK GARCIA | VICE PRESIDENT |
| DAVID HAMILTON | SECRETARY |
| ANGIE HANAN | BOARD MEMBER |
| ADAM SCHOOF | BOARD MEMBER |
| DR. SHIRLEY ROSE-GILLIAM | BOARD MEMBER |
| SONYA JONES | BOARD MEMBER |

### PROJECT DESIGN TEAM


PROGRAM MANAGEMENT
FBISD 2023 Bond Team
2323 Texas Parkway
Missouri City, TX 77489
Phone Number: 281-327-5481

ARCHITECT
MWA Architects
11767 Katy Freeway, Suite 430
Houston, Texas 77079
Phone Number: 713-782-8188

FOOD SERVICE
Food Design Professionals
26215 Oak Ridge Drive
The Woodlands, Texas 77380
Phone Number: 281-350-2323

MEP ENGINEERS
Stanton Engineering Group
1300 W. Sam Houston Pkwy South, Suite 121
Houston, Texas 77042
Phone Number: 713-300-9292

STRUCTURAL ENGINEER
Stanley Spurling & Hamilton
3301 Edloe Street, Suite 200
Houston, Texas 77027
Phone Number: 713-776-9433


| Sheet List Table | |
|---|---|
| Sheet Number | Sheet Title |
| School: k-Hunters Glen ES | |
| k-A.000 | COVER AND INDEX |
| k-A00-01 | GENERAL NOTES AND ABBREVIATIONS |
| k-D.101 | DEMO PLAN |
| k-D.101-2 | DEMO PLAN PHOTOS |
| k-D.101-3 | DEMO PLAN PHOTOS |
| k-QF1 | FS DEMO PLAN |
| k-ED.100 | ELECTRICAL DEMOLITION AND TEMPORARY KITCHEN PLAN |
| k-PD1.01 | PLUMBING DEMOLITION FLOOR PLAN |
| k-TD201 | TECHNOLOGY DEMOLITION FLOOR PLAN |
| k-A.101 | SITE PLAN |
| k-A.201 | OVERALL FLOOR PLAN |
| k-A.300 | SLAB DIMENSION CONTROL PLAN |
| k-A.301 | KITCHEN PLAN |
| k-A.302 | TEMPORARY KITCHEN LAYOUT |
| k-A.401 | REFLECTED CEILING PLAN |
| k-A.501 | FINISH FLOOR PLAN |
| k-A.502 | PARTITION SCHEDULE |
| k C1.0 | GRADING AND PAVING PLAN |
| k-QF0.0 | FS GENERAL COORDINATION NOTES |
| k-QF1.0 | FS EQUIPMENT PLAN |
| k-QF1.1 | FS FACILITY MODEL |
| K-QF1.2 | FS EQUIPMENT MODEL |
| k-QF1.3 | FS SPECIAL CONDITIONS & MECHANICAL PLAN |
| k-QF1.4 | FS PLUMBING PLAN |
| k-QF1.5 | FS ELECTRICAL PLAN |
| k-QF1.6 | FS CONDENSING UNITS |
| k-QFS1.7 | FS WALK-INS |
| k-QF2.0 | FS TEMPORARY SERVING |
| k-QF3.1 | FS ELEVATIONS |
| k-QF4.1 | FS SECTIONS AND DETAILS |
| k-QF4.2 | FS DETAILS |
| k-QF4.3 | FS DETAILS |
| k-M1.01 | MECHANICAL PLANS |
| k-M2.01 | KITCHEN MECHANICAL DETAILS |
| k-M2.02 | MECHANICAL DETAILS (CONT.) |
| E.000 | ELECTRICAL AND FIRE ALARM SCHEDULES |
| E.001 | ELECTRICALAND FIRE ALARM NOTES |
| E.010 | ELECTRICAL DEVICE DETAILS |
| E.011 | ELECTRICAL DETAILS |
| E.012 | ELECTRICAL DETAILS |
| E.013 | ELECTRICAL KITCHEN DETAILS |
| E.060 | LIGHTING SCHEDULES |
| k-E.100 | LIGHTING FLOOR PLANS |
| k-E.200 | ELECTRICAL FLOOR PLANS |
| k-E.300 | FIRE ALARM FLOOR PLANS |
| k-E.400 | ELECTRICAL SCHEMATIC |
| k-P1.01 | PLUMBING FLOOR PLAN |
| k-P1.02 | PLUMBING FLOOR PLAN TEMPORARY KITCHEN |
| k-T000 | TECHNOLOGY SYMBOLS & LEGEND |
| k-T200 | TECHNOLOGY COMPOSITE FLOOR |
| k-T201 | TECHNOLOGY NEW_RENOVATION KITCHEN PLAN |
| k-T300 | TECHNOLOGY TEMPORARY KITCHEN PLAN |
| k-T202 | TECHNOLOGY ENLARGED VIEWS |
| k-T400 | TECHNOLOGY TYPICAL DETAILS |
| k-T401 | TECHNOLOGY TYPICAL DETAILS |
| k-T500 | TECHNOLOGY TYPICAL DETAILS |
| k-TN-000 | TECHNOLOGY - INDEX SHEET |
| k-TN-001 | TECHNOLOGY - DEMO |
| k-TN-100 | TECHNOLOGY - OVERALL |
| k-TN-101 | TECHNOLOGY - KITCHEN |
| k-TN-500 | TECHNOLOGY - DETAILS |
| k-TN-600 | TTECHNOLOGY - SECURITY DETAILS |
| k-TN-700 | TECHNOLOGY - AV DETAILS |

REGISTERED ARCHITECT
MICHAEL A. MAGNER
22651
STATE OF TEXAS

18 JULY 2025

ISSUED FOR PERMIT AND BIDDING - JULY 18, 2025

k

PART 1 - GENERAL

1.1 GENERAL DEMOLITION NOTES

A. VERIFY EXISTING SITE AND BUILDING CONDITIONS IN FIELD PRIOR TO BIDDING. NOTIFY ARCHITECT OF ANY DISCREPANCIES PRIOR TO BIDDING.

B. CONTRACTOR SHALL COORDINATE WITH OWNER THE SALVAGE OF ITEMS, FURNITURE AND EQUIPMENT INDICATED TO BE REMOVED.

C. CLAIMS FOR ADDITIONAL COST OR TIME DUE TO EXISTING CONDITIONS THAT COULD HAVE BEEN REASONABLY ANTICIPATED DURING A SITE VISIT BY THE CONTRACTOR PRIOR TO BIDDING WILL NOT BE APPROVED.

D. PROTECT EXISTING FINISHES SHOWN TO REMAIN DURING CONSTRUCTION TO PREVENT DAMAGE. REPAIR OR REPLACE DAMAGED MATERIALS AND FINISHES TO MATCH EXISTING AT NO ADDITIONAL COST TO FORT BEND ISD (OWNER).

E. EXISTING AREAS REQUIRING MINOR DEMOLITION OR REPAIR FOR EXECUTION OF WORK SHALL BE REPAIRED TO MATCH EXISTING ADJACENT MATERIALS, UNLESS NOTED OTHERWISE.

F. DO NOT DAMAGE CASEWORK AND EQUIPMENT NOT DESIGNATED TO BE REMOVED OR RELOCATED.EXISTING CASEWORK SHALL REMAIN THE PROPERTY OF THE OWNER.

G. CONTRACTOR TO VERIFY LOCATION OF ELEC. SWITCHES, OUTLETS, GRILLES, CLEAN-OUTS, COVER PLATES, ACCESS DOORS, AND OTHER EQUIPMENT AND DEVICES THAT MAY CONFLICT WITH THE RENOVATION AND NEW CONSTRUCTION OF WALLS, FLOORS, AND CEILINGS PRIOR TO COMMENCEMENT OF WORK. CONTRACTOR SHALL LIKEWISE CONFIRM THAT ELECTRICAL CONDUIT ROUTING SHALL BE CONCEALED WITHIN WALLS. NOTIFY ARCHITECT IF WALL THICKNESS WILL NOT ALLOW FOR CONCEALMENT.

H. REMOVE ANY EXISTING CORNER GUARDS IN THE KITCHEN AREA.

I. PRIOR TO EXECUTION OF DEMOLITION WORK, SCHEDULE A WALK-THROUGH WITH OWNER AND ARCHITECT TO CONFIRM SCOPE OF WORK AND TO REVIEW EXISTING CONDITIONS.

J. EXISTING FLOOR FINISHES AND ACOUSTIC CEILING TILE TO BE REMOVED THROUGHOUT.

K. REFER TO MEP DRAWINGS FOR DEMOLITION AND ALTERATION OF UTILITIES.

L. AT ALL EXISTING WALLS REQUIRING DEMOLITION TO INSTALL NEW PIPING BEHIND SINKS, CUT AND PATCH WALLS AS REQUIRED TO MATCH ADJACENT SURFACE.

M. CLEAN AND PREPARE SUBFLOOR FOR INSTALLATION OF NEW FLOOR FINISH.

N. DEMOLITION ACTIVITIES SHALL BE PERFORMED AS TO PRODUCE MINIMAL DISTURBANCE TO EXISTING FACILITY OCCUPANTS. MINIMIZE EXCESSIVE AND PROLONGED NOISE LEVELS AND DUST.

O. ASBESTOS-CONTAINING MATERIALS. REFER TO SPECIFICATION 02 26 23 FOR ASBESTOS INFORMATION APPLICABLE TO KITCHEN AREAS. FORT BEND ISD HAS RETAINED A SEPARATE ENVIRONMENTAL CONSULTANT FOR THE REMOVAL OF ASBESTOS. GC TO COORDINATE WITH ENVIRONMENTAL CONSULTANT TO CARRY OUT ASBESTOS ABATEMENT FOR ALL AFFECTED KITCHEN AREAS.

1.2 FLOOR PLAN GENERAL NOTES

A. FIELD VERIFY EXISTING CONDITIONS PRIOR TO GENERATING SHOP DRAWINGS AND FABRICATION OF EQUIPMENT.
B. FLOOR FINISH CHANGES SHALL OCCUR AT THE CENTERLINE OF DOORS UNLESS NOTED OTHERWISE. FLOOR FINISH CHANGES SHALL HAVE THRESHOLDS OR REDUCERS STRIPS.
C. DOORS THAT ARE TO BE REPLACED AND INSTALLED IN EXISTING FRAMES SHALL BE MACHINED FOR HARDWARE DIMENSIONS AT EXISTING FRAMES, CONTRACTOR SHALL FIELD VERIFY FRAME CONDITIONS AND DIMENSIONS.
D. CONTRACTOR TO PROVIDE SHEET METAL REINFORCING STRAP AS REQUIRED FOR MOUNTING OF ALL GRAB BARS, CABINETS, MIRRORS, SHELVING, ETC.
E. SAW CUT AND REMOVE EXISTING SLAB AND FLOOR FINISHES AS REQUIRED TO INSTALL NEW PLUMBING LINES, FLOOR DRAINS, PLUMBING FIXTURES, OR ELECTRICAL ITEMS. SPLICE NEW REINFORCING BARS DOWELED INTO EXISTING CONCRETE, AND PROVIDE NEW VAPOR RETARDER AND WATERSTOPS, AND PATCH W/ 3000 PSI CONCRETE AFTER INSTALLATION OF UTILITIES AND FIXTURES. PREPARE CONCRETE TO RECEIVE NEW FINISH.
F. COORDINATE HOUSEKEEPING PAD DIMENSIONS AND LOCATIONS WITH EQUIPMENT TO BE INSTALLED. HOUSEKEEPING PADS SHALL BE A MIN. OF 4" THICK REINF. W/ #3 BARS AT 15" O.C. BOTH WAYS. PROVIDE 1" BY 45-DEGREE CHAMFERED EDGES.

1.3 COMPLETE PERFORMANCE

L. THE CONTRACTOR SHALL FURNISH AND INSTALL ALL ITEMS SPECIFIED HEREIN AND AS INDICATED ON THE DRAWINGS. THE CONTRACTOR SHALL ALSO FURNISH AND INSTALL ALL ITEMS NECESSARY TO MAKE THE SYSTEMS FUNCTION WHICH MAY BE REASONABLY IMPLIED AS ESSENTIAL, WHETHER MENTIONED IN THE CONTRACT DOCUMENTS OR NOT.

M. WORK SHALL BE EXECUTED IN STRICT ACCORDANCE WITH THE BEST PRACTICE OF THE TRADES IN A THOROUGH, SUBSTANTIAL AND WORKMANLIKE MANNER BY COMPETENT WORKMEN.

1.4 SITE FAMILIARIZATION

A. GENERAL: BECOME FAMILIAR WITH THE DRAWINGS AND SPECIFICATIONS, EXAMINE THE PREMISES, AND UNDERSTAND THE CONDITIONS UNDER WHICH THE CONTRACT SHALL BE PERFORMED, PRIOR TO SUBMITTING A BID.

B. SITE: BE INFORMED OF THE SITE CONDITIONS, VERIFY LOCATIONS OF NEW AND EXISTING EQUIPMENT, AND DETERMINE EXACT REQUIREMENTS FOR CONNECTIONS.

C. COORDINATION: TENDER OF A PROPOSAL FOR THIS PROJECT INFERS THAT THE CONTRACTOR HAS VISITED THE SITE AND HAS BECOME FAMILIAR WITH THE DRAWINGS, SPECIFICATIONS, AND SITE CONDITIONS AND HAS INCLUDED IN HIS PROPOSAL ALL WORK NECESSARY TO PROPERLY INSTALL COMPLETE AND FUNCTIONING SYSTEMS ON THE PROJECT. FAILURE TO COMPLY WITH THIS REQUIREMENT SHALL NOT BE CONSIDERED JUSTIFICATION FOR THE OMISSION OR FAULTY INSTALLATION OF ANY WORK COVERED BY THE CONTRACT DOCUMENTS.

1.5 CODES AND STANDARDS

A. GENERAL: ALL WORK SHALL COMPLY WITH THE MOST RECENTLY REVISED VERSIONS OF ALL APPLICABLE LAWS, RULES, REGULATIONS AND ORDINANCES OF ALL FEDERAL, STATE AND LOCAL AUTHORITIES AND APPLICABLE UTILITIES. NONE OF THE TERMS OR PROVISIONS OF THIS SPECIFICATION SHALL BE CONSTRUED AS WAIVING ANY PART OF THE LAWS, RULES, REGULATIONS OR REQUIREMENTS OF THESE AUTHORITIES.

B. CONFLICT: IN THE EVENT OF CONFLICT BETWEEN THE CONTRACT DOCUMENTS AND THE LOCAL ENFORCING AUTHORITY, THE LATTER SHALL RULE. ANY MODIFICATIONS RESULTING THEREFROM SHALL BE MADE WITHOUT ANY ADDITIONAL COST TO THE OWNER OR ARCHITECT. THIS CONTRACTOR SHALL REPORT ANY SUCH MODIFICATIONS TO THE ARCHITECT AND SECURE HIS APPROVAL PRIOR TO PROCEEDING WITH THE WORK.

C. PRECEDENCE: WHERE CONTRACT DOCUMENT REQUIREMENTS EXCEED THE REQUIREMENTS OF THE CODES AND STANDARDS, THE CONTRACT DOCUMENTS SHALL TAKE PRECEDENCE PROVIDED THEY ARE NOT IN CONFLICT WITH THOSE CODES AND STANDARDS.

D. APPROVAL LABELS: ALL ITEMS OF EQUIPMENT AND ALL MATERIALS FOR WHICH APPROVED STANDARDS HAVE BEEN ESTABLISHED BY UNDERWRITERS' LABORATORIES, INC. (UL), FACTORY MUTUAL (FM), CERTIFIED BALLAST MANUFACTURER (CBM), ELECTRICAL TESTING LABORATORY (ETL), NATIONAL MANUFACTURERS ASSOCIATION (NEMA), AMERICAN STANDARD CODES, ASME, AGA, AMCA, ASA, ANSI, ASHRAE, AND ARI SHALL BE SO APPROVED AND SHALL BEAR APPROVAL LABELS ATTESTING TO SAME.

1.6 DRAWINGS AND SPECIFICATIONS

A. DRAWINGS: THE SET OF ORIGINAL DRAWINGS HAS BEEN MODIFIED AND INDICATE APPROXIMATE EXISTING LOCATIONS OF THE FLOOR FINISH ITEMS. ALL ITEMS ARE SHOWN APPROXIMATELY TO SCALE. FIELD VERIFY CONDITIONS.

B. SPECIFICATIONS: THE SPECIFICATIONS ARE INTENDED TO SUPPLEMENT THE DRAWINGS AND IT IS NOT IN THE SCOPE OF THE SPECIFICATIONS TO MENTION ANY PART OF THE WORK THAT THE DRAWINGS ARE COMPETENT TO FULLY EXPLAIN. CONVERSELY, ANY PART OF THE WORK THAT THE SPECIFICATIONS ARE COMPETENT TO FULLY EXPLAIN MAY NOT BE MENTIONED ON THE DRAWINGS. DRAWINGS AND SPECIFICATIONS ARE COMPLIMENTARY/SUPPLEMENTARY DOCUMENTS TO EACH OTHER.

C. DISAGREEMENT: DISAGREEMENT BETWEEN THE DRAWINGS AND SPECIFICATIONS OR WITHIN THE DRAWINGS OR SPECIFICATIONS SHALL BE ESTIMATED AND/OR BID USING THE BETTER QUALITY OR GREATER QUANTITY OF MATERIAL OR INSTALLATION, AND A CLARIFICATION REQUEST FOR INFORMATION SHALL BE MADE TO THE ARCHITECT IN A TIMELY MANNER AFTER THE PROJECT IS UNDER CONTRACT.

1.7 DISCREPANCIES

A. CLARIFICATION: CLARIFICATION OF SIGNIFICANT COST MATTERS SHALL BE OBTAINED BEFORE SUBMITTING A PROPOSAL FOR THE WORK AS TO DISCREPANCIES OR OMISSIONS FROM THE CONTRACT DOCUMENTS OR QUESTIONS AS TO THE INTENT THEREOF.

B. INTERPRETATIONS: SHOULD ANY DOUBT OR QUESTION ARISE RESPECTING THE TRUE MEANING OF DRAWINGS OR SPECIFICATIONS, REFERENCE SHALL BE MADE TO THE ARCHITECT, WHOSE WRITTEN DECISION SHALL BE FINAL AND CONCLUSIVE. NO ALLEGED STATEMENT BY THE ARCHITECT WILL BE ACCEPTED AS AN EXCUSE FOR NON-COMPLIANCE OR INFERIOR WORK.

C. CONTRACTOR AGREEMENT: CONSIDERATION WILL NOT BE GRANTED FOR MISUNDERSTANDING OF THE AMOUNT OF WORK TO BE PERFORMED. TENDER OF A PROPOSAL CONVEYS FULL CONTRACTOR AGREEMENT OF THE ITEMS AND CONDITIONS SPECIFIED, SHOWN, SCHEDULED, OR REQUIRED BY THE NATURE OF THE PROJECT, AND ALL COSTS ARE INCLUDED IN THE PROPOSAL.

1.8 REQUESTS FOR INFORMATION (RFI)

A. GENERAL: SUBMIT ALL CONTRACTOR REQUESTS FOR INFORMATION (RFI) IN WRITING TO THE ARCHITECT FOR RESPONSE. SUBMIT RFI ON A STANDARD FORM THAT HAS A SPACE FOR THE REQUESTED INFORMATION AND THE ARCHITECT'S RESPONSE.
B. SOLUTION PROPOSAL: IN GENERAL, THE CONTRACTOR SHALL PROPOSE SOLUTIONS TO IDENTIFY PROBLEMS FOR REVIEW AND APPROVAL OF THE ARCHITECT. THE RFI SHALL INCLUDE HAND SKETCHES, MARKED DRAWING PRINTS, EQUIPMENT CUTSHEETS, DRAWING AND SPECIFICATION REFERENCES, AND ANY OTHER BACK-UP INFORMATION, ETC., AS REQUIRED TO SUFFICIENTLY EXPLAIN THE PROBLEM AND PROPOSED SOLUTION.

1.9 QUALITY ASSURANCE

A. GENERAL: MATERIALS AND EQUIPMENT SHALL BE NEW, OF BEST GRADE AND QUALITY, AND STANDARD PRODUCTS OF REPUTABLE MANUFACTURERS REGULARLY ENGAGED IN THE PRODUCTION OF SUCH MATERIALS AND EQUIPMENT.
B. WORKMANSHIP: WORK SHALL BE EXECUTED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE BEST PRACTICE OF THE TRADES IN A THOROUGH, SUBSTANTIAL, WORKMANLIKE MANNER BY COMPETENT WORKMEN, PRESENTING A NEAT APPEARANCE WHEN COMPLETED.
C. JUDGMENT: IN ALL CASES, THE ARCHITECT SHALL BE THE SOLE JUDGE OF THE QUALITY AND EQUIVALENCE OF MANUFACTURERS, PRODUCTS, MATERIALS, AND METHODS.
D. MANUFACTURERS/PRODUCTS/MATERIALS/METHODS: MANUFACTURERS, PRODUCTS, MATERIALS, AND METHODS DESCRIBED IN THE VARIOUS SECTIONS OF THE SPECIFICATIONS AND INDICATED ON THE DRAWINGS ARE INTENDED TO ESTABLISH A STANDARD OF QUALITY ONLY. IT IS NOT THE INTENTION OF THE ARCHITECT TO DISCRIMINATE AGAINST ANY MANUFACTURER, PRODUCT, MATERIAL, OR METHOD THAT IS EQUAL TO THE STANDARDS AS INDICATED AND/OR SPECIFIED, NOR IS IT INTENDED TO PRECLUDE OPEN, COMPETITIVE BIDDING. THE FACT THAT A SPECIFIC MANUFACTURER IS LISTED AS AN ACCEPTABLE MANUFACTURER SHALL NOT BE INTERPRETED TO MEAN THAT THE MANUFACTURER'S STANDARD PRODUCT WILL MEET THE REQUIREMENTS OF THE PROJECT DESIGN, SPECIFICATIONS, AND SPACE CONSTRAINTS.
   1. WHEREVER A DEFINITE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS SPECIFIED AND THERE IS NOT A STATEMENT THAT ANOTHER MANUFACTURER, PRODUCT, MATERIAL, OR METHOD WILL BE ACCEPTABLE, IT IS THE INTENTION OF THE ARCHITECT THAT THE SPECIFIED MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS THE ONLY ONE THAT SHALL BE USED WITHOUT PRIOR APPROVAL.
   2. WHEREVER A DEFINITE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS SPECIFIED AS "NO SUBSTITUTE", IT IS THE INTENTION OF THE ARCHITECT THAT THE LISTED ITEM IS THE ONLY ONE ACCEPTABLE.
E. COORDINATION: WHERE EQUIPMENT IS USED ON THE PROJECT, IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR OR SUBCONTRACTOR INVOLVED TO VERIFY THAT THE EQUIPMENT WILL FIT IN THE SPACE AVAILABLE, INCLUDING ALL REQUIRED CODE AND MAINTENANCE CLEARANCES, AND TO COORDINATE ALL EQUIPMENT REQUIREMENTS AND PROVISIONS WITH THE SYSTEM DESIGN, ALL AFFECTED DIVISIONS, AND ALL OTHER CONTRACTORS. WHERE THE USE OF ALTERNATE OR SUBSTITUTE MATERIALS AFFECTS THE COST OF PROVISIONS MADE BY OTHER CONTRACTORS, THE CONTRACTOR PROVIDING THE ALTERNATE OR SUBSTITUTE SHALL BE RESPONSIBLE FOR THE OTHER CONTRACTOR'S COST ADJUSTMENT. THERE SHALL BE NO ADDITIONAL COST TO THE OWNER OR ARCHITECT DUE TO THE USE OR ACCEPTANCE OF ANY ALTERNATE OR SUBSTITUTE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD.

1.10 PRIOR APPROVAL

A. SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES: THE CONTRACTOR'S SUBMITTAL AND ARCHITECT'S ACCEPTANCE OF SHOP DRAWINGS, PRODUCT DATA, OR SAMPLES THAT RELATE TO CONSTRUCTION ACTIVITIES NOT COMPLYING WITH THE CONTRACT DOCUMENTS DOES NOT CONSTITUTE AN ACCEPTABLE OR VALID REQUEST FOR SUBSTITUTION, NOR DOES IT CONSTITUTE APPROVAL.

1.11 COORDINATION

A. BY SUBMITTING SHOP DRAWINGS ON THE PROJECT, THIS CONTRACTOR IS INDICATING THAT ALL NECESSARY COORDINATION HAS BEEN COMPLETED AND THAT THE SYSTEMS, PRODUCTS AND EQUIPMENT SUBMITTED CAN BE INSTALLED IN THE BUILDING AND WILL OPERATE AS SPECIFIED AND INTENDED, IN FULL COORDINATION WITH ALL OTHER DISCIPLINES.

1.12 SHOP DRAWINGS AND SUBMITTALS

A. GENERAL: AFTER THE CONTRACT IS AWARDED BUT PRIOR TO PROCEEDING WITH THE WORK REQUIRING SHOP DRAWING REVIEW, THE CONTRACTOR SHALL OBTAIN COMPLETE SHOP DRAWINGS AND PRODUCT DATA FROM THE MANUFACTURERS, SUPPLIERS, VENDORS, AND SUB- CONTRACTORS FOR ALL MATERIALS AND EQUIPMENT SPECIFIED HEREIN, AND MAKE FORMAL SUBMISSION TO THE ARCHITECT. A MINIMUM PERIOD OF TWO (2) WEEKS SHOULD BE ALLOWED IN THE CONSTRUCTION SCHEDULE EXCLUSIVE OF TRAVEL TIME FOR THE ARCHITECTS REVIEW.

B. CERTIFICATION: EACH CONTRACTOR RESPONSIBLE FOR THE WORK SHALL REVIEW AND CERTIFY THE SHOP DRAWING, SUBMITTAL AND/OR PRODUCT DATA TO BE IN FULL COMPLIANCE WITH THE REQUIREMENTS OF THE CONTRACT DOCUMENTS.

C. THE ARCHITECTS REVIEW OF SHOP DRAWINGS AND SUBMITTAL DATA SHALL NOT RELIEVE THE CONTRACTOR OF THE RESPONSIBILITY FOR DIMENSIONS OR ERRORS THAT MAY BE CONTAINED THEREIN, OR FOR DEVIATIONS FROM ANY REQUIREMENTS OF THE CONTRACT DOCUMENTS. IT SHALL BE CLEARLY UNDERSTOOD THAT THE ARCHITECTS NOTING SOME ERRORS BUT OVERLOOKING SOME OTHERS DOES NOT GRANT THE CONTRACTOR PERMISSION TO PROCEED IN ERROR. REGARDLESS OF ANY INFORMATION CONTAINED IN THE SHOP DRAWING OR PRODUCT DATA, THE CONTRACT DOCUMENTS SHALL GOVERN THE WORK AND ARE NEITHER WAIVED NOR SUPERSEDED IN ANY WAY BY THE REVIEW OF SHOP DRAWINGS, PRODUCT DATA AND SAMPLES.

1.13 EXECUTION AND COORDINATION OF WORK

A. MANUFACTURER'S RECOMMENDATIONS: WITH EXCEPTIONS AS SPECIFIED AND/OR INDICATED ON THE DRAWINGS OR IN THE SPECIFICATIONS, APPLY, INSTALL, ERECT, USE, CLEAN, AND CONDITION, MANUFACTURED ARTICLES, MATERIALS, AND EQUIPMENT PER MANUFACTURER'S CURRENT PRINTED RECOMMENDATIONS. KEEP COPIES OF SUCH PRINTED RECOMMENDATIONS AT JOB SITE AND MAKE THEM AVAILABLE AS REQUIRED.

1.14 SUPERVISION

A. A COMPETENT SUPERINTENDENT APPROVED BY THE ARCHITECT, SHALL BE KEPT BY THE CONTRACTOR AT THE BUILDING TO RECEIVE INSTRUCTIONS AND TO ACT FOR THE CONTRACTOR. ONCE THE SUPERINTENDENT HAS BEEN APPROVED, NO CHANGE SHALL BE MADE WITHOUT APPROVAL OF ARCHITECT. REPRESENTATIVES OF THE OWNER, ARCHITECT SHALL HAVE THE RIGHT TO OBSERVE THE WORK AT ANY TIME. THE CONTRACTOR SHALL HAVE A REPRESENTATIVE AVAILABLE WHEN HIS WORK IS BEING OBSERVED AND HE SHALL GIVE ASSISTANCE AS MAY BE REQUIRED TO THE ARCHITECT'S REPRESENTATIVE.

B. THE PROJECT SHALL BE CONSTRUCTED BY EMPLOYEES OF THE CONTRACTOR OR BY WORKERS UNDER HIS SUPERVISION. ANY SUBCONTRACTORS EMPLOYED BY THE CONTRACTOR SHALL BE APPROVED BY THE OWNER'S REPRESENTATIVE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL EQUIPMENT, MATERIAL AND WORK PERFORMED BY ANY SUBCONTRACTOR.

1.15 STORAGE AND PROTECTION OF MATERIALS

A. THE CONTRACTOR SHALL PROPERLY STORE ALL MATERIAL AND EQUIPMENT AT THE JOBSITE AND PROTECT IT FROM THE ELEMENTS AND FROM DAMAGE. ANY EQUIPMENT DAMAGED DUE TO IMPROPER PROTECTION SHALL BE REPLACED BY THE CONTRACTOR AT HIS EXPENSE.

B. THE CONTRACTOR SHALL PROTECT THE WORK, EQUIPMENT, AND MATERIAL OF ALL OTHER TRADES FROM DAMAGE BY HIS WORK OR OTHER WORKMEN, AND SHALL MAKE GOOD ALL DAMAGE THUS CAUSED.

C. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL WORK, MATERIALS, AND EQUIPMENT UNTIL FINALLY INSPECTED, TESTED, AND ACCEPTED; PROTECT WORK AGAINST THEFT, INJURY OR DAMAGE: AND CAREFULLY STORE MATERIAL AND EQUIPMENT RECEIVED ON SITE WHICH ARE NOT IMMEDIATELY INSTALLED. CLOSE OPEN ENDS OF WORK WITH TEMPORARY COVERS OR PLUGS DURING CONSTRUCTION TO PREVENT ENTRY OF OBSTRUCTING MATERIAL. THE CONTRACTOR SHALL COVER AND PROTECT IN AN ACCEPTABLE MANNER TO THE OWNER, EXISTING REMAINING EQUIPMENT AND MATERIALS.

D. IF ANY MATERIAL OR EQUIPMENT IS RECEIVED PRIOR TO THE TIME IT IS REQUIRED, THE CONTRACTOR SHALL BE RESPONSIBLE FOR ITS PROPER STORAGE AND PROTECTION UNTIL SUCH TIME AS IT MAY BE REQUIRED. THE CONTRACTOR SHALL PAY FOR ALL COSTS OF DEMURRAGE OR STORAGE.

1.16 DRAYAGE AND HAULING


A. THE CONTRACTOR SHALL KEEP THE JOBSITE FREE FROM THE ACCUMULATION OF TRASH AND CONSTRUCTION DEBRIS, REGARDLESS OF WHICH SUBCONTRACTOR MAY BE RESPONSIBLE.

1.17 CUTTING AND PATCHING


A. WHERE IT BECOMES NECESSARY TO CUT THROUGH ANY WALL, FLOOR OR CEILING TO PERMIT THE INSTALLATION OF ANY WORK, OR TO REPAIR ANY DEFECTS THAT MAY APPEAR, THE CUTTING SHALL BE PERFORMED UNDER THE SUPERVISION OF THE GENERAL CONTRACTOR. INFORM THE OWNER'S REPRESENTATIVE BEFORE ANY WORK COMMENCES. NO STRUCTURAL MEMBER SHALL BE ALTERED WITHOUT THE WRITTEN PERMISSION OF THE ARCHITECT.

B. VERIFICATION: SHOULD A QUESTION ARISE REGARDING THE ACCEPTABLE LEVEL OF NOISE OR VIBRATION IN A PARTICULAR SPACE OR PIECE OF EQUIPMENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING THE SERVICES OF AN APPROVED ACOUSTICAL CONSULTANT TO DETERMINE ACTUAL NOISE/VIBRATION CONDITIONS.


## 01 GENERAL NOTES





## 09 WINDOW CORNER
SCALE: 6" = 1'-0" XREF





## 10 DOOR STRIKE JAMB
SCALE: 6" = 1'-0" XREF





## 23 WINDOW HEAD
SCALE: 6" = 1'-0" XREF





## 17 WINDOW SILL
SCALE: 6" = 1'-0" XREF





## 24 DOOR WINDOW HEAD
SCALE: 6" = 1'-0" XREF




## 18 DOOR SILL
SCALE: 6" = 1'-0" XREF





## 11 DOOR HINGE JAMB
SCALE: 6" = 1'-0" XREF




## 12 WINDOW MULLION
SCALE: 6" = 1'-0" XREF

| | |
|---|---|
| SEQUENCE OF CONSTRUCTION (AS OF 01/27/2025). Schools will be renovated in groups as shown. These groups contain two or three major kitchen renovations and some cafeteria/miscellaneous renovations. This sequencing is critical for FBISD food service to provide the uninterrupted meal services to their schools. | |
| GROUPING 1 | AUSTIN PARKWAY ES + SUGAR MILL ES, kitchen renovations. *Plus: COMMON WEALTH ES, CONERSTONE ES misc. renovations.* |
| GROUPING 2 | SETTLERS WAY ES + PALMER ES kitchen renovations. *Plus: SULLIVAN ES, SIENNA CROSSING ES, HERITAGE ROSE ES misc. renovations* |
| GROUPING 3 | HUNTER'S GLEN ES + HIGHLANDS ES + PECAN GROVE ES kitchen renovations. *Plus: RIDGEGATE ES, DULLES ES misc. renovations.* |

## 03 PROJECT SCHEDULE




## 06 WINDOW JAMB
SCALE: 6" = 1'-0" XREF

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
6951 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL
REGISTERED ARCHITECT
NOEL ANTHONY MOYA
ZIMA
STATE OF TEXAS
7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

GENERAL NOTES AND ABBREVIATIONS

A00-01

## GENERAL DEMOLITION NOTES

(NOT ALL NOTES USED ON EACH SHEET)

1. REFER TO SHEET A00-01 FOR DEMOLITION GENERAL NOTES. THESE NOTES APPLY TO ALL SCHOOL KITCHENS.
2. COORDINATE EXTENT OF SAW CUTTING AREAS WITH NEW RECESSED SLAB FOR COOLER/FREEZER LAYOUTS, NEW SERVICE ENTRANCE FLOOR AND EXISTING KITCHEN LAYOUTS THAT REMAIN. SEE STRUCTURAL DRAWINGS AND SLAB DIMENSION CONTROL PLANS FOR ADDITIONAL SCOPE.
3. REMOVE PROTECT AND REINSTALL ALL EXISTING SURFACE MOUNTED FIRE EXTINGUISHERS (TYPES ABC AND K) AT ALL KITCHENS.
4. SAWCUT AND RE-LOCATE EXPOSED CONDUITS AND WIREMOLD TO INSIDE OF WALLS. PATCH AND PAINT. EXCEPTION: WAREWASH AREA BELOW TABLE HEIGHT AND DRY STORAGE ROOMS.
5. CONTRACTOR TO RELOCATE EXISTING KITCHEN EQUIPMENT AND OFFICE FURNITURE TO TEMPORARY KITCHEN LAYOUT AS REQUESTED BY KITCHEN MANAGER. ALSO THAT THE IT EQUIPMENT IS PROTECTED DURING RENOVATIONS. ALL EXISTING EQUIPMENT SHALL BE RETURNED TO OWNER.
6. EXISTING TACKBOARDS TO BE REMOVED BY OWNER.
7. IF PRESENT, EXISTING SAFE IN EACH KITCHEN TO BE TEMPORARILY REMOVED DURING RENOVATION AND REINSTALLED IN KITCHEN AREA.
8. ORIGIN POINT OF EXISTING CEILING GRID SHALL BE IDENTIFIED. NEW CEILING WILL BE INSTALLED (AS MUCH AS POSSIBLE) AT THE SAME ORIGIN POINT SO THAT SPRINKLER SYSTEM PIPING CAN REMAIN UNCHANGED.
9. ABOVE-CEILING INFRASTRUCTURE SHALL REMAIN UNDISTURBED AS MUCH AS IS POSSIBLE. CEILING DEVICES ARE TO BE REMOVED FROM EXISTING GRID/TILE THEN DURING RE-INSTALATION OF CEILING DEVICES SHALL BE LOCATED AS CLOSE TO ORIGINAL LOCATION AS POSSIBLE INTO THE NEW GRID/TILE. PROTECT AND STORE EXISTING INFRASTRUCTURE (CABLING, ELECTRICAL POWER, PIPING) DURING CONSTRUCTION.
10. EXISTING HOOD IN WAREWASH AND (2) HOODS IN PRODUCTION AREA ARE TO BE CLEANED, INSPECTED, SERVICED AND REFURBISHED TO A LIKE NEW CONDITION. THEY ARE TO REMAIN IN PLACE.

## 3 DEMOLITION NOTES


## KEYED DEMOLITION NOTES

(NOT ALL NOTES USED ON EACH SHEET)

1. REMOVE EXISTING THINSET SYNTHETIC TERRAZZO FLOOR AND TERRAZZO COVE BASE MATERIAL IF ANY EXISTS THROUGHTOUT KITCHEN AREA. CLEAN AND PREPARE SUBFLOOR TO RECEIVE NEW FLOOR. RE: FINISH PLAN FOR NEW FLOOR FINISH MATERIAL.
2. REMOVE EXISTING QUARRY TILE FLOORING AND BASE. CLEAN AND PREPARE SUBFLOOR TO RECEIVE NEW FLOORING. RE: FINISH SCHEDULE FOR NEW FLOOR FINISH MATERIAL.
3. CEILING DEVICES: REMOVE SMOKE DETECTORS, STROBES, EXIT SIGNAGE, MOTION DETECTORS AND CEILING SPEAKERS. PROTECT AND RE-INSTALL AFTER FINISHES ARE APPLIED.
4. REMOVE EXISTING LOCKERS. PROTECT AND RE-INSTALL AFTER FINISHES APPLIED.
5. REMOVE EXISTING WASHER AND DRYER. VERIFY WITH FBISD FOR RELOCATION TO WAREHOUSE.
6. TEMPORARILY REMOVE EXISTING WALL MOUNTED CLOCK AND STORE FOR REINSTALLATION AFTER WALL RECEIVED NEW FINSH.
7. REMOVE EXISTING WALK-IN COOLER/FREEZER AND CONDENSING UNIT LOCATED IN ADJACENT SPACE. MITIGATE ANY MOLD FOUND.
8. REMOVE EXISTING DOOR AND PROTECT EXISTING FRAME TO REMAIN
9. REMOVE EXISTING DOOR AND FRAME, PROTECT FRAME AND OR DOOR IF IT IS SCHEDULED TO REMAIN.
10. REMOVE PARTIAL EXISTING CMU PARTITION FOR NEW DOOR OPENING
11. INSPECT EXISTING WAREWASH COUNTER DOOR AND S.S. PASS-THRU WINDOW CHUTE. REPAIR REPLACE DAMAGED COMPONENTS. CLEAN, LUBRICATE AND RE-INSTALL.
12. EXISTING CARD READER ACCESS TO REMAIN
13. EXISTING WINDOW TO REMAIN
14. REMOVE EXISTING KITCHEN EQUIPMENT THROUGHOUT KITCHEN INCLUDING WALK-IN COOLER / FREEZER AND CONDENSING UNIT LOCATED IN ADJACENT ROOM OR OUTSIDE OF THE BUILDING. VERIFY WITH OWNER FOR RELOCATION TO WAREHOUSE. SOME EQUIPMENT IS TO BE RE-USED IN TEMPORARY SERVING LINES. SEE ALSO GENERAL DEMOLITION NOTE 6.
15. REMOVE EXISTING FRP AND PREP FOR NEW TILE FINISH.
16. COORDINATE REMOVAL AND STORAGE OF ANY EXISTING FURNITURE ITEMS WITH OWNER . SEE ALSO GENERAL DEMOLITION NOTE 5.
17. REMOVE EXISTING SOAP AND PAPER TOWEL DISPENSER AND RETURN TO OWNER
18. EXISTING WALL MOUNTED ACCESSORIES SIGNS, DISPLAY BOARDS, AND MATS TO BE REMOVED BY FORT BEND ISD (VERIFY EQUIPMENT - IF ANY).
19. REMOVE EXISTING SURFACE MOUNTED FIRE EXTINGUISHER. RE-INSTALL AFTER NEW FINISH APPLIED.
20. REMOVE EXISTING ACOUSTIC CEILING TILE CEILNG SYSTEM AND LIGHT FIXTURES, HVAC DEVICES, SENSORS, ETC. THROUGHTOUT RENOVATED AREAS. PREP FOR NEW SUSPENDED CEILING. EXISTING SPRINKLE SYSTEM TO REMAIN AS-IS UNLESS ROOM CONFIGURATION HAS CHANGED IN NEW DESIGN. PROTECT RECESSED SPRINKLER HEADS AND - RE-INSTALL IN NEW CEILING.
21. REMOVE EXISTING CASEWORK/SHELVING
22. EXISTING CERAMIC WALL TILE TO REMAIN. PROTECT FROM DAMAAGE.
23. REMOVE EXISTING COAT HANGER / ROD / SHELF
24. REMOVE EXISTING PLUMBING FIXTURES IN RESTROOMS. RE: PLUMBING FOR NEW FIXTURES.
25. REMOVE EXISTING UTILITY SINK. RE: PLUMBING FOR NEW PLUMBING FIXTURES.
26. REMOVE EXISTING MOP HOLDER. REPLACE WITH NEW UNIT AS SPECIFIED.
27. REMOVE EXISTING WALL MOUNTED CLEANING SOLUTION DISPENSER (BY FBISD VENDOR)
28. HOOD TO REMAIN - SEE GENERAL DEMOLITION NOTE 10.
29. HOOD TO REMAIN - SEE GENERAL DEMOLITION NOTE 10.
30. REMOVE FLOORING IN THIS AREA FOR NOTE 1.
31. REMOVE CARTIDGE FILTER AND WATER PURTICATION CABNET


## DEMOLITION LEGEND

- EXISTING PARTITION TO REMAIN
- REMOVE EXISTING PARTITION
- EXISTING CMU PARTITION
- REMOVE DOOR AND FRAME TO REMAIN
- REMOVE EXISTING DOOR AND FRAME
- EXISTING PLUMBING FIXTURES (WATER CLOSET, HAND LAVATORY, AND MOP SINK TO BE REMOVED. RE: PLUMBING DRAWINGS.
- EXISTING ACOUSTIC CEILING TILE AND GRID TO BE REMOVED. RE: ELECTRICAL DRAWINGS.
- SPRINKLER HEAD (RECESSED)
- CLOCK
- CEILING MOUNTED SPEAKERS




## 1 DEMOLITION FLOOR PLAN

SCALE: 1/4" = 1'-0"




## 2 DEMOLITION REFLECTED CEILING PLAN

SCALE: 1/4" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL

REGISTERED ARCHITECT MICHAEL A. MAGNUSEN 22651 STATE OF TEXAS

7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

DEMO PLAN

k-D.101

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\K-Hunters Glen ES\k-D.101 DEMO PLAN.dwg, Jul 23, 2025 - 2:01pm


PHOTO D1


PHOTO D2




PHOTO D3



PHOTO D4



PHOTO D5



PHOTO D6



PHOTO D7



PHOTO D8




PHOTO D9


PHOTO D10




PHOTO D11




PHOTO D12




PHOTO D13




PHOTO D14




PHOTO D15



PHOTO D16




PHOTO D17



PHOTO D18




PHOTO D19



PHOTO D20

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD,
MISSOURI CITY, TX 77489

SEAL
JOHN R. REGINELLI ARCHITECT
STATE OF TEXAS
7/15/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

DEMO PLAN PHOTOS

k-D.101-2

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\K-Hunters Glen ES\k-D.101-2 DEMO PLAN PHOTOS.dwg, Jul 23, 2025 - 2:02pm



PHOTO D21



PHOTO D22



PHOTO D23



PHOTO D24



PHOTO D25



PHOTO D26



PHOTO D27



PHOTO D28

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD,
MISSOURI CITY, TX 77489

SEAL

REGISTERED ARCHITECT
KEITH A. MARTIN
22651
STATE OF TEXAS

7/15/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

DEMO PLAN PHOTOS

k-D.101-3

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\K-Hunters Glen ES\k-D 101-3 DEMO PLAN PHOTOS.dwg Jul 23, 2025 - 2:02pm


## NEW PANEL

## TEMP KITCHEN


**PANEL LTK** — 150A MCB, 208Y/120V, 3ϕ, 4 WIRE — AVAILABLE FAULT: <10,000A, SCCR & AIC: 10,000A — MOUNTING: SURFACE

| NOTES | EQUIP. NO. | LOAD | DESCRIPTION | WIRE | CB | CKT | A | B | C | CKT | CB | WIRE | DESCRIPTION | LOAD | EQUIP. NO. | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E810 | 2766 | HOT WELLS | 2–12 | 20/2GFI | 1 | ■ | | | 2 | 20/1 | 3–12 | TRANSPORT CART | 1920 | E806 | |
| | – | – | – | +12G | – | 3 | | ■ | | 4 | 20/1 | 3–12 | TRANSPORT CART | 1920 | E806 | |
| | E810A | 1643 | HOT WELLS | 2–12 | 20/2GFI | 5 | | | ■ | 6 | 20/1 | 3–12 | TRANSPORT CART | 1920 | E806 | |
| | – | – | – | +12G | – | 7 | ■ | | | 8 | 20/1 | 3–12 | TRANSPORT CART | 1920 | E806 | |
| | E810B | 600 | COLD PAN | 3–12 | 20/1GFI | 9 | | ■ | | 10 | 20/1 | 3–12 | 2 REC | 360 | E800A | |
| | E810C | 1200 | BEVERAGE | 3–12 | 20/1GFI | 11 | | | ■ | 12 | 20/1 | 3–12 | 2 REC – DESK | 360 | E800B | |
| | E810C | 1200 | BEVERAGE | 3–12 | 20/1GFI | 13 | ■ | | | 14 | 20/1 | 3–12 | 2 REC | 360 | E800A | |
| | E811 | 180 | CASH REGISTER | 3–12 | 20/1GFI | 15 | | ■ | | 16 | 20/1 | 3–12 | 3 REC | 360 | E800A | |
| | E810B | 600 | COLD PAN | 3–12 | 20/1GFI | 17 | | | ■ | 18 | 20/1 | 3–12 | TEMP. KITCHEN LTS/FAN | 566 | | |
| | E810A | 1643 | HOT WELLS | 2–12 | 20/2GFI | 19 | ■ | | | 20 | 20/1 | | SPARE | | | |
| | – | – | – | +12G | – | 21 | | ■ | | 22 | 20/1 | | SPARE | | | |
| | E810 | 2766 | HOT WELLS | 2–12 | 20/2GFI | 23 | | | ■ | 24 | 20/1 | | SPARE | | | |
| | – | – | – | +12G | – | 25 | ■ | | | 26 | 20/1 | | SPARE | | | |
| | E808 | 1622 | HEATED CABINET | 2–12 | 20/2 | 27 | | ■ | | 28 | 20/1 | | SPARE | | | |
| | – | – | – | +12N+12G | – | 29 | | | ■ | 30 | 20/1 | 3–12 | EXISTING CIRCUIT | 500 | | 3 |
| | E809 | 984 | REFRIGERATOR | 3–12 | 20/1 | 31 | ■ | | | 32 | 20/1 | 3–12 | EXISTING CIRCUIT | 500 | | 3 |
| | E808 | 1622 | HEATED CABINET | 2–12 | 20/2 | 33 | | ■ | | 34 | 15/2 | 2–12 | EXISTING CIRCUIT | 1000 | | 3 |
| | – | – | – | +12N+12G | – | 35 | | | ■ | 36 | – | +12N+12G | – | – | | |
| | E809 | 984 | REFRIGERATOR | 3–12 | 20/1 | 37 | ■ | | | 38 | 20/2 | 2–12 | EXISTING CIRCUIT | 1000 | | 3 |
| | | | SPARE | | 20/1 | 39 | | ■ | | 40 | – | +12N+12G | – | – | | |
| | | | SPARE | | 20/1 | 41 | | | ■ | 42 | 50/2 | 2–8 | EXISTING CIRCUIT | 5000 | | 3 |
| | | | SPARE | | 20/1 | 43 | ■ | | | 44 | – | +8N+10G | – | – | | |
| | TOTAL LOAD @ 100% = 35498VA | | | | | TOTAL LOAD @ 100% = 99A | | | | | | | | | | |


1. REF. KITCHEN CONSULTANT'S "FCS" DRAWINGS FOR KITCHEN EQUIPMENT NUMBERS.
2. A DEMAND FACTOR PERCENT OF 65% HAS BEEN APPLIED TO THE KITCHEN EQUIPMENT LOAD PURSUANT TO NEC 220–20 AND NEC TABLE 220–20.
3. IDENTIFY ANY CIRCUITS OR PARTIAL CIRCUITS THAT EXTEND BEYOND THE AREA OF RENOVATION. PROVIDE TEMPORARY FEED TO MAINTAIN ALL CIRCUITS SERVING ELEMENTS/SPACES NOT TO BE REMOVED DURING CONSTRUCTION. RECONNECT EXISTING CIRCUITS/DEVICES TO REMAIN TO TEMPORARY KITCHEN PANEL ONCE AVAILABLE USING CB(S) PROVIDED. ALL PARTIAL CIRCUITS SHALL REMAIN AND REMAIN ACTIVE BOTH DURING AND AFTER CONSTRUCTION.




**T1** **TEMPORARY KITCHEN - LIGHTING PLAN**
SCALE: 1/4" = 1'– 0"




**T2** **TEMPORARY KITCHEN - ELECTRICAL PLAN**
SCALE: 1/4" = 1'– 0"




**1** **DEMOLITION FLOOR PLAN**
SCALE: 1/8" = 1'– 0"

## ELECTRICAL KEYED NOTES

GENERAL NOTES:

- CUT WALLS AS REQUIRED TO FLUSH MOUNT NEW DEVICES IN EXISTING WALLS. PATCH/REPAIR WALLS TO MATCH.

DEMOLITION NOTES:

A. EXISTING STANDBY GENERATOR PANEL TO REMAIN.

B. EXISTING KITCHEN PANELS TO BE REPLACED WITH NEW. MODIFY EXISTING WALLS TO MATCH NEW PANEL LAYOUTS AND DIMENSIONS.

C. EXISTING LIGHTING FIXTURES AND CEILING DEVICES TO BE REMOVED THROUGHOUT.

D. EXISTING WALK–IN COOLER/FREEZER AND ASSOCIATED EQUIPMENT TO BE REMOVED.

E. EXISTING WALL ELECTRICAL DEVICES TO BE REMOVED. EXISTING J–BOXES MAY BE REUSED WHERE NEW DEVICES ARE TO BE INSTALLED AT THE SAME LOCATIONS.

F. EXISTING ELECTRICAL DEVICES TO BE REMOVED.

G. NEW 208Y/120V PANEL AND TRANSFORMER FOR TEMPORARY KITCHEN TO BE INSTALLED PRIOR TO DEMOLITION. PANEL AND TRANSFORMER TO BE REMOVED AT END OF KITCHEN RENOVATION AND TURNED OVER TO THE DISTRICT. INSTALL TRANSFORMER ON PREMADE FIBERCRETE PAD AND WAFFLE TYPE VIBRATION ISOLATION PADS. DO NOT PROVIDE A POURED IN PLACE CONCRETE PAD AT THIS LOCATION.

H. PROVIDE RECEPTACLES AND LIGHT FIXTURES FOR TEMPORARY KITCHEN DURING RENOVATION. ALL TEMPORARY DEVICES AND EQUIPMENT TO BE REMOVED AT END OF KITCHEN RENOVATION AND OFFERED TO THE OWNER AS SALVAGE.

I. CONDUITS ROUTED FROM TEMPORARY KITCHEN WALL AND BENEATH SERVING LINE. PROVIDE MULTICHANNEL ROLLOVER CABLE PROTECTOR FOR EXPOSED CONDUITS NOT UNDER THE SERVING LINE. ALL CONDUITS UNDER THE SERVING LINE SHALL BE SECURED TO/ROUTED ON TOP OF UNISTRUT AND NOT DIRECTLY ON THE FLOOR. DO NOT ANCHOR UNISTRUT TO THE EXISTING FLOORING. COORDINATE POWER AND DATA OUTLET LOCATIONS WITH OTHER TRADES.

J. REMOVE EXISTING LIGHT FIXTURES ABOVE NEW KITCHEN EXTENSION. MODIFY EXISTING WIRING TO MAINTAIN REMAINING FIXTURE OPERATION.

K. HARDWIRE KITCHEN EQUIPMENT TO LOCAL ON/OFF SWITCH. TYPICAL.

L. SURFACE MOUNT FIXTURES ON TEMPORARY KITCHEN CEILING. TYPICAL.

M. WIRE TEMPORARY KITCHEN FAN TO LOCAL LIGHTING CIRCUIT AND CONTROLS. FAN SHALL BE ON/OFF WITH LIGHTS.

N. EXISTING EXTERIOR LIGHT FIXTURES TO BE REMOVED.

O. PROVIDE NEW FIRE ALARM DEVICES AS PART OF THE TEMPORARY KITCHEN BUILDOUT.

P. PROVIDE NEW TEMPORARY LIGHT FIXTURES IN THE EXISTING CAFETERIA CEILING ABOVE THE SERVING LINE. COORDINATE LOCATIONS WITH TEMPORARY SERVING LINE AND EXISTING CONDITIONS. CONNECT TO EXISTING LIGHTING CONTROLS/CIRCUIT. ALL TEMPORARY LIGHT FIXTURES SHALL BE REMOVED AT THE END OF KITCHEN RENOVATION AND OFFERED TO THE OWNER AS SALVAGE. PROVIDE REPLACEMENT CEILING TILES.

Q. PROVIDE IN–USE WEATHERPROOF COVER FOR RECEPTACLE.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025


ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING


ELECTRICAL DEMO AND TEMP PLANS

k-ED.100


STANTON ENGINEERING GROUP
INFO@STANTON–ENG.COM (713) 300–6266
TEXAS ENG. FIRM REG NO. F–21833 | TBPE


©2025 ALL RIGHTS RESERVED


12800 W. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77040




## DEMOLITION KEYED NOTES

D1 EXISTING CLEAN OUT SHALL BE REPLACED WITH NEW. CHIP OUT SLAB AROUND CLEANOUT TO REMOVE.

D2 EXISTING FLOOR DRAIN SHALL BE REPLACED WITH NEW, INCLUDING P-TRAP. CHIP OUT SLAB AROUND DRAIN TO REMOVE FLOOR DRAIN AND EXISTING P-TRAP.

D3 CUT AND CAP EXISTING HW/CW FOR FUTURE EXTENSION. DEMOLISH ALL PIPING WITHIN KITCHEN. DEMOLITION SHALL BE DELAYED UNTIL NEW CW MAIN AND HW PIPING LOOP IS INSTALLED IN PARALLEL. CW/HW SERVICE TO THE TEMPORARY KITCHEN SHALL BE UNINTERRUPTED DURING OCCUPIED HOURS. COORDINATE SWITCHOVER FROM EXISTING PIPING TO NEW WITH OCCUPANCY SCHEDULE.

D4 EXISTING FLOOR DRAIN TIED TO GREASE WASTE SYSTEM. DRAIN IS BEING USED FOR TEMPORARY KITCHEN INDIRECT WASTE AND SHALL REMAIN ACTIVE DURING OCCUPIED HOURS. COORDINATE DEMOLITION AND REPLACEMENT WITH TEMPORARY KITCHEN USAGE.

D5 DEMOLISH EXISTING DRAIN A CAP BELOW SLAB.

D6 EXISTING SPACE BEING DEMOLISHED. CAP EXISTING SANITARY MAIN BELOW SLAB AND REMOVE UPSTREAM PIPING. CUT/CHIP OUT SLAB AS REQUIRED AND REPAIR TO MATCH EXISTING.

D7 TEMPORARILY CAP EXISTING SANITARY MAIN BELOW SLAB AND REMOVE UPSTREAM PIPING. CUT/CHIP OUT SLAB AS REQUIRED AND REPAIR TO MATCH EXISTING. PIPING TO BE REPLACED WITH NEW TRUNK AND ADDITIONAL DRAIN BRANCH LINES.

D8 CUT AND CAP EXISTING SANITARY MAIN BELOW GRADE FOR EXTENSION IN RENOVATION PHASE. ALL UPSTREAM PIPING SHALL BE ABANDONED IN PLACE. CAP ANY OPEN ENDS BEFORE BURIAL.

**1 PLUMBING DEMOLITION FLOOR PLAN**

SCALE: 1/4" = 1'- 0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL

STATE OF TEXAS
TYLER W. HERRING
106052
LICENSED
PROFESSIONAL
ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

PLUMBING DEMOLITION FLOOR PLAN

**k-PD1.01**


STANTON ENGINEERING GROUP
INFORMATION-TECHNOLOGY (713) 300-6080 | TEXAS ENGINEERING REG. NO.F-12333 | 1300 W. SAM HOUSTON PARKWAY S., SUITE 125, HOUSTON, TX 77042


© 2025 ALL RIGHTS RESERVED




1 k-TD201 TECHNOLOGY DEMOLITION FLOOR PLAN
1/4" = 1'-0"

**TECHNOLOGY DEMOLITION PLAN GENERAL NOTES**

1. ALL DATA, VOICE, VIDEO AND SECURITY SYSTEMS SHALL REMAIN OPERATIONAL AT ALL TIMES DURING BUSINESS HOURS UNLESS OTHERWISE NOTED. ANY SYSTEM DOWNTIME SHALL BE SCHEDULED WITH THE ARCHITECT/ENGINEER AND OWNER AT LEAST TEN (10) WORKING DAYS IN ADVANCE. CONTRACTOR SHALL DEVELOP A PHASING PLAN AND SCHEDULE OF ANY REQUIRED SYSTEM DOWNTIME FOR REVIEW AND APPROVAL BY THE ARCHITECT/ENGINEER AND OWNER PRIOR TO ANY CONSTRUCTION ACTIVITIES.
2. OWNER SHALL BE RESPONSIBLE FOR POWER DOWN AND START-UP OF ALL DATA, VOICE, VIDEO AND SECURITY SYSTEMS. CONTRACTOR SHALL COORDINATE WITH THE ARCHITECT/ENGINEER AND OWNER AND PROVIDE A MINIMUM OF TEN (10) WORKING DAYS NOTICE FOR SCHEDULING OF ANY REQUIRED DOWNTIME.
3. ALL EXISTING WIRELESS ACCESS POINTS ARE TO BE REMOVED AND RETURNED TO OWNER. CONTRACTOR SHALL RE-INSTALL ALL EXISTING AND NEW WIRELESS ACCESS POINTS AT COMPLETION OF PROJECT.
4. COORDINATE REMOVAL OF EXISTING CAMERA WITH OWNER/ARCHITECT DURING CONSTRUCTION.

**TECHNOLOGY DEMOLITION PLAN KEYED NOTES**

**NOT ALL KEYED BELOW APPLY TO THIS SHEET**

(1) EXISTING DATA/VOICE/WIRELESS ACCESS POINT OUTLET TO BE REMOVED. CONTRACTOR SHALL REMOVE AND DISPOSE OF ALL 4-PAIR CABLES AND WORKSTATION CONNECTING HARDWARE TERMINATED AT THIS LOCATION. IF LOCATION IS NOT RE-USED, CONTRACTOR SHALL SUPPLY AND INSTALL BLANK COVER. CONTRACTOR IS TO REMOVE EACH CABLE TO BE DEMOLISHED FROM THE PATCH PANEL OR TERMINATION BLOCK IN THE TELECOMMUNICATIONS ROOM, REMOVE THE ENTIRE LENGTH OF THE CABLE AND THE CORRESPONDING MODULAR CONNECTOR, FACEPLATE AND ACCESSORIES. NO ABANDONED CABLING IS TO BE LEFT ABOVE CEILING. CONTRACTOR SHALL INSTALL ALL EXISTING AND NEW WIRELESS ACCESS POINTS AT COMPLETION OF PROJECT.

(2) EXISTING VIDEO SURVEILLANCE CAMERA. CONTRACTOR SHALL REMOVE AND RETURN TO OWNER.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD PKG 13 KG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD


07/18/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY DEMOLITION FLOOR PLAN


SHEET NO.
k-TD201




## 10 CANOPY DETAILS
3/4" = 1'-0"





## 11 CANOPY PLAN
3/4" = 1'-0"





## 12 CANOPY SECTION
3/4" = 1'-0"

NUMBERED NOTES: FOR 2/a-A.101
1. COOLER RENTAL UNIT; APPROX. 8' X 10' BASIS OF DESIGN: MODEL DT810 BY POLAR LEASING REFRIGERATION RENTAL.
2. INCLUDE OPTIONAL DIAMOND TREAD RAMP SUITABLE FOR WHEELED TRAFFIC
3. LOCATION SHOWN IS SUBJECT TO OWNER APPROX. LOCATION MUST NOT BLOCK DELIVERIES TO REAR DOOR, MUST BE WITH 10' OF AREA DRAIN, AND WITHIN 100' OF ELECTRICAL POWER.
4. CONTRACTOR SHALL SCAN PAVING FOR BURIED UTILITIES BEFOR CUTTING CONC.




| PHASING CHART FOR ALL SCHOOLS | | |
|---|---|---|
| PHASE 1 | | |
| SCHOOLS | FREEZER START DATE : | FREEZER END DATE : |
| *AUSTIN PARKWAY ES* | 11/7/2025 | 5/13/2026 |
| SUGAR MILL ES | | |
| COMMONWEALTH ES | | |
| CONERSTONE ES | | |
| PHASE 2 | | |
| SETTLERS WAY ES | 5/29/2026 | 10/28/2026 |
| PALMER ES | | |
| SULLIVANN ES | | |
| SIENNA CROSSING ES | | |
| HERITAGE ROSE ES | | |
| PHASE 3 | | |
| HUNTERS GLEN ES | 3/19/2027 | 3/19/2027 |
| PECAN GROVE ES | | |
| HIGHLANDS ES | | |
| DULLES ES | | |

## 1 SITE PLAN
SCALE: 1" = 30'-0"




## 2 ENLARGED SITE PLAN
SCALE: 1/16"=1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
6955 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL
REGISTERED ARCHITECT MICHAEL A. WILLIAMSON 22651 STATE OF TEXAS
7/15/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

SITE PLAN

k-A.101

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\K-Hunters Glen ES\k-A.101 SITE PLAN.dwg, Jul 23, 2025 - 2:04pm

# 2 CODE ANALYSIS

SCOPE OF WORK: KITCHEN REPLACEMENT OF FLOOR, WALL, AND CEILING FINISHES, AS WELL AS, REPLACEMENT OF KITCHEN EQUIPMENT. PROVIDE ADDITIONAL KITCHEN STORAGE FOR CEP. UPGRADE TO BACK DOOR DELIVERY AREA.

**ADOPTED CODES WITH AMMENDMENTS OF CITY OF MISSOURI CITY, TX**

- 2021 INTERNATIONAL BUILDING CODE
- 2021 INTERNATIONAL RESIDENTIAL CODE
- 2021 INTERNATIONAL PLUMBING CODE
- 2021 INTERNATIONAL MECHANICAL CODE
- 2023 NATIONAL ELECTRIC CODE NFPA 70
- 2021 INTERNATIONAL ENERGY CONSERVATION CODE
- 2021 INTERNATIONAL FUEL GAS CODE
- 2021 INTERNATIONAL FIRE CODE

**INTERIOR WALL AND CEILING FINISH REQUIREMENTS BY OCCUPANCY:**

**SPRINKLERED**

INTERIOR EXIT STAIRWAYS AND RAMPS AND EXIT PASSAGEWAYS **B**

CORRIDORS AND ENCLOSURE FOR EXIT ACCESS STAIRWAYS AND RAMPS **C**

ROOMS AND ENCLOSED SPACES **C**

**FLOORING SHALL BE CLASS II**

**2021 INTERNATIONAL EXISTING BUILDING CODE**

301.3.1 PRESCRIPTIVE COMPLIANCE METHOD. REPAIRS, ALTERATIONS, ADDITIONS AND CHANGES OF OCCUPANCY COMPLYING WITH CHAPTER FIVE OF THIS CODE IN BUILDINGS COMPLYING WITH THE INTERNATIONAL FIRE CODE SHALL BE CONSIDERED IN COMPLIANCE WITH THE PROVISIONS OF THIS CODE.

302.3 EXISTING MATERIALS. MATERIALS ALREADY IN USE IN A BUILDING IN COMPLIANCE WITH REQUIREMENTS OR APPROVALS IN EFFECT AT THE TIME OF THEIR ERECTION OR INSTALLATION SHALL BE PERMITTED TO REMAIN IN USE UNLESS DETERMINED BY THE BUILDING OFFICIAL TO BE UNSAFE.

302.4 NEW AND REPLACEMENT MATERIALS. EXCEPT AS OTHERWISE REQUIRED OR PERMITTED BY THIS CODE, MATERIALS PERMITTED BY THE APPLICABLE CODE FOR NEW CONSTRUCTION SHALL BE USED. LIKE MATERIALS SHALL BE PERMITTED FOR REPAIRS AND ALTERATIONS, PROVIDED THAT NO UNSAFE CONDITION IS CREATED. HAZARDOUS MATERIALS SHALL NOT BE USED WHERE THE CODE FOR NEW CONSTRUCTION WOULD NOT PERMIT THEIR USE IN BUILDINGS OF SIMILAR OCCUPANCY, PURPOSE AND LOCATION.

**ALTERATION - LEVEL 1** INCLUDE THE REMOVAL AND REPLACEMENT OR THE COVERING OF EXISTING MATERIALS, ELEMENTS, EQUIPMENT, OR FIXTURES USING NEW MATERIALS, ELEMENTS, EQUIPMENT, OR FIXTURES THAT SERVE THE SAME PURPOSE.

**ALTERATION - LEVEL 2** INCLUDE THE ADDITION OR ELIMINATION OF ANY DOOR OR WINDOW, THE RECONFIGURATION OR EXTENSION OF ANY SYSTEM, OR THE INSTALLATION OF ANY ADDITIONAL EQUIPMENT, AND SHALL APPLY WHERE THE WORK IS EQUAL TO OR LESS THAN 50% OF THE BUILDING AREA.

THIS BUILDING'S CONSTRUCTION IS TYPE IIB.

THIS BUILDING'S OCCUPANCY IS E.

THIS BUILDING'S IS SPRINKLERED.


THERE WILL NOT BE ANY MODIFACATIONS TO THE HOOD SYSTEMS IN THE KITCHENS BEYOND REPLACEMENT OF MOTOR FOR LIKE KIND IF NEEDED.

THE BUILDING WILL NOT HAVE ADDITIONAL SQUARE FOOTAGE AS PART OF THE WORK.

NEW CONSTRUCTION ELEMENTS, COMPONENTS, SYSTEMS AND SPACES SHALL COMPLY WITH THE REQUIREMENTS OF THE INTERNATIONAL BUILDING CODES

## RESPONSIBILITY MATRIX

| ITEM | | | | CONTRACTOR RESPONSIBILITY | | OWNER RESPONSIBILITY | | NOTES |
|---|---|---|---|---|---|---|---|---|
| **EQUIPMENT** | **MAKE** | **MODEL** | **BASIS OF DESIGN** | FURNISHED | INSTALL | FURNISHED | INSTALL | |
| MARKERBOARD | | | MUST BE MAGNETIC, LOW GLOS, WHITE. NO GREY ALLOWED, 5' X 10' | X | X | | | |
| MOTORIZED FOLDING PARTITION | | | TOP SUPPORTED AND CONTINUOUSLY HINGED, MADE OF 3" THICK STEEL WITH FULL SOUND SEALS. THEY FEATURE AUTOMATIC FLOOR SEALS THAT DEPLOY WHEN POSITIONED. MARKERBOARD FINISHES ARE SUGGESTED FOR CLASSROOM USE. LARGE PARTITIONS SHOULD BE ELECTRONICALLY OPERATED, INTEGRATED WITH THE SCHOOL SYSTEM, AND SUPPORTED FROM THE BOTTOM IN A RECESSED MANNER. | X | X | | | |
| PAPER TOWEL DISPENSER | | | 1 PAPER TOWEL DISPENSER PER SINK | | X | X | | |
| SOAP DISPENSER | | | 1 SOAP DISPENSER PER SINK | | X | X | | |
| COMMERCIAL WASHER | GE | GTW750CPLDG | STAINLESS STEEL; ASTM A666, TYPE 304 WITH NUMBER 4 FINISH. ELECTRIC, 480 VOLTS, 40 LB CAPACITY, MINIMUM EXTRACTOR FORCE 140 G FACTOR | X | X | | | |
| COMMERCIAL DRYER | GE | GTD75ECPLDG | HEAVY DUTY EMBOSSED STEEL WITH ELECTROSTATICALLY APPLIED BACKED ENAMEL FINISH. | X | X | | | |
| MOP RACK | | | BROOM AND MOP HANGGERS FOR A MINIMUM OF TWELVE (12) HANGERS TO BE PROVIDED IN THE CONTRACT | X | X | | | |
| KITCHEN MENU SYSTEM DEVICE | | | RE: J-QFI 1.0 SF EQUIPMENT PLAN | X | X | | | REFERED TO IT DRAWINGS |
| LOCKERS | | | 12"W X 15"D, 2 TIER, 60" HIGH. 16 GA. DOOR WITH 20GA. BODY | X | X | | | |
| MIRROR | | | TOP EDGE 74 INCHES (1880 MM) MINIMUM ABOVE THE FINISH FLOOR OR GROUND &. BOTTOM EDGE OF THE REFLECTING SURFACE 40 INCHES (1015 MM) MAXIMUM | X | X | | | |
| GRAB BARS | | | AS REQUIRED BY ADA | X | X | | | |
| HOOKS | | | J-HOOKS | X | X | | | |
| TIME CLOCK | KRONOS | | EXISTING UNIT | | X | | | COORDINATE HEIGHT, DATA, POWER AND ROUGH-IN REQUIREMENTS WITH FBISD IT. REMOVE, PROTECT & REINSTALL EXISTITNG TIME CLOCK. |
| **KITCHEN OFFICE FURNITURE** | | | | | | | | |
| AUSTIN PARKWAY ES | | | | | | X | X | |
| PECAN GROVE ES | | | | | | X | X | |
| SETTLERS WAY ES | | | | | | X | X | |
| SUGAR MILL ES | | | | | | X | X | |
| HIGHLANDS ES | | | | | | X | X | |
| PALMER ES | | | | | | X | X | |
| HUNTERS GLEN ES | | | | | | X | X | |




1 OVERALL FLOOR PLAN
SCALE: 1/16" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL

REGISTERED ARCHITECT
ROBERT A. WEAVER
22653
STATE OF TEXAS

7/15/2025



MWA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

OVERALL
FLOOR PLAN

k-A.201

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\K-Hunters Glen ES\k-A.201 FLOOR PLAN.dwg, Jul 23, 2025 - 2:05pm




# 1 SLAB DEPRESSION PLAN

SCALE: 1/4" = 1'-0"

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\K-Hunters Glen ES\k-A.300 SLAB DIMENSION CONTROL PLAN.dwg Jul 23, 2025 - 2:05pm

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL
REGISTERED ARCHITECT
22651
STATE OF TEXAS
7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

SLAB DEPRESSION PLAN
k-A.200

## DOOR SCHEDULE

| DOOR # | DOOR WIDTH | DOOR HEIGHT | DOOR TYPE | DOOR MATERIAL | DOOR FINISH | FIRE RATING | FRAME THICKNESS | FRAME FINISH | KEY | HARDWARE | DETAILS | | | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | | SILL | JAMB | HEAD | |
| A005 | 3'-0" | X 7'-0" | SF4 | SOLID CORE | P LAM | NR | 4 1/2" | ANOD AL | | 103 | | 22/A00-01 | 16/A00-01 | |
| A006 | 3'-0" | X 7'-0" | SF4 | SOLID CORE | P LAM | NR | 4 1/2" | ANOD AL | | 501 | | 22/A00-01 | 16/A00-01 | |
| A007 | 3'-0" | X 7'-0" | SF4 | SOLID CORE | P LAM | NR | 4 1/2" | ANOD AL | | 341 | | 22/A00-01 | 16/A00-01 | |
| A008 | 3'-0" | X 7'-0" | SF4 | SOLID CORE | P LAM | NR | 4 1/2" | ANOD AL | | 501C | | 22/A00-01 | 16/A00-01 | |
| A012 | 4'-0" | X 7'-0" | HM1 | H.M. | PAINT | NR | 6" | PAINT HM | | 715V | 21/A00-01 | 04/A00-01 | 04/A00-01 | |
| 109A | 3'-0" | X 7'-0" | SF4 | SOLID CORE | P LAM | NR | 4 1/2" | ANOD AL | | 501H | | 22/A00-01 | 16/A00-01 | |
| 109B | 3'-0" | X 7'-0" | SF1 | ALUM/GLASS | ANOD AL | NR | 4 1/2" | ANOD AL | | C201AH | 18/A00-01 | 10&11/A00-01 | 23&24/A00-01 | CARD READER, CLOSER, BUZZER |
| 109C | 3'-0" | X 7'-0" | SF1 | ALUM/GLASS | ANOD AL | NR | 4 1/2" | ANOD AL | | C201AH | 18/A00-01 | 10&11/A00-01 | 23&24/A00-01 | CARD READER, CLOSER, BUZZER |
| 109D | 3'-0" | X 7'-0" | SF4 | SOLID CORE | P LAM | NR | 4 1/2" | ANOD AL | | 501H | | 22/A00-01 | 16/A00-01 | |




## 2 DOOR SCHEDULE

## FLOOR PLAN - GENERAL NOTES

1. REFER TO SHEET FOR GENERAL NOTES. GENERAL NOTES APPLY TO ALL SCHOOL KITCHENS.
2. REFER TO SHEET FOR PARTITION TYPES.
3. EXIXSTING EXPOSED CONDUITS AND DATA CABLING IN WIREMOLD TO BE ROUTED INSIDE WALLS (EXCEPT AT WAREWASH AREA BELOW TABLE HEIGHT AND DRY STORAGE ROOMS). PATCH AND REPAIR AS REQUIRED TO ACHIEVE SMOOTH CLEAN WALL SURFACE.

## PARTITION LEGEND

- EXISTING CMU PARTITION
- NEW CMU SCHEDULED PARTITION
- EXISTING METAL PARTITION
- NEW FRAMED SCHEDULED PARTITION

## FLOOR PLAN - KEYED NOTES

(NOT ALL NOTES USED ON EACH SHEET)

01 PROVIDE NEW MOP SINK UTILITY SHELF
RE: PLUMBING FOR MOP SINK
RE: SPEC 10 28 00 FOR UTILITY SHELF

02 REMOVE, STORE & REPLACE WALL MOUNTED FIRE EXTINGUISHER

03 PROVIDE NEW WALL MOUNTED FIRE EXTINGUISHER
RE: SPEC SECTIONS 10 44 13

04 PROVIDE NEW LOCKERS
RE: SPEC 10 51 13.

05 PROVIDE WASHER AND DRYER
RE: SPEC 11 45 20

06 REMOVE, PROTECT & REINSTALL WALL MOUNTED CLOCK.

07 PROVIDE CONDENSING UNIT
FOR WALK-IN COOLER/FREEZER
RE: MECHANICAL AND SPEC 11 40 00

08 PROVIDE POWER AND DATA FOR MENU BOARD.
RE: ELECTRICAL, TECHNOLOGY DRAWINGS & FOOD SEF


09 PROVIDE P-LAM SHELVING
REFER TO DETAIL FOR BRACKET SUPPORT

10 FURNITURE & NON FOOD SVE EQUIPMENT RETURN TO C
STORAGE

11 INSPECT & SREVICE TOLLING COUNTER DOORS. RETUR
NEW CONDITION.

12 COMMERCIAL CLOSED WASHER 40LB CAPACITY.
COMMERCIAL CLOSED DRYER 55LB CAPACITY.
BASIS OF DESIGN: WASHER; SPEED QUEEN SYN040
DRYER; SPEED QUEEN ST055.
REFER TO ELECTRICAL & PLUMBING FOR CONNECTIONS

## 3 FLOOR PLAN NOTES





## 1 KITCHEN PLAN

SCALE: 1/4" = 1'-0"












## 4 MAKERBOARD ELEVATION

SCALE: 1/2"=1'-0"





## 5 RAMP @ REAR DOOR

SCALE: 3/16"=1'-0"




## A

SCALE: 1/2"=1'-0"




ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL
7/15/2025


ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

KITCHEN PLAN

k-A.301

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\K-Hunters Glen ES\k-A.301 KITCHEN PLAN.dwg Jul 30, 2025 - 10:01am

## TEMPORARY KITCHEN FLOOR PLAN KEYED NOTES 05/A-A03-02

01 PROVIDE & INSTALL 555 SF OF RAM BOARD TO PROTECT EXISTING FLOORING. REMOVE AFTER CONSTRUCTION IS COMPLETE. CONTRACTOR MUST REPAIR FLOORING DAMAGED DURING CONSTRUCTION.

02 PROVIDE SCHEDULED PARTITIONS. BUILD PARTITIONS ON TOP OF RAM BOARD. DO NOT ATTACH PARTITIONS TO FLOOR.


03 ATTACH PARTITIONS TO EXISTING WALL. REPAIR WALL TO MATCH EXISTING AFTER CONSTRUCTION IS COMPLETE.

## TEMPORARY KITCHEN RCP KEYED NOTES 03/A-A03-02

04 ALL NEW SCHEDULED PARTITIONS AND CEILINGS FOR TEMPORARY STORAGE LAYOUT TO BE EPOXY PAINTED SW 7014 EIDER WHITE WITH SPECIFIED 4" RUBBER BASE. REMOVE WHEN CONSTRUCTION IS COMPLETED.

05 MOUNT TEMPORARY FLUORESCENT LIGHTS TO TEMPORARY CEILING.

## 3 KEYED NOTES
SCALE: 1/4"=1'-0"




## 4 TEMPORARY LAYOUT SECTION
SCALE: 1"=1'-0"




## 1 TEMPORARY KITCHEN RCP
SCALE: 1/4" = 1'-0"




## 2 TEMPORARY KITCHEN FLOOR PLAN
SCALE: 1/4" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL
REGISTERED ARCHITECT
22651
STATE OF TEXAS
7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

TEMPORARY KITCHEN LAYOUT
k-A.302

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\K-Hunters Glen ES\k-A.302 TEMPORARY KITCHEN LAYOUT.dwg Jul 23, 2025 - 2:06pm

## RCP - GENERAL NOTES


1. CEILING GRID SHALL BE INSTALLED TO MATCH EXISTING GRID'S POINT OF ORIGIN. THIS WILL REDUCE NEED TO RE-LOCATE ABOVE CEILING DUCTS, SPRINKLER PIPING AND OTHER SUPPORT SYSTEMS.
2. REFER TO SHEET A00-01 FOR GENERAL NOTES. GENERAL NOTES APPLY TO ALL SEVEN SCHOOL KITCHEN REMODELS.
3. LIGHTING LEVELS SHOULD BE 50 FC IN PREPARATION AREAS, WARE WASH AND SERVING LINES, OR MEET MINIMUM HEALTH CODE LEVELS, WHICHEVER ITS GREATER. SEE MEP PLANS
4. REPLACE HVAC DEVICES. REPLACE LIGHTING WITH 24"x24" LED LAY IN LIGHT AS SCHEDULED IN ELECTRICAL PLANS.
5. REFER TO MECHANICAL, ELECTRICAL SHEETS FOR DEVICE SCHEDULES.

## RCP - NUMBERED NOTES

01 PROVIDE 30"x30" MIN. ACCESS HATCH IN SOFFIT CENTERED ON MOTOR.


02 AFTER LOWERING THE NEW POWER RETRACTION SYSTEM. REPAIR AND PAINT SOFFITS AND SIDWALLS OF FURR TO MATCH EXISTING.

## 2 RCP GENERAL NOTES




## 3 FOOD SERVICE AREA ELEVATION

SCALE: 3/16" = 1'-0"




## 1 REFLECTED CEILING PLAN

SCALE: 1/4" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL

7/15/2025



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING


REFLECTED CEILING PLAN

k-A.401

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\K-Hunters Glen ES\k-A.401 REFLECTED CEILING PLAN.dwg Jul 23, 2025 - 2:06pm




## 10 MOPSINK ELEVATIONS
SCALE: 1/4"=1'-0"




## 11 LOCKER HOUSEKEEPING PAD
SCALE: 3"=1'-0"

## PAINT COLOR SCHEDULE
UNLESS OTHERWISE INDICATED FIELD COLOR IS PT-1 (SW 7014 EIDER WHITE)


SW 7014 EIDER WHITE (EPOXY PAINT)

## WALL TILE
CERAMIC WALL TILE (WT-1)
REFER TO TILE PATTERN AT SERVING AND RESTROOM
FIELD WALL TILE: DALTILE RITTENHOUSE SQUARE K175 BISCUIT (3X6)

## QUARRY TILE
QUARRY TILE AND BASE - SURE-STEP II OQ30
TILE COLOR SELECTION TO BE APPROVED BY FBISD
EPOXY GROUT COLOR: STERLING SILVER BY LATICRETE


A — PROVIDE ROOM SIGN TO REPLACE EXISTING. SEE LAYOUT FOR TYPE A OR TYPE B SIGN LOCATIONS.

## 2 FLOOR FINISH LEGEND





## 1 FINISH FLOOR PLAN
SCALE: 1/4" = 1'-0"

ALL FINISHED NOT DENOTED IN DRAWINGS SHALL BE SELECTED DURING THE SUBMITTAL PROCESS





## TYPE A
ROOM SIGNAGE - FIXED NAMES





## TYPE B
KITCHEN RESTROOM SIGNAGE


## 3 ROOM SIGNAGE
SCALE: 6"=1'-0"




## 5 FLOOR TRANSITION - THRESHOLD
SCALE: 3"=1'-0"





## 6 RR ELEVATIONS
SCALE: 1/4"=1'0"





WALL TILE PATTERN - RESTROOM


## 4 WALL TILE PATTERN
SCALE: 1/4"=1'0"




## 7 UTILITY ELEVATIONS
SCALE: 1/4"=1'0"




## 8 STOREFRONT ELEVATIONS
SCALE: 1/4"=1'-0"




## 9 STOREFRONT SECTION
SCALE: 1/2"=1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL
REGISTERED ARCHITECT
KEITH E. MOORE
22651
STATE OF TEXAS
7/15/2025


ARCHITECTS
AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

FINISH FLOOR PLAN

k-A.501

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\K-Hunters Glen ES\k-A.501 FINISH FLOOR PLAN.dwg Jul 28, 2025 - 5:40pm

1. AT WALLS THAT TERMINATE ABOVE CEILING, CONTRACTOR MAY CONTINUE METAL STUD FRAMED WALLS TO UNDERSIDE OF METAL DECK AND OMIT DIAGONAL BRACING IF HEIGHT DOES NOT EXCEED LIMITING HEIGHT OF METAL STUD AS INDICATED ON CHART BELOW.

2. PROVIDE INTERMEDIATE BRACING AT ALL PARTITIONS THAT EXCEED LIMITING HEIGHT OF METAL STUDS AS INDICATED ON CHART BELOW.

3. ALL BRACING SHALL BE AT STUD POINTS.

CMU PARTITION NOTES:


1. MATCH EXISTING CMU COURSING (TYP.):
   BRIARGATE ES (4" CMU STARTER COURSE)
   LAKE OLYMPIA MS (4" CMU STARTER COURSE)
   MISSION BEND ES (8" CMU STARTER COURSE)
   RIDGEMONT ES (8" CMU STARTER COURSE)
   TOWNEWEST ES (8" CMU STARTER COURSE)
2. PROVIDE CMU LINTELS FOR ALL OPENINGS IN INTERIOR CMU PARTITIONS. COORDINATE WITH STRUCTURAL.
3. PROVIDE A 3/4" SPACE BETWEEN TOP OF CMU AND STRUCTURE/DECK FOR POTENTIAL DEFLECTION. SEAL WITH APPROPRIATE CAULK.
4. REFER TO FINISH SCHEDULES FOR CERAMIC TILE LOCATIONS.

GYPSUM WALLBOARD PARTITION NOTES:


1. ALL METAL STUDS PARTITIONS ARE 25 GAUGE METAL STUDS AT 16" O.C. UNLESS OTHERWISE NOTED. IF THE LIMITING HEIGHT FOR A PARTITION TYPE IS EXCEEDED, INCREASE SIZE AND/OR GAUGE OF METAL STUDS AS INDICATED ON "LIMITING HEIGHT OF METAL STUDS" TABLE. NOTIFY THE ARCHITECT PRIOR TO INSTALLATION.

LIMITING HEIGHT OF METAL STUDS


| STUD SIZE | SPACING | 25 GA | 20 GA |
|---|---|---|---|
| 2-1/2" | 16" | 11'-3" | 12'-10" |
| 3-5/8" | 16" | 14'-4" | 16'-5" |
| 6" | 16" | 19'-9" | 24'-6" |





PARTITION A
SCALE: 1-1/2" = 1'-0"




PARTITION B1
SCALE: 1-1/2" = 1'-0"




PARTITION B2
SCALE: 1-1/2" = 1'-0"




PARTITION B3
SCALE: 1-1/2" = 1'-0"




PARTITION B4
SCALE: 1-1/2" = 1'-0"




PARTITION B5
SCALE: 1-1/2" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL

REGISTERED ARCHITECT
ROBERT A. MAGUIRE
#26511
STATE OF TEXAS

7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

PARTITION SCHEDULE

k-A.502

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\k-A.502 PARTITION SCHEDULE.dwg Jul 30, 2025 - 10:46am

# REFER TO FOODSERVICE DESIGN PROFESSIONALS SPECIFICATIONS AND SUBSEQUENT SHEETS FOR ADDITIONAL COORDINATION INFORMATION

**EXISTING EQUIPMENT NOTES (IF EXISTING EQUIPMENT IS PROVIDED IN THIS PROJECT):**

1. EXISTING EQUIPMENT NOT SCHEDULED FOR RE-USE TO BE RELOCATED BY THE K.E.C. COORDINATE WITH OWNER FOR NEW LOCATION.
2. ALL UTILITIES NOT SCHEDULED FOR RE-USE TO BE CAPPED & COVERED BY REQUIRED DISCIPLINE.
3. K.E.C. TO VERIFY ALL EXISTING UTILITY LOCATIONS & COORDINATE WITH ALL EQUIPMENT AS REQUIRED.

8 EXISTING EQUIPMENT NOTES
NOT TO SCALE

**ARCHITECT TO VERIFY/COORDINATE THE AESTHETIC OPTIONS BELOW (FOOD SERVICE COLOR, MATERIAL, OR SIGNAGE SELECTIONS) IF THESE ITEMS ARE PROVIDED IN THIS PROJECT:**

1. COUNTERTOPS: STONE (STAINLESS STEEL IS PROVIDED UNLESS OTHERWISE SPECIFIED).
2. TRAY SLIDES: CORIAN OR STONE (STAINLESS STEEL IS PROVIDED UNLESS OTHERWISE SPECIFIED).
3. COUNTER FRONTS: CERAMIC TILE, 3 FORM, OR PLASTIC LAMINATE.
4. SNEEZE GUARDS: STONE INSETS.
5. GENERAL COLOR, MATERIAL AND GRAPHIC SELECTIONS:
   - A. DISPLAY AIR SCREEN MERCHANDISERS - COLOR SELECTION: POWDER COAT OR PLASTIC LAMINATE (S/S IS PROVIDED UNLESS OTHERWISE SPECIFIED).
   - B. BAKERY DISPLAY CASES - COLOR SELECTION: POWDER COAT OR PLASTIC LAMINATE (S/S IS PROVIDED UNLESS OTHERWISE SPECIFIED).
   - C. PASS THRU OR REACH IN HOLDING CABINETS - COLOR SELECTION: POWDER COAT (MFG.: TRUE) OR PLASTIC LAMINATE (MFG.: TRAULSEN) (S/S IS PROVIDED UNLESS OTHERWISE SPECIFIED).
   - D. HANGING HEAT LAMPS - TRACK AND FIXTURE COLOR SELECTION.
   - E. HEATED MERCHANDISERS.
   - F. PORTABLE GUIDE RAILS - STANCHION AND BELT COLOR SELECTION.
   - G. POPCORN MACHINE - SIGNAGE SELECTION.
   - H. BOTTLE COOLER - SIGNAGE SELECTION.
   - I. GRAPHICS PACKAGE INFORMATION.
   - J. HOT FOOD WELL COVERS.
6. ARCHITECT TO VERIFY/COORDINATE THE FINISHES BELOW:
   - A. WALLS: CERAMIC TILE, FLAT FRP, OR MOLDED FRP (SMOOTH, IMPERVIOUS, AND EASILY CLEANABLE AS APPROVED BY LOCAL JURISDICTION).
   - B. CEILINGS: REMOVABLE VINYL FACE TILE (SMOOTH, IMPERVIOUS, AND EASILY CLEANABLE AS APPROVED BY LOCAL JURISDICTION).
   - C. FLOORS: TILE, EPOXY, OR RUBBERIZED FLOORING SYSTEM (SMOOTH, IMPERVIOUS, EASILY CLEANABLE AND SLIP RESISTANT AS APPROVED BY LOCAL JURISDICTION) (COORDINATE FLOOR TILE TRANSITION AT SERVING LINES).
   - D. FLOORS: WALK-IN ASSEMBLY - EXTEND KITCHEN FLOOR FLUSH INTO WALK-IN ASSEMBLY WITH COVED BASE.
   - E. FURR DOWNS ABOVE SERVING COUNTERS.

5 ARCHITECTURAL COORDINATION NOTES
NOT TO SCALE

**CRITICAL NOTES:**

1. CONTRACTOR MUST COORDINATE AND VERIFY ALL DIMENSIONS WITH FOOD SERVICE EQUIPMENT SHOP DRAWINGS AND MANUFACTURER'S DATA. DIMENSIONS SHOWN ARE FOR DESIGN AND BIDDING PURPOSES ONLY.
2. WALK-IN ASSEMBLY DOORS MUST BE LEFT OPEN WHILE INTERIOR CONCRETE FLOOR CURES.
3. INSTALL PROTECTIVE COVER ON WALK-IN ASSEMBLY WALL PANELS BEFORE INSTALLING CONCRETE FLOORS AND CURBS.
4. REFER TO GENERAL SPECS - DIVISION 27 TO PROVIDE CONDUIT, DATA, AND INTERCONNECT THE PANIC ALARM INSIDE FREEZER TO THE BUILDING AUTOMATION SYSTEM FOR NOTIFICATION TO DISTRICT PERSONNEL IN THE EVENT OF STAFF ENTRAPMENT.
5. PIPING AND DRAINAGE SYSTEMS (SANITARY AND GREASE-LADEN). SYSTEMS MUST BE CLEANED AND FLUSHED BEFORE THE FINAL CONNECTION WITH FOOD SERVICE EQUIPMENT - CRITICAL (DIV. 22).

7 CRITICAL NOTES
NOT TO SCALE

**DIVISION 26 (ELECTRICAL) IS RESPONSIBLE FOR BUT NOT LIMITED TO:**

1. **DO NOT ROUGH IN FROM FDP DRAWINGS. REFER TO THE KITCHEN EQUIPMENT CONTRACTOR'S DIMENSIONED SHOP DRAWINGS. DIMENSIONS INDICATED ARE TO BE VERIFIED BY KITCHEN EQUIPMENT CONTRACTOR AND ADJUSTED AS REQUIRED BY EQUIPMENT AND FIELD CONDITIONS.**
2. SECTION 11 40 00 TO VERIFY UTILITY REQUIREMENTS OF ANY EXISTING EQUIPMENT.
3. ALL CONNECTIONS SHALL BE MADE FOLLOWING LOCAL CODES AND NATIONAL STANDARDS, EXCEPT WHERE PLANS AND SPECIFICATIONS EXCEED THOSE CODES AND STANDARDS.
4. VERIFY ALL ELECTRICAL REQUIREMENTS WITH ENGINEERING DRAWINGS.
5. ROUGH-IN AND FINAL CONNECTION OF ELECTRICAL SYSTEMS TO FOOD SERVICE EQUIPMENT, WALK-IN ASSEMBLIES, AND BETWEEN COMPONENTS (INCLUDING MATERIALS AND LABOR). ACCESSORIES PROVIDED LOOSE WITH FOOD SERVICE EQUIPMENT BY SECTION 11 40 00 TO BE FIELD INSTALLED BY DIVISION 26.
6. EMPTY EMT CONDUIT WITH PULL-WIRE AND WIDE-SWEEP BENDS FOR REFRIGERANT PIPING TO REMOTE FOOD SERVICE EQUIPMENT REFRIGERATION SYSTEMS.
7. EMPTY EMT CONDUIT WITH PULL-WIRE AND WIDE-SWEEP BENDS FOR INTERCONNECT CABLES BETWEEN LAN AND POS TERMINALS, CHANGE-MAKERS, PRE-CHECK UNITS, PRINTERS, CPUS, ETC. DIVISION 26 TO VERIFY WHERE THE CONDUIT IS TO RUN FOR POS SYSTEM (I.E., MANAGER'S OFFICE OR IDF ROOM).
8. EMPTY EMT CONDUIT WITH PULL-WIRE AND WIDE-SWEEP BENDS FOR FIRE SUPPRESSION SYSTEMS. INTERCONNECT FIRE PROTECTION SYSTEM TO PANEL BOX SHUNT TRIPS AND BUILDING ALARM.
9. WALK-IN LIGHT FIXTURE INSTALLATION (PROVIDED LOOSE BY SECTION 11 40 00) (IF WALK-IN IS PROVIDED IN THIS PROJECT).
10. TABLE LIMIT SWITCH INSTALLATION (PROVIDED LOOSE BY SECTION 11 40 00) (IF DISHMACHINE IS PROVIDED IN THIS PROJECT).
11. ELECTRICAL MATERIALS AND DEVICES (SHUNT-TRIP BREAKERS, SURGE PROTECTORS, LIGHTING CONTROL DEVICES, CONDUIT, WIRE, ETC.).
12. SWITCHES AND STAINLESS STEEL DISCONNECTS AS REQUIRED (PROVIDE, LOCATE, AND INSTALL – TO BE IN AN ACCESSIBLE LOCATION).
13. CHARGING STATIONS FOR FORKLIFTS, PALLET STACKERS, AND PALLET JACKS (SIZE, PROVIDE, LOCATE, AND INSTALL) (IF EQUIPMENT IS PROVIDED IN THIS PROJECT).
14. INTERCONNECTION BETWEEN CONDENSATE FAN AND DISHMACHINE CONTROL PANEL (IF EQUIPMENT IS PROVIDED IN THIS PROJECT).
15. INTERCONNECTION BETWEEN EXHAUST HOOD FANS AND SWITCH (IF EQUIPMENT IS PROVIDED IN THIS PROJECT).
16. INTERCONNECTION BETWEEN EXHAUST HOOD LIGHTS AND SWITCH (IF EQUIPMENT IS PROVIDED IN THIS PROJECT).
17. DOOR HEATERS, LIGHTS, COILS, AND PRESSURE RELIEF PORTS PRE-WIRED TO JUNCTION BOX AT TOP OF WALK-IN ASSEMBLIES (IF EQUIPMENT IS PROVIDED IN THIS PROJECT) PROVIDED BY SECTION 11 40 00. FINAL CONNECTION BY DIV. 26.
18. IF ANY ELECTRICAL ACCESSORIES, FITTINGS, AND CORD/PLUGS ARE PROVIDED LOOSE WITH EQUIPMENT BY 11 40 00, DIV.26 IS TO ATTACH TO EQUIPMENT AND PROVIDE FINAL CONNECTION.
19. PROVIDE WATERPROOF RECEPTACLES IN WET AREAS.
20. ALL ELECTRICAL CONNECTIONS BENEATH EXHAUST HOODS (IF EQUIPMENT IS PROVIDED IN THIS PROJECT) TO EXTEND TO SHUNT TRIP BREAKERS WITH ELECTRICAL PANEL BOX FOR SHUTDOWN DURING FIRE MODE.
21. RECEPTACLES ARE TO BE PRE-WIRED TO THE JUNCTION BOX OR LOAD CENTER FOR FINAL CONNECTION BY DIVISION 26.
22. ALL ELECTRICAL LIGHTING, POWER, AND DISTRIBUTION SYSTEMS.
23. DO NOT INTERCONNECT MORE THAN THREE (3) CONVENIENCE OUTLETS ON ONE (1) BREAKER.
24. OTHER THAN CONVENIENCE OUTLETS, ALL ELECTRICAL CONNECTIONS SHOWN ON FOOD SERVICE PLANS ARE DEDICATED BREAKERS.
25. DOORBELL AT RECEIVING DOOR (PROVIDE AND INSTALL – TO BE AUDIBLE THROUGHOUT KITCHEN, OFFICE, AND DRY STORAGE ROOM).
26. ADEQUATE LIGHTING AT RECEIVING DOOR.
27. PROVIDE AND INSTALL TWO EMERGENCY STROBE BEACONS THAT INTERCONNECT TO PANIC ALARM IN WALK-IN FREEZER. ONE (1) IN KITCHEN ABOVE WALK-IN FREEZER DOOR ONE (1) IN CAFETORIUM (IF WALK-IN IS PROVIDED IN THIS PROJECT). REFER TO GENERAL SPECIFICATIONS FOR ADDITIONAL DETAILS.
28. DEDICATED CIRCUIT FOR HEATED DRAIN LINE CONNECTION IN WALK-IN FREEZER AT EACH COIL (IF WALK-IN IS PROVIDED IN THIS PROJECT).

**NOTE: ELECTRICAL CONNECTIONS INDICATED ARE THOSE REQUIRED FOR THE FOOD SERVICE EQUIPMENT AND THOSE REQUIRED FOR SUPPORT EQUIPMENT FURNISHED BY DIVISION 26. FOR ADDITIONAL REQUIREMENTS, REFER TO THE ELECTRICAL ENGINEER'S DRAWINGS.**

6 ELECTRICAL COORDINATION NOTES
NOT TO SCALE

**DIVISION 22 (PLUMBING) RESPONSIBLE FOR BUT NOT LIMITED TO:**

1. **DO NOT ROUGH-IN FROM FDP DRAWINGS. REFER TO THE KITCHEN EQUIPMENT CONTRACTOR'S DIMENSIONED SHOP DRAWINGS. DIMENSIONS INDICATED ARE TO BE VERIFIED BY KITCHEN EQUIPMENT CONTRACTOR AND ADJUSTED AS REQUIRED BY EQUIPMENT AND/OR FIELD CONDITIONS.**
2. SECTION 11 40 00 TO VERIFY UTILITY REQUIREMENTS OF ANY EXISTING EQUIPMENT.
3. ALL CONNECTIONS SHALL BE MADE IN ACCORDANCE WITH LOCAL CODES AND NATIONAL STANDARDS, EXCEPT WHERE PLANS AND SPECIFICATIONS EXCEED THOSE CODES AND STANDARDS.
4. VERIFY ALL PLUMBING REQUIREMENTS WITH ENGINEERING DRAWINGS.
5. EMPTY PVC CONDUIT WITH WIDE-SWEEP BENDS FOR REFRIGERANT PIPING TO BEVERAGE LINES, CO2 LINES, AND REMOTE FOOD SERVICE EQUIPMENT REFRIGERATION SYSTEMS.
6. ROUGH-IN AND FINAL PLUMBING CONNECTIONS TO FOOD SERVICE EQUIPMENT AND BETWEEN COMPONENTS (INCLUDING MATERIALS AND LABOR). ACCESSORIES PROVIDED LOOSE WITH FOOD SERVICE EQUIPMENT BY SECTION 11 40 00 TO BE FIELD INSTALLED BY DIVISION 22. THIS INCLUDES BUT IS NOT LIMITED TO INSTALLATION OF ALL FAUCETS (WATER FILL FAUCETS, PRE-RINSE FAUCETS, ETC.), HOSES, GAS DISCONNECTS, AND DRAINS FROM EQUIPMENT POINT OF CONNECTION TO BUILDING PLUMBING SYSTEMS. ALL DRAIN LINES ARE PROVIDED AND INSTALLED BY DIV. 22.
7. KITCHEN EQUIPMENT CONTRACTOR IS RESPONSIBLE FOR PROVIDING ALL FAUCETS (WATER FILL FAUCETS, PRE-RINSE FAUCETS, ETC.), DRAIN FITTINGS, MIXING VALVES, CONTROL VALVES, WATER PRESSURE REGULATORS, VACUUM BREAKERS, AND ALL ACCESSORIES FOR EQUIPMENT SPECIFIED UNDER 11 40 00. DIVISION 22 IS RESPONSIBLE FOR INSTALLATION.
8. INDIRECT DRAIN LINE RUNS FROM EQUIPMENT TO NEAREST DRAIN OR FLOOR SINK. LINES TO BE TYPE 'K' COPPER.
9. IF ANY PLUMBING ACCESSORIES OR FITTINGS ARE PROVIDED LOOSE WITH EQUIPMENT BY 11 40 00, DIV. 22 IS TO ATTACH TO EQUIPMENT AND PROVIDE FINAL CONNECTION.
10. GAS SUPPLY SYSTEMS WITH ALL COMPONENTS AND FITTINGS AS REQUIRED FOR A COMPLETE SYSTEM.
11. WATER SUPPLY SYSTEMS WITH ALL COMPONENTS AND FITTINGS AS REQUIRED FOR A COMPLETE SYSTEM.
12. COMPRESSED AIR SYSTEMS WITH ALL COMPONENTS AND FITTINGS AS REQUIRED FOR A COMPLETE SYSTEM (IF REQUIRED FOR THIS PROJECT).
13. PIPING AND DRAINAGE SYSTEMS (SANITARY AND GREASE-LADEN). SYSTEMS MUST BE CLEANED AND FLUSHED BEFORE THE FINAL CONNECTION WITH FOOD SERVICE EQUIPMENT - CRITICAL.
14. FLOOR SINKS (PROVIDE AND INSTALL). FLANGE AND GRATES TO BE FLUSH WITH FINISHED FLOOR.
15. FLOOR DRAINS (PROVIDE AND INSTALL). FLANGE AND GRATES TO BE FLUSH WITH FINISHED FLOOR.
16. TRENCH DRAINS (PROVIDE AND INSTALL). TRENCH LINERS PROVIDED BY 11 40 00. FLANGE AND LINERS TO BE FLUSH WITH FINISHED FLOOR.
17. GREASE TRAPS AS REQUIRED. VERIFY WITH LOCAL CODES TO BYPASS OR PIPE THRU GREASE TRAP AND/OR INTERCEPTOR.
18. P-TRAPS AS REQUIRED (INCLUDING ALL DISPOSERS).
19. INTERCONNECT WATER THRU WATER FILTER (FILTER PROVIDED BY 11 40 00 UNLESS OTHERWISE SPECIFIED) TO EQUIPMENT.
20. GAS QUICK DISCONNECT INSTALLATION (QUICK DISCONNECT PROVIDED BY 11 40 00).
21. SAFETY RESTRAINT CABLE INSTALLATION (SAFETY RESTRAINT CABLE PROVIDED BY 11 40 00).
22. SPECIFIED COUPLINGS AND PIPING TO ALL EQUIPMENT FURNISHED BY 11 40 00.
23. AIR COMPRESSORS (IF REQUIRED FOR THIS PROJECT) (SIZE, PROVIDE, AND INSTALL, UNLESS OTHERWISE SPECIFIED).
24. WATER SOFTENERS (IF REQUIRED FOR THIS PROJECT) (SIZE, PROVIDE, AND INSTALL, UNLESS OTHERWISE SPECIFIED).
25. PRESSURE BOILERS (IF REQUIRED FOR THIS PROJECT) (SIZE, PROVIDE, AND INSTALL, UNLESS OTHERWISE SPECIFIED).
26. HAND SINKS (PROVIDE (UNLESS OTHERWISE SPECIFIED) AND INSTALL). PROVIDE HOT WATER TEMPERING VALVE IF REQUIRED. WATER TEMPERATURE TO BE AT LEAST 100 DEGREES AND FLOW FOR AT LEAST 20 SECONDS.
27. ICE BIN DRAIN INSULATION (IF ICE MACHINE IS PROVIDED IN THIS PROJECT) (PROVIDE AND INSTALL).
28. UNIONS AT DISPOSER SOLENOID VALVES (IF DISPOSER IS PROVIDED IN THIS PROJECT) (PROVIDE AND INSTALL).
29. BACK FLOW PREVENTION AS REQUIRED (PROVIDE AND INSTALL - INCLUDING ALL DISPOSERS). BACK- SIPHONAGE SHALL BE INSTALLED AT ALL FIXTURES AND EQUIPMENT WHERE BACKFLOW AND/OR BACK-SIPHONAGE MAY OCCUR AND WHERE A MINIMUM AIR GAP CANNOT BE PROVIDED BETWEEN THE WATER TO THE FIXTURE OR EQUIPMENT AT ITS FLOOD/LEVEL RIM. VACUUM BREAKERS, WHEN FURNISHED WITH EQUIPMENT, SHALL OVERRIDE THE ABOVE, IF ACCEPTABLE WITH APPLICABLE CODES. DIVISION 22 RESPONSIBLE FOR VERIFYING REQUIREMENT WITH LOCAL CODES.
30. JANITOR SINK WITH FAUCET (PROVIDE AND INSTALL).
31. FREEZE PROOF HYDRANT AT EXTERIOR OF BUILDING BY RECEIVING DOOR (PROVIDE AND INSTALL).
32. REVERSE OSMOSIS SYSTEMS (SIZE, PROVIDE (UNLESS OTHERWISE SPECIFIED), LOCATE AND INSTALL).
33. ALL PIPING WITHIN COUNTER BODY OR UNDER FABRICATED COUNTERS TO BE RUN TO A CONNECTION POINT BELOW COUNTER BODY BY SECTION 11 40 00. FINAL CONNECTION BY DIVISION 22.
34. EXHAUST HOOD CONDENSATE DRAIN CONNECTIONS (IF EXHAUST HOOD IS PROVIDED IN THIS PROJECT) (PROVIDE AND INSTALL).
35. INTERCONNECTION OF 1/2" CW TO PRE-RINSE AND DISPOSERS CONE/BODY INLETS PIPED THROUGH SOLENOID AND VACUUM BREAKER (IF DISPOSER IS PROVIDED IN THIS PROJECT).
36. FIRE SYSTEM PIPING. EXPOSED PIPING TO BE CHROME PLATED.
37. PIPE 1/2" COLD WATER TO SWIRL INLETS AT DISPOSERS (IF DISPOSER IS PROVIDED IN THIS PROJECT).
38. WATER TREATMENT FOR ICE BUILDERS (NON-CHLORINATED WATER WITH A PH LEVEL OF 10 OR HIGHER) AND ANY DRAINS AND OVERFLOWS. PIPING FROM ICE BUILDERS TO TUMBLE CHILLERS BY DIV. 23 (IF ICE BUILDERS AND TUMBLE CHILLERS ARE PROVIDED IN THIS PROJECT).

**NOTE: WATER AND DRAIN CONNECTIONS INDICATED ARE THOSE REQUIRED FOR THE FOOD SERVICE EQUIPMENT AND THOSE REQUIRED FOR SUPPORT EQUIPMENT FURNISHED BY DIVISION 22. FOR ADDITIONAL WATER AND DRAIN REQUIREMENTS REFER TO MECHANICAL DRAWINGS.**

**NOTE: REFER TO ELECTRICAL/MECHANICAL DRAWINGS FOR REQUIREMENTS OF EXHAUST FANS AND MAKE-UP AIR HANDLERS AND LOCATION OF AN INTERLOCK AND START/STOP CONTROLS TO BE LOCATED WITHIN FOOD SERVICE AREA BY DIVISION 26.**

4 PLUMBING COORDINATION NOTES
NOT TO SCALE

**DIVISION 23 (MECHANICAL) RESPONSIBLE FOR BUT NOT LIMITED TO:**

1. **DO NOT ROUGH-IN FROM FDP DRAWINGS. REFER TO THE KITCHEN EQUIPMENT CONTRACTOR'S DIMENSIONED SHOP DRAWINGS. DIMENSIONS INDICATED ARE TO BE VERIFIED BY KITCHEN EQUIPMENT CONTRACTOR AND ADJUSTED AS REQUIRED BY EQUIPMENT AND/OR FIELD CONDITIONS.**
2. SECTION 11 40 00 TO VERIFY UTILITY REQUIREMENTS OF ANY EXISTING EQUIPMENT.
3. ALL CONNECTIONS SHALL BE MADE FOLLOWING LOCAL CODES AND NATIONAL STANDARDS, EXCEPT WHERE PLANS AND SPECIFICATIONS EXCEED THOSE CODES AND STANDARDS.
4. VERIFY ALL MECHANICAL REQUIREMENTS WITH ENGINEERING DRAWINGS.
5. EMPTY EMT CONDUIT WITH PULL-WIRE AND WIDE-SWEEP BENDS FOR REFRIGERANT PIPING TO REMOTE FOOD SERVICE EQUIPMENT REFRIGERATION SYSTEMS.
6. ROUGH-IN AND FINAL CONNECTION OF MECHANICAL SYSTEMS TO FOOD SERVICE EQUIPMENT, WALK-IN ASSEMBLIES, AND BETWEEN COMPONENTS (INCLUDING MATERIALS AND LABOR).
7. TESTING AND BALANCING FOR ROOMS AND EXHAUST HOODS TO BE PERFORMED BY MECHANICAL CONTRACTOR. BALANCE REPORT FOR FOOD SERVICE EXHAUST HOODS TO BE PROVIDED TO FOODSERVICE DESIGN PROFESSIONALS (FDP) IMMEDIATELY UPON COMPLETION (SEND TO HOUSTON.SUBMITTAL@FDP.ORG FOR HOUSTON OFFICE AND DALLAS.SUBMITTAL@FDP.ORG FOR DALLAS OFFICE) AND MUST BE SUBMITTED WITH O&M MANUALS.
8. EXHAUST HOODS, CONDENSATE HOODS, FIRE SUPPRESSION SYSTEMS, CONNECTIONS AND CONTROLS (PROVIDE AND INSTALL – *UNLESS OTHERWISE SPECIFIED*). PROVIDE TEMPERED AIR AT ALL SUPPLY DUCTS.
   - A. IF EXHAUST/CONDENSATE HOODS AND FIRE SUPPRESSION SYSTEMS ARE SPECIFIED UNDER SECTION 11 40 00, DIVISION 23 IS RESPONSIBLE FOR ALL EXHAUST AND CONDENSATE HOOD CONNECTIONS (PROVIDE AND INSTALL).
9. VFD SYSTEM AND CONTROLLERS, WHEN REQUIRED BY CODE (PROVIDE AND INSTALL).
10. PROVIDE AND INSTALL ALL VENTILATION (DIRECT OR INDIRECT), AIR CONDITIONING AND HEATING SYSTEMS (UNLESS OTHERWISE SPECIFIED).
11. COORDINATE SUPPLY AND RETURN DUCTS ABOVE SERVING COUNTERS OR OPEN-AIR REFRIGERATED MERCHANDISERS. NO COLD AIR TO BLOW DIRECTLY ON HOT FOOD COUNTERS.
12. COORDINATE SUPPLY AND RETURN DUCTS AWAY FROM EQUIPMENT WITH TOP MOUNTED REFRIGERATION. NO COLD AIR TO BLOW DIRECTLY ON COMPRESSORS.
13. MECHANICAL CONTRACTOR TO LOCATE TEMPERATURE MONITORS WITHIN RETURN DUCTS.
14. CIRCULATING AIR ABOVE WALK-IN ASSEMBLIES (PROVIDE AND INSTALL).
15. CIRCULATING AIR ABOVE AND IN AIR GAPS AT WAREHOUSE COLD STORAGE ASSEMBLIES (PROVIDE AND INSTALL).
16. WATER CHILLERS AS REQUIRED (IF EQUIPMENT IS PROVIDED IN THIS PROJECT) (PROVIDE, SIZE AND LOCATE).
17. PIPING FROM ICE BUILDERS TO TUMBLE CHILLERS (IF EQUIPMENT IS PROVIDED IN THIS PROJECT) (PROVIDE, SIZE AND LOCATE).

3 MECHANICAL COORDINATION NOTES
NOT TO SCALE

**GENERAL CONTRACTOR RESPONSIBLE FOR BUT NOT LIMITED TO:**

1. ANY WALL PENETRATION REQUIRED FOR FOOD SERVICE EQUIPMENT UTILITIES. ESCUTCHEON PLATES OR S/S SLEEVES TO BE PROVIDED AND INSTALLED AS NEEDED.
2. BULK FREEZER VENTILATION PIPE (IF BULK FREEZER IS PROVIDED IN THIS PROJECT) (PROVIDE AND INSTALL, UNLESS OTHERWISE SPECIFIED).
3. CORE DRILLING FOR GUIDE RAILS (IF GUIDE RAILS ARE PROVIDED IN THIS PROJECT).
4. REFRIGERATION ROOF CURBS / ROOF JACK (IF REFRIGERATION SYSTEM IS PROVIDED IN THIS PROJECT AND LOCATED ON ROOF).
5. INTERIOR BOLLARDS (IF REQUIRED FOR THIS PROJECT) – TO BE EPOXY PAINTED PER LOCAL CODES (PROVIDE AND INSTALL).
6. FURNISH AND INSTALL 3/4" PLYWOOD BLOCKING IN THE WALL FOR MOUNTING EQUIPMENT FURNISHED BY SECTION 11 40 00 AS REQUIRED.
7. WALK-IN DEPRESSIONS (TO BE DEAD LEVEL) AND SAND LEVELING BED (IF WALK-IN IS PROVIDED IN THIS PROJECT AND RECESS IS SHOWN).
8. STRUCTURAL BRACING FOR BULK WALK-IN CEILING PANELS IF REQUIRED.
9. MENU SYSTEM VIDEO MONITORS IN SERVERY (UNLESS OTHERWISE SPECIFIED).
10. STRUCTURAL BRACING FOR MENU SYSTEM VIDEO MONITORS IF REQUIRED.
11. INTERIOR/EXTERIOR REFRIGERATION PENETRATIONS AND SLEEVES AT BUILDING PENETRATIONS.
12. DOORSCOPE VIEWER (PEEPHOLE) WITH WIDE VIEWING ANGLE AT RECEIVING DOOR.
13. CANOPY AT RECEIVING DOOR. COORDINATE HEIGHT WITH THE HEIGHT OF RECEIVING DOOR (8') AND THE MOUNTING HEIGHT OF AIR SCREEN ABOVE THE DOOR.
14. SOAP AND TOWEL DISPENSER PROVIDED BY OWNER. G.C. RESPONSIBLE FOR INSTALLATION.
15. WASHER AND DRYER (PROVIDE AND INSTALL, UNLESS OTHERWISE SPECIFIED).
16. DWARF WALL AT EXPOSED FRONT/ENDS OF CAFETERIA SERVING COUNTERS WITH FINISH AS SELECTED BY ARCHITECT (IF REQUIRED IN THIS PROJECT).

2 GENERAL CONTRACTOR COORDINATION NOTES
NOT TO SCALE

**HEALTH DEPARTMENT REQUIREMENTS (VERIFY WITH LOCAL JURISDICTIONS):**

1. FLOORS: VERIFY WITH DIVISION 9. FLOORS TO BE SMOOTH, IMPERVIOUS, EASILY CLEANABLE AND SLIP RESISTANT.
2. WALLS: VERIFY WITH ARCHITECTURAL DOCUMENTS. WALLS TO BE SMOOTH, IMPERVIOUS, AND EASILY CLEANABLE.
3. CEILING: LAY-IN TILES. CEILING TILES TO BE SMOOTH, IMPERVIOUS, AND EASILY CLEANABLE.
4. EMPLOYEE TOILET: TO BE LOCATED OFF MAIN CORRIDOR AND ADJACENT TO MAIN KITCHEN. RESTROOM MUST HAVE A VESTIBULE AND NOT OPEN TO KITCHEN / PREP AREAS. TOILETS TO BE WELL VENTILATED.
5. LAVATORIES: WALL HUNG LAVATORIES LOCATED WITHIN ALL FUNCTIONAL WORKING AREAS.
6. UTENSIL CLEANING/SANITIZING: ACCOMPLISHED IN UTENSIL WASH AREA WITH (3) 2'-0" x 2'-2" x 15" MINIMUM DEEP SINKS AND WAREWASH MACHINE.
7. MECHANICAL CLEANING/SANITIZING OF TABLEWARE: ACCOMPLISHED BY WAREWASH MACHINE.
8. STOREROOMS: AMPLE DAILY STORAGE PROVIDED IN ENCLOSED STORE ROOMS. STORE ROOMS TO BE VENTILATED AND MAINTAIN PROPER TEMPERATURE.
9. WATER HEATER: LOCATED IN THE MECHANICAL ROOM ADJACENT TO KITCHEN. TO BE SIZED TO PROVIDE AMPLE WATER TO MAINTAIN PROPER WATER TEMPERATURE THROUGHOUT HOURS OF OPERATION.
10. GREASE TRAP: LOCATED AT EXTERIOR OF BUILDING. REFER TO ENGINEER'S DRAWINGS.
11. FOOD SERVICE EQUIPMENT: ALL FLOOR-MOUNTED EQUIPMENT IS TO BE SEALED TO THE FLOOR TO PROVIDE AN EASILY CLEANABLE SURFACE AND PREVENT SEEPAGE. EQUIPMENT NOT MOUNTED TO THE FLOOR IS TO BE WALL MOUNTED ON WALL CARRIERS, OR ELEVATED ON LEGS TO PROVIDE AT LEAST A SIX-INCH CLEARANCE BETWEEN FLOOR AND EQUIPMENT.
12. MOP SINK: LOCATED IN JANITOR CLOSET OFF MAIN KITCHEN CORRIDOR, AND LOCATED IN CLOSE PROXIMITY TO THE SERVERY WAREWASH AREA.
13. EXHAUST HOODS: EXHAUST HOODS PROVIDED OVER COOKING EQUIPMENT WITH LIQUID CHEMICAL ANSUL FIRE EXTINGUISHING SYSTEM.
14. LIGHTING AND PROTECTIVE SHIELDING: RECESSED CEILING-MOUNTED FLUORESCENT LIGHT FIXTURES FITTED WITH CLEAR LEXAN DIFFUSERS.
15. GARBAGE AND REFUSE: CENTRAL TRASH COLLECTION PROVIDED FOR BUILDING LOCATED NEAR RECEIVING AREA ON SMOOTH CONCRETE SURFACE.
16. POISONOUS AND TOXIC MATERIAL STORAGE: LOCATED IN RESPECTIVE JANITOR CLOSETS WITH LOCKING HARDWARE.

1 HEALTH DEPARTMENT COORDINATION NOTES
NOT TO SCALE

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL

FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
DOCUMENT NOT VALID UNLESS THIS DOCUMENT APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 48854119 ON: 07/18/2025

MWA ARCHITECTS


ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

FS GENERAL COORDINATION NOTES

K-QF0.0

| FOOD SERVICE DRAWING INDEX | |
|---|---|
| FDP SHEET NUMBER | FDP SHEET NAME |
| K-QF0.0 | FS GENERAL COORDINATION NOTES |
| K-QF1.0 | FS EQUIPMENT PLAN |
| K-QF1.1 | FS FACILITY MODEL |
| K-QF1.2 | FS EQUIPMENT MODEL |
| K-QF1.3 | FS SPECIAL CONDITIONS & MECHANICAL PLAN |
| K-QF1.4 | FS PLUMBING PLAN |
| K-QF1.5 | FS ELECTRICAL PLAN |
| K-QF1.6 | FS CONDENSING UNITS |
| K-QF1.7 | FS WALK-INS |
| K-QF1.8 | FS SERVING LINE |
| K-QF1.9 | FS SERVING LINE |
| K-QF2.0 | FS DEMO PLAN |
| K-QF2.1 | FS TEMPORARY SERVING |
| K-QF3.1 | FS ELEVATIONS |
| K-QF4.1 | FS SECTIONS & DETAILS |
| K-QF4.2 | FS DETAILS |
| K-QF4.3 | FS DETAILS |




1 FOOD SERVICE EQUIPMENT PLAN
1/4" = 1'-0"

| FOOD SERVICE EQUIPMENT SCHEDULE | | | | | |
|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR GENERAL CONTRACTOR & HEALTH DEPARTMENT COORDINATION NOTES | | | | | |
| FDP ITEM | FDP QTY | FDP DESCRIPTION | FDP REMARKS | MANUFACTURER | MODEL |
| 101 | 1 | AIR SCREEN | | MARS | STD248-1U A-OB |
| 102 | 1 | COLD STORAGE ASSEMBLY | | AMERICAN PANEL | |
| 103 | 1 | COLD STORAGE REFRIGERATION SYSTEM | | RDT | ZS1-02Z-C T3-AST |
| 104 | 2 | COLD STORAGE SHELVING | | METRO | METROMA X Q |
| 107 | 1 | DRY STORAGE SHELVING | | METRO | METROMA X Q |
| 108 | 1 | CAN RACK | | NEW AGE | 1250CK |
| 109 | 1 | ICE MACHINE W/ BIN | | MANITOWOC | UYF0310A |
| 110 | 1 | CLOTHES WASHER | | WHIRLPOOL | RESIDENTIAL |
| 110A | 1 | CLOTHES DRYER | | WHIRLPOOL | RESIDENTIAL |
| 111W | 1 | WALL MOUNTED OVERSHELF | | CUSTOM FABRICATED | |
| 122 | 1 | TWO COMPARTMENT SINK WITHOUT DISPOSER | | CUSTOM FABRICATED | |
| 123 | 1 | DISPOSER - 3HP | | SALVAJOR | 300-CA-18-ARSS-LD |
| 125 | 1 | 20 QT. MIXER W/STAND | | HOBART | HL2000 |
| 128 | 4 | UTILITY CART | | LAKESIDE | 522 |
| 129 | 3 | WORKTABLE W/S.BAR UT.RACK | | CUSTOM FABRICATED | |
| 138 | 4 | PAN RACK | | CRES COR | 207-UA-13 A |
| 139 | 1 | INSUL MOBILE PROOFER | | CRES COR | H-137-WS UA-12D |
| 151 | 2 | FIRE PROTECTION SYSTEM | | ANSUL | R102 |
| 152 | 1 | EXHAUST HOOD | EXISTING | | |
| 153 | 1 | EXHAUST HOOD | EXISTING | | |
| 161 | 2 | CONVECTION OVEN | | BLODGETT | DFG-200 DBL |
| 165 | 1 | TWO BURNER RANGE | | VULCAN | V2B18B |
| 172 | 1 | COMBI OVEN | | RATIONAL | ICP 6-FULL/6-FULL N/G |
| 186 | 2 | PASS-THRU HEATED CABINET-1DR | | TRAULSEN | AHF132WP |
| 188 | 2 | PASS-THRU REFRIGERATOR-1DR | | TRAULSEN | AHT132WPUT |
| 201M.1 | 1 | SERVING COUNTER-MODULAR | | COUNTERCRAFT | SCOL-408-MOD |
| 214 | 2 | CASH REGISTER | OWNER FURNISHED | | |
| 249 | 1 | THREE COMPARTMENT SINK NO DISPOSER | | CUSTOM FABRICATED | |
| 250 | 1 | DISHMACHINE | | HOBART | CL44-BAS |
| 254 | 2 | SOILED & CLEAN DISHTABLE | | CUSTOM FABRICATED | |
| 255 | 2 | MOBILE DRYING RACK | | METRO | PR48VX3 |
| 260 | 4 | HAND SINK | FURNISHED & INSTALLED BY DIV. 22 | | |
| 614 | 1 | FILL FAUCET | | T&S | B-0610 |
| 615 | 2 | MENU MONITOR | BY OWNER | | |
| 800 | 1 | 15 GAL. BRAISING PAN | | GROEN | BPM-15GA |
| 801 | 1 | S/S CORNER GUARDS | LOCATED ON EVERY EXPOSED CORNER THROUGHOUT KITCHEN | CUSTOM FABRICATED | |
| 802 | 1 | WALL BUMPERS | LOCATED ON ALL EXPOSED BUILDING WALLS | PAWLING | MD-1 |
| 803 | 1 | WATER SOFTENER | | HOBART | WS-40 |
| 804 | 4 | S/S SPLASH GUARDS | | CUSTOM FABRICATED | |

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL


FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
FCS
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
ELECTRONIC SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO: 48854119 ON: 07/18/2025


ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS EQUIPMENT PLAN

K-QF1.0

ISOMETRIC VIEWS WITHIN THIS DRAWING ARE NOT TO SCALE AND ARE PROVIDED FOR REFERENCE PURPOSES ONLY. ISOMETRIC VIEWS ARE NOT INTENDED FOR REGULATORY APPROVAL, PERMITTING, NOR CONSTRUCTION. REFER TO FLOOR PLANS AND DETAILS FOR SPECIFIC PROJECT INFORMATION.



1 FS FACILITY MODEL

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL

FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
FCSI 48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 48854119 ON: 07/18/2025

MWA ARCHITECTS


ARCHITECTS
AND PLANNING
CONSULTANTS

11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS FACILITY MODEL

K-QF1.1

ISOMETRIC VIEWS WITHIN THIS DRAWING ARE NOT TO SCALE AND ARE PROVIDED FOR REFERENCE PURPOSES ONLY. ISOMETRIC VIEWS ARE NOT INTENDED FOR REGULATORY APPROVAL, PERMITTING, NOR CONSTRUCTION. REFER TO FLOOR PLANS AND DETAILS FOR SPECIFIC PROJECT INFORMATION.



1 FS EQUIPMENT MODEL

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL

FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
46854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
ITEMS APPEARING ON THIS DOCUMENT WILL BE AUTHORIZED BY MELISSA MOORE, FCSI NO. 46854119 ON: 07/18/2025



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS EQUIPMENT MODEL

K-QF1.2


| FOOD SERVICE MECHANICAL SCHEDULE | | | | | | |
|---|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR MECHANICAL COORDINATION NOTES | | | | | | |
| FDP NO. | FDP QTY | FDP TYPE | FDP SIZE | FDP LOC | FDP CFM | FDP S.P. |
| M101 | 1 | EXHAUST | 4" X 16" | | 400 | 0.30" |
| M102 | 1 | EXHAUST | 4" X 16" | | 800 | 0.30" |
| M103 | 1 | DRYER VENT | 6" DIA. | | --- | --- |

NOTE:
SECTION 11 40 00 TO COORDINATE FINAL LOCATION AND SIZE OF WALL BLOCKING.





5 WALL BLOCKING DETAIL
NOT TO SCALE


NOTE:
SECTION 11 40 00 TO COORDINATE FINAL LOCATION OF ALL TRENCH LINERS WITH EQUIPMENT POUR PATH.





6 TRENCH LINER DETAIL
NOT TO SCALE





1 FOOD SERVICE SPECIAL CONDITIONS PLAN
1/4" = 1'-0"




CLOSURE PANEL DETAIL





ISOMETRIC - SUPPORT BRACKET





SECTION - CLOSURE PANEL

3 COLD STORAGE ASSEMBLY ENCLOSURE PANEL DETAIL
NOT TO SCALE




COLD STORAGE ASSEMBLY REFRIGERATION SYSTEM GROUND MOUNT 4" PLATFORM DETAIL
4 NOT TO SCALE

SLAB TO BE MODIFIED AS REQUIRED TO ALLOW FOR A 4 1/2" DEPRESSION SLAB. PROVIDE NEW LEVEL CONCRETE PAD FOR COLD STORAGE ASSEMBLY.




WALL SECTION @ EXTERIOR DOOR

2 COLD STORAGE ASSEMBLY 4 1/2" DEPRESSION DETAIL
NOT TO SCALE

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL

FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
488584119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 488584119 ON: 07/18/2025



ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

FS SPECIAL CONDITIONS & MECHANICAL PLAN

K-QF1.3

| FOOD SERVICE PLUMBING SCHEDULE | | | | | | |
|---|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR PLUMBING COORDINATION NOTES | | | | | | |
| FDP PNO | FDP PSIZE | FDP PCONN | FDP PSERVICE TO | FDP PLOC | FDP PAFF | FDP PREMARKS |
| | | | | | | <varies> |
| P5 | 3/4" | H & C WATER | JANITOR SINK | WALL | 48" | JANITOR SINK BY PLUMBER |
| P6 | 4" | FLOOR DRAIN | JANITOR SINK | FLOOR | VERIFY | JANITOR SINK BY PLUMBER |
| P7 | 3/4" | H & C WATER | HOSE BIBB | WALL | 18" | BTC |
| P10 | VERIFY | FLOOR DRAIN | GENERAL AREA DRAIN | FLOOR | VERIFY | --- |
| P11C | 1/2" | H & C WATER | FAUCET | WALL | 18" | FURNISHED & INSTALLED BY DIV. 22 |
| P11D | 1 1/2" | DIRECT DRAIN | HAND SINK | WALL | 15" | FURNISHED & INSTALLED BY DIV. 22 |
| P12 | VERIFY | FLOOR DRAIN | EQUIP. DRAIN | FLOOR | VERIFY | NO SLOPE |
| P15 | 4" | FLOOR DRAIN | FUNNEL FLOOR DRAIN | FLOOR | 0" | --- |
| P109 | 3/4" | COLD WATER | WATER/ ICE | WALL | 60" | BTC |
| P109A | 12" SQ. | FLOOR SINK | ICE MACHINE | FLOOR | 0" | FULL GRATE |
| P110 | 3/4" | H & C WATER | CLOTHES WASHER | WALL | 48" | BTC; VALVE BOX |
| P110A | 2" | INDIRECT DRAIN | CLOTHES WASHER | WALL | 48" | VALVE BOX |
| P122 | 3/4" | H & C WATER | FAUCET | WALL | 13" | BTC |
| P122A | 12" SQ. | FLOOR SINK | SINK | FLOOR | 0" | 3/4 GRATE |
| P123 | 3/4" | H & C WATER | FAUCET / DISPOSER | WALL | 13" | BTC |
| P123A | 2" | DIRECT DRAIN | DISPOSER | WALL | 10" | BTC |
| P161 | (2)3/4" | NATURAL GAS | CONVECTION OVEN | WALL | 18"/36" | BTC - 60 MBTU/HR EACH |
| P163A | 3/4" | NATURAL GAS | TILT BRAISING PAN | WALL | 18" | BTC - 65 MBTU/HR |
| P163B | 3/4" | H & C WATER | TILT BRAISING PAN | WALL | 36" | BTC |
| P165 | 1" | NATURAL GAS | RANGE | WALL | 18" | BTC - 70 MBTU/HR |
| P172 | (2)3/4" | COLD WATER | COMBI OVEN | WALL | 24"/48" | BTC - INTERCONNECT THRU FILTERS |
| P172A | 3/4" | COLD WATER | COMBI OVEN | WALL | 48" | BTC |
| P172B | 12"SQ. | FLOOR SINK | EQUIPMENT | FLOOR | 0" | 3/4 GRATE |
| P172C | (2)3/4" | NATURAL GAS | COMBI OVEN | WALL | 18"/36" | BTC - 105 MBTU/HR EACH |
| P172D | 3/4" | COLD WATER | COMBI OVEN | WALL | 66" | BTC; INTERCONNECT TO P172 |
| P172E | 3/4" | COLD WATER | COMBI OVEN WATER FILTER | WALL | 66" | BTC |
| P249 | 3/4" | H & C WATER | FAUCET | WALL | 13" | BTC |
| P249A | 12" SQ. | FLOOR SINK | SINK | FLOOR | 0" | THREE QUARTER GRATE |
| P250 | 12" SQ. | FLOOR SINK | BOOSTER / DISHMACHINE | FLOOR | 18" | BTC |
| P250A | 3/4" | HOT WATER | DISHMACHINE | WALL | 18" | EXT. THRU W.FILTER TO BOOSTER / DISH MACHINE - 140DEG.MIN. |
| P250B | 3/4" | COLD WATER | DISHMACHINE | WALL | 18" | BTC |
| P614 | 1/2" | H & C WATER | FILL FAUCET | WALL | 42" | BTC |
| P800 | 12" SQ. | FLOOR SINK | EQUIPMENT | FLOOR | 0" | 3/4 GRATE |




1 FOOD SERVICE PLUMBING PLAN
1/4" = 1'-0"

SECTION 11 40 00 TO PROVIDE LOOSE WITH FOOD SERVICE EQUIPMENT. INSTALLATION BY DIV. 22 & 26.


- (A) VACUUM BREAKER
- (B) DISPOSER
- (C) TIME DELAY
- (D) CONTROL PANEL
- (E) SOLENOID VALVE

DIVISION 22 TO PROVIDE AND INSTALL


- (F) 1/2" CW INLET
- (G) FLOW CONTROL
- (H) 1/2" CW
- (I) 2" DRAIN LINE WITH P-TRAP & Y ADAPTOR
- (J) 1-1/2" TAILPIECE
- (K) GATE VALVE
- (L) 1/2" CW SUPPLY
- (M) SHOCK STOP
- (N) RPZ BACK FLOW PREVENTOR

DIVISION 26 TO PROVIDE AND INSTALL


- (O) POWER SUPPLY




6 DISPOSER WITH VACUUM BREAKER DETAIL
NOT TO SCALE





7 EXHAUST HOOD - GAS LINE ROUTING DETAIL
NOT TO SCALE




3 GAS DISCONNECT DETAIL
NOT TO SCALE




5 DRAIN PIPING FASTENER DETAIL
NOT TO SCALE




8 WAREWASH - PERFORATED OVER SHELF DETAIL
NOT TO SCALE

| | | | | | |
|---|---|---|---|---|---|
| ○ | HW | HOT WATER | ▢ | FFD | FUNNEL FLOOR DRAIN |
| ○ | CW | COLD WATER | ◣ | EVC | EXHAUST VENT CONNECTION |
| ○ | HTW | 180 F HOT WATER | ⋈ | SVC | SUPPLY VENT CONNECTION |
| ◎ | | CHILLED WATER | ◔ | FR | DIRECT-CONNECTED FLUE RISER |
| ● | W | DIRECT WASTE | ◍ | PS | PIPE SLEEVE |
| ○ | IW | INDIRECT WASTE | ⊙ | | COMPRESSED AIR |
| ⊙ | | GAS SUPPLY | ♦ | | CO2 |
| ◕ | | STEAM SUPPLY | | AFF | ABOVE FINISHED FLOOR |
| ⊘ | CR | CONDENSATE RETURN | | BTC | BRANCH TO CONN. ON EQUIP |
| ◉ | DR | DRAIN | | DFA | DROP FROM ABOVE |
| ▢ | FD | FLOOR DRAIN | | CLG | CEILING |
| ▤ | FST | FLOOR SINK 3/4 GRATE | | | |
| ▥ | FSH | FLOOR SINK 3/4 GRATE | | | |

2 PLUMBING SYMBOLS
NOT TO SCALE

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL

FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
FCS
48834119
PROFESSIONAL MEMBER
7/15/2025
THIS ITEM IS DIGITALLY SIGNED AND SEALED BY MELISSA MOORE, FCSI NO: 48834119 ON: 07/18/2025


ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS PLUMBING PLAN


K-QF1.4


| FOOD SERVICE ELECTRICAL SCHEDULE | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR ELECTRICAL COORDINATION NOTES | | | | | | | | |
| FDP ENO | FDP ECONN | FDP ELOAD | FDP EVOLT | FDP EPH | FDP ESERVICE TO | FDP ELOC | FDP EAFF | FDP EREMARKS |
| E10 | DR | 16.0A | 120 | 1 | CONVENIENCE | WALL | 24" | MOUNT HORIZONTAL |
| E13 | WPR | 16.0A | 120 | 1 | CONVENIENCE | WALL | 24" | MOUNT HORIZONTAL |
| E15 | JB | --- | --- | --- | FIRE PROT. SYSTEM | WALL | 48" | RECESSED EMPTY CONDUIT FOR FIRE PULL |
| E101 | JB | 5.1A | 120 | 1 | AIR SCREEN | WALL | 82" | BTC; MAGNETIC REED SWITCH ON DOOR JAMB & DOOR |
| E102A | JB | 16.0A | 120 | 1 | DOOR HEATER/LIGHTS | CLG | DFA | BTC |
| E102B | JB | 5.0A | 120 | 1 | TEMP. ALARM | CLG | DFA | BTC |
| E102C | JB | 5.0A | 120 | 1 | PRESSURE RELIEF PORT | CLG | DFA | BTC |
| E102E | JB | 10.0A | 120 | 1 | PANIC ALARM BUTTON | CLG | DFA | BTC-INTERCONNECT TO STROBE LIGHT/HORN ABOVE FREEZER DOOR AND IN CAFETORIUM |
| E103 | JB/DS | 21.9A | 208 | 3 | REFRIGERATION SYSTEM | VERIFY | VERIFY | BTC |
| E103C | JB | 9.1A | 208 | 1 | FREEZER COIL | CLG | DFA | BTC |
| E103D | JB | 1.8A | 120 | 1 | COOLER COIL | CLG | DFA | BTC |
| E103E | JB | --- | --- | --- | DATA CONNECTION | CLG | DFA | BTC; RUN TO NEAREST IDF / MDF ROOM |
| E103F | JB | 16.0A | 120 | 1 | DRAIN LINE HEATER | CLG | DFA | BTC; DEDICATED CIRCUIT |
| E109 | DR | 11.9A | 120 | 1 | ICE MACHINE | WALL | 60" | --- |
| E110 | DR | 16.0A | 120 | 1 | CLOTHES WASHER | WALL | 48" | -- |
| E110A | SR | 30.0A | 208 | 1 | CLOTHES DRYER | WALL | 48" | VERIFY NEMA PLUG RECEPTACLE |
| E123 | JB | 3.0HP | 208 | 3 | DISPOSER | WALL | 24" | BTC; CONNECT THRU C.P. TO DISPOSER |

| FOOD SERVICE ELECTRICAL SCHEDULE | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR ELECTRICAL COORDINATION NOTES | | | | | | | | |
| FDP ENO | FDP ECONN | FDP ELOAD | FDP EVOLT | FDP EPH | FDP ESERVICE TO | FDP ELOC | FDP EAFF | FDP EREMARKS |
| E129 | DCR | 16.0A | 120 | 1 | TABLE RECEPTACLE | CLG | 84" | TWISTLOCK PLUG & RECEPTACLE |
| E139 | DCR | 15.0A | 120 | 1 | INSUL. MOBILE PROOFER | CEILING | DFA | -- |
| E151 | JB | 1.0A | 120 | 1 | FIRE PROT. SYSTEM | CLG | DFA | BTC |
| E161 | (2)DR | 6.0A EA. | 120 | 1 | CONVECTION OVEN | WALL | 24"/48" | SHUNT TRIP BREAKER |
| E163 | DR | 5.0A | 120 | 1 | TILT BRAISING PAN | WALL | 24" | SHUNT TRIP BREAKER |
| E187 | JB | 15.5A | 120/208 | 1 | HEATED CABINET | WALL | 96" | BTC; MOUNT ON KITCHEN SIDE |
| E188 | JB | 7.2A | 120 | 1 | REFRIGERATOR | WALL | 96" | BTC; MOUNT ON KITCHEN SIDE-OMIT PLUG, UNIT TO BE HARDWIRED |
| E201A | PMR | 28.0A | 208 | 1 | HOT FOOD COUNTER | FLOOR | 4.5" | BTC |
| E201B | PMR | 16.0A | 120 | 1 | COLD FOOD COUNTER | FLR | 4.5" | --- |
| E209 | PMR | 8.0A | 120 | 1 | DROP FRONT MILK COOLER-8 CASE | FLR | 4.5" | --- |
| E214 | PMR | 16.0A | 120 | 1 | CASH REGISTER | FLR | 4.5" | DEDICATED CIRCUIT |
| E214A | CS | --- | --- | --- | POS | FLOOR | 6" | BTC; CONDUIT W/DATA LINE TO RUN TO MANAGER'S OFFICE OR IDF ROOM-VERIFY |
| E250 | JB/DS-JB | 51.7A | 480 | 3 | DISHMACHINE | WALL | 66" | BTC; EXTEND FROM JB/DS AT NEAREST WALL |
| E615 | DR | 5.0A | 120 | 1 | VIDEO / DATA SYSTEM | CLG | VERIFY | PROVIDE DCO AT VIDEO LOCATION |
| E615A | JB | --- | --- | --- | VIDEO / DATA SYSTEM | CLG | VERIFY | PROVIDE JB AT DATA LOCATION |





1 FOOD SERVICE ELECTRICAL PLAN
1/4" = 1'-0"






6 COLD STORAGE ASSEMBLY ENTRAPMENT PANIC ALARM DETAIL
NOT TO SCALE




3 PEDESTAL MOUNTED RECEPTACLE DETAIL
NOT TO SCALE




4 FIRE PROTECTION SYSTEM TYPICAL DETAIL
NOT TO SCALE




5 FIRE PROTECTION SYSTEM RECESSED FIRE PULL DETAIL
NOT TO SCALE

| | | | | | |
|---|---|---|---|---|---|
| | SCR | CONDUIT STUB BTC ON RECEPT FURNISH WITH EQUIPMENT | | CC | CONDUIT FOR COMPUTER CABLES |
| • | CS | CONDUIT STUB UP/OUT FOR DIRECT CONNECTION | | BTC | BRANCH TO CONNECTION ON EQUIPMENT |
| | DR | DUPLEX RECEPTACLE | | WPR | WATERPROOF RECEPTACLE (SPRING COVER) |
| | SR | SINGLE PURPOSE RECEPTACLE-1PH | | FPB | FIRE PROTECTION BUZZER |
| | SR | SINGLE PURPOSE RECPTACLE-3PH | | BSC | BEVERAGE SYSTEM CONDUIT |
| | FR | FLUSH FLOOR RECEPTACLE | | DFA | DROP FROM ABOVE |
| | PMR | PEDESTAL MOUNTED RECEPTACLE | | AFF | ABOVE FINISH FLOOR |
| | DCR | DROP CORD RECEPTACLE | | CS/JB | JUNCTION BOX ON PEDESTAL |
| | JB | JUNCTION BOX ON CEILING | | SW | SWITCH |
| | JB | JUNCTION BOX IN WALL | | D | DATA |
| | JB/DS | JUNCTION BOX WITH DISCONNECT BY DIV.26 | | | |

2 ELECTRICAL SYMBOLS
NOT TO SCALE

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO: 48854119 ON: 07/18/2025


ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

FS ELECTRICAL PLAN

K-QF1.5

**MODEL NO. ZS1-02Z-CT3-EST OUTDOOR AIR COOLED REFRIGERATION SYSTEM**
**ITEM NO. 103**




NOTE:
- CRANKCASE HEATERS
- FAN CYCLING SWITCHES
- 24" STANDS & STAINLESS STEEL SKIRTING TO BE SHIPPED LOOSE FOR FIELD INSTALLATION
- DOOR SENSOR FOR EACH WALK-IN
- REFRIGERANT DETECTION SYSTEM
- CHECK VALVE (SHIPPED LOOSE)
- SHUT OFF VALVE (SHIPPED LOOSE)

RACK WEIGHT: 600 LBS.

## ENGINEERING SUMMARY

**POWER SUPPLY: 208-230/60/3**
**CONNECTED LOAD: 21.8 AMPS**

**MOPD: 30 AMP**
**MINIMUM CIRCUIT AMPACITY: 24.1**

| SYSTEM | FIXTURES ITEM # | DESCRIPTION | TEMP °F FIXT. | TEMP °F SUCT. | REQ'D FIXTURE BTU/H | REFRIG. R- | CONDENSING UNIT COMPRESSOR MODEL NO. | RATING @ 60 HZ RLA | V | PH | BTU CAP @ AMB °F 110 | TYPE | REC. CAP. (lbs) | CONDENSER | EVAPORATOR COILS ITEM # | MODEL NO. | QTY | FAN MOTORS @ 60 HZ RLA | V | PH | HEATERS @ 60 HZ RLA | V | PH | DEFR. TYPE | DEFROST CONTROLLER TYPE | CONTROLLER QTY | ACCESSORIES TSTAT | SOL. VALVE | EXP. VLV. | REFRIGERANT LINE SIZES (IN) SUCT. | SUCT. LINE RISER | LIQUID | LINE RUN (FT) | TYPE | TOTAL SYSTEM LOAD |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| A | 102 | WALK-IN COOLER | 35 | 25 | 8506 | 454A | YS11KAE | 11.2 | 208 | 3 | 11700 | Z | 14.0 | L1R | - | BEL0095 | 1 | 1.8 | 115 | 1 | | | | O.C. | ECOSMART | 1 | F | F | EF | 5/8 | 5/8 | 3/8 | 100 | M | 11.2 |
| B | 102 | WALK-IN FREEZER | -10 | -20 | 7607 | 454A | YF07KSE | 10.6 | 208 | 3 | 7610 | Z | 14.0 | L1R | - | BEL0080 | 1 | 1.0 | 208 | 1 | 9.1 | 208 | 1 | ELEC | ECOSMART | 1 | F | F | EF | 7/8 | 7/8 | 3/8 | 100 | M | 10.6 |


ALL EVAPORATOR COILS WILL REQUIRE A HOUSE POWER SUPPLY

c UL us LISTED

NOTE:
IT IS THE INSTALLING CONTRACTORS RESPONSIBILITY TO FOLLOW ALL APPLICABLE CODES AND CURRENT REFRIGERATION INDUSTRY STANDARDS AND PRACTICES WHEN DETERMINING LINE SIZES, AND INSTALLING AND STARTING UP RDT EQUIPMENT.


| COMPRESSOR TYPE | DEFROST TYPE | LINE TYPE | EVAPORATOR ACCESSORIES |
|---|---|---|---|
| Z SCROLL | O.C. OFF CYCLE<br>ELEC ELECTRIC | M MAIN - UP TO 100' | EF EEV FACTORY EQUIPPED ON EVAP<br>F FACTORY EQUIPPED ON EVAP |

### PLANVIEW/ CLEARANCE REQUIREMENTS





NOTE: MINIMUM CLEARANCE REQUIRED FOR PROPER OPERATION.
NOTE: ROOF CURB OR GROUND PAD CAN BE SAME SIZE AS OUTDOOR UNIT

### SUCTION LINE VERTICAL RISE DETAIL




- Install trap every transition from horizontal to vertical.
- Insulate suction lines with 3/4" wall Armaflex insulation.
- All joints brazed with minimum 15% silver content brazing rod.
- Install "P" trap on suction line every 15' vertical rise.
- Not to exceed 45' vertically over all.
- *If compressor is above the evaporator, Install inverted trap on top of the rise to prevent oil from seeping down when fixture(s) is turned off.

### EVAPORATOR DETAILS - MODEL BEL




| AIR DEFROST Size | DIMENSIONS A (Inches) | B (Inches) | C (Inches) | D (Inches) | CONNECTIONS (Inches) Coil Inlet | Suction | Drain | Approx. Net Wt. Lbs. | ELECTRICAL DATA Qty. Motors | EC Motor Fan Amps 115V | 208V |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 095 | 45-1/2 | 33-1/4 | - | - | 1/2 OD | 5/8 OD | 3/4 MPT | 51 | 2 | 1.8 | 1.0 |

| ELECTRIC DEFROST | DIMENSIONS A (Inches) | B (Inches) | C (Inches) | D (Inches) | CONNECTIONS (Inches) Coil Inlet | Suction | Drain | Approx. Net Wt. Lbs. | ELECTRICAL DATA Qty. Motors | EC Motor Fan Amps | Heater Amps as wired for 208-230/60/1 | 208-230/60/3 | 460/60/1 |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 080 | 45-1/2 | 33-1/4 | - | - | 1/2 OD | 5/8 OD | 3/4 MPT | 54 | 2 | 1.0 | 9.1 | 5.7 | 4.6 |

### ZS SERIES ENGINEERING SPECIFICATIONS

Multi compressor, outdoor, air cooled. The refrigeration package shall be a pre-engineered and factory-assembled unit, trade name "ZS", as manufactured by Refrigeration Design Technologies, 1808 FM Road 66, P.O. Box 622, Waxahachie, Texas 75168. Phone: (972) 937-3215; Fax: (972) 937-0970.

1. Air-Cooled Refrigeration System
The RDT UL Listed "Air-Cooled" Refrigeration system shall be housed in a weather-protected compact powder coated steel frame. The entire housing shall be brushed stainless steel. The unit shall include an air-cooled aluminum fin copper tube condenser designed to operate at 15 degrees TD. The exterior housing shall feature stainless steel one piece louvers. Lifting points shall be integrated in the framing component. Condenser fan motors shall be mounted within the enclosure. The condenser intake surface shall be protected with stainless steel expanded metal guard to protect against vandalism and hail damage.

Each unit shall be equipped with a ball-bearing fan motor, suction filter, sight glass, liquid filter/drier, liquid line inlet and outlet valve, defrost cycle and high pressure super-hose connections. Each unit shall be equipped with fan cycling controls and/or head pressure regulator where required for low ambient conditions.

Condensing unit shall contain scroll, hermetic, semi-hermetic, and/or discus type compressor(s) assembled to operate with the refrigerant specified for both medium and low temperature applications.

2. Evaporator Coils
A. Evaporator coils shall be direct expansion type fabricated of copper tubes with aluminum fins.
B. All evaporator coils shall be provided with solenoid valve, thermostatic or electronic expansion valve and thermostat.

3. Pre-Piping
All refrigerant lines shall be extended to outside of the housing in a neat and orderly manner. All tubing shall be securely supported and anchored with non-corrosive coated clamps.

All joints must be brazed, not soldered.

All piping and controls shall be factory pressure-tested with dry nitrogen.

4. Control Panel
The package shall have a factory-mounted and pre-wired control panel, with main disconnect (non fused) where required, circuit breakers, contactors wired for single point power connection.

General Information
Contractors shall verify all dimensions onsite and coordinate with other trades.

General contractor shall prepare the platform, curbed openings and weatherproofing the unit after installation.

Refrigeration Contractor
All copper tubing to be refrigerant grade. A.C.R. or type "L".

Brazing should be used for all refrigerant piping. Silver solder or soft solder is not acceptable.

All piping to be pressure tested with nitrogen at 300 psi. After the condensing unit and coil have been connected the balance of the system shall be leak tested with the valves open at 200 psi.

The complete system shall be evacuated with a vacuum pump. Each unit should be charged tested and adjusted to assure operation.

Contractor should provide and install the drain-line heater in freezer. Heater shall be connected by electrical contractor. Seal all penetrations through the walk-in units with foam.

Electrical Contractor
Electrical contractor to provide power for refrigeration package and connect control and defrost system as called for in the wiring diagram.


Electrical contractor to connect drain-line heater in the freezer.

All electrical wiring and installation shall be in accordance with the wiring diagram and local codes. Seal all penetrations through the walk-in units with foam.

Plumbing Contractor
Plumbing contractor to provide copper drain lines for walk-in refrigerator and freezer, pitched 1/4" per foot of run. Trap drain-line outside of refrigerated space to avoid entrance of warm, moist air.


All plumbing installation shall be in accordance with local codes.

### EVAPORATOR MOUNTING DETAIL (TYPICAL)




| COIL MODEL | DISTANCE FROM WALL |
|---|---|
| BEL | 1-1/3"H |
| BEM/BEH | 1/2 " W |

### EVAPORATOR PLACEMENT & CLEARANCE REQUIREMENTS LOW PROFILE EVAPORATOR COILS (I.E. - BEL)





SINGLE EVAPORATOR

NOTE:
H = TOTAL HEIGHT OF THE EVAP. COIL

### WIRING DIAGRAM - ECOSMART - AKEA1AE DEMAND DEFROST W/KE2 DOOR SWITCH FOR WALK-IN COOLER WITH ONE COIL 115/60/1

*REFERENCE ENGINEERING SUMMARY FOR COIL AMP DRAW.

| SYS | DESCRIPTION | VOLTAGE |
|---|---|---|
| A | WALK-IN COOLER | 115/1 |





FACTORY WIRING ———
FIELD WIRING - - - - -

### WIRING DIAGRAM - ECOSMART - AKEB1EE DEMAND DEFROST W/KE2 DOOR SWITCH FOR WALK-IN FREEZER WITH ONE COIL 208-230/60/1

*REFERENCE ENGINEERING SUMMARY FOR COIL AMP DRAW.

| SYS | DESCRIPTION | VOLTAGE |
|---|---|---|
| B | WALK-IN FREEZER | 208/1 |




FACTORY WIRING ———
FIELD WIRING - - - - -

### APPROVAL STATUS

THIS DRAWING REPRESENTS OUR UNDERSTANDING OF THE SPECIFICATIONS. PLEASE REVIEW IT CAREFULLY FOR ACCURACY. CLEARLY AND IN DETAIL NOTE CHANGES REQUIRED.

MARK APPROPRIATE BOX, SIGN, AND DATE BELOW.

- ☐ APPROVED FOR FABRICATION NO CHANGES
- ☐ APPROVED FOR FABRICATION WITH CHANGES NOTED
- ☐ REVISE AND RE-SUBMIT DRAWING

BY: _____ DATE: _____

### NOTICE

THIS DRAWING BEING AN INSTRUMENT OF SERVICE IS AND WILL REMAIN PROPERTY OF REFRIGERATION DESIGN TECHNOLOGIES AND CANNOT BE USED WITHOUT WRITTEN AUTHORIZATION.

| No. | Revision/Issue | Date |
|---|---|---|
| 0 | ORIGINAL ISSUE | 10-3-24 |
| 1 | CHANGED TO A2L EQUIPMENT | 7-16-25 |


REFRIGERATION DESIGN TECHNOLOGIES
1808 FM Road 66 / P.O. Box 622
Waxahachie, Texas
(800) 736-9518
www.rdtonline.com


Consultant:
Foodservice Design Professionals, LLC
The Woodlands, TX

Dealer
-
-

**Hunters Glen Elementary School**
**Fort Bend ISD**

Project No: 31086
Designed By: E. Milligan
Drawn By: A. Rodriguez
Sheet 1.1 of sheets

ISSUE:
12/05/2024 DD PACKAGE
03/11/2025 50% CD PKG.
05/23/2025 90% CD PKG.
07/18/2025 ISSUED FOR BIDDING AND PERMITTING

FOODSERVICE DESIGN PROFESSIONALS


FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489


SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
THIS ITEM APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 48854119 ON: 07/15/2025


ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS CONDENSING UNITS

K-QF1.6






COOLER DOOR ELEVATION





DOOR ELECTRICAL CONNECTION





TRIM ANGLE
DETAIL #3




PANEL MOUNTED ELECTRICAL CONNECTION





SECTION E – E





SECTION K – K


American Panel's walk–in floor panels with AmeriTuff structural support are designed to withstand uniformly distributed stationary loads of 15,000 lbs. per square foot. American Panel's warranty does not cover damage caused by pallet jacks, forklifts or any other form of heavy–duty rolling traffic. A concrete wearing floor must be installed on top of the AmeriTuff walk–in floor panels for those rolling applications.




TRIM ANGLE
DETAIL #2




CLOSURE PANEL ABOVE
WALK–IN DETAIL #4E




DETAIL "A"
WAINSCOT AT
INTERIOR CORNER

| INSULATION R–VALUES | | |
|---|---|---|
| PANEL TYPE | COOLER | FREEZER |
| 4" WALLS, ROOFS | R–29 | R–32 |
| 5" WALLS, ROOFS | R–36 | R–40 |
| FLOORS | R–25 | R–28 |
| DOORS | R–32 | |

| COOLER DOOR | |
|---|---|
| DOOR FRAME KWH/DAY | 2.424 |

| FREEZER DOOR | |
|---|---|
| DOOR FRAME KWH/DAY | 4.392 |

| WALK-IN PANEL R-8967 | | |
|---|---|---|
| BUILDING UNITS | R-8967 | 37X12 |
| **USA** | | |
| SURFACE BURNING CHARACTERISTICS | | |
| MATERIAL DETAILS | "FLAME SPREAD" | "SMOKE DEVELOPED" |
| ALUMINUM PANELS, PAINTED OR UNPAINTED, 5" OR LESS | 15 | 350 |
| "GALVANIZED STEEL OR STAINLESS STEEL PANELS, PAINTED OR UNPAINTED, 5" OR LESS" | 10 | 400 TO 500 |
| CORE MATERIAL, 6" THICK | 20 | 250 |

AMERICAN PANEL WALK–IN COOLERS AND FREEZERS COMPLY WITH THE 2021 INTERNATIONAL ENERGY CONSERVATION CODE (IECC), SECTION C403.11

THIS AMERICAN PANEL WALK–IN WILL BE MANUFACTURED TO UL & NSF REQUIREMENTS. AMERICAN PANEL ACCEPTS NO LIABILITY FOR LOCAL CODE REQUIREMENTS OF WHICH AMERICAN PANEL HAS NOT BEEN MADE AWARE OF IN WRITING PRIOR TO FABRICATION.

~SPECIFICATIONS~

**BOX HEIGHT:** FREEZER – 10'–2" OVERALL (7'–6 1/4" INTERIOR)
COOLER – 10'–2" OVERALL (7'–6 1/4" INTERIOR)

**CONSTRUCTION:** FOAMED IN PLACE
NSF LISTED, STANDARD NO. 7

**INSULATION:** 4" URETHANE, FINISHED PANEL
UL CLASSIFIED FLAME SPREAD 20
CORE SMOKE DEVELOPED 250

**INSTALLATION:** INDOOR

**FLOOR:** (SEE DETAIL)
FREEZER – STANDARD W/AMERITUFF STRUCTURAL FLOOR
(1/8" INTEGRAL DIAMOND ALUMINUM TREAD PLATE, 3/4" MARINE PLYWOOD UNDERLAYMENT, FIBERGLASS GRATING SUPPORT)
COOLER – STANDARD W/36" DEEP INTERIOR RAMP & AMERITUFF STRUCTURAL FLOOR
(1/8" INTEGRAL DIAMOND ALUMINUM TREAD PLATE, 3/4" MARINE PLYWOOD UNDERLAYMENT, FIBERGLASS GRATING SUPPORT)

**DOOR HARDWARE & ACCESSORIES:** (EACH DOOR)
SMOOTH POLISHED DOOR HARDWARE
POWER TO BE STUBBED OUT CEILING PANEL
DRY CONTACT LEADS TO BE STUBBED OUT CEILING PANEL IN A SEPARATE STUB OUT
DEADBOLT HANDLE W/KEYED CYLINDER LOCK, PADLOCK
PROVISION & QUARTER TURN INSIDE RELEASE (EXTERIOR DOOR ONLY)
1/8" STAINLESS STEEL THRESHOLD COVER PLATE
14 GA STAINLESS STEEL SUB THRESHOLD
FRAME HEATER WIRE
HYDRAULIC DOOR CLOSER
IC+ WALK–IN DOOR CONTROLLER AND ALARM SYSTEM INCLUDING:
INTEGRATED LIGHT SWITCH WITH AUTOMATIC LIGHT OFF AND 3–WAY & 4–WAY CAPABILITY
TEMPERATURE MONITOR AND LOGGER WITH HIGH TEMP. AND LOW TEMP. VISUAL AND AUDIO ALARM
F OR C TEMPERATURE SELECTION
INTEGRATED DRY CONTACT FOR ALARM SIGNALING & POWER FAILURE (1A @ 24VAC, 1A @ 30VDC)
DOOR AND WINDOW HEATER CONTROL (WHEN SO EQUIPPED)
HACCP PREVIEW VIA ONBOARD LCD SCREEN
HACCP DOWNLOAD VIA USB
WIFI CONNECTIVITY (INTERNET ENABLED WIFI NETWORK NEEDED)
BATTERY BACKUP
TEMPERATURE ALARM NOTIFICATION VIA EMAIL &/OR EMAIL TO SMS TEXT MESSAGES
POWER FAILURE NOTIFICATION VIA EMAIL &/OR EMAIL TO SMS TEXT MESSAGES
(FOR THIS FEATURE TO WORK THE LOCAL WIFI NETWORK MUST BE POWER PROTECTED AND WORKING AT THE TIME OF POWER FAILURE EVENT)
AUTOMATIC AND ON DEMAND TRANSMISSION OF HACCP DATA VIA EMAIL
ADAPTIVE SETTINGS
MOMENTARY BACK–TO–BACK LIGHT SWITCH W/PILOT
25' AIR TEMPERATURE PROBE
25' SECOND PROBE (EXTENDED) FOR MONITORING THE TEMPERATURE AT A SECOND LOCATION OR FOR MONITORING A SECOND CABINET
DOOR SWITCH TO ENABLE DOOR AJAR ALARM, DOOR AJAR NOTIFICATION VIA EMAIL &/OR EMAIL TO SMS TEXT MESSAGES, AND AUTOMATIC LIGHTS ON WHEN DOOR OPENS
PANIC ALARM WITH ILLUMINATED PANIC BUTTON, ALARM BUZZER WITH LED, & NOTIFICATION VIA EMAIL &/OR EMAIL TO SMS TEXT MESSAGES (1–COOLER, 2–FREEZER)
KASON SCREW–IN VAPOR PROOF LIGHT FIXTURE
W/8.5 WATT SYLVANIA LED BULB & GLOBE
CCI CLEAR VU SWINGING DOOR
3 – KASON #1346 ADJUSTABLE SPRING LOADED HINGES
HEATED VISION WINDOW (14" x 24")
1/8" DIAMOND ALUMINUM TREAD PLATE KICKPLATES @ 36" HIGH I/S & O/S DOOR & FRAME
KASON 1826 INTELLO–VENT WITH LIGHTS (FREEZER DOOR ONLY) – FIELD INTERCONNECTION REQUIRED

**PANEL MOUNTED ACCESSORIES:**
1 – KASON 1826 INTELLO–VENT WITH LIGHTS – FIELD INTERCONNECTION REQUIRED (FOAMED IN PANEL – PER PLAN) (COOLER ONLY)

**ACCESSORIES:** (SHIPPED LOOSE)
2 – PCS. TRIM ANGLE – 18 GA STAINLESS STEEL, #3 FINISH
CLOSURE PANEL TO AN EXISTING CEILING (PER PLAN) — **VERIFY LENGTH**
18 GA STAINLESS STEEL, #3 FINISH
2 – 48" (1810LC) LED LIGHT FIXTURE(S) @ 40W EACH (LIGHTS TO BE INSTALLED PERPENDICULAR TO COILS)
1/8" DIAMOND ALUMINUM TREAD PLATE WAINSCOT @ 36" HIGH (EXPOSED EXTERIOR ONLY)
1 – 1/8" DIAMOND ALUMINUM TREAD PLATE CORNER GUARD(S) @ 36" HIGH
ALUMINUM COVED BASE MOLDING (COMPLETE INTERIOR ONLY)
ROOF SUPPORT ANGLE W/BEAUTY TRIM
2 – BAKELITE LABEL(S) (BLACK) ("FREEZER", "COOLER")
1 – BAKELITE LABEL (YELLOW W/BLACK LETTERING) ("VACUUM PRESSURE RELIEF")
6 MIL POLYETHYLENE VAPOR BARRIER
3 – BELL BOX(ES) & COVER PLATE(S)
2 – DOOR STOP(S)
2 – EDWARDS 960 SERIES STROBE BEACONS
1 – EMERGENCY PRESSURE RELEASE

**METAL FINISHES:**
INTERIOR & EXTERIOR DOOR & FRAME – 18 GA STAINLESS STEEL, #3 FINISH
INTERIOR WALLS & CEILING – WHITE .040 STUCCO ALUMINUM
EXPOSED EXTERIOR – 20 GA STAINLESS STEEL, #3 FINISH
UNEXPOSED EXTERIOR – 26 GA STUCCO ACRYLUME
EXTERIOR FLOOR – 26 GA STUCCO ACRYLUME
EXTERIOR ROOF – 26 GA STUCCO ACRYLUME
INTERIOR FLOOR – AMERITUFF STRUCTURAL FLOOR
(1/8" INTEGRAL DIAMOND ALUMINUM TREAD PLATE, 3/4" MARINE PLYWOOD UNDERLAYMENT, FIBERGLASS GRATING SUPPORT)

**REFRIGERATION:** BY OTHERS

NOTE: THE LARGEST DOOR PANEL ON THIS JOB IS 57.5" x 114.5".
NOTE: THE LARGEST ROOF/FLOOR PANEL ON THIS JOB IS 46.5" x 129".
CUSTOMER IS TO VERIFY THAT THIS PANEL SIZE WILL NOT CONFLICT WITH ANY JOB SITE RESTRICTIONS.
NOTE: CUSTOMER IS TO VERIFY ALL DIMENSIONS, SECTIONS, DETAILS AND SPECIFICATIONS
NOTE: MAXIMUM LIGHT CIRCUIT LOAD IS 1200W 120VAC TUNGSTEN, 5A 120VAC ELECTRONIC BALLAST. FOR HIGHER LOADS ADDITIONAL LIGHT FIXTURES MUST BE CONTROLLED VIA RELAY (BY OTHERS).

| ELECTRICAL DATA |
|---|
| ⚽ = POINT OF ELECTRICAL CONNECTIONS. |
| WALK–IN DOORS: 115v/1ø – 350w* |
| PANEL MOUNTED ACC. 115v/1ø – 23w (EACH VENT) |

*NOTE: ADD WATTAGE FOR EACH ADDITIONAL LIGHT FIXTURE IN ACCESSORIES.

ITEM #102 WALK–IN COOLER/FREEZER

☐ APPROVED SIGNATURE _____
☐ APPROVED AS NOTED PRINT NAME _____
☐ REVISE & RESUBMIT DATE _____

1) Please verify that door swing and location are correct.
2) If this walk–in is to be installed in a depression, or quarry tile is to be applied to the interior, depression depths or tile thickness must be specified to insure proper door height.
3) All site preparation, floor or slab construction, plumbing, electrical connections (including control wiring) by others.
4) ⚽ Electrical: 115–60–1 required above latch side of each door, through ceiling, to operate frame heater and light.
5) Special note to General Contractor and his Sub Contractor for quarry tile or concrete wearing floors: the sheet metal panel facings may be susceptible to staining due to excessive moisture created by hydration of concrete type materials. Therefore, it is absolutely necessary that each room be properly ventilated. Also note that special precautions must be taken when using muriatic acid due to effects hydrochloric acid fumes have on aluminum and stainless steel.
6) This drawing and information contained herein are the exclusive property of American Panel Corporation. It shall be returned to American Panel Corporation upon demand and shall not be reproduced in whole or part, disclosed to anyone else, or used without the written consent of American Panel Corporation.

| REV. | DATE | DESCRIPTION | DR | WQ |
|---|---|---|---|---|
| A | 1/22/25 | REVISED LAYOUT, SPECS; ADDED DETAIL | DH | WQ |

American Panel — AMERICAN PANEL CORPORATION, 5800 S.E. 78th St. Ocala, Florida 34472, Ph. (352) 245–7055 Fax (352) 245–6726

CUSTOMER: FOODSERVICE DESIGN PROFESSIONALS
PROJECT: HUNTERS GLEN ES–FBSD – FORT BEND, TX
DATE: 10/09/24 | DRAWN BY: JG/TB | P.O.#:
SCALE: 3/8"=1'–0" | PROPOSAL#: PD213275 | JOB#: | SHEET: 1 of 1

ALL DIMENSIONS MUST BE FIELD VERIFIED PRIOR TO FABRICATION AND INSTALLATION

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS


FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL — MELISSA MOORE — FCSI 48854119 — PROFESSIONAL MEMBER
Melissa Moore
7/15/2025 APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 48854119 ON: 07182025


ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS WALK-INS

K-QF1.7





1 CC1 ITEM #1 PLAN

SCALE: 1/2" = 1'-0"





4 CC1 ITEM #1 SECTION VIEW

SCALE: 1/2" = 1'-0"





8 CC1 ITEM #1 CONTROL PANEL LAYOUT

SCALE: 1 1/2" = 1'-0"





2 CC1 ITEM #1 FRONT ELEVATION

SCALE: 1/2" = 1'-0"




11 CC1 ITEM #1 3D PERSPECTIVE

SCALE:




3 CC1 ITEM #1 REAR ELEVATION

SCALE: 1/2" = 1'-0"



12 CC1 ITEM #1 3D PERSPECTIVE 2

SCALE:

| NO | SERVICE | NEMA | L1 | TRIP |
|---|---|---|---|---|
| 1 | 208V CASHIER RECEPTACLE 208v, 1ø | 5-20R | | 20A |
| 2 | 208V CASHIER RECEPTACLE 208v, 1ø | 5-20R | | 20A |
| 3 | LED LIGHTING 208v, 1ø | 5-15P | | 15A |

NOTE: THIS IS NOT A LOAD CENTER, THIS IS A JUNCTION/DISTRIBUTION BLOCK INSIDE THE BREAKER BOX

11A CC1 ELECTRICAL SCHEDULE
CASHIER COUNTER

| NO | SERVICE | NEMA | L1 | L2 | L3 | TRIP |
|---|---|---|---|---|---|---|
| 1 | THREE HOT FOOD WELL 208v, 1ø, 30A EA. | THREE 5-30R | 10 | 10 | 10 | 30A |
| 2 | | | | | | 30A |
| 3 | TWO HOT FOOD WELL 208v, 1ø, 30A EA. | TWO 5-30R | 10 | 10 | | 30A |
| 4 | | | | | | 30A |
| 5 | 48" HEAT LAMP 208v, 1ø, 1500W | 5-15P | 15 | | | 15A |
| 6 | | | | 15 | | 15A |
| 7 | LED LIGHTING 208v, 1ø | 5-15P | | | 15 | 15A |
| 8 | SPACE | | | | | |

TOTAL LOAD: 35 | 35 | 25 | 125 AMPS

NOTE: THIS IS NOT A LOAD CENTER, THIS IS A JUNCTION/DISTRIBUTION BLOCK INSIDE THE BREAKER BOX

11B CC1 ELECTRICAL SCHEDULE
HOT FOOD COUNTER #1
(TWO (2) REQUIRED)

| NO | SERVICE | NEMA | L1 | TRIP |
|---|---|---|---|---|
| 1 | RECESSED FROST TOP 208v, 1ø | 5-15P | 15 | 15A |
| 2 | RECESSED HOT/FROST TOP 208v, 1ø | 5-15P | 15 | 15A |
| 3 | LED LIGHTING 208v, 1ø | 5-15P | 15 | 15A |

TOTAL LOAD: 45 | 45

NOTE: THIS IS NOT A LOAD CENTER, THIS IS A JUNCTION/DISTRIBUTION BLOCK INSIDE THE BREAKER BOX

11C CC1 ELECTRICAL SCHEDULE
HOT/FROST COUNTER
(TWO (2) REQUIRED)

EQUIPMENT BY OTHERS

COUNTERCRAFT LAYOUTS, MEPS, AND LOAD CENTERS ARE BASED ON SPECIFIED MANUFACTURERS AND MODELS AS OUTLINED IN THE SPECIFICATIONS IN THE CONTRACT DOCUMENTS. COUNTERCRAFT MUST BE NOTIFIED OF ANY CHANGES TO THE CONTRACT DOCUMENTS IN A TIMELY MANNER.

| NO | REVISIONS | DATE | BY |
|---|---|---|---|
| 1 | PRELIMINARY DWG | 12/21/2024 | MAX |
| 2 | REVISIONS | 1/1/2025 | MAX |
| 3 | | | |
| 4 | | | |
| 5 | | | |
| 6 | | | |
| 7 | | | |
| 8 | | | |
| 9 | | | |

ANOTHER QUALITY PRODUCT FROM
CounterCraft
7007 STEARNS HOUSTON,TEXAS 77021
(713) 747-3611

PROJECT: FBISD Bond Package 013
FOOD SERVICE CONSULTANT: FOODSERVICE DESIGN PROFESSIONALS
PROJECT NO: -
DATE: 11/26/2024
SCALE: As indicated
DRAWN BY: MAX.C
CHECKED BY: E.S
SHEET NO: CC1
OF SHEET

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FDP
FOODSERVICE DESIGN PROFESSIONALS


FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
ELECTRONIC SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI, FCSI 48854119 ON: 07/18/2025

ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS SERVING LINE

K-QF1.8




2 CC2 LAYOUT

SCALE: 3/4" = 1'-0"

EQUIPMENT BY OTHERS

COUNTERCRAFT LAYOUTS, MEPS, AND LOAD CENTERS ARE BASED ON SPECIFIED MANUFACTURERS AND MODELS AS OUTLINED IN THE SPECIFICATIONS IN THE CONTRACT DOCUMENTS. COUNTERCRAFT MUST BE NOTIFIED OF ANY CHANGES TO THE CONTRACT DOCUMENTS IN A TIMELY MANNER.

| NO | REVISIONS | DATE | BY |
|---|---|---|---|
| 1 | PRELIMINARY DWG | 10/21/2024 | MAX |
| 2 | REVISIONS | 11/26/2024 | MAX |
| 3 | | | |
| 4 | | | |
| 5 | | | |
| 6 | | | |
| 7 | | | |
| 8 | | | |
| 9 | | | |

ANOTHER QUALITY PRODUCT FROM
CounterCraft
7007 STEARNS HOUSTON,TEXAS 77021
(713) 747-3611

PROJECT: FBISD Bond Package 013
FOOD SERVICE CONSULTANT: FOODSERVICE DESIGN PROFESSIONALS

PROJECT NO. -
DATE 11/26/2024
SCALE 3/4" = 1'-0"
DRAWN BY MAX.C
CHECKED BY E.S
SHEET NO. CC2
OF SHEET

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489


SEAL

FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
FCSI 48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
ANY PRINTED COPIES APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 48854119 ON: 07/18/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS SERVING LINE

K-QF1.9




1 FOOD SERVICE EQUIPMENT PLAN - DEMO PLAN
1/4" = 1'-0"

NOTE: ALL EQUIPMENT MAKERED WITH A
DIAGONAL HATCH TO BE RELOCATED
PER TEMPORARY SERVING PLAN SHEET K-QF2.0

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FDP
FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489


SEAL

FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
FCSI
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
DOCUMENTS APPEARING ON THIS SHEET WERE AUTHORIZED BY MELISSA MOORE, FCSI NO. 48854119 ON: 07/18/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS DEMO PLAN

K-QF2.0




3 FOOD SERVICE ELECTRICAL PLAN - TEMPORARY SERVING
1/4" = 1'-0"

| FOOD SERVICE ELECTRICAL SCHEDULE - TEMPORARY SERVING | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR ELECTRICAL COORDINATION NOTES | | | | | | | | |
| FDP ENO | FDP ECONN | FDP ELOAD | FDP EVOLT | FDP EPH | FDP ESERVICE TO | FDP ELOC | FDP EAFF | FDP EREMARKS |
| E800A | DR | 16.0A | 120 | 1 | CONVENIENCE | WALL | 24" | --- |
| E800B | DR | 16.0A | 120 | 1 | CONVENIENCE | WALL | 24" | DEDICATED CIRCUIT |
| E800C | JB | --- | --- | -- | DATA CONNECTION | WALL | 24" | --- |
| E806 | DR | 16.0A | 120 | 1 | TRANSPORT CABINET | WALL | 24" | --- |
| E808 | JB | 7.8A | 120/208 | 1 | HEATED CABINET | WALL | 96" | BTC; OMIT PLUG, UNIT TO BE HARDWIRED |
| E809 | JB | 8.2A | 120 | 1 | REFRIGERATOR | WALL | 96" | BTC; OMIT PLUG, UNIT TO BE HARDWIRED |
| E810 | CS/SR | 13.3A | 208 | 1 | (4) HOT WELLS | WALL | 24" | EXTEND TO EQUIPMENT - CONFIRM NEMA PLUG |
| E810A | SR | 7.9A | 208 | 1 | (2) HOT WELLS | WALL | 24" | EXTEND TO EQUIPMENT - CONFIRM NEMA PLUG |
| E810B | DR | 5.0A | 120 | 1 | COLD PAN | WALL | 24" | EXTEND TO EQUIPMENT |
| E810C | DR | 10.0A | 120 | 1 | BEVERAGE | WALL | 24" | EXTEND TO EQUIPMENT |
| E811 | DR | 16.0A | 120 | 1 | CASH REGISTER | WALL | 24" | DEDICATED CIRCUIT - EXTEND TO EQUIPMENT |
| E811A | JB | - | --- | 1 | POS | WALL | 24" | BTC |

| | | | | | |
|---|---|---|---|---|---|
| | SCR | CONDUIT STUB BTC ON RECEPT FURNISH WITH EQUIPMENT | | CC | CONDUIT FOR COMPUTER CABLES |
| • | CS | CONDUIT STUB UP/OUT FOR DIRECT CONNECTION | | BTC | BRANCH TO CONNECTION ON EQUIPMENT |
| | DR | DUPLEX RECEPTACLE | | WPR | WATERPROOF RECEPTACLE (SPRING COVER) |
| | SR | SINGLE PURPOSE RECEPTACLE-1PH | | FPB | FIRE PROTECTION BUZZER |
| | SR | SINGLE PURPOSE RECPTACLE-3PH | | BSC | BEVERAGE SYSTEM CONDUIT |
| | FR | FLUSH FLOOR RECEPTACLE | | DFA | DROP FROM ABOVE |
| | PMR | PEDESTAL MOUNTED RECEPTACLE | | AFF | ABOVE FINISH FLOOR |
| | DCR | DROP CORD RECEPTACLE | | CS/JB | JUNCTION BOX ON PEDESTAL |
| | JB | JUNCTION BOX ON CEILING | | SW | SWITCH |
| | JB | JUNCTION BOX IN WALL | | D | DATA |
| | JB/DS | JUNCTION BOX WITH DISCONNECT BY DIV.26 | | | |


5 ELECTRICAL SYMBOLS 1
NOT TO SCALE

| FOOD SERVICE PLUMBING SCHEDULE - TEMPORARY SERVING | | | | | | |
|---|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR PLUMBING COORDINATION NOTES | | | | | | |
| FDP PNO | FDP PSIZE | FDP PCONN | FDP PSERVICE TO | FDP PLOC | FDP PAFF | FDP PREMARKS |
| | | | | | | <varies> |
| P11C | 1/2" | H & C WATER | FAUCET | WALL | 18" | FURNISHED & INSTALLED BY DIV. 22 |
| P11D | 1 1/2" | DIRECT DRAIN | HAND SINK | WALL | 15" | FURNISHED & INSTALLED BY DIV. 22 |
| P249 | 3/4" | H & C WATER | FAUCET | WALL | 13" | BTC |


| | | | | | |
|---|---|---|---|---|---|
| ○ | HW | HOT WATER | ⊡ | FFD | FUNNEL FLOOR DRAIN |
| ○ | CW | COLD WATER | ◣ | EVC | EXHAUST VENT CONNECTION |
| ○ | HTW | 180 F HOT WATER | ⋈ | SVC | SUPPLY VENT CONNECTION |
| ◍ | | CHILLED WATER | ◔ | FR | DIRECT-CONNECTED FLUE RISER |
| ● | W | DIRECT WASTE | ◍ | PS | PIPE SLEEVE |
| ○ | IW | INDIRECT WASTE | ⊙ | | COMPRESSED AIR |
| ⊙ | | GAS SUPPLY | ♦ | | CO2 |
| ◕ | | STEAM SUPPLY | | AFF | ABOVE FINISHED FLOOR |
| ⊗ | CR | CONDENSATE RETURN | | BTC | BRANCH TO CONN. ON EQUIP |
| ● | DR | DRAIN | | DFA | DROP FROM ABOVE |
| ▢ | FD | FLOOR DRAIN | | CLG | CEILING |
| ▟ | FST | FLOOR SINK 3/4 GRATE | | | |
| ▯ | FSH | FLOOR SINK 3/4 GRATE | | | |

4 PLUMBING SYMBOLS 1
NOT TO SCALE

| FOOD SERVICE EQUIPMENT SCHEDULE - TEMPORARY SERVING | | | | | |
|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR GENERAL CONTRACTOR & HEALTH DEPARTMENT COORDINATION NOTES | | | | | |
| FDP ITEM | FDP QTY | FDP DESCRIPTION | FDP REMARKS | MANUFACTURER | MODEL |
| 209 | 2 | DROP FRONT MILK COOLER - 8 CASE | | TRAULSEN | RMC34D4 |
| 804 | 2 | S/S SPLASH GUARDS | | CUSTOM FABRICATED | |
| 805 | 1 | THREE COMPARTMENT SINK NO DISPOSER | EXISTING | | |
| 806 | 4 | TRANSPORT CART | EXISTING | | |
| 807 | 2 | HAND LAV | EXISTING | | |
| 808 | 2 | REACH IN HEATED CABINET - 1DR | EXISTING | | |
| 809 | 2 | REACH IN REFRIGERATOR - 1DR. | EXISTING | | |
| 810 | 1 | DRY STORAGE SHELVING | EXISTING | | |
| 811 | 1 | CASH REGISTER | OWNER FURNISHED | | |
| 812 | 1 | SERVING LINE | EXISTING | | |




1 FOOD SERVICE EQUIPMENT PLAN - TEMPORARY SERVING
1/4" = 1'-0"




2 FOOD SERVICE PLUMBING PLAN - TEMPORARY SERVING
1/4" = 1'-0"

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489


SEAL

FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
ITEMS APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 48854119 ON: 07/15/2025



ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS TEMPORARY SERVING


K-QF2.1




11 ELEVATION @ HOLDING
1/2" = 1'-0"




10 ELEVATION @ DISPOSER & TRAY DROP WINDOW
1/2" = 1'-0"




9 ELEVATION @ DISHMACHINE
1/2" = 1'-0"




8 ELEVATION @ THREE COMPARTMENT SINK
1/2" = 1'-0"




7 ELEVATION @ SETUP TABLE & MOBILE HEATED CABINET
1/2" = 1'-0"




6 ELEVATION @ PRODUCTION 2
1/2" = 1'-0"




5 ELEVATION @ PRODUCTION 1
1/2" = 1'-0"




4 ELEVATION @SETUP TABLE & MIXER
1/2" = 1'-0"



3 ELEVATION @ COLD STORAGE ASSEMBLY
1/2" = 1'-0"



2 ELEVATION @ SETUP TABLE
1/2" = 1'-0"



1 ELEVATION @ PREP SINK & ICE MACINE
1/2" = 1'-0"

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489


SEAL

FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
ALL PRINTS APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO: 48854119 ON: 07/15/2025


ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS ELEVATIONS


K-QF3.1




## 3 MECHANICAL ROOF FLOOR PLAN

SCALE: 1/8" = 1'-0"


NORTH




## 2 RENO MECHANICAL FLOOR PLAN - KITCHEN AREA

SCALE: 1/8" = 1'-0"

NORTH




## 1 DEMO MECHANICAL FLOOR PLAN - KITCHEN AREA

SCALE: 1/8" = 1'-0"

NORTH

## AIR DEVICE SCHEDULE

| MARK | DESCRIPTION |
|---|---|
| A | CEILING DIFFUSER – 24" X 24" FACE, PATTERN TYPE, STEEL CONSTRUCTION, OBD/RADIATION DAMPER, WHITE FINISH, U.L. LISTED PRICE SCD A1–12" X 12" |
| B | CEILING RETURN GRILLE – 24" X 24" PERFORATED FACE, STEEL CONSTRUCTION, RADIATION DAMPER, WHITE FINISH, U.L. LISTED PRICE PDFR B1–12" X 12" |
| C | CEILING EXHAUST GRILLE – 24" X 24" PERFORATED FACE, STEEL CONST., OBD/RADIATION DAMPER, WHITE FINISH, NECK SIZE SHOWN, U.L. LISTED PRICE PDDR C1–12" X 12" |

NOTES:

1. REFER TO ARCHITECTURAL REFLECTED CEILING PLAN TO VERIFY CEILING TYPES FOR AIR DEVICES.

## KITCHEN HOOD REFURBISHMENT NOTES

HOOD REFURBISHMENT FOR KITCHEN HOODS (QUANTITY 2):

- STEAM WASH AND DEEP CLEAN STAINLESS STEEL HOOD ASSEMBLY, CASING, AND SUPPLY GRILLES WHERE APPLICABLE.
- REPLACE GREASE FILTER RACKS.
- CLEAN EXISTING MAKE-UP AIR AND GREASE EXHAUST DUCT.
- RELAMP EXISTING LIGHT FIXTURES WITH NEW 4000K BULBS LISTED FOR USE IN AN ENCLOSED KITCHEN HOOD FIXTURE.
- COORDINATE WITH DIVISION 11 FOR REPLACEMENT OF ANSUL FIRE SUPPRESSION SYSTEM.
- HOOD ASSEMBLIES SHALL BE CLEANED TO MEET THE STANDARDS ESTABLISHED IN NFPA STANDARD 96.

## KITCHEN HOOD EXHAUST & MAKE-UP AIR UNIT SCHEDULE

| | |
|---|---|
| MARK | ESF-1,2 |
| SERVES | KITCHEN HOOD-1 & 2 |
| **SUPPLY SECTION** | |
| TYPE | INDIRECT GAS-FIRED MAKE-UP AIR UNIT |
| DRIVE | DIRECT |
| SPEED CONTROL | VFD |
| SUPPLY CFM | 2250 |
| EXT. S.P. (IN. W.G.) | 0.375 |
| HORSEPOWER (WATTS) | 1-1/2 HP |
| VOLTAGE | 480V/3-PHASE |
| UNIT MCA | 4.6 A |
| UNIT MOCP | 15 A |
| HEATING MEDIUM | NATURAL GAS |
| INPUT/OUTPUT (MBH) | 150.0/121.5 |
| TURNDOWN RATIO | 4:1 |
| MANUFACTURER | GREENHECK |
| MODEL | IGX-P109-H12-MF-E |
| **EXHAUST SECTION** | |
| TYPE | UPBLAST BELT DRIVE CENTRIFUGAL |
| EXHAUST CFM | 3600 |
| EXT. S.P. (IN. W.G.) | 0.75 |
| HORSEPOWER (WATTS) | 1-1/2 HP |
| VOLTAGE | 480V/3-PHASE |
| UNIT MCA | 3.75 A |
| UNIT MOCP | 15 A |
| MANUFACTURER | GREENHECK |
| EXHAUST FAN MODEL | CUBE-200-15 |

NOTES

1. EXHAUST FAN: PROVIDE FAN WITH PRE-FABRICATED ROOF CURB ADAPTER, VENTED CURB EXTENSION, HINGING KIT, HEAT BAFFLE, DRAIN CONNECTION, GREASE TRAP, AND DISCONNECT SWITCH. FANS SHALL BE UL LISTED FOR USE WITH TYPE 1 GREASE HOOD.
2. EXHAUST FAN: PROVIDE NEW MOTOR STARTER, SIZED FOR EXHAUST FAN MOTOR AND INSTALLED IN PLACE OF EXISTING. REFERENCE THE SPECIFICATIONS FOR STARTER REQUIREMENTS. COORDINATE WITH DIV.25 FOR RE-TERMINATION OF PERMISSIVE ON/OFF CONTROL. COORDINATE WITH DIV.26 FOR RE-TERMINATION OF LOCAL HOOD SWITCH INTERLOCK FOR START/STOP CONTROL.
3. SUPPLY FAN/FURNACE: FLUE GAS FROM HEATING COIL SHALL BE POWER VENTED.
4. SUPPLY FAN/FURNACE: WEATHERHOOD WITH ALUMINUM MESH.
5. SUPPLY FAN/FURNACE: 5 YEAR HEAT EXCHANGER WARRANTY.
6. SUPPLY FAN/FURNACE CONTROLS: INTEGRAL HEATER CONTROLS WITH BAS INTERLOCK FOR PERMISSIVE ON/OFF AND LOCAL SWITCH INTERLOCK FOR CONTROL FROM KITCHEN HOOD SWITCH. FURNACE CONTROLS SHALL BE PROGRAMMED FOR 64°F LAT, WITH A LOCKOUT FOR O/A TEMPERATURES ABOVE THE LAT SETPOINT. COORDINATE WITH DIV.25 AND DIV.26 FOR CONTROLS AND SWITCH INTERLOCKS.
7. TWO POINT POWER CONNECTION: ONE FOR EXHAUST FAN AND ONE FOR INTAKE/SUPPLY FAN.
8. INTERLOCK FAN(S) WITH ASSOCIATED COOKING HOOD
9. INTERLOCK FAN WITH SWITCH ON KITCHEN HOOD.
10. UNIT TO BE PROVIDED WITH GALVANIZED STEEL FAN PACK EXTENSION/COMBINATION CURB.
11. REFER TO WRITTEN SPECS FOR ADDITIONAL REQUIREMENTS.

## MECHANICAL RENO KEYED NOTES

1. TIE-IN NEW DUCTWORK TO EXISTING DUCTWORK AT WALL PENETRATION.
2. CONNECT NEW AIR DEVICE AND TAP TO EXISTING E/A TRUNK DUCT.
3. REWORK EXISTING EXHAUST AND SUPPLY DUCTWORK FROM EXISTING KITCHEN HOOD UP TO FAN, AS REQUIRED, WITH NEW TRANSITIONS AND SUPPLY AIR DUCTWORK OFFSETS TO MATE WITH NEW FAN CURB.
4. EXISTING ELECTRIC DUCT HEATER TO BE RETAINED FOR RE-INSTALLATION IN RENOVATION PHASE.
5. NEW DRYER VENT DUCT AND VENT CAP.
6. TEMP. KITCHEN – CEILING MOUNTED CABINET EXHAUST FAN.
7. TEMP. KITCHEN – 24"X24" SIDE WALL GRILLE. SURFACE MOUNT OPTIONAL. AUXILIARY FRAME. TITUS CT-700.
8. RECONFIGURE DUCTWORK TO CONNECT TO NEW DISHMACHINE HOOD OUTLETS. REF. KITCHEN CONSULTANT DRAWINGS FOR EXACT DIMENSIONS OF DUCT CONNECTIONS.
9. CONDENSATE EXHAUST DUCT UP THROUGH ROOF TO NEW EXHAUST FAN SET ON NEW ROOF CURB. REUSE EXISTING ROOF PENETRATION.

## MECHANICAL DEMO KEYED NOTES

1. DEMOLISH EXISTING AIR DEVICE, BRANCH DUCT, DAMPER AND TAP BACK TO TRUNK DUCT. CAP AND SEAL RESULTING OPENING.
2. EXISTING E/A TRUNK DUCT TO REMAIN.
3. DISCONNECT EXISTING S/A AND E/A DUCTWORK SERVING KITCHEN HOODS FROM FAN ASSEMBLY ON ROOF. DEMOLISH SUPPLY AND EXHAUST FAN PLENUM ASSEMBLY SERVING KITCHEN HOODS, ALONG WITH CURB. NEW CURB TO BE PROVIDED AND INSTALLED AS PART OF RENOVATION.
4. DEMOLISH ALL EXISTING AIR DEVICES, DUCTWORK, AND DUCTWORK ACCESSORIES SERVING KITCHEN AREA BACK TO MECH. ROOM WALL PENETRATION.
5. EXISTING ELECTRIC DUCT HEATER TO BE RETAINED FOR RE-INSTALLATION IN RENOVATION PHASE.
6. REFURBISH EXISTING KITCHEN HOOD. REFER TO "KITCHEN HOOD REFURBISHMENT NOTES".
7. DEMOLISH AND REPLACE EXISTING DRYER EXHAUST DUCT AND FLUE VENT CAP.
8. DEMOLISH EXISTING CONDENSATE HOOD, ASSOCIATED DUCTWORK, AND ROOF EXHAUST FAN.

## EXHAUST FAN SCHEDULE

| MARK | EF-TK | EF-CF | EF-14 |
|---|---|---|---|
| SERVES | TEMPORARY KITCHEN | COOLER/FREEZER | DISH WASHER |
| TYPE | CEILING CABINET | INLINE FAN | ROOF UPBLAST |
| DRIVE | DIRECT | DIRECT | DIRECT |
| SPEED CONTROL | INTEGRAL SPEED CONTROLLER | CONSTANT | CONSTANT |
| CFM | 1055 | 1000 | 1200 |
| EXT. S.P. (IN. W.G.) | 0.3 | 0.35 | 0.60 |
| IMP. SIZE (IN.) | 8.0 | 13.5 | |
| HORSEPOWER (WATTS) | 1/3 HP | 1/6 HP | 1/6 HP |
| VOLTAGE | 120V/1-PHASE | 120V/1-PHASE | 120V/1-PHASE |
| MANUFACTURER | COOK | COOK | COOK |
| MODEL | GC-862 | 1355QN10D | CUE-140-VG |
| SONES (MAX.) | 15.0 | 15.0 | 15.0 |
| NOTES | 1 THRU 4 | 1 THRU 4 | 1 THRU 4 |

NOTES

1. STATIC PRESSURE SHOWN IS EXTERNAL TO THE UNIT. MANUFACTURER SHALL ADD DAMPER AND ACCESSORY LOSSES TO THIS VALUE BEFORE SELECTING FAN. FANS SHALL BE CAPABLE OF 120% OF THE SCHEDULED CFM CAPACITY.
2. INTEGRAL DISCONNECT SWITCH.
3. RUBBER IN-SHEAR ISOLATORS.
4. REFER TO WRITTEN SPECS FOR ADDITIONAL REQUIREMENTS.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL





ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

KITCHEN AREA
MECHANICAL PLANS
K-M1.01


STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM | (713) 305-4080
TEXAS ENG. FIRM REG. NO. F-018337-00


2021 ALL RIGHTS RESERVED


12300 N. SAM HOUSTON PARKWAY E., SUITE 175, HOUSTON, TX 77067

## MECHANICAL SYMBOL SCHEDULE

| | |
|---|---|
| CWS | CONDENSER WATER SUPPLY |
| CWR | CONDENSER WATER RETURN |
| CHS | CHILLED WATER SUPPLY |
| CHR | CHILLED WATER RETURN |
| HWS | HEATING WATER SUPPLY |
| HWR | HEATING WATER RETURN |
| RS | REFRIGERANT SUPPLY |
| RR | REFRIGERANT RETURN |
| D | CONDENSATE LINE |
| | PETE'S PLUG |
| | ISOLATION VALVE |
| | ELECTRONIC CONTROL VALVE |
| | BUTTERFLY VALVE |
| | BALL VALVE |
| | UNION OR FLANGE |
| | STRAINER |
| | AUTOMATIC AIR VENT |
| T | LOCAL CONTROL THERMOSTAT |
| T | TEMPERATURE SENSOR |
| H | HUMIDITY SENSOR |
| FD | FIRE DAMPER |
| SD | SMOKE DAMPER |
| FSD | FIRE/SMOKE COMBINATION DAMPER |
| MD | MOTORIZED DAMPER |
| C | CARBON MONOXIDE SENSOR |
| CO2 | CARBON DIOXIDE SENSOR |
| | SUPPLY AIR DIFFUSER |
| | RETURN AIR GRILLE |
| | EXHAUST GRILLE |
| RA | RETURN AIR OPENING IN WALL |
| VD | VOLUME DAMPERS |
| | DUCT ELEVATION CHANGE |
| | 90° DUCT ELBOW WITH TURNING VANES |
| | FLEXIBLE DUCT |
| M | DAMPER MOTOR |
| T | TEMPERATURE TRANSMITTER |
| FS | FLOW SWITCH |
| P | DIFFERENTIAL PRESSURE SENSOR |
| SD | DUCT SMOKE DETECTOR |
| PS | STATIC PRESSURE SENSOR |
| PH | STATIC PRESSURE SENSOR HI-LIMIT |
| | ACCESS PANEL |

| | |
|---|---|
| A.P. | ACCESS PANEL |
| AHU | AIR HANDLING UNIT |
| B | BOILER |
| CH | CHILLER |
| CHP | CHILLED WATER PUMP |
| CVT | CONSTANT VOLUME TERMINAL |
| DH | DEHUMIDIFIER |
| E/A | EXHAUST AIR |
| EF | EXHAUST FAN |
| F&B | FACE & BYPASS |
| FF | FLY FAN |
| HDT | HORIZONTAL DRAW THROUGH |
| HWP | HOT WATER PUMP |
| KEF | KITCHEN EXHAUST FAN |
| KSF | KITCHEN SUPPLY FAN |
| O/A | OUTSIDE AIR |
| OBD | OPPOSED-BLADES DAMPER |
| PT | PRE-TREAT |
| R/A | RETURN AIR |
| RAHU | ROOF-MOUNTED AIR HANDLING UNIT |
| S/A | SUPPLY AIR |
| SA | SOUND ATTENUATOR |
| SF | SUPPLY FAN |
| SPD | SPILTER DAMPER |
| SZ | SINGLE ZONE |
| VAV | VARIABLE AIR VOLUME |
| VB | VAV BOX |
| VD | VOLUME DAMPER |
| VDT | VERTICAL DRAW THROUGH |
| VFD | VARIABLE FREQUENCY DRIVE |
| WH | WATER HEATER |
| ⌀ | DESIGNATION FOR "ROUND" |
| ⌀ | DESIGNATION FOR "OVAL" |

## GENERAL MECHANICAL NOTES


1. REFER TO WRITTEN SPECIFICATIONS FOR ADDITIONAL INFORMATION.
2. COORDINATE INSTALLATION OF EQUIPMENT AND PIPING WITH THE ELECTRICAL CONTRACTOR TO INSURE NEC CLEARANCE (42 INCHES) IN FRONT OF ALL ELECTRICAL PANELS. DO NOT INSTALL DUCTWORK OR WATER PIPING OVER THE TOP OF ELECTRICAL PANELS SEE DETAIL 1/M2.01.
3. DUCT SIZES SHOWN ARE NET FREE AIR PASSAGE DIMENSIONS, DUCTS ARE NOT LINED, BUT ARE EXTERNALLY INSULATED. RUNOUTS TO CEILING OUTLETS SHALL BE EXTERNALLY INSULATED GALVANIZED SHEET METAL WITH SPIN-IN V.D. AT TRUNK TAPS, SEE DETAIL 1 & 2/M2.01.
4. REFER TO ARCHITECTURAL REFLECTED CEILING DRAWINGS FOR EXACT LOCATIONS OF CEILING OUTLETS IN RELATION TO OTHER CEILING ENTITIES. OUTLETS MUST BE COMPATIBLE WITH THE CEILING TYPES FOR THE VARIOUS AREAS.
5. IN AREAS WHERE SUPPLY AIR ENTERS CEILING CAVITY THRU RETURN AIR GRILLES AND FREE RETURNS TO AHU'S VIA CEILING CAVITY, PROVIDE RETURN AIR OPENING IN WALL-TO-DECK ABOVE CEILING THAT BLOCK PATH, REFER TO ARCHITECTURAL DRAWINGS. RETURN AIR ELBOWS SHALL BE SIZED AT 1 SQ. FT PER 400 CFM SUPPLY AIR.
6. ARRANGE PIPING CONNECTIONS TO ALL EQUIPMENT TO ALLOW EASY REMOVAL OF EQUIPMENT, SUB-ASSEMBLIES, COILS, FANS, MOTORS, FILTERS, ACCESS PANELS, ETC... PROVIDE UNIONS, FLANGES AND VALVES AT CONNECTIONS. PROVIDE AND INSTALL VICTAULIC JOINTS AT COILS, REF. SPECIFICATIONS. PLACE STOP VALVES ON SYSTEM SIDE OF REMOVABLE PIPE SECTIONS.
7. CONTRACTOR SHALL FIELD MEASURE STRUCTURAL ELEMENTS AND COORDINATE EQUIPMENT, PIPING AND DUCT ROUTING TO FIT EXISTING CONSTRUCTION. PROVIDE OFFSETS, BOOTS FOR ENVELOP OBSTRUCTIONS THAT CANNOT BE AVOIDED. CONSTRUCTION SHALL BE PER SMACNA FIGURE 2-10.

## AIR DEVICE SCHEDULE

| MARK | DESCRIPTION |
|---|---|
| A | CEILING DIFFUSER – 24" X 24" FACE, PATTERN TYPE, STEEL CONSTRUCTION, OBD/RADIATION DAMPER, WHITE FINISH, U.L. LISTED PRICE SCD |
| B | CEILING RETURN GRILLE – 24" X 24" PERFORATED FACE, STEEL CONSTRUCTION, RADIATION DAMPER, WHITE FINISH, U.L. LISTED PRICE PDFR |
| C | CEILING EXHAUST GRILLE – 24" X 24" PERFORATED FACE, STEEL CONST., OBD/RADIATION DAMPER, WHITE FINISH, NECK SIZE SHOWN, U.L. LISTED PRICE PDDR |

NOTES:

1. REFER TO ARCHITECTURAL REFLECTED CEILING PLAN TO VERIFY CEILING TYPES FOR AIR DEVICES.
2. ALL CEILINGS ARE FIRE RATED PER U.L. LISTINGS ON ARCHITECTURAL DRAWINGS. PROVIDE FIRE PROTECTION FOR ALL CEILING DEVICES PER DETAIL 13/M-17 AND SPECIFICATIONS.





### 6 KITCHEN UPBLAST EXHAUST FAN DETAIL

NO SCALE

NOTES

1. ARCHITECTURAL ROOF CURB INSTALLATION REQUIREMENTS SHALL SUPERCEDE THIS DETAIL.
2. INSTALL SHEETMETAL COVERING OVER WOOD BLOCKING IN THE AIRSTREAM OR OPEN TO THE CEILING CAVITY.





### 4 EXTERNALLY INSULATED DUCT SUPPORT DETAIL

NO SCALE

NOTES:

1. ROUND MEDIUM PRESSURE DUCT MAY BE SUPPORTED WITH DUCT STRAPS.
2. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.





### 2 DUCTWORK DETAIL

NO SCALE

NOTES:

1. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.





### 5 AIR DEVICE DETAIL

NO SCALE

NOTES:

1. RADIATION DAMPER SHALL ONLY BE PROVIDED IN CEILING DEVICES INSTALLED IN RATED CEILING ASSEMBLIES. REFER TO ARCHITECTURAL REFLECTED CEILING PLAN TO DETERMINE WHICH, IF ANY, CEILINGS ARE RATED.
2. REFER TO SPECIFICATIONS OF FOR ADDITIONAL INFORMATION AND REQUIREMENTS.




| TAP SIZE | ROD SIZE | DAMPER THICKNESS |
|---|---|---|
| UP TO 10" | 1/4" | 20 GA |
| OVER 10" | 3/8" | 18 GA |


HARDWARE MANUFACTURERS SHALL BE VENTLOCK, AMERICAN ELGEN, YOUNG AND DURO-DYNE.

### 3 DUCT TAP CONNECTION DETAIL

NO SCALE

NOTES:

1. DELETE CONICAL SECTION IF TOO LARGE FOR THE DUCT.
2. REFER TO SPECIFICATIONS OF FOR ADDITIONAL INFORMATION AND REQUIREMENTS.




### 1 MECHANICAL - ELECTRICAL COORDINATION DETAIL

NO SCALE

NOTES:

1. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.

STANTON ENGINEERING GROUP
INFORMATION@STANTON-ENG.COM | (713) 305-6282 | TEXAS ENG. FIRM REG. NO. F-018337-00 | 2025 ALL RIGHTS RESERVED | 1300 W. SAM HOUSTON PARKWAY N., SUITE 121, HOUSTON, TX 77043

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
6955 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489


SEAL

STATE OF TEXAS
TYLER W. HERRING
106052
LICENSED PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

MECHANICAL NOTES AND DETAILS
K-M2.01





## 5 RESIDENTIAL CLOTHES DRYER FLUE VENT

NO SCALE

NOTES:

1. VENT TERMINATION AT WALL FOR STACKABLE WASHER/DRYER SHALL BE AT 60" AFF.
2. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.





## 4 SUPPLY/EXHAUST KITCHEN PLENUM DETAIL

NO SCALE

NOTES:

1. xxxxx





## 3 ROOF EXHAUST FAN AND VENT DETAIL

NO SCALE


NOTES:

1. NO WOOD BLOCKING SHALL BE LEFT EXPOSED IN THE CEILING PLENUM. COVER ALL EXPOSED WOOD WITH 1/2" SHEETROCK OR 20 GAUGE GALVANIZED SHEETMETAL.
2. ROOF VENT WILL NOT HAVE FAN/MOTOR ASSEMBLY, DISCONNECT SWITCH OR OBD.
3. ARCHITECTURAL ROOF CURB INSTALLATION REQUIREMENTS SHALL SUPERCEDE THIS DETAIL WHERE APPLICABLE.
4. ALL FANS SCHEDULED TO BE PROVIDED WITH 140MPH WIND RATING, INCLUDING FACTORY PROVIDED CURB. CURB INSTALLATION SHALL FOLLOW MANUFACTURER'S REQUIREMENTS FOR SECURING TO ROOF AND EQUIPMENT WHERE IT DIFFERS FROM THE DETAIL.
5. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.




## 2 INLINE EXHAUST FAN DETAIL

NO SCALE




## 1 CABINET EXHAUST FAN

NO SCALE

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL

STATE OF TEXAS
TYLER W. HERRING
106052
LICENSED PROFESSIONAL ENGINEER
07.18.2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

MECHANICAL DETAILS (CONT'D.)

K-M2.02

STANTON ENGINEERING GROUP
INFORMATION@STANTONENG.COM (713) 300-6060
TEXAS ENG. FIRM REG. NO. F-018332 © 2025 ALL RIGHTS RESERVED
1300 W. SAM HOUSTON PARKWAY S., SUITE 121, HOUSTON, TX 77042

# ELECTRICAL AND LOW VOLTAGE LEGEND AND SYMBOLS

- A — TYPE 'A' LIGHT FIXTURE
- LIGHT FIXTURE WITH EMERGENCY BACKUP
- EXIT SIGN/EXIT SIGN WITH DIRECTIONAL ARROW
- EMERGENCY EGRESS LIGHT FIXTURE
- WALL MOUNTED FIXTURE OR SCONCE
- CEILING DOWNLIGHT OR CYLINDER
- WALL PACK FIXTURE
- INV — LIGHTING INVERTER

- 20A, 277V TOGGLE/3-WAY/4-WAY SWITCH
- 20A, 277V MOMENTARY 3-POSITION TOGGLE SWITCH
- 20A, 277V, MOMENTARY 3-POSITION KEY SWITCH
- 20A, 277V MAINTAINED 2-POSITION/3-WAY/4-WAY KEY SWITCH
- 20A, 277V TOGGLE SWITCH W/ INTEGRAL NIGHT LIGHT
- MOTOR RATED ON/OFF SWITCH, MP W/ PILOT LIGHT (SWITCH RATING SHALL BE ≥ UPSTREAM OCPD & VOLTAGE)
- DPST — DOUBLE POLE SINGLE THROW (DPST) SWITCH WITH RED PILOT LIGHT.
- TDN — TIMER SWITCH

## NETWORK LIGHTING CONTROLS

- MULTIBUTTON LOW VOLTAGE LIGHTING SWITCH PROVIDE NUMBER OF BUTTONS INDICATED IN SINGLE PLATE.
- MULTIPLE DIMMER SWITCHES PROVIDE NUMBER OF SWITCHES INDICATED IN SINGLE PLATE.
- MULTIPLE KEY TYPE SWITCHES PROVIDE NUMBER OF SWITCHES INDICATED IN SINGLE PLATE.
- VSC — WALL SENSOR SWITCH
- 20A, 277V, STANDALONE DIMMER SWITCH (DISPLAY CABINET)
- OC — 360° CEILING SENSOR
- OW — 180° CEILING SENSOR
- OC — CEILING SENSOR
- DC — WALL MOUNT SENSOR
- PD — DAYLIGHT PHOTOSENSOR
- RC / RCK — LIGHTING ROOM CONTROLLER/POWER PACK
- ELR — EMERGENCY LIGHTING RELAY/CONTROL UNIT
- PLC — PLUG LOAD CONTROLLER

- 20A, 125V SIMPLEX/DUPLEX/QUAD RECEPTACLE
- GFI — 20A, 125V DUPLEX RECEPTACLE WITH GFCI PROTECTION
- GFI WP — 20A, 125V DUPLEX RECEPTACLE WITH GFCI PROTECTION AND WEATHERPROOF COVER.
- GFI — REMOTE GFCI DEVICE, REF SPECS AND EDF GFI DETAIL.
- 20A, 125V DUPLEX/QUAD RECEPTACLE W/ USB-A PORTS PROVIDE 2-5A PORTS PER DEVICE — HUBBELL USB20A5
- 20A, 125V SIMPLEX/DUPLEX/QUAD IG/COMPUTER RECEPTACLE
- GFI — 20A, 125V, IG/COMPUTER DUPLEX RECEPTACLE WITH GFCI
- PLUG LOAD CONTROLLED DUPLEX
- NEMA / IEC / CS — NEMA/IEC/CS NUMBERED POWER OUTLET MATCH PROVIDED EQUIPMENT CONNECTION OR CIRCUIT.
- TV — 20A, 125V IG DUPLEX RECEPTACLE AT PROJECTOR, TV, OR INTERACTIVE MEDIA LOCATION.
- LOW VOLTAGE OUTLET
- CEILING MOUNTED RECEPTACLE
- CEILING MOUNTED LOW VOLTAGE OUTLET
- SINGLE SERVICE FLOOR BOX WITH DUPLEX/QUAD REC
- SINGLE SERVICE FLOOR BOX WITH DUPLEX/QUAD IG REC
- SINGLE SERVICE LOW VOLTAGE FLOOR BOXES
- MULTI SERVICE FLOOR BOX WITH QUAD/QUAD IG REC
- CR — CORD REEL
- DC — DROP CORD
- EPO — EMERGENCY POWER OFF (EPO) SWITCH
- PB — PUSH BUTTON
- SP — TELEPOWER POLE

- J — J-BOX
- CEILING MOUNTED J-BOX
- CA — J-BOX FOR ACCESS CONTROL DEVICE
- HD — JUNCTION BOX AND FINAL CONNECTION TO HAND DRYER BY DIVISION 26.
- HDWR — JUNCTION BOX AND FINAL CONNECTION TO ELECTRIFIED DOOR HARDWARE BY DIVISION 26.
- HEAT — JUNCTION BOX AND FINAL CONNECTION TO HEAT TRACE EQUIPMENT BY DIVISION 26.
- WC — JUNCTION BOX AND FINAL CONNECTION TO POWERED PLUMBING EQUIPMENT BY DIVISION 26.
- SF — JUNCTION BOX AND FINAL CONNECTION TO SYSTEM FURNITURE BY DIVISION 26.

- CONTACTOR
- NON-FUSED DISCONNECT SWITCH
- NON-FUSED DOUBLE THROW DISCONNECT
- FUSED DISCONNECT SWITCH
- DISCONNECT/CB WITH SHUNT TRIP
- ENCLOSED CIRCUIT BREAKER
- MOTOR STARTER 'VFD' INDICATES VARIABLE FREQUENCY DRIVE MOTOR STARTER
- MOTOR STARTER WITH INTEGRAL DISCONNECT
- MOTOR
- TC — TIME CLOCK

- ELECTRICAL PANELBOARD
- ELECTRICAL METER
- SPD — TVSS OR SPD
- GANN — GENERATOR REMOTE ANNUNCIATOR

- LOW VOLTAGE CABLING PATHWAY, REF. SPECIFICATIONS

## KITCHEN SYMBOL LEGEND

- LOAD CENTER, BY FOOD SERVICE PROVIDE UNDERGROUND CONDUIT STUBBED UP AT LOAD CENTER LOCATION PER SUBMITTAL SHOP DRAWINGS.
- P — POINT OF SALE EQUIPMENT, BY FOOD SERVICE. PROVIDE UNDERGROUND CONDUIT STUBBED UP POS LOCATION PER SUBMITTAL SHOP DRAWINGS.
- F — REMOTE FIRE PULL, REFERENCE INSTALLATION DETAIL
- B — BELL/BUZZER WITH 120V TO LOW VOLTAGE TRANSFORMER
- D — DROP CORD
- DB — DOORBELL BUTTON
- V — CEILING STROBE FOR ENTRAPMENT ALARM
- CLR/FRZR V — WALL STROBE FOR ENTRAPMENT ALARM

## COORDINATION SYMBOL LEGEND

- DDC — HVAC CONTROL PANEL. REQUIRES POWER AND DATA CONNECTIONS WITHIN CABINET COOR EXACT LOCATION AND REQUIREMENTS WITH CONTROLS CONTRACTOR PRIOR TO ROUGH-IN.
- SD — SMOKE DAMPER
- FD — FIRE/SMOKE COMBINATION DAMPER
- M / MD — MOTORIZED DAMPER

## SITE PLAN

- UTILITY POLE
- POLE MOUNTED TRANSFORMER BANK
- SITE POLE LIGHT
- UGE — FLUSH IN GRADE ELECTRICAL PULL BOX
- LV / T — FLUSH IN GRADE, LOW VOLTAGE HAND HOLE
- CONCRETE BOLLARD
- (X)PP — POWER POLE
- (X)SP — SERVICE POLE OR RACK
- (X)XP — XFMR POLE
- (X)LVP — LOW VOLTAGE POLE
- (X)TP — TRANSITION POLE
- OHP — OVERHEAD POWER WIRING
- 480V — 480V OVERHEAD POWER WIRING
- UGP — UNDERGROUND PRIMARY ELECTRICAL
- UGS — UNDERGROUND SECONDARY ELECTRICAL
- UGE — UNDERGROUND EMERGENCY ELECTRICAL

## DIVISION 28 LEGENDS

### FIRE ALARM

- F — FIRE ALARM PULL STATION W/ STOPPER II
- F / S — WALL FIRE ALARM AUDIO/VISUAL DEVICE
- WP — OUTDOOR WEATHERPROOF FIRE AUDIO/VISUAL DEVICE
- H — WALL FIRE ALARM AUDIO DEVICE
- V — WALL FIRE ALARM VISUAL DEVICE
- H / S — CEILING FIRE ALARM AUDIO/VISUAL DEVICE
- S — CEILING FIRE ALARM AUDIO DEVICE
- V — CEILING FIRE ALARM VISUAL DEVICE
- W — DUCT SMOKE DETECTOR
- I / S — CEILING SMOKE DETECTOR
- H — CEILING HEAT DETECTOR
- CO — CEILING CARBON MONOXIDE DETECTOR
- S / CO — CEILING COMBINATION SMOKE/CARBON MONOXIDE DETECTOR
- FR — FIRE ALARM RELAY FOR STAGE SOUND RACK OVERRIDE
- BEAM SMOKE DETECTOR
- FANN — FIRE ALARM REMOTE ANNUNCIATOR OR LOCAL OPERATOR'S CONSOLE
- FACP — FIRE ALARM CONTROL PANEL
- FAPS — FIRE ALARM POWER SUPPLY/AMPLIFIER
- G — INDICATES DEVICE WITH PROTECTIVE GUARD
- WG — INDICATES DEVICE WITH WIRE GUARD
- HC — INDICATES DEVICE RATED FOR HAZARDOUS CONDITIONS
- SD — SMOKE DAMPER
- FD — FIRE/SMOKE COMBINATION DAMPER

## MULTI-SERVICE FLOOR BOX NOTES

FLOOR POWER AND LOW VOLTAGE

PROVIDE HEAVY-DUTY MULTI-GANG FLUSH IN GRADE OR FIRE RATED POKE-THRU OUTLET WITH HEAVY DUTY METAL HINGED COVER WITH CABLE EXIT SLOT.
FLOOR BOX MUST BE RATED FOR INSTALLATION IN GRADE.

FOR EACH FLOOR BOX PROVIDE:
1. PROVIDE:
   - 1.A. ONE QUAD OR TWO DUPLEX RECEPTACLES.
   - 1.B. PROVIDE IG RECEPTACLES WHERE SHOWN.
   - 1.C. POWER CONNECTION TO TABLE (WHERE SHOWN)
2. BLANK STAINLESS STEEL COVER FOR UN-USED GANGS.
3. PROVIDE ONE 3/4"C UNDERGROUND CONDUIT FOR POWER.
4. PROVIDE ONE 1"C UNDERGROUND CONDUIT WITH WATERPROOF INNER DUCT FOR DATA.
5. PROVIDE ONE 1"C UNDERGROUND CONDUIT WITH WATERPROOF INNER DUCT FOR LOW VOLTAGE CABLING
6. PROVIDE DIVIDERS TO MAINTAIN SEPARATION BETWEEN SERVICES.

UNDERGROUND CONDUITS MUST BE WATER TIGHT TO PREVENT MOISTURE ENTERING CONDUITS.
DO NOT COMBINE CONDUIT FOR POWER & LOW VOLTAGE.

REFERENCE FLOOR PLANS AND SPECIFICATIONS FOR QUANTITY OF DATA DROPS AND ADDITIONAL INFORMATION.

COORDINATE WITH ARCHITECT TO PROVIDE COVER/RING TO MATCH FLOOR MATERIAL AND SUBMIT COVER FINISH FOR ARCHITECT TO SELECT PRIOR TO ORDERING.

## GENERAL NOTES / TAGS

| | |
|---|---|
| +18" | INDICATES DEVICES AT +18" AFF |
| +42" | INDICATES DEVICES AT +42" AFF |
| +96" | INDICATES DEVICES AT +96" AFF |
| +12 FT | INDICATES DEVICES AT +12 FT AFF, ETC. |
| * | INDICATES DEVICES ABOVE COUNTER, REF ARCH |
| CLG | INDICATES DEVICES AT CEILING |
| PMR | INDICATES PEDESTAL MOUNTED DEVICE, REF PMR DETAIL |
| TV | INDICATES DEVICES AT TELEVISION/DISPLAY LOCATION |
| IM | INDICATES DEVICES AT INTERACTIVE MEDIA LOCATION |
| PROJ | INDICATES DEVICES AT PROJECTOR LOCATION |
| S | INDICATES SURFACE MOUNTED DEVICE |
| IEC | INDICATES IEC POWER OUTLET |
| NEMA | INDICATES NEMA NUMBERED POWER OUTLET |
| GFI | INDICATES GROUND FAULT INTERRUPT (GFI) PROTECTION |
| WP | INDICATES WEATHERPROOF DEVICES |
| GFI WP | INDICATES GFI PROTECTED WEATHERPROOF DEVICE |
| G | INDICATES DEVICE WITH PROTECTIVE GUARD |
| WG | INDICATES DEVICE WITH WIRE GUARD |
| 3R | INDICATES NEMA 3R RATED DEVICE |
| 4XSS | INDICATES NEMA 4XSS RATED DEVICE |
| EM | INDICATES DEVICE ON EM/STANDBY POWER |
| VFD | INDICATES VARIABLE FREQUENCY DRIVE (VFD) |
| E | EXISTING DEVICES TO REMAIN |
| D | EXISTING DEVICES TO BE DEMO/REMOVED |
| R | EXISTING DEVICES TO BE RELOCATED |
| REP | EXISTING DEVICES TO BE REPLACED |
| | (X) = (E) FOR EXISTING |
| | (X) = (D) FOR DEMO |
| | (X) = (R) FOR RELOCATION |
| | (X) = (N) FOR NEW |

- HOMERUN TO CIRCUIT NOTED

1. RECEPTACLES AND DATA OUTLETS SHALL BE MOUNTED AT +18" AFF UNLESS NOTED ON THE DRAWINGS.
2. REF. SPECIFICATIONS FOR MOUNTING HEIGHT OF OTHER DEVICES.
3. ELECTRICAL RECEPTACLES, TELEPHONES, ETC... ARE SHOWN FOR GENERAL LOCATION. HEIGHTS ARE NOTED SO THE ESTIMATOR WILL KNOW WHETHER THEY ARE ABOVE OR BELOW COUNTERS. PRIOR TO INSTALLATION, REVIEW THE ARCHITECTURAL DRAWINGS AND SPECIFICATIONS. IN THE EVENT OF CONFLICT, THE ARCHITECT'S LOCATION WILL GENERALLY PREVAIL BUT SHOULD BE CLARIFIED BY RFI. PROVIDE DEVICES SHOWN ON THE ELECTRICAL DRAWING EVEN IF NOT SHOWN ON ARCHITECTURAL DRAWINGS.
4. COORDINATE POWER AND DATA WITH THE FURNITURE SUPPLIER PRIOR TO ROUGH-IN. AT CASEWORK WITH KNEE SPACE, MOUNT RECEPTACLES AND DATA OUTLETS IN KNEE SPACE. COORDINATE WITH ARCHITECT AND FURNITURE SUPPLIER TO ENSURE THAT PROTECTIVE GROMMETS ARE PROVIDED IN THE COUNTER.
4. ALL DEVICES SHOWN AT THE SAME LOCATION AND ELEVATION SHALL BE GROUPED TOGETHER AND SPACED 2 INCHES BETWEEN BOXES.
5. PROVIDE SS COVER PLATE FOR ALL EMPTY JBOX.
6. ALL NON-LOCKING 125V AND 250V, 15A AND 20A RECEPTACLES SHALL BE TAMPER RESISTANT TYPE.

STANTON ENGINEERING GROUP
INFORMATION: (713) 360-6080
TEXAS ENG. FIRM REG. NO. F-018537-0 © 2025 ALL RIGHTS RESERVED
12999 W. SAM HOUSTON PKWY N., SUITE 725, HOUSTON, TX 77064

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL AND FIRE ALARM SCHEDULES
k-E.000

PROVIDE CONDUIT & SLEEVES THRU FIRE WALLS, WALLS AND FLOORS FOR LOW VOLTAGE CABLING WIRING, ETC.

ALL CONDUIT & J-BOXES FOR LOW VOLTAGE CABLING SHALL BE PROVIDED AND INSTALLED BY THE ELECTRICAL CONTRACTOR. ALL LOW VOLTAGE CABLING IN WALLS, EXPOSED AREAS AND ABOVE INACCESSIBLE CEILINGS SHALL REQUIRE CONDUIT AND J-BOXES. REFERENCE SPECIFICATIONS AND TECHNOLOGY DOCUMENTS FOR ADDITIONAL INFORMATION/REQUIREMENTS.

PULL BOXES AND BELOW GRADE CONDUIT FOR LOW VOLTAGE CABLING, WIRING, ETC. BY ELEC CONTRACTOR.

## FIRE ALARM SYSTEM DESCRIPTION AND SEQUENCE OF OPERATION

1. FIRE ALARM SYSTEM SHALL BE DESIGNED TO MEET NFPA REQUIREMENTS AS WELL AS CITY AND NATIONAL BUILDING CODES. PROVIDE COMPLETE FIRE ALARM SYSTEM, DEVICES AND WIRING.
2. INSTALL FIRE ALARM CONTROL PANEL IN RECEPTION AREA. INSTALL REMOTE POWER SUPPLY PANELS IN MECHANICAL/ELECTRICAL ROOMS.
3. FIRE ALARM PANEL, POWER SUPPLIES, DEVICES, ETC. SHALL BE MANUFACTURED BY THE SAME MANUFACTURER AS THE FIRE ALARM CONTROL PANEL.
4. FIRE ALARM REMOTE POWER SUPPLIES AND PANELS SHALL BE LOCATED IN MECHANICAL OR ELECTRICAL ROOMS ONLY. DO NOT LOCATE IN STORAGE ROOMS, DATA CLOSETS OR FINISHED SPACES.
4. PROVIDE AUDIBLE, INTELLIGIBLE AND VISUAL ALARM COVERAGE OF THE AREA OF RENOVATION AS REQUIRED BY CODE.
5. PROVIDE SMOKE DETECTORS AT EACH FIRE ALARM PANEL, REMOTE TRANSPONDER PANEL, BOOSTER PANEL AND REMOTE ANNUNCIATOR PER NFPA 72.
6. IN ADDITION TO THE SPECIFIED FIRE ALARM EQUIPMENT, THE FIRE ALARM CONTRACTOR SHALL PROVIDE
   - 6.A. SURGE PROTECTORS FOR ALL NEW 120V POWER CONNECTIONS TO FIRE ALARM EQUIPMENT.
   - 6.B. SURGE PROTECTORS FOR ALL SIGNALING LINE CIRCUITS (SLC), NOTIFICATION CIRCUITS AND INITIATING CIRCUITS CONNECTED TO THE FIRE ALARM CONTROL PANEL WHICH LEAVE THE BUILDING.
7. SHOULD ANY DETECTOR, MONITOR OR PULL STATION ACTIVATE, ALL SPEAKERS SHALL SOUND AND STROBES FLASH. AIR HANDLING EQUIPMENT SHALL BE DEACTIVATED. AN ALARM SIGNAL SHALL BE SENT TO A REMOTE LOCATION VIA AUTOMATIC DIALER. ALSO, DE-ENERGIZE SUPPLY FANS, EXHAUST FANS AND OTHER AIR CIRCULATING DEVICES IF 2000 CFM OR OVER, SERVING THE AREA IN ALARM.
8. ALL LOW VOLTAGE WIRING SHALL BE FPLP RATED WIRE, WITH MINIMUM WIRE SIZE PER SPECIFICATIONS.
   - 8.A. PLENUM RATED CABLE ABOVE ACCESSIBLE CEILING SHALL BE SUPPORTED BY J-HOOKS, SPACED AT FOUR (4) FEET ON CENTER.
   - 8.B. INSTALL FIRE ALARM CABLES IN CONDUIT FOR AREAS WITHOUT CEILING OR ABOVE INACCESSIBLE CEILINGS.
   - 8.C. EXPOSED CONDUIT IN FINISHED SPACES SHALL BE ALLOWED WHERE NO OTHER OPTION EXISTS AND ONLY WITH PRIOR WRITTEN APPROVAL BY THE OWNER. ALL EXPOSED CONDUIT SHALL BE PAINTED TO MATCH.
   - 8.D. ALL CABLING THROUGH WALLS, FIRE WALLS AND FLOORS SHALL BE INSTALLED IN SLEEVES WITH PROTECTIVE BUSHINGS ON BOTH ENDS.
9. FIRE ALARM SYSTEM SHALL BE MONITORED BY A UL LISTED CENTRAL RECEIVING STATION.
10. INTERLOCK LIGHTING CONTROL PANELS WITH FIRE ALARM SYSTEM TO ENABLE ALL LIGHTING UPON ACTIVATION.
11. REFER TO THE WRITTEN SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.

## FIRE ALARM SYSTEM NOTES

1. GENERAL CONTRACTOR SHALL COORDINATE WITH ELECTRICAL AND FIRE ALARM SUBCONTRACTOR FOR LOCATIONS OF REMOTE POWER SUPPLIES. FIRE ALARM POWER SUPPLIES ARE NOT SHOWN ON THIS DRAWING AND SHALL BE LOCATED BY FIRE ALARM SUBCONTRACTOR IN ORDER TO ACCOMMODATE HIS FIRE ALARM SYSTEM BATTERY AND VOLTAGE DROP CALCULATIONS PER MANUFACTURER'S RECOMMENDATION & NFPA REQUIREMENTS. ELECTRICAL CONTRACTOR SHALL INCLUDE ADDITIONAL DEDICATED 120V CIRCUITS IN BASE BID TO SERVE FIRE ALARM POWER SUPPLIES IN DIFFERENT AREAS. PROVIDE 2–12 +12G, 3/4"C AND SPARE 20A/1P CB(S) IN LOCAL LIFE SAFETY EMERGENCY 120V PANELS TO SERVE FIRE ALARM REMOTE POWER SUPPLIES.
2. FIRE ALARM CONTRACTOR IS RESPONSIBLE FOR DESIGN AND FOR FINAL CORRECT LOCATION OF DEVICES TO RELIEVE NUISANCE ALARMS, SUCH AS INSTALLING A HEAT DETECTOR IN FRONT OF AN OVEN WHICH WILL RELEASE STEAM, THUS POTENTIALLY SETTING OFF THE ALARM. ALSO, THE CONTRACTOR IS RESPONSIBLE FOR DETECTORS REQUIRED BY CODE EVEN IF NOT SHOWN ON DRAWING, LIKE A CLOSET. IF THERE IS UNCERTAINTY, BRING UP DURING THE BID PROCESS AND THEY WILL BE ADDRESSED DURING THE BIDDING PROCESS.
3. FIELD VERIFY ENVIRONMENTAL ISSUES THAT CAN ADVERSELY AFFECT OPERATION OF SMOKE DETECTORS. DO NOT LOCATE NEAR AIR FLOW DEVICES LEADING TO PREMATURE BUILD UP OF DUST CAUSING NUISANCE TROUBLE SIGNALS. DEVICE RELOCATION OR TYPE CHANGE WILL BE COVERED UNDER WARRANTY.

## FIRE ALARM SCOPE OF WORK

1. THERE IS AN EXISTING FIRE ALARM SYSTEM IN EACH BUILDING.
   - 1.A. TEST THE EXISTING SYSTEM PRIOR TO BEGINNING DEMO. NOTE ANY FAULTS OR TROUBLES AND PROVIDE A WRITTEN REPORT TO THE OWNER.
   - 1.B. EXPAND THE EXISTING SYSTEM AS REQUIRED TO INTEGRATE THE NEW DEVICES IN THE AREA OF RENOVATION.
2. PROVIDE WIRING AND DEVICES AS INDICATED TO PROVIDE COMPLETE AUDIBLE, INTELLIGIBLE AND VISUAL ALARM COVERAGE OF RENOVATED AREAS AS REQUIRED BY CODE.
   - 2.A. PROVIDE SMOKE DETECTOR COVERAGE OF ALL STORAGE ROOMS AND ADDITIONALLY AS SHOWN ON THE DRAWINGS.
   - 2.B. PROVIDE HEAT DETECTOR COVERAGE OF THE KITCHEN, CUSTODIAL ROOMS, AND ADDITIONALLY AS SHOWN ON THE DRAWINGS.
   - 2.C. PROVIDE DUCT MOUNTED DETECTORS AT EACH NEW AIR HANDLING UNIT SUPPLY AND RETURN CONNECTION EXCEEDING 2000 CFM. IF FREE AIR RETURN, PROVIDE FREE AIR DETECTING COVERAGE OF THE RETURN AIR OPENINGS TO THE MECHANICAL ROOM. ENSURE AIR FLOW CANNOT PREVENT OPERATION OF THE DETECTORS AND PROVIDE ADEQUATE CLEARANCE PER NFPA 72.
   - 2.D. CONTROL RELAYS SHALL BE LOCATED WITHIN 3 FT OF THE CONTROLLED CIRCUIT OR APPLIANCE.
3. PROVIDE SMOKE DETECTORS AT EACH NEW FIRE ALARM PANEL, REMOTE TRANSPONDER PANEL, BOOSTER PANEL AND REMOTE ANNUNCIATOR PER NFPA 72.
4. PROVIDE LED REMOTE ALARM WITH ENGRAVED STAINLESS STEEL PLATE WHERE DUCT DETECTORS ARE NOT LOCATED IN MECHANICAL ROOM, LOCATED ABOVE CEILINGS OR WHERE MOUNTED TOO HIGH OR VIEW IS BLOCKED BY DUCTWORK IN MECHANICAL ROOM.
   - 4.A. REMOTE LED LIGHT INDICATOR FOR DUCT SMOKE DETECTORS SHALL BE MOUNTED FLUSH IN CEILING OR MOUNTED IN WALL AT +7FT.
   - 4.B. STAINLESS STEEL PLATE SHALL BE ENGRAVED WITH THE DUCT SMOKE DETECTOR AS–BUILT IDENTIFICATION NUMBER.
5. REFER TO THE WRITTEN SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.

## SPARES

1. THE FIRE ALARM CONTRACTOR SHALL INCLUDE IN HIS BID THE COST TO PROVIDE AND INSTALL THE ADDITIONAL SPARE PARTS AND ASSOCIATED CABLING PER THE SPECIFICATIONS. SPARES SHALL BE INSTALLED AS INSTRUCTED BY THE OWNER. UNINSTALLED DEVICES SHALL BE DELIVERED TO THE OWNER AS ATTIC STOCK.

## GENERAL RENOVATION AND REMODELING NOTES

1. READ ALL MEP AND ARCH. DRAWINGS TO IDENTIFY AREAS OF RENOVATION AND SCOPE OF WORK.
2. ALL RENOVATION AND DEMOLITION WORK SHALL NOT AFFECT AREAS NOT INCLUDED IN THE AREAS OF WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE CONTINUITY OF ALL SERVICES (POWER, TELEPHONE, FIRE ALARM, DATA, SECURITY, ETC.) IN NON–DEMOLITION/RENOVATION AREAS. ALL SERVICES SHALL BE MAINTAINED AT ALL TIMES.
3. ALL OUTAGES AFFECTING NON–DEMOLITION/RENOVATION AREAS SHALL BE SCHEDULED WITH THE OWNER WITH A MINIMUM 2 WEEKS ADVANCE NOTICE. OUTAGES SHALL BE COORDINATED WITH OTHER TRADES TO MINIMIZE THE QUANTITY AND IMPACT ON BUILDING OPERATION.
4. THIS ELECTRICAL DRAWING ONLY SHOWS SOME EXISTING ELECTRICAL PANELS, DEVICES AND LIGHT FIXTURES IN AREAS OF RENOVATION. ALL OTHER ELECTRICAL EQUIPMENT, WIRING DEVICES, LOW VOLTAGE SYSTEMS, J–BOXES AND CONDUITS SHALL BE LOCATED AND FIELD VERIFIED BY CONTRACTOR.
5. CONTRACTOR SHALL FIELD VERIFY AND MARK UP THE FOLLOWINGS IN AREAS OF RENOVATION:
   - 5.A. EXISTING DATA, AUDIO, VIDEO, SPEAKERS AND OTHER LOW VOLTAGE OUTLETS AND DEVICES.
   - 5.B. EXISTING CEILING MOUNTED PROJECTORS.
   - 5.C. EXISTING SECURITY, CCTV, ACCESS CONTROL DEVICES.
   - 5.D. EXISTING FIRE ALARM DEVICES.
   - 5.E. EXISTING WIRELESS ACCESS POINTS AND GRID LABELING.
   - 5.F. EXISTING LIGHT FIXTURES AND SWITCHES.
   - 5.G. EXISTING ELECTRICAL DEVICES, J–BOXES, CONDUIT, WIRING, WIRING SUPPORTS, ETC.
   - 5.H. EXISTING ELECTRICAL SWITCHGEAR.
   - 5.I. EXISTING CONTROL PANELS AND CONTROL CIRCUITS.
   - 5.J. EXISTING HANGER WIRE FROM CONC. CEILING.
6. ALL REMOVED DEVICES SHALL BE OFFERED TO THE OWNER AS SALVAGE.
7. ALL EXISTING DEVICES SHALL BE REINSTALLED IN NEW CEILINGS AT SAME LOCATION EXCEPT WHERE SHOWN TO BE NEW.
8. CONDUIT/WIRE NOT TO BE REUSED SHALL BE REMOVED ALL THE WAY BACK TO THE UPSTREAM EQUIPMENT.
   - 8.A. PROVIDE ADDITIONAL SUPPORTS FOR EXISTING CONDUIT/WIRE TO REMAIN TO MEET CURRENT CODE REQUIREMENTS.
9. ANY MATERIAL THAT HAS SALVAGE VALUE SHALL BE OFFERED TO THE OWNER, AND IF ACCEPTED, DELIVERED TO HIS WAREHOUSE. IF NOT ACCEPTED IT SHALL BE PROPERLY DISPOSED OF WITH THE OTHER CONSTRUCTION DEBRIS.
10. RELOCATE CONDUIT AS NECESSARY TO ALLOW NEW OR MODIFIED CONSTRUCTION. REPAIR EXISTING ELECTRICAL SYSTEMS DAMAGED BY CONSTRUCTION ACTIVITES.
11. WHERE PARTIAL CIRCUITS OR SYSTEMS ARE TO BE REUSED, ENSURE THAT THEY REMAIN ACTIVE. WHERE EXISTING EQUIPMENT IS RELOCATED OR REPLACED WITH NEW, MODIFY, EXTEND AND RELOCATE EXISTING CIRCUIT TO CONNECT TO EQUIPMENT, UNLESS SHOWN TO HAVE NEW CIRCUIT.
12. WHERE AUXILIARY SYSTEMS SUCH AS SECURITY, DATA, SOUND, ETC. INTERFACE WITH EXISTING EQUIPMENT THAT IS REPLACED OR MODIFIED (MECHANICAL, ELECTRICAL OR PLUMBING), DISCONNECT AND RECONNECT THESE SYSTEMS.
13. WHERE NEW CIRCUIT BREAKERS ARE TO BE INSTALLED IN EXISTING PANELS OR SWITCHBOARD, VERIFY THAT THE CIRCUIT BREAKER WILL FIT IN THE ALLOTTED SPACE. PROVIDE NEMA 1 ENCLOSURE ADJACENT TO PANEL & WIRE CONNECT TO BUSSING IF THERE IS INSUFFICIENT SPACE.
14. WHERE PARTIAL CIRCUITS OR SYSTEMS ARE TO BE REUSED, ENSURE THAT THEY REMAIN ACTIVE. WHERE EXISTING EQUIPMENT IS RELOCATED OR REPLACED WITH NEW, MODIFY, EXTEND AND RELOCATE EXISTING CIRCUIT TO CONNECT TO EQUIPMENT, UNLESS SHOWN TO HAVE NEW CIRCUIT.
15. WHEN REPLACING LIGHTS AND CEILINGS, ENSURE THAT EXISTING DATA, TELEVISION AND PA CABLES TO REMAIN CONTINUE TO MEET THE CURRENT STANDARDS. FOR DATA CABLES, THIS IS THE IEEE 802.1. FOR TELEVISION AND PA CABLE, A FOUR INCH DISTANCE IS NEEDED FROM ALL LIGHT FIXTURES. NEW DROP LOCATION SHOULD BE WITHIN THREE FEET OF POWER OUTLET.
16. PAINT NEW AND EXISTING EXPOSED RACEWAY IN AREAS OF RENOVATION TO MATCH FINISHES.
17. ANY DAMAGE TO EXISTING BUILDING, ELECTRICAL EQUIPMENT, WIRING DEVICES, CONDUIT, WIRING, ETC. SHALL BE REPLACED BY THE CONTRACTOR AT NO COST TO THE OWNER. ALL MATERIALS USED FOR THE REPLACEMENT MUST MEET RENOVATION PROJECT STANDARDS.
18. INTERESTED CONTRACTORS MUST VISIT THE SITE PRIOR TO BIDDING TO BECOME FAMILIAR WITH THE PROJECT REQUIREMENTS AND EXISTING CONDITIONS AND SHALL INCLUDE IN THEIR PROPOSALS COSTS TO REPAIR, RELOCATE, MODIFY AND REMOVE EXISTING ELEMENTS AS REQUIRED TO COMPLETE INSTALLATION OF ALL SYSTEMS SHOWN ON THESE DRAWINGS.
19. SEE DRAWINGS FOR ADDITIONAL REQUIREMENTS.

## ELEC REQUIREMENTS FOR BUILDING RENOVATION

1. ELECTRICAL CONTRACTOR SHALL BEGIN FIELD VERIFYING ALL EXISTING BRANCH CIRCUITS FOR EXISTING AREAS TO BE RENOVATED IMMEDIATELY AFTER THE CONTRACT IS ISSUED.
2. ELECTRICAL CONTRACTOR SHALL FIELD VERIFY EXISTING CIRCUITS WITH OWNER'S MAINTENANCE PERSONNEL AFTER NORMAL BUILDING HOURS AS REQUIRED.
3. ELECTRICAL CONTRACTOR SHALL INCLUDE COST RELATED TO FIELD VERIFY EXISTING CIRCUITS IN BASE PROPOSAL.
4. FIND AND RECORD ALL EXISTING DEVICES IN CEILINGS, WALLS AND CASEWORK IN AREAS TO BE RENOVATED. PROVIDE A COPY OF THE FIELD VERIFIED DEVICE DRAWINGS TO OWNER PRIOR TO BEGINNING WORK.
5. ALL EXISTING DEVICES TO REMAIN SHALL BE REINSTALLED IN NEW CEILINGS AND WALLS EXCEPT WHERE INDICATED TO BE REMOVED/RELOCATED/REPLACED.
6. EXISTING DEVICES IN WALLS TO BE FURRED OUT OR RECEIVE NEW SURFACE TREATMENT SHALL REMAIN. EXTEND JBOX TO NEW WALL SURFACE AND RECONNECT TO EXISTING CIRCUITS. EXTEND WIRING/CABLING FROM NEAREST ACCESSIBLE POINT AS NECESSARY.
7. REINSTALL ALL DEVICES NOT SHOWN TO BE REMOVED.
8. EXISTING LIGHT FIXTURES SHALL REMAIN EXCEPT WHERE SHOWN AS NEW. EXTEND EXIST CONDUIT AND WIRE DOWN TO NEW LIGHT FIXTURES, REFERENCE SPECIFICATIONS FOR ADDITIONAL INFORMATION.
9. ALL EXISTING EXIT SIGNS SHALL BE REINSTALLED AND RECONNECTED TO EXISTING CIRCUITS EXCEPT IN CORRIDORS AND AREAS OF RENOVATION SHOWING NEW.
10. ALL NEW DEVICES IN EXISTING WALLS IN FINISHED SPACES SHALL BE INSTALLED FLUSH MOUNTED, NO EXPOSED CONDUIT OR WIREMOLD ALLOWED. CUT EXISTING WALLS AND PATCH/REPAIR TO MATCH EXISTING AS REQUIRED.
    - 10.1. DEVICES/CONDUIT IN CUSTODIAL, MECHANICAL AND ELECTRICAL ROOMS MAY BE EXPOSED AND SURFACE MOUNTED.
11. PROVIDE NEW DIRECTORY FOR ALL EXISTING AND NEW PANELS SHOWING FIELD VERIFIED CIRCUITS.
12. ANY FEEDER AND BRANCH CIRCUIT NOT TO BE REUSED SHALL BE REMOVED COMPLETELY UP TO CB IN EXISTING PANEL.
13. ANY CIRCUIT OR PARTIAL CIRCUIT TO BE REUSED SHALL REMAIN ACTIVE.

## GENERAL EQUIPMENT ELECTRICAL NOTE

THE ELECTRICAL DESIGN HAS BEEN COORDINATED FOR SPACE, INSTALLATION AND ELECTRICAL REQUIREMENTS WITH EQUIPMENT THAT IS SCHEDULED BY OTHER DIVISIONS. THE REQUIREMENTS FOR OTHER EQUIPMENT AND MODELS FROM ACCEPTABLE MANUFACTURERS HAVE NOT BEEN VERIFIED OR COORDINATED. THE GENERAL CONTRACTOR SHALL VERIFY THESE REQUIREMENTS PRIOR TO USING OTHER EQUIPMENT IN HIS BID AND INCLUDE ANY ADDITIONAL COSTS FOR INSTALLATION OF THE EQUIPMENT. THIS INCLUDES GENERAL CONSTRUCTION AND MEP COSTS.

ELECTRICAL CONTRACTOR SHALL COORDINATE WITH OWNER/OTHER TRADES FOR EXACT ELECTRICAL REQUIREMENTS OF EQUIPMENT PRIOR TO ORDERING CB(S). FIELD VERIFY EQUIPMENT NAMEPLATE RATINGS AND EQUIPMENT CONNECTION LOCATIONS WITH OTHER TRADES PRIOR TO ROUGH–IN.

TYPICAL OF HVAC EQUIPMENT, SHOP EQUIPMENT, KITCHEN EQUIPMENT, ELECTRIC ROLLUP DOORS, ETC.

## GENERAL ELECTRICAL NOTES

1. REFER TO THE WRITTEN SPECIFICATIONS FOR ADDITIONAL INFORMATION.
2. INSTALL SYSTEMS IN ACCORDANCE WITH THE NATIONAL ELECTRIC CODE.
3. PROVIDE LIGHT FIXTURE FIRE PROTECTION AND CONDUIT FIRE SEALING TO MAINTAIN FIRE RATING OF WALLS AND CEILINGS PER ARCHITECT'S SCHEDULE. REF. SPECIFICATIONS AND ARCH. DRAWINGS FOR ADDITIONAL INFORMATION.
4. ELECTRICAL RECEPTACLES, TELEPHONES, ETC... ARE SHOWN FOR GENERAL LOCATION. HEIGHTS ARE NOTED SO THE ESTIMATOR WILL KNOW WHETHER THEY ARE ABOVE OR BELOW COUNTERS. PRIOR TO INSTALLATION, REVIEW THE ARCHITECTURAL DRAWINGS AND SPECIFICATIONS. IN THE EVENT OF CONFLICT, THE ARCHITECT'S LOCATION WILL GENERALLY PREVAIL BUT SHOULD BE CLARIFIED BY RFI. PROVIDE DEVICES SHOWN ON THE ELECTRICAL DRAWING EVEN IF NOT SHOWN ON ARCHITECTURAL DRAWINGS.
5. COORDINATE POWER AND DATA WITH THE FURNITURE SUPPLIER PRIOR TO ROUGH–IN. AT CASEWORK WITH WIRE SPACE, MOUNT RECEPTACLES AND DATA OUTLETS IN KNEE SPACE. COORDINATE WITH ARCHITECT AND FURNITURE SUPPLIER TO ENSURE THAT PROTECTIVE GROMMETS ARE PROVIDED IN THE COUNTER.
6. DO NOT INSTALL ELECTRICAL PANELS AND TRANSFORMERS UNTIL 1/4" SCALE DRAWINGS SHOWING LOCATION OF THIS EQUIPMENT RELATIVE TO MECHANICAL/PLUMBING EQUIPMENT, DUCTWORK AND PIPING IS SUBMITTED AND APPROVED. NEC CODE CLEARANCE MUST BE MAINTAINED.
7. ELECTRICAL EQUIPMENT HAS BEEN COORDINATED WITH PIPING AND DUCTWORK. DO NOT RELOCATE PANELS WITHOUT PRIOR APPROVAL.
8. ELECTRICAL DEVICES IN FIRE RATED WALLS SHALL BE A MINIMUM OF 24" AWAY FROM DEVICES ON THE OPPOSITE SIDE OF THE WALL TO MAINTAIN FIRE RATING.
9. MINIMUM SIZE CONDUIT FOR POWER SHALL BE 3/4", MIN. SIZE FLEX CONDUIT MAY BE 1/2". MINIMUM SIZE CONDUIT FOR DATA SHALL BE 1"C. DO NOT COMBINE CONDUIT FOR DATA.
10. MAX. LENGTH FOR FLEX CONDUIT SHALL BE 6 FT. ALL FLEX CONDUIT SHALL BE LISTED FOR GROUNDING.
11. LIGHT FIXTURE WHIPS MAY BE MIN. 1/2" FLEX CONDUIT WITH MIN. #12 WIRE. LIGHT FIXTURE WHIPS SHALL BE NO MORE THAN 6 FT LONG.
12. PROVIDE GREEN GROUND WIRE WITH ALL CIRCUITS SIZED PER NEC. BOND GREEN GROUND WIRE TO EACH END OF CONDUIT.
13. GROUND TRANSFORMER SECONDARIES TO BUILDING STEEL AND GROUND ROD. PROVIDE CONDUIT TO PROTECT GROUNDING CONDUCTOR AND BOND EACH END OF CONDUIT TO GROUNDING SYSTEM. MIN. SIZE OF CONDUIT FOR GROUND WIRE SHALL BE 3/4"C.
14. PROVIDE J–BOXES, CONDUIT AND SLEEVES THRU ALL FIRE WALLS FOR DATA, TELEPHONE, SECURITY, FIRE ALARM AND SOUND SYSTEMS WIRINGS, ETC. SEE SPECIFICATIONS.
15. PROVIDE PULL BOXES, JUNCTION BOXES, WIRING TROUGHS AND CABINETS WHEREVER REQUIRED FOR PROPER INSTALLATION OF VARIOUS ELECTRICAL SYSTEMS.
16. WHERE PORTIONS OF INTERIOR RACEWAY SYSTEM ARE EXPOSED TO WIDELY DIFFERENT TEMPERATURES, PROVIDE AIR SEALING PER NEC TO PREVENT CIRCULATION OF AIR FROM WARMER TO A COOLER SECTION.
17. ALL WIRING SHALL BE 600 VOLT, SOFT DRAWN ANNEALED COPPER, 98% CONDUCTIVITY, CONTINUOUS FROM OUTLET TO OUTLET. MINIMUM WIRE SIZE #12. ALL WIRE SHALL BE STRANDED TYPE THHN OR THWN–2 (WET RATED FOR 90° C). ALL WIRES SHALL BE COLOR CODED WITH SAME COLOR CONNECTED TO SAME UNGROUNDED PHASE THROUGHOUT THE INSTALLATION.
18. ALL ELECTRICAL WIRING SHALL BE INSTALLED IN CONDUIT. NO SURFACE MOUNTED WIREMOLD SHALL BE ALLOWED IN FINISHED SPACES. MC CABLE SHALL BE ALLOWED INSIDE EXIST STUD WALLS OR CHASE WALLS.
19. PROVIDE AND INSTALL FINAL CONNECTIONS TO ALL EQUIPMENT PROVIDED BY OTHER TRADES AND/OR FURNISHED BY OWNER INCLUDING ALL NECESSARY CONDUIT, CORDS, PLUGS, WHIPS, HARDWIRING, ETC. IN PARTICULAR CONFIRM CONNECTION REQUIREMENTS WITH DELIVERED EQUIPMENT PRIOR TO ROUGH–IN.
20. ALL MATERIAL MUST BE NEW AND OF GOOD QUALITY AND SHALL BEAR THE STAMP OF APPROVAL OF THE UNDERWRITERS' LABORATORIES, INC. (U.L.).

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
6955 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING


ELECTRICAL AND FIRE ALARM NOTES

k-E.001


STANTON ENGINEERING GROUP
INFO@STANTON–ENGR.COM (713) 305–6266


TEXAS ENG. FIRM REG. NO. F–018330 | © 2025 ALL RIGHTS RESERVED



12999 W. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77040




## 1 TYPICAL DATA OUTLETS

NO SCALE


NOTES:
1. PROVIDE DEEP 4 11/16" X 4 11/16" X 2 1/8", 2-GANG BACK BOX FOR ALL DATA OUTLETS.
   1.A. PROVIDE SINGLE GANG MUDRING FOR DATA OUTLETS WITH 1-4 DROPS.
   1.B. PROVIDE PULL STRING IN ALL LOW VOLTAGE CONDUITS.
2. LOW VOLTAGE CABLING AND DEVICES BY DIVISION 27.
3. REFERENCE TECHNOLOGY DRAWINGS FOR ADDITIONAL INFORMATION.




## 2 TYPICAL POWER & DATA OUTLET DETAIL

NO SCALE

NOTES:
1. LOCATE DEVICES GROUPED TOGETHER AS CLOSELY TOGETHER AS POSSIBLE.
   1.A. USE CADDY TSGB16, RBS16 OR SIMILAR MOUNTING BAR IN SHEETROCK WALLS.




## 3 TYPICAL ELECTRICAL DEVICES

NO SCALE

NOTES:
1. ALL DEVICES SHALL BE COLOR CODED PER SPECIFICATIONS WITH 302/304 STAINLESS STEEL, STANDARD SIZE, FACEPLATES.
2. ONLY SELECT RECEPTACLES ARE SHOWN HERE. PROVIDE SIMILAR LABELS ON ALL SWITCHES, NEMA POWER OUTLETS, ETC.
3. PROVIDE LABEL WITH RED TEXT READING "EMERGENCY" FOR DEVICES ON GENERATOR FED CIRCUITS.
4. PROVIDE TYPEWRITTEN OR PREMADE CIRCUIT LABELS INDICATING THE ELECTRICAL CIRCUIT ON:
   4.A. INSTALLED WIRING AT EACH SPLICE POINT
   4.B. EACH J-BOX ABOVE CEILING WITH WIRING INSTALLED OR MODIFIED AS PART OF THIS PROJECT.
   4.C. AFFIXED TO THE FRONT OF EACH NEW AND EXISTING DEVICE FACEPLATE IN THE AREA OF RENOVATION.

XX-## CIRCUIT LABEL
   A. XX = PANEL DESIGNATION
   B. ## = AS-BUILT CIRCUIT DESIGNATION

STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM (713) 305-6080
TEXAS ENG. FIRM REG NO. F-18332-00 2025 ALL RIGHTS RESERVED
12999 W. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77040

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL


STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL DEVICE DETAILS


k-E.010




## 10 MECHANICAL - ELECTRICAL COORDINATION DETAIL

NO SCALE

**COORDINATE WITH OTHER TRADES TO ENSURE NO PIPING AND DUCTWORK ABOVE ELECTRICAL EQUIPMENT AS SHOWN. PROVIDE WORKING CLEARANCE IN FRONT OF STARTERS, DISCONNECTS, PANELS, XFMRS AND ADDITIONALLY PER CODE.**




## 11 CONDUIT ROOF PENETRATION DETAIL


NO SCALE




## 12 ROOF AND CANOPY CONDUIT SUPPORT DETAIL

NO SCALE

1. COORDINATE WITH ARCHITECTURAL DRAWINGS, DETAILS, SPECIFICATIONS AND OTHER TRADES.





## 13 CANOPY LIGHT MOUNTING DETAIL TYPE 1

NO SCALE

NOTES:

1. MOUNTING PLATES SHALL BE WELDED TO CANOPY TO MOUNT LIGHT FIXTURES.
2. FOR FIXTURES WITH END CONDUIT ATTACHMENTS ALL CANOPY PENETRATIONS SHALL BE MADE OFF CENTER FROM THE FIXTURE WIRING ENTRY POINT AND SHALL HAVE WEATHERTIGHT SEALING. (SHOWN HERE)
3. CANOPY PENETRATIONS ABOVE FIXTURES SHALL BE PERMITTED ONLY WHERE THE SUPPLIED FIXTURE HAS NO END CONDUIT ATTACHMENTS.
4. CONDUIT SHALL BE SEALED BOTH ABOVE AND BELOW THE CANOPY PENETRATION AND AGAIN AT THE FIXTURE ENTRY POINT TO PREVENT WATER FROM ENTERING THE LIGHTING FIXTURE.
5. CANOPY PENETRATIONS SHALL BE MADE AS CLOSE TO CONDUIT ENTRY PENETRATION POINT AS POSSIBLE AND CONDUIT SHALL BE ROUTED TO MINIMIZE EXPOSED CONDUIT.





## 7 EDF GFI PROTECTION DETAIL

NO SCALE

NOTES:

1. MODIFY EXISTING WALL AS NEEDED TO INSTALL NEW RECEPTACLE AND REMOTE GFI TEST SWITCH. PATCH/REPAIR WALL AS NEEDED TO MATCH EXISTING.
2. WIRE NEW RECEPTACLE DOWNSTREAM OF REMOTE GFI TEST SWITCH.
3. REMOTE GFI TEST SWITCH SHALL BE A DEAD FRONT GFI DEVICE TO BE INSTALLED FLUSH MOUNTED IN WALL WITH EDF SERVED AND PROVIDE GFI PROTECTION FOR THE RECEPTACLE LOCATED WITHIN THE EDF HOUSING.
4. GFI TEST SWITCH SHALL BE READILY ACCESSIBLE PER NEC 210.8.
5. COORDINATE RECEPTACLE LOCATION(S) WITHIN EDF HOUSINGS WITH MANUFACTURER'S INSTALLATION INSTRUCTIONS.





## 8 TRANSFORMER CONNECTION AND GROUNDING DETAIL

NO SCALE


NOTES:

1. INSTALL GROUND ROD ADJACENT TO TRANSFORMER AND SEAL PENETRATION AROUND GROUND ROD.
2. WHERE AN ISOLATED GROUND IS PROVIDED MAKE THE CONNECTION AT THE TRANSFORMER AND RUN DIRECTLY TO THE ISOLATED GROUND BAR IN THE PANELBOARD. DO NOT DEFINE THE ISOLATED GROUND AT THE PANELBOARD.
3. FINAL CONNECTIONS TO TRANSFORMERS SHALL BE MADE IN FLEXIBLE CONDUIT. PROVIDE LIQUID TIGHT CONSTRUCTION AND FITTINGS IN WET, DAMP OR OUTSIDE AREAS EXCEPT WHERE LOCATED IN AIR HANDLING ROOMS. REFERENCE SPECIFICATIONS FOR ADDITIONAL INFORMATION.





## 9 PIGTAIL WIRING DETAIL FOR ELECTRICAL DEVICE

NO SCALE





## 1 CONDUIT/J-BOX DETAIL FOR LIGHT FIXTURES IN LAY-IN CEILING

NO SCALE




## 2 FIXTURE SUPPORT DETAIL

NO SCALE





## 3 TRAPEZE MOUNTED CONDUIT DETAIL

NO SCALE

NOTES:

1. ALL SUPPORT DEVICES SHALL BE UL LISTED AND NEC APPROVED.
2. REFER TO NEC FOR CONDUIT SUPPORT SPACING.





## 4 WALL MOUNTED CONDUITS

NO SCALE

NOTES:

1. ALL SUPPORT DEVICES SHALL BE UL LISTED AND NEC APPROVED.
2. REFER TO NEC FOR CONDUIT SUPPORT SPACING.





## 5 FIREWALL PENETRATION DETAIL

NO SCALE

NOTES:

1. FIRE RATING OF COMPLETED FIREPROOFED ASSEMBLY SHALL BE EQUAL OR EXCEED RATING OF WALL.




## 6 GROUNDING BUSHING WIRING DETAIL

NO SCALE

NOTE:

1. PROVIDE AND INSTALL GROUNDING BUSHINGS FOR DISCONNECT SWITCHES, PANELS AND TRANSFORMERS.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT

HUNTERS GLEN ELEMENTARY SCHOOL
6955 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL DETAILS

k-E.011


STANTON ENGINEERING GROUP
INFORMATION-DESIGN
(713) 360-6080
TEXAS ENG. FIRM REG. NO. F-018532 (C) 2025 ALL RIGHTS RESERVED
12800 N. SAM HOUSTON PARKWAY E., SUITE 125, HOUSTON, TX 77060




## 5 TYPICAL BRANCH CIRCUIT PANEL LABELING DETAIL

NO SCALE

NOTES:

1. LAYOUT OF PANELBOARD, INCLUDING LOCATIONS OF NAMEPLATES, CIRCUIT DIRECTORY, AND OTHER LABELING IS SHOWN FOR REFERENCE ONLY, FIELD LOCATE AS NEEDED BASED ON TRUE EQUIPMENT LAYOUT AND DIMENSIONS.
2. REFERENCE OWNER'S DESIGN GUIDELINES FOR ADDITIONAL LABELING REQUIREMENTS.

(1) PROVIDE LAMACOID NAMEPLATE WITH 5/16" LETTERS SHOWING PANEL NAME, AMPERAGE RATING, VOLTAGE, AND FROM WHERE POWER IS DERIVED. ATTACH WITH MASTIC AND TWO SCREWS. COORDINATE TO GIVE SAME NAME AS PANEL SCHEDULE. IF USED AS MAIN SERVICE PANEL, PROVIDE SHORT CIRCUIT AVAILABLE AND RATING INFORMATION.

(2) PROVIDE PERMANENT ARC FAULT WARNING LABEL.


(3) FOR ALL NEW ELECTRICAL EQUIPMENT, PROVIDE PERMANENTLY AFFIXED LABEL STATING FAULT CURRENT AT THE TIME OF INSTALLATION AND CALCULATION. THE LABEL SHALL BE MINIMUM 2" X 3" IN SIZE, AND INCLUDE THE DATE OF THE CALCULATION. REFERENCE ELECTRICAL DRAWINGS AND EQUIPMENT SHORT CIRCUIT ANALYSIS TABLE. ATTACH WITH MASTIC AND TWO SCREWS.

(4) PROVIDE INFORMATION PER INDUSTRY STANDARDS, BUT SHALL INCLUDE VOLTAGE, PHASE, BUS AMPERAGE, AND SHORT CIRCUIT RATING

(5) FOR EACH CIRCUIT PROVIDE PERMANENT LABEL INDICATING CIRCUIT BREAKER NUMBER, NUMBER SHALL MATCH CIRCUIT DIRECTORY.

(6) CIRCUIT DIRECTORY TO BE COMPLETED AT END OF JOB, TYPEWRITTEN, STATING EQUIPMENT OR ROOMS SERVED BY CIRCUIT. EVEN CIRCUIT ON RIGHT SIDE OF CARD, ODD ON LEFT. PROVIDE LAMINATED DIRECTORY FOR EXTERIOR OR WET LOCATIONS.

(7) PROVIDE PERMANENT LABEL INDICATING COLOR CODING OF PHASE CONDUCTORS BASED ON VOLTAGE USING BUILDING COLOR SCHEME AS IDENTIFIED IN THE OWNER'S DESIGN GUIDELINES.




## 1 TYPICAL DISCONNECT, STARTER, & CONTACTOR LABELING DETAIL

NO SCALE

NOTES:

1. LOCATIONS OF NAMEPLATES SHOWN FOR REFERENCE ONLY, FIELD LOCATE AS NEEDED BASED ON TRUE EQUIPMENT LAYOUT AND DIMENSIONS. REFERENCE OWNER'S DESIGN GUIDELINES FOR ADDITIONAL LABELING REQUIREMENTS.

(1) PROVIDE AN ENGRAVED NAMEPLATE SHOWING LOAD SERVED, EQUIPMENT VOLTAGE, AND CIRCUIT NUMBER MATCHING AS-BUILT CONDITIONS.

(2) PROVIDE AN ENGRAVED NAMEPLATE SHOWING LOADS SERVED, VOLTAGES, AND CIRCUIT NUMBERS MATCHING AS-BUILT CONDITIONS FOR ALL CONTACTOR CIRCUITS. LOADS SERVED SHALL BE "LIGHTING", "FAN", "RECEPTACLES", "PUMP", "WATER HEATER", OR SIMILAR DESCRIPTIVE NOTE.

**DISHWASHER**
**480V, 3PH, 3 WIRE**
**FROM HK-2/4/6**

## 2 DISCONNECT LABELING

NO SCALE

NOTES:

1. PROVIDE LABEL ON EACH DISCONNECT AND FUSED SWITCH.
   1.1. FOR DISCONNECTS AND FUSED SWITCHES REPLACE "PANEL P1NA" WITH THE LOAD SERVED.
   1.2. REFER TO OWNER'S STANDARDS FOR ADDITIONAL LABEL REQUIREMENTS.
2. PROVIDE LABEL ON ELECTRICAL PANEL AND TRANSFORMER.
   2.1. REPLACE "PANEL P1NA" WITH THE PANEL OR TRANSFORMER NAME BEING LABELED.
3. REPLACE "400A FUSED SWITCH" WITH UPSTREAM SOURCE OR CONNECTION.
   3.1. IF FED FROM A XFMR REPLACE "400A FUSED SWITCH" WITH "XFMR XX" WHERE XX IS THE FIELD VERIFIED XFMR NAME.
4. REPLACE VOLTAGE CONFIGURATION TO MATCH THE EQUIPMENT BEING LABELED.
5. REFERENCE FLOOR PLANS FOR EQUIPMENT LOCATIONS.

**⚠ WARNING**

**Arc Flash and Shock Hazard**
**Appropriate PPE Required**


| FLASH PROTECTION | | SHOCK PROTECTION | |
|---|---|---|---|
| Incident Energy at: | 16 in | Shock Risk When Cover is Removed | 480 VAC |
| Min. Arc Rating: | 0.45 cal/cm² | Limited Approach | 42 in |
| Arc Flash Boundary: | 10 in | Restricted Approach: | 12 in |
| PPE: Per NFPA 70E 2015 | 1 | Equipment Name: **PANEL HA** Prot Dev: 225/3 CB from Panel DA | |

## 3 TYPICAL ARC FLASH LABEL DETAIL

NO SCALE

NOTES:

1. VALUES AND NAMES SHOWN HERE ARE FOR REFERENCE ONLY, MODIFY TO REFLECT PROJECT'S ARC FLASH STUDY VALUES AND EQUIPMENT NAMES.
2. IF MIN. ARC RATING IS OVER 40CAL/CM² MODIFY "WARNING" TEXT TO READ "DANGER" AND PROVIDE RED SHADING IN LIEU OF ORANGE SHOWN.




## 4 TYPICAL TRANSFORMER LABELING DETAIL

NO SCALE

NOTES:

1. LOCATIONS OF NAMEPLATES SHOWN FOR REFERENCE ONLY, FIELD LOCATE AS NEEDED BASED ON TRUE EQUIPMENT LAYOUT AND DIMENSIONS.

(1) PROVIDE AN ENGRAVED NAMEPLATE SHOWING EQUIPMENT NAME, RATING, VOLTAGE, SOURCE.

STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM | (713) 303-6080
TEXAS ENG. FIRM REG. NO. F-018332 | © 2025 ALL RIGHTS RESERVED
1300 W. SAM HOUSTON PARKWAY S., SUITE 121, HOUSTON, TX 77042

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL




07.18.2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL DETAILS

k-E.012

## KITCHEN AREA ELECTRICAL NOTES

1. REFER TO KITCHEN CONSULTANTS "FS" DRAWINGS FOR ADDITIONAL REQUIREMENTS PARTICULARLY NOTING MOUNTING HEIGHTS OF EQUIPMENT OUTLETS AND JUNCTION BOXES, AND WHETHER SERVICE IS FROM WALL, FLOOR OR OVERHEAD.
2. SOME RECEPTACLES SHALL BE MOUNTED HORIZONTALLY, REFER TO KITCHEN CONSULTANTS "FS" DRAWINGS.
3. FOR DEVICES WITH SERVICE FROM FLOOR, RUN UNDERGROUND CONDUIT FROM DEVICES TO NEAREST COLUMN OR WALL THEN TURN CONDUIT UP AND RUN CONDUIT IN CEILING CAVITY.
4. LIGHT SWITCHES AND RECEPTACLES NOT SERVING A SPECIFIC PIECE OF EQUIPMENT SHALL BE MOUNTED AT ADA HEIGHTS.
5. CONNECTION TYPE SHOWN ON KITCHEN ELECTRICAL FLOOR PLAN IS FOR BIDDING PURPOSES, COORDINATE WITH KITCHEN EQUIPMENT SUPPLIER FOR FINAL CONNECTIONS:
   - 5.A. OBTAIN WIRING INSTRUCTIONS FOR EACH PIECE OF EQUIPMENT FROM EQUIPMENT SUPPLIER PRIOR TO ORDERING WIRING DEVICES AND ROUGH-IN.
   - 5.B. IF EQUIPMENT REQUIRES CORD AND PLUG CONNECTION, CONTRACTOR SHALL PROVIDE NEMA POWER CORD, PLUG, AND RECEPTACLES PER MANUFACTURER'S INSTRUCTION.
   - 5.C. IF EQUIPMENT REQUIRES JUNCTION BOX AND/OR DISCONNECT SWITCH, CONTRACTOR SHALL PROVIDE JUNCTION BOX AND DISCONNECT SWITCH AND CONNECT EQUIPMENT WITH SEALTITE FLEXIBLE CONDUIT.
6. ALL DISCONNECT SWITCHES IN THE KITCHEN AREA SHALL BE NEMA 4XSS STAINLESS STEEL.
7. WHERE PORTIONS OF INTERIOR RACEWAY SYSTEM ARE EXPOSED TO WIDELY DIFFERENT TEMPERATURES, PROVIDE AIR SEALING PER NEC TO PREVENT CIRCULATION OF AIR FROM WARMER TO A COOLER SECTION.
8. FLEXIBLE CONDUIT IN KITCHENS, FOOD PRODUCTION SPLASH ZONES AND WASH DOWN AREAS, FOOD PROCESSING, AND SIMILAR AREAS SHALL BE LIQUID TIGHT CONSTRUCTION INCORPORATING A BACTERIAL GROWTH INHIBITING PVC JACKET THAT MAY BE CLEANED WITHOUT DEGREDATION TO THE JACKET BLEACHING ELEMENTS AND APPROVED FITTINGS FOR WET LOCATION.
   - 8.A. AFC SZ TYPE LFMC OR EQUAL BY KAF-TECH.
9. INTERLOCK KITCHEN EXHAUST HOOD FIRE SYSTEM WITH FIRE ALARM SYSTEM.
10. PROVIDE RELAYS AND INTERLOCK KITCHEN HOOD FANS WITH FIRE ALARM SYSTEM. ACTUATION OF ANY ALARM INITIATING DEVICE SHALL DE-ENERGIZE KITCHEN HOOD FANS.
11. ALL GFI RECEPTACLES IN KITCHEN SHALL BE PASS & SEYMOUR MODEL 2097TRWR-XX TO EXCEED UL943 VOLTAGE SURGE REQUIREMENTS.





## 4 FIRE PROTECTION SYSTEM DETAIL

NO SCALE

NOTES:

1. ANSUL MODEL R-120 FIRE PROTECTION SYSTEM AND TANK(S)
2. ELECTRICAL CONTRACTOR TO FURNISH AND INSTALL POWER DISCONNECT DEVICES FOR ALL EQUIPMENT BELOW THE HOOD, SHUTTING OFF ALL SERVICE, INCLUDING CONTROL VOLTAGE, UPON ACTIVATION OF THE FIRE PROTECTION SYSTEM.
3. MICRO-SWITCH FURNISHED WITH SYSTEM TO BE INTERWIRED TO THE SHUT-OFF DEVICES FOR THE COOKING EQUIPMENT BY THE ELECTRICAL CONTRACTOR.
4. ELECTRICAL CONTRACTOR TO FURNISH AND INSTALL AN OCTAGON SHAPED HANDY BOX FOR THE PULL STATION AT 54" ABOVE THE FLOOR WITH 1/2" CONDUIT FROM THE TOP OF THE BOX TO 6" ABOVE THE CEILING.
5. GAS SHUT-OFF VALVE FURNISHED WITH THE SYSTEM (IF REQUIRED) TO BE INSTALLED IN THE GAS LINE SERVING THE COOKING EQUIPMENT BY THE PLUMBING CONTRACTOR. VERIFY SIZE OF GAS LINE.
6. ALL EXPOSED PIPEWORK TO BE STAINLESS STEEL OR CHROME WHERE EXPOSED.
7. VERIFY LOCATION OF REMOTE MANUAL PULL STATION.
8. UNIT MUST BE PLACED WITHIN EASY ACCESS OF EXIT DOOR.





## 5 KITCHEN HOOD FAN CONTROL SCHEMATIC

NO SCALE

NOTES:

1. THE FANS SHALL BE WIRED SO THAT ONE LOCAL SWITCH TURNS ON ASSOCIATED SUPPLY AND EXHAUST FANS.
2. IF THE FIRE ALARM IS IN ALARM, A FIRE ALARM CONTROL CONTACT SHALL CAUSE THE SUPPLY FAN TO STOP AND THE EXHAUST FAN TO START, EVEN IF THE CONTROL SWITCH IS "OFF".
3. SCHEMATIC IS DIAGRAMMATIC. PROVIDE INTERLOCK WIRING BASED ON EQUIPMENT PROVIDED AND FAN VOLTAGE TO IMPLEMENT THE SEQUENCE SPECIFIED.
4. COORDINATE BETWEEN FIRE ALARM CONTRACTOR, CONTROLS CONTRACTOR AND ELECTRICAL CONTRACTOR TO PROVIDE A COMPLETE INSTALLATION.
5. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.





## 1 GAS VALVE DETAIL

NO SCALE

NOTES:

1. GAS VALVE HOUSINGS ARE NOT SHOWN ON THE ELECTRICAL DRAWING. GC AND ELECTRICAL CONTRACTOR SHALL COORDINATE SIZE AND LOCATION OF GAS VALVE HOUSINGS.
2. SEE FOOD SERVICE CONSULTANT'S DRAWINGS ADDITIONAL INFORMATION AND REQUIREMENTS.
3. PROVIDE MINIMUM 3/4"C AS SHOWN ON THIS DETAIL.





## 2 RECESSED FIRE PULL DETAILS

NO SCALE

NOTES:

1. VERIFY LOCATION OF REMOTE MANUAL PULL STATION.
   - 1.A. MANUAL PULL STATION MUST BE PLACED WITHIN EASY ACCESS OF EXIT DOOR.
   - 1.B. MANUAL PULL STATION MUST BE PLACED NO LESS THAN 4 FEET AWAY FROM KITCHEN HOOD BUT WITHIN A MAXIMUM OF 20 FEET FROM THE KITCHEN HOOD.




## 3 TYPICAL PEDESTAL MOUNTED DEVICE

NO SCALE

NOTES:

1. ALL FACEPLATES SHALL BE STAINLESS STEEL.
2. PEDESTAL BOX PROVIDED BY DIVISION 26.
   - 2.A. A STANDARD DUPLEX INSTALLATION IS SHOWN FOR REFERENCE, PROVIDE SIMILAR INSTALLATION FOR QUAD RECEPTACLES, GFI RECEPTACLES, DATA OUTLETS, NEMA POWER OUTLETS, ETC.
   - 2.B. ALL PEDESTAL BOXES TO BE DOUBLE FACED WITH ONE BLANK FACE FOR FUTURE GROWTH. 2-GANG PEDESTALS WITH ONE BLANK FACE FOR QUAD RECEPTACLE LOCATIONS.
   - 2.C. PEDESTAL BOXES TO BE SIZED BY DIVISION 26 TO PROVIDE SCHEDULED DEVICES ON A SINGLE FACE AND SUFFICIENT DEPTH FOR BACK TO BACK DEVICES ON DOUBLE FACED PEDESTALS.
   - 2.D. BASIS OF DESIGN:
     - 2.D.A. 1-GANG ELECTRICAL DEVICES: LEGRAND LBP2 OR WATER SAVER E400SA-WS
     - 2.D.B. 1-GANG LOW VOLTAGE DEVICES: LEGRAND LBP2 OR WATER SAVER E400SA-WS
     - 2.D.C. 2-GANG ELECTRICAL DEVICES: WATER SAVER E600SA-WS
     - 2.D.D. 2-GANG LOW VOLTAGE DEVICES: WATER SAVER E600SA-WS
3. INSTALLATION REQUIREMENTS:
   - 3.A. STUB UP CONDUIT ABOVE FLOOR TO PEDESTAL BOX CONNECTION LOCATION.
   - 3.B. GROUT GAP BETWEEN FINISHED FLOOR AND BOTTOM OF PEDESTAL BOX.
   - 3.C. PROVIDE TRANSITION PIECE TO CONTINUE FINISHED FLOOR TO BOTTOM EDGE OF SERVICE FITTING AND CONCEAL GROUT. TRANSITION PIECE TO MATCH ARCHITECT'S FINISH SCHEDULE.
   - 3.D. PEDESTAL BOX TO BE INSTALLED SQUARE TO THE FINISHED FLOOR.
4. PROVIDE TYPEWRITTEN OR PREMADE CIRCUIT LABELS ON INSTALLED WIRING AT EACH DEVICE AND SPLICE POINT.
5. PROVIDE TYPEWRITTEN LABEL AFFIXED TO THE FRONT OF EACH DEVICE FACEPLATE INDICATING ELECTRICAL CIRCUIT.

   CIRCUIT LABEL

   XX-## — A. XX = PANEL DESIGNATION

   B. ## = AS-BUILT CIRCUIT DESIGNATION

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL
KITCHEN DETAILS

k-E.013


STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM (713) 360-4080


TEXAS ENG. FIRM REG. NO. F-018530 © 2025 ALL RIGHTS RESERVED


12999 W. SAM HOUSTON PKWY N., SUITE 125, HOUSTON, TX 77064

LIGHTING SYSTEM FUNCTIONAL TESTING AND DOCUMENTATION NOTES:

1. PRIOR TO PASSING FINAL INSPECTION, THE CONTRACTOR SHALL PERFORM FUNCTIONAL TESTING IN THE PRESENCE OF THE REGISTERED DESIGN PROFESSIONAL, THE OWNER AND/OR THEIR AGENT. THE FUNCTIONAL TESTING SHALL BE AS REQUIRED BY SECTION C408.3.1 OF THE 2021 IECC.
   1.A. THE FUNCTIONAL TESTING SHALL PROVIDE EVIDENCE THAT THE LIGHTING CONTROL SYSTEMS, INCLUDING BOTH HARDWARE AND SOFTWARE, ARE CALIBRATED, ADJUSTED, PROGRAMMED AND IN PROPER WORKING CONDITION IN ACCORDANCE WITH THE CONSTRUCTION DOCUMENTS AND MANUFACTURER'S INSTRUCTIONS.
   1.B. THE FUNCTIONAL TESTING SHALL BE IN ACCORDANCE WITH SECTIONS C408.3.1.1 AND C408.3.1.2 OF THE 2021 IECC FOR THE APPLICABLE CONTROL TYPE.
   1.C. A WRITTEN REPORT SHALL BE GENERATED DOCUMENTING THE FUNCTIONAL TESTING RESULTS IN ACCORDANCE WITH THE 2015 IECC REQUIREMENTS.
2. ALL LIGHTING CONTROLS O&M MANUALS, AS-BUILTS, TESTING REPORTS AND DOCUMENTATION RELATED TO THE LIGHTING CONTROL SYSTEM SHALL BE PROVIDED IN THEIR FINAL AND APPROVED FORM WITHIN 60 DAYS OF THE CERTIFICATE OF OCCUPANCY. ALL DOCUMENTS CERTIFYING THAT THE INSTALLED LIGHTING CONTROLS MEET DOCUMENTED PERFORMANCE CRITERIA OF SECTION C405 OF THE 2021 IECC SHALL BE INCLUDED IN THE O&M MANUALS.
3. ALL DOCUMENTS FROM ITEMS #1 AND #2 ABOVE SHALL BE COMBINED AND PROVIDED TO THE OWNER WITHIN 90 DAYS FROM THE DATE OF RECEIPT OF THE CERTIFICATE OF OCCUPANCY.

# LIGHT FIXTURE SCHEDULE

## EXTERIOR LIGHT FIXTURE SCHEDULE

| | | | |
|---|---|---|---|
| RECESSED 6" DOWNLIGHT WET LOCATION | D5<br>D5Y | 6" DIAMETER RECESSED LED DOWNLIGHT, SPECULAR CLEAR REFLECTOR, MEDIUM (56') BEAM DISTRIBUTION, 1000 LUMENS, 4000K COLOR TEMPERATURE, 120-277V MULTIVOLT INPUT, 1% 0-10V DIMMING DRIVER.<br>LIGHTOLIER 6R-N / C6L-10-9-40-M-Z10-U / C6-R-DL-CC | 9W |
| RECESSED 6" DOWNLIGHT WET LOCATION | D6<br>D6Y | 6" DIAMETER RECESSED LED DOWNLIGHT, SPECULAR CLEAR REFLECTOR, MEDIUM (56') BEAM DISTRIBUTION, 2000 LUMENS, 4000K COLOR TEMPERATURE, 120-277V MULTIVOLT INPUT, 1% 0-10V DIMMING DRIVER.<br>LIGHTOLIER 6R-N / C6L-20-9-40-M-Z10-U / C6-R-DL-CC | 22W |
| SURFACE CANOPY SQUARE LED | WC1<br>WC1X<br>WC1Y | 9" SQUARE SURFACE LED CANOPY LIGHT, 4000K COLOR TEMPERATURE, 3500 LUMENS, 120-277V MULTIVOLT INPUT, DARK BRONZE FINISH.<br>EELP VR7-T-28L-QT-40K (EBLED9W) | 28W |
| EXTERIOR WALL PACK | WP1<br>WP1X<br>WP1Y | 7" WDE WALL MOUNTED LED, 4000K COLOR TEMPERATURE, 5000 LUMENS, TYPE 3 DISTRIBUTION, 120-277 MULTIVOLT INPUT, WET LOCATION, 10KV KA SURGE PROTECTION.<br>REFER TO ARCH FOR MOUNTING HEIGHT.<br>FINISH TO BE SELECTED BY ARCHITECT FROM ALL AVAILABLE FINISHES.<br>GARDCO GEOFORM SMALL GWS-A04-740-UNV-XX FINISH (EM) | 34W |
| EXTERIOR WALL PACK | WP2<br>WP2X<br>WP2Y | 12" WDE WALL MOUNTED LED, 4000K COLOR TEMPERATURE, 8500 LUMENS, TYPE 3 DISTRIBUTION, 120-277 MULTIVOLT INPUT, WET LOCATION. REFER TO ARCH FOR MOUNTING HEIGHT.<br>REFER TO ARCH FOR MOUNTING HEIGHT.<br>FINISH TO BE SELECTED BY ARCHITECT FROM ALL AVAILABLE FINISHES.<br>GARDCO GEOFORM MEDIUM GWM-A11-740-T3M-UNV-XX FINISH (REMOTE EM BATTERY) | 52W |
| EXTERIOR WALL PACK | WP3<br>WP3X<br>WP3Y | 17" WDE WALL MOUNTED LED, 4000K COLOR TEMPERATURE, 12500 LUMENS, TYPE 3 DISTRIBUTION, 120-277 MULTIVOLT INPUT, WET LOCATION. REFER TO ARCH FOR MOUNTING HEIGHT.<br>REFER TO ARCH FOR MOUNTING HEIGHT.<br>FINISH TO BE SELECTED BY ARCHITECT FROM ALL AVAILABLE FINISHES.<br>GARDCO GEOFORM MEDIUM GWM-A14-740-T3M-UNV-XX FINISH (REMOTE EM BATTERY) | 77W |

1. LIGHT FIXTURE CATALOG NUMBERS AND DESCRIPTIONS ARE SCHEDULED FOR ESTABLISHING QUALITY, APPEARANCE AND PERFORMANCE OF THE FIXTURES. EXACT CATALOG NUMBERS DESCRIBING MOUNTING CONDITIONS AND REQUIREMENT RELATED TO TRIM FOR ALL FIXTURES SHALL BE CONFIRMED (BY THE ELECTRICAL CONTRACTOR) WITH THE ROOM FINISH SCHEDULE AND REFLECTED CEILING PLANS ON THE ARCHITECTURAL PLANS PRIOR TO BIDDING AND SUBMITTING LIGHT FIXTURES. PROVIDE DRY WALL KIT AS REQUIRED.
2. ALL 'X', 'Y', AND 'Z' TYPE FIXTURES SHALL HAVE EMERGENCY POWER BACKUP. EMERGENCY POWER SOURCES SHALL MONITOR POWER UPSTREAM OF THE LIGHTING CONTROLS TO SEE IF POWER IS LOST. BATTERY PACKS AND INVERTERS SHALL BE CAPABLE OF POWERING THE DESIGNATED FIXTURE(S) WITH AN OUTPUT OF 1400 LUMENS FOR A MINIMUM OF 90-MINUTES. PROVIDE REMOTE BATTERY PACKS OR INVERTERS AS NECESSARY. EMERGENCY LIGHTS SHALL OPERATE ONLY UPON LOSS OF POWER; ALSO, PROVIDE AND WIRE TEST SWITCH AND LED INDICATOR LIGHT FOR EMERGENCY BATTERY. SEE WIRING INSTRUCTION SUPPLIED BY EMERGENCY BATTERY MANUFACTURER.
   2.A. 'X' TYPE FIXTURES (AX, ETC.) HAVE EMERGENCY GENERATOR POWER LIGHTING TRANSFER DEVICES.
   2.B. 'Y' TYPE FIXTURES (MY, ETC.) HAVE INDIVIDUAL 90-MINUTE EMERGENCY BATTERY POWER.
   2.C. 'Z' TYPE FIXTURES (GTZ, ETC.) HAVE 90-MINUTE INVERTER EMERGENCY BATTERY POWER.
3. PROVIDE BASE COVER FOR ALL LIGHT POLES.
4. ALL EXTERIOR FIXTURES SHALL BE WET RATED WITH COLD WEATHER BALLASTS AND BATTERY PACKS.
5. PROVIDE SPARE FIXTURES AND EMERGENCY DEVICES PER SPECIFICATIONS.
6. WHERE FIXTURE FINISHES ARE INDICATED TO BE SELECTED BY ARCHITECT THE CONTRACTOR SHALL INCLUDE IN THEIR BID ALL AVAILABLE FINISHES. SUBMIT COMPLETE FIXTURE FINISH OPTIONS AS PART OF THE LIGHTING SUBMITTAL PACKAGE.
7. EQUAL BY PHILIPS (CW LIGHTING), COOPER (PUTTERMAN SCHAROK), AND LITHONIA (LESCO) SHALL BE ACCEPTABLE.

## INTERIOR LIGHT FIXTURE SCHEDULE

| APPLICATION | TYPE | DESCRIPTION | WATTS |
|---|---|---|---|
| 1X4 RECESSED LAY-IN CEILING SELECTABLE CCT & LUMENS | A1<br>A1X<br>A1Y | 2X4 RECESSED LED, SMOOTH FROSTED ACRYLIC LENS, EXTRUDED ALUMINUM FRAME, WHITE FINISH, LAY-IN CEILING, 6000 LUMENS, 4000K COLOR TEMPERATURE, 120-347V MULTIVOLT INPUT, 5% 0-10V DIMMING.<br>SET FIELD SELECTABLE SWITCHES TO NEUTRAL WHITE (4000K) AND HIGH (47W).<br>DAYBRITE 2SBP3550L8CS-4-UNJ-DIM | 47W |
| 1X4 RECESSED LAY-IN CEILING SELECTABLE CCT & LUMENS | B1<br>B1X<br>B1Y | 1X4 RECESSED LED, SMOOTH FROSTED ACRYLIC LENS, EXTRUDED ALUMINUM FRAME, WHITE FINISH, LAY-IN CEILING, 4500 LUMENS, 4000K COLOR TEMPERATURE, 120-347V MULTIVOLT INPUT, 5% 0-10V DIMMING.<br>SET FIELD SELECTABLE SWITCHES TO NEUTRAL WHITE (4000K) AND HIGH (36W).<br>DAYBRITE 1SBP3040L8CS-4-UNJ-DIM | 36W |
| 2X2 RECESSED LAY-IN CEILING SELECTABLE CCT & LUMENS | B2<br>B2X<br>B2Y | 2X2 RECESSED LED, SMOOTH FROSTED ACRYLIC LENS, EXTRUDED ALUMINUM FRAME, WHITE FINISH, LAY-IN CEILING, 4250 LUMENS, 4000K COLOR TEMPERATURE, 120-347V MULTIVOLT INPUT, 5% 0-10V DIMMING.<br>SET FIELD SELECTABLE SWITCHES TO NEUTRAL WHITE (4000K) AND HIGH (36W).<br>DAYBRITE 2SBP3040L8CS-2-UNJ-DIM | 39W |
| 4FT STRIP LED MECHANICAL & STORAGE ROOMS | C<br>CX<br>CY | 4 FOOT STRIP LED, STEEL HOUSING, FROSTED ACRYLIC LENS, 4000 LUMENS, 3500K COLOR TEMPERATURE, CHAIN HANGING SET, WIRE GUARD, 120-277V MULTIVOLT INPUT, 0-10V DIMMING DRIVER. PROVIDE CHAIN HANGING SET AND WIREGUARD IN MECHANICAL ROOMS AND AREAS WITHOUT CEILINGS.<br>SET FIELD SELECTABLE SWITCHES TO NEUTRAL WHITE (4000K) AND HIGH (36W).<br>DAYBRITE SDS-4-2448L-8CST-UNV-DIM | 30W |
| RECESSED 6" DOWNLIGHT | D1<br>D1X<br>D1Y | 6" DIAMETER RECESSED LED DOWNLIGHT, MATTE WHITE FINISH, WIDE (76') BEAM DISTRIBUTION, 1000 LUMENS, 4000K COLOR TEMPERATURE, 120-277V MULTIVOLT INPUT, 1% 0-10V DIMMING DRIVER.<br>LIGHTOLIER 6R-N / C6L-10-9-40-W-Z10-U / C6-R-DL-WH | 9W |
| RECESSED 6" DOWNLIGHT | D2<br>D2X<br>D2Y | 6" DIAMETER RECESSED LED DOWNLIGHT, MATTE WHITE FINISH, WIDE (76') BEAM DISTRIBUTION, 2000 LUMENS, 4000K COLOR TEMPERATURE, 120-277V MULTIVOLT INPUT, 1% 0-10V DIMMING DRIVER.<br>LIGHTOLIER 6R-N / C6L-20-9-40-W-Z10-U / C6-R-DL-WH | 22W |
| EXIT SIGN | XB<br>XS<br>XD | DIE CAST ALUMINUM LED EXIT LIGHT, RED LETTERS, MATTE BLACK HOUSING W/ BRUSHED ALUMINUM FACE, UNIVERSAL ARROWS, 120/277 VOLT DUAL INPUT, 90 MINUTE EMERGENCY BATTERY. VERIFY LETTER AND FACE COLOR WITH OWNER/ARCHITECT PRIOR TO ORDERING.<br>XS=SINGLE FACE, XD=DOUBLE FACE, XB=BACK MOUNTED<br>PHILIPS CHLORIDE ER55L-3-R<br>SURELITES GX7-1/2-R<br>LITHONIA LQC-1/2-R-EL N | 5W |
| EXIT SIGN INTEGRAL BATTERY INTEGRAL EM LIGHT BAR | YB<br>YS<br>YD | THERMOPLASTIC LED EXIT LIGHT WITH INTEGRAL EM LIGHT, RED LETTERS, WHITE HOUSING W/ WHITE FACE, UNIVERSAL ARROWS, 120-277 MULTIVOLT INPUT, 90 MINUTE EMERGENCY BATTERY. VERIFY LETTER AND FACE WITH OWNER/ARCHETICT PRIOR TO ORDERING.<br>YS=SINGLE FACE, YD=DOUBLE FACE, YB=BACK MOUNTED<br>SIGNTEX CLP-BB-U-R-W-DG | 5W |
| TWIN HEAD EM LIGHT INTEGRAL BATTERY WET LOCATION | YT1 | TWIN HEAD EM LIGHT, INJECTION-MOLDED THERMOPLASTIC WHITE HOUSING, GASKETED CLEAR POLYCARBONATE COVER, LED LAMPS, 90-MINUTE EMERGENCY BATTERY.<br>CHLORIDE TPU-W-N-LM7-W | 7W |

# LIGHTING CONTROL SEQUENCE OF OPERATIONS

| ROOM TYPE | AUTO ON | MANUAL ON (VACANCY) | AUTO OFF (20 MIN MAX) | PARTIAL OFF AT NORMAL HOURS | AUTO ON AFTER HOURS | AUTO OFF AFTER HOURS (20 MIN MAX) | TIME ON | TIME OFF | ASTRONOMIC OR PHOTOCELL ON/OFF | AUTO STEP CONTROL WITH OFF | AUTO CONTINUOUS DIM WITH OFF | MANUAL BI-LEVEL REDUCTION CONTROL | MANUAL CONTINUOUS DIM CONTROL | MANUAL ON/OFF SWITCH | MANUAL DIMMER SWITCH | DISPLAY, ACCENT, TASK CONTROL | PLUG LOAD CONTROL | SEQUENCE OF OPERATION |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | OCCUPANCY SENSOR | | | | | | TIME SWITCH/SCHEDULING | | | DAYLIGHT CONTROL | | LIGHT REDUCTION | | MANUAL CONTROL | | | | |
| Kitchen/Serving | | | | | | | • | • | | | | • | | • | | | | LOCAL ON/OFF CONTROLS, LOCAL CONTROLS MAY OVERRIDE BUILDING SCHEDULE AND TURN ALL LIGHTS ON FOR MAXIMUM 2HRS. NETWORK LIGHTING CONTROLS ROOM CONTROLLER CONNECTED TO BUILDING CONTROLS; ON/OFF BASED ON BUILDING SCHEDULE, AFTER HOURS ON/OFF BASED ON OCCUPANCY, COORDINATE SCHEDULING WITH OWNER. WHERE ≥150W IN DAYLIGHT AREA, USE CONTINUOUS DIMMING DAYLIGHTING CONTROL. |
| Restrooms | 100% | | 20 MIN | | | | | | | | | | | • | | | | AUTO ON 100%, AUTO OFF BY LOCAL OCCUPANCY SENSOR. LOCAL ON/OFF CONTROLS ONLY, NO FULLY NETWORKED SYSTEM. |
| Custodial rooms | | • | 20 MIN | | | | | | | | | | | • | • | | | MANUAL ON, AUTO OFF BY LOCAL OCCUPANCY SENSOR. LOCAL ON/OFF CONTROLS ONLY, NO FULLY NETWORKED SYSTEM. |
| Storage rooms | 50% | | 20 MIN | | | | | | | | | | | • | • | | | AUTO ON 50%, AUTO OFF BY LOCAL OCCUPANCY SENSOR. LOCAL ON/OFF/DIMMING CONTROLS ONLY, NO FULLY NETWORKED SYSTEM. |
| Private Offices | 50% | | 20 MIN | | | | | | | | | | | • | • | | • | AUTO ON 50%, AUTO OFF BY LOCAL OCCUPANCY SENSOR. LOCAL ON/OFF/DIMMING CONTROLS ONLY, NO FULLY NETWORKED SYSTEM. |
| Corridors | | | | | 100% | 20 MIN | • | • | | | | | | • | | | | LOCAL ON/OFF CONTROLS, LOCAL CONTROLS MAY OVERRIDE BUILDING SCHEDULE AND TURN ALL LIGHTS ON FOR MAXIMUM 2HRS. NETWORK LIGHTING CONTROLS ROOM CONTROLLER CONNECTED TO BUILDING CONTROLS; ON/OFF BASED ON BUILDING SCHEDULE, AFTER HOURS ON/OFF BASED ON OCCUPANCY, COORDINATE SCHEDULING WITH OWNER. WHERE ≥150W IN DAYLIGHT AREA, USE CONTINUOUS DIMMING DAYLIGHTING CONTROL. |
| Electrical Rooms | | | | | | | | | | | | | | • | | | | MANUAL ON/OFF; LOCAL CONTROL DEVICE NOT TIED TO LVLCS. |
| Building Facade/Landscape | | | | | | | • | • | | | | | | | | | | CONNECTED TO BUILDING CONTROLS THROUGH LIGHTING CONTACTOR; ON/OFF BASED ON BUILDING SCHEDULE. |

1. DIMMER SWITCHES SHALL ACTIVATE PRESET ALL ON LIGHTING LEVEL WHEN PRESSED IN THE UP POSITION. LIGHTING LEVELS MAY BE RAISED/LOWERED BY HOLDING THE DIMMER PADDLE. WHEN PRESSED IN THE DOWN POSITION ALL LIGHTS SHALL SMOOTHLY DIM TO OFF.
2. AT LEAST 50 PERCENT OF ALL 125V, 15- AND 20-AMP RECEPTACLES INSTALLED IN ENCLOSED OFFICES, CONFERENCE ROOMS, ROOMS USED PRIMARILY FOR COPY OR PRINT FUNCTIONS, BREAKROOMS, CLASSROOMS AND INDIVIDUAL WORKSTATIONS, INCLUDING THOSE INSTALLED IN MODULAR PARTITIONS AND MODULE OFFICE WORKSTATION SYSTEMS SHALL HAVE PLUG LOAD CONTROL PER IECC 2021 C405.11.

# LIGHTING CONTACTOR SCHEDULE

**CONTACTOR CT1**

| POLE | DESCRIPTION | NORMAL CKT | EM CKT | CONTROL ZONE | CONTACTOR LOCATION | CONTACTOR TYPE |
|---|---|---|---|---|---|---|
| CT1-1 | KITCHEN/SERVING AREA - ZONE 'a' | HK-3 | - | Kitchen-a | CENTRAL PLANT | MAGNETICALLY HELD |
| CT1-2 | SPARE | | | Kitchen-a | CENTRAL PLANT | MAGNETICALLY HELD |
| CT1-3 | SPARE | | | Kitchen-a | CENTRAL PLANT | MAGNETICALLY HELD |

**CONTACTOR CT2**

| | | | | | | |
|---|---|---|---|---|---|---|
| CT2-1 | KITCHEN/SERVING AREA - ZONE 'b' | HK-3 | - | Kitchen-b | CENTRAL PLANT | MAGNETICALLY HELD |
| CT2-2 | SPARE | | | Kitchen-b | CENTRAL PLANT | MAGNETICALLY HELD |
| CT2-3 | SPARE | | | Kitchen-b | CENTRAL PLANT | MAGNETICALLY HELD |

**CONTACTOR CT3**

| | | | | | | |
|---|---|---|---|---|---|---|
| CT3-1 | KITCHEN SOFFIT/CANOPY LTS | HK-5 | - | Exterior | CENTRAL PLANT | MAGNETICALLY HELD |
| CT3-2 | | | | Exterior | CENTRAL PLANT | MAGNETICALLY HELD |
| CT3-3 | | | | Exterior | CENTRAL PLANT | MAGNETICALLY HELD |

1. REFERENCE TYPICAL LIGHTING CONTACTOR WIRING DIAGRAM.
2. EMERGENCY AND NORMAL ZONES WITHIN THE KITCHEN/SERVING SHALL HAVE SEPARATE CONTROLS TO ALLOW FOR LIGHTING REDUCTION CONTROL.
3. LIGHTING CONTACTORS SHALL BE DIN RAIL MOUNTED, MAGNETICALLY HELD TYPE WITH THREE WIRE CONTROL BY THE BAS.
   3.A. PROVIDE CABINET AT EACH LOCATION TO MOUNT ALL CONTACTORS IN A SINGLE ENCLOSURE. ENCLOSURE SIZED BY DIVISION 26.
   3.B. PROVIDE SEPARATE HOA SWITCHES IN THE FRONT COVER OF THE ENCLOSURE WIRED TO CONTROL THE FOLLOWING ZONES SEPARATELY.
      3.B.1. INTERIOR LIGHTING (ALL INTERIOR LIGHTING GROUPS)
      3.B.2. EXTERIOR LIGHTING (ALL EXTERIOR LIGHTING GROUPS)
      3.B.3. HOA SWITCH SHALL PASS THE BAS SIGNALS IN AUTO MODE, DISENGAGE ALL CONTACTORS IN THE OFF POSITION, AND ENGAGE ALL THE CONTACTORS IN THE ON POSITION.
   3.C. SPARE CAPACITY:
      3.C.1. PROVIDE MINIMUM TWO (2) SPARE POLE ON EACH COMBINED TYPE CONTACTOR FOR FUTURE USE.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
6955 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

LIGHTING SCHEDULES

k-E.060


STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM (713) 303-6080 | TEXAS ENG. FIRM REG. NO. F-018332 | 1300 W. SAM HOUSTON PARKWAY S., SUITE 121, HOUSTON, TX 77042


© 2025 ALL RIGHTS RESERVED

## ELECTRICAL KEYED NOTES

GENERAL NOTES:

- CUT WALLS AS REQUIRED TO FLUSH MOUNT NEW DEVICES IN EXISTING WALLS. PATCH/REPAIR WALLS TO MATCH.

LIGHTING RENOVATION NOTES:

A. KITCHEN LIGHTS TO BE CONTROLLED BY LOCAL MOMENTARY SWITCHES AND BAS. LIGHTING CONTACTOR LOCATIONS SHOWN SCHEMATICALLY ONLY. LOCATE LIGHTING CONTACTOR ENCLOSURE IN THE ADJACENT CENTRAL PLANT SPACE, FIELD VERIFY. REFERENCE LIGHTING CONTROL DETAIL. TYPICAL.
   LEFT SWITCH SHALL CONTROL ZONE 'a' NORMAL POWER LIGHTING FIXTURES.
   RIGHT SWITCH SHALL CONTROL ZONE 'b' EMERGENCY LIGHTING FIXTURES.


B. PROVIDE PLUG LOAD CONTROLS TIED TO THE LIGHTING IN OFFICE SPACES.

C. WIRE EXIT SIGNS UPSTREAM OF LIGHTING CONTROLS. TYPICAL.

D. EXTERIOR LIGHTS TO BE CONTROLLED BY BAS. LIGHTING CONTACTOR LOCATIONS SHOWN SCHEMATICALLY ONLY. LOCATE LIGHTING CONTACTOR ENCLOSURE IN THE ADJACENT CENTRAL PLANT SPACE, FIELD VERIFY. REFERENCE LIGHTING CONTROL DETAIL. TYPICAL.

E. AFTER REMOVAL OF THE TEMPORARY KITCHEN, PROVIDE NEW EXIT SIGN AT ORIGINAL LOCATION AND RECONNECT TO EXISTING CAFETERIAL LIGHTING CIRCUIT.

F. PATCH/REPAIR EXTERIOR SOFFIT TO ACCOMMODATE NEW SURFACE MOUNTED FIXTURES.




**1 LIGHTING RENOVATION PLAN**
SCALE: 1/4" = 1'- 0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING


LIGHTING FLOOR PLANS

k-E.100


STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM (713) 300-6056
TEXAS ENG. FIRM REG. NO. F-13183210


2025 ALL RIGHTS RESERVED


12800 W. SAM HOUSTON PARKWAY N., SUITE 121, HOUSTON, TX 77040




## 1 ELECTRICAL RENOVATION PLAN

SCALE: 1/4" = 1'- 0"

## ELECTRICAL KEYED NOTES

GENERAL NOTES:

- CUT WALLS AS REQUIRED TO FLUSH MOUNT NEW DEVICES IN EXISTING WALLS. PATCH/REPAIR WALLS TO MATCH.

ELECTRICAL RENOVATION NOTES:

A. CONNECT NEW FREEZER/COOLER AND CONDENSER TO EXISTING STANDBY GENERATOR.

B. PROVIDE ILLUMINATED PUSH BUTTON IN COOLER AND FREEZER. WHEN PRESSED RED STROBE DEVICES IN KITCHEN AND CAFETERIA SHALL ACTIVATE. TYPICAL.

C. PROVIDE HORN/STROBE DEVICE TIED TO PUSH BUTTONS IN FREEZER/COOLER.
(EDWARDS 860 SERIES OR EQUAL).

D. PROVIDE NEW DOORBELL BUTTON AT RECEIVING DOOR. DOORBELL BUTTON SHALL BE THE CLOSEST DEVICE TO THE DOOR FRAME.

E. PROVIDE NEW VIBRATING BUZZER TIED TO DOORBELL BUTTON AT RECEIVING DOOR. BUZZER TO BE WALL MOUNTED JUST BELOW THE CEILING.

F. PROVIDE NEW ELECTRICAL DEVICES MATCHING NEW KITCHEN EQUIPMENT AND ROOM LAYOUTS. REFERENCE FOOD SERVICE DRAWINGS. TYPICAL.

G. PROVIDE ROUGH-IN FOR LOW VOLTAGE DEVICES. REFERENCE TECHNOLOGY DRAWINGS, TYPICAL.

H. POWER AND DATA ROUGH-IN FOR KITCHEN MENU BOARD.

I. POWER AND DATA ROUGH-IN FOR POINT OF SALE (POS) LOCATION.

J. PROVIDE DROP CORD RECEPTACLE WITH HUBBELL KELLEMS LIQUIDTIGHT GRIPS FOR STRAIN RELIEF, TYPICAL OF ALL.

K. PROVIDE J-BOXES AND CONDUIT FOR REMOTE FIRE PULLS, SEE FOOD SERVICE DETAIL DRAWING FOR REQUIREMENTS, TYPICAL

L. WIRE ANSUL SYSTEM TO HOOD EQUIPMENT CONTROL CONTRACTOR. UPON ANSUL SYSTEM ACTIVATION ALL POWER TO EQUIPMENT BENEATH THE HOODS SHALL BE DEACTIVATED. MOUNT CONTACTOR CABINET(S) JUST BELOW THE CEILING.

M. PROVIDE SEPARATE SWITCHES TO TURN ON HOOD LIGHTS AND FANS. WIRE HOOD TEMP SENSOR AHEAD OF HOOD LIGHT SWITCH. USE 120V CIRCUIT TO CONTROL HOOD FANS THROUGH EXISTING STARTER. PROVIDE CONTROLS TRANSFORMER AS REQUIRED TO MATCH STARTER CONTROL INPUT VOLTAGE. TYPICAL.

N. PROVIDE PLUG LOAD CONTROLS TIED TO THE LIGHTING IN OFFICE SPACES.

O. INTERCONNECT DISH MACHINE TO VENT CONTROL. INTERCONNECT TABLE LIMIT SWITCH TO DISHMACHINE.

P. EXISTING MECHANICAL EQUIPMENT TO BE REPLACED. CONNECT TO CIRCUIT AS SHOWN. RECONNECT TO EXISTING STARTER/CONTACTORS, FIELD VERIFY.

Q. SAWCUT FLOOR TO INSTALL NEW PEDESTAL MOUNTED DEVICE BENEATH NEW SERVING LINES, DO NOT REUSE EXISTING STUB UPS OR DEVICES. POUR BACK SLAB AND PROVIDE NEW FINISHES, REFERENCE ARCHITECTURAL.

R. REFERENCE EDF GFI PROTECTION DETAIL FOR INSTALLATION REQUIREMENTS, TYPICAL.

S. WIRE MICRO SWITCH IN DOOR FRAME TO AIR SCREEN. COOR W/ FOOD SERVICE CONTRACTOR PRIOR TO ROUGH-IN. LOCATE LOCAL MOTOR RATED SWITCH ABOVE CEILING ADJACENT TO THE AIR SCREEN.

COOLER/FREEZER NOTES:

1. PROVIDE SEALING FOR CONDUIT IN COOLER AND FREEZER. WHERE PORTIONS OF INTERIOR RACEWAY SYSTEM ARE EXPOSED TO WIDELY DIFFERENT TEMPERATURES, CIRCULATION OF AIR FROM WARMER TO A COLDER SECTION SHALL BE PREVENTED PER N.E.C. ARTICLE 300.7 (A).
2. PROVIDE GROUND-FAULT PROTECTION OF EQUIPMENT FOR ELECTRIC HEAT TRACING AND HEATING PANELS IN THE FREEZER PER N.E.C. ARTICLE 427.22.
3. ELECTRICAL CONTRACTOR SHALL PROVIDE LIQUID TIGHT CONDUIT AND WIRING FOR LIGHT FIXTURES AND LIGHT SWITCHES IN WALK-IN COOLER AND FREEZER, SEE FOODSERVICE CONSULTANT'S DRAWINGS.

STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM | (713) 300-6080
TEXAS ENG. FIRM REG. NO. F-01853 | © 2025 ALL RIGHTS RESERVED
1200 N. SAM HOUSTON PARKWAY E., SUITE 121, HOUSTON, TX 77060

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL


STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL FLOOR PLANS

k-E.200




**1 FIRE ALARM RENOVATION PLAN**
SCALE: 1/4" = 1'- 0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL




07.18.2025


MWA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

FIRE ALARM
FLOOR PLANS

k-E.300

STANTON ENGINEERING GROUP
INFORMATION: (713) 300-6060
TEXAS ENG. FIRM REG. NO. F-21853 | © 2025 ALL RIGHTS RESERVED
12999 W. SAM HOUSTON PARKWAY N., SUITE 725, HOUSTON, TX 77064




## 1 PARTIAL ELECTRICAL RISER

NO SCALE

NOTES:
1. FIELD VERIFY ALL EXISTING ELECTRICAL PANELS AND FEEDERS SHOWN ON DRAWINGS.
2. REF ELECTRICAL FLOOR PLANS FOR PANEL LOCATIONS.
3. ALL OUTAGES SHALL BE SCHEDULED/CONFIRMED IN WRITING WITH THE OWNER A MINIMUM OF TWO WEEKS PRIOR TO ANY OUTAGE.
4. AT THE END OF THE PROJECT PROVIDE A NEW TYPEWRITTEN PANEL SCHEDULE USING BUILDING ROOM NUMBERS FOR ALL PANELS WITH CIRCUITS ADDED, REMOVED, OR MODIFIED AS PART OF THE PROJECT.
5. REFERENCE PANEL SCHEDULES AND SHORT CIRCUIT TABLE FOR AIC AND SCCR VALUES.

## NEW KITCHEN PANEL — KITCHEN

**PANEL HK** — 225A MLO, 480Y/277V, 3ϕ, 4 WIRE — AVAILABLE FAULT: 20,250A — SCCR & AIC: 25,000A — MOUNTING: RECESSED — STAINLESS STEEL COVER

| NOTES | EQUIP. NO. | LOAD | DESCRIPTION | WIRE | CB | CKT | CKT | CB | WIRE | DESCRIPTION | LOAD | EQUIP. NO. | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 6 | | 376 | KITCHEN ROOM LIGHTS | 3–12 | 20/1 | 1 | 2 | 15/3 | 3–12 | ESF–1 | 4986 | | |
| 7 | | 1095 | KITCHEN LIGHTS | 3–12 | 20/1 | 3 | 4 | – | +12G | ( 1.5HP / 1.5HP ) | – | | |
| | | 84 | KITCHEN SOFFIT LIGHTS | 3–12 | 20/1 | 5 | 6 | – | 3/4"C | – | – | | |
| | | | SPARE | | 20/1 | 7 | 8 | 15/3 | 3–12 | ESF–2 | 4986 | | |
| | | | SPARE | | 20/1 | 9 | 10 | – | +12G | ( 1.5HP / 1.5HP ) | – | | |
| | | | SPARE | | 20/1 | 11 | 12 | – | 3/4"C | – | – | | |
| | | | SPARE | | 20/1 | 13 | 14 | | | SPACE | | | |
| | | | SPARE | | 20/1 | 15 | 16 | | | SPACE | | | |
| | | | SPARE | | 20/1 | 17 | 18 | | | SPACE | | | |
| | | | SPARE | | 20/1 | 19 | 20 | | | SPACE | | | |
| | | | SPARE | | 20/1 | 21 | 22 | | | SPACE | | | |
| | | | SPACE | | | 23 | 24 | | | SPACE | | | |
| | | | SPACE | | | 25 | 26 | | | SPACE | | | |
| | | | SPACE | | | 27 | 28 | | | SPACE | | | |
| | | | SPACE | | | 29 | 30 | | | SPACE | | | |
| | | | SPACE | | | 31 | 32 | | | SPACE | | | |
| | | | SPACE | | | 33 | 34 | | | SPACE | | | |
| | | | SPACE | | | 35 | 36 | | | SPACE | | | |
| | | | SPACE | | | 37 | 38 | 70/3 | 3–6 | DISHMACHINE | 42963 | E250 | |
| | | | SPACE | | | 39 | 40 | – | +8G | – | – | | |
| | | | SPACE | | | 41 | 42 | – | 3/4"C | – | – | | |
| | | | TOTAL LOAD ❶ 100% = 54490VA | | | | TOTAL LOAD ❶ 100% = 66A | | | | TOTAL LOAD ❶ 125% = 82A | | |

## NEW KITCHEN PANEL — KITCHEN

**PANEL LK** — 225A MLO, 208Y/120V, 3ϕ, 4 WIRE — AVAILABLE FAULT: <10,000A — SCCR & AIC: 10,000A — MOUNTING: RECESSED — STAINLESS STEEL COVER

| NOTES | EQUIP. NO. | LOAD | DESCRIPTION | WIRE | CB | CKT | CKT | CB | WIRE | DESCRIPTION | LOAD | EQUIP. NO. | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E10 | 640 | 3 REC – RR/STOR/CUST & BELL | 3–12 | 20/1 | 1 | 2 | 20/1 | 3–12 | 1 REC – KITCHEN | 180 | E10 | |
| | E110 | 1920 | WASHING MACHINE | 3–12 | 20/1 | 3 | 4 | 20/1 | 3–12 | 1 REC – KITCHEN | 180 | E10 | |
| | E110A | 5000 | DRYER | 2–10 | 30/2GFI | 5 | 6 | 20/1 | 3–12 | 1 REC – KITCHEN | 180 | E10 | |
| | E151 | – | – | +10N+10G | 3/4"C | 7 | 8 | 20/2 | 2–10 | HEATED CABINET | 3224 | E187 | |
| | | 540 | 3 REC – OFFICE | 3–12 | 20/1 | 9 | 10 | 3/4"C | +10G | – | – | | |
| | E10 | 540 | 3 REC – KITCHEN | 3–12 | 20/1 | 11 | 12 | 20/2 | 2–10 | HEATED CABINET | 3224 | E187 | |
| | E10 | 360 | 2 REC – SERVING LINE | 3–12 | 20/1 | 13 | 14 | 3/4"C | +10G | – | – | | |
| | E10 | 360 | 2 REC – SERVING LINE | 3–12 | 20/1 | 15 | 16 | 20/3 | 3–12 | DISPOSER | 3960 | E123 | |
| | | 1000 | 2 EDF – CAFETERIA | 3–12 | 20/1 | 17 | 18 | – | +12G | ( 3 HP ) | – | | |
| | E615 | 500 | 2 MENU BOARDS | 3–12 | 20/1 | 19 | 20 | – | 3/4"C | – | – | | |
| | E209 | 960 | MILK COOLER | 3–12 | 20/1 | 21 | 22 | 20/1 | 3–12 | AIR SCREEN | 612 | E101 | |
| | E201A | 5824 | HOT FOOD COUNTER | 2–8 | 35/2 | 23 | 24 | 15/1 | 3–12 | EF–CF ( 1/6HP ) | 528 | | |
| | | – | – | +10G | 3/4"C | 25 | 26 | 15/1 | 3–12 | EF–14 ( 1/6HP ) | 528 | | |
| | E201B | 1920 | COLD FOOD COUNTER | 3–12 | 20/1 | 27 | 28 | 20/1 | 3–12 | EF–2 ( 1/6HP ) | 528 | | |
| | E214 | 360 | CASH REGISTERS | 3–12 | 20/1 | 29 | 30 | 20/1 | | SPARE | | | |
| | E201B | 1920 | COLD FOOD COUNTER | 3–12 | 20/1 | 31 | 32 | 20/1 | | SPARE | | | |
| | E201A | 5824 | HOT FOOD COUNTER | 2–8 | 35/2 | 33 | 34 | 20/1 | | SPARE | | | |
| | | – | – | +10G | 3/4"C | 35 | 36 | 20/1 | | SPARE | | | |
| | E209 | 960 | MILK COOLER | 3–12 | 20/1 | 37 | 38 | 20/1 | | SPARE | | | |
| | | 360 | 2 REC – CAFETERIA | 3–12 | 20/1 | 39 | 40 | 20/1 | | SPARE | | | |
| | | | SPARE | | 20/1 | 41 | 42 | 20/1 | | SPARE | | | |
| | E153/E153M | 250 | HOOD LTS & SENSOR | 3–12 | 20/1 | 43 | 44 | 20/1GFI | 3–12 | DROP CORD | 180 | E129 | |
| | E153/E153M | 250 | HOOD LTS & SENSOR | 3–12 | 20/1 | 45 | 46 | 20/1GFI | 3–12 | DROP CORD | 180 | E129 | |
| 8 | E161 | 720 | CONVECTION OVEN | 3–12 | 20/1GFI | 47 | 48 | 20/1GFI | 3–12 | MOBILE PROOFER | 1800 | E139A | |
| 8 | E161 | 720 | CONVECTION OVEN | 3–12 | 20/1GFI | 49 | 50 | 20/1GFI | 3–12 | 20QT MIXER | 960 | E125 | |
| 8 | E161 | 720 | CONVECTION OVEN | 3–12 | 20/1GFI | 51 | 52 | 20/1GFI | 3–12 | DROP CORD | 180 | E129 | |
| 8 | E161 | 720 | CONVECTION OVEN | 3–12 | 20/1GFI | 53 | 54 | 20/1GFI | 3–12 | DROP CORD | 180 | E129 | |
| 8 | E163 | 600 | TILT BRAISING PAN | 3–12 | 20/1 | 55 | 56 | 20/1GFI | 3–12 | DROP CORD | 180 | E129 | |
| 8 | E172 | 3120 | COMBI OVEN | 2–12 | 20/2 | 57 | 58 | 20/1GFI | 3–12 | DROP CORD | 180 | E129 | |
| | | – | – | +12G | 3/4"C | 59 | 60 | 20/1 | 3–12 | EXISTING CIRCUIT | 500 | | 5 |
| 8 | E172 | 3120 | COMBI OVEN | 2–12 | 20/2 | 61 | 62 | 20/2 | 2–12 | EXISTING CIRCUIT | 1000 | | 5 |
| | | – | – | +12G | 3/4"C | 63 | 64 | – | +12N+12G | – | – | | 5 |
| | | 250 | EXISTING CIRCUIT | 3–12 | 20/1 | 65 | 66 | 20/2 | 2–12 | EXISTING CIRCUIT | 1000 | | 5 |
| 9 | | 0 | TEMP LOAD CENTER | 4–3 | 100/3 | 67 | 68 | – | +12N+12G | – | – | | 5 |
| | | – | – | +8G | – | 69 | 70 | 30/2 | 2–10 | EXISTING CIRCUIT | 3000 | | 5 |
| | | – | – | 1.25"C | – | 71 | 72 | – | +10N+10G | – | – | | |
| | | | TOTAL LOAD ❶ 100% = 61942VA | | | | TOTAL LOAD ❶ 100% = 172A | | | | TOTAL LOAD ❶ 65% = 112A | | |

## KITCHEN HOOD CONTACTOR SCHEDULE

**HOOD 1**

| POLE | DESCRIPTION | NORMAL CKT | EM CKT | CONTROL ZONE | EQUIPMENT LOCATION | CONTACTOR TYPE |
|---|---|---|---|---|---|---|
| CK1–1 | CONVECTION OVEN | LK–47 | – | HOOD 1 | KITCHEN | ELECTRICALLY HELD – NO |
| CK1–2 | CONVECTION OVEN | LK–49 | – | HOOD 1 | KITCHEN | ELECTRICALLY HELD – NO |
| CK1–3 | CONVECTION OVEN | LK–51 | – | HOOD 1 | KITCHEN | ELECTRICALLY HELD – NO |
| CK1–4 | CONVECTION OVEN | LK–53 | – | HOOD 1 | KITCHEN | ELECTRICALLY HELD – NO |
| CK1–5 | SPARE | | | | | ELECTRICALLY HELD – NO |
| CK1–6 | SPARE | | | | | ELECTRICALLY HELD – NO |
| CK1–7 | SPARE | | | | | ELECTRICALLY HELD – NO |
| CK1–8 | SPARE | | | | | ELECTRICALLY HELD – NO |

**HOOD 2**

| POLE | DESCRIPTION | NORMAL CKT | EM CKT | CONTROL ZONE | EQUIPMENT LOCATION | CONTACTOR TYPE |
|---|---|---|---|---|---|---|
| CK2–1 | TILT BRAISING PAN | LK–55 | – | HOOD 2 | KITCHEN | ELECTRICALLY HELD – NO |
| CK2–2 | COMBI–OVEN | LK–57/59 | – | HOOD 2 | KITCHEN | ELECTRICALLY HELD – NO |
| CK2–3 | ( 2–POLE ) | – | – | – | – | ELECTRICALLY HELD – NO |
| CK2–4 | COMBI–OVEN | LK–61/63 | – | HOOD 2 | KITCHEN | ELECTRICALLY HELD – NO |
| CK2–5 | ( 2–POLE ) | – | – | – | – | ELECTRICALLY HELD – NO |
| CK2–6 | SPARE | | | | | ELECTRICALLY HELD – NO |
| CK2–7 | SPARE | | | | | ELECTRICALLY HELD – NO |
| CK2–8 | SPARE | | | | | ELECTRICALLY HELD – NO |

1. REFERENCE FLOOR PLANS FOR EQUIPMENT LOCATIONS AND ADDITIONAL INFORMATION.
2. EACH KITCHEN HOOD CONTACTOR HALL BE CONTROLLED ON/OFF BY THE APPROPRIATE HOOD ANSUL SYSTEM. WHEN ACTIVATED ALL POWER WITHIN THE COOKING HOOD SHALL BE DE–ENERGIZED.

## EXIST SQUARE D QED SWITCHBOARD — CENTRAL PLANT

**(E)SWBD M** — 2000A MCB, 480Y/277V, 3ϕ, 4 WIRE — AVAILABLE FAULT: 37,000A — SCCR & AIC: 100,000A — FREE STANDING

| NOTES | CIRCUIT | DESCRIPTION | CB | FEEDER SIZE | AMPS |
|---|---|---|---|---|---|
| | 1 | EXIST CIRCUIT | 60/3 | EXIST FEEDER | |
| | 2 | EXIST SPD | 60/3 | EXIST FEEDER | |
| | 3 | EXIST DISTRIBUTION PANEL AC | 1200/3 | EXIST FEEDER | |
| | 4 | EXIST DISTRIBUTION PANEL DA | 400/3 | EXIST FEEDER | 314A |
| | 5 | EXIST DISTRIBUTION PANEL DC | 400/3 | EXIST FEEDER | |
| | 6 | EXIST DISTRIBUTION PANEL DB | 400/3 | EXIST FEEDER | |
| 2,4 | 7 | NEW PANEL HK | 225/3 | 4–4/0 +4G, 2.5"C | 66A |
| | 8 | EXIST CAPACITOR | 250/3 | EXIST FEEDER | |
| | | | | TOTAL LOAD ❶ 100% = | 314A |
| | | | | TOTAL LOAD ❶ 125% = | 393A |

1. THE EXISTING 2000A FEEDER IS SUFFICIENT FOR THE REVISED LOAD.
2. UPDATE PANEL SCHEDULE TO MATCH REVISED EQUIPMENT DESCRIPTION.

## EXIST GE NHB PANELBOARD — STORAGE ROOM

**(E)PANEL DA** — 400A MLO, 480Y/277V, 3ϕ, 4 WIRE — AVAILABLE FAULT: 27,000A — SCCR & AIC: 35,000A — MOUNTING: SURFACE

| NOTES | LOAD | DESCRIPTION | WIRE | CB | CKT | CKT | CB | WIRE | DESCRIPTION | LOAD | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | 3000 | EXIST CIRCUIT | EXIST | 20/1 | 1 | 2 | 20/1 | EXIST | LIGHTS CAFETORIUM RMS | 2300 | 1 |
| 1 | 3000 | LIGHTS CAFETORIUM | EXIST | 20/1 | 3 | 4 | 20/1 | EXIST | LIGHTS CAFETORIUM | 3000 | 1 |
| | 9150 | AHU #2 | EXIST | 20/3 | 5 | 6 | 20/1 | EXIST | KITCHEN LIGHTS | | 2 |
| | – | – | – | – | 7 | 8 | 60/3 | EXIST | DUCT HEATER 3 | 39000 | |
| | – | – | – | – | 9 | 10 | – | – | ( STAGE ) | – | |
| | 130000 | PANEL PA | EXIST | 225/3 | 11 | 12 | – | – | – | – | |
| | – | – | – | – | 13 | 14 | 70/3 | 3–6 | TEMP KITCHEN PANEL LTK | 37918 | 4 |
| | – | – | – | – | 15 | 16 | – | +8G | – | – | |
| | 33750 | XFRMR TLCAB | EXIST | 125/3 | 17 | 18 | – | 3/4"C | – | – | |
| | – | – | – | – | 19 | 20 | | | SPACE | | |
| | – | – | – | – | 21 | 22 | | | SPACE | | |
| | | SPACE | | | 23 | 24 | | | SPACE | | |
| | | SPACE | | | 25 | 26 | | | SPACE | | |
| | | SPACE | | | 27 | 28 | | | SPACE | | |
| | | SPACE | | | 29 | 30 | | | SPACE | | |
| | | TOTAL LOAD ❶ 100% = 261118VA | | | | TOTAL LOAD ❶ 100% = 314A | | | TOTAL LOAD ❶ 125% = 393A | | |

1. THE EXISTING 400A FEEDER IS SUFFICIENT FOR THE REVISED LOAD.
2. UPDATE PANEL SCHEDULE TO MATCH REVISED EQUIPMENT DESCRIPTION.

## EXIST EM STANDBY PANELBOARD — CENTRAL PLANT

**(E)PANEL EL** — 100A MCB, 208Y/120V, 3ϕ, 4 WIRE — AVAILABLE FAULT: <10,000A — SCCR & AIC: 10,000A — MOUNTING: SURFACE

| NOTES | EQUIP. NO. | LOAD | DESCRIPTION | WIRE | CB | CKT | CKT | CB | WIRE | DESCRIPTION | LOAD | EQUIP. NO. | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | 500 | PA SYSTEM | EXIST | 20/1 | 1 | 2 | 20/1 | | EXIST SPARE | | | |
| | | 500 | SECURITY SYSTEM | EXIST | 20/1 | 3 | 4 | 20/1 | | EXIST SPARE | | | |
| | | 250 | FACP | EXIST | 20/1 | 5 | 6 | 20/1 | | EXIST SPARE | | | |
| | | 250 | F/A RPS | EXIST | 20/1 | 7 | 8 | 20/1 | | EXIST SPARE | | | |
| | | 250 | F/A RPS | EXIST | 20/1 | 9 | 10 | 20/1 | | EXIST SPARE | | | |
| | | 250 | GENERATOR ACCESSORIES | EXIST | 20/1 | 11 | 12 | 20/1 | | EXIST SPARE | | | |
| 4 | E188 | 864 | REFRIGERATOR | 3–12 | 20/1 | 13 | 14 | 20/1 | | EXIST SPARE | | | |
| 4 | E188 | 864 | REFRIGERATOR | 3–12 | 20/1 | 15 | 16 | 25/3 | 3–10 | REFRIGERATION SYSTEM | 6192 | E103 | 4 |
| 4 | E109 | 1428 | ICE MACHINE | 3–12 | 20/1 | 17 | 18 | – | +10G | – | – | | |
| 4 | E151 | 240 | HOOD ANSUL SYSTEMS | 3–12 | 20/1 | 19 | 20 | – | 3/4"C | – | – | | |
| 4 | E102B | 600 | COOLER TEMP. ALARM | 3–12 | 20/1 | 21 | 22 | 20/1EGF | 3–12 | COOLER DOOR HEATER/LTS | 600 | E102A | 4 |
| 4 | E102C | 600 | COOLER PRESSURE PORT | 3–12 | 20/1 | 23 | 24 | 20/1EGF | 3–12 | FREEZER DOOR HEATER/LTS | 600 | E102A | 4 |
| 4 | E102E | 120 | PANIC ALARM BUTTONS | 3–12 | 20/1 | 25 | 26 | 20/1EGF | 3–12 | FREEZER DRAIN LINE HEATER | 600 | E103F | 4 |
| 4 | E103D | 216 | COOLER COIL | 3–12 | 20/1 | 27 | 28 | | | SPACE | | | |
| 4 | E102B | 600 | FREEZER TEMP. ALARM | 3–12 | 20/1 | 29 | 30 | | | SPACE | | | |
| 4 | E102C | 600 | FREEZER PRESSURE PORT | 3–12 | 20/1 | 31 | 32 | | | SPACE | | | |
| 4 | E103C | 1893 | FREEZER COIL | 2–10 | 20/2 | 33 | 34 | | | SPACE | | | |
| | | – | – | +10G | – | 35 | 36 | | | SPACE | | | |
| | | | EXIST SPARE | | 40/3 | 37 | 38 | 30/3 | EXIST | SPD | 50 | | |
| | | – | – | – | – | 39 | 40 | – | – | – | – | | |
| | | – | – | – | – | 41 | 42 | – | – | – | – | | |
| | | | TOTAL LOAD ❶ 100% = 18067VA | | | | TOTAL LOAD ❶ 100% = 50A | | | TOTAL LOAD ❶ 125% = 63A | | | |

1. THE EXISTING 100A FEEDER IS SUFFICIENT FOR THE REVISED LOAD.
2. UPDATE PANEL SCHEDULE TO MATCH REVISED EQUIPMENT DESCRIPTION.

GENERAL PANEL REQUIREMENTS:
A. REF ELECTRICAL FLOOR PLANS FOR PANEL LOCATIONS.
B. FIELD VERIFY EXISTING CIRCUITS PRIOR TO BEGINNING WORK.
C. ALL OUTAGES SHALL BE SCHEDULED AND CONFIRMED IN WRITING WITH THE OWNER A MINIMUM OF TWO WEEKS PRIOR TO ANY OUTAGE.
D. AT THE END OF THE PROJECT PROVIDE A NEW TYPEWRITTEN PANEL SCHEDULE USING BUILDING ROOM NUMBERS FOR ALL PANELS WITH CIRCUITS ADDED, REMOVED, OR MODIFIED AS PART OF THE PROJECT.

PANEL NOTES:
1. REVISE/REWORK WIRING/CONDUIT AS REQUIRED TO ADD/REMOVE DEVICES FROM EXISTING CIRCUIT.
2. EXISTING CIRCUIT TO BE DEMO.
3. REUSE EXISTING SPARE CB AND WIRE NEW CIRCUIT.
4. PROVIDE NEW CB & WIRE NEW CIRCUIT.
5. IDENTIFY ANY CIRCUITS OR PARTIAL CIRCUITS THAT EXTEND BEYOND THE AREA OF RENOVATION. PROVIDE TEMPORARY FEED TO MAINTAIN ALL CIRCUITS SERVING ELEMENTS/SPACES NOT TO BE REMOVED DURING CONSTRUCTION. RECONNECT EXISTING CIRCUITS/DEVICES TO REMAIN TO TEMPORARY KITCHEN PANEL ONCE AVAILABLE USING CB(S) PROVIDED. ALL PARTIAL CIRCUITS SHALL REMAIN AND REMAIN ACTIVE BOTH DURING AND AFTER CONSTRUCTION.
6. KITCHEN LIGHTS TO BE DUAL ZONES WIRED THROUGH LIGHTING CONTACTORS AND CONTROLLED ON/OFF BY THE BAS AND LOCAL LIGHTING SWITCHES.
7. EXTERIOR LIGHTS TO BE WIRED THROUGH LIGHTING CONTACTOR AND CONTROLLED ON/OFF BY THE BAS.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL




MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL SCHEMATIC

k-E.400

STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM (713) 300-6080
TEXAS ENG. FIRM REG. NO. F-23332 | 1300 W. SAM HOUSTON PARKWAY S., SUITE 125, HOUSTON, TX 77042
©2025 ALL RIGHTS RESERVED

## PLUMBING SYMBOLS LEGEND

| | | | |
|---|---|---|---|
| ——— | SANITARY WASTE BELOW SLAB | SAN. | SANITARY |
| ——— | SANITARY WASTE ABOVE SLAB | CW | DOMESTIC COLD WATER |
| —— V. —— | VENT PIPING ABOVE SLAB | HW | DOMESTIC HOT WATER |
| ——— | VENT PIPING | WC | WATER CLOSET |
| —— G —— | GAS PIPING, 4-8oz | UR | URINAL |
| —— G5 —— | GAS PIPING, 5LB | LAV | LAVATORY |
| —·—·— | DOMESTIC COLD WATER PIPING | SK | SINK |
| —·—·—·— | DOMESTIC HOT WATER PIPING | EDF | ELECTRIC DRINKING FOUNTAIN |
| —— D —— | DRAIN/RELIEF VENT PIPING | WH | WALL HYDRANT |
| —⋈— | STOP VALVE | HB | HOSEBIBB |
| 2CO | DOUBLE SAN. CLEANOUT (2-WAY) | CP | HOT WATER CIRCULATOR PUMP |
| CO | SANITARY SEWER CLEANOUT | FD | FLOOR DRAIN |
| WCO | WALL CLEANOUT | FSINK | FLOOR SINK |
| EXIST. | EXISTING | | |
| (R) | REMOVE (DEMOLISH) | | |
| (D) | DEMOLISH (REMOVE) | | |
| (E) | EXISTING — NO WORK | | |

## PLUMBING FIXTURE NOTES

1. ALL FIXTURES SHALL MEET WATER CONSERVATION PERFORMANCE STANDARDS MANDATED BY SENATE BILL 587. ALL FIXTURES SHALL HAVE FLOW RESTRICTION DEVICES (DRINKING FOUNTAINS SHALL BE SELF-CLOSING) TO COMPLY WITH THESE REQUIREMENTS.
2. ALL FIXTURES SHALL HAVE CONTROLS REQUIRING OPERATING FORCE NO GREATER THAN FIVE (5) POUNDS.
3. FOR LAVATORIES AND SINKS, ALL FAUCETS SHALL BE NO-LEAD SOLID BRASS, MEETING ALL REQUIREMENTS OF ANSI/NSF 61, SECTION 9 AND CERTIFIED AS SUCH. ALSO, INSTALL SYMMONS 7-210 MIXING VALVE ON HOT WATER SUPPLY SIDE OF ALL FAUCETS UNLESS HIGH TEMPERATURE LIMIT IS PROVIDED WITH FAUCET. MAXIMUM WATER TEMPERATURE FOR ALL FAUCETS THAT DELIVER HOT OR TEPID WATER SHALL BE 110°F. ALL METERING FAUCETS SHALL HAVE A MINIMUM TEN (10) SECONDS OF WATER FLOW, AND, INSTALL TRUEBRO HANDI LAV-GUARD VANDAL-PROOF INSULATION KITS OVER P-TRAP, SUPPLIES, STOPS AND ALL SHARP EDGES FOR ALL SINKS AND LAVATORIES (TRAP WRAP FROM BROCAR OR PROWRAP FROM McGUIRE SHALL BE ACCEPTABLE).
4. ALL PLUMBING FIXTURES REFERENCED AS "ADA", "TAS" OR "HANDICAP COMPLIANT" SHALL MEET ALL REQUIREMENTS OF THE ADA AND THE TEXAS ACCESSIBILITY STANDARDS. IT SHALL BE THE PLUMBING CONTRACTORS RESPONSIBILITY TO MEET THESE REQUIREMENTS.
5. IN MANY CASES, FIXTURES WITH THE SAME PLUMBING DESIGNATION HAVE DIFFERENT INSTALLATION HEIGHTS — REFERENCE ARCHITECTURAL DRAWINGS FOR ALL INSTALLATION HEIGHTS AND HANDICAP FIXTURE DESIGNATIONS. FIXTURES DESIGNATED AS ADULT HANDICAP SHALL MEET ALL REQUIREMENTS OF THE ADA. FIXTURES DESIGNATED AS CHILD HANDICAP SHALL MEET ALL REQUIREMENTS OF THE TEXAS ACCESSIBILITY STANDARDS FOR THE APPROPRIATE CHILDREN'S AGE GROUP (REF. ARCH. DWGS. AND SPECIFICATIONS).

## PLUMBING MATERIALS

SANITARY WASTE AND VENT

BELOW SLAB/GRADE: SCHEDULE 40, DWV PVC

ABOVE SLAB: STANDARD WEIGHT, CAST IRON, NO-HUB PIPING.

STORM DRAIN PIPING

BELOW SLAB/GRADE: SCHEDULE 40, DWV PVC

ABOVE SLAB, 8" AND UNDER: STANDARD WEIGHT, CAST IRON, NO-HUB PIPING.

ABOVE SLAB, 10" AND ABOVE: SERVICE WEIGHT, CAST IRON, BELL & SPIGOT.

NATURAL GAS

BELOW GRADE (OUTSIDE): YELLOW POLYETHYLENE PIPE WITH COATED STEEL RISER AND TRACER WIRE.

ABOVE SLAB: SCHEDULE 40 BLACK STEEL. PIPING 2.5" AND LARGER SHALL BE WELDED. PIPING 2" AND SMALLER SHALL HAVE SCREWED FITTINGS.

DOMESTIC WATER

INTERIOR: TYPE L COPPER WITH SOLDER TYPE WROUGHT COPPER FITTINGS, MADE UP WITH LEAD-FREE SOLDER.

EXTERIOR: TYPE K COPPER WITH SWEAT FITTINGS AND LEAD-FREE SOLDER. BEYOND 5 FEET FROM BUILDING, SCHEDULE 40 PVC.

## FIRE SPRINKLER SYSTEM NOTES


1. THE EXISTING FIRE SPRINKLER SYSTEM SHALL BE MODIFIED AND/OR EXPANDED TO COVER THE AREA OF RENOVATION IN ENTIRETY. ALL NEW AND REVISED PIPING SHALL BE ENGINEERED AND INSTALLED BY A LICENSED FIRE SPRINKLER CONTRACTOR.
2. REFERENCE THE SPECIFICATIONS, DIVISION 21, FOR MORE INFORMATION.

## GENERAL PLUMBING NOTES

1. SEE ARCHITECTURAL DRAWINGS AND SPECIFICATIONS FOR ADDITIONAL WORK DESCRIPTION. SEE THIS SHEET (P4.00) FOR PLUMBING SYMBOLS LEGEND.
2. COORDINATE PLUMBING SYSTEMS INSTALLATION WITH ARCHITECTURAL, STRUCTURAL, HVAC SYSTEMS, ELECTRICAL SYSTEMS, CONDUITS, ETC.... OFFSET PIPING AS REQUIRED TO PROVIDE A FUNCTIONING SYSTEM WITH ADEQUATE SPACE FOR SERVICING AND REPAIRS.
3. MAKE CONNECTIONS OF NEW PIPE SYSTEMS IN TO EXISTING PIPE SYSTEMS WITH THREADED OR SWEAT JOINTS. PROVIDE ELECTROLYSIS ISOLATING UNIONS AT CONNECTION OF DISSIMILAR MATERIALS. REFERENCE THE SPECIFICATIONS.
4. SITE SERVICES ARE SHOWN FOR REFERENCE ONLY. PLUMBING CONTRACTOR SHALL REFERENCE CIVIL DRAWINGS, INCLUDING LOCATIONS OF SERVICES, SIZES OF PIPES, FLOWLINE ELEVATIONS, ETC..
5. DO NOT INSTALL PLUMBING PIPING OVER ANY ELECTRICAL EQUIPMENT. REFERENCE ELECTRICAL DRAWINGS FOR LOCATIONS OF ELECTRICAL EQUIPMENT AND COORDINATE WITH ELECTRICAL SUBCONTRACTORS ACCORDINGLY. SEE DETAIL 2/MEP1. THIS INCLUDES FIRE SPRINKLER PIPING.
6. ALL PIPES THROUGH WALLS OR FLOORS SHALL BE SLEEVED AND SEALED PER DETAIL 5/P4.02. FIRE CAULK WHERE REQUIRED. THIS INCLUDES ALL WALLS, INTERIOR AND EXTERIOR. THIS INCLUDES FIRE SPRINKLER PIPING.
7. ALL CLEANOUTS SHALL BE CONNECTED TO SANITARY LINES USING WYES AND/OR LONG RADIUS ELLS. SANITARY TEES ARE NOT ACCEPTABLE. 2" MINIMUM SIZE. ALL WALL CLEAN OUTS IN VERTICAL RISERS, OR BANKS OF FIXTURES SHALL BE INSTALLED 4" ABOVE THE FLOOD RIM LEVEL OF THE LOWEST CONNECTED FIXTURE AND A MINIMUM OF 24" AFF.
8. ALL WASTE AND VENT PIPING BELOW SLAB SHALL BE 2" MINIMUM.
9. LOCATE PLUMBING VENTS THROUGH ROOF NOT NEARER THAN SIX (6) FEET AWAY FROM EDGE OF BUILDING AND TEN (10) FEET AWAY FROM ANY FRESH AIR INTAKES. OFFSET VENT PIPING, AS REQUIRED, IN CEILING SPACE BETWEEN CEILING AND ROOF TO MEET THESE REQUIREMENTS. SEE DETAIL 3/P4.02.
10. ALL DOMESTIC WATER PIPING (CW, HW AND HWR) SHALL BE INSULATED PER THE WRITTEN SPECIFICATIONS.
11. TOP OF FLOOR DRAINS IN MECHANICAL, AHU AND BOILER ROOMS SHALL BE SET 1-1/2" BELOW FINISHED FLOOR SURFACE. CONCRETE FLOOR SHALL BE SLOPED TO DRAIN, REFERENCE ARCHITECTURAL DRAWINGS. IN ALL OTHER LOCATIONS, FLOOR DRAINS SHALL BE SET FLUSH WITH FINISHED FLOOR, TAKING INTO ACCOUNT ANY FLOOR SLOPE OR FLOOR FINISH (TILE, TERRAZZO, ETC.) AS SHOWN ON ARCHITECTURAL DRAWINGS.
12. PROVIDE AN ISOLATING VALVE AT EACH WATER TAP OFF HOT AND COLD WATER MAINS TO ALLOW FOR SERVICING. VALVE SHALL BE BALL VALVE IF PIPE SIZE IS 2" OR LESS AND GATE VALVE OR BUTTERFLY VALVE IF LARGER THAN 2". SEE WRITTEN SPECIFICATIONS. VALVES SHALL BE EASILY ACCESSIBLE. PROVIDE 18" X 18", FIRE-RATED, STAINLESS STEEL ACCESS PANELS WITH PUSH, QUARTER-TURN CYLINDER LOCK DOORS WHERE VALVES ARE INSTALLED ABOVE INACCESSIBLE CEILINGS OR IN WALL CHASES (MIFAB MODEL MPFR-SS-C). BALL VALVES AND BUTTERFLY VALVES INSTALLED ABOVE CEILINGS SHALL BE INSTALLED SUCH THAT HANDLE IS ON BOTTOM OF PIPE. ISOLATING WATER VALVES ABOVE CEILINGS SHALL BE INSTALLED NO MORE THAN 24" ABOVE CEILING. VALVES ABOVE INACCESSIBLE CEILINGS SHALL BE INSTALLED WITHIN REASONABLE REACH OF CEILING MOUNTED ACCESS PANEL.
13. WATER HAMMER ARRESTERS SHALL BE INSTALLED IN ADDITION TO AIR CHAMBERS PER THE RISER DIAGRAMS. SEE SPECIFICATIONS.
14. MECHANICALLY CLEAN ALL WASTE LINES WITH ROTARY MACHINE TO PROVE FREE FLOWING, SEE SPECIFICATIONS.
15. PROVIDE VENTED SLEEVE (2 PIPE SIZES LARGER THAN GAS PIPE UNLESS NOTED OTHERWISE) FOR ALL GAS PIPING IN GROUND BELOW PAVING OR SIDEWALKS AND INSIDE BUILDING IN WALLS AND IN UNVENTILATED CEILING SPACES, SEE SPECIFICATIONS.
16. GAS PIPING SHALL BE 1/2" MINIMUM. TAP GAS PIPING ON TOP OR SIDES ONLY. DO NOT INSTALL VALVES IN CEILING PLENUM IN ANY INACCESSIBLE LOCATION. ALL GAS VALVES SHALL BE EASILY ACCESSIBLE. REFER TO DETAIL 9/P4.01 FOR TYPICAL GAS CONNECTION INSTALLATION. REFER TO DETAIL 8/P4.02 FOR TYPICAL PRV INSTALLATION.
17. CENTER WALL HYDRANTS IN BRICK PATTERN OF EXTERIOR WALLS, REFERENCE THE ARCHITECTURAL DRAWINGS AND SPECIFICATIONS.
18. ALL REFRIGERATORS WITH ICE MAKERS, COMMERCIAL TYPE COFFEE MAKERS, ICE MAKERS, COFFEE VENDING MACHINES AND OTHER ITEMS PROVIDED BY OTHERS THAT REQUIRE A WATER CONNECTION SHALL HAVE A CW VALVE BOX, "VBOX", INSTALLED TO ALLOW EASY ACCESS AND REMOVAL OF MACHINE. ALSO, INSTALL IN-LINE FILTER IN WATER CONNECTION.
19. REFER TO CIVIL DRAWINGS FOR SITE SANITARY, SITE STORM SEWER, FIRE SERVICE AND DOMESTIC WATER SERVICE. PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR ALL PIPING INSIDE BUILDING TO OUTSIDE LOCATIONS SHOWN ON PLUMBING DRAWINGS. PLUMBING CONTRACTOR SHALL INCLUDE COST OF FINAL TIE-INS TO SITE SERVICES.
20. PER THE DRAWINGS, ALL DRAINS (FLOOR DRAINS, FLOOR SINKS, HUB DRAINS, KITCHEN DRAINS, SHOWER DRAINS, ETC.) SHALL BE VENTED AND TRAP PRIMED — NO EXCEPTIONS. TRAP PRIMING SHALL BE ACCOMPLISHED USING WATER CLOSET FLUSH VALVE TRAP PRIMING DEVICES OR PROSET SYSTEMS TRAP GUARD SEWER GAS EMISSION PROTECTION, AS SHOWN ON DRAWINGS. REFERENCE PLUMBING FLOOR PLANS AND RISER DIAGRAMS.
21. ALL PIPING LOCATED ON ROOF (GAS PIPING) SHALL BE INSTALLED ON ROOF PIPE SUPPORTS PER DETAIL 10/P4.02, 6-FOOT ON CENTER. INSTALL ROOF PIPE JACK PER DETAIL 9/P4.02 FOR ALL PIPING THROUGH ROOF.
22. COORDINATE LOCATIONS OF ALL ROOF DRAINS AND OVERFLOW ROOF DRAINS WITH ARCHITECTURAL DRAWINGS.
23. FOR COMBINATION WASTE AND VENT SYSTEMS (WHERE APPLICABLE ON DRAWINGS), DRAIN P-TRAPS SHALL BE SIZE OF PIPE SHOWN ON DRAWINGS (I.E. TWO PIPE SIZES LARGER THAN DRAIN SIZE). FOR EXAMPLE, A 4" FLOOR DRAIN SHALL HAVE A 6" P-TRAP.
24. FOR ALL PLUMBING FIXTURES, IF COPPER PIPING IS STUBBED THROUGH WALL FOR DRAIN CONNECTION, INSTALL MARWEL FITTING AT DRAIN CONNECTION FOR EASE OF SERVICING AND REPAIRS. COPPER DRAIN PIPING WILL ONLY BE ALLOWED FOR DIRECT/STRAIGHT STUB-OUT OF FIXTURE DRAIN PIPING THROUGH WALL.
25. DO NOT INSTALL ANY PIPING BENEATH CVT OR VAV BOXES. THIS INCLUDES FIRE SPRINKLER PIPING.
26. WHERE UNDERGROUND VENT PIPE SIZE IS NOT NOTATED, VENT SHALL BE 2" DIAMETER.
27. WHERE UNDERGROUND SANITARY PIPE SIZE IS NOT NOTATED, REFER TO THE RISER DIAGRAMS FOR SIZE. NOT BELOW GRADE SANITARY PIPE SHALL BE SMALLER THAN 2". NO SANITARY LINE OR P-TRAP FOR A DRAIN/FIXTURE SHALL BE SMALLER THAN THE FIXTURE CONNECTION SIZE SHOWN ON THE DRAIN/FIXTURE SCHEDULE.
28. WHERE ABOVE GROUND VENT PIPE SIZE IS NOT NOTATED, REFER TO THE RISER DIAGRAMS FOR VENT SIZE.
29. WHERE CW/HW PIPING SIZE TO THE FIXTURE IS NOT SHOWN ON THE FLOOR PLAN, REFER TO THE RISER DIAGRAMS FOR CW/HW PIPE SIZE. NO PIPING TO FIXTURE SHALL BE SMALLER THAN THE FIXTURE CONNECTION SIZE SHOWN ON THE FIXTURE SCHEDULE.
30. TO INSTALL NEW PLUMBING SYSTEMS BELOW EXISTING CONCRETE SLABS, FIRST PLUMBING CONTRACTOR SHALL LAY OUT CUT. THEN, DEMOLITION CONTRACTOR SHALL SAW CUT SLAB TO CONTROL CRACKING AND REMOVE ALL CONCRETE. PLUMBING CONTRACTOR SHALL THEN EXCAVATE FILL TO PROPER SLOPE, INSTALL NEW PIPING SYSTEMS AS REQUIRED, THEN BACKFILL AND COMPACT TO PROPER DENSITY. THE CONCRETE CONTRACTOR SHALL THEN INSTALL NEW SIX (6) MIL POLYETHYLENE VAPOR BARRIER AND SEAL, INSTALL NEW REINFORCING STEEL AND WELD ON TO EXISTING, THEN RE-POUR CONCRETE TO NEW LEVEL. DO NOT CUT THROUGH GRADE BEAMS WITHOUT APPROVAL FROM THE STRUCTURAL ENGINEER. SEE ARCHITECTURAL AND STRUCTURAL DRAWINGS AND SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.
31. ALL ABANDONED FIXTURES, DRAINS AND PIPING (INCLUDING PIPING ABANDONED IN THE PAST) IN AREAS WHERE WORK IS BEING DONE SHALL BE COMPLETELY REMOVED FROM BUILDING (INCLUDING PIPING BELOW SLAB/GRADE — UNLESS SHOWN OTHERWISE ON DRAWINGS). EXISTING WATER PIPING SHALL BE CAPPED AT EXISTING WATER MAIN TAPS AND ALL ABANDONED PIPING REMOVED. ABANDONED VENT PIPING SHALL BE COMPLETELY REMOVED, INCLUDING EXISTING VTR'S NOT RE-USED. PATCH AS REQUIRED. ONLY ACTIVE PIPING, FIXTURES AND DRAINS SHALL REMAIN IN BUILDING WHERE WORK IS BEING DONE.

## GAS PRV SCHEDULE

| MARK | PRV-K |
|---|---|
| LOCATION | MECH. YARD |
| SERVES | KITCHEN |
| GAS LOAD | 585 CFH |
| DISTANCE FROM METER | 150 FT |
| DISTANCE TO LAST OUTLET | 200 FT |
| INLET (SIZE/PRESSURE) | 1" / 5 PSI |
| OUTLET (SIZE/PRESSURE) | 2" / 7-12 IN WC |




### 4 GAS PRESSURE REGULATOR DETAIL (PRV)

NO SCALE

NOTES:
1. GAS REGULATOR SHALL BE ANSI Z21.80 CERTIFIED FOR LINE PRESSURE REGULATION BETWEEN THE SERVICE REGULATOR AND CONNECTED EQUIPMENT.
2. ALL GAS REGULATORS WITH INLET PRESSURE ABOVE 2 PSI SHALL BE EQUIPPED WITH A FACTORY INSTALLED OVERPRESSURE PROTECTION DEVICE, AS PART OF THE ANSI Z21.80 CERTIFICATION.
3. GAS REGULATOR SHALL BE EQUIPPED WITH A VENT LIMITING DEVICE, SIZED IN ACCORDANCE WITH THE REGULATOR OUTLET PRESSURE.
4. ALL REGULATORS INSTALLED OUTDOORS SHALL BE RATED FOR OUTDOOR INSTALLATION.
5. BASIS OF DESIGN IN THE MAXITROL 325-L SERIES OF REGULATORS

## PLUMBING DRAINS, CLEANOUTS AND HYDRANTS


| MARK | MIN. CONNECTION SIZES (IN.) SAN | VENT | CW | HW | DESCRIPTION/SPECIFICATION FOR FIXTURE OR EQUIPMENT |
|---|---|---|---|---|---|
| FD | 4 | 2 | 1/2 | – | TOILET FLOOR DRAIN — TWO-PIECE CAST IRON WITH SEEPAGE FLANGE, REVERSIBLE CLAMPING COLLAR, 1/2" TRAP PRIMER TAP, 6" SQUARE, NICKEL BRONZE HSTRAINER AND SECURITY SCREWS JR SMITH MODEL 2005-03-K06PB-P050-U |
| FD2 | 4 | 2 | 1/2 | – | EQUIPMENT FLOOR DRAIN — CAST IRON, MEDIUM DEPTH DRAIN WITH FLANGE, CLAMPING DEVICE, SEEPAGE OPENINGS, DUCTILE IRON TRUE-FIT SEDIMENT BUCKET WITH 12" STAINLESS STEEL RIM LESS GRATE, 1/2" TRAP PRIMER TAP ZURN MODEL ZS-540-LC-P DRAIN SHALL BE DESIGNED SUCH THAT GRATE CANNOT BE INSTALLED WITHOUT SEDIMENT BUCKET. |
| FD3 | 4 | 2 | 1/2 | – | GRATED MECHANICAL ROOM FLOOR DRAIN — CAST IRON WITH FLANGE, SEEPAGE OPENINGS, 9" HEAVY-DUTY DUCTILE IRON GRATE WITH STAINLESS STEEL VENEER, CLAMPING DEVICE AND 1/2" TRAP PRIMER TAP ZURN MODEL ZS-550-C-P |
| FD4 | 4 | 2 | 1/2 | – | CANWASH FLOOR DRAIN — ALL GALVANIZED CAST IRON, MEDIUM DEPTH DRAIN WITH FLANGE, CLAMPING DEVICE, SEEPAGE OPENINGS, GALVANIZED SUR-SET SEDIMENT BUCKET WITH 12" GALVANIZED DUCTILE IRON RIM AND GRATE, 1/2" TRAP PRIMER TAP ZURN MODEL ZS-540-P-G-HD. DRAIN SHALL BE DESIGNED SUCH THAT GRATE CANNOT BE INSTALLED WITHOUT SEDIMENT BUCKET. |
| FD5 | 4 | 2 | 1/2 | – | KITCHEN FLOOR DRAINS SHALL BE SIMILAR EXCEPT WITH 7" SQUARE, BRONZE GRATE JR SMITH MODEL 2005-03-K07PB-P050-U PROVIDE 4" DIAMETER STAINLESS STEEL FUNNEL WHERE SHOWN ON DRAWINGS. REFERENCE KITCHEN CONNECTION SCHEDULE ON PLUMBING RENOVATION FLOOR PLAN SHEET. |
| FS KITCHEN FS | 4 | 2 | 1/2 | – | FLOOR SINK — CAST IRON, 8" DEEP SUMP, A.R.E. INTERIOR, INTEGRAL FLANGE FOR SUPPORT, CLAMPING DEVICE WHERE VAPOR BARRIER IS INSTALLED BETWEEN SLAB AND CONCRETE BEDDING FOR FLOOR, ALUMINUM SECONDARY DOME STRAINER AND 12" SQUARE HEAVY DUTY STAINLESS STEEL TRACTOR DUTY FRAME WITH 3/4-TRACTOR GRATE AND 1/2" TRAP PRIMER TAP JR SMITH MODEL 3150Y-04-C-13. |
| CO | VARIES | – | – | – | FLOOR CLEANOUT — ADJUSTABLE EXTENSION HOUSING, CAST IRON FERRULE WITH FULL-LINE-SIZE BRASS PLUG (UP TO 4"), 5" DIAMETER STAINLESS STEEL ACCESS COVER WITH VANDAL-PROOF SCREW, ROUND FRAME AND TOP LOAD RATING COMPATIBLE WITH FLOOR TYPE (REFERENCE ARCHITECTURAL DRAWINGS FOR FLOOR TYPES) ZURN MODEL ZS-1400-VP. PROVIDE CARPET FLANGE FOR CARPETED AREAS (CARPET MARKER SHALL NOT BE ACCEPTABLE) AND TERRAZZO RECESS FOR TERRAZZO FLOORS.<br>OUTDOOR CLEANOUT — SAME AS TYPE "CO" EXCEPT WITH HEAVY-DUTY NICKEL BRONZE TOP ZURN MODEL ZN-1400-HD-VP. INSTALL 18" X 18" X 6" THICK CONCRETE PAD AROUND EACH OUTDOOR CLEANOUT. |
| WCO | VARIES | – | – | – | WALL CLEANOUT — CAST IRON FERRULE WITH COUNTERSUNK HEAD (FULL-LINE-SIZE PVC PLUG UP TO 4") MI-FAB MODEL CM-SD. ACCESS COVER SHALL BE 8" SQUARE, SURFACE MOUNT, FLUSH INSTALLATION, 16-GAUGE STAINLESS STEEL ACCESS DOOR WITH FLANGED FRAME AND VANDAL-PROOF OPTION MI-FAB MODEL UA-SS-VP. ACID WASTE CLEANOUT (AWCO) SHALL BE SAME EXCEPT ACID WASTE PIPING.<br>INSIDE CABINETWORK WHERE CLEANOUT IS NOT VISIBLE, ACCESS PANEL MAY BE ROUND STAINLESS STEEL TYPE WITH VANDAL-PROOF CENTER SCREW MI-FAB MODEL C1450-RD-3-6. |
| 2CO | 4 | – | – | – | DOUBLE CLEANOUTS — SAME AS OUTDOOR CLEANOUTS. INSTALLED FOR TWO-WAY RODDING. SINGLE CLEANOUT WITH 2-WAY FITTING IS NOT ACCEPTABLE, PROVIDE TWO SEPARATE CLEANOUTS. INSTALL 18" X 18" X 6" THICK CONCRETE PAD AROUND EACH OUTDOOR CLEANOUT. |
| HB | – | – | 3/4 | – | HOSEBIBB — 3/4" HOSE THREAD, INTEGRAL VACUUM BREAKER SPOUT, ROUGH CHROME FINISH WITH REMOVABLE KEYED HANDLE, WALL FLANGE CHICAGO MODEL 952. |
| WH | – | – | 3/4 | – | RESTROOM WALL HYDRANT — NARROW WALL, WARM CLIMATE TYPE HOSE BOX, QUARTER-TURN WHEEL HANDLE, ASSE APPROVED ANTI-SIPHON INTEGRAL VACUUM BREAKER AND DUAL CHECK VALVE, 3/4" STRAIGHT INLET HOSE CONNECTION, CAST STAINLESS STEEL HYDRANT BOX, FLUSH MOUNTED 16-GAUGE STAINLESS STEEL FRAME AND 180° DROP DOWN DOOR WITH KEY LOCK AND WALL CLAMP JR SMITH MODEL 5518 |
| WH2 | – | – | 3/4 | – | EXTERIOR WALL HYDRANT — NON-FREEZE HOSE BOX, QUARTER-TURN WHEEL HANDLE, ASSE APPROVED ANTI-SIPHON INTEGRAL VACUUM BREAKER AND DUAL CHECK VALVE, 3/4" STRAIGHT INLET HOSE CONNECTION, CAST STAINLESS STEEL HYDRANT BOX, FLUSH MOUNTED 16-GAUGE STAINLESS STEEL FRAME AND 180° DROP DOWN DOOR WITH KEY LOCK AND WALL CLAMP JR SMITH MODEL 5519 |
| WH3 | – | – | 3/4 | 3/4 | CANWASH WALL HYDRANT — NON-FREEZE HOSE BOX WITH STRAIGHT INLET CONNECTION, HOT AND COLD MIXING, REMOVABLE KEYED HANDLE, ASSE APPROVED ANTI-SIPHON INTEGRAL BACKFLOW PREVENTER WITH 3/4" HOSE CONNECTION, HEAVY DUTY BRASS CASING, POLISHED BRONZE HYDRANT BOX WITH HINGED COVER, "WATER" CAST ON COVER, DRIP LIP AND WALL CLAMP J.R. SMITH MODEL 5560-QT-WC-H-W-PB. |
| WBOX | 2 | 2 | 3/4 | 3/4 | CLOTHES WASHER DRAIN/VALVE BOX — HEAVY-GAUGE GALVANIZED STEEL CONSTRUCTION, RECESSED IN WALL VALVE AND DRAIN CONNECTIONS, WATTS DUO-CLOZ VALVE GUY GRAY MODEL WB-200. |

## PLUMBING FIXTURES AND EQUIPMENT

| MARK | MIN. CONNECTION SIZES (IN.) SAN | VENT | CW | HW | DESCRIPTION/SPECIFICATION |
|---|---|---|---|---|---|
| WC | 4 | 2 | 1 | – | WATER CLOSET — WALL MOUNTED, WHITE VITREOUS CHINA, SIPHON JET ACTION, 1.28 GPF, ELONGATED BOWL, TOP SPUD, ADA/TAS COMPLIANT, AMERICAN STANDARD AFWALL: SLOAN ROYAL 111-1.28 FLUSH VALVE WITH VANDAL-PROOF FREE-SPINNING TOP CAP, 1.28 GPF, VANDAL-PROOF STOP AND ADA/TAS COMPLIANT LEVER ACTUATOR WITH LEVER INSTALLED ON LEFT SIDE (FOR FIXTURES DESIGNATED AS "HANDICAP"). INSTALL LEVER ON "WIDE-SIDE" OF TOILET STALL): BEMIS 1655-SS/C EXTRA HEAVY DUTY, WHITE, OPEN FRONT SEAT LESS COVER WITH SELF-SUSTAINING, STAINLESS STEEL CHECK HINGE; AND, FLOOR MOUNTED CARRIER. |
| LV | 1-1/4 | 1-1/4 | 1/2 | 1/2 | LAVATORY GOOSENECK FAUCET — WALL HUNG, WHITE VITREOUS CHINA, FRONT OVERFLOW, SELF-DRAINING DECK AREA, 21" X 18", ADA/TAS COMPLIANT AMERICAN STANDARD LUCERNE 0355.012; DECK MOUNTED FAUCET, 4" CENTERS, FIXED, CHROME PLATED, 5.25" GOOSENECK SPOUT, PRESSURE COMPENSATING LAMINAR FLOW NON-AERATING 0.5 GPM OUTLET, 4" WRISTBLADE HANDLES, ADJUSTABLE COMPRESSION CARTRIDGES, CHICAGO 895-317GN2AE72ABCP; CHROME PLATED, 17-GAUGE CAST BRASS GRID DRAIN WITH WHEELCHAIR OFFSET FITTING; CHROME PLATED, 17-GAUGE CAST BRASS P-TRAP WITH CLEANOUT PLUG; CHROME PLATED, CAST BRASS, LOOSE KEY ANGLE STOP WITH CHROME PLATED COPPER RISER; TRUEBRO HANDI LAV-GUARD VANDAL-PROOF, WHITE INSULATION KITS; AND, FLOOR MOUNTED, CONCEALED ARMS CARRIER. PROVIDE ASSE 1070 LISTED MIXING VALVE, LEONARD 170-LF OR EQUAL (MUST BE CAPABLE OF ADJUSTMENT ABOVE 130°F). |
| LV2 | 1-1/4 | 1-1/4 | 1/2 | 1/2 | LAVATORY — WALL HUNG, WHITE VITREOUS CHINA, FRONT OVERFLOW, SELF-DRAINING DECK AREA, 21" X 18", ADA/TAS COMPLIANT AMERICAN STANDARD LUCERNE 0355.012; CHROME PLATED, ALL CAST BRASS CONSTRUCTION, ADA/TAS COMPLIANT, VANDAL-PROOF FAUCET WITH 4" WRIST BLADE HANDLES, COMPRESSION STYLE CARTRIDGES, CHROME DECK PLATE, VANDAL-PROOF AERATOR, COPPER SUPPLIES AND CERTIFIED FOR MEETING ALL REQUIREMENTS OF NSF 61 SECTION 9 CHICAGO MARATHON MODEL 802-E70-317ABCP; CHROME PLATED, 17-GAUGE CAST BRASS GRID DRAIN WITH WHEELCHAIR OFFSET FITTING; CHROME PLATED, 17-GAUGE CAST BRASS P-TRAP WITH CLEANOUT PLUG; CHROME PLATED, CAST BRASS, LOOSE KEY ANGLE STOP WITH CHROME PLATED COPPER RISER; TRUEBRO HANDI LAV-GUARD VANDAL-PROOF, WHITE INSULATION KITS; AND, FLOOR MOUNTED, CONCEALED ARMS CARRIER. PROVIDE ASSE 1070 LISTED MIXING VALVE, LEONARD 170-LF OR EQUAL (MUST BE CAPABLE OF ADJUSTMENT ABOVE 130°F). |
| EDF | 1-1/2 | 1-1/2 | 1/2 | – | BI-LEVEL ELECTRIC DRINKING FOUNTAINS WITH BOTTLE FILLER — WALL MOUNTED, ALL STAINLESS STEEL, ADA AND TAS COMPLIANT FOR ALL AGES, 8 GPH AT ARI STANDARDS, 2-STREAM ALL METAL BUBBLER FITTING WITH VANDAL-RESISTANT KIT AND FRONT PUSH BUTTON ACTUATION, PUSH BUTTON ACTIVATED BOTTLE FILLER WITH 1.1GPM FILL RATE AND ANTI-MICROBIAL COATING, INTEGRAL WATER FILTER, LEAD-FREE (CERTIFIED FOR MEETING ALL REQUIREMENTS OF NSF 61 SECTION 9), REFRIGERANT HFC-134a, MAINTENANCE ACCESS PANEL, HALSEY-TAYLOR MODEL HTHBWVRBBL; CHROME PLATED, 17-GAUGE CAST BRASS P-TRAP WITH CLEANOUT PLUG; CHROME PLATED, CAST BRASS, LOOSE KEY ANGLE STOP WITH CHROME PLATED COPPER RISER; FLOOR MOUNTED CHAIR CARRIER; AND, STAINLESS STEEL ADA APRON FOR LOCATIONS REQUIRED BY ADA OR TAS. |
| MB | 3 | 2 | 3/4 | 3/4 | MOP BASIN — 24" X 24" X 12" DEEP TERRAZZO, TWO (2) STAINLESS STEEL SPLASH CATCHER PANELS, 8" DROP FRONT WITH STAINLESS STEEL CAP, CAST BRASS DRAIN WITH STAINLESS STEEL STRAINER STERN WILLIAMS HILOW MODEL HI-1800-BP; FAUCET SHALL BE POLISHED CHROME PLATED SERVICE SINK TYPE WITH VACUUM BREAKER, INTEGRAL SUPPLY CHECK STOPS, SPOUT WITH PAIL HOOK, HOSE END AND TOP BRACE CHICAGO MODEL 897-CCF (INSTALL BACKING/BRACING INSIDE WALL TO SUPPORT FAUCET AND TOP BRACE). |
| LP-1 | 3 | 2 | 3/4 | 3/4 | LAVATORY PUMP — FACTORY BUILT, LIFT PUMP FOR GRAY WATER WASTE, TOP ACCESS TO INTERNAL 1/6HP PUMP AND FLOAT SWITCH, 1.5" TOP AND SIDE INLETS, 1.5" TOP OUTLET, INTEGRAL CHECK VALVE AT BOTTOM INLET CONNECTIONS, 9FT POWER CORD WITH GROUNDED PLUG;<br>LIBERTY PUMPS MODEL 406 |

## KITCHEN PLUMBING CONNECTION SCHEDULE


| MARK | DESCRIPTION |
|---|---|
| P5 | 3/4" CW AND 3/4" HW — IN WALL, 36" AFF, TO MOP BASIN ("MB") FAUCET. REFERENCE PLUMBING FIXTURE SCHEDULE. |
| P6 | 3" DRAIN IN FLOOR FOR MOP BASIN ("MB") DRAIN. REFERENCE PLUMBING FIXTURE SCHEDULE. |
| P7 | 3/4" CW AND 3/4" HW — IN WALL, 18" AFF, TO HOSE BIBB. |
| P10 | FLOOR DRAIN — 3" OUTLET; FLUSH WITH FLOOR; TWO-PIECE CAST IRON WITH SEEPAGE FLANGE, REVERSIBLE CLAMPING COLLAR, 7" SQUARE HEAVY-DUTY POLISHED BRONZE GRATE, 1/2" TRAP PRIMER TAP, AND TRAP SEAL DEVICE (MODEL 2692) JR SMITH MODEL 2005-03-K07PB-P050-U. |
| P11C | 1/2" CW AND 1/2" HW — IN WALL, FOR HAND LAVATORY WITH FOOT CONTROLS ("LV"). REFERENCE PLUMBING FIXTURE SCHEDULE. |
| P11D | 2" DRAIN — IN WALL, FOR HAND LAVATORY WITH FOOT CONTROLS ("LV"). REFERENCE PLUMBING FIXTURE SCHEDULE. |
| P12 | FLOOR SINK — 4" OUTLET; FLUSH WITH FLOOR; CAST IRON, 8" DEEP SUMP, A.R.E. INTERIOR, INTEGRAL FLANGE FOR SUPPORT, CLAMPING DEVICE WHERE VAPOR BARRIER IS INSTALLED BETWEEN SLAB AND CONCRETE BEDDING FOR FLOOR, ALUMINUM SECONDARY DOME STRAINER AND 12" SQUARE HEAVY DUTY NICKEL BRONZE FRAME W




## 13 FLUSH VALVE TRAP PRIMING TUBE DETAIL

NO SCALE

MI-FAB MODEL MI-702-MOD FLUSH VALVE TRAP PRIMER, OR EQUAL





## 14 GAS PIPING ROOF SUPPORT DETAIL

NO SCALE

NOTES:


1. GAS PIPING SUPPORT SHALL BE PORTABLE PIPE HANGERS, INC. MODEL PP10-R. PIPING SHALL BE INSTALLED 12" ABOVE FINISHED ROOF. PROVIDE 18" X 18" CAREY TREAD-TYPE MATERIAL BENEATH EACH PIPE SUPPORT.
2. FIELD LOCATE ROOF STRUCTURAL SUPPORTS AND PLACE BASE OF PIPE SUPPORT OVER ROOF SUPPORTS ONLY. PROVIDE BASE OF ADEQUATE LENGTH TO SPAN ROOF JOIST TO PREVENT SUPPORTS SETTING ON ROOF DECK ONLY.
3. INSTALL SIX (6) FOOT-ON-CENTERS.
4. PIPE SUPPORT MANUFACTURER'S REPRESENTATIVE SHALL PERSONALLY INSPECT INSTALLATIONS OF PIPE SUPPORTS AND MAKE CORRECTIONS AND HEIGHT ADJUSTMENTS TO INSTALLATIONS, AS REQUIRED, DURING INSPECTION.




## 9 ROOF PIPE JACK DETAIL

NO SCALE


NOTE: COORDINATE WITH ARCHITECTURAL DRAWINGS, DETAILS AND SPECIFICATIONS.




## 13 GAS PIPING WALL-TO-ROOF TRANSITION DETAIL

NO SCALE

| TANKLESS WATER HEATER SCHED. | | |
|---|---|---|
| MARK | IEWH-1 | |
| SERVES | LAVATORY | |
| LOCATION | BELOW COUNTER | |
| HEATER KW | 1.8 KW | |
| TEMP RISE (@ 0.5 GPM) | 25°F | |
| VOLTAGE/PHASE | 120V/1PH | |
| EEMAX MODEL | SPEX1812T | |





## 11 TANKLESS WATER HEATER

NO SCALE

NOTES:

1. LOCATION OF VALVE AND PIPING SHALL NOT INTERFERE WITH ANY ADA/HANDICAP KNEE-SPACE CLEARANCE REQUIREMENTS.
2. ALL PIPING SHALL BE CHROME PLATED CAST BRASS AND SHALL BE INSULATED BY TRUEBRO HANDI LAV-GUARD INSULATION KITS. INSULATION KITS SHALL COVER P-TRAP, MIXING VALVE, WATER STOPS, PIPING AND ALL SHARP EDGES (ONLY WHERE CABINETWORK KNEESPACE SCREEN NOT PROVIDED).
3. ALL CW AND HW CONNECTIONS SHALL HAVE COMPRESSION TYPE FITTINGS.
4. FURNISH & INSTALL 0.5-GPM AERATOR ON FAUCET COMPATIBLE WITH TANKLESS EWH REQUIREMENTS.
5. WATER HEATER SHALL HAVE INTEGRAL ASSE-1070 COMPLIANT TEMPERED MIXING VALVE.





## 10 ELECTRONIC TRAP PRIMING MANIFOLD DETAIL (TP)

NO SCALE

NOTES:


1. REFERENCE SCHEDULE ON SHEET P3.00




## 8 SAMPLE TEST WELL DETAIL (STW)


NO SCALE

NOTES:




## 7 TYPICAL GAS CONNECTION


NO SCALE




## 6 HOT WATER BALANCING STATION


NO SCALE

PROVIDE AT EACH JUNCTION OF BRANCH HOT WATER RETURN LOOPS TO MAIN CIRCULATING HOT WATER LINE, SEE PLUMBING PLANS.




## 5 WALL PENETRATION DETAIL


NO SCALE




## 4 PVC-TO-CAST IRON INSTALLATION DETAIL

NO SCALE


MISSION TRANSITION COUPLING DESIGNED AND CERTIFIED FOR THIS SPECIFIC APPLICATION SHALL BE ACCEPTABLE IN LIEU OF HUSKY COUPLING IN THIS DETAIL.




## 3 ROOF VENT DETAIL

NO SCALE

COORDINATE WITH ARCHITECTURAL DRAWINGS AND SPECIFICATIONS.





## 2 MIXING VALVE DETAIL

NO SCALE

NOTES

1. UNDERCOUNTER MIXING VALVE SHALL BE MOUNTED ON WALL IN FIXTURE KNEE-SPACE. LOCATION OF VALVE AND PIPING SHALL NOT INTERFERE WITH ANY ADA/HANDICAP KNEE-SPACE CLEARANCE REQUIREMENTS.
2. ALL PIPING SHALL BE CHROME PLATED CAST BRASS AND SHALL BE INSULATED BY TRUEBRO HANDI LAV-GUARD INSULATION KITS. INSULATION KITS SHALL COVER P-TRAP, MIXING VALVE, WATER STOPS, PIPING AND ALL SHARP EDGES (ONLY WHERE CABINETWORK KNEESPACE SCREEN NOT PROVIDED).
3. ALL CW AND HW CONNECTIONS SHALL HAVE COMPRESSION TYPE FITTINGS.
4. FOR ABOVE CEILING INSTALLATION, VALVE SHALL BE INSTALLED IN AN EASILY/READILY ACCESSIBLE LOCATION. SEE KITCHEN PLUMBING CONNECTION SCHEDULE FOR REQUIRED KITCHEN LOCATIONS.
5. LAVATORY MIXING VALVES SHALL HAVE AN OUTPUT ADJUSTMENT RANGE UP TO OR ABOVE 130°F.
   SINK MIXING VALVES SHALL HAVE AN OUTPUT ADJUSTMENT RANGE UP TO OR ABOVE 140°F.




## 1 MECHANICAL - ELECTRICAL COORDINATION DETAIL

NO SCALE

DO NOT INSTALL ANY PIPING BENEATH CVT BOXES. DO NOT INSTALL ANY PIPING (EXCEPT FIRE SPRINKLER PIPING AND OTHER PIPES SHOWN SPECIFICALLY ON THE PLUMBING FLOOR PLANS) OVER COMPUTER CLASSROOMS, BOOKROOMS, IDF/MDF/SERVER ROOMS OR OTHER ROOMS NOTED ON THE PLUMBING FLOOR PLANS.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
6955 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL

STATE OF TEXAS — INTERIM REVIEW — NOT FOR CONSTRUCTION — 07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

PLUMBING SCHEDULES & DETAILS

**k-P0.02**

PRELIMINARY
NOT FOR CONSTRUCTION OR BIDDING PURPOSES


STANTON ENGINEERING GROUP
INFORMATION@STANTON-ENG.COM | (713) 300-6080
TEXAS ENGINEERING FIRM REG. NO. F-01833 | 1300 W. SAM HOUSTON PARKWAY S., SUITE 121, HOUSTON, TX 77042

ALL RIGHTS RESERVED

# TECHNOLOGY SYMBOLS & LEGEND

## VOICE SYMBOLS

| | |
|---|---|
| | SINGLE VOICE OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| X | VOICE OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |
| | SINGLE VOICE OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED. |
| X | VOICE OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED, X = NUMBER OF CABLE TERMINATIONS PER LOCATION AS INDICATED. |
| | POWER/COMMUNICATIONS POLE WITH A SINGLE VOICE OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| X | POWER/COMMUNICATIONS POLE WITH X = NUMBER OF VOICE OUTLETS, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| | SINGLE VOICE OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE-THRU AS SPECIFIED. |
| X | VOICE OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE -THRU AS SPECIFIED WITH X = NUMBER OF VOICE TERMINATIONS PER LOCATION. |
| W | SINGLE VOICE OUTLET FOR WALL-MOUNTED PHONE, CABLE TYPE AS SPECIFIED, MOUNTED +52-INCHES A.F.F. UNLESS OTHERWISE NOTED. |

## VOICE/DATA SYMBOLS

| | |
|---|---|
| | SINGLE VOICE & SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| X Y | VOICE & DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. X = NUMBER OF VOICE TERMINATIONS , Y = NUMBER OF DATA TERMINATIONS PER LOCATION. |
| | SINGLE VOICE & SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED. |
| X Y | VOICE & DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED, X = NUMBER OF VOICE OUTLETS AND Y = NUMBER OF DATA OUTLETS PER LOCATION AS INDICATED. |
| | POWER/COMMUNICATIONS POLE WITH A SINGLE VOICE OUTLET AND SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| X Y | POWER/COMMUNICATIONS POLE WITH X = NUMBER OF VOICE TERMINATIONS, Y = NUMBER OF DATA TERMINATIONS, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| | SINGLE VOICE OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE-THRU AS SPECIFIED. |
| X Y | VOICE OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE -THRU AS SPECIFIED WITH X = NUMBER OF VOICE TERMINATIONS, Y = NUMBER OF DATA TERMINATIONS PER LOCATION. |

## DATA SYMBOLS

| | |
|---|---|
| | SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| X | DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |
| | SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED. |
| X | DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED, X = NUMBER OF CABLE TERMINATIONS PER LOCATION AS INDICATED. |
| | POWER/COMMUNICATIONS POLE WITH A SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| X | POWER/COMMUNICATIONS POLE WITH X = NUMBER OF DATA OUTLETS, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| | SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE-THRU AS SPECIFIED. |
| X | DATA OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE -THRU AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |
| W | SINGLE DATA OUTLET FOR WALL-MOUNTED IP PHONE, CABLE TYPE AS SPECIFIED, MOUNTED +52-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| X | DATA CABLE FOR COMPUTER ON WHEELS, CABLE TYPE AS SPECIFIED MOUNTED + 18-INCHES A.F.F UNLESS OTHERWISE NOTED. X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |
| X | DATA CABLE FOR CEILING MOUNTED WIRELESS ACCESS POINT, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A GREEN ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. |
| X | DATA CABLE FOR CEILING MOUNTED VIDEO SURVEILLANCE CAMERA, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A ORANGE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. REFER TO SECURITY DRAWINGS PRIOR TO INSTALLATION. |
| | DATA CABLE FOR CEILING MOUNTED PROJECTOR, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A BLUE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. REFER TO AUDIO/VISUAL DRAWINGS PRIOR TO INSTALLATION. |
| X | DATA CABLE FOR CEILING MOUNTED AUDIO/VISUAL EQUIPMENT ENCLOSURE, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A BLUE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. REFER TO AUDIO/VISUAL DRAWINGS PRIOR TO INSTALLATION. |
| X | DATA CABLE FOR WALL MOUNTED PROJECTOR, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A BLUE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. REFER TO AUDIO/VISUAL DRAWINGS PRIOR TO INSTALLATION. |

## FIBER OPTIC SYMBOLS

| | |
|---|---|
| | SINGLE FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| X | FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |
| | SINGLE FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED. |
| X | FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED, X = NUMBER OF CABLE TERMINATIONS PER LOCATION AS INDICATED. |
| | POWER/COMMUNICATIONS POLE WITH A SINGLE FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| X | POWER/COMMUNICATIONS POLE WITH X = NUMBER OF FIBER OPTIC OUTLETS, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| | SINGLE FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE-THRU AS SPECIFIED. |
| X | FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE -THRU AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |

## DATA SYMBOLS, CONT.

| | |
|---|---|
| X CAME | DATA CABLE FOR EXTERIOR WALL MOUNTED VIDEO SURVEILLANCE CAMERA, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A ORANGE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW, REFER TO SECURITY DRAWINGS PRIOR TO INSTALLATION. |
| X CAMW | DATA CABLE FOR INTERIOR WALL MOUNTED SURVEILLANCE CAMERA, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A ORANGE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. |
| X CAME | DATA CABLE FOR EXTERIOR WALL MOUNTED SURVEILLANCE CAMERA, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A ORANGE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. |
| X WAPW | DATA CABLE FOR INTERIOR WALL MOUNTED WIRELESS ACCESS POINT, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A GREEN ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. |
| X WAPE | DATA CABLE FOR EXTERIOR WALL MOUNTED WIRELESS ACCESS POINT, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A GREEN ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. |

## ROUGH-IN & MISC. SYMBOLS

| | |
|---|---|
| R | ROUGH-IN LOCATION, INFRASTRUCTURE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| R | ROUGH-IN LOCATION, INFRASTRUCTURE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED. |
| R | POWER POLE WITH ROUGH-IN LOCATION, INFRASTRUCTURE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| R | ROUGH-IN LOCATION. TERMINATED IN FLOOR BOX/POKE-THRU AS SPECIFIED. |
| WAP | WIRELESS ACCESS POINT. EQUIPMENT AS SPECIFIED. |

## CABLE PLANT & RISER DIAGRAM

| | |
|---|---|
| | MAINTENANCE HOLE, SIZE & TYPE AS SPECIFIED. |
| | PULLBOX, SIZE AND TYPE AS SPECIFIED. |
| UGC | DIRECT BURIED COMMUNICATIONS, CABLE TYPE AS SPECIFIED. |
| AER | AERIAL COMMUNICATIONS, CABLE TYPE AS SPECIFIED. |
| | CONDUIT, SIZE AND TYPE AS SPECIFIED. |

## GENERAL SYMBOLS

| | |
|---|---|
| # SHEET — DRAWING TITLE SCALE: SCALE | DRAWING TITLE CALLOUT, # = DETAIL NUMBER. |
| # SHEET | DETAIL CALLOUT, # = DETAIL NUMBER. |
| # SHEET | SECTION CALLOUT, # = DETAIL NUMBER. |
| SHEET # | ELEVATION CALLOUT, # = DETAIL NUMBER. |
| # | KEYED NOTE, # = KEYED NOTE NUMBER. |
| # | REVISION TRIANGLE, # = REVISION NUMBER (PER SHEET). |
| TR (IDF XXX) | INDICATES TELECOMMUNICATIONS REGION |

## ABBREVIATIONS

| | |
|---|---|
| A.F.F. | ABOVE FINISHED FLOOR |
| A.F.G. | ABOVE FINISHED GRADE |
| AER | AERIAL |
| DEMARC | DEMARCATION POINT |
| EMT | ELECTRIC METALLIC TUBE |
| F.O.C. | FIBER OPTIC CABLE |
| GIP | GALVANIZED IRON PIPE |
| HE | PAINTERCOM HEAD-END |
| IMC | INTERMEDIATE METAL CONDUIT |
| ISP | INSIDE CABLE PLANT |
| IDF | INTERMEDIATE DISTRIBUTION FRAME |
| MDF | MAIN DISTRIBUTION FRAME |
| MH | MAINTENANCE HOLE |
| MM | MULTIMODE |
| OSP | OUTSIDE CABLE PLANT |
| PB | PULLBOX |
| PR | PAIR |
| PVC | POLYVINYL CHLORIDE |
| RSC | RIGID STEEL CONDUIT |
| SM | SINGLE MODE |
| SP | SERVICE PROVIDER |
| STP | SHIELDED TWISTED PAIR |
| TB | TERMINAL BLOCK |
| TR | TELECOMMUNICATION REGION |
| UGC | UNDERGROUND COMMUNICATION |
| UON | UNLESS OTHERWISE NOTED |
| UTP | UNSHIELDED TWISTED PAIR |

## NOTES

1. CONTRACTOR SHALL REVIEW DRAWINGS AND SPECIFICATIONS THAT MAKE UP THE CONTRACT DOCUMENTS AND COMPLETE ALL WORK INCLUDED THEREIN.
2. SCALE OF TECHNOLOGY DRAWINGS IS PROVIDED FOR REFERENCE ONLY. CONTRACTOR SHALL BE RESPONSIBLE FOR PROPER CABLE LENGTHS, SIZE OF PATHWAYS, DIMENSIONS, ETC.
3. TECHNOLOGY DRAWINGS SHALL BE USED TO COMPLEMENT THE WRITTEN SPECIFICATIONS.
4. ANY DISCREPANCY OR CONFLICT WITHIN OR BETWEEN THE DRAWINGS AND SPECIFICATIONS SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT/DESIGN CONSULTANT'S. DISCREPANCIES OR CONFLICTS NOT BROUGHT TO THE ATTENTION OF THE ARCHITECT/DESIGN CONSULTANT AND SUBSEQUENTLY CLARIFIED DURING THE BIDDING OF THE PROJECT WILL BE DEEMED TO HAVE BEEN BID OR PROPOSED IN THE MORE COSTLY OR DIFFICULT MANNER, AND THE BETTER QUALITY OR GREATER QUANTITY OF WORK SHALL BE PROVIDED BY THE CONTRACTOR IN ACCORDANCE WITH THE ARCHITECT'S/DESIGN CONSULTANT'S INTERPRETATION.

## INDEX OF DRAWINGS


k-T000 TECHNOLOGY SYMBOLS & LEGEND
k-TD201 TECHNOLOGY DEMOLITION FLOOR PLAN
k-T200 TECHNOLOGY COMPOSITE FLOOR PLAN
k-T201 TECHNOLOGY NEW/RENOVATION KITCHEN PLAN
k-T202 TECHNOLOGY TEMPORARY KITCHEN PLAN
k-T300 TECHNOLOGY ENLARGED VIEWS
k-T400 TECHNOLOGY TYPICAL DETAILS
k-T401 TECHNOLOGY TYPICAL DETAILS
k-T500 TECHNOLOGY TYPICAL DETAILS


ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD


07/18/2025


ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY SYMBOLS & LEGEND

SHEET NO.
k-T000




1 k-T200 TECHNOLOGY COMPOSITE FLOOR PLAN
1/16" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL

ENGINEERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD


07/18/2025


ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY COMPOSITE FLOOR PLAN

SHEET NO.
k-T200




1 k-T201 TECHNOLOGY NEW/RENOVATION KITCHEN PLAN
1/4" = 1'-0"

**TECHNOLOGY FLOOR PLANS GENRAL NOTES:**

1. THE TECHNOLOGY REGION / WIRING BOUNDARIES ARE IDENTIFIED ON THE OVERALL SHEETS ONLY AND NOT ON THE ENLARGED SHEETS. CONTRACTOR SHALL REFER TO THE OVERALL SHEETS FOR ALL TECHNOLOGY REGIONS / WIRING BOUNDARIES.
2. ALL CONDUIT PATHWAYS, ROUGH-INS, BACKBOXES, FLOOR BOXES, CONDUIT SLEEVES, ETC. INDICATED ON THE TECHNOLOGY DRAWINGS ARE TO BE PROVIDED AND INSTALLED BY DIVISION 26.
3. ALL POWER INDICATED ON THE TECHNOLOGY DRAWINGS IS TO BE PROVIDED AND INSTALLED BY DIVISION 26.
4. CONTRACTOR SHALL RESTORE ALL PENETRATIONS PROVIDED THROUGH FIRE RATED WALLS/STRUCTURES FOR TECHNOLOGY CABLING BACK TO THE ORIGINAL RATING.
5. CONTRACTOR SHALL RESTORE ALL PENETRATIONS PROVIDED THROUGH NON-RATED WALLS/STRUCTURES FOR TECHNOLOGY CABLING FOR SOUND TO REDUCE NOISE TRAVELING THROUGH PENETRATIONS.
6. TECHNOLOGY CABLING SHALL BE ROUTED IN SEPARATE PATHWAYS IN J-HOOKS, CONDUITS, CONDUIT SLEEVES, CORES, ETC. THROUGHOUT THE ENTIRE PATHWAY. DIFFERENT MEDIA TYPES (DATA, VIDEO, SECURITY, ETC.) SHALL NOT SHARE THE SAME J-HOOK, CONDUIT, CONDUIT SLEEVE, CORE, ETC.
7. UNLESS NOTED OTHERWISE, ALL CONDUITS FOR TECHNOLOGY DEVICES SHALL ROUTE FROM THE DEVICE LOCATION AND TERMINATE ABOVE AN ACCESSIBLE CEILING (AN OPEN CEILING OR CLOUD TYPE CEILING IS NOT CONSIDERED AN ACCESSIBLE CEILING) IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF A MAIN CORRIDOR OR NEAREST MDF/IDF. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF / IDF ROOM TO MINIMIZE THE CABLE LENGTH ENSURING CABLE LENGTH DOES NOT EXCEED 275 FEET.
8. UNLESS NOTED OTHERWISE ALL CONDUITS SHALL BE HOMERUN FROM THE DEVICE LOCATION AND NO DAISY CHAINING OF DEVICES/ ROUGH-INS SHALL BE ALLOWED.
9. CONDUIT SEGMENTS SHALL BE NO MORE THAN 100-FEET IN LENGTH WITH NO MORE THAN THE EQUIVALENT OF (2) 90 DEGREE BENDS BETWEEN PULLING POINTS.
10. CONDUITS SHALL MAINTAIN A BEND RADIUS OF 6 TIMES THE DIAMETER OF THE CONDUIT FOR CONDUITS 2-INCHES OR SMALLER AND 10 TIMES THE DIAMETER OF THE CONDUIT FOR CONDUITS GREATER THAN 2-INCHES.
11. ALL CONDUITS SHALL HAVE A PULL STRING INSTALLED FOR PULLING OF CABLE. CLEARLY LABEL AS "PULL STRING" INDICATING OPPOSITE END LOCATION.
12. ALL SPARE CONDUITS OR CONDUITS FILLED WITH LESS THAN THE MAXIMUM ALLOWED FILL RATIO SHALL HAVE A PULL STRING INSTALLED AND LEFT FOR FUTURE PULLING OF CABLE. CLEARLY LABEL AS "PULL STRING" INDICATING OPPOSITE END LOCATION.
13. EQUIPMENT NOT RELATED TO THE SUPPORT OF THE TELECOMMUNICATIONS ROOM (E.G., PIPING, DUCTWORK, PNEUMATIC TUBING) SHALL NOT BE INSTALLED IN, PASS THROUGH, OR ENTER THE TELECOMMUNICATIONS ROOM.
14. ALL CONDUITS FOR TECHNOLOGY DEVICES SHALL ROUTE FROM THE DEVICE LOCATION AND TERMINATE ABOVE A LAY-IN TYPE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE A LAY- IN TYPE CEILING TO PREVENT THE CABLES FROM BEING EXPOSED, THE CONDUIT SHALL ROUTE TO THE NEAREST LAY-IN TYPE CEILING OFF A MAIN CORRIDOR OR NEAREST MDF/IDF. THE CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE MAIN CORRIDOR OR NEAREST MDF/IDF TO MINIMIZE THE CABLE LENGTH ENSURING THE CABLE LENGTH DOES NOT EXCEED 275 FEET. CONDUIT, CONNECTIONS, J-BOXES, SUSPENSION, ANCHORAGES, AND OTHER CONDUIT COMPONENTS EXPOSED TO VIEW IN PUBLIC SPACES SHALL BE ROUTED AND INSTALLED CAREFULLY TO MINIMIZE VISUAL IMPACT AND SHALL BE FULLY PAINTED TO MATCH UNLESS NOTED OTHERWISE.
15. CONDUIT(S) INSTALLED IN-SLAB OR UNDER-SLAB TO FLOOR BOXES, POKE-THURS, AND TO WORKAREA OUTLETS, ETC. SHALL BE INSTALLED WITH WET RATED CABLE(S).
16. NO GRID WIRE SHALL BE UTILIZED FOR SUPPORTS ONLY USE SOLID SUPPORTS (CLIPS, ALL-THREAD, ANCHORS, ETC.).

**TECHNOLOGY PLAN KEYED NOTES**

**NOT ALL KEYED BELOW APPLY TO THIS SHEET**

1. DATA CABLE FOR CONTRACTOR FURNISHED / CONTRACTOR INSTALLED MENU BOARD. REFERENCE ARCHITECTURAL AND FOOD SERVICE DRAWINGS FOR MOUNTING HEIGHT AND ADDITIONAL INFORMATION. BUILDING POWER ADJACENT TO DATA RECEPTACLE IS REQUIRED.
2. INDOOR / OUTDOOR RATED DATA CABLE FOR POINT OF SALE LOCATION. PROVIDE (1) 1-INCH CONDUIT FOR DATA TO THE WALL BEHIND POINT OF SALE LOCATION AND UP WALL TO ABOVE ACCESSIBLE CEILING. CONDUITS SHALL TERMINATE INSIDE A DOUBLE GANG BOX THAT IS SECURED TO THE POINT OF SALE LOCATION. REFER TO FOOD SERVICE / KITCHEN DRAWINGS FOR EXACT LOCATION AND CONDUIT ROUGH-IN REQUIREMENTS.
3. DATA CABLE FOR TEMPERATURE MONITORING OF FREEZER COOLER. REFER TO FOOD SERVICE / KITCHEN DRAWINGS FOR EXACT LOCATION AND CONDUIT ROUGH-IN REQUIREMENTS AND TERMINATION POINT AND CONNECTIVITY NEEDS IN FREEZER / COOLER CONTROL UNIT.
4. DATA CABLE FOR TEMPORARY POINT OF SALES CASH REGISTER. COORDINATE WITH OWNER, ARCHITECT, AND CONSULTANT FOR ROUTING OF CABLES TO POINT OF SALE CASH REGISTER PRIOR TO INSTALLATION

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL

LICENSED REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 10-31-25
RCDD


07/18/2025


ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY NEW/RENOVATION KITCHEN PLAN

SHEET NO.
k-T201




1 k-T202 TECHNOLOGY TEMPORARY KITCHEN FLOOR PLAN
1/4" = 1'-0"

**TECHNOLOGY FLOOR PLANS GENRAL NOTES:**

1. THE TECHNOLOGY REGION / WIRING BOUNDARIES ARE IDENTIFIED ON THE OVERALL SHEETS ONLY AND NOT ON THE ENLARGED SHEETS. CONTRACTOR SHALL REFER TO THE OVERALL SHEETS FOR ALL TECHNOLOGY REGIONS / WIRING BOUNDARIES.
2. ALL CONDUIT PATHWAYS, ROUGH-INS, BACKBOXES, FLOOR BOXES, CONDUIT SLEEVES, ETC. INDICATED ON THE TECHNOLOGY DRAWINGS ARE TO BE PROVIDED AND INSTALLED BY DIVISION 26.
3. ALL POWER INDICATED ON THE TECHNOLOGY DRAWINGS IS TO BE PROVIDED AND INSTALLED BY DIVISION 26.
4. CONTRACTOR SHALL RESTORE ALL PENETRATIONS PROVIDED THROUGH FIRE RATED WALLS/STRUCTURES FOR TECHNOLOGY CABLING BACK TO THE ORIGINAL RATING.
5. CONTRACTOR SHALL RESTORE ALL PENETRATIONS PROVIDED THROUGH NON-RATED WALLS/STRUCTURES FOR TECHNOLOGY CABLING FOR SOUND TO REDUCE NOISE TRAVELING THROUGH PENETRATIONS.
6. TECHNOLOGY CABLING SHALL BE ROUTED IN SEPARATE PATHWAYS IN J-HOOKS, CONDUITS, CONDUIT SLEEVES, CORES, ETC. THROUGHOUT THE ENTIRE PATHWAY. DIFFERENT MEDIA TYPES (DATA, VIDEO, SECURITY, ETC.) SHALL NOT SHARE THE SAME J-HOOK, CONDUIT, CONDUIT SLEEVE, CORE, ETC.
7. UNLESS NOTED OTHERWISE, ALL CONDUITS FOR TECHNOLOGY DEVICES SHALL ROUTE FROM THE DEVICE LOCATION AND TERMINATE ABOVE AN ACCESSIBLE CEILING (AN OPEN CEILING OR CLOUD TYPE CEILING IS NOT CONSIDERED AN ACCESSIBLE CEILING) IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF A MAIN CORRIDOR OR NEAREST MDF/IDF. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF / IDF ROOM TO MINIMIZE THE CABLE LENGTH ENSURING CABLE LENGTH DOES NOT EXCEED 275 FEET.
8. UNLESS NOTED OTHERWISE ALL CONDUITS SHALL BE HOMERUN FROM THE DEVICE LOCATION AND NO DAISY CHAINING OF DEVICES/ ROUGH-INS SHALL BE ALLOWED.
9. CONDUIT SEGMENTS SHALL BE NO MORE THAN 100-FEET IN LENGTH WITH NO MORE THAN THE EQUIVALENT OF (2) 90 DEGREE BENDS BETWEEN PULLING POINTS.
10. CONDUITS SHALL MAINTAIN A BEND RADIUS OF 6 TIMES THE DIAMETER OF THE CONDUIT FOR CONDUITS 2-INCHES OR SMALLER AND 10 TIMES THE DIAMETER OF THE CONDUIT FOR CONDUITS GREATER THAN 2-INCHES.
11. ALL CONDUITS SHALL HAVE A PULL STRING INSTALLED FOR PULLING OF CABLE. CLEARLY LABEL AS "PULL STRING" INDICATING OPPOSITE END LOCATION.
12. ALL SPARE CONDUITS OR CONDUITS FILLED WITH LESS THAN THE MAXIMUM ALLOWED FILL RATIO SHALL HAVE A PULL STRING INSTALLED AND LEFT FOR FUTURE PULLING OF CABLE. CLEARLY LABEL AS "PULL STRING" INDICATING OPPOSITE END LOCATION.
13. EQUIPMENT NOT RELATED TO THE SUPPORT OF THE TELECOMMUNICATIONS ROOM (E.G., PIPING, DUCTWORK, PNEUMATIC TUBING) SHALL NOT BE INSTALLED IN, PASS THROUGH, OR ENTER THE TELECOMMUNICATIONS ROOM.
14. ALL CONDUITS FOR TECHNOLOGY DEVICES SHALL ROUTE FROM THE DEVICE LOCATION AND TERMINATE ABOVE A LAY-IN TYPE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE A LAY- IN TYPE CEILING TO PREVENT THE CABLES FROM BEING EXPOSED, THE CONDUIT SHALL ROUTE TO THE NEAREST LAY-IN TYPE CEILING OFF A MAIN CORRIDOR OR NEAREST MDF/IDF. THE CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE MAIN CORRIDOR OR NEAREST MDF/IDF TO MINIMIZE THE CABLE LENGTH ENSURING THE CABLE LENGTH DOES NOT EXCEED 275 FEET. CONDUIT, CONNECTIONS, J-BOXES, SUSPENSION, ANCHORAGES, AND OTHER CONDUIT COMPONENTS EXPOSED TO VIEW IN PUBLIC SPACES SHALL BE ROUTED AND INSTALLED CAREFULLY TO MINIMIZE VISUAL IMPACT AND SHALL BE FULLY PAINTED TO MATCH UNLESS NOTED OTHERWISE.
15. CONDUIT(S) INSTALLED IN-SLAB OR UNDER-SLAB TO FLOOR BOXES, POKE-THURS, AND TO WORKAREA OUTLETS, ETC. SHALL BE INSTALLED WITH WET RATED CABLE(S).
16. NO GRID WIRE SHALL BE UTILIZED FOR SUPPORTS ONLY USE SOLID SUPPORTS (CLIPS, ALL-THREAD, ANCHORS, ETC.).

**TECHNOLOGY PLAN KEYED NOTES**

NOT ALL KEYED BELOW APPLY TO THIS SHEET

1. DATA CABLE FOR OWNER FURNISHED / OWNER INSTALLED MENU BOARD. REFERENCE ARCHITECTURAL AND FOOD SERVICE DRAWINGS FOR MOUNTING HEIGHT AND ADDITIONAL INFORMATION. BUILDING POWER ADJACENT TO DATA RECEPTACLE IS REQUIRED.1.DATA CABLE FOR OWNER FURNISHED / OWNER INSTALLED MENU BOARD. REFERENCE ARCHITECTURAL AND FOOD SERVICE DRAWINGS FOR MOUNTING HEIGHT AND ADDITIONAL INFORMATION. BUILDING POWER ADJACENT TO DATA RECEPTACLE IS REQUIRED.
2. INDOOR / OUTDOOR RATED DATA CABLE FOR POINT OF SALE LOCATION. PROVIDE (1) 1-INCH CONDUIT FOR DATA TO THE WALL BEHIND POINT OF SALE LOCATION AND UP WALL TO ABOVE ACCESSIBLE CEILING. CONDUITS SHALL TERMINATE INSIDE A DOUBLE GANG BOX THAT IS SECURED TO THE POINT OF SALE LOCATION. REFER TO FOOD SERVICE / KITCHEN DRAWINGS FOR EXACT LOCATION AND CONDUIT ROUGH-IN REQUIREMENTS.
3. DATA CABLE FOR TEMPERATURE MONITORING OF FREEZER COOLER. REFER TO FOOD SERVICE / KITCHEN DRAWINGS FOR EXACT LOCATION AND CONDUIT ROUGH-IN REQUIREMENTS AND TERMINATION POINT AND CONNECTIVITY NEEDS IN FREEZER / COOLER CONTROL UNIT.
4. DATA CABLE FOR TEMPORARY POINT OF SALES CASH REGISTER. COORDINATE WITH OWNER, ARCHITECT, AND CONSULTANT FOR ROUTING OF CABLES TO POINT OF SALE CASH REGISTER PRIOR TO INSTALLATION

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL

LICENSED REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 10-31-25
RCDD


07/18/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY TEMPORARY KITCHEN PLAN

SHEET NO.
k-T202




1 k-T300 HUNTERS GLENN EXISTING IDF WALL RACK
N.T.S.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD

07/18/2025

ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING


TECHNOLOGY ENLARGED VIEWS

SHEET NO.
k-T300

NOTE TO CONTRACTOR:

UNLESS OTHERWISE NOTED, LOW VOLTAGE CABLING SHALL BE INSTALLED WITHIN 6-INCHES OF THE CEILING AND ACCESSIBLE BY A TECHNICIAN ON A STANDARD A-FRAME LADDER.

CONTRACTOR SHALL MAINTAIN AT LEAST 6-INCHES OF SEPRATION BETWEEN CABLING BUNDLES AND MECHANICAL DUCTWORKS, EQUIPMENT, PIPIING OR OTHER SYSTEMS IN THE CEILING PLENUM.





KEYED NOTES:

1. J-HOOK WITH RETAINER CLIP ABOVE ACCESSIBLE CEILING (BY DIV 27).
2. DATA CABLE ABOVE ACCESSIBLE CEILING (BY DIV 27).
3. A/V CABLE ABOVE ACCESSIBLE CEILING (BY DIV 27).
4. SECURITY CABLE ABOVE ACCESSIBLE CEILING (BY DIV 28).
5. SPARE J-HOOK (BY DIV 27).

## 1 T400 TYPICAL J-HOOK CABLE PATHWAY

SCALE: N.T.S.





KEYED NOTES:

1. SCHEDULED FLOOR OR DECK.
2. CONDUIT SLEEVE (BY DIV 26).
3. NYLON BUSHING (BY DIV 26).

## 2 T400 TYPICAL CONDUIT SLEEVE THROUGH FLOOR OR DECK DETAIL

SCALE: N.T.S.





KEYED NOTES:

1. SCHEDULED WALL.
2. SCHEDULED CEILING.
3. CONDUIT SLEEVE (BY DIV 26).
4. NYLON BUSHING (BY DIV 26).

## 3 T400 TYPICAL CONDUIT SLEEVE GOING THROUGH WALL

SCALE: N.T.S.





KEYED NOTES:

1. SCHEDULED WALL.
2. SCHEDULED CEILING.
3. SCHEDULED DECK ABOVE.
4. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX WITH DOUBLE GANG PLASTER RING (BY DIV 26).
5. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH. (BY DIV 26).

## 4 T400 TYPICAL TECHNOLOGY CONDUIT ROUGH-IN

SCALE: N.T.S.





KEYED NOTES:

1. SCHEDULED STUD.
2. SCHEDULED WALL.
3. J-HOOK WITH RETAINER CLIP ABOVE ACCESSIBLE CEILING (BY DIV 27).
4. DATA CABLE ABOVE ACCESSIBLE CEILING (BY DIV 27).
5. 20 FOOT SERVICE LOOP ABOVE ACCESSIBLE CEILING NEATLY COILED AND SECURED TO J-HOOK (BY DIV 27).
6. SURFACE MOUNT BOX ABOVE ACCESSIBLE CEILING SECURED TO BUILDING STRUCTURE (BY DIV 27).
7. DATA INSERT (BY DIV 27).

## 5 T400 TYPICAL ABOVE CEILING SINGLE DATA OUTLET (WALL MOUNTED)

SCALE: N.T.S.





KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH PHONE STUDS (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. CABLE AS SPECIFIED (BY DIV 27).

## 6 T400 TYPICAL WALL PHONE OUTLET CONFIGURATION

SCALE: N.T.S.





KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH DESIGNATION IN WINDOW (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. CABLE AS SPECIFIED (BY DIV 27).
7. ELECTRICAL RECEPTACLE, GANG BOX AND CONDUIT SHOWN FOR REFERENCE ONLY (REFER TO DIV 26).

## 7 T400 TYPICAL DUAL DATA OUTLET CONFIGURATION

SCALE: N.T.S.





KEYED NOTES:

1. 4 11/16-INCH X 4 11/16-INCH X 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. DOUBLE GANG PLASTER RING (BY DIV 26).
4. SURFACE MOUNT BOX INSIDE THE 4 11/16-INCH X 4 11/16-INCH X 2 1/8-INCH DOUBLE GANG BOX (BY DIV 27).
5. RJ-45 INSERT (BY DIV 27).

## 8 T400 TYPICAL WALL-MOUNTED WIRELESS ACCESS POINT

SCALE: N.T.S.




KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH DESIGNATION IN WINDOW (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. BLANK INSERT (BY DIV 27).
7. CABLE AS SPECIFIED (BY DIV 27).
8. ELECTRICAL RECEPTACLE, GANG BOX AND CONDUIT SHOWN FOR REFERENCE ONLY (REFER TO DIV 26).

## 9 T400 TYPICAL THREE DATA OUTLET CONFIGURATION

SCALE: N.T.S.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL





07/18/2025


ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY TYPICAL DETAILS

SHEET NO.
k-T400





KEYED NOTES:

1. ALL THREAD TO BUILDING STRUCTURE (BY DIV. 27)
2. SCHEDULING CEILING
3. IN-PLENUM CEILING BRACKET PN 49223-CBC ATTACHED TO ALL THREAD (BY DIV. 27)
4. SURFACE MOUNT BOX ABOVE ACCESSIBLE CEILING SECURED TO BRACKET (BY DIV. 27)
5. DATA CABLE (BY DIV. 27)
6. DATA INSERT (BY DIV. 27)

## 1 T401 TYPICAL ABOVE CEILING DATA OUTLET

SCALE: N.T.S.





KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH DESIGNATION IN WINDOW (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. CABLE AS SPECIFIED (BY DIV 27).
7. ELECTRICAL RECEPTACLE, GANG BOX AND CONDUIT SHOWN FOR REFERENCE ONLY (REFER TO DIV 26). ELECTRICAL RECEPTACLE TO BE INSTALLED AT 36" A.F.F AND ADJACENT TO COW / SECONDARY TEACHING OUTLET LOCATION.

## 2 T401 TYPICAL COW / SECONDARY TEACHER'S DATA OUTLET CONFIGURATION

SCALE: N.T.S.





KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH DESIGNATION IN WINDOW (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. BLANK INSERT (BY DIV 27).
7. CABLE AS SPECIFIED (BY DIV 27).
8. ELECTRICAL RECEPTACLE, GANG BOX AND CONDUIT SHOWN FOR REFERENCE ONLY (REFER TO DIV 26).

## 3 T401 TYPICAL THREE DATA OUTLET CONFIGURATION

SCALE: N.T.S.




KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH DESIGNATION IN WINDOW (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. CABLE AS SPECIFIED (BY DIV 27).
7. ELECTRICAL RECEPTACLE, GANG BOX AND CONDUIT SHOWN FOR REFERENCE ONLY (REFER TO DIV 26).

## 4 T401 TYPICAL FOUR DATA OUTLET CONFIGURATION


SCALE: N.T.S.

| TBB/GE CONDUCTOR SIZING | |
|---|---|
| LENGTH IN LINEAR M (FT) | SIZE (AWG) |
| LESS THAN 4 (13) | 6 |
| 4 - 6 (14-20) | 4 |
| 6 - 8 (21 - 26) | 3 |
| 8 - 10 (27 - 33) | 2 |
| 10 - 13 (34 - 41) | 1 |
| 13 - 16 (42 - 52) | 1/0 |
| 16 - 20 (53 - 66) | 2/0 |
| 20 - 26 (67 - 84) | 3/0 |
| 26 - 32 (85 - 105) | 4/0 |
| 32 - 38 (106 - 125) | 250 kcmil |
| 38 - 46 (126 - 150) | 300 kcmil |
| 46 - 53 (151 - 175) | 350 kcmil |
| 53 - 76 (176 - 250) | 500 kcmil |
| 76 - 91 (251 - 300) | 600 kcmil |
| GREATER THAN 91 (301) | 750 kcmil |

ROUTE THE TBB TO EACH TGB IN AS STRAIGHT A PATH AS POSSIBLE. THE TBB SHOULD BE INSTALLED AS A CONTINUOUS CONDUCTOR, AVOIDING SPLICES WHERE POSSIBLE.

## 5 T401 TBB CONDUCTOR SIZING

SCALE: N.T.S.





1. TELECOMMUNICATIONS MAIN GROUNDING BUS BAR (PBB)(BY DIV. 27)
2. TELECOMMUNICATIONS GROUNDING BUS BAR (SBB)(BY DIV 27)
3. TELECOMMUNICATIONS BONDING CONDUCTOR (TBC). REFER TO CONDUCTOR SIZING CHART FOR EXACT SIZE REQUIREMENTS (BY DIV 27)
4. CONNECT TO GROUNDED BUILDING STEEL WHEN EXPOSED IN ROOM.
5. TELECOMMUNICATIONS BONDING BACKBONE (TBB). REFER TO CONDUCTOR SIZING CHART FOR EXACT SIZE REQUIREMENTS (BY DIV 26)
6. TELECOMMUNICATIONS BONDING CONDUCTOR (TBC). BY ELECTRICAL CONTRACTOR.REFER TO CONDUCTOR SIZING CHART FOR EXACT SIZE REQUIREMENTS.
7. GROUNDING EQUALIZER CONDUCTOR (GEC)(BY DIV 26)
8. BOUND WITH GROUDING COLLARS TO EACH CONTINUOUS CONDUIT THAT ENTERS THE TELECOM ROOM. (BY DIV 26).
9. BOND TO EACH ACCESS CONTROL PANEL AND OTHER SECURITY PANELS IN HE TELECOM ROOM. (BY DIV 27)

## 6 T401 TYPICAL GROUNDING DIAGRAM

SCALE: N.T.S.

System No. W-L-3218
F Ratings - 1, 2, 3 and 4 Hr (See Items 1 and 3)
T Ratings - 3/4 and 1 Hr (See Item 3)
L Rating At Ambient - Less Than 1, 1.3, 4 or 7 CFM (See Item 3)
L Rating At 400 F - Less Than 1, 2 or 3 CFM (See Item 3)




**Section A-A**

1. Wall Assembly - The 1, 2, 3 or 4 hr fire-rated gypsum board/stud wall assembly shall be constructed of the materials and in the manner described within the individual U300, U400 or V400 Series Wall and Partition Designs in the UL Fire Resistance Directory and shall incorporate the following construction features:
   A. Studs - Wall framing shall consist of either wood studs or steel channel studs. Wood studs to consist of nom 2 by 4 in. (51 by 102 mm) lumber spaced max 16 in. (406 mm) OC. Steel studs to be min 3-1/2 in. (89 mm) wide and spaced max 24 in. (610 mm) OC.
   B. Gypsum Board* - Thickness, type, number of layers and fasteners as specified in the individual Wall and Partition Design. Opening in gypsum board to be max 1/4 in. (6 mm) larger then width and height dimensions of firestop device(s).
   The hourly F Rating of the firestop system is dependent upon the hourly rating of the wall in which it is installed.
2. Firestop Device* - One, two, three, four or seven firestop device modules ganged together. Each firestop device module consists of a 3 by 3 by 10-1/2 in. (76 by 76 by 267 mm) long galv steel tube with an intumescent material lining. Firestop device modules to be installed in accordance with the accompanying installation instructions. The space between the firestop device module(s) and the periphery of the opening shall be min 0 in. ( 0 mm, point contact) to max 1/8 in. (3.2 mm). In round openings, the space between the firestop device and the periphery of the opening shall be min 0 in. (point contact) to max 1/2 in. (13 mm). Firestop device module(s) secured in place by means of steel wall plates installed with gasketing material supplied with product. Steel wall plates installed on both sides of wall and secured to each device by means of steel set screws provided with device. Each four- and seven-gang steel wall plate shall be fastened to the studs with steel screws sized to extend through the gypsum board layers and penetrate 1/2 in. (13 mm) into the framing member. Each firestop device module is to be installed with ends projecting an equal distance beyond each surface of the wall assembly.
   As an alternate, the four- and seven-gang steel wall plates may be installed directly against the studs for walls having 16 and 24 in. (406 and 610 mm) center-to-center stud spacing, respectively, prior to installation of the gypsum board layers. The steel wall plates shall be secured to the stud by means of steel screws. After installation of the steel wall plates and firestop device modules, the gypsum board shall be installed as specified in the individual U300 or U400 Design with a maximum 1/8 in. (3.2 mm) gap between the firestop device module and the cutout in the gypsum board. Gap between the firestop device module and the cutout in the gypsum board may be filled with gypsum joint compound or fill material (Item 4).
   SPECIFIED TECHNOLOGIES INC - EZ PATH Series 33 Fire Rated Pathway

2A. Firestop Device* - Extension Module - (Optional, Not Shown) - Module attached to ends of 3 by 3 by 10-1/2 in. (76 by 76 by 267 mm) long firestop device (Item 3) to increase its length to facilitate installation in thicker walls. Each module consists of a 3 by 3 by 6 in. (76 by 76 by 152 mm) long galv steel tube with an intumescent material lining. Extension module to be installed in accordance with the accompanying installation instructions. When module is used, firestop device (Item 2) and extension module(s) secured in place by means of steel wall plates installed with gasketing material supplied with product. Steel wall plates installed on both sides of wall and secured to each device or extension module(s) by means of steel set screws provided with wall plates. Firestop device and extension module(s) assembly to be installed with ends projecting an equal distance beyond each surface of the wall assembly.
   SPECIFIED TECHNOLOGIES INC - EZ PATH Extension

3. Cables - Within the loading area for each firestop device module, the cables may represent a 0 to 100 percent visual fill. Cable fill to be distributed at a uniform height across the width of the firestop device module. Cables to be rigidly supported on both sides of the wall assembly. Any combination of the following types of cables may be used:
   A. Max 400 pair No. 24 AWG (or smaller) copper conductor telecommunication cable with polyvinyl chloride (PVC) jacketing and insulation.
   B. Max 350 kcmil single copper conductor power cable with XLPE jacket and insulation
   C. Max 7/C No. 12 AWG copper conductor control cable with PVC or XLPE jacket and insulation.
   D. Max 3/C No. 10 AWG metal clad or armored cable with steel or aluminum jacket.
   E. Max 3/C No. 8 AWG NM cable (Romex) with PVC insulation and jacket.
   F. Max four pair No. 22 AWG (or smaller) copper conductor data cable with PVC or plenum rated jacketing and insulation.
   G. Max RG/U coaxial cable with fluorinated ethylene insulation and jacketing.
   H. Fiber optic cable with PVC or polyethylene (PE) jacket and insulation having a max diam of 5/8 in. (16 mm).
   I. Optical Fiber Raceway+ - Max 1-1/2 in. (38 mm) diam (or smaller) optical fiber raceway ("innerduct") formed of either PVC or polyvinylidene fluoride (PVDF) with optical fiber cable fill. Raceways installed in accordance with the National Electrical Code (NFPA 70).
   When the hourly rating of the wall assembly is 1 hr, the T Rating is 3/4 hr. When the hourly fire rating of the wall assembly is greater than 1 hr, the T Rating is 3/4 hr when Item 3A, 3B, 3C, 3D or 3E is used. Otherwise the T Rating is 1 hr. When Item 3A, 3B, 3C, 3D or 3E is used, the maximum F Rating is 2 hr. When max 200 pair No. 24 AWG telecommunication cable is used or when Item 3F, 3G, 3H or 3I is used, the maximum F Rating is 4 hr.
   The L Rating for each empty firestop device module is less than 1 cfm at ambient and at 400F. When Item 3A is used, the L Rating for each firestop device module with 100 percent visual fill is 4 cfm at ambient and 3 cfm at 400F. When Item 3F is used, the L Rating for each firestop device module with 100 percent visual fill is 1.3 cfm at ambient and 1 cfm at 400F. When Item 3G or 3H is used, the L Rating for each firestop device module with 100 percent visual fill is 7 cfm at ambient and 2 cfm at 400F.
4. Fill, Void or Cavity Material* - Sealant or Putty - (Not Shown) - As an alternate to gypsum joint compound, the gap between the firestop device module and the cutout in the gypsum board may be sealed with fill material on each side of the wall assembly when four- and seven-gang steel wall plates are installed directly against the wood or steel studs.
   SPECIFIED TECHNOLOGIES INC - SpecSeal Series SSS Sealant, SpecSeal LCI Sealant, SpecSeal Putty
   *Bearing the UL Classification Mark

## 7 T401 TYPICAL STI EZ-PATH SLEEVE DETAIL

SCALE: N.T.S.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL


BICSI ID # 564970
EXPIRES 12-31-25
RCDD
07/18/2025



ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY TYPICAL DETAILS

SHEET NO.
k-T401













1 T500 TYPICAL HORIZONTAL DATA CABLE LABELING SCHEME

SCALE: N.T.S.






2 T500 TYPICAL FIBER BACKBONE LABELING SCHEME

SCALE: N.T.S.




3 T500 TYPICAL COPPER BACKBONE LABELING SCHEME

SCALE: N.T.S.




4 T500 ABOVE ASSESSIBLE CEILING LABELING SCHEME

SCALE: N.T.S.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
HUNTERS GLEN ELEMENTARY SCHOOL
695 INDEPENDENCE BLVD
MISSOURI CITY, TX 77489

SEAL




07/18/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25

DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY TYPICAL DETAILS

SHEET NO.

k-T500

## AUDIO/VISUAL MULTIMEDIA LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| A## V## | WALL AV ROUGH-IN DETAIL |
| A## V## | CEILING AV ROUGH-IN DETAIL |
| A## V## | FLOOR AV ROUGH-IN DETAIL |
| IWB IWB | INTERACTIVE WHITE BOARD - WALL - CEILING |
| PJ PJ | MULTIMEDIA PROJECTOR |
| FP# FP# | MULTIMEDIA FLAT PANEL DISPLAY |
| S S | LOUDSPEAKER, WALL MOUNTED AND CEILING MOUNTED RESPECTIVELY - # INDICATES TYPE |
| CP# | CONTROL PANEL |
| TP# | TOUCH PANEL |
| M | MICROPHONE, CEILING MOUNTED - # INDICATES TYPE |
| VC | VOLUME CONTROL |
| WB | WALL BOX ENCLOSURE |
| D1 A1 | D1 = DIGITAL SINGLE SIDED CLOCK / A1 = ANALOG SINGLE SIDED CLOCK |
| D2 A2 | D2 = DIGITAL DOUBLE SIDED CLOCK / A2 = ANALOG DOUBLE SIDED CLOCK |
| ENC | CEILING AV ENCLOSURE |
| C C | PRESENTATION CAMERA - CEILING - WALL MOUNTED |

## PREMISE SECURITY LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| CR | CARD READER |
| CR M | CARD READER MULLION |
| KP | INTRUSION DETECTION KEYPAD |
| IC | INTERCOM (1 DATA CABLE) |
| IC MS | INTERCOM MASTER STATION (1 DATA CABLE) |
| PB | PANIC/DURESS BUTTON |
| LD | LOCK DOWN BUTTON |
| MD | MOTION DETECTOR |
| GB | ACCOUSTICAL GLASS BREAK SENSOR |
| BM | BIOMETRIC READER |
| RX | REQUEST TO EXIT - SURFACE PIR |
| KS | KEY SWITCH |
| LA | LOCAL ALARM SOUNDER |
| RG | RED/GREEN INDICATOR LIGHT |
| DB | DOORBELL |
| DH | MAGNETIC DOOR HOLD |
| DR | DOOR RELEASE |
| RX | REQUEST TO EXIT - INTEGRAL TO DOOR HARDWARE |
| DC | DOOR CONTACT / MONITOR |
| ES EL EH | ELECTRIFIED STRIKE - ELECTRIFIED LATCH - ELECTRIFIED HARDWARE (REFER TO SCHEDULES) |
| C C | STANDARD IP SURVEILLANCE CAMERA, (1) CABLE |
| C C C | 180° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° FISHEYE LENS CAMERA |
| IR | IR ILLUMINATOR |

## STRUCTURED CABLING LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF DATA CABLE(S)/JACK(S) |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) |
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| W | WALL MOUNT PHONE (1 CABLE/JACK) |
| W | WALL MOUNT PHONE, SURFACE MOUNT (1 CABLE/JACK) |
| # | FLOOR MOUNTED OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| #/# | FLOOR MOUNTED OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| # | CEILING MOUNTED DATA OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) |
| AP# | CEILING MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| AP# | WALL MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| | CABLING SLEEVE(S) |
| | TYPICAL LADDER RACK |
| | TYPICAL CABLE TRAY, BASKET STYLE |

## GENERAL ANNOTATION LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| MER | MAIN EQUIPMENT ROOM |
| TR | TELECOMMUNICATION ROOM |
| MDF | MAIN DISTRIBUTION FRAME |
| IDF | INTERMEDIATE DISTRIBUTION FRAME |
| ETR | EXISTING TO REMAIN |
| PBO | PROVIDED BY OTHERS |
| AFF | ABOVE FINISHED FLOOR |
| AFG | ABOVE FINISHED GRADE |
| AC | ABOVE COUNTER |
| EC | ELECTRICAL CONTRACTOR |
| PSC | PREMISE SECURITY CONTRACTOR |
| SCC | STRUCTURAL CABLING CONTRACTOR |
| AVC | AV/MULTIMEDIA CONTRACTOR |
| UNO | UNLESS NOTED OTHERWISE |
| ACS | ACCESS CONTROL SYSTEM |
| VSS | VIDEO SURVEILLANCE SYSTEM |

## TECHNOLOGY - GENERAL NOTES

1. EACH KEYNOTE MAY NOT BE UTILIZED ON EVERY SHEET.
2. ALL CONDUIT MEASUREMENTS REFER TO STANDARD CONDUIT TRADE SIZES.
3. ALL CABLES SHALL BE CONCEALED.
4. EACH CONTRACTOR SHALL PROVIDE AND INSTALL ALL NECESSARY SLEEVES, WHETHER OR NOT SPECIFICALLY NOTED ON PROJECT DRAWINGS. ALL SLEEVES SHALL BE 2" UNLESS NOTED OTHERWISE ON THE DRAWINGS. CABLE FILL PERCENTAGE SHALL COMPLY WITH NEC.
5. DEVICE LOCATIONS ARE APPROXIMATE. CONTRACTOR SHALL REVIEW CONDITIONS AND COORDINATE WITH OTHER TRADES AS NECESSARY FOR EXACT PLACEMENT.

## TECHNOLOGY SYMBOLS LEGEND

NOT ALL SYMBOLS ARE USED

- A## V## — AV WALL ROUGH-IN WITH DATA
- # — KEYNOTE
- C — Proposed Camera Direction — SURVEILLANCE CAMERA
- #-## — Camera Schedule Number (Floor #-Camera #) — Camera (N)ew, (E)xisting Rough-in, (D)emo
- C — Proposed Camera Direction — PTZ CAMERA
- #-## PTZ
- C — Proposed Camera Direction — FIXED SURVEILLANCE CAMERA
- #-##
- C — 360°/MULTI-SENSOR FIXED SURVEILLANCE CAMERA OR FISHEYE LENS CAMERA
- Approximate view of lens
- Lens View Angle
- ##° #mm — C — 360°/MULTI-SENSOR FIXED SURVEILLANCE CAMERA OR FISHEYE LENS CAMERA
- Lens size
- C M — MICROPHONE WITH AUDIO LINKED TO CAMERA
- C CR — CARD READER LINKED TO CAMERA
- SYMBOL TAG — CR # — (#) = DIFFERENT TYPES OF CARD READERS: M = MULLION; W = WIRELESS (Proprietary); Wi = Wi-Fi (802.11); POE = POWER OVER ETHERNET
- SYMBOL TAG — KP # — (#) = DIFFERENT TYPES OF CARD READERS: TS = TOUCHSCREEN; PU = PUSH BUTTON
- TOP = DETAIL NUMBER; # / #### — DETAIL REFERENCE; BOTTOM = SHEET NUMBER
- NORTH ARROW
- SHEET NUMBER; # / #### — SECTION MARKER; DETAIL NUMBER
- DIRECTION OF ELEVATION; # / #### — ELEVATION MARKER; SHEET NUMBER; DETAIL NUMBER
- DIRECTION OF ELEVATION; SHEET NUMBER; # / #### — DIRECTION OF ELEVATION; DETAIL NUMBER
- BAR IS ONE INCH ON ORIGINAL DRAWING. IF NOT ONE INCH ON THIS DRAWING ADJUST SCALES ACCORDINGLY

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Hunters Glen Elementary School
685 Independence Blvd, Missouri City, TX 77489

SEAL

Bicsi — Brian C Porter — BICSI ID # 258657 — EXPIRES 10-31-27 — NCCD

07-18-25


MVA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY - TITLE SHEET

k-TN000

**DEMO KEYNOTES**

1. REMOVE, AND PROTECT DURING CONSTRUCTION, INSTALL IN EXISTING LOCATION AFTER NEW ACT GRID IS IN PLACE.
2. DEVICES IN ACT ARE TO BE REMOVED AND PROTECTED DURING CONSTRUCTION AND REINSTALLED IN THE SAME LOCATION AFTER THE NEW CEILING GRID IS IN PLACE. DECIVES INCLUDE: SPEAKERS, ACCESS POINTS AND INTRUSION MOTION DETECTORS.
3. EXISTING CARD READER, DOOR CONTACT, & REX (REQUEST TO EXIT) TO BE DEMOLISHED, REMOVE DEVICES AND PROTECT WIREING.




1 HUNTERS GLEN - DEMO PLAN
SCALE: 3/16" = 1'-0"

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Hunters Glen Elementary School
6855 Independence Blvd, Missouri City, TX 77489

SEAL

Bicsi
Brian C Porter
BICSI ID # 295857
EXPIRES 12-31-27

07-18-25



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Hunters Glen ES - DEMO

k-TN.001

## TECHNOLOGY KEYNOTES

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.




1 BACKGROUND 1 (HUNTERS GLEN)
SCALE: 1" = 20'-0"

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Hunters Glen Elementary School
6855 Independence Blvd, Missouri City, TX 77489

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 295857
EXPIRES 12-31-27
07-18-25


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Hunters Glen ES - OVERALL

k-TN.100




1 HUNTERS GLEN - KITCHEN PLAN
SCALE: 3/16" = 1'-0"

**TECHNOLOGY KEYNOTES**

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Hunters Glen Elementary School
685 Independence Blvd, Missouri City, TX 77489

SEAL




07-18-25


MWA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING
AND
PERMITTING
TECHNOLOGY - Hunters Glen
ES - KITCHEN


k-TN.101

**GENERAL NOTE**


1. FACE PLATE DETAIL FOR OUTLET CONFIGURATION PURPOSES ONLY. CONTRACTOR TO SELECT TYPE OF FACE PLATE TO MATCH CONNECTIVITY HARDWARE, FLOOR BOX AND/OR MODULAR FURNITURE OPENING.





1 DATA ROUGH-IN DETAILS
SCALE: NS





2 TYPICAL CABLING SLEEVE
SCALE: NTS





3 PANDUIT J-HOOK DETAIL
SCALE: NTS





4 LABELING & CABLING SCHEMES
SCALE: NTS





5 CABLE PATHWAY CROSS SECTION
SCALE: NTS




6 DROPPED CEILING MOUNTING DETAIL
SCALE: NS




7 I-JOIST MOUNTING DETAIL
SCALE: NS




8 BAR JOIST MOUNTING DETAIL
SCALE: NS

| CAMERA TYPE | MANUFACTURER | MODEL NUMBER | GENERAL DESCRIPTION |
|---|---|---|---|
| C1 | iPro | WV-S8574L | 4x4K (33MP) EXTERIOR MULTI-SENSOR - PARKING LOTS, STADIUM |
| C2 | iPro | WV-S8544L | 4x4MP (16MP) EXTERIOR MULTI-SENSOR - BUILDING PERIMETER |
| C3 | iPro | WV-S25500-V3LN | 5MP EXTERIOR VANDAL DOME |
| C4 | iPro | WV-S22500-V3L | 5MP INTERIOR VANDAL DOME - CORR., COMMON, SPED |
| C5 | iPro | WV-S4156A | 5MP 360 (FISHEYE) - STAIRWELLS |

9 CAMERA SCHEDULE
SCALE: NTS

| Symbol | Purpose | Size | Mount | Backbox | Notes |
|---|---|---|---|---|---|
| FP1 | Digital Signage/Menu Boards | +49" | Ceiling Pole | N/A | Data and Power Outlets on ceiling |

10 DISPLAY SCHEDULE
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Hunters Glen Elementary School
685 Independence Blvd, Missouri City, TX 77489

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256557
EXPIRES 12-31-27
RCDD

07-18-25



MVA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Hunters Glen ES - DETAILS


k-TN.500

GENERAL NOTES:


1. REFER TO SECURITY SCHEDULE AND WRITTEN SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
2. ALL MOUNTING DETAILS ARE REFERENCE FOR ALL FIXED DOME, 180°, 360°, PTZ, AND "BULLET/BOX" CAMERAS.





1 TYPICAL CAMERA INSTALLATION SECTION DETAIL
SCALE: NS




6 WALL MOUNTED CAMERA DETAIL
SCALE: NS




4 TILE BRIDGE DETAIL
SCALE: NS





5 CEILING MOUNTED CAMERA DETAIL
SCALE: NS


ACCESS CONROL DETAILS AND GENERAL NOTES:

1. CONDUIT ROUGH-IN IS A GUIDE FOR WHAT WILL BE REQUIRED FOR EACH DOOR. AS DOOR COMPONENTS CHANGE, EXACT CONDUIT LOCATION WILL ALSO NEED TO BE ADJUSTED.


2. PROTECT EXISTING-TO-REMAIN ACCESS CONTROL DEVICES AND CABLE THROUGHOUT RENOVATION WORK. IF CABLE AND/OR DEVICES ARE DAMAGED, SECURITY CONTRACTOR TO REPLACE WITH NEW.




1 ACCESS CONTROL - WIRING DETAIL - EXIT DEVICE W/ BUILT-IN REX
SCALE: NTS




2 ACCESS CONTROL - STEEL/HOLLOW METAL DOOR.
SCALE: NTS




KP PB LD

3 ROUGH-IN DETAILS: KP, PB, LD
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Hunters Glen Elementary School
6855 Independence Blvd, Missouri City, TX 77489

SEAL





07-18-25

MVA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING
AND
PERMITTING

TECHNOLOGY - Hunters Glen ES - SECURITY DETAILS

k-TN.600




6 CEILING MOUNT DISPLAY - A/V ROUGH-IN DETAIL
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

k

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Hunters Glen Elementary School
6855 Independence Blvd, Missouri City, TX 77489

SEAL




07-18-25

MWA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY - Hunters Glen ES - AV DETAILS

k-TN.700

# FBISD BP013 KITCHEN RENOVATIONS ES

LANTERN LANE ELEMENTARY SCHOOL
3323 MISSION VALEY , MISSOURI CITY, TX 77459

FORT BEND INDEPENDENT SCHOOL DISTRICT BOND 2023

| Sheet List Table | |
|---|---|
| Sheet Number | Sheet Title |
| School: I-Lantern Lane | |
| I_A0.00 | COVER AND INDEX |
| I-A.101 | Site Plan |
| I-A.201 | Overall Floor Plan |
| I-A.301 | Kitchen Plan |
| I-A.501 | Finish Floor Plan |
| I-TN-000 | TECHNOLOGY - INDEX SHEET |
| I-TN-100 | TECHNOLOGY - OVERALL |
| I-TN-101 | TECHNOLOGY - KITCHEN |
| I-TN-500 | TECHNOLOGY - DETAILS |
| I-TN-600 | TECHNOLOGY - SECURITY DETAILS |

REGISTERED ARCHITECT MICHAEL A. MAGNER 22651 STATE OF TEXAS
18 JULY 2025

ISSUED FOR PERMIT AND BIDDING - JULY 18, 2025

## FORT BEND INDEPENDENT SCHOOL DISTRICT

## ADMINISTRATION

| | |
|---|---|
| DR. MARCELL SMITH | SUPERINTENDENT OF FBISD |
| DR. ANDRIA SCHUR, Ed.D. | CHIEF OF SCHOOLS |

## BOARD OF TRUSTEES

| | |
|---|---|
| KRISTIN K. TASSIN | PRESIDENT |
| RICK GARCIA | VICE PRESIDENT |
| DAVID HAMILTON | SECRETARY |
| ANGIE HANAN | BOARD MEMBER |
| ADAM SCHOOF | BOARD MEMBER |
| DR. SHIRLEY ROSE-GILLIAM | BOARD MEMBER |
| SONYA JONES | BOARD MEMBER |

## PROJECT DESIGN TEAM

PROGRAM MANAGEMENT
FBISD 2023 Bond Team
2323 Texas Parkway
Missouri City, TX 77489
Phone Number: 281-327-5481

ARCHITECT
MWA Architects
11767 Katy Freeway, Suite 430
Houston, Texas 77079
Phone Number: 713-782-8188

FOOD SERVICE
Food Design Professionals
26215 Oak Ridge Drive
The Woodlands, Texas 77380
Phone Number: 281-350-2323


MEP ENGINEERS
Stanton Engineering Group
1300 W. Sam Houston Pkwy South, Suite 121
Houston, Texas 77042
Phone Number: 713-300-9292

STRUCTURAL ENGINEER
Stanley Spurling & Hamilton
3301 Edloe Street, Suite 200
Houston, Texas 77027
Phone Number: 713-776-9433

# INDEX OF DRAWINGS

Sheet List Table

| Sheet Number | Sheet Title |
|---|---|
| I–A.000 | COVER SHEET |
| I–A.101 | SITE PLAN |
| I–A.201 | FLOOR PLAN |
| I–A.301 | KITCHEN AREA PLAN |
| I–A.501 | FINISH FLOOR PLAN |




1 SITE PLAN
SCALE: 1" = 30'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

I

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
LANTERN LANE ELEMENTARY SCHOOL
3323 MISSION VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL
REGISTERED ARCHITECT
MICHAEL A. WEBER
23651
STATE OF TEXAS
7/15/2025


MWA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

SITE PLAN

I-A.101

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\L-Lantern Lane ES\I-A.101 SITE PLAN.dwg Jul 23, 2025 - 2:20pm

2015 INTERNATIONAL EXISTING BUILDING CODE

301.1.1 PRESCRIPTIVE COMPLIANCE METHOD. REPAIRS, ALTERATIONS, ADDITIONS AND CHANGES OF OCCUPANCY COMPLYING WITH CHAPTER FOUR OF THIS CODE IN BUILDINGS COMPLYING WITH THE INTERNATIONAL FIRE CODE SHALL BE CONSIDERED IN COMPLIANCE WITH THE PROVISIONS OF THIS CODE.

401.2.1 EXISTING MATERIALS. MATERIALS ALREADY IN USE IN A BUILDING IN COMPLIANCE WITH REQUIREMENTS OR APPROVALS IN EFFECT AT THE TIME OF THEIR ERECTION OR INSTALLATION SHALL BE PERMITTED TO REMAIN IN USE UNLESS DETERMINED BY THE BUILDING OFFICIAL TO BE UNSAFE PER SECTION 115.

401.2.2 NEW AND REPLACEMENT MATERIALS. EXCEPT AS OTHERWISE REQUIRED OR PERMITTED BY THIS CODE, MATERIALS PERMITTED BY THE APPLICABLE CODE FOR NEW CONSTRUCTION SHALL BE USED. LIKE MATERIALS SHALL BE PERMITTED FOR REPAIRS AND ALTERATIONS, PROVIDED NO HAZARD TO LIFE, HEALTH OR PROPERTY IS CREATED. HAZARDOUS MATERIALS SHALL NOT BE USED WHERE THE CODE FOR NEW CONSTRUCTION WOULD NOT PERMIT THEIR USE IN BUILDINGS OF SIMILAR OCCUPANCY, PURPOSE AND LOCATION.

Area increase due to frontage and fire sprinkler protection TYPE IIIB

$A_a = [A_t + (NS \times I_f)] \times Sa$

ALLOWABLE BUILDING AREA ONE STORY = 58,000 + (14,500 x 1.5) x 1 = 79,750 SF

ONE SINGLE STORY 74,867 SF.

## Project Information

PROJECT: LANTERN LANE ELEMENTARY SCHOOL
LOCATION: 3323 MISSION VALLEY DRIVE
MISSOURI CITY, TX 77459
SCOPE OF WORK: ADDITIONAL KITCHEN STORAGE FOR CEP.
SECURITY CAMERAS OVER SERVING LINES.

## Missouri City Adopted Building Code

2015 INTERNATIONAL EXISTING BUILDING CODE
2015 INTERNATIONAL BUILDING CODE
2015 INTERNATIONAL FUEL GAS CODE
2015 INTERNATIONAL MECHANICAL CODE
2015 INTERNATIONAL PLUMBING CODE
2014 NATIONAL ELECTRICAL CODE
2015 INTERNATIONAL ENERGY CONSERVATION CODE

## Chapter 3 - Use and Occupancy Classification

GROUP E (EDUCATIONAL - IBC 2015 SECTION 305)
EXISTING FULLY SPRINKLERED BUILDING
REVISIONS/UPDATES TO FIRE SPRINKLER, KITCHEN HOOD SUPPRESSION, FIRE ALARM AND CHEMICAL STORAGE WILL REQUIRE AN EVALUATION AND APPROVAL FROM MISSOURI CITY FIRE DEPARTMENT

## Chapter 5 - General Building Heights and Area

ALLOWABLE BUILDING HEIGHT:
TWO STORIES W/ 55 FT MAX. HEIGHT FOR GROUP E
(AS ALLOWED BY TABLE 503)

EXISTING BUILDING HEIGHT PROVIDED:
HEIGHT TO ROOF: 15'-0"

INCIDENTAL USE SEPARATION:
SEPARATIONS REQUIRED: INCIDENTAL USE AREAS, AS PER TABLE 509, LAUNDRY ROOMS OVER 100 S.F. ARE REQUIRED TO BE ONE HOUR RATED OR HAVE AUTOMATIC FIRE EXTINGUISHING SYSTEM.

INCIDENTAL USE ROOM AREAS PROVIDED WITH EXISTING AUTOMATIC SPRINKLER SYSTEM.

TOTAL EXISTING BUILDING AREA IS 74,867 SF.

## Chapter 6 - Construction Type Fire Resistance Ratings

EXISTING CONSTRUCTION: TYPE IIB

TABLES 601 AND 602

| BUILDING ELEMENTS | REQUIRED (FOR TYPE IIB) | PROVIDED |
|---|---|---|
| STRUCTURAL FRAME (TABLE 601) | NO RATING | NO RATING |
| EXTERIOR BEARING WALLS (TABLE 601) | NO RATING | NO RATING |
| INTERIOR BEARING WALLS (TABLE 601) | NO RATING | NO RATING |
| EXTERIOR NON-BEARING WALLS (TABLE 602) | NO RATING | NO RATING (WALLS GREATER THAN 30' FROM PROPERTY LINE) |
| INTERIOR NON-BEARING WALLS (TABLE 601) | NO RATING | NO RATING |
| FLOOR CONSTRUCTION (TABLE 601) | NO RATING | NO RATING |
| ROOF CONSTRUCTION (TABLE 601) | NO RATING | NO RATING |

## Chapter 9 - Fire Protection Systems


AUTOMATIC SPRINKLER SYSTEM: EXISTING SPRINKLER SYSTEM PROVIDED THROUGHOUT.

## Chapter 29 - Plumbing

Fixture Count per Table 2902.1
Occupant Load Basis:

12 Occupants

| | Total Fixtures REQUIRED | Total Fixtures PROVIDED |
|---|---|---|
| Unisex: | | |
| W.C. | 1 per 50 | 1 |
| lavatories | 1 per 50 | 1 |
| Drinking Fountains | 1 per 100 | 2 |




1 OVERALL FLOOR PLAN
SCALE: 1/16" = 1'-0"

# 2 CODE ANALYSIS

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

I

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
LANTERN LANE ELEMENTARY SCHOOL
3323 MISSION VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL
REGISTERED ARCHITECT
MICHAEL K. WILLIAMS
#22651
STATE OF TEXAS
7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

OVERALL FLOOR PLAN

I-A.201

F:\2022\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\L-Lantern Lane ES\I-A.201 FLOOR PLAN.dwg Jul 23, 2025 - 2:20pm

## FLOOR PLAN - GENERAL NOTES

1. REFER TO SHEET FOR GENERAL NOTES. GENERAL NOTES APPLY TO ALL SCHOOL KITCHENS.
2. REFER TO SHEET FOR PARTITION TYPES.
3. EXIXSTING EXPOSED CONDUITS AND DATA CABLING IN WIREMOLD TO BE ROUTED INSIDE WALLS (EXCEPT AT WAREWASH AREA BELOW TABLE HEIGHT AND DRY STORAGE ROOMS). PATCH AND REPAIR AS REQUIRED TO ACHIEVE SMOOTH CLEAN WALL SURFACE.

## PARTITION LEGEND

EXISTING CMU PARTITION

NEW CMU SCHEDULED PARTITION

## FLOOR PLAN - KEYED NOTES

(NOT ALL NOTES USED ON EACH SHEET)

01 PROVIDE NEW MOP SINK UTILITY SHELF
RE: PLUMBING FOR MOP SINK
RE: SPEC 10 28 00 FOR UTILITY SHELF

02 REMOVE, STORE & REPLACE WALL MOUNTED FIRE EXTINGUISHER

03 PROVIDE NEW WALL MOUNTED FIRE EXTINGUISHER
RE: SPEC SECTIONS 10 44 13

04 PROVIDE NEW LOCKERS
RE: SPEC 10 51 13.

05 PROVIDE WASHER AND DRYER
RE: SPEC 11 45 20

06 REMOVE, PROTECT & REINSTALL WALL MOUNTED CLOCK.

07 PROVIDE CONDENSING UNIT
FOR WALK-IN COOLER/FREEZER
RE: MECHANICAL AND SPEC 11 40 00


08 PROVIDE POWER AND DATA FOR MENU BOARD.
RE: ELECTRICAL, TECHNOLOGY DRAWINGS & FOOD SERVICE.

09 PROVIDE P-LAM SHELVING.
REFER TO DETAIL FOR BRACKET SUPPORT

10 FURNITURE & NON FOOD SVE EQUIPMENT RETURN TO OWNER FO STORAGE

11 INSPECT & SREVICE TOLLING COUNTER DOORS. RETURN TO LIKE NEW CONDITION.

# 2 FLOOR PLAN NOTES




## 1 KITCHEN AREA PLAN

SCALE: 1/4" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

I

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
LANTERN LANE ELEMENTARY SCHOOL
3323 MISSION VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL

REGISTERED ARCHITECT
MICHAEL W. WILLIAMS
22651
STATE OF TEXAS

7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

KITCHEN AREA PLAN

I-A.301

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\L-Lantern Lane ES\I-A.301 KITCHEN AREA PLAN.dwg Jul 23, 2025 - 2:20pm

## PAINT COLOR SCHEDULE

UNLESS OTHERWISE INDICATED FIELD COLOR IS PT-1 (SW 7014 EIDER WHITE)

SW 7014 EIDER WHITE (EPOXY PAINT)


## WALL TILE

CERAMIC WALL TILE (WT-1)
REFER TO TILE PATTERN AT SERVING AND RESTROOM
FIELD WALL TILE: DALTILE RITTENHOUSE SQUARE K175 BISCUIT (3X6)

A


PROVIDE ROOM SIGN TO REPLACE EXISTING. SEE LAYOUT FOR TYPE A OR TYPE B SIGN LOCATIONS.

## 2 FINISH FLOOR LEGEND




TYPE A


ROOM SIGNAGE - FIXED NAMES




TYPE B


KITCHEN RESTROOM SIGNAGE

## 3 ROOM SIGNAGE




WALL TILE PATTERN - RESTROOM

## 4 WALL TILE PATTERN




## 1 FINISH FLOOR PLAN

SCALE: 1/4" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

I

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT

LANTERN LANE ELEMENTARY SCHOOL
3323 MISSION VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL

REGISTERED ARCHITECT KEITH A. WERNER 22651 STATE OF TEXAS

7/15/2025


MWA ARCHITECTS

ARCHITECTS AND PLANNING CONSULTANTS

11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

FINISH FLOOR PLAN

I-A.501

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\I-Lantern Lane ES\I-A 501 FINISH FLOOR PLAN.dwg Jul 23, 2025 - 2:20pm

## AUDIO/VISUAL MULTIMEDIA LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| A## V## | WALL AV ROUGH-IN DETAIL |
| A## V## | CEILING AV ROUGH-IN DETAIL |
| A## V## | FLOOR AV ROUGH-IN DETAIL |
| IWB IWB | INTERACTIVE WHITE BOARD - WALL - CEILING |
| PJ PJ | MULTIMEDIA PROJECTOR |
| FP# FP# | MULTIMEDIA FLAT PANEL DISPLAY |
| S S | LOUDSPEAKER, WALL MOUNTED AND CEILING MOUNTED RESPECTIVELY - # INDICATES TYPE |
| CP# | CONTROL PANEL |
| TP# | TOUCH PANEL |
| M | MICROPHONE, CEILING MOUNTED - # INDICATES TYPE |
| VC | VOLUME CONTROL |
| WB | WALL BOX ENCLOSURE |
| D1 A1 | D1 = DIGITAL SINGLE SIDED CLOCK / A1 = ANALOG SINGLE SIDED CLOCK |
| D2 A2 | D2 = DIGITAL DOUBLE SIDED CLOCK / A2 = ANALOG DOUBLE SIDED CLOCK |
| ENC | CEILING AV ENCLOSURE |
| C C | PRESENTATION CAMERA - CEILING - WALL MOUNTED |

## PREMISE SECURITY LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| CR | CARD READER |
| CR M | CARD READER MULLION |
| KP | INTRUSION DETECTION KEYPAD |
| IC | INTERCOM (1 DATA CABLE) |
| IC MS | INTERCOM MASTER STATION (1 DATA CABLE) |
| PB | PANIC/DURESS BUTTON |
| LD | LOCK DOWN BUTTON |
| MD | MOTION DETECTOR |
| GB | ACCOUSTICAL GLASS BREAK SENSOR |
| BM | BIOMETRIC READER |
| RX | REQUEST TO EXIT - SURFACE PIR |
| KS | KEY SWITCH |
| LA | LOCAL ALARM SOUNDER |
| RG | RED/GREEN INDICATOR LIGHT |
| DB | DOORBELL |
| DH | MAGNETIC DOOR HOLD |
| DR | DOOR RELEASE |
| RX | REQUEST TO EXIT - INTEGRAL TO DOOR HARDWARE |
| DC | DOOR CONTACT / MONITOR |
| ES EL EH | ELECTRIFIED STRIKE - ELECTRIFIED LATCH - ELECTRIFIED HARDWARE (REFER TO SCHEDULES) |
| C C | STANDARD IP SURVEILLANCE CAMERA, (1) CABLE |
| C C C | 180° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° FISHEYE LENS CAMERA |
| IR | IR ILLUMINATOR |

## STRUCTURED CABLING LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF DATA CABLE(S)/JACK(S) |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) |
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| W | WALL MOUNT PHONE (1 CABLE/JACK) |
| W | WALL MOUNT PHONE, SURFACE MOUNT (1 CABLE/JACK) |
| # | FLOOR MOUNTED OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| #/# | FLOOR MOUNTED OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| # | CEILING MOUNTED DATA OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) |
| AP# | CEILING MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| AP# | WALL MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| | CABLING SLEEVE(S) |
| | TYPICAL LADDER RACK |
| | TYPICAL CABLE TRAY, BASKET STYLE |

## GENERAL ANNOTATION LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| MER | MAIN EQUIPMENT ROOM |
| TR | TELECOMMUNICATION ROOM |
| MDF | MAIN DISTRIBUTION FRAME |
| IDF | INTERMEDIATE DISTRIBUTION FRAME |
| ETR | EXISTING TO REMAIN |
| PBO | PROVIDED BY OTHERS |
| AFF | ABOVE FINISHED FLOOR |
| AFG | ABOVE FINISHED GRADE |
| AC | ABOVE COUNTER |
| EC | ELECTRICAL CONTRACTOR |
| PSC | PREMISE SECURITY CONTRACTOR |
| SCC | STRUCTURAL CABLING CONTRACTOR |
| AVC | AV/MULTIMEDIA CONTRACTOR |
| UNO | UNLESS NOTED OTHERWISE |
| ACS | ACCESS CONTROL SYSTEM |
| VSS | VIDEO SURVEILLANCE SYSTEM |

## TECHNOLOGY - GENERAL NOTES

1. EACH KEYNOTE MAY NOT BE UTILIZED ON EVERY SHEET.
2. ALL CONDUIT MEASUREMENTS REFER TO STANDARD CONDUIT TRADE SIZES.
3. ALL CABLES SHALL BE CONCEALED.
4. EACH CONTRACTOR SHALL PROVIDE AND INSTALL ALL NECESSARY SLEEVES, WHETHER OR NOT SPECIFICALLY NOTED ON PROJECT DRAWINGS. ALL SLEEVES SHALL BE 2" UNLESS NOTED OTHERWISE ON THE DRAWINGS. CABLE FILL PERCENTAGE SHALL COMPLY WITH NEC.
5. DEVICE LOCATIONS ARE APPROXIMATE. CONTRACTOR SHALL REVIEW CONDITIONS AND COORDINATE WITH OTHER TRADES AS NECESSARY FOR EXACT PLACEMENT.

## TECHNOLOGY SYMBOLS LEGEND

NOT ALL SYMBOLS ARE USED

- AV WALL ROUGH-IN WITH DATA
- KEYNOTE
- Proposed Camera Direction SURVEILLANCE CAMERA
- Camera Schedule Number (Floor #-Camera #) Camera (N)ew, (E)xisting Rough-in, (D)emo
- Proposed Camera Direction PTZ CAMERA PTZ
- Proposed Camera Direction FIXED SURVEILLANCE CAMERA
- 360°/MULTI-SENSOR FIXED SURVEILLANCE CAMERA OR FISHEYE LENS CAMERA
- Approximate view of lens
- Lens View Angle
- 360°/MULTI-SENSOR FIXED SURVEILLANCE CAMERA OR FISHEYE LENS CAMERA
- Lens size
- MICROPHONE WITH AUDIO LINKED TO CAMERA
- CARD READER LINKED TO CAMERA
- SYMBOL TAG — (#) = DIFFERENT TYPES OF CARD READERS: M = MULLION; W = WIRELESS (Proprietary); Wi = Wi-Fi (802.11); POE = POWER OVER ETHERNET
- SYMBOL TAG — (#) = DIFFERENT TYPES OF CARD READERS: TS = TOUCHSCREEN; PU = PUSH BUTTON
- TOP = DETAIL NUMBER; DETAIL REFERENCE; BOTTOM = SHEET NUMBER
- NORTH ARROW
- SHEET NUMBER; SECTION MARKER; DETAIL NUMBER
- DIRECTION OF ELEVATION; ELEVATION MARKER; SHEET NUMBER; DETAIL NUMBER
- DIRECTION OF ELEVATION; SHEET NUMBER; DIRECTION OF ELEVATION; DETAIL NUMBER
- BAR IS ONE INCH ON ORIGINAL DRAWING. IF NOT ONE INCH ON THIS DRAWING ADJUST SCALES ACCORDINGLY

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

I

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Lanterns Lane Elementary School
3323 Mission Valley Dr, Missouri City, TX 77459

SEAL

BICSI Registered Communications Distribution Designer
Bicsi
Brian C Porter
BICSI ID # 258557
EXPIRES 10-31-27
RCDD

07-18-25

MVA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY - TITLE SHEET

I-TN000

## TECHNOLOGY KEYNOTES

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.




1 LANTERN LANE (OVERALL)
SCALE: 1" = 20'-0"

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

I

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Lanterns Lane Elementary School
3323 Mission Valley Dr, Missouri City, TX 77459

SEAL

ASSOCIATED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 258657
EXPIRES 12-31-27

07-18-25


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Lantern Lane ES - OVERALL

I-TN.100

## TECHNOLOGY KEYNOTES

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.




1 LANTERN LANE - KITCHEN PLAN
SCALE: 3/16" = 1'-0"



TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

I

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Lanterns Lane Elementary School
3323 Mission Valley Dr, Missouri City, TX 77459

SEAL

ASSISTIVE COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 258657
EXPIRES 10-31-27
ecpd
07-18-25


ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Lantern Lane ES - KITCHEN


I-TN.101

**GENERAL NOTE**


1. FACE PLATE DETAIL FOR OUTLET CONFIGURATION PURPOSES ONLY. CONTRACTOR TO SELECT TYPE OF FACE PLATE TO MATCH CONNECTIVITY HARDWARE, FLOOR BOX AND/OR MODULAR FURNITURE OPENING.





1 DATA ROUGH-IN DETAILS
SCALE: NS





2 TYPICAL CABLING SLEEVE
SCALE: NTS





3 PANDUIT J-HOOK DETAIL
SCALE: NTS





4 LABELING & CABLING SCHEMES
SCALE: NTS





5 CABLE PATHWAY CROSS SECTION
SCALE: NTS




6 DROPPED CEILING MOUNTING DETAIL
SCALE: NS




7 I-JOIST MOUNTING DETAIL
SCALE: NS




8 BAR JOIST MOUNTING DETAIL
SCALE: NS

| CAMERA TYPE | MANUFACTURER | MODEL NUMBER | GENERAL DESCRIPTION |
|---|---|---|---|
| C1 | iPro | WV-S8574L | 4x4K (33MP) EXTERIOR MULTI-SENSOR - PARKING LOTS, STADIUM |
| C2 | iPro | WV-S8544L | 4x4MP (16MP) EXTERIOR MULTI-SENSOR - BUILDING PERIMETER |
| C3 | iPro | WV-S25500-V3LN | 5MP EXTERIOR VANDAL DOME |
| C4 | iPro | WV-S22500-V3L | 5MP INTERIOR VANDAL DOME - CORR., COMMON, SPED |
| C5 | iPro | WV-S4156A | 5MP 360 (FISHEYE) - STAIRWELLS |

9 CAMERA SCHEDULE
SCALE: NTS

| Symbol | Purpose | Size | Mount | Backbox | Notes |
|---|---|---|---|---|---|
| FP1 | Digital Signage/Menu Boards | +49" | Ceiling Pole | N/A | Data and Power Outlets on ceiling |

10 DISPLAY SCHEDULE
SCALE: NTS

TRUENORTH
A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

I

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Lantern Lane Elementary School
3323 Mission Valley Dr, Missouri City, TX 77459

SEAL




07-18-25



MVA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Lantern Lane ES - DETAILS


I-TN.500

GENERAL NOTES:


1. REFER TO SECURITY SCHEDULE AND WRITTEN SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
2. ALL MOUNTING DETAILS ARE REFERENCE FOR ALL FIXED DOME, 180°, 360°, PTZ, AND "BULLET/BOX" CAMERAS.





1 TYPICAL CAMERA INSTALLATION SECTION DETAIL
SCALE: NS




6 WALL MOUNTED CAMERA DETAIL
SCALE: NS




4 TILE BRIDGE DETAIL
SCALE: NS





5 CEILING MOUNTED CAMERA DETAIL
SCALE: NS


ACCESS CONROL DETAILS AND GENERAL NOTES:

1. CONDUIT ROUGH-IN IS A GUIDE FOR WHAT WILL BE REQUIRED FOR EACH DOOR. AS DOOR COMPONENTS CHANGE, EXACT CONDUIT LOCATION WILL ALSO NEED TO BE ADJUSTED.


2. PROTECT EXISTING-TO-REMAIN ACCESS CONTROL DEVICES AND CABLE THROUGHOUT RENOVATION WORK. IF CABLE AND/OR DEVICES ARE DAMAGED, SECURITY CONTRACTOR TO REPLACE WITH NEW.




1 ACCESS CONTROL - WIRING DETAIL - EXIT DEVICE W/ BUILT-IN REX
SCALE: NTS




2 ACCESS CONTROL - STEEL/HOLLOW METAL DOOR.
SCALE: NTS




KP PB LD

3 ROUGH-IN DETAILS: KP, PB, LD
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

I

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Lanterns Lane Elementary School
3323 Mission Valley Dr, Missouri City, TX 77459

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256657
EXPIRES 12-31-27
RCDD

07-18-25


MVA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING
AND
PERMITTING

TECHNOLOGY - Lantern Lane ES - SECURITY DETAILS

I-TN.600

# FBISD BP013 KITCHEN RENOVATIONS ES

## PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DR, MISSOURI CITY, TX 77459

FORT BEND INDEPENDENT SCHOOL DISTRICT 2023 BOND

## FORT BEND INDEPENDENT SCHOOL DISTRICT

### ADMINISTRATION

| | |
|---|---|
| DR. MARCELL SMITH | SUPERINTENDENT OF FBISD |
| DR. ANDRIA SCHUR, Ed.D. | CHIEF OF SCHOOLS |

### BOARD OF TRUSTEES

| | |
|---|---|
| KRISTIN K. TASSIN | PRESIDENT |
| RICK GARCIA | VICE PRESIDENT |
| DAVID HAMILTON | SECRETARY |
| ANGIE HANAN | BOARD MEMBER |
| ADAM SCHOOF | BOARD MEMBER |
| DR. SHIRLEY ROSE-GILLIAM | BOARD MEMBER |
| SONYA JONES | BOARD MEMBER |

### PROJECT DESIGN TEAM


**PROGRAM MANAGEMENT**
FBISD 2023 Bond Team
2323 Texas Parkway
Missouri City, TX 77489
Phone Number: 281-327-5481

**ARCHITECT**
MWA Architects
11767 Katy Freeway, Suite 430
Houston, Texas 77079
Phone Number: 713-782-8188

**FOOD SERVICE**
Food Design Professionals
26215 Oak Ridge Drive
The Woodlands, Texas 77380
Phone Number: 281-350-2323

**MEP ENGINEERS**
Stanton Engineering Group
1300 W. Sam Houston Pkwy South, Suite 121
Houston, Texas 77042
Phone Number: 713-300-9292

**STRUCTURAL ENGINEER**
Stanley Spurling & Hamilton
3301 Edloe Street, Suite 200
Houston, Texas 77027
Phone Number: 713-776-9433


| Sheet List Table | |
|---|---|
| Sheet Number | Sheet Title |
| School: o-Palmer ES | |
| o-A.000 | COVER AND INDEX |
| o-A00-01 | GENERAL NOTES AND ABBREVIATIONS |
| o-D.101 | DEMO PLAN |
| o-D.101-2 | DEMO PLAN PHOTOS |
| o-ED.100 | ELECTRICAL DEMOLITION AND TEMP PLANS |
| o-PD1.01 | PLUMBING DEMOLITION FLOOR PLAN |
| o-TD201 | TECHNOLOGY DEMOLITION FLOOR PLAN |
| o-A.101 | SITE PLAN |
| o-A.200 | SLAB DIMENSION CONTROL PLAN |
| o-A.201 | FLOOR PLAN |
| o-A.301 | KITCHEN PLAN |
| o-A.302 | TEMPORARY KITCHEN LAYOUT |
| o-A.401 | REFLECTED CEILING PLAN |
| o-A.501 | FINISH FLOOR PLAN |
| o-A.502 | PARTITION SCHEDULE |
| o-S1 | KITCHEN PLAN |
| o-S2 | SECTIONS AND TYPICAL DETAILS |
| o-QF1 | FS GENERAL COORDINATION NOTES |
| o-QF1.0 | FS EQUIPMENT PLAN |
| o-QF1.1 | FS FACILITY MODEL |
| o-QF1.2 | FS EQUIPMENT MODEL |
| o-QF1.3 | FS SPECIAL CONDITIONS & MECHANICAL PLAN |
| o-QF1.4 | FS PLUMBING PLAN |
| o-QF1.5 | FS ELECTRICAL PLAN |
| o-QF1.6 | FS CONDENSING UNITS |
| o-QF1.7 | FS WALK-INS |
| o-QF2.0 | FS TEMPORARY SERVING |
| o-M1.01 | MECHANICAL PLANS |
| E.000 | ELECTRICAL AND FIRE ALARM SCHEDULES |
| E.001 | ELECTRICAL AND FIRE ALARM NOTES |
| E.010 | ELECTRICAL DEVICE DETAILS |
| E.011 | ELECTRICAL DETAILS |
| E.012 | ELECTRICAL DETAILS |
| E.013 | ELECTRICAL KITCHEN DETAILS |
| E.060 | LIGHTING SCHEDULES |
| o-E.100 | LIGHTING FLOOR PLAN |
| o-E.200 | ELECTRICAL FLOOR PLANS |
| o-E.300 | FIRE ALARM FLOOR PLANS |
| o-E.400 | ELECTRICAL SCHEMATIC |
| o-P1.01 | PLUMBING FLOOR PLAN |
| o-P1.02 | PLUMBING TEMPORARY KITCHEN PLAN |
| o-T000 | TECHNOLOGY SYMBOLS & LEGEND |
| o-T200 | TECHNOLOGY COMPOSITE FLOOR PLAN |
| o-T201 | TECHNOLOGY NEW_RENOVATION KITCHEN PLAN |
| o-T202 | TECHNOLOGY TEMPORARY KITCHEN PLAN |
| o-T300 | TECHNOLOGY ENLARGED VIEWS |
| o-T400 | TECHNOLOGY TYPICAL DETAILS |
| o-T401 | TECHNOLOGY TYPICAL DETAILS |
| o-T500 | TECHNOLOGY TYPICAL DETAILS |
| o-TN-000 | TECHNOLOGY - INDEX SHEET |
| o-TN-001 | TECHNOLOGY - DEMO |
| o-TN-100 | TECHNOLOGY - OVERALL |
| o-TN-101 | TECHNOLOGY - KITCHEN |
| o-TN-500 | TECHNOLOGY - DETAILS |
| o-TN-600 | TTECHNOLOGY - SECURITY DETAILS |
| o-TN-700 | TECHNOLOGY - AV DETAILS |

REGISTERED ARCHITECT MICHAEL A. MAGNER 22651 STATE OF TEXAS
18 JULY 2025

ISSUED FOR PERMIT AND BIDDING - JULY 18, 2025

0

PART 1 - GENERAL

1.1 GENERAL DEMOLITION NOTES

A. VERIFY EXISTING SITE AND BUILDING CONDITIONS IN FIELD PRIOR TO BIDDING. NOTIFY ARCHITECT OF ANY DISCREPANCIES PRIOR TO BIDDING.

B. CONTRACTOR SHALL COORDINATE WITH OWNER THE SALVAGE OF ITEMS, FURNITURE AND EQUIPMENT INDICATED TO BE REMOVED.

C. CLAIMS FOR ADDITIONAL COST OR TIME DUE TO EXISTING CONDITIONS THAT COULD HAVE BEEN REASONABLY ANTICIPATED DURING A SITE VISIT BY THE CONTRACTOR PRIOR TO BIDDING WILL NOT BE APPROVED.

D. PROTECT EXISTING FINISHES SHOWN TO REMAIN DURING CONSTRUCTION TO PREVENT DAMAGE. REPAIR OR REPLACE DAMAGED MATERIALS AND FINISHES TO MATCH EXISTING AT NO ADDITIONAL COST TO FORT BEND ISD (OWNER).

E. EXISTING AREAS REQUIRING MINOR DEMOLITION OR REPAIR FOR EXECUTION OF WORK SHALL BE REPAIRED TO MATCH EXISTING ADJACENT MATERIALS, UNLESS NOTED OTHERWISE.

F. DO NOT DAMAGE CASEWORK AND EQUIPMENT NOT DESIGNATED TO BE REMOVED OR RELOCATED.EXISTING CASEWORK SHALL REMAIN THE PROPERTY OF THE OWNER.

G. CONTRACTOR TO VERIFY LOCATION OF ELEC. SWITCHES, OUTLETS, GRILLES, CLEAN-OUTS, COVER PLATES, ACCESS DOORS, AND OTHER EQUIPMENT AND DEVICES THAT MAY CONFLICT WITH THE RENOVATION AND NEW CONSTRUCTION OF WALLS, FLOORS, AND CEILINGS PRIOR TO COMMENCEMENT OF WORK. CONTRACTOR SHALL LIKEWISE CONFIRM THAT ELECTRICAL CONDUIT ROUTING SHALL BE CONCEALED WITHIN WALLS. NOTIFY ARCHITECT IF WALL THICKNESS WILL NOT ALLOW FOR CONCEALMENT.

H. REMOVE ANY EXISTING CORNER GUARDS IN THE KITCHEN AREA.

I. PRIOR TO EXECUTION OF DEMOLITION WORK, SCHEDULE A WALK-THROUGH WITH OWNER AND ARCHITECT TO CONFIRM SCOPE OF WORK AND TO REVIEW EXISTING CONDITIONS.

J. EXISTING FLOOR FINISHES AND ACOUSTIC CEILING TILE TO BE REMOVED THROUGHOUT.

K. REFER TO MEP DRAWINGS FOR DEMOLITION AND ALTERATION OF UTILITIES.

L. AT ALL EXISTING WALLS REQUIRING DEMOLITION TO INSTALL NEW PIPING BEHIND SINKS, CUT AND PATCH WALLS AS REQUIRED TO MATCH ADJACENT SURFACE.

M. CLEAN AND PREPARE SUBFLOOR FOR INSTALLATION OF NEW FLOOR FINISH.

N. DEMOLITION ACTIVITIES SHALL BE PERFORMED AS TO PRODUCE MINIMAL DISTURBANCE TO EXISTING FACILITY OCCUPANTS. MINIMIZE EXCESSIVE AND PROLONGED NOISE LEVELS AND DUST.

O. ASBESTOS-CONTAINING MATERIALS. REFER TO SPECIFICATION 02 26 23 FOR ASBESTOS INFORMATION APPLICABLE TO KITCHEN AREAS. FORT BEND ISD HAS RETAINED A SEPARATE ENVIRONMENTAL CONSULTANT FOR THE REMOVAL OF ASBESTOS. GC TO COORDINATE WITH ENVIRONMENTAL CONSULTANT TO CARRY OUT ASBESTOS ABATEMENT FOR ALL AFFECTED KITCHEN AREAS.

1.2 FLOOR PLAN GENERAL NOTES

A. FIELD VERIFY EXISTING CONDITIONS PRIOR TO GENERATING SHOP DRAWINGS AND FABRICATION OF EQUIPMENT.

B. FLOOR FINISH CHANGES SHALL OCCUR AT THE CENTERLINE OF DOORS UNLESS NOTED OTHERWISE. FLOOR FINISH CHANGES SHALL HAVE THRESHOLDS OR REDUCERS STRIPS.

C. DOORS THAT ARE TO BE REPLACED AND INSTALLED IN EXISTING FRAMES SHALL BE MACHINED FOR HARDWARE DIMENSIONS AT EXISTING FRAMES, CONTRACTOR SHALL FIELD VERIFY FRAME CONDITIONS AND DIMENSIONS.

D. CONTRACTOR TO PROVIDE SHEET METAL REINFORCING STRAP AS REQUIRED FOR MOUNTING OF ALL GRAB BARS, CABINETS, MIRRORS, SHELVING, ETC.

E. SAW CUT AND REMOVE EXISTING SLAB AND FLOOR FINISHES AS REQUIRED TO INSTALL NEW PLUMBING LINES, FLOOR DRAINS, PLUMBING FIXTURES, OR ELECTRICAL ITEMS. SPLICE NEW REINFORCING BARS DOWELED INTO EXISTING CONCRETE, AND PROVIDE NEW VAPOR RETARDER AND WATERSTOPS, AND PATCH W/ 3000 PSI CONCRETE AFTER INSTALLATION OF UTILITIES AND FIXTURES. PREPARE CONCRETE TO RECEIVE NEW FINISH.

F. COORDINATE HOUSEKEEPING PAD DIMENSIONS AND LOCATIONS WITH EQUIPMENT TO BE INSTALLED. HOUSEKEEPING PADS SHALL BE A MIN. OF 4" THICK REINF. W/ #3 BARS AT 15" O.C. BOTH WAYS. PROVIDE 1" BY 45-DEGREE CHAMFERED EDGES.

1.3 COMPLETE PERFORMANCE

L. THE CONTRACTOR SHALL FURNISH AND INSTALL ALL ITEMS SPECIFIED HEREIN AND AS INDICATED ON THE DRAWINGS. THE CONTRACTOR SHALL ALSO FURNISH AND INSTALL ALL ITEMS NECESSARY TO MAKE THE SYSTEMS FUNCTION WHICH MAY BE REASONABLY IMPLIED AS ESSENTIAL, WHETHER MENTIONED IN THE CONTRACT DOCUMENTS OR NOT.

M. WORK SHALL BE EXECUTED IN STRICT ACCORDANCE WITH THE BEST PRACTICE OF THE TRADES IN A THOROUGH, SUBSTANTIAL AND WORKMANLIKE MANNER BY COMPETENT WORKMEN.

1.4 SITE FAMILIARIZATION

A. GENERAL: BECOME FAMILIAR WITH THE DRAWINGS AND SPECIFICATIONS, EXAMINE THE PREMISES, AND UNDERSTAND THE CONDITIONS UNDER WHICH THE CONTRACT SHALL BE PERFORMED, PRIOR TO SUBMITTING A BID.

B. SITE: BE INFORMED OF THE SITE CONDITIONS, VERIFY LOCATIONS OF NEW AND EXISTING EQUIPMENT, AND DETERMINE EXACT REQUIREMENTS FOR CONNECTIONS.

C. COORDINATION: TENDER OF A PROPOSAL FOR THIS PROJECT INFERS THAT THE CONTRACTOR HAS VISITED THE SITE AND HAS BECOME FAMILIAR WITH THE DRAWINGS, SPECIFICATIONS, AND SITE CONDITIONS AND HAS INCLUDED IN HIS PROPOSAL ALL WORK NECESSARY TO PROPERLY INSTALL COMPLETE AND FUNCTIONING SYSTEMS ON THE PROJECT. FAILURE TO COMPLY WITH THIS REQUIREMENT SHALL NOT BE CONSIDERED JUSTIFICATION FOR THE OMISSION OR FAULTY INSTALLATION OF ANY WORK COVERED BY THE CONTRACT DOCUMENTS.

1.5 CODES AND STANDARDS

A. GENERAL: ALL WORK SHALL COMPLY WITH THE MOST RECENTLY REVISED VERSIONS OF ALL APPLICABLE LAWS, RULES, REGULATIONS AND ORDINANCES OF ALL FEDERAL, STATE AND LOCAL AUTHORITIES AND APPLICABLE UTILITIES. NONE OF THE TERMS OR PROVISIONS OF THIS SPECIFICATION SHALL BE CONSTRUED AS WAIVING ANY PART OF THE LAWS, RULES, REGULATIONS OR REQUIREMENTS OF THESE AUTHORITIES.

B. CONFLICT: IN THE EVENT OF CONFLICT BETWEEN THE CONTRACT DOCUMENTS AND THE LOCAL ENFORCING AUTHORITY, THE LATTER SHALL RULE. ANY MODIFICATIONS RESULTING THEREFROM SHALL BE MADE WITHOUT ANY ADDITIONAL COST TO THE OWNER OR ARCHITECT. THIS CONTRACTOR SHALL REPORT ANY SUCH MODIFICATIONS TO THE ARCHITECT AND SECURE HIS APPROVAL PRIOR TO PROCEEDING WITH THE WORK.

C. PRECEDENCE: WHERE CONTRACT DOCUMENT REQUIREMENTS EXCEED THE REQUIREMENTS OF THE CODES AND STANDARDS, THE CONTRACT DOCUMENTS SHALL TAKE PRECEDENCE PROVIDED THEY ARE NOT IN CONFLICT WITH THOSE CODES AND STANDARDS.

D. APPROVAL LABELS: ALL ITEMS OF EQUIPMENT AND ALL MATERIALS FOR WHICH APPROVED STANDARDS HAVE BEEN ESTABLISHED BY UNDERWRITERS' LABORATORIES. INC. (UL), FACTORY MUTUAL (FM), CERTIFIED BALLAST MANUFACTURER (CBM), ELECTRICAL TESTING LABORATORY (ETL), NATIONAL MANUFACTURERS ASSOCIATION (NEMA), AMERICAN STANDARD CODES, ASME, AGA, AMCA, ASA, ANSI, ASHRAE, AND ARI SHALL BE SO APPROVED AND SHALL BEAR APPROVAL LABELS ATTESTING TO SAME.

1.6 DRAWINGS AND SPECIFICATIONS

A. DRAWINGS: THE SET OF ORIGINAL DRAWINGS HAS BEEN MODIFIED AND INDICATE APPROXIMATE EXISTING LOCATIONS OF THE FLOOR FINISH ITEMS. ALL ITEMS ARE SHOWN APPROXIMATELY TO SCALE. FIELD VERIFY CONDITIONS.

B. SPECIFICATIONS: THE SPECIFICATIONS ARE INTENDED TO SUPPLEMENT THE DRAWINGS AND IT IS NOT IN THE SCOPE OF THE SPECIFICATIONS TO MENTION ANY PART OF THE WORK THAT THE DRAWINGS ARE COMPETENT TO FULLY EXPLAIN. CONVERSELY, ANY PART OF THE WORK THAT THE SPECIFICATIONS ARE COMPETENT TO FULLY EXPLAIN MAY NOT BE MENTIONED ON THE DRAWINGS. DRAWINGS AND SPECIFICATIONS ARE COMPLIMENTARY/SUPPLEMENTARY DOCUMENTS TO EACH OTHER.

C. DISAGREEMENT: DISAGREEMENT BETWEEN THE DRAWINGS AND SPECIFICATIONS OR WITHIN THE DRAWINGS OR SPECIFICATIONS SHALL BE ESTIMATED AND/OR BID USING THE BETTER QUALITY OR GREATER QUANTITY OF MATERIAL OR INSTALLATION, AND A CLARIFICATION REQUEST FOR INFORMATION SHALL BE MADE TO THE ARCHITECT IN A TIMELY MANNER AFTER THE PROJECT IS UNDER CONTRACT.

1.7 DISCREPANCIES

A. CLARIFICATION: CLARIFICATION OF SIGNIFICANT COST MATTERS SHALL BE OBTAINED BEFORE SUBMITTING A PROPOSAL FOR THE WORK AS TO DISCREPANCIES OR OMISSIONS FROM THE CONTRACT DOCUMENTS OR QUESTIONS AS TO THE INTENT THEREOF.

B. INTERPRETATIONS: SHOULD ANY DOUBT OR QUESTION ARISE RESPECTING THE TRUE MEANING OF DRAWINGS OR SPECIFICATIONS, REFERENCE SHALL BE MADE TO THE ARCHITECT, WHOSE WRITTEN DECISION SHALL BE FINAL AND CONCLUSIVE. NO ALLEGED STATEMENT BY THE ARCHITECT WILL BE ACCEPTED AS AN EXCUSE FOR NON-COMPLIANCE OR INFERIOR WORK.

C. CONTRACTOR AGREEMENT: CONSIDERATION WILL NOT BE GRANTED FOR MISUNDERSTANDING OF THE AMOUNT OF WORK TO BE PERFORMED. TENDER OF A PROPOSAL CONVEYS FULL CONTRACTOR AGREEMENT OF THE ITEMS AND CONDITIONS SPECIFIED, SHOWN, SCHEDULED, OR REQUIRED BY THE NATURE OF THE PROJECT, AND ALL COSTS ARE INCLUDED IN THE PROPOSAL.

1.8 REQUESTS FOR INFORMATION (RFI)

A. GENERAL: SUBMIT ALL CONTRACTOR REQUESTS FOR INFORMATION (RFI) IN WRITING TO THE ARCHITECT FOR RESPONSE. SUBMIT RFI ON A STANDARD FORM THAT HAS A SPACE FOR THE REQUESTED INFORMATION AND THE ARCHITECT'S RESPONSE.

B. SOLUTION PROPOSAL: IN GENERAL, THE CONTRACTOR SHALL PROPOSE SOLUTIONS TO IDENTIFY PROBLEMS FOR REVIEW AND APPROVAL OF THE ARCHITECT. THE RFI SHALL INCLUDE HAND SKETCHES, MARKED DRAWING PRINTS, EQUIPMENT CUTSHEETS, DRAWING AND SPECIFICATION REFERENCES, AND ANY OTHER BACK-UP INFORMATION, ETC., AS REQUIRED TO SUFFICIENTLY EXPLAIN THE PROBLEM AND PROPOSED SOLUTION.

1.9 QUALITY ASSURANCE

A. GENERAL: MATERIALS AND EQUIPMENT SHALL BE NEW, OF BEST GRADE AND QUALITY, AND STANDARD PRODUCTS OF REPUTABLE MANUFACTURERS REGULARLY ENGAGED IN THE PRODUCTION OF SUCH MATERIALS AND EQUIPMENT.

B. WORKMANSHIP: WORK SHALL BE EXECUTED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE BEST PRACTICE OF THE TRADES IN A THOROUGH, SUBSTANTIAL, WORKMANLIKE MANNER BY COMPETENT WORKMEN, PRESENTING A NEAT APPEARANCE WHEN COMPLETED.

C. JUDGMENT: IN ALL CASES, THE ARCHITECT SHALL BE THE SOLE JUDGE OF THE QUALITY AND EQUIVALENCE OF MANUFACTURERS, PRODUCTS, MATERIALS, AND METHODS.

D. MANUFACTURERS/PRODUCTS/MATERIALS/METHODS: MANUFACTURERS, PRODUCTS, MATERIALS, AND METHODS DESCRIBED IN THE VARIOUS SECTIONS OF THE SPECIFICATIONS AND INDICATED ON THE DRAWINGS ARE INTENDED TO ESTABLISH A STANDARD OF QUALITY ONLY. IT IS NOT THE INTENTION OF THE ARCHITECT TO DISCRIMINATE AGAINST ANY MANUFACTURER, PRODUCT, MATERIAL, OR METHOD THAT IS EQUAL TO THE STANDARDS AS INDICATED AND/OR SPECIFIED, NOR IS IT INTENDED TO PRECLUDE OPEN, COMPETITIVE BIDDING. THE FACT THAT A SPECIFIC MANUFACTURER IS LISTED AS AN ACCEPTABLE MANUFACTURER SHALL NOT BE INTERPRETED TO MEAN THAT THE MANUFACTURER'S STANDARD PRODUCT WILL MEET THE REQUIREMENTS OF THE PROJECT DESIGN, SPECIFICATIONS, AND SPACE CONSTRAINTS.

1. WHEREVER A DEFINITE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS SPECIFIED AND THERE IS NOT A STATEMENT THAT ANOTHER MANUFACTURER, PRODUCT, MATERIAL, OR METHOD WILL BE ACCEPTABLE, IT IS THE INTENTION OF THE ARCHITECT THAT THE SPECIFIED MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS THE ONLY ONE THAT SHALL BE USED WITHOUT PRIOR APPROVAL.
2. WHEREVER A DEFINITE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS SPECIFIED AS "NO SUBSTITUTE", IT IS THE INTENTION OF THE ARCHITECT THAT THE LISTED ITEM IS THE ONLY ONE ACCEPTABLE.

E. COORDINATION: WHERE EQUIPMENT IS USED ON THE PROJECT, IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR OR SUBCONTRACTOR INVOLVED TO VERIFY THAT THE EQUIPMENT WILL FIT IN THE SPACE AVAILABLE, INCLUDING ALL REQUIRED CODE AND MAINTENANCE CLEARANCES, AND TO COORDINATE ALL EQUIPMENT REQUIREMENTS AND PROVISIONS WITH THE SYSTEM DESIGN, ALL AFFECTED DIVISIONS, AND ALL OTHER CONTRACTORS. WHERE THE USE OF ALTERNATE OR SUBSTITUTE MATERIALS AFFECTS THE COST OF PROVISIONS MADE BY OTHER CONTRACTORS, THE CONTRACTOR PROVIDING THE ALTERNATE OR SUBSTITUTE SHALL BE RESPONSIBLE FOR THE OTHER CONTRACTOR'S COST ADJUSTMENT. THERE SHALL BE NO ADDITIONAL COST TO THE OWNER OR ARCHITECT DUE TO THE USE OR ACCEPTANCE OF ANY ALTERNATE OR SUBSTITUTE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD.

1.10 PRIOR APPROVAL

A. SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES: THE CONTRACTOR'S SUBMITTAL AND ARCHITECT'S ACCEPTANCE OF SHOP DRAWINGS, PRODUCT DATA, OR SAMPLES THAT RELATE TO CONSTRUCTION ACTIVITIES NOT COMPLYING WITH THE CONTRACT DOCUMENTS DOES NOT CONSTITUTE AN ACCEPTABLE OR VALID REQUEST FOR SUBSTITUTION, NOR DOES IT CONSTITUTE APPROVAL.

1.11 COORDINATION

A. BY SUBMITTING SHOP DRAWINGS ON THE PROJECT, THIS CONTRACTOR IS INDICATING THAT ALL NECESSARY COORDINATION HAS BEEN COMPLETED AND THAT THE SYSTEMS, PRODUCTS AND EQUIPMENT SUBMITTED CAN BE INSTALLED IN THE BUILDING AND WILL OPERATE AS SPECIFIED AND INTENDED, IN FULL COORDINATION WITH ALL OTHER DISCIPLINES.

1.12 SHOP DRAWINGS AND SUBMITTALS

A. GENERAL: AFTER THE CONTRACT IS AWARDED BUT PRIOR TO PROCEEDING WITH THE WORK REQUIRING SHOP DRAWING REVIEW, THE CONTRACTOR SHALL OBTAIN COMPLETE SHOP DRAWINGS AND PRODUCT DATA FROM THE MANUFACTURERS, SUPPLIERS, VENDORS, AND SUB- CONTRACTORS FOR ALL MATERIALS AND EQUIPMENT SPECIFIED HEREIN, AND MAKE FORMAL SUBMISSION TO THE ARCHITECT. A MINIMUM PERIOD OF TWO (2) WEEKS SHOULD BE ALLOWED IN THE CONSTRUCTION SCHEDULE EXCLUSIVE OF TRAVEL TIME FOR THE ARCHITECTS REVIEW.

B. CERTIFICATION: EACH CONTRACTOR RESPONSIBLE FOR THE WORK SHALL REVIEW AND CERTIFY THE SHOP DRAWING, SUBMITTAL AND/OR PRODUCT DATA TO BE IN FULL COMPLIANCE WITH THE REQUIREMENTS OF THE CONTRACT DOCUMENTS.

C. THE ARCHITECTS REVIEW OF SHOP DRAWINGS AND SUBMITTAL DATA SHALL NOT RELIEVE THE CONTRACTOR OF THE RESPONSIBILITY FOR DIMENSIONS OR ERRORS THAT MAY BE CONTAINED THEREIN, OR FOR DEVIATIONS FROM ANY REQUIREMENTS OF THE CONTRACT DOCUMENTS. IT SHALL BE CLEARLY UNDERSTOOD THAT THE ARCHITECTS NOTING SOME ERRORS BUT OVERLOOKING SOME OTHERS DOES NOT GRANT THE CONTRACTOR PERMISSION TO PROCEED IN ERROR. REGARDLESS OF ANY INFORMATION CONTAINED IN THE SHOP DRAWING OR PRODUCT DATA, THE CONTRACT DOCUMENTS SHALL GOVERN THE WORK AND ARE NEITHER WAIVED NOR SUPERSEDED IN ANY WAY BY THE REVIEW OF SHOP DRAWINGS, PRODUCT DATA AND SAMPLES.

1.13 EXECUTION AND COORDINATION OF WORK

A. MANUFACTURER'S RECOMMENDATIONS: WITH EXCEPTIONS AS SPECIFIED AND/OR INDICATED ON THE DRAWINGS OR IN THE SPECIFICATIONS, APPLY, INSTALL, ERECT, USE, CLEAN, AND CONDITION, MANUFACTURED ARTICLES, MATERIALS, AND EQUIPMENT PER MANUFACTURER'S CURRENT PRINTED RECOMMENDATIONS. KEEP COPIES OF SUCH PRINTED RECOMMENDATIONS AT JOB SITE AND MAKE THEM AVAILABLE AS REQUIRED.

1.14 SUPERVISION

A. A COMPETENT SUPERINTENDENT APPROVED BY THE ARCHITECT, SHALL BE KEPT BY THE CONTRACTOR AT THE BUILDING TO RECEIVE INSTRUCTIONS AND TO ACT FOR THE CONTRACTOR. ONCE THE SUPERINTENDENT HAS BEEN APPROVED, NO CHANGE SHALL BE MADE WITHOUT APPROVAL OF ARCHITECT. REPRESENTATIVES OF THE OWNER, ARCHITECT SHALL HAVE THE RIGHT TO OBSERVE THE WORK AT ANY TIME. THE CONTRACTOR SHALL HAVE A REPRESENTATIVE AVAILABLE WHEN HIS WORK IS BEING OBSERVED AND HE SHALL GIVE ASSISTANCE AS MAY BE REQUIRED TO THE ARCHITECT'S REPRESENTATIVE.

B. THE PROJECT SHALL BE CONSTRUCTED BY EMPLOYEES OF THE CONTRACTOR OR BY WORKERS UNDER HIS SUPERVISION. ANY SUBCONTRACTORS EMPLOYED BY THE CONTRACTOR SHALL BE APPROVED BY THE OWNER'S REPRESENTATIVE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL EQUIPMENT, MATERIAL AND WORK PERFORMED BY ANY SUBCONTRACTOR.

1.15 STORAGE AND PROTECTION OF MATERIALS

A. THE CONTRACTOR SHALL PROPERLY STORE ALL MATERIAL AND EQUIPMENT AT THE JOBSITE AND PROTECT IT FROM THE ELEMENTS AND FROM DAMAGE. ANY EQUIPMENT DAMAGED DUE TO IMPROPER PROTECTION SHALL BE REPLACED BY THE CONTRACTOR AT HIS EXPENSE.

B. THE CONTRACTOR SHALL PROTECT THE WORK, EQUIPMENT, AND MATERIAL OF ALL OTHER TRADES FROM DAMAGE BY HIS WORK OR OTHER WORKMEN, AND SHALL MAKE GOOD ALL DAMAGE THUS CAUSED.

C. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL WORK, MATERIALS, AND EQUIPMENT UNTIL FINALLY INSPECTED, TESTED, AND ACCEPTED. PROTECT WORK AGAINST THEFT, INJURY OR DAMAGE: AND CAREFULLY STORE MATERIAL AND EQUIPMENT RECEIVED ON SITE WHICH ARE NOT IMMEDIATELY INSTALLED. CLOSE OPEN ENDS OF WORK WITH TEMPORARY COVERS OR PLUGS DURING CONSTRUCTION TO PREVENT ENTRY OF OBSTRUCTING MATERIAL. THE CONTRACTOR SHALL COVER AND PROTECT IN AN ACCEPTABLE MANNER TO THE OWNER, EXISTING REMAINING EQUIPMENT AND MATERIALS.

D. IF ANY MATERIAL OR EQUIPMENT IS RECEIVED PRIOR TO THE TIME IT IS REQUIRED, THE CONTRACTOR SHALL BE RESPONSIBLE FOR ITS PROPER STORAGE AND PROTECTION UNTIL SUCH TIME AS IT MAY BE REQUIRED. THE CONTRACTOR SHALL PAY FOR ALL COSTS OF DEMURRAGE OR STORAGE.

1.16 DRAYAGE AND HAULING


A. THE CONTRACTOR SHALL KEEP THE JOBSITE FREE FROM THE ACCUMULATION OF TRASH AND CONSTRUCTION DEBRIS, REGARDLESS OF WHICH SUBCONTRACTOR MAY BE RESPONSIBLE.

1.17 CUTTING AND PATCHING


A. WHERE IT BECOMES NECESSARY TO CUT THROUGH ANY WALL, FLOOR OR CEILING TO PERMIT THE INSTALLATION OF ANY WORK, OR TO REPAIR ANY DEFECTS THAT MAY APPEAR, THE CUTTING SHALL BE PERFORMED UNDER THE SUPERVISION OF THE GENERAL CONTRACTOR. INFORM THE OWNER'S REPRESENTATIVE BEFORE ANY WORK COMMENCES. NO STRUCTURAL MEMBER SHALL BE ALTERED WITHOUT THE WRITTEN PERMISSION OF THE ARCHITECT.

B. VERIFICATION: SHOULD A QUESTION ARISE REGARDING THE ACCEPTABLE LEVEL OF NOISE OR VIBRATION IN A PARTICULAR SPACE OR PIECE OF EQUIPMENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING THE SERVICES OF AN APPROVED ACOUSTICAL CONSULTANT TO DETERMINE ACTUAL NOISE/VIBRATION CONDITIONS.


## 01 GENERAL NOTES





## 21 EXTERIOR DOOR SILL
SCALE: 6" = 1'-0" XREF





## 22 DOOR JAMB
SCALE: 6" = 1'-0" XREF





## 23 WINDOW HEAD
SCALE: 6" = 1'-0" XREF





## 24 DOOR WINDOW HEAD
SCALE: 6" = 1'-0" XREF





## 15 WINDOW JAMB AT WALL
SCALE: ###############





## 16 DOOR HEAD
SCALE: 6" = 1'-0" XREF





## 17 WINDOW SILL
SCALE: 6" = 1'-0" XREF





## 18 DOOR SILL
SCALE: 6" = 1'-0" XREF





## 09 WINDOW CORNER
SCALE: ###############




## 10 DOOR STRIKE JAMB
SCALE: ###############




## 11 DOOR HINGE JAMB
SCALE: ###############





## 12 WINDOW MULLION
SCALE: ###############


SEQUENCE OF CONSTRUCTION (AS OF 01/27/2025) Schools will be renovated in groups as shown. These groups contain two or three major kitchen renovations and some cafeteria/miscellaneous renovations. This sequencing is critical for FBISD food service to provide the uninterrupted meal services to their schools.

| | |
|---|---|
| GROUPING 1 | AUSTIN PARKWAY ES + SUGAR MILL ES, kitchen renovations. *Plus: COMMON WEALTH ES, CONERSTONE ES misc. renovations.* |
| GROUPING 2 | SETTLERS WAY ES + PALMER ES kitchen renovations. *Plus: SULLIVAN ES, SIENNA CROSSING ES, HERITAGE ROSE ES misc. renovations* |
| GROUPING 3 | HUNTER'S GLEN ES + HIGHLANDS ES + PECAN GROVE ES kitchen renovations. *Plus: RIDGEGATE ES, DULLES ES misc. renovations.* |

## 03 PROJECT SCHEDULE




## 04 EXTERIOR DOOR HEAD JAMB
SCALE: 6" = 1'-0" XREF




## 06 WINDOW JAMB
SCALE: 6" = 1'-0" XREF

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

0

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL
REGISTERED ARCHITECT
BRAD A. MANAUSA
22651
STATE OF TEXAS
7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

GENERAL NOTES AND ABBREVIATIONS

A00-01

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\A00-01 GENERAL NOTES AND ABBREVIATIONS.dwg Jul 23, 2025 - 4:24pm

## GENERAL DEMOLITION NOTES
(NOT ALL NOTES USED ON EACH SHEET)

1. REFER TO SHEET A00-01 FOR DEMOLITION GENERAL NOTES. THESE NOTES APPLY TO ALL SCHOOL KITCHENS.
2. COORDINATE EXTENT OF SAW CUTTING AREAS WITH NEW RECESSED SLAB FOR COOLER/FREEZER LAYOUTS, NEW SERVICE ENTRANCE FLOOR AND EXISTING KITCHEN LAYOUTS THAT REMAIN. SEE STRUCTURAL DRAWINGS AND SLAB DIMENSION CONTROL PLANS FOR ADDITIONAL SCOPE.
3. REMOVE PROTECT AND REINSTALL ALL EXISTING SURFACE MOUNTED FIRE EXTINGUISHERS (TYPES ABC AND K) AT ALL KITCHENS.
4. SAWCUT AND RE-LOCATE EXPOSED CONDUITS AND WIREMOLD TO INSIDE OF WALLS. PATCH AND PAINT. EXCEPTION: WAREWASH AREA BELOW TABLE HEIGHT AND DRY STORAGE ROOMS.
5. CONTRACTOR TO RELOCATE EXISTING KITCHEN EQUIPMENT AND OFFICE FURNITURE TO TEMPORARY KITCHEN LAYOUT AS REQUESTED BY KITCHEN MANAGER. ALSO THAT THE IT EQUIPMENT IS PROTECTED DURING RENOVATIONS. ALL EXISTING EQUIPMENT SHALL BE RETURNED TO OWNER.
6. EXISTING TACKBOARDS TO BE REMOVED BY OWNER.
7. IF PRESENT, EXISTING SAFE IN EACH KITCHEN TO BE TEMPORARILY REMOVED DURING RENOVATION AND REINSTALLED IN KITCHEN AREA.
8. ORIGIN POINT OF EXISTING CEILING GRID SHALL BE IDENTIFIED. NEW CEILING WILL BE INSTALLED (AS MUCH AS POSSIBLE) AT THE SAME ORIGIN POINT SO THAT SPRINKLER SYSTEM PIPING CAN REMAIN UNCHANGED.
9. ABOVE-CEILING INFRASTRUCTURE SHALL REMAIN UNDISTURBED AS MUCH AS IS POSSIBLE. CEILING DEVICES ARE TO BE REMOVED FROM EXISTING GRID/TILE THEN DURING RE-INSTALATION OF CEILING DEVICES SHALL BE LOCATED AS CLOSE TO ORIGINAL LOCATION AS POSSIBLE INTO THE NEW GRID/TILE. PROTECT AND STORE EXISTING INFRASTRUCTURE (CABLING, ELECTRICAL POWER, PIPING) DURING CONSTRUCTION.
10. EXISTING HOOD IN WAREWASH AND (2) HOODS IN PRODUCTION AREA ARE TO BE CLEANED, INSPECTED, SERVICED AND REFURBISHED TO A LIKE NEW CONDITION. THEY ARE TO REMAIN IN PLACE.

## KEYED DEMOLITION NOTES
(NOT ALL NOTES USED ON EACH SHEET)

1. REMOVE EXISTING THINSET SYNTHETIC TERRAZZO FLOOR AND TERRAZZO COVE BASE MATERIAL IF ANY EXISTS THROUGHTOUT KITCHEN AREA. CLEAN AND PREPARE SUBFLOOR TO RECEIVE NEW FLOOR. RE: FINISH PLAN FOR NEW FLOOR FINISH MATERIAL.
2. REMOVE EXISTING QUARRY TILE FLOORING AND BASE. CLEAN AND PREPARE SUBFLOOR TO RECEIVE NEW FLOORING. RE: FINISH SCHEDULE FOR NEW FLOOR FINISH MATERIAL.
3. CEILING DEVICES: REMOVE SMOKE DETECTORS, STROBES, EXIT SIGNAGE, MOTION DETECTORS AND CEILING SPEAKERS. PROTECT AND RE-INSTALL AFTER FINISHES ARE APPLIED.
4. REMOVE EXISTING LOCKERS. PROTECT AND RE-INSTALL AFTER FINISHES APPLIED.
5. REMOVE EXISTING WASHER AND DRYER. VERIFY WITH FBISD FOR RELOCATION TO WAREHOUSE.
6. TEMPORARILY REMOVE EXISTING WALL MOUNTED CLOCK AND STORE FOR REINSTALLATION AFTER WALL RECEIVED NEW FINISH.
7. REMOVE EXISTING WALK-IN COOLER/FREEZER AND CONDENSING UNIT LOCATED IN ADJACENT SPACE. MITIGATE ANY MOLD FOUND.
8. REMOVE EXISTING DOOR AND PROTECT EXISTING FRAME TO REMAIN
9. REMOVE EXISTING DOOR AND FRAME. PROTECT FRAME AND OR DOOR IF IT IS SCHEDULED TO REMAIN.
10. REMOVE PARTIAL EXISTING CMU PARTITION FOR NEW DOOR OPENING
11. INSPECT EXISTING WAREWASH COUNTER DOOR AND S.S. PASS-THRU WINDOW CHUTE. REPAIR REPLACE DAMAGED COMPONENTS. CLEAN, LUBRICATE AND RE-INSTALL.
12. EXISTING CARD READER ACCESS TO REMAIN
13. EXISTING WINDOW TO REMAIN
14. REMOVE EXISTING KITCHEN EQUIPMENT THROUGHOUT KITCHEN INCLUDING WALK-IN COOLER / FREEZER AND CONDENSING UNIT LOCATED IN ADJACENT ROOM OR OUTSIDE OF THE BUILDING. VERIFY WITH OWNER FOR RELOCATION TO WAREHOUSE. SOME EQUIPMENT IS TO BE RE-USED IN TEMPORARY SERVING LINES. SEE ALSO GENERAL DEMOLITION NOTE 6.
15. REMOVE EXISTING FRP AND PREP FOR NEW TILE FINISH.
16. COORDINATE REMOVAL AND STORAGE OF ANY EXISTING FURNITURE ITEMS WITH OWNER . SEE ALSO GENERAL DEMOLITION NOTE 5.
17. REMOVE EXISTING SOAP AND PAPER TOWEL DISPENSER AND RETURN TO OWNER
18. EXISTING WALL MOUNTED ACCESSORIES SIGNS, DISPLAY BOARDS, AND MATS TO BE REMOVED BY FORT BEND ISD (VERIFY EQUIPMENT - IF ANY).
19. REMOVE EXISTING SURFACE MOUNTED FIRE EXTINGUISHER. RE-INSTALL AFTER NEW FINISH APPLIED.
20. REMOVE EXISTING ACOUSTIC CEILING TILE CEILNG SYSTEM AND LIGHT FIXTURES, HVAC DEVICES, SENSORS, ETC. THROUGHTOUT RENOVATED AREAS. PREP FOR NEW SUSPENDED CEILING. EXISTING SPRINKLE SYSTEM TO REMAIN AS-IS UNLESS ROOM CONFIGURATION HAS CHANGED IN NEW DESIGN. PROTECT RECESSED SPRINKLER HEADS AND - RE-INSTALL IN NEW CEILING.
21. REMOVE EXISTING CASEWORK/SHELVING
22. EXISTING CERAMIC WALL TILE TO REMAIN. PROTECT FROM DAMAAGE.
23. REMOVE EXISTING COAT HANGER / ROD / SHELF
24. REMOVE EXISTING PLUMBING FIXTURES IN RESTROOMS. RE: PLUMBING FOR NEW FIXTURES.
25. REMOVE EXISTING UTILITY SINK. RE: PLUMBING FOR NEW PLUMBING FIXTURES.
26. REMOVE EXISTING MOP HOLDER. REPLACE WITH NEW UNIT AS SPECIFIED.
27. REMOVE EXISTING WALL MOUNTED CLEANING SOLUTION DISPENSER (BY FBISD VENDOR)
28. HOOD TO REMAIN - SEE GENERAL DEMOLITION NOTE 10.
29. HOOD TO REMAIN - SEE GENERAL DEMOLITION NOTE 10.
30. REMOVE FLOORING IN THIS AREA FOR NOTE 1.
31. REMOVE CARTIDGE FILTER AND WATER PURTICATION CABNET


## DEMOLITION LEGEND

- EXISTING PARTITION TO REMAIN
- REMOVE EXISTING PARTITION
- EXISTING CMU PARTITION
- REMOVE DOOR AND FRAME TO REMAIN
- REMOVE EXISTING DOOR AND FRAME
- EXISTING PLUMBING FIXTURES (WATER CLOSET, HAND LAVATORY, AND MOP SINK TO BE REMOVED. RE: PLUMBING DRAWINGS.
- EXISTING ACOUSTIC CEILING TILE AND GRID TO BE REMOVED. RE: ELECTRICAL DRAWINGS.
- SPRINKLER HEAD (RECESSED)
- CLOCK
- CEILING MOUNTED SPEAKERS


# 3 DEMOLITION NOTES

## OLD FLOOR LEGEND

OLD QUARRY TILE
(1,562 SF)




1 DEMOLITION FLOOR PLAN
SCALE: 1/4" = 1'-0"




2 DEMOLITION REFLECTED CEILING PLAN
SCALE: 1/4" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

0

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL
REGISTERED ARCHITECT
KRISTY A. MAZZEI
#22651
STATE OF TEXAS
7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

DEMO PLANS

o-D.101

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\O-Palmer ES\o-D.101 DEMO PLAN.dwg Jul 23, 2025 - 4:24pm




PHOTO D1



PHOTO D2




PHOTO D3



PHOTO D4




PHOTO D5




PHOTO D6



PHOTO D7



PHOTO D8




PHOTO D9




PHOTO D10



PHOTO D11




PHOTO D12




PHOTO D13



PHOTO D14




PHOTO D15




PHOTO D16




PHOTO D17




PHOTO D18



PHOTO D19



PHOTO D20

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

0

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DR,
SUGAR LAND, TX 77459

SEAL
REGISTERED ARCHITECT
ROBERT M. WILLIAMS
23051
STATE OF TEXAS
7/15/2025

MWA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
DEMO PLAN
PHOTOS
o-D.101-2


F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWG\SD\drawings\O-Palmer ES\o-D.101-2 DEMO PLAN PHOTOS.dwg, Jul 23, 2025 - 4:25pm

## NEW PANEL — TEMP KITCHEN


**PANEL LTK** — 150A MCB, 208Y/120V, 3ø, 4 WIRE — AVAILABLE FAULT: <10,000A — SCCR & AIC: 10,000A — MOUNTING: SURFACE

| NOTES | EQUIP. NO. | LOAD | DESCRIPTION | WIRE | CB | CKT | A | B | C | CKT | CB | WIRE | DESCRIPTION | LOAD | EQUIP. NO. | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E810 | 2766 | HOT WELLS | 2–12 | 20/2GFI | 1 | ■ | | | 2 | 20/1 | 3–12 | TRANSPORT CART | 1920 | E806 | |
| | | – | – | +12G | – | 3 | | ■ | | 4 | 20/1 | 3–12 | TRANSPORT CART | 1920 | E806 | |
| | E810A | 1643 | HOT WELLS | 2–12 | 20/2GFI | 5 | | | ■ | 6 | 20/1 | 3–12 | TRANSPORT CART | 1920 | E806 | |
| | | – | – | +12G | – | 7 | ■ | | | 8 | 20/1 | 3–12 | TRANSPORT CART | 1920 | E806 | |
| | E810B | 600 | COLD PAN | 3–12 | 20/1GFI | 9 | | ■ | | 10 | 20/1 | 3–12 | 2 REC | 360 | E800A | |
| | E810C | 1200 | BEVERAGE | 3–12 | 20/1GFI | 11 | | | ■ | 12 | 20/1 | 3–12 | 2 REC – DESK | 360 | E800B | |
| | E810C | 1200 | BEVERAGE | 3–12 | 20/1GFI | 13 | ■ | | | 14 | 20/1 | 3–12 | 2 REC | 360 | E800A | |
| | E811 | 180 | CASH REGISTER | 3–12 | 20/1GFI | 15 | | ■ | | 16 | 20/1 | 3–12 | 3 REC | 360 | E800A | |
| | E810B | 600 | COLD PAN | 3–12 | 20/1GFI | 17 | | | ■ | 18 | 20/1 | 3–12 | TEMP. KITCHEN LTS/FAN | 566 | | |
| | E810A | 1643 | HOT WELLS | 2–12 | 20/2GFI | 19 | ■ | | | 20 | 20/1 | | SPARE | | | |
| | | – | – | +12G | – | 21 | | ■ | | 22 | 20/1 | | SPARE | | | |
| | E810 | 2766 | HOT WELLS | 2–12 | 20/2GFI | 23 | | | ■ | 24 | 20/1 | | SPARE | | | |
| | | – | – | +12G | – | 25 | ■ | | | 26 | 20/1 | | SPARE | | | |
| | E808 | 1622 | HEATED CABINET | 2–12 | 20/2 | 27 | | ■ | | 28 | 20/1 | | SPARE | | | |
| | | – | – | +12N+12G | – | 29 | | | ■ | 30 | 20/1 | 3–12 | EXISTING CIRCUIT | 500 | | 3 |
| | E809 | 984 | REFRIGERATOR | 3–12 | 20/1 | 31 | ■ | | | 32 | 20/1 | 3–12 | EXISTING CIRCUIT | 500 | | 3 |
| | E808 | 1622 | HEATED CABINET | 2–12 | 20/2 | 33 | | ■ | | 34 | 15/2 | 2–12 | EXISTING CIRCUIT | 1000 | | 3 |
| | | – | – | +12N+12G | – | 35 | | | ■ | 36 | – | +12N+12G | – | – | | |
| | E809 | 984 | REFRIGERATOR | 3–12 | 20/1 | 37 | ■ | | | 38 | 20/2 | 2–12 | EXISTING CIRCUIT | 1000 | | 3 |
| | | | SPARE | | 20/1 | 39 | | ■ | | 40 | – | +12N+12G | – | – | | |
| | | | SPARE | | 20/1 | 41 | | | ■ | 42 | 50/2 | 2–8 | EXISTING CIRCUIT | 5000 | | 3 |
| | | | SPARE | | 20/1 | 43 | ■ | | | 44 | – | +8N+10G | – | – | | |
| | TOTAL LOAD @ 100% = 35498VA | | | | | | TOTAL LOAD @ 100% = 99A | | | | | | | | | |


1. REF. KITCHEN CONSULTANT'S "FCS" DRAWINGS FOR KITCHEN EQUIPMENT NUMBERS.
2. A DEMAND FACTOR PERCENT OF 65% HAS BEEN APPLIED TO THE KITCHEN EQUIPMENT LOAD PURSUANT TO NEC 220–20 AND NEC TABLE 220–20.
3. IDENTIFY ANY CIRCUITS OR PARTIAL CIRCUITS THAT EXTEND BEYOND THE AREA OF RENOVATION. PROVIDE TEMPORARY FEED TO MAINTAIN ALL CIRCUITS SERVING ELEMENTS/SPACES NOT TO BE REMODELED DURING CONSTRUCTION. RECONNECT EXISTING CIRCUITS/DEVICES TO REMAIN TO TEMPORARY KITCHEN PANEL ONCE AVAILABLE USING CB(S) PROVIDED. ALL PARTIAL CIRCUITS SHALL REMAIN AND REMAIN ACTIVE BOTH DURING AND AFTER CONSTRUCTION.




**T1** **TEMPORARY KITCHEN - LIGHTING PLAN**
SCALE: 1/4" = 1'– 0"




**T2** **TEMPORARY KITCHEN - ELECTRICAL PLAN**
SCALE: 1/4" = 1'– 0"




**1** **DEMOLITION FLOOR PLAN**
SCALE: 1/8" = 1'– 0"

## ELECTRICAL KEYED NOTES

GENERAL NOTES:

- CUT WALLS AS REQUIRED TO FLUSH MOUNT NEW DEVICES IN EXISTING WALLS. PATCH/REPAIR WALLS TO MATCH.

DEMOLITION NOTES:

A. EXISTING STANDBY GENERATOR PANEL TO REMAIN.

B. EXISTING KITCHEN PANELS TO BE REPLACED WITH NEW. MODIFY EXISTING WALLS TO MATCH NEW PANEL LAYOUTS AND DIMENSIONS.

C. EXISTING LIGHTING FIXTURES AND CEILING DEVICES TO BE REMOVED THROUGHOUT.

D. EXISTING WALK–IN COOLER/FREEZER AND ASSOCIATED EQUIPMENT TO BE REMOVED.

E. EXISTING WALL ELECTRICAL DEVICES TO BE REMOVED. EXISTING J–BOXES MAY BE REUSED WHERE NEW DEVICES ARE TO BE INSTALLED AT THE SAME LOCATIONS.

F. EXISTING ELECTRICAL DEVICES TO BE REMOVED.

G. NEW 208Y/120V PANEL AND TRANSFORMER FOR TEMPORARY KITCHEN TO BE INSTALLED PRIOR TO DEMOLITION. PANEL AND TRANSFORMER TO BE REMOVED AT END OF KITCHEN RENOVATION AND TURNED OVER TO THE DISTRICT. INSTALL TRANSFORMER ON PREMADE FIBERCRETE PAD AND WAFFLE TYPE VIBRATION ISOLATION PADS. DO NOT PROVIDE A POURED IN PLACE CONCRETE PAD AT THIS LOCATION.

H. PROVIDE RECEPTACLES AND LIGHT FIXTURES FOR TEMPORARY KITCHEN DURING RENOVATION. ALL TEMPORARY DEVICES AND EQUIPMENT TO BE REMOVED AT END OF KITCHEN RENOVATION AND OFFERED TO THE OWNER AS SALVAGE.

I. CONDUITS ROUTED FROM TEMPORARY KITCHEN WALL AND BENEATH SERVING LINE. PROVIDE MULTICHANNEL ROLLOVER CABLE PROTECTOR FOR EXPOSED CONDUITS NOT UNDER THE SERVING LINE. ALL CONDUITS UNDER THE SERVING LINE SHALL BE SECURED TO/ROUTED ON TOP OF UNISTRUT AND NOT DIRECTLY ON THE FLOOR. DO NOT ANCHOR UNISTRUT TO THE EXISTING FLOORING. COORDINATE POWER AND DATA OUTLET LOCATIONS WITH OTHER TRADES.

J. REMOVE EXISTING LIGHT FIXTURES ABOVE NEW KITCHEN EXTENSION. MODIFY EXISTING WIRING TO MAINTAIN REMAINING FIXTURE OPERATION.

K. HARDWIRE KITCHEN EQUIPMENT TO LOCAL ON/OFF SWITCH. TYPICAL.

L. SURFACE MOUNT FIXTURES ON TEMPORARY KITCHEN CEILING. TYPICAL.

M. WIRE TEMPORARY KITCHEN FAN TO LOCAL LIGHTING CIRCUIT AND CONTROLS. FAN SHALL BE ON/OFF WITH LIGHTS.

N. EXISTING EXTERIOR LIGHT FIXTURES TO BE REMOVED.

O. PROVIDE NEW FIRE ALARM DEVICES AS PART OF THE TEMPORARY KITCHEN BUILDOUT.

P. PROVIDE NEW TEMPORARY LIGHT FIXTURES IN THE EXISTING CAFETERIA CEILING ABOVE THE SERVING LINE. COORDINATE LOCATIONS WITH TEMPORARY SERVING LINE AND EXISTING CONDITIONS. CONNECT TO EXISTING LIGHTING CONTROLS/CIRCUIT. ALL TEMPORARY LIGHT FIXTURES SHALL BE REMOVED AT THE END OF KITCHEN RENOVATION AND OFFERED TO THE OWNER AS SALVAGE. PROVIDE REPLACEMENT CEILING TILES.

Q. PROVIDE IN–USE WEATHERPROOF COVER FOR RECEPTACLE.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

0

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL

STATE OF TEXAS — GEORGE L. STANTON — 38582 — REGISTERED — PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL DEMO AND TEMP PLANS

o-ED.100


STANTON ENGINEERING GROUP
INFORMATION PROVIDED (713) 300–6080 | TEXAS ENGINEERING FIRM REG. NO.F–12322 | 1300 W. SAM HOUSTON PARKWAY S., SUITE 125, HOUSTON, TX 77042


© 2025 ALL RIGHTS RESERVED




## DEMOLITION KEYED NOTES

D1 EXISTING CLEAN OUT SHALL BE REPLACED WITH NEW. CHIP OUT SLAB AROUND CLEANOUT TO REMOVE.

D2 EXISTING FLOOR DRAIN SHALL BE REPLACED WITH NEW, INCLUDING P-TRAP. CHIP OUT SLAB AROUND DRAIN TO REMOVE FLOOR DRAIN AND EXISTING P-TRAP.

D3 CUT AND CAP EXISTING HW/CW FOR FUTURE EXTENSION. DEMOLISH ALL PIPING WITHIN KITCHEN. DEMOLITION SHALL BE DELAYED UNTIL NEW CW MAIN AND HW PIPING LOOP IS INSTALLED IN PARALLEL. CW/HW SERVICE TO THE TEMPORARY KITCHEN SHALL BE UNINTERRUPTED DURING OCCUPIED HOURS. COORDINATE SWITCHOVER FROM EXISTING PIPING TO NEW WITH OCCUPANCY SCHEDULE.

D4 EXISTING FLOOR DRAIN TIED TO GREASE WASTE SYSTEM. DRAIN IS BEING USED FOR TEMPORARY KITCHEN INDIRECT WASTE AND SHALL REMAIN ACTIVE DURING OCCUPIED HOURS. COORDINATE DEMOLITION AND REPLACEMENT WITH TEMPORARY KITCHEN USAGE.

D5 DEMOLISH EXISTING DRAIN A CAP BELOW SLAB.

D6 EXISTING SPACE BEING DEMOLISHED. CAP EXISTING SANITARY MAIN BELOW SLAB AND REMOVE UPSTREAM PIPING. CUT/CHIP OUT SLAB AS REQUIRED AND REPAIR TO MATCH EXISTING.

D7 TEMPORARILY CAP EXISTING SANITARY MAIN BELOW SLAB AND REMOVE UPSTREAM PIPING. CUT/CHIP OUT SLAB AS REQUIRED AND REPAIR TO MATCH EXISTING. PIPING TO BE REPLACED WITH NEW TRUNK AND ADDITIONAL DRAIN BRANCH LINES.

D8 CUT AND CAP EXISTING SANITARY MAIN BELOW GRADE FOR EXTENSION IN RENOVATION PHASE. ALL UPSTREAM PIPING SHALL BE ABANDONED IN PLACE. CAP ANY OPEN ENDS BEFORE BURIAL.

**1 PLUMBING DEMOLITION FLOOR PLAN**
SCALE: 1/4" = 1'- 0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

o

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL

STATE OF TEXAS
TYLER W. HERRING
106052
LICENSED
PROFESSIONAL
ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING


PLUMBING DEMOLITION FLOOR PLAN

**o-PD1.01**


STANTON ENGINEERING GROUP
INFORMATION-TECHNOLOGY (713) 300-60360


TEXAS ENGINEERING REG. NO. F-12344 © 2025 ALL RIGHTS RESERVED


12300 W. SAM HOUSTON PARKWAY S., SUITE 125, HOUSTON, TX 77042




1 TECHNOLOGY DEMOLITION FLOOR PLAN
o-TD201 1/4" = 1'-0"

**TECHNOLOGY DEMOLITION PLAN GENERAL NOTES**

1. ALL DATA, VOICE, VIDEO AND SECURITY SYSTEMS SHALL REMAIN OPERATIONAL AT ALL TIMES DURING BUSINESS HOURS UNLESS OTHERWISE NOTED. ANY SYSTEM DOWNTIME SHALL BE SCHEDULED WITH THE ARCHITECT/ENGINEER AND OWNER AT LEAST TEN (10) WORKING DAYS IN ADVANCE. CONTRACTOR SHALL DEVELOP A PHASING PLAN AND SCHEDULE OF ANY REQUIRED SYSTEM DOWNTIME FOR REVIEW AND APPROVAL BY THE ARCHITECT/ENGINEER AND OWNER PRIOR TO ANY CONSTRUCTION ACTIVITIES.
2. OWNER SHALL BE RESPONSIBLE FOR POWER DOWN AND START-UP OF ALL DATA, VOICE, VIDEO AND SECURITY SYSTEMS. CONTRACTOR SHALL COORDINATE WITH THE ARCHITECT/ENGINEER AND OWNER AND PROVIDE A MINIMUM OF TEN (10) WORKING DAYS NOTICE FOR SCHEDULING OF ANY REQUIRED DOWNTIME.
3. ALL EXISTING WIRELESS ACCESS POINTS ARE TO BE REMOVED AND RETURNED TO OWNER. CONTRACTOR SHALL RE-INSTALL ALL EXISTING AND NEW WIRELESS ACCESS POINTS AT COMPLETION OF PROJECT.
4. COORDINATE REMOVAL OF EXISTING CAMERA WITH OWNER/ARCHITECT DURING CONSTRUCTION.

**TECHNOLOGY DEMOLITION PLAN KEYED NOTES**

**NOT ALL KEYED BELOW APPLY TO THIS SHEET**

(1) EXISTING DATA/VOICE/WIRELESS ACCESS POINT OUTLET TO BE REMOVED. CONTRACTOR SHALL REMOVE AND DISPOSE OF ALL 4-PAIR CABLES AND WORKSTATION CONNECTING HARDWARE TERMINATED AT THIS LOCATION. IF LOCATION IS NOT RE-USED, CONTRACTOR SHALL SUPPLY AND INSTALL BLANK COVER. CONTRACTOR IS TO REMOVE EACH CABLE TO BE DEMOLISHED FROM THE PATCH PANEL OR TERMINATION BLOCK IN THE TELECOMMUNICATIONS ROOM. REMOVE THE ENTIRE LENGTH OF THE CABLE AND THE CORRESPONDING MODULAR CONNECTOR, FACEPLATE AND ACCESSORIES. NO ABANDONED CABLING IS TO BE LEFT ABOVE CEILING. CONTRACTOR SHALL INSTALL ALL EXISTING AND NEW WIRELESS ACCESS POINTS AT COMPLETION OF PROJECT.

(2) EXISTING VIDEO SURVEILLANCE CAMERA. CONTRACTOR SHALL REMOVE AND RETURN TO OWNER.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

O

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD


07/18/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY DEMOLITION FLOOR PLAN

SHEET NO.
o-TD201




2 ENLARGED SITE PLAN
SCALE: 1/8" = 1'-0"

1 SITE PLAN
SCALE: 1" = 30'-0"

NUMBERED NOTES: FOR 2/a-A.101

1. COOLER RENTAL UNIT; APPROX. 8' X 10' BASIS OF DESIGN: MODEL DT810 BY POLAR LEASING REFRIGERATION RENTAL
2. INCLUDE OPTIONAL DIAMOND TREAD RAMP SUITABLE FOR WHEELED TRAFFIC
3. LOCATION SHOWN IS SUBJECT TO OWNER APPROX. LOCATION MUST NOT BLOCK DELIVERIES TO REAR DOOR, MUST BE WITH 10' OF AREA DRAIN, AND WITHIN 100' OF ELECTRICAL POWER.
4. CONTRACTOR SHALL SCAN PAVING FOR BURIED UTILITIES BEFOR CUTTING CONC.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

0

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT

PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL

7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING


SITE PLAN

o-A.101


F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\O-Palmer ES\o-A.101 SITE PLAN.dwg Jul 23, 2025 - 4:25pm




## 10 CANOPY DETAILS
3/4" = 1'-0"




## 11 CANOPY PLAN
3/4" = 1'-0"





## 12 CANOPY SECTION
3/4" = 1'-0"

NOTES:
1. SAW CUT AND REMOVE EXISTING SLAB AND FLOOR FINISHES AS REQUIRED TO INSTALL NEW PLUMBING LINES, FLOOR DRAINS, FIXTURES, OR ELECTRICAL ITEMS.
2. SHADED AREA REPRESENTS APPROXIMATE SAWCUT AREAS NEEDED FOR PLUMBING ALTERATIONS.
3. CONTRACTOR TO DETERMINE EXTENT OF CONCRETE SLAB SAW CUTTING AS REQUIRED FOR ALL UTILITIES REQUIRED FOR THIS PROJECT.
4. SPLICE NEW REINFORCING BARS AND DOWELED INTO EXISTING CONCRETE, AND PROVIDE NEW VAPOR RETARDER AND WATERSTOPS, AND PATCH W/ 3000 PSI CONCRETE AFTER INSTALLATION OF UTILITIES AND FIXTURES.
5. PREPARE CONCRETE TO RECEIVE NEW FINISH.

HATCHED AREA REPRESENTS APPROXIMATE AREA THAT WILL NEED TO BE EXCAVATED IN ORDER TO MAKE PLUMBING ALTERATIONS OUTSIDE THE BUILDING. CONTRACTOR TO REMOVE CONCRETE WALKS, PAVING, AND EXCAVATE AS REQUIRED IN ORDER TO INSTALL NEW PLUMBING. BACK FILL AND RESTORE AFFECTED AREAS. REFER TO CIVIL DETAILS.

SAW CUT AND REMOVE EXISTING SLAB AND FLOOR FINISHES AS REQUIRED TO INSTALL NEW PLUMBING LINES, FLOOR DRAINS, FIXTURES, OR ELECTRICAL ITEMS. SPLICE NEW REINFORCING BARS AND DOWELED INTO EXISTING CONCRETE, AND PROVIDE NEW VAPOR RETARDER AND WATERSTOPS, AND PATCH W/ 3000 PSI CONCRETE AFTER INSTALLATION OF UTILITIES AND FIXTURES. PREPARE CONCRETE TO RECEIVE NEW FINISH.

SHADED AREA REPRESENTS APPROXIMATE SAWCUT AREAS NEEDED FOR PLUMBING ALTERATIONS. CONTRACTOR TO DETERMINE EXTENT OF CONCRETE SLAB SAW CUTTING AS REQUIRED FOR ALL PLUMBING REQUIRED FOR THIS PROJECT.




## 1 SLAB DEPRESSION PLAN
SCALE: 1/4" = 1'-0"

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\O-Palmer ES\o-A.200 SLAB DIMENSION CONTROL PLAN.dwg Jul 23, 2025 - 4:25pm

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

O

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL

REGISTERED ARCHITECT
MICHAEL A. WAPES
#26511
STATE OF TEXAS

7/15/2025


ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

SLAB DIMENSION CONTROL PLAN

o-A.200

# 2 CODE ANALYSIS

SCOPE OF WORK: KITCHEN REPLACEMENT OF FLOOR, WALL, AND CEILING FINISHES, AS WELL AS, REPLACEMENT OF KITCHEN EQUIPMENT. PROVIDE ADDITIONAL KITCHEN STORAGE FOR CEP. UPGRADE TO BACK DOOR DELIVERY AREA.

**ADOPTED CODES WITH AMMENDMENTS OF CITY OF MISSOURI CITY, TX**

- 2021 INTERNATIONAL BUILDING CODE
- 2021 INTERNATIONAL RESIDENTIAL CODE
- 2021 INTERNATIONAL PLUMBING CODE
- 2021 INTERNATIONAL MECHANICAL CODE
- 2023 NATIONAL ELECTRIC CODE NFPA 70
- 2021 INTERNATIONAL ENERGY CONSERVATION CODE
- 2021 INTERNATIONAL FUEL GAS CODE
- 2021 INTERNATIONAL FIRE CODE

**INTERIOR WALL AND CEILING FINISH REQUIREMENTS BY OCCUPANCY:**

**SPRINKLERED**

INTERIOR EXIT STAIRWAYS AND RAMPS AND EXIT PASSAGEWAYS **B**

CORRIDORS AND ENCLOSURE FOR EXIT ACCESS STAIRWAYS AND RAMPS **C**

ROOMS AND ENCLOSED SPACES **C**

**FLOORING SHALL BE CLASS II**

**2021 INTERNATIONAL EXISTING BUILDING CODE**

301.3.1 PRESCRIPTIVE COMPLIANCE METHOD. REPAIRS, ALTERATIONS, ADDITIONS AND CHANGES OF OCCUPANCY COMPLYING WITH CHAPTER FIVE OF THIS CODE IN BUILDINGS COMPLYING WITH THE INTERNATIONAL FIRE CODE SHALL BE CONSIDERED IN COMPLIANCE WITH THE PROVISIONS OF THIS CODE.

302.3 EXISTING MATERIALS. MATERIALS ALREADY IN USE IN A BUILDING IN COMPLIANCE WITH REQUIREMENTS OR APPROVALS IN EFFECT AT THE TIME OF THEIR ERECTION OR INSTALLATION SHALL BE PERMITTED TO REMAIN IN USE UNLESS DETERMINED BY THE BUILDING OFFICIAL TO BE UNSAFE.

302.4 NEW AND REPLACEMENT MATERIALS. EXCEPT AS OTHERWISE REQUIRED OR PERMITTED BY THIS CODE, MATERIALS PERMITTED BY THE APPLICABLE CODE FOR NEW CONSTRUCTION SHALL BE USED. LIKE MATERIALS SHALL BE PERMITTED FOR REPAIRS AND ALTERATIONS, PROVIDED THAT NO UNSAFE CONDITION IS CREATED. HAZARDOUS MATERIALS SHALL NOT BE USED WHERE THE CODE FOR NEW CONSTRUCTION WOULD NOT PERMIT THEIR USE IN BUILDINGS OF SIMILAR OCCUPANCY, PURPOSE AND LOCATION.

**ALTERATION - LEVEL 1** INCLUDE THE REMOVAL AND REPLACEMENT OR THE COVERING OF EXISTING MATERIALS, ELEMENTS, EQUIPMENT, OR FIXTURES USING NEW MATERIALS, ELEMENTS, EQUIPMENT, OR FIXTURES THAT SERVE THE SAME PURPOSE.

**ALTERATION - LEVEL 2** INCLUDE THE ADDITION OR ELIMINATION OF ANY DOOR OR WINDOW, THE RECONFIGURATION OR EXTENSION OF ANY SYSTEM, OR THE INSTALLATION OF ANY ADDITIONAL EQUIPMENT, AND SHALL APPLY WHERE THE WORK IS EQUAL TO OR LESS THAN 50% OF THE BUILDING AREA.

THIS BUILDING'S CONSTRUCTION IS TYPE IIB.

THIS BUILDING'S OCCUPANCY IS E.

THIS BUILDING'S IS SPRINKLERED.


THERE WILL NOT BE ANY MODIFACATIONS TO THE HOOD SYSTEMS IN THE KITCHENS BEYOND REPLACEMENT OF MOTOR FOR LIKE KIND IF NEEDED.

THE BUILDING WILL NOT HAVE ADDITIONAL SQUARE FOOTAGE AS PART OF THE WORK.

NEW CONSTRUCTION ELEMENTS, COMPONENTS, SYSTEMS AND SPACES SHALL COMPLY WITH THE REQUIREMENTS OF THE INTERNATIONAL BUILDING CODES

## RESPONSIBILITY MATRIX

| ITEM | | | | CONTRACTOR RESPONSIBILITY | | OWNER RESPONSIBILITY | | NOTES |
|---|---|---|---|---|---|---|---|---|
| **EQUIPMENT** | **MAKE** | **MODEL** | **BASIS OF DESIGN** | FURNISHED | INSTALL | FURNISHED | INSTALL | |
| MARKERBOARD | | | MUST BE MAGNETIC; LOW GLOS, WHITE. NO GREY ALLOWED, 5' X 10' | X | X | | | |
| MOTORIZED FOLDING PARTITION | | | TOP SUPPORTED AND CONTINUOUSLY HINGED, MADE OF 3" THICK STEEL WITH FULL SOUND SEALS. THEY FEATURE AUTOMATIC FLOOR SEALS THAT DEPLOY WHEN POSITIONED. MARKERBOARD FINISHES ARE SUGGESTED FOR CLASSROOM USE. LARGE PARTITIONS SHOULD BE ELECTRONICALLY OPERATED, INTEGRATED WITH THE SCHOOL SYSTEM, AND SUPPORTED FROM THE BOTTOM IN A RECESSED MANNER. | X | X | | | |
| PAPER TOWEL DISPENSER | | | 1 PAPER TOWEL DISPENSER PER SINK | | X | X | | |
| SOAP DISPENSER | | | 1 SOAP DISPENSER PER SINK | | X | X | | |
| COMMERCIAL WASHER | GE | GTW760CPLOG | STAINLESS STEEL; ASTM A666, TYPE 304 WITH NUMBER 4 FINISH. ELECTRIC, 480 VOLTS, 40 LB CAPACITY, MINIMUM EXTRACTOR FORCE 140 G FACTOR. | X | X | | | |
| COMMERCIAL DRYER | GE | GTD75ECPLDG | HEAVY DUTY EMBOSSED STEEL WITH ELECTROSTATICALLY APPLIED BACKED ENAMEL FINISH. | X | X | | | |
| MOP RACK | | | BROOM AND MOP HANGGERS FOR A MINIMUM OF TWELVE (12) HANGERS TO BE PROVIDED IN THE CONTRACT | X | X | | | |
| KITCHEN MENU SYSTEM DEVICE | | | RE: J-QP1.0 SF EQUIPMENT PLAN | X | X | | | REFERED TO IT DRAWINGS |
| LOCKERS | | | 12"W X 15"D, 2 TIER, 60" HIGH. 16 GA. DOOR WITH 20GA. BODY | X | X | | | |
| MIRROR | | | TOP EDGE 74 INCHES (1880 MM) MINIMUM ABOVE THE FINISH FLOOR OR GROUND & BOTTOM EDGE OF THE REFLECTING SURFACE 40 INCHES (1015 MM) MAXIMUM | X | X | | | |
| GRAB BARS | | | AS REQUIRED BY ADA | X | X | | | |
| HOOKS | | | J-HOOKS | X | X | | | |
| TIME CLOCK | KRONOS | | EXISTING UNIT | | X | | | COORDINATE HEIGHT, DATA, POWER AND ROUGH-IN REQUIREMENTS WITH FBISD IT. REMOVE, PROTECT & REINSTALL EXISTING TIME CLOCK. |
| **KITCHEN OFFICE FURNITURE** | | | | | | | | |
| AUSTIN PARKWAY ES | | | | | | X | X | |
| PECAN GROVE ES | | | | | | X | X | |
| SETTLERS WAY ES | | | | | | X | X | |
| SUGAR MILL ES | | | | | | X | X | |
| HIGHLANDS ES | | | | | | X | X | |
| PALMER ES | | | | | | X | X | |
| HUNTERS GLEN ES | | | | | | X | X | |



1 OVERALL FLOOR PLAN
SCALE: 1/16" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

O

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT

PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL

7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING


OVERALL FLOOR PLAN

o-A.201

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\O-Palmer ES\o-A.201 FLOOR PLAN.dwg, Jul 23, 2025 - 4:26pm

## DOOR SCHEDULE

| DOOR # | DOOR WIDTH | DOOR HEIGHT | DOOR TYPE | DOOR MATERIAL | DOOR FINISH | FIRE RATING | FRAME THICKNESS | FRAME FINISH | KEY | HARDWARE | DETAILS | | | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | | SILL | JAMB | HEAD | |
| A005 | 3'-0" | X 7'-0" | SF4 | SOLID CORE | P LAM | NR | 4 1/2" | ANOD AL | | 103 | | 22/A00-01 | 16/A00-01 | |
| A006 | 3'-0" | X 7'-0" | SF4 | SOLID CORE | P LAM | NR | 4 1/2" | ANOD AL | | 501 | | 22/A00-01 | 16/A00-01 | |
| A007 | 3'-0" | X 7'-0" | SF4 | SOLID CORE | P LAM | NR | 4 1/2" | ANOD AL | | 341 | | 22/A00-01 | 16/A00-01 | |
| A008 | 3'-0" | X 7'-0" | SF4 | SOLID CORE | P LAM | NR | 4 1/2" | ANOD AL | | 501C | | 22/A00-01 | 16/A00-01 | |
| A012 | 4'-0" | X 7'-0" | HM1 | H.M. | PAINT | NR | 6" | PAINT HM | | 715V | 21/A00-01 | 04/A00-01 | 04/A00-01 | |
| 109A | 3'-0" | X 7'-0" | SF4 | SOLID CORE | P LAM | NR | 4 1/2" | ANOD AL | | 501H | | 22/A00-01 | 16/A00-01 | |
| 109B | 3'-0" | X 7'-0" | SF1 | ALUM/GLASS | ANOD AL | NR | 4 1/2" | ANOD AL | | C201AH | 18/A00-01 | 10&11/A00-01 | 23&24/A00-01 | CARD READER, CLOSER, BUZZER |
| 109C | 3'-0" | X 7'-0" | SF1 | ALUM/GLASS | ANOD AL | NR | 4 1/2" | ANOD AL | | C201AH | 18/A00-01 | 10&11/A00-01 | 23&24/A00-01 | CARD READER, CLOSER, BUZZER |
| 109D | 3'-0" | X 7'-0" | SF4 | SOLID CORE | P LAM | NR | 4 1/2" | ANOD AL | | 501H | | 22/A00-01 | 16/A00-01 | |




## 2 DOOR SCHEDULE

## FLOOR PLAN - GENERAL NOTES

1. REFER TO SHEET FOR GENERAL NOTES. GENERAL NOTES APPLY TO ALL SCHOOL KITCHENS.
2. REFER TO SHEET FOR PARTITION TYPES.
3. EXIXSTING EXPOSED CONDUITS AND DATA CABLING IN WIREMOLD TO BE ROUTED INSIDE WALLS (EXCEPT AT WAREWASH AREA BELOW TABLE HEIGHT AND DRY STORAGE ROOMS). PATCH AND REPAIR AS REQUIRED TO ACHIEVE SMOOTH CLEAN WALL SURFACE.

## PARTITION LEGEND

- EXISTING CMU PARTITION
- NEW CMU SCHEDULED PARTITION
- EXISTING METAL PARTITION
- NEW FRAMED SCHEDULED PARTITION

## 3 FLOOR PLAN NOTES

## FLOOR PLAN - KEYED NOTES

(NOT ALL NOTES USED ON EACH SHEET)

01 PROVIDE NEW MOP SINK UTILITY SHELF
RE: PLUMBING FOR MOP SINK
RE: SPEC 10 28 00 FOR UTILITY SHELF

02 REMOVE, STORE & REPLACE WALL MOUNTED FIRE EXTINGUISHER

03 PROVIDE NEW WALL MOUNTED FIRE EXTINGUISHER
RE: SPEC SECTIONS 10 44 13

04 PROVIDE NEW LOCKERS
RE: SPEC 10 51 13.

05 PROVIDE WASHER AND DRYER
RE: SPEC 11 45 20

06 REMOVE, PROTECT & REINSTALL WALL MOUNTED CLOCK.

07 PROVIDE CONDENSING UNIT
FOR WALK-IN COOLER/FREEZER
RE: MECHANICAL AND SPEC 11 40 00


08 PROVIDE POWER AND DATA FOR MENU BOARD.
RE: ELECTRICAL, TECHNOLOGY DRAWINGS & FOOD SI

09 PROVIDE P-LAM SHELVING
REFER TO DETAIL FOR BRACKET SUPPORT

10 FURNITURE & NON FOOD SVE EQUIPMENT RETURN TC STORAGE


11 INSPECT & SREVICE TOLLING COUNTER DOORS. RETU NEW CONDITION.

12 COMMERCIAL CLOSED WASHER 40LB CAPACITY.
COMMERCIAL CLOSED DRYER 55LB CAPACITY.
BASIS OF DESIGN: WASHER; SPEED QUEEN SYN040
DRYER; SPEED QUEEN ST055.
REFER TO ELECTRICAL & PLUMBING FOR CONNECTIOI












## 1 KITCHEN PLAN

SCALE: 1/4" = 1'-0"





## 4 MAKERBOARD ELEVATION


SCALE: 1/2"=1'-0"




## 5 RAMP @ REAR DOOR

SCALE: 3/16"=1'-0"




## A

SCALE: 1/2"=1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

O

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL
REGISTERED ARCHITECT
KEVIN M. HAWKINS
42651
STATE OF TEXAS
7/15/2025



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

KITCHEN PLAN

o-A.301

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\O-Palmer ES\o-A 301 KITCHEN PLAN.dwg Jul 30, 2025 - 10:02am




## 3 TEMPORARY LAYOUT SECTION

SCALE: 1"=1'0"

### TEMPORARY KITCHEN FLOOR PLAN KEYED NOTES 05/A-A03-02

01 PROVIDE & INSTALL 555 SF OF RAM BOARD TO PROTECT EXISTING FLOORING. REMOVE AFTER CONSTRUCTION IS COMPLETE. CONTRACTOR MUST REPAIR FLOORING DAMAGED DURING CONSTRUCTION.

02 PROVIDE SCHEDULED PARTITIONS. BUILD PARTITIONS ON TOP OF RAM BOARD. DO NOT ATTACH PARTITIONS TO FLOOR.


03 ATTACH PARTITIONS TO EXISTING WALL. REPAIR WALL TO MATCH EXISTING AFTER CONSTRUCTION IS COMPLETE.

### TEMPORARY KITCHEN RCP KEYED NOTES 03/A-A03-02

04 ALL NEW SCHEDULED PARTITIONS AND CEILINGS FOR TEMPORARY STORAGE LAYOUT TO BE EPOXY PAINTED SW 7014 EIDER WHITE WITH SPECIFIED 4" RUBBER BASE. REMOVE WHEN CONSTRUCTION IS COMPLETED.

05 MOUNT TEMPORARY FLUORESCENT LIGHTS TO TEMPORARY CEILING.


## 4 KEYED NOTES




**STUDENT DINING**
400
4,793 SF

## 1 TEMPORARY KITCHEN RCP

SCALE: 1/4" = 1'-0"




**STUDENT DINING**
400
4,793 SF

## 2 TEMPORARY KITCHEN FLOOR PLAN

SCALE: 1/4" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

O

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT

PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL
7/15/2025

ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

TEMPORARY KITCHEN LAYOUT
o-A.302

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\O-Palmer ES\o-A.302 TEMPORARY KITCHEN LAYOUT.dwg Jul 23, 2025 - 4:26pm

## RCP - GENERAL NOTES


1. CEILING GRID SHALL BE INSTALLED TO MATCH EXISTING GRID'S POINT OF ORIGIN. THIS WILL REDUCE NEED TO RE-LOCATE ABOVE CEILING DUCTS, SPRINKLER PIPING AND OTHER SUPPORT SYSTEMS.
2. REFER TO SHEET A00-01 FOR GENERAL NOTES. GENERAL NOTES APPLY TO ALL SEVEN SCHOOL KITCHEN REMODELS.
3. LIGHTING LEVELS SHOULD BE 50 FC IN PREPARATION AREAS, WARE WASH AND SERVING LINES, OR MEET MINIMUM HEALTH CODE LEVELS, WHICHEVER ITS GREATER. SEE MEP PLANS
4. REPLACE HVAC DEVICES. REPLACE LIGHTING WITH 24"x24" LED LAY IN LIGHT AS SCHEDULED IN ELECTRICAL PLANS.
5. REFER TO MECHANICAL, ELECTRICAL SHEETS FOR DEVICE SCHEDULES.

## RCP - NUMBERED NOTES

(01) PROVIDE 30"x30" MIN. ACCESS HATCH IN SOFFIT CENTERED ON MOTOR.


(02) AFTER LOWERING THE NEW POWER RETRACTION SYSTEM. REPAIR AND PAINT SOFFITS AND SIDWALLS OF FURR TO MATCH EXISTING.

## 2 RCP GENERAL NOTES




## 3 FOOD SERVICE AREA ELEVATION

SCALE: 3/16" = 1'-0"




## 1 REFLECTED CEILING PLAN

SCALE: 1/4" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

o

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL
REGISTERED ARCHITECT
ROBERT L. MEYER
22651
STATE OF TEXAS
7/15/2025



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

REFLECTED CEILING PLAN

o-A.401

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\O-Palmer ES\o-A.401 REFLECTED CEILING PLAN.dwg, Jul 23, 2025 - 4:27pm




## 3 SHELF SECTION CUT
SCALE: 3"=1'-0"


### PAINT COLOR SCHEDULE
UNLESS OTHERWISE INDICATED FIELD COLOR IS PT-1 (SW 7014 EIDER WHITE)

SW 7014 EIDER WHITE (EPOXY PAINT)


### WALL TILE
CERAMIC WALL TILE (WT-1)
REFER TO TILE PATTERN AT SERVING AND RESTROOM
FIELD WALL TILE: DALTILE RITTENHOUSE SQUARE K175 BISCUIT (3X6)

A — PROVIDE ROOM SIGN TO REPLACE EXISTING. SEE LAYOUT FOR TYPE A OR TYPE B SIGN LOCATIONS.

## 2 FLOOR FINISH LEGEND





## 4 SHELF SECTION CUT
SCALE: 3"=1'-0"





NEW QUARRY TILE TO EXISTING VCT OR LVT FLOORING TRANSITION OCCURS AT CENTERLINE OF DOOR

## 5 FLOOR TRANSITION - THRESHOLD
SCALE: 3"=1'-0"





WALL TILE PATTERN - RESTROOM


## 6 WALL TILE PATTERN
SCALE: 1/4"=1'-0"




## 14 SILL @ KITCHEN/DINING
SCALE: 1:1





## TYPE A
ROOM SIGNAGE - FIXED NAMES





## TYPE B
KITCHEN RESTROOM SIGNAGE


## 7 ROOM SIGNAGE
SCALE: 6"-1'-0"





## 8 RR ELEVATIONS
SCALE: 1/4"=1'-0"





## 9 UTILITY ELEVATIONS
SCALE: 1/4"=1'-0"





## 10 STOREFRONT ELEVATIONS
SCALE: 1/4"=1'-0"





## 13 MOPSINK ELEVATIONS
SCALE: 1/4"=1'-0"




## 11 STOREFRONT SECTION
SCALE: 1/2"=1'-0"




## 12 LOCKER HOUSEKEEPING PAD
SCALE: 3"=1'-0"




## 1 FINISH FLOOR PLAN
SCALE: 1/4" = 1'-0"

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\O-Palmer ES\o-A.501 FINISH FLOOR PLAN.dwg Jul 23, 2025 - 4:27pm

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

O

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL

REGISTERED ARCHITECT — STATE OF TEXAS — 12651


7/15/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

FINISH FLOOR PLAN


o-A.501





PARTITION A
SCALE: 1-1/2" = 1'-0"





PARTITION B1
SCALE: 1-1/2" = 1'-0"





PARTITION B2
SCALE: 1-1/2" = 1'-0"




PARTITION B3
SCALE: 1-1/2" = 1'-0"




34




PARTITION B5
SCALE: 1-1/2" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |

0

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL

FOR
INTERIM REVIEW
AND NOT INTENDED FOR CONSTRUCTION, BIDDING OR PERMIT PURPOSES.


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 05/23/25

PARTITION SCHEDULE

o-A.502

## GENERAL NOTES

1. ALL CONCRETE SHALL TEST 4000 PSI AT 28 DAYS.
2. ALL CONCRETE REINFORCING BARS SHALL CONFORM TO ASTM A615 GRADE 60.
3. DETAILING AND FABRICATION OF CONCRETE REINFORCEMENT AND ACCESSORIES SHALL BE IN ACCORDANCE WITH ACI-315 LATEST EDITION.
4. LAP ALL CONTINUOUS REINFORCING BARS 50 DIAMETERS AT SPLICES, TEES, AND CORNERS.
5. THE USE OF HEAT TO FACILITATE THE BENDING OF REINFORCING BARS WILL NOT BE PERMITTED.
6. NO ENGINEERING DRAWING MAY BE REPRODUCED FOR USE AS SHOP DRAWINGS.
7. CONTRACTOR SHALL COORDINATE ALL LOCATIONS OF ALL ANCHOR BOLTS AND OPENINGS FOR MECHANICAL, PIPING, AND ELECTRICAL EQUIPMENT WITH THE RESPECTIVE ENGINEERING AND VENDOR DRAWINGS.

## SLAB NOTE


4" CONC. SLAB ON 10 MIL POLY FILM ON 2" MAX. SAND FILL. REINFORCE WITH #3 @ 15"c.c. E.W. IN CENTER OF SLAB.

## SLAB SIDEWALK SLAB NOTE

4" CONC. SLAB ON 2" MAX. SAND FILL. REINF. W/ #3 @ 18"c.c. IN CENTER OF SLAB.

## GEOTECHNICAL NOTE:

ALLOWABLE BEARING CAPACITY IS ASSUMED TO BE 1500 PSF AND SHALL BE CONFIRMED PRIOR TO CONSTRUCTION.




## FOUNDATION PLAN

SCALE: 1/4"=1'-0"

## FIELD VERIFICATION NOTE

1. CONTRACTOR SHALL VERIFY ALL DIMENSIONS PRIOR TO FABRICATION OR CONSTRUCTION.
2. CONTRACTOR SHALL VERIFY AND NOTIFY ENGINEER OF EXISTING CONDITIONS IN NEED OF REVIEW AND POSSIBLE MODIFICATION PRIOR TO FABRICATION.

ISSUE:

| | |
|---|---|
| 03/07/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



KEN STANLEY
69701
REGISTERED PROFESSIONAL ENGINEER
STATE OF TEXAS
*July 17, 2025*


STANLEY SPURLING & HAMILTON, INC.
50 Years
Consulting Engineering Services
T.B.P.E. Registration # F-000175
www.sshinc.net
3301 Edloe Street, Suite 200 Houston, Texas 77027 Tel 713-776-9433
E-MAIL: info@sshinc.net | 0002-0256



PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

KITCHEN PLAN


S1





1 SECTION
SCALE: 3/4"=1'-0"





2 SECTION
SCALE: 3/4"=1'-0"




3 SECTION
SCALE: 3/4"=1'-0"




4 SECTION
SCALE: 3/4"=1'-0"




## MIN. REBAR LAP SCHEDULE FOR f'm = 1,500 psi

| BAR SIZE | 6" CMU | 8" CMU | 10" CMU | 12" CMU |
|---|---|---|---|---|
| #3 | 12" | 12" | 12" | 12" |
| #4 | 20" | 15" | 12" | 12" |
| #5 | 32" | 23" | 18" | 15" |
| #6 | 54" | 43" | 34" | 28" |
| #7 | NA | 60" | 46" | 38" |
| #8 | NA | 72" | 71" | 57" |
| #9 | NA | NA | 82" | 74" |

## CONCRETE MASONRY NOTES

1. CONCRETE MASONRY UNITS AND CONSTRUCTION TO BE PER "NATIONAL CONCRETE MASONRY ASSOCIATION" RECOMMENDATIONS (WHERE NOT COVERED BY THE LOCAL BUILDING CODE).
2. ALL MASONRY GROUT TO BE PER TABLE 1 (THIS SHEET); ALL MORTAR PER TABLE 2 (THIS SHEET).
3. FILL CELLS WITH GROUT AT VERTICAL REINFORCEMENT.
4. CAST-IN-ANCHORS EMBEDDED IN CONCRETE MASONRY SHALL EXTEND BEYOND REINFORCING 1" MIN.
5. COMPRESSIVE STRENGTH OF MASONRY SHALL BE 1500 PSI AT 28 DAYS.
6. CMU SHALL BE PLACED IN A RUNNING BOND PATTERN UNLESS SPECIFICALLY NOTED OTHERWISE ON THE PLANS.
7. CONTROL JOINTS SHALL HAVE NO HORIZONTAL REINFORCING THROUGH THE JOINT AND VERTICAL REINFORCING ON BOTH SIDES OF JOINT. CONTROL JOINTS SHALL BE UNGROUTED WITH A BACKER ROD AND SEALANT ON BOTH SIDES OF WALL.
8. BOND BEAMS AND REINFORCING SHALL BE CONTINUOUS AT CONTROL JOINT WITH BACKER ROD AND SEALANT CONTINUOUS WITH JOINT.

## CONCRETE BLOCK LINTEL SCHEDULE

| WALL THICKNESS \ MAXIMUM SPAN | 4'-6" | 9'-0" |
|---|---|---|
| 4" | GROUT, 1 COURSE 1~#4 CONT. | #3 STIRRUPS @ 16" c.c., GROUT 2 COURSES, 1~#4 CONT. |
| 6" & 8" & 12" | GROUT, 1 COURSE 2~#5 CONT. | #3 STIRRUPS @ 16" c.c., GROUT 2 COURSES, 2~#5 CONT. TOP & BOT. |

## TABLE 1. GROUT PROPORTIONS BY VOLUME

| TYPE | PARTS BY VOLUME OF PORTLAND CEMENT OR PORTLAND BLAST-FURNACE SLAG CEMENT | PARTS BY VOLUME OF HYDRATED LIME OR LIME PUTTY | AGGREGATE MEASURED IN DAMP, LOOSE CONDITION | |
|---|---|---|---|---|
| | | | FINE | COARSE |
| FINE GROUT (<4" WIDE CAVITY) | 1 | 0 TO 1/10 | 2¼ TO 3 TIMES THE SUM OF THE VOLUMES OF THE CEMENTITIOUS MATERIAL | |
| COARSE GROUT (>4" WIDE CAVITY) | 1 | 0 TO 1/10 | 2¼ TO 3 TIMES THE SUM OF THE VOLUMES OF THE CEMENTITIOUS MATERIAL | 1 TO 2 TIMES THE SUM OF THE VOLUMES OF THE CEMENTITIOUS MATERIAL |

## TABLE 2. MORTAR PROPORTIONS BY VOLUME

| MATERIAL | TYPE | PORTLAND CEMENT OR BLENDED CEMENT | MASONRY CEMENT | HYDRATED LIME OR LIME PUTTY | AGGREGATE RATIO (MEASURE IN DAMP, LOOSE CONDITION) |
|---|---|---|---|---|---|
| CEMENT LIME | S | 1 | .... | OVER ¼ TO ½ | NOT LESS THAN 2¼ & NOT MORE THAN 3 TIMES THE SUM OF THE SEPARATE VOLUMES OF CEMENTITIOUS MATERIALS |
| MASONRY CEMENT | S | 1/2 | 1 | .... | |

## LOOSE LINTEL SCHEDULE

| SPAN | LINTEL | SPAN | LINTEL |
|---|---|---|---|
| 0' TO 6' | L3½x3½x¼ | 8' TO 9' | L5x3½x5/16 |
| 6' TO 7' | L4x3½"x¼ | 9' TO 10' | L6x3½x5/16 |
| 7' TO 8' | L4x3½x5/16 | 10' TO 12' | L7x4x⅜ |


LOOSE LINTEL MIN. BEARING OF 8".

**NOTE: CONTROL JOINTS SHALL BE LOCATED AT THE FOLLOWING**

1. AT ALL CHANGES IN WALL HEIGHT.
2. AT ALL CHANGES IN WALL THICKNESS SUCH AS CHASES, COLUMNS OR PILASTERS.
3. AT (ABOVE) MOVEMENT JOINTS IN FOUNDATIONS AND FLOORS.
4. AT (BELOW) MOVEMENT JOINTS IN ROOFS AND FLOORS THAT BEAR ON A WALL.
5. ADJACENT TO CORNERS OF WALLS OR INTERSECTIONS WITHIN A DISTANCE OF ONE-HALF THE NORMAL CONTROL JOINT SPACING.
6. CONTROL JOINTS SHALL BE SPACED NO MORE THAN 25'-0" APART.
7. DO NOT PLACE CONTROL JOINT ABOVE OR BELOW OPENINGS.
8. CONTRACTOR SHALL PROVIDE A CONTROL JOINT PLAN PRIOR TO FABRICATION OR CONSTRUCTION.

## TYPICAL ELEVATION OF CONCRETE MASONRY WALL AND NOTES

SCALE: N.T.S.




CONTRACTOR SHALL COVER ALL EXPOSED REBAR DURING CONSTRUCTION.

## TYPICAL REBAR CAP DETAIL

SCALE: N.T.S.

ISSUE:

| | |
|---|---|
| 03/07/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

SECTIONS AND TYPICAL DETAILS

S2




*July 17, 2025*


STANLEY SPURLING & HAMILTON, INC.
Consulting Engineering Services
T.B.P.E. Registration # F-000175
www.sshinc.net
50 Years
3301 Edloe Street, Suite 200 Houston, Texas 77027 Tel 713-776-9433
E-MAIL: info@sshinc.net | 0002-0256

# REFER TO FOODSERVICE DESIGN PROFESSIONALS SPECIFICATIONS AND SUBSEQUENT SHEETS FOR ADDITIONAL COORDINATION INFORMATION

**EXISTING EQUIPMENT NOTES (IF EXISTING EQUIPMENT IS PROVIDED IN THIS PROJECT):**

1. EXISTING EQUIPMENT NOT SCHEDULED FOR RE-USE TO BE RELOCATED BY THE K.E.C. COORDINATE WITH OWNER FOR NEW LOCATION.
2. ALL UTILITIES NOT SCHEDULED FOR RE-USE TO BE CAPPED & COVERED BY REQUIRED DISCIPLINE.
3. K.E.C. TO VERIFY ALL EXISTING UTILITY LOCATIONS & COORDINATE WITH ALL EQUIPMENT AS REQUIRED.

8 EXISTING EQUIPMENT NOTES
NOT TO SCALE

**ARCHITECT TO VERIFY/COORDINATE THE AESTHETIC OPTIONS BELOW (FOOD SERVICE COLOR, MATERIAL, OR SIGNAGE SELECTIONS) IF THESE ITEMS ARE PROVIDED IN THIS PROJECT:**

1. COUNTERTOPS: STONE (STAINLESS STEEL IS PROVIDED UNLESS OTHERWISE SPECIFIED).
2. TRAY SLIDES: CORIAN OR STONE (STAINLESS STEEL IS PROVIDED UNLESS OTHERWISE SPECIFIED).
3. COUNTER FRONTS: CERAMIC TILE, 3 FORM, OR PLASTIC LAMINATE.
4. SNEEZE GUARDS: STONE INSETS.
5. GENERAL COLOR, MATERIAL AND GRAPHIC SELECTIONS:
   - A. DISPLAY AIR SCREEN MERCHANDISERS - COLOR SELECTION: POWDER COAT OR PLASTIC LAMINATE (S/S IS PROVIDED UNLESS OTHERWISE SPECIFIED).
   - B. BAKERY DISPLAY CASES - COLOR SELECTION: POWDER COAT OR PLASTIC LAMINATE (S/S IS PROVIDED UNLESS OTHERWISE SPECIFIED).
   - C. PASS THRU OR REACH IN HOLDING CABINETS - COLOR SELECTION: POWDER COAT (MFG.: TRUE) OR PLASTIC LAMINATE (MFG.: TRAULSEN) (S/S IS PROVIDED UNLESS OTHERWISE SPECIFIED).
   - D. HANGING HEAT LAMPS - TRACK AND FIXTURE COLOR SELECTION.
   - E. HEATED MERCHANDISERS.
   - F. PORTABLE GUIDE RAILS - STANCHION AND BELT COLOR SELECTION.
   - G. POPCORN MACHINE - SIGNAGE SELECTION.
   - H. BOTTLE COOLER - SIGNAGE SELECTION.
   - I. GRAPHICS PACKAGE INFORMATION.
   - J. HOT FOOD WELL COVERS.
6. ARCHITECT TO VERIFY/COORDINATE THE FINISHES BELOW:
   - A. WALLS: CERAMIC TILE, FLAT FRP, OR MOLDED FRP (SMOOTH, IMPERVIOUS, AND EASILY CLEANABLE AS APPROVED BY LOCAL JURISDICTION).
   - B. CEILINGS: REMOVABLE VINYL FACE TILE (SMOOTH, IMPERVIOUS, AND EASILY CLEANABLE AS APPROVED BY LOCAL JURISDICTION).
   - C. FLOORS: TILE, EPOXY, OR RUBBERIZED FLOORING SYSTEM (SMOOTH, IMPERVIOUS, EASILY CLEANABLE AND SLIP RESISTANT AS APPROVED BY LOCAL JURISDICTION) (COORDINATE FLOOR TILE TRANSITION AT SERVING LINES).
   - D. FLOORS: WALK-IN ASSEMBLY - EXTEND KITCHEN FLOOR FLUSH INTO WALK-IN ASSEMBLY WITH COVED BASE.
   - E. FURR DOWNS ABOVE SERVING COUNTERS.

5 ARCHITECTURAL COORDINATION NOTES
NOT TO SCALE

**CRITICAL NOTES:**

1. CONTRACTOR MUST COORDINATE AND VERIFY ALL DIMENSIONS WITH FOOD SERVICE EQUIPMENT SHOP DRAWINGS AND MANUFACTURER'S DATA. DIMENSIONS SHOWN ARE FOR DESIGN AND BIDDING PURPOSES ONLY.
2. WALK-IN ASSEMBLY DOORS MUST BE LEFT OPEN WHILE INTERIOR CONCRETE FLOOR CURES.
3. INSTALL PROTECTIVE COVER ON WALK-IN ASSEMBLY WALL PANELS BEFORE INSTALLING CONCRETE FLOORS AND CURBS.
4. REFER TO GENERAL SPECS - DIVISION 27 TO PROVIDE CONDUIT, DATA, AND INTERCONNECT THE PANIC ALARM INSIDE FREEZER TO THE BUILDING AUTOMATION SYSTEM FOR NOTIFICATION TO DISTRICT PERSONNEL IN THE EVENT OF STAFF ENTRAPMENT.
5. PIPING AND DRAINAGE SYSTEMS (SANITARY AND GREASE-LADEN). SYSTEMS MUST BE CLEANED AND FLUSHED BEFORE THE FINAL CONNECTION WITH FOOD SERVICE EQUIPMENT - CRITICAL (DIV. 22).

7 CRITICAL NOTES
NOT TO SCALE

**DIVISION 26 (ELECTRICAL) IS RESPONSIBLE FOR BUT NOT LIMITED TO:**

1. **DO NOT ROUGH IN FROM FDP DRAWINGS. REFER TO THE KITCHEN EQUIPMENT CONTRACTOR'S DIMENSIONED SHOP DRAWINGS. DIMENSIONS INDICATED ARE TO BE VERIFIED BY KITCHEN EQUIPMENT CONTRACTOR AND ADJUSTED AS REQUIRED BY EQUIPMENT AND FIELD CONDITIONS.**
2. SECTION 11 40 00 TO VERIFY UTILITY REQUIREMENTS OF ANY EXISTING EQUIPMENT.
3. ALL CONNECTIONS SHALL BE MADE FOLLOWING LOCAL CODES AND NATIONAL STANDARDS, EXCEPT WHERE PLANS AND SPECIFICATIONS EXCEED THOSE CODES AND STANDARDS.
4. VERIFY ALL ELECTRICAL REQUIREMENTS WITH ENGINEERING DRAWINGS.
5. ROUGH-IN AND FINAL CONNECTION OF ELECTRICAL SYSTEMS TO FOOD SERVICE EQUIPMENT, WALK-IN ASSEMBLIES, AND BETWEEN COMPONENTS (INCLUDING MATERIALS AND LABOR). ACCESSORIES PROVIDED LOOSE WITH FOOD SERVICE EQUIPMENT BY SECTION 11 40 00 TO BE FIELD INSTALLED BY DIVISION 26.
6. EMPTY EMT CONDUIT WITH PULL-WIRE AND WIDE-SWEEP BENDS FOR REFRIGERANT PIPING TO REMOTE FOOD SERVICE EQUIPMENT REFRIGERATION SYSTEMS.
7. EMPTY EMT CONDUIT WITH PULL-WIRE AND WIDE-SWEEP BENDS FOR INTERCONNECT CABLES BETWEEN LAN AND POS TERMINALS, CHANGE-MAKERS, PRE-CHECK UNITS, PRINTERS, CPUS, ETC. DIVISION 26 TO VERIFY WHERE THE CONDUIT IS TO RUN FOR POS SYSTEM (I.E., MANAGER'S OFFICE OR IDF ROOM).
8. EMPTY EMT CONDUIT WITH PULL-WIRE AND WIDE-SWEEP BENDS FOR FIRE SUPPRESSION SYSTEMS. INTERCONNECT FIRE PROTECTION SYSTEM TO PANEL BOX SHUNT TRIPS AND BUILDING ALARM.
9. WALK-IN LIGHT FIXTURE INSTALLATION (PROVIDED LOOSE BY SECTION 11 40 00) (IF WALK-IN IS PROVIDED IN THIS PROJECT).
10. TABLE LIMIT SWITCH INSTALLATION (PROVIDED LOOSE BY SECTION 11 40 00) (IF DISHMACHINE IS PROVIDED IN THIS PROJECT).
11. ELECTRICAL MATERIALS AND DEVICES (SHUNT-TRIP BREAKERS, SURGE PROTECTORS, LIGHTING CONTROL DEVICES, CONDUIT, WIRE, ETC.).
12. SWITCHES AND STAINLESS STEEL DISCONNECTS AS REQUIRED (PROVIDE, LOCATE, AND INSTALL – TO BE IN AN ACCESSIBLE LOCATION).
13. CHARGING STATIONS FOR FORKLIFTS, PALLET STACKERS, AND PALLET JACKS (SIZE, PROVIDE, LOCATE, AND INSTALL) (IF EQUIPMENT IS PROVIDED IN THIS PROJECT).
14. INTERCONNECTION BETWEEN CONDENSATE FAN AND DISHMACHINE CONTROL PANEL (IF EQUIPMENT IS PROVIDED IN THIS PROJECT).
15. INTERCONNECTION BETWEEN EXHAUST HOOD FANS AND SWITCH (IF EQUIPMENT IS PROVIDED IN THIS PROJECT).
16. INTERCONNECTION BETWEEN EXHAUST HOOD LIGHTS AND SWITCH (IF EQUIPMENT IS PROVIDED IN THIS PROJECT).
17. DOOR HEATERS, LIGHTS, COILS, AND PRESSURE RELIEF PORTS PRE-WIRED TO JUNCTION BOX AT TOP OF WALK-IN ASSEMBLIES (IF EQUIPMENT IS PROVIDED IN THIS PROJECT) PROVIDED BY SECTION 11 40 00. FINAL CONNECTION BY DIV. 26.
18. IF ANY ELECTRICAL ACCESSORIES, FITTINGS, AND CORD/PLUGS ARE PROVIDED LOOSE WITH EQUIPMENT BY 11 40 00, DIV.26 IS TO ATTACH TO EQUIPMENT AND PROVIDE FINAL CONNECTION.
19. PROVIDE WATERPROOF RECEPTACLES IN WET AREAS.
20. ALL ELECTRICAL CONNECTIONS BENEATH EXHAUST HOODS (IF EQUIPMENT IS PROVIDED IN THIS PROJECT) TO EXTEND TO SHUNT TRIP BREAKERS WITH ELECTRICAL PANEL BOX FOR SHUTDOWN DURING FIRE MODE.
21. RECEPTACLES ARE TO BE PRE-WIRED TO THE JUNCTION BOX OR LOAD CENTER FOR FINAL CONNECTION BY DIVISION 26.
22. ALL ELECTRICAL LIGHTING, POWER, AND DISTRIBUTION SYSTEMS.
23. DO NOT INTERCONNECT MORE THAN THREE (3) CONVENIENCE OUTLETS ON ONE (1) BREAKER.
24. OTHER THAN CONVENIENCE OUTLETS, ALL ELECTRICAL CONNECTIONS SHOWN ON FOOD SERVICE PLANS ARE DEDICATED BREAKERS.
25. DOORBELL AT RECEIVING DOOR (PROVIDE AND INSTALL – TO BE AUDIBLE THROUGHOUT KITCHEN, OFFICE, AND DRY STORAGE ROOM).
26. ADEQUATE LIGHTING AT RECEIVING DOOR.
27. PROVIDE AND INSTALL TWO EMERGENCY STROBE BEACONS THAT INTERCONNECT TO PANIC ALARM IN WALK-IN FREEZER. ONE (1) IN KITCHEN ABOVE WALK-IN FREEZER DOOR ONE (1) IN CAFETORIUM (IF WALK-IN IS PROVIDED IN THIS PROJECT). REFER TO GENERAL SPECIFICATIONS FOR ADDITIONAL DETAILS.
28. DEDICATED CIRCUIT FOR HEATED DRAIN LINE CONNECTION IN WALK-IN FREEZER AT EACH COIL (IF WALK-IN IS PROVIDED IN THIS PROJECT).

**NOTE: ELECTRICAL CONNECTIONS INDICATED ARE THOSE REQUIRED FOR THE FOOD SERVICE EQUIPMENT AND THOSE REQUIRED FOR SUPPORT EQUIPMENT FURNISHED BY DIVISION 26. FOR ADDITIONAL REQUIREMENTS, REFER TO THE ELECTRICAL ENGINEER'S DRAWINGS.**

6 ELECTRICAL COORDINATION NOTES
NOT TO SCALE

**DIVISION 22 (PLUMBING) RESPONSIBLE FOR BUT NOT LIMITED TO:**

1. **DO NOT ROUGH-IN FROM FDP DRAWINGS. REFER TO THE KITCHEN EQUIPMENT CONTRACTOR'S DIMENSIONED SHOP DRAWINGS. DIMENSIONS INDICATED ARE TO BE VERIFIED BY KITCHEN EQUIPMENT CONTRACTOR AND ADJUSTED AS REQUIRED BY EQUIPMENT AND/OR FIELD CONDITIONS.**
2. SECTION 11 40 00 TO VERIFY UTILITY REQUIREMENTS OF ANY EXISTING EQUIPMENT.
3. ALL CONNECTIONS SHALL BE MADE IN ACCORDANCE WITH LOCAL CODES AND NATIONAL STANDARDS, EXCEPT WHERE PLANS AND SPECIFICATIONS EXCEED THOSE CODES AND STANDARDS.
4. VERIFY ALL PLUMBING REQUIREMENTS WITH ENGINEERING DRAWINGS.
5. EMPTY PVC CONDUIT WITH WIDE-SWEEP BENDS FOR REFRIGERANT PIPING TO BEVERAGE LINES, CO2 LINES, AND REMOTE FOOD SERVICE EQUIPMENT REFRIGERATION SYSTEMS.
6. ROUGH-IN AND FINAL PLUMBING CONNECTIONS TO FOOD SERVICE EQUIPMENT AND BETWEEN COMPONENTS (INCLUDING MATERIALS AND LABOR). ACCESSORIES PROVIDED LOOSE WITH FOOD SERVICE EQUIPMENT BY SECTION 11 40 00 TO BE FIELD INSTALLED BY DIVISION 22. THIS INCLUDES BUT IS NOT LIMITED TO INSTALLATION OF ALL FAUCETS (WATER FILL FAUCETS, PRE-RINSE FAUCETS, ETC.), HOSES, GAS DISCONNECTS, AND DRAINS FROM EQUIPMENT POINT OF CONNECTION TO BUILDING PLUMBING SYSTEMS. ALL DRAIN LINES ARE PROVIDED AND INSTALLED BY DIV. 22.
7. KITCHEN EQUIPMENT CONTRACTOR IS RESPONSIBLE FOR PROVIDING ALL FAUCETS (WATER FILL FAUCETS, PRE-RINSE FAUCETS, ETC.), DRAIN FITTINGS, MIXING VALVES, CONTROL VALVES, WATER PRESSURE REGULATORS, VACUUM BREAKERS, AND ALL ACCESSORIES FOR EQUIPMENT SPECIFIED UNDER 11 40 00. DIVISION 22 IS RESPONSIBLE FOR INSTALLATION.
8. INDIRECT DRAIN LINE RUNS FROM EQUIPMENT TO NEAREST DRAIN OR FLOOR SINK. LINES TO BE TYPE 'K' COPPER.
9. IF ANY PLUMBING ACCESSORIES OR FITTINGS ARE PROVIDED LOOSE WITH EQUIPMENT BY 11 40 00, DIV. 22 IS TO ATTACH TO EQUIPMENT AND PROVIDE FINAL CONNECTION.
10. GAS SUPPLY SYSTEMS WITH ALL COMPONENTS AND FITTINGS AS REQUIRED FOR A COMPLETE SYSTEM.
11. WATER SUPPLY SYSTEMS WITH ALL COMPONENTS AND FITTINGS AS REQUIRED FOR A COMPLETE SYSTEM.
12. COMPRESSED AIR SYSTEMS WITH ALL COMPONENTS AND FITTINGS AS REQUIRED FOR A COMPLETE SYSTEM (IF REQUIRED FOR THIS PROJECT).
13. PIPING AND DRAINAGE SYSTEMS (SANITARY AND GREASE-LADEN). SYSTEMS MUST BE CLEANED AND FLUSHED BEFORE THE FINAL CONNECTION WITH FOOD SERVICE EQUIPMENT - CRITICAL.
14. FLOOR SINKS (PROVIDE AND INSTALL). FLANGE AND GRATES TO BE FLUSH WITH FINISHED FLOOR.
15. FLOOR DRAINS (PROVIDE AND INSTALL). FLANGE AND GRATES TO BE FLUSH WITH FINISHED FLOOR.
16. TRENCH DRAINS (PROVIDE AND INSTALL). TRENCH LINERS PROVIDED BY 11 40 00. FLANGE AND LINERS TO BE FLUSH WITH FINISHED FLOOR.
17. GREASE TRAPS AS REQUIRED. VERIFY WITH LOCAL CODES TO BYPASS OR PIPE THRU GREASE TRAP AND/OR INTERCEPTOR.
18. P-TRAPS AS REQUIRED (INCLUDING ALL DISPOSERS).
19. INTERCONNECT WATER THRU WATER FILTER (FILTER PROVIDED BY 11 40 00 UNLESS OTHERWISE SPECIFIED) TO EQUIPMENT.
20. GAS QUICK DISCONNECT INSTALLATION (QUICK DISCONNECT PROVIDED BY 11 40 00).
21. SAFETY RESTRAINT CABLE INSTALLATION (SAFETY RESTRAINT CABLE PROVIDED BY 11 40 00).
22. SPECIFIED COUPLINGS AND PIPING TO ALL EQUIPMENT FURNISHED BY 11 40 00.
23. AIR COMPRESSORS (IF REQUIRED FOR THIS PROJECT) (SIZE, PROVIDE, AND INSTALL, UNLESS OTHERWISE SPECIFIED).
24. WATER SOFTENERS (IF REQUIRED FOR THIS PROJECT) (SIZE, PROVIDE, AND INSTALL, UNLESS OTHERWISE SPECIFIED).
25. PRESSURE BOILERS (IF REQUIRED FOR THIS PROJECT) (SIZE, PROVIDE, AND INSTALL, UNLESS OTHERWISE SPECIFIED).
26. HAND SINKS (PROVIDE (UNLESS OTHERWISE SPECIFIED) AND INSTALL). PROVIDE HOT WATER TEMPERING VALVE IF REQUIRED. WATER TEMPERATURE TO BE AT LEAST 100 DEGREES AND FLOW FOR AT LEAST 20 SECONDS.
27. ICE BIN DRAIN INSULATION (IF ICE MACHINE IS PROVIDED IN THIS PROJECT) (PROVIDE AND INSTALL).
28. UNIONS AT DISPOSER SOLENOID VALVES (IF DISPOSER IS PROVIDED IN THIS PROJECT) (PROVIDE AND INSTALL).
29. BACK FLOW PREVENTION AS REQUIRED (PROVIDE AND INSTALL - INCLUDING ALL DISPOSERS). BACK- SIPHONAGE SHALL BE INSTALLED AT ALL FIXTURES AND EQUIPMENT WHERE BACKFLOW AND/OR BACK-SIPHONAGE MAY OCCUR AND WHERE A MINIMUM AIR GAP CANNOT BE PROVIDED BETWEEN THE WATER TO THE FIXTURE OR EQUIPMENT AT ITS FLOOD/LEVEL RIM. VACUUM BREAKERS, WHEN FURNISHED WITH EQUIPMENT, SHALL OVERRIDE THE ABOVE, IF ACCEPTABLE WITH APPLICABLE CODES. DIVISION 22 RESPONSIBLE FOR VERIFYING REQUIREMENT WITH LOCAL CODES.
30. JANITOR SINK WITH FAUCET (PROVIDE AND INSTALL).
31. FREEZE PROOF HYDRANT AT EXTERIOR OF BUILDING BY RECEIVING DOOR (PROVIDE AND INSTALL).
32. REVERSE OSMOSIS SYSTEMS (SIZE, PROVIDE (UNLESS OTHERWISE SPECIFIED), LOCATE AND INSTALL).
33. ALL PIPING WITHIN COUNTER BODY OR UNDER FABRICATED COUNTERS TO BE RUN TO A CONNECTION POINT BELOW COUNTER BODY BY SECTION 11 40 00. FINAL CONNECTION BY DIVISION 22.
34. EXHAUST HOOD CONDENSATE DRAIN CONNECTIONS (IF EXHAUST HOOD IS PROVIDED IN THIS PROJECT) (PROVIDE AND INSTALL).
35. INTERCONNECTION OF 1/2" CW TO PRE-RINSE AND DISPOSERS CONE/BODY INLETS PIPED THROUGH SOLENOID AND VACUUM BREAKER (IF DISPOSER IS PROVIDED IN THIS PROJECT).
36. FIRE SYSTEM PIPING. EXPOSED PIPING TO BE CHROME PLATED.
37. PIPE 1/2" COLD WATER TO SWIRL INLETS AT DISPOSERS (IF DISPOSER IS PROVIDED IN THIS PROJECT).
38. WATER TREATMENT FOR ICE BUILDERS (NON-CHLORINATED WATER WITH A PH LEVEL OF 10 OR HIGHER) AND ANY DRAINS AND OVERFLOWS. PIPING FROM ICE BUILDERS TO TUMBLE CHILLERS BY DIV. 23 (IF ICE BUILDERS AND TUMBLE CHILLERS ARE PROVIDED IN THIS PROJECT).

**NOTE: WATER AND DRAIN CONNECTIONS INDICATED ARE THOSE REQUIRED FOR THE FOOD SERVICE EQUIPMENT AND THOSE REQUIRED FOR SUPPORT EQUIPMENT FURNISHED BY DIVISION 22. FOR ADDITIONAL WATER AND DRAIN REQUIREMENTS REFER TO MECHANICAL DRAWINGS.**

**NOTE: REFER TO ELECTRICAL/MECHANICAL DRAWINGS FOR REQUIREMENTS OF EXHAUST FANS AND MAKE-UP AIR HANDLERS AND LOCATION OF AN INTERLOCK AND START/STOP CONTROLS TO BE LOCATED WITHIN FOOD SERVICE AREA BY DIVISION 26.**

4 PLUMBING COORDINATION NOTES
NOT TO SCALE

**DIVISION 23 (MECHANICAL) RESPONSIBLE FOR BUT NOT LIMITED TO:**

1. **DO NOT ROUGH-IN FROM FDP DRAWINGS. REFER TO THE KITCHEN EQUIPMENT CONTRACTOR'S DIMENSIONED SHOP DRAWINGS. DIMENSIONS INDICATED ARE TO BE VERIFIED BY KITCHEN EQUIPMENT CONTRACTOR AND ADJUSTED AS REQUIRED BY EQUIPMENT AND/OR FIELD CONDITIONS.**
2. SECTION 11 40 00 TO VERIFY UTILITY REQUIREMENTS OF ANY EXISTING EQUIPMENT.
3. ALL CONNECTIONS SHALL BE MADE FOLLOWING LOCAL CODES AND NATIONAL STANDARDS, EXCEPT WHERE PLANS AND SPECIFICATIONS EXCEED THOSE CODES AND STANDARDS.
4. VERIFY ALL MECHANICAL REQUIREMENTS WITH ENGINEERING DRAWINGS.
5. EMPTY EMT CONDUIT WITH PULL-WIRE AND WIDE-SWEEP BENDS FOR REFRIGERANT PIPING TO REMOTE FOOD SERVICE EQUIPMENT REFRIGERATION SYSTEMS.
6. ROUGH-IN AND FINAL CONNECTION OF MECHANICAL SYSTEMS TO FOOD SERVICE EQUIPMENT, WALK-IN ASSEMBLIES, AND BETWEEN COMPONENTS (INCLUDING MATERIALS AND LABOR).
7. TESTING AND BALANCING FOR ROOMS AND EXHAUST HOODS TO BE PERFORMED BY MECHANICAL CONTRACTOR. BALANCE REPORT FOR FOOD SERVICE EXHAUST HOODS TO BE PROVIDED TO FOODSERVICE DESIGN PROFESSIONALS (FDP) IMMEDIATELY UPON COMPLETION (SEND TO HOUSTON.SUBMITTAL@FDP.ORG FOR HOUSTON OFFICE AND DALLAS.SUBMITTAL@FDP.ORG FOR DALLAS OFFICE) AND MUST BE SUBMITTED WITH O&M MANUALS.
8. EXHAUST HOODS, CONDENSATE HOODS, FIRE SUPPRESSION SYSTEMS, CONNECTIONS AND CONTROLS (PROVIDE AND INSTALL – *UNLESS OTHERWISE SPECIFIED*). PROVIDE TEMPERED AIR AT ALL SUPPLY DUCTS.
   - A. IF EXHAUST/CONDENSATE HOODS AND FIRE SUPPRESSION SYSTEMS ARE SPECIFIED UNDER SECTION 11 40 00, DIVISION 23 IS RESPONSIBLE FOR ALL EXHAUST AND CONDENSATE HOOD CONNECTIONS (PROVIDE AND INSTALL).
9. VFD SYSTEM AND CONTROLLERS, WHEN REQUIRED BY CODE (PROVIDE AND INSTALL).
10. PROVIDE AND INSTALL ALL VENTILATION (DIRECT OR INDIRECT), AIR CONDITIONING AND HEATING SYSTEMS (UNLESS OTHERWISE SPECIFIED).
11. COORDINATE SUPPLY AND RETURN DUCTS ABOVE SERVING COUNTERS OR OPEN-AIR REFRIGERATED MERCHANDISERS. NO COLD AIR TO BLOW DIRECTLY ON HOT FOOD COUNTERS.
12. COORDINATE SUPPLY AND RETURN DUCTS AWAY FROM EQUIPMENT WITH TOP MOUNTED REFRIGERATION. NO COLD AIR TO BLOW DIRECTLY ON COMPRESSORS.
13. MECHANICAL CONTRACTOR TO LOCATE TEMPERATURE MONITORS WITHIN RETURN DUCTS.
14. CIRCULATING AIR ABOVE WALK-IN ASSEMBLIES (PROVIDE AND INSTALL).
15. CIRCULATING AIR ABOVE AND IN AIR GAPS AT WAREHOUSE COLD STORAGE ASSEMBLIES (PROVIDE AND INSTALL).
16. WATER CHILLERS AS REQUIRED (IF EQUIPMENT IS PROVIDED IN THIS PROJECT) (PROVIDE, SIZE AND LOCATE).
17. PIPING FROM ICE BUILDERS TO TUMBLE CHILLERS (IF EQUIPMENT IS PROVIDED IN THIS PROJECT) (PROVIDE, SIZE AND LOCATE).

3 MECHANICAL COORDINATION NOTES
NOT TO SCALE

**GENERAL CONTRACTOR RESPONSIBLE FOR BUT NOT LIMITED TO:**

1. ANY WALL PENETRATION REQUIRED FOR FOOD SERVICE EQUIPMENT UTILITIES. ESCUTCHEON PLATES OR S/S SLEEVES TO BE PROVIDED AND INSTALLED AS NEEDED.
2. BULK FREEZER VENTILATION PIPE (IF BULK FREEZER IS PROVIDED IN THIS PROJECT) (PROVIDE AND INSTALL, UNLESS OTHERWISE SPECIFIED).
3. CORE DRILLING FOR GUIDE RAILS (IF GUIDE RAILS ARE PROVIDED IN THIS PROJECT).
4. REFRIGERATION ROOF CURBS / ROOF JACK (IF REFRIGERATION SYSTEM IS PROVIDED IN THIS PROJECT AND LOCATED ON ROOF).
5. INTERIOR BOLLARDS (IF REQUIRED FOR THIS PROJECT) – TO BE EPOXY PAINTED PER LOCAL CODES (PROVIDE AND INSTALL).
6. FURNISH AND INSTALL 3/4" PLYWOOD BLOCKING IN THE WALL FOR MOUNTING EQUIPMENT FURNISHED BY SECTION 11 40 00 AS REQUIRED.
7. WALK-IN DEPRESSIONS (TO BE DEAD LEVEL) AND SAND LEVELING BED (IF WALK-IN IS PROVIDED IN THIS PROJECT AND RECESS IS SHOWN).
8. STRUCTURAL BRACING FOR BULK WALK-IN CEILING PANELS IF REQUIRED.
9. MENU SYSTEM VIDEO MONITORS IN SERVERY (UNLESS OTHERWISE SPECIFIED).
10. STRUCTURAL BRACING FOR MENU SYSTEM VIDEO MONITORS IF REQUIRED.
11. INTERIOR/EXTERIOR REFRIGERATION PENETRATIONS AND SLEEVES AT BUILDING PENETRATIONS.
12. DOORSCOPE VIEWER (PEEPHOLE) WITH WIDE VIEWING ANGLE AT RECEIVING DOOR.
13. CANOPY AT RECEIVING DOOR. COORDINATE HEIGHT WITH THE HEIGHT OF RECEIVING DOOR (8') AND THE MOUNTING HEIGHT OF AIR SCREEN ABOVE THE DOOR.
14. SOAP AND TOWEL DISPENSER PROVIDED BY OWNER. G.C. RESPONSIBLE FOR INSTALLATION.
15. WASHER AND DRYER (PROVIDE AND INSTALL, UNLESS OTHERWISE SPECIFIED).
16. DWARF WALL AT EXPOSED FRONT/ENDS OF CAFETERIA SERVING COUNTERS WITH FINISH AS SELECTED BY ARCHITECT (IF REQUIRED IN THIS PROJECT).

2 GENERAL CONTRACTOR COORDINATION NOTES
NOT TO SCALE

**HEALTH DEPARTMENT REQUIREMENTS (VERIFY WITH LOCAL JURISDICTIONS):**

1. FLOORS: VERIFY WITH DIVISION 9. FLOORS TO BE SMOOTH, IMPERVIOUS, EASILY CLEANABLE AND SLIP RESISTANT.
2. WALLS: VERIFY WITH ARCHITECTURAL DOCUMENTS. WALLS TO BE SMOOTH, IMPERVIOUS, AND EASILY CLEANABLE.
3. CEILING: LAY-IN TILES. CEILING TILES TO BE SMOOTH, IMPERVIOUS, AND EASILY CLEANABLE.
4. EMPLOYEE TOILET: TO BE LOCATED OFF MAIN CORRIDOR AND ADJACENT TO MAIN KITCHEN. RESTROOM MUST HAVE A VESTIBULE AND NOT OPEN TO KITCHEN / PREP AREAS. TOILETS TO BE WELL VENTILATED.
5. LAVATORIES: WALL HUNG LAVATORIES LOCATED WITHIN ALL FUNCTIONAL WORKING AREAS.
6. UTENSIL CLEANING/SANITIZING: ACCOMPLISHED IN UTENSIL WASH AREA WITH (3) 2'-0" x 2'-2" x 15" MINIMUM DEEP SINKS AND WAREWASH MACHINE.
7. MECHANICAL CLEANING/SANITIZING OF TABLEWARE: ACCOMPLISHED BY WAREWASH MACHINE.
8. STOREROOMS: AMPLE DAILY STORAGE PROVIDED IN ENCLOSED STORE ROOMS. STORE ROOMS TO BE VENTILATED AND MAINTAIN PROPER TEMPERATURE.
9. WATER HEATER: LOCATED IN THE MECHANICAL ROOM ADJACENT TO KITCHEN. TO BE SIZED TO PROVIDE AMPLE WATER TO MAINTAIN PROPER WATER TEMPERATURE THROUGHOUT HOURS OF OPERATION.
10. GREASE TRAP: LOCATED AT EXTERIOR OF BUILDING. REFER TO ENGINEER'S DRAWINGS.
11. FOOD SERVICE EQUIPMENT: ALL FLOOR-MOUNTED EQUIPMENT IS TO BE SEALED TO THE FLOOR TO PROVIDE AN EASILY CLEANABLE SURFACE AND PREVENT SEEPAGE. EQUIPMENT NOT MOUNTED TO THE FLOOR IS TO BE WALL MOUNTED ON WALL CARRIERS, OR ELEVATED ON LEGS TO PROVIDE AT LEAST A SIX-INCH CLEARANCE BETWEEN FLOOR AND EQUIPMENT.
12. MOP SINK: LOCATED IN JANITOR CLOSET OFF MAIN KITCHEN CORRIDOR, AND LOCATED IN CLOSE PROXIMITY TO THE SERVERY WAREWASH AREA.
13. EXHAUST HOODS: EXHAUST HOODS PROVIDED OVER COOKING EQUIPMENT WITH LIQUID CHEMICAL ANSUL FIRE EXTINGUISHING SYSTEM.
14. LIGHTING AND PROTECTIVE SHIELDING: RECESSED CEILING-MOUNTED FLUORESCENT LIGHT FIXTURES FITTED WITH CLEAR LEXAN DIFFUSERS.
15. GARBAGE AND REFUSE: CENTRAL TRASH COLLECTION PROVIDED FOR BUILDING LOCATED NEAR RECEIVING AREA ON SMOOTH CONCRETE SURFACE.
16. POISONOUS AND TOXIC MATERIAL STORAGE: LOCATED IN RESPECTIVE JANITOR CLOSETS WITH LOCKING HARDWARE.

1 HEALTH DEPARTMENT COORDINATION NOTES
NOT TO SCALE

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL

FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
ELECTRONICALLY SEALED (PRINTING ONLY)
DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 48854119 ON: 07/18/2025

MWA ARCHITECTS

ARCHITECTS AND PLANNING CONSULTANTS


11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

FS GENERAL COORDINATION NOTES

O-QF0.0

| FOOD SERVICE DRAWING INDEX | |
|---|---|
| FDP SHEET NUMBER | FDP SHEET NAME |
| O-QF0.0 | FS GENERAL COORDINATION NOTES |
| O-QF1.0 | FS EQUIPMENT PLAN |
| O-QF1.1 | FS FACILITY MODEL |
| O-QF1.2 | FS EQUIPMENT MODEL |
| O-QF1.3 | FS SPECIAL CONDITIONS & MECHANICAL PLAN |
| O-QF1.4 | FS PLUMBING PLAN |
| O-QF1.5 | FS ELECTRICAL PLAN |
| O-QF1.6 | FS CONDENSING UNITS |
| O-QF1.7 | FS WALK-INS |
| O-QF1.8 | FS SERVING LINE |
| O-QF1.9 | FS SERVING LINE |
| O-QF2.0 | FS DEMO PLAN |
| O-QF2.1 | FS TEMPORARY SERVING |
| O-QF3.1 | FS ELEVATIONS |
| O-QF4.1 | FS SECTIONS & DETAILS |
| O-QF4.2 | FS DETAILS |
| O-QF4.3 | FS DETAILS |




1 FOOD SERVICE EQUIPMENT PLAN
1/4" = 1'-0"

| FOOD SERVICE EQUIPMENT SCHEDULE | | | | | |
|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR GENERAL CONTRACTOR & HEALTH DEPARTMENT COORDINATION NOTES | | | | | |
| FDP ITEM | FDP QTY | FDP DESCRIPTION | FDP REMARKS | MANUFACTURER | MODEL |
| 101 | 1 | AIR SCREEN | | MARS | STD248-1UA-O |
| 102 | 1 | COLD STORAGE ASSEMBLY | | AMERICAN PANEL | |
| 103 | 1 | COLD STORAGE REFRIGERATION SYSTEM | | RDT | ZS1-02Z-CT3-AST |
| 104 | 2 | COLD STORAGE SHELVING | | METRO | METROMAX Q |
| 107 | 1 | DRY STORAGE SHELVING | | METRO | METROMAX Q |
| 108 | 1 | CAN RACK | | NEW AGE | 1250CK |
| 109 | 1 | ICE MACHINE W/ BIN | | MANITOWOC | UYF0310A |
| 110 | 1 | CLOTHES WASHER | | WHIRLPOOL | RESIDENTIAL |
| 110A | 1 | CLOTHES DRYER | | WHIRLPOOL | RESIDENTIAL |
| 111W | 1 | WALL MOUNTED OVERSHELF | | CUSTOM FABRICATED | |
| 122 | 1 | TWO COMPARTMENT SINK WITHOUT DISPOSER | | CUSTOM FABRICATED | |
| 123 | 1 | DISPOSER - 3HP | | SALVAJOR | 300-CA-18-ARSS-LD |
| 125 | 1 | 20 QT. MIXER W/STAND | | HOBART | HL200 |
| 128 | 4 | UTILITY CART | | LAKESIDE | 522 |
| 129 | 3 | WORKTABLE W/S.BAR UT.RACK | | CUSTOM FABRICATED | |
| 138 | 4 | PAN RACK | | CRES COR | 207-UA-13A |
| 139 | 1 | INSUL MOBILE PROOFER | | CRES COR | H-137-WSUA-12D |
| 151 | 2 | FIRE PROTECTION SYSTEM | | ANSUL | R102 |
| 152 | 1 | EXHAUST HOOD | EXISTING | | |
| 153 | 1 | EXHAUST HOOD | EXISTING | | |
| 161 | 2 | CONVECTION OVEN | | BLODGETT | DFP-200 DBL |
| 165 | 1 | TWO BURNER RANGE | | VULCAN | V2B18B |
| 172 | 1 | COMBI OVEN | | RATIONAL | ICP 6-FULL/6-FULL N/G |
| 186 | 2 | PASS-THRU HEATED CABINET-1DR | | TRAULSEN | AHF132WP |
| 188 | 2 | PASS-THRU REFRIGERATOR-1DR | | TRAULSEN | AHT132WPUT |
| 201M.1 | 1 | SERVING COUNTER-MODULAR | | COUNTERCRAFT | SCOL-408-MOD |
| 214 | 2 | CASH REGISTER | OWNER FURNISHED | | |
| 249 | 1 | THREE COMPARTMENT SINK NO DISPOSER | | CUSTOM FABRICATED | |
| 250 | 1 | DISHMACHINE | | HOBART | CL44-BAS |
| 254 | 2 | SOILED & CLEAN DISHTABLE | | CUSTOM FABRICATED | |
| 255 | 2 | MOBILE DRYING RACK | | METRO | PR48VX3 |
| 260 | 4 | HAND SINK | FURNISHED & INSTALLED BY DIV. 22 | | |
| 614 | 1 | FILL FAUCET | | T&S | B-0610 |
| 615 | 2 | MENU MONITOR | BY OWNER | | |
| 800 | 1 | 15 GAL. BRAISING PAN | | GROEN | BPM-15GA |
| 801 | 1 | S/S CORNER GUARDS | LOCATED ON EVERY EXPOSED CORNER THROUGHOUT KITCHEN | CUSTOM FABRICATED | |
| 802 | 1 | WALL BUMPERS | LOCATED ON ALL EXPOSED BUILDING WALLS | PAWLING | MD-1 |
| 803 | 1 | WATER SOFTENER | | HOBART | WS-40 |
| 804 | 4 | S/S SPLASH GUARDS | | CUSTOM FABRICATED | |

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL


CONSERVICE CONSULTANTS
MELISSA MOORE
FCSI
48854119
CONSTRUCTION SPECIFICATIONS INSTITUTE
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 48854119
ON: 07/18/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS EQUIPMENT PLAN

O-QF1.0

ISOMETRIC VIEWS WITHIN THIS DRAWING ARE NOT TO SCALE AND ARE PROVIDED FOR REFERENCE PURPOSES ONLY. ISOMETRIC VIEWS ARE NOT INTENDED FOR REGULATORY APPROVAL, PERMITTING, NOR CONSTRUCTION. REFER TO FLOOR PLANS AND DETAILS FOR SPECIFIC PROJECT INFORMATION.



1 FS FACILITY MODEL

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL


FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY MELISSA MOORE ON THE DATE ADJACENT TO THE SEAL. PRINTED COPIES OF THIS DOCUMENT WERE NOT SIGNED OR SEALED. THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO: 48854119 ON: 07/18/2025


ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS FACILITY MODEL

O-QF1.1

ISOMETRIC VIEWS WITHIN THIS DRAWING ARE NOT TO SCALE AND ARE PROVIDED FOR REFERENCE PURPOSES ONLY. ISOMETRIC VIEWS ARE NOT INTENDED FOR REGULATORY APPROVAL, PERMITTING, NOR CONSTRUCTION. REFER TO FLOOR PLANS AND DETAILS FOR SPECIFIC PROJECT INFORMATION.



1 FS EQUIPMENT MODEL

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL


FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
46854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
PRINTED COPIES OF THIS DOCUMENT WERE AUTHORIZED BY MELISSA MOORE, FCSI NO. 46854119 ON: 07/18/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS EQUIPMENT MODEL


O-QF1.2

| FOOD SERVICE MECHANICAL SCHEDULE | | | | | | |
|---|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR MECHANICAL COORDINATION NOTES | | | | | | |
| FDP NO. | FDP QTY | FDP TYPE | FDP SIZE | FDP LOC | FDP CFM | FDP S.P. |
| M101 | 1 | EXHAUST | 4" X 16" | | 400 | 0.30" |
| M102 | 1 | EXHAUST | 4" X 16" | | 800 | 0.30" |
| M103 | 1 | DRYER VENT | 6" DIA. | | --- | --- |





1 FOOD SERVICE SPECIAL CONDITIONS PLAN
1/4" = 1'-0"

NOTE:
SECTION 11 40 00 TO COORDINATE FINAL LOCATION AND SIZE OF WALL BLOCKING.





5 WALL BLOCKING DETAIL
NOT TO SCALE


NOTE:
SECTION 11 40 00 TO COORDINATE FINAL LOCATION OF ALL TRENCH LINERS WITH EQUIPMENT POUR PATH.




6 TRENCH LINER DETAIL
NOT TO SCALE





3 COLD STORAGE ASSEMBLY ENCLOSURE PANEL DETAIL
NOT TO SCALE




COLD STORAGE ASSEMBLY REFRIGERATION SYSTEM GROUND MOUNT 4" PLATFORM DETAIL
4 NOT TO SCALE

SLAB TO BE MODIFIED AS REQUIRED TO ALLOW FOR A 4 1/2" DEPRESSION SLAB. PROVIDE NEW LEVEL CONCRETE PAD FOR COLD STORAGE ASSEMBLY.




WALL SECTION @ EXTERIOR DOOR

2 COLD STORAGE ASSEMBLY 4 1/2" DEPRESSION DETAIL
NOT TO SCALE

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FDP
FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459


SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
ELECTRONICALLY APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO: 48854119 ON: 07/18/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS SPECIAL CONDITIONS & MECHANICAL PLAN

O-QF1.3

| FOOD SERVICE PLUMBING SCHEDULE | | | | | | |
|---|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR PLUMBING COORDINATION NOTES | | | | | | |
| FDP PNO | FDP PSIZE | FDP PCONN | FDP PSERVICE TO | FDP PLOC | FDP PAFF | FDP PREMARKS |
| P5 | 3/4" | H & C WATER | JANITOR SINK | WALL | 48" | JANITOR SINK BY PLUMBER |
| P6 | 4" | FLOOR DRAIN | JANITOR SINK | FLOOR | VERIFY | JANITOR SINK BY PLUMBER |
| P7 | 3/4" | H & C WATER | HOSE BIBB | WALL | 18" | BTC |
| P10 | VERIFY | FLOOR DRAIN | GENERAL AREA DRAIN | FLOOR | VERIFY | --- |
| P11C | 1/2" | H & C WATER | FAUCET | WALL | 18" | FURNISHED & INSTALLED BY DIV. 22 |
| P11D | 1 1/2" | DIRECT DRAIN | HAND SINK | WALL | 15" | FURNISHED & INSTALLED BY DIV. 22 |
| P12 | VERIFY | FLOOR DRAIN | EQUIP. DRAIN | FLOOR | VERIFY | NO SLOPE |
| P15 | 4" | FLOOR DRAIN | FUNNEL FLOOR DRAIN | FLOOR | 0" | --- |
| P109 | 3/4" | COLD WATER | WATER/ ICE | WALL | 60" | BTC |
| P109A | 12" SQ. | FLOOR SINK | ICE MACHINE | FLOOR | 0" | FULL GRATE |
| P110 | 3/4" | H & C WATER | CLOTHES WASHER | WALL | 48" | BTC; VALVE BOX |
| P110A | 2" | INDIRECT DRAIN | CLOTHES WASHER | WALL | 48" | VALVE BOX |
| P122 | 3/4" | H & C WATER | FAUCET | WALL | 13" | BTC |
| P122A | 12" SQ. | FLOOR SINK | SINK | FLOOR | 0" | 3/4 GRATE |
| P123 | 3/4" | H & C WATER | FAUCET / DISPOSER | WALL | 13" | BTC |
| P123A | 2" | DIRECT DRAIN | DISPOSER | WALL | 10" | BTC |
| P161 | (2)3/4" | NATURAL GAS | CONVECTION OVEN | WALL | 18"/36" | BTC - 60 MBTU/HR EACH |
| P163A | 3/4" | NATURAL GAS | TILT BRAISING PAN | WALL | 18" | BTC - 65 MBTU/HR |
| P163B | 3/4" | H & C WATER | TILT BRAISING PAN | WALL | 36" | BTC |
| P165 | 1" | NATURAL GAS | RANGE | WALL | 18" | BTC - 70 MBTU/HR |
| P172 | (2)3/4" | COLD WATER | COMBI OVEN | WALL | 24"/48" | BTC - INTERCONNECT THRU FILTERS |
| P172A | 3/4" | COLD WATER | COMBI OVEN | WALL | 48" | BTC |
| P172B | 12"SQ. | FLOOR SINK | EQUIPMENT | FLOOR | 0" | 3/4 GRATE |
| P172C | (2)3/4" | NATURAL GAS | COMBI OVEN | WALL | 18"/36" | BTC: 105 MBTU/HR EACH |
| P172D | 3/4" | COLD WATER | COMBI OVEN | WALL | 66" | BTC; INTERCONNECT TO P172 |
| P172E | 3/4" | COLD WATER | COMBI OVEN WATER FILTER | WALL | 66" | BTC |
| P249 | 3/4" | H & C WATER | FAUCET | WALL | 13" | BTC |
| P249A | 12" SQ. | FLOOR SINK | SINK | FLOOR | 0" | THREE QUARTER GRATE |
| P250 | 12" SQ. | FLOOR SINK | BOOSTER / DISHMACHINE | FLOOR | 18" | BTC |
| P250A | 3/4" | HOT WATER | DISHMACHINE | WALL | 18" | EXT. THRU W.FILTER TO BOOSTER / DISH MACHINE - 140DEG.MIN. |
| P250B | 3/4" | COLD WATER | DISHMACHINE | WALL | 18" | BTC |
| P614 | 1/2" | H & C WATER | FILL FAUCET | WALL | 42" | BTC |
| P800 | 12" SQ. | FLOOR SINK | EQUIPMENT | FLOOR | 0" | 3/4 GRATE |




1 FOOD SERVICE PLUMBING PLAN
1/4" = 1'-0"

SECTION 11 40 00 TO PROVIDE LOOSE WITH FOOD SERVICE EQUIPMENT. INSTALLATION BY DIV. 22 & 26.


- (A) VACUUM BREAKER
- (B) DISPOSER
- (C) TIME DELAY
- (D) CONTROL PANEL
- (E) SOLENOID VALVE

DIVISION 22 TO PROVIDE AND INSTALL


- (F) 1/2" CW INLET
- (G) FLOW CONTROL
- (H) 1/2" CW
- (I) 2" DRAIN LINE WITH P-TRAP & Y ADAPTOR
- (J) 1-1/2" TAILPIECE
- (K) GATE VALVE
- (L) 1/2" CW SUPPLY
- (M) SHOCK STOP
- (N) RPZ BACK FLOW PREVENTOR

DIVISION 26 TO PROVIDE AND INSTALL


- (O) POWER SUPPLY





6 DISPOSER WITH VACUUM BREAKER DETAIL
NOT TO SCALE





7 EXHAUST HOOD - GAS LINE ROUTING DETAIL
NOT TO SCALE




3 GAS DISCONNECT DETAIL
NOT TO SCALE




5 DRAIN PIPING FASTENER DETAIL
NOT TO SCALE




8 WAREWASH - PERFORATED OVER SHELF DETAIL
NOT TO SCALE

| | | | | | |
|---|---|---|---|---|---|
| ○ | HW | HOT WATER | □ | FFD | FUNNEL FLOOR DRAIN |
| ○ | CW | COLD WATER | ◣ | EVC | EXHAUST VENT CONNECTION |
| ○ | HTW | 180 F HOT WATER | ⋈ | SVC | SUPPLY VENT CONNECTION |
| ⊕ | | CHILLED WATER | ↳ | FR | DIRECT-CONNECTED FLUE RISER |
| ● | W | DIRECT WASTE | ⊖ | PS | PIPE SLEEVE |
| ○ | IW | INDIRECT WASTE | ⊙ | | COMPRESSED AIR |
| ⊙ | | GAS SUPPLY | ♦ | | CO2 |
| ◕ | | STEAM SUPPLY | | AFF | ABOVE FINISHED FLOOR |
| ⊗ | CR | CONDENSATE RETURN | | BTC | BRANCH TO CONN. ON EQUIP |
| ● | DR | DRAIN | | DFA | DROP FROM ABOVE |
| □ | FD | FLOOR DRAIN | | CLG | CEILING |
| ▦ | FST | FLOOR SINK 3/4 GRATE | | | |
| ▥ | FSH | FLOOR SINK 3/4 GRATE | | | |

2 PLUMBING SYMBOLS
NOT TO SCALE

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FDP
FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
ELECTRONICALLY SIGNING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 48854119 ON: 07/18/2025



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS PLUMBING PLAN


O-QF1.4

| FOOD SERVICE ELECTRICAL SCHEDULE | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR ELECTRICAL COORDINATION NOTES | | | | | | | | |
| FDP ENO | FDP ECONN | FDP ELOAD | FDP EVOLT | FDP EPH | FDP ESERVICE TO | FDP ELOC | FDP EAFF | FDP EREMARKS |
| E10 | DR | 16.0A | 120 | 1 | CONVENIENCE | WALL | 24" | MOUNT HORIZONTAL |
| E13 | WPR | 16.0A | 120 | 1 | CONVENIENCE | WALL | 24" | MOUNT HORIZONTAL |
| E15 | JB | --- | --- | --- | FIRE PROT. SYSTEM | WALL | 48" | RECESSED EMPTY CONDUIT FOR FIRE PULL |
| E101 | JB | 5.1A | 120 | 1 | AIR SCREEN | WALL | 82" | BTC; MAGNETIC REED SWITCH ON DOOR JAMB & DOOR |
| E102A | JB | 16.0A | 120 | 1 | DOOR HEATER/LIGHTS | CLG | DFA | BTC |
| E102B | JB | 5.0A | 120 | 1 | TEMP. ALARM | CLG | DFA | BTC |
| E102C | JB | 5.0A | 120 | 1 | PRESSURE RELIEF PORT | CLG | DFA | BTC |
| E102E | JB | 10.0A | 120 | 1 | PANIC ALARM BUTTON | CLG | DFA | BTC-INTERCONNECT TO STROBE LIGHT/HORN ABOVE FREEZER DOOR AND IN CAFETORIUM |
| E103 | JB/DS | 25.0A | 208 | 3 | REFRIGERATION SYSTEM | VERIFY | VERIFY | BTC - WEATHERPROOF DISCONNECT SWITCH |
| E103C | JB | 9.1A | 208 | 1 | FREEZER COIL | CLG | DFA | BTC |
| E103D | JB | 1.8A | 120 | 1 | COOLER COIL | CLG | DFA | BTC |
| E103E | JB | --- | --- | --- | DATA CONNECTION | CLG | DFA | BTC; RUN TO NEAREST IDF / MDF ROOM |
| E103F | JB | 16.0A | 120 | 1 | DRAIN LINE HEATER | CLG | DFA | BTC; DEDICATED CIRCUIT |
| E109 | DR | 11.9A | 120 | 1 | ICE MACHINE | WALL | 60" | --- |
| E110 | DR | 16.0A | 120 | 1 | CLOTHES WASHER | WALL | 48" | -- |
| E110A | SR | 30.0A | 208 | 1 | CLOTHES DRYER | WALL | 48" | VERIFY NEMA PLUG RECEPTACLE |
| E123 | JB | 3.0HP | 208 | 3 | DISPOSER | WALL | 24" | BTC; CONNECT THRU C.P. TO DISPOSER |

| FOOD SERVICE ELECTRICAL SCHEDULE | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR ELECTRICAL COORDINATION NOTES | | | | | | | | |
| FDP ENO | FDP ECONN | FDP ELOAD | FDP EVOLT | FDP EPH | FDP ESERVICE TO | FDP ELOC | FDP EAFF | FDP EREMARKS |
| E129 | DCR | 16.0A | 120 | 1 | TABLE RECEPTACLE | CLG | 84" | TWISTLOCK PLUG & RECEPTACLE |
| E139 | DCR | 15.0A | 120 | 1 | INSUL. MOBILE PROOFER | CEILING | DFA | -- |
| E151 | JB | 1.0A | 120 | 1 | FIRE PROT. SYSTEM | CLG | DFA | BTC |
| E161 | (2)DR | 6.0A EA. | 120 | 1 | CONVECTION OVEN | WALL | 24"/48" | SHUNT TRIP BREAKER |
| E163 | DR | 5.0A | 120 | 1 | TILT BRAISING PAN | WALL | 24" | SHUNT TRIP BREAKER |
| E172 | (2)JB | 15.0A EA. | 208 | 1 | COMBI OVEN | WALL | 24"/48" | BTC; RE: NOTE #4- SHUNT TRIP BREAKER |
| E187 | JB | 15.5A | 120/208 | 1 | HEATED CABINET | WALL | 96" | BTC; MOUNT ON KITCHEN SIDE |
| E188 | JB | 7.2A | 120 | 1 | REFRIGERATOR | WALL | 96" | BTC; MOUNT ON KITCHEN SIDE-OMIT PLUG, UNIT TO BE HARDWIRED |
| E201A | PMR | 28.0A | 208 | 1 | HOT FOOD COUNTER | FLOOR | 4.5" | BTC |
| E201B | PMR | 16.0A | 120 | 1 | COLD FOOD COUNTER | FLR | 4.5" | --- |
| E209 | PMR | 8.0A | 120 | 1 | DROP FRONT MILK COOLER-8 CASE | FLR | 4.5" | --- |
| E214 | PMR | 16.0A | 120 | 1 | CASH REGISTER | FLR | 4.5" | DEDICATED CIRCUIT |
| E214A | CS | --- | --- | --- | POS | FLOOR | 6" | BTC; CONDUIT W/DATA LINE TO RUN TO MANAGER'S OFFICE OR IDF ROOM-VERIFY |
| E250 | JB/DS-JB | 51.7A | 480 | 3 | DISHMACHINE | WALL | 66" | BTC; EXTEND FROM JB/DS AT NEAREST WALL |
| E615 | DR | 5.0A | 120 | 1 | VIDEO / DATA SYSTEM | CLG | VERIFY | PROVIDE DCO AT VIDEO LOCATION |
| E615A | JB | --- | --- | --- | VIDEO / DATA SYSTEM | CLG | VERIFY | PROVIDE JB AT DATA LOCATION |


DIVISION 26 TO PROVIDE, COORDINATE, AND INSTALL THE FOLLOWING:
1. AUDIBLE DOORBELL AT RECEIVING DOOR ON EXTERIOR WALL THAT CAN BE HEARD THROUGHOUT THE ENTIRE KITCHEN, OFFICE AND DRY STORAGE ROOM.
2. ADEQUATE LIGHTING AT RECEIVING DOOR.
3. EDWARDS 860 SERIES (OR EQUAL) RED LENS, SURFACE-MOUNTED XENON EMERGENCY STROBE BEACONS. ONE (1) TO BE LOCATED IN THE KITCHEN ABOVE WALK-IN FREEZER DOOR (OR COOLER DOOR WHEN FREEZER IS WITHIN COOLER IN AN 'INLINE' ASSEMBLY), AND ONE (1) TO BE LOCATED IN THE CAFETORIUM (COORDINATE LOCATION WITH OWNERS). PROVIDE CONDUIT, WIRING, AND INTERCONNECT THE ILLUMINATED PUSH BUTTON PANIC ALARM IN THE WALK-IN FREEZER TO BOTH STROBE BEACONS (CRITICAL).
DIVISION 27 TO PROVIDE THE FOLLOWING:
1. CONDUIT, DATA, AND INTERCONNECTION FROM THE ILLUMINATED PUSH BUTTON PANIC ALARM INSIDE THE WALK-IN FREEZER TO
1 THE BUILDING AUTOMATION SYSTEM. WHEN ACTIVATED, FACILITY PERSONNEL TO BE NOTIFIED - COORDINATE NOTIFICATION REQUIREMENTS WITH THE OWNER (CRITICAL).
NOTE:
(FOR GRAPHICAL REPRESENTATION ONLY)
SECTION 11 40 00 TO VERIFY LOCATION OF REFRIGERATION SYSTEM WITH APPROVED ARCHITECTURAL DRAWINGS.
E101
E110
E110A
E13
E15
E15
VERIFY FINAL LOCATION WITH FIRE MARSHAL.
TO BE LOCATED BETWEEN 10' AND 20' FROM ASSOCIATED HOOD AND IN PATH OF EGRESS.
REFER TO ENGINEER / ARCHITECTURAL DRAWINGS FOR ADDITIONAL ELECTRICAL REQUIREMENTS.
E129
E13
E13
E129
E139
DIV. 26 TO INTERCONNECT TEMP SENSOR TO EXHAUST / SUPPLY FANS.
RECOMMENDED LOCATION OF HOOD FAN & LIGHT SWITCHES. "AT FULL HT WALL LOCATION
E161
E161
E172
E163
E129
E129
E129
E129
ALL ELECTRICAL BELOW HOOD TO HAVE SHUNT TRIP BREAKERS.
E187
E188
E188
E187
E10
E10
E10
E10
E10
E109
UTILITY CONNECTIONS TO BE ON KITCHEN SIDE OF WALL.
DIV. 26 TO INTERCONNECT TABLE LIMIT SWITCH TO DISHMACHINE.
DIV. 26 TO INTERCONNECT DISHMACHINE EXHAUST FAN TO DISHMACHINE VENT FAN CONTROL.
E250
E123
E209
E201A
E201B
E201B
E201A
E209
E214A
E214
E214
E615A
E615
E615A
E615
E103E
E103D
E102C
E102A
E102A
E102E
E102B
E102C
E102E
E102B
E103F
E103E
E103D
EXTEND TO LT. FIXTURES
EXTEND TO LT. FIXTURES
E151
E151
E102A
E102C
E102E
E102B
E103
E103
E103

**MODEL NO. ZS1-02Z-CT3-EST OUTDOOR AIR COOLED REFRIGERATION SYSTEM**
**ITEM NO. 103.1**




NOTE:
- CRANKCASE HEATERS
- FAN CYCLING SWITCH
- (2) DOOR SENSORS (SHIPPED LOOSE)
- 24" STAND W/ SKIRTS (SHIPPED LOOSE)
- REFRIGERANT DETECTION SYSTEM
- CHECK VALVE (SHIPPED LOOSE)
- SHUT OFF VALVE (SHIPPED LOOSE)

RACK WEIGHT: 500 LBS.

## ENGINEERING SUMMARY

**POWER SUPPLY: 208-230/60/3**
**CONNECTED LOAD: 25 AMPS**

**MOPD: 35 AMP**
**MINIMUM CIRCUIT AMPACITY: 28.0**

| SYSTEM | FIXTURES ITEM # | DESCRIPTION | TEMP °F FIXT. | TEMP °F SUCT. | REQ'D FIXTURE BTU/H | REFRIG. R. | CONDENSING UNIT COMPRESSOR MODEL NO. | H.P. | RATING @ 60 HZ RLA | V | PH | BTU CAP @ AMB °F 110 | TYPE | REC. CAP. (lbs) | CONDENSER | EVAPORATOR COILS ITEM # | MODEL NO. | QTY | FAN MOTORS @ 60 HZ RLA | V | PH | HEATERS @ 60 HZ RLA | V | PH | DEFR. TYPE | DEFROST CONTROLLER TYPE | CONTROLLER QTY | ACCESSORIES TSTAT | SOL. VALVE | EXP. V.L.V. | REFRIGERANT LINE SIZES (IN) SUCT. | SUCT. LINE RISER | LIQUID | LINE RUN (FT) | TYPE | TOTAL SYSTEM LOAD |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| A | 102 | WALK-IN COOLER | 35 | 25 | 9798 | 454A | YS11KAE | | 11.2 | 208 | 3 | 11700 | Z | 14.0 | L1R | | BEL0095 | 1 | 1.8 | 115 | 1 | | | | O.C. | ECOSMART | 1 | F | F | EF | 5/8 | 5/8 | 3/8 | 100 | M | 11.2 |
| B | 102 | WALK-IN FREEZER | -10 | -20 | 8924 | 454A | YF10KAE | | 13.8 | 208 | 3 | 11050 | Z | 26.1 | L2R | | BEL0080 | 1 | 1.0 | 208 | 1 | 9.1 | 208 | 1 | ELEC | ECOSMART | 1 | F | F | EF | 7/8 | 7/8 | 3/8 | 100 | M | 13.8 |

ALL EVAPORATOR COILS WILL REQUIRE A HOUSE POWER SUPPLY

c UL us LISTED

NOTE:
IT IS THE INSTALLING CONTRACTORS RESPONSIBILITY TO FOLLOW ALL APPLICABLE CODES AND CURRENT REFRIGERATION INDUSTRY STANDARDS AND PRACTICES WHEN DETERMINING LINE SIZES, AND INSTALLING AND STARTING UP RDT EQUIPMENT.


COMPRESSOR TYPE
Z SCROLL
H HERMETIC
S SEMI-HERMETIC
D DISCUS

DEFROST TYPE
O.C. OFF CYCLE
ELEC ELECTRIC

LINE TYPE
M MAIN - UP TO 100'
B BRANCH - UP TO 50'
T TRUNK - UP TO 200'


EVAPORATOR ACCESSORIES
EF EEV FACTORY EQUIPPED ON EVAP
TF TXV FACTORY EQUIPPED ON EVAP
F FACTORY EQUIPPED ON EVAP
O PROVIDED BY OTHERS
L LOOSE (FIELD INSTALLATION)

### PLANVIEW/ CLEARANCE REQUIREMENTS





NOTE: MINIMUM CLEARANCE REQUIRED FOR PROPER OPERATION
NOTE: ROOF CURB OR GROUND PAD CAN BE SAME SIZE AS OUTDOOR UNIT

### SUCTION LINE VERTICAL RISE DETAIL




- Install trap every transition from horizontal to vertical.
- Insulate suction lines with 3/4" wall Armaflex insulation.
- All joints brazed with minimum 15% silver content brazing rod.
- Install "P" trap on suction line every 15' vertical rise.
- Not to exceed 45' vertically over all.
- *If compressor is above the evaporator, Install inverted trap on top of the rise to prevent oil from seeping down when fixture(s) is turned off.

### EVAPORATOR DETAILS - MODEL BEL




| AIR DEFROST Size | DIMENSIONS A | B | C | D | CONNECTIONS (Inches) Coil Inlet | Drain | Approx. Net Wt. | ELECTRICAL DATA Qty. Motors | EC Motor Fan Amps 115V | 208V |
|---|---|---|---|---|---|---|---|---|---|---|
| | Inches | Inches | Inches | Inches | | | | | | |
| 095 | 45-1/2 | 33-1/4 | - | - | 1/2 OD | 3/4 MPT | 51 | 2 | 1.8 | 1.0 |

| ELECTRIC DEFROST | DIMENSIONS A | B | C | D | CONNECTIONS (Inches) Coil Inlet | Suction | Drain | Approx. Net Wt. | ELECTRICAL DATA Qty. Motors | EC Motor Fan Amps | Heater Amps as wired for 208-230/60/1 | 208-230/60/3 | 460/60/3 |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Inches | Inches | Inches | Inches | | | | Lbs. | | | | | |
| 080 | 45-1/2 | 33-1/4 | - | - | 1/2 OD | 5/8 OD | 3/4 MPT | 54 | 2 | 1.0 | 9.1 | 5.7 | 4.6 |

### ZS SERIES ENGINEERING SPECIFICATIONS

Multi compressor, outdoor, air cooled. The refrigeration package shall be a pre-engineered and factory-assembled unit, trade name "ZS", as manufactured by Refrigeration Design Technologies, 1808 FM Road 66, P.O. Box 622, Waxahachie, Texas 75168. Phone: (972) 937-3215; Fax: (972) 937-0970.

1. Air-Cooled Refrigeration System
The RDT UL Listed "Air-Cooled" Refrigeration system shall be housed in a weather-protected compact powder coated steel frame. The entire housing shall be brushed stainless steel. The unit shall include an air-cooled aluminum fin copper tube condenser designed to operate at 15 degrees TD. The exterior housing shall feature stainless steel one piece louvers. Lifting points shall be integrated in the framing component. Condenser fan motors shall be mounted within the enclosure. The condenser intake surface shall be protected with stainless steel expanded metal guard to protect against vandalism and hail damage.

Each unit shall be equipped with a ball-bearing fan motor, suction filter, sight glass, liquid filter/drier, liquid line inlet and outlet valve, defrost cycle and high pressure super-hose connections. Each unit shall be equipped with fan cycling controls and/or head pressure regulator where required for low ambient conditions.

Condensing unit shall contain scroll, hermetic, semi-hermetic, and/or discus type compressor(s) assembled to operate with the refrigerant specified for both medium and low temperature applications.

2. Evaporator Coils
A. Evaporator coils shall be direct expansion type fabricated of copper tubes with aluminum fins.
B. All evaporator coils shall be provided with solenoid valve, thermostatic or electronic expansion valve and thermostat.

3. Pre-Piping
All refrigerant lines shall be extended to outside of the housing in a neat and orderly manner. All tubing shall be securely supported and anchored with non-corrosive coated clamps.

All joints must be brazed, not soldered.

All piping and controls shall be factory pressure-tested with dry nitrogen.

4. Control Panel
The package shall have a factory-mounted and pre-wired control panel, with main disconnect (non fused) where required, circuit breakers, contactors wired for single point power connection.

General Information
Contractors shall verify all dimensions onsite and coordinate with other trades.

General contractor shall prepare the platform, curbed openings and weatherproofing the unit after installation.

Refrigeration Contractor
All copper tubing to be refrigerant grade. A.C.R. or type "L".

Brazing should be used for all refrigerant piping. Silver solder or soft solder is not acceptable.

All piping to be pressure tested with nitrogen at 300 psi. After the condensing unit and coil have been connected the balance of the system shall be leak tested with the valves open at 200 psi.

The complete system shall be evacuated with a vacuum pump. Each unit should be charged tested and adjusted to assure operation.

Contractor should provide and install the drain-line heater in freezer. Heater shall be connected by electrical contractor. Seal all penetrations through the walk-in units with foam.

Electrical Contractor
Electrical contractor to provide power for refrigeration package and connect control and defrost system as called for in the wiring diagram.


Electrical contractor to connect drain-line heater in the freezer.

All electrical wiring and installation shall be in accordance with the wiring diagram and local codes. Seal all penetrations through the walk-in units with foam.

Plumbing Contractor
Plumbing contractor to provide copper drain lines for walk-in refrigerator and freezer, pitched 1/4" per foot of run. Trap drain-line outside of refrigerated space to avoid entrance of warm, moist air.


All plumbing installation shall be in accordance with local codes.

### EVAPORATOR MOUNTING DETAIL (TYPICAL)




| COIL MODEL | DISTANCE FROM WALL |
|---|---|
| BEL | 1-1/3"H |
| BEM/BEH | 1/2 " W |

### EVAPORATOR PLACEMENT & CLEARANCE REQUIREMENTS LOW PROFILE EVAPORATOR COILS (I.E. - BEL)





NOTE:
H = TOTAL HEIGHT OF THE EVAP. COIL

SINGLE EVAPORATOR

### WIRING DIAGRAM - ECO-SMART - AKOA1AE DEMAND DEFROST W/KE2 DOOR SWITCH FOR WALK-IN COOLER WITH ONE COIL 115/60/1

*REFERENCE ENGINEERING SUMMARY FOR COIL AMP DRAW:


| SYS | DESCRIPTION | VOLTAGE |
|---|---|---|
| A | WALK-IN COOLER | 115/1 |




### WIRING DIAGRAM - ECO-SMART - AKOB1EE DEMAND DEFROST W/KE2 DOOR SWITCH FOR WALK-IN FREEZER WITH ONE COIL 208-230/60/1

*REFERENCE ENGINEERING SUMMARY FOR COIL AMP DRAW:

| SYS | DESCRIPTION | VOLTAGE |
|---|---|---|
| B | WALK-IN FREEZER | 208/1 |




### APPROVAL STATUS

THIS DRAWING REPRESENTS OUR UNDERSTANDING OF THE SPECIFICATIONS. PLEASE REVIEW IT CAREFULLY FOR ACCURACY. CLEARLY AND IN DETAIL NOTE CHANGES REQUIRED.

MARK APPROPRIATE BOX, SIGN, AND DATE BELOW.

- ☐ APPROVED FOR FABRICATION NO CHANGES
- ☐ APPROVED FOR FABRICATION WITH CHANGES NOTED
- ☐ REVISE AND RE-SUBMIT DRAWING

BY: _____ DATE: _____

### NOTICE

THIS DRAWING BEING AN INSTRUMENT OF SERVICE IS AND WILL REMAIN PROPERTY OF REFRIGERATION DESIGN TECHNOLOGIES AND CANNOT BE USED WITHOUT WRITTEN AUTHORIZATION.

| No. | Revision/Issue | Date |
|---|---|---|
| 0 | ORIGINAL ISSUE | 10-02-24 |
| 1 | CHANGED A2L EQUIPMENT | 7-16-25 |

REFRIGERATION DESIGN TECHNOLOGIES
1808 FM Road 66 / P.O. Box 622
Waxahachie, Texas
(800) 736-9518
www.rdtonline.com

Consultant:
Foodservice Design Professionals
Southlake, TX

Dealer
-
-

**Palmer Elementary School**
**Sugar Land, TX**

Project No: 31078
Designed By: J GOODWYN
Drawn By: J GOODWYN
Sheet 1.1 of sheets

ISSUE:
12/05/2024 DD PACKAGE
03/11/2025 50% CD PKG.
05/23/2025 90% CD PKG.
07/18/2025 ISSUED FOR BIDDING AND PERMITTING

FOODSERVICE DESIGN PROFESSIONALS


FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459


SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
ELECTRONICALLY APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 48854119 ON: 07/18/2025


ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS CONDENSING UNITS

O-QF1.6






COOLER DOOR ELEVATION




DOOR ELECTRICAL CONNECTION




TRIM ANGLE
DETAIL #3




PANEL MOUNTED ELECTRICAL CONNECTION

~SPECIFICATIONS~

BOX HEIGHT:
FREEZER – 10'-2" OVERALL (7'-6 1/4" INTERIOR)
COOLER – 10'-2" OVERALL (7'-6 1/4" INTERIOR)

CONSTRUCTION:
FOAMED IN PLACE
NSF LISTED, STANDARD NO. 7

INSULATION:
4" URETHANE, FINISHED PANEL
UL CLASSIFIED FLAME SPREAD 20
CORE SMOKE DEVELOPED 250

INSTALLATION:
INDOOR

FLOOR: (SEE DETAILS)
FREEZER – STANDARD W/AMERITUFF STRUCTURAL FLOOR
(1/8" INTEGRAL DIAMOND ALUMINUM TREAD PLATE,
3/4" MARINE PLYWOOD UNDERLAYMENT, FIBERGLASS GRATING SUPPORT)
COOLER – STANDARD W/36" DEEP INTERIOR RAMP & AMERITUFF STRUCTURAL FLOOR
(1/8" INTEGRAL DIAMOND ALUMINUM TREAD PLATE,
3/4" MARINE PLYWOOD UNDERLAYMENT, FIBERGLASS GRATING SUPPORT)

DOOR HARDWARE & ACCESSORIES: (EACH DOOR)
SMOOTH POLISHED DOOR HARDWARE
POWER TO BE STUBBED OUT CEILING PANEL
DRY CONTACT LEADS TO BE STUBBED OUT CEILING PANEL IN A SEPARATE STUB OUT
DEADBOLT HANDLE W/KEYED CYLINDER LOCK, PADLOCK
PROVISION & QUARTER TURN INSIDE RELEASE (EXTERIOR DOOR ONLY)
1/8" STAINLESS STEEL THRESHOLD COVER PLATE
14 GA STAINLESS STEEL SUB THRESHOLD
FRAME HEATER WIRE
HYDRAULIC DOOR CLOSER
IC+ WALK-IN DOOR CONTROLLER AND ALARM SYSTEM INCLUDING:
INTEGRATED LIGHT SWITCH WITH AUTOMATIC LIGHT OFF AND 3-WAY & 4-WAY CAPABILITY
TEMPERATURE MONITOR AND LOGGER WITH HIGH TEMP. AND LOW TEMP. VISUAL AND AUDIO ALARM
F OR C TEMPERATURE SELECTION
INTEGRATED DRY CONTACT FOR ALARM SIGNALING & POWER FAILURE (1A @ 24VAC, 1A @ 30VDC)
DOOR AND WINDOW HEATER CONTROL (WHEN SO EQUIPPED)
HACCP PREVIEW VIA ONBOARD LCD SCREEN
HACCP DOWNLOAD VIA USB
WIFI CONNECTIVITY (INTERNET ENABLED WIFI NETWORK NEEDED)
BATTERY BACKUP
TEMPERATURE ALARM NOTIFICATION VIA EMAIL &/OR EMAIL TO SMS TEXT MESSAGES
POWER FAILURE NOTIFICATION VIA EMAIL &/OR EMAIL TO SMS TEXT MESSAGES
(FOR THIS FEATURE TO WORK THE LOCAL WIFI NETWORK MUST BE
POWER PROTECTED AND WORKING AT THE TIME OF POWER FAILURE EVENT)
AUTOMATIC AND ON DEMAND TRANSMISSION OF HACCP DATA VIA EMAIL
ADAPTIVE SETTINGS
MOMENTARY BACK-TO-BACK LIGHT SWITCH W/PILOT
25° AIR TEMPERATURE PROBE
25' SECOND PROBE (EXTENDED) FOR MONITORING THE TEMPERATURE AT
A SECOND LOCATION OR FOR MONITORING A SECOND CABINET
DOOR SWITCH TO ENABLE DOOR AJAR ALARM, DOOR AJAR NOTIFICATION VIA EMAIL &/OR
EMAIL TO SMS TEXT MESSAGES, AND AUTOMATIC LIGHTS ON WHEN DOOR OPENS
PANIC ALARM WITH ILLUMINATED PANIC BUTTON, ALARM BUZZER WITH LED,
& NOTIFICATION VIA EMAIL &/OR EMAIL TO SMS TEXT MESSAGES (1-COOLER, 2-FREEZER)
KASON SCREW-IN VAPOR PROOF LIGHT FIXTURE
W/8.5 WATT SYLVANIA LED BULB & GLOBE
CCI CLEAR VU SWINGING DOOR
3 – KASON #1346 ADJUSTABLE SPRING LOADED HINGES
HEATED VISION WINDOW (14" x 24")
1/8" DIAMOND ALUMINUM TREAD PLATE KICKPLATES @ 36" HIGH I/S & O/S DOOR & FRAME
KASON 1826 INTELLO-VENT WITH LIGHTS (FREEZER DOOR ONLY) – FIELD INTERCONNECTION REQUIRED

PANEL MOUNTED ACCESSORIES:
1 – KASON 1826 INTELLO-VENT WITH LIGHTS – FIELD INTERCONNECTION REQUIRED
(FOAMED IN PANEL – PER PLAN) (COOLER ONLY)

ACCESSORIES: (SHIPPED LOOSE)
2 – PCS. TRIM ANGLE – 18 GA STAINLESS STEEL, #3 FINISH
CLOSURE PANEL TO AN EXISTING CEILING (PER PLAN) – VERIFY LENGTH
18 GA STAINLESS STEEL, #3 FINISH
2 – 48" (1810LC) LED LIGHT FIXTURE(S) @ 40W EACH, (LIGHTS TO BE INSTALLED PERPENDICULAR TO COILS)
1/8" DIAMOND ALUMINUM TREAD PLATE WAINSCOT @ 36" HIGH (EXPOSED EXTERIOR ONLY)
1 – 1/8" DIAMOND ALUMINUM TREAD PLATE CORNER GUARD(S) @ 36" HIGH
ALUMINUM COVED BASE MOLDING (COMPLETE INTERIOR ONLY)
ROOF SUPPORT ANGLE W/BEAUTY TRIM
2 – BAKELITE LABEL(S) (BLACK) ("FREEZER", "COOLER")
1 – BAKELITE LABEL (YELLOW W/BLACK LETTERING) ("VACUUM PRESSURE RELIEF")
6 MIL POLYETHYLENE VAPOR BARRIER
5 – BELL BOX(ES) & COVER PLATE(S)
2 – DOOR STOP(S)
2 – EDWARDS 880 SERIES STROBE BEACONS
1 – EMERGENCY PRESSURE RELEASE

METAL FINISHES:
INTERIOR & EXTERIOR DOOR & FRAME – 18 GA STAINLESS STEEL, #3 FINISH
INTERIOR WALLS & CEILING – WHITE .040 STUCCO ALUMINUM
EXPOSED EXTERIOR – 20 GA STAINLESS STEEL, #3 FINISH
UNEXPOSED EXTERIOR – 26 GA STUCCO ACRYLUME
EXTERIOR FLOOR – 26 GA STUCCO ACRYLUME
EXTERIOR ROOF – 26 GA STUCCO ACRYLUME
INTERIOR FLOOR – AMERITUFF STRUCTURAL FLOOR
(1/8" INTEGRAL DIAMOND ALUMINUM TREAD PLATE,
3/4" MARINE PLYWOOD UNDERLAYMENT, FIBERGLASS GRATING SUPPORT)

REFRIGERATION: BY OTHERS

NOTE: THE LARGEST DOOR PANEL ON THIS JOB IS 57.5" x 114.5".
NOTE: THE LARGEST ROOF/FLOOR PANEL ON THIS JOB IS 46.5" x 129".
CUSTOMER IS TO VERIFY THAT THIS PANEL SIZE WILL NOT CONFLICT WITH ANY JOB SITE RESTRICTIONS.


NOTE: CUSTOMER IS TO VERIFY ALL DIMENSIONS, SECTIONS, DETAILS AND SPECIFICATIONS

NOTE: MAXIMUM LIGHT CIRCUIT LOAD IS 1200W 120VAC TUNGSTEN, 5A 120VAC ELECTRONIC BALLAST. FOR HIGHER LOADS ADDITIONAL LIGHT FIXTURES MUST BE CONTROLLED VIA RELAY (BY OTHERS).


| ELECTRICAL DATA |
|---|
| = POINT OF ELECTRICAL CONNECTIONS. |
| WALK-IN DOORS: 115v/1ø – 350w* |
| PANEL MOUNTED ACC: 115v/1ø – 23w (EACH VENT) |

*NOTE: ADD WATTAGE FOR EACH ADDITIONAL LIGHT FIXTURE IN ACCESSORIES.

ITEM #102 WALK-IN COOLER/FREEZER





SECTION E – E





SECTION K – K


American Panel's walk-in floor panels with AmeriTuff structural support are designed to withstand uniformly distributed stationary loads of 15,000 lbs. per square foot. American Panel's warranty does not cover damage caused by pallet jacks, forklifts or any other form of heavy-duty rolling traffic. A concrete wearing floor must be installed on top of the AmeriTuff walk-in floor panels for those rolling applications.




TRIM ANGLE
DETAIL #2




CLOSURE PANEL ABOVE WALK-IN DETAIL #4E




DETAIL "A" WAINSCOT AT INTERIOR CORNER

| INSULATION R-VALUES | | |
|---|---|---|
| PANEL TYPE | COOLER | FREEZER |
| 4" WALLS, ROOFS | R-29 | R-32 |
| 5" WALLS, ROOFS | R-36 | R-40 |
| FLOORS | R-25 | R-28 |
| DOORS | R-32 | |

| COOLER DOOR | |
|---|---|
| DOOR FRAME KWH/DAY | 2.424 |

| FREEZER DOOR | |
|---|---|
| DOOR FRAME KWH/DAY | 4.392 |

| WALK-IN PANEL R-8967 | | |
|---|---|---|
| BUILDING UNITS | R-8967 | 37M2 |
| USA | | |
| SURFACE BURNING CHARACTERISTICS | | |
| MATERIAL DETAILS | "FLAME SPREAD" | "SMOKE DEVELOPED" |
| ALUMINUM PANELS, PAINTED OR UNPAINTED, 5" OR LESS | 15 | 350 |
| "GALVANIZED STEEL OR STAINLESS STEEL PANELS, PAINTED OR UNPAINTED, 5" OR LESS" | 10 | 400 TO 500 |
| CORE MATERIAL, 6" THICK | 20 | 250 |

AMERICAN PANEL WALK-IN COOLERS AND FREEZERS COMPLY WITH THE 2021 INTERNATIONAL ENERGY CONSERVATION CODE (IECC), SECTION C403.11

THIS AMERICAN PANEL WALK-IN WILL BE MANUFACTURED TO UL & NSF REQUIREMENTS. AMERICAN PANEL ACCEPTS NO LIABILITY FOR LOCAL CODE REQUIREMENTS OF WHICH AMERICAN PANEL HAS NOT BEEN MADE AWARE OF IN WRITING PRIOR TO FABRICATION.

1) Please verify that door swing and location are correct.

2) If this walk-in is to be installed in a depression, or quarry tile is to be applied to the interior, depression depths or tile thickness must be specified to insure proper door height.

3) All site preparation, floor or slab construction, plumbing, electrical connections (including control wiring) by others.

4) Electrical: 115-60-1 required above latch side of each door, through ceiling, to operate frame heater and light.

5) Special note to General Contractor and his Sub Contractor for quarry tile or concrete wearing floors: the sheet metal panel facings may be susceptible to staining due to excessive moisture created by hydration of concrete type materials. Therefore, it is absolutely necessary that each room be properly ventilated. Also note that special precautions must be taken when using muriatic acid due to effects hydrochloric acid fumes have on aluminum and stainless steel.

6) This drawing and information contained herein are the exclusive property of American Panel Corporation. It shall be returned to American Panel Corporation upon demand and shall not be reproduced in whole or part, disclosed to anyone else, or used without the written consent of American Panel Corporation.

☐ APPROVED
☐ APPROVED AS NOTED
☐ REVISE & RESUBMIT
SIGNATURE _____
PRINT NAME _____
DATE _____

| REV. | DATE | DESCRIPTION | REV. BY | OWN'S BY |
|---|---|---|---|---|
| A | 1/22/25 | REVISED SPECS | DH | WQ |

American Panel
AMERICAN PANEL CORPORATION
5800 S.E. 78th St. Ocala, Florida 34472
Ph. (352) 245-7055 Fax (352) 245-0726

CUSTOMER: FOODSERVICE DESIGN PROFESSIONALS
PROJECT: PALMER ES-FBISD – FORT BEND, TX
DATE: 10/7/24 | DRAWN BY: LC/TR | P.O.#:
SCALE: 3/8"=1'-0" | PROPOSAL#: PD213253 | JOB#: | SHEET 1 of 1

ALL DIMENSIONS MUST BE FIELD VERIFIED PRIOR TO FABRICATION AND INSTALLATION

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS


# FBISD BP 013 KITCHEN RENOVATIONS
## FORT BEND INDEPENDENT SCHOOL DISTRICT
## PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
FCSI 48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
ELECTRONICALLY APPROVING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 48854119 ON: 07/18/2025


ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS WALK-INS

O-QF1.7





1 CC1 ITEM #1 PLAN

SCALE: 1/2" = 1'-0"





4 CC1 ITEM #1 SECTION VIEW

SCALE: 1/2" = 1'-0"





8 CC1 ITEM #1 CONTROL PANEL LAYOUT

SCALE: 1 1/2" = 1'-0"





2 CC1 ITEM #1 FRONT ELEVATION

SCALE: 1/2" = 1'-0"




11 CC1 ITEM #1 3D PERSPECTIVE

SCALE:




3 CC1 ITEM #1 REAR ELEVATION

SCALE: 1/2" = 1'-0"



12 CC1 ITEM #1 3D PERSPECTIVE 2

SCALE:




1A CC1 ELECTRICAL SCHEDULE
CASHIER COUNTER




1B CC1 ELECTRICAL SCHEDULE
HOT FOOD COUNTER #1
(TWO (2) REQUIRED)




1C CC1 ELECTRICAL SCHEDULE
HOT/FROST COUNTER
(TWO (2) REQUIRED)

EQUIPMENT BY OTHERS

COUNTERCRAFT LAYOUTS, MEPS, AND LOAD CENTERS ARE BASED ON SPECIFIED MANUFACTURERS AND MODELS AS OUTLINED IN THE SPECIFICATIONS IN THE CONTRACT DOCUMENTS. COUNTERCRAFT MUST BE NOTIFIED OF ANY CHANGES TO THE CONTRACT DOCUMENTS IN A TIMELY MANNER.

| NO | REVISIONS | DATE | BY |
|---|---|---|---|
| 1 | PRELIMINARY DWG | 10/21/2024 | MAX |
| 2 | | 11/26/2024 | MAX |
| 3 | | | |
| 4 | | | |
| 5 | | | |
| 6 | | | |
| 7 | | | |
| 8 | | | |
| 9 | | | |

ANOTHER QUALITY PRODUCT FROM
CounterCraft
7007 STEARNS, HOUSTON,TEXAS 77021
(713) 747-5611

PROJECT: FBISD Bond Package 013
FOOD SERVICE CONSULTANT: FOODSERVICE DESIGN PROFESSIONALS

PROJECT NO. -
DATE 11/26/2024
SCALE: As indicated
DRAWN BY: MAX.C
CHECKED BY: E.S
SHEET NO. CC1
OF SHEET

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FDP
FOODSERVICE DESIGN PROFESSIONALS


FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
488544119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
THE DOCUMENT APPEARING ON THIS SHEET WAS AUTHORIZED BY MELISSA MOORE, FCSI NO: 488544119 ON: 07/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS SERVING LINE


O-QF1.8




**3 MECHANICAL ROOF FLOOR PLAN**
SCALE: 1/8" = 1'-0"




**2 RENO MECHANICAL FLOOR PLAN - KITCHEN AREA**
SCALE: 1/8" = 1'-0"




**1 DEMO MECHANICAL FLOOR PLAN - KITCHEN AREA**
SCALE: 1/8" = 1'-0"

## AIR DEVICE SCHEDULE

| MARK | DESCRIPTION |
|---|---|
| A | CEILING DIFFUSER – 24" X 24" FACE, PATTERN TYPE, STEEL CONSTRUCTION, OBD/RADIATION DAMPER, WHITE FINISH, U.L LISTED<br>PRICE SCD A1-12" X 12" |
| B | CEILING RETURN GRILLE – 24" X 24" PERFORATED FACE, STEEL CONSTRUCTION, RADIATION DAMPER, WHITE FINISH, U.L. LISTED<br>PRICE PDFR B1-12" X 12" |
| C | CEILING EXHAUST GRILLE – 24" X 24" PERFORATED FACE, STEEL CONST., OBD/RADIATION DAMPER, WHITE FINISH, NECK SIZE SHOWN, U.L. LISTED<br>PRICE PDDR C1-12" X 12" |

NOTES:
1. REFER TO ARCHITECTURAL REFLECTED CEILING PLAN TO VERIFY CEILING TYPES FOR AIR DEVICES.

## KITCHEN HOOD REFURBISHMENT NOTES

HOOD REFURBISHMENT FOR KITCHEN HOODS (QUANTITY 2):
- STEAM WASH AND DEEP CLEAN STAINLESS STEEL HOOD ASSEMBLY, CASING, AND SUPPLY GRILLES WHERE APPLICABLE.
- REPLACE GREASE FILTER RACKS.
- CLEAN EXISTING MAKE-UP AIR AND GREASE EXHAUST DUCT.
- RELAMP EXISTING LIGHT FIXTURES WITH NEW 4000K BULBS LISTED FOR USE IN AN ENCLOSED KITCHEN HOOD FIXTURE.
- COORDINATE WITH DIVISION 11 FOR REPLACEMENT OF ANSUL FIRE SUPPRESSION SYSTEM.
- HOOD ASSEMBLIES SHALL BE CLEANED TO MEET THE STANDARDS ESTABLISHED IN NFPA STANDARD 96.

## KITCHEN HOOD EXHAUST & MAKE-UP AIR UNIT SCHEDULE

| MARK | ESF-1,2 |
|---|---|
| SERVES | KITCHEN HOOD-1 & 2 |
| **SUPPLY SECTION** | |
| TYPE | INDIRECT GAS-FIRED MAKE-UP AIR UNIT |
| DRIVE | DIRECT |
| SPEED CONTROL | VFD |
| SUPPLY CFM | 2250 |
| EXT. S.P. (IN. W.G.) | 0.375 |
| HORSEPOWER (WATTS) | 1-1/2 HP |
| VOLTAGE | 480V/3-PHASE |
| UNIT MCA | 4.6 A |
| UNIT MOCP | 15 A |
| HEATING MEDIUM | NATURAL GAS |
| INPUT/OUTPUT (MBH) | 150.0/121.5 |
| TURNDOWN RATIO | 4:1 |
| MANUFACTURER | GREENHECK |
| MODEL | IGX-P109-H12-MF-E |
| **EXHAUST SECTION** | |
| TYPE | UPBLAST BELT DRIVE CENTRIFUGAL |
| EXHAUST CFM | 3600 |
| EXT. S.P. (IN. W.G.) | 0.75 |
| HORSEPOWER (WATTS) | 1-1/2 HP |
| VOLTAGE | 480V/3-PHASE |
| UNIT MCA | 3.75 A |
| UNIT MOCP | 15 A |
| MANUFACTURER | GREENHECK |
| EXHAUST FAN MODEL | CUBE-200-15 |

NOTES
1. EXHAUST FAN: PROVIDE FAN WITH PRE-FABRICATED ROOF CURB ADAPTER, VENTED CURB EXTENSION, HINGING KIT, HEAT BAFFLE, DRAIN CONNECTION, GREASE TRAP, AND DISCONNECT SWITCH. FANS SHALL BE UL LISTED FOR USE WITH TYPE 1 GREASE HOOD.
2. EXHAUST FAN: PROVIDE NEW MOTOR STARTER, SIZED FOR EXHAUST FAN MOTOR AND INSTALLED IN PLACE OF EXISTING. REFERENCE THE SPECIFICATIONS FOR STARTER REQUIREMENTS. COORDINATE WITH DIV.25 FOR RE-TERMINATION OF PERMISSIVE ON/OFF CONTROL. COORDINATE WITH DIV.26 FOR RE-TERMINATION OF LOCAL HOOD SWITCH INTERLOCK FOR START/STOP CONTROL.
3. SUPPLY FAN/FURNACE: FLUE GAS FROM HEATING COIL SHALL BE POWER VENTED.
4. SUPPLY FAN/FURNACE: WEATHERHOOD WITH ALUMINUM MESH.
5. SUPPLY FAN/FURNACE: 5 YEAR HEAT EXCHANGER WARRANTY.
6. SUPPLY FAN/FURNACE CONTROLS: INTEGRAL HEATER CONTROLS WITH BAS INTERLOCK FOR PERMISSIVE ON/OFF AND LOCAL SWITCH INTERLOCK FOR CONTROL FROM KITCHEN HOOD SWITCH. FURNACE CONTROLS SHALL BE PROGRAMMED FOR 64°F LAT, WITH A LOCKOUT FOR O/A TEMPERATURES ABOVE THE LAT SETPOINT. COORDINATE WITH DIV.25 AND DIV.26 FOR CONTROLS AND SWITCH INTERLOCKS.
7. TWO POINT POWER CONNECTION: ONE FOR EXHAUST FAN AND ONE FOR INTAKE/SUPPLY FAN.
8. INTERLOCK FAN(S) WITH ASSOCIATED COOKING HOOD
9. INTERLOCK FAN WITH SWITCH ON KITCHEN HOOD.
10. UNIT TO BE PROVIDED WITH GALVANIZED STEEL FAN PACK EXTENSION/COMBINATION CURB.
11. REFER TO WRITTEN SPECS FOR ADDITIONAL REQUIREMENTS.

## MECHANICAL RENO KEYED NOTES

1. TIE-IN NEW DUCTWORK TO EXISTING DUCTWORK AT WALL PENETRATION.
2. CONNECT NEW AIR DEVICE AND TAP TO EXISTING E/A TRUNK DUCT.
3. REWORK EXISTING EXHAUST AND SUPPLY DUCTWORK FROM EXISTING KITCHEN HOOD UP TO FAN, AS REQUIRED, WITH NEW TRANSITIONS AND SUPPLY AIR DUCTWORK OFFSETS TO MATE WITH NEW FAN CURB.
4. EXISTING ELECTRIC DUCT HEATER TO BE RETAINED FOR RE-INSTALLATION IN RENOVATION PHASE.
5. NEW DRYER VENT DUCT AND VENT CAP.
6. TEMP. KITCHEN – CEILING MOUNTED CABINET EXHAUST FAN.
7. TEMP. KITCHEN – 24"X24" SIDE WALL GRILLE. SURFACE MOUNT OPTIONAL. AUXILIARY FRAME. TITUS CT-700.
8. RECONFIGURE DUCTWORK TO CONNECT TO NEW DISHMACHINE HOOD OUTLETS. REF. KITCHEN CONSULTANT DRAWINGS FOR EXACT DIMENSIONS OF DUCT CONNECTIONS.
9. CONDENSATE EXHAUST DUCT UP THROUGH ROOF TO NEW EXHAUST FAN SET ON NEW ROOF CURB. REUSE EXISTING ROOF PENETRATION.

## EXHAUST FAN SCHEDULE

| MARK | EF-TK | EF-CF | EF-14 |
|---|---|---|---|
| SERVES | TEMPORARY KITCHEN | COOLER/FREEZER | DISH WASHER |
| TYPE | CEILING CABINET | INLINE FAN | ROOF UPBLAST |
| DRIVE | DIRECT | DIRECT | DIRECT |
| SPEED CONTROL | INTEGRAL SPEED CONTROLLER | CONSTANT | CONSTANT |
| CFM | 1055 | 1000 | 1200 |
| EXT. S.P. (IN. W.G.) | 0.3 | 0.35 | 0.60 |
| IMP. SIZE (IN.) | 8.0 | 13.5 | |
| HORSEPOWER (WATTS) | 1/3 HP | 1/6 HP | 1/6 HP |
| VOLTAGE | 120V/1-PHASE | 120V/1-PHASE | 120V/1-PHASE |
| MANUFACTURER | COOK | COOK | COOK |
| MODEL | GC-862 | 1355QN10D | CUE-140-VG |
| SONES (MAX.) | 15.0 | 15.0 | 15.0 |
| NOTES | 1 THRU 4 | 1 THRU 4 | 1 THRU 4 |

NOTES
1. STATIC PRESSURE SHOWN IS EXTERNAL TO THE UNIT. MANUFACTURER SHALL ADD DAMPER AND ACCESSORY LOSSES TO THIS VALUE BEFORE SELECTING FAN. FANS SHALL BE CAPABLE OF 120% OF THE SCHEDULED CFM CAPACITY.
2. INTEGRAL DISCONNECT SWITCH.
3. RUBBER IN-SHEAR ISOLATORS.
4. REFER TO WRITTEN SPECS FOR ADDITIONAL REQUIREMENTS.

## MECHANICAL DEMO KEYED NOTES

1. DEMOLISH EXISTING AIR DEVICE, BRANCH DUCT, DAMPER AND TAP BACK TO TRUNK DUCT. CAP AND SEAL RESULTING OPENING.
2. EXISTING E/A TRUNK DUCT TO REMAIN.
3. DISCONNECT EXISTING S/A AND E/A DUCTWORK SERVING KITCHEN HOODS FROM FAN ASSEMBLY ON ROOF. DEMOLISH SUPPLY AND EXHAUST FAN PLENUM ASSEMBLY SERVING KITCHEN HOODS, ALONG WITH CURB. NEW CURB TO BE PROVIDED AND INSTALLED AS PART OF RENOVATION.
4. DEMOLISH ALL EXISTING AIR DEVICES, DUCTWORK, AND DUCTWORK ACCESSORIES SERVING KITCHEN AREA BACK TO MECH. ROOM WALL PENETRATION.
5. EXISTING ELECTRIC DUCT HEATER TO BE RETAINED FOR RE-INSTALLATION IN RENOVATION PHASE.
6. REFURBISH EXISTING KITCHEN HOOD. REFER TO "KITCHEN HOOD REFURBISHMENT NOTES".
7. DEMOLISH AND REPLACE EXISTING DRYER EXHAUST DUCT AND FLUE VENT CAP.
8. DEMOLISH EXISTING CONDENSATE HOOD, ASSOCIATED DUCTWORK, AND ROOF EXHAUST FAN.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

0

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL

STATE OF TEXAS
TYLER W. HERRING
106052
LICENSED
ARCHITECT
07.18.2025

ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

KITCHEN AREA
MECHANICAL PLANS
O-M1.01

STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM (713) 300-6092
TEXAS ENG. FIRM REG. NO. F-018332
©2025 ALL RIGHTS RESERVED
1300 W. SAM HOUSTON PARKWAY N., SUITE 121, HOUSTON, TX 77043

## MECHANICAL SYMBOL SCHEDULE

| | |
|---|---|
| CWS | CONDENSER WATER SUPPLY |
| CWR | CONDENSER WATER RETURN |
| CHS | CHILLED WATER SUPPLY |
| CHR | CHILLED WATER RETURN |
| HWS | HEATING WATER SUPPLY |
| HWR | HEATING WATER RETURN |
| RS | REFRIGERANT SUPPLY |
| RR | REFRIGERANT RETURN |
| D | CONDENSATE LINE |
| | PETE'S PLUG |
| | ISOLATION VALVE |
| | ELECTRONIC CONTROL VALVE |
| | BUTTERFLY VALVE |
| | BALL VALVE |
| | UNION OR FLANGE |
| | STRAINER |
| | AUTOMATIC AIR VENT |
| T | LOCAL CONTROL THERMOSTAT |
| T | TEMPERATURE SENSOR |
| H | HUMIDITY SENSOR |
| FD | FIRE DAMPER |
| SD | SMOKE DAMPER |
| FSD | FIRE/SMOKE COMBINATION DAMPER |
| MD | MOTORIZED DAMPER |
| C | CARBON MONOXIDE SENSOR |
| C | CARBON DIOXIDE SENSOR |
| | SUPPLY AIR DIFFUSER |
| | RETURN AIR GRILLE |
| | EXHAUST GRILLE |
| RA | RETURN AIR OPENING IN WALL |
| VD | VOLUME DAMPERS |
| | DUCT ELEVATION CHANGE |
| | 90° DUCT ELBOW WITH TURNING VANES |
| | FLEXIBLE DUCT |
| M | DAMPER MOTOR |
| T | TEMPERATURE TRANSMITTER |
| FS | FLOW SWITCH |
| P | DIFFERENTIAL PRESSURE SENSOR |
| SD | DUCT SMOKE DETECTOR |
| PS | STATIC PRESSURE SENSOR |
| PH | STATIC PRESSURE SENSOR HI-LIMIT |
| | ACCESS PANEL |

| | |
|---|---|
| A.P. | ACCESS PANEL |
| AHU | AIR HANDLING UNIT |
| B | BOILER |
| CH | CHILLER |
| CHP | CHILLED WATER PUMP |
| CVT | CONSTANT VOLUME TERMINAL |
| DH | DEHUMIDIFIER |
| E/A | EXHAUST AIR |
| EF | EXHAUST FAN |
| F&B | FACE & BYPASS |
| FF | FLY FAN |
| HDT | HORIZONTAL DRAW THROUGH |
| HWP | HOT WATER PUMP |
| KEF | KITCHEN EXHAUST FAN |
| KSF | KITCHEN SUPPLY FAN |
| O/A | OUTSIDE AIR |
| OBD | OPPOSED-BLADES DAMPER |
| PT | PRE-TREAT |
| R/A | RETURN AIR |
| RAHU | ROOF-MOUNTED AIR HANDLING UNIT |
| S/A | SUPPLY AIR |
| SA | SOUND ATTENUATOR |
| SF | SUPPLY FAN |
| SPD | SPILTER DAMPER |
| SZ | SINGLE ZONE |
| VAV | VARIABLE AIR VOLUME |
| VB | VAV BOX |
| VD | VOLUME DAMPER |
| VDT | VERTICAL DRAW THROUGH |
| VFD | VARIABLE FREQUENCY DRIVE |
| WH | WATER HEATER |
| ⌀ | DESIGNATION FOR "ROUND" |
| ⌀ | DESIGNATION FOR "OVAL" |

## GENERAL MECHANICAL NOTES


1. REFER TO WRITTEN SPECIFICATIONS FOR ADDITIONAL INFORMATION.
2. COORDINATE INSTALLATION OF EQUIPMENT AND PIPING WITH THE ELECTRICAL CONTRACTOR TO INSURE NEC CLEARANCE (42 INCHES) IN FRONT OF ALL ELECTRICAL PANELS. DO NOT INSTALL DUCTWORK OR WATER PIPING OVER THE TOP OF ELECTRICAL PANELS SEE DETAIL 1/M2.01.
3. DUCT SIZES SHOWN ARE NET FREE AIR PASSAGE DIMENSIONS, DUCTS ARE NOT LINED, BUT ARE EXTERNALLY INSULATED. RUNOUTS TO CEILING OUTLETS SHALL BE EXTERNALLY INSULATED GALVANIZED SHEET METAL WITH SPIN-IN V.D. AT TRUNK TAPS, SEE DETAIL 1 & 2/M2.01.
4. REFER TO ARCHITECTURAL REFLECTED CEILING DRAWINGS FOR EXACT LOCATIONS OF CEILING OUTLETS IN RELATION TO OTHER CEILING ENTITIES. OUTLETS MUST BE COMPATIBLE WITH THE CEILING TYPES FOR THE VARIOUS AREAS.
5. IN AREAS WHERE SUPPLY AIR ENTERS CEILING CAVITY THRU RETURN AIR GRILLES AND FREE RETURNS TO AHU'S VIA CEILING CAVITY, PROVIDE RETURN AIR OPENING IN WALL-TO-DECK ABOVE CEILING THAT BLOCK PATH, REFER TO ARCHITECTURAL DRAWINGS. RETURN AIR ELBOWS SHALL BE SIZED AT 1 SQ. FT PER 400 CFM SUPPLY AIR.
6. ARRANGE PIPING CONNECTIONS TO ALL EQUIPMENT TO ALLOW EASY REMOVAL OF EQUIPMENT, SUB-ASSEMBLIES, COILS, FANS, MOTORS, FILTERS, ACCESS PANELS, ETC... PROVIDE UNIONS, FLANGES AND VALVES AT CONNECTIONS. PROVIDE AND INSTALL VICTAULIC JOINTS AT COILS, REF. SPECIFICATIONS. PLACE STOP VALVES ON SYSTEM SIDE OF REMOVABLE PIPE SECTIONS.
7. CONTRACTOR SHALL FIELD MEASURE STRUCTURAL ELEMENTS AND COORDINATE EQUIPMENT, PIPING AND DUCT ROUTING TO FIT EXISTING CONSTRUCTION. PROVIDE OFFSETS, BOOTS FOR ENVELOP OBSTRUCTIONS THAT CANNOT BE AVOIDED. CONSTRUCTION SHALL BE PER SMACNA FIGURE 2-10.

## AIR DEVICE SCHEDULE

| MARK | DESCRIPTION |
|---|---|
| A | CEILING DIFFUSER – 24" X 24" FACE, PATTERN TYPE, STEEL CONSTRUCTION, OBD/RADIATION DAMPER, WHITE FINISH, U.L. LISTED PRICE SCD |
| B | CEILING RETURN GRILLE – 24" X 24" PERFORATED FACE, STEEL CONSTRUCTION, RADIATION DAMPER, WHITE FINISH, U.L. LISTED PRICE PDFR |
| C | CEILING EXHAUST GRILLE – 24" X 24" PERFORATED FACE, STEEL CONST., OBD/RADIATION DAMPER, WHITE FINISH, NECK SIZE SHOWN, U.L. LISTED PRICE PDDR |

NOTES:

1. REFER TO ARCHITECTURAL REFLECTED CEILING PLAN TO VERIFY CEILING TYPES FOR AIR DEVICES.
2. ALL CEILINGS ARE FIRE RATED PER U.L. LISTINGS ON ARCHITECTURAL DRAWINGS. PROVIDE FIRE PROTECTION FOR ALL CEILING DEVICES PER DETAIL 13/M-17 AND SPECIFICATIONS.





### 6 KITCHEN UPBLAST EXHAUST FAN DETAIL

NO SCALE

NOTES

1. ARCHITECTURAL ROOF CURB INSTALLATION REQUIREMENTS SHALL SUPERCEDE THIS DETAIL.
2. INSTALL SHEETMETAL COVERING OVER WOOD BLOCKING IN THE AIRSTREAM OR OPEN TO THE CEILING CAVITY.





### 4 EXTERNALLY INSULATED DUCT SUPPORT DETAIL

NO SCALE

NOTES:

1. ROUND MEDIUM PRESSURE DUCT MAY BE SUPPORTED WITH DUCT STRAPS.
2. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.





### 2 DUCTWORK DETAIL

NO SCALE

NOTES:

1. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.





### 5 AIR DEVICE DETAIL

NO SCALE

NOTES:

1. RADIATION DAMPER SHALL ONLY BE PROVIDED IN CEILING DEVICES INSTALLED IN RATED CEILING ASSEMBLIES. REFER TO ARCHITECTURAL REFLECTED CEILING PLAN TO DETERMINE WHICH, IF ANY, CEILINGS ARE RATED.
2. REFER TO SPECIFICATIONS OF FOR ADDITIONAL INFORMATION AND REQUIREMENTS.




| TAP SIZE | ROD SIZE | DAMPER THICKNESS |
|---|---|---|
| UP TO 10" | 1/4" | 20 GA |
| OVER 10" | 3/8" | 18 GA |


HARDWARE MANUFACTURERS SHALL BE VENTLOCK, AMERICAN ELGEN, YOUNG AND DURO-DYNE.

### 3 DUCT TAP CONNECTION DETAIL

NO SCALE

NOTES:

1. DELETE CONICAL SECTION IF TOO LARGE FOR THE DUCT.
2. REFER TO SPECIFICATIONS OF FOR ADDITIONAL INFORMATION AND REQUIREMENTS.




### 1 MECHANICAL - ELECTRICAL COORDINATION DETAIL

NO SCALE

NOTES:

1. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.

STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM (713) 305-6282 | TEXAS ENG. FIRM REG. NO. F-018537-00 | 2025 ALL RIGHTS RESERVED
1300 W. SAM HOUSTON PARKWAY N., SUITE 175, HOUSTON, TX 77043

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

O

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459


SEAL

STATE OF TEXAS
TYLER W. HERRING
106052
LICENSED PROFESSIONAL ENGINEER
07.18.2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

MECHANICAL NOTES AND DETAILS
O-M2.01





## 5 RESIDENTIAL CLOTHES DRYER FLUE VENT

NO SCALE

NOTES:

1. VENT TERMINATION AT WALL FOR STACKABLE WASHER/DRYER SHALL BE AT 60" AFF.
2. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.





## 4 SUPPLY/EXHAUST KITCHEN PLENUM DETAIL

NO SCALE

NOTES:

1. xxxxx





## 3 ROOF EXHAUST FAN AND VENT DETAIL

NO SCALE


NOTES:

1. NO WOOD BLOCKING SHALL BE LEFT EXPOSED IN THE CEILING PLENUM. COVER ALL EXPOSED WOOD WITH 1/2" SHEETROCK OR 20 GAUGE GALVANIZED SHEETMETAL.
2. ROOF VENT WILL NOT HAVE FAN/MOTOR ASSEMBLY, DISCONNECT SWITCH OR OBD.
3. ARCHITECTURAL ROOF CURB INSTALLATION REQUIREMENTS SHALL SUPERCEDE THIS DETAIL WHERE APPLICABLE.
4. ALL FANS SCHEDULED TO BE PROVIDED WITH 140MPH WIND RATING, INCLUDING FACTORY PROVIDED CURB. CURB INSTALLATION SHALL FOLLOW MANUFACTURER'S REQUIREMENTS FOR SECURING TO ROOF AND EQUIPMENT WHERE IT DIFFERS FROM THE DETAIL.
5. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.




## 2 INLINE EXHAUST FAN DETAIL

NO SCALE




## 1 CABINET EXHAUST FAN

NO SCALE

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

O

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL

STATE OF TEXAS
TYLER W. HERRING
106052
LICENSED PROFESSIONAL ENGINEER
07.18.2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

MECHANICAL DETAILS (CONT'D.)

O-M2.02

STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM | (713) 300-4080
TEXAS ENG. FIRM REG. NO. F-8183 | (c) 2021 ALL RIGHTS RESERVED
13915 N. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77060

# ELECTRICAL AND LOW VOLTAGE LEGEND AND SYMBOLS

- A — TYPE 'A' LIGHT FIXTURE
- LIGHT FIXTURE WITH EMERGENCY BACKUP
- EXIT SIGN/EXIT SIGN WITH DIRECTIONAL ARROW
- EMERGENCY EGRESS LIGHT FIXTURE
- WALL MOUNTED FIXTURE OR SCONCE
- CEILING DOWNLIGHT OR CYLINDER
- WALL PACK FIXTURE
- INV — LIGHTING INVERTER

- 20A, 277V TOGGLE/3-WAY/4-WAY SWITCH
- 20A, 277V MOMENTARY 3-POSITION TOGGLE SWITCH
- 20A, 277V, MOMENTARY 3-POSITION KEY SWITCH
- 20A, 277V MAINTAINED 2-POSITION/3-WAY/4-WAY KEY SWITCH
- 20A, 277V TOGGLE SWITCH W/ INTEGRAL NIGHT LIGHT
- MOTOR RATED ON/OFF SWITCH, MP W/ PILOT LIGHT (SWITCH RATING SHALL BE ≥ UPSTREAM OCPD & VOLTAGE)
- DPST — DOUBLE POLE SINGLE THROW (DPST) SWITCH WITH RED PILOT LIGHT.
- TDR — TIMER SWITCH

## NETWORK LIGHTING CONTROLS

- MULTIBUTTON LOW VOLTAGE LIGHTING SWITCH PROVIDE NUMBER OF BUTTONS INDICATED IN SINGLE PLATE.
- MULTIPLE DIMMER SWITCHES PROVIDE NUMBER OF SWITCHES INDICATED IN SINGLE PLATE.
- MULTIPLE KEY TYPE SWITCHES PROVIDE NUMBER OF SWITCHES INDICATED IN SINGLE PLATE.
- VSC — WALL SENSOR SWITCH
- 20A, 277V, STANDALONE DIMMER SWITCH (DISPLAY CABINET)
- OCS — 360° CEILING SENSOR
- OCW — 180° CEILING SENSOR
- OCR — CEILING SENSOR
- OC — WALL MOUNT SENSOR
- PCO — DAYLIGHT PHOTOSENSOR
- RC / RCR — LIGHTING ROOM CONTROLLER/POWER PACK
- ELR — EMERGENCY LIGHTING RELAY/CONTROL UNIT
- PLC — PLUG LOAD CONTROLLER

- 20A, 125V SIMPLEX/DUPLEX/QUAD RECEPTACLE
- GFI — 20A, 125V DUPLEX RECEPTACLE WITH GFCI PROTECTION
- GFI WP — 20A, 125V DUPLEX RECEPTACLE WITH GFCI PROTECTION AND WEATHERPROOF COVER.
- GFI — REMOTE GFCI DEVICE, REF SPECS AND EDF GFI DETAIL.
- 20A, 125V DUPLEX/QUAD RECEPTACLE W/ USB-A PORTS PROVIDE 2-5A PORTS PER DEVICE — HUBBELL USB20A5
- 20A, 125V SIMPLEX/DUPLEX/QUAD IG/COMPUTER RECEPTACLE
- GFI — 20A, 125V, IG/COMPUTER DUPLEX RECEPTACLE WITH GFCI
- PLUG LOAD CONTROLLED DUPLEX
- NEMA / IEC / CS — NEMA/IEC/CS NUMBERED POWER OUTLET MATCH PROVIDED EQUIPMENT CONNECTION OR CIRCUIT.
- TV / IG — 20A, 125V IG DUPLEX RECEPTACLE AT PROJECTOR, TV, OR INTERACTIVE MEDIA LOCATION.
- LOW VOLTAGE OUTLET
- CEILING MOUNTED RECEPTACLE
- CEILING MOUNTED LOW VOLTAGE OUTLET
- SINGLE SERVICE FLOOR BOX WITH DUPLEX/QUAD REC
- SINGLE SERVICE FLOOR BOX WITH DUPLEX/QUAD IG REC
- SINGLE SERVICE LOW VOLTAGE FLOOR BOXES
- MULTI SERVICE FLOOR BOX WITH QUAD/QUAD IG REC
- CR — CORD REEL
- DC — DROP CORD
- EPO — EMERGENCY POWER OFF (EPO) SWITCH
- PB — PUSH BUTTON
- SP — TELEPOWER POLE

- J — J-BOX
- CEILING MOUNTED J-BOX
- CA — J-BOX FOR ACCESS CONTROL DEVICE
- HD — JUNCTION BOX AND FINAL CONNECTION TO HAND DRYER BY DIVISION 26.
- HDWR — JUNCTION BOX AND FINAL CONNECTION TO ELECTRIFIED DOOR HARDWARE BY DIVISION 26.
- HEAT — JUNCTION BOX AND FINAL CONNECTION TO HEAT TRACE EQUIPMENT BY DIVISION 26.
- WC — JUNCTION BOX AND FINAL CONNECTION TO POWERED PLUMBING EQUIPMENT BY DIVISION 26.
- SF — JUNCTION BOX AND FINAL CONNECTION TO SYSTEM FURNITURE BY DIVISION 26.

- CONTACTOR
- NON-FUSED DISCONNECT SWITCH
- NON-FUSED DOUBLE THROW DISCONNECT
- FUSED DISCONNECT SWITCH
- DISCONNECT/CB WITH SHUNT TRIP
- ENCLOSED CIRCUIT BREAKER
- MOTOR STARTER 'VFD' INDICATES VARIABLE FREQUENCY DRIVE MOTOR STARTER
- MOTOR STARTER WITH INTEGRAL DISCONNECT
- MOTOR
- TC — TIME CLOCK

- ELECTRICAL PANELBOARD
- ELECTRICAL METER
- SPD — TVSS OR SPD
- GANN — GENERATOR REMOTE ANNUNCIATOR

- LOW VOLTAGE CABLING PATHWAY, REF. SPECIFICATIONS

## KITCHEN SYMBOL LEGEND

- LOAD CENTER, BY FOOD SERVICE PROVIDE UNDERGROUND CONDUIT STUBBED UP AT LOAD CENTER LOCATION PER SUBMITTAL SHOP DRAWINGS.
- P — POINT OF SALE EQUIPMENT, BY FOOD SERVICE. PROVIDE UNDERGROUND CONDUIT STUBBED UP POS LOCATION PER SUBMITTAL SHOP DRAWINGS.
- F — REMOTE FIRE PULL, REFERENCE INSTALLATION DETAIL
- B — BELL/BUZZER WITH 120V TO LOW VOLTAGE TRANSFORMER
- D — DROP CORD
- DB — DOORBELL BUTTON
- V — CEILING STROBE FOR ENTRAPMENT ALARM
- V — CLR/FRZR — WALL STROBE FOR ENTRAPMENT ALARM

## COORDINATION SYMBOL LEGEND

- DDC — HVAC CONTROL PANEL. REQUIRES POWER AND DATA CONNECTIONS WITHIN CABINET COOR EXACT LOCATION AND REQUIREMENTS WITH CONTROLS CONTRACTOR PRIOR TO ROUGH-IN.
- SD — SMOKE DAMPER
- FSD — FIRE/SMOKE COMBINATION DAMPER
- M / MD — MOTORIZED DAMPER

## SITE PLAN

- UTILITY POLE
- POLE MOUNTED TRANSFORMER BANK
- SITE POLE LIGHT
- UGE — FLUSH IN GRADE ELECTRICAL PULL BOX
- LV / T — FLUSH IN GRADE, LOW VOLTAGE HAND HOLE
- CONCRETE BOLLARD
- (X)PP — POWER POLE
- (X)SP — SERVICE POLE OR RACK
- (X)XP — XFMR POLE
- (X)LVP — LOW VOLTAGE POLE
- (X)TP — TRANSITION POLE
- OHP — OVERHEAD POWER WIRING
- 480V — 480V OVERHEAD POWER WIRING
- UGP — UNDERGROUND PRIMARY ELECTRICAL
- UGS — UNDERGROUND SECONDARY ELECTRICAL
- UGE — UNDERGROUND EMERGENCY ELECTRICAL

## DIVISION 28 LEGENDS

### FIRE ALARM

- F — FIRE ALARM PULL STATION W/ STOPPER II
- F / S — WALL FIRE ALARM AUDIO/VISUAL DEVICE
- WP — OUTDOOR WEATHERPROOF FIRE AUDIO/VISUAL DEVICE
- H — WALL FIRE ALARM AUDIO DEVICE
- V — WALL FIRE ALARM VISUAL DEVICE
- H / S — CEILING FIRE ALARM AUDIO/VISUAL DEVICE
- H — CEILING FIRE ALARM AUDIO DEVICE
- V — CEILING FIRE ALARM VISUAL DEVICE
- DH / V — DUCT SMOKE DETECTOR
- I / S — CEILING SMOKE DETECTOR
- H — CEILING HEAT DETECTOR
- CO — CEILING CARBON MONOXIDE DETECTOR
- S / CO — CEILING COMBINATION SMOKE/CARBON MONOXIDE DETECTOR
- FR — FIRE ALARM RELAY FOR STAGE SOUND RACK OVERRIDE
- BD — BEAM SMOKE DETECTOR
- FANN — FIRE ALARM REMOTE ANNUNCIATOR OR LOCAL OPERATOR'S CONSOLE
- FACP — FIRE ALARM CONTROL PANEL
- FAPS — FIRE ALARM POWER SUPPLY/AMPLIFIER

- G — INDICATES DEVICE WITH PROTECTIVE GUARD
- WG — INDICATES DEVICE WITH WIRE GUARD
- HC — INDICATES DEVICE RATED FOR HAZARDOUS CONDITIONS
- SD — SMOKE DAMPER
- FSD — FIRE/SMOKE COMBINATION DAMPER

## MULTI-SERVICE FLOOR BOX NOTES

FLOOR POWER AND LOW VOLTAGE

PROVIDE HEAVY-DUTY MULTI-GANG FLUSH IN GRADE OR FIRE RATED POKE-THRU OUTLET WITH HEAVY DUTY METAL HINGED COVER WITH CABLE EXIT SLOT.
FLOOR BOX MUST BE RATED FOR INSTALLATION IN GRADE.

FOR EACH FLOOR BOX PROVIDE:
1. PROVIDE:
   - 1.A. ONE QUAD OR TWO DUPLEX RECEPTACLES.
   - 1.B. PROVIDE IG RECEPTACLES WHERE SHOWN.
   - 1.C. POWER CONNECTION TO TABLE (WHERE SHOWN)
2. BLANK STAINLESS STEEL COVER FOR UN-USED GANGS.
3. PROVIDE ONE 3/4"C UNDERGROUND CONDUIT FOR POWER.
4. PROVIDE ONE 1"C UNDERGROUND CONDUIT WITH WATERPROOF INNER DUCT FOR DATA.
5. PROVIDE ONE 1"C UNDERGROUND CONDUIT WITH WATERPROOF INNER DUCT FOR LOW VOLTAGE CABLING
6. PROVIDE DIVIDERS TO MAINTAIN SEPARATION BETWEEN SERVICES.

UNDERGROUND CONDUITS MUST BE WATER TIGHT TO PREVENT MOISTURE ENTERING CONDUITS.
DO NOT COMBINE CONDUIT FOR POWER & LOW VOLTAGE.

REFERENCE FLOOR PLANS AND SPECIFICATIONS FOR QUANTITY OF DATA DROPS AND ADDITIONAL INFORMATION.

COORDINATE WITH ARCHITECT TO PROVIDE COVER/RING TO MATCH FLOOR MATERIAL AND SUBMIT COVER FINISH FOR ARCHITECT TO SELECT PRIOR TO ORDERING.

## GENERAL NOTES / TAGS

| | |
|---|---|
| +18" | INDICATES DEVICES AT +18" AFF |
| +42" | INDICATES DEVICES AT +42" AFF |
| +96" | INDICATES DEVICES AT +96" AFF |
| +12 FT | INDICATES DEVICES AT +12 FT AFF, ETC. |
| * | INDICATES DEVICES ABOVE COUNTER, REF ARCH |
| CLG | INDICATES DEVICES AT CEILING |
| PMR | INDICATES PEDESTAL MOUNTED DEVICE, REF PMR DETAIL |
| TV | INDICATES DEVICES AT TELEVISION/DISPLAY LOCATION |
| IM | INDICATES DEVICES AT INTERACTIVE MEDIA LOCATION |
| PROJ | INDICATES DEVICES AT PROJECTOR LOCATION |
| S | INDICATES SURFACE MOUNTED DEVICE |
| IEC | INDICATES IEC POWER OUTLET |
| NEMA | INDICATES NEMA NUMBERED POWER OUTLET |
| GFI | INDICATES GROUND FAULT INTERRUPT (GFI) PROTECTION |
| WP | INDICATES WEATHERPROOF DEVICES |
| GFI WP | INDICATES GFI PROTECTED WEATHERPROOF DEVICE |
| G | INDICATES DEVICE WITH PROTECTIVE GUARD |
| WG | INDICATES DEVICE WITH WIRE GUARD |
| 3R | INDICATES NEMA 3R RATED DEVICE |
| 4XSS | INDICATES NEMA 4XSS RATED DEVICE |
| EM | INDICATES DEVICE ON EM/STANDBY POWER |
| VFD | INDICATES VARIABLE FREQUENCY DRIVE (VFD) |
| E | EXISTING DEVICES TO REMAIN |
| D | EXISTING DEVICES TO BE DEMO/REMOVED |
| R | EXISTING DEVICES TO BE RELOCATED |
| REP | EXISTING DEVICES TO BE REPLACED |
| | (X) = (E) FOR EXISTING |
| | (X) = (D) FOR DEMO |
| | (X) = (R) FOR RELOCATION |
| | (X) = (N) FOR NEW |

- HOMERUN TO CIRCUIT NOTED

1. RECEPTACLES AND DATA OUTLETS SHALL BE MOUNTED AT +18" AFF UNLESS NOTED ON THE DRAWINGS.
2. REF. SPECIFICATIONS FOR MOUNTING HEIGHT OF OTHER DEVICES.
3. ELECTRICAL RECEPTACLES, TELEPHONES, ETC... ARE SHOWN FOR GENERAL LOCATION. HEIGHTS ARE NOTED SO THE ESTIMATOR WILL KNOW WHETHER THEY ARE ABOVE OR BELOW COUNTERS. PRIOR TO INSTALLATION, REVIEW THE ARCHITECTURAL DRAWINGS AND SPECIFICATIONS. IN THE EVENT OF CONFLICT, THE ARCHITECT'S LOCATION WILL GENERALLY PREVAIL BUT SHOULD BE CLARIFIED BY RFI. PROVIDE DEVICES SHOWN ON THE ELECTRICAL DRAWING EVEN IF NOT SHOWN ON ARCHITECTURAL DRAWINGS.
4. COORDINATE POWER AND DATA WITH THE FURNITURE SUPPLIER PRIOR TO ROUGH-IN. AT CASEWORK WITH KNEE SPACE, MOUNT RECEPTACLES AND DATA OUTLETS IN KNEE SPACE. COORDINATE WITH ARCHITECT AND FURNITURE SUPPLIER TO ENSURE THAT PROTECTIVE GROMMETS ARE PROVIDED IN THE COUNTER.
4. ALL DEVICES SHOWN AT THE SAME LOCATION AND ELEVATION SHALL BE GROUPED TOGETHER AND SPACED 2 INCHES BETWEEN BOXES.
5. PROVIDE SS COVER PLATE FOR ALL EMPTY JBOX.
6. ALL NON-LOCKING 125V AND 250V, 15A AND 20A RECEPTACLES SHALL BE TAMPER RESISTANT TYPE.

STANTON ENGINEERING GROUP
INFORMATION-DESIGN (713) 360-6080
TEXAS ENG. FIRM REG NO. F-018537-0 © 2025 ALL RIGHTS RESERVED
1200 W. SAM HOUSTON PKWY NORTH, SUITE 125, HOUSTON, TX 77043

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL

STATE OF TEXAS — GEORGE L. STANTON — 38582 — REGISTERED PROFESSIONAL ENGINEER
07.18.2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL AND FIRE ALARM SCHEDULES
o-E.000

PROVIDE CONDUIT & SLEEVES THRU FIRE WALLS, WALLS AND FLOORS FOR LOW VOLTAGE CABLING WIRING, ETC.

ALL CONDUIT & J-BOXES FOR LOW VOLTAGE CABLING SHALL BE PROVIDED AND INSTALLED BY THE ELECTRICAL CONTRACTOR. ALL LOW VOLTAGE CABLING IN WALLS, EXPOSED AREAS AND ABOVE INACCESSIBLE CEILINGS SHALL REQUIRE CONDUIT AND J-BOXES. REFERENCE SPECIFICATIONS AND TECHNOLOGY DOCUMENTS FOR ADDITIONAL INFORMATION/REQUIREMENTS.

PULL BOXES AND BELOW GRADE CONDUIT FOR LOW VOLTAGE CABLING, WIRING, ETC. BY ELEC CONTRACTOR.

## FIRE ALARM SYSTEM DESCRIPTION AND SEQUENCE OF OPERATION

1. FIRE ALARM SYSTEM SHALL BE DESIGNED TO MEET NFPA REQUIREMENTS AS WELL AS CITY AND NATIONAL BUILDING CODES. PROVIDE COMPLETE FIRE ALARM SYSTEM, DEVICES AND WIRING.
2. INSTALL FIRE ALARM CONTROL PANEL IN RECEPTION AREA. INSTALL REMOTE POWER SUPPLY PANELS IN MECHANICAL/ELECTRICAL ROOMS.
3. FIRE ALARM PANEL, POWER SUPPLIES, DEVICES, ETC. SHALL BE MANUFACTURED BY THE SAME MANUFACTURER AS THE FIRE ALARM CONTROL PANEL.
4. FIRE ALARM REMOTE POWER SUPPLIES AND PANELS SHALL BE LOCATED IN MECHANICAL OR ELECTRICAL ROOMS ONLY. DO NOT LOCATE IN STORAGE ROOMS, DATA CLOSETS OR FINISHED SPACES.
4. PROVIDE AUDIBLE, INTELLIGIBLE AND VISUAL ALARM COVERAGE OF THE AREA OF RENOVATION AS REQUIRED BY CODE.
5. PROVIDE SMOKE DETECTORS AT EACH FIRE ALARM PANEL, REMOTE TRANSPONDER PANEL, BOOSTER PANEL AND REMOTE ANNUNCIATOR PER NFPA 72.
6. IN ADDITION TO THE SPECIFIED FIRE ALARM EQUIPMENT, THE FIRE ALARM CONTRACTOR SHALL PROVIDE
   6.A. SURGE PROTECTORS FOR ALL NEW 120V POWER CONNECTIONS TO FIRE ALARM EQUIPMENT.
   6.B. SURGE PROTECTORS FOR ALL SIGNALING LINE CIRCUITS (SLC), NOTIFICATION CIRCUITS AND INITIATING CIRCUITS CONNECTED TO THE FIRE ALARM CONTROL PANEL WHICH LEAVE THE BUILDING.
7. SHOULD ANY DETECTOR, MONITOR OR PULL STATION ACTIVATE, ALL SPEAKERS SHALL SOUND AND STROBES FLASH. AIR HANDLING EQUIPMENT SHALL BE DEACTIVATED. AN ALARM SIGNAL SHALL BE SENT TO A REMOTE LOCATION VIA AUTOMATIC DIALER. ALSO, DE-ENERGIZE SUPPLY FANS, EXHAUST FANS AND OTHER AIR CIRCULATING DEVICES IF 2000 CFM OR OVER, SERVING THE AREA IN ALARM.
8. ALL LOW VOLTAGE WIRING SHALL BE FPLP RATED WIRE, WITH MINIMUM WIRE SIZE PER SPECIFICATIONS.
   8.A. PLENUM RATED CABLE ABOVE ACCESSIBLE CEILING SHALL BE SUPPORTED BY J-HOOKS, SPACED AT FOUR (4) FEET ON CENTER.
   8.B. INSTALL FIRE ALARM CABLES IN CONDUIT FOR AREAS WITHOUT CEILING OR ABOVE INACCESSIBLE CEILINGS.
   8.C. EXPOSED CONDUIT IN FINISHED SPACES SHALL BE ALLOWED WHERE NO OTHER OPTION EXISTS AND ONLY WITH PRIOR WRITTEN APPROVAL BY THE OWNER. ALL EXPOSED CONDUIT SHALL BE PAINTED TO MATCH.
   8.D. ALL CABLING THROUGH WALLS, FIRE WALLS AND FLOORS SHALL BE INSTALLED IN SLEEVES WITH PROTECTIVE BUSHINGS ON BOTH ENDS.
9. FIRE ALARM SYSTEM SHALL BE MONITORED BY A UL LISTED CENTRAL RECEIVING STATION.
10. INTERLOCK LIGHTING CONTROL PANELS WITH FIRE ALARM SYSTEM TO ENABLE ALL LIGHTING UPON ACTIVATION.
11. REFER TO THE WRITTEN SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.

## FIRE ALARM SYSTEM NOTES

1. GENERAL CONTRACTOR SHALL COORDINATE WITH ELECTRICAL AND FIRE ALARM SUBCONTRACTOR FOR LOCATIONS OF REMOTE POWER SUPPLIES. FIRE ALARM POWER SUPPLIES ARE NOT SHOWN ON THIS DRAWING AND SHALL BE LOCATED BY FIRE ALARM SUBCONTRACTOR IN ORDER TO ACCOMMODATE HIS FIRE ALARM SYSTEM BATTERY AND VOLTAGE DROP CALCULATIONS PER MANUFACTURER'S RECOMMENDATION & NFPA REQUIREMENTS. ELECTRICAL CONTRACTOR SHALL INCLUDE ADDITIONAL DEDICATED 120V CIRCUITS IN BASE BID TO SERVE FIRE ALARM POWER SUPPLIES IN DIFFERENT AREAS. PROVIDE 2–12 +12G, 3/4"C AND SPARE 20A/1P CB(S) IN LOCAL LIFE SAFETY EMERGENCY 120V PANELS TO SERVE FIRE ALARM REMOTE POWER SUPPLIES.
2. FIRE ALARM CONTRACTOR IS RESPONSIBLE FOR DESIGN AND FOR FINAL CORRECT LOCATION OF DEVICES TO RELIEVE NUISANCE ALARMS, SUCH AS INSTALLING A HEAT DETECTOR IN FRONT OF AN OVEN WHICH WILL RELEASE STEAM, THUS POTENTIALLY SETTING OFF THE ALARM. ALSO, THE CONTRACTOR IS RESPONSIBLE FOR DETECTORS REQUIRED BY CODE EVEN IF NOT SHOWN ON DRAWING, LIKE A CLOSET. IF THERE IS UNCERTAINTY, BRING UP DURING THE BID PROCESS AND THEY WILL BE ADDRESSED DURING THE BIDDING PROCESS.
3. FIELD VERIFY ENVIRONMENTAL ISSUES THAT CAN ADVERSELY AFFECT OPERATION OF SMOKE DETECTORS. DO NOT LOCATE NEAR AIR FLOW DEVICES LEADING TO PREMATURE BUILD UP OF DUST CAUSING NUISANCE TROUBLE SIGNALS. DEVICE RELOCATION OR TYPE CHANGE WILL BE COVERED UNDER WARRANTY.

## FIRE ALARM SCOPE OF WORK

1. THERE IS AN EXISTING FIRE ALARM SYSTEM IN EACH BUILDING.
   1.A. TEST THE EXISTING SYSTEM PRIOR TO BEGINNING DEMO. NOTE ANY FAULTS OR TROUBLES AND PROVIDE A WRITTEN REPORT TO THE OWNER.
   1.B. EXPAND THE EXISTING SYSTEM AS REQUIRED TO INTEGRATE THE NEW DEVICES IN THE AREA OF RENOVATION.
2. PROVIDE WIRING AND DEVICES AS INDICATED TO PROVIDE COMPLETE AUDIBLE, INTELLIGIBLE AND VISUAL ALARM COVERAGE OF RENOVATED AREAS AS REQUIRED BY CODE.
   2.A. PROVIDE SMOKE DETECTOR COVERAGE OF ALL STORAGE ROOMS AND ADDITIONALLY AS SHOWN ON THE DRAWINGS.
   2.B. PROVIDE HEAT DETECTOR COVERAGE OF THE KITCHEN, CUSTODIAL ROOMS, AND ADDITIONALLY AS SHOWN ON THE DRAWINGS.
   2.C. PROVIDE DUCT MOUNTED DETECTORS AT EACH NEW AIR HANDLING UNIT SUPPLY AND RETURN CONNECTION EXCEEDING 2000 CFM. IF FREE AIR RETURN, PROVIDE FREE AIR DETECTING COVERAGE OF THE RETURN AIR OPENINGS TO THE MECHANICAL ROOM. ENSURE AIR FLOW CANNOT PREVENT OPERATION OF THE DETECTORS AND PROVIDE ADEQUATE CLEARANCE PER NFPA 72.
   2.D. CONTROL RELAYS SHALL BE LOCATED WITHIN 3 FT OF THE CONTROLLED CIRCUIT OR APPLIANCE.
3. PROVIDE SMOKE DETECTORS AT EACH NEW FIRE ALARM PANEL, REMOTE TRANSPONDER PANEL, BOOSTER PANEL AND REMOTE ANNUNCIATOR PER NFPA 72.
4. PROVIDE LED REMOTE ALARM WITH ENGRAVED STAINLESS STEEL PLATE WHERE DUCT DETECTORS ARE NOT LOCATED IN MECHANICAL ROOM, LOCATED ABOVE CEILINGS OR WHERE MOUNTED TOO HIGH OR VIEW IS BLOCKED BY DUCTWORK IN MECHANICAL ROOM.
   4.A. REMOTE LED LIGHT INDICATOR FOR DUCT SMOKE DETECTORS SHALL BE MOUNTED FLUSH IN CEILING OR MOUNTED IN WALL AT +7FT.
   4.B. STAINLESS STEEL PLATE SHALL BE ENGRAVED WITH THE DUCT SMOKE DETECTOR AS–BUILT IDENTIFICATION NUMBER.
5. REFER TO THE WRITTEN SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.

## SPARES

1. THE FIRE ALARM CONTRACTOR SHALL INCLUDE IN HIS BID THE COST TO PROVIDE AND INSTALL THE ADDITIONAL SPARE PARTS AND ASSOCIATED CABLING PER THE SPECIFICATIONS. SPARES SHALL BE INSTALLED AS INSTRUCTED BY THE OWNER. UNINSTALLED DEVICES SHALL BE DELIVERED TO THE OWNER AS ATTIC STOCK.

## GENERAL RENOVATION AND REMODELING NOTES

1. READ ALL MEP AND ARCH. DRAWINGS TO IDENTIFY AREAS OF RENOVATION AND SCOPE OF WORK.
2. ALL RENOVATION AND DEMOLITION WORK SHALL NOT AFFECT AREAS NOT INCLUDED IN THE AREAS OF WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE CONTINUITY OF ALL SERVICES (POWER, TELEPHONE, FIRE ALARM, DATA, SECURITY, ETC.) IN NON–DEMOLITION/RENOVATION AREAS. ALL SERVICES SHALL BE MAINTAINED AT ALL TIMES.
3. ALL OUTAGES AFFECTING NON–DEMOLITION/RENOVATION AREAS SHALL BE SCHEDULED WITH THE OWNER WITH A MINIMUM 2 WEEKS ADVANCE NOTICE. OUTAGES SHALL BE COORDINATED WITH OTHER TRADES TO MINIMIZE THE QUANTITY AND IMPACT ON BUILDING OPERATION.
4. THIS ELECTRICAL DRAWING ONLY SHOWS SOME EXISTING ELECTRICAL PANELS, DEVICES AND LIGHT FIXTURES IN AREAS OF RENOVATION. ALL OTHER ELECTRICAL EQUIPMENT, WIRING DEVICES, LOW VOLTAGE SYSTEMS, J–BOXES AND CONDUITS SHALL BE LOCATED AND FIELD VERIFIED BY CONTRACTOR.
5. CONTRACTOR SHALL FIELD VERIFY AND MARK UP THE FOLLOWINGS IN AREAS OF RENOVATION:
   5.A. EXISTING DATA, AUDIO, VIDEO, SPEAKERS AND OTHER LOW VOLTAGE OUTLETS AND DEVICES.
   5.B. EXISTING CEILING MOUNTED PROJECTORS.
   5.C. EXISTING SECURITY, CCTV, ACCESS CONTROL DEVICES.
   5.D. EXISTING FIRE ALARM DEVICES.
   5.E. EXISTING WIRELESS ACCESS POINTS AND GRID LABELING.
   5.F. EXISTING LIGHT FIXTURES AND SWITCHES.
   5.G. EXISTING ELECTRICAL DEVICES, J–BOXES, CONDUIT, WIRING, WIRING SUPPORTS, ETC.
   5.H. EXISTING ELECTRICAL SWITCHGEAR.
   5.I. EXISTING CONTROL PANELS AND CONTROL CIRCUITS.
   5.J. EXISTING HANGER WIRE FROM CONC. CEILING.
6. ALL REMOVED DEVICES SHALL BE OFFERED TO THE OWNER AS SALVAGE.
7. ALL EXISTING DEVICES SHALL BE REINSTALLED IN NEW CEILINGS AT SAME LOCATION EXCEPT WHERE SHOWN TO BE NEW.
8. CONDUIT/WIRE NOT TO BE REUSED SHALL BE REMOVED ALL THE WAY BACK TO THE UPSTREAM EQUIPMENT.
   8.A. PROVIDE ADDITIONAL SUPPORTS FOR EXISTING CONDUIT/WIRE TO REMAIN TO MEET CURRENT CODE REQUIREMENTS.
9. ANY MATERIAL THAT HAS SALVAGE VALUE SHALL BE OFFERED TO THE OWNER, AND IF ACCEPTED, DELIVERED TO HIS WAREHOUSE. IF NOT ACCEPTED IT SHALL BE PROPERLY DISPOSED OF WITH THE OTHER CONSTRUCTION DEBRIS.
10. RELOCATE CONDUIT AS NECESSARY TO ALLOW NEW OR MODIFIED CONSTRUCTION. REPAIR EXISTING ELECTRICAL SYSTEMS DAMAGED BY CONSTRUCTION ACTIVITES.
11. WHERE PARTIAL CIRCUITS OR SYSTEMS ARE TO BE REUSED, ENSURE THAT THEY REMAIN ACTIVE. WHERE EXISTING EQUIPMENT IS RELOCATED OR REPLACED WITH NEW, MODIFY, EXTEND AND RELOCATE EXISTING CIRCUIT TO CONNECT TO EQUIPMENT, UNLESS SHOWN TO HAVE NEW CIRCUIT.
12. WHERE AUXILIARY SYSTEMS SUCH AS SECURITY, DATA, SOUND, ETC. INTERFACE WITH EXISTING EQUIPMENT THAT IS REPLACED OR MODIFIED (MECHANICAL, ELECTRICAL OR PLUMBING), DISCONNECT AND RECONNECT THESE SYSTEMS.
13. WHERE NEW CIRCUIT BREAKERS ARE TO BE INSTALLED IN EXISTING PANELS OR SWITCHBOARD, VERIFY THAT THE CIRCUIT BREAKER WILL FIT IN THE ALLOTTED SPACE. PROVIDE NEMA 1 ENCLOSURE ADJACENT TO PANEL & WIRE CONNECT TO BUSSING IF THERE IS INSUFFICIENT SPACE.
14. WHERE PARTIAL CIRCUITS OR SYSTEMS ARE TO BE REUSED, ENSURE THAT THEY REMAIN ACTIVE. WHERE EXISTING EQUIPMENT IS RELOCATED OR REPLACED WITH NEW, MODIFY, EXTEND AND RELOCATE EXISTING CIRCUIT TO CONNECT TO EQUIPMENT, UNLESS SHOWN TO HAVE NEW CIRCUIT.
15. WHEN REPLACING LIGHTS AND CEILINGS, ENSURE THAT EXISTING DATA, TELEVISION AND PA CABLES TO REMAIN CONTINUE TO MEET THE CURRENT STANDARDS. FOR DATA CABLES, THIS IS THE IEEE 802.1. FOR TELEVISION AND PA CABLE, A FOUR INCH DISTANCE IS NEEDED FROM ALL LIGHT FIXTURES. NEW DROP LOCATION SHOULD BE WITHIN THREE FEET OF POWER OUTLET.
16. PAINT NEW AND EXISTING EXPOSED RACEWAY IN AREAS OF RENOVATION TO MATCH FINISHES.
17. ANY DAMAGE TO EXISTING BUILDING, ELECTRICAL EQUIPMENT, WIRING DEVICES, CONDUIT, WIRING, ETC. SHALL BE REPLACED BY THE CONTRACTOR AT NO COST TO THE OWNER. ALL MATERIALS USED FOR THE REPLACEMENT MUST MEET RENOVATION PROJECT STANDARDS.
18. INTERESTED CONTRACTORS MUST VISIT THE SITE PRIOR TO BIDDING TO BECOME FAMILIAR WITH THE PROJECT REQUIREMENTS AND EXISTING CONDITIONS AND SHALL INCLUDE IN THEIR PROPOSALS COSTS TO REPAIR, RELOCATE, MODIFY AND REMOVE EXISTING ELEMENTS AS REQUIRED TO COMPLETE INSTALLATION OF ALL SYSTEMS SHOWN ON THESE DRAWINGS.
19. SEE DRAWINGS FOR ADDITIONAL REQUIREMENTS.

## ELEC REQUIREMENTS FOR BUILDING RENOVATION

1. ELECTRICAL CONTRACTOR SHALL BEGIN FIELD VERIFYING ALL EXISTING BRANCH CIRCUITS FOR EXISTING AREAS TO BE RENOVATED IMMEDIATELY AFTER THE CONTRACT IS ISSUED.
2. ELECTRICAL CONTRACTOR SHALL FIELD VERIFY EXISTING CIRCUITS WITH OWNER'S MAINTENANCE PERSONNEL AFTER NORMAL BUILDING HOURS AS REQUIRED.
3. ELECTRICAL CONTRACTOR SHALL INCLUDE COST RELATED TO FIELD VERIFY EXISTING CIRCUITS IN BASE PROPOSAL.
4. FIND AND RECORD ALL EXISTING DEVICES IN CEILINGS, WALLS AND CASEWORK IN AREAS TO BE RENOVATED. PROVIDE A COPY OF THE FIELD VERIFIED DEVICE DRAWINGS TO OWNER PRIOR TO BEGINNING WORK.
5. ALL EXISTING DEVICES TO REMAIN SHALL BE REINSTALLED IN NEW CEILINGS AND WALLS EXCEPT WHERE INDICATED TO BE REMOVED/RELOCATED/REPLACED.
6. EXISTING DEVICES IN WALLS TO BE FURRED OUT OR RECEIVE NEW SURFACE TREATMENT SHALL REMAIN. EXTEND J-BOX TO NEW WALL SURFACE AND RECONNECT TO EXISTING CIRCUITS. EXTEND WIRING/CABLING FROM NEAREST ACCESSIBLE POINT AS NECESSARY.
7. REINSTALL ALL DEVICES NOT SHOWN TO BE REMOVED.
8. EXISTING LIGHT FIXTURES SHALL REMAIN EXCEPT WHERE SHOWN AS NEW. EXTEND EXIST CONDUIT AND WIRE DOWN TO NEW LIGHT FIXTURES, REFERENCE SPECIFICATIONS FOR ADDITIONAL INFORMATION.
9. ALL EXISTING EXIT SIGNS SHALL BE REINSTALLED AND RECONNECTED TO EXISTING CIRCUITS EXCEPT IN CORRIDORS AND AREAS OF RENOVATION SHOWING NEW.
10. ALL NEW DEVICES IN EXISTING WALLS IN FINISHED SPACES SHALL BE INSTALLED FLUSH MOUNTED, NO EXPOSED CONDUIT OR WIREMOLD ALLOWED. CUT EXISTING WALLS AND PATCH/REPAIR TO MATCH EXISTING AS REQUIRED.
    10.1. DEVICES/CONDUIT IN CUSTODIAL, MECHANICAL AND ELECTRICAL ROOMS MAY BE EXPOSED AND SURFACE MOUNTED.
11. PROVIDE NEW DIRECTORY FOR ALL EXISTING AND NEW PANELS SHOWING FIELD VERIFIED CIRCUITS.
12. ANY FEEDER AND BRANCH CIRCUIT NOT TO BE REUSED SHALL BE REMOVED COMPLETELY UP TO CB IN EXISTING PANEL.
13. ANY CIRCUIT OR PARTIAL CIRCUIT TO BE REUSED SHALL REMAIN ACTIVE.

## GENERAL EQUIPMENT ELECTRICAL NOTE

THE ELECTRICAL DESIGN HAS BEEN COORDINATED FOR SPACE, INSTALLATION AND ELECTRICAL REQUIREMENTS WITH EQUIPMENT THAT IS SCHEDULED BY OTHER DIVISIONS. THE REQUIREMENTS FOR OTHER EQUIPMENT AND MODELS FROM ACCEPTABLE MANUFACTURERS HAVE NOT BEEN VERIFIED OR COORDINATED. THE GENERAL CONTRACTOR SHALL VERIFY THESE REQUIREMENTS PRIOR TO USING OTHER EQUIPMENT IN HIS BID AND INCLUDE ANY ADDITIONAL COSTS FOR INSTALLATION OF THE EQUIPMENT. THIS INCLUDES GENERAL CONSTRUCTION AND MEP COSTS.

ELECTRICAL CONTRACTOR SHALL COORDINATE WITH OWNER/OTHER TRADES FOR EXACT ELECTRICAL REQUIREMENTS OF EQUIPMENT PRIOR TO ORDERING CB(S). FIELD VERIFY EQUIPMENT NAMEPLATE RATINGS AND EQUIPMENT CONNECTION LOCATIONS WITH OTHER TRADES PRIOR TO ROUGH–IN.

TYPICAL OF HVAC EQUIPMENT, SHOP EQUIPMENT, KITCHEN EQUIPMENT, ELECTRIC ROLLUP DOORS, ETC.

## GENERAL ELECTRICAL NOTES

1. REFER TO THE WRITTEN SPECIFICATIONS FOR ADDITIONAL INFORMATION.
2. INSTALL SYSTEMS IN ACCORDANCE WITH THE NATIONAL ELECTRIC CODE.
3. PROVIDE LIGHT FIXTURE FIRE PROTECTION AND CONDUIT FIRE SEALING TO MAINTAIN FIRE RATING OF WALLS AND CEILINGS PER ARCHITECT'S SCHEDULE. REF. SPECIFICATIONS AND ARCH. DRAWINGS FOR ADDITIONAL INFORMATION.
4. ELECTRICAL RECEPTACLES, TELEPHONES, ETC... ARE SHOWN FOR GENERAL LOCATION. HEIGHTS ARE NOTED SO THE ESTIMATOR WILL KNOW WHETHER THEY ARE ABOVE OR BELOW COUNTERS. PRIOR TO INSTALLATION, REVIEW THE ARCHITECTURAL DRAWINGS AND SPECIFICATIONS. IN THE EVENT OF CONFLICT, THE ARCHITECT'S LOCATION WILL GENERALLY PREVAIL BUT SHOULD BE CLARIFIED BY RFI. PROVIDE DEVICES SHOWN ON THE ELECTRICAL DRAWING EVEN IF NOT SHOWN ON ARCHITECTURAL DRAWINGS.
5. COORDINATE POWER AND DATA WITH THE FURNITURE SUPPLIER PRIOR TO ROUGH–IN. AT CASEWORK WITH WIRE SPACE, MOUNT RECEPTACLES AND DATA OUTLETS IN KNEE SPACE. COORDINATE WITH ARCHITECT AND FURNITURE SUPPLIER TO ENSURE THAT PROTECTIVE GROMMETS ARE PROVIDED IN THE COUNTER.
6. DO NOT INSTALL ELECTRICAL PANELS AND TRANSFORMERS UNTIL 1/4" SCALE DRAWINGS SHOWING LOCATION OF THIS EQUIPMENT RELATIVE TO MECHANICAL/PLUMBING EQUIPMENT, DUCTWORK AND PIPING IS SUBMITTED AND APPROVED. NEC CODE CLEARANCE MUST BE MAINTAINED.
7. ELECTRICAL EQUIPMENT HAS BEEN COORDINATED WITH PIPING AND DUCTWORK. DO NOT RELOCATE PANELS WITHOUT PRIOR APPROVAL.
8. ELECTRICAL DEVICES IN FIRE RATED WALLS SHALL BE A MINIMUM OF 24" AWAY FROM DEVICES ON THE OPPOSITE SIDE OF THE WALL TO MAINTAIN FIRE RATING.
9. MINIMUM SIZE CONDUIT FOR POWER SHALL BE 3/4", MIN. SIZE FLEX CONDUIT MAY BE 1/2". MINIMUM SIZE CONDUIT FOR DATA SHALL BE 1"C. DO NOT COMBINE CONDUIT FOR DATA GROUNDING.
10. MAX. LENGTH FOR FLEX CONDUIT SHALL BE 6 FT. ALL FLEX CONDUIT SHALL BE LISTED FOR GROUNDING.
11. LIGHT FIXTURE WHIPS MAY BE MIN. 1/2" FLEX CONDUIT WITH MIN. #12 WIRE. LIGHT FIXTURE WHIPS SHALL BE NO MORE THAN 6 FT LONG.
12. PROVIDE GREEN GROUND WIRE WITH ALL CIRCUITS SIZED PER NEC. BOND GREEN GROUND WIRE TO EACH END OF CONDUIT.
13. GROUND TRANSFORMER SECONDARIES TO BUILDING STEEL AND GROUND ROD. PROVIDE CONDUIT TO PROTECT GROUNDING CONDUCTOR AND BOND EACH END OF CONDUIT TO GROUNDING SYSTEM. MIN. SIZE OF CONDUIT FOR GROUND WIRE SHALL BE 3/4"C.
14. PROVIDE J–BOXES, CONDUIT AND SLEEVES THRU ALL FIRE WALLS FOR DATA, TELEPHONE, SECURITY, FIRE ALARM AND SOUND SYSTEMS WIRINGS, ETC. SEE SPECIFICATIONS.
15. PROVIDE PULL BOXES, JUNCTION BOXES, WIRING TROUGHS AND CABINETS WHEREVER REQUIRED FOR PROPER INSTALLATION OF VARIOUS ELECTRICAL SYSTEMS.
16. WHERE PORTIONS OF INTERIOR RACEWAY SYSTEM ARE EXPOSED TO WIDELY DIFFERENT TEMPERATURES, PROVIDE AIR SEALING PER NEC TO PREVENT CIRCULATION OF AIR FROM WARMER TO A COOLER SECTION.
17. ALL WIRING SHALL BE 600 VOLT, SOFT DRAWN ANNEALED COPPER, 98% CONDUCTIVITY, CONTINUOUS FROM OUTLET TO OUTLET. MINIMUM WIRE SIZE #12. ALL WIRE SHALL BE STRANDED TYPE THHN OR THWN–2 (WET RATED FOR 90° C). ALL WIRES SHALL BE COLOR CODED WITH SAME COLOR CONNECTED TO SAME UNGROUNDED PHASE THROUGHOUT THE INSTALLATION.
18. ALL ELECTRICAL WIRING SHALL BE INSTALLED IN CONDUIT. NO SURFACE MOUNTED WIREMOLD SHALL BE ALLOWED IN FINISHED SPACES. MC CABLE SHALL BE ALLOWED INSIDE EXIST STUD WALLS OR CHASE WALLS.
19. PROVIDE AND INSTALL FINAL CONNECTIONS TO ALL EQUIPMENT PROVIDED BY OTHER TRADES AND/OR FURNISHED BY OWNER INCLUDING ALL NECESSARY CONDUIT, CORDS, PLUGS, WHIPS, HARDWIRING, ETC. IN PARTICULAR CONFIRM CONNECTION REQUIREMENTS WITH DELIVERED EQUIPMENT PRIOR TO ROUGH–IN.
20. ALL MATERIAL MUST BE NEW AND OF GOOD QUALITY AND SHALL BEAR THE STAMP OF APPROVAL OF THE UNDERWRITERS' LABORATORIES, INC. (U.L.).

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL




07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL AND FIRE ALARM NOTES

o-E.001


STANTON ENGINEERING GROUP
INFO@STANTON–ENGR.COM (713) 305–6282
TEXAS ENG. FIRM REG. NO. F–018330 | © 2025 ALL RIGHTS RESERVED
12999 W. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77064




## 1 TYPICAL DATA OUTLETS

NO SCALE


NOTES:
1. PROVIDE DEEP 4 11/16" X 4 11/16" X 2 1/8", 2-GANG BACK BOX FOR ALL DATA OUTLETS.
   1.A. PROVIDE SINGLE GANG MUDRING FOR DATA OUTLETS WITH 1-4 DROPS.
   1.B. PROVIDE PULL STRING IN ALL LOW VOLTAGE CONDUITS.
2. LOW VOLTAGE CABLING AND DEVICES BY DIVISION 27.
3. REFERENCE TECHNOLOGY DRAWINGS FOR ADDITIONAL INFORMATION.




## 2 TYPICAL POWER & DATA OUTLET DETAIL

NO SCALE

NOTES:
1. LOCATE DEVICES GROUPED TOGETHER AS CLOSELY TOGETHER AS POSSIBLE.
   1.A. USE CADDY TSGB16, RBS16 OR SIMILAR MOUNTING BAR IN SHEETROCK WALLS.




## 3 TYPICAL ELECTRICAL DEVICES

NO SCALE

NOTES:
1. ALL DEVICES SHALL BE COLOR CODED PER SPECIFICATIONS WITH 302/304 STAINLESS STEEL, STANDARD SIZE, FACEPLATES.
2. ONLY SELECT RECEPTACLES ARE SHOWN HERE. PROVIDE SIMILAR LABELS ON ALL SWITCHES, NEMA POWER OUTLETS, ETC.
3. PROVIDE LABEL WITH RED TEXT READING "EMERGENCY" FOR DEVICES ON GENERATOR FED CIRCUITS.
4. PROVIDE TYPEWRITTEN OR PREMADE CIRCUIT LABELS INDICATING THE ELECTRICAL CIRCUIT ON:
   4.A. INSTALLED WIRING AT EACH SPLICE POINT
   4.B. EACH J-BOX ABOVE CEILING WITH WIRING INSTALLED OR MODIFIED AS PART OF THIS PROJECT.
   4.C. AFFIXED TO THE FRONT OF EACH NEW AND EXISTING DEVICE FACEPLATE IN THE AREA OF RENOVATION.

XX-## CIRCUIT LABEL
   A. XX = PANEL DESIGNATION
   B. ## = AS-BUILT CIRCUIT DESIGNATION

STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM (713) 305-6080
TEXAS ENG. FIRM REG NO. F-18332-00 2025 ALL RIGHTS RESERVED
12999 W. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77040

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

0

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL


STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025

MWA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL
DEVICE DETAILS


o-E.010




## 10 MECHANICAL - ELECTRICAL COORDINATION DETAIL


NO SCALE

**COORDINATE WITH OTHER TRADES TO ENSURE NO PIPING AND DUCTWORK ABOVE ELECTRICAL EQUIPMENT AS SHOWN. PROVIDE WORKING CLEARANCE IN FRONT OF STARTERS, DISCONNECTS, PANELS, XFMRS AND ADDITIONALLY PER CODE.**




## 11 CONDUIT ROOF PENETRATION DETAIL

NO SCALE





## 7 EDF GFI PROTECTION DETAIL

NO SCALE

NOTES:


1. MODIFY EXISTING WALL AS NEEDED TO INSTALL NEW RECEPTACLE AND REMOTE GFI TEST SWITCH. PATCH/REPAIR WALL AS NEEDED TO MATCH EXISTING.
2. WIRE NEW RECEPTACLE DOWNSTREAM OF REMOTE GFI TEST SWITCH.
3. REMOTE GFI TEST SWITCH SHALL BE A DEAD FRONT GFI DEVICE TO BE INSTALLED FLUSH MOUNTED IN WALL WITH EDF SERVED AND PROVIDE GFI PROTECTION FOR THE RECEPTACLE LOCATED WITHIN THE EDF HOUSING.
4. GFI TEST SWITCH SHALL BE READILY ACCESSIBLE PER NEC 210.8.
5. COORDINATE RECEPTACLE LOCATION(S) WITHIN EDF HOUSINGS WITH MANUFACTURER'S INSTALLATION INSTRUCTIONS.




## 12 ROOF AND CANOPY CONDUIT SUPPORT DETAIL

NO SCALE

1. COORDINATE WITH ARCHITECTURAL DRAWINGS, DETAILS, SPECIFICATIONS AND OTHER TRADES.





## 13 CANOPY LIGHT MOUNTING DETAIL TYPE 1

NO SCALE

NOTES:

1. MOUNTING PLATES SHALL BE WELDED TO CANOPY TO MOUNT LIGHT FIXTURES.
2. FOR FIXTURES WITH END CONDUIT ATTACHMENTS ALL CANOPY PENETRATIONS SHALL BE MADE OFF CENTER FROM THE FIXTURE WIRING ENTRY POINT AND SHALL HAVE WEATHERTIGHT SEALING. (SHOWN HERE)
3. CANOPY PENETRATIONS ABOVE FIXTURES SHALL BE PERMITTED ONLY WHERE THE SUPPLIED FIXTURE HAS NO END CONDUIT ATTACHMENTS.
4. CONDUIT SHALL BE SEALED BOTH ABOVE AND BELOW THE CANOPY PENETRATION AND AGAIN AT THE FIXTURE ENTRY POINT TO PREVENT WATER FROM ENTERING THE LIGHTING FIXTURE.
5. CANOPY PENETRATIONS SHALL BE MADE AS CLOSE TO CONDUIT ENTRY PENETRATION POINT AS POSSIBLE AND CONDUIT SHALL BE ROUTED TO MINIMIZE EXPOSED CONDUIT.





## 8 TRANSFORMER CONNECTION AND GROUNDING DETAIL

NO SCALE


NOTES:

1. INSTALL GROUND ROD ADJACENT TO TRANSFORMER AND SEAL PENETRATION AROUND GROUND ROD.
2. WHERE AN ISOLATED GROUND IS PROVIDED MAKE THE CONNECTION AT THE TRANSFORMER AND RUN DIRECTLY TO THE ISOLATED GROUND BAR IN THE PANELBOARD. DO NOT DEFINE THE ISOLATED GROUND AT THE PANELBOARD.
3. FINAL CONNECTIONS TO TRANSFORMERS SHALL BE MADE IN FLEXIBLE CONDUIT. PROVIDE LIQUID TIGHT CONSTRUCTION AND FITTINGS IN WET, DAMP OR OUTSIDE AREAS EXCEPT WHERE LOCATED IN AIR HANDLING ROOMS. REFERENCE SPECIFICATIONS FOR ADDITIONAL INFORMATION.





## 9 PIGTAIL WIRING DETAIL FOR ELECTRICAL DEVICE

NO SCALE





## 1 CONDUIT/J-BOX DETAIL FOR LIGHT FIXTURES IN LAY-IN CEILING

NO SCALE




## 2 FIXTURE SUPPORT DETAIL

NO SCALE





## 3 TRAPEZE MOUNTED CONDUIT DETAIL

NO SCALE

NOTES:

1. ALL SUPPORT DEVICES SHALL BE UL LISTED AND NEC APPROVED.
2. REFER TO NEC FOR CONDUIT SUPPORT SPACING.





## 4 WALL MOUNTED CONDUITS

NO SCALE

NOTES:

1. ALL SUPPORT DEVICES SHALL BE UL LISTED AND NEC APPROVED.
2. REFER TO NEC FOR CONDUIT SUPPORT SPACING.





## 5 FIREWALL PENETRATION DETAIL

NO SCALE

NOTES:

1. FIRE RATING OF COMPLETED FIREPROOFED ASSEMBLY SHALL BE EQUAL OR EXCEED RATING OF WALL.




## 6 GROUNDING BUSHING WIRING DETAIL

NO SCALE

NOTE:

1. PROVIDE AND INSTALL GROUNDING BUSHINGS FOR DISCONNECT SWITCHES, PANELS AND TRANSFORMERS.

STANTON ENGINEERING GROUP

INFO@STANTON-ENG.COM (713) 300-6060 | TEXAS ENG. FIRM REG. NO. F-018332 | © 2025 ALL RIGHTS RESERVED | 1300 W. SAM HOUSTON PARKWAY S., SUITE 121, HOUSTON, TX 77042

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

0

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER

07.18.2025

MWA ARCHITECTS


ARCHITECTS AND PLANNING CONSULTANTS

11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL DETAILS

o-E.011




## 5 TYPICAL BRANCH CIRCUIT PANEL LABELING DETAIL

NO SCALE

NOTES:

1. LAYOUT OF PANELBOARD, INCLUDING LOCATIONS OF NAMEPLATES, CIRCUIT DIRECTORY, AND OTHER LABELING IS SHOWN FOR REFERENCE ONLY, FIELD LOCATE AS NEEDED BASED ON TRUE EQUIPMENT LAYOUT AND DIMENSIONS.
2. REFERENCE OWNER'S DESIGN GUIDELINES FOR ADDITIONAL LABELING REQUIREMENTS.

(1) PROVIDE LAMACOID NAMEPLATE WITH 5/16" LETTERS SHOWING PANEL NAME, AMPERAGE RATING, VOLTAGE, AND FROM WHERE POWER IS DERIVED. ATTACH WITH MASTIC AND TWO SCREWS. COORDINATE TO GIVE SAME NAME AS PANEL SCHEDULE. IF USED AS MAIN SERVICE PANEL, PROVIDE SHORT CIRCUIT AVAILABLE AND RATING INFORMATION.

(2) PROVIDE PERMANENT ARC FAULT WARNING LABEL.


(3) FOR ALL NEW ELECTRICAL EQUIPMENT, PROVIDE PERMANENTLY AFFIXED LABEL STATING FAULT CURRENT AT THE TIME OF INSTALLATION AND CALCULATION. THE LABEL SHALL BE MINIMUM 2" X 3" IN SIZE, AND INCLUDE THE DATE OF THE CALCULATION. REFERENCE ELECTRICAL DRAWINGS AND EQUIPMENT SHORT CIRCUIT ANALYSIS TABLE. ATTACH WITH MASTIC AND TWO SCREWS.

(4) PROVIDE INFORMATION PER INDUSTRY STANDARDS, BUT SHALL INCLUDE VOLTAGE, PHASE, BUS AMPERAGE, AND SHORT CIRCUIT RATING

(5) FOR EACH CIRCUIT PROVIDE PERMANENT LABEL INDICATING CIRCUIT BREAKER NUMBER, NUMBER SHALL MATCH CIRCUIT DIRECTORY.

(6) CIRCUIT DIRECTORY TO BE COMPLETED AT END OF JOB, TYPEWRITTEN, STATING EQUIPMENT OR ROOMS SERVED BY CIRCUIT. EVEN CIRCUIT ON RIGHT SIDE OF CARD, ODD ON LEFT. PROVIDE LAMINATED DIRECTORY FOR EXTERIOR OR WET LOCATIONS.

(7) PROVIDE PERMANENT LABEL INDICATING COLOR CODING OF PHASE CONDUCTORS BASED ON VOLTAGE USING BUILDING COLOR SCHEME AS IDENTIFIED IN THE OWNER'S DESIGN GUIDELINES.




## 1 TYPICAL DISCONNECT, STARTER, & CONTACTOR LABELING DETAIL

NO SCALE

NOTES:

1. LOCATIONS OF NAMEPLATES SHOWN FOR REFERENCE ONLY, FIELD LOCATE AS NEEDED BASED ON TRUE EQUIPMENT LAYOUT AND DIMENSIONS. REFERENCE OWNER'S DESIGN GUIDELINES FOR ADDITIONAL LABELING REQUIREMENTS.

(1) PROVIDE AN ENGRAVED NAMEPLATE SHOWING LOAD SERVED, EQUIPMENT VOLTAGE, AND CIRCUIT NUMBER MATCHING AS-BUILT CONDITIONS.

(2) PROVIDE AN ENGRAVED NAMEPLATE SHOWING LOADS SERVED, VOLTAGES, AND CIRCUIT NUMBERS MATCHING AS-BUILT CONDITIONS FOR ALL CONTACTOR CIRCUITS. LOADS SERVED SHALL BE "LIGHTING", "FAN", "RECEPTACLES", "PUMP", "WATER HEATER", OR SIMILAR DESCRIPTIVE NOTE.

**DISHWASHER**
**480V, 3PH, 3 WIRE**
**FROM HK-2/4/6**

## 2 DISCONNECT LABELING

NO SCALE

NOTES:

1. PROVIDE LABEL ON EACH DISCONNECT AND FUSED SWITCH.
   1.1. FOR DISCONNECTS AND FUSED SWITCHES REPLACE "PANEL P1NA" WITH THE LOAD SERVED.
   1.2. REFER TO OWNER'S STANDARDS FOR ADDITIONAL LABEL REQUIREMENTS.
2. PROVIDE LABEL ON ELECTRICAL PANEL AND TRANSFORMER.
   2.1. REPLACE "PANEL P1NA" WITH THE PANEL OR TRANSFORMER NAME BEING LABELED.
3. REPLACE "400A FUSED SWITCH" WITH UPSTREAM SOURCE OR CONNECTION.
   3.1. IF FED FROM A XFMR REPLACE "400A FUSED SWITCH" WITH "XFMR XX" WHERE XX IS THE FIELD VERIFIED XFMR NAME.
4. REPLACE VOLTAGE CONFIGURATION TO MATCH THE EQUIPMENT BEING LABELED.
5. REFERENCE FLOOR PLANS FOR EQUIPMENT LOCATIONS.

**⚠ WARNING**

**Arc Flash and Shock Hazard**
**Appropriate PPE Required**


| FLASH PROTECTION | | SHOCK PROTECTION | |
|---|---|---|---|
| Incident Energy at: | 18 in | Shock Risk When Cover is Removed | 480 VAC |
| Min. Arc Rating: | 0.45 cal/cm² | Limited Approach | 42 in |
| Arc Flash Boundary: | 10 in | Restricted Approach | 12 in |
| PPE: Per NFPA 70E 2015 | 1 | Equipment Name: **PANEL HA** Prot Dev: 225/3 CB from Panel DA | |

## 3 TYPICAL ARC FLASH LABEL DETAIL

NO SCALE

NOTES:

1. VALUES AND NAMES SHOWN HERE ARE FOR REFERENCE ONLY, MODIFY TO REFLECT PROJECT'S ARC FLASH STUDY VALUES AND EQUIPMENT NAMES.
2. IF MIN. ARC RATING IS OVER 40CAL/CM² MODIFY "WARNING" TEXT TO READ "DANGER" AND PROVIDE RED SHADING IN LIEU OF ORANGE SHOWN.




## 4 TYPICAL TRANSFORMER LABELING DETAIL

NO SCALE

NOTES:

1. LOCATIONS OF NAMEPLATES SHOWN FOR REFERENCE ONLY, FIELD LOCATE AS NEEDED BASED ON TRUE EQUIPMENT LAYOUT AND DIMENSIONS.

(1) PROVIDE AN ENGRAVED NAMEPLATE SHOWING EQUIPMENT NAME, RATING, VOLTAGE, SOURCE.

STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM (713) 300-6080
TEXAS ENGINEERING FIRM REG NO. F-018332-00 © 2025 ALL RIGHTS RESERVED
1200 W. SAM HOUSTON PARKWAY N., SUITE 121, HOUSTON, TX 77043

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

0

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL




07.18.2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL DETAILS

o-E.012

## KITCHEN AREA ELECTRICAL NOTES

1. REFER TO KITCHEN CONSULTANTS "FS" DRAWINGS FOR ADDITIONAL REQUIREMENTS PARTICULARLY NOTING MOUNTING HEIGHTS OF EQUIPMENT OUTLETS AND JUNCTION BOXES, AND WHETHER SERVICE IS FROM WALL, FLOOR OR OVERHEAD.
2. SOME RECEPTACLES SHALL BE MOUNTED HORIZONTALLY, REFER TO KITCHEN CONSULTANTS "FS" DRAWINGS.
3. FOR DEVICES WITH SERVICE FROM FLOOR, RUN UNDERGROUND CONDUIT FROM DEVICES TO NEAREST COLUMN OR WALL THEN TURN CONDUIT UP AND RUN CONDUIT IN CEILING CAVITY.
4. LIGHT SWITCHES AND RECEPTACLES NOT SERVING A SPECIFIC PIECE OF EQUIPMENT SHALL BE MOUNTED AT ADA HEIGHTS.
5. CONNECTION TYPE SHOWN ON KITCHEN ELECTRICAL FLOOR PLAN IS FOR BIDDING PURPOSES, COORDINATE WITH KITCHEN EQUIPMENT SUPPLIER FOR FINAL CONNECTIONS:
   - 5.A. OBTAIN WIRING INSTRUCTIONS FOR EACH PIECE OF EQUIPMENT FROM EQUIPMENT SUPPLIER PRIOR TO ORDERING WIRING DEVICES AND ROUGH-IN.
   - 5.B. IF EQUIPMENT REQUIRES CORD AND PLUG CONNECTION, CONTRACTOR SHALL PROVIDE NEMA POWER CORD, PLUG, AND RECEPTACLES PER MANUFACTURER'S INSTRUCTION.
   - 5.C. IF EQUIPMENT REQUIRES JUNCTION BOX AND/OR DISCONNECT SWITCH, CONTRACTOR SHALL PROVIDE JUNCTION BOX AND DISCONNECT SWITCH AND CONNECT EQUIPMENT WITH SEALTITE FLEXIBLE CONDUIT.
6. ALL DISCONNECT SWITCHES IN THE KITCHEN AREA SHALL BE NEMA 4XSS STAINLESS STEEL.
7. WHERE PORTIONS OF INTERIOR RACEWAY SYSTEM ARE EXPOSED TO WIDELY DIFFERENT TEMPERATURES, PROVIDE AIR SEALING PER NEC TO PREVENT CIRCULATION OF AIR FROM WARMER TO A COOLER SECTION.
8. FLEXIBLE CONDUIT IN KITCHENS, FOOD PRODUCTION SPLASH ZONES AND WASH DOWN AREAS, FOOD PROCESSING, AND SIMILAR AREAS SHALL BE LIQUID TIGHT CONSTRUCTION INCORPORATING A BACTERIAL GROWTH INHIBITING PVC JACKET THAT MAY BE CLEANED WITHOUT DEGREDATION TO THE JACKET BLEACHING ELEMENTS AND APPROVED FITTINGS FOR WET LOCATION.
   - 8.A. AFC SZ TYPE LFMC OR EQUAL BY KAF-TECH.
9. INTERLOCK KITCHEN EXHAUST HOOD FIRE SYSTEM WITH FIRE ALARM SYSTEM.
10. PROVIDE RELAYS AND INTERLOCK KITCHEN HOOD FANS WITH FIRE ALARM SYSTEM. ACTUATION OF ANY ALARM INITIATING DEVICE SHALL DE-ENERGIZE KITCHEN HOOD FANS.
11. ALL GFI RECEPTACLES IN KITCHEN SHALL BE PASS & SEYMOUR MODEL 2097TRWR-XX TO EXCEED UL943 VOLTAGE SURGE REQUIREMENTS.





## 4 FIRE PROTECTION SYSTEM DETAIL

NO SCALE

NOTES:

1. ANSUL MODEL R-120 FIRE PROTECTION SYSTEM AND TANK(S)
2. ELECTRICAL CONTRACTOR TO FURNISH AND INSTALL POWER DISCONNECT DEVICES FOR ALL EQUIPMENT BELOW THE HOOD, SHUTTING OFF ALL SERVICE, INCLUDING CONTROL VOLTAGE, UPON ACTIVATION OF THE FIRE PROTECTION SYSTEM.
3. MICRO-SWITCH FURNISHED WITH SYSTEM TO BE INTERWIRED TO THE SHUT-OFF DEVICES FOR THE COOKING EQUIPMENT BY THE ELECTRICAL CONTRACTOR.
4. ELECTRICAL CONTRACTOR TO FURNISH AND INSTALL AN OCTAGON SHAPED HANDY BOX FOR THE PULL STATION AT 54" ABOVE THE FLOOR WITH 1/2" CONDUIT FROM THE TOP OF THE BOX TO 6" ABOVE THE CEILING.
5. GAS SHUT-OFF VALVE FURNISHED WITH THE SYSTEM (IF REQUIRED) TO BE INSTALLED IN THE GAS LINE SERVING THE COOKING EQUIPMENT BY THE PLUMBING CONTRACTOR. VERIFY SIZE OF GAS LINE.
6. ALL EXPOSED PIPEWORK TO BE STAINLESS STEEL OR CHROME WHERE EXPOSED.
7. VERIFY LOCATION OF REMOTE MANUAL PULL STATION.
8. UNIT MUST BE PLACED WITHIN EASY ACCESS OF EXIT DOOR.





## 5 KITCHEN HOOD FAN CONTROL SCHEMATIC

NO SCALE

NOTES:

1. THE FANS SHALL BE WIRED SO THAT ONE LOCAL SWITCH TURNS ON ASSOCIATED SUPPLY AND EXHAUST FANS.
2. IF THE FIRE ALARM IS IN ALARM, A FIRE ALARM CONTROL CONTACT SHALL CAUSE THE SUPPLY FAN TO STOP AND THE EXHAUST FAN TO START, EVEN IF THE CONTROL SWITCH IS "OFF".
3. SCHEMATIC IS DIAGRAMMATIC. PROVIDE INTERLOCK WIRING BASED ON EQUIPMENT PROVIDED AND FAN VOLTAGE TO IMPLEMENT THE SEQUENCE SPECIFIED.
4. COORDINATE BETWEEN FIRE ALARM CONTRACTOR, CONTROLS CONTRACTOR AND ELECTRICAL CONTRACTOR TO PROVIDE A COMPLETE INSTALLATION.
5. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.





## 1 GAS VALVE DETAIL

NO SCALE

NOTES:

1. GAS VALVE HOUSINGS ARE NOT SHOWN ON THE ELECTRICAL DRAWING. GC AND ELECTRICAL CONTRACTOR SHALL COORDINATE SIZE AND LOCATION OF GAS VALVE HOUSINGS.
2. SEE FOOD SERVICE CONSULTANT'S DRAWINGS ADDITIONAL INFORMATION AND REQUIREMENTS.
3. PROVIDE MINIMUM 3/4"C AS SHOWN ON THIS DETAIL.





## 2 RECESSED FIRE PULL DETAILS

NO SCALE

NOTES:

1. VERIFY LOCATION OF REMOTE MANUAL PULL STATION.
   - 1.A. MANUAL PULL STATION MUST BE PLACED WITHIN EASY ACCESS OF EXIT DOOR.
   - 1.B. MANUAL PULL STATION MUST BE PLACED NO LESS THAN 4 FEET AWAY FROM KITCHEN HOOD BUT WITHIN A MAXIMUM OF 20 FEET FROM THE KITCHEN HOOD.




## 3 TYPICAL PEDESTAL MOUNTED DEVICE

NO SCALE

NOTES:

1. ALL FACEPLATES SHALL BE STAINLESS STEEL.
2. PEDESTAL BOX PROVIDED BY DIVISION 26.
   - 2.A. A STANDARD DUPLEX INSTALLATION IS SHOWN FOR REFERENCE, PROVIDE SIMILAR INSTALLATION FOR QUAD RECEPTACLES, GFI RECEPTACLES, DATA OUTLETS, NEMA POWER OUTLETS, ETC.
   - 2.B. ALL PEDESTAL BOXES TO BE DOUBLE FACED WITH ONE BLANK FACE FOR FUTURE GROWTH. 2-GANG PEDESTALS WITH ONE BLANK FACE FOR QUAD RECEPTACLE LOCATIONS.
   - 2.C. PEDESTAL BOXES TO BE SIZED BY DIVISION 26 TO PROVIDE SCHEDULED DEVICES ON A SINGLE FACE AND SUFFICIENT DEPTH FOR BACK TO BACK DEVICES ON DOUBLE FACED PEDESTALS.
   - 2.D. BASIS OF DESIGN:
     - 2.D.A. 1-GANG ELECTRICAL DEVICES: LEGRAND LBP2 OR WATER SAVER E400SA-WS
     - 2.D.B. 1-GANG LOW VOLTAGE DEVICES: LEGRAND LBP2 OR WATER SAVER E400SA-WS
     - 2.D.C. 2-GANG ELECTRICAL DEVICES: WATER SAVER E600SA-WS
     - 2.D.D. 2-GANG LOW VOLTAGE DEVICES: WATER SAVER E600SA-WS
3. INSTALLATION REQUIREMENTS:
   - 3.A. STUB UP CONDUIT ABOVE FLOOR TO PEDESTAL BOX CONNECTION LOCATION.
   - 3.B. GROUT GAP BETWEEN FINISHED FLOOR AND BOTTOM OF PEDESTAL BOX.
   - 3.C. PROVIDE TRANSITION PIECE TO CONTINUE FINISHED FLOOR TO BOTTOM EDGE OF SERVICE FITTING AND CONCEAL GROUT. TRANSITION PIECE TO MATCH ARCHITECT'S FINISH SCHEDULE.
   - 3.D. PEDESTAL BOX TO BE INSTALLED SQUARE TO THE FINISHED FLOOR.
4. PROVIDE TYPEWRITTEN OR PREMADE CIRCUIT LABELS ON INSTALLED WIRING AT EACH DEVICE AND SPLICE POINT.
5. PROVIDE TYPEWRITTEN LABEL AFFIXED TO THE FRONT OF EACH DEVICE FACEPLATE INDICATING ELECTRICAL CIRCUIT.

   CIRCUIT LABEL

   XX-## — A. XX = PANEL DESIGNATION

   B. ## = AS-BUILT CIRCUIT DESIGNATION

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

0

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL




07.18.2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL
KITCHEN DETAILS

o-E.013

STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM (713) 360-4080
TEXAS ENG. FIRM REG. NO. F-018537 | 12999 W. SAM HOUSTON PKWY N., SUITE 125, HOUSTON, TX 77064
© 2025 ALL RIGHTS RESERVED

LIGHTING SYSTEM FUNCTIONAL TESTING AND DOCUMENTATION NOTES:

1. PRIOR TO PASSING FINAL INSPECTION, THE CONTRACTOR SHALL PERFORM FUNCTIONAL TESTING IN THE PRESENCE OF THE REGISTERED DESIGN PROFESSIONAL, THE OWNER AND/OR THEIR AGENT. THE FUNCTIONAL TESTING SHALL BE AS REQUIRED BY SECTION C408.3.1 OF THE 2021 IECC.
   1.A. THE FUNCTIONAL TESTING SHALL PROVIDE EVIDENCE THAT THE LIGHTING CONTROL SYSTEMS, INCLUDING BOTH HARDWARE AND SOFTWARE, ARE CALIBRATED, ADJUSTED, PROGRAMMED AND IN PROPER WORKING CONDITION IN ACCORDANCE WITH THE CONSTRUCTION DOCUMENTS AND MANUFACTURER'S INSTRUCTIONS.
   1.B. THE FUNCTIONAL TESTING SHALL BE IN ACCORDANCE WITH SECTIONS C408.3.1.1 AND C408.3.1.2 OF THE 2021 IECC FOR THE APPLICABLE CONTROL TYPE.
   1.C. A WRITTEN REPORT SHALL BE GENERATED DOCUMENTING THE FUNCTIONAL TESTING RESULTS IN ACCORDANCE WITH THE 2015 IECC REQUIREMENTS.
2. ALL LIGHTING CONTROLS O&M MANUALS, AS-BUILTS, TESTING REPORTS AND DOCUMENTATION RELATED TO THE LIGHTING CONTROL SYSTEM SHALL BE PROVIDED IN THEIR FINAL AND APPROVED FORM WITHIN 60 DAYS OF THE CERTIFICATE OF OCCUPANCY. ALL DOCUMENTS CERTIFYING THAT THE INSTALLED LIGHTING CONTROLS MEET DOCUMENTED PERFORMANCE CRITERIA OF SECTION C405 OF THE 2021 IECC SHALL BE INCLUDED IN THE O&M MANUALS.
3. ALL DOCUMENTS FROM ITEMS #1 AND #2 ABOVE SHALL BE COMBINED AND PROVIDED TO THE OWNER WITHIN 90 DAYS FROM THE DATE OF RECEIPT OF THE CERTIFICATE OF OCCUPANCY.

# LIGHT FIXTURE SCHEDULE

## EXTERIOR LIGHT FIXTURE SCHEDULE

| | | | |
|---|---|---|---|
| RECESSED 6" DOWNLIGHT WET LOCATION | D5<br>D5Y | 6" DIAMETER RECESSED LED DOWNLIGHT, SPECULAR CLEAR REFLECTOR, MEDIUM (56') BEAM DISTRIBUTION, 1000 LUMENS, 4000K COLOR TEMPERATURE, 120-277V MULTIVOLT INPUT, 1% 0-10V DIMMING DRIVER.<br>LIGHTOLIER 6R-N / C6L-10-9-40-M-Z10-U / C6-R-DL-CC | 9W |
| RECESSED 6" DOWNLIGHT WET LOCATION | D6<br>D6Y | 6" DIAMETER RECESSED LED DOWNLIGHT, SPECULAR CLEAR REFLECTOR, MEDIUM (56') BEAM DISTRIBUTION, 2000 LUMENS, 4000K COLOR TEMPERATURE, 120-277V MULTIVOLT INPUT, 1% 0-10V DIMMING DRIVER.<br>LIGHTOLIER 6R-N / C6L-20-9-40-M-Z10-U / C6-R-DL-CC | 22W |
| SURFACE CANOPY SQUARE LED | WC1<br>WC1X<br>WC1Y | 9" SQUARE SURFACE LED CANOPY LIGHT, 4000K COLOR TEMPERATURE, 3500 LUMENS, 120-277V MULTIVOLT INPUT, DARK BRONZE FINISH.<br>EELP VR7-T-28L-QT-40K (EBLED9W) | 28W |
| EXTERIOR WALL PACK | WP1<br>WP1X<br>WP1Y | 7" WDE WALL MOUNTED LED, 4000K COLOR TEMPERATURE, 5000 LUMENS, TYPE 3 DISTRIBUTION, 120-277 MULTIVOLT INPUT, WET LOCATION, 10KV KA SURGE PROTECTION.<br>REFER TO ARCH FOR MOUNTING HEIGHT.<br>FINISH TO BE SELECTED BY ARCHITECT FROM ALL AVAILABLE FINISHES.<br>GARDCO GEOFORM SMALL GWS-A04-740-UNV-XX FINISH (EM) | 34W |
| EXTERIOR WALL PACK | WP2<br>WP2X<br>WP2Y | 12" WDE WALL MOUNTED LED, 4000K COLOR TEMPERATURE, 8500 LUMENS, TYPE 3 DISTRIBUTION, 120-277 MULTIVOLT INPUT, WET LOCATION. REFER TO ARCH FOR MOUNTING HEIGHT.<br>REFER TO ARCH FOR MOUNTING HEIGHT.<br>FINISH TO BE SELECTED BY ARCHITECT FROM ALL AVAILABLE FINISHES.<br>GARDCO GEOFORM MEDIUM GWM-A11-740-T3M-UNV-XX FINISH (REMOTE EM BATTERY) | 52W |
| EXTERIOR WALL PACK | WP3<br>WP3X<br>WP3Y | 17" WDE WALL MOUNTED LED, 4000K COLOR TEMPERATURE, 12500 LUMENS, TYPE 3 DISTRIBUTION, 120-277 MULTIVOLT INPUT, WET LOCATION. REFER TO ARCH FOR MOUNTING HEIGHT.<br>REFER TO ARCH FOR MOUNTING HEIGHT.<br>FINISH TO BE SELECTED BY ARCHITECT FROM ALL AVAILABLE FINISHES.<br>GARDCO GEOFORM MEDIUM GWM-A14-740-T3M-UNV-XX FINISH (REMOTE EM BATTERY) | 77W |

1. LIGHT FIXTURE CATALOG NUMBERS AND DESCRIPTIONS ARE SCHEDULED FOR ESTABLISHING QUALITY, APPEARANCE AND PERFORMANCE OF THE FIXTURES. EXACT CATALOG NUMBERS DESCRIBING MOUNTING CONDITIONS AND REQUIREMENT RELATED TO TRIM FOR ALL FIXTURES SHALL BE CONFIRMED (BY THE ELECTRICAL CONTRACTOR) WITH THE ROOM FINISH SCHEDULE AND REFLECTED CEILING PLANS ON THE ARCHITECTURAL PLANS PRIOR TO BIDDING AND SUBMITTING LIGHT FIXTURES. PROVIDE DRY WALL KIT AS REQUIRED.
2. ALL 'X', 'Y', AND 'Z' TYPE FIXTURES SHALL HAVE EMERGENCY POWER BACKUP. EMERGENCY POWER SOURCES SHALL MONITOR POWER UPSTREAM OF THE LIGHTING CONTROLS TO SEE IF POWER IS LOST. BATTERY PACKS AND INVERTERS SHALL BE CAPABLE OF POWERING THE DESIGNATED FIXTURE(S) WITH AN OUTPUT OF 1400 LUMENS FOR A MINIMUM OF 90-MINUTES. PROVIDE REMOTE BATTERY PACKS OR INVERTERS AS NECESSARY. EMERGENCY LIGHTS SHALL OPERATE ONLY UPON LOSS OF POWER; ALSO, PROVIDE AND WIRE TEST SWITCH AND LED INDICATOR LIGHT FOR EMERGENCY BATTERY. SEE WIRING INSTRUCTION SUPPLIED BY EMERGENCY BATTERY MANUFACTURER.
   2.A. 'X' TYPE FIXTURES (AX, ETC.) HAVE EMERGENCY GENERATOR POWER LIGHTING TRANSFER DEVICES.
   2.B. 'Y' TYPE FIXTURES (MY, ETC.) HAVE INDIVIDUAL 90-MINUTE EMERGENCY BATTERY POWER.
   2.C. 'Z' TYPE FIXTURES (GTZ, ETC.) HAVE 90-MINUTE INVERTER EMERGENCY BATTERY POWER.
3. PROVIDE BASE COVER FOR ALL LIGHT POLES.
4. ALL EXTERIOR FIXTURES SHALL BE WET RATED WITH COLD WEATHER BALLASTS AND BATTERY PACKS.
5. PROVIDE SPARE FIXTURES AND EMERGENCY DEVICES PER SPECIFICATIONS.
6. WHERE FIXTURE FINISHES ARE INDICATED TO BE SELECTED BY ARCHITECT THE CONTRACTOR SHALL INCLUDE IN THEIR BID ALL AVAILABLE FINISHES. SUBMIT COMPLETE FIXTURE FINISH OPTIONS AS PART OF THE LIGHTING SUBMITTAL PACKAGE.
7. EQUAL BY PHILIPS (CW LIGHTING), COOPER (PUTTERMAN SCHAROK), AND LITHONIA (LESCO) SHALL BE ACCEPTABLE.

## INTERIOR LIGHT FIXTURE SCHEDULE

| APPLICATION | TYPE | DESCRIPTION | WATTS |
|---|---|---|---|
| 1X4 RECESSED LAY-IN CEILING SELECTABLE CCT & LUMENS | A1<br>A1X<br>A1Y | 2X4 RECESSED LED, SMOOTH FROSTED ACRYLIC LENS, EXTRUDED ALUMINUM FRAME, WHITE FINISH, LAY-IN CEILING, 6000 LUMENS, 4000K COLOR TEMPERATURE, 120-347V MULTIVOLT INPUT, 5% 0-10V DIMMING.<br>SET FIELD SELECTABLE SWITCHES TO NEUTRAL WHITE (4000K) AND HIGH (47W).<br>DAYBRITE 2SBP3550L8CS-4-UNJ-DIM | 47W |
| 1X4 RECESSED LAY-IN CEILING SELECTABLE CCT & LUMENS | B1<br>B1X<br>B1Y | 1X4 RECESSED LED, SMOOTH FROSTED ACRYLIC LENS, EXTRUDED ALUMINUM FRAME, WHITE FINISH, LAY-IN CEILING, 4500 LUMENS, 4000K COLOR TEMPERATURE, 120-347V MULTIVOLT INPUT, 5% 0-10V DIMMING.<br>SET FIELD SELECTABLE SWITCHES TO NEUTRAL WHITE (4000K) AND HIGH (36W).<br>DAYBRITE 1SBP3040L8CS-4-UNJ-DIM | 36W |
| 2X2 RECESSED LAY-IN CEILING SELECTABLE CCT & LUMENS | B2<br>B2X<br>B2Y | 2X2 RECESSED LED, SMOOTH FROSTED ACRYLIC LENS, EXTRUDED ALUMINUM FRAME, WHITE FINISH, LAY-IN CEILING, 4250 LUMENS, 4000K COLOR TEMPERATURE, 120-347V MULTIVOLT INPUT, 5% 0-10V DIMMING.<br>SET FIELD SELECTABLE SWITCHES TO NEUTRAL WHITE (4000K) AND HIGH (36W).<br>DAYBRITE 2SBP3040L8CS-2-UNJ-DIM | 39W |
| 4FT STRIP LED MECHANICAL & STORAGE ROOMS | C<br>CX<br>CY | 4 FOOT STRIP LED, STEEL HOUSING, FROSTED ACRYLIC LENS, 4000 LUMENS, 3500K COLOR TEMPERATURE, CHAIN HANGING SET, WIRE GUARD, 120-277V MULTIVOLT INPUT, 0-10V DIMMING DRIVER. PROVIDE CHAIN HANGING SET AND WIREGUARD IN MECHANICAL ROOMS AND AREAS WITHOUT CEILINGS.<br>SET FIELD SELECTABLE SWITCHES TO NEUTRAL WHITE (4000K) AND HIGH (36W).<br>DAYBRITE SDS-4-2448L-8CST-UNV-DIM | 30W |
| RECESSED 6" DOWNLIGHT | D1<br>D1X<br>D1Y | 6" DIAMETER RECESSED LED DOWNLIGHT, MATTE WHITE FINISH, WIDE (76') BEAM DISTRIBUTION, 1000 LUMENS, 4000K COLOR TEMPERATURE, 120-277V MULTIVOLT INPUT, 1% 0-10V DIMMING DRIVER.<br>LIGHTOLIER 6R-N / C6L-10-9-40-W-Z10-U / C6-R-DL-WH | 9W |
| RECESSED 6" DOWNLIGHT | D2<br>D2X<br>D2Y | 6" DIAMETER RECESSED LED DOWNLIGHT, MATTE WHITE FINISH, WIDE (76') BEAM DISTRIBUTION, 2000 LUMENS, 4000K COLOR TEMPERATURE, 120-277V MULTIVOLT INPUT, 1% 0-10V DIMMING DRIVER.<br>LIGHTOLIER 6R-N / C6L-20-9-40-W-Z10-U / C6-R-DL-WH | 22W |
| EXIT SIGN | XB<br>XS<br>XD | DIE CAST ALUMINUM LED EXIT LIGHT, RED LETTERS, MATTE BLACK HOUSING W/ BRUSHED ALUMINUM FACE, UNIVERSAL ARROWS, 120/277 VOLT DUAL INPUT, 90 MINUTE EMERGENCY BATTERY. VERIFY LETTER AND FACE COLOR WITH OWNER/ARCHITECT PRIOR TO ORDERING.<br>XS=SINGLE FACE, XD=DOUBLE FACE, XB=BACK MOUNTED<br>PHILIPS CHLORIDE ER55L-3-R<br>SURELITES CX7-1/2-R<br>LITHONIA LQC-1/2-R-EL N | 5W |
| EXIT SIGN INTEGRAL BATTERY INTEGRAL EM LIGHT BAR | YB<br>YS<br>YD | THERMOPLASTIC LED EXIT LIGHT WITH INTEGRAL EM LIGHT, RED LETTERS, WHITE HOUSING W/ WHITE FACE, UNIVERSAL ARROWS, 120-277 MULTIVOLT INPUT, 90 MINUTE EMERGENCY BATTERY. VERIFY LETTER AND FACE WITH OWNER/ARCHETICT PRIOR TO ORDERING.<br>YS=SINGLE FACE, YD=DOUBLE FACE, YB=BACK MOUNTED<br>SIGNTEX CLP-BB-U-R-W-DG | 5W |
| TWIN HEAD EM LIGHT INTEGRAL BATTERY WET LOCATION | YT1 | TWIN HEAD EM LIGHT, INJECTION-MOLDED THERMOPLASTIC WHITE HOUSING, GASKETED CLEAR POLYCARBONATE COVER, LED LAMPS, 90-MINUTE EMERGENCY BATTERY.<br>CHLORIDE TPU-W-N-LM7-W | 7W |

# LIGHTING CONTROL SEQUENCE OF OPERATIONS

| ROOM TYPE | AUTO ON | MANUAL ON (VACANCY) | AUTO OFF (20 MIN MAX) | PARTIAL OFF AT NORMAL HOURS | AUTO ON AFTER HOURS | AUTO OFF AFTER HOURS (20 MIN MAX) | TIME ON | TIME OFF | ASTRONOMIC OR PHOTOCELL ON/OFF | AUTO STEP CONTROL WITH OFF | AUTO CONTINUOUS DIM WITH OFF | MANUAL BI-LEVEL REDUCTION CONTROL | MANUAL CONTINUOUS DIM CONTROL | MANUAL ON/OFF SWITCH | MANUAL DIMMER SWITCH | DISPLAY, ACCENT, TASK CONTROL | PLUG LOAD CONTROL | SEQUENCE OF OPERATION |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | OCCUPANCY SENSOR | | | | | | TIME SWITCH/SCHEDULING | | | DAYLIGHT CONTROL | | LIGHT REDUCTION | | MANUAL CONTROL | | | PLUG LOAD CONTROL | |
| Kitchen/Serving | | | | | | | • | • | | | | • | | • | | | | LOCAL ON/OFF CONTROLS, LOCAL CONTROLS MAY OVERRIDE BUILDING SCHEDULE AND TURN ALL LIGHTS ON FOR MAXIMUM 2HRS. NETWORK LIGHTING CONTROLS ROOM CONTROLLER CONNECTED TO BUILDING CONTROLS; ON/OFF BASED ON BUILDING SCHEDULE, AFTER HOURS ON/OFF BASED ON OCCUPANCY, COORDINATE SCHEDULING WITH OWNER. WHERE ≥150W IN DAYLIGHT AREA, USE CONTINUOUS DIMMING DAYLIGHTING CONTROL. |
| Restrooms | 100% | | 20 MIN | | | | | | | | | | | • | | | | AUTO ON 100%, AUTO OFF BY LOCAL OCCUPANCY SENSOR. LOCAL ON/OFF CONTROLS ONLY, NO FULLY NETWORKED SYSTEM. |
| Custodial rooms | | • | 20 MIN | | | | | | | | | | | • | • | | | MANUAL ON, AUTO OFF BY LOCAL OCCUPANCY SENSOR. LOCAL ON/OFF CONTROLS ONLY, NO FULLY NETWORKED SYSTEM. |
| Storage rooms | 50% | | 20 MIN | | | | | | | | | | | • | • | | | AUTO ON 50%, AUTO OFF BY LOCAL OCCUPANCY SENSOR. LOCAL ON/OFF/DIMMING CONTROLS ONLY, NO FULLY NETWORKED SYSTEM. |
| Private Offices | 50% | | 20 MIN | | | | | | | | | | | • | • | | • | AUTO ON 50%, AUTO OFF BY LOCAL OCCUPANCY SENSOR. LOCAL ON/OFF/DIMMING CONTROLS ONLY, NO FULLY NETWORKED SYSTEM. |
| Corridors | | | | | 100% | 20 MIN | • | • | | | | | | • | | | | LOCAL ON/OFF CONTROLS, LOCAL CONTROLS MAY OVERRIDE BUILDING SCHEDULE AND TURN ALL LIGHTS ON FOR MAXIMUM 2HRS. NETWORK LIGHTING CONTROLS ROOM CONTROLLER CONNECTED TO BUILDING CONTROLS; ON/OFF BASED ON BUILDING SCHEDULE, AFTER HOURS ON/OFF BASED ON OCCUPANCY, COORDINATE SCHEDULING WITH OWNER. WHERE ≥150W IN DAYLIGHT AREA, USE CONTINUOUS DIMMING DAYLIGHTING CONTROL. |
| Electrical Rooms | | | | | | | | | | | | | | • | | | | MANUAL ON/OFF; LOCAL CONTROL DEVICE NOT TIED TO LVLCS. |
| Building Facade/Landscape | | | | | | | • | • | | | | | | | | | | CONNECTED TO BUILDING CONTROLS THROUGH LIGHTING CONTACTOR; ON/OFF BASED ON BUILDING SCHEDULE. |

1. DIMMER SWITCHES SHALL ACTIVATE PRESET ALL ON LIGHTING LEVEL WHEN PRESSED IN THE UP POSITION. LIGHTING LEVELS MAY BE RAISED/LOWERED BY HOLDING THE DIMMER PADDLE. WHEN PRESSED IN THE DOWN POSITION ALL LIGHTS SHALL SMOOTHLY DIM TO OFF.
2. AT LEAST 50 PERCENT OF ALL 125V, 15- AND 20-AMP RECEPTACLES INSTALLED IN ENCLOSED OFFICES, CONFERENCE ROOMS, ROOMS USED PRIMARILY FOR COPY OR PRINT FUNCTIONS, BREAKROOMS, CLASSROOMS AND INDIVIDUAL WORKSTATIONS, INCLUDING THOSE INSTALLED IN MODULAR PARTITIONS AND MODULE OFFICE WORKSTATION SYSTEMS SHALL HAVE PLUG LOAD CONTROL PER IECC 2021 C405.11.

# LIGHTING CONTACTOR SCHEDULE

**CONTACTOR CT1**

| POLE | DESCRIPTION | NORMAL CKT | EM CKT | CONTROL ZONE | CONTACTOR LOCATION | CONTACTOR TYPE |
|---|---|---|---|---|---|---|
| CT1-1 | KITCHEN/SERVING AREA – ZONE 'a' | HK-3 | – | Kitchen-a | CENTRAL PLANT | MAGNETICALLY HELD |
| CT1-2 | SPARE | | | Kitchen-a | CENTRAL PLANT | MAGNETICALLY HELD |
| CT1-3 | SPARE | | | Kitchen-a | CENTRAL PLANT | MAGNETICALLY HELD |

**CONTACTOR CT2**

| | | | | | | |
|---|---|---|---|---|---|---|
| CT2-1 | KITCHEN/SERVING AREA – ZONE 'b' | HK-3 | – | Kitchen-b | CENTRAL PLANT | MAGNETICALLY HELD |
| CT2-2 | SPARE | | | Kitchen-b | CENTRAL PLANT | MAGNETICALLY HELD |
| CT2-3 | SPARE | | | Kitchen-b | CENTRAL PLANT | MAGNETICALLY HELD |

**CONTACTOR CT3**

| | | | | | | |
|---|---|---|---|---|---|---|
| CT3-1 | KITCHEN SOFFIT/CANOPY LTS | HK-5 | – | Exterior | CENTRAL PLANT | MAGNETICALLY HELD |
| CT3-2 | | | | Exterior | CENTRAL PLANT | MAGNETICALLY HELD |
| CT3-3 | | | | Exterior | CENTRAL PLANT | MAGNETICALLY HELD |

1. REFERENCE TYPICAL LIGHTING CONTACTOR WIRING DIAGRAM.
2. EMERGENCY AND NORMAL ZONES WITHIN THE KITCHEN/SERVING SHALL HAVE SEPARATE CONTROLS TO ALLOW FOR LIGHTING REDUCTION CONTROL.
3. LIGHTING CONTACTORS SHALL BE DIN RAIL MOUNTED, MAGNETICALLY HELD TYPE WITH THREE WIRE CONTROL BY THE BAS.
   3.A. PROVIDE CABINET AT EACH LOCATION TO MOUNT ALL CONTACTORS IN A SINGLE ENCLOSURE. ENCLOSURE SIZED BY DIVISION 26.
   3.B. PROVIDE SEPARATE HOA SWITCHES IN THE FRONT COVER OF THE ENCLOSURE WIRED TO CONTROL THE FOLLOWING ZONES SEPARATELY.
      3.B.1. INTERIOR LIGHTING (ALL INTERIOR LIGHTING GROUPS)
      3.B.2. EXTERIOR LIGHTING (ALL EXTERIOR LIGHTING GROUPS)
      3.B.3. HOA SWITCH SHALL PASS THE BAS SIGNALS IN AUTO MODE, DISENGAGE ALL CONTACTORS IN THE OFF POSITION, AND ENGAGE ALL THE CONTACTORS IN THE ON POSITION.
   3.C. SPARE CAPACITY:
      3.C.1. PROVIDE MINIMUM TWO (2) SPARE POLE ON EACH COMBINED TYPE CONTACTOR FOR FUTURE USE.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

O

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

LIGHTING SCHEDULES

o-E.060


STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM (713) 303-6080 | TEXAS ENG. FIRM REG. NO. F-018332 | 1300 W. SAM HOUSTON PARKWAY S., SUITE 121, HOUSTON, TX 77042


© 2025 ALL RIGHTS RESERVED

## ELECTRICAL KEYED NOTES

GENERAL NOTES:

- CUT WALLS AS REQUIRED TO FLUSH MOUNT NEW DEVICES IN EXISTING WALLS. PATCH/REPAIR WALLS TO MATCH.

LIGHTING RENOVATION NOTES:

A. KITCHEN LIGHTS TO BE CONTROLLED BY LOCAL MOMENTARY SWITCHES AND BAS. LIGHTING CONTACTOR LOCATIONS SHOWN SCHEMATICALLY ONLY. LOCATE LIGHTING CONTACTOR ENCLOSURE IN THE ADJACENT CENTRAL PLANT SPACE, FIELD VERIFY. REFERENCE LIGHTING CONTROL DETAIL. TYPICAL.
   LEFT SWITCH SHALL CONTROL ZONE 'a' NORMAL POWER LIGHTING FIXTURES.
   RIGHT SWITCH SHALL CONTROL ZONE 'b' EMERGENCY LIGHTING FIXTURES.


B. PROVIDE PLUG LOAD CONTROLS TIED TO THE LIGHTING IN OFFICE SPACES.

C. WIRE EXIT SIGNS UPSTREAM OF LIGHTING CONTROLS. TYPICAL.

D. EXTERIOR LIGHTS TO BE CONTROLLED BY BAS. LIGHTING CONTACTOR LOCATIONS SHOWN SCHEMATICALLY ONLY. LOCATE LIGHTING CONTACTOR ENCLOSURE IN THE ADJACENT CENTRAL PLANT SPACE, FIELD VERIFY. REFERENCE LIGHTING CONTROL DETAIL. TYPICAL.

E. AFTER REMOVAL OF THE TEMPORARY KITCHEN, PROVIDE NEW EXIT SIGN AT ORIGINAL LOCATION AND RECONNECT TO EXISTING CAFETERIAL LIGHTING CIRCUIT.

F. PATCH/REPAIR EXTERIOR SOFFIT TO ACCOMMODATE NEW SURFACE MOUNTED FIXTURES.




**1 LIGHTING RENOVATION PLAN**
SCALE: 1/4" = 1'- 0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

0

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING


LIGHTING FLOOR PLANS


o-E.100


STANTON ENGINEERING GROUP
INFORMATION-TECHNOLOGY (713) 300-60360


TEXAS ENGINEERING FIRM REG. NO.F-12343 © 2025 ALL RIGHTS RESERVED


1300 W. SAM HOUSTON PARKWAY S., SUITE 125, HOUSTON, TX 77042


EXISTING TRANSFORMER PAD
T
MH
MH
COLD STORAGE REFRIGERATION SYSTEM
EXIST ATS
EXIST EH
EXIST TXEL
EXIST EL
EXIST AC
EXIST M
EXIST LE
EXIST KK
EXIST DA
CB
EL-16/18/20
LK-22
LK-28
EL-25
EL-23
EL-27
EXTEND TO LTS
EL-22
EL-24
EL-33
EL-31
EL-27
HOOD_1
HOOD_2
HK-2/4/6
HK-8/10/12
LK-24
EF-CF
EF-14
LK-26
HK
LK
(E)EDH-1
(E)AC-13
CLR/FRZR
GFI LK-1
GFI LK-3
GFI LK-11
GFI LK-13
GFI LK-15
GFI EL-19
NEMA LK-7/9
GFI+42" LK-1
PLK-9
FLK-9
LK-39
LK-19
PWR LK-21
PWR LK-23/25
PWR LK-27
PWR LK-29/31
PWR LK-33/35
PWR LK-37
LK-44
LK-46
LK-48
LK-50
LK-52
LK-54
LK-56
LK-58
LK-47
LK-49
LK-51
LK-53
LK-55
LK-57/59
LK-41/43
LK-45
LK-2
LK-4
LK-6
LK-13
LK-15
LK-17
LK-12/14
LK-8/10
LK-16/18/20
LK-38/40/42
+8FT,4XSS
LK-33/35
EL-29/31
EL-21
EL-19
EL-17
EL-15
EL-13
EL-11
EL-9
EL-7
EL-5
EL-3
EL-1
4XSS
6XSS
8XSS
10XSS
12XSS
14XSS
16XSS
18XSS
20XSS
22XSS
24XSS
26XSS
28/30
32/34
36/38
40/42
48/50
52/54
56/58
60/62
64/66
68/70
72/74
76/78
80/82
84/86
88/90
92/94
96/98
100/102
104/106
108/110
112/114
116/118
120/122
124/126
128/130
132/134
136/138
140/142
144/146
148/150
152/154
156/158
160/162
164/166
168/170
172/174
176/178
180/182
184/186
188/190
192/194
196/198
200/202
204/206
208/210
212/214
216/218
220/222
224/226
228/230
232/234
236/238
240/242
244/246
248/250
252/254
256/258
260/262
264/266
268/270
272/274
276/278
280/282
284/286
288/290
292/294
296/298
300/302
304/306
308/310
312/314
316/318
320/322
324/326
328/330
332/334
336/338
340/342
344/346
348/350
352/354
356/358
360/362
364/366
368/370
372/374
376/378
380/382
384/386
388/390
392/394
396/398
400/402
404/406
408/410
412/414
416/418
420/422
424/426
428/430
432/434
436/438
440/442
444/446
448/450
452/454
456/458
460/462
464/466
468/470
472/474
476/478
480/482
484/486
488/490
492/494
496/498
500/502
504/506
508/510
512/514
516/518
520/522
524/526
528/530
532/534
536/538
540/542
544/546
548/550
552/554
556/558
560/562
564/566
568/570
572/574
576/578
580/582
584/586
588/590
592/594
596/598
600/602
604/606
608/610
612/614
616/618
620/622
624/626
628/630
632/634
636/638
640/642
644/646
648/650
652/654
656/658
660/662
664/666
668/670
672/674
676/678
680/682
684/686
688/690
692/694
696/698
700/702
704/706
708/710
712/714
716/718
720/722
724/726
728/730
732/734
736/738
740/742
744/746
748/750
752/754
756/758
760/762
764/766
768/770
772/774
776/778
780/782
784/786
788/790
792/794
796/798
800/802
804/806
808/810
812/814
816/818
820/822
824/826
828/830
832/834
836/838
840/842
844/846
848/850
852/854
856/858
860/862
864/866
868/870
872/874
876/878
880/882
884/886
888/890
892/894
896/898
900/902
904/906
908/910
912/914
916/918
920/922
924/926
928/930
932/934
936/938
940/942
944/946
948/950
952/954
956/958
960/962
964/966
968/970
972/974
976/978
980/982
984/986
988/990
992/994
996/998
1000/1002
1004/1006
1008/1010
1012/1014
1016/1018
1020/1022
1024/1026
1028/1030
1032/1034
1036/1038
1040/1042
1044/1046
1048/1050
1052/1054
1056/1058
1060/1062
1064/1066
1068/1070
1072/1074
1076/1078
1080/1082
1084/1086
1088/1090
1092/1094
1096/1098
1100/1102
1104/1106
1108/1110
1112/1114
1116/1118
1120/1122
1124/1126
1128/1130
1132/1134
1136/1138
1140/1142
1144/1146
1148/1150
1152/1154
1156/1158
1160/1162
1164/1166
1168/1170
1172/1174
1176/1178
1180/1182
1184/1186
1188/1190
1192/1194
1196/1198
1200/1202
1204/1206
1208/1210
1212/1214
1216/1218
1220/1222
1224/1226
1228/1230
1232/1234
1236/1238
1240/1242
1244/1246
1248/1250
1252/1254
1256/1258
1260/1262
1264/1266
1268/1270
1272/1274
1276/1278
1280/1282
1284/1286
1288/1290
1292/1294
1296/1298
1300/1302
1304/1306
1308/1310
1312/1314
1316/1318
1320/1322
1324/1326
1328/1330
1332/1334
1336/1338
1340/1342
1344/1346
1348/1350
1352/1354
1356/1358
1360/1362
1364/1366
1368/1370
1372/1374
1376/1378
1380/1382
1384/1386
1388/1390
1392/1394
1396/1398
1400/1402
1404/1406
1408/1410
1412/1414
1416/1418
1420/1422
1424/1426
1428/1430
1432/1434
1436/1438
1440/1442
1444/1446
1448/1450
1452/1454
1456/1458
1460/1462
1464/1466
1468/1470
1472/1474
1476/1478
1480/1482
1484/1486
1488/1490
1492/1494
1496/1498
1500/1502
1504/1506
1508/1510
1512/1514
1516/1518
1520/1522
1524/1526
1528/1530
1532/1534
1536/1538
1540/1542
1544/1546
1548/1550
1552/1554
1556/1558
1560/1562
1564/1566
1568/1570
1572/1574
1576/1578
1580/1582
1584/1586
1588/1590
1592/1594
1596/1598
1600/1602
1604/1606
1608/1610
1612/1614
1616/1618
1620/1622
1624/1626
1628/1630
1632/1634
1636/1638
1640/1642
1644/1646
1648/1650
1652/1654
1656/1658
1660/1662
1664/1666
1668/1670
1672/1674
1676/1678
1680/1682
1684/1686
1688/1690
1692/1694
1696/1698
1700/1702
1704/1706
1708/1710
1712/1714
1716/1718
1720/1722
1724/1726
1728/1730
1732/1734
1736/1738
1740/1742
1744/1746
1748/1750
1752/1754
1756/1758
1760/1762
1764/1766
1768/1770
1772/1774
1776/1778
1780/1782
1784/1786
1788/1790
1792/1794
1796/1798
1800/1802
1804/1806
1808/1810
1812/1814
1816/1818
1820/1822
1824/1826
1828/1830
1832/1834
1836/1838
1840/1842
1844/1846
1848/1850
1852/1854
1856/1858
1860/1862
1864/1866
1868/1870
1872/1874
1876/1878
1880/1882
1884/1886
1888/1890
1892/1894
1896/1898
1900/1902
1904/1906
1908/1910
1912/1914
1916/1918
1920/1922
1924/1926
1928/1930
1932/1934
1936/1938
1940/1942
1944/1946
1948/1950
1952/1954
1956/1958
1960/1962
1964/1966
1968/1970
1972/1974
1976/1978
1980/1982
1984/1986
1988/1990
1992/1994
1996/1998
2000/2002
2004/2006
2008/2010
2012/2014
2016/2018
2020/2022
2024/2026
2028/2030
2032/2034
2036/2038
2040/2042
2044/2046
2048/2050
2052/2054
2056/2058
2060/2062
2064/2066
2068/2070
2072/2074
2076/2078
2080/2082
2084/2086
2088/2090
2092/2094
2096/2098
2100/2102
2104/2106
2108/2110
2112/2114
2116/2118
2120/2122
2124/2126
2128/2130
2132/2134
2136/2138
2140/2142
2144/2146
2148/2150
2152/2154
2156/2158
2160/2162
2164/2166
2168/2170
2172/2174
2176/2178
2180/2182
2184/2186
2188/2190
2192/2194
2196/2198
2200/2202
2204/2206
2208/2210
2212/2214
2216/2218
2220/2222
2224/2226
2228/2230
2232/2234
2236/2238
2240/2242
2244/2246
2248/2250
2252/2254
2256/2258
2260/2262
2264/2266
2268/2270
2272/2274
2276/2278
2280/2282
2284/2286
2288/2290
2292/2294
2296/2298
2300/2302
2304/2306
2308/2310
2312/2314
2316/2318
2320/2322
2324/2326
2328/2330
2332/2334
2336/2338
2340/2342
2344/2346
2348/2350
2352/2354
2356/2358
2360/2362
2364/2366
2368/2370
2372/2374
2376/2378
2380/2382
2384/2386
2388/2390
2392/2394
2396/2398
2400/2402
2404/2406
2408/2410
2412/2414
2416/2418
2420/2422
2424/2426
2428/2430
2432/2434
2436/2438
2440/2442
2444/2446
2448/2450
2452/2454
2456/2458
2460/2462
2464/2466
2468/2470
2472/2474
2476/2478
2480/2482
2484/2486
2488/2490
2492/2494
2496/2498
2500/2502
2504/2506
2508/2510
2512/2514
2516/2518
2520/2522
2524/2526
2528/2530
2532/2534
2536/2538
2540/2542
2544/2546
2548/2550
2552/2554
2556/2558
2560/2562
2564/2566
2568/2570
2572/2574
2576/2578
2580/2582
2584/2586
2588/2590
2592/2594
2596/2598
2600/2602
2604/2606
2608/2610
2612/2614
2616/2618
2620/2622
2624/2626
2628/2630
2632/2634
2636/2638
2640/2642
2644/2646
2648/2650
2652/2654
2656/2658
2660/2662
2664/2666
2668/2670
2672/2674
2676/2678
2680/2682
2684/2686
2688/2690
2692/2694
2696/2698
2700/2702
2704/2706
2708/2710
2712/2714
2716/2718
2720/2722
2724/2726
2728/2730
2732/2734
2736/2738
2740/2742
2744/2746
2748/2750
2752/2754
2756/2758
2760/2762
2764/2766
2768/2770
2772/2774
2776/2778
2780/2782
2784/2786
2788/2790
2792/2794
2796/2798
2800/2802
2804/2806
2808/2810
2812/2814
2816/2818
2820/2822
2824/2826
2828/2830
2832/2834
2836/2838
2840/2842
2844/2846
2848/2850
2852/2854
2856/2858
2860/2862
2864/2866
2868/2870
2872/2874
2876/2878
2880/2882
2884/2886
2888/2890
2892/2894
2896/2898
2900/2902
2904/2906
2908/2910
2912/2914
2916/2918
2920/2922
2924/2926
2928/2930
2932/2934
2936/2938
2940/2942
2944/2946
2948/2950
2952/2954
2956/2958
2960/2962
2964/2966
2968/2970
2972/2974
2976/2978
2980/2982
2984/2986
2988/2990
2992/2994
2996/2998
3000/3002
3004/3006
3008/3010
3012/3014
3016/3018
3020/3022
3024/3026
3028/3030
3032/3034
3036/3038
3040/3042
3044/3046
3048/3050
3052/3054
3056/3058
3060/3062
3064/3066
3068/3070
3072/3074
3076/3078
3080/3082
3084/3086
3088/3090
3092/3094
3096/3098
3100/3102
3104/3106
3108/3110
3112/3114
3116/3118
3120/3122
3124/3126
3128/3130
3132/3134
3136/3138
3140/3142
3144/3146
3148/3150
3152/3154
3156/3158
3160/3162
3164/3166
3168/3170
3172/3174
3176/3178
3180/3182
3184/3186
3188/3190
3192/3194
3196/3198
3200/3202
3204/3206
3208/3210
3212/3214
3216/3218
3220/3222
3224/3226
3228/3230
3232/3234
3236/3238
3240/3242
3244/3246
3248/3250
3252/3254
3256/3258
3260/3262
3264/3266
3268/3270
3272/3274
3276/3278
3280/3282
3284/3286
3288/3290
3292/3294
3296/3298
3300/3302
3304/3306
3308/3310
3312/3314
3316/3318
3320/3322
3324/3326
3328/3330
3332/3334
3336/3338
3340/3342
3344/3346
3348/3350
3352/3354
3356/3358
3360/3362
3364/3366
3368/3370
3372/3374
3376/3378
3380/3382
3384/3386
3388/3390
3392/3394
3396/3398
3400/3402
3404/3406
3408/3410
3412/3414
3416/3418
3420/3422
3424/3426
3428/3430
3432/3434
3436/3438
3440/3442
3444/3446
3448/3450
3452/3454
3456/3458
3460/3462
3464/3466
3468/3470
3472/3474
3476/3478
3480/3482
3484/3486
3488/3490
3492/3494
3496/3498
3500/3502
3504/3506
3508/3510
3512/3514
3516/3518
3520/3522
3524/3526
3528/3530
3532/3534
3536/3538
3540/3542
3544/3546
3548/3550
3552/3554
3556/3558
3560/3562
3564/3566
3568/3570
3572/3574
3576/3578
3580/3582
3584/3586
3588/3590
3592/3594
3596/3598
3600/3602
3604/3606
3608/3610
3612/3614
3616/3618
3620/3622
3624/3626
3628/3630
3632/3634
3636/3638
3640/3642
3644/3646
3648/3650
3652/3654
3656/3658
3660/3662
3664/3666
3668/3670
3672/3674
3676/3678
3680/3682
3684/3686
3688/3690
3692/3694
3696/3698
3700/3702
3704/3706
3708/3710
3712/3714
3716/3718
3720/3722
3724/3726
3728/3730
3732/3734
3736/3738
3740/3742
3744/3746
3748/3750
3752/3754
3756/3758
3760/3762
3764/3766
3768/3770
3772/3774
3776/3778
3780/3782
3784/3786
3788/3790
3792/3794
3796/3798
3800/3802
3804/3806
3808/3810
3812/3814
3816/3818
3820/3822
3824/3826
3828/3830
3832/3834
3836/3838
3840/3842
3844/3846
3848/3850
3852/3854
3856/3858
3860/3862
3864/3866
3868/3870
3872/3874
3876/3878
3880/3882
3884/3886
3888/3890
3892/3894
3896/3898
3900/3902
3904/3906
3908/3910
3912/3914
3916/3918
3920/3922
3924/3926
3928/3930
3932/3934
3936/3938
3940/3942
3944/3946
3948/3950
3952/3954
3956/3958
3960/3962
3964/3966
3968/3970
3972/3974
3976/3978
3980/3982
3984/3986
3988/3990
3992/3994
3996/3998
4000/4002
4004/4006
4008/4010
4012/4014
4016/4018
4020/4022
4024/4026
4028/4030
4032/4034
4036/4038
4040/4042
4044/4046
4048/4050
4052/4054
4056/4058
4060/4062
4064/4066
4068/4070
4072/4074
4076/4078
4080/4082
4084/4086
4088/4090
4092/4094
4096/4098
4100/4102
4104/4106
4108/4110
4112/4114
4116/4118
4120/4122
4124/4126
4128/4130
4132/4134
4136/4138
4140/4142
4144/4146
4148/4150
4152/4154
4156/4158
4160/4162
4164/4166
4168/4170
4172/4174
4176/4178
4180/4182
4184/4186
4188/4190
4192/4194
4196/4198
4200/4202
4204/4206
4208/4210
4212/4214
4216/4218
4220/4222
4224/4226
4228/4230
4232/4234
4236/4238
4240/4242
4244/4246
4248/4250
4252/4254
4256/4258
4260/4262
4264/4266
4268/4270
4272/4274
4276/4278
4280/4282
4284/4286
4288/4290
4292/4294
4296/4298
4300/4302
4304/4306
4308/4310
4312/4314
4316/4318
4320/4322
4324/4326
4328/4330
4332/4334
4336/4338
4340/4342
4344/4346
4348/4350
4352/4354
4356/4358
4360/4362
4364/4366
4368/4370
4372/4374
4376/4378
4380/4382
4384/4386
4388/4390
4392/4394
4396/4398
4400/4402
4404/4406
4408/4410
4412/4414
4416/4418
4420/4422
4424/4426
4428/4430
4432/4434
4436/4438
4440/4442
4444/4446
4448/4450
4452/4454
4456/4458
4460/4462
4464/4466
4468/4470
4472/4474
4476/4478
4480/4482
4484/4486
4488/4490
4492/4494
4496/4498
4500/4502
4504/4506
4508/4510
4512/4514
4516/4518
4520/4522
4524/4526
4528/4530
4532/4534
4536/4538
4540/4542
4544/4546
4548/4550
4552/4554
4556/4558
4560/4562
4564/4566
4568/4570
4572/4574
4576/4578
4580/4582
4584/4586
4588/4590
4592/4594
4596/4598
4600/4602
4604/4606
4608/4610
4612/4614
4616/4618
4620/4622
4624/4626
4628/4630
4632/4634
4636/4638
4640/4642
4644/4646
4648/4650
4652/4654
4656/4658
4660/4662
4664/4666
4668/4670
4672/4674
4676/4678
4680/4682
4684/4686
4688/4690
4692/4694
4696/4698
4700/4702
4704/4706
4708/4710
4712/4714
4716/4718
4720/4722
4724/4726
4728/4730
4732/4734
4736/4738
4740/4742
4744/4746
4748/4750
4752/4754
4756/4758
4760/4762
4764/4766
4768/4770
4772/4774
4776/4778
4780/4782
4784/4786
4788/4790
4792/4794
4796/4798
4800/4802
4804/4806
4808/4810
4812/4814
4816/4818
4820/4822
4824/4826
4828/4830
4832/4834
4836/4838
4840/4842
4844/4846
4848/4850
4852/4854
4856/4858
4860/4862
4864/4866
4868/4870
4872/4874
4876/4878
4880/4882
4884/4886
4888/4890
4892/4894
4896/4898
4900/4902
4904/4906
4908/4910
4912/4914
4916/4918
4920/4922
4924/4926
4928/4930
4932/4934
4936/4938
4940/4942
4944/4946
4948/4950
4952/4954
4956/4958
4960/4962
4964/4966
4968/4970
4972/4974
4976/4978
4980/4982
4984/4986
4988/4990
4992/4994
4996/4998
5000/5002
5004/5006
5008/5010
5012/5014
5016/5018
5020/5022
5024/5026
5028/5030
5032/5034
5036/5038
5040/5042
5044/5046
5048/5050
5052/5054
5056/5058
5060/5062
5064/5066
5068/5070
5072/5074
5076/5078
5080/5082
5084/5086
5088/5090
5092/5094
5096/5098
5100/5102
5104/5106
5108/5110
5112/5114
5116/5118
5120/5122
5124/5126
5128/5130
5132/5134
5136/5138
5140/5142
5144/5146
5148/5150
5152/5154
5156/5158
5160/5162
5164/5166
5168/5170
5172/5174
5176/5178
5180/5182
5184/5186
5188/5190
5192/5194
5196/5198
5200/5202
5204/5206
5208/5210
5212/5214
5216/5218
5220/5222
5224/5226
5228/5230
5232/5234
5236/5238
5240/5242
5244/5246
5248/5250
5252/5254
5256/5258
5260/5262
5264/5266
5268/5270
5272/5274
5276/5278
5280/5282
5284/5286
5288/5290
5292/5294
5296/5298
5300/5302
5304/5306
5308/5310
5312/5314
5316/5318
5320/5322
5324/5326
5328/5330
5332/5334
5336/5338
5340/5342
5344/5346
5348/5350
5352/5354
5356/5358
5360/5362
5364/5366
5368/5370
5372/5374
5376/5378
5380/5382
5384/5386
5388/5390
5392/5394
5396/5398
5400/5402
5404/5406
5408/5410
5412/5414
5416/5418
5420/5422
5424/5426
5428/5430
5432/5434
5436/5438
5440/5442
5444/5446
5448/5450
5452/5454
5456/5458
5460/5462
5464/5466
5468/5470
5472/5474
5476/5478
5480/5482
5484/5486
5488/5490
5492/5494
5496/5498
5500/5502
5504/5506
5508/5510
5512/5514
5516/5518
5520/5522
5524/5526
5528/5530
5532/5534
5536/5538
5540/5542
5544/5546
5548/5550
5552/5554
5556/5558
5560/5562
5564/5566
5568/5570
5572/5574
5576/5578
5580/5582
5584/5586
5588/5590
5592/5594
5596/5598
5600/5602
5604/5606
5608/5610
5612/5614
5616/5618
5620/5622
5624/5626
5628/5630
5632/5634
5636/5638
5640/5642
5644/5646
5648/5650
5652/5654
5656/5658
5660/5662
5664/5666
5668/5670
5672/5674
5676/5678
5680/5682
5684/5686
5688/5690
5692/5694
5696/5698
5700/5702
5704/5706
5708/5710
5712/5714
5716/5718
5720/5722
5724/5726
5728/5730
5732/5734
5736/5738
5740/5742
5744/5746
5748/5750
5752/5754
5756/5758
5760/5762
5764/5766
5768/5770
5772/5774
5776/5778
5780/5782
5784/5786
5788/5790
5792/5794
5796/5798
5800/5802
5804/5806
5808/5810
5812/5814
5816/5818
5820/5822
5824/5826
5828/5830
5832/5834
5836/5838
5840/5842
5844/5846
5848/5850
5852/5854
5856/5858
5860/5862
5864/5866
5868/5870
5872/5874
5876/5878
5880/5882
5884/5886
5888/5890
5892/5894
5896/5898
5900/5902
5904/5906
5908/5910
5912/5914
5916/5918
5920/5922
5924/5926
5928/5930
5932/5934
5936/5938
5940/5942
5944/5946
5948/5950
5952/5954
5956/5958
5960/5962
5964/5966
5968/5970
5972/5974
5976/5978
5980/5982
5984/5986
5988/5990
5992/5994
5996/5998
6000/6002
6004/6006
6008/6010
6012/6014
6016/6018
6020/6022
6024/6026
6028/6030
6032/6034
6036/6038
6040/6042
6044/6046
6048/6050
6052/6054
6056/6058
6060/6062
6064/6066
6068/6070
6072/6074
6076/6078
6080/6082
6084/6086
6088/6090
6092/6094
6096/6098
6100/6102
6104/6106
6108/6110
6112/6114
6116/6118
6120/6122
6124/6126
6128/6130
6132/6134
6136/6138
6140/6142
6144/6146
6148/6150
6152/6154
6156/6158
6160/6162
6164/6166
6168/6170
6172/6174
6176/6178
6180/6182
6184/6186
6188/6190
6192/6194
6196/6198
6200/6202
6204/6206
6208/6210
6212/6214
6216/6218
6220/6222
6224/6226
6228/6230
6232/6234
6236/6238
6240/6242
6244/6246
6248/6250
6252/6254
6256/6258
6260/6262
6264/6266
6268/6270
6272/6274
6276/6278
6280/6282
6284/6286
6288/6290
6292/6294
6296/6298
6300/6302
6304/6306
6308/6310
6312/6314
6316/6318
6320/6322
6324/6326
6328/6330
6332/6334
6336/6338
6340/6342
6344/6346
6348/6350
6352/6354
6356/6358
6360/6362
6364/6366
6368/6370
6372/6374
6376/6378
6380/6382
6384/6386
6388/6390
6392/6394
6396/6398
6400/6402
6404/6406
6408/6410
6412/6414
6416/6418
6420/6422
6424/6426
6428/6430
6432/6434
6436/6438
6440/6442
6444/6446
6448/6450
6452/6454
6456/6458
6460/6462
6464/6466
6468/6470
6472/6474
6476/6478
6480/6482
6484/6486
6488/6490
6492/6494
6496/6498
6500/6502
6504/6506
6508/6510
6512/6514
6516/6518
6520/6522
6524/6526
6528/6530
6532/6534
6536/6538
6540/6542
6544/6546
6548/6550
6552/6554
6556/6558
6560/6562
6564/6566
6568/6570
6572/6574
6576/6578
6580/6582
6584/6586
6588/6590
6592/6594
6596/6598
6600/6602
6604/6606
6608/6610
6612/6614
6616/6618
6620/6622
6624/6626
6628/6630
6632/6634
6636/6638
6640/6642
6644/6646
6648/6650
6652/6654
6656/6658
6660/6662
6664/6666
6668/6670
6672/6674
6676/6678
6680/6682
6684/6686
6688/6690
6692/6694
6696/6698
6700/6702
6704/6706
6708/6710
6712/6714
6716/6718
6720/6722
6724/6726
6728/6730
6732/6734
6736/6738
6740/6742
6744/6746
6748/6750
6752/6754
6756/6758
6760/6762
6764/6766
6768/6770
6772/6774
6776/6778
6780/6782
6784/6786
6788/6790
6792/6794
6796/6798
6800/6802
6804/6806
6808/6810
6812/6814
6816/6818
6820/6822
6824/6826
6828/6830
6832/6834
6836/6838
6840/6842
6844/6846
6848/6850
6852/6854
6856/6858
6860/6862
6864/6866
6868/6870
6872/6874
6876/6878
6880/6882
6884/6886
6888/6890
6892/6894
6896/6898
6900/6902
6904/6906
6908/6910
6912/6914
6916/6918
6920/6922
6924/6926
6928/6930
6932/6934
6936/6938
6940/6942
6944/6946
6948/6950
6952/6954
6956/6958
6960/6962
6964/6966
6968/6970
6972/6974
6976/6978
6980/6982
6984/6986
6988/6990
6992/6994
6996/6998
7000/7002
7004/7006
7008/7010
7012/7014
7016/7018
7020/7022
7024/7026
7028/7030
7032/7034
7036/7038
7040/7042
7044/7046
7048/7050
7052/7054
7056/7058
7060/7062
7064/7066
7068/7070
7072/7074
7076/7078
7080/7082
7084/7086
7088/7090
7092/7094
7096/7098
7100/7102
7104/7106
7108/7110
7112/7114
7116/7118
7120/7122
7124/7126
7128/7130
7132/7134
7136/7138
7140/7142
7144/7146
7148/7150
7152/7154
7156/7158
7160/7162
7164/7166
7168/7170
7172/7174
7176/7178
7180/7182
7184/7186
7188/7190
7192/7194
7196/7198
7200/7202
7204/7206
7208/7210
7212/7214
7216/7218
7220/7222
7224/7226
7228/7230
7232/7234
7236/7238
7240/7242
7244/7246
7248/7250
7252/7254
7256/7258
7260/7262
7264/7266
7268/7270
7272/7274
7276/7278
7280/7282
7284/7286
7288/7290
7292/7294
7296/7298
7300/7302
7304/7306
7308/7310
7312/7314
7316/7318
7320/7322
7324/7326
7328/7330
7332/7334
7336/7338
7340/7342
7344/7346
7348/7350
7352/7354
7356/7358
7360/7362
7364/7366
7368/7370
7372/7374
7376/7378
7380/7382
7384/7386
7388/7390
7392/7394
7396/7398
7400/7402
7404/7406
7408/7410
7412/7414
7416/7418
7420/7422
7424/7426
7428/7430
7432/7434
7436/7438
7440/7442
7444/7446
7448/7450
7452/7454
7456/7458
7460/7462
7464/7466
7468/7470
7472/7474
7476/7478
7480/7482
7484/7486
7488/7490
7492/7494
7496/7498
7500/7502
7504/7506
7508/7510
7512/7514
7516/7518
7520/7522
7524/7526
7528/7530
7532/7534
7536/7538
7540/7542
7544/7546
7548/7550
7552/7554
7556/7558
7560/7562
7564/7566
7568/7570
7572/7574
7576/7578
7580/7582
7584/7586
7588/7590
7592/7594
7596/7598
7600/7602
7604/7606
7608/7610
7612/7614
7616/7618
7620/7622
7624/7626
7628/7630
7632/7634
7636/7638
7640/7642
7644/7646
7648/7650
7652/7654
7656/7658
7660/7662
7664/7666
7668/7670
7672/7674
7676/7678
7680/7682
7684/7686
7688/7690
7692/7694
7696/7698
7700/7702
7704/7706
7708/7710
7712/7714
7716/7718
7720/7722
7724/7726
7728/7730
7732/7734
7736/7738
7740/7742
7744/7746
7748/7750
7752/7754
7756/7758
7760/7762
7764/7766
7768/7770
7772/7774
7776/7778
7780/7782
7784/7786
7788/7790
7792/7794
7796/7798
7800/7802
7804/7806
7808/7810
7812/7814
7816/7818
7820/7822
7824/7826
7828/7830
7832/7834
7836/7838
7840/7842
7844/7846
7848/7850
7852/7854
7856/7858
7860/7862
7864/7866
7868/7870
7872/7874
7876/7878
7880/7882
7884/7886
7888/7890
7892/7894
7896/7898
7900/7902
7904/7906
7908/7910
7912/7914
7916/7918
7920/7922
7924/7926
7928/7930
7932/7934
7936/7938
7940/7942
7944/7946
7948/7950
7952/7954
7956/7958
7960/7962
7964/7966
7968/7970
7972/7974
7976/7978
7980/7982
7984/7986
7988/7990
7992/7994
7996/7998
8000/8002
8004/8006
8008/8010
8012/8014
8016/8018
8020/8022
8024/8026
8028/8030
8032/8034
8036/8038
8040/8042
8044/8046
8048/8050
8052/8054
8056/8058
8060/8062
8064/8066
8068/8070
8072/8074
8076/8078
8080/8082
8084/8086
8088/8090
8092/8094
8096/8098
8100/8102
8104/8106
8108/8110
8112/8114
8116/8118
8120/8122
8124/8126
8128/8130
8132/8134
8136/8138
8140/8142
8144/8146
8148/8150
8152/8154
8156/8158
8160/8162
8164/8166
8168/8170
8172/8174
8176/8178
8180/8182
8184/8186
8188/8190
8192/8194
8196/8198
8200/8202
8204/8206
8208/8210
8212/8214
8216/8218
8220/8222
8224/8226
8228/8230
8232/8234
8236/8238
8240/8242
8244/8246
8248/8250
8252/8254
8256/8258
8260/8262
8264/8266
8268/8270
8272/8274
8276/8278
8280/8282
8284/8286
8288/8290
8292/8294
8296/8298
8300/8302
8304/8306
8308/8310
8312/8314
8316/8318
8320/8322
8324/8326
8328/8330
8332/8334
8336/8338
8340/8342
8344/8346
8348/8350
8352/8354
8356/8358
8360/8362
8364/8366
8368/8370
8372/8374
8376/8378
8380/8382
8384/8386
8388/8390
8392/8394
8396/8398
8400/8402
8404/8406
8408/8410
8412/8414
8416/8418
8420/8422
8424/8426
8428/8430
8432/8434
8436/8438
8440/8442
8444/8446
8448/8450
8452/8454
8456/8458
8460/8462
8464/8466
8468/8470
8472/8474
8476/8478
8480/8482
8484/8486
8488/8490
8492/8494
8496/8498
8500/8502
8504/8506
8508/8510
8512/8514
8516/8518
8520/8522
8524/8526
8528/8530
8532/8534
8536/8538
8540/8542
8544/8546
8548/8550
8552/8554
8556/8558
8560/8562
8564/8566
8568/8570
8572/8574
8576/8578
8580/8582
8584/8586
8588/8590
8592/8594
8596/8598
8600/8602
8604/8606
8608/8610
8612/8614
8616/8618
8620/8622
8624/8626
8628/8630
8632/8634
8636/8638
8640/8642
8644/8646
8648/8650
8652/8654
8656/8658
8660/8662
8664/8666
8668/8670
8672/8674
8676/8678
8680/8682
8684/8686
8688/8690
8692/8694
8696/8698
8700/8702
8704/8706
8708/8710
8712/8714
8716/8718
8720/8722
8724/8726
8728/8730
8732/8734
8736/8738
8740/8742
8744/8746
8748/8750
8752/8754
8756/8758
8760/8762
8764/8766
8768/8770
8772/8774
8776/8778
8780/8782
8784/8786
8788/8790
8792/8794
8796/8798
8800/8802
8804/8806
8808/8810
8812/8814
8816/8818
8820/8822
8824/8826
8828/8830
8832/8834
8836/8838
8840/8842
8844/8846
8848/8850
8852/8854
8856/8858
8860/8862
8864/8866
8868/8870
8872/8874
8876/8878
8880/8882
8884/8886
8888/8890
8892/8894
8896/8898
8900/8902
8904/8906
8908/8910
8912/8914
8916/8918
8920/8922
8924/8926
8928/8930
8932/8934
8936/8938
8940/8942
8944/8946
8948/8950
8952/8954
8956/8958
8960/8962
8964/8966
8968/8970
8972/8974
8976/8978
8980/8982
8984/8986
8988/8990
8992/8994
8996/8998
9000/9002
9004/9006
9008/9010
9012/9014
9016/9018
9020/9022
9024/9026
9028/9030
9032/9034
9036/9038
9040/9042
9044/9046
9048/9050
9052/9054
9056/9058
9060/9062
9064/9066
9068/9070
9072/9074
9076/9078
9080/9082
9084/9086
9088/9090
9092/9094
9096/9098
9100/9102
9104/9106
9108/9110
9112/9114
9116/9118
9120/9122
9124/9126
9128/9130
9132/9134
9136/9138
9140/9142
9144/9146
9148/9150
9152/9154
9156/9158
9160/9162
9164/9166
9168/9170
9172/9174
9176/9178
9180/9182
9184/9186
9188/9190
9192/9194
9196/9198
9200/9202
9204/9206
9208/9210
9212/9214
9216/9218
9220/9222
9224/9226
9228/9230
9232/9234
9236/9238
9240/9242
9244/9246
9248/9250
9252/9254
9256/9258
9260/9262
9264/9266
9268/9270
9272/9274
9276/9278
9280/9282
9284/9286
9288/9290
9292/9294
9296/9298
9300/9302
9304/9306
9308/9310
9312/9314
9316/9318
9320/9322
9324/9326
9328/9330
9332/9334
9336/9338
9340/9342
9344/9346
9348/9350
9352/9354
9356/9358
9360/9362
9364/9366
9368/9370
9372/9374
9376/9378
9380/9382
9384/9386
9388/9390
9392/9394
9396/9398
9400/9402
9404/9406
9408/9410
9412/9414
9416/9418
9420/9422
9424/9426
9428/9430
9432/9434
9436/9438
9440/9442
9444/9446
9448/9450
9452/9454
9456/9458
9460/9462
9464/9466
9468/9470
9472/9474
9476/9478
9480/9482
9484/9486
9488/9490
9492/9494
9496/9498
9500/9502
9504/9506
9508/9510
9512/9514
9516/9518
9520/9522
9524/9526
9528/9530
9532/9534
9536/9538
9540/9542
9544/9546
9548/9550
9552/9554
9556/9558
9560/9562
9564/9566
9568/9570
9572/9574
9576/9578
9580/9582
9584/9586
9588/9590
9592/9594
9596/9598
9600/9602
9604/9606
9608/9610
9612/9614
9616/9618
9620/9622
9624/9626
9628/9630
9632/9634
9636/9638
9640/9642
9644/9646
9648/9650
9652/9654
9656/9658
9660/9662
9664/9666
9668/9670
9672/9674
9676/9678
9680/9682
9684/9686
9688/9690
9692/9694
9696/9698
9700/9702
9704/9706
9708/9710
9712/9714
9716/9718
9720/9722
9724/9726
9728/9730
9732/9734
9736/9738
9740/9742
9744/9746
9748/9750
9752/9754
9756/9758
9760/9762
9764/9766
9768/9770
9772/9774
9776/9778
9780/9782
9784/9786
9788/9790
9792/9794
9796/9798
9800/9802
9804/9806
9808/9810
9812/9814
9816/9818
9820/9822
9824/9826
9828/9830
9832/9834
9836/9838
9840/9842
9844/9846
9848/9850
9852/9854
9856/9858
9860/9862
9864/9866
9868/9870
9872/9874
9876/9878
9880/9882
9884/9886
9888/9890
9892/9894
9896/9898
9900/9902
9904/9906
9908/9910
9912/9914
9916/9918
9920/9922
9924/9926
9928/9930
9932/9934
9936/9938
9940/9942
9944/9946
9948/9950
9952/9954
9956/9958
9960/9962
9964/9966
9968/9970
9972/9974
9976/9978
9980/9982
9984/9986
9988/9990
9992/9994
9996/9998
10000/10002
10004/10006
10008/10010
10012/10014
10016/10018
10020/10022
10024/10026
10028/10030
10032/10034
10036/10038
10040/10042
10044/10046
10048/10050
10052/10054
10056/10058
10060/10062
10064/10066
10068/10070
10072/10074
10076/10078
10080/10082
10084/10086
10088/10090
10092/10094
10096/10098
10100/10102
10104/10106
10108/10110
10112/10114
10116/10118
10120/10122
10124/10126
10128/10130
10132/10134
10136/10138
10140/10142
10144/10146
10148/10150
10152/10154
10156/10158
10160/10162
10164/10166
10168/10170
10172/10174
10176/10178
10180/10182
10184/10186
10188/10190
10192/10194
10196/10198
10200/10202
10204/10206
10208/10210
10212/10214
10216/10218
10220/10222
10224/10226
10228/10230
10232/10234
10236/10238
10240/10242
10244/10246
10248/10250
10252/10254
10256/10258
10260/10262
10264/10266
10268/10270
10272/10274
10276/10278
10280/10282
10284/10286
10288/10290
10292/10294
10296/10298
10300/10302
10304/10306
10308/10310
10312/10314
10316/10318
10320/10322
10324/10326
10328/10330
10332/10334
10336/10338
10340/10342
10344/10346
10348/10350
10352/10354
10356/10358
10360/10362
10364/10366
10368/10370
10372/10374
10376/10378
10380/10382
10384/10386
10388/10390
10392/10394
10396/10398
10400/10402
10404/10406
10408/10410
10412/10414
10416/10418
10420/10422
10424/10426
10428/10430
10432/10434
10436/10438
10440/10442
10444/10446
10448/10450
10452/10454
10456/10458
10460/10462
10464/10466
10468/10470
10472/10474
10476/10478
10480/10482
10484/10486
10488/10490
10492/10494
10496/10498
10500/10502
10504/10506
10508/10510




**1 FIRE ALARM RENOVATION PLAN**
SCALE: 1/4" = 1'- 0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

0

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING


FIRE ALARM FLOOR PLANS

o-E.300


STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM (713) 300-4080


TEXAS ENG. FIRM REG. NO. F-21853 | © 2025 ALL RIGHTS RESERVED


12999 W. SAM HOUSTON PARKWAY S., SUITE 725, HOUSTON, TX 77072




## 1 PARTIAL ELECTRICAL RISER

NO SCALE

NOTES:
1. FIELD VERIFY ALL EXISTING ELECTRICAL PANELS AND FEEDERS SHOWN ON DRAWINGS.
2. REF ELECTRICAL FLOOR PLANS FOR PANEL LOCATIONS.
3. ALL OUTAGES SHALL BE SCHEDULED/CONFIRMED IN WRITING WITH THE OWNER A MINIMUM OF TWO WEEKS PRIOR TO ANY OUTAGE.
4. AT THE END OF THE PROJECT PROVIDE A NEW TYPEWRITTEN PANEL SCHEDULE USING BUILDING ROOM NUMBERS FOR ALL PANELS WITH CIRCUITS ADDED, REMOVED, OR MODIFIED AS PART OF THE PROJECT.
5. REFERENCE PANEL SCHEDULES AND SHORT CIRCUIT TABLE FOR AIC AND SCCR VALUES.

### NEW KITCHEN PANEL — KITCHEN

**PANEL HK** — 225A MLO, 480Y/277V, 3ϕ, 4 WIRE — AVAILABLE FAULT: 20,250A — SCCR & AIC: 25,000A — MOUNTING: RECESSED — STAINLESS STEEL COVER

| NOTES | EQUIP. NO. | LOAD | DESCRIPTION | WIRE | CB | CKT | A | B | C | CKT | CB | WIRE | DESCRIPTION | LOAD | EQUIP. NO. | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 6 | | 376 | KITCHEN ROOM LIGHTS | 3–12 | 20/1 | 1 | | | | 2 | 15/3 | 3–12 | ESF–1 | 4986 | | |
| 7 | | 1095 | KITCHEN LIGHTS | 3–12 | 20/1 | 3 | | | | 4 | – | +12G | ( 1.5HP / 1.5HP ) | – | | |
| | | 84 | KITCHEN SOFFIT LIGHTS | 3–12 | 20/1 | 5 | | | | 6 | – | 3/4"C | – | – | | |
| | | | SPARE | | 20/1 | 7 | | | | 8 | 15/3 | 3–12 | ESF–2 | 4986 | | |
| | | | SPARE | | 20/1 | 9 | | | | 10 | – | +12G | ( 1.5HP / 1.5HP ) | – | | |
| | | | SPARE | | 20/1 | 11 | | | | 12 | – | 3/4"C | – | – | | |
| | | | SPARE | | 20/1 | 13 | | | | 14 | | | SPACE | | | |
| | | | SPARE | | 20/1 | 15 | | | | 16 | | | SPACE | | | |
| | | | SPARE | | 20/1 | 17 | | | | 18 | | | SPACE | | | |
| | | | SPARE | | 20/1 | 19 | | | | 20 | | | SPACE | | | |
| | | | SPARE | | 20/1 | 21 | | | | 22 | | | SPACE | | | |
| | | | SPACE | | | 23 | | | | 24 | | | SPACE | | | |
| | | | SPACE | | | 25 | | | | 26 | | | SPACE | | | |
| | | | SPACE | | | 27 | | | | 28 | | | SPACE | | | |
| | | | SPACE | | | 29 | | | | 30 | | | SPACE | | | |
| | | | SPACE | | | 31 | | | | 32 | | | SPACE | | | |
| | | | SPACE | | | 33 | | | | 34 | | | SPACE | | | |
| | | | SPACE | | | 35 | | | | 36 | | | SPACE | | | |
| | | | SPACE | | | 37 | | | | 38 | 70/3 | 3–6 | DISHMACHINE | 42963 | E250 | |
| | | | SPACE | | | 39 | | | | 40 | – | +8G | – | – | | |
| | | | SPACE | | | 41 | | | | 42 | – | 3/4"C | – | – | | |
| | | TOTAL LOAD ❶ 100% = | 54490VA | | | TOTAL LOAD ❶ 100% = | | | | 66A | | | TOTAL LOAD ❶ 125% = | 82A | | |

### NEW KITCHEN PANEL — KITCHEN

**PANEL LK** — 225A MLO, 208Y/120V, 3ϕ, 4 WIRE — AVAILABLE FAULT: <10,000A — SCCR & AIC: 10,000A — MOUNTING: RECESSED — STAINLESS STEEL COVER

| NOTES | EQUIP. NO. | LOAD | DESCRIPTION | WIRE | CB | CKT | A | B | C | CKT | CB | WIRE | DESCRIPTION | LOAD | EQUIP. NO. | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E10 | 640 | 3 REC – RR/STOR/CUST & BELL | 3–12 | 20/1 | 1 | | | | 2 | 20/1 | 3–12 | 1 REC – KITCHEN | 180 | E10 | |
| | E110 | 1920 | WASHING MACHINE | 3–12 | 20/1 | 3 | | | | 4 | 20/1 | 3–12 | 1 REC – KITCHEN | 180 | E10 | |
| | E110A | 5000 | DRYER | 2–10 | 30/2GFI | 5 | | | | 6 | 20/1 | 3–12 | 1 REC – KITCHEN | 180 | E10 | |
| | E151 | – | – | +10N+10G | 3/4"C | 7 | | | | 8 | 20/2 | 2–10 | HEATED CABINET | 3224 | E187 | |
| | | 540 | 3 REC – OFFICE | 3–12 | 20/1 | 9 | | | | 10 | 3/4"C | +10G | – | – | | |
| | E10 | 540 | 3 REC – KITCHEN | 3–12 | 20/1 | 11 | | | | 12 | 20/2 | 2–10 | HEATED CABINET | 3224 | E187 | |
| | E10 | 360 | 2 REC – SERVING LINE | 3–12 | 20/1 | 13 | | | | 14 | 3/4"C | +10G | – | | | |
| | E10 | 360 | 2 REC – SERVING LINE | 3–12 | 20/1 | 15 | | | | 16 | 20/3 | 3–12 | DISPOSER | 3960 | E123 | |
| | | 1000 | 2 EDF – CAFETERIA | 3–12 | 20/1 | 17 | | | | 18 | – | +12G | ( 3 HP ) | – | | |
| | E615 | 500 | 2 MENU BOARDS | 3–12 | 20/1 | 19 | | | | 20 | – | 3/4"C | – | – | | |
| | E209 | 960 | MILK COOLER | 3–12 | 20/1 | 21 | | | | 22 | 20/1 | 3–12 | AIR SCREEN | 612 | E101 | |
| | E201A | 5824 | HOT FOOD COUNTER | 2–8 | 35/2 | 23 | | | | 24 | 15/1 | 3–12 | EF–CF ( 1/6HP ) | 528 | | |
| | | – | – | +10G | 3/4"C | 25 | | | | 26 | 15/1 | 3–12 | EF–14 ( 1/6HP ) | 528 | | |
| | E201B | 1920 | COLD FOOD COUNTER | 3–12 | 20/1 | 27 | | | | 28 | 20/1 | 3–12 | EF–2 ( 1/6HP ) | 528 | | |
| | E214 | 360 | CASH REGISTERS | 3–12 | 20/1 | 29 | | | | 30 | 20/1 | | SPARE | | | |
| | E201B | 1920 | COLD FOOD COUNTER | 3–12 | 20/1 | 31 | | | | 32 | 20/1 | | SPARE | | | |
| | E201A | 5824 | HOT FOOD COUNTER | 2–8 | 35/2 | 33 | | | | 34 | 20/1 | | SPARE | | | |
| | | – | – | +10G | 3/4"C | 35 | | | | 36 | 20/1 | | SPARE | | | |
| | E209 | 960 | MILK COOLER | 3–12 | 20/1 | 37 | | | | 38 | 20/1 | | SPARE | | | |
| | | 360 | 2 REC – CAFETERIA | 3–12 | 20/1 | 39 | | | | 40 | 20/1 | | SPARE | | | |
| | | | SPARE | | 20/1 | 41 | | | | 42 | 20/1 | | SPARE | | | |
| | E153/E153M | 250 | HOOD LTS & SENSOR | 3–12 | 20/1 | 43 | | | | 44 | 20/1GFI | 3–12 | DROP CORD | 180 | E129 | |
| | E153/E153M | 250 | HOOD LTS & SENSOR | 3–12 | 20/1 | 45 | | | | 46 | 20/1GFI | 3–12 | DROP CORD | 180 | E129 | |
| 8 | E161 | 720 | CONVECTION OVEN | 3–12 | 20/1GFI | 47 | | | | 48 | 20/1GFI | 3–12 | MOBILE PROOFER | 1800 | E139A | |
| 8 | E161 | 720 | CONVECTION OVEN | 3–12 | 20/1GFI | 49 | | | | 50 | 20/1GFI | 3–12 | 20QT MIXER | 960 | E125 | |
| 8 | E161 | 720 | CONVECTION OVEN | 3–12 | 20/1GFI | 51 | | | | 52 | 20/1GFI | 3–12 | DROP CORD | 180 | E129 | |
| 8 | E161 | 720 | CONVECTION OVEN | 3–12 | 20/1GFI | 53 | | | | 54 | 20/1GFI | 3–12 | DROP CORD | 180 | E129 | |
| 8 | E163 | 600 | TILT BRAISING PAN | 3–12 | 20/1 | 55 | | | | 56 | 20/1GFI | 3–12 | DROP CORD | 180 | E129 | |
| 8 | E172 | 3120 | COMBI OVEN | 2–12 | 20/2 | 57 | | | | 58 | 20/1GFI | 3–12 | DROP CORD | 180 | E129 | |
| | | – | – | +12G | 3/4"C | 59 | | | | 60 | 20/1 | 3–12 | EXISTING CIRCUIT | 500 | | 5 |
| 8 | E172 | 3120 | COMBI OVEN | 2–12 | 20/2 | 61 | | | | 62 | 20/2 | 2–12 | EXISTING CIRCUIT | 1000 | | 5 |
| | | – | – | +12G | 3/4"C | 63 | | | | 64 | – | +12N+12G | – | – | | 5 |
| | | 250 | EXISTING CIRCUIT | 3–12 | 20/1 | 65 | | | | 66 | 20/2 | 2–12 | EXISTING CIRCUIT | 1000 | | 5 |
| 9 | | 0 | TEMP LOAD CENTER | 4–3 | 100/3 | 67 | | | | 68 | – | +12N+12G | – | – | | 5 |
| | | – | – | +8G | – | 69 | | | | 70 | 30/2 | 2–10 | EXISTING CIRCUIT | 3000 | | 5 |
| | | – | – | 1.25"C | – | 71 | | | | 72 | – | +10N+10G | – | – | | |
| | | TOTAL LOAD ❶ 100% = | 61942VA | | | TOTAL LOAD ❶ 100% = | | | | 172A | | | TOTAL LOAD ❶ 65% = | 112A | | |

### KITCHEN HOOD CONTACTOR SCHEDULE

**HOOD 1**

| POLE | DESCRIPTION | NORMAL CKT | EM CKT | CONTROL ZONE | EQUIPMENT LOCATION | CONTACTOR TYPE |
|---|---|---|---|---|---|---|
| CK1–1 | CONVECTION OVEN | LK–47 | – | HOOD 1 | KITCHEN | ELECTRICALLY HELD – NO |
| CK1–2 | CONVECTION OVEN | LK–49 | – | HOOD 1 | KITCHEN | ELECTRICALLY HELD – NO |
| CK1–3 | CONVECTION OVEN | LK–51 | – | HOOD 1 | KITCHEN | ELECTRICALLY HELD – NO |
| CK1–4 | CONVECTION OVEN | LK–53 | – | HOOD 1 | KITCHEN | ELECTRICALLY HELD – NO |
| CK1–5 | SPARE | | | | | ELECTRICALLY HELD – NO |
| CK1–6 | SPARE | | | | | ELECTRICALLY HELD – NO |
| CK1–7 | SPARE | | | | | ELECTRICALLY HELD – NO |
| CK1–8 | SPARE | | | | | ELECTRICALLY HELD – NO |

**HOOD 2**

| POLE | DESCRIPTION | NORMAL CKT | EM CKT | CONTROL ZONE | EQUIPMENT LOCATION | CONTACTOR TYPE |
|---|---|---|---|---|---|---|
| CK2–1 | TILT BRAISING PAN | LK–55 | – | HOOD 2 | KITCHEN | ELECTRICALLY HELD – NO |
| CK2–2 | COMBI–OVEN | LK–57/59 | – | HOOD 2 | KITCHEN | ELECTRICALLY HELD – NO |
| CK2–3 | ( 2–POLE ) | – | – | – | – | ELECTRICALLY HELD – NO |
| CK2–4 | COMBI–OVEN | LK–61/63 | – | HOOD 2 | KITCHEN | ELECTRICALLY HELD – NO |
| CK2–5 | ( 2–POLE ) | – | – | – | – | ELECTRICALLY HELD – NO |
| CK2–6 | SPARE | | | | | ELECTRICALLY HELD – NO |
| CK2–7 | SPARE | | | | | ELECTRICALLY HELD – NO |
| CK2–8 | SPARE | | | | | ELECTRICALLY HELD – NO |

1. REFERENCE FLOOR PLANS FOR EQUIPMENT LOCATIONS AND ADDITIONAL INFORMATION.
2. EACH KITCHEN HOOD CONTACTOR HALL BE CONTROLLED ON/OFF BY THE APPROPRIATE HOOD ANSUL SYSTEM. WHEN ACTIVATED ALL POWER WITHIN THE COOKING HOOD SHALL BE DE–ENERGIZED.

### EXIST SWITCHBOARD — CENTRAL PLANT

**(E)SWBD M** — 2000A MLO, 480Y/277V, 3ϕ, 4 WIRE — AVAILABLE FAULT: 50,000A — SCCR & AIC: 50,000A — FREE STANDING

| NOTES | CIRCUIT | DESCRIPTION | CB | FEEDER SIZE | AMPS |
|---|---|---|---|---|---|
| | 1 | EXIST DISTRIBUTION PANEL DC | 400/3 | EXIST FEEDER | |
| 2,4 | 2 | NEW PANEL HK | 225/3 | 4–4/0 +4G, 2.5"C | 66A |
| | 3 | EXIST DISTRIBUTION PANEL DA | 400/3 | EXIST FEEDER | 274A |
| | 4 | EXIST DISTRIBUTION PANEL DB | 400/3 | EXIST FEEDER | |
| | 5 | EXIST DISTRIBUTION PANEL AC | 1200/3 | EXIST FEEDER | |
| | | | | TOTAL LOAD ❶ 100% = | 339A |
| | | | | TOTAL LOAD ❶ 125% = | 424A |

1. THE EXISTING 2000A FEEDER IS SUFFICIENT FOR THE REVISED LOAD.
2. UPDATE PANEL SCHEDULE TO MATCH REVISED EQUIPMENT DESCRIPTION.

### EXIST GE NHB PANELBOARD

**(E)PANEL DA** — 400A MLO, 480Y/277V, 3ϕ, 4 WIRE — AVAILABLE FAULT: 27,000A — SCCR & AIC: 35,000A — MOUNTING: SURFACE

| NOTES | LOAD | DESCRIPTION | WIRE | CB | CKT | A | B | C | CKT | CB | WIRE | DESCRIPTION | LOAD | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | 39000 | DUCT HEATER 2 | EXIST | 60/3 | 1 | | | | 2 | 20/3 | EXIST | AHU #2 | 9150 | |
| | – | ( STAGE ) | – | – | 3 | | | | 4 | – | – | – | – | |
| | – | – | – | – | 5 | | | | 6 | – | – | – | – | |
| 2 | | KITCHEN LIGHTS | EXIST | 20/1 | 7 | | | | 8 | 20/1 | EXIST | LIGHTS CAFETORIUM RMS | 2300 | 1 |
| 1 | 3000 | LIGHTS CAFETORIUM | EXIST | 20/1 | 9 | | | | 10 | 20/1 | EXIST | EXIST CIRCUIT | 3000 | |
| 1 | 3000 | LIGHTS CAFETORIUM | EXIST | 20/1 | 11 | | | | 12 | 70/3 | 3–6 | TEMP KITCHEN PANEL LTK | 3791B | 4 |
| | | SPACE | | | 13 | | | | 14 | – | +8G | – | – | |
| | | SPACE | | | 15 | | | | 16 | – | 3/4"C | – | – | |
| | | SPACE | | | 17 | | | | 18 | | | SPACE | | |
| | | SPACE | | | 19 | | | | 20 | | | SPACE | | |
| | | SPACE | | | 21 | | | | 22 | | | SPACE | | |
| | | SPACE | | | 23 | | | | 24 | | | SPACE | | |
| | 130000 | PANEL PA | EXIST | 225/3 | 25 | | | | 26 | – | – | – | – | |
| | – | ( SUBFEED BREAKER ) | – | – | 27 | | | | 28 | – | – | – | – | |
| | – | – | – | – | 29 | | | | 30 | – | – | – | – | |
| | | TOTAL LOAD ❶ 100% = | 227368VA | | | TOTAL LOAD ❶ 100% = | | | 274A | | | TOTAL LOAD ❶ 125% = | 342A | |

1. THE EXISTING 400A FEEDER IS SUFFICIENT FOR THE REVISED LOAD.
2. UPDATE PANEL SCHEDULE TO MATCH REVISED EQUIPMENT DESCRIPTION.

### EXIST EM STANDBY PANELBOARD — CENTRAL PLANT

**(E)PANEL EL** — 100A MCB, 208Y/120V, 3ϕ, 4 WIRE — AVAILABLE FAULT: <10,000A — SCCR & AIC: 10,000A — MOUNTING: SURFACE

| NOTES | EQUIP. NO. | LOAD | DESCRIPTION | WIRE | CB | CKT | A | B | C | CKT | CB | WIRE | DESCRIPTION | LOAD | EQUIP. NO. | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | 250 | F/A RPS | EXIST | 20/1 | 1 | | | | 2 | 20/1 | EXIST | F/A RPS | 250 | | |
| | | 250 | F/A RPS | EXIST | 20/1 | 3 | | | | 4 | 20/1 | EXIST | F/A RPS | 250 | | |
| | | 250 | F/A RPS | EXIST | 20/1 | 5 | | | | 6 | 20/1 | EXIST | F/A RPS | 250 | | |
| | | 250 | F/A RPS | EXIST | 20/1 | 7 | | | | 8 | 20/1 | EXIST | GEN JACKET HTR | 1000 | | |
| | | 250 | GEN ANTI COND | EXIST | 20/1 | 9 | | | | 10 | 20/1 | EXIST | GEN JACKET HTR | 1000 | | |
| | | 250 | GEN BATTERY CHARGER | EXIST | 20/1 | 11 | | | | 12 | 20/1 | EXIST | FACP | 250 | | |
| | | 250 | SECURITY SYSTEM | EXIST | 20/1 | 13 | | | | 14 | 20/1 | EXIST | PA SYSTEM | 500 | | |
| 3 | E188 | 864 | REFRIGERATOR | 3–12 | 20/1 | 15 | | | | 16 | 25/3 | 3–10 | REFRIGERATION SYSTEM | 6192 | E103 | 4 |
| 3 | E188 | 864 | REFRIGERATOR | 3–12 | 20/1 | 17 | | | | 18 | – | +10G | – | – | | |
| 3 | E109 | 1428 | ICE MACHINE | 3–12 | 20/1 | 19 | | | | 20 | – | 3/4"C | – | – | | |
| 3 | E151 | 240 | HOOD ANSUL SYSTEMS | 3–12 | 20/1 | 21 | | | | 22 | 20/1EGF | 3–12 | COOLER DOOR HEATER/LTS | 600 | E102A | 4 |
| 3 | E102B | 600 | COOLER TEMP. ALARM | 3–12 | 20/1 | 23 | | | | 24 | 20/1EGF | 3–12 | FREEZER DOOR HEATER/LTS | 600 | E102A | 4 |
| 3 | E102C | 600 | COOLER PRESSURE PORT | 3–12 | 20/1 | 25 | | | | 26 | 20/1EGF | 3–12 | FREEZER DRAIN LINE HEATER | 600 | E103F | 4 |
| 3 | E102E | 120 | PANIC ALARM BUTTONS | 3–12 | 20/1 | 27 | | | | 28 | 20/2 | 2–10 | FREEZER COIL | 1893 | E103C | 4 |
| 3 | E103D | 216 | COOLER COIL | 3–12 | 20/1 | 29 | | | | 30 | – | +10G | – | – | | |
| 3 | E102B | 600 | FREEZER TEMP. ALARM | 3–12 | 20/1 | 31 | | | | 32 | 20/1 | | EXIST SPARE | | | |
| 3 | E102C | 600 | FREEZER PRESSURE PORT | 3–12 | 20/1 | 33 | | | | 34 | 20/1 | | EXIST SPARE | | | |
| | | | EXIST SPARE | | 20/1 | 35 | | | | 36 | 20/1 | | EXIST SPARE | | | |
| | | | EXIST SPARE | | 20/1 | 37 | | | | 38 | 30/3 | EXIST | SPD | 50 | | |
| | | | EXIST SPARE | | 20/1 | 39 | | | | 40 | – | – | – | – | | |
| | | | EXIST SPARE | | 20/1 | 41 | | | | 42 | – | – | – | – | | |
| | | TOTAL LOAD ❶ 100% = | 21317VA | | | TOTAL LOAD ❶ 100% = | | | | 59A | | | TOTAL LOAD ❶ 125% = | 74A | | |

1. THE EXISTING 100A FEEDER IS SUFFICIENT FOR THE REVISED LOAD.
2. UPDATE PANEL SCHEDULE TO MATCH REVISED EQUIPMENT DESCRIPTION.

GENERAL PANEL REQUIREMENTS:
A. REF ELECTRICAL FLOOR PLANS FOR PANEL LOCATIONS.
B. FIELD VERIFY EXISTING CIRCUITS PRIOR TO BEGINNING WORK.
C. ALL OUTAGES SHALL BE SCHEDULED AND CONFIRMED IN WRITING WITH THE OWNER A MINIMUM OF TWO WEEKS PRIOR TO ANY OUTAGE.
D. AT THE END OF THE PROJECT PROVIDE A NEW TYPEWRITTEN PANEL SCHEDULE USING BUILDING ROOM NUMBERS FOR ALL PANELS WITH CIRCUITS ADDED, REMOVED, OR MODIFIED AS PART OF THE PROJECT.

PANEL NOTES:
1. REVISE/REWORK WIRING/CONDUIT AS REQUIRED TO ADD/REMOVE DEVICES FROM EXISTING CIRCUIT.
2. EXISTING CIRCUIT TO BE DEMO.
3. REUSE EXISTING SPARE CB AND WIRE NEW CIRCUIT.
4. PROVIDE NEW CB & WIRE NEW CIRCUIT.
5. IDENTIFY ANY CIRCUITS OR PARTIAL CIRCUITS THAT EXTEND BEYOND THE AREA OF RENOVATION. PROVIDE TEMPORARY FEED TO MAINTAIN ALL CIRCUITS SERVING ELEMENTS/SPACES NOT TO BE REMOVED DURING CONSTRUCTION. RECONNECT EXISTING CIRCUITS/DEVICES TO REMAIN TO TEMPORARY KITCHEN PANEL ONCE AVAILABLE USING CB(S) PROVIDED. ALL PARTIAL CIRCUITS SHALL REMAIN AND REMAIN ACTIVE BOTH DURING AND AFTER CONSTRUCTION.
6. KITCHEN LIGHTS TO BE DUAL ZONES WIRED THROUGH LIGHTING CONTACTORS AND CONTROLLED ON/OFF BY THE BAS AND LOCAL LIGHTING SWITCHES.
7. EXTERIOR LIGHTS TO BE WIRED THROUGH LIGHTING CONTACTOR AND CONTROLLED ON/OFF BY THE BAS.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

0

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL

STATE OF TEXAS — GEORGE L. STANTON — 38582 — REGISTERED — PROFESSIONAL ENGINEER — 07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL SCHEMATIC

o-E.400


STANTON ENGINEERING GROUP
INFORMATION–ENGINEER | TECHNOLOGY FIRM REG NO. F–21833 | (713) 300–6080


© 2025 ALL RIGHTS RESERVED


12800 N. SAM HOUSTON PARKWAY E., SUITE 125, HOUSTON, TX 77060

# TECHNOLOGY SYMBOLS & LEGEND

## VOICE SYMBOLS

| | |
|---|---|
| | SINGLE VOICE OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| X | VOICE OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |
| | SINGLE VOICE OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED. |
| X | VOICE OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED, X = NUMBER OF CABLE TERMINATIONS PER LOCATION AS INDICATED. |
| | POWER/COMMUNICATIONS POLE WITH A SINGLE VOICE OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| X | POWER/COMMUNICATIONS POLE WITH X = NUMBER OF VOICE OUTLETS, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| | SINGLE VOICE OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE-THRU AS SPECIFIED. |
| X | VOICE OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE -THRU AS SPECIFIED WITH X = NUMBER OF VOICE TERMINATIONS PER LOCATION. |
| W | SINGLE VOICE OUTLET FOR WALL-MOUNTED PHONE, CABLE TYPE AS SPECIFIED, MOUNTED +52-INCHES A.F.F. UNLESS OTHERWISE NOTED. |

## DATA SYMBOLS

| | |
|---|---|
| | SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| X | DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |
| | SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED. |
| X | DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED, X = NUMBER OF CABLE TERMINATIONS PER LOCATION AS INDICATED. |
| | POWER/COMMUNICATIONS POLE WITH A SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| X | POWER/COMMUNICATIONS POLE WITH X = NUMBER OF DATA OUTLETS, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| | SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE-THRU AS SPECIFIED. |
| X | DATA OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE -THRU AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |
| W | SINGLE DATA OUTLET FOR WALL-MOUNTED IP PHONE, CABLE TYPE AS SPECIFIED, MOUNTED +52-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| X | DATA CABLE FOR COMPUTER ON WHEELS, CABLE TYPE AS SPECIFIED MOUNTED + 18-INCHES A.F.F UNLESS OTHERWISE NOTED. X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |
| X | DATA CABLE FOR CEILING MOUNTED WIRELESS ACCESS POINT, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A GREEN ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. |
| X | DATA CABLE FOR CEILING MOUNTED VIDEO SURVEILLANCE CAMERA, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A ORANGE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. REFER TO SECURITY DRAWINGS PRIOR TO INSTALLATION. |
| | DATA CABLE FOR CEILING MOUNTED PROJECTOR, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A BLUE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. REFER TO AUDIO/VISUAL DRAWINGS PRIOR TO INSTALLATION. |
| X | DATA CABLE FOR CEILING MOUNTED AUDIO/VISUAL EQUIPMENT ENCLOSURE, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A BLUE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. REFER TO AUDIO/VISUAL DRAWINGS PRIOR TO INSTALLATION. |
| X | DATA CABLE FOR WALL MOUNTED PROJECTOR, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A BLUE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. REFER TO AUDIO/VISUAL DRAWINGS PRIOR TO INSTALLATION. |

## DATA SYMBOLS, CONT.

| | |
|---|---|
| X CAME | DATA CABLE FOR EXTERIOR WALL MOUNTED VIDEO SURVEILLANCE CAMERA, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A ORANGE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW, REFER TO SECURITY DRAWINGS PRIOR TO INSTALLATION. |
| X CAMW | DATA CABLE FOR INTERIOR WALL MOUNTED SURVEILLANCE CAMERA, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A ORANGE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. |
| X CAME | DATA CABLE FOR EXTERIOR WALL MOUNTED SURVEILLANCE CAMERA, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A ORANGE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. |
| X WAPW | DATA CABLE FOR INTERIOR WALL MOUNTED WIRELESS ACCESS POINT, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A GREEN ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. |
| X WAPE | DATA CABLE FOR EXTERIOR WALL MOUNTED WIRELESS ACCESS POINT, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A GREEN ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. |

## CABLE PLANT & RISER DIAGRAM

| | |
|---|---|
| | MAINTENANCE HOLE, SIZE & TYPE AS SPECIFIED. |
| | PULLBOX, SIZE AND TYPE AS SPECIFIED. |
| UGC | DIRECT BURIED COMMUNICATIONS, CABLE TYPE AS SPECIFIED. |
| AER | AERIAL COMMUNICATIONS, CABLE TYPE AS SPECIFIED. |
| | CONDUIT, SIZE AND TYPE AS SPECIFIED. |

## VOICE/DATA SYMBOLS

| | |
|---|---|
| | SINGLE VOICE & SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| X Y | VOICE & DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. X = NUMBER OF VOICE TERMINATIONS , Y = NUMBER OF DATA TERMINATIONS PER LOCATION. |
| | SINGLE VOICE & SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED. |
| X Y | VOICE & DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED, X = NUMBER OF VOICE OUTLETS AND Y = NUMBER OF DATA OUTLETS PER LOCATION AS INDICATED. |
| | POWER/COMMUNICATIONS POLE WITH A SINGLE VOICE OUTLET AND SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| X Y | POWER/COMMUNICATIONS POLE WITH X = NUMBER OF VOICE TERMINATIONS, Y = NUMBER OF DATA TERMINATIONS, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| | SINGLE VOICE OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE-THRU AS SPECIFIED. |
| X Y | VOICE OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE -THRU AS SPECIFIED WITH X = NUMBER OF VOICE TERMINATIONS, Y = NUMBER OF DATA TERMINATIONS PER LOCATION. |

## FIBER OPTIC SYMBOLS

| | |
|---|---|
| | SINGLE FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| X | FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |
| | SINGLE FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED. |
| X | FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED, X = NUMBER OF CABLE TERMINATIONS PER LOCATION AS INDICATED. |
| | POWER/COMMUNICATIONS POLE WITH A SINGLE FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| X | POWER/COMMUNICATIONS POLE WITH X = NUMBER OF FIBER OPTIC OUTLETS, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| | SINGLE FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE-THRU AS SPECIFIED. |
| X | FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE -THRU AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |

## ROUGH-IN & MISC. SYMBOLS

| | |
|---|---|
| R | ROUGH-IN LOCATION, INFRASTRUCTURE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| R | ROUGH-IN LOCATION, INFRASTRUCTURE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED. |
| R | POWER POLE WITH ROUGH-IN LOCATION, INFRASTRUCTURE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| R | ROUGH-IN LOCATION. TERMINATED IN FLOOR BOX/POKE-THRU AS SPECIFIED. |
| WAP | WIRELESS ACCESS POINT. EQUIPMENT AS SPECIFIED. |

## GENERAL SYMBOLS

| | |
|---|---|
| # SHEET — DRAWING TITLE SCALE: SCALE | DRAWING TITLE CALLOUT, # = DETAIL NUMBER. |
| # SHEET | DETAIL CALLOUT, # = DETAIL NUMBER. |
| # SHEET | SECTION CALLOUT, # = DETAIL NUMBER. |
| SHEET # | ELEVATION CALLOUT, # = DETAIL NUMBER. |
| # | KEYED NOTE, # = KEYED NOTE NUMBER. |
| # | REVISION TRIANGLE, # = REVISION NUMBER (PER SHEET). |
| TR (IDF XXX) | INDICATES TELECOMMUNICATIONS REGION |

## ABBREVIATIONS

| | |
|---|---|
| A.F.F. | ABOVE FINISHED FLOOR |
| A.F.G. | ABOVE FINISHED GRADE |
| AER | AERIAL |
| DEMARC | DEMARCATION POINT |
| EMT | ELECTRIC METALLIC TUBE |
| F.O.C. | FIBER OPTIC CABLE |
| GIP | GALVANIZED IRON PIPE |
| HE | PAINTERCOM HEAD-END |
| IMC | INTERMEDIATE METAL CONDUIT |
| ISP | INSIDE CABLE PLANT |
| IDF | INTERMEDIATE DISTRIBUTION FRAME |
| MDF | MAIN DISTRIBUTION FRAME |
| MH | MAINTENANCE HOLE |
| MM | MULTIMODE |
| OSP | OUTSIDE CABLE PLANT |
| PB | PULLBOX |
| PR | PAIR |
| PVC | POLYVINYL CHLORIDE |
| RSC | RIGID STEEL CONDUIT |
| SM | SINGLE MODE |
| SP | SERVICE PROVIDER |
| STP | SHIELDED TWISTED PAIR |
| TB | TERMINAL BLOCK |
| TR | TELECOMMUNICATION REGION |
| UGC | UNDERGROUND COMMUNICATION |
| UON | UNLESS OTHERWISE NOTED |
| UTP | UNSHIELDED TWISTED PAIR |

## NOTES

1. CONTRACTOR SHALL REVIEW DRAWINGS AND SPECIFICATIONS THAT MAKE UP THE CONTRACT DOCUMENTS AND COMPLETE ALL WORK INCLUDED THEREIN.
2. SCALE OF TECHNOLOGY DRAWINGS IS PROVIDED FOR REFERENCE ONLY. CONTRACTOR SHALL BE RESPONSIBLE FOR PROPER CABLE LENGTHS, SIZE OF PATHWAYS, DIMENSIONS, ETC.
3. TECHNOLOGY DRAWINGS SHALL BE USED TO COMPLEMENT THE WRITTEN SPECIFICATIONS.
4. ANY DISCREPANCY OR CONFLICT WITHIN OR BETWEEN THE DRAWINGS AND SPECIFICATIONS SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT/DESIGN CONSULTANT'S. DISCREPANCIES OR CONFLICTS NOT BROUGHT TO THE ATTENTION OF THE ARCHITECT/DESIGN CONSULTANT AND SUBSEQUENTLY CLARIFIED DURING THE BIDDING OF THE PROJECT WILL BE DEEMED TO HAVE BEEN BID OR PROPOSED IN THE MORE COSTLY OR DIFFICULT MANNER, AND THE BETTER QUALITY OR GREATER QUANTITY OF WORK SHALL BE PROVIDED BY THE CONTRACTOR IN ACCORDANCE WITH THE ARCHITECT'S/DESIGN CONSULTANT'S INTERPRETATION.

## INDEX OF DRAWINGS


o-T000 TECHNOLOGY SYMBOLS & LEGEND
o-T0201 TECHNOLOGY DEMOLITION FLOOR PLAN
o-T200 TECHNOLOGY COMPOSITE FLOOR PLAN
o-T201 TECHNOLOGY NEW/RENOVATION KITCHEN PLAN
o-T202 TECHNOLOGY TEMPORARY KITCHEN PLAN
o-T300 TECHNOLOGY ENLARGED VIEWS
o-T400 TECHNOLOGY TYPICAL DETAILS
o-T401 TECHNOLOGY TYPICAL DETAILS
o-T500 TECHNOLOGY TYPICAL DETAILS


ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

O

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
BICSI
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD

07/18/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY SYMBOLS & LEGEND

SHEET NO.
o-T000




1 o-T200 TECHNOLOGY COMPOSITE FLOOR PLAN
1/16" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

O

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD


07/18/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY COMPOSITE FLOOR PLAN

SHEET NO.
o-T200




1 / o-T201 TECHNOLOGY NEW/RENOVATION KITCHEN PLAN
1/4" = 1'-0"

**TECHNOLOGY FLOOR PLANS GENRAL NOTES:**

1. THE TECHNOLOGY REGION / WIRING BOUNDARIES ARE IDENTIFIED ON THE OVERALL SHEETS ONLY AND NOT ON THE ENLARGED SHEETS. CONTRACTOR SHALL REFER TO THE OVERALL SHEETS FOR ALL TECHNOLOGY REGIONS / WIRING BOUNDARIES.
2. ALL CONDUIT PATHWAYS, ROUGH-INS, BACKBOXES, FLOOR BOXES, CONDUIT SLEEVES, ETC. INDICATED ON THE TECHNOLOGY DRAWINGS ARE TO BE PROVIDED AND INSTALLED BY DIVISION 26.
3. ALL POWER INDICATED ON THE TECHNOLOGY DRAWINGS IS TO BE PROVIDED AND INSTALLED BY DIVISION 26.
4. CONTRACTOR SHALL RESTORE ALL PENETRATIONS PROVIDED THROUGH FIRE RATED WALLS/STRUCTURES FOR TECHNOLOGY CABLING BACK TO THE ORIGINAL RATING.
5. CONTRACTOR SHALL RESTORE ALL PENETRATIONS PROVIDED THROUGH NON-RATED WALLS/STRUCTURES FOR TECHNOLOGY CABLING FOR SOUND TO REDUCE NOISE TRAVELING THROUGH PENETRATIONS.
6. TECHNOLOGY CABLING SHALL BE ROUTED IN SEPARATE PATHWAYS IN J-HOOKS, CONDUITS, CONDUIT SLEEVES, CORES, ETC. THROUGHOUT THE ENTIRE PATHWAY. DIFFERENT MEDIA TYPES (DATA, VIDEO, SECURITY, ETC.) SHALL NOT SHARE THE SAME J-HOOK, CONDUIT, CONDUIT SLEEVE, CORE, ETC.
7. UNLESS NOTED OTHERWISE, ALL CONDUITS FOR TECHNOLOGY DEVICES SHALL ROUTE FROM THE DEVICE LOCATION AND TERMINATE ABOVE AN ACCESSIBLE CEILING (AN OPEN CEILING OR CLOUD TYPE CEILING IS NOT CONSIDERED AN ACCESSIBLE CEILING) IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF A MAIN CORRIDOR OR NEAREST MDF/IDF. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF / IDF ROOM TO MINIMIZE THE CABLE LENGTH ENSURING CABLE LENGTH DOES NOT EXCEED 275 FEET.
8. UNLESS NOTED OTHERWISE ALL CONDUITS SHALL BE HOMERUN FROM THE DEVICE LOCATION AND NO DAISY CHAINING OF DEVICES/ ROUGH-INS SHALL BE ALLOWED.
9. CONDUIT SEGMENTS SHALL BE NO MORE THAN 100-FEET IN LENGTH WITH NO MORE THAN THE EQUIVALENT OF (2) 90 DEGREE BENDS BETWEEN PULLING POINTS.
10. CONDUITS SHALL MAINTAIN A BEND RADIUS OF 6 TIMES THE DIAMETER OF THE CONDUIT FOR CONDUITS 2-INCHES OR SMALLER AND 10 TIMES THE DIAMETER OF THE CONDUIT FOR CONDUITS GREATER THAN 2-INCHES.
11. ALL CONDUITS SHALL HAVE A PULL STRING INSTALLED FOR PULLING OF CABLE. CLEARLY LABEL AS "PULL STRING" INDICATING OPPOSITE END LOCATION.
12. ALL SPARE CONDUITS OR CONDUITS FILLED WITH LESS THAN THE MAXIMUM ALLOWED FILL RATIO SHALL HAVE A PULL STRING INSTALLED AND LEFT FOR FUTURE PULLING OF CABLE. CLEARLY LABEL AS "PULL STRING" INDICATING OPPOSITE END LOCATION.
13. EQUIPMENT NOT RELATED TO THE SUPPORT OF THE TELECOMMUNICATIONS ROOM (E.G., PIPING, DUCTWORK, PNEUMATIC TUBING) SHALL NOT BE INSTALLED IN, PASS THROUGH, OR ENTER THE TELECOMMUNICATIONS ROOM.
14. ALL CONDUITS FOR TECHNOLOGY DEVICES SHALL ROUTE FROM THE DEVICE LOCATION AND TERMINATE ABOVE A LAY-IN TYPE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE A LAY- IN TYPE CEILING TO PREVENT THE CABLES FROM BEING EXPOSED, THE CONDUIT SHALL ROUTE TO THE NEAREST LAY-IN TYPE CEILING OFF A MAIN CORRIDOR OR NEAREST MDF/IDF. THE CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE MAIN CORRIDOR OR NEAREST MDF/IDF TO MINIMIZE THE CABLE LENGTH ENSURING THE CABLE LENGTH DOES NOT EXCEED 275 FEET. CONDUIT, CONNECTIONS, J-BOXES, SUSPENSION, ANCHORAGES, AND OTHER CONDUIT COMPONENTS EXPOSED TO VIEW IN PUBLIC SPACES SHALL BE ROUTED AND INSTALLED CAREFULLY TO MINIMIZE VISUAL IMPACT AND SHALL BE FULLY PAINTED TO MATCH UNLESS NOTED OTHERWISE.
15. CONDUIT(S) INSTALLED IN-SLAB OR UNDER-SLAB TO FLOOR BOXES, POKE-THURS, AND TO WORKAREA OUTLETS, ETC. SHALL BE INSTALLED WITH WET RATED CABLE(S).
16. NO GRID WIRE SHALL BE UTILIZED FOR SUPPORTS ONLY USE SOLID SUPPORTS (CLIPS, ALL-THREAD, ANCHORS, ETC.).

**TECHNOLOGY PLAN KEYED NOTES**

**NOT ALL KEYED BELOW APPLY TO THIS SHEET**

(1) DATA CABLE FOR CONTRACTOR FURNISHED / CONTRACTOR INSTALLED MENU BOARD. REFERENCE ARCHITECTURAL AND FOOD SERVICE DRAWINGS FOR MOUNTING HEIGHT AND ADDITIONAL INFORMATION. BUILDING POWER ADJACENT TO DATA RECEPTACLE IS REQUIRED.

(2) INDOOR / OUTDOOR RATED DATA CABLE FOR POINT OF SALE LOCATION. PROVIDE (1) 1-INCH CONDUIT FOR DATA TO THE WALL BEHIND POINT OF SALE LOCATION AND UP WALL TO ABOVE ACCESSIBLE CEILING. CONDUITS SHALL TERMINATE INSIDE A DOUBLE GANG BOX THAT IS SECURED TO THE POINT OF SALE LOCATION. REFER TO FOOD SERVICE / KITCHEN DRAWINGS FOR EXACT LOCATION AND CONDUIT ROUGH-IN REQUIREMENTS.

(3) DATA CABLE FOR TEMPERATURE MONITORING OF FREEZER COOLER. REFER TO FOOD SERVICE / KITCHEN DRAWINGS FOR EXACT LOCATION AND CONDUIT ROUGH-IN REQUIREMENTS AND TERMINATION POINT AND CONNECTIVITY NEEDS IN FREEZER / COOLER CONTROL UNIT.

(4) DATA CABLE FOR TEMPORARY POINT OF SALES CASH REGISTER. COORDINATE WITH OWNER, ARCHITECT, AND CONSULTANT FOR ROUTING OF CABLES TO POINT OF SALE CASH REGISTER PRIOR TO INSTALLATION

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

O

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD


07/18/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY NEW/RENOVATION KITCHEN PLAN

SHEET NO.
o-T201




1 / e-T202 TECHNOLOGY TEMPORARY KITCHEN FLOOR PLAN
1/4" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

0

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD


07/18/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY TEMPORARY KITCHEN PLAN

SHEET NO.
o-T202




1 o-T300 PALMER ES EXISTING WALL MOUNTED IDF RACK
N.T.S




2 o-T300 PALMER ES EXISTING WALL MOUNTED IDF RACK - PANEL DETAIL
N.T.S

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

0

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD

07/18/2025

MWA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING


TECHNOLOGY ENLARGED VIEWS

SHEET NO.
o-T300

NOTE TO CONTRACTOR:

UNLESS OTHERWISE NOTED, LOW VOLTAGE CABLING SHALL BE INSTALLED WITHIN 6-INCHES OF THE CEILING AND ACCESSIBLE BY A TECHNICIAN ON A STANDARD A-FRAME LADDER.

CONTRACTOR SHALL MAINTAIN AT LEAST 6-INCHES OF SEPRATION BETWEEN CABLING BUNDLES AND MECHANICAL DUCTWORKS, EQUIPMENT, PIPIING OR OTHER SYSTEMS IN THE CEILING PLENUM.





KEYED NOTES:

1. J-HOOK WITH RETAINER CLIP ABOVE ACCESSIBLE CEILING (BY DIV 27).
2. DATA CABLE ABOVE ACCESSIBLE CEILING (BY DIV 27).
3. A/V CABLE ABOVE ACCESSIBLE CEILING (BY DIV 27).
4. SECURITY CABLE ABOVE ACCESSIBLE CEILING (BY DIV 28).
5. SPARE J-HOOK (BY DIV 27).

## 1 T400 TYPICAL J-HOOK CABLE PATHWAY

SCALE: N.T.S.





KEYED NOTES:

1. SCHEDULED FLOOR OR DECK.
2. CONDUIT SLEEVE (BY DIV 26).
3. NYLON BUSHING (BY DIV 26).

## 2 T400 TYPICAL CONDUIT SLEEVE THROUGH FLOOR OR DECK DETAIL

SCALE: N.T.S.





KEYED NOTES:

1. SCHEDULED WALL.
2. SCHEDULED CEILING.
3. CONDUIT SLEEVE (BY DIV 26).
4. NYLON BUSHING (BY DIV 26).

## 3 T400 TYPICAL CONDUIT SLEEVE GOING THROUGH WALL

SCALE: N.T.S.





KEYED NOTES:

1. SCHEDULED WALL.
2. SCHEDULED CEILING.
3. SCHEDULED DECK ABOVE.
4. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX WITH DOUBLE GANG PLASTER RING (BY DIV 26).
5. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH. (BY DIV 26).

## 4 T400 TYPICAL TECHNOLOGY CONDUIT ROUGH-IN

SCALE: N.T.S.





KEYED NOTES:

1. SCHEDULED STUD.
2. SCHEDULED WALL.
3. J-HOOK WITH RETAINER CLIP ABOVE ACCESSIBLE CEILING (BY DIV 27).
4. DATA CABLE ABOVE ACCESSIBLE CEILING (BY DIV 27).
5. 20 FOOT SERVICE LOOP ABOVE ACCESSIBLE CEILING NEATLY COILED AND SECURED TO J-HOOK (BY DIV 27).
6. SURFACE MOUNT BOX ABOVE ACCESSIBLE CEILING SECURED TO BUILDING STRUCTURE (BY DIV 27).
7. DATA INSTER (BY DIV 27).

## 5 T400 TYPICAL ABOVE CEILING SINGLE DATA OUTLET (WALL MOUNTED)

SCALE: N.T.S.





KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH PHONE STUDS (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. CABLE AS SPECIFIED (BY DIV 27).

## 6 T400 TYPICAL WALL PHONE OUTLET CONFIGURATION

SCALE: N.T.S.





KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH DESIGNATION IN WINDOW (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. CABLE AS SPECIFIED (BY DIV 27).
7. ELECTRICAL RECEPTACLE, GANG BOX AND CONDUIT SHOWN FOR REFERENCE ONLY (REFER TO DIV 26).

## 7 T400 TYPICAL DUAL DATA OUTLET CONFIGURATION

SCALE: N.T.S.





KEYED NOTES:

1. 4 11/16-INCH X 4 11/16-INCH X 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. DOUBLE GANG PLASTER RING (BY DIV 26).
4. SURFACE MOUNT BOX INSIDE THE 4 11/16-INCH X 4 11/16-INCH X 2 1/8-INCH DOUBLE GANG BOX (BY DIV 27).
5. RJ-45 INSERT (BY DIV 27).

## 8 T400 TYPICAL WALL-MOUNTED WIRELESS ACCESS POINT

SCALE: N.T.S.




KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH DESIGNATION IN WINDOW (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. BLANK INSERT (BY DIV 27).
7. CABLE AS SPECIFIED (BY DIV 27).
8. ELECTRICAL RECEPTACLE, GANG BOX AND CONDUIT SHOWN FOR REFERENCE ONLY (REFER TO DIV 26).

## 9 T400 TYPICAL THREE DATA OUTLET CONFIGURATION

SCALE: N.T.S.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

O

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD


07/18/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY TYPICAL DETAILS

SHEET NO.
o-T400





KEYED NOTES:

1. ALL THREAD TO BUILDING STRUCTURE (BY DIV. 27)
2. SCHEDULING CEILING
3. IN-PLENUM CEILING BRACKET PN 49223-CBC ATTACHED TO ALL THREAD (BY DIV. 27)
4. SURFACE MOUNT BOX ABOVE ACCESSIBLE CEILING SECURED TO BRACKET (BY DIV. 27)
5. DATA CABLE (BY DIV. 27)
6. DATA INSERT (BY DIV. 27)

## 1 / T401 TYPICAL ABOVE CEILING DATA OUTLET

SCALE: N.T.S.





KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH DESIGNATION IN WINDOW (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. CABLE AS SPECIFIED (BY DIV 27).
7. ELECTRICAL RECEPTACLE, GANG BOX AND CONDUIT SHOWN FOR REFERENCE ONLY (REFER TO DIV 26). ELECTRICAL RECEPTACLE TO BE INSTALLED AT 36" A.F.F AND ADJACENT TO COW / SECONDARY TEACHING OUTLET LOCATION.

## 2 / T401 TYPICAL COW / SECONDARY TEACHER'S DATA OUTLET CONFIGURATION

SCALE: N.T.S.





KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH DESIGNATION IN WINDOW (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. BLANK INSERT (BY DIV 27).
7. CABLE AS SPECIFIED (BY DIV 27).
8. ELECTRICAL RECEPTACLE, GANG BOX AND CONDUIT SHOWN FOR REFERENCE ONLY (REFER TO DIV 26).

## 3 / T401 TYPICAL THREE DATA OUTLET CONFIGURATION

SCALE: N.T.S.




KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH DESIGNATION IN WINDOW (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. CABLE AS SPECIFIED (BY DIV 27).
7. ELECTRICAL RECEPTACLE, GANG BOX AND CONDUIT SHOWN FOR REFERENCE ONLY (REFER TO DIV 26).

## 4 / T401 TYPICAL FOUR DATA OUTLET CONFIGURATION


SCALE: N.T.S.

| TBB/GE CONDUCTOR SIZING | |
|---|---|
| LENGTH IN LINEAR M (FT) | SIZE (AWG) |
| LESS THAN 4 (13) | 6 |
| 4 - 6 (14-20) | 4 |
| 6 - 8 (21 - 26) | 3 |
| 8 - 10 (27 - 33) | 2 |
| 10 - 13 (34 - 41) | 1 |
| 13 - 16 (42 - 52) | 1/0 |
| 16 - 20 (53 - 66) | 2/0 |
| 20 - 26 (67 - 84) | 3/0 |
| 26 - 32 (85 - 105) | 4/0 |
| 32 - 38 (106 - 125) | 250 kcmil |
| 38 - 46 (126 - 150) | 300 kcmil |
| 46 - 53 (151 - 175) | 350 kcmil |
| 53 - 76 (176 - 250) | 500 kcmil |
| 76 - 91 (251 - 300) | 600 kcmil |
| GREATER THAN 91 (301) | 750 kcmil |

ROUTE THE TBB TO EACH TGB IN AS STRAIGHT A PATH AS POSSIBLE. THE TBB SHOULD BE INSTALLED AS A CONTINUOUS CONDUCTOR, AVOIDING SPLICES WHERE POSSIBLE.

## 5 / T401 TBB CONDUCTOR SIZING

SCALE: N.T.S.





1. TELECOMMUNICATIONS MAIN GROUNDING BUS BAR (PBB)(BY DIV. 27)
2. TELECOMMUNICATIONS GROUNDING BUS BAR (SBB)(BY DIV 27)
3. TELECOMMUNICATIONS BONDING CONDUCTOR (TBC). REFER TO CONDUCTOR SIZING CHART FOR EXACT SIZE REQUIREMENTS (BY DIV 27)
4. CONNECT TO GROUNDED BUILDING STEEL WHEN EXPOSED IN ROOM.
5. TELECOMMUNICATIONS BONDING BACKBONE (TBB). REFER TO CONDUCTOR SIZING CHART FOR EXACT SIZE REQUIREMENTS (BY DIV 26)
6. TELECOMMUNICATIONS BONDING CONDUCTOR (TBC). BY ELECTRICAL CONTRACTOR.REFER TO CONDUCTOR SIZING CHART FOR EXACT SIZE REQUIREMENTS.
7. GROUNDING EQUALIZER CONDUCTOR (GEC)(BY DIV 26)
8. BOUND WITH GROUDING COLLARS TO EACH CONTINUOUS CONDUIT THAT ENTERS THE TELECOM ROOM. (BY DIV 26).
9. BOND TO EACH ACCESS CONTROL PANEL AND OTHER SECURITY PANELS IN HE TELECOM ROOM. (BY DIV 27)

## 6 / T401 TYPICAL GROUNDING DIAGRAM

SCALE: N.T.S.

System No. W-L-3218
F Ratings - 1, 2, 3 and 4 Hr (See Items 1 and 3)
T Ratings - 3/4 and 1 Hr (See Item 3)
L Rating At Ambient - Less Than 1, 1.3, 4 or 7 CFM (See Item 3)
L Rating At 400 F - Less Than 1, 2 or 3 CFM (See Item 3)




1. Wall Assembly - The 1, 2, 3 or 4 hr fire-rated gypsum board/stud wall assembly shall be constructed of the materials and in the manner described within the individual U300, U400 or V400 Series Wall and Partition Designs in the UL Fire Resistance Directory and shall incorporate the following construction features:
   A. Studs - Wall framing shall consist of either wood studs or steel channel studs. Wood studs to consist of nom 2 by 4 in. (51 by 102 mm) lumber spaced max 16 in. (406 mm) OC. Steel studs to be min 3-1/2 in. (89 mm) wide and spaced max 24 in. (610 mm) OC.
   B. Gypsum Board* - Thickness, type, number of layers and fasteners as specified in the individual Wall and Partition Design. Opening in gypsum board to be max 1/4 in. (6 mm) larger then width and height dimensions of firestop device(s).

   The hourly F Rating of the firestop system is dependent upon the hourly rating of the wall in which it is installed.
2. Firestop Device* - One, two, three, four or seven firestop device modules ganged together. Each firestop device module consists of a 3 by 3 by 10-1/2 in. (76 by 76 by 267 mm) long galv steel tube with an intumescent material lining. Firestop device modules to be installed in accordance with the accompanying installation instructions. The space between the firestop device module(s) and the periphery of the opening shall be min 0 in. ( 0 mm, point contact) to max 1/8 in. (3.2 mm). In round openings, the space between the firestop device and the periphery of the opening shall be min 0 in. (point contact) to max 1/2 in. (13 mm). Firestop device module(s) secured in place by means of steel wall plates installed with gasketing material supplied with product. Steel wall plates installed on both sides of wall and secured to each device by means of steel set screws provided with device. Each four- and seven-gang steel wall plate shall be fastened to the studs with steel screws sized to extend through the gypsum board layers and penetrate 1/2 in. (13 mm) into the framing member. Each firestop device module is to be installed with ends projecting an equal distance beyond each surface of the wall assembly.

   As an alternate, the four- and seven-gang steel wall plates may be installed directly against the studs for walls having 16 and 24 in. (406 and 610 mm) center-to-center stud spacing, respectively, prior to installation of the gypsum board layers. The steel wall plates shall be secured to the stud by means of steel screws. After installation of the steel wall plates and firestop device modules, the gypsum board shall be installed as specified in the individual U300 or U400 Design with a maximum 1/8 in. (3.2 mm) gap between the firestop device module and the cutout in the gypsum board. Gap between the firestop device module and the cutout in the gypsum board may be filled with gypsum joint compound or fill material (Item 4).

   SPECIFIED TECHNOLOGIES INC - EZ PATH Series 33 Fire Rated Pathway

2A. Firestop Device* - Extension Module - (Optional, Not Shown) - Module attached to ends of 3 by 3 by 10-1/2 in. (76 by 76 by 267 mm) long firestop device (Item 3) to increase its length to facilitate installation in thicker walls. Each module consists of a 3 by 3 by 6 in. (76 by 76 by 152 mm) long galv steel tube with an intumescent material lining. Extension module to be installed in accordance with the accompanying installation instructions. When module is used, firestop device (Item 2) and extension module(s) secured in place by means of steel wall plates installed with gasketing material supplied with product. Steel wall plates installed on both sides of wall and secured to each device or extension module(s) by means of steel set screws provided with wall plates. Firestop device and extension module(s) assembly to be installed with ends projecting an equal distance beyond each surface of the wall assembly.

   SPECIFIED TECHNOLOGIES INC - EZ PATH Extension

3. Cables - Within the loading area for each firestop device module, the cables may represent a 0 to 100 percent visual fill. Cable fill to be distributed at a uniform height across the width of the firestop device module. Cables to be rigidly supported on both sides of the wall assembly. Any combination of the following types of cables may be used:
   A. Max 400 pair No. 24 AWG (or smaller) copper conductor telecommunication cable with polyvinyl chloride (PVC) jacketing and insulation.
   B. Max 350 kcmil single copper conductor power cable with XLPE jacket and insulation
   C. Max 7/C No. 12 AWG copper conductor control cable with PVC or XLPE jacket and insulation.
   D. Max 3/C No. 10 AWG metal clad or armored cable with steel or aluminum jacket.
   E. Max 3/C No. 8 AWG NM cable (Romex) with PVC insulation and jacket.
   F. Max four pair No. 22 AWG (or smaller) copper conductor data cable with PVC or plenum rated jacketing and insulation.
   G. Max RG/U coaxial cable with fluorinated ethylene insulation and jacketing.
   H. Fiber optic cable with PVC or polyethylene (PE) jacket and insulation having a max diam of 5/8 in. (16 mm).
   I. Optical Fiber Raceway+ - Max 1-1/2 in. (38 mm) diam (or smaller) optical fiber raceway ("innerduct") formed of either PVC or polyvinylidene fluoride (PVDF) with optical fiber cable fill. Raceways installed in accordance with the National Electrical Code (NFPA 70).

   When the hourly rating of the wall assembly is 1 hr, the T Rating is 3/4 hr. When the hourly fire rating of the wall assembly is greater than 1 hr, the T Rating is 3/4 hr when Item 3A, 3B, 3C, 3D or 3E is used. Otherwise the T Rating is 1 hr. When Item 3A, 3B, 3C, 3D or 3E is used, the maximum F Rating is 2 hr. When max 200 pair No. 24 AWG telecommunication cable is used or when Item 3F, 3G, 3H or 3I is used, the maximum F Rating is 4 hr.

   The L Rating for each empty firestop device module is less than 1 cfm at ambient and at 400F. When Item 3A is used, the L Rating for each firestop device module with 100 percent visual fill is 4 cfm at ambient and 3 cfm at 400F. When Item 3F is used, the L Rating for each firestop device module with 100 percent visual fill is 1.3 cfm at ambient and 1 cfm at 400F. When Item 3G or 3H is used, the L Rating for each firestop device module with 100 percent visual fill is 7 cfm at ambient and 2 cfm at 400F.
4. Fill, Void or Cavity Material* - Sealant or Putty - (Not Shown) - As an alternate to gypsum joint compound, the gap between the firestop device module and the cutout in the gypsum board may be sealed with fill material on each side of the wall assembly when four- and seven-gang steel wall plates are installed directly against the wood or steel studs.

   SPECIFIED TECHNOLOGIES INC - SpecSeal Series SSS Sealant, SpecSeal LCI Sealant, SpecSeal Putty

   *Bearing the UL Classification Mark

## 7 / T401 TYPICAL STI EZ-PATH SLEEVE DETAIL

SCALE: N.T.S.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

O

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD


07/18/2025



ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY TYPICAL DETAILS

SHEET NO.
o-T401













1 T500 TYPICAL HORIZONTAL DATA CABLE LABELING SCHEME

SCALE: N.T.S.






2 T500 TYPICAL FIBER BACKBONE LABELING SCHEME

SCALE: N.T.S.




3 T500 TYPICAL COPPER BACKBONE LABELING SCHEME

SCALE: N.T.S.




4 T500 ABOVE ASSESSIBLE CEILING LABELING SCHEME

SCALE: N.T.S.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

O

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PALMER ELEMENTARY SCHOOL
4208 CROW VALLEY DRIVE
MISSOURI CITY, TX 77459

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD

07/18/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY TYPICAL DETAILS

SHEET NO.
o-T500

## AUDIO/VISUAL MULTIMEDIA LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| A## V## | WALL AV ROUGH-IN DETAIL |
| A## V## | CEILING AV ROUGH-IN DETAIL |
| A## V## | FLOOR AV ROUGH-IN DETAIL |
| IWB IWB | INTERACTIVE WHITE BOARD - WALL - CEILING |
| PJ PJ | MULTIMEDIA PROJECTOR |
| FP# FP# | MULTIMEDIA FLAT PANEL DISPLAY |
| S S | LOUDSPEAKER, WALL MOUNTED AND CEILING MOUNTED RESPECTIVELY - # INDICATES TYPE |
| CP# | CONTROL PANEL |
| TP# | TOUCH PANEL |
| M | MICROPHONE, CEILING MOUNTED - # INDICATES TYPE |
| VC | VOLUME CONTROL |
| WB | WALL BOX ENCLOSURE |
| D1 A1 | D1 = DIGITAL SINGLE SIDED CLOCK / A1 = ANALOG SINGLE SIDED CLOCK |
| D2 A2 | D2 = DIGITAL DOUBLE SIDED CLOCK / A2 = ANALOG DOUBLE SIDED CLOCK |
| ENC | CEILING AV ENCLOSURE |
| C C | PRESENTATION CAMERA - CEILING - WALL MOUNTED |

## PREMISE SECURITY LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| CR | CARD READER |
| CR M | CARD READER MULLION |
| KP | INTRUSION DETECTION KEYPAD |
| IC | INTERCOM (1 DATA CABLE) |
| IC MS | INTERCOM MASTER STATION (1 DATA CABLE) |
| PB | PANIC/DURESS BUTTON |
| LD | LOCK DOWN BUTTON |
| MD | MOTION DETECTOR |
| GB | ACCOUSTICAL GLASS BREAK SENSOR |
| BM | BIOMETRIC READER |
| RX | REQUEST TO EXIT - SURFACE PIR |
| KS | KEY SWITCH |
| LA | LOCAL ALARM SOUNDER |
| RG | RED/GREEN INDICATOR LIGHT |
| DB | DOORBELL |
| DH | MAGNETIC DOOR HOLD |
| DR | DOOR RELEASE |
| RX | REQUEST TO EXIT - INTEGRAL TO DOOR HARDWARE |
| DC | DOOR CONTACT / MONITOR |
| ES EL EH | ELECTRIFIED STRIKE - ELECTRIFIED LATCH - ELECTRIFIED HARDWARE (REFER TO SCHEDULES) |
| C C | STANDARD IP SURVEILLANCE CAMERA, (1) CABLE |
| C C C | 180° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° FISHEYE LENS CAMERA |
| IR | IR ILLUMINATOR |

## STRUCTURED CABLING LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF DATA CABLE(S)/JACK(S) |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) |
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| W | WALL MOUNT PHONE (1 CABLE/JACK) |
| W | WALL MOUNT PHONE, SURFACE MOUNT (1 CABLE/JACK) |
| # | FLOOR MOUNTED OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| #/# | FLOOR MOUNTED OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| # | CEILING MOUNTED DATA OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) |
| AP# | CEILING MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| AP# | WALL MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| | CABLING SLEEVE(S) |
| | TYPICAL LADDER RACK |
| | TYPICAL CABLE TRAY, BASKET STYLE |

## GENERAL ANNOTATION LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| MER | MAIN EQUIPMENT ROOM |
| TR | TELECOMMUNICATION ROOM |
| MDF | MAIN DISTRIBUTION FRAME |
| IDF | INTERMEDIATE DISTRIBUTION FRAME |
| ETR | EXISTING TO REMAIN |
| PBO | PROVIDED BY OTHERS |
| AFF | ABOVE FINISHED FLOOR |
| AFG | ABOVE FINISHED GRADE |
| AC | ABOVE COUNTER |
| EC | ELECTRICAL CONTRACTOR |
| PSC | PREMISE SECURITY CONTRACTOR |
| SCC | STRUCTURAL CABLING CONTRACTOR |
| AVC | AV/MULTIMEDIA CONTRACTOR |
| UNO | UNLESS NOTED OTHERWISE |
| ACS | ACCESS CONTROL SYSTEM |
| VSS | VIDEO SURVEILLANCE SYSTEM |

## TECHNOLOGY - GENERAL NOTES

1. EACH KEYNOTE MAY NOT BE UTILIZED ON EVERY SHEET.
2. ALL CONDUIT MEASUREMENTS REFER TO STANDARD CONDUIT TRADE SIZES.
3. ALL CABLES SHALL BE CONCEALED.
4. EACH CONTRACTOR SHALL PROVIDE AND INSTALL ALL NECESSARY SLEEVES, WHETHER OR NOT SPECIFICALLY NOTED ON PROJECT DRAWINGS. ALL SLEEVES SHALL BE 2" UNLESS NOTED OTHERWISE ON THE DRAWINGS. CABLE FILL PERCENTAGE SHALL COMPLY WITH NEC.
5. DEVICE LOCATIONS ARE APPROXIMATE. CONTRACTOR SHALL REVIEW CONDITIONS AND COORDINATE WITH OTHER TRADES AS NECESSARY FOR EXACT PLACEMENT.

## TECHNOLOGY SYMBOLS LEGEND

NOT ALL SYMBOLS ARE USED

- A## V## — AV WALL ROUGH-IN WITH DATA
- # — KEYNOTE
- C — Proposed Camera Direction — SURVEILLANCE CAMERA
- #-## — Camera Schedule Number (Floor #-Camera #)
- Camera (N)ew, (E)xisting Rough-in, (D)emo
- C — Proposed Camera Direction — PTZ CAMERA
- #-## PTZ
- C — Proposed Camera Direction — FIXED SURVEILLANCE CAMERA
- #-##
- C — 360°/MULTI-SENSOR FIXED SURVEILLANCE CAMERA OR FISHEYE LENS CAMERA
- Approximate view of lens
- Lens View Angle
- ##° #mm — C — 360°/MULTI-SENSOR FIXED SURVEILLANCE CAMERA OR FISHEYE LENS CAMERA
- Lens size
- C M — MICROPHONE WITH AUDIO LINKED TO CAMERA
- C CR — CARD READER LINKED TO CAMERA
- SYMBOL TAG — CR # — (#) = DIFFERENT TYPES OF CARD READERS:
  M = MULLION
  W = WIRELESS (Proprietary)
  Wi = Wi-Fi (802.11)
  POE = POWER OVER ETHERNET
- SYMBOL TAG — KP # — (#) = DIFFERENT TYPES OF CARD READERS:
  TS = TOUCHSCREEN
  PU = PUSH BUTTON
- # / #### — TOP = DETAIL NUMBER / DETAIL REFERENCE / BOTTOM = SHEET NUMBER
- NORTH ARROW
- # / #### — SHEET NUMBER / SECTION MARKER / DETAIL NUMBER
- # / #### — DIRECTION OF ELEVATION / ELEVATION MARKER / SHEET NUMBER / DETAIL NUMBER
- # / #### — DIRECTION OF ELEVATION / SHEET NUMBER / DIRECTION OF ELEVATION / DETAIL NUMBER
- BAR IS ONE INCH ON ORIGINAL DRAWING. IF NOT ONE INCH ON THIS DRAWING ADJUST SCALES ACCORDINGLY

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

0

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Palmer Elementary School
4208 Crow Valley Dr. Missouri City, TX 77459

SEAL

BICSI CERTIFIED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 258657
EXPIRES 10-31-27
RCDD

07-18-25

MVA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY - TITLE SHEET

o-TN000

**DEMO KEYNOTES**

1. REMOVE, AND PROTECT DURING CONSTRUCTION, INSTALL IN EXISTING LOCATION AFTER NEW ACT GRID IS IN PLACE.
2. DEVICES IN ACT ARE TO BE REMOVED AND PROTECTED DURING CONSTRUCTION AND REINSTALLED IN THE SAME LOCATION AFTER THE NEW CEILING GRID IS IN PLACE. DECIVES INCLUDE: SPEAKERS, ACCESS POINTS AND INTRUSION MOTION DETECTORS.
3. EXISTING CARD READER, DOOR CONTACT, & REX (REQUEST TO EXIT) TO BE DEMOLISHED, REMOVE DEVICES AND PROTECT WIREING.




1 PALMER - DEMO PLAN
SCALE: 3/16" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

0

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Palmer Elementary School
4208 Crow Valley Dr. Missouri City, TX 77459

SEAL

BICSI REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256557
EXPIRES 12-31-27
RCDD

07-18-25


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING


TECHNOLOGY - Palmer ES - DEMO

o-TN.001


TRUENORTH A PMY COMPANY

## TECHNOLOGY KEYNOTES

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.




02
02 - Gym
5,002 SF
1st Floor
5,002 SF




1 BACKGROUND 1 (PALMER ES)
SCALE: 1" = 20'-0"

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

0

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Palmer Elementary School
4208 Crow Valley Dr. Missouri City, TX 77459

SEAL


REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256557
EXPIRES 12-31-27

07-18-25

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Palmer ES - OVERALL

o-TN.100




1 PALMER - KITCHEN PLAN
SCALE: 3/16" = 1'-0"

**TECHNOLOGY KEYNOTES**

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

0

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT

Palmer Elementary School

4208 Crow Valley Dr. Missouri City, TX 77459

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 259557
EXPIRES 12-31-27
RCDD

07-18-25

MVA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY - Palmer ES - KITCHEN


o-TN.101

**GENERAL NOTE**


1. FACE PLATE DETAIL FOR OUTLET CONFIGURATION PURPOSES ONLY. CONTRACTOR TO SELECT TYPE OF FACE PLATE TO MATCH CONNECTIVITY HARDWARE, FLOOR BOX AND/OR MODULAR FURNITURE OPENING.





1 DATA ROUGH-IN DETAILS
SCALE: NS





2 TYPICAL CABLING SLEEVE
SCALE: NTS





3 PANDUIT J-HOOK DETAIL
SCALE: NTS





4 LABELING & CABLING SCHEMES
SCALE: NTS





5 CABLE PATHWAY CROSS SECTION
SCALE: NTS




6 DROPPED CEILING MOUNTING DETAIL
SCALE: NS




7 I-JOIST MOUNTING DETAIL
SCALE: NS




8 BAR JOIST MOUNTING DETAIL
SCALE: NS

| CAMERA TYPE | MANUFACTURER | MODEL NUMBER | GENERAL DESCRIPTION |
|---|---|---|---|
| C1 | iPro | WV-S8574L | 4x4K (33MP) EXTERIOR MULTI-SENSOR - PARKING LOTS, STADIUM |
| C2 | iPro | WV-S8544L | 4x4MP (16MP) EXTERIOR MULTI-SENSOR - BUILDING PERIMETER |
| C3 | iPro | WV-S25500-V3LN | 5MP EXTERIOR VANDAL DOME |
| C4 | iPro | WV-S22500-V3L | 5MP INTERIOR VANDAL DOME - CORR., COMMON, SPED |
| C5 | iPro | WV-S4156A | 5MP 360 (FISHEYE) - STAIRWELLS |

9 CAMERA SCHEDULE
SCALE: NTS

| Symbol | Purpose | Size | Mount | Backbox | Notes |
|---|---|---|---|---|---|
| FP1 | Digital Signage/Menu Boards | +49" | Ceiling Pole | N/A | Data and Power Outlets on ceiling |

10 DISPLAY SCHEDULE
SCALE: NTS

TRUENORTH
A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

0

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Palmer Elementary School
4208 Crow Valley Dr. Missouri City, TX 77459

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256557
EXPIRES 12-31-27
RCDD

07-18-25

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY - Palmer ES - DETAILS


o-TN.500

GENERAL NOTES:


1. REFER TO SECURITY SCHEDULE AND WRITTEN SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
2. ALL MOUNTING DETAILS ARE REFERENCE FOR ALL FIXED DOME, 180°, 360°, PTZ, AND "BULLET/BOX" CAMERAS.





1 TYPICAL CAMERA INSTALLATION SECTION DETAIL
SCALE: NS




6 WALL MOUNTED CAMERA DETAIL
SCALE: NS




4 TILE BRIDGE DETAIL
SCALE: NS





5 CEILING MOUNTED CAMERA DETAIL
SCALE: NS


ACCESS CONROL DETAILS AND GENERAL NOTES:

1. CONDUIT ROUGH-IN IS A GUIDE FOR WHAT WILL BE REQUIRED FOR EACH DOOR. AS DOOR COMPONENTS CHANGE, EXACT CONDUIT LOCATION WILL ALSO NEED TO BE ADJUSTED.


2. PROTECT EXISTING-TO-REMAIN ACCESS CONTROL DEVICES AND CABLE THROUGHOUT RENOVATION WORK. IF CABLE AND/OR DEVICES ARE DAMAGED, SECURITY CONTRACTOR TO REPLACE WITH NEW.




1 ACCESS CONTROL - WIRING DETAIL - EXIT DEVICE W/ BUILT-IN REX
SCALE: NTS




2 ACCESS CONTROL - STEEL/HOLLOW METAL DOOR.
SCALE: NTS




KP PB LD

3 ROUGH-IN DETAILS: KP, PB, LD
SCALE: NTS

TRUENORTH
A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

0

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Palmer Elementary School
4208 Crow Valley Dr. Missouri City, TX 77459

SEAL





07-18-25


MWA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING
AND
PERMITTING

TECHNOLOGY - Palmer ES - SECURITY DETAILS

o-TN.600




6 CEILING MOUNT DISPLAY - A/V ROUGH-IN DETAIL
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

0

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Palmer Elementary School
4208 Crow Valley Dr. Missouri City, TX 77459

SEAL




07-18-25

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Palmer ES - AV DETAILS

o-TN.700

# FBISD BP013 KITCHEN RENOVATIONS ES

## PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DR, RICHMOND, TX 77406

FORT BEND INDEPENDENT SCHOOL DISTRICT

## FORT BEND INDEPENDENT SCHOOL DISTRICT

### ADMINISTRATION

| | |
|---|---|
| DR. MARCELL SMITH | SUPERINTENDENT OF FBISD |
| DR. ANDRIA SCHUR, Ed.D. | CHIEF OF SCHOOLS |

### BOARD OF TRUSTEES

| | |
|---|---|
| KRISTIN K. TASSIN | PRESIDENT |
| RICK GARCIA | VICE PRESIDENT |
| DAVID HAMILTON | SECRETARY |
| ANGIE HANAN | BOARD MEMBER |
| ADAM SCHOOF | BOARD MEMBER |
| DR. SHIRLEY ROSE-GILLIAM | BOARD MEMBER |
| SONYA JONES | BOARD MEMBER |

### PROJECT DESIGN TEAM


PROGRAM MANAGEMENT
FBISD 2023 Bond Team
2323 Texas Parkway
Missouri City, TX 77489
Phone Number: 281-327-5481

ARCHITECT
MWA Architects
11767 Katy Freeway, Suite 430
Houston, Texas 77079
Phone Number: 713-782-8188

FOOD SERVICE
Food Design Professionals
26215 Oak Ridge Drive
The Woodlands, Texas 77380
Phone Number: 281-350-2323

MEP ENGINEERS
Stanton Engineering Group
1300 W. Sam Houston Pkwy South, Suite 121
Houston, Texas 77042
Phone Number: 713-300-9292

STRUCTURAL ENGINEER
Stanley Spurling & Hamilton
3301 Edloe Street, Suite 200
Houston, Texas 77027
Phone Number: 713-776-9433


| Sheet List Table | |
|---|---|
| Sheet Number | Sheet Title |
| School: p-Pecan Grove ES | |
| p-A.000 | COVER AND INDEX |
| p-A00-01 | GENERAL NOTES AND ABBREVIATIONS |
| p-D.101 | DEMO PLAN |
| p-D.101-2 | DEMO PLAN PHOTOS |
| p-D.101-3 | DEMO PLAN PHOTOS |
| p-ED.100 | ELECTRICAL DEMOLITION AND TEMP PLANS |
| p-PD1.01 | PLUMBING DEMOLITION FLOOR PLAN |
| p-TD201 | TECHNOLOGY DEMOLITION FLOOR PLAN |
| p-A.101 | SITE PLAN |
| p-A.200 | SLAB DIMENSION CONTROL PLAN |
| p-A.201 | OVERALL FLOOR PLAN |
| p-A.301 | KITCHEN PLAN |
| p-A.302 | TEMPORARY KITCHEN LAYOUT |
| p-A.401 | REFLECTED CEILING PLAN |
| p-A.501 | FINISH FLOOR PLAN |
| p-A.502 | PARTITION SCHEDULE |
| p-S1 | KITCHEN PLAN |
| p-S2 | SECTIONS AND TYPICAL DETAILS |
| p-QF1 | FS GENERAL COORDINATION NOTES |
| p-QF1.0 | FS EQUIPMENT PLAN |
| p-QF1.1 | FS FACILITY MODEL |
| p-QF1.2 | FS EQUIPMENT MODEL |
| p-QF1.3 | FS SPECIAL CONDITIONS & MECHANICAL PLAN |
| p-QF1.4 | FS PLUMBING PLAN |
| p-QF1.5 | FS ELECTRICAL PLAN |
| p-QF1.6 | CONDENSING UNITS |
| p-M1.01 | MECHANICAL PLANS |
| p-M2.01 | KITCHEN MECHANICAL DETAILS |
| E.000 | ELECTRICAL AND FIRE ALARM SCHEDULES |
| E.001 | ELECTRICAL AND FIRE ALARM NOTES |
| E.010 | ELECTRICAL DEVICE DETAILS |
| E.011 | ELECTRICAL DETAILS |
| E.012 | ELECTRICAL DETAILS |
| E.013 | ELECTRICAL KITCHEN DETAILS |
| E.060 | LIGHTING SCHEDULES |
| p-E100 | LIGHTING FLOOR PLAN |
| p-E200 | ELECTRICAL FLOOR PLANS |
| p-E.300 | FIRE ALARM FLOOR PLANS |
| p-E.400 | ELECTRICAL SCHEMATIC |
| p-P0.01 | PLUMBING NOTES AND SCHEDULES |
| p-P0.02 | PLUMBING SCHEDULES AND DETAILS |
| p-P1.01 | PLUMBING FLOOR PLAN |
| p-P1.02 | PLUMBING FLOOR PLAN - TEMPORARY KITCHEN PLAN |
| p-T000 | TECHNOLOGY SYMBOLS & LEGEND |
| p-T200 | TECHNOLOGY COMPOSITE FLOOR PLAN |
| p-T201 | TECHNOLOGY NEW_RENOVATION KITCHEN PLAN |
| p-T202 | TECHNOLOGY TEMPORARY KITCHEN PLAN |
| p-T300 | TECHNOLOGY ENLARGED VIEWS |
| p-T400 | TECHNOLOGY TYPICAL DETAILS |
| p-T401 | TECHNOLOGY TYPICAL DETAILS |
| p-T500 | TECHNOLOGY TYPICAL DETAILS |
| p-TN-000 | TECHNOLOGY - INDEX SHEET |
| p-TN-001 | TECHNOLOGY - KITCHEN DEMOLITION |
| p-TN-100 | TECHNOLOGY - OVERALL |
| p-TN-101 | TECHNOLOGY - KITCHEN |
| p-TN-500 | TECHNOLOGY - DETAILS |
| p-TN-600 | TECHNOLOGY - SECURITY DETAILS |
| p-TN-700 | TECHNOLOGY - AV DETAILS |

REGISTERED ARCHITECT
MICHAEL A. MAGUIRE
22651
STATE OF TEXAS
18 July 2025

ISSUED FOR PERMIT AND BIDDING - JULY 18, 2025

p

PART 1 - GENERAL

1.1 GENERAL DEMOLITION NOTES

A. VERIFY EXISTING SITE AND BUILDING CONDITIONS IN FIELD PRIOR TO BIDDING. NOTIFY ARCHITECT OF ANY DISCREPANCIES PRIOR TO BIDDING.

B. CONTRACTOR SHALL COORDINATE WITH OWNER THE SALVAGE OF ITEMS, FURNITURE AND EQUIPMENT INDICATED TO BE REMOVED.

C. CLAIMS FOR ADDITIONAL COST OR TIME DUE TO EXISTING CONDITIONS THAT COULD HAVE BEEN REASONABLY ANTICIPATED DURING A SITE VISIT BY THE CONTRACTOR PRIOR TO BIDDING WILL NOT BE APPROVED.

D. PROTECT EXISTING FINISHES SHOWN TO REMAIN DURING CONSTRUCTION TO PREVENT DAMAGE. REPAIR OR REPLACE DAMAGED MATERIALS AND FINISHES TO MATCH EXISTING AT NO ADDITIONAL COST TO FORT BEND ISD (OWNER).

E. EXISTING AREAS REQUIRING MINOR DEMOLITION OR REPAIR FOR EXECUTION OF WORK SHALL BE REPAIRED TO MATCH EXISTING ADJACENT MATERIALS, UNLESS NOTED OTHERWISE.

F. DO NOT DAMAGE CASEWORK AND EQUIPMENT NOT DESIGNATED TO BE REMOVED OR RELOCATED.EXISTING CASEWORK SHALL REMAIN THE PROPERTY OF THE OWNER.

G. CONTRACTOR TO VERIFY LOCATION OF ELEC. SWITCHES, OUTLETS, GRILLES, CLEAN-OUTS, COVER PLATES, ACCESS DOORS, AND OTHER EQUIPMENT AND DEVICES THAT MAY CONFLICT WITH THE RENOVATION AND NEW CONSTRUCTION OF WALLS, FLOORS, AND CEILINGS PRIOR TO COMMENCEMENT OF WORK. CONTRACTOR SHALL LIKEWISE CONFIRM THAT ELECTRICAL CONDUIT ROUTING SHALL BE CONCEALED WITHIN WALLS. NOTIFY ARCHITECT IF WALL THICKNESS WILL NOT ALLOW FOR CONCEALMENT.

H. REMOVE ANY EXISTING CORNER GUARDS IN THE KITCHEN AREA.

I. PRIOR TO EXECUTION OF DEMOLITION WORK, SCHEDULE A WALK-THROUGH WITH OWNER AND ARCHITECT TO CONFIRM SCOPE OF WORK AND TO REVIEW EXISTING CONDITIONS.

J. EXISTING FLOOR FINISHES AND ACOUSTIC CEILING TILE TO BE REMOVED THROUGHOUT.

K. REFER TO MEP DRAWINGS FOR DEMOLITION AND ALTERATION OF UTILITIES.

L. AT ALL EXISTING WALLS REQUIRING DEMOLITION TO INSTALL NEW PIPING BEHIND SINKS, CUT AND PATCH WALLS AS REQUIRED TO MATCH ADJACENT SURFACE.

M. CLEAN AND PREPARE SUBFLOOR FOR INSTALLATION OF NEW FLOOR FINISH.

N. DEMOLITION ACTIVITIES SHALL BE PERFORMED AS TO PRODUCE MINIMAL DISTURBANCE TO EXISTING FACILITY OCCUPANTS. MINIMIZE EXCESSIVE AND PROLONGED NOISE LEVELS AND DUST.

O. ASBESTOS-CONTAINING MATERIALS. REFER TO SPECIFICATION 02 26 23 FOR ASBESTOS INFORMATION APPLICABLE TO KITCHEN AREAS. FORT BEND ISD HAS RETAINED A SEPARATE ENVIRONMENTAL CONSULTANT FOR THE REMOVAL OF ASBESTOS. GC TO COORDINATE WITH ENVIRONMENTAL CONSULTANT TO CARRY OUT ASBESTOS ABATEMENT FOR ALL AFFECTED KITCHEN AREAS.

1.2 FLOOR PLAN GENERAL NOTES

A. FIELD VERIFY EXISTING CONDITIONS PRIOR TO GENERATING SHOP DRAWINGS AND FABRICATION OF EQUIPMENT.
B. FLOOR FINISH CHANGES SHALL OCCUR AT THE CENTERLINE OF DOORS UNLESS NOTED OTHERWISE. FLOOR FINISH CHANGES SHALL HAVE THRESHOLDS OR REDUCERS STRIPS.
C. DOORS THAT ARE TO BE REPLACED AND INSTALLED IN EXISTING FRAMES SHALL BE MACHINED FOR HARDWARE DIMENSIONS AT EXISTING FRAMES, CONTRACTOR SHALL FIELD VERIFY FRAME CONDITIONS AND DIMENSIONS.
D. CONTRACTOR TO PROVIDE SHEET METAL REINFORCING STRAP AS REQUIRED FOR MOUNTING OF ALL GRAB BARS, CABINETS, MIRRORS, SHELVING, ETC.
E. SAW CUT AND REMOVE EXISTING SLAB AND FLOOR FINISHES AS REQUIRED TO INSTALL NEW PLUMBING LINES, FLOOR DRAINS, PLUMBING FIXTURES, OR ELECTRICAL ITEMS. SPLICE NEW REINFORCING BARS DOWELED INTO EXISTING CONCRETE, AND PROVIDE NEW VAPOR RETARDER AND WATERSTOPS, AND PATCH W/ 3000 PSI CONCRETE AFTER INSTALLATION OF UTILITIES AND FIXTURES. PREPARE CONCRETE TO RECEIVE NEW FINISH.
F. COORDINATE HOUSEKEEPING PAD DIMENSIONS AND LOCATIONS WITH EQUIPMENT TO BE INSTALLED. HOUSEKEEPING PADS SHALL BE A MIN. OF 4" THICK REINF. W/ #3 BARS AT 15" O.C. BOTH WAYS. PROVIDE 1" BY 45-DEGREE CHAMFERED EDGES.

1.3 COMPLETE PERFORMANCE

L. THE CONTRACTOR SHALL FURNISH AND INSTALL ALL ITEMS SPECIFIED HEREIN AND AS INDICATED ON THE DRAWINGS. THE CONTRACTOR SHALL ALSO FURNISH AND INSTALL ALL ITEMS NECESSARY TO MAKE THE SYSTEMS FUNCTION WHICH MAY BE REASONABLY IMPLIED AS ESSENTIAL, WHETHER MENTIONED IN THE CONTRACT DOCUMENTS OR NOT.

M. WORK SHALL BE EXECUTED IN STRICT ACCORDANCE WITH THE BEST PRACTICE OF THE TRADES IN A THOROUGH, SUBSTANTIAL AND WORKMANLIKE MANNER BY COMPETENT WORKMEN.

1.4 SITE FAMILIARIZATION

A. GENERAL: BECOME FAMILIAR WITH THE DRAWINGS AND SPECIFICATIONS, EXAMINE THE PREMISES, AND UNDERSTAND THE CONDITIONS UNDER WHICH THE CONTRACT SHALL BE PERFORMED, PRIOR TO SUBMITTING A BID.

B. SITE: BE INFORMED OF THE SITE CONDITIONS, VERIFY LOCATIONS OF NEW AND EXISTING EQUIPMENT, AND DETERMINE EXACT REQUIREMENTS FOR CONNECTIONS.

C. COORDINATION: TENDER OF A PROPOSAL FOR THIS PROJECT INFERS THAT THE CONTRACTOR HAS VISITED THE SITE AND HAS BECOME FAMILIAR WITH THE DRAWINGS, SPECIFICATIONS, AND SITE CONDITIONS AND HAS INCLUDED IN HIS PROPOSAL ALL WORK NECESSARY TO PROPERLY INSTALL COMPLETE AND FUNCTIONING SYSTEMS ON THE PROJECT. FAILURE TO COMPLY WITH THIS REQUIREMENT SHALL NOT BE CONSIDERED JUSTIFICATION FOR THE OMISSION OR FAULTY INSTALLATION OF ANY WORK COVERED BY THE CONTRACT DOCUMENTS.

1.5 CODES AND STANDARDS

A. GENERAL: ALL WORK SHALL COMPLY WITH THE MOST RECENTLY REVISED VERSIONS OF ALL APPLICABLE LAWS, RULES, REGULATIONS AND ORDINANCES OF ALL FEDERAL, STATE AND LOCAL AUTHORITIES AND APPLICABLE UTILITIES. NONE OF THE TERMS OR PROVISIONS OF THIS SPECIFICATION SHALL BE CONSTRUED AS WAIVING ANY PART OF THE LAWS, RULES, REGULATIONS OR REQUIREMENTS OF THESE AUTHORITIES.

B. CONFLICT: IN THE EVENT OF CONFLICT BETWEEN THE CONTRACT DOCUMENTS AND THE LOCAL ENFORCING AUTHORITY, THE LATTER SHALL RULE. ANY MODIFICATIONS RESULTING THEREFROM SHALL BE MADE WITHOUT ANY ADDITIONAL COST TO THE OWNER OR ARCHITECT. THIS CONTRACTOR SHALL REPORT ANY SUCH MODIFICATIONS TO THE ARCHITECT AND SECURE HIS APPROVAL PRIOR TO PROCEEDING WITH THE WORK.

C. PRECEDENCE: WHERE CONTRACT DOCUMENT REQUIREMENTS EXCEED THE REQUIREMENTS OF THE CODES AND STANDARDS, THE CONTRACT DOCUMENTS SHALL TAKE PRECEDENCE PROVIDED THEY ARE NOT IN CONFLICT WITH THOSE CODES AND STANDARDS.

D. APPROVAL LABELS: ALL ITEMS OF EQUIPMENT AND ALL MATERIALS FOR WHICH APPROVED STANDARDS HAVE BEEN ESTABLISHED BY UNDERWRITERS' LABORATORIES, INC. (UL), FACTORY MUTUAL (FM), CERTIFIED BALLAST MANUFACTURER (CBM), ELECTRICAL TESTING LABORATORY (ETL), NATIONAL MANUFACTURERS ASSOCIATION (NEMA), AMERICAN STANDARD CODES, ASME, AGA, AMCA, ASA, ANSI, ASHRAE, AND ARI SHALL BE SO APPROVED AND SHALL BEAR APPROVAL LABELS ATTESTING TO SAME.

1.6 DRAWINGS AND SPECIFICATIONS

A. DRAWINGS: THE SET OF ORIGINAL DRAWINGS HAS BEEN MODIFIED AND INDICATE APPROXIMATE EXISTING LOCATIONS OF THE FLOOR FINISH ITEMS. ALL ITEMS ARE SHOWN APPROXIMATELY TO SCALE. FIELD VERIFY CONDITIONS.

B. SPECIFICATIONS: THE SPECIFICATIONS ARE INTENDED TO SUPPLEMENT THE DRAWINGS AND IT IS NOT IN THE SCOPE OF THE SPECIFICATIONS TO MENTION ANY PART OF THE WORK THAT THE DRAWINGS ARE COMPETENT TO FULLY EXPLAIN. CONVERSELY, ANY PART OF THE WORK THAT THE SPECIFICATIONS ARE COMPETENT TO FULLY EXPLAIN MAY NOT BE MENTIONED ON THE DRAWINGS. DRAWINGS AND SPECIFICATIONS ARE COMPLIMENTARY/SUPPLEMENTARY DOCUMENTS TO EACH OTHER.

C. DISAGREEMENT: DISAGREEMENT BETWEEN THE DRAWINGS AND SPECIFICATIONS OR WITHIN THE DRAWINGS OR SPECIFICATIONS SHALL BE ESTIMATED AND/OR BID USING THE BETTER QUALITY OR GREATER QUANTITY OF MATERIAL OR INSTALLATION, AND A CLARIFICATION REQUEST FOR INFORMATION SHALL BE MADE TO THE ARCHITECT IN A TIMELY MANNER AFTER THE PROJECT IS UNDER CONTRACT.

1.7 DISCREPANCIES

A. CLARIFICATION: CLARIFICATION OF SIGNIFICANT COST MATTERS SHALL BE OBTAINED BEFORE SUBMITTING A PROPOSAL FOR THE WORK AS TO DISCREPANCIES OR OMISSIONS FROM THE CONTRACT DOCUMENTS OR QUESTIONS AS TO THE INTENT THEREOF.

B. INTERPRETATIONS: SHOULD ANY DOUBT OR QUESTION ARISE RESPECTING THE TRUE MEANING OF DRAWINGS OR SPECIFICATIONS, REFERENCE SHALL BE MADE TO THE ARCHITECT, WHOSE WRITTEN DECISION SHALL BE FINAL AND CONCLUSIVE. NO ALLEGED STATEMENT BY THE ARCHITECT WILL BE ACCEPTED AS AN EXCUSE FOR NON-COMPLIANCE OR INFERIOR WORK.

C. CONTRACTOR AGREEMENT: CONSIDERATION WILL NOT BE GRANTED FOR MISUNDERSTANDING OF THE AMOUNT OF WORK TO BE PERFORMED. TENDER OF A PROPOSAL CONVEYS FULL CONTRACTOR AGREEMENT OF THE ITEMS AND CONDITIONS SPECIFIED, SHOWN, SCHEDULED, OR REQUIRED BY THE NATURE OF THE PROJECT, AND ALL COSTS ARE INCLUDED IN THE PROPOSAL.

1.8 REQUESTS FOR INFORMATION (RFI)

A. GENERAL: SUBMIT ALL CONTRACTOR REQUESTS FOR INFORMATION (RFI) IN WRITING TO THE ARCHITECT FOR RESPONSE. SUBMIT RFI ON A STANDARD FORM THAT HAS A SPACE FOR THE REQUESTED INFORMATION AND THE ARCHITECT'S RESPONSE.
B. SOLUTION PROPOSAL: IN GENERAL, THE CONTRACTOR SHALL PROPOSE SOLUTIONS TO IDENTIFY PROBLEMS FOR REVIEW AND APPROVAL OF THE ARCHITECT. THE RFI SHALL INCLUDE HAND SKETCHES, MARKED DRAWING PRINTS, EQUIPMENT CUTSHEETS, DRAWING AND SPECIFICATION REFERENCES, AND ANY OTHER BACK-UP INFORMATION, ETC., AS REQUIRED TO SUFFICIENTLY EXPLAIN THE PROBLEM AND PROPOSED SOLUTION.

1.9 QUALITY ASSURANCE

A. GENERAL: MATERIALS AND EQUIPMENT SHALL BE NEW, OF BEST GRADE AND QUALITY, AND STANDARD PRODUCTS OF REPUTABLE MANUFACTURERS REGULARLY ENGAGED IN THE PRODUCTION OF SUCH MATERIALS AND EQUIPMENT.
B. WORKMANSHIP: WORK SHALL BE EXECUTED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE BEST PRACTICE OF THE TRADES IN A THOROUGH, SUBSTANTIAL, WORKMANLIKE MANNER BY COMPETENT WORKMEN, PRESENTING A NEAT APPEARANCE WHEN COMPLETED.
C. JUDGMENT: IN ALL CASES, THE ARCHITECT SHALL BE THE SOLE JUDGE OF THE QUALITY AND EQUIVALENCE OF MANUFACTURERS, PRODUCTS, MATERIALS, AND METHODS.
D. MANUFACTURERS/PRODUCTS/MATERIALS/METHODS: MANUFACTURERS, PRODUCTS, MATERIALS, AND METHODS DESCRIBED IN THE VARIOUS SECTIONS OF THE SPECIFICATIONS AND INDICATED ON THE DRAWINGS ARE INTENDED TO ESTABLISH A STANDARD OF QUALITY ONLY. IT IS NOT THE INTENTION OF THE ARCHITECT TO DISCRIMINATE AGAINST ANY MANUFACTURER, PRODUCT, MATERIAL, OR METHOD THAT IS EQUAL TO THE STANDARDS AS INDICATED AND/OR SPECIFIED, NOR IS IT INTENDED TO PRECLUDE OPEN, COMPETITIVE BIDDING. THE FACT THAT A SPECIFIC MANUFACTURER IS LISTED AS AN ACCEPTABLE MANUFACTURER SHALL NOT BE INTERPRETED TO MEAN THAT THE MANUFACTURER'S STANDARD PRODUCT WILL MEET THE REQUIREMENTS OF THE PROJECT DESIGN, SPECIFICATIONS, AND SPACE CONSTRAINTS.
   1. WHEREVER A DEFINITE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS SPECIFIED AND THERE IS NOT A STATEMENT THAT ANOTHER MANUFACTURER, PRODUCT, MATERIAL, OR METHOD WILL BE ACCEPTABLE, IT IS THE INTENTION OF THE ARCHITECT THAT THE SPECIFIED MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS THE ONLY ONE THAT SHALL BE USED WITHOUT PRIOR APPROVAL.
   2. WHEREVER A DEFINITE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS SPECIFIED AS "NO SUBSTITUTE", IT IS THE INTENTION OF THE ARCHITECT THAT THE LISTED ITEM IS THE ONLY ONE ACCEPTABLE.
E. COORDINATION: WHERE EQUIPMENT IS USED ON THE PROJECT, IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR OR SUBCONTRACTOR INVOLVED TO VERIFY THAT THE EQUIPMENT WILL FIT IN THE SPACE AVAILABLE, INCLUDING ALL REQUIRED CODE AND MAINTENANCE CLEARANCES, AND TO COORDINATE ALL EQUIPMENT REQUIREMENTS AND PROVISIONS WITH THE SYSTEM DESIGN, ALL AFFECTED DIVISIONS, AND ALL OTHER CONTRACTORS. WHERE THE USE OF ALTERNATE OR SUBSTITUTE MATERIALS AFFECTS THE COST OF PROVISIONS MADE BY OTHER CONTRACTORS, THE CONTRACTOR PROVIDING THE ALTERNATE OR SUBSTITUTE SHALL BE RESPONSIBLE FOR THE OTHER CONTRACTOR'S COST ADJUSTMENT. THERE SHALL BE NO ADDITIONAL COST TO THE OWNER OR ARCHITECT DUE TO THE USE OR ACCEPTANCE OF ANY ALTERNATE OR SUBSTITUTE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD.

1.10 PRIOR APPROVAL

A. SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES: THE CONTRACTOR'S SUBMITTAL AND ARCHITECT'S ACCEPTANCE OF SHOP DRAWINGS, PRODUCT DATA, OR SAMPLES THAT RELATE TO CONSTRUCTION ACTIVITIES NOT COMPLYING WITH THE CONTRACT DOCUMENTS DOES NOT CONSTITUTE AN ACCEPTABLE OR VALID REQUEST FOR SUBSTITUTION, NOR DOES IT CONSTITUTE APPROVAL.

1.11 COORDINATION

A. BY SUBMITTING SHOP DRAWINGS ON THE PROJECT, THIS CONTRACTOR IS INDICATING THAT ALL NECESSARY COORDINATION HAS BEEN COMPLETED AND THAT THE SYSTEMS, PRODUCTS AND EQUIPMENT SUBMITTED CAN BE INSTALLED IN THE BUILDING AND WILL OPERATE AS SPECIFIED AND INTENDED, IN FULL COORDINATION WITH ALL OTHER DISCIPLINES.

1.12 SHOP DRAWINGS AND SUBMITTALS

A. GENERAL: AFTER THE CONTRACT IS AWARDED BUT PRIOR TO PROCEEDING WITH THE WORK REQUIRING SHOP DRAWING REVIEW, THE CONTRACTOR SHALL OBTAIN COMPLETE SHOP DRAWINGS AND PRODUCT DATA FROM THE MANUFACTURERS, SUPPLIERS, VENDORS, AND SUB- CONTRACTORS FOR ALL MATERIALS AND EQUIPMENT SPECIFIED HEREIN, AND MAKE FORMAL SUBMISSION TO THE ARCHITECT. A MINIMUM PERIOD OF TWO (2) WEEKS SHOULD BE ALLOWED IN THE CONSTRUCTION SCHEDULE EXCLUSIVE OF TRAVEL TIME FOR THE ARCHITECTS REVIEW.

B. CERTIFICATION: EACH CONTRACTOR RESPONSIBLE FOR THE WORK SHALL REVIEW AND CERTIFY THE SHOP DRAWING, SUBMITTAL AND/OR PRODUCT DATA TO BE IN FULL COMPLIANCE WITH THE REQUIREMENTS OF THE CONTRACT DOCUMENTS.

C. THE ARCHITECTS REVIEW OF SHOP DRAWINGS AND SUBMITTAL DATA SHALL NOT RELIEVE THE CONTRACTOR OF THE RESPONSIBILITY FOR DIMENSIONS OR ERRORS THAT MAY BE CONTAINED THEREIN, OR FOR DEVIATIONS FROM ANY REQUIREMENTS OF THE CONTRACT DOCUMENTS. IT SHALL BE CLEARLY UNDERSTOOD THAT THE ARCHITECTS NOTING SOME ERRORS BUT OVERLOOKING SOME OTHERS DOES NOT GRANT THE CONTRACTOR PERMISSION TO PROCEED IN ERROR. REGARDLESS OF ANY INFORMATION CONTAINED IN THE SHOP DRAWING OR PRODUCT DATA, THE CONTRACT DOCUMENTS SHALL GOVERN THE WORK AND ARE NEITHER WAIVED NOR SUPERSEDED IN ANY WAY BY THE REVIEW OF SHOP DRAWINGS, PRODUCT DATA AND SAMPLES.

1.13 EXECUTION AND COORDINATION OF WORK

A. MANUFACTURER'S RECOMMENDATIONS: WITH EXCEPTIONS AS SPECIFIED AND/OR INDICATED ON THE DRAWINGS OR IN THE SPECIFICATIONS, APPLY, INSTALL, ERECT, USE, CLEAN, AND CONDITION, MANUFACTURED ARTICLES, MATERIALS, AND EQUIPMENT PER MANUFACTURER'S CURRENT PRINTED RECOMMENDATIONS. KEEP COPIES OF SUCH PRINTED RECOMMENDATIONS AT JOB SITE AND MAKE THEM AVAILABLE AS REQUIRED.

1.14 SUPERVISION

A. A COMPETENT SUPERINTENDENT APPROVED BY THE ARCHITECT, SHALL BE KEPT BY THE CONTRACTOR AT THE BUILDING TO RECEIVE INSTRUCTIONS AND TO ACT FOR THE CONTRACTOR. ONCE THE SUPERINTENDENT HAS BEEN APPROVED, NO CHANGE SHALL BE MADE WITHOUT APPROVAL OF ARCHITECT. REPRESENTATIVES OF THE OWNER, ARCHITECT SHALL HAVE THE RIGHT TO OBSERVE THE WORK AT ANY TIME. THE CONTRACTOR SHALL HAVE A REPRESENTATIVE AVAILABLE WHEN HIS WORK IS BEING OBSERVED AND HE SHALL GIVE ASSISTANCE AS MAY BE REQUIRED TO THE ARCHITECT'S REPRESENTATIVE.

B. THE PROJECT SHALL BE CONSTRUCTED BY EMPLOYEES OF THE CONTRACTOR OR BY WORKERS UNDER HIS SUPERVISION. ANY SUBCONTRACTORS EMPLOYED BY THE CONTRACTOR SHALL BE APPROVED BY THE OWNER'S REPRESENTATIVE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL EQUIPMENT, MATERIAL AND WORK PERFORMED BY ANY SUBCONTRACTOR.

1.15 STORAGE AND PROTECTION OF MATERIALS

A. THE CONTRACTOR SHALL PROPERLY STORE ALL MATERIAL AND EQUIPMENT AT THE JOBSITE AND PROTECT IT FROM THE ELEMENTS AND FROM DAMAGE. ANY EQUIPMENT DAMAGED DUE TO IMPROPER PROTECTION SHALL BE REPLACED BY THE CONTRACTOR AT HIS EXPENSE.

B. THE CONTRACTOR SHALL PROTECT THE WORK, EQUIPMENT, AND MATERIAL OF ALL OTHER TRADES FROM DAMAGE BY HIS WORK OR OTHER WORKMEN, AND SHALL MAKE GOOD ALL DAMAGE THUS CAUSED.

C. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL WORK, MATERIALS, AND EQUIPMENT UNTIL FINALLY INSPECTED, TESTED, AND ACCEPTED; PROTECT WORK AGAINST THEFT, INJURY OR DAMAGE; AND CAREFULLY STORE MATERIAL AND EQUIPMENT RECEIVED ON SITE WHICH ARE NOT IMMEDIATELY INSTALLED. CLOSE OPEN ENDS OF WORK WITH TEMPORARY COVERS OR PLUGS DURING CONSTRUCTION TO PREVENT ENTRY OF OBSTRUCTING MATERIAL. THE CONTRACTOR SHALL COVER AND PROTECT IN AN ACCEPTABLE MANNER TO THE OWNER, EXISTING REMAINING EQUIPMENT AND MATERIALS.

D. IF ANY MATERIAL OR EQUIPMENT IS RECEIVED PRIOR TO THE TIME IT IS REQUIRED, THE CONTRACTOR SHALL BE RESPONSIBLE FOR ITS PROPER STORAGE AND PROTECTION UNTIL SUCH TIME AS IT MAY BE REQUIRED. THE CONTRACTOR SHALL PAY FOR ALL COSTS OF DEMURRAGE OR STORAGE.

1.16 DRAYAGE AND HAULING


A. THE CONTRACTOR SHALL KEEP THE JOBSITE FREE FROM THE ACCUMULATION OF TRASH AND CONSTRUCTION DEBRIS, REGARDLESS OF WHICH SUBCONTRACTOR MAY BE RESPONSIBLE.

1.17 CUTTING AND PATCHING


A. WHERE IT BECOMES NECESSARY TO CUT THROUGH ANY WALL, FLOOR OR CEILING TO PERMIT THE INSTALLATION OF ANY WORK, OR TO REPAIR ANY DEFECTS THAT MAY APPEAR, THE CUTTING SHALL BE PERFORMED UNDER THE SUPERVISION OF THE GENERAL CONTRACTOR. INFORM THE OWNER'S REPRESENTATIVE BEFORE ANY WORK COMMENCES. NO STRUCTURAL MEMBER SHALL BE ALTERED WITHOUT THE WRITTEN PERMISSION OF THE ARCHITECT.

B. VERIFICATION: SHOULD A QUESTION ARISE REGARDING THE ACCEPTABLE LEVEL OF NOISE OR VIBRATION IN A PARTICULAR SPACE OR PIECE OF EQUIPMENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING THE SERVICES OF AN APPROVED ACOUSTICAL CONSULTANT TO DETERMINE ACTUAL NOISE/VIBRATION CONDITIONS.


## 01 GENERAL NOTES





## 21 EXTERIOR DOOR SILL
SCALE: 6" = 1'-0" XREF





## 22 DOOR JAMB
SCALE: 6" = 1'-0" XREF





## 23 WINDOW HEAD
SCALE: 6" = 1'-0" XREF





## 24 DOOR WINDOW HEAD
SCALE: 6" = 1'-0" XREF




## 15 WINDOW JAMB AT WALL
SCALE: ###############





## 16 DOOR HEAD
SCALE: 6" = 1'-0" XREF





## 17 WINDOW SILL
SCALE: 6" = 1'-0" XREF





## 18 DOOR SILL
SCALE: 6" = 1'-0" XREF





## 09 WINDOW CORNER
SCALE: ###############




## 10 DOOR STRIKE JAMB
SCALE: ###############




## 11 DOOR HINGE JAMB
SCALE: ###############





## 12 WINDOW MULLION
SCALE: ###############


SEQUENCE OF CONSTRUCTION (AS OF 01/27/2025). Schools will be renovated in groups as shown. These groups contain two or three major kitchen renovations and some cafeteria/miscellaneous renovations. This sequencing is critical for FBISD food service to provide the uninterrupted meal services to their schools.

| | |
|---|---|
| GROUPING 1 | AUSTIN PARKWAY ES + SUGAR MILL ES, kitchen renovations. *Plus: COMMON WEALTH ES, CONERSTONE ES misc. renovations.* |
| GROUPING 2 | SETTLERS WAY ES + PALMER ES kitchen renovations. *Plus: SULLIVAN ES, SIENNA CROSSING ES, HERITAGE ROSE ES misc. renovations* |
| GROUPING 3 | HUNTER'S GLEN ES + HIGHLANDS ES + PECAN GROVE ES kitchen renovations. *Plus: RIDGEGATE ES, DULLES ES misc. renovations.* |

## 03 PROJECT SCHEDULE




## 04 EXTERIOR DOOR HEAD JAMB
SCALE: 6" = 1'-0" XREF




## 06 WINDOW JAMB
SCALE: 6" = 1'-0" XREF

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DRIVE
RICHMOND, TX 77406

SEAL
REGISTERED ARCHITECT
HOWARD A. WEBSTER
23013
STATE OF TEXAS
7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

GENERAL NOTES AND ABBREVIATIONS

A00-01

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\A00-01 GENERAL NOTES AND ABBREVIATIONS.dwg, Jul 23, 2025 - 4:32pm

## GENERAL DEMOLITION NOTES
(NOT ALL NOTES USED ON EACH SHEET)

1. REFER TO SHEET A00-01 FOR DEMOLITION GENERAL NOTES. THESE NOTES APPLY TO ALL SCHOOL KITCHENS.
2. COORDINATE EXTENT OF SAW CUTTING AREAS WITH NEW RECESSED SLAB FOR COOLER/FREEZER LAYOUTS, NEW SERVICE ENTRANCE FLOOR AND EXISTING KITCHEN LAYOUTS THAT REMAIN. SEE STRUCTURAL DRAWINGS AND SLAB DIMENSION CONTROL PLANS FOR ADDITIONAL SCOPE.
3. REMOVE PROTECT AND REINSTALL ALL EXISTING SURFACE MOUNTED FIRE EXTINGUISHERS (TYPES ABC AND K) AT ALL KITCHENS.
4. SAWCUT AND RE-LOCATE EXPOSED CONDUITS AND WIREMOLD TO INSIDE OF WALLS. PATCH AND PAINT. EXCEPTION: WAREWASH AREA BELOW TABLE HEIGHT AND DRY STORAGE ROOMS.
5. CONTRACTOR TO RELOCATE EXISTING KITCHEN EQUIPMENT AND OFFICE FURNITURE TO TEMPORARY KITCHEN LAYOUT AS REQUESTED BY KITCHEN MANAGER. ALSO THAT THE IT EQUIPMENT IS PROTECTED DURING RENOVATIONS. ALL EXISTING EQUIPMENT SHALL BE RETURNED TO OWNER.
6. EXISTING TACKBOARDS TO BE REMOVED BY OWNER.
7. IF PRESENT, EXISTING SAFE IN EACH KITCHEN TO BE TEMPORARILY REMOVED DURING RENOVATION AND REINSTALLED IN KITCHEN AREA.
8. ORIGIN POINT OF EXISTING CEILING GRID SHALL BE IDENTIFIED. NEW CEILING WILL BE INSTALLED (AS MUCH AS POSSIBLE) AT THE SAME ORIGIN POINT SO THAT SPRINKLER SYSTEM PIPING CAN REMAIN UNCHANGED.
9. ABOVE-CEILING INFRASTRUCTURE SHALL REMAIN UNDISTURBED AS MUCH AS IS POSSIBLE. CEILING DEVICES ARE TO BE REMOVED FROM EXISTING GRID/TILE THEN DURING RE-INSTALLATION OF CEILING DEVICES SHALL BE LOCATED AS CLOSE TO ORIGINAL LOCATION AS POSSIBLE INTO THE NEW GRID/TILE. PROTECT AND STORE EXISTING INFRASTRUCTURE (CABLING, ELECTRICAL POWER, PIPING) DURING CONSTRUCTION.
10. EXISTING HOOD IN WAREWASH AND (2) HOODS IN PRODUCTION AREA ARE TO BE CLEANED, INSPECTED, SERVICED AND REFURBISHED TO A LIKE NEW CONDITION. THEY ARE TO REMAIN IN PLACE.


## KEYED DEMOLITION NOTES
(NOT ALL NOTES USED ON EACH SHEET)

1. REMOVE EXISTING THINSET SYNTHETIC TERRAZZO FLOOR AND TERRAZZO COVE BASE MATERIAL IF ANY EXISTS THROUGHTOUT KITCHEN AREA. CLEAN AND PREPARE SUBFLOOR TO RECEIVE NEW FLOOR. RE: FINISH PLAN FOR NEW FLOOR FINISH MATERIAL.
2. REMOVE EXISTING QUARRY TILE FLOORING AND BASE. CLEAN AND PREPARE SUBFLOOR TO RECEIVE NEW FLOORING. RE: FINISH SCHEDULE FOR NEW FLOOR FINISH MATERIAL.
3. CEILING DEVICES: REMOVE SMOKE DETECTORS, STROBES, EXIT SIGNAGE, MOTION DETECTORS AND CEILING SPEAKERS. PROTECT AND RE-INSTALL AFTER FINISHES ARE APPLIED.
4. REMOVE EXISTING LOCKERS. PROTECT AND RE-INSTALL AFTER FINISHES APPLIED.
5. REMOVE EXISTING WASHER AND DRYER. VERIFY WITH FBISD FOR RELOCATION TO WAREHOUSE.
6. TEMPORARILY REMOVE EXISTING WALL MOUNTED CLOCK AND STORE FOR REINSTALLATION AFTER WALL RECEIVED NEW FINISH.
7. REMOVE EXISTING WALK-IN COOLER/FREEZER AND CONDENSING UNIT LOCATED IN ADJACENT SPACE. MITIGATE ANY MOLD FOUND.
8. REMOVE EXISTING DOOR AND PROTECT EXISTING FRAME TO REMAIN
9. REMOVE EXISTING DOOR AND FRAME, PROTECT FRAME AND OR DOOR IF IT IS SCHEDULED TO REMAIN.
10. REMOVE PARTIAL EXISTING CMU PARTITION FOR NEW DOOR OPENING
11. INSPECT EXISTING WAREWASH COUNTER DOOR AND S.S. PASS-THRU WINDOW CHUTE. REPAIR REPLACE DAMAGED COMPONENTS. CLEAN, LUBRICATE AND RE-INSTALL.
12. EXISTING CARD READER ACCESS TO REMAIN
13. EXISTING WINDOW TO REMAIN
14. REMOVE EXISTING KITCHEN EQUIPMENT THROUGHOUT KITCHEN INCLUDING WALK-IN COOLER / FREEZER AND CONDENSING UNIT LOCATED IN ADJACENT ROOM OR OUTSIDE OF THE BUILDING. VERIFY WITH OWNER FOR RELOCATION TO WAREHOUSE. SOME EQUIPMENT IS TO BE RE-USED IN TEMPORARY SERVING LINES. SEE ALSO GENERAL DEMOLITION NOTE 6.
15. REMOVE EXISTING FRP AND PREP FOR NEW TILE FINISH.
16. COORDINATE REMOVAL AND STORAGE OF ANY EXISTING FURNITURE ITEMS WITH OWNER . SEE ALSO GENERAL DEMOLITION NOTE 5.
17. REMOVE EXISTING SOAP AND PAPER TOWEL DISPENSER AND RETURN TO OWNER
18. EXISTING WALL MOUNTED ACCESSORIES SIGNS, DISPLAY BOARDS, AND MATS TO BE REMOVED BY FORT BEND ISD (VERIFY EQUIPMENT - IF ANY).
19. REMOVE EXISTING SURFACE MOUNTED FIRE EXTINGUISHER. RE-INSTALL AFTER NEW FINISH APPLIED.
20. REMOVE EXISTING ACOUSTIC CEILING TILE CEILNG SYSTEM AND LIGHT FIXTURES, HVAC DEVICES, SENSORS, ETC. THROUGHTOUT RENOVATED AREAS. PREP FOR NEW SUSPENDED CEILING. EXISTING SPRINKLE SYSTEM TO REMAIN AS-IS UNLESS ROOM CONFIGURATION HAS CHANGED IN NEW DESIGN. PROTECT RECESSED SPRINKLER HEADS AND - RE-INSTALL IN NEW CEILING.
21. REMOVE EXISTING CASEWORK/SHELVING
22. EXISTING CERAMIC WALL TILE TO REMAIN. PROTECT FROM DAMAAGE.
23. REMOVE EXISTING COAT HANGER / ROD / SHELF
24. REMOVE EXISTING PLUMBING FIXTURES IN RESTROOMS. RE: PLUMBING FOR NEW FIXTURES.
25. REMOVE EXISTING UTILITY SINK. RE: PLUMBING FOR NEW PLUMBING FIXTURES.
26. REMOVE EXISTING MOP HOLDER. REPLACE WITH NEW UNIT AS SPECIFIED.
27. REMOVE EXISTING WALL MOUNTED CLEANING SOLUTION DISPENSER (BY FBISD VENDOR)
28. HOOD TO REMAIN - SEE GENERAL DEMOLITION NOTE 10.
29. HOOD TO REMAIN - SEE GENERAL DEMOLITION NOTE 10.
30. REMOVE FLOORING IN THIS AREA FOR NOTE 1.
31. REMOVE CARTIDGE FILTER AND WATER PURTICATION CABNET


## DEMOLITION LEGEND

- EXISTING PARTITION TO REMAIN
- REMOVE EXISTING PARTITION
- EXISTING CMU PARTITION
- REMOVE DOOR AND FRAME TO REMAIN
- REMOVE EXISTING DOOR AND FRAME
- EXISTING PLUMBING FIXTURES (WATER CLOSET, HAND LAVATORY, AND MOP SINK TO BE REMOVED. RE: PLUMBING DRAWINGS.
- EXISTING ACOUSTIC CEILING TILE AND GRID TO BE REMOVED. RE: ELECTRICAL DRAWINGS.
- SPRINKLER HEAD (RECESSED)
- CLOCK
- CEILING MOUNTED SPEAKERS

# 3 DEMOLITION NOTES




## 1 DEMOLITION FLOOR PLAN
SCALE: 1/4" = 1'-0"




## 2 DEMOLITION REFLECTED CEILING PLAN
SCALE: 1/4" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

p

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DRIVE
RICHMOND, TX 77406

SEAL
REGISTERED ARCHITECT
ROBERT A. WEBER
22653
STATE OF TEXAS
7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

DEMO PLAN

p-D.101

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\P-Pecan Grove ES\p-D.101 DEMO PLAN.dwg Jul 23, 2025 - 4:32pm


PHOTO D1




PHOTO D2



PHOTO D3



PHOTO D4



PHOTO D5



PHOTO D6



PHOTO D7




PHOTO D8



PHOTO D9




PHOTO D10




PHOTO D11




PHOTO D12




PHOTO D13




PHOTO D14



PHOTO D15



PHOTO D16



PHOTO D17



PHOTO D18



PHOTO D19



PHOTO D20

stay
Mazzo

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

p

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT

PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DR,
RICHMOND, TX 77406

SEAL
REGISTERED ARCHITECT
ANTHONY M. AMARO
22651
STATE OF TEXAS
7/15/2025

MWA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
DEMO PLAN
PHOTOS

p-D.101-2

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\P-Pecan Grove ES\p-D.101-2 DEMO PLAN PHOTOS.dwg Jul 23, 2025 - 4:33pm



PHOTO D21




PHOTO D22



PHOTO D23



PHOTO D24


PHOTO D25




PHOTO D26




PHOTO D27




PHOTO D28



PHOTO D29




PHOTO D30

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

p

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DR,
RICHMOND, TX 77406

SEAL

REGISTERED ARCHITECT
KEVIN A. MAHAN
22651
STATE OF TEXAS

7/15/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
DEMO PLAN PHOTOS

p-D.101-3


F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\P-Pecan Grove ES\p-D 101-3 DEMO PLAN PHOTOS.dwg Jul 23, 2025 - 4:33pm

## NEW PANEL — TEMP KITCHEN

**PANEL LTK** — 150A MCB, 208Y/120V, 3ϕ, 4 WIRE — AVAILABLE FAULT: <10,000A — SCCR & AIC: 10,000A — MOUNTING: SURFACE


| NOTES | EQUIP. NO. | LOAD | DESCRIPTION | WIRE | CB | CKT | A | B | C | CKT | CB | WIRE | DESCRIPTION | LOAD | EQUIP. NO. | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E810 | 2766 | HOT WELLS | 2–12 | 20/2GFI | 1 | ■ | | | 2 | 20/1 | 3–12 | TRANSPORT CART | 1920 | E806 | |
| | – | – | – | +12G | – | 3 | | ■ | | 4 | 20/1 | 3–12 | TRANSPORT CART | 1920 | E806 | |
| | E810A | 1643 | HOT WELLS | 2–12 | 20/2GFI | 5 | | | ■ | 6 | 20/1 | 3–12 | TRANSPORT CART | 1920 | E806 | |
| | | – | – | +12G | – | 7 | ■ | | | 8 | 20/1 | 3–12 | TRANSPORT CART | 1920 | E806 | |
| | E810B | 600 | COLD PAN | 3–12 | 20/1GFI | 9 | | ■ | | 10 | 20/1 | 3–12 | 2 REC | 360 | E800A | |
| | E810C | 1200 | BEVERAGE | 3–12 | 20/1GFI | 11 | | | ■ | 12 | 20/1 | 3–12 | 2 REC – DESK | 360 | E800B | |
| | E810C | 1200 | BEVERAGE | 3–12 | 20/1GFI | 13 | ■ | | | 14 | 20/1 | 3–12 | 2 REC | 360 | E800A | |
| | E811 | 180 | CASH REGISTER | 3–12 | 20/1GFI | 15 | | ■ | | 16 | 20/1 | 3–12 | 3 REC | 360 | E800A | |
| | E810B | 600 | COLD PAN | 3–12 | 20/1GFI | 17 | | | ■ | 18 | 20/1 | 3–12 | TEMP. KITCHEN LTS/FAN | 566 | | |
| | E810A | 1643 | HOT WELLS | 2–12 | 20/2GFI | 19 | ■ | | | 20 | 20/1 | | SPARE | | | |
| | – | – | – | +12G | – | 21 | | ■ | | 22 | 20/1 | | SPARE | | | |
| | E810 | 2766 | HOT WELLS | 2–12 | 20/2GFI | 23 | | | ■ | 24 | 20/1 | | SPARE | | | |
| | – | – | – | +12G | – | 25 | ■ | | | 26 | 20/1 | | SPARE | | | |
| | E808 | 1622 | HEATED CABINET | 2–12 | 20/2 | 27 | | ■ | | 28 | 20/1 | | SPARE | | | |
| | – | – | – | +12N+12G | – | 29 | | | ■ | 30 | 20/1 | 3–12 | EXISTING CIRCUIT | 500 | | 3 |
| | E809 | 984 | REFRIGERATOR | 3–12 | 20/1 | 31 | ■ | | | 32 | 20/1 | 3–12 | EXISTING CIRCUIT | 500 | | 3 |
| | E808 | 1622 | HEATED CABINET | 2–12 | 20/2 | 33 | | ■ | | 34 | 15/2 | 2–12 | EXISTING CIRCUIT | 1000 | | 3 |
| | – | – | – | +12N+12G | – | 35 | | | ■ | 36 | – | +12N+12G | – | – | | |
| | E809 | 984 | REFRIGERATOR | 3–12 | 20/1 | 37 | ■ | | | 38 | 20/2 | 2–12 | EXISTING CIRCUIT | 1000 | | 3 |
| | | | SPARE | | 20/1 | 39 | | ■ | | 40 | – | +12N+12G | – | – | | |
| | | | SPARE | | 20/1 | 41 | | | ■ | 42 | 50/2 | 2–8 | EXISTING CIRCUIT | 5000 | | 3 |
| | | | SPARE | | 20/1 | 43 | ■ | | | 44 | – | +8N+10G | – | – | | |
| | TOTAL LOAD @ 100% = | | 35498VA | | TOTAL LOAD @ 100% = | | 99A | | | | | | | | | |

1. REF. KITCHEN CONSULTANT'S "FCS" DRAWINGS FOR KITCHEN EQUIPMENT NUMBERS.
2. A DEMAND FACTOR PERCENT OF 65% HAS BEEN APPLIED TO THE KITCHEN EQUIPMENT LOAD PURSUANT TO NEC 220–20 AND NEC TABLE 220–20.
3. IDENTIFY ANY CIRCUITS OR PARTIAL CIRCUITS THAT EXTEND BEYOND THE AREA OF RENOVATION. PROVIDE TEMPORARY FEED TO MAINTAIN ALL CIRCUITS SERVING ELEMENTS/SPACES NOT TO BE REMOVED DURING CONSTRUCTION. RECONNECT EXISTING CIRCUITS/DEVICES TO REMAIN TO TEMPORARY KITCHEN PANEL ONCE AVAILABLE USING CB(S) PROVIDED. ALL PARTIAL CIRCUITS SHALL REMAIN AND REMAIN ACTIVE BOTH DURING AND AFTER CONSTRUCTION.





## T1 TEMPORARY KITCHEN - LIGHTING PLAN


SCALE: 1/4" = 1'– 0"




## T2 TEMPORARY KITCHEN - ELECTRICAL PLAN

SCALE: 1/4" = 1'– 0"


(C)GENERATOR
EXISTING TRANSFORMER PAD
MH
RELOCATE AND REINSTALL EXISTING WALL PACK FIXTURE. RECONNECT TO EXISTING CIRCUIT/CONTROLS.
EXIST ATS
EXIST EH
EXIST TXEL
EXIST EL
EXIST HK
EXIST LKA
EXIST LKB
EXIST AC
EXIST M
EXIST LT
EXIST DA
EXIST WH
EXIST WC
EXIST WC
EXIST WH
EXIST WC
EXIST WC
EXIST WH
EXIST WC
EXIST WC




## DEMOLITION KEYED NOTES

D1 EXISTING CLEAN OUT SHALL BE REPLACED WITH NEW. CHIP OUT SLAB AROUND CLEANOUT TO REMOVE.

D2 EXISTING FLOOR DRAIN SHALL BE REPLACED WITH NEW, INCLUDING P-TRAP. CHIP OUT SLAB AROUND DRAIN TO REMOVE FLOOR DRAIN AND EXISTING P-TRAP.

D3 CUT AND CAP EXISTING HW/CW FOR FUTURE EXTENSION. DEMOLISH ALL PIPING WITHIN KITCHEN. DEMOLITION SHALL BE DELAYED UNTIL NEW CW MAIN AND HW PIPING LOOP IS INSTALLED IN PARALLEL. CW/HW SERVICE TO THE TEMPORARY KITCHEN SHALL BE UNINTERRUPTED DURING OCCUPIED HOURS. COORDINATE SWITCHOVER FROM EXISTING PIPING TO NEW WITH OCCUPANCY SCHEDULE.

D4 EXISTING FLOOR DRAIN TIED TO GREASE WASTE SYSTEM. DRAIN IS BEING USED FOR TEMPORARY KITCHEN INDIRECT WASTE AND SHALL REMAIN ACTIVE DURING OCCUPIED HOURS. COORDINATE DEMOLITION AND REPLACEMENT WITH TEMPORARY KITCHEN USAGE.

D5 DEMOLISH EXISTING DRAIN A CAP BELOW SLAB.

D6 EXISTING SPACE BEING DEMOLISHED. CAP EXISTING SANITARY MAIN BELOW SLAB AND REMOVE UPSTREAM PIPING. CUT/CHIP OUT SLAB AS REQUIRED AND REPAIR TO MATCH EXISTING.

D7 TEMPORARILY CAP EXISTING SANITARY MAIN BELOW SLAB AND REMOVE UPSTREAM PIPING. CUT/CHIP OUT SLAB AS REQUIRED AND REPAIR TO MATCH EXISTING. PIPING TO BE REPLACED WITH NEW TRUNK AND ADDITIONAL DRAIN BRANCH LINES.

D8 CUT AND CAP EXISTING SANITARY MAIN BELOW GRADE FOR EXTENSION IN RENOVATION PHASE. ALL UPSTREAM PIPING SHALL BE ABANDONED IN PLACE. CAP ANY OPEN ENDS BEFORE BURIAL.

**1 PLUMBING DEMOLITION FLOOR PLAN**

SCALE: 1/4" = 1'- 0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

p

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD SOUTH DRIVE
RICHMOND, TX 77406

SEAL

STATE OF TEXAS
TYLER W. HERRING
106052
LICENSED
PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

PLUMBING DEMOLITION FLOOR PLAN

**p-PD1.01**


STANTON ENGINEERING GROUP
INFORMATION PLEASE | TEXAS REGISTERED ENGINEERING FIRM F-12,443 | (713) 300-6080 | 1300 W. SAM HOUSTON PARKWAY S., SUITE 125, HOUSTON, TX 77042


COPYRIGHT © 2025 ALL RIGHTS RESERVED




1 TECHNOLOGY DEMOLITION FLOOR PLAN
p-TD201 1/4" = 1'-0"

**TECHNOLOGY DEMOLITION PLAN GENERAL NOTES**

1. ALL DATA, VOICE, VIDEO AND SECURITY SYSTEMS SHALL REMAIN OPERATIONAL AT ALL TIMES DURING BUSINESS HOURS UNLESS OTHERWISE NOTED. ANY SYSTEM DOWNTIME SHALL BE SCHEDULED WITH THE ARCHITECT/ENGINEER AND OWNER AT LEAST TEN (10) WORKING DAYS IN ADVANCE. CONTRACTOR SHALL DEVELOP A PHASING PLAN AND SCHEDULE OF ANY REQUIRED SYSTEM DOWNTIME FOR REVIEW AND APPROVAL BY THE ARCHITECT/ENGINEER AND OWNER PRIOR TO ANY CONSTRUCTION ACTIVITIES.
2. OWNER SHALL BE RESPONSIBLE FOR POWER DOWN AND START-UP OF ALL DATA, VOICE, VIDEO AND SECURITY SYSTEMS. CONTRACTOR SHALL COORDINATE WITH THE ARCHITECT/ENGINEER AND OWNER AND PROVIDE A MINIMUM OF TEN (10) WORKING DAYS NOTICE FOR SCHEDULING OF ANY REQUIRED DOWNTIME.
3. ALL EXISTING WIRELESS ACCESS POINTS ARE TO BE REMOVED AND RETURNED TO OWNER. CONTRACTOR SHALL RE-INSTALL ALL EXISTING AND NEW WIRELESS ACCESS POINTS AT COMPLETION OF PROJECT.
4. COORDINATE REMOVAL OF EXISTING CAMERA WITH OWNER/ARCHITECT DURING CONSTRUCTION.

**TECHNOLOGY DEMOLITION PLAN KEYED NOTES**

**NOT ALL KEYED BELOW APPLY TO THIS SHEET**

(1) EXISTING DATA/VOICE/WIRELESS ACCESS POINT OUTLET TO BE REMOVED. CONTRACTOR SHALL REMOVE AND DISPOSE OF ALL 4-PAIR CABLES AND WORKSTATION CONNECTING HARDWARE TERMINATED AT THIS LOCATION. IF LOCATION IS NOT RE-USED, CONTRACTOR SHALL SUPPLY AND INSTALL BLANK COVER. CONTRACTOR IS TO REMOVE EACH CABLE TO BE DEMOLISHED FROM THE PATCH PANEL OR TERMINATION BLOCK IN THE TELECOMMUNICATIONS ROOM. REMOVE THE ENTIRE LENGTH OF THE CABLE AND THE CORRESPONDING MODULAR CONNECTOR, FACEPLATE AND ACCESSORIES. NO ABANDONED CABLING IS TO BE LEFT ABOVE CEILING. CONTRACTOR SHALL INSTALL ALL EXISTING AND NEW WIRELESS ACCESS POINTS AT COMPLETION OF PROJECT.

(2) EXISTING VIDEO SURVEILLANCE CAMERA. CONTRACTOR SHALL REMOVE AND RETURN TO OWNER.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

p

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD SOUTH DRIVE
RICHMOND, TX 77406

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD

07/18/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY DEMOLITION FLOOR PLAN


SHEET NO.
p-TD201

NUMBERED NOTES: FOR 2/a-A.101

1. COOLER RENTAL UNIT; APPROX. 8' X 10' BASIS OF DESIGN: MODEL DT810 BY POLAR LEASING REFRIGERATION RENTAL
2. INCLUDE OPTIONAL DIAMOND TREAD RAMP SUITABLE FOR WHEELED TRAFFIC
3. LOCATION SHOWN IS SUBJECT TO OWNER APPROX. LOCATION MUST NOT BLOCK DELIVERIES TO REAR DOOR. MUST BE WITH 10' OF AREA DRAIN, AND WITHIN 100' OF ELECTRICAL POWER.
4. CONTRACTOR SHALL SCAN PAVING FOR BURIED UTILITIES BEFOR CUTTING CONC.




1 SITE PLAN
SCALE: 1" = 30'-0"




2 ENLARGED SITE PLAN
SCALE: 1/8" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

p

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DRIVE
RICHMOND, TX 77406

SEAL
REGISTERED ARCHITECT
PHILIP A. WEAVER
22551
STATE OF TEXAS
7/15/2025



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING


SITE PLAN

p-A.101


F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\P-Pecan Grove ES\p-A.101 SITE PLAN.dwg Jul 23, 2025 - 4:34pm





10 CANOPY DETAILS
3/4" = 1'-0"




11 CANOPY PLAN
3/4" = 1'-0"




12 CANOPY SECTION
3/4" = 1'-0"




1 SLAB DEPRESSION PLAN
SCALE: 1/4" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

p

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DRIVE
RICHMOND, TX 77406

SEAL
REGISTERED ARCHITECT
MICHAEL A. WHITE
22651
STATE OF TEXAS
7/15/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

SLAB DIMENSION CONTROL PLAN
p-A.200

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\P Pecan Grove ES\p-A 200 SLAB DIMENSION CONTROL PLAN.dwg Jul 23, 2025 - 4:34pm

# 2 CODE ANALYSIS

SCOPE OF WORK: KITCHEN REPLACEMENT OF FLOOR, WALL, AND CEILING FINISHES, AS WELL AS, REPLACEMENT OF KITCHEN EQUIPMENT. PROVIDE SECURITY CAMERAS OVER SERVING LINE.

**FORT BEND COUNTY BUILDING CODES:**

- 2021 INTERNATIONAL FIRE CODE

**INTERIOR WALL AND CEILING FINISH REQUIREMENTS BY OCCUPANCY:**

**SPRINKLERED**

| | |
|---|---|
| INTERIOR EXIT STAIRWAYS AND RAMPS AND EXIT PASSAGEWAYS | **B** |
| CORRIDORS AND ENCLOSURE FOR EXIT ACCESS STAIRWAYS AND RAMPS | **C** |
| ROOMS AND ENCLOSED SPACES | **C** |

**FLOORING SHALL BE CLASS II**

**2021 INTERNATIONAL EXISTING BUILDING CODE**

301.3.1 PRESCRIPTIVE COMPLIANCE METHOD. REPAIRS, ALTERATIONS, ADDITIONS AND CHANGES OF OCCUPANCY COMPLYING WITH CHAPTER FIVE OF THIS CODE IN BUILDINGS COMPLYING WITH THE INTERNATIONAL FIRE CODE SHALL BE CONSIDERED IN COMPLIANCE WITH THE PROVISIONS OF THIS CODE.

302.3 EXISTING MATERIALS. MATERIALS ALREADY IN USE IN A BUILDING IN COMPLIANCE WITH REQUIREMENTS OR APPROVALS IN EFFECT AT THE TIME OF THEIR ERECTION OR INSTALLATION SHALL BE PERMITTED TO REMAIN IN USE UNLESS DETERMINED BY THE BUILDING OFFICIAL TO BE UNSAFE .

302.4 NEW AND REPLACEMENT MATERIALS. EXCEPT AS OTHERWISE REQUIRED OR PERMITTED BY THIS CODE, MATERIALS PERMITTED BY THE APPLICABLE CODE FOR NEW CONSTRUCTION SHALL BE USED. LIKE MATERIALS SHALL BE PERMITTED FOR REPAIRS AND ALTERATIONS, PROVIDED THAT NO UNSAFE CONDITION IS CREATED. HAZARDOUS MATERIALS SHALL NOT BE USED WHERE THE CODE FOR NEW CONSTRUCTION WOULD NOT PERMIT THEIR USE IN BUILDINGS OF SIMILAR OCCUPANCY, PURPOSE AND LOCATION.

**ALTERATION - LEVEL 1** INCLUDE THE REMOVAL AND REPLACEMENT OR THE COVERING OF EXISTING MATERIALS, ELEMENTS, EQUIPMENT, OR FIXTURES USING NEW MATERIALS, ELEMENTS, EQUIPMENT, OR FIXTURES THAT SERVE THE SAME PURPOSE.

**ALTERATION - LEVEL 2** INCLUDE THE ADDITION OR ELIMINATION OF ANY DOOR OR WINDOW, THE RECONFIGURATION OR EXTENSION OF ANY SYSTEM. OR THE INSTALLATION OF ANY ADDITIONAL EQUIPMENT, AND SHALL APPLY WHERE THE WORK IS EQUAL TO OR LESS THAN 50% OF THE BUILDING AREA.

THIS BUILDING'S CONSTRUCTION IS TYPE IIB.


THIS BUILDING'S OCCUPANCY IS E.

THIS BUILDING'S IS SPRINKLERED.

THERE WILL NOT BE ANY MODIFACATIONS TO THE HOOD SYSTEMS IN THE KITCHENS BEYOND REPLACEMENT OF MOTOR FOR LIKE KIND IF NEEDED.

THE BUILDING WILL NOT HAVE ADDITIONAL SQUARE FOOTAGE AS PART OF THE WORK.

NEW CONSTRUCTION ELEMENTS, COMPONENTS, SYSTEMS AND SPACES SHALL COMPLY WITH THE REQUIREMENTS OF THE INTERNATIONAL BUILDING CODES




1 OVERALL FLOOR PLAN
SCALE: 1/16" = 1'-0"


ISSUE:
12/05/2024 DD PACKAGE
03/11/2025 50% CD PKG.
05/23/2025 90% CD PKG.
07/18/2025 ISSUED FOR BIDDING AND PERMITTING

p

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DRIVE
RICHMOND, TX 77406

SEAL
REGISTERED ARCHITECT
MICHAEL A. WILLIAMS
22651
STATE OF TEXAS
7/15/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING


OVERALL FLOOR PLAN

p-A.201


F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\P-Pecan Grove ES\p-A.201 FLOOR PLAN.dwg, Jul 23, 2025 - 4:34pm

## DOOR SCHEDULE

| DOOR # | DOOR WIDTH | DOOR HEIGHT | DOOR TYPE | DOOR MATERIAL | DOOR FINISH | FIRE RATING | FRAME THICKNESS | FRAME FINISH | KEY | HARDWARE | DETAILS | | | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | | SILL | JAMB | HEAD | |
| A005 | 3'-0" | X 7'-0" | SF4 | SOLID CORE | P LAM | NR | 4 1/2" | ANOD AL | | 103 | | 22/A00-01 | 16/A00-01 | |
| A006 | 3'-0" | X 7'-0" | SF4 | SOLID CORE | P LAM | NR | 4 1/2" | ANOD AL | | 501 | | 22/A00-01 | 16/A00-01 | |
| A007 | 3'-0" | X 7'-0" | SF4 | SOLID CORE | P LAM | NR | 4 1/2" | ANOD AL | | 341 | | 22/A00-01 | 16/A00-01 | |
| A008 | 3'-0" | X 7'-0" | SF4 | SOLID CORE | P LAM | NR | 4 1/2" | ANOD AL | | 501C | | 22/A00-01 | 16/A00-01 | |
| A012 | 4'-0" | X 7'-0" | HM1 | H.M. | PAINT | NR | 6" | PAINT HM | | 715V | 21/A00-01 | 04/A00-01 | 04/A00-01 | |
| 109A | 3'-0" | X 7'-0" | SF4 | SOLID CORE | P LAM | NR | 4 1/2" | ANOD AL | | 501H | | 22/A00-01 | 16/A00-01 | |
| 109B | 3'-0" | X 7'-0" | SF1 | ALUM/GLASS | ANOD AL | NR | 4 1/2" | ANOD AL | | C201AH | 18/A00-01 | 10&11/A00-01 | 23&24/A00-01 | CARD READER, CLOSER, BUZZER |
| 109C | 3'-0" | X 7'-0" | SF1 | ALUM/GLASS | ANOD AL | NR | 4 1/2" | ANOD AL | | C201AH | 18/A00-01 | 10&11/A00-01 | 23&24/A00-01 | CARD READER, CLOSER, BUZZER |
| 109D | 3'-0" | X 7'-0" | SF4 | SOLID CORE | P LAM | NR | 4 1/2" | ANOD AL | | 501H | | 22/A00-01 | 16/A00-01 | |





NEW DOOR AND FRAME HOLLOW METAL DOOR NEW H.M. FRAME

NEW DOOR AND FRAME HOLLOW METAL DOOR NEW H.M. FRAME

NEW DOOR AND FRAME S. C. WOOD DOOR ALUM. FRAME

NEW DOOR AND FRAME ALUM/GLASS ALUM. FRAME

## 3 DOOR SCHEDULE





## 4 MAKERBOARD ELEVATION

SCALE: 1/2"=1'-0"

## RESPONSIBILITY MATRIX

| ITEM | | | | CONTRACTOR RESPONSIBILITY | | OWNER RESPONSIBILITY | | NOTES |
|---|---|---|---|---|---|---|---|---|
| **EQUIPMENT** | **MAKE** | **MODEL** | **BASIS OF DESIGN** | FURNISHED | INSTALL | FURNISHED | INSTALL | |
| MARKERBOARD | | | MUST BE MAGNETIC; LOW GLOS, WHITE. NO GREY ALLOWED. 5' X 10' | X | X | | | |
| MOTORIZED FOLDING PARTITION | | | TOP SUPPORTED AND CONTINUOUSLY HINGED, MADE OF 3" THICK STEEL WITH FULL SOUND SEALS. THEY FEATURE AUTOMATIC FLOOR SEALS THAT DEPLOY WHEN POSITIONED. MARKERBOARD FINISHES ARE SUGGESTED FOR CLASSROOM USE. LARGE PARTITIONS SHOULD BE ELECTRONICALLY OPERATED, INTEGRATED WITH THE SCHOOL SYSTEM, AND SUPPORTED FROM THE BOTTOM IN A RECESSED MANNER. | X | X | | | |
| PAPER TOWEL DISPENSER | | | 1 PAPER TOWEL DISPENSER PER SINK | | X | X | | |
| SOAP DISPENSER | | | 1 SOAP DISPENSER PER SINK | | X | X | | |
| COMMERCIAL WASHER | GE | GTW750CPLDG | STAINLESS STEEL; ASTM A666, TYPE 304 WITH NUMBER 4 FINISH. ELECTRIC, 480 VOLTS, 40 LB CAPACITY. MINIMUM EXTRACTOR FORCE 140 G FACTOR. | X | X | | | |
| COMMERCIAL DRYER | GE | GTD75ECPLDG | HEAVY DUTY EMBOSSED STEEL WITH ELECTROSTATICALLY APPLIED BACKED ENAMEL FINISH. | X | X | | | |
| MOP RACK | | | BROOM AND MOP HANGGERS FOR A MINIMUM OF TWELVE (12) HANGERS TO BE PROVIDED IN THE CONTRACT | X | X | | | |
| KITCHEN MENU SYSTEM DEVICE | | | RE: J-QFI 0 SF EQUIPMENT PLAN | X | X | | | REFERED TO IT DRAWINGS |
| LOCKERS | | | 12"W X 15"D, 2 TIER, 60" HIGH. 16 GA. DOOR WITH 20GA. BODY | X | X | | | |
| MIRROR | | | TOP EDGE 74 INCHES (1880 MM) MINIMUM ABOVE THE FINISH FLOOR OR GROUND & BOTTOM EDGE OF THE REFLECTING SURFACE 40 INCHES (1015 MM) MAXIMUM | X | X | | | |
| GRAB BARS | | | AS REQUIRED BY ADA | X | X | | | |
| HOOKS | | | J-HOOKS | X | X | | | |
| TIME CLOCK | KRONOS | | EXISTING UNIT | | X | | | COORDINATE HEIGHT, DATA, POWER AND ROUGH-IN REQUIREMENTS WITH FBISD IT. REMOVE, PROTECT & REINSTALL EXISITING TIME CLOCK. |
| **KITCHEN OFFICE FURNITURE** | | | | | | | | |
| AUSTIN PARKWAY ES | | | | | | X | X | |
| PECAN GROVE ES | | | | | | X | X | |
| SETTLERS WAY ES | | | | | | X | X | |
| SUGAR MILL ES | | | | | | X | X | |
| HIGHLANDS ES | | | | | | X | X | |
| PALMER ES | | | | | | X | X | |
| HUNTERS GLEN ES | | | | | | X | X | |




ELEVATION A

ELEVATION B


ELEVATION C

## 5 OWNER PROVIDED ARTWORK IN PLACE NOW

SCALE: 1/4"=1'-0"


1. INSPECT CURRENT INSTALLATION & PHOTOGRAPH
2. CAREFULLY REMOVE AND STORE ARTWORK IN LOCATION DESIGNATED BY SCHOOL. PROTECT FROM DAMAGE
3. RE-INSTALL AS PER CURRENT CONDITION

NOTE: THIS ARTWORK IS LIGHTED. PERSERVE CIRCUTS





## 5 ENLARGED VIEW

SCALE: 1/2"=1'-0"




## 6 ENLARGED VIEW

SCALE: 1/2"=1'-0"




## 7 ENLARGED VIEW

SCALE: 1/2"=1'-0"

## FLOOR PLAN - GENERAL NOTES

1. REFER TO SHEET FOR GENERAL NOTES. GENERAL NOTES APPLY TO ALL SCHOOL KITCHENS.
2. REFER TO SHEET FOR PARTITION TYPES.
3. EXIXSTING EXPOSED CONDUITS AND DATA CABLING IN WIREMOLD TO BE ROUTED INSIDE WALLS (EXCEPT AT WAREWASH AREA BELOW TABLE HEIGHT AND DRY STORAGE ROOMS). PATCH AND REPAIR AS REQUIRED TO ACHIEVE SMOOTH CLEAN WALL SURFACE.

## PARTITION LEGEND

- EXISTING CMU PARTITION
- NEW CMU SCHEDULED PARTITION
- EXISTING METAL PARTITION
- NEW FRAMED SCHEDULED PARTITION

## 2 FLOOR PLAN NOTES

## FLOOR PLAN - KEYED NOTES

(NOT ALL NOTES USED ON EACH SHEET)

01 PROVIDE NEW MOP SINK UTILITY SHELF
RE: PLUMBING FOR MOP SINK
RE: SPEC 10 28 00 FOR UTILITY SHELF

02 REMOVE, STORE & REPLACE WALL MOUNTED FIRE EXTINGUISHER

03 PROVIDE NEW WALL MOUNTED FIRE EXTINGUISHER
RE: SPEC SECTIONS 10 44 13

04 PROVIDE NEW LOCKERS
RE: SPEC 10 51 13.

05 PROVIDE WASHER AND DRYER
RE: SPEC 11 45 20

06 REMOVE, PROTECT & REINSTALL WALL MOUNTED CLOCK.

07 PROVIDE CONDENSING UNIT
FOR WALK-IN COOLER/FREEZER
RE: MECHANICAL AND SPEC 11 40 00


08 PROVIDE POWER AND DATA FOR MENU BOARD.
RE: ELECTRICAL, TECHNOLOGY DRAWINGS & FOOD SI

09 PROVIDE P-LAM SHELVING
REFER TO DETAIL FOR BRACKET SUPPORT

10 FURNITURE & NON FOOD SVE EQUIPMENT RETURN TC STORAGE

11 INSPECT & SREVICE TOLLING COUNTER DOORS. RETU NEW CONDITION.

12 COMMERCIAL CLOSED WASHER 40LB CAPACITY.
COMMERCIAL CLOSED DRYER 55LB CAPACITY.
BASIS OF DESIGN: WASHER; SPEED QUEEN SYN040
DRYER; SPEED QUEEN ST055.
REFER TO ELECTRICAL & PLUMBING FOR CONNECTIOI




## 1 KITCHEN PLAN

SCALE: 1" = 4'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DRIVE
RICHMOND, TX 77406

SEAL

REGISTERED ARCHITECT
KOREY A. NEWMAN
22551
STATE OF TEXAS

7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

KITCHEN PLAN

p-A.301

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\P-Pecan Grove ES\p-A.301 KITCHEN PLAN.dwg Jul 30, 2025 - 10:41am

## TEMPORARY KITCHEN FLOOR PLAN KEYED NOTES 05/A-A03-02

01 PROVIDE & INSTALL 555 SF OF RAM BOARD TO PROTECT EXISTING FLOORING. REMOVE AFTER CONSTRUCTION IS COMPLETE. CONTRACTOR MUST REPAIR FLOORING DAMAGED DURING CONSTRUCTION.

02 PROVIDE SCHEDULED PARTITIONS. BUILD PARTITIONS ON TOP OF RAM BOARD. DO NOT ATTACH PARTITIONS TO FLOOR.


03 ATTACH PARTITIONS TO EXISTING WALL. REPAIR WALL TO MATCH EXISTING AFTER CONSTRUCTION IS COMPLETE.

## TEMPORARY KITCHEN RCP KEYED NOTES 03/A-A03-02

04 ALL NEW SCHEDULED PARTITIONS AND CEILINGS FOR TEMPORARY STORAGE LAYOUT TO BE EPOXY PAINTED SW 7014 EIDER WHITE WITH SPECIFIED 4" RUBBER BASE. REMOVE WHEN CONSTRUCTION IS COMPLETED.


05 MOUNT TEMPORARY FLUORESCENT LIGHTS TO TEMPORARY CEILING.

## 3 KEYED NOTES





## 4 TEMPORARY LAYOUT SECTION

SCALE: 1"=1'-0"




## 1 KITCHEN PLAN

SCALE: 1/4" = 1'-0"




## 2 TEMPORARY KITCHEN FLOOR PLAN

SCALE: 1/4" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

p

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DRIVE
RICHMOND, TX 77406

SEAL

REGISTERED ARCHITECT
MELISSA A. MADDEN
#29651
STATE OF TEXAS

7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

TEMPORARY KITCHEN LAYOUT
p-A.302

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\P-Pecan Grove ES\p-A.302 TEMPORARY KITCHEN LAYOUT.dwg Jul 23, 2025 - 4:35pm

## RCP - GENERAL NOTES


1. CEILING GRID SHALL BE INSTALLED TO MATCH EXISTING GRID'S POINT OF ORIGIN. THIS WILL REDUCE NEED TO RE-LOCATE ABOVE CEILING DUCTS, SPRINKLER PIPING AND OTHER SUPPORT SYSTEMS.
2. REFER TO SHEET A00-01 FOR GENERAL NOTES. GENERAL NOTES APPLY TO ALL SEVEN SCHOOL KITCHEN REMODELS.
3. LIGHTING LEVELS SHOULD BE 50 FC IN PREPARATION AREAS, WARE WASH AND SERVING LINES, OR MEET MINIMUM HEALTH CODE LEVELS, WHICHEVER ITS GREATER. SEE MEP PLANS
4. REPLACE HVAC DEVICES. REPLACE LIGHTING WITH 24"x24" LED LAY IN LIGHT AS SCHEDULED IN ELECTRICAL PLANS.
5. REFER TO MECHANICAL, ELECTRICAL SHEETS FOR DEVICE SCHEDULES.

## RCP - NUMBERED NOTES

01 PROVIDE 30"x30" MIN. ACCESS HATCH IN SOFFIT CENTERED ON MOTOR.

02 AFTER LOWERING THE NEW POWER RETRACTION SYSTEM. REPAIR AND PAINT SOFFITS AND SIDWALLS OF FURR TO MATCH EXISTING.

## 2 RCP GENERAL NOTES




## 1 REFLECTED CEILING PLAN

SCALE: 1/4" = 1'-0"




## 3 FOOD SERVICE AREA ELEVATION

SCALE: 3/16" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

p

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DRIVE
RICHMOND, TX 77406

SEAL
REGISTERED ARCHITECT
ROBERT W. WILLIAMS
22651
STATE OF TEXAS
7/15/2025



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING


REFLECTED CEILING PLAN

p-A.401


F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\P-Pecan Grove ES\p-A.401 REFLECTED CEILING PLAN.dwg Jul 23, 2025 - 4:35pm





## 3 MOPSINK ELEVATIONS
SCALE: 1/4"=1'-0"




## 4 LOCKER HOUSEKEEPING PAD
SCALE: 3"=1'-0"




## TYPE A
ROOM SIGNAGE - FIXED NAMES




## TYPE B
KITCHEN RESTROOM SIGNAGE

## 7 ROOM SIGNAGE
SCALE: 6"=1'-0"


### PAINT COLOR SCHEDULE
UNLESS OTHERWISE INDICATED FIELD COLOR IS PT-1 (SW 7014 EIDER WHITE)
SW 7014 EIDER WHITE (EPOXY PAINT)

### WALL TILE
CERAMIC WALL TILE (WT-1)
REFER TO TILE PATTERN AT SERVING AND RESTROOM
FIELD WALL TILE: DALTILE RITTENHOUSE SQUARE K175 BISCUIT (3X6)


### QUARRY TILE
QUARRY TILE AND BASE - SURE-STEP II OQ30
TILE COLOR SELECTION TO BE APPROVED BY FBISD
EPOXY GROUT COLOR: STERLING SILVER BY LATICRETE

A — PROVIDE ROOM SIGN TO REPLACE EXISTING. SEE LAYOUT FOR TYPE A OR TYPE B SIGN LOCATIONS.


## 2 FLOOR FINISH LEGEND





## 5 FLOOR TRANSITION - THRESHOLD
SCALE: 3"=1'-0"




## 1 FINISH FLOOR PLAN
SCALE: 1/4" = 1'-0"





## 8 RR ELEVATIONS
SCALE: 1/4"=1'-0"





WALL TILE PATTERN - RESTROOM


## 6 WALL TILE PATTERN
SCALE: 1/4"=1'-0"




## 9 UTILITY ELEVATIONS
SCALE: 1/4"=1'-0"




## 10 STOREFRONT ELEVATIONS
SCALE: 1/4"=1'-0"




## 11 STOREFRONT SECTION
SCALE: 1/2"=1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

p

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DRIVE
RICHMOND, TX 77406

SEAL
STEPHEN HERRED ARCHITECT
REGISTERED
32651
STATE OF TEXAS
7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING


FINISH FLOOR PLAN

p-A.501


F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\P-Pecan Grove ES\p-A.501 FINISH FLOOR PLAN.dwg Jul 28, 2025 - 6:23pm





PARTITION A
SCALE: 1-1/2" = 1'-0"





PARTITION B1
SCALE: 1-1/2" = 1'-0"





PARTITION B2
SCALE: 1-1/2" = 1'-0"




PARTITION B3
SCALE: 1-1/2" = 1'-0"




RTITION B4
1-1/2" = 1'-0"




PARTITION B5
SCALE: 1-1/2" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |

p

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DRIVE
RICHMOND, TX 77406

SEAL

FOR
INTERIM REVIEW
AND NOT INTENDED
FOR CONSTRUCTION,
BIDDING OR PERMIT
PURPOSES.


ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 05/23/25

PARTITION
SCHEDULE

p-A.502

## GENERAL NOTES

1. ALL CONCRETE SHALL TEST 4000 PSI AT 28 DAYS.
2. ALL CONCRETE REINFORCING BARS SHALL CONFORM TO ASTM A615 GRADE 60.
3. DETAILING AND FABRICATION OF CONCRETE REINFORCEMENT AND ACCESSORIES SHALL BE IN ACCORDANCE WITH ACI-315 LATEST EDITION.
4. LAP ALL CONTINUOUS REINFORCING BARS 50 DIAMETERS AT SPLICES, TEES, AND CORNERS.
5. THE USE OF HEAT TO FACILITATE THE BENDING OF REINFORCING BARS WILL NOT BE PERMITTED.
6. NO ENGINEERING DRAWING MAY BE REPRODUCED FOR USE AS SHOP DRAWINGS.
7. CONTRACTOR SHALL COORDINATE ALL LOCATIONS OF ALL ANCHOR BOLTS AND OPENINGS FOR MECHANICAL, PIPING, AND ELECTRICAL EQUIPMENT WITH THE RESPECTIVE ENGINEERING AND VENDOR DRAWINGS.

## SLAB NOTE


4" CONC. SLAB ON 10 MIL POLY FILM ON 2" MAX. SAND FILL. REINFORCE WITH #3 @ 15"c.c. E.W. IN CENTER OF SLAB.

## SLAB SIDEWALK SLAB NOTE

4" CONC. SLAB ON 2" MAX. SAND FILL. REINF. W/ #3 @ 18"c.c. IN CENTER OF SLAB.

## GEOTECHNICAL NOTE:

ALLOWABLE BEARING CAPACITY IS ASSUMED TO BE 1500 PSF AND SHALL BE CONFIRMED PRIOR TO CONSTRUCTION.




FOUNDATION PLAN
SCALE: 1/4"=1'-0"

## FIELD VERIFICATION NOTE

1. CONTRACTOR SHALL VERIFY ALL DIMENSIONS PRIOR TO FABRICATION OR CONSTRUCTION.
2. CONTRACTOR SHALL VERIFY AND NOTIFY ENGINEER OF EXISTING CONDITIONS IN NEED OF REVIEW AND POSSIBLE MODIFICATION PRIOR TO FABRICATION.

ISSUE:

| | |
|---|---|
| 03/07/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DRIVE
RICHMOND, TX 77406


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



REGISTERED PROFESSIONAL ENGINEER
KEN STANLEY
69701
LICENSED
STATE OF TEXAS
*July 17, 2025*


STANLEY SPURLING & HAMILTON, INC.
Consulting Engineering Services
T.B.P.E. Registration # F-000175
www.sshinc.net
3301 Edloe Street, Suite 200 Houston, Texas 77027 Tel 713-776-9433
E-MAIL: info@sshinc.net | 0002-0256



PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

KITCHEN PLAN


S1





1 SECTION
SCALE: 3/4"=1'-0"





2 SECTION
SCALE: 3/4"=1'-0"




3 SECTION
SCALE: 3/4"=1'-0"




4 SECTION
SCALE: 3/4"=1'-0"




## MIN. REBAR LAP SCHEDULE FOR f'm = 1,500 psi

| BAR SIZE | 6" CMU | 8" CMU | 10" CMU | 12" CMU |
|---|---|---|---|---|
| #3 | 12" | 12" | 12" | 12" |
| #4 | 20" | 15" | 12" | 12" |
| #5 | 32" | 23" | 18" | 15" |
| #6 | 54" | 43" | 34" | 28" |
| #7 | NA | 60" | 46" | 38" |
| #8 | NA | 72" | 71" | 57" |
| #9 | NA | NA | 82" | 74" |

## CONCRETE MASONRY NOTES

1. CONCRETE MASONRY UNITS AND CONSTRUCTION TO BE PER "NATIONAL CONCRETE MASONRY ASSOCIATION" RECOMMENDATIONS (WHERE NOT COVERED BY THE LOCAL BUILDING CODE).
2. ALL MASONRY GROUT TO BE PER TABLE 1 (THIS SHEET); ALL MORTAR PER TABLE 2 (THIS SHEET).
3. FILL CELLS WITH GROUT AT VERTICAL REINFORCEMENT.
4. CAST-IN-ANCHORS EMBEDDED IN CONCRETE MASONRY SHALL EXTEND BEYOND REINFORCING 1" MIN.
5. COMPRESSIVE STRENGTH OF MASONRY SHALL BE 1500 PSI AT 28 DAYS.
6. CMU SHALL BE PLACED IN A RUNNING BOND PATTERN UNLESS SPECIFICALLY NOTED OTHERWISE ON THE PLANS.
7. CONTROL JOINTS SHALL HAVE NO HORIZONTAL REINFORCING THROUGH THE JOINT AND VERTICAL REINFORCING ON BOTH SIDES OF JOINT. CONTROL JOINTS SHALL BE UNGROUTED WITH A BACKER ROD AND SEALANT ON BOTH SIDES OF WALL.
8. BOND BEAMS AND REINFORCING SHALL BE CONTINUOUS AT CONTROL JOINT WITH BACKER ROD AND SEALANT CONTINUOUS WITH JOINT.

## CONCRETE BLOCK LINTEL SCHEDULE

| WALL THICKNESS \ MAXIMUM SPAN | 4'-6" | 9'-0" |
|---|---|---|
| 4" | GROUT 1 COURSE 1~#4 CONT. | #3 STIRRUPS @ 16" c.c. GROUT 2 COURSES 1~#4 CONT. |
| 6" 8" & 12" | GROUT 1 COURSE 2~#5 CONT. | #3 STIRRUPS @ 16" c.c. GROUT 2 COURSES 2~#5 CONT. TOP & BOT. |

## TABLE 1. GROUT PROPORTIONS BY VOLUME

| TYPE | PARTS BY VOLUME OF PORTLAND CEMENT OR PORTLAND BLAST-FURNACE SLAG CEMENT | PARTS BY VOLUME OF HYDRATED LIME OR LIME PUTTY | AGGREGATE MEASURED IN DAMP, LOOSE CONDITION | |
|---|---|---|---|---|
| | | | FINE | COARSE |
| FINE GROUT (<4" WIDE CAVITY) | 1 | 0 TO 1/10 | 2¼ TO 3 TIMES THE SUM OF THE VOLUMES OF THE CEMENTITIOUS MATERIAL | |
| COARSE GROUT (>4" WIDE CAVITY) | 1 | 0 TO 1/10 | 2¼ TO 3 TIMES THE SUM OF THE VOLUMES OF THE CEMENTITIOUS MATERIAL | 1 TO 2 TIMES THE SUM OF THE VOLUMES OF THE CEMENTITIOUS MATERIAL |

## TABLE 2. MORTAR PROPORTIONS BY VOLUME

| MATERIAL | TYPE | PORTLAND CEMENT OR BLENDED CEMENT | MASONRY CEMENT | HYDRATED LIME OR LIME PUTTY | AGGREGATE RATIO (MEASURE IN DAMP, LOOSE CONDITION) |
|---|---|---|---|---|---|
| CEMENT LIME | S | 1 | .... | OVER ¼ TO ½ | NOT LESS THAN 2¼ & NOT MORE THAN 3 TIMES THE SUM OF THE SEPARATE VOLUMES OF CEMENTITIOUS MATERIALS |
| MASONRY/ CEMENT | S | 1/2 | 1 | .... | |


NOTE: CONTROL JOINTS SHALL BE LOCATED AT THE FOLLOWING

1. AT ALL CHANGES IN WALL HEIGHT.
2. AT ALL CHANGES IN WALL THICKNESS SUCH AS CHASES, COLUMNS OR PILASTERS.
3. AT (ABOVE) MOVEMENT JOINTS IN FOUNDATIONS AND FLOORS.
4. AT (BELOW) MOVEMENT JOINTS IN ROOFS AND FLOORS THAT BEAR ON A WALL.
5. ADJACENT TO CORNERS OF WALLS OR INTERSECTIONS WITHIN A DISTANCE OF ONE-HALF THE NORMAL CONTROL JOINT SPACING.
6. CONTROL JOINTS SHALL BE SPACED NO MORE THAN 25'-0" APART.
7. DO NOT PLACE CONTROL JOINT ABOVE OR BELOW OPENINGS.
8. CONTRACTOR SHALL PROVIDE A CONTROL JOINT PLAN PRIOR TO FABRICATION OR CONSTRUCTION.

## LOOSE LINTEL SCHEDULE

| SPAN | LINTEL | SPAN | LINTEL |
|---|---|---|---|
| 0' TO 6' | L3½x3½x5/16 | 8' TO 9' | L5x3½x5/16 |
| 6' TO 7' | L4x3½"x¼ | 9' TO 10' | L6x3½x5/16 |
| 7' TO 8' | L4x3½x5/16 | 10' TO 12' | L7x4x⅜ |

LOOSE LINTEL MIN. BEARING OF 8".




CONTRACTOR SHALL COVER ALL EXPOSED REBAR DURING CONSTRUCTION.

TYPICAL REBAR CAP DETAIL
SCALE: N.T.S.

TYPICAL ELEVATION OF CONCRETE MASONRY WALL AND NOTES
SCALE: N.T.S.

ISSUE:

| | |
|---|---|
| 03/07/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DRIVE
RICHMOND, TX 77406


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

SECTIONS AND TYPICAL DETAILS

S2




July 17, 2025


STANLEY SPURLING & HAMILTON, INC.
Consulting Engineering Services
T.B.P.E. Registration # F-000175
www.sshinc.net
50 Years
3301 Edloe Street, Suite 200 Houston, Texas 77027 Tel 713-776-9433
E-MAIL: info@sshinc.net
0002-0256

# REFER TO FOODSERVICE DESIGN PROFESSIONALS SPECIFICATIONS AND SUBSEQUENT SHEETS FOR ADDITIONAL COORDINATION INFORMATION

**EXISTING EQUIPMENT NOTES (IF EXISTING EQUIPMENT IS PROVIDED IN THIS PROJECT):**

1. EXISTING EQUIPMENT NOT SCHEDULED FOR RE-USE TO BE RELOCATED BY THE K.E.C. COORDINATE WITH OWNER FOR NEW LOCATION.
2. ALL UTILITIES NOT SCHEDULED FOR RE-USE TO BE CAPPED & COVERED BY REQUIRED DISCIPLINE.
3. K.E.C. TO VERIFY ALL EXISTING UTILITY LOCATIONS & COORDINATE WITH ALL EQUIPMENT AS REQUIRED.

8 EXISTING EQUIPMENT NOTES
NOT TO SCALE

**ARCHITECT TO VERIFY/COORDINATE THE AESTHETIC OPTIONS BELOW (FOOD SERVICE COLOR, MATERIAL, OR SIGNAGE SELECTIONS) IF THESE ITEMS ARE PROVIDED IN THIS PROJECT:**

1. COUNTERTOPS: STONE (STAINLESS STEEL IS PROVIDED UNLESS OTHERWISE SPECIFIED).
2. TRAY SLIDES: CORIAN OR STONE (STAINLESS STEEL IS PROVIDED UNLESS OTHERWISE SPECIFIED).
3. COUNTER FRONTS: CERAMIC TILE, 3 FORM, OR PLASTIC LAMINATE.
4. SNEEZE GUARDS: STONE INSETS.
5. GENERAL COLOR, MATERIAL AND GRAPHIC SELECTIONS:
   - A. DISPLAY AIR SCREEN MERCHANDISERS - COLOR SELECTION: POWDER COAT OR PLASTIC LAMINATE (S/S IS PROVIDED UNLESS OTHERWISE SPECIFIED).
   - B. BAKERY DISPLAY CASES - COLOR SELECTION: POWDER COAT OR PLASTIC LAMINATE (S/S IS PROVIDED UNLESS OTHERWISE SPECIFIED).
   - C. PASS THRU OR REACH IN HOLDING CABINETS - COLOR SELECTION: POWDER COAT (MFG.: TRUE) OR PLASTIC LAMINATE (MFG.: TRAULSEN) (S/S IS PROVIDED UNLESS OTHERWISE SPECIFIED).
   - D. HANGING HEAT LAMPS - TRACK AND FIXTURE COLOR SELECTION.
   - E. HEATED MERCHANDISERS.
   - F. PORTABLE GUIDE RAILS - STANCHION AND BELT COLOR SELECTION.
   - G. POPCORN MACHINE - SIGNAGE SELECTION.
   - H. BOTTLE COOLER - SIGNAGE SELECTION.
   - I. GRAPHICS PACKAGE INFORMATION.
   - J. HOT FOOD WELL COVERS.
6. ARCHITECT TO VERIFY/COORDINATE THE FINISHES BELOW:
   - A. WALLS: CERAMIC TILE, FLAT FRP, OR MOLDED FRP (SMOOTH, IMPERVIOUS, AND EASILY CLEANABLE AS APPROVED BY LOCAL JURISDICTION).
   - B. CEILINGS: REMOVABLE VINYL FACE TILE (SMOOTH, IMPERVIOUS, AND EASILY CLEANABLE AS APPROVED BY LOCAL JURISDICTION).
   - C. FLOORS: TILE, EPOXY, OR RUBBERIZED FLOORING SYSTEM (SMOOTH, IMPERVIOUS, EASILY CLEANABLE AND SLIP RESISTANT AS APPROVED BY LOCAL JURISDICTION) (COORDINATE FLOOR TILE TRANSITION AT SERVING LINES).
   - D. FLOORS: WALK-IN ASSEMBLY - EXTEND KITCHEN FLOOR FLUSH INTO WALK-IN ASSEMBLY WITH COVED BASE.
   - E. FURR DOWNS ABOVE SERVING COUNTERS.

5 ARCHITECTURAL COORDINATION NOTES
NOT TO SCALE

**CRITICAL NOTES:**

1. CONTRACTOR MUST COORDINATE AND VERIFY ALL DIMENSIONS WITH FOOD SERVICE EQUIPMENT SHOP DRAWINGS AND MANUFACTURER'S DATA. DIMENSIONS SHOWN ARE FOR DESIGN AND BIDDING PURPOSES ONLY.
2. WALK-IN ASSEMBLY DOORS MUST BE LEFT OPEN WHILE INTERIOR CONCRETE FLOOR CURES.
3. INSTALL PROTECTIVE COVER ON WALK-IN ASSEMBLY WALL PANELS BEFORE INSTALLING CONCRETE FLOORS AND CURBS.
4. REFER TO GENERAL SPECS - DIVISION 27 TO PROVIDE CONDUIT, DATA, AND INTERCONNECT THE PANIC ALARM INSIDE FREEZER TO THE BUILDING AUTOMATION SYSTEM FOR NOTIFICATION TO DISTRICT PERSONNEL IN THE EVENT OF STAFF ENTRAPMENT.
5. PIPING AND DRAINAGE SYSTEMS (SANITARY AND GREASE-LADEN). SYSTEMS MUST BE CLEANED AND FLUSHED BEFORE THE FINAL CONNECTION WITH FOOD SERVICE EQUIPMENT - CRITICAL (DIV. 22).

7 CRITICAL NOTES
NOT TO SCALE

**DIVISION 26 (ELECTRICAL) IS RESPONSIBLE FOR BUT NOT LIMITED TO:**

1. **DO NOT ROUGH IN FROM FDP DRAWINGS. REFER TO THE KITCHEN EQUIPMENT CONTRACTOR'S DIMENSIONED SHOP DRAWINGS. DIMENSIONS INDICATED ARE TO BE VERIFIED BY KITCHEN EQUIPMENT CONTRACTOR AND ADJUSTED AS REQUIRED BY EQUIPMENT AND FIELD CONDITIONS.**
2. SECTION 11 40 00 TO VERIFY UTILITY REQUIREMENTS OF ANY EXISTING EQUIPMENT.
3. ALL CONNECTIONS SHALL BE MADE FOLLOWING LOCAL CODES AND NATIONAL STANDARDS, EXCEPT WHERE PLANS AND SPECIFICATIONS EXCEED THOSE CODES AND STANDARDS.
4. VERIFY ALL ELECTRICAL REQUIREMENTS WITH ENGINEERING DRAWINGS.
5. ROUGH-IN AND FINAL CONNECTION OF ELECTRICAL SYSTEMS TO FOOD SERVICE EQUIPMENT, WALK-IN ASSEMBLIES, AND BETWEEN COMPONENTS (INCLUDING MATERIALS AND LABOR). ACCESSORIES PROVIDED LOOSE WITH FOOD SERVICE EQUIPMENT BY SECTION 11 40 00 TO BE FIELD INSTALLED BY DIVISION 26.
6. EMPTY EMT CONDUIT WITH PULL-WIRE AND WIDE-SWEEP BENDS FOR REFRIGERANT PIPING TO REMOTE FOOD SERVICE EQUIPMENT REFRIGERATION SYSTEMS.
7. EMPTY EMT CONDUIT WITH PULL-WIRE AND WIDE-SWEEP BENDS FOR INTERCONNECT CABLES BETWEEN LAN AND POS TERMINALS, CHANGE-MAKERS, PRE-CHECK UNITS, PRINTERS, CPUS, ETC. DIVISION 26 TO VERIFY WHERE THE CONDUIT IS TO RUN FOR POS SYSTEM (I.E., MANAGER'S OFFICE OR IDF ROOM).
8. EMPTY EMT CONDUIT WITH PULL-WIRE AND WIDE-SWEEP BENDS FOR FIRE SUPPRESSION SYSTEMS. INTERCONNECT FIRE PROTECTION SYSTEM TO PANEL BOX SHUNT TRIPS AND BUILDING ALARM.
9. WALK-IN LIGHT FIXTURE INSTALLATION (PROVIDED LOOSE BY SECTION 11 40 00) (IF WALK-IN IS PROVIDED IN THIS PROJECT).
10. TABLE LIMIT SWITCH INSTALLATION (PROVIDED LOOSE BY SECTION 11 40 00) (IF DISHMACHINE IS PROVIDED IN THIS PROJECT).
11. ELECTRICAL MATERIALS AND DEVICES (SHUNT-TRIP BREAKERS, SURGE PROTECTORS, LIGHTING CONTROL DEVICES, CONDUIT, WIRE, ETC.).
12. SWITCHES AND STAINLESS STEEL DISCONNECTS AS REQUIRED (PROVIDE, LOCATE, AND INSTALL – TO BE IN AN ACCESSIBLE LOCATION).
13. CHARGING STATIONS FOR FORKLIFTS, PALLET STACKERS, AND PALLET JACKS (SIZE, PROVIDE, LOCATE, AND INSTALL) (IF EQUIPMENT IS PROVIDED IN THIS PROJECT).
14. INTERCONNECTION BETWEEN CONDENSATE FAN AND DISHMACHINE CONTROL PANEL (IF EQUIPMENT IS PROVIDED IN THIS PROJECT).
15. INTERCONNECTION BETWEEN EXHAUST HOOD FANS AND SWITCH (IF EQUIPMENT IS PROVIDED IN THIS PROJECT).
16. INTERCONNECTION BETWEEN EXHAUST HOOD LIGHTS AND SWITCH (IF EQUIPMENT IS PROVIDED IN THIS PROJECT).
17. DOOR HEATERS, LIGHTS, COILS, AND PRESSURE RELIEF PORTS PRE-WIRED TO JUNCTION BOX AT TOP OF WALK-IN ASSEMBLIES (IF EQUIPMENT IS PROVIDED IN THIS PROJECT) PROVIDED BY SECTION 11 40 00. FINAL CONNECTION BY DIV. 26.
18. IF ANY ELECTRICAL ACCESSORIES, FITTINGS, AND CORD/PLUGS ARE PROVIDED LOOSE WITH EQUIPMENT BY 11 40 00, DIV.26 IS TO ATTACH TO EQUIPMENT AND PROVIDE FINAL CONNECTION.
19. PROVIDE WATERPROOF RECEPTACLES IN WET AREAS.
20. ALL ELECTRICAL CONNECTIONS BENEATH EXHAUST HOODS (IF EQUIPMENT IS PROVIDED IN THIS PROJECT) TO EXTEND TO SHUNT TRIP BREAKERS WITH ELECTRICAL PANEL BOX FOR SHUTDOWN DURING FIRE MODE.
21. RECEPTACLES ARE TO BE PRE-WIRED TO THE JUNCTION BOX OR LOAD CENTER FOR FINAL CONNECTION BY DIVISION 26.
22. ALL ELECTRICAL LIGHTING, POWER, AND DISTRIBUTION SYSTEMS.
23. DO NOT INTERCONNECT MORE THAN THREE (3) CONVENIENCE OUTLETS ON ONE (1) BREAKER.
24. OTHER THAN CONVENIENCE OUTLETS, ALL ELECTRICAL CONNECTIONS SHOWN ON FOOD SERVICE PLANS ARE DEDICATED BREAKERS.
25. DOORBELL AT RECEIVING DOOR (PROVIDE AND INSTALL – TO BE AUDIBLE THROUGHOUT KITCHEN, OFFICE, AND DRY STORAGE ROOM).
26. ADEQUATE LIGHTING AT RECEIVING DOOR.
27. PROVIDE AND INSTALL TWO EMERGENCY STROBE BEACONS THAT INTERCONNECT TO PANIC ALARM IN WALK-IN FREEZER. ONE (1) IN KITCHEN ABOVE WALK-IN FREEZER DOOR ONE (1) IN CAFETORIUM (IF WALK-IN IS PROVIDED IN THIS PROJECT). REFER TO GENERAL SPECIFICATIONS FOR ADDITIONAL DETAILS.
28. DEDICATED CIRCUIT FOR HEATED DRAIN LINE CONNECTION IN WALK-IN FREEZER AT EACH COIL (IF WALK-IN IS PROVIDED IN THIS PROJECT).

**NOTE: ELECTRICAL CONNECTIONS INDICATED ARE THOSE REQUIRED FOR THE FOOD SERVICE EQUIPMENT AND THOSE REQUIRED FOR SUPPORT EQUIPMENT FURNISHED BY DIVISION 26. FOR ADDITIONAL REQUIREMENTS, REFER TO THE ELECTRICAL ENGINEER'S DRAWINGS.**

6 ELECTRICAL COORDINATION NOTES
NOT TO SCALE

**DIVISION 22 (PLUMBING) RESPONSIBLE FOR BUT NOT LIMITED TO:**

1. **DO NOT ROUGH-IN FROM FDP DRAWINGS. REFER TO THE KITCHEN EQUIPMENT CONTRACTOR'S DIMENSIONED SHOP DRAWINGS. DIMENSIONS INDICATED ARE TO BE VERIFIED BY KITCHEN EQUIPMENT CONTRACTOR AND ADJUSTED AS REQUIRED BY EQUIPMENT AND/OR FIELD CONDITIONS.**
2. SECTION 11 40 00 TO VERIFY UTILITY REQUIREMENTS OF ANY EXISTING EQUIPMENT.
3. ALL CONNECTIONS SHALL BE MADE IN ACCORDANCE WITH LOCAL CODES AND NATIONAL STANDARDS, EXCEPT WHERE PLANS AND SPECIFICATIONS EXCEED THOSE CODES AND STANDARDS.
4. VERIFY ALL PLUMBING REQUIREMENTS WITH ENGINEERING DRAWINGS.
5. EMPTY PVC CONDUIT WITH WIDE-SWEEP BENDS FOR REFRIGERANT PIPING TO BEVERAGE LINES, CO2 LINES, AND REMOTE FOOD SERVICE EQUIPMENT REFRIGERATION SYSTEMS.
6. ROUGH-IN AND FINAL PLUMBING CONNECTIONS TO FOOD SERVICE EQUIPMENT AND BETWEEN COMPONENTS (INCLUDING MATERIALS AND LABOR). ACCESSORIES PROVIDED LOOSE WITH FOOD SERVICE EQUIPMENT BY SECTION 11 40 00 TO BE FIELD INSTALLED BY DIVISION 22. THIS INCLUDES BUT IS NOT LIMITED TO INSTALLATION OF ALL FAUCETS (WATER FILL FAUCETS, PRE-RINSE FAUCETS, ETC.), HOSES, GAS DISCONNECTS, AND DRAINS FROM EQUIPMENT POINT OF CONNECTION TO BUILDING PLUMBING SYSTEMS. ALL DRAIN LINES ARE PROVIDED AND INSTALLED BY DIV. 22.
7. KITCHEN EQUIPMENT CONTRACTOR IS RESPONSIBLE FOR PROVIDING ALL FAUCETS (WATER FILL FAUCETS, PRE-RINSE FAUCETS, ETC.), DRAIN FITTINGS, MIXING VALVES, CONTROL VALVES, WATER PRESSURE REGULATORS, VACUUM BREAKERS, AND ALL ACCESSORIES FOR EQUIPMENT SPECIFIED UNDER 11 40 00. DIVISION 22 IS RESPONSIBLE FOR INSTALLATION.
8. INDIRECT DRAIN LINE RUNS FROM EQUIPMENT TO NEAREST DRAIN OR FLOOR SINK. LINES TO BE TYPE 'K' COPPER.
9. IF ANY PLUMBING ACCESSORIES OR FITTINGS ARE PROVIDED LOOSE WITH EQUIPMENT BY 11 40 00, DIV. 22 IS TO ATTACH TO EQUIPMENT AND PROVIDE FINAL CONNECTION.
10. GAS SUPPLY SYSTEMS WITH ALL COMPONENTS AND FITTINGS AS REQUIRED FOR A COMPLETE SYSTEM.
11. WATER SUPPLY SYSTEMS WITH ALL COMPONENTS AND FITTINGS AS REQUIRED FOR A COMPLETE SYSTEM.
12. COMPRESSED AIR SYSTEMS WITH ALL COMPONENTS AND FITTINGS AS REQUIRED FOR A COMPLETE SYSTEM (IF REQUIRED FOR THIS PROJECT).
13. PIPING AND DRAINAGE SYSTEMS (SANITARY AND GREASE-LADEN). SYSTEMS MUST BE CLEANED AND FLUSHED BEFORE THE FINAL CONNECTION WITH FOOD SERVICE EQUIPMENT - CRITICAL.
14. FLOOR SINKS (PROVIDE AND INSTALL). FLANGE AND GRATES TO BE FLUSH WITH FINISHED FLOOR.
15. FLOOR DRAINS (PROVIDE AND INSTALL). FLANGE AND GRATES TO BE FLUSH WITH FINISHED FLOOR.
16. TRENCH DRAINS (PROVIDE AND INSTALL). TRENCH LINERS PROVIDED BY 11 40 00. FLANGE AND LINERS TO BE FLUSH WITH FINISHED FLOOR.
17. GREASE TRAPS AS REQUIRED. VERIFY WITH LOCAL CODES TO BYPASS OR PIPE THRU GREASE TRAP AND/OR INTERCEPTOR.
18. P-TRAPS AS REQUIRED (INCLUDING ALL DISPOSERS).
19. INTERCONNECT WATER THRU WATER FILTER (FILTER PROVIDED BY 11 40 00 UNLESS OTHERWISE SPECIFIED) TO EQUIPMENT.
20. GAS QUICK DISCONNECT INSTALLATION (QUICK DISCONNECT PROVIDED BY 11 40 00).
21. SAFETY RESTRAINT CABLE INSTALLATION (SAFETY RESTRAINT CABLE PROVIDED BY 11 40 00).
22. SPECIFIED COUPLINGS AND PIPING TO ALL EQUIPMENT FURNISHED BY 11 40 00.
23. AIR COMPRESSORS (IF REQUIRED FOR THIS PROJECT) (SIZE, PROVIDE, AND INSTALL, UNLESS OTHERWISE SPECIFIED).
24. WATER SOFTENERS (IF REQUIRED FOR THIS PROJECT) (SIZE, PROVIDE, AND INSTALL, UNLESS OTHERWISE SPECIFIED).
25. PRESSURE BOILERS (IF REQUIRED FOR THIS PROJECT) (SIZE, PROVIDE, AND INSTALL, UNLESS OTHERWISE SPECIFIED).
26. HAND SINKS (PROVIDE (UNLESS OTHERWISE SPECIFIED) AND INSTALL). PROVIDE HOT WATER TEMPERING VALVE IF REQUIRED. WATER TEMPERATURE TO BE AT LEAST 100 DEGREES AND FLOW FOR AT LEAST 20 SECONDS.
27. ICE BIN DRAIN INSULATION (IF ICE MACHINE IS PROVIDED IN THIS PROJECT) (PROVIDE AND INSTALL).
28. UNIONS AT DISPOSER SOLENOID VALVES (IF DISPOSER IS PROVIDED IN THIS PROJECT) (PROVIDE AND INSTALL).
29. BACK FLOW PREVENTION AS REQUIRED (PROVIDE AND INSTALL - INCLUDING ALL DISPOSERS). BACK- SIPHONAGE SHALL BE INSTALLED AT ALL FIXTURES AND EQUIPMENT WHERE BACKFLOW AND/OR BACK-SIPHONAGE MAY OCCUR AND WHERE A MINIMUM AIR GAP CANNOT BE PROVIDED BETWEEN THE WATER TO THE FIXTURE OR EQUIPMENT AT ITS FLOOD/LEVEL RIM. VACUUM BREAKERS, WHEN FURNISHED WITH EQUIPMENT, SHALL OVERRIDE THE ABOVE, IF ACCEPTABLE WITH APPLICABLE CODES. DIVISION 22 RESPONSIBLE FOR VERIFYING REQUIREMENT WITH LOCAL CODES.
30. JANITOR SINK WITH FAUCET (PROVIDE AND INSTALL).
31. FREEZE PROOF HYDRANT AT EXTERIOR OF BUILDING BY RECEIVING DOOR (PROVIDE AND INSTALL).
32. REVERSE OSMOSIS SYSTEMS (SIZE, PROVIDE (UNLESS OTHERWISE SPECIFIED), LOCATE AND INSTALL).
33. ALL PIPING WITHIN COUNTER BODY OR UNDER FABRICATED COUNTERS TO BE RUN TO A CONNECTION POINT BELOW COUNTER BODY BY SECTION 11 40 00. FINAL CONNECTION BY DIVISION 22.
34. EXHAUST HOOD CONDENSATE DRAIN CONNECTIONS (IF EXHAUST HOOD IS PROVIDED IN THIS PROJECT) (PROVIDE AND INSTALL).
35. INTERCONNECTION OF 1/2" CW TO PRE-RINSE AND DISPOSERS CONE/BODY INLETS PIPED THROUGH SOLENOID AND VACUUM BREAKER (IF DISPOSER IS PROVIDED IN THIS PROJECT).
36. FIRE SYSTEM PIPING. EXPOSED PIPING TO BE CHROME PLATED.
37. PIPE 1/2" COLD WATER TO SWIRL INLETS AT DISPOSERS (IF DISPOSER IS PROVIDED IN THIS PROJECT).
38. WATER TREATMENT FOR ICE BUILDERS (NON-CHLORINATED WATER WITH A PH LEVEL OF 10 OR HIGHER) AND ANY DRAINS AND OVERFLOWS. PIPING FROM ICE BUILDERS TO TUMBLE CHILLERS BY DIV. 23 (IF ICE BUILDERS AND TUMBLE CHILLERS ARE PROVIDED IN THIS PROJECT).

**NOTE: WATER AND DRAIN CONNECTIONS INDICATED ARE THOSE REQUIRED FOR THE FOOD SERVICE EQUIPMENT AND THOSE REQUIRED FOR SUPPORT EQUIPMENT FURNISHED BY DIVISION 22. FOR ADDITIONAL WATER AND DRAIN REQUIREMENTS REFER TO MECHANICAL DRAWINGS.**

**NOTE: REFER TO ELECTRICAL/MECHANICAL DRAWINGS FOR REQUIREMENTS OF EXHAUST FANS AND MAKE-UP AIR HANDLERS AND LOCATION OF AN INTERLOCK AND START/STOP CONTROLS TO BE LOCATED WITHIN FOOD SERVICE AREA BY DIVISION 26.**

4 PLUMBING COORDINATION NOTES
NOT TO SCALE

**DIVISION 23 (MECHANICAL) RESPONSIBLE FOR BUT NOT LIMITED TO:**

1. **DO NOT ROUGH-IN FROM FDP DRAWINGS. REFER TO THE KITCHEN EQUIPMENT CONTRACTOR'S DIMENSIONED SHOP DRAWINGS. DIMENSIONS INDICATED ARE TO BE VERIFIED BY KITCHEN EQUIPMENT CONTRACTOR AND ADJUSTED AS REQUIRED BY EQUIPMENT AND/OR FIELD CONDITIONS.**
2. SECTION 11 40 00 TO VERIFY UTILITY REQUIREMENTS OF ANY EXISTING EQUIPMENT.
3. ALL CONNECTIONS SHALL BE MADE FOLLOWING LOCAL CODES AND NATIONAL STANDARDS, EXCEPT WHERE PLANS AND SPECIFICATIONS EXCEED THOSE CODES AND STANDARDS.
4. VERIFY ALL MECHANICAL REQUIREMENTS WITH ENGINEERING DRAWINGS.
5. EMPTY EMT CONDUIT WITH PULL-WIRE AND WIDE-SWEEP BENDS FOR REFRIGERANT PIPING TO REMOTE FOOD SERVICE EQUIPMENT REFRIGERATION SYSTEMS.
6. ROUGH-IN AND FINAL CONNECTION OF MECHANICAL SYSTEMS TO FOOD SERVICE EQUIPMENT, WALK-IN ASSEMBLIES, AND BETWEEN COMPONENTS (INCLUDING MATERIALS AND LABOR).
7. TESTING AND BALANCING FOR ROOMS AND EXHAUST HOODS TO BE PERFORMED BY MECHANICAL CONTRACTOR. BALANCE REPORT FOR FOOD SERVICE EXHAUST HOODS TO BE PROVIDED TO FOODSERVICE DESIGN PROFESSIONALS (FDP) IMMEDIATELY UPON COMPLETION (SEND TO HOUSTON.SUBMITTAL@FDP.ORG FOR HOUSTON OFFICE AND DALLAS.SUBMITTAL@FDP.ORG FOR DALLAS OFFICE) AND MUST BE SUBMITTED WITH O&M MANUALS.
8. EXHAUST HOODS, CONDENSATE HOODS, FIRE SUPPRESSION SYSTEMS, CONNECTIONS AND CONTROLS (PROVIDE AND INSTALL – *UNLESS OTHERWISE SPECIFIED*). PROVIDE TEMPERED AIR AT ALL SUPPLY DUCTS.
   - A. IF EXHAUST/CONDENSATE HOODS AND FIRE SUPPRESSION SYSTEMS ARE SPECIFIED UNDER SECTION 11 40 00, DIVISION 23 IS RESPONSIBLE FOR ALL EXHAUST AND CONDENSATE HOOD CONNECTIONS (PROVIDE AND INSTALL).
9. VFD SYSTEM AND CONTROLLERS, WHEN REQUIRED BY CODE (PROVIDE AND INSTALL).
10. PROVIDE AND INSTALL ALL VENTILATION (DIRECT OR INDIRECT), AIR CONDITIONING AND HEATING SYSTEMS (UNLESS OTHERWISE SPECIFIED).
11. COORDINATE SUPPLY AND RETURN DUCTS ABOVE SERVING COUNTERS OR OPEN-AIR REFRIGERATED MERCHANDISERS. NO COLD AIR TO BLOW DIRECTLY ON HOT FOOD COUNTERS.
12. COORDINATE SUPPLY AND RETURN DUCTS AWAY FROM EQUIPMENT WITH TOP MOUNTED REFRIGERATION. NO COLD AIR TO BLOW DIRECTLY ON COMPRESSORS.
13. MECHANICAL CONTRACTOR TO LOCATE TEMPERATURE MONITORS WITHIN RETURN DUCTS.
14. CIRCULATING AIR ABOVE WALK-IN ASSEMBLIES (PROVIDE AND INSTALL).
15. CIRCULATING AIR ABOVE AND IN AIR GAPS AT WAREHOUSE COLD STORAGE ASSEMBLIES (PROVIDE AND INSTALL).
16. WATER CHILLERS AS REQUIRED (IF EQUIPMENT IS PROVIDED IN THIS PROJECT) (PROVIDE, SIZE AND LOCATE).
17. PIPING FROM ICE BUILDERS TO TUMBLE CHILLERS (IF EQUIPMENT IS PROVIDED IN THIS PROJECT) (PROVIDE, SIZE AND LOCATE).

3 MECHANICAL COORDINATION NOTES
NOT TO SCALE

**GENERAL CONTRACTOR RESPONSIBLE FOR BUT NOT LIMITED TO:**

1. ANY WALL PENETRATION REQUIRED FOR FOOD SERVICE EQUIPMENT UTILITIES. ESCUTCHEON PLATES OR S/S SLEEVES TO BE PROVIDED AND INSTALLED AS NEEDED.
2. BULK FREEZER VENTILATION PIPE (IF BULK FREEZER IS PROVIDED IN THIS PROJECT) (PROVIDE AND INSTALL, UNLESS OTHERWISE SPECIFIED).
3. CORE DRILLING FOR GUIDE RAILS (IF GUIDE RAILS ARE PROVIDED IN THIS PROJECT).
4. REFRIGERATION ROOF CURBS / ROOF JACK (IF REFRIGERATION SYSTEM IS PROVIDED IN THIS PROJECT AND LOCATED ON ROOF).
5. INTERIOR BOLLARDS (IF REQUIRED FOR THIS PROJECT) – TO BE EPOXY PAINTED PER LOCAL CODES (PROVIDE AND INSTALL).
6. FURNISH AND INSTALL 3/4" PLYWOOD BLOCKING IN THE WALL FOR MOUNTING EQUIPMENT FURNISHED BY SECTION 11 40 00 AS REQUIRED.
7. WALK-IN DEPRESSIONS (TO BE DEAD LEVEL) AND SAND LEVELING BED (IF WALK-IN IS PROVIDED IN THIS PROJECT AND RECESS IS SHOWN).
8. STRUCTURAL BRACING FOR BULK WALK-IN CEILING PANELS IF REQUIRED.
9. MENU SYSTEM VIDEO MONITORS IN SERVERY (UNLESS OTHERWISE SPECIFIED).
10. STRUCTURAL BRACING FOR MENU SYSTEM VIDEO MONITORS IF REQUIRED.
11. INTERIOR/EXTERIOR REFRIGERATION PENETRATIONS AND SLEEVES AT BUILDING PENETRATIONS.
12. DOORSCOPE VIEWER (PEEPHOLE) WITH WIDE VIEWING ANGLE AT RECEIVING DOOR.
13. CANOPY AT RECEIVING DOOR. COORDINATE HEIGHT WITH THE HEIGHT OF RECEIVING DOOR (8') AND THE MOUNTING HEIGHT OF AIR SCREEN ABOVE THE DOOR.
14. SOAP AND TOWEL DISPENSER PROVIDED BY OWNER. G.C. RESPONSIBLE FOR INSTALLATION.
15. WASHER AND DRYER (PROVIDE AND INSTALL, UNLESS OTHERWISE SPECIFIED).
16. DWARF WALL AT EXPOSED FRONT/ENDS OF CAFETERIA SERVING COUNTERS WITH FINISH AS SELECTED BY ARCHITECT (IF REQUIRED IN THIS PROJECT).

2 GENERAL CONTRACTOR COORDINATION NOTES
NOT TO SCALE

**HEALTH DEPARTMENT REQUIREMENTS (VERIFY WITH LOCAL JURISDICTIONS):**

1. FLOORS: VERIFY WITH DIVISION 9. FLOORS TO BE SMOOTH, IMPERVIOUS, EASILY CLEANABLE AND SLIP RESISTANT.
2. WALLS: VERIFY WITH ARCHITECTURAL DOCUMENTS. WALLS TO BE SMOOTH, IMPERVIOUS, AND EASILY CLEANABLE.
3. CEILING: LAY-IN TILES. CEILING TILES TO BE SMOOTH, IMPERVIOUS, AND EASILY CLEANABLE.
4. EMPLOYEE TOILET: TO BE LOCATED OFF MAIN CORRIDOR AND ADJACENT TO MAIN KITCHEN. RESTROOM MUST HAVE A VESTIBULE AND NOT OPEN TO KITCHEN / PREP AREAS. TOILETS TO BE WELL VENTILATED.
5. LAVATORIES: WALL HUNG LAVATORIES LOCATED WITHIN ALL FUNCTIONAL WORKING AREAS.
6. UTENSIL CLEANING/SANITIZING: ACCOMPLISHED IN UTENSIL WASH AREA WITH (3) 2'-0" x 2'-2" x 15" MINIMUM DEEP SINKS AND WAREWASH MACHINE.
7. MECHANICAL CLEANING/SANITIZING OF TABLEWARE: ACCOMPLISHED BY WAREWASH MACHINE.
8. STOREROOMS: AMPLE DAILY STORAGE PROVIDED IN ENCLOSED STORE ROOMS. STORE ROOMS TO BE VENTILATED AND MAINTAIN PROPER TEMPERATURE.
9. WATER HEATER: LOCATED IN THE MECHANICAL ROOM ADJACENT TO KITCHEN. TO BE SIZED TO PROVIDE AMPLE WATER TO MAINTAIN PROPER WATER TEMPERATURE THROUGHOUT HOURS OF OPERATION.
10. GREASE TRAP: LOCATED AT EXTERIOR OF BUILDING. REFER TO ENGINEER'S DRAWINGS.
11. FOOD SERVICE EQUIPMENT: ALL FLOOR-MOUNTED EQUIPMENT IS TO BE SEALED TO THE FLOOR TO PROVIDE AN EASILY CLEANABLE SURFACE AND PREVENT SEEPAGE. EQUIPMENT NOT MOUNTED TO THE FLOOR IS TO BE WALL MOUNTED ON WALL CARRIERS, OR ELEVATED ON LEGS TO PROVIDE AT LEAST A SIX-INCH CLEARANCE BETWEEN FLOOR AND EQUIPMENT.
12. MOP SINK: LOCATED IN JANITOR CLOSET OFF MAIN KITCHEN CORRIDOR, AND LOCATED IN CLOSE PROXIMITY TO THE SERVERY WAREWASH AREA.
13. EXHAUST HOODS: EXHAUST HOODS PROVIDED OVER COOKING EQUIPMENT WITH LIQUID CHEMICAL ANSUL FIRE EXTINGUISHING SYSTEM.
14. LIGHTING AND PROTECTIVE SHIELDING: RECESSED CEILING-MOUNTED FLUORESCENT LIGHT FIXTURES FITTED WITH CLEAR LEXAN DIFFUSERS.
15. GARBAGE AND REFUSE: CENTRAL TRASH COLLECTION PROVIDED FOR BUILDING LOCATED NEAR RECEIVING AREA ON SMOOTH CONCRETE SURFACE.
16. POISONOUS AND TOXIC MATERIAL STORAGE: LOCATED IN RESPECTIVE JANITOR CLOSETS WITH LOCKING HARDWARE.

1 HEALTH DEPARTMENT COORDINATION NOTES
NOT TO SCALE

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DRIVE
RICHMOND, TX 77406

SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
THE ITEM APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 48854119 ON: 07/15/2025



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

FS GENERAL COORDINATION NOTES

P-QF0.0

| FOOD SERVICE DRAWING INDEX | |
|---|---|
| FDP SHEET NUMBER | FDP SHEET NAME |
| P-QF0.0 | FS GENERAL COORDINATION NOTES |
| P-QF1.0 | FS EQUIPMENT PLAN |
| P-QF1.1 | FS FACILITY MODEL |
| P-QF1.2 | FS EQUIPMENT MODEL |
| P-QF1.3 | FS SPECIAL CONDITIONS & MECHANICAL PLAN |
| P-QF1.4 | FS PLUMBING PLAN |
| P-QF1.5 | FS ELECTRICAL PLAN |
| P-QF1.6 | FS CONDENSING UNITS |
| P-QF1.7 | FS WALK-INS |
| P-QF1.8 | FS SERVING LINE |
| P-QF1.9 | FS SERVING LINE |
| P-QF2.0 | FS DEMO PLAN |
| P-QF2.1 | FS TEMPORARY SERVING |
| P-QF3.1 | FS ELEVATIONS |
| P-QF4.1 | FS SECTIONS & DETAILS |
| P-QF4.2 | FS DETAILS |
| P-QF4.3 | FS DETAILS |




1 FOOD SERVICE EQUIPMENT PLAN
1/4" = 1'-0"

| FOOD SERVICE EQUIPMENT SCHEDULE | | | | | |
|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR GENERAL CONTRACTOR & HEALTH DEPARTMENT COORDINATION NOTES | | | | | |
| FDP ITEM | FDP QTY | FDP DESCRIPTION | FDP REMARKS | MANUFACTURER | MODEL |
| | 355 | | | | |
| 101 | 1 | AIR SCREEN | | MARS | STD248-1UA-OB |
| 102 | 1 | COLD STORAGE ASSEMBLY | | AMERICAN PANEL | |
| 103 | 1 | COLD STORAGE REFRIGERATION SYSTEM | | | |
| 104 | 2 | COLD STORAGE SHELVING | | METRO | METROMAX Q |
| 107 | 1 | DRY STORAGE SHELVING | | METRO | METROMAX Q |
| 108 | 1 | CAN RACK | | NEW AGE | 1250CK |
| 109 | 1 | ICE MACHINE W/ BIN | | MANITOWOC | UYF0310A |
| 110 | 1 | CLOTHES WASHER | | WHIRLPOOL | RESIDENTIAL |
| 110A | 1 | CLOTHES DRYER | | WHIRLPOOL | RESIDENTIAL |
| 111W | 1 | WALL MOUNTED OVERSHELF | | CUSTOM FABRIACTED | |
| 122 | 1 | TWO COMPARTMENT SINK WITHOUT DISPOSER | | CUSTOM FABRIACTED | |
| 123 | 1 | DISPOSER - 3HP | | SALVAJOR | 300-CA-18-ARSS-LD |
| 125 | 1 | 20 QT. MIXER W/STAND | | HOBART | HL200 |
| 128 | 4 | UTILITY CART | | LAKESIDE | 522 |
| 129 | 3 | WORKTABLE W/S.BAR UT.RACK | | CUSTOM FABRIACTED | |
| 138 | 4 | PAN RACK | | CRES COR | 207-UA-13A |
| 139 | 1 | INSUL MOBILE PROOFER | | CRES COR | H-137-WSUA-12D |
| 151 | 2 | FIRE PROTECTION SYSTEM | | ANSUL | R102 |
| 152 | 1 | EXHAUST HOOD | EXISTING | | |
| 153 | 1 | EXHAUST HOOD | EXISTING | | |
| 161 | 2 | CONVECTION OVEN | | BLODGETT | DFG-200 DBL |
| 165 | 1 | TWO BURNER RANGE | | VULCAN | V2B18B |
| 172 | 1 | COMBI OVEN | | RATIONAL | ICP 6-FULL/6-FULL N/G |
| 186 | 2 | PASS-THRU HEATED CABINET-1DR | | TRAULSEN | AHF132WP |
| 188 | 2 | PASS-THRU REFRIGERATOR-1DR | | TRAULSEN | AHT132WPUT |
| 201M.1 | 1 | SERVING COUNTER-MODULAR | | COUNTERCRAFT | SCOL-408-MOD |
| 214 | 2 | CASH REGISTER | OWNER FURNISHED | | |
| 249 | 1 | THREE COMPARTMENT SINK NO DISPOSER | | CUSTOM FABRIACTED | |
| 250 | 1 | DISHMACHINE | | HOBART | CL44-BAS |
| 254 | 2 | SOILED & CLEAN DISHTABLE | | CUSTOM FABRIACTED | |
| 255 | 2 | MOBILE DRYING RACK | | METRO | PR48VX3 |
| 260 | 4 | HAND SINK | FURNISHED & INSTALLED BY DIV. 22 | | |
| 614 | 1 | FILL FAUCET | | T&S | B-0610 |
| 615 | 2 | MENU MONITOR | BY OWNER | | |
| 800 | 1 | 15 GAL. BRAISING PAN | | GROEN | BPM-15GA |
| 801 | 1 | S/S CORNER GUARDS | LOCATED ON EVERY EXPOSED CORNER THROUGHOUT KITCHEN | CUSTOM FABRIACTED | |
| 802 | 1 | WALL BUMPERS | LOCATED ON ALL EXPOSED BUILDING WALLS | PAWLING | MD-1 |
| 803 | 1 | WATER SOFTENER | | HOBART | WS-40 |
| 804 | 4 | S/S SPLASH GUARDS | | | |

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DRIVE
RICHMOND, TX 77406


SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
88854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
THE ITEMS APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 88854119 ON: 07/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS EQUIPMENT PLAN

P-QF1.0

ISOMETRIC VIEWS WITHIN THIS DRAWING ARE NOT TO SCALE AND ARE PROVIDED FOR REFERENCE PURPOSES ONLY. ISOMETRIC VIEWS ARE NOT INTENDED FOR REGULATORY APPROVAL, PERMITTING, NOR CONSTRUCTION. REFER TO FLOOR PLANS AND DETAILS FOR SPECIFIC PROJECT INFORMATION.



1 FS FACILITY MODEL

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FDP
FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DRIVE
RICHMOND, TX 77406

SEAL


FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
FCSI
488544119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
ITEMS APPEARING ON THIS DOCUMENT WERE AUTHORIZED BY MELISSA MOORE, FCSI NO. 488544119 ON: 07/15/2025

MWA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS FACILITY MODEL

P-QF1.1

ISOMETRIC VIEWS WITHIN THIS DRAWING ARE NOT TO SCALE AND ARE PROVIDED FOR REFERENCE PURPOSES ONLY. ISOMETRIC VIEWS ARE NOT INTENDED FOR REGULATORY APPROVAL, PERMITTING, NOR CONSTRUCTION. REFER TO FLOOR PLANS AND DETAILS FOR SPECIFIC PROJECT INFORMATION.



1 FS EQUIPMENT MODEL

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DRIVE
RICHMOND, TX 77406

SEAL

FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
68854119
PROFESSIONAL MEMBER
7/15/2025
THE ITEM APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 68854119 ON: 07/18/2025


ARCHITECTS
AND PLANNING
CONSULTANTS

11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

FS EQUIPMENT MODEL

P-QF1.2


| FOOD SERVICE MECHANICAL SCHEDULE | | | | | | |
|---|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR MECHANICAL COORDINATION NOTES | | | | | | |
| FDP NO. | FDP QTY | FDP TYPE | FDP SIZE | FDP LOC | FDP CFM | FDP S.P. |
| M101 | 1 | EXHAUST | 4" X 16" | | 400 | 0.30" |
| M102 | 1 | EXHAUST | 4" X 16" | | 800 | 0.30" |
| M103 | 1 | DRYER VENT | 6" DIA. | | --- | --- |

NOTE:
SECTION 11 40 00 TO COORDINATE FINAL LOCATION AND SIZE OF WALL BLOCKING.




5 WALL BLOCKING DETAIL
NOT TO SCALE


NOTE:
SECTION 11 40 00 TO COORDINATE FINAL LOCATION OF ALL TRENCH LINERS WITH EQUIPMENT POUR PATH.





6 TRENCH LINER DETAIL
NOT TO SCALE




1 FOOD SERVICE SPECIAL CONDITIONS PLAN
1/4" = 1'-0"





3 COLD STORAGE ASSEMBLY ENCLOSURE PANEL DETAIL
NOT TO SCALE




COLD STORAGE ASSEMBLY REFRIGERATION SYSTEM GROUND MOUNT 4" PLATFORM DETAIL
4 NOT TO SCALE

SLAB TO BE MODIFIED AS REQUIRED TO ALLOW FOR A 4 1/2" DEPRESSION SLAB. PROVIDE NEW LEVEL CONCRETE PAD FOR COLD STORAGE ASSEMBLY.




WALL SECTION @ EXTERIOR DOOR

2 COLD STORAGE ASSEMBLY 4 1/2" DEPRESSION DETAIL
NOT TO SCALE

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DRIVE
RICHMOND, TX 77406

SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
FCSI 888544119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
DRAWING OR THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 888544119 ON 07/18/2025


ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



**PROJ. NO.:** 23-25
**DATE:** 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS SPECIAL CONDITIONS & MECHANICAL PLAN

P-QF1.3

| FOOD SERVICE PLUMBING SCHEDULE | | | | | | |
|---|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR PLUMBING COORDINATION NOTES | | | | | | |
| FDP PNO | FDP PSIZE | FDP PCONN | FDP PSERVICE TO | FDP PLOC | FDP PAFF | FDP PREMARKS |
| P5 | 3/4" | H & C WATER | JANITOR SINK | WALL | 48" | JANITOR SINK BY PLUMBER |
| P6 | 4" | FLOOR DRAIN | JANITOR SINK | FLOOR | VERIFY | JANITOR SINK BY PLUMBER |
| P7 | 3/4" | H & C WATER | HOSE BIBB | WALL | 18" | BTC |
| P10 | VERIFY | FLOOR DRAIN | GENERAL AREA DRAIN | FLOOR | VERIFY | --- |
| P11C | 1/2" | H & C WATER | FAUCET | WALL | 18" | FURNISHED & INSTALLED BY DIV. 22 |
| P11D | 1 1/2" | DIRECT DRAIN | HAND SINK | WALL | 15" | FURNISHED & INSTALLED BY DIV. 22 |
| P12 | VERIFY | FLOOR DRAIN | EQUIP. DRAIN | FLOOR | VERIFY | NO SLOPE |
| P15 | 4" | FLOOR DRAIN | FUNNEL FLOOR DRAIN | FLOOR | 0" | --- |
| P109 | 3/4" | COLD WATER | WATER/ ICE | WALL | 60" | BTC |
| P109A | 12" SQ. | FLOOR SINK | ICE MACHINE | FLOOR | 0" | FULL GRATE |
| P110 | 3/4" | H & C WATER | CLOTHES WASHER | WALL | 48" | BTC; VALVE BOX |
| P110A | 2" | INDIRECT DRAIN | CLOTHES WASHER | WALL | 48" | VALVE BOX |
| P122 | 3/4" | H & C WATER | FAUCET | WALL | 13" | BTC |
| P122A | 12" SQ. | FLOOR SINK | SINK | FLOOR | 0" | 3/4 GRATE |
| P123 | 3/4" | H & C WATER | FAUCET / DISPOSER | WALL | 13" | BTC |
| P123A | 2" | DIRECT DRAIN | DISPOSER | WALL | 10" | BTC |
| P161 | (2)3/4" | NATURAL GAS | CONVECTION OVEN | WALL | 18"/36" | BTC - 60 MBTU/HR EACH |
| P163A | 3/4" | NATURAL GAS | TILT BRAISING PAN | WALL | 18" | BTC - 65 MBTU/HR |
| P163B | 3/4" | H & C WATER | TILT BRAISING PAN | WALL | 36" | BTC |
| P165 | 1" | NATURAL GAS | RANGE | WALL | 18" | BTC - 70 MBTU/HR |
| P172 | (2)3/4" | COLD WATER | COMBI OVEN | WALL | 24"/48" | BTC - INTERCONNECT THRU FILTERS |
| P172A | 3/4" | COLD WATER | COMBI OVEN | WALL | 48" | BTC |
| P172B | 12"SQ. | FLOOR SINK | EQUIPMENT | FLOOR | 0" | 3/4 GRATE |
| P172C | (2)3/4" | NATURAL GAS | COMBI OVEN | WALL | 18"/36" | BTC - 105 MBTU/HR EACH |
| P172D | 3/4" | COLD WATER | COMBI OVEN | WALL | 66" | BTC; INTERCONNECT TO P172 |
| P172E | 3/4" | COLD WATER | COMBI OVEN WATER FILTER | WALL | 66" | BTC |
| P249 | 3/4" | H & C WATER | FAUCET | WALL | 13" | BTC |
| P249A | 12" SQ. | FLOOR SINK | SINK | FLOOR | 0" | THREE QUARTER GRATE |
| P250 | 12" SQ. | FLOOR SINK | BOOSTER / DISHMACHINE | FLOOR | 18" | BTC |
| P250A | 3/4" | HOT WATER | DISHMACHINE | WALL | 18" | EXT. THRU W.FILTER TO BOOSTER / DISH MACHINE - 140DEG.MIN. |
| P250B | 3/4" | COLD WATER | DISHMACHINE | WALL | 18" | BTC |
| P614 | 1/2" | H & C WATER | FILL FAUCET | WALL | 42" | BTC |
| P800 | 12" SQ. | FLOOR SINK | EQUIPMENT | FLOOR | 0" | 3/4 GRATE |



NOTE:
(FOR GRAPHICAL REPRESENTATION ONLY)
SECTION 11 40 00 TO VERIFY LOCATION OF REFRIGERATION SYSTEM WITH APPROVED ARCHITECTURAL DRAWINGS. REFRIGERATION LINE RUNS ARE TO BE THE RESPONSIBILITY OF SECTION 11 40 00 AND COVERED UNDER THIS CONTRACT.




1 FOOD SERVICE PLUMBING PLAN
1/4" = 1'-0"

SECTION 11 40 00 TO PROVIDE LOOSE WITH FOOD SERVICE EQUIPMENT. INSTALLATION BY DIV. 22 & 26.


- (A) VACUUM BREAKER
- (B) DISPOSER
- (C) TIME DELAY
- (D) CONTROL PANEL
- (E) SOLENOID VALVE

DIVISION 22 TO PROVIDE AND INSTALL


- (F) 1/2" CW INLET
- (G) FLOW CONTROL
- (H) 1/2" CW
- (I) 2" DRAIN LINE WITH P-TRAP & Y ADAPTOR
- (J) 1-1/2" TAILPIECE
- (K) GATE VALVE
- (L) 1/2" CW SUPPLY
- (M) SHOCK STOP
- (N) RPZ BACK FLOW PREVENTOR

DIVISION 26 TO PROVIDE AND INSTALL


- (O) POWER SUPPLY





6 DISPOSER WITH VACUUM BREAKER DETAIL
NOT TO SCALE





7 EXHAUST HOOD - GAS LINE ROUTING DETAIL
NOT TO SCALE




3 GAS DISCONNECT DETAIL
NOT TO SCALE




5 DRAIN PIPING FASTENER DETAIL
NOT TO SCALE




8 WAREWASH - PERFORATED OVER SHELF DETAIL
NOT TO SCALE

| | | | | | |
|---|---|---|---|---|---|
| ○ | HW | HOT WATER | ▢ | FFD | FUNNEL FLOOR DRAIN |
| ○ | CW | COLD WATER | ◣ | EVC | EXHAUST VENT CONNECTION |
| ○ | HTW | 180 F HOT WATER | ◢ | SVC | SUPPLY VENT CONNECTION |
| ◎ | | CHILLED WATER | ◔ | FR | DIRECT-CONNECTED FLUE RISER |
| ● | W | DIRECT WASTE | ◎ | PS | PIPE SLEEVE |
| ○ | IW | INDIRECT WASTE | ⊙ | | COMPRESSED AIR |
| ⊙ | | GAS SUPPLY | ♦ | | CO2 |
| ◕ | | STEAM SUPPLY | | AFF | ABOVE FINISHED FLOOR |
| ⊙ | CR | CONDENSATE RETURN | | BTC | BRANCH TO CONN. ON EQUIP |
| ◉ | DR | DRAIN | | DFA | DROP FROM ABOVE |
| ▢ | FD | FLOOR DRAIN | | CLG | CEILING |
| ▟ | FST | FLOOR SINK 3/4 GRATE | | | |
| ▟ | FSH | FLOOR SINK 3/4 GRATE | | | |

2 PLUMBING SYMBOLS
NOT TO SCALE

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FDP
FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DRIVE
RICHMOND, TX 77406

SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
THE ITEM APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO.-48854119 ON: 07/15/2025

ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS PLUMBING PLAN


P-QF1.4

| FOOD SERVICE ELECTRICAL SCHEDULE | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR ELECTRICAL COORDINATION NOTES | | | | | | | | |
| FDP ENO | FDP ECONN | FDP ELOAD | FDP EVOLT | FDP EPH | FDP ESERVICE TO | FDP ELOC | FDP EAFF | FDP EREMARKS |
| E10 | DR | 16.0A | 120 | 1 | CONVENIENCE | WALL | 24" | MOUNT HORIZONTAL |
| E13 | WPR | 16.0A | 120 | 1 | CONVENIENCE | WALL | 24" | MOUNT HORIZONTAL |
| E15 | JB | --- | --- | --- | FIRE PROT. SYSTEM | WALL | 48" | RECESSED EMPTY CONDUIT FOR FIRE PULL |
| E101 | JB | 5.1A | 120 | 1 | AIR SCREEN | WALL | 82" | BTC; MAGNETIC REED SWITCH ON DOOR JAMB & DOOR |
| E102A | JB | 16.0A | 120 | 1 | DOOR HEATER/LIGHTS | CLG | DFA | BTC |
| E102B | JB | 5.0A | 120 | 1 | TEMP. ALARM | CLG | DFA | BTC |
| E102C | JB | 5.0A | 120 | 1 | PRESSURE RELIEF PORT | CLG | DFA | BTC |
| E102E | JB | 10.0A | 120 | 1 | PANIC ALARM BUTTON | CLG | DFA | BTC-INTERCONNECT TO STROBE LIGHT/HORN ABOVE FREEZER DOOR AND IN CAFETORIUM |
| E103 | JB/DS | 21.9A | 208 | 3 | REFRIGERATION SYSTEM | VERIFY | VERIFY | BTC |
| E103C | JB | 9.1A | 208 | 1 | FREEZER COIL | CLG | DFA | BTC |
| E103D | JB | 1.8A | 120 | 1 | COOLER COIL | CLG | DFA | BTC |
| E103E | JB | --- | --- | --- | DATA CONNECTION | CLG | DFA | BTC; RUN TO NEAREST IDF / MDF ROOM |
| E103F | JB | 16.0A | 120 | 1 | DRAIN LINE HEATER | CLG | DFA | BTC; DEDICATED CIRCUIT |
| E109 | DR | 11.9A | 120 | 1 | ICE MACHINE | WALL | 60" | --- |
| E110 | DR | 16.0A | 120 | 1 | CLOTHES WASHER | WALL | 48" | -- |
| E110A | SR | 30.0A | 208 | 1 | CLOTHES DRYER | WALL | 48" | VERIFY NEMA PLUG RECEPTACLE |
| E123 | JB | 3.0HP | 208 | 3 | DISPOSER | WALL | 24" | BTC; CONNECT THRU C.P. TO DISPOSER |

| FOOD SERVICE ELECTRICAL SCHEDULE | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR ELECTRICAL COORDINATION NOTES | | | | | | | | |
| FDP ENO | FDP ECONN | FDP ELOAD | FDP EVOLT | FDP EPH | FDP ESERVICE TO | FDP ELOC | FDP EAFF | FDP EREMARKS |
| E129 | DCR | 16.0A | 120 | 1 | TABLE RECEPTACLE | CLG | 84" | TWISTLOCK PLUG & RECEPTACLE |
| E139 | DCR | 15.0A | 120 | 1 | INSUL. MOBILE PROOFER | CEILING | DFA | -- |
| E151 | JB | 1.0A | 120 | 1 | FIRE PROT. SYSTEM | CLG | DFA | BTC |
| E161 | (2)DR | 6.0A EA. | 120 | 1 | CONVECTION OVEN | WALL | 24"/48" | SHUNT TRIP BREAKER |
| E163 | DR | 5.0A | 120 | 1 | TILT BRAISING PAN | WALL | 24" | SHUNT TRIP BREAKER |
| E172 | (2)JB | 15.0A EA. | 208 | 1 | COMBI OVEN | WALL | 24"/48" | BTC- SHUNT TRIP BREAKER |
| E187 | JB | 15.5A | 120/208 | 1 | HEATED CABINET | WALL | 96" | BTC; MOUNT ON KITCHEN SIDE |
| E188 | JB | 7.2A | 120 | 1 | REFRIGERATOR | WALL | 96" | BTC; MOUNT ON KITCHEN SIDE-OMIT PLUG, UNIT TO BE HARDWIRED |
| E201A | PMR | 28.0A | 208 | 1 | HOT FOOD COUNTER | FLOOR | 4.5" | BTC |
| E201B | PMR | 16.0A | 120 | 1 | COLD FOOD COUNTER | FLR | 4.5" | --- |
| E209 | PMR | 8.0A | 120 | 1 | DROP FRONT MILK COOLER-8 CASE | FLR | 4.5" | --- |
| E214 | PMR | 16.0A | 120 | 1 | CASH REGISTER | FLR | 4.5" | DEDICATED CIRCUIT |
| E214A | CS | --- | --- | --- | POS | FLOOR | 6" | BTC; CONDUIT W/DATA LINE TO RUN TO MANAGER'S OFFICE OR IDF ROOM-VERIFY |
| E250 | JB/DS-JB | 51.7A | 480 | 3 | DISHMACHINE | WALL | 66" | BTC; EXTEND FROM JB/DS AT NEAREST WALL |
| E615 | DR | 5.0A | 120 | 1 | VIDEO / DATA SYSTEM | CLG | VERIFY | PROVIDE DCO AT VIDEO LOCATION |
| E615A | JB | --- | --- | --- | VIDEO / DATA SYSTEM | CLG | VERIFY | PROVIDE JB AT DATA LOCATION |

DIVISION 26 TO PROVIDE, COORDINATE, AND INSTALL THE FOLLOWING:
1. AUDIBLE DOORBELL AT RECEIVING DOOR ON EXTERIOR WALL THAT CAN BE HEARD THROUGHOUT THE ENTIRE KITCHEN, OFFICE AND DRY STORAGE ROOM.
2. ADEQUATE LIGHTING AT RECEIVING DOOR.
3. EDWARDS 860 SERIES (OR EQUAL) RED LENS, SURFACE-MOUNTED XENON EMERGENCY STROBE BEACONS. ONE (1) TO BE LOCATED IN THE KITCHEN ABOVE WALK-IN FREEZER DOOR (OR COOLER DOOR WHEN FREEZER IS WITHIN COOLER IN AN 'INLINE' ASSEMBLY), AND ONE (1) TO BE LOCATED IN THE CAFETORIUM (COORDINATE LOCATION WITH OWNERS). PROVIDE CONDUIT, WIRING, AND INTERCONNECT THE ILLUMINATED PUSH BUTTON PANIC ALARM IN THE WALK-IN FREEZER TO BOTH STROBE BEACONS (***CRITICAL***).


DIVISION 27 TO PROVIDE THE FOLLOWING:
1. CONDUIT, DATA, AND INTERCONNECTION FROM THE ILLUMINATED PUSH BUTTON PANIC ALARM INSIDE THE WALK-IN FREEZER TO THE BUILDING AUTOMATION SYSTEM. WHEN ACTIVATED, FACILITY PERSONNEL TO BE NOTIFIED - COORDINATE NOTIFICATION REQUIREMENTS WITH THE OWNER (***CRITICAL***).





1 FOOD SERVICE ELECTRICAL PLAN
1/4" = 1'-0"





NOTE:
(FOR GRAPHICAL REPRESENTATION ONLY)
SECTION 11 40 00 TO VERIFY LOCATION OF REFRIGERATION SYSTEM WITH APPROVED ARCHITECTURAL DRAWINGS.








6 COLD STORAGE ASSEMBLY ENTRAPMENT PANIC ALARM DETAIL
NOT TO SCALE





3 PEDESTAL MOUNTED RECEPTACLE DETAIL
NOT TO SCALE

NOTE:
REFER TO FDP EQUIPMENT PLAN FOR SPECIFIC COMPONENTS UNDER HOOD. ALL EQUIPMENT SHOWN HERE FOR GRAPHICAL REPRESENTATION ONLY.




| | |
|---|---|
| A | S/S ENCLOSURE W/AGENT TANK AND NITROGEN CARTRIDGE |
| B | DUCT NOZZLE(S) |
| C | PLENUM NOZZLE(S) |
| D | SURFACE PROTECTION NOZZLE(S) |
| E | FUSIBLE LINK(S) |
| F | (2) WIRES FROM FIRE SYSTEM TO SHUNT TRIP BREAKERS FOR SHUT DOWN OF ELECTRICAL CONNECTIONS LOCATED BENEATH EXHAUST HOOD DURING FIRE MODE |
| G | REMOTE FIRE PULL |
| H | GAS VALVE |
| I | GAS SUPPLY (AS REQUIRED) |

4 FIRE PROTECTION SYSTEM TYPICAL DETAIL
NOT TO SCALE




5 FIRE PROTECTION SYSTEM RECESSED FIRE PULL DETAIL
NOT TO SCALE

| | | | | | |
|---|---|---|---|---|---|
| SCR | CONDUIT STUB BTC ON RECEPT FURNISH WITH EQUIPMENT | | CC | CONDUIT FOR COMPUTER CABLES |
| CS | CONDUIT STUB UP/OUT FOR DIRECT CONNECTION | | BTC | BRANCH TO CONNECTION ON EQUIPMENT |
| DR | DUPLEX RECEPTACLE | | WPR | WATERPROOF RECEPTACLE (SPRING COVER) |
| SR | SINGLE PURPOSE RECEPTACLE-1PH | | FPB | FIRE PROTECTION BUZZER |
| SR | SINGLE PURPOSE RECPTACLE-3PH | | BSC | BEVERAGE SYSTEM CONDUIT |
| FR | FLUSH FLOOR RECEPTACLE | | DFA | DROP FROM ABOVE |
| PMR | PEDESTAL MOUNTED RECEPTACLE | | AFF | ABOVE FINISH FLOOR |
| DCR | DROP CORD RECEPTACLE | | CS/JB | JUNCTION BOX ON PEDESTAL |
| JB | JUNCTION BOX ON CEILING | | SW | SWITCH |
| JB | JUNCTION BOX IN WALL | | D | DATA |
| JB/DS | JUNCTION BOX WITH DISCONNECT BY DIV.26 | | | |

2 ELECTRICAL SYMBOLS
NOT TO SCALE

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DRIVE
RICHMOND, TX 77406


SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
488543119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
ELECTRONICALLY SEALING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 488543119 ON 07/18/2025


ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS ELECTRICAL PLAN

P-QF1.5

**MODEL NO. ZS1-02Z-CT3-EST OUTDOOR AIR COOLED REFRIGERATION SYSTEM**
**ITEM NO. 103**




NOTE:
- CRANKCASE HEATERS
- FAN CYCLING SWITCHES
- 24" STANDS & STAINLESS STEEL SKIRTING TO BE SHIPPED LOOSE FOR FIELD INSTALLATION
- DOOR SENSOR FOR EACH WALK-IN
- REFRIGERANT DETECTION SYSTEM
- CHECK VALVE (SHIPPED LOOSE)
- SHUT OFF VALVE (SHIPPED LOOSE)

RACK WEIGHT: 600 LBS.

# ADT ENGINEERING SUMMARY

**POWER SUPPLY: 208-230/60/3**
**CONNECTED LOAD: 21.8 AMPS**

**MOPD: 30 AMP**
**MINIMUM CIRCUIT AMPACITY: 24.1**

| SYSTEM | ITEM # | DESCRIPTION | FIXTURES: TEMP °F FIXT. | FIXTURES: TEMP °F SUCT. | REQ'D FIXTURE BTU/H | REFRIG. | CONDENSING UNIT: COMPRESSOR MODEL NO. | H.P. | RATING @ 60 HZ RLA | V | PH | BTU CAP @ AMB °F 110 | TYPE | REC. CAP. (lbs) | CONDENSER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| A | 102 | WALK-IN COOLER | 35 | 25 | 8506 | 454A | YS11KAE | | 11.2 | 208 | 3 | 11700 | Z | 14.0 | L1R |
| B | 102 | WALK-IN FREEZER | -10 | -20 | 7607 | 454A | YF07KSE | | 10.6 | 208 | 3 | 7610 | Z | 14.0 | L1R |

| SYSTEM | ITEM # | MODEL NO. | EVAPORATOR COILS: QTY | FAN MOTORS @ 60 HZ RLA | V | PH | HEATERS @ 60 HZ RLA | V | PH | DEFR. TYPE | DEFROST CONTROLLER TYPE | CONTROLLER QTY | ACCESSORIES TSTAT | SOL. VALVE | EXP. VLV. | REFRIGERANT LINE SIZES (IN) SUCT. | SUCT. LINE RISER | LIQUID | LINE RUN (FT) | TYPE | TOTAL SYSTEM LOAD |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| A | 102 | BEL0095 | 1 | 1.8 | 115 | 1 | | | | O.C. | ECOSMART | 1 | F | F | EF | 5/8 | 5/8 | 3/8 | 100 | M | 11.2 |
| B | 102 | BEL0065 | 1 | 1.0 | 208 | 1 | 9.1 | 208 | 1 | ELEC | ECOSMART | 1 | F | F | EF | 7/8 | 7/8 | 3/8 | 100 | M | 10.6 |


ALL EVAPORATOR COILS WILL REQUIRE A HOUSE POWER SUPPLY

c UL us LISTED

NOTE:
IT IS THE INSTALLING CONTRACTORS RESPONSIBILITY TO FOLLOW ALL APPLICABLE CODES AND CURRENT REFRIGERATION INDUSTRY STANDARDS AND PRACTICES WHEN DETERMINING LINE SIZES, AND INSTALLING AND STARTING UP RDT EQUIPMENT.


| COMPRESSOR TYPE | DEFROST TYPE | LINE TYPE | EVAPORATOR ACCESSORIES |
|---|---|---|---|
| Z SCROLL | O.C. OFF CYCLE<br>ELEC ELECTRIC | M MAIN - UP TO 100' | EF EEV FACTORY EQUIPPED ON EVAP<br>F FACTORY EQUIPPED ON EVAP |

## PLANVIEW/ CLEARANCE REQUIREMENTS





NOTE: MINIMUM CLEARANCE REQUIRED FOR PROPER OPERATION
NOTE: ROOF CURB OR GROUND PAD CAN BE SAME SIZE AS OUTDOOR UNIT

## SUCTION LINE VERTICAL RISE DETAIL




- Install trap every transition from horizontal to vertical.
- Insulate suction lines with 3/4" wall Armaflex insulation.
- All joints brazed with minimum 15% silver content brazing rod.
- Install "P" trap on suction line every 15' vertical rise.
- Not to exceed 45' vertically over all.
- *If compressor is above the evaporator, Install inverted trap on top of the rise to prevent oil from seeping down when fixture(s) is turned off.

## EVAPORATOR DETAILS - MODEL BEL




| AIR DEFROST Size | DIMENSIONS A Inches | B Inches | C Inches | D Inches | CONNECTIONS (Inches) Coil Inlet | Suction | Drain | Approx. Net Wt. Lbs. | ELECTRICAL DATA Qty. Motors | EC Motor Fan Amps 115V | 208V |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 095 | 45-1/2 | 33-1/4 | | | 1/2 OD | 5/8 OD | 3/4 MPT | 51 | 2 | 1.8 | 1.0 |

| ELECTRIC DEFROST | DIMENSIONS A Inches | B Inches | C Inches | D Inches | CONNECTIONS (Inches) Coil Inlet | Suction | Drain | Approx. Net Wt. Lbs. | ELECTRICAL DATA Qty. Motors | EC Motor Fan Amps | Heater Amps as wired for 208-230/60/1 | 208-230/60/3 | 460/60/1 |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 065 | 45-1/2 | 33-1/4 | - | - | 1/2 OD | 5/8 OD | 3/4 MPT | 54 | 2 | 1.0 | 9.1 | 5.7 | 4.6 |

## ZS SERIES ENGINEERING SPECIFICATIONS

Multi compressor, outdoor, air cooled. The refrigeration package shall be a pre-engineered and factory-assembled unit, trade name "ZS", as manufactured by Refrigeration Design Technologies, 1808 FM Road 66, P.O. Box 622, Waxahachie, Texas 75168. Phone: (972) 937-3215; Fax: (972) 937-0970.

1. Air-Cooled Refrigeration System
The RDT UL Listed "Air-Cooled" Refrigeration system shall be housed in a weather-protected compact powder coated steel frame. The entire housing shall be brushed stainless steel. The unit shall include an air-cooled aluminum fin copper tube condenser designed to operate at 15 degrees TD. The exterior housing shall feature stainless steel one piece louvers. Lifting points shall be integrated in the framing component. Condenser fan motors shall be mounted within the enclosure. The condenser intake surface shall be protected with stainless steel expanded metal guard to protect against vandalism and hail damage.

Each unit shall be equipped with a ball-bearing fan motor, suction filter, sight glass, liquid filter/drier, liquid line inlet and outlet valve, defrost cycle and high pressure super-hose connections. Each unit shall be equipped with fan cycling controls and/or head pressure regulator where required for low ambient conditions.

Condensing unit shall contain scroll, hermetic, semi-hermetic, and/or discus type compressor(s) assembled to operate with the refrigerant specified for both medium and low temperature applications.

2. Evaporator Coils
A. Evaporator coils shall be direct expansion type fabricated of copper tubes with aluminum fins.
B. All evaporator coils shall be provided with solenoid valve, thermostatic or electronic expansion valve and thermostat.

3. Pre-Piping
All refrigerant lines shall be extended to outside of the housing in a neat and orderly manner. All tubing shall be securely supported and anchored with non-corrosive coated clamps.

All joints must be brazed, not soldered.

All piping and controls shall be factory pressure-tested with dry nitrogen.

4. Control Panel
The package shall have a factory-mounted and pre-wired control panel, with main disconnect (non fused) where required, circuit breakers, contactors wired for single point power connection.

General Information
Contractors shall verify all dimensions onsite and coordinate with other trades.

General contractor shall prepare the platform, curbed openings and weatherproofing the unit after installation.

Refrigeration Contractor
All copper tubing to be refrigerant grade. A.C.R. or type "L".

Brazing should be used for all refrigerant piping. Silver solder or soft solder is not acceptable.

All piping to be pressure tested with nitrogen at 300 psi. After the condensing unit and coil have been connected the balance of the system shall be leak tested with the valves open at 200 psi.

The complete system shall be evacuated with a vacuum pump. Each unit should be charged tested and adjusted to assure operation.

Contractor should provide and install the drain-line heater in freezer. Heater shall be connected by electrical contractor. Seal all penetrations through the walk-in units with foam.

Electrical Contractor
Electrical contractor to provide power for refrigeration package and connect control and defrost system as called for in the wiring diagram.


Electrical contractor to connect drain-line heater in the freezer.

All electrical wiring and installation shall be in accordance with the wiring diagram and local codes. Seal all penetrations through the walk-in units with foam.

Plumbing Contractor
Plumbing contractor to provide copper drain lines for walk-in refrigerator and freezer, pitched 1/4" per foot of run. Trap drain-line outside of refrigerated space to avoid entrance of warm, moist air.


All plumbing installation shall be in accordance with local codes.

## EVAPORATOR MOUNTING DETAIL (TYPICAL)




| COIL MODEL | DISTANCE FROM WALL |
|---|---|
| BEL | 1-1/3"H |
| BEM/BEH | 1/2 " W |

## EVAPORATOR PLACEMENT & CLEARANCE REQUIREMENTS LOW PROFILE EVAPORATOR COILS (I.E. - BEL)





SINGLE EVAPORATOR

NOTE:
H = TOTAL HEIGHT OF THE EVAP. COIL

## WIRING DIAGRAM - ECOSMART - AKEA1AE DEMAND DEFROST W/KE2 DOOR SWITCH FOR WALK-IN COOLER WITH ONE COIL 115/60/1

*REFERENCE ENGINEERING SUMMARY FOR COIL AMP DRAW.

| SYS | DESCRIPTION | VOLTAGE |
|---|---|---|
| A | WALK-IN COOLER | 115/1 |





FACTORY WIRING ———
FIELD WIRING - - - -

## WIRING DIAGRAM - ECOSMART - AKEB1EE DEMAND DEFROST W/KE2 DOOR SWITCH FOR WALK-IN FREEZER WITH ONE COIL 208-230/60/1

*REFERENCE ENGINEERING SUMMARY FOR COIL AMP DRAW.

| SYS | DESCRIPTION | VOLTAGE |
|---|---|---|
| B | WALK-IN FREEZER | 208/1 |




FACTORY WIRING ———
FIELD WIRING - - - -

## APPROVAL STATUS

THIS DRAWING REPRESENTS OUR UNDERSTANDING OF THE SPECIFICATIONS. PLEASE REVIEW IT CAREFULLY FOR ACCURACY. CLEARLY AND IN DETAIL NOTE CHANGES REQUIRED.

MARK APPROPRIATE BOX, SIGN, AND DATE BELOW.

- ☐ APPROVED FOR FABRICATION NO CHANGES
- ☐ APPROVED FOR FABRICATION WITH CHANGES NOTED
- ☐ REVISE AND RE-SUBMIT DRAWING

BY: _____ DATE: _____

## NOTICE

THIS DRAWING BEING AN INSTRUMENT OF SERVICE IS AND WILL REMAIN PROPERTY OF REFRIGERATION DESIGN TECHNOLOGIES AND CANNOT BE USED WITHOUT WRITTEN AUTHORIZATION.

| No. | Revision/Issue | Date |
|---|---|---|
| 0 | ORIGINAL ISSUE | 10-2-24 |
| 1 | CHANGED TO A2L EQUIPMENT | 7-16-25 |


REFRIGERATION DESIGN TECHNOLOGIES
1808 FM Road 66 / P.O. Box 622
Waxahachie, Texas
(800) 736-9518
www.rdtonline.com


Consultant:
Foodservice Design Professionals, LLC
The Woodlands, TX

Dealer
-
-

**Pecan Grove Elementary School**
**Fort Bend ISD**

Project No: 31080
Designed By: E. Milligan
Drawn By: A. Rodriguez
Sheet 1.1 of sheets

ISSUE:
12/05/2024 DD PACKAGE
03/11/2025 50% CD PKG.
05/23/2025 90% CD PKG.
07/18/2025 ISSUED FOR BIDDING AND PERMITTING

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DRIVE
RICHMOND, TX 77406

FOODSERVICE DESIGN PROFESSIONALS

SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
68854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 68854119 ON: 07/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS CONDENSING UNITS

P-QF1.6

# REFER TO FOODSERVICE DESIGN PROFESSIONALS SPECIFICATIONS AND SUBSEQUENT SHEETS FOR ADDITIONAL COORDINATION INFORMATION

**EXISTING EQUIPMENT NOTES (IF EXISTING EQUIPMENT IS PROVIDED IN THIS PROJECT):**

1. EXISTING EQUIPMENT NOT SCHEDULED FOR RE-USE TO BE RELOCATED BY THE K.E.C. COORDINATE WITH OWNER FOR NEW LOCATION.
2. ALL UTILITIES NOT SCHEDULED FOR RE-USE TO BE CAPPED & COVERED BY REQUIRED DISCIPLINE.
3. K.E.C. TO VERIFY ALL EXISTING UTILITY LOCATIONS & COORDINATE WITH ALL EQUIPMENT AS REQUIRED.

8 EXISTING EQUIPMENT NOTES
NOT TO SCALE

**ARCHITECT TO VERIFY/COORDINATE THE AESTHETIC OPTIONS BELOW (FOOD SERVICE COLOR, MATERIAL, OR SIGNAGE SELECTIONS) IF THESE ITEMS ARE PROVIDED IN THIS PROJECT:**

1. COUNTERTOPS: STONE (STAINLESS STEEL IS PROVIDED UNLESS OTHERWISE SPECIFIED).
2. TRAY SLIDES: CORIAN OR STONE (STAINLESS STEEL IS PROVIDED UNLESS OTHERWISE SPECIFIED).
3. COUNTER FRONTS: CERAMIC TILE, 3 FORM, OR PLASTIC LAMINATE.
4. SNEEZE GUARDS: STONE INSETS.
5. GENERAL COLOR, MATERIAL AND GRAPHIC SELECTIONS:
   - A. DISPLAY AIR SCREEN MERCHANDISERS - COLOR SELECTION: POWDER COAT OR PLASTIC LAMINATE (S/S IS PROVIDED UNLESS OTHERWISE SPECIFIED).
   - B. BAKERY DISPLAY CASES - COLOR SELECTION: POWDER COAT OR PLASTIC LAMINATE (S/S IS PROVIDED UNLESS OTHERWISE SPECIFIED).
   - C. PASS THRU OR REACH IN HOLDING CABINETS - COLOR SELECTION: POWDER COAT (MFG.: TRUE) OR PLASTIC LAMINATE (MFG.: TRAULSEN) (S/S IS PROVIDED UNLESS OTHERWISE SPECIFIED).
   - D. HANGING HEAT LAMPS - TRACK AND FIXTURE COLOR SELECTION.
   - E. HEATED MERCHANDISERS.
   - F. PORTABLE GUIDE RAILS - STANCHION AND BELT COLOR SELECTION.
   - G. POPCORN MACHINE - SIGNAGE SELECTION.
   - H. BOTTLE COOLER - SIGNAGE SELECTION.
   - I. GRAPHICS PACKAGE INFORMATION.
   - J. HOT FOOD WELL COVERS.
6. ARCHITECT TO VERIFY/COORDINATE THE FINISHES BELOW:
   - A. WALLS: CERAMIC TILE, FLAT FRP, OR MOLDED FRP (SMOOTH, IMPERVIOUS, AND EASILY CLEANABLE AS APPROVED BY LOCAL JURISDICTION).
   - B. CEILINGS: REMOVABLE VINYL FACE TILE (SMOOTH, IMPERVIOUS, AND EASILY CLEANABLE AS APPROVED BY LOCAL JURISDICTION).
   - C. FLOORS: TILE, EPOXY, OR RUBBERIZED FLOORING SYSTEM (SMOOTH, IMPERVIOUS, EASILY CLEANABLE AND SLIP RESISTANT AS APPROVED BY LOCAL JURISDICTION) (COORDINATE FLOOR TILE TRANSITION AT SERVING LINES).
   - D. FLOORS: WALK-IN ASSEMBLY - EXTEND KITCHEN FLOOR FLUSH INTO WALK-IN ASSEMBLY WITH COVED BASE.
   - E. FURR DOWNS ABOVE SERVING COUNTERS.

5 ARCHITECTURAL COORDINATION NOTES
NOT TO SCALE

**CRITICAL NOTES:**

1. CONTRACTOR MUST COORDINATE AND VERIFY ALL DIMENSIONS WITH FOOD SERVICE EQUIPMENT SHOP DRAWINGS AND MANUFACTURER'S DATA. DIMENSIONS SHOWN ARE FOR DESIGN AND BIDDING PURPOSES ONLY.
2. WALK-IN ASSEMBLY DOORS MUST BE LEFT OPEN WHILE INTERIOR CONCRETE FLOOR CURES.
3. INSTALL PROTECTIVE COVER ON WALK-IN ASSEMBLY WALL PANELS BEFORE INSTALLING CONCRETE FLOORS AND CURBS.
4. REFER TO GENERAL SPECS - DIVISION 27 TO PROVIDE CONDUIT, DATA, AND INTERCONNECT THE PANIC ALARM INSIDE FREEZER TO THE BUILDING AUTOMATION SYSTEM FOR NOTIFICATION TO DISTRICT PERSONNEL IN THE EVENT OF STAFF ENTRAPMENT.
5. PIPING AND DRAINAGE SYSTEMS (SANITARY AND GREASE-LADEN). SYSTEMS MUST BE CLEANED AND FLUSHED BEFORE THE FINAL CONNECTION WITH FOOD SERVICE EQUIPMENT - CRITICAL (DIV. 22).

7 CRITICAL NOTES
NOT TO SCALE

**DIVISION 26 (ELECTRICAL) IS RESPONSIBLE FOR BUT NOT LIMITED TO:**

1. **DO NOT ROUGH IN FROM FDP DRAWINGS. REFER TO THE KITCHEN EQUIPMENT CONTRACTOR'S DIMENSIONED SHOP DRAWINGS. DIMENSIONS INDICATED ARE TO BE VERIFIED BY KITCHEN EQUIPMENT CONTRACTOR AND ADJUSTED AS REQUIRED BY EQUIPMENT AND FIELD CONDITIONS.**
2. SECTION 11 40 00 TO VERIFY UTILITY REQUIREMENTS OF ANY EXISTING EQUIPMENT.
3. ALL CONNECTIONS SHALL BE MADE FOLLOWING LOCAL CODES AND NATIONAL STANDARDS, EXCEPT WHERE PLANS AND SPECIFICATIONS EXCEED THOSE CODES AND STANDARDS.
4. VERIFY ALL ELECTRICAL REQUIREMENTS WITH ENGINEERING DRAWINGS.
5. ROUGH-IN AND FINAL CONNECTION OF ELECTRICAL SYSTEMS TO FOOD SERVICE EQUIPMENT, WALK-IN ASSEMBLIES, AND BETWEEN COMPONENTS (INCLUDING MATERIALS AND LABOR). ACCESSORIES PROVIDED LOOSE WITH FOOD SERVICE EQUIPMENT BY SECTION 11 40 00 TO BE FIELD INSTALLED BY DIVISION 26.
6. EMPTY EMT CONDUIT WITH PULL-WIRE AND WIDE-SWEEP BENDS FOR REFRIGERANT PIPING TO REMOTE FOOD SERVICE EQUIPMENT REFRIGERATION SYSTEMS.
7. EMPTY EMT CONDUIT WITH PULL-WIRE AND WIDE-SWEEP BENDS FOR INTERCONNECT CABLES BETWEEN LAN AND POS TERMINALS, CHANGE-MAKERS, PRE-CHECK UNITS, PRINTERS, CPUS, ETC. DIVISION 26 TO VERIFY WHERE THE CONDUIT IS TO RUN FOR POS SYSTEM (I.E., MANAGER'S OFFICE OR IDF ROOM).
8. EMPTY EMT CONDUIT WITH PULL-WIRE AND WIDE-SWEEP BENDS FOR FIRE SUPPRESSION SYSTEMS. INTERCONNECT FIRE PROTECTION SYSTEM TO PANEL BOX SHUNT TRIPS AND BUILDING ALARM.
9. WALK-IN LIGHT FIXTURE INSTALLATION (PROVIDED LOOSE BY SECTION 11 40 00) (IF WALK-IN IS PROVIDED IN THIS PROJECT).
10. TABLE LIMIT SWITCH INSTALLATION (PROVIDED LOOSE BY SECTION 11 40 00) (IF DISHMACHINE IS PROVIDED IN THIS PROJECT).
11. ELECTRICAL MATERIALS AND DEVICES (SHUNT-TRIP BREAKERS, SURGE PROTECTORS, LIGHTING CONTROL DEVICES, CONDUIT, WIRE, ETC.).
12. SWITCHES AND STAINLESS STEEL DISCONNECTS AS REQUIRED (PROVIDE, LOCATE, AND INSTALL – TO BE IN AN ACCESSIBLE LOCATION).
13. CHARGING STATIONS FOR FORKLIFTS, PALLET STACKERS, AND PALLET JACKS (SIZE, PROVIDE, LOCATE, AND INSTALL) (IF EQUIPMENT IS PROVIDED IN THIS PROJECT).
14. INTERCONNECTION BETWEEN CONDENSATE FAN AND DISHMACHINE CONTROL PANEL (IF EQUIPMENT IS PROVIDED IN THIS PROJECT).
15. INTERCONNECTION BETWEEN EXHAUST HOOD FANS AND SWITCH (IF EQUIPMENT IS PROVIDED IN THIS PROJECT).
16. INTERCONNECTION BETWEEN EXHAUST HOOD LIGHTS AND SWITCH (IF EQUIPMENT IS PROVIDED IN THIS PROJECT).
17. DOOR HEATERS, LIGHTS, COILS, AND PRESSURE RELIEF PORTS PRE-WIRED TO JUNCTION BOX AT TOP OF WALK-IN ASSEMBLIES (IF EQUIPMENT IS PROVIDED IN THIS PROJECT) PROVIDED BY SECTION 11 40 00. FINAL CONNECTION BY DIV. 26.
18. IF ANY ELECTRICAL ACCESSORIES, FITTINGS, AND CORD/PLUGS ARE PROVIDED LOOSE WITH EQUIPMENT BY 11 40 00, DIV.26 IS TO ATTACH TO EQUIPMENT AND PROVIDE FINAL CONNECTION.
19. PROVIDE WATERPROOF RECEPTACLES IN WET AREAS.
20. ALL ELECTRICAL CONNECTIONS BENEATH EXHAUST HOODS (IF EQUIPMENT IS PROVIDED IN THIS PROJECT) TO EXTEND TO SHUNT TRIP BREAKERS WITH ELECTRICAL PANEL BOX FOR SHUTDOWN DURING FIRE MODE.
21. RECEPTACLES ARE TO BE PRE-WIRED TO THE JUNCTION BOX OR LOAD CENTER FOR FINAL CONNECTION BY DIVISION 26.
22. ALL ELECTRICAL LIGHTING, POWER, AND DISTRIBUTION SYSTEMS.
23. DO NOT INTERCONNECT MORE THAN THREE (3) CONVENIENCE OUTLETS ON ONE (1) BREAKER.
24. OTHER THAN CONVENIENCE OUTLETS, ALL ELECTRICAL CONNECTIONS SHOWN ON FOOD SERVICE PLANS ARE DEDICATED BREAKERS.
25. DOORBELL AT RECEIVING DOOR (PROVIDE AND INSTALL – TO BE AUDIBLE THROUGHOUT KITCHEN, OFFICE, AND DRY STORAGE ROOM).
26. ADEQUATE LIGHTING AT RECEIVING DOOR.
27. PROVIDE AND INSTALL TWO EMERGENCY STROBE BEACONS THAT INTERCONNECT TO PANIC ALARM IN WALK-IN FREEZER. ONE (1) IN KITCHEN ABOVE WALK-IN FREEZER DOOR ONE (1) IN CAFETORIUM (IF WALK-IN IS PROVIDED IN THIS PROJECT). REFER TO GENERAL SPECIFICATIONS FOR ADDITIONAL DETAILS.
28. DEDICATED CIRCUIT FOR HEATED DRAIN LINE CONNECTION IN WALK-IN FREEZER AT EACH COIL (IF WALK-IN IS PROVIDED IN THIS PROJECT).

**NOTE: ELECTRICAL CONNECTIONS INDICATED ARE THOSE REQUIRED FOR THE FOOD SERVICE EQUIPMENT AND THOSE REQUIRED FOR SUPPORT EQUIPMENT FURNISHED BY DIVISION 26. FOR ADDITIONAL REQUIREMENTS, REFER TO THE ELECTRICAL ENGINEER'S DRAWINGS.**

6 ELECTRICAL COORDINATION NOTES
NOT TO SCALE

**DIVISION 22 (PLUMBING) RESPONSIBLE FOR BUT NOT LIMITED TO:**

1. **DO NOT ROUGH-IN FROM FDP DRAWINGS. REFER TO THE KITCHEN EQUIPMENT CONTRACTOR'S DIMENSIONED SHOP DRAWINGS. DIMENSIONS INDICATED ARE TO BE VERIFIED BY KITCHEN EQUIPMENT CONTRACTOR AND ADJUSTED AS REQUIRED BY EQUIPMENT AND/OR FIELD CONDITIONS.**
2. SECTION 11 40 00 TO VERIFY UTILITY REQUIREMENTS OF ANY EXISTING EQUIPMENT.
3. ALL CONNECTIONS SHALL BE MADE IN ACCORDANCE WITH LOCAL CODES AND NATIONAL STANDARDS, EXCEPT WHERE PLANS AND SPECIFICATIONS EXCEED THOSE CODES AND STANDARDS.
4. VERIFY ALL PLUMBING REQUIREMENTS WITH ENGINEERING DRAWINGS.
5. EMPTY PVC CONDUIT WITH WIDE-SWEEP BENDS FOR REFRIGERANT PIPING TO BEVERAGE LINES, CO2 LINES, AND REMOTE FOOD SERVICE EQUIPMENT REFRIGERATION SYSTEMS.
6. ROUGH-IN AND FINAL PLUMBING CONNECTIONS TO FOOD SERVICE EQUIPMENT AND BETWEEN COMPONENTS (INCLUDING MATERIALS AND LABOR). ACCESSORIES PROVIDED LOOSE WITH FOOD SERVICE EQUIPMENT BY SECTION 11 40 00 TO BE FIELD INSTALLED BY DIVISION 22. THIS INCLUDES BUT IS NOT LIMITED TO INSTALLATION OF ALL FAUCETS (WATER FILL FAUCETS, PRE-RINSE FAUCETS, ETC.), HOSES, GAS DISCONNECTS, AND DRAINS FROM EQUIPMENT POINT OF CONNECTION TO BUILDING PLUMBING SYSTEMS. ALL DRAIN LINES ARE PROVIDED AND INSTALLED BY DIV. 22.
7. KITCHEN EQUIPMENT CONTRACTOR IS RESPONSIBLE FOR PROVIDING ALL FAUCETS (WATER FILL FAUCETS, PRE-RINSE FAUCETS, ETC.), DRAIN FITTINGS, MIXING VALVES, CONTROL VALVES, WATER PRESSURE REGULATORS, VACUUM BREAKERS, AND ALL ACCESSORIES FOR EQUIPMENT SPECIFIED UNDER 11 40 00. DIVISION 22 IS RESPONSIBLE FOR INSTALLATION.
8. INDIRECT DRAIN LINE RUNS FROM EQUIPMENT TO NEAREST DRAIN OR FLOOR SINK. LINES TO BE TYPE 'K' COPPER.
9. IF ANY PLUMBING ACCESSORIES OR FITTINGS ARE PROVIDED LOOSE WITH EQUIPMENT BY 11 40 00, DIV. 22 IS TO ATTACH TO EQUIPMENT AND PROVIDE FINAL CONNECTION.
10. GAS SUPPLY SYSTEMS WITH ALL COMPONENTS AND FITTINGS AS REQUIRED FOR A COMPLETE SYSTEM.
11. WATER SUPPLY SYSTEMS WITH ALL COMPONENTS AND FITTINGS AS REQUIRED FOR A COMPLETE SYSTEM.
12. COMPRESSED AIR SYSTEMS WITH ALL COMPONENTS AND FITTINGS AS REQUIRED FOR A COMPLETE SYSTEM (IF REQUIRED FOR THIS PROJECT).
13. PIPING AND DRAINAGE SYSTEMS (SANITARY AND GREASE-LADEN). SYSTEMS MUST BE CLEANED AND FLUSHED BEFORE THE FINAL CONNECTION WITH FOOD SERVICE EQUIPMENT - CRITICAL.
14. FLOOR SINKS (PROVIDE AND INSTALL). FLANGE AND GRATES TO BE FLUSH WITH FINISHED FLOOR.
15. FLOOR DRAINS (PROVIDE AND INSTALL). FLANGE AND GRATES TO BE FLUSH WITH FINISHED FLOOR.
16. TRENCH DRAINS (PROVIDE AND INSTALL). TRENCH LINERS PROVIDED BY 11 40 00. FLANGE AND LINERS TO BE FLUSH WITH FINISHED FLOOR.
17. GREASE TRAPS AS REQUIRED. VERIFY WITH LOCAL CODES TO BYPASS OR PIPE THRU GREASE TRAP AND/OR INTERCEPTOR.
18. P-TRAPS AS REQUIRED (INCLUDING ALL DISPOSERS).
19. INTERCONNECT WATER THRU WATER FILTER (FILTER PROVIDED BY 11 40 00 UNLESS OTHERWISE SPECIFIED) TO EQUIPMENT.
20. GAS QUICK DISCONNECT INSTALLATION (QUICK DISCONNECT PROVIDED BY 11 40 00).
21. SAFETY RESTRAINT CABLE INSTALLATION (SAFETY RESTRAINT CABLE PROVIDED BY 11 40 00).
22. SPECIFIED COUPLINGS AND PIPING TO ALL EQUIPMENT FURNISHED BY 11 40 00.
23. AIR COMPRESSORS (IF REQUIRED FOR THIS PROJECT) (SIZE, PROVIDE, AND INSTALL, UNLESS OTHERWISE SPECIFIED).
24. WATER SOFTENERS (IF REQUIRED FOR THIS PROJECT) (SIZE, PROVIDE, AND INSTALL, UNLESS OTHERWISE SPECIFIED).
25. PRESSURE BOILERS (IF REQUIRED FOR THIS PROJECT) (SIZE, PROVIDE, AND INSTALL, UNLESS OTHERWISE SPECIFIED).
26. HAND SINKS (PROVIDE (UNLESS OTHERWISE SPECIFIED) AND INSTALL). PROVIDE HOT WATER TEMPERING VALVE IF REQUIRED. WATER TEMPERATURE TO BE AT LEAST 100 DEGREES AND FLOW FOR AT LEAST 20 SECONDS.
27. ICE BIN DRAIN INSULATION (IF ICE MACHINE IS PROVIDED IN THIS PROJECT) (PROVIDE AND INSTALL).
28. UNIONS AT DISPOSER SOLENOID VALVES (IF DISPOSER IS PROVIDED IN THIS PROJECT) (PROVIDE AND INSTALL).
29. BACK FLOW PREVENTION AS REQUIRED (PROVIDE AND INSTALL - INCLUDING ALL DISPOSERS). BACK- SIPHONAGE SHALL BE INSTALLED AT ALL FIXTURES AND EQUIPMENT WHERE BACKFLOW AND/OR BACK-SIPHONAGE MAY OCCUR AND WHERE A MINIMUM AIR GAP CANNOT BE PROVIDED BETWEEN THE WATER TO THE FIXTURE OR EQUIPMENT AT ITS FLOOD/LEVEL RIM. VACUUM BREAKERS, WHEN FURNISHED WITH EQUIPMENT, SHALL OVERRIDE THE ABOVE, IF ACCEPTABLE WITH APPLICABLE CODES. DIVISION 22 RESPONSIBLE FOR VERIFYING REQUIREMENT WITH LOCAL CODES.
30. JANITOR SINK WITH FAUCET (PROVIDE AND INSTALL).
31. FREEZE PROOF HYDRANT AT EXTERIOR OF BUILDING BY RECEIVING DOOR (PROVIDE AND INSTALL).
32. REVERSE OSMOSIS SYSTEMS (SIZE, PROVIDE (UNLESS OTHERWISE SPECIFIED), LOCATE AND INSTALL).
33. ALL PIPING WITHIN COUNTER BODY OR UNDER FABRICATED COUNTERS TO BE RUN TO A CONNECTION POINT BELOW COUNTER BODY BY SECTION 11 40 00. FINAL CONNECTION BY DIVISION 22.
34. EXHAUST HOOD CONDENSATE DRAIN CONNECTIONS (IF EXHAUST HOOD IS PROVIDED IN THIS PROJECT) (PROVIDE AND INSTALL).
35. INTERCONNECTION OF 1/2" CW TO PRE-RINSE AND DISPOSERS CONE/BODY INLETS PIPED THROUGH SOLENOID AND VACUUM BREAKER (IF DISPOSER IS PROVIDED IN THIS PROJECT).
36. FIRE SYSTEM PIPING. EXPOSED PIPING TO BE CHROME PLATED.
37. PIPE 1/2" COLD WATER TO SWIRL INLETS AT DISPOSERS (IF DISPOSER IS PROVIDED IN THIS PROJECT).
38. WATER TREATMENT FOR ICE BUILDERS (NON-CHLORINATED WATER WITH A PH LEVEL OF 10 OR HIGHER) AND ANY DRAINS AND OVERFLOWS. PIPING FROM ICE BUILDERS TO TUMBLE CHILLERS BY DIV. 23 (IF ICE BUILDERS AND TUMBLE CHILLERS ARE PROVIDED IN THIS PROJECT).

**NOTE: WATER AND DRAIN CONNECTIONS INDICATED ARE THOSE REQUIRED FOR THE FOOD SERVICE EQUIPMENT AND THOSE REQUIRED FOR SUPPORT EQUIPMENT FURNISHED BY DIVISION 22. FOR ADDITIONAL WATER AND DRAIN REQUIREMENTS REFER TO MECHANICAL DRAWINGS.**

**NOTE: REFER TO ELECTRICAL/MECHANICAL DRAWINGS FOR REQUIREMENTS OF EXHAUST FANS AND MAKE-UP AIR HANDLERS AND LOCATION OF AN INTERLOCK AND START/STOP CONTROLS TO BE LOCATED WITHIN FOOD SERVICE AREA BY DIVISION 26.**

4 PLUMBING COORDINATION NOTES
NOT TO SCALE

**DIVISION 23 (MECHANICAL) RESPONSIBLE FOR BUT NOT LIMITED TO:**

1. **DO NOT ROUGH-IN FROM FDP DRAWINGS. REFER TO THE KITCHEN EQUIPMENT CONTRACTOR'S DIMENSIONED SHOP DRAWINGS. DIMENSIONS INDICATED ARE TO BE VERIFIED BY KITCHEN EQUIPMENT CONTRACTOR AND ADJUSTED AS REQUIRED BY EQUIPMENT AND/OR FIELD CONDITIONS.**
2. SECTION 11 40 00 TO VERIFY UTILITY REQUIREMENTS OF ANY EXISTING EQUIPMENT.
3. ALL CONNECTIONS SHALL BE MADE FOLLOWING LOCAL CODES AND NATIONAL STANDARDS, EXCEPT WHERE PLANS AND SPECIFICATIONS EXCEED THOSE CODES AND STANDARDS.
4. VERIFY ALL MECHANICAL REQUIREMENTS WITH ENGINEERING DRAWINGS.
5. EMPTY EMT CONDUIT WITH PULL-WIRE AND WIDE-SWEEP BENDS FOR REFRIGERANT PIPING TO REMOTE FOOD SERVICE EQUIPMENT REFRIGERATION SYSTEMS.
6. ROUGH-IN AND FINAL CONNECTION OF MECHANICAL SYSTEMS TO FOOD SERVICE EQUIPMENT, WALK-IN ASSEMBLIES, AND BETWEEN COMPONENTS (INCLUDING MATERIALS AND LABOR).
7. TESTING AND BALANCING FOR ROOMS AND EXHAUST HOODS TO BE PERFORMED BY MECHANICAL CONTRACTOR. BALANCE REPORT FOR FOOD SERVICE EXHAUST HOODS TO BE PROVIDED TO FOODSERVICE DESIGN PROFESSIONALS (FDP) IMMEDIATELY UPON COMPLETION (SEND TO HOUSTON.SUBMITTAL@FDP.ORG FOR HOUSTON OFFICE AND DALLAS.SUBMITTAL@FDP.ORG FOR DALLAS OFFICE) AND MUST BE SUBMITTED WITH O&M MANUALS.
8. EXHAUST HOODS, CONDENSATE HOODS, FIRE SUPPRESSION SYSTEMS, CONNECTIONS AND CONTROLS (PROVIDE AND INSTALL – *UNLESS OTHERWISE SPECIFIED*). PROVIDE TEMPERED AIR AT ALL SUPPLY DUCTS.
   - A. IF EXHAUST/CONDENSATE HOODS AND FIRE SUPPRESSION SYSTEMS ARE SPECIFIED UNDER SECTION 11 40 00, DIVISION 23 IS RESPONSIBLE FOR ALL EXHAUST AND CONDENSATE HOOD CONNECTIONS (PROVIDE AND INSTALL).
9. VFD SYSTEM AND CONTROLLERS, WHEN REQUIRED BY CODE (PROVIDE AND INSTALL).
10. PROVIDE AND INSTALL ALL VENTILATION (DIRECT OR INDIRECT), AIR CONDITIONING AND HEATING SYSTEMS (UNLESS OTHERWISE SPECIFIED).
11. COORDINATE SUPPLY AND RETURN DUCTS ABOVE SERVING COUNTERS OR OPEN-AIR REFRIGERATED MERCHANDISERS. NO COLD AIR TO BLOW DIRECTLY ON HOT FOOD COUNTERS.
12. COORDINATE SUPPLY AND RETURN DUCTS AWAY FROM EQUIPMENT WITH TOP MOUNTED REFRIGERATION. NO COLD AIR TO BLOW DIRECTLY ON COMPRESSORS.
13. MECHANICAL CONTRACTOR TO LOCATE TEMPERATURE MONITORS WITHIN RETURN DUCTS.
14. CIRCULATING AIR ABOVE WALK-IN ASSEMBLIES (PROVIDE AND INSTALL).
15. CIRCULATING AIR ABOVE AND IN AIR GAPS AT WAREHOUSE COLD STORAGE ASSEMBLIES (PROVIDE AND INSTALL).
16. WATER CHILLERS AS REQUIRED (IF EQUIPMENT IS PROVIDED IN THIS PROJECT) (PROVIDE, SIZE AND LOCATE).
17. PIPING FROM ICE BUILDERS TO TUMBLE CHILLERS (IF EQUIPMENT IS PROVIDED IN THIS PROJECT) (PROVIDE, SIZE AND LOCATE).

3 MECHANICAL COORDINATION NOTES
NOT TO SCALE

**GENERAL CONTRACTOR RESPONSIBLE FOR BUT NOT LIMITED TO:**

1. ANY WALL PENETRATION REQUIRED FOR FOOD SERVICE EQUIPMENT UTILITIES. ESCUTCHEON PLATES OR S/S SLEEVES TO BE PROVIDED AND INSTALLED AS NEEDED.
2. BULK FREEZER VENTILATION PIPE (IF BULK FREEZER IS PROVIDED IN THIS PROJECT) (PROVIDE AND INSTALL, UNLESS OTHERWISE SPECIFIED).
3. CORE DRILLING FOR GUIDE RAILS (IF GUIDE RAILS ARE PROVIDED IN THIS PROJECT).
4. REFRIGERATION ROOF CURBS / ROOF JACK (IF REFRIGERATION SYSTEM IS PROVIDED IN THIS PROJECT AND LOCATED ON ROOF).
5. INTERIOR BOLLARDS (IF REQUIRED FOR THIS PROJECT) – TO BE EPOXY PAINTED PER LOCAL CODES (PROVIDE AND INSTALL).
6. FURNISH AND INSTALL 3/4" PLYWOOD BLOCKING IN THE WALL FOR MOUNTING EQUIPMENT FURNISHED BY SECTION 11 40 00 AS REQUIRED.
7. WALK-IN DEPRESSIONS (TO BE DEAD LEVEL) AND SAND LEVELING BED (IF WALK-IN IS PROVIDED IN THIS PROJECT AND RECESS IS SHOWN).
8. STRUCTURAL BRACING FOR BULK WALK-IN CEILING PANELS IF REQUIRED.
9. MENU SYSTEM VIDEO MONITORS IN SERVERY (UNLESS OTHERWISE SPECIFIED).
10. STRUCTURAL BRACING FOR MENU SYSTEM VIDEO MONITORS IF REQUIRED.
11. INTERIOR/EXTERIOR REFRIGERATION PENETRATIONS AND SLEEVES AT BUILDING PENETRATIONS.
12. DOORSCOPE VIEWER (PEEPHOLE) WITH WIDE VIEWING ANGLE AT RECEIVING DOOR.
13. CANOPY AT RECEIVING DOOR. COORDINATE HEIGHT WITH THE HEIGHT OF RECEIVING DOOR (8') AND THE MOUNTING HEIGHT OF AIR SCREEN ABOVE THE DOOR.
14. SOAP AND TOWEL DISPENSER PROVIDED BY OWNER. G.C. RESPONSIBLE FOR INSTALLATION.
15. WASHER AND DRYER (PROVIDE AND INSTALL, UNLESS OTHERWISE SPECIFIED).
16. DWARF WALL AT EXPOSED FRONT/ENDS OF CAFETERIA SERVING COUNTERS WITH FINISH AS SELECTED BY ARCHITECT (IF REQUIRED IN THIS PROJECT).

2 GENERAL CONTRACTOR COORDINATION NOTES
NOT TO SCALE

**HEALTH DEPARTMENT REQUIREMENTS (VERIFY WITH LOCAL JURISDICTIONS):**

1. FLOORS: VERIFY WITH DIVISION 9. FLOORS TO BE SMOOTH, IMPERVIOUS, EASILY CLEANABLE AND SLIP RESISTANT.
2. WALLS: VERIFY WITH ARCHITECTURAL DOCUMENTS. WALLS TO BE SMOOTH, IMPERVIOUS, AND EASILY CLEANABLE.
3. CEILING: LAY-IN TILES. CEILING TILES TO BE SMOOTH, IMPERVIOUS, AND EASILY CLEANABLE.
4. EMPLOYEE TOILET: TO BE LOCATED OFF MAIN CORRIDOR AND ADJACENT TO MAIN KITCHEN. RESTROOM MUST HAVE A VESTIBULE AND NOT OPEN TO KITCHEN / PREP AREAS. TOILETS TO BE WELL VENTILATED.
5. LAVATORIES: WALL HUNG LAVATORIES LOCATED WITHIN ALL FUNCTIONAL WORKING AREAS.
6. UTENSIL CLEANING/SANITIZING: ACCOMPLISHED IN UTENSIL WASH AREA WITH (3) 2'-0" x 2'-2" x 15" MINIMUM DEEP SINKS AND WAREWASH MACHINE.
7. MECHANICAL CLEANING/SANITIZING OF TABLEWARE: ACCOMPLISHED BY WAREWASH MACHINE.
8. STOREROOMS: AMPLE DAILY STORAGE PROVIDED IN ENCLOSED STORE ROOMS. STORE ROOMS TO BE VENTILATED AND MAINTAIN PROPER TEMPERATURE.
9. WATER HEATER: LOCATED IN THE MECHANICAL ROOM ADJACENT TO KITCHEN. TO BE SIZED TO PROVIDE AMPLE WATER TO MAINTAIN PROPER WATER TEMPERATURE THROUGHOUT HOURS OF OPERATION.
10. GREASE TRAP: LOCATED AT EXTERIOR OF BUILDING. REFER TO ENGINEER'S DRAWINGS.
11. FOOD SERVICE EQUIPMENT: ALL FLOOR-MOUNTED EQUIPMENT IS TO BE SEALED TO THE FLOOR TO PROVIDE AN EASILY CLEANABLE SURFACE AND PREVENT SEEPAGE. EQUIPMENT NOT MOUNTED TO THE FLOOR IS TO BE WALL MOUNTED ON WALL CARRIERS, OR ELEVATED ON LEGS TO PROVIDE AT LEAST A SIX-INCH CLEARANCE BETWEEN FLOOR AND EQUIPMENT.
12. MOP SINK: LOCATED IN JANITOR CLOSET OFF MAIN KITCHEN CORRIDOR, AND LOCATED IN CLOSE PROXIMITY TO THE SERVERY WAREWASH AREA.
13. EXHAUST HOODS: EXHAUST HOODS PROVIDED OVER COOKING EQUIPMENT WITH LIQUID CHEMICAL ANSUL FIRE EXTINGUISHING SYSTEM.
14. LIGHTING AND PROTECTIVE SHIELDING: RECESSED CEILING-MOUNTED FLUORESCENT LIGHT FIXTURES FITTED WITH CLEAR LEXAN DIFFUSERS.
15. GARBAGE AND REFUSE: CENTRAL TRASH COLLECTION PROVIDED FOR BUILDING LOCATED NEAR RECEIVING AREA ON SMOOTH CONCRETE SURFACE.
16. POISONOUS AND TOXIC MATERIAL STORAGE: LOCATED IN RESPECTIVE JANITOR CLOSETS WITH LOCKING HARDWARE.

1 HEALTH DEPARTMENT COORDINATION NOTES
NOT TO SCALE

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DRIVE
RICHMOND, TX 77406

SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
THE ITEM APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 48854119 ON: 07/15/2025



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

FS GENERAL COORDINATION NOTES

P-QF0.0

| FOOD SERVICE DRAWING INDEX | |
|---|---|
| FDP SHEET NUMBER | FDP SHEET NAME |
| P-QF0.0 | FS GENERAL COORDINATION NOTES |
| P-QF1.0 | FS EQUIPMENT PLAN |
| P-QF1.1 | FS FACILITY MODEL |
| P-QF1.2 | FS EQUIPMENT MODEL |
| P-QF1.3 | FS SPECIAL CONDITIONS & MECHANICAL PLAN |
| P-QF1.4 | FS PLUMBING PLAN |
| P-QF1.5 | FS ELECTRICAL PLAN |
| P-QF1.6 | FS CONDENSING UNITS |
| P-QF1.7 | FS WALK-INS |
| P-QF1.8 | FS SERVING LINE |
| P-QF1.9 | FS SERVING LINE |
| P-QF2.0 | FS DEMO PLAN |
| P-QF2.1 | FS TEMPORARY SERVING |
| P-QF3.1 | FS ELEVATIONS |
| P-QF4.1 | FS SECTIONS & DETAILS |
| P-QF4.2 | FS DETAILS |
| P-QF4.3 | FS DETAILS |




1 FOOD SERVICE EQUIPMENT PLAN
1/4" = 1'-0"

| FOOD SERVICE EQUIPMENT SCHEDULE | | | | | |
|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR GENERAL CONTRACTOR & HEALTH DEPARTMENT COORDINATION NOTES | | | | | |
| FDP ITEM | FDP QTY | FDP DESCRIPTION | FDP REMARKS | MANUFACTURER | MODEL |
| | 355 | | | | |
| 101 | 1 | AIR SCREEN | | MARS | STD248-1UA-OB |
| 102 | 1 | COLD STORAGE ASSEMBLY | | AMERICAN PANEL | |
| 103 | 1 | COLD STORAGE REFRIGERATION SYSTEM | | | |
| 104 | 2 | COLD STORAGE SHELVING | | METRO | METROMAX Q |
| 107 | 1 | DRY STORAGE SHELVING | | METRO | METROMAX Q |
| 108 | 1 | CAN RACK | | NEW AGE | 1250CK |
| 109 | 1 | ICE MACHINE W/ BIN | | MANITOWOC | UYF0310A |
| 110 | 1 | CLOTHES WASHER | | WHIRLPOOL | RESIDENTIAL |
| 110A | 1 | CLOTHES DRYER | | WHIRLPOOL | RESIDENTIAL |
| 111W | 1 | WALL MOUNTED OVERSHELF | | CUSTOM FABRIACTED | |
| 122 | 1 | TWO COMPARTMENT SINK WITHOUT DISPOSER | | CUSTOM FABRIACTED | |
| 123 | 1 | DISPOSER - 3HP | | SALVAJOR | 300-CA-18-ARSS-LD |
| 125 | 1 | 20 QT. MIXER W/STAND | | HOBART | HL200 |
| 128 | 4 | UTILITY CART | | LAKESIDE | 522 |
| 129 | 3 | WORKTABLE W/S.BAR UT.RACK | | CUSTOM FABRIACTED | |
| 138 | 4 | PAN RACK | | CRES COR | 207-UA-13A |
| 139 | 1 | INSUL MOBILE PROOFER | | CRES COR | H-137-WSUA-12D |
| 151 | 2 | FIRE PROTECTION SYSTEM | | ANSUL | R102 |
| 152 | 1 | EXHAUST HOOD | EXISTING | | |
| 153 | 1 | EXHAUST HOOD | EXISTING | | |
| 161 | 2 | CONVECTION OVEN | | BLODGETT | DFG-200 DBL |
| 165 | 1 | TWO BURNER RANGE | | VULCAN | V2B18B |
| 172 | 1 | COMBI OVEN | | RATIONAL | ICP 6-FULL/6-FULL N/G |
| 186 | 2 | PASS-THRU HEATED CABINET-1DR | | TRAULSEN | AHF132WP |
| 188 | 2 | PASS-THRU REFRIGERATOR-1DR | | TRAULSEN | AHT132WPUT |
| 201M.1 | 1 | SERVING COUNTER-MODULAR | | COUNTERCRAFT | SCOL-408-MOD |
| 214 | 2 | CASH REGISTER | OWNER FURNISHED | | |
| 249 | 1 | THREE COMPARTMENT SINK NO DISPOSER | | CUSTOM FABRIACTED | |
| 250 | 1 | DISHMACHINE | | HOBART | CL44-BAS |
| 254 | 2 | SOILED & CLEAN DISHTABLE | | CUSTOM FABRIACTED | |
| 255 | 2 | MOBILE DRYING RACK | | METRO | PR48VX3 |
| 260 | 4 | HAND SINK | FURNISHED & INSTALLED BY DIV. 22 | | |
| 614 | 1 | FILL FAUCET | | T&S | B-0610 |
| 615 | 2 | MENU MONITOR | BY OWNER | | |
| 800 | 1 | 15 GAL. BRAISING PAN | | GROEN | BPM-15GA |
| 801 | 1 | S/S CORNER GUARDS | LOCATED ON EVERY EXPOSED CORNER THROUGHOUT KITCHEN | CUSTOM FABRIACTED | |
| 802 | 1 | WALL BUMPERS | LOCATED ON ALL EXPOSED BUILDING WALLS | PAWLING | MD-1 |
| 803 | 1 | WATER SOFTENER | | HOBART | WS-40 |
| 804 | 4 | S/S SPLASH GUARDS | | | |

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DRIVE
RICHMOND, TX 77406


SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
88854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
THE ITEMS APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 88854119 ON: 07/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS EQUIPMENT PLAN

P-QF1.0

ISOMETRIC VIEWS WITHIN THIS DRAWING ARE NOT TO SCALE AND ARE PROVIDED FOR REFERENCE PURPOSES ONLY. ISOMETRIC VIEWS ARE NOT INTENDED FOR REGULATORY APPROVAL, PERMITTING, NOR CONSTRUCTION. REFER TO FLOOR PLANS AND DETAILS FOR SPECIFIC PROJECT INFORMATION.



1 FS FACILITY MODEL

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FDP
FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DRIVE
RICHMOND, TX 77406

SEAL


FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
FCSI
488544119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
ITEMS APPEARING ON THIS DOCUMENT WERE AUTHORIZED BY MELISSA MOORE, FCSI NO. 488544119 ON: 07/15/2025

MWA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS FACILITY MODEL

P-QF1.1

ISOMETRIC VIEWS WITHIN THIS DRAWING ARE NOT TO SCALE AND ARE PROVIDED FOR REFERENCE PURPOSES ONLY. ISOMETRIC VIEWS ARE NOT INTENDED FOR REGULATORY APPROVAL, PERMITTING, NOR CONSTRUCTION. REFER TO FLOOR PLANS AND DETAILS FOR SPECIFIC PROJECT INFORMATION.



1 FS EQUIPMENT MODEL

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DRIVE
RICHMOND, TX 77406

SEAL

FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
68854119
PROFESSIONAL MEMBER
7/15/2025
THE ITEM APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 68854119 ON: 07/18/2025


ARCHITECTS
AND PLANNING
CONSULTANTS

11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

FS EQUIPMENT MODEL

P-QF1.2


| FOOD SERVICE MECHANICAL SCHEDULE | | | | | | |
|---|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR MECHANICAL COORDINATION NOTES | | | | | | |
| FDP NO. | FDP QTY | FDP TYPE | FDP SIZE | FDP LOC | FDP CFM | FDP S.P. |
| M101 | 1 | EXHAUST | 4" X 16" | | 400 | 0.30" |
| M102 | 1 | EXHAUST | 4" X 16" | | 800 | 0.30" |
| M103 | 1 | DRYER VENT | 6" DIA. | | --- | --- |

NOTE:
SECTION 11 40 00 TO COORDINATE FINAL LOCATION AND SIZE OF WALL BLOCKING.




5 WALL BLOCKING DETAIL
NOT TO SCALE


NOTE:
SECTION 11 40 00 TO COORDINATE FINAL LOCATION OF ALL TRENCH LINERS WITH EQUIPMENT POUR PATH.





6 TRENCH LINER DETAIL
NOT TO SCALE




1 FOOD SERVICE SPECIAL CONDITIONS PLAN
1/4" = 1'-0"





3 COLD STORAGE ASSEMBLY ENCLOSURE PANEL DETAIL
NOT TO SCALE




COLD STORAGE ASSEMBLY REFRIGERATION SYSTEM GROUND MOUNT 4" PLATFORM DETAIL
4 NOT TO SCALE

SLAB TO BE MODIFIED AS REQUIRED TO ALLOW FOR A 4 1/2" DEPRESSION SLAB. PROVIDE NEW LEVEL CONCRETE PAD FOR COLD STORAGE ASSEMBLY.




WALL SECTION @ EXTERIOR DOOR

2 COLD STORAGE ASSEMBLY 4 1/2" DEPRESSION DETAIL
NOT TO SCALE

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DRIVE
RICHMOND, TX 77406

SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
FCSI 888544119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
DRAWING OR THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 888544119 ON 07/18/2025


ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



**PROJ. NO.:** 23-25
**DATE:** 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS SPECIAL CONDITIONS & MECHANICAL PLAN

P-QF1.3

| FOOD SERVICE PLUMBING SCHEDULE | | | | | | |
|---|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR PLUMBING COORDINATION NOTES | | | | | | |
| FDP PNO | FDP PSIZE | FDP PCONN | FDP PSERVICE TO | FDP PLOC | FDP PAFF | FDP PREMARKS |
| P5 | 3/4" | H & C WATER | JANITOR SINK | WALL | 48" | JANITOR SINK BY PLUMBER |
| P6 | 4" | FLOOR DRAIN | JANITOR SINK | FLOOR | VERIFY | JANITOR SINK BY PLUMBER |
| P7 | 3/4" | H & C WATER | HOSE BIBB | WALL | 18" | BTC |
| P10 | VERIFY | FLOOR DRAIN | GENERAL AREA DRAIN | FLOOR | VERIFY | --- |
| P11C | 1/2" | H & C WATER | FAUCET | WALL | 18" | FURNISHED & INSTALLED BY DIV. 22 |
| P11D | 1 1/2" | DIRECT DRAIN | HAND SINK | WALL | 15" | FURNISHED & INSTALLED BY DIV. 22 |
| P12 | VERIFY | FLOOR DRAIN | EQUIP. DRAIN | FLOOR | VERIFY | NO SLOPE |
| P15 | 4" | FLOOR DRAIN | FUNNEL FLOOR DRAIN | FLOOR | 0" | --- |
| P109 | 3/4" | COLD WATER | WATER/ ICE | WALL | 60" | BTC |
| P109A | 12" SQ. | FLOOR SINK | ICE MACHINE | FLOOR | 0" | FULL GRATE |
| P110 | 3/4" | H & C WATER | CLOTHES WASHER | WALL | 48" | BTC; VALVE BOX |
| P110A | 2" | INDIRECT DRAIN | CLOTHES WASHER | WALL | 48" | VALVE BOX |
| P122 | 3/4" | H & C WATER | FAUCET | WALL | 13" | BTC |
| P122A | 12" SQ. | FLOOR SINK | SINK | FLOOR | 0" | 3/4 GRATE |
| P123 | 3/4" | H & C WATER | FAUCET / DISPOSER | WALL | 13" | BTC |
| P123A | 2" | DIRECT DRAIN | DISPOSER | WALL | 10" | BTC |
| P161 | (2)3/4" | NATURAL GAS | CONVECTION OVEN | WALL | 18"/36" | BTC - 60 MBTU/HR EACH |
| P163A | 3/4" | NATURAL GAS | TILT BRAISING PAN | WALL | 18" | BTC - 65 MBTU/HR |
| P163B | 3/4" | H & C WATER | TILT BRAISING PAN | WALL | 36" | BTC |
| P165 | 1" | NATURAL GAS | RANGE | WALL | 18" | BTC - 70 MBTU/HR |
| P172 | (2)3/4" | COLD WATER | COMBI OVEN | WALL | 24"/48" | BTC - INTERCONNECT THRU FILTERS |
| P172A | 3/4" | COLD WATER | COMBI OVEN | WALL | 48" | BTC |
| P172B | 12"SQ. | FLOOR SINK | EQUIPMENT | FLOOR | 0" | 3/4 GRATE |
| P172C | (2)3/4" | NATURAL GAS | COMBI OVEN | WALL | 18"/36" | BTC - 105 MBTU/HR EACH |
| P172D | 3/4" | COLD WATER | COMBI OVEN | WALL | 66" | BTC; INTERCONNECT TO P172 |
| P172E | 3/4" | COLD WATER | COMBI OVEN WATER FILTER | WALL | 66" | BTC |
| P249 | 3/4" | H & C WATER | FAUCET | WALL | 13" | BTC |
| P249A | 12" SQ. | FLOOR SINK | SINK | FLOOR | 0" | THREE QUARTER GRATE |
| P250 | 12" SQ. | FLOOR SINK | BOOSTER / DISHMACHINE | FLOOR | 18" | BTC |
| P250A | 3/4" | HOT WATER | DISHMACHINE | WALL | 18" | EXT. THRU W.FILTER TO BOOSTER / DISH MACHINE - 140DEG.MIN. |
| P250B | 3/4" | COLD WATER | DISHMACHINE | WALL | 18" | BTC |
| P614 | 1/2" | H & C WATER | FILL FAUCET | WALL | 42" | BTC |
| P800 | 12" SQ. | FLOOR SINK | EQUIPMENT | FLOOR | 0" | 3/4 GRATE |



NOTE:
(FOR GRAPHICAL REPRESENTATION ONLY)
SECTION 11 40 00 TO VERIFY LOCATION OF REFRIGERATION SYSTEM WITH APPROVED ARCHITECTURAL DRAWINGS. REFRIGERATION LINE RUNS ARE TO BE THE RESPONSIBILITY OF SECTION 11 40 00 AND COVERED UNDER THIS CONTRACT.




1 FOOD SERVICE PLUMBING PLAN
1/4" = 1'-0"

SECTION 11 40 00 TO PROVIDE LOOSE WITH FOOD SERVICE EQUIPMENT. INSTALLATION BY DIV. 22 & 26.


- (A) VACUUM BREAKER
- (B) DISPOSER
- (C) TIME DELAY
- (D) CONTROL PANEL
- (E) SOLENOID VALVE

DIVISION 22 TO PROVIDE AND INSTALL


- (F) 1/2" CW INLET
- (G) FLOW CONTROL
- (H) 1/2" CW
- (I) 2" DRAIN LINE WITH P-TRAP & Y ADAPTOR
- (J) 1-1/2" TAILPIECE
- (K) GATE VALVE
- (L) 1/2" CW SUPPLY
- (M) SHOCK STOP
- (N) RPZ BACK FLOW PREVENTOR

DIVISION 26 TO PROVIDE AND INSTALL


- (O) POWER SUPPLY





6 DISPOSER WITH VACUUM BREAKER DETAIL
NOT TO SCALE





7 EXHAUST HOOD - GAS LINE ROUTING DETAIL
NOT TO SCALE




3 GAS DISCONNECT DETAIL
NOT TO SCALE




5 DRAIN PIPING FASTENER DETAIL
NOT TO SCALE




8 WAREWASH - PERFORATED OVER SHELF DETAIL
NOT TO SCALE

| | | | | | |
|---|---|---|---|---|---|
| ○ | HW | HOT WATER | ▢ | FFD | FUNNEL FLOOR DRAIN |
| ○ | CW | COLD WATER | ◣ | EVC | EXHAUST VENT CONNECTION |
| ○ | HTW | 180 F HOT WATER | ◢ | SVC | SUPPLY VENT CONNECTION |
| ◎ | | CHILLED WATER | ◔ | FR | DIRECT-CONNECTED FLUE RISER |
| ● | W | DIRECT WASTE | ◎ | PS | PIPE SLEEVE |
| ○ | IW | INDIRECT WASTE | ⊙ | | COMPRESSED AIR |
| ⊙ | | GAS SUPPLY | ♦ | | CO2 |
| ◕ | | STEAM SUPPLY | | AFF | ABOVE FINISHED FLOOR |
| ⊙ | CR | CONDENSATE RETURN | | BTC | BRANCH TO CONN. ON EQUIP |
| ◉ | DR | DRAIN | | DFA | DROP FROM ABOVE |
| ▢ | FD | FLOOR DRAIN | | CLG | CEILING |
| ▟ | FST | FLOOR SINK 3/4 GRATE | | | |
| ▟ | FSH | FLOOR SINK 3/4 GRATE | | | |

2 PLUMBING SYMBOLS
NOT TO SCALE

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FDP
FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DRIVE
RICHMOND, TX 77406

SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
THE ITEM APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO.-48854119 ON: 07/15/2025

ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS PLUMBING PLAN


P-QF1.4

| FOOD SERVICE ELECTRICAL SCHEDULE | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR ELECTRICAL COORDINATION NOTES | | | | | | | | |
| FDP ENO | FDP ECONN | FDP ELOAD | FDP EVOLT | FDP EPH | FDP ESERVICE TO | FDP ELOC | FDP EAFF | FDP EREMARKS |
| E10 | DR | 16.0A | 120 | 1 | CONVENIENCE | WALL | 24" | MOUNT HORIZONTAL |
| E13 | WPR | 16.0A | 120 | 1 | CONVENIENCE | WALL | 24" | MOUNT HORIZONTAL |
| E15 | JB | --- | --- | --- | FIRE PROT. SYSTEM | WALL | 48" | RECESSED EMPTY CONDUIT FOR FIRE PULL |
| E101 | JB | 5.1A | 120 | 1 | AIR SCREEN | WALL | 82" | BTC; MAGNETIC REED SWITCH ON DOOR JAMB & DOOR |
| E102A | JB | 16.0A | 120 | 1 | DOOR HEATER/LIGHTS | CLG | DFA | BTC |
| E102B | JB | 5.0A | 120 | 1 | TEMP. ALARM | CLG | DFA | BTC |
| E102C | JB | 5.0A | 120 | 1 | PRESSURE RELIEF PORT | CLG | DFA | BTC |
| E102E | JB | 10.0A | 120 | 1 | PANIC ALARM BUTTON | CLG | DFA | BTC-INTERCONNECT TO STROBE LIGHT/HORN ABOVE FREEZER DOOR AND IN CAFETORIUM |
| E103 | JB/DS | 21.9A | 208 | 3 | REFRIGERATION SYSTEM | VERIFY | VERIFY | BTC |
| E103C | JB | 9.1A | 208 | 1 | FREEZER COIL | CLG | DFA | BTC |
| E103D | JB | 1.8A | 120 | 1 | COOLER COIL | CLG | DFA | BTC |
| E103E | JB | --- | --- | --- | DATA CONNECTION | CLG | DFA | BTC; RUN TO NEAREST IDF / MDF ROOM |
| E103F | JB | 16.0A | 120 | 1 | DRAIN LINE HEATER | CLG | DFA | BTC; DEDICATED CIRCUIT |
| E109 | DR | 11.9A | 120 | 1 | ICE MACHINE | WALL | 60" | --- |
| E110 | DR | 16.0A | 120 | 1 | CLOTHES WASHER | WALL | 48" | -- |
| E110A | SR | 30.0A | 208 | 1 | CLOTHES DRYER | WALL | 48" | VERIFY NEMA PLUG RECEPTACLE |
| E123 | JB | 3.0HP | 208 | 3 | DISPOSER | WALL | 24" | BTC; CONNECT THRU C.P. TO DISPOSER |

| FOOD SERVICE ELECTRICAL SCHEDULE | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR ELECTRICAL COORDINATION NOTES | | | | | | | | |
| FDP ENO | FDP ECONN | FDP ELOAD | FDP EVOLT | FDP EPH | FDP ESERVICE TO | FDP ELOC | FDP EAFF | FDP EREMARKS |
| E129 | DCR | 16.0A | 120 | 1 | TABLE RECEPTACLE | CLG | 84" | TWISTLOCK PLUG & RECEPTACLE |
| E139 | DCR | 15.0A | 120 | 1 | INSUL. MOBILE PROOFER | CEILING | DFA | -- |
| E151 | JB | 1.0A | 120 | 1 | FIRE PROT. SYSTEM | CLG | DFA | BTC |
| E161 | (2)DR | 6.0A EA. | 120 | 1 | CONVECTION OVEN | WALL | 24"/48" | SHUNT TRIP BREAKER |
| E163 | DR | 5.0A | 120 | 1 | TILT BRAISING PAN | WALL | 24" | SHUNT TRIP BREAKER |
| E172 | (2)JB | 15.0A EA. | 208 | 1 | COMBI OVEN | WALL | 24"/48" | BTC- SHUNT TRIP BREAKER |
| E187 | JB | 15.5A | 120/208 | 1 | HEATED CABINET | WALL | 96" | BTC; MOUNT ON KITCHEN SIDE |
| E188 | JB | 7.2A | 120 | 1 | REFRIGERATOR | WALL | 96" | BTC; MOUNT ON KITCHEN SIDE-OMIT PLUG, UNIT TO BE HARDWIRED |
| E201A | PMR | 28.0A | 208 | 1 | HOT FOOD COUNTER | FLOOR | 4.5" | BTC |
| E201B | PMR | 16.0A | 120 | 1 | COLD FOOD COUNTER | FLR | 4.5" | --- |
| E209 | PMR | 8.0A | 120 | 1 | DROP FRONT MILK COOLER-8 CASE | FLR | 4.5" | --- |
| E214 | PMR | 16.0A | 120 | 1 | CASH REGISTER | FLR | 4.5" | DEDICATED CIRCUIT |
| E214A | CS | --- | --- | --- | POS | FLOOR | 6" | BTC; CONDUIT W/DATA LINE TO RUN TO MANAGER'S OFFICE OR IDF ROOM-VERIFY |
| E250 | JB/DS-JB | 51.7A | 480 | 3 | DISHMACHINE | WALL | 66" | BTC; EXTEND FROM JB/DS AT NEAREST WALL |
| E615 | DR | 5.0A | 120 | 1 | VIDEO / DATA SYSTEM | CLG | VERIFY | PROVIDE DCO AT VIDEO LOCATION |
| E615A | JB | --- | --- | --- | VIDEO / DATA SYSTEM | CLG | VERIFY | PROVIDE JB AT DATA LOCATION |

DIVISION 26 TO PROVIDE, COORDINATE, AND INSTALL THE FOLLOWING:
1. AUDIBLE DOORBELL AT RECEIVING DOOR ON EXTERIOR WALL THAT CAN BE HEARD THROUGHOUT THE ENTIRE KITCHEN, OFFICE AND DRY STORAGE ROOM.
2. ADEQUATE LIGHTING AT RECEIVING DOOR.
3. EDWARDS 860 SERIES (OR EQUAL) RED LENS, SURFACE-MOUNTED XENON EMERGENCY STROBE BEACONS. ONE (1) TO BE LOCATED IN THE KITCHEN ABOVE WALK-IN FREEZER DOOR (OR COOLER DOOR WHEN FREEZER IS WITHIN COOLER IN AN 'INLINE' ASSEMBLY), AND ONE (1) TO BE LOCATED IN THE CAFETORIUM (COORDINATE LOCATION WITH OWNERS). PROVIDE CONDUIT, WIRING, AND INTERCONNECT THE ILLUMINATED PUSH BUTTON PANIC ALARM IN THE WALK-IN FREEZER TO BOTH STROBE BEACONS (***CRITICAL***).


DIVISION 27 TO PROVIDE THE FOLLOWING:
1. CONDUIT, DATA, AND INTERCONNECTION FROM THE ILLUMINATED PUSH BUTTON PANIC ALARM INSIDE THE WALK-IN FREEZER TO THE BUILDING AUTOMATION SYSTEM. WHEN ACTIVATED, FACILITY PERSONNEL TO BE NOTIFIED - COORDINATE NOTIFICATION REQUIREMENTS WITH THE OWNER (***CRITICAL***).





1 FOOD SERVICE ELECTRICAL PLAN
1/4" = 1'-0"





NOTE:
(FOR GRAPHICAL REPRESENTATION ONLY)
SECTION 11 40 00 TO VERIFY LOCATION OF REFRIGERATION SYSTEM WITH APPROVED ARCHITECTURAL DRAWINGS.








6 COLD STORAGE ASSEMBLY ENTRAPMENT PANIC ALARM DETAIL
NOT TO SCALE





3 PEDESTAL MOUNTED RECEPTACLE DETAIL
NOT TO SCALE

NOTE:
REFER TO FDP EQUIPMENT PLAN FOR SPECIFIC COMPONENTS UNDER HOOD. ALL EQUIPMENT SHOWN HERE FOR GRAPHICAL REPRESENTATION ONLY.




| | |
|---|---|
| A | S/S ENCLOSURE W/AGENT TANK AND NITROGEN CARTRIDGE |
| B | DUCT NOZZLE(S) |
| C | PLENUM NOZZLE(S) |
| D | SURFACE PROTECTION NOZZLE(S) |
| E | FUSIBLE LINK(S) |
| F | (2) WIRES FROM FIRE SYSTEM TO SHUNT TRIP BREAKERS FOR SHUT DOWN OF ELECTRICAL CONNECTIONS LOCATED BENEATH EXHAUST HOOD DURING FIRE MODE |
| G | REMOTE FIRE PULL |
| H | GAS VALVE |
| I | GAS SUPPLY (AS REQUIRED) |

4 FIRE PROTECTION SYSTEM TYPICAL DETAIL
NOT TO SCALE




5 FIRE PROTECTION SYSTEM RECESSED FIRE PULL DETAIL
NOT TO SCALE

| | | | | | |
|---|---|---|---|---|---|
| SCR | CONDUIT STUB BTC ON RECEPT FURNISH WITH EQUIPMENT | | CC | CONDUIT FOR COMPUTER CABLES |
| CS | CONDUIT STUB UP/OUT FOR DIRECT CONNECTION | | BTC | BRANCH TO CONNECTION ON EQUIPMENT |
| DR | DUPLEX RECEPTACLE | | WPR | WATERPROOF RECEPTACLE (SPRING COVER) |
| SR | SINGLE PURPOSE RECEPTACLE-1PH | | FPB | FIRE PROTECTION BUZZER |
| SR | SINGLE PURPOSE RECPTACLE-3PH | | BSC | BEVERAGE SYSTEM CONDUIT |
| FR | FLUSH FLOOR RECEPTACLE | | DFA | DROP FROM ABOVE |
| PMR | PEDESTAL MOUNTED RECEPTACLE | | AFF | ABOVE FINISH FLOOR |
| DCR | DROP CORD RECEPTACLE | | CS/JB | JUNCTION BOX ON PEDESTAL |
| JB | JUNCTION BOX ON CEILING | | SW | SWITCH |
| JB | JUNCTION BOX IN WALL | | D | DATA |
| JB/DS | JUNCTION BOX WITH DISCONNECT BY DIV.26 | | | |

2 ELECTRICAL SYMBOLS
NOT TO SCALE

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DRIVE
RICHMOND, TX 77406


SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
488543119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
ELECTRONICALLY SEALING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 488543119 ON 07/18/2025


ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS ELECTRICAL PLAN

P-QF1.5

**MODEL NO. ZS1-02Z-CT3-EST OUTDOOR AIR COOLED REFRIGERATION SYSTEM**
**ITEM NO. 103**




NOTE:
- CRANKCASE HEATERS
- FAN CYCLING SWITCHES
- 24" STANDS & STAINLESS STEEL SKIRTING TO BE SHIPPED LOOSE FOR FIELD INSTALLATION
- DOOR SENSOR FOR EACH WALK-IN
- REFRIGERANT DETECTION SYSTEM
- CHECK VALVE (SHIPPED LOOSE)
- SHUT OFF VALVE (SHIPPED LOOSE)

RACK WEIGHT: 600 LBS.

# ADT ENGINEERING SUMMARY

**POWER SUPPLY: 208-230/60/3**
**CONNECTED LOAD: 21.8 AMPS**

**MOPD: 30 AMP**
**MINIMUM CIRCUIT AMPACITY: 24.1**

| SYSTEM | ITEM # | DESCRIPTION | FIXTURES: TEMP °F FIXT. | FIXTURES: TEMP °F SUCT. | REQ'D FIXTURE BTU/H | REFRIG. | CONDENSING UNIT: COMPRESSOR MODEL NO. | H.P. | RATING @ 60 HZ RLA | V | PH | BTU CAP @ AMB °F 110 | TYPE | REC. CAP. (lbs) | CONDENSER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| A | 102 | WALK-IN COOLER | 35 | 25 | 8506 | 454A | YS11KAE | | 11.2 | 208 | 3 | 11700 | Z | 14.0 | L1R |
| B | 102 | WALK-IN FREEZER | -10 | -20 | 7607 | 454A | YF07KSE | | 10.6 | 208 | 3 | 7610 | Z | 14.0 | L1R |

| SYSTEM | ITEM # | MODEL NO. | EVAPORATOR COILS: QTY | FAN MOTORS @ 60 HZ RLA | V | PH | HEATERS @ 60 HZ RLA | V | PH | DEFR. TYPE | DEFROST CONTROLLER TYPE | CONTROLLER QTY | ACCESSORIES TSTAT | SOL. VALVE | EXP. VLV. | REFRIGERANT LINE SIZES (IN) SUCT. | SUCT. LINE RISER | LIQUID | LINE RUN (FT) | TYPE | TOTAL SYSTEM LOAD |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| A | 102 | BEL0095 | 1 | 1.8 | 115 | 1 | | | | O.C. | ECOSMART | 1 | F | F | EF | 5/8 | 5/8 | 3/8 | 100 | M | 11.2 |
| B | 102 | BEL0065 | 1 | 1.0 | 208 | 1 | 9.1 | 208 | 1 | ELEC | ECOSMART | 1 | F | F | EF | 7/8 | 7/8 | 3/8 | 100 | M | 10.6 |


ALL EVAPORATOR COILS WILL REQUIRE A HOUSE POWER SUPPLY

c UL us LISTED

NOTE:
IT IS THE INSTALLING CONTRACTORS RESPONSIBILITY TO FOLLOW ALL APPLICABLE CODES AND CURRENT REFRIGERATION INDUSTRY STANDARDS AND PRACTICES WHEN DETERMINING LINE SIZES, AND INSTALLING AND STARTING UP RDT EQUIPMENT.


| COMPRESSOR TYPE | DEFROST TYPE | LINE TYPE | EVAPORATOR ACCESSORIES |
|---|---|---|---|
| Z SCROLL | O.C. OFF CYCLE<br>ELEC ELECTRIC | M MAIN - UP TO 100' | EF EEV FACTORY EQUIPPED ON EVAP<br>F FACTORY EQUIPPED ON EVAP |

## PLANVIEW/ CLEARANCE REQUIREMENTS





NOTE: MINIMUM CLEARANCE REQUIRED FOR PROPER OPERATION
NOTE: ROOF CURB OR GROUND PAD CAN BE SAME SIZE AS OUTDOOR UNIT

## SUCTION LINE VERTICAL RISE DETAIL




- Install trap every transition from horizontal to vertical.
- Insulate suction lines with 3/4" wall Armaflex insulation.
- All joints brazed with minimum 15% silver content brazing rod.
- Install "P" trap on suction line every 15' vertical rise.
- Not to exceed 45' vertically over all.
- *If compressor is above the evaporator, Install inverted trap on top of the rise to prevent oil from seeping down when fixture(s) is turned off.

## EVAPORATOR DETAILS - MODEL BEL




| AIR DEFROST Size | DIMENSIONS A Inches | B Inches | C Inches | D Inches | CONNECTIONS (Inches) Coil Inlet | Suction | Drain | Approx. Net Wt. Lbs. | ELECTRICAL DATA Qty. Motors | EC Motor Fan Amps 115V | 208V |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 095 | 45-1/2 | 33-1/4 | | | 1/2 OD | 5/8 OD | 3/4 MPT | 51 | 2 | 1.8 | 1.0 |

| ELECTRIC DEFROST | DIMENSIONS A Inches | B Inches | C Inches | D Inches | CONNECTIONS (Inches) Coil Inlet | Suction | Drain | Approx. Net Wt. Lbs. | ELECTRICAL DATA Qty. Motors | EC Motor Fan Amps | Heater Amps as wired for 208-230/60/1 | 208-230/60/3 | 460/60/1 |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 065 | 45-1/2 | 33-1/4 | - | - | 1/2 OD | 5/8 OD | 3/4 MPT | 54 | 2 | 1.0 | 9.1 | 5.7 | 4.6 |

## ZS SERIES ENGINEERING SPECIFICATIONS

Multi compressor, outdoor, air cooled. The refrigeration package shall be a pre-engineered and factory-assembled unit, trade name "ZS", as manufactured by Refrigeration Design Technologies, 1808 FM Road 66, P.O. Box 622, Waxahachie, Texas 75168. Phone: (972) 937-3215; Fax: (972) 937-0970.

1. Air-Cooled Refrigeration System
The RDT UL Listed "Air-Cooled" Refrigeration system shall be housed in a weather-protected compact powder coated steel frame. The entire housing shall be brushed stainless steel. The unit shall include an air-cooled aluminum fin copper tube condenser designed to operate at 15 degrees TD. The exterior housing shall feature stainless steel one piece louvers. Lifting points shall be integrated in the framing component. Condenser fan motors shall be mounted within the enclosure. The condenser intake surface shall be protected with stainless steel expanded metal guard to protect against vandalism and hail damage.

Each unit shall be equipped with a ball-bearing fan motor, suction filter, sight glass, liquid filter/drier, liquid line inlet and outlet valve, defrost cycle and high pressure super-hose connections. Each unit shall be equipped with fan cycling controls and/or head pressure regulator where required for low ambient conditions.

Condensing unit shall contain scroll, hermetic, semi-hermetic, and/or discus type compressor(s) assembled to operate with the refrigerant specified for both medium and low temperature applications.

2. Evaporator Coils
A. Evaporator coils shall be direct expansion type fabricated of copper tubes with aluminum fins.
B. All evaporator coils shall be provided with solenoid valve, thermostatic or electronic expansion valve and thermostat.

3. Pre-Piping
All refrigerant lines shall be extended to outside of the housing in a neat and orderly manner. All tubing shall be securely supported and anchored with non-corrosive coated clamps.

All joints must be brazed, not soldered.

All piping and controls shall be factory pressure-tested with dry nitrogen.

4. Control Panel
The package shall have a factory-mounted and pre-wired control panel, with main disconnect (non fused) where required, circuit breakers, contactors wired for single point power connection.

General Information
Contractors shall verify all dimensions onsite and coordinate with other trades.

General contractor shall prepare the platform, curbed openings and weatherproofing the unit after installation.

Refrigeration Contractor
All copper tubing to be refrigerant grade. A.C.R. or type "L".

Brazing should be used for all refrigerant piping. Silver solder or soft solder is not acceptable.

All piping to be pressure tested with nitrogen at 300 psi. After the condensing unit and coil have been connected the balance of the system shall be leak tested with the valves open at 200 psi.

The complete system shall be evacuated with a vacuum pump. Each unit should be charged tested and adjusted to assure operation.

Contractor should provide and install the drain-line heater in freezer. Heater shall be connected by electrical contractor. Seal all penetrations through the walk-in units with foam.

Electrical Contractor
Electrical contractor to provide power for refrigeration package and connect control and defrost system as called for in the wiring diagram.


Electrical contractor to connect drain-line heater in the freezer.

All electrical wiring and installation shall be in accordance with the wiring diagram and local codes. Seal all penetrations through the walk-in units with foam.

Plumbing Contractor
Plumbing contractor to provide copper drain lines for walk-in refrigerator and freezer, pitched 1/4" per foot of run. Trap drain-line outside of refrigerated space to avoid entrance of warm, moist air.


All plumbing installation shall be in accordance with local codes.

## EVAPORATOR MOUNTING DETAIL (TYPICAL)




| COIL MODEL | DISTANCE FROM WALL |
|---|---|
| BEL | 1-1/3"H |
| BEM/BEH | 1/2 " W |

## EVAPORATOR PLACEMENT & CLEARANCE REQUIREMENTS LOW PROFILE EVAPORATOR COILS (I.E. - BEL)





SINGLE EVAPORATOR

NOTE:
H = TOTAL HEIGHT OF THE EVAP. COIL

## WIRING DIAGRAM - ECOSMART - AKEA1AE DEMAND DEFROST W/KE2 DOOR SWITCH FOR WALK-IN COOLER WITH ONE COIL 115/60/1

*REFERENCE ENGINEERING SUMMARY FOR COIL AMP DRAW.

| SYS | DESCRIPTION | VOLTAGE |
|---|---|---|
| A | WALK-IN COOLER | 115/1 |





FACTORY WIRING ———
FIELD WIRING - - - -

## WIRING DIAGRAM - ECOSMART - AKEB1EE DEMAND DEFROST W/KE2 DOOR SWITCH FOR WALK-IN FREEZER WITH ONE COIL 208-230/60/1

*REFERENCE ENGINEERING SUMMARY FOR COIL AMP DRAW.

| SYS | DESCRIPTION | VOLTAGE |
|---|---|---|
| B | WALK-IN FREEZER | 208/1 |




FACTORY WIRING ———
FIELD WIRING - - - -

## APPROVAL STATUS

THIS DRAWING REPRESENTS OUR UNDERSTANDING OF THE SPECIFICATIONS. PLEASE REVIEW IT CAREFULLY FOR ACCURACY. CLEARLY AND IN DETAIL NOTE CHANGES REQUIRED.

MARK APPROPRIATE BOX, SIGN, AND DATE BELOW.

- ☐ APPROVED FOR FABRICATION NO CHANGES
- ☐ APPROVED FOR FABRICATION WITH CHANGES NOTED
- ☐ REVISE AND RE-SUBMIT DRAWING

BY: _____ DATE: _____

## NOTICE

THIS DRAWING BEING AN INSTRUMENT OF SERVICE IS AND WILL REMAIN PROPERTY OF REFRIGERATION DESIGN TECHNOLOGIES AND CANNOT BE USED WITHOUT WRITTEN AUTHORIZATION.

| No. | Revision/Issue | Date |
|---|---|---|
| 0 | ORIGINAL ISSUE | 10-2-24 |
| 1 | CHANGED TO A2L EQUIPMENT | 7-16-25 |


REFRIGERATION DESIGN TECHNOLOGIES
1808 FM Road 66 / P.O. Box 622
Waxahachie, Texas
(800) 736-9518
www.rdtonline.com


Consultant:
Foodservice Design Professionals, LLC
The Woodlands, TX

Dealer
-
-

**Pecan Grove Elementary School**
**Fort Bend ISD**

Project No: 31080
Designed By: E. Milligan
Drawn By: A. Rodriguez
Sheet 1.1 of sheets

ISSUE:
12/05/2024 DD PACKAGE
03/11/2025 50% CD PKG.
05/23/2025 90% CD PKG.
07/18/2025 ISSUED FOR BIDDING AND PERMITTING

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DRIVE
RICHMOND, TX 77406


FOODSERVICE DESIGN PROFESSIONALS


SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
68854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 68854119 ON: 07/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS CONDENSING UNITS

P-QF1.6






COOLER DOOR ELEVATION




DOOR ELECTRICAL CONNECTION




TRIM ANGLE
DETAIL #3




PANEL MOUNTED ELECTRICAL CONNECTION

~SPECIFICATIONS~

BOX HEIGHT: FREEZER – 10'-2" OVERALL (7'-6 1/4" INTERIOR)
COOLER – 10'-2" OVERALL (7'-6 1/4" INTERIOR)

CONSTRUCTION: FOAMED IN PLACE
NSF LISTED, STANDARD NO. 7

INSULATION: 4" URETHANE, FINISHED PANEL
UL CLASSIFIED FLAME SPREAD 20
CORE SMOKE DEVELOPED 250

INSTALLATION: INDOOR

FLOOR: (SEE DETAILS) FREEZER – STANDARD W/AMERITUFF STRUCTURAL FLOOR
(1/8" INTEGRAL DIAMOND ALUMINUM TREAD PLATE, 3/4" MARINE PLYWOOD UNDERLAYMENT, FIBERGLASS GRATING SUPPORT)
COOLER – STANDARD W/36" DEEP INTERIOR RAMP & AMERITUFF STRUCTURAL FLOOR
(1/8" INTEGRAL DIAMOND ALUMINUM TREAD PLATE, 3/4" MARINE PLYWOOD UNDERLAYMENT, FIBERGLASS GRATING SUPPORT)

DOOR HARDWARE & ACCESSORIES: (EACH DOOR)
SMOOTH POLISHED DOOR HARDWARE
POWER TO BE STUBBED OUT CEILING PANEL
DRY CONTACT LEADS TO BE STUBBED OUT CEILING PANEL IN A SEPARATE STUB OUT
DEADBOLT HANDLE W/KEYED CYLINDER LOCK, PADLOCK
PROVISION & QUARTER TURN INSIDE RELEASE (EXTERIOR DOOR ONLY)
1/8" STAINLESS STEEL THRESHOLD COVER PLATE
14 GA STAINLESS STEEL SUB THRESHOLD
FRAME HEATER WIRE
HYDRAULIC DOOR CLOSER
IC+ WALK-IN DOOR CONTROLLER AND ALARM SYSTEM INCLUDING:
INTEGRATED LIGHT SWITCH WITH AUTOMATIC LIGHT OFF AND 3-WAY & 4-WAY CAPABILITY
TEMPERATURE MONITOR AND LOGGER WITH HIGH TEMP. AND LOW TEMP. VISUAL AND AUDIO ALARM
F OR C TEMPERATURE SELECTION
INTEGRATED DRY CONTACT FOR ALARM SIGNALING & POWER FAILURE (1A @ 24VAC, 1A @ 30VDC)
DOOR AND WINDOW HEATER CONTROL (WHEN SO EQUIPPED)
HACCP PREVIEW VIA ONBOARD LCD SCREEN
HACCP DOWNLOAD VIA USB
WIFI CONNECTIVITY (INTERNET ENABLED WIFI NETWORK NEEDED)
BATTERY BACKUP
TEMPERATURE ALARM NOTIFICATION VIA EMAIL &/OR EMAIL TO SMS TEXT MESSAGES
POWER FAILURE NOTIFICATION VIA EMAIL &/OR EMAIL TO SMS TEXT MESSAGES
(FOR THIS FEATURE TO WORK THE LOCAL WIFI NETWORK MUST BE POWER PROTECTED AND WORKING AT THE TIME OF POWER FAILURE EVENT)
AUTOMATIC AND ON DEMAND TRANSMISSION OF HACCP DATA VIA EMAIL
ADAPTIVE SETTINGS
MOMENTARY BACK-TO-BACK LIGHT SWITCH W/PILOT
25' AIR TEMPERATURE PROBE
25' SECOND PROBE (EXTENDED) FOR MONITORING THE TEMPERATURE AT A SECOND LOCATION OR FOR MONITORING A SECOND CABINET
DOOR SWITCH TO ENABLE DOOR AJAR ALARM, DOOR AJAR NOTIFICATION VIA EMAIL &/OR EMAIL TO SMS TEXT MESSAGES, AND AUTOMATIC LIGHTS ON WHEN DOOR OPENS
PANIC ALARM WITH ILLUMINATED PANIC BUTTON, ALARM BUZZER WITH LED, & NOTIFICATION VIA EMAIL &/OR EMAIL TO SMS TEXT MESSAGES (1-COOLER, 2-FREEZER)
KASON SCREW-IN VAPOR PROOF LIGHT FIXTURE
W/8.5 WATT SYLVANIA LED BULB & GLOBE
CCI CLEAR VU SWINGING DOOR
3 – KASON #1346 ADJUSTABLE SPRING LOADED HINGES
HEATED VISION WINDOW (14" x 24")
1/8" DIAMOND ALUMINUM TREAD PLATE KICKPLATES @ 36" HIGH I/S & O/S DOOR & FRAME
KASON 1826 INTELLO-VENT WITH LIGHTS (FREEZER DOOR ONLY) – FIELD INTERCONNECTION REQUIRED

PANEL MOUNTED ACCESSORIES: (SHIPPED LOOSE)
1 – KASON 1826 INTELLO-VENT WITH LIGHTS – FIELD INTERCONNECTION REQUIRED
(FOAMED IN PANEL – PER PLAN) (COOLER ONLY)
2 – PCS. TRIM ANGLE – 18 GA STAINLESS STEEL, #3 FINISH
CLOSURE PANEL TO AN EXISTING CEILING (PER PLAN) — VERIFY LENGTH
18 GA STAINLESS STEEL, #3 FINISH
2 – 48" (1810LC) LED LIGHT FIXTURE(S) @ 40W EACH (LIGHTS TO BE INSTALLED PERPENDICULAR TO COILS)
1/8" DIAMOND ALUMINUM TREAD PLATE WAINSCOT @ 36" HIGH (EXPOSED EXTERIOR ONLY)
1 – 1/8" DIAMOND ALUMINUM TREAD PLATE CORNER GUARD(S) @ 36" HIGH
ALUMINUM COVED BASE MOLDING (COMPLETE INTERIOR ONLY)
ROOF SUPPORT ANGLE W/BEAUTY TRIM
2 – BAKELITE LABEL(S) (BLACK) ("FREEZER", "COOLER")
1 – BAKELITE LABEL (YELLOW W/BLACK LETTERING) ("VACUUM PRESSURE RELIEF")
6 MIL POLYETHYLENE VAPOR BARRIER
5 – BELL BOX(ES) & COVER PLATE(S)
2 – DOOR STOP(S)
2 – EDWARDS 860 SERIES STROBE BEACONS
1 – EMERGENCY PRESSURE RELEASE

METAL FINISHES: INTERIOR & EXTERIOR DOOR & FRAME – 18 GA STAINLESS STEEL, #3 FINISH
INTERIOR WALLS & CEILING – WHITE .040 STUCCO ALUMINUM
EXPOSED EXTERIOR – 20 GA STAINLESS STEEL, #3 FINISH
UNEXPOSED EXTERIOR – 26 GA STUCCO ACRYLUME
EXTERIOR FLOOR – 26 GA STUCCO ACRYLUME
EXTERIOR ROOF – 26 GA STUCCO ACRYLUME
INTERIOR FLOOR – AMERITUFF STRUCTURAL FLOOR
(1/8" INTEGRAL DIAMOND ALUMINUM TREAD PLATE, 3/4" MARINE PLYWOOD UNDERLAYMENT, FIBERGLASS GRATING SUPPORT)


REFRIGERATION: BY OTHERS

NOTE: THE LARGEST DOOR PANEL ON THIS JOB IS 57.5" x 114.5".
NOTE: THE LARGEST ROOF/FLOOR PANEL ON THIS JOB IS 46.5" x 129".
CUSTOMER IS TO VERIFY THAT THIS PANEL SIZE WILL NOT CONFLICT WITH ANY JOB SITE RESTRICTIONS.
NOTE: CUSTOMER IS TO VERIFY ALL DIMENSIONS, SECTIONS, DETAILS AND SPECIFICATIONS.
NOTE: MAXIMUM LIGHT CIRCUIT LOAD IS 1200W 120VAC TUNGSTEN, 5A 120VAC ELECTRONIC BALLAST. FOR HIGHER LOADS ADDITIONAL LIGHT FIXTURES MUST BE CONTROLLED VIA RELAY (BY OTHERS).


| ELECTRICAL DATA | |
|---|---|
| ⏚ = POINT OF ELECTRICAL CONNECTIONS. | |
| WALK-IN DOORS: | 115v/1ø – 350w* |
| PANEL MOUNTED ACC: | 115v/1ø – 23w (EACH VENT) |

*NOTE: ADD WATTAGE FOR EACH ADDITIONAL LIGHT FIXTURE IN ACCESSORIES.

## ITEM #102 WALK-IN COOLER/FREEZER





SECTION E – E





SECTION K – K


American Panel's walk-in floor panels with AmeriTuff structural support are designed to withstand uniformly distributed stationary loads of 15,000 lbs. per square foot. American Panel's warranty does not cover damage caused by pallet jacks, forklifts or any other form of heavy-duty rolling traffic. A concrete wearing floor must be installed on top of the AmeriTuff walk-in floor panels for those rolling applications.




TRIM ANGLE
DETAIL #2




CLOSURE PANEL ABOVE WALK-IN DETAIL #4E




DETAIL "A" WAINSCOT AT INTERIOR CORNER

| INSULATION R-VALUES | | |
|---|---|---|
| PANEL TYPE | COOLER | FREEZER |
| 4" WALLS, ROOFS | R-29 | R-32 |
| 5" WALLS, ROOFS | R-36 | R-40 |
| FLOORS | R-25 | R-28 |
| DOORS | R-32 | |

| COOLER DOOR | |
|---|---|
| DOOR FRAME KWHr/DAY | 2.424 |

| FREEZER DOOR | |
|---|---|
| DOOR FRAME KWHr/DAY | 4.392 |

| WALK-IN PANEL R-8967 | | |
|---|---|---|
| BUILDING UNITS | R-8967 | 37N2 |
| USA | | |
| SURFACE BURNING CHARACTERISTICS | | |
| MATERIAL DETAILS | "FLAME SPREAD" | "SMOKE DEVELOPED" |
| ALUMINUM PANELS, PAINTED OR UNPAINTED, 5" OR LESS | 15 | 350 |
| *GALVANIZED STEEL OR STAINLESS STEEL PANELS, PAINTED OR UNPAINTED, 5" OR LESS* | 10 | 400 TO 500 |
| CORE MATERIAL, 6" THICK | 20 | 250 |

AMERICAN PANEL WALK-IN COOLERS AND FREEZERS COMPLY WITH THE 2021 INTERNATIONAL ENERGY CONSERVATION CODE (IECC), SECTION C403.11

THIS AMERICAN PANEL WALK-IN WILL BE MANUFACTURED TO UL & NSF REQUIREMENTS. AMERICAN PANEL ACCEPTS NO LIABILITY FOR LOCAL CODE REQUIREMENTS OF WHICH AMERICAN PANEL HAS NOT BEEN MADE AWARE OF IN WRITING PRIOR TO FABRICATION.

☐ APPROVED SIGNATURE _____
☐ APPROVED AS NOTED PRINT NAME _____
☐ REVISE & RESUBMIT DATE _____

1) Please verify that door swing and location are correct.
2) If this walk-in is to be installed in a depression, or quarry tile is to be applied to the interior, depression depths or tile thickness must be specified to insure proper door height.
3) All site preparation, floor or slab construction, plumbing, electrical connections (including control wiring) by others.
4) ⏚ Electrical: 115-60-1 required above latch side of each door, through ceiling, to operate frame heater and light.
5) Special note to General Contractor and his Sub Contractor for quarry tile or concrete wearing floors: the sheet metal panel facings may be susceptible to staining due to excessive moisture created by hydration of concrete type materials. Therefore, it is absolutely necessary that each room be properly ventilated. Also note that special precautions must be taken when using muriatic acid due to effects hydrochloric acid fumes have on aluminum and stainless steel.
6) This drawing and information contained herein are the exclusive property of American Panel Corporation. It shall be returned to American Panel Corporation upon demand and shall not be reproduced in whole or part, disclosed to anyone else, or used without the written consent of American Panel Corporation.

| REV. | DATE | DESCRIPTION | DH REV. BY | WQ DWG BY |
|---|---|---|---|---|
| A | 1/22/25 | REVISED LAYOUT, SPECS; ADDED DETAIL | DH | WQ |

American Panel — AMERICAN PANEL CORPORATION, 5800 S.E. 78th St. Ocala, Florida 34472, Ph. (352) 245-7055 Fax (352) 245-0726

CUSTOMER: FOODSERVICE DESIGN PROFESSIONALS
PROJECT: SETTLERS WAY ES-FBISD – FORT BEND, TX
DATE: 10/9/24 | DRAWN BY: PM/TR | P.O.#:
SCALE: 3/8"=1'-0" | PROPOSAL#: PD213271 | JOB#: | SHEET: 1 of 1

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

# FBISD BP 013 KITCHEN RENOVATIONS
## FORT BEND INDEPENDENT SCHOOL DISTRICT
## PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DRIVE
RICHMOND, TX 77406


SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL — MELISSA MOORE — 488541119 — PROFESSIONAL MEMBER
Melissa Moore 7/15/2025
THIS ITEM IS PRINTING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 488541119 ON 07/18/2025

AWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS WALK-INS


P-QF1.7

ALL DIMENSIONS MUST BE FIELD VERIFIED PRIOR TO FABRICATION AND INSTALLATION





1 CC1 ITEM #1 PLAN

SCALE: 1/2" = 1'-0"





4 CC1 ITEM #1 SECTION VIEW

SCALE: 1/2" = 1'-0"





8 CC1 ITEM #1 CONTROL PANEL LAYOUT

SCALE: 1 1/2" = 1'-0"





2 CC1 ITEM #1 FRONT ELEVATION

SCALE: 1/2" = 1'-0"




11 CC1 ITEM #1 3D PERSPECTIVE

SCALE:




3 CC1 ITEM #1 REAR ELEVATION

SCALE: 1/2" = 1'-0"



12 CC1 ITEM #1 3D PERSPECTIVE 2

SCALE:

| NO | SERVICE | NEMA | L1 | TRIP |
|---|---|---|---|---|
| | THREE HOT FOOD WELL 208v, 1Ø, 900w EA. | THREE 5-20P | 7.5 | 20 |
| | TWO HOT FOOD WELL 208v, 1Ø, 600w EA. | TWO 5-20P | 5.0 | 20 |
| | 48" HEAT LAMP 208v, 1Ø, 1180W | 6-15P | 9.8 | 20 |
| | LED LIGHTING 208v, 1Ø | 5-15P | 1.0 | 15 |
| | | | | |

NOTE: THIS IS NOT A LOAD CENTER, THIS IS A JUNCTION/DISTRIBUTION BLOCK INSIDE THE BREAKER BOX

11A CC1 ELECTRICAL SCHEDULE
CASHIER COUNTER

| NO | SERVICE | NEMA | L1 | L2 | L3 | TRIP |
|---|---|---|---|---|---|---|
| | THREE HOT FOOD WELL 208v, 1Ø, 900w EA. | THREE 5-20P | 7.5 | | | 20 |
| | | | | 7.5 | | 20 |
| | TWO HOT FOOD WELL 208v, 1Ø, 600w EA. | TWO 5-20P | 5.0 | | | 20 |
| | | | | 5.0 | | 20 |
| | 48" HEAT LAMP 208v, 1Ø, 1180W | 6-15P | 9.8 | | | 20 |
| | | | | 9.8 | | 20 |
| | LED LIGHTING 208v, 1Ø | 5-15P | 1.0 | | | 15 |
| | | | | 1.0 | | 15 |
| | BACK COOLER 208v, 1Ø | 5-15P | 1.0 | | | 15 |
| | | | | 1.0 | | 15 |
| | | | L1= 27.3 | L2= 24.3 | L3= 0.0 | |
| | | | 120/208V, 3Ø, 3Ø 4W, 127-220V | | | |

NOTE: THIS IS NOT A LOAD CENTER, THIS IS A JUNCTION/DISTRIBUTION BLOCK INSIDE THE BREAKER BOX

11B CC1 ELECTRICAL SCHEDULE
HOT FOOD COUNTER #1
(TWO (2) REQUIRED)

| NO | SERVICE | NEMA | L1 | TRIP |
|---|---|---|---|---|
| | RECESSED FROST TOP 208v, 1Ø | 5-15P | 5.0 | 20 |
| | | | 5.0 | 20 |
| | RECESSED HOT/FROST TOP 208v, 1Ø | 5-15P | 5.0 | 20 |
| | | | 5.0 | 20 |
| | LED LIGHTING 208v, 1Ø | 5-15P | 1.0 | 15 |
| | | | 1.0 | 15 |
| | | | L1= 17.0 | L2= 17.0 |
| | | | 120/208V, 3Ø, 3Ø 4W, 127-220V | |

NOTE: THIS IS NOT A LOAD CENTER, THIS IS A JUNCTION/DISTRIBUTION BLOCK INSIDE THE BREAKER BOX

11C CC1 ELECTRICAL SCHEDULE
HOT/FROST COUNTER
(TWO (2) REQUIRED)

EQUIPMENT BY OTHERS

COUNTERCRAFT LAYOUTS, MEPS, AND LOAD CENTERS ARE BASED ON SPECIFIED MANUFACTURERS AND MODELS AS OUTLINED IN THE SPECIFICATIONS IN THE CONTRACT DOCUMENTS. COUNTERCRAFT MUST BE NOTIFIED OF ANY CHANGES TO THE CONTRACT DOCUMENTS IN A TIMELY MANNER.

| NO | REVISIONS | DATE | BY |
|---|---|---|---|
| 1 | PRELIMINARY DWG | 10/21/2024 | MAX |
| 2 | REVISIONS | 11/26/2024 | MAX |
| 3 | | | |
| 4 | | | |
| 5 | | | |
| 6 | | | |
| 7 | | | |
| 8 | | | |
| 9 | | | |

ANOTHER QUALITY PRODUCT FROM
CounterCraft
7007 STEARNS HOUSTON,TEXAS 77021
(713) 747-3611

PROJECT: FBISD Bond Package 013
FOOD SERVICE CONSULTANT: FOODSERVICE DESIGN PROFESSIONALS

PROJECT NO.: -
DATE: 11/26/2024
SCALE: As indicated
DRAWN BY: MAX.C
CHECKED BY: E.S
SHEET NO.: CC1
OF SHEET

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FDP
FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DRIVE
RICHMOND, TX 77406


SEAL

FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
THE ITEM APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO: 48854119 ON: 07/15/2025

ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS SERVING LINE

P-QF1.8




2 / CC2 LAYOUT

SCALE: 3/4" = 1'-0"

EQUIPMENT BY OTHERS

COUNTERCRAFT LAYOUTS, MEPS, AND LOAD CENTERS ARE BASED ON SPECIFIED MANUFACTURERS AND MODELS AS OUTLINED IN THE SPECIFICATIONS IN THE CONTRACT DOCUMENTS. COUNTERCRAFT MUST BE NOTIFIED OF ANY CHANGES TO THE CONTRACT DOCUMENTS IN A TIMELY MANNER.

| NO | REVISIONS / PRELIMINARY/DWG | DATE | BY |
|---|---|---|---|
| 1 | REVISIONS | 12/2/2024 | MAX |
| 2 | | 11/26/2024 | MAX |
| 3 | | | |
| 4 | | | |
| 5 | | | |
| 6 | | | |
| 7 | | | |
| 8 | | | |
| 9 | | | |

ANOTHER QUALITY PRODUCT FROM
CounterCraft
7007 STEARNS HOUSTON,TEXAS 77021
(713) 747-3611

PROJECT: FBISD Bond Package 013
FOOD SERVICE CONSULTANT: FOODSERVICE DESIGN PROFESSIONALS

PROJECT NO: -
DATE: 11/26/2024
SCALE: 3/4" = 1'-0"
DRAWN BY: MAX.C
CHECKED BY: E.S
SHEET NO: CC2
OF SHEET

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FDP
FOODSERVICE DESIGN PROFESSIONALS


FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DRIVE
RICHMOND, TX 77406

SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
88854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
THE ITEM APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 88854119 ON: 07/15/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS SERVING LINE

P-QF1.9




1 FOOD SERVICE EQUIPMENT PLAN - DEMO PLAN
1/4" = 1'-0"

NOTE: ALL EQUIPMENT MAKERED WITH A DIAGONAL HATCH TO BE RELOCATED PER TEMPORARY SERVING PLAN SHEET P-QF2.0

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

# FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DRIVE
RICHMOND, TX 77406

SEAL


FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
FCSI
488544119
PROFESSIONAL MEMBER
7/15/2025
DOCUMENT PREPARING ON THIS SHEET WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 488544119
CPL 07/15/2025


ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


**PROJ. NO.:** 23-25
**DATE:** 07/18/25
ISSUED FOR BIDDING AND PERMITTING

FS DEMO PLAN

P-QF2.0




4 FOOD SERVICE ELECTRICAL PLAN - TEMPORARY SERVING
1/4" = 1'-0"

| FOOD SERVICE ELECTRICAL SCHEDULE - TEMPORARY SERVING | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR ELECTRICAL COORDINATION NOTES | | | | | | | | |
| FDP ENO | FDP ECONN | FDP ELOAD | FDP EVOLT | FDP EPH | FDP ESERVICE TO | FDP ELOC | FDP EAFF | FDP EREMARKS |
| E800A | DR | 16.0A | 120 | 1 | CONVENIENCE | WALL | 24" | --- |
| E800B | DR | 16.0A | 120 | 1 | CONVENIENCE | WALL | 24" | DEDICATED CIRCUIT |
| E800C | JB | --- | --- | -- | DATA CONNECTION | WALL | 24" | --- |
| E806 | DR | 16.0A | 120 | 1 | TRANSPORT CABINET | WALL | 24" | --- |
| E808 | SR | 7.8A | 120/208 | 1 | HEATED CABINET | WALL | 96" | BTC; OMIT PLUG, UNIT TO BE HARDWIRED |
| E809 | DR | 8.2A | 120 | 1 | REFRIGERATOR | WALL | 96" | BTC; OMIT PLUG, UNIT TO BE HARDWIRED |
| E810 | CS/SR | 13.3A | 208 | 1 | (4) HOT WELLS | WALL | 24" | EXTEND TO EQUIPMENT - CONFIRM NEMA PLUG |
| E810A | SR | 7.9A | 208 | 1 | (2) HOT WELLS | WALL | 24" | EXTEND TO EQUIPMENT - CONFIRM NEMA PLUG |
| E810B | DR | 5.0A | 120 | 1 | COLD PAN | WALL | 24" | EXTEND TO EQUIPMENT |
| E810C | DR | 10.0A | 120 | 1 | BEVERAGE | WALL | 24" | EXTEND TO EQUIPMENT |
| E811 | DR | 16.0A | 120 | 1 | CASH REGISTER | WALL | 24" | DEDICATED CIRCUIT - EXTEND TO EQUIPMENT |
| E811A | JB | - | --- | 1 | POS | WALL | 24" | BTC |

| | | | | | |
|---|---|---|---|---|---|
| | SCR | CONDUIT STUB BTC ON RECEPT FURNISH WITH EQUIPMENT | | CC | CONDUIT FOR COMPUTER CABLES |
| • | CS | CONDUIT STUB UP/OUT FOR DIRECT CONNECTION | | BTC | BRANCH TO CONNECTION ON EQUIPMENT |
| | DR | DUPLEX RECEPTACLE | | WPR | WATERPROOF RECEPTACLE (SPRING COVER) |
| | SR | SINGLE PURPOSE RECEPTACLE-1PH | ⟋ | FPB | FIRE PROTECTION BUZZER |
| | SR | SINGLE PURPOSE RECPTACLE-3PH | | BSC | BEVERAGE SYSTEM CONDUIT |
| | FR | FLUSH FLOOR RECEPTACLE | | DFA | DROP FROM ABOVE |
| | PMR | PEDESTAL MOUNTED RECEPTACLE | | AFF | ABOVE FINISH FLOOR |
| | DCR | DROP CORD RECEPTACLE | | CS/JB | JUNCTION BOX ON PEDESTAL |
| | JB | JUNCTION BOX ON CEILING | | SW | SWITCH |
| | JB | JUNCTION BOX IN WALL | | D | DATA |
| | JB/DS | JUNCTION BOX WITH DISCONNECT BY DIV.26 | | | |


5 ELECTRICAL SYMBOLS 1
NOT TO SCALE

| FOOD SERVICE PLUMBING SCHEDULE - TEMPORARY SERVING | | | | | | |
|---|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR PLUMBING COORDINATION NOTES | | | | | | |
| FDP PNO | FDP PSIZE | FDP PCONN | FDP PSERVICE TO | FDP PLOC | FDP PAFF | FDP PREMARKS |
| P11C | 1/2" | H & C WATER | FAUCET | WALL | 18" | FURNISHED & INSTALLED BY DIV. 22 |
| P11D | 1 1/2" | DIRECT DRAIN | HAND SINK | WALL | 15" | FURNISHED & INSTALLED BY DIV. 22 |
| P249 | 3/4" | H & C WATER | FAUCET | WALL | 13" | BTC |


| | | | | | |
|---|---|---|---|---|---|
| | HW | HOT WATER | | FFD | FUNNEL FLOOR DRAIN |
| | CW | COLD WATER | | EVC | EXHAUST VENT CONNECTION |
| | HTW | 180 F HOT WATER | | SVC | SUPPLY VENT CONNECTION |
| | | CHILLED WATER | | FR | DIRECT-CONNECTED FLUE RISER |
| | W | DIRECT WASTE | | PS | PIPE SLEEVE |
| | IW | INDIRECT WASTE | | | COMPRESSED AIR |
| | | GAS SUPPLY | | | CO2 |
| | | STEAM SUPPLY | | AFF | ABOVE FINISHED FLOOR |
| | CR | CONDENSATE RETURN | | BTC | BRANCH TO CONN. ON EQUIP |
| | DR | DRAIN | | DFA | DROP FROM ABOVE |
| | FD | FLOOR DRAIN | | CLG | CEILING |
| | FST | FLOOR SINK 3/4 GRATE | | | |
| | FSH | FLOOR SINK 3/4 GRATE | | | |

3 PLUMBING SYMBOLS 1
NOT TO SCALE

| FOOD SERVICE EQUIPMENT SCHEDULE - TEMPORARY SERVING | | | | | |
|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR GENERAL CONTRACTOR & HEALTH DEPARTMENT COORDINATION NOTES | | | | | |
| FDP ITEM | FDP QTY | FDP DESCRIPTION | FDP REMARKS | MANUFACTURER | MODEL |
| 209 | 2 | DROP FRONT MILK COOLER - 8 CASE | | TRAULSEN | RMC34D4 |
| 804 | 2 | S/S SPLASH GUARDS | | CUSTOM FABRIACTED | |
| 805 | 1 | THREE COMPARTMENT SINK NO DISPOSER | EXISTING | | |
| 806 | 4 | TRANSPORT CART | EXISTING | | |
| 807 | 2 | HAND LAV | EXISTING | | |
| 808 | 2 | REACH IN HEATED CABINET - 1DR | EXISTING | | |
| 809 | 2 | REACH IN REFRIGERATOR - 1DR. | EXISTING | | |
| 810 | 1 | DRY STORAGE SHELVING | EXISTING | | |
| 811 | 1 | CASH REGISTER | OWNER FURNISHED | | |
| 812 | 1 | SERVING COUNTER | EXISTING | | |




1 FOOD SERVICE EQUIPMENT PLAN - TEMPORARY SERVING
1/4" = 1'-0"




2 FOOD SERVICE PLUMBING PLAN - TEMPORARY SERVING
1/4" = 1'-0"

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DRIVE
RICHMOND, TX 77406

SEAL


FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
888544119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
THIS ITEM IS DIGITALLY SIGNED AND SEALED BY MELISSA MOORE, FCSI NO. 888544119
ON: 07/18/2025


ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



**PROJ. NO.:** 23-25
**DATE:** 07/18/25
ISSUED FOR BIDDING AND PERMITTING

FS TEMPORARY SERVING


P-QF2.1




11 ELEVATION @ HOLDING
1/2" = 1'-0"




10 ELEVATION @ DISPOSER & TRAY DROP WINDOW
1/2" = 1'-0"




9 ELEVATION @ DISHMACHINE
1/2" = 1'-0"




8 ELEVATION @ THREE COMPARTMENT SINK
1/2" = 1'-0"




7 ELEVATION @ SETUP TABLE & MOBILE HEATED CABINET
1/2" = 1'-0"




6 ELEVATION @ PRODUCTION 2
1/2" = 1'-0"




5 ELEVATION @ PRODUCTION 1
1/2" = 1'-0"




4 ELEVATION @ SETUP TABLE & MIXER
1/2" = 1'-0"



3 ELEVATION @ COLD STORAGE ASSEMBLY
1/2" = 1'-0"



2 ELEVATION @ SETUP TABLE
1/2" = 1'-0"



1 ELEVATION @ PREP SINK & ICE MACHINE
1/2" = 1'-0"

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DRIVE
RICHMOND, TX 77406


SEAL

FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
46854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
DOCUMENT WAS PREPARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO.-46854119 ON: 07/18/2025



ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS ELEVATIONS


P-QF3.1





7 DRAINBOARD SECTION
NOT TO SCALE





6 WORKTABLE - ISLAND W/ S.BAR UT RACK & END UC DCO SECTION
NOT TO SCALE





5 SINK - UTENSIL WASH SECTION
NOT TO SCALE




3 DRAINBOARD - UTENSIL WASH SECTION
NOT TO SCALE




4 SINK - PREP TABLE SECTION
NOT TO SCALE




8 WAREWASH - TRAY DROP/SOAK SINK SECTION
NOT TO SCALE

**SECTION DETAIL NOTES**:

1. 1 1/2" X 1 1/2" X 1/8" GALVANIZED ANGLE IRON.
2. 1" X 4" 14 GAUGE STAINLESS STEEL HAT CHANNEL.
3. 16 GAUGE STAINLESS STEEL C-CHANNEL.
4. 16 GAUGE STAINLESS STEEL UNDER SHELF, COVE UP REAR 2", TURN DOWN FRONT 1 1/2".
5. 1/2" CEMENT BACKERBOARD WITH TILE FRONT BY TRADE CONTRACTOR OR COUNTER MANUFACTURER. VERIFY FINISH WITH ARCHITECTURAL DRAWINGS.
6. COLD PAN - 2" RIGID INSULATION WITH 1" C.P. DRAIN - 16 GAUGE STAINLESS STEEL SECTION FALSE BOTTOM. PERFORATE FALSE BOTTOM WITH 1/4" DIA. HOLES AT 3" O.C.
7. 18 GAUGE STAINLESS STEEL INSULATED DOUBLE PAN DOOR WITH RECESSED PULL.
8. MANIFOLD DRAINS AT HOT FOOD UNITS WITH 1" TYPE 'K' COPPER AND EXTEND TO VALVE IN PLUMBING COMPARTMENT.
9. FINISHED TRUE AND LEVEL MASONRY BASE BY DIVISION 09. CLOSE COUNTER BODY AT BASE AND SEAL BY SECTION 11 40 00.
10. FISHER #22314 DRAIN WITH TAILPIECE AND OVERFLOW.
11. 14 GAUGE STAINLESS STEEL BRACKET WITH DRAIN HANDLE BUSHING.
12. 16 GAUGE STAINLESS STEEL 'Z' CLIP TO WALL AND SEAL.
13. 1 5/8" DIA. 16 GAUGE STAINLESS STEEL LEGS AND CROSS RAILS.
14. 1/2" S/S TUBING DRAIN LINE - STRAP TO SHELF AND WALL - EXTEND DOWN TO TOP OF SPLASH.
15. 1 5/8" DIA. 16 GAUGE STAINLESS STEEL TUBING - SUPPORT FRONT OF SHELF WITH 1/2" ALL-THREAD INSIDE TUBING EXTENDING TO STRUCTURE ABOVE.
16. 1/4" S/S BAR STOCK WELDED TO TOP OF EACH POST - POT HOOKS TO BE COMPONENT HARDWARE #J77-4401 SPACED 8" O.C.
17. 1 5/8" 16 GAUGE STAINLESS STEEL TUBING - BOLT TO ANGLE IRON AND EXTEND UP THRU SPLASH TO 7'-0" A.F.F.
18. OVER SHELF - 16 GAUGE STAINLESS STEEL, COVE UP REAR 2", TURN FRONT AND ENDS DOWN 1", ENDS TO BE CAPPED WITH EASED CORNERS WHERE ADJACENT TO WALL / FIXTURE.
19. 18 GAUGE STAINLESS STEEL LOUVERED PANEL.
20. 18 GAUGE STAINLESS STEEL LOUVERED DOUBLE PAN DOOR WITH RECESSED PULLS.
21. NUMBER NOT USED.
22. 18 GAUGE STAINLESS STEEL INSULATED DOUBLE PAN SLIDING DOOR WITH COMPONENT HARDWARE COMPONENTS

    A. #B57 - (VERIFY LENGTH) EXTRUDED ALUMINUM TRACK.
    B. #B58-5511 & #B58-5521 FRONT & REAR DOOR SHEAVES.
    C. #B62-1093 DOOR GUIDE.
    D. #B60-1086 DOOR STOPS WHERE NEEDED.
    E. #P62-1010 RECESS PULLS.

1 SECTION DETAIL NOTES
NOT TO SCALE

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DRIVE
RICHMOND, TX 77406

SEAL


FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
#88554119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
ELECTRONICALLY SEALING ON THIS DOCUMENT BY MELISSA MOORE, FCSI NO. #88554119
ON: 07/18/2025

ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

**PROJ. NO.:** 23-25
**DATE:** 07/18/25
ISSUED FOR BIDDING AND PERMITTING


FS SECTIONS & DETAILS

P-QF4.1





3 COLD STORAGE ASSEMBLY ESCUTCHEON & PENETRATION DETAIL
NOT TO SCALE


NOTE:
COORDINATE ALL RECEPTACLES WITH ELECTRICAL CONTRACT DRAWING REQUIREMENTS, REFER TO ELECTRICAL PLAN




5 WORKTABLE - ELECTRICAL RECEPTACLE MOUNTED UNDER TOP DETAIL
NOT TO SCALE


| COMPONENT HARDWARE DRAWER PAN AND SLIDES | | |
|---|---|---|
| TYPE | DRAWER PAN MODEL NO. | DRAWER SLIDE MODEL NO. |
| UTILITY | S80-2020 | S52-2020 |
| BREAD | S83-2020 | S52-0026 |
| REFRIGERATOR | S81-1520 | S52-0024 |








6 DRAWER ASSEMBLY DETAIL
NOT TO SCALE


NOTE: DO NOT LOCATE CAN OPENER PAD IN A POSITION THAT WOULD ALLOW CAN OPENER TO OBSTRUCT OPENING OF DRAWERS, DOORS, ETC.





10 SINK - PREP MARINE EDGE CAN OPENER DETAIL
NOT TO SCALE





11 UNDER SHELF DETAIL
NOT TO SCALE




12 FIRE PROTECTION SYSTEM FIRE PULL DETAIL
NOT TO SCALE




13 EXHAUST HOOD CLOSURE PANEL DETAIL
NOT TO SCALE




14 DISHTABLE - SOILED & CLEAN CONNECTION DETAIL
NOT TO SCALE

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

# FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
## PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DRIVE
RICHMOND, TX 77406


SEAL

FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
FCSI 68654119
PROFESSIONAL MEMBER
7/15/2025
ITEMS APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 68654119
ON: 07/15/2025



ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS DETAILS

P-QF4.2





1 EDGE DETAILS
NOT TO SCALE





4 WAREWASH - TRAY DROP WINDOW SECTION
NOT TO SCALE





3 WAREWASH - TRAY DROP SECTION
NOT TO SCALE





2 BACKSPLASH DETAILS
NOT TO SCALE





6 SPLASH @ SYPHON BREAKER
NOT TO SCALE





8 VACUUM BREAKER DETAIL
NOT TO SCALE





5 DISHMACHINE VENT RISER DETAIL
NOT TO SCALE





12 HOSE BIBB DETAIL
NOT TO SCALE





11 SINK ASSEMBLY DETAIL
NOT TO SCALE





9 DISPOSER SWITCH BRACKET DETAIL
NOT TO SCALE





7 SPLASH @ UPRIGHT (DISH TABLE) DETAIL
NOT TO SCALE





13 SINK - DISPOSER W/ REMOVABLE ANGLED RACK GUIDE DETAIL
NOT TO SCALE




14 FILL FAUCET DETAIL
NOT TO SCALE




15 COLD STORAGE ASSEMBLY WALL PENETRATION DETAIL
NOT TO SCALE




## CUSTOM FABRICATION NOTES:

A. WORK SHALL BE DONE IN AN APPROVED WORKMANLIKE MANNER, TO COMPLETE SATISFACTION OF FOODSERVICE DESIGN PROFESSIONALS (FDP).

B. STAINLESS STEEL SHALL BE U.S. STANDARD GAUGES AS CALLED FOR. 18-8, TYPE 304, NOT OVER .012% MAXIMUM CARBON, NO. 4 FINISH.

C. GALVANIZED IRON SHALL BE ARMCO OR EQUAL. FRAMEWORK OF GALVANIZED IRON SHALL BE WELDED CONSTRUCTION, HAVING WELDS SMOOTH, AND WHERE GALVANIZING HAS BURNED OFF, TOUCHED UP WITH HIGH-GRADE ALUMINUM BRONZE.

D. LEGS AND CROSSRAIL SHALL BE CONTINUOUSLY WELDED, UNLESS OTHERWISE NOTED, AND GROUND SMOOTH.

E. BOTTOM OF LEGS AT FLOOR SHALL BE FITTED WITH SANITARY STAINLESS STEEL BULLET-TYPE FOOT, WITH NO LESS THAN 1/2" ADJUSTMENT.

F. LEGS SHALL BE FASTENED TO EQUIPMENT AS FOLLOWS:

01. TO SINKS BY MEANS OF CLOSED GUSSETS. GUSSETS SHALL BE S/S, REINFORCED WITH BUSHING, HAVING SET SCREWS FOR SECURING LEGS.

02. TO TABLES AND DRAINBOARDS WITH CLOSED GUSSETS WHICH SHALL BE WELDED TO GALVANIZED HAT SECTIONS OR CHANNELS, 14 GAUGE OR HEAVIER, EXPOSED HAT SECTIONS HAVING CLOSED ENDS. BRACING SHALL BE UNDERSIDE OF TOPS.

G. CLOSED GUSSETS SHALL BE 3" MINIMUM DIAMETER AT TOP, WELDED TO FRAME MEMBERS OR TO SINK BOTTOM.

H. ROLLS SHALL BE 1 1/2" DIAMETER, EXCEPT AS DETAILED TO THE CONTRARY, WITH CORNERS BULLNOSED, GROUND, AND POLISHED.

I. SEAMS AND JOINTS SHALL BE SHOP-WELDED WHERE POSSIBLE. WELDS TO BE GROUND AND POLISHED TO MATCH ORIGINAL FINISH. MATERIALS 18 GAUGE OR HEAVIER SHALL BE WELDED.

J. METAL TOPS SHALL BE ONE-PIECE WELDED CONSTRUCTION UNLESS SPECIFIED OTHERWISE, REINFORCED ON UNDERSIDE WITH GALVANIZED HAT SECTIONS OR CHANNELS WELDED IN PLACE. CROSSBRACE TO BE NOT MORE THAN 30" ON CENTERS.

K. HARDWARE SHALL BE SOLID MATERIALS AND EXCEPT WHERE EXPOSED OR SPECIFIED TO THE CONTRARY, OF CAST BRASS, CHROME-PLATED. IDENTIFY ALL HARDWARE WITH MANUFACTURER'S NAME AND NUMBER SO THAT BROKEN OR WORN PARTS MAY BE ORDERED AND REPLACED.

L. FABRICATE SINK COMPARTMENTS WITH 3/4" COVED VERTICAL AND HORIZONTAL CORNERS. MULTIPLE- COMPARTMENT PARTITIONS TO BE DOUBLE THICKNESS, CONTINUOUSLY WELDED WHERE SHEETS JOIN AT TOP. FRONT OF MULTIPLE-COMPARTMENT PARTITIONS TO BE CONTINUOUS ON EXTERIOR. BOTTOMS SHALL BE CREASED TO DRAIN.

M. ENDS OF FIXTURES, SPLASHBACKS, SHELVES, ETC., SHALL BE FINISHED FLUSH TO WALLS OR ADJOINING FIXTURES.

N. DISHTABLES, DRAINBOARDS, SPLASHBACKS, AND TURN-UP EDGES SHALL HAVE RADIUS BENDS IN ALL HORIZONTAL AND VERTICAL CORNERS, COVED AT INTERSECTIONS.

O. ROUNDED AND COVED CORNERS OR RADIUS BENDS SHALL BE 1/2" RADIUS OR LONGER.

P. UNDERSIDES OF TOPS TO BE COATED WITH HEAVY-BODIED RESINOUS MATERIAL COMPOUND FOR PERMANENT, NON-FLAKING ADHESION TO METAL, 1/8" THICK, APPLIED AFTER REINFORCING MEMBERS HAVE BEEN INSTALLED, DRYING WITHOUT DIRT-CATCHING CREVICES.

Q. SHELVES ARE TO BE TURNED UP 2" ON THE BACK EDGE. TURN OTHER EDGES DOWN 1 1/2" TO FORM OPEN CHANNELS. REINFORCE SHELF UNITS TO SUPPORT 40 LBS. PER SQUARE FOOT LOADING, PLUS 100% IMPACT LOADING.

R. TRIMWORK AND FRAMING AT MASONRY OPENINGS SHALL BE 18 GAUGE STAINLESS STEEL AND FORMED SO AS TO FIT SNUG TO WALLS AND ADJACENT SURFACES. FRAMING SHALL EXTEND A MINIMUM OF 2" ON EACH SURFACE. SEAL TRIMWORK TO WALLS. REFER TO DRAWINGS.

S. METAL COMPONENTS, UNLESS SPECIFIED OR NOTED OTHERWISE, TO BE THE FOLLOWING GAUGES:

| | |
|---|---|
| TABLETOPS | 14 GAUGE STAINLESS STEEL |
| WALL SHELVES | 16 GAUGE STAINLESS STEEL |
| UNDER SHELVES | 16 GAUGE STAINLESS STEEL |
| SINKS & DRAINBOARDS | 14 GAUGE STAINLESS STEEL |
| EXHAUST DUCTS | 18 GAUGE STAINLESS STEEL |
| LEGS - 1 5/8" DIA. | 16 GAUGE STAINLESS STEEL |

10 CUSTOM FAB NOTES
NOT TO SCALE

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD S DRIVE
RICHMOND, TX 77406

SEAL

FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
46854119
PROFESSIONAL MEMBER
7/15/2025
THE INDIVIDUAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO.-46854119 ON: 07/15/2025


ARCHITECTS

ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

FS DETAILS

P-QF4.3




1 TECHNOLOGY DEMOLITION FLOOR PLAN
p-TD201 1/4" = 1'-0"

**TECHNOLOGY DEMOLITION PLAN GENERAL NOTES**

1. ALL DATA, VOICE, VIDEO AND SECURITY SYSTEMS SHALL REMAIN OPERATIONAL AT ALL TIMES DURING BUSINESS HOURS UNLESS OTHERWISE NOTED. ANY SYSTEM DOWNTIME SHALL BE SCHEDULED WITH THE ARCHITECT/ENGINEER AND OWNER AT LEAST TEN (10) WORKING DAYS IN ADVANCE. CONTRACTOR SHALL DEVELOP A PHASING PLAN AND SCHEDULE OF ANY REQUIRED SYSTEM DOWNTIME FOR REVIEW AND APPROVAL BY THE ARCHITECT/ENGINEER AND OWNER PRIOR TO ANY CONSTRUCTION ACTIVITIES.
2. OWNER SHALL BE RESPONSIBLE FOR POWER DOWN AND START-UP OF ALL DATA, VOICE, VIDEO AND SECURITY SYSTEMS. CONTRACTOR SHALL COORDINATE WITH THE ARCHITECT/ENGINEER AND OWNER AND PROVIDE A MINIMUM OF TEN (10) WORKING DAYS NOTICE FOR SCHEDULING OF ANY REQUIRED DOWNTIME.
3. ALL EXISTING WIRELESS ACCESS POINTS ARE TO BE REMOVED AND RETURNED TO OWNER. CONTRACTOR SHALL RE-INSTALL ALL EXISTING AND NEW WIRELESS ACCESS POINTS AT COMPLETION OF PROJECT.
4. COORDINATE REMOVAL OF EXISTING CAMERA WITH OWNER/ARCHITECT DURING CONSTRUCTION.

**TECHNOLOGY DEMOLITION PLAN KEYED NOTES**

**NOT ALL KEYED BELOW APPLY TO THIS SHEET**

(1) EXISTING DATA/VOICE/WIRELESS ACCESS POINT OUTLET TO BE REMOVED. CONTRACTOR SHALL REMOVE AND DISPOSE OF ALL 4-PAIR CABLES AND WORKSTATION CONNECTING HARDWARE TERMINATED AT THIS LOCATION. IF LOCATION IS NOT RE-USED, CONTRACTOR SHALL SUPPLY AND INSTALL BLANK COVER. CONTRACTOR IS TO REMOVE EACH CABLE TO BE DEMOLISHED FROM THE PATCH PANEL OR TERMINATION BLOCK IN THE TELECOMMUNICATIONS ROOM. REMOVE THE ENTIRE LENGTH OF THE CABLE AND THE CORRESPONDING MODULAR CONNECTOR, FACEPLATE AND ACCESSORIES. NO ABANDONED CABLING IS TO BE LEFT ABOVE CEILING. CONTRACTOR SHALL INSTALL ALL EXISTING AND NEW WIRELESS ACCESS POINTS AT COMPLETION OF PROJECT.

(2) EXISTING VIDEO SURVEILLANCE CAMERA. CONTRACTOR SHALL REMOVE AND RETURN TO OWNER.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

p

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD SOUTH DRIVE
RICHMOND, TX 77406

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD

07/18/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY DEMOLITION FLOOR PLAN

SHEET NO.
p-TD201

# TECHNOLOGY SYMBOLS & LEGEND

## VOICE SYMBOLS

| | |
|---|---|
| | SINGLE VOICE OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| X | VOICE OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |
| | SINGLE VOICE OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED. |
| X | VOICE OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED, X = NUMBER OF CABLE TERMINATIONS PER LOCATION AS INDICATED. |
| | POWER/COMMUNICATIONS POLE WITH A SINGLE VOICE OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| X | POWER/COMMUNICATIONS POLE WITH X = NUMBER OF VOICE OUTLETS, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| | SINGLE VOICE OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE-THRU AS SPECIFIED. |
| X | VOICE OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE -THRU AS SPECIFIED WITH X = NUMBER OF VOICE TERMINATIONS PER LOCATION. |
| W | SINGLE VOICE OUTLET FOR WALL-MOUNTED PHONE, CABLE TYPE AS SPECIFIED, MOUNTED +52-INCHES A.F.F. UNLESS OTHERWISE NOTED. |

## DATA SYMBOLS

| | |
|---|---|
| | SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| X | DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |
| | SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED. |
| X | DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED, X = NUMBER OF CABLE TERMINATIONS PER LOCATION AS INDICATED. |
| | POWER/COMMUNICATIONS POLE WITH A SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| X | POWER/COMMUNICATIONS POLE WITH X = NUMBER OF DATA OUTLETS, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| | SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE-THRU AS SPECIFIED. |
| X | DATA OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE -THRU AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |
| W | SINGLE DATA OUTLET FOR WALL-MOUNTED IP PHONE, CABLE TYPE AS SPECIFIED, MOUNTED +52-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| X | DATA CABLE FOR COMPUTER ON WHEELS, CABLE TYPE AS SPECIFIED MOUNTED + 18-INCHES A.F.F UNLESS OTHERWISE NOTED. X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |
| X | DATA CABLE FOR CEILING MOUNTED WIRELESS ACCESS POINT, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A GREEN ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. |
| X | DATA CABLE FOR CEILING MOUNTED VIDEO SURVEILLANCE CAMERA, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A ORANGE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. REFER TO SECURITY DRAWINGS PRIOR TO INSTALLATION. |
| | DATA CABLE FOR CEILING MOUNTED PROJECTOR, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A BLUE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. REFER TO AUDIO/VISUAL DRAWINGS PRIOR TO INSTALLATION. |
| X | DATA CABLE FOR CEILING MOUNTED AUDIO/VISUAL EQUIPMENT ENCLOSURE, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A BLUE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. REFER TO AUDIO/VISUAL DRAWINGS PRIOR TO INSTALLATION. |
| X | DATA CABLE FOR WALL MOUNTED PROJECTOR, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A BLUE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. REFER TO AUDIO/VISUAL DRAWINGS PRIOR TO INSTALLATION. |

## DATA SYMBOLS, CONT.

| | |
|---|---|
| X CAME | DATA CABLE FOR EXTERIOR WALL MOUNTED VIDEO SURVEILLANCE CAMERA, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A ORANGE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW, REFER TO SECURITY DRAWINGS PRIOR TO INSTALLATION. |
| X CAMW | DATA CABLE FOR INTERIOR WALL MOUNTED SURVEILLANCE CAMERA, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A ORANGE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. |
| X CAME | DATA CABLE FOR EXTERIOR WALL MOUNTED SURVEILLANCE CAMERA, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A ORANGE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. |
| X WAPW | DATA CABLE FOR INTERIOR WALL MOUNTED WIRELESS ACCESS POINT, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A GREEN ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. |
| X WAPE | DATA CABLE FOR EXTERIOR WALL MOUNTED WIRELESS ACCESS POINT, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A GREEN ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. |

## CABLE PLANT & RISER DIAGRAM

| | |
|---|---|
| | MAINTENANCE HOLE, SIZE & TYPE AS SPECIFIED. |
| | PULLBOX, SIZE AND TYPE AS SPECIFIED. |
| UGC | DIRECT BURIED COMMUNICATIONS, CABLE TYPE AS SPECIFIED. |
| AER | AERIAL COMMUNICATIONS, CABLE TYPE AS SPECIFIED. |
| | CONDUIT, SIZE AND TYPE AS SPECIFIED. |

## VOICE/DATA SYMBOLS

| | |
|---|---|
| | SINGLE VOICE & SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| X Y | VOICE & DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. X = NUMBER OF VOICE TERMINATIONS , Y = NUMBER OF DATA TERMINATIONS PER LOCATION. |
| | SINGLE VOICE & SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED. |
| X Y | VOICE & DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED, X = NUMBER OF VOICE OUTLETS AND Y = NUMBER OF DATA OUTLETS PER LOCATION AS INDICATED. |
| | POWER/COMMUNICATIONS POLE WITH A SINGLE VOICE OUTLET AND SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| X Y | POWER/COMMUNICATIONS POLE WITH X = NUMBER OF VOICE TERMINATIONS, Y = NUMBER OF DATA TERMINATIONS, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| | SINGLE VOICE OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE-THRU AS SPECIFIED. |
| X Y | VOICE OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE -THRU AS SPECIFIED WITH X = NUMBER OF VOICE TERMINATIONS, Y = NUMBER OF DATA TERMINATIONS PER LOCATION. |

## FIBER OPTIC SYMBOLS

| | |
|---|---|
| | SINGLE FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| X | FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |
| | SINGLE FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED. |
| X | FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED, X = NUMBER OF CABLE TERMINATIONS PER LOCATION AS INDICATED. |
| | POWER/COMMUNICATIONS POLE WITH A SINGLE FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| X | POWER/COMMUNICATIONS POLE WITH X = NUMBER OF FIBER OPTIC OUTLETS, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| | SINGLE FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE-THRU AS SPECIFIED. |
| X | FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE -THRU AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |

## ROUGH-IN & MISC. SYMBOLS

| | |
|---|---|
| R | ROUGH-IN LOCATION, INFRASTRUCTURE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| R | ROUGH-IN LOCATION, INFRASTRUCTURE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED. |
| R | POWER POLE WITH ROUGH-IN LOCATION, INFRASTRUCTURE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| R | ROUGH-IN LOCATION. TERMINATED IN FLOOR BOX/POKE-THRU AS SPECIFIED. |
| WAP | WIRELESS ACCESS POINT. EQUIPMENT AS SPECIFIED. |

## GENERAL SYMBOLS

| | |
|---|---|
| # SHEET — DRAWING TITLE — SCALE: SCALE | DRAWING TITLE CALLOUT, # = DETAIL NUMBER. |
| # SHEET | DETAIL CALLOUT, # = DETAIL NUMBER. |
| # SHEET | SECTION CALLOUT, # = DETAIL NUMBER. |
| SHEET # | ELEVATION CALLOUT, # = DETAIL NUMBER. |
| # | KEYED NOTE, # = KEYED NOTE NUMBER. |
| # | REVISION TRIANGLE, # = REVISION NUMBER (PER SHEET). |
| TR (IDF XXX) | INDICATES TELECOMMUNICATIONS REGION |

## ABBREVIATIONS

| | |
|---|---|
| A.F.F. | ABOVE FINISHED FLOOR |
| A.F.G. | ABOVE FINISHED GRADE |
| AER | AERIAL |
| DEMARC | DEMARCATION POINT |
| EMT | ELECTRIC METALLIC TUBE |
| F.O.C. | FIBER OPTIC CABLE |
| GIP | GALVANIZED IRON PIPE |
| HE | PAINTERCOM HEAD-END |
| IMC | INTERMEDIATE METAL CONDUIT |
| ISP | INSIDE CABLE PLANT |
| IDF | INTERMEDIATE DISTRIBUTION FRAME |
| MDF | MAIN DISTRIBUTION FRAME |
| MH | MAINTENANCE HOLE |
| MM | MULTIMODE |
| OSP | OUTSIDE CABLE PLANT |
| PB | PULLBOX |
| PR | PAIR |
| PVC | POLYVINYL CHLORIDE |
| RSC | RIGID STEEL CONDUIT |
| SM | SINGLE MODE |
| SP | SERVICE PROVIDER |
| STP | SHIELDED TWISTED PAIR |
| TB | TERMINAL BLOCK |
| TR | TELECOMMUNICATION REGION |
| UGC | UNDERGROUND COMMUNICATION |
| UON | UNLESS OTHERWISE NOTED |
| UTP | UNSHIELDED TWISTED PAIR |

## NOTES

1. CONTRACTOR SHALL REVIEW DRAWINGS AND SPECIFICATIONS THAT MAKE UP THE CONTRACT DOCUMENTS AND COMPLETE ALL WORK INCLUDED THEREIN.
2. SCALE OF TECHNOLOGY DRAWINGS IS PROVIDED FOR REFERENCE ONLY. CONTRACTOR SHALL BE RESPONSIBLE FOR PROPER CABLE LENGTHS, SIZE OF PATHWAYS, DIMENSIONS, ETC.
3. TECHNOLOGY DRAWINGS SHALL BE USED TO COMPLEMENT THE WRITTEN SPECIFICATIONS.
4. ANY DISCREPANCY OR CONFLICT WITHIN OR BETWEEN THE DRAWINGS AND SPECIFICATIONS SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT/DESIGN CONSULTANT'S. DISCREPANCIES OR CONFLICTS NOT BROUGHT TO THE ATTENTION OF THE ARCHITECT/DESIGN CONSULTANT AND SUBSEQUENTLY CLARIFIED DURING THE BIDDING OF THE PROJECT WILL BE DEEMED TO HAVE BEEN BID OR PROPOSED IN THE MORE COSTLY OR DIFFICULT MANNER, AND THE BETTER QUALITY OR GREATER QUANTITY OF WORK SHALL BE PROVIDED BY THE CONTRACTOR IN ACCORDANCE WITH THE ARCHITECT'S/DESIGN CONSULTANT'S INTERPRETATION.

## INDEX OF DRAWINGS


p-T000 TECHNOLOGY SYMBOLS & LEGEND
p-TD201 TECHNOLOGY DEMOLITION FLOOR PLAN
p-T200 TECHNOLOGY COMPOSITE FLOOR PLAN
p-T201 TECHNOLOGY NEW/RENOVATION KITCHEN PLAN
p-T202 TECHNOLOGY TEMPORARY KITCHEN PLAN
p-T300 TECHNOLOGY ENLARGED VIEWS
p-T400 TECHNOLOGY TYPICAL DETAILS
p-T401 TECHNOLOGY TYPICAL DETAILS
p-T500 TECHNOLOGY TYPICAL DETAILS


ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

p

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD SOUTH DRIVE
RICHMOND, TX 77406

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD


07/18/2025


ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY SYMBOLS & LEGEND

SHEET NO.
p-T000




1 TECHNOLOGY COMPOSITE FLOOR PLAN
1/16" = 1'-0"
p-T200

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY COMPOSITE FLOOR PLAN

SHEET NO.
p-T200

ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY SUITE 430
HOUSTON, TEXAS 77079
MWA ARCHITECTS


REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
BICSI ID # 564870
Expires 2/28/26
07/18/2025

SEAL

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD SOUTH DRIVE
RICHMOND, TX 77406

p

ISSUE:
12/05/2024 DD PACKAGE
03/11/2025 50% CD PKG.
05/16/2025 90% CD PKG.
07/18/2025 ISSUED FOR BIDDING AND PERMITTING




1 TECHNOLOGY NEW/RENOVATION KITCHEN PLAN
p-T201 1/4" = 1'-0"

**TECHNOLOGY FLOOR PLANS GENRAL NOTES:**

1. THE TECHNOLOGY REGION / WIRING BOUNDARIES ARE IDENTIFIED ON THE OVERALL SHEETS ONLY AND NOT ON THE ENLARGED SHEETS. CONTRACTOR SHALL REFER TO THE OVERALL SHEETS FOR ALL TECHNOLOGY REGIONS / WIRING BOUNDARIES.
2. ALL CONDUIT PATHWAYS, ROUGH-INS, BACKBOXES, FLOOR BOXES, CONDUIT SLEEVES, ETC. INDICATED ON THE TECHNOLOGY DRAWINGS ARE TO BE PROVIDED AND INSTALLED BY DIVISION 26.
3. ALL POWER INDICATED ON THE TECHNOLOGY DRAWINGS IS TO BE PROVIDED AND INSTALLED BY DIVISION 26.
4. CONTRACTOR SHALL RESTORE ALL PENETRATIONS PROVIDED THROUGH FIRE RATED WALLS/STRUCTURES FOR TECHNOLOGY CABLING BACK TO THE ORIGINAL RATING.
5. CONTRACTOR SHALL RESTORE ALL PENETRATIONS PROVIDED THROUGH NON-RATED WALLS/STRUCTURES FOR TECHNOLOGY CABLING FOR SOUND TO REDUCE NOISE TRAVELING THROUGH PENETRATIONS.
6. TECHNOLOGY CABLING SHALL BE ROUTED IN SEPARATE PATHWAYS IN J-HOOKS, CONDUITS, CONDUIT SLEEVES, CORES, ETC. THROUGHOUT THE ENTIRE PATHWAY. DIFFERENT MEDIA TYPES (DATA, VIDEO, SECURITY, ETC.) SHALL NOT SHARE THE SAME J-HOOK, CONDUIT, CONDUIT SLEEVE, CORE, ETC.
7. UNLESS NOTED OTHERWISE, ALL CONDUITS FOR TECHNOLOGY DEVICES SHALL ROUTE FROM THE DEVICE LOCATION AND TERMINATE ABOVE AN ACCESSIBLE CEILING (AN OPEN CEILING OR CLOUD TYPE CEILING IS NOT CONSIDERED AN ACCESSIBLE CEILING) IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF A MAIN CORRIDOR OR NEAREST MDF/IDF. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF / IDF ROOM TO MINIMIZE THE CABLE LENGTH ENSURING CABLE LENGTH DOES NOT EXCEED 275 FEET.
8. UNLESS NOTED OTHERWISE ALL CONDUITS SHALL BE HOMERUN FROM THE DEVICE LOCATION AND NO DAISY CHAINING OF DEVICES/ ROUGH-INS SHALL BE ALLOWED.
9. CONDUIT SEGMENTS SHALL BE NO MORE THAN 100-FEET IN LENGTH WITH NO MORE THAN THE EQUIVALENT OF (2) 90 DEGREE BENDS BETWEEN PULLING POINTS.
10. CONDUITS SHALL MAINTAIN A BEND RADIUS OF 6 TIMES THE DIAMETER OF THE CONDUIT FOR CONDUITS 2-INCHES OR SMALLER AND 10 TIMES THE DIAMETER OF THE CONDUIT FOR CONDUITS GREATER THAN 2-INCHES.
11. ALL CONDUITS SHALL HAVE A PULL STRING INSTALLED FOR PULLING OF CABLE. CLEARLY LABEL AS "PULL STRING" INDICATING OPPOSITE END LOCATION.
12. ALL SPARE CONDUITS OR CONDUITS FILLED WITH LESS THAN THE MAXIMUM ALLOWED FILL RATIO SHALL HAVE A PULL STRING INSTALLED AND LEFT FOR FUTURE PULLING OF CABLE. CLEARLY LABEL AS "PULL STRING" INDICATING OPPOSITE END LOCATION.
13. EQUIPMENT NOT RELATED TO THE SUPPORT OF THE TELECOMMUNICATIONS ROOM (E.G., PIPING, DUCTWORK, PNEUMATIC TUBING) SHALL NOT BE INSTALLED IN, PASS THROUGH, OR ENTER THE TELECOMMUNICATIONS ROOM.
14. ALL CONDUITS FOR TECHNOLOGY DEVICES SHALL ROUTE FROM THE DEVICE LOCATION AND TERMINATE ABOVE A LAY-IN TYPE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE A LAY- IN TYPE CEILING TO PREVENT THE CABLES FROM BEING EXPOSED, THE CONDUIT SHALL ROUTE TO THE NEAREST LAY-IN TYPE CEILING OFF A MAIN CORRIDOR OR NEAREST MDF/IDF. THE CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE MAIN CORRIDOR OR NEAREST MDF/IDF TO MINIMIZE THE CABLE LENGTH ENSURING THE CABLE LENGTH DOES NOT EXCEED 275 FEET. CONDUIT, CONNECTIONS, J-BOXES, SUSPENSION, ANCHORAGES, AND OTHER CONDUIT COMPONENTS EXPOSED TO VIEW IN PUBLIC SPACES SHALL BE ROUTED AND INSTALLED CAREFULLY TO MINIMIZE VISUAL IMPACT AND SHALL BE FULLY PAINTED TO MATCH UNLESS NOTED OTHERWISE.
15. CONDUIT(S) INSTALLED IN-SLAB OR UNDER-SLAB TO FLOOR BOXES, POKE-THURS, AND TO WORKAREA OUTLETS, ETC. SHALL BE INSTALLED WITH WET RATED CABLE(S).
16. NO GRID WIRE SHALL BE UTILIZED FOR SUPPORTS ONLY USE SOLID SUPPORTS (CLIPS, ALL-THREAD, ANCHORS, ETC.).

**TECHNOLOGY PLAN KEYED NOTES**

**NOT ALL KEYED BELOW APPLY TO THIS SHEET**

1. DATA CABLE FOR CONTRACTOR FURNISHED / CONTRACTOR INSTALLED MENU BOARD. REFERENCE ARCHITECTURAL AND FOOD SERVICE DRAWINGS FOR MOUNTING HEIGHT AND ADDITIONAL INFORMATION. BUILDING POWER ADJACENT TO DATA RECEPTACLE IS REQUIRED.
2. INDOOR / OUTDOOR RATED DATA CABLE FOR POINT OF SALE LOCATION. PROVIDE (1) 1-INCH CONDUIT FOR DATA TO THE WALL BEHIND POINT OF SALE LOCATION AND UP WALL TO ABOVE ACCESSIBLE CEILING. CONDUITS SHALL TERMINATE INSIDE A DOUBLE GANG BOX THAT IS SECURED TO THE POINT OF SALE LOCATION. REFER TO FOOD SERVICE / KITCHEN DRAWINGS FOR EXACT LOCATION AND CONDUIT ROUGH-IN REQUIREMENTS.
3. DATA CABLE FOR TEMPERATURE MONITORING OF FREEZER COOLER. REFER TO FOOD SERVICE / KITCHEN DRAWINGS FOR EXACT LOCATION AND CONDUIT ROUGH-IN REQUIREMENTS AND TERMINATION POINT AND CONNECTIVITY NEEDS IN FREEZER / COOLER CONTROL UNIT.
4. DATA CABLE FOR TEMPORARY POINT OF SALES CASH REGISTER. COORDINATE WITH OWNER, ARCHITECT, AND CONSULTANT FOR ROUTING OF CABLES TO POINT OF SALE CASH REGISTER PRIOR TO INSTALLATION

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

p

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD SOUTH DRIVE
RICHMOND, TX 77406

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD


07/18/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY NEW/RENOVATION KITCHEN PLAN

SHEET NO.
p-T201




1 p-T202 TECHNOLOGY TEMPORARY KITCHEN FLOOR PLAN
1/4" = 1'-0"

**TECHNOLOGY FLOOR PLANS GENRAL NOTES:**

1. THE TECHNOLOGY REGION / WIRING BOUNDARIES ARE IDENTIFIED ON THE OVERALL SHEETS ONLY AND NOT ON THE ENLARGED SHEETS. CONTRACTOR SHALL REFER TO THE OVERALL SHEETS FOR ALL TECHNOLOGY REGIONS / WIRING BOUNDARIES.
2. ALL CONDUIT PATHWAYS, ROUGH-INS, BACKBOXES, FLOOR BOXES, CONDUIT SLEEVES, ETC. INDICATED ON THE TECHNOLOGY DRAWINGS ARE TO BE PROVIDED AND INSTALLED BY DIVISION 26.
3. ALL POWER INDICATED ON THE TECHNOLOGY DRAWINGS IS TO BE PROVIDED AND INSTALLED BY DIVISION 26.
4. CONTRACTOR SHALL RESTORE ALL PENETRATIONS PROVIDED THROUGH FIRE RATED WALLS/STRUCTURES FOR TECHNOLOGY CABLING BACK TO THE ORIGINAL RATING.
5. CONTRACTOR SHALL RESTORE ALL PENETRATIONS PROVIDED THROUGH NON-RATED WALLS/STRUCTURES FOR TECHNOLOGY CABLING FOR SOUND TO REDUCE NOISE TRAVELING THROUGH PENETRATIONS.
6. TECHNOLOGY CABLING SHALL BE ROUTED IN SEPARATE PATHWAYS IN J-HOOKS, CONDUITS, CONDUIT SLEEVES, CORES, ETC. THROUGHOUT THE ENTIRE PATHWAY. DIFFERENT MEDIA TYPES (DATA, VIDEO, SECURITY, ETC.) SHALL NOT SHARE THE SAME J-HOOK, CONDUIT, CONDUIT SLEEVE, CORE, ETC.
7. UNLESS NOTED OTHERWISE, ALL CONDUITS FOR TECHNOLOGY DEVICES SHALL ROUTE FROM THE DEVICE LOCATION AND TERMINATE ABOVE AN ACCESSIBLE CEILING (AN OPEN CEILING OR CLOUD TYPE CEILING IS NOT CONSIDERED AN ACCESSIBLE CEILING) IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF A MAIN CORRIDOR OR NEAREST MDF/IDF. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF / IDF ROOM TO MINIMIZE THE CABLE LENGTH ENSURING CABLE LENGTH DOES NOT EXCEED 275 FEET.
8. UNLESS NOTED OTHERWISE ALL CONDUITS SHALL BE HOMERUN FROM THE DEVICE LOCATION AND NO DAISY CHAINING OF DEVICES/ ROUGH-INS SHALL BE ALLOWED.
9. CONDUIT SEGMENTS SHALL BE NO MORE THAN 100-FEET IN LENGTH WITH NO MORE THAN THE EQUIVALENT OF (2) 90 DEGREE BENDS BETWEEN PULLING POINTS.
10. CONDUITS SHALL MAINTAIN A BEND RADIUS OF 6 TIMES THE DIAMETER OF THE CONDUIT FOR CONDUITS 2-INCHES OR SMALLER AND 10 TIMES THE DIAMETER OF THE CONDUIT FOR CONDUITS GREATER THAN 2-INCHES.
11. ALL CONDUITS SHALL HAVE A PULL STRING INSTALLED FOR PULLING OF CABLE. CLEARLY LABEL AS "PULL STRING" INDICATING OPPOSITE END LOCATION.
12. ALL SPARE CONDUITS OR CONDUITS FILLED WITH LESS THAN THE MAXIMUM ALLOWED FILL RATIO SHALL HAVE A PULL STRING INSTALLED AND LEFT FOR FUTURE PULLING OF CABLE. CLEARLY LABEL AS "PULL STRING" INDICATING OPPOSITE END LOCATION.
13. EQUIPMENT NOT RELATED TO THE SUPPORT OF THE TELECOMMUNICATIONS ROOM (E.G., PIPING, DUCTWORK, PNEUMATIC TUBING) SHALL NOT BE INSTALLED IN, PASS THROUGH, OR ENTER THE TELECOMMUNICATIONS ROOM.
14. ALL CONDUITS FOR TECHNOLOGY DEVICES SHALL ROUTE FROM THE DEVICE LOCATION AND TERMINATE ABOVE A LAY-IN TYPE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE A LAY- IN TYPE CEILING TO PREVENT THE CABLES FROM BEING EXPOSED, THE CONDUIT SHALL ROUTE TO THE NEAREST LAY-IN TYPE CEILING OFF A MAIN CORRIDOR OR NEAREST MDF/IDF . THE CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE MAIN CORRIDOR OR NEAREST MDF/IDF TO MINIMIZE THE CABLE LENGTH ENSURING THE CABLE LENGTH DOES NOT EXCEED 275 FEET. CONDUIT, CONNECTIONS, J-BOXES, SUSPENSION, ANCHORAGES, AND OTHER CONDUIT COMPONENTS EXPOSED TO VIEW IN PUBLIC SPACES SHALL BE ROUTED AND INSTALLED CAREFULLY TO MINIMIZE VISUAL IMPACT AND SHALL BE FULLY PAINTED TO MATCH UNLESS NOTED OTHERWISE.
15. CONDUIT(S) INSTALLED IN-SLAB OR UNDER-SLAB TO FLOOR BOXES, POKE-THURS, AND TO WORKAREA OUTLETS, ETC. SHALL BE INSTALLED WITH WET RATED CABLE(S).
16. NO GRID WIRE SHALL BE UTILIZED FOR SUPPORTS ONLY USE SOLID SUPPORTS (CLIPS, ALL-THREAD, ANCHORS, ETC.).

**TECHNOLOGY PLAN KEYED NOTES**

**NOT ALL KEYED BELOW APPLY TO THIS SHEET**

(1) DATA CABLE FOR CONTRACTOR FURNISHED / CONTRACTOR INSTALLED MENU BOARD. REFERENCE ARCHITECTURAL AND FOOD SERVICE DRAWINGS FOR MOUNTING HEIGHT AND ADDITIONAL INFORMATION. BUILDING POWER ADJACENT TO DATA RECEPTACLE IS REQUIRED.

(2) INDOOR / OUTDOOR RATED DATA CABLE FOR POINT OF SALE LOCATION. PROVIDE (1) 1-INCH CONDUIT FOR DATA TO THE WALL BEHIND POINT OF SALE LOCATION AND UP WALL TO ABOVE ACCESSIBLE CEILING. CONDUITS SHALL TERMINATE INSIDE A DOUBLE GANG BOX THAT IS SECURED TO THE POINT OF SALE LOCATION. REFER TO FOOD SERVICE / KITCHEN DRAWINGS FOR EXACT LOCATION AND CONDUIT ROUGH-IN REQUIREMENTS.

(3) DATA CABLE FOR TEMPERATURE MONITORING OF FREEZER COOLER. REFER TO FOOD SERVICE / KITCHEN DRAWINGS FOR EXACT LOCATION AND CONDUIT ROUGH-IN REQUIREMENTS AND TERMINATION POINT AND CONNECTIVITY NEEDS IN FREEZER / COOLER CONTROL UNIT.

(4) DATA CABLE FOR TEMPORARY POINT OF SALES CASH REGISTER. COORDINATE WITH OWNER, ARCHITECT, AND CONSULTANT FOR ROUTING OF CABLES TO POINT OF SALE CASH REGISTER PRIOR TO INSTALLATION

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

p

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD SOUTH DRIVE
RICHMOND, TX 77406

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD


07/18/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY TEMPORARY KITCHEN PLAN

SHEET NO.
p-T202




1 p-T300 PECAN GROVE ES - EXISTING WALL MOUNTED RACK
N.T.S.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

p

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD SOUTH DRIVE
RICHMOND, TX 77406

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD

07/18/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING


TECHNOLOGY ENLARGED VIEWS

SHEET NO.
p-T300

NOTE TO CONTRACTOR:

UNLESS OTHERWISE NOTED, LOW VOLTAGE CABLING SHALL BE INSTALLED WITHIN 6-INCHES OF THE CEILING AND ACCESSIBLE BY A TECHNICIAN ON A STANDARD A-FRAME LADDER.

CONTRACTOR SHALL MAINTAIN AT LEAST 6-INCHES OF SEPRATION BETWEEN CABLING BUNDLES AND MECHANICAL DUCTWORKS, EQUIPMENT, PIPIING OR OTHER SYSTEMS IN THE CEILING PLENUM.





KEYED NOTES:

1. J-HOOK WITH RETAINER CLIP ABOVE ACCESSIBLE CEILING (BY DIV 27).
2. DATA CABLE ABOVE ACCESSIBLE CEILING (BY DIV 27).
3. A/V CABLE ABOVE ACCESSIBLE CEILING (BY DIV 27).
4. SECURITY CABLE ABOVE ACCESSIBLE CEILING (BY DIV 28).
5. SPARE J-HOOK (BY DIV 27).

## 1 / T400 TYPICAL J-HOOK CABLE PATHWAY

SCALE: N.T.S.





KEYED NOTES:

1. SCHEDULED FLOOR OR DECK.
2. CONDUIT SLEEVE (BY DIV 26).
3. NYLON BUSHING (BY DIV 26).

## 2 / T400 TYPICAL CONDUIT SLEEVE THROUGH FLOOR OR DECK DETAIL

SCALE: N.T.S.





KEYED NOTES:

1. SCHEDULED WALL.
2. SCHEDULED CEILING.
3. CONDUIT SLEEVE (BY DIV 26).
4. NYLON BUSHING (BY DIV 26).

## 3 / T400 TYPICAL CONDUIT SLEEVE GOING THROUGH WALL

SCALE: N.T.S.





KEYED NOTES:

1. SCHEDULED WALL.
2. SCHEDULED CEILING.
3. SCHEDULED DECK ABOVE.
4. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX WITH DOUBLE GANG PLASTER RING (BY DIV 26).
5. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH. (BY DIV 26).

## 4 / T400 TYPICAL TECHNOLOGY CONDUIT ROUGH-IN

SCALE: N.T.S.





KEYED NOTES:

1. SCHEDULED STUD.
2. SCHEDULED WALL.
3. J-HOOK WITH RETAINER CLIP ABOVE ACCESSIBLE CEILING (BY DIV 27).
4. DATA CABLE ABOVE ACCESSIBLE CEILING (BY DIV 27).
5. 20 FOOT SERVICE LOOP ABOVE ACCESSIBLE CEILING NEATLY COILED AND SECURED TO J-HOOK (BY DIV 27).
6. SURFACE MOUNT BOX ABOVE ACCESSIBLE CEILING SECURED TO BUILDING STRUCTURE (BY DIV 27).
7. DATA INSTER (BY DIV 27).

## 5 / T400 TYPICAL ABOVE CEILING SINGLE DATA OUTLET (WALL MOUNTED)

SCALE: N.T.S.





KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH PHONE STUDS (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. CABLE AS SPECIFIED (BY DIV 27).

## 6 / T400 TYPICAL WALL PHONE OUTLET CONFIGURATION

SCALE: N.T.S.





KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH DESIGNATION IN WINDOW (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. CABLE AS SPECIFIED (BY DIV 27).
7. ELECTRICAL RECEPTACLE, GANG BOX AND CONDUIT SHOWN FOR REFERENCE ONLY (REFER TO DIV 26).

## 7 / T400 TYPICAL DUAL DATA OUTLET CONFIGURATION

SCALE: N.T.S.





KEYED NOTES:

1. 4 11/16-INCH X 4 11/16-INCH X 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. DOUBLE GANG PLASTER RING (BY DIV 26).
4. SURFACE MOUNT BOX INSIDE THE 4 11/16-INCH X 4 11/16-INCH X 2 1/8-INCH DOUBLE GANG BOX (BY DIV 27).
5. RJ-45 INSERT (BY DIV 27).

## 8 / T400 TYPICAL WALL-MOUNTED WIRELESS ACCESS POINT

SCALE: N.T.S.




KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH DESIGNATION IN WINDOW (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. BLANK INSERT (BY DIV 27).
7. CABLE AS SPECIFIED (BY DIV 27).
8. ELECTRICAL RECEPTACLE, GANG BOX AND CONDUIT SHOWN FOR REFERENCE ONLY (REFER TO DIV 26).

## 9 / T400 TYPICAL THREE DATA OUTLET CONFIGURATION

SCALE: N.T.S.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

p

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD SOUTH DRIVE
RICHMOND, TX 77406

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD

07/18/2025



ARCHITECTS
AND PLANNING
CONSULTANTS

11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY TYPICAL DETAILS

SHEET NO.
p-T400





KEYED NOTES:

1. ALL THREAD TO BUILDING STRUCTURE (BY DIV. 27)
2. SCHEDULING CEILING
3. IN-PLENUM CEILING BRACKET PN 49223-CBC ATTACHED TO ALL THREAD (BY DIV. 27)
4. SURFACE MOUNT BOX ABOVE ACCESSIBLE CEILING SECURED TO BRACKET (BY DIV. 27)
5. DATA CABLE (BY DIV. 27)
6. DATA INSERT (BY DIV. 27)

## 1 T401 TYPICAL ABOVE CEILING DATA OUTLET

SCALE: N.T.S.





KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH DESIGNATION IN WINDOW (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. CABLE AS SPECIFIED (BY DIV 27).
7. ELECTRICAL RECEPTACLE, GANG BOX AND CONDUIT SHOWN FOR REFERENCE ONLY (REFER TO DIV 26). ELECTRICAL RECEPTACLE TO BE INSTALLED AT 36" A.F.F AND ADJACENT TO COW / SECONDARY TEACHING OUTLET LOCATION.

## 2 T401 TYPICAL COW / SECONDARY TEACHER'S DATA OUTLET CONFIGURATION

SCALE: N.T.S.





KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH DESIGNATION IN WINDOW (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. BLANK INSERT (BY DIV 27).
7. CABLE AS SPECIFIED (BY DIV 27).
8. ELECTRICAL RECEPTACLE, GANG BOX AND CONDUIT SHOWN FOR REFERENCE ONLY (REFER TO DIV 26).

## 3 T401 TYPICAL THREE DATA OUTLET CONFIGURATION

SCALE: N.T.S.




KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH DESIGNATION IN WINDOW (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. CABLE AS SPECIFIED (BY DIV 27).
7. ELECTRICAL RECEPTACLE, GANG BOX AND CONDUIT SHOWN FOR REFERENCE ONLY (REFER TO DIV 26).

## 4 T401 TYPICAL FOUR DATA OUTLET CONFIGURATION


SCALE: N.T.S.

| TBB/GE CONDUCTOR SIZING | |
|---|---|
| LENGTH IN LINEAR M (FT) | SIZE (AWG) |
| LESS THAN 4 (13) | 6 |
| 4 - 6 (14-20) | 4 |
| 6 - 8 (21 - 26) | 3 |
| 8 - 10 (27 - 33) | 2 |
| 10 - 13 (34 - 41) | 1 |
| 13 - 16 (42 - 52) | 1/0 |
| 16 - 20 (53 - 66) | 2/0 |
| 20 - 26 (67 - 84) | 3/0 |
| 26 - 32 (85 - 105) | 4/0 |
| 32 - 38 (106 - 125) | 250 kcmil |
| 38 - 46 (126 - 150) | 300 kcmil |
| 46 - 53 (151 - 175) | 350 kcmil |
| 53 - 76 (176 - 250) | 500 kcmil |
| 76 - 91 (251 - 300) | 600 kcmil |
| GREATER THAN 91 (301) | 750 kcmil |

ROUTE THE TBB TO EACH TGB IN AS STRAIGHT A PATH AS POSSIBLE. THE TBB SHOULD BE INSTALLED AS A CONTINUOUS CONDUCTOR, AVOIDING SPLICES WHERE POSSIBLE.

## 5 T401 TBB CONDUCTOR SIZING

SCALE: N.T.S.





1. TELECOMMUNICATIONS MAIN GROUNDING BUS BAR (PBB)(BY DIV. 27)
2. TELECOMMUNICATIONS GROUNDING BUS BAR (SBB)(BY DIV 27)
3. TELECOMMUNICATIONS BONDING CONDUCTOR (TBC). REFER TO CONDUCTOR SIZING CHART FOR EXACT SIZE REQUIREMENTS (BY DIV 27)
4. CONNECT TO GROUNDED BUILDING STEEL WHEN EXPOSED IN ROOM.
5. TELECOMMUNICATIONS BONDING BACKBONE (TBB). REFER TO CONDUCTOR SIZING CHART FOR EXACT SIZE REQUIREMENTS (BY DIV 26)
6. TELECOMMUNICATIONS BONDING CONDUCTOR (TBC). BY ELECTRICAL CONTRACTOR.REFER TO CONDUCTOR SIZING CHART FOR EXACT SIZE REQUIREMENTS.
7. GROUNDING EQUALIZER CONDUCTOR (GEC)(BY DIV 26)
8. BOUND WITH GROUDING COLLARS TO EACH CONTINUOUS CONDUIT THAT ENTERS THE TELECOM ROOM. (BY DIV 26).
9. BOND TO EACH ACCESS CONTROL PANEL AND OTHER SECURITY PANELS IN HE TELECOM ROOM. (BY DIV 27)

## 6 T401 TYPICAL GROUNDING DIAGRAM

SCALE: N.T.S.

System No. W-L-3218
F Ratings - 1, 2, 3 and 4 Hr (See Items 1 and 3)
T Ratings - 3/4 and 1 Hr (See Item 3)
L Rating At Ambient - Less Than 1, 1.3, 4 or 7 CFM (See Item 3)
L Rating At 400 F - Less Than 1, 2 or 3 CFM (See Item 3)




Section A-A

1. Wall Assembly - The 1, 2, 3 or 4 hr fire-rated gypsum board/stud wall assembly shall be constructed of the materials and in the manner described within the individual U300, U400 or V400 Series Wall and Partition Designs in the UL Fire Resistance Directory and shall incorporate the following construction features:

   A. Studs - Wall framing shall consist of either wood studs or steel channel studs. Wood studs to consist of nom 2 by 4 in. (51 by 102 mm) lumber spaced max 16 in. (406 mm) OC. Steel studs to be min 3-1/2 in. (89 mm) wide and spaced max 24 in. (610 mm) OC.

   B. Gypsum Board* - Thickness, type, number of layers and fasteners as specified in the individual Wall and Partition Design. Opening in gypsum board to be max 1/4 in. (6 mm) larger then width and height dimensions of firestop device(s).

   The hourly F Rating of the firestop system is dependent upon the hourly rating of the wall in which it is installed.

2. Firestop Device* - One, two, three, four or seven firestop device modules ganged together. Each firestop device module consists of a 3 by 3 by 10-1/2 in. (76 by 76 by 267 mm) long galv steel tube with an intumescent material lining. Firestop device modules to be installed in accordance with the accompanying installation instructions. The space between the firestop device module(s) and the periphery of the opening shall be min 0 in. ( 0 mm, point contact) to max 1/8 in. (3.2 mm). In round openings, the space between the firestop device and the periphery of the opening shall be min 0 in. (point contact) to max 1/2 in. (13 mm). Firestop device module(s) secured in place by means of steel wall plates installed with gasketing material supplied with product. Steel wall plates installed on both sides of wall and secured to each device by means of steel set screws provided with device. Each four- and seven-gang steel wall plate shall be fastened to the studs with steel screws sized to extend through the gypsum board layers and penetrate 1/2 in. (13 mm) into the framing member. Each firestop device module is to be installed with ends projecting an equal distance beyond each surface of the wall assembly.

   As an alternate, the four- and seven-gang steel wall plates may be installed directly against the studs for walls having 16 and 24 in. (406 and 610 mm) center-to-center stud spacing, respectively, prior to installation of the gypsum board layers. The steel wall plates shall be secured to the stud by means of steel screws. After installation of the steel wall plates and firestop device modules, the gypsum board shall be installed as specified in the individual U300 or U400 Design with a maximum 1/8 in. (3.2 mm) gap between the firestop device module and the cutout in the gypsum board. Gap between the firestop device module and the cutout in the gypsum board may be filled with gypsum joint compound or fill material (Item 4).

   SPECIFIED TECHNOLOGIES INC - EZ PATH Series 33 Fire Rated Pathway

2A. Firestop Device* - Extension Module - (Optional, Not Shown) - Module attached to ends of 3 by 3 by 10-1/2 in. (76 by 76 by 267 mm) long firestop device (Item 3) to increase its length to facilitate installation in thicker walls. Each module consists of a 3 by 3 by 6 in. (76 by 76 by 152 mm) long galv steel tube with an intumescent material lining. Extension module to be installed in accordance with the accompanying installation instructions. When module is used, firestop device (Item 2) and extension module(s) secured in place by means of steel wall plates installed with gasketing material supplied with product. Steel wall plates installed on both sides of wall and secured to each device or extension module(s) by means of steel set screws provided with wall plates. Firestop device and extension module(s) assembly to be installed with ends projecting an equal distance beyond each surface of the wall assembly.

   SPECIFIED TECHNOLOGIES INC - EZ PATH Extension

3. Cables - Within the loading area for each firestop device module, the cables may represent a 0 to 100 percent visual fill. Cable fill to be distributed at a uniform height across the width of the firestop device module. Cables to be rigidly supported on both sides of the wall assembly. Any combination of the following types of cables may be used:

   A. Max 400 pair No. 24 AWG (or smaller) copper conductor telecommunication cable with polyvinyl chloride (PVC) jacketing and insulation.
   B. Max 350 kcmil single copper conductor power cable with XLPE jacket and insulation
   C. Max 7/C No. 12 AWG copper conductor control cable with PVC or XLPE jacket and insulation.
   D. Max 3/C No. 10 AWG metal clad or armored cable with steel or aluminum jacket.
   E. Max 3/C No. 8 AWG NM cable (Romex) with PVC insulation and jacket.
   F. Max four pair No. 22 AWG (or smaller) copper conductor data cable with PVC or plenum rated jacketing and insulation.
   G. Max RG/U coaxial cable with fluorinated ethylene insulation and jacketing.
   H. Fiber optic cable with PVC or polyethylene (PE) jacket and insulation having a max diam of 5/8 in. (16 mm).
   I. Optical Fiber Raceway+ - Max 1-1/2 in. (38 mm) diam (or smaller) optical fiber raceway ("innerduct") formed of either PVC or polyvinylidene fluoride (PVDF) with optical fiber cable fill. Raceways installed in accordance with the National Electrical Code (NFPA 70).

   When the hourly rating of the wall assembly is 1 hr, the T Rating is 3/4 hr. When the hourly fire rating of the wall assembly is greater than 1 hr, the T Rating is 3/4 hr when Item 3A, 3B, 3C, 3D or 3E is used. Otherwise the T Rating is 1 hr. When Item 3A, 3B, 3C, 3D or 3E is used, the maximum F Rating is 2 hr. When max 200 pair No. 24 AWG telecommunication cable is used or when Item 3F, 3G, 3H or 3I is used, the maximum F Rating is 4 hr.

   The L Rating for each empty firestop device module is less than 1 cfm at ambient and at 400F. When Item 3A is used, the L Rating for each firestop device module with 100 percent visual fill is 4 cfm at ambient and 3 cfm at 400F. When Item 3F is used, the L Rating for each firestop device module with 100 percent visual fill is 1.3 cfm at ambient and 1 cfm at 400F. When Item 3G or 3H is used, the L Rating for each firestop device module with 100 percent visual fill is 7 cfm at ambient and 2 cfm at 400F.

4. Fill, Void or Cavity Material* - Sealant or Putty - (Not Shown) - As an alternate to gypsum joint compound, the gap between the firestop device module and the cutout in the gypsum board may be sealed with fill material on each side of the wall assembly when four- and seven-gang steel wall plates are installed directly against the wood or steel studs.

   SPECIFIED TECHNOLOGIES INC - SpecSeal Series SSS Sealant, SpecSeal LCI Sealant, SpecSeal Putty

   *Bearing the UL Classification Mark

## 7 T401 TYPICAL STI EZ-PATH SLEEVE DETAIL

SCALE: N.T.S.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

p

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
PECAN GROVE ELEMENTARY SCHOOL
3330 OLD SOUTH DRIVE
RICHMOND, TX 77406

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD

07/18/2025


ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY TYPICAL DETAILS

SHEET NO.
p-T401

## AUDIO/VISUAL MULTIMEDIA LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| A## V## | WALL AV ROUGH-IN DETAIL |
| A## V## | CEILING AV ROUGH-IN DETAIL |
| A## V## | FLOOR AV ROUGH-IN DETAIL |
| iWB iWB | INTERACTIVE WHITE BOARD - WALL - CEILING |
| PJ PJ | MULTIMEDIA PROJECTOR |
| FP# FP# | MULTIMEDIA FLAT PANEL DISPLAY |
| S S | LOUDSPEAKER, WALL MOUNTED AND CEILING MOUNTED RESPECTIVELY - # INDICATES TYPE |
| CP# | CONTROL PANEL |
| TP# | TOUCH PANEL |
| M | MICROPHONE, CEILING MOUNTED - # INDICATES TYPE |
| VC | VOLUME CONTROL |
| WB | WALL BOX ENCLOSURE |
| D1 A1 | D1 = DIGITAL SINGLE SIDED CLOCK / A1 = ANALOG SINGLE SIDED CLOCK |
| D2 A2 | D2 = DIGITAL DOUBLE SIDED CLOCK / A2 = ANALOG DOUBLE SIDED CLOCK |
| ENC | CEILING AV ENCLOSURE |
| C C | PRESENTATION CAMERA - CEILING - WALL MOUNTED |

## PREMISE SECURITY LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| CR | CARD READER |
| CR M | CARD READER MULLION |
| KP | INTRUSION DETECTION KEYPAD |
| IC | INTERCOM (1 DATA CABLE) |
| IC MS | INTERCOM MASTER STATION (1 DATA CABLE) |
| PB | PANIC/DURESS BUTTON |
| LD | LOCK DOWN BUTTON |
| MD | MOTION DETECTOR |
| GB | ACCOUSTICAL GLASS BREAK SENSOR |
| BM | BIOMETRIC READER |
| RX | REQUEST TO EXIT - SURFACE PIR |
| KS | KEY SWITCH |
| LA | LOCAL ALARM SOUNDER |
| RG | RED/GREEN INDICATOR LIGHT |
| DB | DOORBELL |
| DH | MAGNETIC DOOR HOLD |
| DR | DOOR RELEASE |
| RX | REQUEST TO EXIT - INTEGRAL TO DOOR HARDWARE |
| DC | DOOR CONTACT / MONITOR |
| ES EL EH | ELECTRIFIED STRIKE - ELECTRIFIED LATCH - ELECTRIFIED HARDWARE (REFER TO SCHEDULES) |
| C C | STANDARD IP SURVEILLANCE CAMERA, (1) CABLE |
| C C C | 180° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° FISHEYE LENS CAMERA |
| IR | IR ILLUMINATOR |

## STRUCTURED CABLING LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF DATA CABLE(S)/JACK(S) |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) |
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| W | WALL MOUNT PHONE (1 CABLE/JACK) |
| W | WALL MOUNT PHONE, SURFACE MOUNT (1 CABLE/JACK) |
| # | FLOOR MOUNTED OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| #/# | FLOOR MOUNTED OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| # | CEILING MOUNTED DATA OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) |
| AP# | CEILING MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| AP# | WALL MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| | CABLING SLEEVE(S) |
| | TYPICAL LADDER RACK |
| | TYPICAL CABLE TRAY, BASKET STYLE |

## GENERAL ANNOTATION LEGEND


| SYMBOL | DESCRIPTION |
|---|---|
| MER | MAIN EQUIPMENT ROOM |
| TR | TELECOMMUNICATION ROOM |
| MDF | MAIN DISTRIBUTION FRAME |
| IDF | INTERMEDIATE DISTRIBUTION FRAME |
| ETR | EXISTING TO REMAIN |
| PBO | PROVIDED BY OTHERS |
| AFF | ABOVE FINISHED FLOOR |
| AFG | ABOVE FINISHED GRADE |
| AC | ABOVE COUNTER |
| EC | ELECTRICAL CONTRACTOR |
| PSC | PREMISE SECURITY CONTRACTOR |
| SCC | STRUCTURAL CABLING CONTRACTOR |
| AVC | AV/MULTIMEDIA CONTRACTOR |
| UNO | UNLESS NOTED OTHERWISE |
| ACS | ACCESS CONTROL SYSTEM |
| VSS | VIDEO SURVEILLANCE SYSTEM |

## TECHNOLOGY - GENERAL NOTES

1. EACH KEYNOTE MAY NOT BE UTILIZED ON EVERY SHEET.
2. ALL CONDUIT MEASUREMENTS REFER TO STANDARD CONDUIT TRADE SIZES.
3. ALL CABLES SHALL BE CONCEALED.
4. EACH CONTRACTOR SHALL PROVIDE AND INSTALL ALL NECESSARY SLEEVES, WHETHER OR NOT SPECIFICALLY NOTED ON PROJECT DRAWINGS. ALL SLEEVES SHALL BE 2" UNLESS NOTED OTHERWISE ON THE DRAWINGS. CABLE FILL PERCENTAGE SHALL COMPLY WITH NEC.
5. DEVICE LOCATIONS ARE APPROXIMATE. CONTRACTOR SHALL REVIEW CONDITIONS AND COORDINATE WITH OTHER TRADES AS NECESSARY FOR EXACT PLACEMENT.

## TECHNOLOGY SYMBOLS LEGEND

NOT ALL SYMBOLS ARE USED




TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

p

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Pecan Grove Elementary School
3330 Old S Dr, Richmond, TX 77406

SEAL




07-18-25


MVA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY - TITLE SHEET

p-TN000

**DEMO KEYNOTES**

1. REMOVE, AND PROTECT DURING CONSTRUCTION, INSTALL IN EXISTING LOCATION AFTER NEW ACT GRID IS IN PLACE.
2. DEVICES IN ACT ARE TO BE REMOVED AND PROTECTED DURING CONSTRUCTION AND REINSTALLED IN THE SAME LOCATION AFTER THE NEW CEILING GRID IS IN PLACE. DECIVES INCLUDE: SPEAKERS, ACCESS POINTS AND INTRUSION MOTION DETECTORS.
3. EXISTING CARD READER, DOOR CONTACT, & REX (REQUEST TO EXIT) TO BE DEMOLISHED, REMOVE DEVICES AND PROTECT WIREING.




1 PECAN GROVE - DEMO PLAN
SCALE: 3/16" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

p

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Pecan Grove Elementary School
3330 Old S Dr, Richmond, TX 77406

SEAL

BICSI REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256557
EXPIRES 12-31-27


07-18-25


MVA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Pecan Grove ES - DEMO

p-TN.001

TRUENORTH A PMT COMPANY




1 BACKGROUND 1 (PECAN GROVE)
SCALE: 1" = 20'-0"

TRUENORTH A PMY COMPANY

## TECHNOLOGY KEYNOTES

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

p

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Pecan Grove Elementary School
3330 Old S Dr, Richmond, TX 77406

SEAL

BICSI Brian C Porter BICSI ID # 258657 EXPIRES 12-31-25 NCCDP

07-18-25



MVA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Pecan Grove ES - OVERALL

p-TN.100

## TECHNOLOGY KEYNOTES

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.




1 PECAN GROVE - KITCHEN PLAN
SCALE: 3/16" = 1'-0"

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

p

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Pecan Grove Elementary School
3330 Old S Dr, Richmond, TX 77406

SEAL

BICSI REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256557
EXPIRES 12-31-27

07-18-25



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Pecan Grove ES - KITCHEN


p-TN.101

**GENERAL NOTE**


1. FACE PLATE DETAIL FOR OUTLET CONFIGURATION PURPOSES ONLY. CONTRACTOR TO SELECT TYPE OF FACE PLATE TO MATCH CONNECTIVITY HARDWARE, FLOOR BOX AND/OR MODULAR FURNITURE OPENING.





1 DATA ROUGH-IN DETAILS
SCALE: NS




2 TYPICAL CABLING SLEEVE
SCALE: NTS




3 PANDUIT J-HOOK DETAIL
SCALE: NTS




4 LABELING & CABLING SCHEMES
SCALE: NTS




5 CABLE PATHWAY CROSS SECTION
SCALE: NTS




6 DROPPED CEILING MOUNTING DETAIL
SCALE: NS




7 I-JOIST MOUNTING DETAIL
SCALE: NS




8 BAR JOIST MOUNTING DETAIL
SCALE: NS

| CAMERA TYPE | MANUFACTURER | MODEL NUMBER | GENERAL DESCRIPTION |
|---|---|---|---|
| C1 | iPro | WV-S8574L | 4x4K (33MP) EXTERIOR MULTI-SENSOR - PARKING LOTS, STADIUM |
| C2 | iPro | WV-S8544L | 4x4MP (16MP) EXTERIOR MULTI-SENSOR - BUILDING PERIMETER |
| C3 | iPro | WV-S25500-V3LN | 5MP EXTERIOR VANDAL DOME |
| C4 | iPro | WV-S22500-V3L | 5MP INTERIOR VANDAL DOME - CORR., COMMON, SPED |
| C5 | iPro | WV-S4156A | 5MP 360 (FISHEYE) - STAIRWELLS |

9 CAMERA SCHEDULE
SCALE: NTS

| Symbol | Purpose | Size | Mount | Backbox | Notes |
|---|---|---|---|---|---|
| FP1 | Digital Signage/Menu Boards | +49" | Ceiling Pole | N/A | Data and Power Outlets on ceiling |

10 DISPLAY SCHEDULE
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

p

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Pecan Grove Elementary School
3330 Old S Dr, Richmond, TX 77406

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256657
EXPIRES 12-31-27
RCDD

07-18-25



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Pecan Grove ES - DETAILS


p-TN.500

GENERAL NOTES:


1. REFER TO SECURITY SCHEDULE AND WRITTEN SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
2. ALL MOUNTING DETAILS ARE REFERENCE FOR ALL FIXED DOME, 180°, 360°, PTZ, AND "BULLET/BOX" CAMERAS.





1 TYPICAL CAMERA INSTALLATION SECTION DETAIL
SCALE: NS




6 WALL MOUNTED CAMERA DETAIL
SCALE: NS




4 TILE BRIDGE DETAIL
SCALE: NS





5 CEILING MOUNTED CAMERA DETAIL
SCALE: NS


ACCESS CONROL DETAILS AND GENERAL NOTES:

1. CONDUIT ROUGH-IN IS A GUIDE FOR WHAT WILL BE REQUIRED FOR EACH DOOR. AS DOOR COMPONENTS CHANGE, EXACT CONDUIT LOCATION WILL ALSO NEED TO BE ADJUSTED.


2. PROTECT EXISTING-TO-REMAIN ACCESS CONTROL DEVICES AND CABLE THROUGHOUT RENOVATION WORK. IF CABLE AND/OR DEVICES ARE DAMAGED, SECURITY CONTRACTOR TO REPLACE WITH NEW.




1 ACCESS CONTROL - WIRING DETAIL - EXIT DEVICE W/ BUILT-IN REX
SCALE: NTS




2 ACCESS CONTROL - STEEL/HOLLOW METAL DOOR.
SCALE: NTS




KP PB LD

3 ROUGH-IN DETAILS: KP, PB, LD
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

p

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Pecan Grove Elementary School
3330 Old S Dr, Richmond, TX 77406

SEAL


REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 254557
EXPIRES 12-31-27
RCDD

07-18-25


MWA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING
AND
PERMITTING
TECHNOLOGY - Pecan Grove ES - SECURITY DETAILS

p-TN.600




6 CEILING MOUNT DISPLAY - A/V ROUGH-IN DETAIL
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

p

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Pecan Grove Elementary School
3330 Old S Dr, Richmond, TX 77406

SEAL

BICSI REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256557
EXPIRES 12-31-27

07-18-25

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Pecan Grove ES - AV DETAILS

p-TN.700

# FBISD BP013 KITCHEN RENOVATIONS ES

| Sheet List Table | |
|---|---|
| Sheet Number | Sheet Title |
| School: q-RIDGEGATE ES | |
| q-A-000 | COVER AND INDEX |
| q-TN-000 | TECHNOLOGY - INDEX SHEET |
| q-TN-100 | TECHNOLOGY - OVERALL |
| q-TN-101 | TECHNOLOGY - KITCHEN |
| q-TN-500 | TECHNOLOGY - DETAILS |
| q-TN-600 | TECHNOLOGY - SECURITY DETAILS |




FORT BEND INDEPENDENT SCHOOL DISTRICT

RIDGEGATE ELEMENTARY SCHOOL
6015 W RIDGECREEK DRIVE, HOUSTON, TX 77053

## ADMINISTRATION

| | |
|---|---|
| DR. MARCELL SMITH | SUPERINTENDENT OF FBISD |
| DR. ANDRIA SCHUR, Ed.D. | CHIEF OF SCHOOLS |

## BOARD OF TRUSTEES

| | |
|---|---|
| KRISTIN K. TASSIN | PRESIDENT |
| RICK GARCIA | VICE PRESIDENT |
| DAVID HAMILTON | SECRETARY |
| ANGIE HANAN | BOARD MEMBER |
| ADAM SCHOOF | BOARD MEMBER |
| DR. SHIRLEY ROSE-GILLIAM | BOARD MEMBER |
| SONYA JONES | BOARD MEMBER |

## PROJECT DESIGN TEAM

PROGRAM MANAGEMENT
FBISD 2023 Bond Team
2323 Texas Parkway
Missouri City, TX 77489
Phone Number: 281-327-5481

ARCHITECT
MWA Architects
11767 Katy Freeway, Suite 430
Houston, Texas 77079
Phone Number: 713-782-8188

FOOD SERVICE
Food Design Professionals
26215 Oak Ridge Drive
The Woodlands, Texas 77380
Phone Number: 281-350-2323

MEP ENGINEERS
Stanton Engineering Group
1300 W. Sam Houston Pkwy South, Suite 121
Houston, Texas 77042
Phone Number: 713-300-9292

STRUCTURAL ENGINEER
Stanley Spurling & Hamilton
3301 Edloe Street, Suite 200
Houston, Texas 77027
Phone Number: 713-776-9433

ISSUED FOR PERMIT AND BIDDING - JULY 18, 2025

q

## AUDIO/VISUAL MULTIMEDIA LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| A## V## | WALL AV ROUGH-IN DETAIL |
| A## V## | CEILING AV ROUGH-IN DETAIL |
| A## V## | FLOOR AV ROUGH-IN DETAIL |
| IWB IWB | INTERACTIVE WHITE BOARD - WALL - CEILING |
| PJ PJ | MULTIMEDIA PROJECTOR |
| FP# FP# | MULTIMEDIA FLAT PANEL DISPLAY |
| S S | LOUDSPEAKER, WALL MOUNTED AND CEILING MOUNTED RESPECTIVELY - # INDICATES TYPE |
| CP# | CONTROL PANEL |
| TP# | TOUCH PANEL |
| M | MICROPHONE, CEILING MOUNTED - # INDICATES TYPE |
| VC | VOLUME CONTROL |
| WB | WALL BOX ENCLOSURE |
| D1 A1 | D1 = DIGITAL SINGLE SIDED CLOCK / A1 = ANALOG SINGLE SIDED CLOCK |
| D2 A2 | D2 = DIGITAL DOUBLE SIDED CLOCK / A2 = ANALOG DOUBLE SIDED CLOCK |
| ENC | CEILING AV ENCLOSURE |
| C C | PRESENTATION CAMERA - CEILING - WALL MOUNTED |

## PREMISE SECURITY LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| CR | CARD READER |
| CR M | CARD READER MULLION |
| KP | INTRUSION DETECTION KEYPAD |
| IC | INTERCOM (1 DATA CABLE) |
| IC MS | INTERCOM MASTER STATION (1 DATA CABLE) |
| PB | PANIC/DURESS BUTTON |
| LD | LOCK DOWN BUTTON |
| MD | MOTION DETECTOR |
| GB | ACCOUSTICAL GLASS BREAK SENSOR |
| BM | BIOMETRIC READER |
| RX | REQUEST TO EXIT - SURFACE PIR |
| KS | KEY SWITCH |
| LA | LOCAL ALARM SOUNDER |
| RG | RED/GREEN INDICATOR LIGHT |
| DB | DOORBELL |
| DH | MAGNETIC DOOR HOLD |
| DR | DOOR RELEASE |
| RX | REQUEST TO EXIT - INTEGRAL TO DOOR HARDWARE |
| DC | DOOR CONTACT / MONITOR |
| ES EL EH | ELECTRIFIED STRIKE - ELECTRIFIED LATCH - ELECTRIFIED HARDWARE (REFER TO SCHEDULES) |
| C C | STANDARD IP SURVEILLANCE CAMERA, (1) CABLE |
| C C C | 180° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° FISHEYE LENS CAMERA |
| IR | IR ILLUMINATOR |

## STRUCTURED CABLING LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF DATA CABLE(S)/JACK(S) |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) |
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| W | WALL MOUNT PHONE (1 CABLE/JACK) |
| W | WALL MOUNT PHONE, SURFACE MOUNT (1 CABLE/JACK) |
| # | FLOOR MOUNTED OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| #/# | FLOOR MOUNTED OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| # | CEILING MOUNTED DATA OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) |
| AP# | CEILING MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| AP# | WALL MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| | CABLING SLEEVE(S) |
| | TYPICAL LADDER RACK |
| | TYPICAL CABLE TRAY, BASKET STYLE |

## GENERAL ANNOTATION LEGEND


| SYMBOL | DESCRIPTION |
|---|---|
| MER | MAIN EQUIPMENT ROOM |
| TR | TELECOMMUNICATION ROOM |
| MDF | MAIN DISTRIBUTION FRAME |
| IDF | INTERMEDIATE DISTRIBUTION FRAME |
| ETR | EXISTING TO REMAIN |
| PBO | PROVIDED BY OTHERS |
| AFF | ABOVE FINISHED FLOOR |
| AFG | ABOVE FINISHED GRADE |
| AC | ABOVE COUNTER |
| EC | ELECTRICAL CONTRACTOR |
| PSC | PREMISE SECURITY CONTRACTOR |
| SCC | STRUCTURAL CABLING CONTRACTOR |
| AVC | AV/MULTIMEDIA CONTRACTOR |
| UNO | UNLESS NOTED OTHERWISE |
| ACS | ACCESS CONTROL SYSTEM |
| VSS | VIDEO SURVEILLANCE SYSTEM |

## TECHNOLOGY - GENERAL NOTES

1. EACH KEYNOTE MAY NOT BE UTILIZED ON EVERY SHEET.
2. ALL CONDUIT MEASUREMENTS REFER TO STANDARD CONDUIT TRADE SIZES.
3. ALL CABLES SHALL BE CONCEALED.
4. EACH CONTRACTOR SHALL PROVIDE AND INSTALL ALL NECESSARY SLEEVES, WHETHER OR NOT SPECIFICALLY NOTED ON PROJECT DRAWINGS. ALL SLEEVES SHALL BE 2" UNLESS NOTED OTHERWISE ON THE DRAWINGS. CABLE FILL PERCENTAGE SHALL COMPLY WITH NEC.
5. DEVICE LOCATIONS ARE APPROXIMATE. CONTRACTOR SHALL REVIEW CONDITIONS AND COORDINATE WITH OTHER TRADES AS NECESSARY FOR EXACT PLACEMENT.

## TECHNOLOGY SYMBOLS LEGEND

NOT ALL SYMBOLS ARE USED




TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

q

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Ridgegate Elementary School
6015 W Ridgecreek Dr. Houston, TX 77053

SEAL

BICSI CERTIFIED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 258657
EXPIRES 10-31-27
RCDD


07-18-25


MVA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY - TITLE SHEET

q-TN000




1 BACKGROUND Q (RIDGEGATE)
SCALE: 1" = 20'-0"

**TECHNOLOGY KEYNOTES**

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

q

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Ridgegate Elementary School
6015 W Ridgecreek Dr. Houston, TX 77053

SEAL

BICSI REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256557
EXPIRES 12-31-27

07-18-25

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Ridgegate ES - OVERALL

q-TN.100

TRUENORTH A PWY COMPANY

## TECHNOLOGY KEYNOTES

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.




1 RIDGEGATE - KITCHEN PLAN
SCALE: 3/16" = 1'-0"

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

q

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Ridgegate Elementary School
6015 W Ridgecreek Dr. Houston, TX 77053

SEAL

BICSI REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256657
EXPIRES 12-31-27
RCDD

07-18-25



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Ridgegate ES - KITCHEN


q-TN.101

**GENERAL NOTE**


1. FACE PLATE DETAIL FOR OUTLET CONFIGURATION PURPOSES ONLY. CONTRACTOR TO SELECT TYPE OF FACE PLATE TO MATCH CONNECTIVITY HARDWARE, FLOOR BOX AND/OR MODULAR FURNITURE OPENING.





1 DATA ROUGH-IN DETAILS
SCALE: NS





2 TYPICAL CABLING SLEEVE
SCALE: NTS





3 PANDUIT J-HOOK DETAIL
SCALE: NTS





4 LABELING & CABLING SCHEMES
SCALE: NTS





5 CABLE PATHWAY CROSS SECTION
SCALE: NTS




6 DROPPED CEILING MOUNTING DETAIL
SCALE: NS




7 I-JOIST MOUNTING DETAIL
SCALE: NS




8 BAR JOIST MOUNTING DETAIL
SCALE: NS

| CAMERA TYPE | MANUFACTURER | MODEL NUMBER | GENERAL DESCRIPTION |
|---|---|---|---|
| C1 | iPro | WV-S8574L | 4x4K (33MP) EXTERIOR MULTI-SENSOR - PARKING LOTS, STADIUM |
| C2 | iPro | WV-S8544L | 4x4MP (16MP) EXTERIOR MULTI-SENSOR - BUILDING PERIMETER |
| C3 | iPro | WV-S25500-V3LN | 5MP EXTERIOR VANDAL DOME |
| C4 | iPro | WV-S22500-V3L | 5MP INTERIOR VANDAL DOME - CORR., COMMON, SPED |
| C5 | iPro | WV-S4156A | 5MP 360 (FISHEYE) - STAIRWELLS |

9 CAMERA SCHEDULE
SCALE: NTS

| Symbol | Purpose | Size | Mount | Backbox | Notes |
|---|---|---|---|---|---|
| FP1 | Digital Signage/Menu Boards | +49" | Ceiling Pole | N/A | Data and Power Outlets on ceiling |

10 DISPLAY SCHEDULE
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

q

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Ridgegate Elementary School
6015 W Ridgecreek Dr. Houston, TX 77053

SEAL




07-18-25



MVA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Ridgegate ES - DETAILS


q-TN.500

GENERAL NOTES:


1. REFER TO SECURITY SCHEDULE AND WRITTEN SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
2. ALL MOUNTING DETAILS ARE REFERENCE FOR ALL FIXED DOME, 180°, 360°, PTZ, AND "BULLET/BOX" CAMERAS.





1 TYPICAL CAMERA INSTALLATION SECTION DETAIL
SCALE: NS




6 WALL MOUNTED CAMERA DETAIL
SCALE: NS




4 TILE BRIDGE DETAIL
SCALE: NS





5 CEILING MOUNTED CAMERA DETAIL
SCALE: NS


ACCESS CONROL DETAILS AND GENERAL NOTES:

1. CONDUIT ROUGH-IN IS A GUIDE FOR WHAT WILL BE REQUIRED FOR EACH DOOR. AS DOOR COMPONENTS CHANGE, EXACT CONDUIT LOCATION WILL ALSO NEED TO BE ADJUSTED.


2. PROTECT EXISTING-TO-REMAIN ACCESS CONTROL DEVICES AND CABLE THROUGHOUT RENOVATION WORK. IF CABLE AND/OR DEVICES ARE DAMAGED, SECURITY CONTRACTOR TO REPLACE WITH NEW.




1 ACCESS CONTROL - WIRING DETAIL - EXIT DEVICE W/ BUILT-IN REX
SCALE: NTS




2 ACCESS CONTROL - STEEL/HOLLOW METAL DOOR.
SCALE: NTS




KP PB LD

3 ROUGH-IN DETAILS: KP, PB, LD
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

q

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Ridgegate Elementary School
6015 W Ridgecreek Dr. Houston, TX 77053

SEAL

BICSI CERTIFIED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Potter
BICSI ID # 256657
EXPIRES 12-31-25
RCDD

07-18-25


MVA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING
AND
PERMITTING

TECHNOLOGY - Ridgegate ES
- SECURITY DETAILS

q-TN.600

# FBISD BP013 KITCHEN RENOVATIONS ES

| Sheet List Table | |
|---|---|
| Sheet Number | Sheet Title |
| School: r-RIDGEMONT ES | |
| r-A-000 | COVER AND INDEX |
| r-TN-000 | TECHNOLOGY - INDEX SHEET |
| r-TN-100 | TECHNOLOGY - OVERALL |
| r-TN-101 | TECHNOLOGY - KITCHEN |
| r-TN-500 | TECHNOLOGY - DETAILS |
| r-TN-600 | TECHNOLOGY - SECURITY DETAILS |




FORT BEND INDEPENDENT SCHOOL DISTRICT

## FORT BEND INDEPENDENT SCHOOL DISTRICT

RIDGEMONT ELEMENTARY SCHOOL
6015 W RAVEN RIDGE DRIVE, HOUSTON, TX 77053

## ADMINISTRATION

| | |
|---|---|
| DR. MARCELL SMITH | SUPERINTENDENT OF FBISD |
| DR. ANDRIA SCHUR, Ed.D. | CHIEF OF SCHOOLS |

## BOARD OF TRUSTEES

| | |
|---|---|
| KRISTIN K. TASSIN | PRESIDENT |
| RICK GARCIA | VICE PRESIDENT |
| DAVID HAMILTON | SECRETARY |
| ANGIE HANAN | BOARD MEMBER |
| ADAM SCHOOF | BOARD MEMBER |
| DR. SHIRLEY ROSE-GILLIAM | BOARD MEMBER |
| SONYA JONES | BOARD MEMBER |

## PROJECT DESIGN TEAM

PROGRAM MANAGEMENT
FBISD 2023 Bond Team
2323 Texas Parkway
Missouri City, TX 77489
Phone Number: 281-327-5481

ARCHITECT
MWA Architects
11767 Katy Freeway, Suite 430
Houston, Texas 77079
Phone Number: 713-782-8188

FOOD SERVICE
Food Design Professionals
26215 Oak Ridge Drive
The Woodlands, Texas 77380
Phone Number: 281-350-2323

MEP ENGINEERS
Stanton Engineering Group
1300 W. Sam Houston Pkwy South, Suite 121
Houston, Texas 77042
Phone Number: 713-300-9292

STRUCTURAL ENGINEER
Stanley Spurling & Hamilton
3301 Edloe Street, Suite 200
Houston, Texas 77027
Phone Number: 713-776-9433

ISSUED FOR PERMIT AND BIDDING - JULY 18, 2025

r

## AUDIO/VISUAL MULTIMEDIA LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| A## V## | WALL AV ROUGH-IN DETAIL |
| A## V## | CEILING AV ROUGH-IN DETAIL |
| A## V## | FLOOR AV ROUGH-IN DETAIL |
| IWB IWB | INTERACTIVE WHITE BOARD - WALL - CEILING |
| PJ PJ | MULTIMEDIA PROJECTOR |
| FP# FP# | MULTIMEDIA FLAT PANEL DISPLAY |
| S S | LOUDSPEAKER, WALL MOUNTED AND CEILING MOUNTED RESPECTIVELY - # INDICATES TYPE |
| CP# | CONTROL PANEL |
| TP# | TOUCH PANEL |
| M | MICROPHONE, CEILING MOUNTED - # INDICATES TYPE |
| VC | VOLUME CONTROL |
| WB | WALL BOX ENCLOSURE |
| D1 A1 | D1 = DIGITAL SINGLE SIDED CLOCK / A1 = ANALOG SINGLE SIDED CLOCK |
| D2 A2 | D2 = DIGITAL DOUBLE SIDED CLOCK / A2 = ANALOG DOUBLE SIDED CLOCK |
| ENC | CEILING AV ENCLOSURE |
| C C | PRESENTATION CAMERA - CEILING - WALL MOUNTED |

## PREMISE SECURITY LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| CR | CARD READER |
| CR M | CARD READER MULLION |
| KP | INTRUSION DETECTION KEYPAD |
| IC | INTERCOM (1 DATA CABLE) |
| IC MS | INTERCOM MASTER STATION (1 DATA CABLE) |
| PB | PANIC/DURESS BUTTON |
| LD | LOCK DOWN BUTTON |
| MD | MOTION DETECTOR |
| GB | ACCOUSTICAL GLASS BREAK SENSOR |
| BM | BIOMETRIC READER |
| RX | REQUEST TO EXIT - SURFACE PIR |
| KS | KEY SWITCH |
| LA | LOCAL ALARM SOUNDER |
| RG | RED/GREEN INDICATOR LIGHT |
| DB | DOORBELL |
| DH | MAGNETIC DOOR HOLD |
| DR | DOOR RELEASE |
| RX | REQUEST TO EXIT - INTEGRAL TO DOOR HARDWARE |
| DC | DOOR CONTACT / MONITOR |
| ES EL EH | ELECTRIFIED STRIKE - ELECTRIFIED LATCH - ELECTRIFIED HARDWARE (REFER TO SCHEDULES) |
| C C | STANDARD IP SURVEILLANCE CAMERA, (1) CABLE |
| C C C | 180° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° FISHEYE LENS CAMERA |
| IR | IR ILLUMINATOR |

## STRUCTURED CABLING LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF DATA CABLE(S)/JACK(S) |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) |
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| W | WALL MOUNT PHONE (1 CABLE/JACK) |
| W | WALL MOUNT PHONE, SURFACE MOUNT (1 CABLE/JACK) |
| # | FLOOR MOUNTED OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| #/# | FLOOR MOUNTED OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| # | CEILING MOUNTED DATA OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) |
| AP# | CEILING MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| AP# | WALL MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| | CABLING SLEEVE(S) |
| | TYPICAL LADDER RACK |
| | TYPICAL CABLE TRAY, BASKET STYLE |

## GENERAL ANNOTATION LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| MER | MAIN EQUIPMENT ROOM |
| TR | TELECOMMUNICATION ROOM |
| MDF | MAIN DISTRIBUTION FRAME |
| IDF | INTERMEDIATE DISTRIBUTION FRAME |
| ETR | EXISTING TO REMAIN |
| PBO | PROVIDED BY OTHERS |
| AFF | ABOVE FINISHED FLOOR |
| AFG | ABOVE FINISHED GRADE |
| AC | ABOVE COUNTER |
| EC | ELECTRICAL CONTRACTOR |
| PSC | PREMISE SECURITY CONTRACTOR |
| SCC | STRUCTURAL CABLING CONTRACTOR |
| AVC | AV/MULTIMEDIA CONTRACTOR |
| UNO | UNLESS NOTED OTHERWISE |
| ACS | ACCESS CONTROL SYSTEM |
| VSS | VIDEO SURVEILLANCE SYSTEM |

## TECHNOLOGY - GENERAL NOTES

1. EACH KEYNOTE MAY NOT BE UTILIZED ON EVERY SHEET.
2. ALL CONDUIT MEASUREMENTS REFER TO STANDARD CONDUIT TRADE SIZES.
3. ALL CABLES SHALL BE CONCEALED.
4. EACH CONTRACTOR SHALL PROVIDE AND INSTALL ALL NECESSARY SLEEVES, WHETHER OR NOT SPECIFICALLY NOTED ON PROJECT DRAWINGS. ALL SLEEVES SHALL BE 2" UNLESS NOTED OTHERWISE ON THE DRAWINGS. CABLE FILL PERCENTAGE SHALL COMPLY WITH NEC.
5. DEVICE LOCATIONS ARE APPROXIMATE. CONTRACTOR SHALL REVIEW CONDITIONS AND COORDINATE WITH OTHER TRADES AS NECESSARY FOR EXACT PLACEMENT.

## TECHNOLOGY SYMBOLS LEGEND

NOT ALL SYMBOLS ARE USED

- AV WALL ROUGH-IN WITH DATA
- KEYNOTE
- Proposed Camera Direction
  SURVEILLANCE CAMERA
  Camera Schedule Number (Floor #-Camera #)
  Camera (N)ew, (E)xisting Rough-in, (D)emo
- Proposed Camera Direction
  PTZ CAMERA
  PTZ
- Proposed Camera Direction
  FIXED SURVEILLANCE CAMERA
- 360°/MULTI-SENSOR FIXED SURVEILLANCE CAMERA OR FISHEYE LENS CAMERA
- Approximate view of lens
  Lens View Angle
  360°/MULTI-SENSOR FIXED SURVEILLANCE CAMERA OR FISHEYE LENS CAMERA
  Lens size
- MICROPHONE WITH AUDIO LINKED TO CAMERA
- CARD READER LINKED TO CAMERA
- SYMBOL TAG — (#) = DIFFERENT TYPES OF CARD READERS:
  M = MULLION
  W = WIRELESS (Proprietary)
  Wi = Wi-Fi (802.11)
  POE = POWER OVER ETHERNET
- SYMBOL TAG — (#) = DIFFERENT TYPES OF CARD READERS:
  TS = TOUCHSCREEN
  PU = PUSH BUTTON
- TOP = DETAIL NUMBER
  DETAIL REFERENCE
  BOTTOM = SHEET NUMBER
- NORTH ARROW
- SHEET NUMBER
  SECTION MARKER
  DETAIL NUMBER
- DIRECTION OF ELEVATION
  ELEVATION MARKER
  SHEET NUMBER
  DETAIL NUMBER
- DIRECTION OF ELEVATION
  SHEET NUMBER
  DIRECTION OF ELEVATION
  DETAIL NUMBER
- BAR IS ONE INCH ON ORIGINAL DRAWING. IF NOT ONE INCH ON THIS DRAWING ADJUST SCALES ACCORDINGLY

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

r

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Ridgemont Elementary School
4910 Raven Ridge Dr., Houston, TX 77053

SEAL

BICSI CERTIFIED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 258557
EXPIRES 10-31-27
NCCDD

07-18-25


MVA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY - TITLE SHEET

r-TN000

## TECHNOLOGY KEYNOTES

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.




1 BACKGROUND R (RIDGEMONT ES)
SCALE: 1" = 20'-0"

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

r

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Ridgemont Elementary School
4910 Raven Ridge Dr., Houston, TX 77053

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian O Porter
BICSI ID # 256657
EXPIRES 12-31-27
RCDD

07-18-25


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Ridgemont ES - OVERALL


r-TN.100

## TECHNOLOGY KEYNOTES

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.




1 RIDGEMONT - KITCHEN PLAN
SCALE: 3/16" = 1'-0"




2 RIDGEMONT - REFLECTED CEILING PLAN
SCALE: 3/16" = 1'-0"

TRUENORTH
A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

r

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Ridgemont Elementary School
4910 Raven Ridge Dr., Houston, TX 77053

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 259557
EXPIRES 12-31-27

07-18-25



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Ridgemont ES - KITCHEN


r-TN.101

**GENERAL NOTE**


1. FACE PLATE DETAIL FOR OUTLET CONFIGURATION PURPOSES ONLY. CONTRACTOR TO SELECT TYPE OF FACE PLATE TO MATCH CONNECTIVITY HARDWARE, FLOOR BOX AND/OR MODULAR FURNITURE OPENING.





1 DATA ROUGH-IN DETAILS
SCALE: NS





2 TYPICAL CABLING SLEEVE
SCALE: NTS





3 PANDUIT J-HOOK DETAIL
SCALE: NTS





4 LABELING & CABLING SCHEMES
SCALE: NTS





5 CABLE PATHWAY CROSS SECTION
SCALE: NTS




6 DROPPED CEILING MOUNTING DETAIL
SCALE: NS




7 I-JOIST MOUNTING DETAIL
SCALE: NS




8 BAR JOIST MOUNTING DETAIL
SCALE: NS

| CAMERA TYPE | MANUFACTURER | MODEL NUMBER | GENERAL DESCRIPTION |
|---|---|---|---|
| C1 | iPro | WV-S8574L | 4x4K (33MP) EXTERIOR MULTI-SENSOR - PARKING LOTS, STADIUM |
| C2 | iPro | WV-S8544L | 4x4MP (16MP) EXTERIOR MULTI-SENSOR - BUILDING PERIMETER |
| C3 | iPro | WV-S25500-V3LN | 5MP EXTERIOR VANDAL DOME |
| C4 | iPro | WV-S22500-V3L | 5MP INTERIOR VANDAL DOME - CORR., COMMON, SPED |
| C5 | iPro | WV-S4156A | 5MP 360 (FISHEYE) - STAIRWELLS |

9 CAMERA SCHEDULE
SCALE: NTS

| Symbol | Purpose | Size | Mount | Backbox | Notes |
|---|---|---|---|---|---|
| FP1 | Digital Signage/Menu Boards | +49" | Ceiling Pole | N/A | Data and Power Outlets on ceiling |

10 DISPLAY SCHEDULE
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

r

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Ridgemont Elementary School
4910 Raven Ridge Dr., Houston, TX 77053

SEAL





07-18-25


ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Ridgemont ES - DETAILS
r-TN.500

GENERAL NOTES:


1. REFER TO SECURITY SCHEDULE AND WRITTEN SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
2. ALL MOUNTING DETAILS ARE REFERENCE FOR ALL FIXED DOME, 180°, 360°, PTZ, AND "BULLET/BOX" CAMERAS.





1 TYPICAL CAMERA INSTALLATION SECTION DETAIL
SCALE: NS




6 WALL MOUNTED CAMERA DETAIL
SCALE: NS




4 TILE BRIDGE DETAIL
SCALE: NS





5 CEILING MOUNTED CAMERA DETAIL
SCALE: NS


ACCESS CONROL DETAILS AND GENERAL NOTES:

1. CONDUIT ROUGH-IN IS A GUIDE FOR WHAT WILL BE REQUIRED FOR EACH DOOR. AS DOOR COMPONENTS CHANGE, EXACT CONDUIT LOCATION WILL ALSO NEED TO BE ADJUSTED.


2. PROTECT EXISTING-TO-REMAIN ACCESS CONTROL DEVICES AND CABLE THROUGHOUT RENOVATION WORK. IF CABLE AND/OR DEVICES ARE DAMAGED, SECURITY CONTRACTOR TO REPLACE WITH NEW.




1 ACCESS CONTROL - WIRING DETAIL - EXIT DEVICE W/ BUILT-IN REX
SCALE: NTS




2 ACCESS CONTROL - STEEL/HOLLOW METAL DOOR.
SCALE: NTS




KP PB LD

3 ROUGH-IN DETAILS: KP, PB, LD
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

r

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Ridgemont Elementary School
4910 Raven Ridge Dr., Houston, TX 77053

SEAL




07-18-25

MVA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING
AND
PERMITTING
TECHNOLOGY - Ridgemont
ES - SECURITY DETAILS

r-TN.600

# FBISD BP013 KITCHEN RENOVATIONS ES

## SETTLERS WAY ELEMENTARY SCHOOL
SETTLERS WAY PARK, 3015 SETTLERS WAY BLVD,
SUGAR LAND, TX 77479

FORT BEND INDEPENDENT SCHOOL DISTRICT BOND 2023

FORT BEND INDEPENDENT SCHOOL DISTRICT

## ADMINISTRATION

| | |
|---|---|
| DR. MARCELL SMITH | SUPERINTENDENT OF FBISD |
| DR. ANDRIA SCHUR, Ed.D. | CHIEF OF SCHOOLS |

## BOARD OF TRUSTEES

| | |
|---|---|
| KRISTIN K. TASSIN | PRESIDENT |
| RICK GARCIA | VICE PRESIDENT |
| DAVID HAMILTON | SECRETARY |
| ANGIE HANAN | BOARD MEMBER |
| ADAM SCHOOF | BOARD MEMBER |
| DR. SHIRLEY ROSE-GILLIAM | BOARD MEMBER |
| SONYA JONES | BOARD MEMBER |

## PROJECT DESIGN TEAM


**PROGRAM MANAGEMENT**
FBISD 2023 Bond Team
2323 Texas Parkway
Missouri City, TX 77489
Phone Number: 281-327-5481

**ARCHITECT**
MWA Architects
11767 Katy Freeway, Suite 430
Houston, Texas 77079
Phone Number: 713-782-8188

**FOOD SERVICE**
Food Design Professionals
26215 Oak Ridge Drive
The Woodlands, Texas 77380
Phone Number: 281-350-2323

**MEP ENGINEERS**
Stanton Engineering Group
1300 W. Sam Houston Pkwy South, Suite 121
Houston, Texas 77042
Phone Number: 713-300-9292

**STRUCTURAL ENGINEER**
Stanley Spurling & Hamilton
3301 Edloe Street, Suite 200
Houston, Texas 77027
Phone Number: 713-776-9433


| Sheet List Table | |
|---|---|
| Sheet Number | Sheet Title |
| School: s-Settlers Way ES | |
| s-A.000 | COVER AND INDEX |
| s-A00-01 | GENERAL NOTES AND ABBREVIATIONS |
| s-D.101 | DEMO PLAN |
| s-D.101-2 | DEMO PLAN PHOTOS |
| s-D.101-3 | DEMO PLAN PHOTOS |
| s-PD1.01 | PLUMBING DEMOLITION FLOOR PLAN |
| s-ED.100 | ELECTRICAL DEMOLITION AND TEMPORARY PLANS |
| s-TD201 | TECHNOLOGY DEMOLITION FLOOR PLAN |
| s-A.101 | SITE PLAN |
| s-A.200 | SLAB DIMENSION CONTROL PLAN |
| s-A.201 | OVERALL FLOOR PLAN |
| s-A.301 | KITCHEN PLAN |
| s-A.302 | TEMPORARY KITCHEN LAYOUT |
| s-A.401 | REFLECTED CEILING PLAN |
| s-A.501 | FINISH FLOOR PLAN |
| s-A.502 | PARTITION SCHEDULE |
| s-S1 | KITCHEN PLAN |
| s-S2 | SECTIONS AND TYPICAL DETAILS |
| s-QF1 | FS GENERAL COORDINATION NOTES |
| s-QF1.0 | FS EQUIPMENT PLAN |
| s-QF1.1 | FS FACILITY MODEL |
| s-QF1.2 | FS EQUIPMENT MODEL |
| s-QF1.3 | FS SPECIAL CONDITIONS & MECHANICAL PLAN |
| s-QF1.4 | FS PLUMBING PLAN |
| s-QF1.5 | FS ELECTRICAL PLAN |
| s-M1.01 | MECHANICAL PLANS |
| s-M2.01 | KITCHEN DETAILS |
| s-E.000 | ELECTRICAL AND FIRE ALARM SCHEDULES |
| s-E.001 | ELECTRICAL AND FIRE ALARM NOTES |
| s-E.010 | ELECTRICAL DEVICE DETAILS |
| E.011 | ELECTRICAL DETAILS |
| E.012 | ELECTRICAL DETAILS |
| E.013 | ELECTRICAL KITCHEN DETAILS |
| E.060 | LIGHTING SCHEDULES |
| s-E.100 | LIGHTING FLOOR PLANS |
| s-E.200 | ELECTRICAL FLOOR PLANS |
| s-E.300 | FIRE ALARM FLOOR PLANS |
| s-E.400 | ELECTRICAL SCHEMATIC |
| s-P0.01 | PLUMBING NOTES & SCHEDULES |
| s-P0.02 | PLUMBING SCHEDULES & DETAILS |
| s-P1.01 | PLUMBING FLOOR PLAN |
| s-P1.02 | PLUMBING TEMPORARY KITCHEN PLAN |
| s-T000 | TECHNOLOGY SYMBOLS & LEGEND |
| s-T200 | TECHNOLOGY COMPOSITE FLOOR PLAN |
| s-T201 | TECHNOLOGY NEW RENOVATION KITCHEN PLAN |
| s-T202 | TECHNOLOGY TEMPORARY KITCHEN FLOOR PLAN |
| s-T300 | TECHNOLOGY ENLARGED VIEWS |
| s-T400 | TECHNOLOGY TYPICAL DETAILS |
| s-T401 | TECHNOLOGY TYPICAL DETAILS |
| s-T500 | TECHNOLOGY TYPICAL DETAILS |
| s-TN-000 | TECHNOLOGY - INDEX SHEET |
| s-TN-001 | TECHNOLOGY - KITCHEN DEMOLITION |
| s-TN-100 | TECHNOLOGY - OVERALL |
| s-TN-101 | TECHNOLOGY - KITCHEN |
| s-TN-500 | TECHNOLOGY - DETAILS |
| s-TN-600 | TECHNOLOGY - SECURITY DETAILS |
| s-TN-700 | TECHNOLOGY - AV DETAILS |

REGISTERED ARCHITECT MICHAEL A. MAGUIRE 22651 STATE OF TEXAS

18 JULY 2025

ISSUED FOR PERMIT AND BIDDING - JULY 18, 2025

S

PART 1 - GENERAL

1.1 GENERAL DEMOLITION NOTES

A. VERIFY EXISTING SITE AND BUILDING CONDITIONS IN FIELD PRIOR TO BIDDING. NOTIFY ARCHITECT OF ANY DISCREPANCIES PRIOR TO BIDDING.

B. CONTRACTOR SHALL COORDINATE WITH OWNER THE SALVAGE OF ITEMS, FURNITURE AND EQUIPMENT INDICATED TO BE REMOVED.

C. CLAIMS FOR ADDITIONAL COST OR TIME DUE TO EXISTING CONDITIONS THAT COULD HAVE BEEN REASONABLY ANTICIPATED DURING A SITE VISIT BY THE CONTRACTOR PRIOR TO BIDDING WILL NOT BE APPROVED.

D. PROTECT EXISTING FINISHES SHOWN TO REMAIN DURING CONSTRUCTION TO PREVENT DAMAGE. REPAIR OR REPLACE DAMAGED MATERIALS AND FINISHES TO MATCH EXISTING AT NO ADDITIONAL COST TO FORT BEND ISD (OWNER).

E. EXISTING AREAS REQUIRING MINOR DEMOLITION OR REPAIR FOR EXECUTION OF WORK SHALL BE REPAIRED TO MATCH EXISTING ADJACENT MATERIALS, UNLESS NOTED OTHERWISE.

F. DO NOT DAMAGE CASEWORK AND EQUIPMENT NOT DESIGNATED TO BE REMOVED OR RELOCATED.EXISTING CASEWORK SHALL REMAIN THE PROPERTY OF THE OWNER.

G. CONTRACTOR TO VERIFY LOCATION OF ELEC. SWITCHES, OUTLETS, GRILLES, CLEAN-OUTS, COVER PLATES, ACCESS DOORS, AND OTHER EQUIPMENT AND DEVICES THAT MAY CONFLICT WITH THE RENOVATION AND NEW CONSTRUCTION OF WALLS, FLOORS, AND CEILINGS PRIOR TO COMMENCEMENT OF WORK. CONTRACTOR SHALL LIKEWISE CONFIRM THAT ELECTRICAL CONDUIT ROUTING SHALL BE CONCEALED WITHIN WALLS. NOTIFY ARCHITECT IF WALL THICKNESS WILL NOT ALLOW FOR CONCEALMENT.

H. REMOVE ANY EXISTING CORNER GUARDS IN THE KITCHEN AREA.

I. PRIOR TO EXECUTION OF DEMOLITION WORK, SCHEDULE A WALK-THROUGH WITH OWNER AND ARCHITECT TO CONFIRM SCOPE OF WORK AND TO REVIEW EXISTING CONDITIONS.

J. EXISTING FLOOR FINISHES AND ACOUSTIC CEILING TILE TO BE REMOVED THROUGHOUT.

K. REFER TO MEP DRAWINGS FOR DEMOLITION AND ALTERATION OF UTILITIES.

L. AT ALL EXISTING WALLS REQUIRING DEMOLITION TO INSTALL NEW PIPING BEHIND SINKS, CUT AND PATCH WALLS AS REQUIRED TO MATCH ADJACENT SURFACE.

M. CLEAN AND PREPARE SUBFLOOR FOR INSTALLATION OF NEW FLOOR FINISH.

N. DEMOLITION ACTIVITIES SHALL BE PERFORMED AS TO PRODUCE MINIMAL DISTURBANCE TO EXISTING FACILITY OCCUPANTS. MINIMIZE EXCESSIVE AND PROLONGED NOISE LEVELS AND DUST.

O. ASBESTOS-CONTAINING MATERIALS. REFER TO SPECIFICATION 02 26 23 FOR ASBESTOS INFORMATION APPLICABLE TO KITCHEN AREAS. FORT BEND ISD HAS RETAINED A SEPARATE ENVIRONMENTAL CONSULTANT FOR THE REMOVAL OF ASBESTOS. GC TO COORDINATE WITH ENVIRONMENTAL CONSULTANT TO CARRY OUT ASBESTOS ABATEMENT FOR ALL AFFECTED KITCHEN AREAS.

1.2 FLOOR PLAN GENERAL NOTES

A. FIELD VERIFY EXISTING CONDITIONS PRIOR TO GENERATING SHOP DRAWINGS AND FABRICATION OF EQUIPMENT.
B. FLOOR FINISH CHANGES SHALL OCCUR AT THE CENTERLINE OF DOORS UNLESS NOTED OTHERWISE. FLOOR FINISH CHANGES SHALL HAVE THRESHOLDS OR REDUCERS STRIPS.
C. DOORS THAT ARE TO BE REPLACED AND INSTALLED IN EXISTING FRAMES SHALL BE MACHINED FOR HARDWARE DIMENSIONS AT EXISTING FRAMES, CONTRACTOR SHALL FIELD VERIFY FRAME CONDITIONS AND DIMENSIONS.
D. CONTRACTOR TO PROVIDE SHEET METAL REINFORCING STRAP AS REQUIRED FOR MOUNTING OF ALL GRAB BARS, CABINETS, MIRRORS, SHELVING, ETC.
E. SAW CUT AND REMOVE EXISTING SLAB AND FLOOR FINISHES AS REQUIRED TO INSTALL NEW PLUMBING LINES, FLOOR DRAINS, PLUMBING FIXTURES, OR ELECTRICAL ITEMS. SPLICE NEW REINFORCING BARS DOWELED INTO EXISTING CONCRETE, AND PROVIDE NEW VAPOR RETARDER AND WATERSTOPS, AND PATCH W/ 3000 PSI CONCRETE AFTER INSTALLATION OF UTILITIES AND FIXTURES. PREPARE CONCRETE TO RECEIVE NEW FINISH.
F. COORDINATE HOUSEKEEPING PAD DIMENSIONS AND LOCATIONS WITH EQUIPMENT TO BE INSTALLED. HOUSEKEEPING PADS SHALL BE A MIN. OF 4" THICK REINF. W/ #3 BARS AT 15" O.C. BOTH WAYS. PROVIDE 1" BY 45-DEGREE CHAMFERED EDGES.

1.3 COMPLETE PERFORMANCE

L. THE CONTRACTOR SHALL FURNISH AND INSTALL ALL ITEMS SPECIFIED HEREIN AND AS INDICATED ON THE DRAWINGS. THE CONTRACTOR SHALL ALSO FURNISH AND INSTALL ALL ITEMS NECESSARY TO MAKE THE SYSTEMS FUNCTION WHICH MAY BE REASONABLY IMPLIED AS ESSENTIAL, WHETHER MENTIONED IN THE CONTRACT DOCUMENTS OR NOT.

M. WORK SHALL BE EXECUTED IN STRICT ACCORDANCE WITH THE BEST PRACTICE OF THE TRADES IN A THOROUGH, SUBSTANTIAL AND WORKMANLIKE MANNER BY COMPETENT WORKMEN.

1.4 SITE FAMILIARIZATION

A. GENERAL: BECOME FAMILIAR WITH THE DRAWINGS AND SPECIFICATIONS, EXAMINE THE PREMISES, AND UNDERSTAND THE CONDITIONS UNDER WHICH THE CONTRACT SHALL BE PERFORMED, PRIOR TO SUBMITTING A BID.

B. SITE: BE INFORMED OF THE SITE CONDITIONS, VERIFY LOCATIONS OF NEW AND EXISTING EQUIPMENT, AND DETERMINE EXACT REQUIREMENTS FOR CONNECTIONS.

C. COORDINATION: TENDER OF A PROPOSAL FOR THIS PROJECT INFERS THAT THE CONTRACTOR HAS VISITED THE SITE AND HAS BECOME FAMILIAR WITH THE DRAWINGS, SPECIFICATIONS, AND SITE CONDITIONS AND HAS INCLUDED IN HIS PROPOSAL ALL WORK NECESSARY TO PROPERLY INSTALL COMPLETE AND FUNCTIONING SYSTEMS ON THE PROJECT. FAILURE TO COMPLY WITH THIS REQUIREMENT SHALL NOT BE CONSIDERED JUSTIFICATION FOR THE OMISSION OR FAULTY INSTALLATION OF ANY WORK COVERED BY THE CONTRACT DOCUMENTS.

1.5 CODES AND STANDARDS

A. GENERAL: ALL WORK SHALL COMPLY WITH THE MOST RECENTLY REVISED VERSIONS OF ALL APPLICABLE LAWS, RULES, REGULATIONS AND ORDINANCES OF ALL FEDERAL, STATE AND LOCAL AUTHORITIES AND APPLICABLE UTILITIES. NONE OF THE TERMS OR PROVISIONS OF THIS SPECIFICATION SHALL BE CONSTRUED AS WAIVING ANY PART OF THE LAWS, RULES, REGULATIONS OR REQUIREMENTS OF THESE AUTHORITIES.

B. CONFLICT: IN THE EVENT OF CONFLICT BETWEEN THE CONTRACT DOCUMENTS AND THE LOCAL ENFORCING AUTHORITY, THE LATTER SHALL RULE. ANY MODIFICATIONS RESULTING THEREFROM SHALL BE MADE WITHOUT ANY ADDITIONAL COST TO THE OWNER OR ARCHITECT. THIS CONTRACTOR SHALL REPORT ANY SUCH MODIFICATIONS TO THE ARCHITECT AND SECURE HIS APPROVAL PRIOR TO PROCEEDING WITH THE WORK.

C. PRECEDENCE: WHERE CONTRACT DOCUMENT REQUIREMENTS EXCEED THE REQUIREMENTS OF THE CODES AND STANDARDS, THE CONTRACT DOCUMENTS SHALL TAKE PRECEDENCE PROVIDED THEY ARE NOT IN CONFLICT WITH THOSE CODES AND STANDARDS.

D. APPROVAL LABELS: ALL ITEMS OF EQUIPMENT AND ALL MATERIALS FOR WHICH APPROVED STANDARDS HAVE BEEN ESTABLISHED BY UNDERWRITERS' LABORATORIES, INC. (UL), FACTORY MUTUAL (FM), CERTIFIED BALLAST MANUFACTURER (CBM), ELECTRICAL TESTING LABORATORY (ETL), NATIONAL MANUFACTURERS ASSOCIATION (NEMA), AMERICAN STANDARD CODES, ASME, AGA, AMCA, ASA, ANSI, ASHRAE, AND ARI SHALL BE SO APPROVED AND SHALL BEAR APPROVAL LABELS ATTESTING TO SAME.

1.6 DRAWINGS AND SPECIFICATIONS

A. DRAWINGS: THE SET OF ORIGINAL DRAWINGS HAS BEEN MODIFIED AND INDICATE APPROXIMATE EXISTING LOCATIONS OF THE FLOOR FINISH ITEMS. ALL ITEMS ARE SHOWN APPROXIMATELY TO SCALE. FIELD VERIFY CONDITIONS.

B. SPECIFICATIONS: THE SPECIFICATIONS ARE INTENDED TO SUPPLEMENT THE DRAWINGS AND IT IS NOT IN THE SCOPE OF THE SPECIFICATIONS TO MENTION ANY PART OF THE WORK THAT THE DRAWINGS ARE COMPETENT TO FULLY EXPLAIN. CONVERSELY, ANY PART OF THE WORK THAT THE SPECIFICATIONS ARE COMPETENT TO FULLY EXPLAIN MAY NOT BE MENTIONED ON THE DRAWINGS. DRAWINGS AND SPECIFICATIONS ARE COMPLIMENTARY/SUPPLEMENTARY DOCUMENTS TO EACH OTHER.

C. DISAGREEMENT: DISAGREEMENT BETWEEN THE DRAWINGS AND SPECIFICATIONS OR WITHIN THE DRAWINGS OR SPECIFICATIONS SHALL BE ESTIMATED AND/OR BID USING THE BETTER QUALITY OR GREATER QUANTITY OF MATERIAL OR INSTALLATION, AND A CLARIFICATION REQUEST FOR INFORMATION SHALL BE MADE TO THE ARCHITECT IN A TIMELY MANNER AFTER THE PROJECT IS UNDER CONTRACT.

1.7 DISCREPANCIES

A. CLARIFICATION: CLARIFICATION OF SIGNIFICANT COST MATTERS SHALL BE OBTAINED BEFORE SUBMITTING A PROPOSAL FOR THE WORK AS TO DISCREPANCIES OR OMISSIONS FROM THE CONTRACT DOCUMENTS OR QUESTIONS AS TO THE INTENT THEREOF.

B. INTERPRETATIONS: SHOULD ANY DOUBT OR QUESTION ARISE RESPECTING THE TRUE MEANING OF DRAWINGS OR SPECIFICATIONS, REFERENCE SHALL BE MADE TO THE ARCHITECT, WHOSE WRITTEN DECISION SHALL BE FINAL AND CONCLUSIVE. NO ALLEGED STATEMENT BY THE ARCHITECT WILL BE ACCEPTED AS AN EXCUSE FOR NON-COMPLIANCE OR INFERIOR WORK.

C. CONTRACTOR AGREEMENT: CONSIDERATION WILL NOT BE GRANTED FOR MISUNDERSTANDING OF THE AMOUNT OF WORK TO BE PERFORMED. TENDER OF A PROPOSAL CONVEYS FULL CONTRACTOR AGREEMENT OF THE ITEMS AND CONDITIONS SPECIFIED, SHOWN, SCHEDULED, OR REQUIRED BY THE NATURE OF THE PROJECT, AND ALL COSTS ARE INCLUDED IN THE PROPOSAL.

1.8 REQUESTS FOR INFORMATION (RFI)

A. GENERAL: SUBMIT ALL CONTRACTOR REQUESTS FOR INFORMATION (RFI) IN WRITING TO THE ARCHITECT FOR RESPONSE. SUBMIT RFI ON A STANDARD FORM THAT HAS A SPACE FOR THE REQUESTED INFORMATION AND THE ARCHITECT'S RESPONSE.
B. SOLUTION PROPOSAL: IN GENERAL, THE CONTRACTOR SHALL PROPOSE SOLUTIONS TO IDENTIFY PROBLEMS FOR REVIEW AND APPROVAL OF THE ARCHITECT. THE RFI SHALL INCLUDE HAND SKETCHES, MARKED DRAWING PRINTS, EQUIPMENT CUTSHEETS, DRAWING AND SPECIFICATION REFERENCES, AND ANY OTHER BACK-UP INFORMATION, ETC., AS REQUIRED TO SUFFICIENTLY EXPLAIN THE PROBLEM AND PROPOSED SOLUTION.

1.9 QUALITY ASSURANCE

A. GENERAL: MATERIALS AND EQUIPMENT SHALL BE NEW, OF BEST GRADE AND QUALITY, AND STANDARD PRODUCTS OF REPUTABLE MANUFACTURERS REGULARLY ENGAGED IN THE PRODUCTION OF SUCH MATERIALS AND EQUIPMENT.
B. WORKMANSHIP: WORK SHALL BE EXECUTED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE BEST PRACTICE OF THE TRADES IN A THOROUGH, SUBSTANTIAL, WORKMANLIKE MANNER BY COMPETENT WORKMEN, PRESENTING A NEAT APPEARANCE WHEN COMPLETED.
C. JUDGMENT: IN ALL CASES, THE ARCHITECT SHALL BE THE SOLE JUDGE OF THE QUALITY AND EQUIVALENCE OF MANUFACTURERS, PRODUCTS, MATERIALS, AND METHODS.
D. MANUFACTURERS/PRODUCTS/MATERIALS/METHODS: MANUFACTURERS, PRODUCTS, MATERIALS, AND METHODS DESCRIBED IN THE VARIOUS SECTIONS OF THE SPECIFICATIONS AND INDICATED ON THE DRAWINGS ARE INTENDED TO ESTABLISH A STANDARD OF QUALITY ONLY. IT IS NOT THE INTENTION OF THE ARCHITECT TO DISCRIMINATE AGAINST ANY MANUFACTURER, PRODUCT, MATERIAL, OR METHOD THAT IS EQUAL TO THE STANDARDS AS INDICATED AND/OR SPECIFIED, NOR IS IT INTENDED TO PRECLUDE OPEN, COMPETITIVE BIDDING. THE FACT THAT A SPECIFIC MANUFACTURER IS LISTED AS AN ACCEPTABLE MANUFACTURER SHALL NOT BE INTERPRETED TO MEAN THAT THE MANUFACTURER'S STANDARD PRODUCT WILL MEET THE REQUIREMENTS OF THE PROJECT DESIGN, SPECIFICATIONS, AND SPACE CONSTRAINTS.
   1. WHEREVER A DEFINITE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS SPECIFIED AND THERE IS NOT A STATEMENT THAT ANOTHER MANUFACTURER, PRODUCT, MATERIAL, OR METHOD WILL BE ACCEPTABLE, IT IS THE INTENTION OF THE ARCHITECT THAT THE SPECIFIED MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS THE ONLY ONE THAT SHALL BE USED WITHOUT PRIOR APPROVAL.
   2. WHEREVER A DEFINITE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS SPECIFIED AS "NO SUBSTITUTE", IT IS THE INTENTION OF THE ARCHITECT THAT THE LISTED ITEM IS THE ONLY ONE ACCEPTABLE.
E. COORDINATION: WHERE EQUIPMENT IS USED ON THE PROJECT, IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR OR SUBCONTRACTOR INVOLVED TO VERIFY THAT THE EQUIPMENT WILL FIT IN THE SPACE AVAILABLE, INCLUDING ALL REQUIRED CODE AND MAINTENANCE CLEARANCES, AND TO COORDINATE ALL EQUIPMENT REQUIREMENTS AND PROVISIONS WITH THE SYSTEM DESIGN, ALL AFFECTED DIVISIONS, AND ALL OTHER CONTRACTORS. WHERE THE USE OF ALTERNATE OR SUBSTITUTE MATERIALS AFFECTS THE COST OF PROVISIONS MADE BY OTHER CONTRACTORS, THE CONTRACTOR PROVIDING THE ALTERNATE OR SUBSTITUTE SHALL BE RESPONSIBLE FOR THE OTHER CONTRACTOR'S COST ADJUSTMENT. THERE SHALL BE NO ADDITIONAL COST TO THE OWNER OR ARCHITECT DUE TO THE USE OR ACCEPTANCE OF ANY ALTERNATE OR SUBSTITUTE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD.

1.10 PRIOR APPROVAL

A. SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES: THE CONTRACTOR'S SUBMITTAL AND ARCHITECT'S ACCEPTANCE OF SHOP DRAWINGS, PRODUCT DATA, OR SAMPLES THAT RELATE TO CONSTRUCTION ACTIVITIES NOT COMPLYING WITH THE CONTRACT DOCUMENTS DOES NOT CONSTITUTE AN ACCEPTABLE OR VALID REQUEST FOR SUBSTITUTION, NOR DOES IT CONSTITUTE APPROVAL.

1.11 COORDINATION

A. BY SUBMITTING SHOP DRAWINGS ON THE PROJECT, THIS CONTRACTOR IS INDICATING THAT ALL NECESSARY COORDINATION HAS BEEN COMPLETED AND THAT THE SYSTEMS, PRODUCTS AND EQUIPMENT SUBMITTED CAN BE INSTALLED IN THE BUILDING AND WILL OPERATE AS SPECIFIED AND INTENDED, IN FULL COORDINATION WITH ALL OTHER DISCIPLINES.

1.12 SHOP DRAWINGS AND SUBMITTALS

A. GENERAL: AFTER THE CONTRACT IS AWARDED BUT PRIOR TO PROCEEDING WITH THE WORK REQUIRING SHOP DRAWING REVIEW, THE CONTRACTOR SHALL OBTAIN COMPLETE SHOP DRAWINGS AND PRODUCT DATA FROM THE MANUFACTURERS, SUPPLIERS, VENDORS, AND SUB- CONTRACTORS FOR ALL MATERIALS AND EQUIPMENT SPECIFIED HEREIN, AND MAKE FORMAL SUBMISSION TO THE ARCHITECT. A MINIMUM PERIOD OF TWO (2) WEEKS SHOULD BE ALLOWED IN THE CONSTRUCTION SCHEDULE EXCLUSIVE OF TRAVEL TIME FOR THE ARCHITECTS REVIEW.

B. CERTIFICATION: EACH CONTRACTOR RESPONSIBLE FOR THE WORK SHALL REVIEW AND CERTIFY THE SHOP DRAWING, SUBMITTAL AND/OR PRODUCT DATA TO BE IN FULL COMPLIANCE WITH THE REQUIREMENTS OF THE CONTRACT DOCUMENTS.

C. THE ARCHITECTS REVIEW OF SHOP DRAWINGS AND SUBMITTAL DATA SHALL NOT RELIEVE THE CONTRACTOR OF THE RESPONSIBILITY FOR DIMENSIONS OR ERRORS THAT MAY BE CONTAINED THEREIN, OR FOR DEVIATIONS FROM ANY REQUIREMENTS OF THE CONTRACT DOCUMENTS. IT SHALL BE CLEARLY UNDERSTOOD THAT THE ARCHITECTS NOTING SOME ERRORS BUT OVERLOOKING SOME OTHERS DOES NOT GRANT THE CONTRACTOR PERMISSION TO PROCEED IN ERROR. REGARDLESS OF ANY INFORMATION CONTAINED IN THE SHOP DRAWING OR PRODUCT DATA, THE CONTRACT DOCUMENTS SHALL GOVERN THE WORK AND ARE NEITHER WAIVED NOR SUPERSEDED IN ANY WAY BY THE REVIEW OF SHOP DRAWINGS, PRODUCT DATA AND SAMPLES.

1.13 EXECUTION AND COORDINATION OF WORK

A. MANUFACTURER'S RECOMMENDATIONS: WITH EXCEPTIONS AS SPECIFIED AND/OR INDICATED ON THE DRAWINGS OR IN THE SPECIFICATIONS, APPLY, INSTALL, ERECT, USE, CLEAN, AND CONDITION, MANUFACTURED ARTICLES, MATERIALS, AND EQUIPMENT PER MANUFACTURER'S CURRENT PRINTED RECOMMENDATIONS. KEEP COPIES OF SUCH PRINTED RECOMMENDATIONS AT JOB SITE AND MAKE THEM AVAILABLE AS REQUIRED.

1.14 SUPERVISION

A. A COMPETENT SUPERINTENDENT APPROVED BY THE ARCHITECT, SHALL BE KEPT BY THE CONTRACTOR AT THE BUILDING TO RECEIVE INSTRUCTIONS AND TO ACT FOR THE CONTRACTOR. ONCE THE SUPERINTENDENT HAS BEEN APPROVED, NO CHANGE SHALL BE MADE WITHOUT APPROVAL OF ARCHITECT. REPRESENTATIVES OF THE OWNER, ARCHITECT SHALL HAVE THE RIGHT TO OBSERVE THE WORK AT ANY TIME. THE CONTRACTOR SHALL HAVE A REPRESENTATIVE AVAILABLE WHEN HIS WORK IS BEING OBSERVED AND HE SHALL GIVE ASSISTANCE AS MAY BE REQUIRED TO THE ARCHITECT'S REPRESENTATIVE.

B. THE PROJECT SHALL BE CONSTRUCTED BY EMPLOYEES OF THE CONTRACTOR OR BY WORKERS UNDER HIS SUPERVISION. ANY SUBCONTRACTORS EMPLOYED BY THE CONTRACTOR SHALL BE APPROVED BY THE OWNER'S REPRESENTATIVE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL EQUIPMENT, MATERIAL AND WORK PERFORMED BY ANY SUBCONTRACTOR.

1.15 STORAGE AND PROTECTION OF MATERIALS

A. THE CONTRACTOR SHALL PROPERLY STORE ALL MATERIAL AND EQUIPMENT AT THE JOBSITE AND PROTECT IT FROM THE ELEMENTS AND FROM DAMAGE. ANY EQUIPMENT DAMAGED DUE TO IMPROPER PROTECTION SHALL BE REPLACED BY THE CONTRACTOR AT HIS EXPENSE.

B. THE CONTRACTOR SHALL PROTECT THE WORK, EQUIPMENT, AND MATERIAL OF ALL OTHER TRADES FROM DAMAGE BY HIS WORK OR OTHER WORKMEN, AND SHALL MAKE GOOD ALL DAMAGE THUS CAUSED.

C. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL WORK, MATERIALS, AND EQUIPMENT UNTIL FINALLY INSPECTED, TESTED, AND ACCEPTED; PROTECT WORK AGAINST THEFT, INJURY OR DAMAGE; AND CAREFULLY STORE MATERIAL AND EQUIPMENT RECEIVED ON SITE WHICH ARE NOT IMMEDIATELY INSTALLED. CLOSE OPEN ENDS OF WORK WITH TEMPORARY COVERS OR PLUGS DURING CONSTRUCTION TO PREVENT ENTRY OF OBSTRUCTING MATERIAL. THE CONTRACTOR SHALL COVER AND PROTECT IN AN ACCEPTABLE MANNER TO THE OWNER, EXISTING REMAINING EQUIPMENT AND MATERIALS.

D. IF ANY MATERIAL OR EQUIPMENT IS RECEIVED PRIOR TO THE TIME IT IS REQUIRED, THE CONTRACTOR SHALL BE RESPONSIBLE FOR ITS PROPER STORAGE AND PROTECTION UNTIL SUCH TIME AS IT MAY BE REQUIRED. THE CONTRACTOR SHALL PAY FOR ALL COSTS OF DEMURRAGE OR STORAGE.

1.16 DRAYAGE AND HAULING


A. THE CONTRACTOR SHALL KEEP THE JOBSITE FREE FROM THE ACCUMULATION OF TRASH AND CONSTRUCTION DEBRIS, REGARDLESS OF WHICH SUBCONTRACTOR MAY BE RESPONSIBLE.

1.17 CUTTING AND PATCHING


A. WHERE IT BECOMES NECESSARY TO CUT THROUGH ANY WALL, FLOOR OR CEILING TO PERMIT THE INSTALLATION OF ANY WORK, OR TO REPAIR ANY DEFECTS THAT MAY APPEAR, THE CUTTING SHALL BE PERFORMED UNDER THE SUPERVISION OF THE GENERAL CONTRACTOR. INFORM THE OWNER'S REPRESENTATIVE BEFORE ANY WORK COMMENCES. NO STRUCTURAL MEMBER SHALL BE ALTERED WITHOUT THE WRITTEN PERMISSION OF THE ARCHITECT.

B. VERIFICATION: SHOULD A QUESTION ARISE REGARDING THE ACCEPTABLE LEVEL OF NOISE OR VIBRATION IN A PARTICULAR SPACE OR PIECE OF EQUIPMENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING THE SERVICES OF AN APPROVED ACOUSTICAL CONSULTANT TO DETERMINE ACTUAL NOISE/VIBRATION CONDITIONS.


## 01 GENERAL NOTES





## 21 EXTERIOR DOOR SILL
SCALE: 6" = 1'-0" XREF





## 22 DOOR JAMB
SCALE: 6" = 1'-0" XREF





## 23 WINDOW HEAD
SCALE: 6" = 1'-0" XREF





## 24 DOOR WINDOW HEAD
SCALE: 6" = 1'-0" XREF




## 15 WINDOW JAMB AT WALL
SCALE: ###############





## 16 DOOR HEAD
SCALE: 6" = 1'-0" XREF





## 17 WINDOW SILL
SCALE: 6" = 1'-0" XREF





## 18 DOOR SILL
SCALE: 6" = 1'-0" XREF





## 09 WINDOW CORNER
SCALE: ###############




## 10 DOOR STRIKE JAMB
SCALE: ###############





## 11 DOOR HINGE JAMB
SCALE: ###############





## 12 WINDOW MULLION
SCALE: ###############

| SEQUENCE OF CONSTRUCTION (AS OF 01/27/2025). Schools will be renovated in groups as shown. These groups contain two or three major kitchen renovations and some cafeteria/miscellaneous renovations. This sequencing is critical for FBISD food service to provide the uninterrupted meal services to their schools. | |
|---|---|
| GROUPING 1 | AUSTIN PARKWAY ES + SUGAR MILL ES, kitchen renovations. *Plus: COMMON WEALTH ES, CONERSTONE ES misc. renovations.* |
| GROUPING 2 | SETTLERS WAY ES + PALMER ES kitchen renovations. *Plus: SULLIVAN ES, SIENNA CROSSING ES, HERITAGE ROSE ES misc. renovations* |
| GROUPING 3 | HUNTER'S GLEN ES + HIGHLANDS ES + PECAN GROVE ES kitchen renovations. *Plus: RIDGEGATE ES, DULLES ES misc. renovations.* |

## 03 PROJECT SCHEDULE




## 04 EXTERIOR DOOR HEAD JAMB
SCALE: 6" = 1'-0" XREF




## 06 WINDOW JAMB
SCALE: 6" = 1'-0" XREF

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD
SUGAR LAND, TX 77479

SEAL
REGISTERED ARCHITECT
ROBERT A. MEYER
23013
STATE OF TEXAS
7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

GENERAL NOTES AND ABBREVIATIONS

A00-01

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\A00-01 GENERAL NOTES AND ABBREVIATIONS.dwg, Jul 23, 2025 - 4:45pm

## GENERAL DEMOLITION NOTES
(NOT ALL NOTES USED ON EACH SHEET)

1. REFER TO SHEET A00-01 FOR DEMOLITION GENERAL NOTES. THESE NOTES APPLY TO ALL SCHOOL KITCHENS.
2. COORDINATE EXTENT OF SAW CUTTING AREAS WITH NEW RECESSED SLAB FOR COOLER/FREEZER LAYOUTS, NEW SERVICE ENTRANCE FLOOR AND EXISTING KITCHEN LAYOUTS THAT REMAIN. SEE STRUCTURAL DRAWINGS AND SLAB DIMENSION CONTROL PLANS FOR ADDITIONAL SCOPE.
3. REMOVE PROTECT AND REINSTALL ALL EXISTING SURFACE MOUNTED FIRE EXTINGUISHERS (TYPES ABC AND K) AT ALL KITCHENS.
4. SAWCUT AND RE-LOCATE EXPOSED CONDUITS AND WIREMOLD TO INSIDE OF WALLS. PATCH AND PAINT. EXCEPTION: WAREWASH AREA BELOW TABLE HEIGHT AND DRY STORAGE ROOMS.
5. CONTRACTOR TO RELOCATE EXISTING KITCHEN EQUIPMENT AND OFFICE FURNITURE TO TEMPORARY KITCHEN LAYOUT AS REQUESTED BY KITCHEN MANAGER. ALSO THAT THE IT EQUIPMENT IS PROTECTED DURING RENOVATIONS. ALL EXISTING EQUIPMENT SHALL BE RETURNED TO OWNER.
6. EXISTING TACKBOARDS TO BE REMOVED BY OWNER.
7. IF PRESENT, EXISTING SAFE IN EACH KITCHEN TO BE TEMPORARILY REMOVED DURING RENOVATION AND REINSTALLED IN KITCHEN AREA.
8. ORIGIN POINT OF EXISTING CEILING GRID SHALL BE IDENTIFIED. NEW CEILING WILL BE INSTALLED (AS MUCH AS POSSIBLE) AT THE SAME ORIGIN POINT SO THAT SPRINKLER SYSTEM PIPING CAN REMAIN UNCHANGED.
9. ABOVE-CEILING INFRASTRUCTURE SHALL REMAIN UNDISTURBED AS MUCH AS IS POSSIBLE. CEILING DEVICES ARE TO BE REMOVED FROM EXISTING GRID/TILE THEN DURING RE-INSTALATION OF CEILING DEVICES SHALL BE LOCATED AS CLOSE TO ORIGINAL LOCATION AS POSSIBLE INTO THE NEW GRID/TILE. PROTECT AND STORE EXISTING INFRASTRUCTURE (CABLING, ELECTRICAL POWER, PIPING) DURING CONSTRUCTION.
10. EXISTING HOOD IN WAREWASH AND (2) HOODS IN PRODUCTION AREA ARE TO BE CLEANED, INSPECTED, SERVICED AND REFURBISHED TO A

## KEYED DEMOLITION NOTES
(NOT ALL NOTES USED ON EACH SHEET)

1. REMOVE EXISTING THINSET SYNTHETIC TERRAZZO FLOOR AND TERRAZZO COVE BASE MATERIAL IF ANY EXISTS THROUGHTOUT KITCHEN AREA. CLEAN AND PREPARE SUBFLOOR TO RECEIVE NEW FLOOR. RE: FINISH PLAN FOR NEW FLOOR FINISH MATERIAL.
2. REMOVE EXISTING QUARRY TILE FLOORING AND BASE. CLEAN AND PREPARE SUBFLOOR TO RECEIVE NEW FLOORING. RE: FINISH SCHEDULE FOR NEW FLOOR FINISH MATERIAL.
3. CEILING DEVICES: REMOVE SMOKE DETECTORS, STROBES, EXIT SIGNAGE, MOTION DETECTORS AND CEILING SPEAKERS. PROTECT AND RE-INSTALL AFTER FINISHES ARE APPLIED.
4. REMOVE EXISTING LOCKERS. PROTECT AND RE-INSTALL AFTER FINISHES APPLIED.
5. REMOVE EXISTING WASHER AND DRYER. VERIFY WITH FBISD FOR RELOCATION TO WAREHOUSE.
6. TEMPORARILY REMOVE EXISTING WALL MOUNTED CLOCK AND STORE FOR REINSTALLATION AFTER WALL RECEIVED NEW FINISH.
7. REMOVE EXISTING WALK-IN COOLER/FREEZER AND CONDENSING UNIT LOCATED IN ADJACENT SPACE. MITIGATE ANY MOLD FOUND.
8. REMOVE EXISTING DOOR AND PROTECT EXISTING FRAME TO REMAIN
9. REMOVE EXISTING DOOR AND FRAME, PROTECT FRAME AND OR DOOR IF IT IS SCHEDULED TO REMAIN.
10. REMOVE PARTIAL EXISTING CMU PARTITION FOR NEW DOOR OPENING
11. INSPECT EXISTING WAREWASH COUNTER DOOR AND S.S. PASS-THRU WINDOW CHUTE. REPAIR REPLACE DAMAGED COMPONENTS. CLEAN, LUBRICATE AND RE-INSTALL.
12. EXISTING CARD READER ACCESS TO REMAIN
13. EXISTING WINDOW TO REMAIN
14. REMOVE EXISTING KITCHEN EQUIPMENT THROUGHOUT KITCHEN INCLUDING WALK-IN COOLER / FREEZER AND CONDENSING UNIT LOCATED IN ADJACENT ROOM OR OUTSIDE OF THE BUILDING. VERIFY WITH OWNER FOR RELOCATION TO WAREHOUSE. SOME EQUIPMENT IS TO BE RE-USED IN TEMPORARY SERVING LINES. SEE ALSO GENERAL DEMOLITION NOTE 6.
15. REMOVE EXISTING FRP AND PREP FOR NEW TILE FINISH.
16. COORDINATE REMOVAL AND STORAGE OF ANY EXISTING FURNITURE ITEMS WITH OWNER . SEE ALSO GENERAL DEMOLITION NOTE 5.
17. REMOVE EXISTING SOAP AND PAPER TOWEL DISPENSER AND RETURN TO OWNER
18. EXISTING WALL MOUNTED ACCESSORIES SIGNS, DISPLAY BOARDS, AND MATS TO BE REMOVED BY FORT BEND ISD (VERIFY EQUIPMENT - IF ANY).
19. REMOVE EXISTING SURFACE MOUNTED FIRE EXTINGUISHER. RE-INSTALL AFTER NEW FINISH APPLIED.
20. REMOVE EXISTING ACOUSTIC CEILING TILE CEILNG SYSTEM AND LIGHT FIXTURES, HVAC DEVICES, SENSORS, ETC. THROUGHTOUT RENOVATED AREAS. PREP FOR NEW SUSPENDED CEILING. EXISTING SPRINKLE SYSTEM TO REMAIN AS-IS UNLESS ROOM CONFIGURATION HAS CHANGED IN NEW DESIGN. PROTECT RECESSED SPRINKLER HEADS AND - RE-INSTALL IN NEW CEILING.
21. REMOVE EXISTING CASEWORK/SHELVING
22. EXISTING CERAMIC WALL TILE TO REMAIN. PROTECT FROM DAMAAGE.
23. REMOVE EXISTING COAT HANGER / ROD / SHELF
24. REMOVE EXISTING PLUMBING FIXTURES IN RESTROOMS. RE: PLUMBING FOR NEW FIXTURES.
25. REMOVE EXISTING UTILITY SINK. RE: PLUMBING FOR NEW PLUMBING FIXTURES.
26. REMOVE EXISTING MOP HOLDER. REPLACE WITH NEW UNIT AS SPECIFIED.
27. REMOVE EXISTING WALL MOUNTED CLEANING SOLUTION DISPENSER (BY FBISD VENDOR)
28. HOOD TO REMAIN - SEE GENERAL DEMOLITION NOTE 10.
29. HOOD TO REMAIN - SEE GENERAL DEMOLITION NOTE 10.
30. REMOVE FLOORING IN THIS AREA FOR NOTE 1.
31. REMOVE CARTIDGE FILTER AND WATER PURTICATION CABNET


## DEMOLITION LEGEND

- EXISTING PARTITION TO REMAIN
- REMOVE EXISTING PARTITION
- EXISTING CMU PARTITION
- REMOVE DOOR AND FRAME TO REMAIN
- REMOVE EXISTING DOOR AND FRAME
- EXISTING PLUMBING FIXTURES (WATER CLOSET, HAND LAVATORY, AND MOP SINK TO BE REMOVED. RE: PLUMBING DRAWINGS.
- EXISTING ACOUSTIC CEILING TILE AND GRID TO BE REMOVED. RE: ELECTRICAL DRAWINGS.
- SPRINKLER HEAD (RECESSED)
- CLOCK
- CEILING MOUNTED SPEAKERS


## 3 DEMOLITION NOTES

## OLD FLOOR LEGEND

OLD QUARRY TILE
(1,562 SF)




## 1 DEMOLITION FLOOR PLAN
SCALE: 1/4" = 1'-0"




## 2 DEMOLITION REFLECTED CEILING PLAN
SCALE: 1/4" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT

SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD
SUGAR LAND, TX 77479

SEAL
REGISTERED ARCHITECT
22651
STATE OF TEXAS
7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

OVERALL FLOOR PLAN

s-A.201

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\S-Settlers Way ES\s-D.101 DEMO PLAN.dwg Jul 23, 2025 - 4:45pm


PHOTO D1


PHOTO D2




PHOTO D3



PHOTO D4



PHOTO D5




PHOTO D6



PHOTO D7



PHOTO D8




PHOTO D9




PHOTO D10



PHOTO D11




PHOTO D12



PHOTO D13




PHOTO D14




PHOTO D15



PHOTO D16



PHOTO D17




PHOTO D18



PHOTO D19



PHOTO D20

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT

SETTLERS WAY ELEMENTARY SCHOOL
SETTLERS WAY PAR, 3015 SETTLERS WAY BLVD,
SUGAR LAND, TX 77479

SEAL

REGISTERED ARCHITECT
MICHAEL K. WILLIAMS
#2651
STATE OF TEXAS

7/15/2025

MWA ARCHITECTS

ARCHITECTS
AND PLANNING
CONSULTANTS

11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

DEMO PLAN PHOTOS

s-D.101-2

F:\2022\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\S-Settlers Way ES\s-D.101-2 DEMO PLAN PHOTOS.dwg Jul 23, 2025 - 4:46pm




PHOTO D21




PHOTO D22



PHOTO D23



PHOTO D24




PHOTO D25



PHOTO D26



PHOTO D27



PHOTO D28




PHOTO D29


PHOTO D30

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
SETTLERS WAY PAR, 3015 SETTLERS WAY BLVD,
SUGAR LAND, TX 77479

SEAL

REGISTERED ARCHITECT
ANDREW M. WILLIAMS
23651
STATE OF TEXAS

7/15/2025

MWA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

DEMO PLAN
PHOTOS

s-D.101-3

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\S-Settlers Way ES\s-D.101-3 DEMO PLAN PHOTOS.dwg Jul 23, 2025 - 4:46pm

## NEW PANEL

## TEMP KITCHEN

**PANEL LTK**


150A MCB
208Y/120V, 3ϕ, 4 WIRE

AVAILABLE FAULT: <10,000A
SCCR & AIC: 10,000A


MOUNTING: SURFACE

| NOTES | EQUIP. NO. | LOAD | DESCRIPTION | WIRE | CB | CKT | A | B | C | CKT | CB | WIRE | DESCRIPTION | LOAD | EQUIP. NO. | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E810 | 2766 | HOT WELLS | 2–12 | 20/2GFI | 1 | ■ | | | 2 | 20/1 | 3–12 | TRANSPORT CART | 1920 | E806 | |
| | – | – | – | +12G | – | 3 | | ■ | | 4 | 20/1 | 3–12 | TRANSPORT CART | 1920 | E806 | |
| | E810A | 1643 | HOT WELLS | 2–12 | 20/2GFI | 5 | | | ■ | 6 | 20/1 | 3–12 | TRANSPORT CART | 1920 | E806 | |
| | – | – | – | +12G | – | 7 | ■ | | | 8 | 20/1 | 3–12 | TRANSPORT CART | 1920 | E806 | |
| | E810B | 600 | COLD PAN | 3–12 | 20/1GFI | 9 | | ■ | | 10 | 20/1 | 3–12 | 2 REC | 360 | E800A | |
| | E810C | 1200 | BEVERAGE | 3–12 | 20/1GFI | 11 | | | ■ | 12 | 20/1 | 3–12 | 2 REC – DESK | 360 | E800B | |
| | E810C | 1200 | BEVERAGE | 3–12 | 20/1GFI | 13 | ■ | | | 14 | 20/1 | 3–12 | 2 REC | 360 | E800A | |
| | E811 | 180 | CASH REGISTER | 3–12 | 20/1GFI | 15 | | ■ | | 16 | 20/1 | 3–12 | 3 REC | 360 | E800A | |
| | E810B | 600 | COLD PAN | 3–12 | 20/1GFI | 17 | | | ■ | 18 | 20/1 | 3–12 | TEMP. KITCHEN LTS/FAN | 566 | | |
| | E810A | 1643 | HOT WELLS | 2–12 | 20/2GFI | 19 | ■ | | | 20 | 20/1 | | SPARE | | | |
| | – | – | – | +12G | – | 21 | | ■ | | 22 | 20/1 | | SPARE | | | |
| | E810 | 2766 | HOT WELLS | 2–12 | 20/2GFI | 23 | | | ■ | 24 | 20/1 | | SPARE | | | |
| | – | – | – | +12G | – | 25 | ■ | | | 26 | 20/1 | | SPARE | | | |
| | E808 | 1622 | HEATED CABINET | 2–12 | 20/2 | 27 | | ■ | | 28 | 20/1 | | SPARE | | | |
| | – | – | – | +12N+12G | – | 29 | | | ■ | 30 | 20/1 | 3–12 | EXISTING CIRCUIT | 500 | | 3 |
| | E809 | 984 | REFRIGERATOR | 3–12 | 20/1 | 31 | ■ | | | 32 | 20/1 | 3–12 | EXISTING CIRCUIT | 500 | | 3 |
| | E808 | 1622 | HEATED CABINET | 2–12 | 20/2 | 33 | | ■ | | 34 | 15/2 | 2–12 | EXISTING CIRCUIT | 1000 | | 3 |
| | – | – | – | +12N+12G | – | 35 | | | ■ | 36 | – | +12N+12G | – | – | | |
| | E809 | 984 | REFRIGERATOR | 3–12 | 20/1 | 37 | ■ | | | 38 | 20/2 | 2–12 | EXISTING CIRCUIT | 1000 | | 3 |
| | | | SPARE | | 20/1 | 39 | | ■ | | 40 | – | +12N+12G | – | – | | |
| | | | SPARE | | 20/1 | 41 | | | ■ | 42 | 50/2 | 2–8 | EXISTING CIRCUIT | 5000 | | 3 |
| | | | SPARE | | 20/1 | 43 | ■ | | | 44 | – | +8N+10G | – | – | | |
| | TOTAL LOAD @ 100% = 35498VA | | | | | | TOTAL LOAD @ 100% = 99A | | | | | | | | | |


1. REF. KITCHEN CONSULTANT'S "FCS" DRAWINGS FOR KITCHEN EQUIPMENT NUMBERS.
2. A DEMAND FACTOR PERCENT OF 65% HAS BEEN APPLIED TO THE KITCHEN EQUIPMENT LOAD PURSUANT TO NEC 220–20 AND NEC TABLE 220–20.
3. IDENTIFY ANY CIRCUITS OR PARTIAL CIRCUITS THAT EXTEND BEYOND THE AREA OF RENOVATION. PROVIDE TEMPORARY FEED TO MAINTAIN ALL CIRCUITS SERVING ELEMENTS/SPACES NOT TO BE REMOVED DURING CONSTRUCTION. RECONNECT EXISTING CIRCUITS/DEVICES TO REMAIN TO TEMPORARY KITCHEN PANEL ONCE AVAILABLE USING CB(S) PROVIDED. ALL PARTIAL CIRCUITS SHALL REMAIN AND REMAIN ACTIVE BOTH DURING AND AFTER CONSTRUCTION.




**T1** **TEMPORARY KITCHEN - LIGHTING PLAN**
SCALE: 1/4" = 1'– 0"




**T2** **TEMPORARY KITCHEN - ELECTRICAL PLAN**
SCALE: 1/4" = 1'– 0"




**1** **DEMOLITION FLOOR PLAN**
SCALE: 1/8" = 1'– 0"

## ELECTRICAL KEYED NOTES

GENERAL NOTES:

- CUT WALLS AS REQUIRED TO FLUSH MOUNT NEW DEVICES IN EXISTING WALLS. PATCH/REPAIR WALLS TO MATCH.

DEMOLITION NOTES:

A. EXISTING STANDBY GENERATOR PANEL TO REMAIN.

B. EXISTING KITCHEN PANELS TO BE REPLACED WITH NEW. MODIFY EXISTING WALLS TO MATCH NEW PANEL LAYOUTS AND DIMENSIONS.

C. EXISTING LIGHTING FIXTURES AND CEILING DEVICES TO BE REMOVED THROUGHOUT.

D. EXISTING WALK–IN COOLER/FREEZER AND ASSOCIATED EQUIPMENT TO BE REMOVED.

E. EXISTING WALL ELECTRICAL DEVICES TO BE REMOVED. EXISTING J–BOXES MAY BE REUSED WHERE NEW DEVICES ARE TO BE INSTALLED AT THE SAME LOCATIONS.

F. EXISTING ELECTRICAL DEVICES TO BE REMOVED.

G. NEW 208Y/120V PANEL AND TRANSFORMER FOR TEMPORARY KITCHEN TO BE INSTALLED PRIOR TO DEMOLITION. PANEL AND TRANSFORMER TO BE REMOVED AT END OF KITCHEN RENOVATION AND TURNED OVER TO THE DISTRICT. INSTALL TRANSFORMER ON PREMADE FIBERCRETE PAD AND WAFFLE TYPE VIBRATION ISOLATION PADS. DO NOT PROVIDE A POURED IN PLACE CONCRETE PAD AT THIS LOCATION.

H. PROVIDE RECEPTACLES AND LIGHT FIXTURES FOR TEMPORARY KITCHEN DURING RENOVATION. ALL TEMPORARY DEVICES AND EQUIPMENT TO BE REMOVED AT END OF KITCHEN RENOVATION AND OFFERED TO THE OWNER AS SALVAGE.

I. CONDUITS ROUTED FROM TEMPORARY KITCHEN WALL AND BENEATH SERVING LINE. PROVIDE MULTICHANNEL ROLLOVER CABLE PROTECTOR FOR EXPOSED CONDUITS NOT UNDER THE SERVING LINE. ALL CONDUITS UNDER THE SERVING LINE SHALL BE SECURED TO/ROUTED ON TOP OF UNISTRUT AND NOT DIRECTLY ON THE FLOOR. DO NOT ANCHOR UNISTRUT TO THE EXISTING FLOORING. COORDINATE POWER AND DATA OUTLET LOCATIONS WITH OTHER TRADES.

J. REMOVE EXISTING LIGHT FIXTURES ABOVE NEW KITCHEN EXTENSION. MODIFY EXISTING WIRING TO MAINTAIN REMAINING FIXTURE OPERATION.

K. HARDWIRE KITCHEN EQUIPMENT TO LOCAL ON/OFF SWITCH. TYPICAL.

L. SURFACE MOUNT FIXTURES ON TEMPORARY KITCHEN CEILING. TYPICAL.

M. WIRE TEMPORARY KITCHEN FAN TO LOCAL LIGHTING CIRCUIT AND CONTROLS. FAN SHALL BE ON/OFF WITH LIGHTS.

N. EXISTING EXTERIOR LIGHT FIXTURES TO BE REMOVED.

O. PROVIDE NEW FIRE ALARM DEVICES AS PART OF THE TEMPORARY KITCHEN BUILDOUT.

P. PROVIDE NEW TEMPORARY LIGHT FIXTURES IN THE EXISTING CAFETERIA CEILING ABOVE THE SERVING LINE. COORDINATE LOCATIONS WITH TEMPORARY SERVING LINE AND EXISTING CONDITIONS. CONNECT TO EXISTING LIGHTING CONTROLS/CIRCUIT. ALL TEMPORARY LIGHT FIXTURES SHALL BE REMOVED AT THE END OF KITCHEN RENOVATION AND OFFERED TO THE OWNER AS SALVAGE. PROVIDE REPLACEMENT CEILING TILES.

Q. PROVIDE IN–USE WEATHERPROOF COVER FOR RECEPTACLE.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

**S**

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD.
SUGAR LAND, TX 77479

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL DEMO AND TEMP PLANS

s-ED.100


STANTON ENGINEERING GROUP
INFO@STANTON-TX.COM | (713) 300–6080


TEXAS ENGINEERING REG. NO. F–23111 © 2025 ALL RIGHTS RESERVED


12800 W. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77043

## NEW PANEL

## TEMP KITCHEN

**PANEL LTK**


150A MCB
208Y/120V, 3ϕ, 4 WIRE

AVAILABLE FAULT: <10,000A
SCCR & AIC: 10,000A


MOUNTING: SURFACE

| NOTES | EQUIP. NO. | LOAD | DESCRIPTION | WIRE | CB | CKT | A | B | C | CKT | CB | WIRE | DESCRIPTION | LOAD | EQUIP. NO. | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E810 | 2766 | HOT WELLS | 2–12 | 20/2GFI | 1 | ■ | | | 2 | 20/1 | 3–12 | TRANSPORT CART | 1920 | E806 | |
| | – | – | – | +12G | – | 3 | | ■ | | 4 | 20/1 | 3–12 | TRANSPORT CART | 1920 | E806 | |
| | E810A | 1643 | HOT WELLS | 2–12 | 20/2GFI | 5 | | | ■ | 6 | 20/1 | 3–12 | TRANSPORT CART | 1920 | E806 | |
| | – | – | – | +12G | – | 7 | ■ | | | 8 | 20/1 | 3–12 | TRANSPORT CART | 1920 | E806 | |
| | E810B | 600 | COLD PAN | 3–12 | 20/1GFI | 9 | | ■ | | 10 | 20/1 | 3–12 | 2 REC | 360 | E800A | |
| | E810C | 1200 | BEVERAGE | 3–12 | 20/1GFI | 11 | | | ■ | 12 | 20/1 | 3–12 | 2 REC – DESK | 360 | E800B | |
| | E810C | 1200 | BEVERAGE | 3–12 | 20/1GFI | 13 | ■ | | | 14 | 20/1 | 3–12 | 2 REC | 360 | E800A | |
| | E811 | 180 | CASH REGISTER | 3–12 | 20/1GFI | 15 | | ■ | | 16 | 20/1 | 3–12 | 3 REC | 360 | E800A | |
| | E810B | 600 | COLD PAN | 3–12 | 20/1GFI | 17 | | | ■ | 18 | 20/1 | 3–12 | TEMP. KITCHEN LTS/FAN | 566 | | |
| | E810A | 1643 | HOT WELLS | 2–12 | 20/2GFI | 19 | ■ | | | 20 | 20/1 | | SPARE | | | |
| | – | – | – | +12G | – | 21 | | ■ | | 22 | 20/1 | | SPARE | | | |
| | E810 | 2766 | HOT WELLS | 2–12 | 20/2GFI | 23 | | | ■ | 24 | 20/1 | | SPARE | | | |
| | – | – | – | +12G | – | 25 | ■ | | | 26 | 20/1 | | SPARE | | | |
| | E808 | 1622 | HEATED CABINET | 2–12 | 20/2 | 27 | | ■ | | 28 | 20/1 | | SPARE | | | |
| | – | – | – | +12N+12G | – | 29 | | | ■ | 30 | 20/1 | 3–12 | EXISTING CIRCUIT | 500 | | 3 |
| | E809 | 984 | REFRIGERATOR | 3–12 | 20/1 | 31 | ■ | | | 32 | 20/1 | 3–12 | EXISTING CIRCUIT | 500 | | 3 |
| | E808 | 1622 | HEATED CABINET | 2–12 | 20/2 | 33 | | ■ | | 34 | 15/2 | 2–12 | EXISTING CIRCUIT | 1000 | | 3 |
| | – | – | – | +12N+12G | – | 35 | | | ■ | 36 | – | +12N+12G | – | – | | |
| | E809 | 984 | REFRIGERATOR | 3–12 | 20/1 | 37 | ■ | | | 38 | 20/2 | 2–12 | EXISTING CIRCUIT | 1000 | | 3 |
| | | | SPARE | | 20/1 | 39 | | ■ | | 40 | – | +12N+12G | – | – | | |
| | | | SPARE | | 20/1 | 41 | | | ■ | 42 | 50/2 | 2–8 | EXISTING CIRCUIT | 5000 | | 3 |
| | | | SPARE | | 20/1 | 43 | ■ | | | 44 | – | +8N+10G | – | – | | |
| | TOTAL LOAD @ 100% = 35498VA | | | | | | TOTAL LOAD @ 100% = 99A | | | | | | | | | |


1. REF. KITCHEN CONSULTANT'S "FCS" DRAWINGS FOR KITCHEN EQUIPMENT NUMBERS.
2. A DEMAND FACTOR PERCENT OF 65% HAS BEEN APPLIED TO THE KITCHEN EQUIPMENT LOAD PURSUANT TO NEC 220–20 AND NEC TABLE 220–20.
3. IDENTIFY ANY CIRCUITS OR PARTIAL CIRCUITS THAT EXTEND BEYOND THE AREA OF RENOVATION. PROVIDE TEMPORARY FEED TO MAINTAIN ALL CIRCUITS SERVING ELEMENTS/SPACES NOT TO BE REMOVED DURING CONSTRUCTION. RECONNECT EXISTING CIRCUITS/DEVICES TO REMAIN TO TEMPORARY KITCHEN PANEL ONCE AVAILABLE USING CB(S) PROVIDED. ALL PARTIAL CIRCUITS SHALL REMAIN AND REMAIN ACTIVE BOTH DURING AND AFTER CONSTRUCTION.




**T1** **TEMPORARY KITCHEN - LIGHTING PLAN**
SCALE: 1/4" = 1'– 0"




**T2** **TEMPORARY KITCHEN - ELECTRICAL PLAN**
SCALE: 1/4" = 1'– 0"




**1** **DEMOLITION FLOOR PLAN**
SCALE: 1/8" = 1'– 0"

## ELECTRICAL KEYED NOTES

GENERAL NOTES:

- CUT WALLS AS REQUIRED TO FLUSH MOUNT NEW DEVICES IN EXISTING WALLS. PATCH/REPAIR WALLS TO MATCH.

DEMOLITION NOTES:

A. EXISTING STANDBY GENERATOR PANEL TO REMAIN.

B. EXISTING KITCHEN PANELS TO BE REPLACED WITH NEW. MODIFY EXISTING WALLS TO MATCH NEW PANEL LAYOUTS AND DIMENSIONS.

C. EXISTING LIGHTING FIXTURES AND CEILING DEVICES TO BE REMOVED THROUGHOUT.

D. EXISTING WALK–IN COOLER/FREEZER AND ASSOCIATED EQUIPMENT TO BE REMOVED.

E. EXISTING WALL ELECTRICAL DEVICES TO BE REMOVED. EXISTING J–BOXES MAY BE REUSED WHERE NEW DEVICES ARE TO BE INSTALLED AT THE SAME LOCATIONS.

F. EXISTING ELECTRICAL DEVICES TO BE REMOVED.

G. NEW 208Y/120V PANEL AND TRANSFORMER FOR TEMPORARY KITCHEN TO BE INSTALLED PRIOR TO DEMOLITION. PANEL AND TRANSFORMER TO BE REMOVED AT END OF KITCHEN RENOVATION AND TURNED OVER TO THE DISTRICT. INSTALL TRANSFORMER ON PREMADE FIBERCRETE PAD AND WAFFLE TYPE VIBRATION ISOLATION PADS. DO NOT PROVIDE A POURED IN PLACE CONCRETE PAD AT THIS LOCATION.

H. PROVIDE RECEPTACLES AND LIGHT FIXTURES FOR TEMPORARY KITCHEN DURING RENOVATION. ALL TEMPORARY DEVICES AND EQUIPMENT TO BE REMOVED AT END OF KITCHEN RENOVATION AND OFFERED TO THE OWNER AS SALVAGE.

I. CONDUITS ROUTED FROM TEMPORARY KITCHEN WALL AND BENEATH SERVING LINE. PROVIDE MULTICHANNEL ROLLOVER CABLE PROTECTOR FOR EXPOSED CONDUITS NOT UNDER THE SERVING LINE. ALL CONDUITS UNDER THE SERVING LINE SHALL BE SECURED TO/ROUTED ON TOP OF UNISTRUT AND NOT DIRECTLY ON THE FLOOR. DO NOT ANCHOR UNISTRUT TO THE EXISTING FLOORING. COORDINATE POWER AND DATA OUTLET LOCATIONS WITH OTHER TRADES.

J. REMOVE EXISTING LIGHT FIXTURES ABOVE NEW KITCHEN EXTENSION. MODIFY EXISTING WIRING TO MAINTAIN REMAINING FIXTURE OPERATION.

K. HARDWIRE KITCHEN EQUIPMENT TO LOCAL ON/OFF SWITCH. TYPICAL.

L. SURFACE MOUNT FIXTURES ON TEMPORARY KITCHEN CEILING. TYPICAL.

M. WIRE TEMPORARY KITCHEN FAN TO LOCAL LIGHTING CIRCUIT AND CONTROLS. FAN SHALL BE ON/OFF WITH LIGHTS.

N. EXISTING EXTERIOR LIGHT FIXTURES TO BE REMOVED.

O. PROVIDE NEW FIRE ALARM DEVICES AS PART OF THE TEMPORARY KITCHEN BUILDOUT.

P. PROVIDE NEW TEMPORARY LIGHT FIXTURES IN THE EXISTING CAFETERIA CEILING ABOVE THE SERVING LINE. COORDINATE LOCATIONS WITH TEMPORARY SERVING LINE AND EXISTING CONDITIONS. CONNECT TO EXISTING LIGHTING CONTROLS/CIRCUIT. ALL TEMPORARY LIGHT FIXTURES SHALL BE REMOVED AT THE END OF KITCHEN RENOVATION AND OFFERED TO THE OWNER AS SALVAGE. PROVIDE REPLACEMENT CEILING TILES.

Q. PROVIDE IN–USE WEATHERPROOF COVER FOR RECEPTACLE.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

**S**

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD.
SUGAR LAND, TX 77479

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING


ELECTRICAL DEMO AND TEMP PLANS

s-ED.100


STANTON ENGINEERING GROUP
INFO@STANTON-TX.COM | (713) 300–6080


TEXAS ENGINEERING REG. NO. F–23111 © 2025 ALL RIGHTS RESERVED


12800 W. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77043




1 TECHNOLOGY DEMOLITION FLOOR PLAN
s-TD201 1/4" = 1'-0"

**TECHNOLOGY DEMOLITION PLAN GENERAL NOTES**

1. ALL DATA, VOICE, VIDEO AND SECURITY SYSTEMS SHALL REMAIN OPERATIONAL AT ALL TIMES DURING BUSINESS HOURS UNLESS OTHERWISE NOTED. ANY SYSTEM DOWNTIME SHALL BE SCHEDULED WITH THE ARCHITECT/ENGINEER AND OWNER AT LEAST TEN (10) WORKING DAYS IN ADVANCE. CONTRACTOR SHALL DEVELOP A PHASING PLAN AND SCHEDULE OF ANY REQUIRED SYSTEM DOWNTIME FOR REVIEW AND APPROVAL BY THE ARCHITECT/ENGINEER AND OWNER PRIOR TO ANY CONSTRUCTION ACTIVITIES.
2. OWNER SHALL BE RESPONSIBLE FOR POWER DOWN AND START-UP OF ALL DATA, VOICE, VIDEO AND SECURITY SYSTEMS. CONTRACTOR SHALL COORDINATE WITH THE ARCHITECT/ENGINEER AND OWNER AND PROVIDE A MINIMUM OF TEN (10) WORKING DAYS NOTICE FOR SCHEDULING OF ANY REQUIRED DOWNTIME.
3. ALL EXISTING WIRELESS ACCESS POINTS ARE TO BE REMOVED AND RETURNED TO OWNER. CONTRACTOR SHALL RE-INSTALL ALL EXISTING AND NEW WIRELESS ACCESS POINTS AT COMPLETION OF PROJECT.
4. COORDINATE REMOVAL OF EXISTING CAMERA WITH OWNER/ARCHITECT DURING CONSTRUCTION.

**TECHNOLOGY DEMOLITION PLAN KEYED NOTES**

**NOT ALL KEYED BELOW APPLY TO THIS SHEET**

(1) EXISTING DATA/VOICE/WIRELESS ACCESS POINT OUTLET TO BE REMOVED. CONTRACTOR SHALL REMOVE AND DISPOSE OF ALL 4-PAIR CABLES AND WORKSTATION CONNECTING HARDWARE TERMINATED AT THIS LOCATION. IF LOCATION IS NOT RE-USED, CONTRACTOR SHALL SUPPLY AND INSTALL BLANK COVER. CONTRACTOR IS TO REMOVE EACH CABLE TO BE DEMOLISHED FROM THE PATCH PANEL OR TERMINATION BLOCK IN THE TELECOMMUNICATIONS ROOM. REMOVE THE ENTIRE LENGTH OF THE CABLE AND THE CORRESPONDING MODULAR CONNECTOR, FACEPLATE AND ACCESSORIES. NO ABANDONED CABLING IS TO BE LEFT ABOVE CEILING. CONTRACTOR SHALL INSTALL ALL EXISTING AND NEW WIRELESS ACCESS POINTS AT COMPLETION OF PROJECT.

(2) EXISTING VIDEO SURVEILLANCE CAMERA. CONTRACTOR SHALL REMOVE AND RETURN TO OWNER.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD
SUGAR LAND, TX 774

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD


07/18/2025


MWA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY DEMOLITION FLOOR PLAN

SHEET NO.
s-TD201




2 ENLARGED SITE PLAN
SCALE: 1/8" = 1'-0"

NUMBERED NOTES: FOR 2/a-A.101

1. COOLER RENTAL UNIT; APPROX. 8' X 10' BASIS OF DESIGN: MODEL DT810 BY POLAR LEASING REFRIGERATION RENTAL
2. INCLUDE OPTIONAL DIAMOND TREAD RAMP SUITABLE FOR WHEELED TRAFFIC
3. LOCATION SHOWN IS SUBJECT TO OWNER APPROX. LOCATION MUST NOT BLOCK DELIVERIES TO REAR DOOR, MUST BE WITH 10' OF AREA DRAIN, AND WITHIN 100' OF ELECTRICAL POWER.
4. CONTRACTOR SHALL SCAN PAVING FOR BURIED UTILITIES BEFOR CUTTING CONC.




1 SITE PLAN
SCALE: 1" = 30'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD
SUGAR LAND, TX 77479

SEAL
REGISTERED ARCHITECT
STATE OF TEXAS
7/15/2025



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING


SITE PLAN

s-A.101


F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\S-Settlers Way ES\s-A.101 SITE PLAN.dwg Jul 23, 2025 - 4:46pm




## 10 CANOPY DETAILS
3/4" = 1'-0"




## 11 CANOPY PLAN
3/4" = 1'-0"





## 12 CANOPY SECTION
3/4" = 1'-0"

NOTES:
1. SAW CUT AND REMOVE EXISTING SLAB AND FLOOR FINISHES AS REQUIRED TO INSTALL NEW PLUMBING LINES, FLOOR DRAINS, FIXTURES, OR ELECTRICAL ITEMS.
2. SHADED AREA REPRESENTS APPROXIMATE SAWCUT AREAS NEEDED FOR PLUMBING ALTERATIONS.
3. CONTRACTOR TO DETERMINE EXTENT OF CONCRETE SLAB SAW CUTTING AS REQUIRED FOR ALL UTILITIES REQUIRED FOR THIS PROJECT.
4. SPLICE NEW REINFORCING BARS AND DOWELED INTO EXISTING CONCRETE, AND PROVIDE NEW VAPOR RETARDER AND WATERSTOPS, AND PATCH W/ 3000 PSI CONCRETE AFTER INSTALLATION OF UTILITIES AND FIXTURES.
5. PREPARE CONCRETE TO RECEIVE NEW FINISH.

HATCHED AREA REPRESENTS APPROXIMATE AREA THAT WILL NEED TO BE EXCAVATED IN ORDER TO MAKE PLUMBING ALTERATIONS OUTSIDE THE BUILDING. CONTRACTOR TO REMOVE CONCRETE WALKS, PAVING, AND EXCAVATE AS REQUIRED IN ORDER TO INSTALL NEW PLUMBING. BACK FILL AND RESTORE AFFECTED AREAS. REFER TO CIVIL DETAILS.

SAW CUT AND REMOVE EXISTING SLAB AND FLOOR FINISHES AS REQUIRED TO INSTALL NEW PLUMBING LINES, FLOOR DRAINS, FIXTURES, OR ELECTRICAL ITEMS. SPLICE NEW REINFORCING BARS AND DOWELED INTO EXISTING CONCRETE, AND PROVIDE NEW VAPOR RETARDER AND WATERSTOPS, AND PATCH W/ 3000 PSI CONCRETE AFTER INSTALLATION OF UTILITIES AND FIXTURES. PREPARE CONCRETE TO RECEIVE NEW FINISH.

SHADED AREA REPRESENTS APPROXIMATE SAWCUT AREAS NEEDED FOR PLUMBING ALTERATIONS. CONTRACTOR TO DETERMINE EXTENT OF CONCRETE SLAB SAW CUTTING AS REQUIRED FOR ALL PLUMBING REQUIRED FOR THIS PROJECT.




## 1 SLAB DEPRESSION PLAN
SCALE: 1/4" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD
SUGAR LAND, TX 77479

SEAL
REGISTERED ARCHITECT
ROBERT L. WILLIAMS
22651
STATE OF TEXAS
7/15/2025


ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

SLAB DIMENSION CONTROL PLAN

s-A.200

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\S-Settlers Way ES\s-A.200 SLAB DIMENSION CONTROL PLAN.dwg Jul 23, 2025 - 4:47pm

SCOPE OF WORK: KITCHEN REPLACEMENT OF FLOOR, WALL, AND CEILING FINISHES, AS WELL AS, REPLACEMENT OF KITCHEN EQUIPMENT. PROVIDE ADDITIONAL KITCHEN STORAGE FOR CEP. UPGRADE TO BACK DOOR DELIVERY AREA.

**ADOPTED CODES W/ AMENDMENTS OF**

**CITY OF MISSOURI CITY, TX**

- 2021 INTERNATIONAL BUILDING CODE
- 2021 INTERNATIONAL RESIDENTIAL CODE
- 2021 INTERNATIONAL PLUMBING CODE
- 2021 INTERNATIONAL MECHANICAL CODE
- 2023 NATIONAL ELECTRIC CODE NFPA 70
- 2021 INTERNATIONAL ENERGY CONSERVATION CODE
- 2021 INTERNATIONAL FUEL GAS CODE
- 2021 INTERNATIONAL FIRE CODE

**INTERIOR WALL AND CEILING FINISH REQUIREMENTS BY OCCUPANCY E:**

**NON SPRINKLED**

INTERIOR EXIT STAIRWAYS AND RAMPS AND EXIT PASSAGEWAYS **A**

CORRIDORS AND ENCLOSURE FOR EXIT ACCESS STAIRWAYS AND RAMPS **B**

ROOMS AND ENCLOSED SPACES **C**

**FLOORING SHALL BE CLASS II**

**2021 INTERNATIONAL EXISTING BUILDING CODE**

301.3.1 PRESCRIPTIVE COMPLIANCE METHOD. REPAIRS, ALTERATIONS, ADDITIONS AND CHANGES OF OCCUPANCY COMPLYING WITH CHAPTER FIVE OF THIS CODE IN BUILDINGS COMPLYING WITH THE INTERNATIONAL FIRE CODE SHALL BE CONSIDERED IN COMPLIANCE WITH THE PROVISIONS OF THIS CODE.

302.3 EXISTING MATERIALS. MATERIALS ALREADY IN USE IN A BUILDING IN COMPLIANCE WITH REQUIREMENTS OR APPROVALS IN EFFECT AT THE TIME OF THEIR ERECTION OR INSTALLATION SHALL BE PERMITTED TO REMAIN IN USE UNLESS DETERMINED BY THE BUILDING OFFICIAL TO BE UNSAFE .

302.4 NEW AND REPLACEMENT MATERIALS. EXCEPT AS OTHERWISE REQUIRED OR PERMITTED BY THIS CODE, MATERIALS PERMITTED BY THE APPLICABLE CODE FOR NEW CONSTRUCTION SHALL BE USED. LIKE MATERIALS SHALL BE PERMITTED FOR REPAIRS AND ALTERATIONS, PROVIDED THAT NO UNSAFE CONDITION IS CREATED. HAZARDOUS MATERIALS SHALL NOT BE USED WHERE THE CODE FOR NEW CONSTRUCTION WOULD NOT PERMIT THEIR USE IN BUILDINGS OF SIMILAR OCCUPANCY, PURPOSE AND LOCATION.

**ALTERATION - LEVEL 1** INCLUDE THE REMOVAL AND REPLACEMENT OR THE COVERING OF EXISTING MATERIALS, ELEMENTS, EQUIPMENT, OR FIXTURES USING NEW MATERIALS, ELEMENTS, EQUIPMENT, OR FIXTURES THAT SERVE THE SAME PURPOSE.

**ALTERATION - LEVEL 2** INCLUDE THE ADDITION OR ELIMINATION OF ANY DOOR OR WINDOW, THE RECONFIGURATION OR EXTENSION OF ANY SYSTEM, OR THE INSTALLATION OF ANY ADDITIONAL EQUIPMENT, AND SHALL APPLY WHERE THE WORK IS EQUAL TO OR LESS THAN 50% OF THE BUILDING AREA.

THIS BUILDING'S CONSTRUCTION IS TYPE IIB.

THIS BUILDING'S OCCUPANCY IS E.

THIS BUILDING'S IS NON-SPRINKLED.

THERE WILL NOT BE ANY MODIFICATIONS TO THE HOOD SYSTEMS IN THE KITCHENS BEYOND REPLACEMENT OF MOTOR FOR LIKE KIND IF NEEDED.


THE BUILDING WILL NOT HAVE ADDITIONAL SQUARE FOOTAGE AS PART OF THE WORK.

NEW CONSTRUCTION ELEMENTS, COMPONENTS, SYSTEMS AND SPACES SHALL COMPLY WITH THE REQUIREMENTS OF THE INTERNATIONAL BUILDING CODES

## RESPONSIBILITY MATRIX

| ITEM | | | | CONTRACTOR RESPONSIBILITY | | OWNER RESPONSIBILITY | | NOTES |
|---|---|---|---|---|---|---|---|---|
| **EQUIPMENT** | **MAKE** | **MODEL** | **BASIS OF DESIGN** | FURNISHED | INSTALL | FURNISHED | INSTALL | |
| MARKERBOARD | | | MUST BE MAGNETIC, LOW GLOS, WHITE. NO GREY ALLOWED. 5' X 10' | X | X | | | |
| MOTORIZED FOLDING PARTITION | | | TOP SUPPORTED AND CONTINUOUSLY HINGED. MADE OF 3" THICK STEEL WITH FULL SOUND SEALS. THEY FEATURE AUTOMATIC FLOOR SEALS THAT DEPLOY WHEN POSITIONED. MARKERBOARD FINISHES ARE SUGGESTED FOR CLASSROOM USE. LARGE PARTITIONS SHOULD BE ELECTRONICALLY OPERATED, INTEGRATED WITH THE SCHOOL SYSTEM, AND SUPPORTED FROM THE BOTTOM IN A RECESSED MANNER. | X | X | | | |
| PAPER TOWEL DISPENSER | | | 1 PAPER TOWEL DISPENSER PER SINK | | | X | X | |
| SOAP DISPENSER | | | 1 SOAP DISPENSER PER SINK | | | X | X | |
| COMMERCIAL WASHER | GE | GTWI750CPLDG | STAINLESS STEEL; ASTM A898, TYPE 304 WITH NUMBER 4 FINISH; ELECTRIC; 480 VOLTS, 40 LB CAPACITY, MINIMUM EXTRACTOR FORCE 140 G FACTOR. | X | X | | | |
| COMMERCIAL DRYER | GE | GTD75ECPLDG | HEAVY DUTY EMBOSSED STEEL WITH ELECTROSTATICALLY APPLIED BACKED ENAMEL FINISH. | X | X | | | |
| MOP RACK | | | BROOM AND MOP HANGGERS FOR A MINIMUM OF TWELVE (12) HANGERS TO BE PROVIDED IN THE CONTRACT | X | X | | | |
| KITCHEN MENU SYSTEM DEVICE | | | RE: J-QF1.0 SF EQUIPMENT PLAN | X | X | | | REFERED TO IT DRAWINGS |
| LOCKERS | | | 12"W X 15"D, 2 TIER, 60" HIGH. 16 GA. DOOR WITH 20GA. BODY | X | X | | | |
| MIRROR | | | TOP EDGE 74 INCHES (1880 MM) MINIMUM ABOVE THE FINISH FLOOR OR GROUND & BOTTOM EDGE OF THE REFLECTING SURFACE 40 INCHES (1015 MM) MAXIMUM | X | X | | | |
| GRAB BARS | | | AS REQUIRED BY ADA | X | X | | | |
| HOOKS | | | J-HOOKS | X | X | | | |
| TIME CLOCK | KRONOS | | EXISTING UNIT | | X | | | COORDINATE HEIGHT, DATA, POWER AND ROUGH-IN REQUIREMENTS WITH FIISD IT. REMOVE, PROTECT & REINSTALL EXISTITING TIME CLOCK. |
| **KITCHEN OFFICE FURNITURE** | | | | | | | | |
| AUSTIN PARKWAY ES | | | | | | X | X | |
| PECAN GROVE ES | | | | | | X | X | |
| SETTLERS WAY ES | | | | | | X | X | |
| SUGAR MILL ES | | | | | | X | X | |
| HIGHLANDS ES | | | | | | X | X | |
| PALMER ES | | | | | | X | X | |
| HUNTERS GLEN ES | | | | | | X | X | |

# 2 CODE ANALYSIS




1 OVERALL FLOOR PLAN
SCALE: 1/16" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT

SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD
SUGAR LAND, TX 77479

SEAL

REGISTERED ARCHITECT
ANNE A. SWINNEA
22651
STATE OF TEXAS

7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING


OVERALL FLOOR PLAN

s-A.201

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\S-Settlers Way ES\s-A.201 FLOOR PLAN.dwg, Jul 23, 2025 - 4:47pm

## DOOR SCHEDULE

| DOOR # | DOOR WIDTH | DOOR HEIGHT | DOOR TYPE | DOOR MATERIAL | DOOR FINISH | FIRE RATING | FRAME THICKNESS | FRAME FINISH | KEY | HARDWARE | DETAILS | | | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | | SILL | JAMB | HEAD | |
| A005 | 3'-0" | X 7'-0" | SF4 | SOLID CORE | P LAM | NR | 4 1/2" | ANOD AL | | 103 | | 22/A00-01 | 16/A00-01 | |
| A006 | 3'-0" | X 7'-0" | SF4 | SOLID CORE | P LAM | NR | 4 1/2" | ANOD AL | | 501 | | 22/A00-01 | 16/A00-01 | |
| A007 | 3'-0" | X 7'-0" | SF4 | SOLID CORE | P LAM | NR | 4 1/2" | ANOD AL | | 341 | | 22/A00-01 | 16/A00-01 | |
| A008 | 3'-0" | X 7'-0" | SF4 | SOLID CORE | P LAM | NR | 4 1/2" | ANOD AL | | 501C | | 22/A00-01 | 16/A00-01 | |
| A012 | 4'-0" | X 7'-0" | HM1 | H.M. | PAINT | NR | 6" | PAINT HM | | 715V | 21/A00-01 | 04/A00-01 | 04/A00-01 | |
| 109A | 3'-0" | X 7'-0" | SF4 | SOLID CORE | P LAM | NR | 4 1/2" | ANOD AL | | 501H | | 22/A00-01 | 16/A00-01 | |
| 109B | 3'-0" | X 7'-0" | SF1 | ALUM/GLASS | ANOD AL | NR | 4 1/2" | ANOD AL | | C201AH | 18/A00-01 | 10&11/A00-01 | 23&24/A00-01 | CARD READER, CLOSER, BUZZER |
| 109C | 3'-0" | X 7'-0" | SF1 | ALUM/GLASS | ANOD AL | NR | 4 1/2" | ANOD AL | | C201AH | 18/A00-01 | 10&11/A00-01 | 23&24/A00-01 | CARD READER, CLOSER, BUZZER |
| 109D | 3'-0" | X 7'-0" | SF4 | SOLID CORE | P LAM | NR | 4 1/2" | ANOD AL | | 501H | | 22/A00-01 | 16/A00-01 | |




NEW DOOR AND FRAME HOLLOW METAL DOOR NEW H.M. FRAME

NEW DOOR AND FRAME HOLLOW METAL DOOR NEW H.M. FRAME

NEW DOOR AND FRAME S. C. WOOD DOOR ALUM. FRAME

NEW DOOR AND FRAME ALUM/GLASS ALUM. FRAME

## 2 DOOR SCHEDULE

## FLOOR PLAN - GENERAL NOTES

1. REFER TO SHEET FOR GENERAL NOTES. GENERAL NOTES APPLY TO ALL SCHOOL KITCHENS.
2. REFER TO SHEET FOR PARTITION TYPES.
3. EXIXSTING EXPOSED CONDUITS AND DATA CABLING IN WIREMOLD TO BE ROUTED INSIDE WALLS (EXCEPT AT WAREWASH AREA BELOW TABLE HEIGHT AND DRY STORAGE ROOMS), PATCH AND REPAIR AS REQUIRED TO ACHIEVE SMOOTH CLEAN WALL SURFACE.

## PARTITION LEGEND

- EXISTING CMU PARTITION
- NEW CMU SCHEDULED PARTITION
- EXISTING METAL PARTITION
- NEW FRAMED SCHEDULED PARTITION

## 3 FLOOR PLAN NOTES

## FLOOR PLAN - KEYED NOTES

(NOT ALL NOTES USED ON EACH SHEET)

01 PROVIDE NEW MOP SINK UTILITY SHELF
RE: PLUMBING FOR MOP SINK
RE: SPEC 10 28 00 FOR UTILITY SHELF

02 REMOVE, STORE & REPLACE WALL MOUNTED FIRE EXTINGUISHER

03 PROVIDE NEW WALL MOUNTED FIRE EXTINGUISHER
RE: SPEC SECTIONS 10 44 13

04 PROVIDE NEW LOCKERS
RE: SPEC 10 51 13.

05 PROVIDE WASHER AND DRYER
RE: SPEC 11 45 20

06 REMOVE, PROTECT & REINSTALL WALL MOUNTED CLOCK.

07 PROVIDE CONDENSING UNIT
FOR WALK-IN COOLER/FREEZER
RE: MECHANICAL AND SPEC 11 40 00


08 PROVIDE POWER AND DATA FOR MENU BOARD.
RE: ELECTRICAL, TECHNOLOGY DRAWINGS & FOOD SERVICE.


09 PROVIDE P-LAM SHELVING
REFER TO DETAIL FOR BRACKET SUPPORT

10 FURNITURE & NON FOOD SVE EQUIPMENT RETURN TO OWNER FO STORAGE

11 INSPECT & SREVICE TOLLING COUNTER DOORS. RETURN TO LIKE NEW CONDITION.


12 COMMERCIAL CLOSED WASHER 40LB CAPACITY .
COMMERCIAL CLOSED DRYER 55LB CAPACITY.
BASIS OF DESIGN: WASHER; SPEED QUEEN SYN040
DRYER; SPEED QUEEN ST055.
REFER TO ELECTRICAL & PLUMBING FOR CONNECTIONS.





## 1 KITCHEN PLAN

SCALE: 1/16" = 1'-0"





## 4 MAKERBOARD ELEVATION

SCALE: 1/2"=1'-0"





## 5 RAMP @ REAR DOOR


SCALE: 3/16"=1'-0"




## A

SCALE: 1/2"=1'-0"




ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD
SUGAR LAND, TX 77479

SEAL

REGISTERED ARCHITECT
ROY T. MOORE
43651
STATE OF TEXAS

7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

KITCHEN PLAN

s-A.301

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\S-Settlers Way ES\s-A.301 KITCHEN PLAN.dwg, Jul 30, 2025 - 9:47am

## TEMPORARY KITCHEN FLOOR PLAN KEYED NOTES 05/A-A03-02

01 PROVIDE & INSTALL 555 SF OF RAM BOARD TO PROTECT EXISTING FLOORING. REMOVE AFTER CONSTRUCTION IS COMPLETE. CONTRACTOR MUST REPAIR FLOORING DAMAGED DURING CONSTRUCTION.

02 PROVIDE SCHEDULED PARTITIONS. BUILD PARTITIONS ON TOP OF RAM BOARD. DO NOT ATTACH PARTITIONS TO FLOOR.


03 ATTACH PARTITIONS TO EXISTING WALL. REPAIR WALL TO MATCH EXISTING AFTER CONSTRUCTION IS COMPLETE.

## TEMPORARY KITCHEN RCP KEYED NOTES 03/A-A03-02

04 ALL NEW SCHEDULED PARTITIONS AND CEILINGS FOR TEMPORARY STORAGE LAYOUT TO BE EPOXY PAINTED SW 7014 EIDER WHITE WITH SPECIFIED 4" RUBBER BASE. REMOVE WHEN CONSTRUCTION IS COMPLETED.


05 MOUNT TEMPORARY FLUORESCENT LIGHTS TO TEMPORARY CEILING.

## 3 KEYED NOTES





## 4 TEMPORARY LAYOUT SECTION

SCALE: 1"=1'-0"




## 1 KITCHEN PLAN

SCALE: 1/4" = 1'-0"




## 2 TEMPORARY KITCHEN FLOOR PLAN

SCALE: 1/4" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD
SUGAR LAND, TX 77479

SEAL
REGISTERED ARCHITECT
ROBERT A. MEYER
22451
STATE OF TEXAS
7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

TEMPORARY KITCHEN LAYOUT
s-A.302

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\S-Settlers Way ES\s-A.302 TEMPORARY KITCHEN LAYOUT.dwg Jul 23, 2025 - 4:48pm

## RCP - GENERAL NOTES


1. CEILING GRID SHALL BE INSTALLED TO MATCH EXISTING GRID'S POINT OF ORIGIN. THIS WILL REDUCE NEED TO RE-LOCATE ABOVE CEILING DUCTS, SPRINKLER PIPING AND OTHER SUPPORT SYSTEMS.
2. REFER TO SHEET A00-01 FOR GENERAL NOTES. GENERAL NOTES APPLY TO ALL SEVEN SCHOOL KITCHEN REMODELS.
3. LIGHTING LEVELS SHOULD BE 50 FC IN PREPARATION AREAS, WARE WASH AND SERVING LINES, OR MEET MINIMUM HEALTH CODE LEVELS, WHICHEVER ITS GREATER. SEE MEP PLANS
4. REPLACE HVAC DEVICES. REPLACE LIGHTING WITH 24"x24" LED LAY IN LIGHT AS SCHEDULED IN ELECTRICAL PLANS.
5. REFER TO MECHANICAL, ELECTRICAL SHEETS FOR DEVICE SCHEDULES.

## RCP - NUMBERED NOTES

01 PROVIDE 30"x30" MIN. ACCESS HATCH IN SOFFIT CENTERED ON MOTOR.


02 AFTER LOWERING THE NEW POWER RETRACTION SYSTEM. REPAIR AND PAINT SOFFITS AND SIDWALLS OF FURR TO MATCH EXISTING.

## 2 RCP GENERAL NOTES




## 3 FOOD SERVICE AREA ELEVATION

SCALE: 3/16" = 1'-0"




## 1 REFLECTED CEILING PLAN

SCALE: 1/4" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT

SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD
SUGAR LAND, TX 77479

SEAL
REGISTERED ARCHITECT
ANIL K. KHANDHADIA
22651
STATE OF TEXAS
7/15/2025



ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING


REFLECTED CEILING PLAN

s-A.401


F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\S-Settlers Way ES\s-A.401 REFLECTED CEILING PLAN.dwg Jul 23, 2025 - 4:48pm





## 3 MOPSINK ELEVATIONS
SCALE: 1/4"=1'-0"




## 12 4
SCALE: 3"=1'-0"




TYPE B
KITCHEN RESTROOM SIGNAGE

## 7 ROOM SIGNAGE
SCALE: 6"=1'-0"


## PAINT COLOR SCHEDULE
UNLESS OTHERWISE INDICATED FIELD COLOR IS PT-1 (SW 7014 EIDER WHITE)

SW 7014 EIDER WHITE (EPOXY PAINT)


## WALL TILE
CERAMIC WALL TILE (WT-1)
REFER TO TILE PATTERN AT SERVING AND RESTROOM
FIELD WALL TILE: DALTILE RITTENHOUSE SQUARE K175 BISCUIT (3X6)

A — PROVIDE ROOM SIGN TO REPLACE EXISTING. SEE LAYOUT FOR TYPE A OR TYPE B SIGN LOCATIONS.

## 2 FLOOR FINISH LEGEND





## 5 FLOOR TRANSITION THRESHOLD
SCALE: 3"=1'-0"





## 1 FINISH FLOOR PLAN
SCALE: 1/4" = 1'-0"

ALL FINISHED NOT DENOTED IN DRAWINGS SHALL BE SELECTED DURING THE SUBMITTAL PROCESS





## 8 RR ELEVATIONS
SCALE: 1/4"=1'-0"





WALL TILE PATTERN - RESTROOM


## 6 WALL TILE PATTERN
SCALE: 1/4"=1'-0"




## 9 UTILITY ELEVATIONS
SCALE: 1/4"=1'-0"




## 10 STOREFRONT ELEVATIONS
SCALE: 1/4"=1'-0"




## 11 STOREFRONT SECTION
SCALE: 1/2"=1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD
SUGAR LAND, TX 77479

SEAL
REGISTERED ARCHITECT
MICHAEL WILLIAM ANDERSON
42651
STATE OF TEXAS
7/15/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

FINISH FLOOR PLAN

s-A.501

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\S-Settlers Way ES\s-A.501 FINISH FLOOR PLAN.dwg Jul 28, 2025 - 6:09pm

1. AT WALLS THAT TERMINATE ABOVE CEILING, CONTRACTOR MAY CONTINUE METAL STUD FRAMED WALLS TO UNDERSIDE OF METAL DECK AND OMIT DIAGONAL BRACING IF HEIGHT DOES NOT EXCEED LIMITING HEIGHT OF METAL STUD AS INDICATED ON CHART BELOW.

2. PROVIDE INTERMEDIATE BRACING AT ALL PARTITIONS THAT EXCEED LIMITING HEIGHT OF METAL STUDS AS INDICATED ON CHART BELOW.

3. ALL BRACING SHALL BE AT STUD POINTS.


CMU PARTITION NOTES:

1. MATCH EXISTING CMU COURSING (TYP.):
   BRIARGATE ES (4" CMU STARTER COURSE)
   LAKE OLYMPIA MS (4" CMU STARTER COURSE)
   MISSION BEND ES (8" CMU STARTER COURSE)
   RIDGEMONT ES (8" CMU STARTER COURSE)
   TOWNEWEST ES (8" CMU STARTER COURSE)
2. PROVIDE CMU LINTELS FOR ALL OPENINGS IN INTERIOR CMU PARTITIONS. COORDINATE WITH STRUCTURAL.
3. PROVIDE A 3/4" SPACE BETWEEN TOP OF CMU AND STRUCTURE/DECK FOR POTENTIAL DEFLECTION. SEAL WITH APPROPRIATE CAULK.
4. REFER TO FINISH SCHEDULES FOR CERAMIC TILE LOCATIONS.


GYPSUM WALLBOARD PARTITION NOTES:

1. ALL METAL STUDS PARTITIONS ARE 25 GAUGE METAL STUDS AT 16" O.C. UNLESS OTHERWISE NOTED. IF THE LIMITING HEIGHT FOR A PARTITION TYPE IS EXCEEDED, INCREASE SIZE AND/OR GAUGE OF METAL STUDS AS INDICATED ON "LIMITING HEIGHT OF METAL STUDS" TABLE. NOTIFY THE ARCHITECT PRIOR TO INSTALLATION.


| LIMITING HEIGHT OF METAL STUDS | | | |
|---|---|---|---|
| STUD SIZE | SPACING | 25 GA. | 20 GA. |
| 2-1/2" | 16" | 11'-3" | 12'-10" |
| 3-5/8" | 16" | 14'-4" | 16'-5" |
| 6" | 16" | 19'-9" | 24'-6" |





PARTITION A
SCALE: 1-1/2" = 1'-0"





PARTITION B1
SCALE: 1-1/2" = 1'-0"





PARTITION B2
SCALE: 1-1/2" = 1'-0"




PARTITION B3
SCALE: 1-1/2" = 1'-0"




PARTITION B4
SCALE: 1-1/2" = 1'-0"




PARTITION B5
SCALE: 1-1/2" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD
SUGAR LAND, TX 77479

SEAL

REGISTERED ARCHITECT
KEITH A. MAGNUSON
#29051
STATE OF TEXAS

7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

PARTITION SCHEDULE

s-A.502

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\s-A.502 PARTITION SCHEDULE.dwg Jul 30, 2025 - 9:50am

## GENERAL NOTES

1. ALL CONCRETE SHALL TEST 4000 PSI AT 28 DAYS.
2. ALL CONCRETE REINFORCING BARS SHALL CONFORM TO ASTM A615 GRADE 60.
3. DETAILING AND FABRICATION OF CONCRETE REINFORCEMENT AND ACCESSORIES SHALL BE IN ACCORDANCE WITH ACI-315 LATEST EDITION.
4. LAP ALL CONTINUOUS REINFORCING BARS 50 DIAMETERS AT SPLICES, TEES, AND CORNERS.
5. THE USE OF HEAT TO FACILITATE THE BENDING OF REINFORCING BARS WILL NOT BE PERMITTED.
6. NO ENGINEERING DRAWING MAY BE REPRODUCED FOR USE AS SHOP DRAWINGS.
7. CONTRACTOR SHALL COORDINATE ALL LOCATIONS OF ALL ANCHOR BOLTS AND OPENINGS FOR MECHANICAL, PIPING, AND ELECTRICAL EQUIPMENT WITH THE RESPECTIVE ENGINEERING AND VENDOR DRAWINGS.

## SLAB NOTE


4" CONC. SLAB ON 10 MIL POLY FILM ON 2" MAX. SAND FILL. REINFORCE WITH #3 @ 15"c.c. E.W. IN CENTER OF SLAB.

## SLAB SIDEWALK SLAB NOTE

4" CONC. SLAB ON 2" MAX. SAND FILL. REINF. W/ #3 @ 18"c.c. IN CENTER OF SLAB.

## GEOTECHNICAL NOTE:

ALLOWABLE BEARING CAPACITY IS ASSUMED TO BE 1500 PSF AND SHALL BE CONFIRMED PRIOR TO CONSTRUCTION.




## FOUNDATION PLAN

SCALE: 1/4"=1'-0"

## FIELD VERIFICATION NOTE

1. CONTRACTOR SHALL VERIFY ALL DIMENSIONS PRIOR TO FABRICATION OR CONSTRUCTION.
2. CONTRACTOR SHALL VERIFY AND NOTIFY ENGINEER OF EXISTING CONDITIONS IN NEED OF REVIEW AND POSSIBLE MODIFICATION PRIOR TO FABRICATION.

ISSUE:

| | |
|---|---|
| 03/07/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD
SUGAR LAND, TX 77479


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079






*July 17, 2025*


STANLEY SPURLING & HAMILTON, INC.
50 Years
Consulting Engineering Services
T.B.P.E. Registration # F-000175
www.sshinc.net
3301 Edloe Street, Suite 200 Houston, Texas 77027 Tel 713-776-9433
E-MAIL: info@sshinc.net | 0002-0256



PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

KITCHEN PLAN


S1





1 SECTION
SCALE: 3/4"=1'-0"





2 SECTION
SCALE: 3/4"=1'-0"




3 SECTION
SCALE: 3/4"=1'-0"




4 SECTION
SCALE: 3/4"=1'-0"




## MIN. REBAR LAP SCHEDULE FOR f'm = 1,500 psi

| BAR SIZE | 6" CMU | 8" CMU | 10" CMU | 12" CMU |
|---|---|---|---|---|
| #3 | 12" | 12" | 12" | 12" |
| #4 | 20" | 15" | 12" | 12" |
| #5 | 32" | 23" | 18" | 15" |
| #6 | 54" | 43" | 34" | 28" |
| #7 | NA | 60" | 46" | 38" |
| #8 | NA | 72" | 71" | 57" |
| #9 | NA | NA | 82" | 74" |

## CONCRETE MASONRY NOTES

1. CONCRETE MASONRY UNITS AND CONSTRUCTION TO BE PER "NATIONAL CONCRETE MASONRY ASSOCIATION" RECOMMENDATIONS (WHERE NOT COVERED BY THE LOCAL BUILDING CODE).
2. ALL MASONRY GROUT TO BE PER TABLE 1 (THIS SHEET); ALL MORTAR PER TABLE 2 (THIS SHEET).
3. FILL CELLS WITH GROUT AT VERTICAL REINFORCEMENT.
4. CAST-IN-ANCHORS EMBEDDED IN CONCRETE MASONRY SHALL EXTEND BEYOND REINFORCING 1" MIN.
5. COMPRESSIVE STRENGTH OF MASONRY SHALL BE 1500 PSI AT 28 DAYS.
6. CMU SHALL BE PLACED IN A RUNNING BOND PATTERN UNLESS SPECIFICALLY NOTED OTHERWISE ON THE PLANS.
7. CONTROL JOINTS SHALL HAVE NO HORIZONTAL REINFORCING THROUGH THE JOINT AND VERTICAL REINFORCING ON BOTH SIDES OF JOINT. CONTROL JOINTS SHALL BE UNGROUTED WITH A BACKER ROD AND SEALANT ON BOTH SIDES OF WALL.
8. BOND BEAMS AND REINFORCING SHALL BE CONTINUOUS AT CONTROL JOINT WITH BACKER ROD AND SEALANT CONTINUOUS WITH JOINT.

## CONCRETE BLOCK LINTEL SCHEDULE

| WALL THICKNESS \ MAXIMUM SPAN | 4'-6" | 9'-0" |
|---|---|---|
| 4" | GROUT 1 COURSE 1~#4 CONT. | #3 STIRRUPS @ 16" c.c. GROUT 2 COURSES 1~#4 CONT. |
| 6" & 8" & 12" | GROUT 1 COURSE 2~#5 CONT. | #3 STIRRUPS @ 16" c.c. GROUT 2 COURSES 2~#5 CONT. TOP & BOT. |

## TABLE 1. GROUT PROPORTIONS BY VOLUME

| TYPE | PARTS BY VOLUME OF PORTLAND CEMENT OR PORTLAND BLAST-FURNACE SLAG CEMENT | PARTS BY VOLUME OF HYDRATED LIME OR LIME PUTTY | AGGREGATE MEASURED IN DAMP, LOOSE CONDITION | |
|---|---|---|---|---|
| | | | FINE | COARSE |
| FINE GROUT (<4" WIDE CAVITY) | 1 | 0 TO 1/10 | 2¼ TO 3 TIMES THE SUM OF THE VOLUMES OF THE CEMENTITIOUS MATERIAL | |
| COARSE GROUT (>4" WIDE CAVITY) | 1 | 0 TO 1/10 | 2¼ TO 3 TIMES THE SUM OF THE VOLUMES OF THE CEMENTITIOUS MATERIAL | 1 TO 2 TIMES THE SUM OF THE VOLUMES OF THE CEMENTITIOUS MATERIAL |

## TABLE 2. MORTAR PROPORTIONS BY VOLUME


| MATERIAL | TYPE | PORTLAND CEMENT OR BLENDED CEMENT | MASONRY CEMENT | HYDRATED LIME OR LIME PUTTY | AGGREGATE RATIO (MEASURE IN DAMP, LOOSE CONDITION) |
|---|---|---|---|---|---|
| CEMENT LIME | S | 1 | .... | OVER ¼ TO ½ | NOT LESS THAN 2¼ & NOT MORE THAN 3 TIMES THE SUM OF THE SEPARATE VOLUMES OF CEMENTITIOUS MATERIALS |
| MASONRY/ CEMENT | S | 1/2 | 1 | .... | |

**NOTE: CONTROL JOINTS SHALL BE LOCATED AT THE FOLLOWING**

1. AT ALL CHANGES IN WALL HEIGHT.
2. AT ALL CHANGES IN WALL THICKNESS SUCH AS CHASES, COLUMNS OR PILASTERS.
3. AT (ABOVE) MOVEMENT JOINTS IN FOUNDATIONS AND FLOORS.
4. AT (BELOW) MOVEMENT JOINTS IN ROOFS AND FLOORS THAT BEAR ON A WALL.
5. ADJACENT TO CORNERS OF WALLS OR INTERSECTIONS WITHIN A DISTANCE OF ONE-HALF THE NORMAL CONTROL JOINT SPACING.
6. CONTROL JOINTS SHALL BE SPACED NO MORE THAN 25'-0" APART.
7. DO NOT PLACE CONTROL JOINT ABOVE OR BELOW OPENINGS.
8. CONTRACTOR SHALL PROVIDE A CONTROL JOINT PLAN PRIOR TO FABRICATION OR CONSTRUCTION.

## LOOSE LINTEL SCHEDULE

| SPAN | LINTEL | SPAN | LINTEL |
|---|---|---|---|
| 0' TO 6' | L3½x3½x¼ | 8' TO 9' | L5x3½x5/16 |
| 6' TO 7' | L4x3½"x¼ | 9' TO 10' | L6x3½x5/16 |
| 7' TO 8' | L4x3½x5/16 | 10' TO 12' | L7x4x⅜ |
| LOOSE LINTEL MIN. BEARING OF 8". | | | |




CONTRACTOR SHALL COVER ALL EXPOSED REBAR DURING CONSTRUCTION.

## TYPICAL ELEVATION OF CONCRETE MASONRY WALL AND NOTES

SCALE: N.T.S.

## TYPICAL REBAR CAP DETAIL

SCALE: N.T.S.

ISSUE:

| | |
|---|---|
| 03/07/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD
SUGAR LAND, TX 77479


ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


KEN STANLEY
69701
LICENSED PROFESSIONAL ENGINEER
STATE OF TEXAS
July 17, 2025


STANLEY SPURLING & HAMILTON, INC.
50 Years
Consulting Engineering Services
T.B.P.E. Registration # F-000175
www.sshinc.net
3301 Edloe Street, Suite 200 Houston, Texas 77027 Tel 713-776-9433
E-MAIL: info@sshinc.net | 0002-0256


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

SECTIONS AND TYPICAL DETAILS

S2

# REFER TO FOODSERVICE DESIGN PROFESSIONALS SPECIFICATIONS AND SUBSEQUENT SHEETS FOR ADDITIONAL COORDINATION INFORMATION

**EXISTING EQUIPMENT NOTES (IF EXISTING EQUIPMENT IS PROVIDED IN THIS PROJECT):**

1. EXISTING EQUIPMENT NOT SCHEDULED FOR RE-USE TO BE RELOCATED BY THE K.E.C. COORDINATE WITH OWNER FOR NEW LOCATION.
2. ALL UTILITIES NOT SCHEDULED FOR RE-USE TO BE CAPPED & COVERED BY REQUIRED DISCIPLINE.
3. K.E.C. TO VERIFY ALL EXISTING UTILITY LOCATIONS & COORDINATE WITH ALL EQUIPMENT AS REQUIRED.

8 EXISTING EQUIPMENT NOTES
NOT TO SCALE

**ARCHITECT TO VERIFY/COORDINATE THE AESTHETIC OPTIONS BELOW (FOOD SERVICE COLOR, MATERIAL, OR SIGNAGE SELECTIONS) IF THESE ITEMS ARE PROVIDED IN THIS PROJECT:**

1. COUNTERTOPS: STONE (STAINLESS STEEL IS PROVIDED UNLESS OTHERWISE SPECIFIED).
2. TRAY SLIDES: CORIAN OR STONE (STAINLESS STEEL IS PROVIDED UNLESS OTHERWISE SPECIFIED).
3. COUNTER FRONTS: CERAMIC TILE, 3 FORM, OR PLASTIC LAMINATE.
4. SNEEZE GUARDS: STONE INSETS.
5. GENERAL COLOR, MATERIAL AND GRAPHIC SELECTIONS:
   - A. DISPLAY AIR SCREEN MERCHANDISERS - COLOR SELECTION: POWDER COAT OR PLASTIC LAMINATE (S/S IS PROVIDED UNLESS OTHERWISE SPECIFIED).
   - B. BAKERY DISPLAY CASES - COLOR SELECTION: POWDER COAT OR PLASTIC LAMINATE (S/S IS PROVIDED UNLESS OTHERWISE SPECIFIED).
   - C. PASS THRU OR REACH IN HOLDING CABINETS - COLOR SELECTION: POWDER COAT (MFG.: TRUE) OR PLASTIC LAMINATE (MFG.: TRAULSEN) (S/S IS PROVIDED UNLESS OTHERWISE SPECIFIED).
   - D. HANGING HEAT LAMPS - TRACK AND FIXTURE COLOR SELECTION.
   - E. HEATED MERCHANDISERS.
   - F. PORTABLE GUIDE RAILS - STANCHION AND BELT COLOR SELECTION.
   - G. POPCORN MACHINE - SIGNAGE SELECTION.
   - H. BOTTLE COOLER - SIGNAGE SELECTION.
   - I. GRAPHICS PACKAGE INFORMATION.
   - J. HOT FOOD WELL COVERS.
6. ARCHITECT TO VERIFY/COORDINATE THE FINISHES BELOW:
   - A. WALLS: CERAMIC TILE, FLAT FRP, OR MOLDED FRP (SMOOTH, IMPERVIOUS, AND EASILY CLEANABLE AS APPROVED BY LOCAL JURISDICTION).
   - B. CEILINGS: REMOVABLE VINYL FACE TILE (SMOOTH, IMPERVIOUS, AND EASILY CLEANABLE AS APPROVED BY LOCAL JURISDICTION).
   - C. FLOORS: TILE, EPOXY, OR RUBBERIZED FLOORING SYSTEM (SMOOTH, IMPERVIOUS, EASILY CLEANABLE AND SLIP RESISTANT AS APPROVED BY LOCAL JURISDICTION) (COORDINATE FLOOR TILE TRANSITION AT SERVING LINES).
   - D. FLOORS: WALK-IN ASSEMBLY - EXTEND KITCHEN FLOOR FLUSH INTO WALK-IN ASSEMBLY WITH COVED BASE.
   - E. FURR DOWNS ABOVE SERVING COUNTERS.

5 ARCHITECTURAL COORDINATION NOTES
NOT TO SCALE

**CRITICAL NOTES:**

1. CONTRACTOR MUST COORDINATE AND VERIFY ALL DIMENSIONS WITH FOOD SERVICE EQUIPMENT SHOP DRAWINGS AND MANUFACTURER'S DATA. DIMENSIONS SHOWN ARE FOR DESIGN AND BIDDING PURPOSES ONLY.
2. WALK-IN ASSEMBLY DOORS MUST BE LEFT OPEN WHILE INTERIOR CONCRETE FLOOR CURES.
3. INSTALL PROTECTIVE COVER ON WALK-IN ASSEMBLY WALL PANELS BEFORE INSTALLING CONCRETE FLOORS AND CURBS.
4. REFER TO GENERAL SPECS - DIVISION 27 TO PROVIDE CONDUIT, DATA, AND INTERCONNECT THE PANIC ALARM INSIDE FREEZER TO THE BUILDING AUTOMATION SYSTEM FOR NOTIFICATION TO DISTRICT PERSONNEL IN THE EVENT OF STAFF ENTRAPMENT.
5. PIPING AND DRAINAGE SYSTEMS (SANITARY AND GREASE-LADEN). SYSTEMS MUST BE CLEANED AND FLUSHED BEFORE THE FINAL CONNECTION WITH FOOD SERVICE EQUIPMENT - CRITICAL (DIV. 22).

7 CRITICAL NOTES
NOT TO SCALE

**DIVISION 26 (ELECTRICAL) IS RESPONSIBLE FOR BUT NOT LIMITED TO:**

1. **DO NOT ROUGH IN FROM FDP DRAWINGS. REFER TO THE KITCHEN EQUIPMENT CONTRACTOR'S DIMENSIONED SHOP DRAWINGS. DIMENSIONS INDICATED ARE TO BE VERIFIED BY KITCHEN EQUIPMENT CONTRACTOR AND ADJUSTED AS REQUIRED BY EQUIPMENT AND FIELD CONDITIONS.**
2. SECTION 11 40 00 TO VERIFY UTILITY REQUIREMENTS OF ANY EXISTING EQUIPMENT.
3. ALL CONNECTIONS SHALL BE MADE FOLLOWING LOCAL CODES AND NATIONAL STANDARDS, EXCEPT WHERE PLANS AND SPECIFICATIONS EXCEED THOSE CODES AND STANDARDS.
4. VERIFY ALL ELECTRICAL REQUIREMENTS WITH ENGINEERING DRAWINGS.
5. ROUGH-IN AND FINAL CONNECTION OF ELECTRICAL SYSTEMS TO FOOD SERVICE EQUIPMENT, WALK-IN ASSEMBLIES, AND BETWEEN COMPONENTS (INCLUDING MATERIALS AND LABOR). ACCESSORIES PROVIDED LOOSE WITH FOOD SERVICE EQUIPMENT BY SECTION 11 40 00 TO BE FIELD INSTALLED BY DIVISION 26.
6. EMPTY EMT CONDUIT WITH PULL-WIRE AND WIDE-SWEEP BENDS FOR REFRIGERANT PIPING TO REMOTE FOOD SERVICE EQUIPMENT REFRIGERATION SYSTEMS.
7. EMPTY EMT CONDUIT WITH PULL-WIRE AND WIDE-SWEEP BENDS FOR INTERCONNECT CABLES BETWEEN LAN AND POS TERMINALS, CHANGE-MAKERS, PRE-CHECK UNITS, PRINTERS, CPUS, ETC. DIVISION 26 TO VERIFY WHERE THE CONDUIT IS TO RUN FOR POS SYSTEM (I.E., MANAGER'S OFFICE OR IDF ROOM).
8. EMPTY EMT CONDUIT WITH PULL-WIRE AND WIDE-SWEEP BENDS FOR FIRE SUPPRESSION SYSTEMS. INTERCONNECT FIRE PROTECTION SYSTEM TO PANEL BOX SHUNT TRIPS AND BUILDING ALARM.
9. WALK-IN LIGHT FIXTURE INSTALLATION (PROVIDED LOOSE BY SECTION 11 40 00) (IF WALK-IN IS PROVIDED IN THIS PROJECT).
10. TABLE LIMIT SWITCH INSTALLATION (PROVIDED LOOSE BY SECTION 11 40 00) (IF DISHMACHINE IS PROVIDED IN THIS PROJECT).
11. ELECTRICAL MATERIALS AND DEVICES (SHUNT-TRIP BREAKERS, SURGE PROTECTORS, LIGHTING CONTROL DEVICES, CONDUIT, WIRE, ETC.).
12. SWITCHES AND STAINLESS STEEL DISCONNECTS AS REQUIRED (PROVIDE, LOCATE, AND INSTALL – TO BE IN AN ACCESSIBLE LOCATION).
13. CHARGING STATIONS FOR FORKLIFTS, PALLET STACKERS, AND PALLET JACKS (SIZE, PROVIDE, LOCATE, AND INSTALL) (IF EQUIPMENT IS PROVIDED IN THIS PROJECT).
14. INTERCONNECTION BETWEEN CONDENSATE FAN AND DISHMACHINE CONTROL PANEL (IF EQUIPMENT IS PROVIDED IN THIS PROJECT).
15. INTERCONNECTION BETWEEN EXHAUST HOOD FANS AND SWITCH (IF EQUIPMENT IS PROVIDED IN THIS PROJECT).
16. INTERCONNECTION BETWEEN EXHAUST HOOD LIGHTS AND SWITCH (IF EQUIPMENT IS PROVIDED IN THIS PROJECT).
17. DOOR HEATERS, LIGHTS, COILS, AND PRESSURE RELIEF PORTS PRE-WIRED TO JUNCTION BOX AT TOP OF WALK-IN ASSEMBLIES (IF EQUIPMENT IS PROVIDED IN THIS PROJECT) PROVIDED BY SECTION 11 40 00. FINAL CONNECTION BY DIV. 26.
18. IF ANY ELECTRICAL ACCESSORIES, FITTINGS, AND CORD/PLUGS ARE PROVIDED LOOSE WITH EQUIPMENT BY 11 40 00, DIV.26 IS TO ATTACH TO EQUIPMENT AND PROVIDE FINAL CONNECTION.
19. PROVIDE WATERPROOF RECEPTACLES IN WET AREAS.
20. ALL ELECTRICAL CONNECTIONS BENEATH EXHAUST HOODS (IF EQUIPMENT IS PROVIDED IN THIS PROJECT) TO EXTEND TO SHUNT TRIP BREAKERS WITH ELECTRICAL PANEL BOX FOR SHUTDOWN DURING FIRE MODE.
21. RECEPTACLES ARE TO BE PRE-WIRED TO THE JUNCTION BOX OR LOAD CENTER FOR FINAL CONNECTION BY DIVISION 26.
22. ALL ELECTRICAL LIGHTING, POWER, AND DISTRIBUTION SYSTEMS.
23. DO NOT INTERCONNECT MORE THAN THREE (3) CONVENIENCE OUTLETS ON ONE (1) BREAKER.
24. OTHER THAN CONVENIENCE OUTLETS, ALL ELECTRICAL CONNECTIONS SHOWN ON FOOD SERVICE PLANS ARE DEDICATED BREAKERS.
25. DOORBELL AT RECEIVING DOOR (PROVIDE AND INSTALL – TO BE AUDIBLE THROUGHOUT KITCHEN, OFFICE, AND DRY STORAGE ROOM).
26. ADEQUATE LIGHTING AT RECEIVING DOOR.
27. PROVIDE AND INSTALL TWO EMERGENCY STROBE BEACONS THAT INTERCONNECT TO PANIC ALARM IN WALK-IN FREEZER. ONE (1) IN KITCHEN ABOVE WALK-IN FREEZER DOOR ONE (1) IN CAFETORIUM (IF WALK-IN IS PROVIDED IN THIS PROJECT). REFER TO GENERAL SPECIFICATIONS FOR ADDITIONAL DETAILS.
28. DEDICATED CIRCUIT FOR HEATED DRAIN LINE CONNECTION IN WALK-IN FREEZER AT EACH COIL (IF WALK-IN IS PROVIDED IN THIS PROJECT).

**NOTE: ELECTRICAL CONNECTIONS INDICATED ARE THOSE REQUIRED FOR THE FOOD SERVICE EQUIPMENT AND THOSE REQUIRED FOR SUPPORT EQUIPMENT FURNISHED BY DIVISION 26. FOR ADDITIONAL REQUIREMENTS, REFER TO THE ELECTRICAL ENGINEER'S DRAWINGS.**

6 ELECTRICAL COORDINATION NOTES
NOT TO SCALE

**DIVISION 22 (PLUMBING) RESPONSIBLE FOR BUT NOT LIMITED TO:**

1. **DO NOT ROUGH-IN FROM FDP DRAWINGS. REFER TO THE KITCHEN EQUIPMENT CONTRACTOR'S DIMENSIONED SHOP DRAWINGS. DIMENSIONS INDICATED ARE TO BE VERIFIED BY KITCHEN EQUIPMENT CONTRACTOR AND ADJUSTED AS REQUIRED BY EQUIPMENT AND/OR FIELD CONDITIONS.**
2. SECTION 11 40 00 TO VERIFY UTILITY REQUIREMENTS OF ANY EXISTING EQUIPMENT.
3. ALL CONNECTIONS SHALL BE MADE IN ACCORDANCE WITH LOCAL CODES AND NATIONAL STANDARDS, EXCEPT WHERE PLANS AND SPECIFICATIONS EXCEED THOSE CODES AND STANDARDS.
4. VERIFY ALL PLUMBING REQUIREMENTS WITH ENGINEERING DRAWINGS.
5. EMPTY PVC CONDUIT WITH WIDE-SWEEP BENDS FOR REFRIGERANT PIPING TO BEVERAGE LINES, CO2 LINES, AND REMOTE FOOD SERVICE EQUIPMENT REFRIGERATION SYSTEMS.
6. ROUGH-IN AND FINAL PLUMBING CONNECTIONS TO FOOD SERVICE EQUIPMENT AND BETWEEN COMPONENTS (INCLUDING MATERIALS AND LABOR). ACCESSORIES PROVIDED LOOSE WITH FOOD SERVICE EQUIPMENT BY SECTION 11 40 00 TO BE FIELD INSTALLED BY DIVISION 22. THIS INCLUDES BUT IS NOT LIMITED TO INSTALLATION OF ALL FAUCETS (WATER FILL FAUCETS, PRE-RINSE FAUCETS, ETC.), HOSES, GAS DISCONNECTS, AND DRAINS FROM EQUIPMENT POINT OF CONNECTION TO BUILDING PLUMBING SYSTEMS. ALL DRAIN LINES ARE PROVIDED AND INSTALLED BY DIV. 22.
7. KITCHEN EQUIPMENT CONTRACTOR IS RESPONSIBLE FOR PROVIDING ALL FAUCETS (WATER FILL FAUCETS, PRE-RINSE FAUCETS, ETC.), DRAIN FITTINGS, MIXING VALVES, CONTROL VALVES, WATER PRESSURE REGULATORS, VACUUM BREAKERS, AND ALL ACCESSORIES FOR EQUIPMENT SPECIFIED UNDER 11 40 00. DIVISION 22 IS RESPONSIBLE FOR INSTALLATION.
8. INDIRECT DRAIN LINE RUNS FROM EQUIPMENT TO NEAREST DRAIN OR FLOOR SINK. LINES TO BE TYPE 'K' COPPER.
9. IF ANY PLUMBING ACCESSORIES OR FITTINGS ARE PROVIDED LOOSE WITH EQUIPMENT BY 11 40 00, DIV. 22 IS TO ATTACH TO EQUIPMENT AND PROVIDE FINAL CONNECTION.
10. GAS SUPPLY SYSTEMS WITH ALL COMPONENTS AND FITTINGS AS REQUIRED FOR A COMPLETE SYSTEM.
11. WATER SUPPLY SYSTEMS WITH ALL COMPONENTS AND FITTINGS AS REQUIRED FOR A COMPLETE SYSTEM.
12. COMPRESSED AIR SYSTEMS WITH ALL COMPONENTS AND FITTINGS AS REQUIRED FOR A COMPLETE SYSTEM (IF REQUIRED FOR THIS PROJECT).
13. PIPING AND DRAINAGE SYSTEMS (SANITARY AND GREASE-LADEN). SYSTEMS MUST BE CLEANED AND FLUSHED BEFORE THE FINAL CONNECTION WITH FOOD SERVICE EQUIPMENT - CRITICAL.
14. FLOOR SINKS (PROVIDE AND INSTALL). FLANGE AND GRATES TO BE FLUSH WITH FINISHED FLOOR.
15. FLOOR DRAINS (PROVIDE AND INSTALL). FLANGE AND GRATES TO BE FLUSH WITH FINISHED FLOOR.
16. TRENCH DRAINS (PROVIDE AND INSTALL). TRENCH LINERS PROVIDED BY 11 40 00. FLANGE AND LINERS TO BE FLUSH WITH FINISHED FLOOR.
17. GREASE TRAPS AS REQUIRED. VERIFY WITH LOCAL CODES TO BYPASS OR PIPE THRU GREASE TRAP AND/OR INTERCEPTOR.
18. P-TRAPS AS REQUIRED (INCLUDING ALL DISPOSERS).
19. INTERCONNECT WATER THRU WATER FILTER (FILTER PROVIDED BY 11 40 00 UNLESS OTHERWISE SPECIFIED) TO EQUIPMENT.
20. GAS QUICK DISCONNECT INSTALLATION (QUICK DISCONNECT PROVIDED BY 11 40 00).
21. SAFETY RESTRAINT CABLE INSTALLATION (SAFETY RESTRAINT CABLE PROVIDED BY 11 40 00).
22. SPECIFIED COUPLINGS AND PIPING TO ALL EQUIPMENT FURNISHED BY 11 40 00.
23. AIR COMPRESSORS (IF REQUIRED FOR THIS PROJECT) (SIZE, PROVIDE, AND INSTALL, UNLESS OTHERWISE SPECIFIED).
24. WATER SOFTENERS (IF REQUIRED FOR THIS PROJECT) (SIZE, PROVIDE, AND INSTALL, UNLESS OTHERWISE SPECIFIED).
25. PRESSURE BOILERS (IF REQUIRED FOR THIS PROJECT) (SIZE, PROVIDE, AND INSTALL, UNLESS OTHERWISE SPECIFIED).
26. HAND SINKS (PROVIDE (UNLESS OTHERWISE SPECIFIED) AND INSTALL). PROVIDE HOT WATER TEMPERING VALVE IF REQUIRED. WATER TEMPERATURE TO BE AT LEAST 100 DEGREES AND FLOW FOR AT LEAST 20 SECONDS.
27. ICE BIN DRAIN INSULATION (IF ICE MACHINE IS PROVIDED IN THIS PROJECT) (PROVIDE AND INSTALL).
28. UNIONS AT DISPOSER SOLENOID VALVES (IF DISPOSER IS PROVIDED IN THIS PROJECT) (PROVIDE AND INSTALL).
29. BACK FLOW PREVENTION AS REQUIRED (PROVIDE AND INSTALL - INCLUDING ALL DISPOSERS). BACK- SIPHONAGE SHALL BE INSTALLED AT ALL FIXTURES AND EQUIPMENT WHERE BACKFLOW AND/OR BACK-SIPHONAGE MAY OCCUR AND WHERE A MINIMUM AIR GAP CANNOT BE PROVIDED BETWEEN THE WATER TO THE FIXTURE OR EQUIPMENT AT ITS FLOOD/LEVEL RIM. VACUUM BREAKERS, WHEN FURNISHED WITH EQUIPMENT, SHALL OVERRIDE THE ABOVE, IF ACCEPTABLE WITH APPLICABLE CODES. DIVISION 22 RESPONSIBLE FOR VERIFYING REQUIREMENT WITH LOCAL CODES.
30. JANITOR SINK WITH FAUCET (PROVIDE AND INSTALL).
31. FREEZE PROOF HYDRANT AT EXTERIOR OF BUILDING BY RECEIVING DOOR (PROVIDE AND INSTALL).
32. REVERSE OSMOSIS SYSTEMS (SIZE, PROVIDE (UNLESS OTHERWISE SPECIFIED), LOCATE AND INSTALL).
33. ALL PIPING WITHIN COUNTER BODY OR UNDER FABRICATED COUNTERS TO BE RUN TO A CONNECTION POINT BELOW COUNTER BODY BY SECTION 11 40 00. FINAL CONNECTION BY DIVISION 22.
34. EXHAUST HOOD CONDENSATE DRAIN CONNECTIONS (IF EXHAUST HOOD IS PROVIDED IN THIS PROJECT) (PROVIDE AND INSTALL).
35. INTERCONNECTION OF 1/2" CW TO PRE-RINSE AND DISPOSERS CONE/BODY INLETS PIPED THROUGH SOLENOID AND VACUUM BREAKER (IF DISPOSER IS PROVIDED IN THIS PROJECT).
36. FIRE SYSTEM PIPING. EXPOSED PIPING TO BE CHROME PLATED.
37. PIPE 1/2" COLD WATER TO SWIRL INLETS AT DISPOSERS (IF DISPOSER IS PROVIDED IN THIS PROJECT).
38. WATER TREATMENT FOR ICE BUILDERS (NON-CHLORINATED WATER WITH A PH LEVEL OF 10 OR HIGHER) AND ANY DRAINS AND OVERFLOWS. PIPING FROM ICE BUILDERS TO TUMBLE CHILLERS BY DIV. 23 (IF ICE BUILDERS AND TUMBLE CHILLERS ARE PROVIDED IN THIS PROJECT).

**NOTE: WATER AND DRAIN CONNECTIONS INDICATED ARE THOSE REQUIRED FOR THE FOOD SERVICE EQUIPMENT AND THOSE REQUIRED FOR SUPPORT EQUIPMENT FURNISHED BY DIVISION 22. FOR ADDITIONAL WATER AND DRAIN REQUIREMENTS REFER TO MECHANICAL DRAWINGS.**

**NOTE: REFER TO ELECTRICAL/MECHANICAL DRAWINGS FOR REQUIREMENTS OF EXHAUST FANS AND MAKE-UP AIR HANDLERS AND LOCATION OF AN INTERLOCK AND START/STOP CONTROLS TO BE LOCATED WITHIN FOOD SERVICE AREA BY DIVISION 26.**

4 PLUMBING COORDINATION NOTES
NOT TO SCALE

**DIVISION 23 (MECHANICAL) RESPONSIBLE FOR BUT NOT LIMITED TO:**

1. **DO NOT ROUGH-IN FROM FDP DRAWINGS. REFER TO THE KITCHEN EQUIPMENT CONTRACTOR'S DIMENSIONED SHOP DRAWINGS. DIMENSIONS INDICATED ARE TO BE VERIFIED BY KITCHEN EQUIPMENT CONTRACTOR AND ADJUSTED AS REQUIRED BY EQUIPMENT AND/OR FIELD CONDITIONS.**
2. SECTION 11 40 00 TO VERIFY UTILITY REQUIREMENTS OF ANY EXISTING EQUIPMENT.
3. ALL CONNECTIONS SHALL BE MADE FOLLOWING LOCAL CODES AND NATIONAL STANDARDS, EXCEPT WHERE PLANS AND SPECIFICATIONS EXCEED THOSE CODES AND STANDARDS.
4. VERIFY ALL MECHANICAL REQUIREMENTS WITH ENGINEERING DRAWINGS.
5. EMPTY EMT CONDUIT WITH PULL-WIRE AND WIDE-SWEEP BENDS FOR REFRIGERANT PIPING TO REMOTE FOOD SERVICE EQUIPMENT REFRIGERATION SYSTEMS.
6. ROUGH-IN AND FINAL CONNECTION OF MECHANICAL SYSTEMS TO FOOD SERVICE EQUIPMENT, WALK-IN ASSEMBLIES, AND BETWEEN COMPONENTS (INCLUDING MATERIALS AND LABOR).
7. TESTING AND BALANCING FOR ROOMS AND EXHAUST HOODS TO BE PERFORMED BY MECHANICAL CONTRACTOR. BALANCE REPORT FOR FOOD SERVICE EXHAUST HOODS TO BE PROVIDED TO FOODSERVICE DESIGN PROFESSIONALS (FDP) IMMEDIATELY UPON COMPLETION (SEND TO HOUSTON.SUBMITTAL@FDP.ORG FOR HOUSTON OFFICE AND DALLAS.SUBMITTAL@FDP.ORG FOR DALLAS OFFICE) AND MUST BE SUBMITTED WITH O&M MANUALS.
8. EXHAUST HOODS, CONDENSATE HOODS, FIRE SUPPRESSION SYSTEMS, CONNECTIONS AND CONTROLS (PROVIDE AND INSTALL – *UNLESS OTHERWISE SPECIFIED*). PROVIDE TEMPERED AIR AT ALL SUPPLY DUCTS.
   - A. IF EXHAUST/CONDENSATE HOODS AND FIRE SUPPRESSION SYSTEMS ARE SPECIFIED UNDER SECTION 11 40 00, DIVISION 23 IS RESPONSIBLE FOR ALL EXHAUST AND CONDENSATE HOOD CONNECTIONS (PROVIDE AND INSTALL).
9. VFD SYSTEM AND CONTROLLERS, WHEN REQUIRED BY CODE (PROVIDE AND INSTALL).
10. PROVIDE AND INSTALL ALL VENTILATION (DIRECT OR INDIRECT), AIR CONDITIONING AND HEATING SYSTEMS (UNLESS OTHERWISE SPECIFIED).
11. COORDINATE SUPPLY AND RETURN DUCTS ABOVE SERVING COUNTERS OR OPEN-AIR REFRIGERATED MERCHANDISERS. NO COLD AIR TO BLOW DIRECTLY ON HOT FOOD COUNTERS.
12. COORDINATE SUPPLY AND RETURN DUCTS AWAY FROM EQUIPMENT WITH TOP MOUNTED REFRIGERATION. NO COLD AIR TO BLOW DIRECTLY ON COMPRESSORS.
13. MECHANICAL CONTRACTOR TO LOCATE TEMPERATURE MONITORS WITHIN RETURN DUCTS.
14. CIRCULATING AIR ABOVE WALK-IN ASSEMBLIES (PROVIDE AND INSTALL).
15. CIRCULATING AIR ABOVE AND IN AIR GAPS AT WAREHOUSE COLD STORAGE ASSEMBLIES (PROVIDE AND INSTALL).
16. WATER CHILLERS AS REQUIRED (IF EQUIPMENT IS PROVIDED IN THIS PROJECT) (PROVIDE, SIZE AND LOCATE).
17. PIPING FROM ICE BUILDERS TO TUMBLE CHILLERS (IF EQUIPMENT IS PROVIDED IN THIS PROJECT) (PROVIDE, SIZE AND LOCATE).

3 MECHANICAL COORDINATION NOTES
NOT TO SCALE

**GENERAL CONTRACTOR RESPONSIBLE FOR BUT NOT LIMITED TO:**

1. ANY WALL PENETRATION REQUIRED FOR FOOD SERVICE EQUIPMENT UTILITIES. ESCUTCHEON PLATES OR S/S SLEEVES TO BE PROVIDED AND INSTALLED AS NEEDED.
2. BULK FREEZER VENTILATION PIPE (IF BULK FREEZER IS PROVIDED IN THIS PROJECT) (PROVIDE AND INSTALL, UNLESS OTHERWISE SPECIFIED).
3. CORE DRILLING FOR GUIDE RAILS (IF GUIDE RAILS ARE PROVIDED IN THIS PROJECT).
4. REFRIGERATION ROOF CURBS / ROOF JACK (IF REFRIGERATION SYSTEM IS PROVIDED IN THIS PROJECT AND LOCATED ON ROOF).
5. INTERIOR BOLLARDS (IF REQUIRED FOR THIS PROJECT) – TO BE EPOXY PAINTED PER LOCAL CODES (PROVIDE AND INSTALL).
6. FURNISH AND INSTALL 3/4" PLYWOOD BLOCKING IN THE WALL FOR MOUNTING EQUIPMENT FURNISHED BY SECTION 11 40 00 AS REQUIRED.
7. WALK-IN DEPRESSIONS (TO BE DEAD LEVEL) AND SAND LEVELING BED (IF WALK-IN IS PROVIDED IN THIS PROJECT AND RECESS IS SHOWN).
8. STRUCTURAL BRACING FOR BULK WALK-IN CEILING PANELS IF REQUIRED.
9. MENU SYSTEM VIDEO MONITORS IN SERVERY (UNLESS OTHERWISE SPECIFIED).
10. STRUCTURAL BRACING FOR MENU SYSTEM VIDEO MONITORS IF REQUIRED.
11. INTERIOR/EXTERIOR REFRIGERATION PENETRATIONS AND SLEEVES AT BUILDING PENETRATIONS.
12. DOORSCOPE VIEWER (PEEPHOLE) WITH WIDE VIEWING ANGLE AT RECEIVING DOOR.
13. CANOPY AT RECEIVING DOOR. COORDINATE HEIGHT WITH THE HEIGHT OF RECEIVING DOOR (8') AND THE MOUNTING HEIGHT OF AIR SCREEN ABOVE THE DOOR.
14. SOAP AND TOWEL DISPENSER PROVIDED BY OWNER. G.C. RESPONSIBLE FOR INSTALLATION.
15. WASHER AND DRYER (PROVIDE AND INSTALL, UNLESS OTHERWISE SPECIFIED).
16. DWARF WALL AT EXPOSED FRONT/ENDS OF CAFETERIA SERVING COUNTERS WITH FINISH AS SELECTED BY ARCHITECT (IF REQUIRED IN THIS PROJECT).

2 GENERAL CONTRACTOR COORDINATION NOTES
NOT TO SCALE

**HEALTH DEPARTMENT REQUIREMENTS (VERIFY WITH LOCAL JURISDICTIONS):**

1. FLOORS: VERIFY WITH DIVISION 9. FLOORS TO BE SMOOTH, IMPERVIOUS, EASILY CLEANABLE AND SLIP RESISTANT.
2. WALLS: VERIFY WITH ARCHITECTURAL DOCUMENTS. WALLS TO BE SMOOTH, IMPERVIOUS, AND EASILY CLEANABLE.
3. CEILING: LAY-IN TILES. CEILING TILES TO BE SMOOTH, IMPERVIOUS, AND EASILY CLEANABLE.
4. EMPLOYEE TOILET: TO BE LOCATED OFF MAIN CORRIDOR AND ADJACENT TO MAIN KITCHEN. RESTROOM MUST HAVE A VESTIBULE AND NOT OPEN TO KITCHEN / PREP AREAS. TOILETS TO BE WELL VENTILATED.
5. LAVATORIES: WALL HUNG LAVATORIES LOCATED WITHIN ALL FUNCTIONAL WORKING AREAS.
6. UTENSIL CLEANING/SANITIZING: ACCOMPLISHED IN UTENSIL WASH AREA WITH (3) 2'-0" x 2'-2" x 15" MINIMUM DEEP SINKS AND WAREWASH MACHINE.
7. MECHANICAL CLEANING/SANITIZING OF TABLEWARE: ACCOMPLISHED BY WAREWASH MACHINE.
8. STOREROOMS: AMPLE DAILY STORAGE PROVIDED IN ENCLOSED STORE ROOMS. STORE ROOMS TO BE VENTILATED AND MAINTAIN PROPER TEMPERATURE.
9. WATER HEATER: LOCATED IN THE MECHANICAL ROOM ADJACENT TO KITCHEN. TO BE SIZED TO PROVIDE AMPLE WATER TO MAINTAIN PROPER WATER TEMPERATURE THROUGHOUT HOURS OF OPERATION.
10. GREASE TRAP: LOCATED AT EXTERIOR OF BUILDING. REFER TO ENGINEER'S DRAWINGS.
11. FOOD SERVICE EQUIPMENT: ALL FLOOR-MOUNTED EQUIPMENT IS TO BE SEALED TO THE FLOOR TO PROVIDE AN EASILY CLEANABLE SURFACE AND PREVENT SEEPAGE. EQUIPMENT NOT MOUNTED TO THE FLOOR IS TO BE WALL MOUNTED ON WALL CARRIERS, OR ELEVATED ON LEGS TO PROVIDE AT LEAST A SIX-INCH CLEARANCE BETWEEN FLOOR AND EQUIPMENT.
12. MOP SINK: LOCATED IN JANITOR CLOSET OFF MAIN KITCHEN CORRIDOR, AND LOCATED IN CLOSE PROXIMITY TO THE SERVERY WAREWASH AREA.
13. EXHAUST HOODS: EXHAUST HOODS PROVIDED OVER COOKING EQUIPMENT WITH LIQUID CHEMICAL ANSUL FIRE EXTINGUISHING SYSTEM.
14. LIGHTING AND PROTECTIVE SHIELDING: RECESSED CEILING-MOUNTED FLUORESCENT LIGHT FIXTURES FITTED WITH CLEAR LEXAN DIFFUSERS.
15. GARBAGE AND REFUSE: CENTRAL TRASH COLLECTION PROVIDED FOR BUILDING LOCATED NEAR RECEIVING AREA ON SMOOTH CONCRETE SURFACE.
16. POISONOUS AND TOXIC MATERIAL STORAGE: LOCATED IN RESPECTIVE JANITOR CLOSETS WITH LOCKING HARDWARE.

1 HEALTH DEPARTMENT COORDINATION NOTES
NOT TO SCALE

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FDP
FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT

SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD
SUGAR LAND, TX 77479

SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY MELISSA MOORE, FCSI NO. 48854119 ON: 07/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

FS GENERAL COORDINATION NOTES

S-QF0.0

| FOOD SERVICE DRAWING INDEX | |
|---|---|
| FDP SHEET NUMBER | FDP SHEET NAME |
| S-QF0.0 | FS GENERAL COORDINATION NOTES |
| S-QF1.0 | FS EQUIPMENT PLAN |
| S-QF1.1 | FS FACILITY MODEL |
| S-QF1.2 | FS EQUIPMENT MODEL |
| S-QF1.3 | FS SPECIAL CONDITIONS & MECHANICAL PLAN |
| S-QF1.4 | FS PLUMBING PLAN |
| S-QF1.5 | FS ELECTRICAL PLAN |
| S-QF1.6 | FS CONDENSING UNITS |
| S-QF1.7 | FS WALK-INS |
| S-QF1.8 | FS SERVING LINE |
| S-QF1.9 | FS SERVING LINE |
| S-QF2.0 | FS DEMO PLAN |
| S-QF2.1 | FS TEMPORARY SERVING |
| S-QF3.1 | FS ELEVATIONS |
| S-QF4.1 | FS SECTIONS & DETAILS |
| S-QF4.2 | FS DETAILS |
| S-QF4.3 | FS DETAILS |




1 FOOD SERVICE EQUIPMENT PLAN
1/4" = 1'-0"

| FOOD SERVICE EQUIPMENT SCHEDULE | | | | | |
|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR GENERAL CONTRACTOR & HEALTH DEPARTMENT COORDINATION NOTES | | | | | |
| FDP ITEM | FDP QTY | FDP DESCRIPTION | FDP REMARKS | MANUFACTURER | MODEL |
| 101 | 1 | AIR SCREEN | | MARS | STD248-1UA-OB |
| 102 | 1 | COLD STORAGE ASSEMBLY | | AMERICAN PANEL | |
| 103 | 1 | COLD STORAGE REFRIGERATION SYSTEM | | RDT | ZS1-02Z-CT3-AST |
| 104 | 2 | COLD STORAGE SHELVING | | METRO | METROMAX Q |
| 107 | 1 | DRY STORAGE SHELVING | | METRO | METROMAX Q |
| 108 | 1 | CAN RACK | | NEW AGE | 1250CK |
| 109 | 1 | ICE MACHINE W/ BIN | | MAITOWOC | UYF0310A |
| 110 | 1 | CLOTHES WASHER | | WHIRLPOOL | RESIDENTIAL |
| 110A | 1 | CLOTHES DRYER | | WHIRLPOOL | RESIDENTIAL |
| 111W | 1 | WALL MOUNTED OVERSHELF | | CUSTOM FABRICATED | |
| 122 | 1 | TWO COMPARTMENT SINK WITHOUT DISPOSER | | CUSTOM FABRICATED | |
| 123 | 1 | DISPOSER - 3HP | | SALVAJOR | 300-CA-18-ARSS-LD |
| 125 | 1 | 20 QT. MIXER W/STAND | | HOBART | HL200 |
| 128 | 4 | UTILITY CART | | LAKESIDE | 522 |
| 129 | 3 | WORKTABLE W/S.BAR UT.RACK | | CUSTOM FABRICATED | |
| 138 | 4 | PAN RACK | | CRES COR | 207-UA-13A |
| 139 | 1 | INSUL MOBILE PROOFER | | CRES COR | H-137-WSUA-12D |
| 151 | 2 | FIRE PROTECTION SYSTEM | | ANSUL | R102 |
| 152 | 1 | EXHAUST HOOD | EXISTING | | |
| 153 | 1 | EXHAUST HOOD | EXISTING | | |
| 161 | 2 | CONVECTION OVEN | | BLODGETT | DFG-200 DBL |
| 165 | 1 | TWO BURNER RANGE | | VULCAN | V2B18B |
| 172 | 1 | COMBI OVEN | | RATIONAL | ICP 6-FULL/6-FULL N/G |
| 186 | 2 | PASS-THRU HEATED CABINET-1DR | | TRAULSEN | AHF132WP |
| 188 | 2 | PASS-THRU REFRIGERATOR-1DR | | TRAULSEN | AHT132WPUT |
| 201M.1 | 1 | SERVING COUNTER-MODULAR | | COUNTERCRAFT | SCOL-408-MOD |
| 214 | 2 | CASH REGISTER | OWNER FURNISHED | | |
| 249 | 1 | THREE COMPARTMENT SINK NO DISPOSER | | CUSTOM FABRICATED | |
| 250 | 1 | DISHMACHINE | | HOBART | CL44-BAS |
| 254 | 2 | SOILED & CLEAN DISHTABLE | | CUSTOM FABRICATED | |
| 255 | 2 | MOBILE DRYING RACK | | METRO | PR48VX3 |
| 260 | 4 | HAND SINK | FURNISHED & INSTALLED BY DIV. 22 | | |
| 614 | 1 | FILL FAUCET | | T&S | B-0610 |
| 615 | 2 | MENU MONITOR | BY OWNER | | |
| 800 | 1 | 15 GAL. BRAISING PAN | | GROEN | BPM-15GA |
| 801 | 1 | S/S CORNER GUARDS | LOCATED ON EVERY EXPOSED CORNER THROUGHOUT KITCHEN | CUSTOM FABRICATED | |
| 802 | 1 | WALL BUMPERS | LOCATED ON ALL EXPOSED BUILDING WALLS | PAWLING | MD-1 |
| 803 | 1 | WATER SOFTENER | | HOBART | WS-40 |
| 804 | 4 | S/S SPLASH GUARDS | | CUSTOM FABRICATED | |

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD
SUGAR LAND, TX 77479


SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
888544119
PROFESSIONAL MEMBER
Melissa Moore
7/18/2025
PRINTED NAME AND TITLE: MELISSA MOORE, FCSI NO. 888544119
DATE


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS EQUIPMENT PLAN

S-QF1.0

ISOMETRIC VIEWS WITHIN THIS DRAWING ARE NOT TO SCALE AND ARE PROVIDED FOR REFERENCE PURPOSES ONLY. ISOMETRIC VIEWS ARE NOT INTENDED FOR REGULATORY APPROVAL, PERMITTING, NOR CONSTRUCTION. REFER TO FLOOR PLANS AND DETAILS FOR SPECIFIC PROJECT INFORMATION.



1 FS FACILITY MODEL

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD
SUGAR LAND, TX 77479

SEAL

FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
7/15/2025
THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY MELISSA MOORE ON THE DATE ADJACENT TO THE SEAL. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.



ARCHITECTS
AND PLANNING
CONSULTANTS

11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS FACILITY MODEL

S-QF1.1

ISOMETRIC VIEWS WITHIN THIS DRAWING ARE NOT TO SCALE AND ARE PROVIDED FOR REFERENCE PURPOSES ONLY. ISOMETRIC VIEWS ARE NOT INTENDED FOR REGULATORY APPROVAL, PERMITTING, NOR CONSTRUCTION. REFER TO FLOOR PLANS AND DETAILS FOR SPECIFIC PROJECT INFORMATION.



1 FS EQUIPMENT MODEL

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD
SUGAR LAND, TX 77479

SEAL


FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
THE ITEM APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 48854119 ON: 07/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS EQUIPMENT MODEL


S-QF1.2

| FOOD SERVICE MECHANICAL SCHEDULE | | | | | | |
|---|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR MECHANICAL COORDINATION NOTES | | | | | | |
| FDP NO. | FDP QTY | FDP TYPE | FDP SIZE | FDP LOC | FDP CFM | FDP S.P. |
| M101 | 1 | EXHAUST | 4" X 16" | | 400 | .030" |
| M102 | 1 | EXHAUST | 4" X 16" | | 800 | .030" |
| M103 | 1 | DRYER VENT | 6" DIA. | | --- | --- |





1 FOOD SERVICE SPECIAL CONDITIONS PLAN
1/4" = 1'-0"

NOTE:
SECTION 11 40 00 TO COORDINATE FINAL LOCATION AND SIZE OF WALL BLOCKING.





5 WALL BLOCKING DETAIL
NOT TO SCALE


NOTE:
SECTION 11 40 00 TO COORDINATE FINAL LOCATION OF ALL TRENCH LINERS WITH EQUIPMENT POUR PATH.




6 TRENCH LINER DETAIL
NOT TO SCALE





3 COLD STORAGE ASSEMBLY ENCLOSURE PANEL DETAIL
NOT TO SCALE




4 COLD STORAGE ASSEMBLY REFRIGERATION SYSTEM GROUND MOUNT 4" PLATFORM DETAIL
NOT TO SCALE

SLAB TO BE MODIFIED AS REQUIRED TO ALLOW FOR A 4 1/2" DEPRESSION SLAB. PROVIDE NEW LEVEL CONCRETE PAD FOR COLD STORAGE ASSEMBLY.




2 COLD STORAGE ASSEMBLY 4 1/2" DEPRESSION DETAIL
NOT TO SCALE

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FDP
FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD
SUGAR LAND, TX 77479


SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
FCSI 108554119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
THIS ITEM WAS PREPARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 108554119 ON: 07/18/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS SPECIAL CONDITIONS & MECHANICAL PLAN

S-QF1.3

| FOOD SERVICE PLUMBING SCHEDULE | | | | | | |
|---|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR PLUMBING COORDINATION NOTES | | | | | | |
| FDP PNO | FDP PSIZE | FDP PCONN | FDP PSERVICE TO | FDP PLOC | FDP PAFF | FDP PREMARKS |
| P5 | 3/4" | H & C WATER | JANITOR SINK | WALL | 48" | JANITOR SINK BY PLUMBER |
| P6 | 4" | FLOOR DRAIN | JANITOR SINK | FLOOR | VERIFY | JANITOR SINK BY PLUMBER |
| P7 | 3/4" | H & C WATER | HOSE BIBB | WALL | 18" | BTC |
| P10 | VERIFY | FLOOR DRAIN | GENERAL AREA DRAIN | FLOOR | VERIFY | --- |
| P11C | 1/2" | H & C WATER | FAUCET | WALL | 18" | FURNISHED & INSTALLED BY DIV. 22 |
| P11D | 1 1/2" | DIRECT DRAIN | HAND SINK | WALL | 15" | FURNISHED & INSTALLED BY DIV. 22 |
| P12 | VERIFY | FLOOR DRAIN | EQUIP. DRAIN | FLOOR | VERIFY | NO SLOPE |
| P15 | 4" | FLOOR DRAIN | FUNNEL FLOOR DRAIN | FLOOR | 0" | --- |
| P109 | 3/4" | COLD WATER | WATER/ ICE | WALL | 60" | BTC |
| P109A | 12" SQ. | FLOOR SINK | ICE MACHINE | FLOOR | 0" | FULL GRATE |
| P110 | 3/4" | H & C WATER | CLOTHES WASHER | WALL | 48" | BTC; VALVE BOX |
| P110A | 2" | INDIRECT DRAIN | CLOTHES WASHER | WALL | 48" | VALVE BOX |
| P122 | 3/4" | H & C WATER | FAUCET | WALL | 13" | BTC |
| P122A | 12" SQ. | FLOOR SINK | SINK | FLOOR | 0" | 3/4 GRATE |
| P123 | 3/4" | H & C WATER | FAUCET / DISPOSER | WALL | 13" | BTC |
| P123A | 2" | DIRECT DRAIN | DISPOSER | WALL | 10" | BTC |
| P161 | (2)3/4" | NATURAL GAS | CONVECTION OVEN | WALL | 18"/36" | BTC - 60 MBTU/HR EACH |
| P163A | 3/4" | NATURAL GAS | TILT BRAISING PAN | WALL | 18" | BTC - 65 MBTU/HR |
| P163B | 3/4" | H & C WATER | TILT BRAISING PAN | WALL | 36" | BTC |
| P165 | 1" | NATURAL GAS | RANGE | WALL | 18" | BTC - 70 MBTU/HR |
| P172 | (2)3/4" | COLD WATER | COMBI OVEN | WALL | 24"/48" | BTC - INTERCONNECT THRU FILTERS |
| P172A | 3/4" | COLD WATER | COMBI OVEN | WALL | 48" | BTC |
| P172B | 12"SQ. | FLOOR SINK | EQUIPMENT | FLOOR | 0" | 3/4 GRATE |
| P172C | (2)3/4" | NATURAL GAS | COMBI OVEN | WALL | 18"/36" | BTC - 105 MBTU/HR EACH |
| P172D | 3/4" | COLD WATER | COMBI OVEN | WALL | 66" | BTC; INTERCONNECT TO P172 |
| P172E | 3/4" | COLD WATER | COMBI OVEN WATER FILTER | WALL | 66" | BTC |
| P249 | 3/4" | H & C WATER | FAUCET | WALL | 13" | BTC |
| P249A | 12" SQ. | FLOOR SINK | SINK | FLOOR | 0" | THREE QUARTER GRATE |
| P250 | 12" SQ. | FLOOR SINK | BOOSTER / DISHMACHINE | FLOOR | 18" | BTC |
| P250A | 3/4" | HOT WATER | DISHMACHINE | WALL | 18" | EXT. THRU W.FILTER TO BOOSTER / DISH MACHINE - 140DEG.MIN. |
| P250B | 3/4" | COLD WATER | DISHMACHINE | WALL | 18" | BTC |
| P614 | 1/2" | H & C WATER | FILL FAUCET | WALL | 42" | BTC |
| P800 | 12" SQ. | FLOOR SINK | EQUIPMENT | FLOOR | 0" | 3/4 GRATE |




1 FOOD SERVICE PLUMBING PLAN
1/4" = 1'-0"

SECTION 11 40 00 TO PROVIDE LOOSE WITH FOOD SERVICE EQUIPMENT. INSTALLATION BY DIV. 22 & 26.


- (A) VACUUM BREAKER
- (B) DISPOSER
- (C) TIME DELAY
- (D) CONTROL PANEL
- (E) SOLENOID VALVE

DIVISION 22 TO PROVIDE AND INSTALL


- (F) 1/2" CW INLET
- (G) FLOW CONTROL
- (H) 1/2" CW
- (I) 2" DRAIN LINE WITH P-TRAP & Y ADAPTOR
- (J) 1-1/2" TAILPIECE
- (K) GATE VALVE
- (L) 1/2" CW SUPPLY
- (M) SHOCK STOP
- (N) RPZ BACK FLOW PREVENTOR

DIVISION 26 TO PROVIDE AND INSTALL


- (O) POWER SUPPLY





6 DISPOSER WITH VACUUM BREAKER DETAIL
NOT TO SCALE





7 EXHAUST HOOD - GAS LINE ROUTING DETAIL
NOT TO SCALE




3 GAS DISCONNECT DETAIL
NOT TO SCALE




5 DRAIN PIPING FASTENER DETAIL
NOT TO SCALE




8 WAREWASH - PERFORATED OVER SHELF DETAIL
NOT TO SCALE

| | | | | | |
|---|---|---|---|---|---|
| ○ | HW | HOT WATER | ▢ | FFD | FUNNEL FLOOR DRAIN |
| ○ | CW | COLD WATER | ◣ | EVC | EXHAUST VENT CONNECTION |
| ○ | HTW | 180 F HOT WATER | ⋈ | SVC | SUPPLY VENT CONNECTION |
| ◎ | | CHILLED WATER | ◔ | FR | DIRECT-CONNECTED FLUE RISER |
| ● | W | DIRECT WASTE | ◎ | PS | PIPE SLEEVE |
| ○ | IW | INDIRECT WASTE | ⊙ | | COMPRESSED AIR |
| ⊙ | | GAS SUPPLY | ♦ | | CO2 |
| ◕ | | STEAM SUPPLY | | AFF | ABOVE FINISHED FLOOR |
| ⊘ | CR | CONDENSATE RETURN | | BTC | BRANCH TO CONN. ON EQUIP |
| ◉ | DR | DRAIN | | DFA | DROP FROM ABOVE |
| ▢ | FD | FLOOR DRAIN | | CLG | CEILING |
| ▟ | FST | FLOOR SINK 3/4 GRATE | | | |
| ▟ | FSH | FLOOR SINK 3/4 GRATE | | | |

2 PLUMBING SYMBOLS
NOT TO SCALE

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FDP
FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD
SUGAR LAND, TX 77479

SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
THIS ITEM WAS ELECTRONICALLY APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 48854119 ON: 07/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS PLUMBING PLAN


S-QF1.4

| FOOD SERVICE ELECTRICAL SCHEDULE | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR ELECTRICAL COORDINATION NOTES | | | | | | | | |
| FDP ENO | FDP ECONN | FDP ELOAD | FDP EVOLT | FDP EPH | FDP ESERVICE TO | FDP ELOC | FDP EAFF | FDP EREMARKS |
| E10 | DR | 16.0A | 120 | 1 | CONVENIENCE | WALL | 24" | MOUNT HORIZONTAL |
| E13 | WPR | 16.0A | 120 | 1 | CONVENIENCE | WALL | 24" | MOUNT HORIZONTAL |
| E15 | JB | --- | --- | --- | FIRE PROT. SYSTEM | WALL | 48" | RECESSED EMPTY CONDUIT FOR FIRE PULL |
| E101 | JB | 5.1A | 120 | 1 | AIR SCREEN | WALL | 82" | BTC; MAGNETIC REED SWITCH ON DOOR JAMB & DOOR |
| E102A | JB | 16.0A | 120 | 1 | DOOR HEATER/LIGHTS | CLG | DFA | BTC |
| E102B | JB | 5.0A | 120 | 1 | TEMP. ALARM | CLG | DFA | BTC |
| E102C | JB | 5.0A | 120 | 1 | PRESSURE RELIEF PORT | CLG | DFA | BTC |
| E102E | JB | 10.0A | 120 | 1 | PANIC ALARM BUTTON | CLG | DFA | BTC-INTERCONNECT TO STROBE LIGHT/HORN ABOVE FREEZER DOOR AND IN CAFETORIUM |
| E103 | JB/DS | 25.0A | 208 | 3 | REFRIGERATION SYSTEM | VERIFY | VERIFY | BTC |
| E103C | JB | 9.1A | 208 | 1 | FREEZER COIL | CLG | DFA | BTC |
| E103D | JB | 1.8A | 120 | 1 | COOLER COIL | CLG | DFA | BTC |
| E103E | JB | --- | --- | --- | DATA CONNECTION | CLG | DFA | BTC; RUN TO NEAREST IDF / MDF ROOM |
| E103F | JB | 16.0A | 120 | 1 | DRAIN LINE HEATER | CLG | DFA | BTC; DEDICATED CIRCUIT |
| E109 | DR | 11.9A | 120 | 1 | ICE MACHINE | WALL | 60" | --- |
| E110 | DR | 16.0A | 120 | 1 | CLOTHES WASHER | WALL | 48" | -- |
| E110A | SR | 30.0A | 208 | 1 | CLOTHES DRYER | WALL | 48" | VERIFY NEMA PLUG RECEPTACLE |
| E123 | JB | 3.0HP | 208 | 3 | DISPOSER | WALL | 24" | BTC; CONNECT THRU C.P. TO DISPOSER |

| FOOD SERVICE ELECTRICAL SCHEDULE | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR ELECTRICAL COORDINATION NOTES | | | | | | | | |
| FDP ENO | FDP ECONN | FDP ELOAD | FDP EVOLT | FDP EPH | FDP ESERVICE TO | FDP ELOC | FDP EAFF | FDP EREMARKS |
| E129 | DCR | 16.0A | 120 | 1 | TABLE RECEPTACLE | CLG | 84" | TWISTLOCK PLUG & RECEPTACLE |
| E139 | DCR | 15.0A | 120 | 1 | INSUL. MOBILE PROOFER | CEILING | DFA | -- |
| E151 | JB | 1.0A | 120 | 1 | FIRE PROT. SYSTEM | CLG | DFA | BTC |
| E161 | (2)DR | 6.0A EA. | 120 | 1 | CONVECTION OVEN | WALL | 24"/48" | SHUNT TRIP BREAKER |
| E163 | DR | 5.0A | 120 | 1 | TILT BRAISING PAN | WALL | 24" | SHUNT TRIP BREAKER |
| E172 | (2)JB | 15.0A EA. | 208 | 1 | COMBI OVEN | WALL | 24"/48" | BTC - SHUNT TRIP BREAKER |
| E187 | JB | 15.5A | 120/208 | 1 | HEATED CABINET | WALL | 96" | BTC; MOUNT ON KITCHEN SIDE |
| E188 | JB | 7.2A | 120 | 1 | REFRIGERATOR | WALL | 96" | BTC; MOUNT ON KITCHEN SIDE-OMIT PLUG, UNIT TO BE HARDWIRED |
| E201A | PMR | 28.0A | 208 | 1 | HOT FOOD COUNTER | FLOOR | 4.5" | BTC |
| E201B | PMR | 16.0A | 120 | 1 | COLD FOOD COUNTER | FLR | 4.5" | --- |
| E209 | PMR | 8.0A | 120 | 1 | DROP FRONT MILK COOLER-8 CASE | FLR | 4.5" | --- |
| E214 | PMR | 16.0A | 120 | 1 | CASH REGISTER | FLR | 4.5" | DEDICATED CIRCUIT |
| E214A | CS | --- | --- | --- | POS | FLOOR | 6" | BTC; CONDUIT W/DATA LINE TO RUN TO MANAGER'S OFFICE OR IDF ROOM-VERIFY |
| E250 | JB/DS-JB | 51.7A | 480 | 3 | DISHMACHINE | WALL | 66" | BTC; EXTEND FROM JB/DS AT NEAREST WALL |
| E615 | DR | 5.0A | 120 | 1 | VIDEO / DATA SYSTEM | CLG | VERIFY | PROVIDE DCO AT VIDEO LOCATION |
| E615A | JB | --- | --- | --- | VIDEO / DATA SYSTEM | CLG | VERIFY | PROVIDE JB AT DATA LOCATION |





6 COLD STORAGE ASSEMBLY ENTRAPMENT PANIC ALARM DETAIL
NOT TO SCALE





DIVISION 26 TO PROVIDE, COORDINATE, AND INSTALL THE FOLLOWING:
1. AUDIBLE DOORBELL AT RECEIVING DOOR ON EXTERIOR WALL THAT CAN BE HEARD THROUGHOUT THE ENTIRE KITCHEN, OFFICE AND DRY STORAGE ROOM.
2. ADEQUATE LIGHTING AT RECEIVING DOOR.
3. EDWARDS 860 SERIES (OR EQUAL) RED LENS, SURFACE-MOUNTED XENON EMERGENCY STROBE BEACONS. ONE (1) TO BE LOCATED IN THE KITCHEN ABOVE WALK-IN FREEZER DOOR (OR COOLER DOOR WHEN FREEZER IS WITHIN COOLER IN AN 'INLINE' ASSEMBLY), AND ONE (1) TO BE LOCATED IN THE CAFETORIUM (COORDINATE LOCATION WITH OWNERS). PROVIDE CONDUIT, WIRING, AND INTERCONNECT THE ILLUMINATED PUSH BUTTON PANIC ALARM IN THE WALK-IN FREEZER TO BOTH STROBE BEACONS (***CRITICAL***).

DIVISION 27 TO PROVIDE THE FOLLOWING:
1. CONDUIT, DATA, AND INTERCONNECTION FROM THE ILLUMINATED PUSH BUTTON PANIC ALARM INSIDE THE WALK-IN FREEZER TO THE BUILDING AUTOMATION SYSTEM. WHEN ACTIVATED, FACILITY PERSONNEL TO BE NOTIFIED - COORDINATE NOTIFICATION REQUIREMENTS WITH THE OWNER (***CRITICAL***).





1 FOOD SERVICE ELECTRICAL PLAN
1/4" = 1'-0"





3 PEDESTAL MOUNTED RECEPTACLE DETAIL
NOT TO SCALE

NOTE:
REFER TO FDP EQUIPMENT PLAN FOR SPECIFIC COMPONENTS UNDER HOOD. ALL EQUIPMENT SHOWN HERE FOR GRAPHICAL REPRESENTATION ONLY.




- (A) S/S ENCLOSURE W/AGENT TANK AND NITROGEN CARTRIDGE
- (B) DUCT NOZZLE(S)
- (C) PLENUM NOZZLE(S)
- (D) SURFACE PROTECTION NOZZLE(S)
- (E) FUSIBLE LINK(S)
- (F) (2) WIRES FROM FIRE SYSTEM TO SHUNT TRIP BREAKERS FOR SHUT DOWN OF ELECTRICAL CONNECTIONS LOCATED BENEATH EXHAUST HOOD DURING FIRE MODE
- (G) REMOTE FIRE PULL
- (H) GAS VALVE
- (I) GAS SUPPLY (AS REQUIRED)

4 FIRE PROTECTION SYSTEM TYPICAL DETAIL
NOT TO SCALE




5 FIRE PROTECTION SYSTEM RECESSED FIRE PULL DETAIL
NOT TO SCALE

| | | | | | |
|---|---|---|---|---|---|
| | SCR | CONDUIT STUB BTC ON RECEPT FURNISH WITH EQUIPMENT | | CC | CONDUIT FOR COMPUTER CABLES |
| • | CS | CONDUIT STUB UP/OUT FOR DIRECT CONNECTION | | BTC | BRANCH TO CONNECTION ON EQUIPMENT |
| | DR | DUPLEX RECEPTACLE | | WPR | WATERPROOF RECEPTACLE (SPRING COVER) |
| | SR | SINGLE PURPOSE RECEPTACLE-1PH | | FPB | FIRE PROTECTION BUZZER |
| | SR | SINGLE PURPOSE RECPTACLE-3PH | | BSC | BEVERAGE SYSTEM CONDUIT |
| | FR | FLUSH FLOOR RECEPTACLE | | DFA | DROP FROM ABOVE |
| | PMR | PEDESTAL MOUNTED RECEPTACLE | | AFF | ABOVE FINISH FLOOR |
| | DCR | DROP CORD RECEPTACLE | | CSJB | JUNCTION BOX ON PEDESTAL |
| | JB | JUNCTION BOX ON CEILING | | SW | SWITCH |
| | JB | JUNCTION BOX IN WALL | | D | DATA |
| | JB/DS | JUNCTION BOX WITH DISCONNECT BY DIV.26 | | | |

2 ELECTRICAL SYMBOLS
NOT TO SCALE

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS


FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD
SUGAR LAND, TX 77479

SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
PRINTED COPIES APPEARING ON THIS SEAL ARE NOT AUTHORIZED BY MELISSA MOORE, FCSI NO. 48854119 ON: 07/18/2025



ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS ELECTRICAL PLAN


S-QF1.5




**3 MECHANICAL ROOF FLOOR PLAN**
SCALE: 1/8" = 1'-0"




**2 RENO MECHANICAL FLOOR PLAN - KITCHEN AREA**
SCALE: 1/8" = 1'-0"




**1 DEMO MECHANICAL FLOOR PLAN - KITCHEN AREA**
SCALE: 1/8" = 1'-0"

## AIR DEVICE SCHEDULE

| MARK | DESCRIPTION |
|---|---|
| A | CEILING DIFFUSER – 24" X 24" FACE, PATTERN TYPE, STEEL CONSTRUCTION, OBD/RADIATION DAMPER, WHITE FINISH, U.L. LISTED PRICE SCD A1–12" X 12" |
| B | CEILING RETURN GRILLE – 24" X 24" PERFORATED FACE, STEEL CONSTRUCTION, RADIATION DAMPER, WHITE FINISH, U.L. LISTED PRICE PDFR B1–12" X 12" |
| C | CEILING EXHAUST GRILLE – 24" X 24" PERFORATED FACE, STEEL CONST., OBD/RADIATION DAMPER, WHITE FINISH, NECK SIZE SHOWN, U.L. LISTED PRICE PDDR C1–12" X 12" |

NOTES:
1. REFER TO ARCHITECTURAL REFLECTED CEILING PLAN TO VERIFY CEILING TYPES FOR AIR DEVICES.

## KITCHEN HOOD REFURBISHMENT NOTES

HOOD REFURBISHMENT FOR KITCHEN HOODS (QUANTITY 2):
- STEAM WASH AND DEEP CLEAN STAINLESS STEEL HOOD ASSEMBLY, CASING, AND SUPPLY GRILLES WHERE APPLICABLE.
- REPLACE GREASE FILTER RACKS.
- CLEAN EXISTING MAKE-UP AIR AND GREASE EXHAUST DUCT.
- RELAMP EXISTING LIGHT FIXTURES WITH NEW 4000K BULBS LISTED FOR USE IN AN ENCLOSED KITCHEN HOOD FIXTURE.
- COORDINATE WITH DIVISION 11 FOR REPLACEMENT OF ANSUL FIRE SUPPRESSION SYSTEM.
- HOOD ASSEMBLIES SHALL BE CLEANED TO MEET THE STANDARDS ESTABLISHED IN NFPA STANDARD 96.

## KITCHEN HOOD EXHAUST & MAKE-UP AIR UNIT SCHEDULE

| MARK | ESF-1,2 |
|---|---|
| SERVES | KITCHEN HOOD-1 & 2 |
| **SUPPLY SECTION** | |
| TYPE | INDIRECT GAS-FIRED MAKE-UP AIR UNIT |
| DRIVE | DIRECT |
| SPEED CONTROL | VFD |
| SUPPLY CFM | 2250 |
| EXT. S.P. (IN. W.G.) | 0.375 |
| HORSEPOWER (WATTS) | 1-1/2 HP |
| VOLTAGE | 480V/3-PHASE |
| UNIT MCA | 4.6 A |
| UNIT MOCP | 15 A |
| HEATING MEDIUM | NATURAL GAS |
| INPUT/OUTPUT (MBH) | 150.0/121.5 |
| TURNDOWN RATIO | 4:1 |
| MANUFACTURER | GREENHECK |
| MODEL | IGX-P109-H12-MF-E |
| **EXHAUST SECTION** | |
| TYPE | UPBLAST BELT DRIVE CENTRIFUGAL |
| EXHAUST CFM | 3600 |
| EXT. S.P. (IN. W.G.) | 0.75 |
| HORSEPOWER (WATTS) | 1-1/2 HP |
| VOLTAGE | 480V/3-PHASE |
| UNIT MCA | 3.75 A |
| UNIT MOCP | 15 A |
| MANUFACTURER | GREENHECK |
| EXHAUST FAN MODEL | CUBE-200-15 |

NOTES
1. EXHAUST FAN: PROVIDE FAN WITH PRE-FABRICATED ROOF CURB ADAPTER, VENTED CURB EXTENSION, HINGING KIT, HEAT BAFFLE, DRAIN CONNECTION, GREASE TRAP, AND DISCONNECT SWITCH. FANS SHALL BE UL LISTED FOR USE WITH TYPE 1 GREASE HOOD.
2. EXHAUST FAN: PROVIDE NEW MOTOR STARTER, SIZED FOR EXHAUST FAN MOTOR AND INSTALLED IN PLACE OF EXISTING. REFERENCE THE SPECIFICATIONS FOR STARTER REQUIREMENTS. COORDINATE WITH DIV.25 FOR RE-TERMINATION OF PERMISSIVE ON/OFF CONTROL. COORDINATE WITH DIV.26 FOR RE-TERMINATION OF LOCAL HOOD SWITCH INTERLOCK FOR START/STOP CONTROL.
3. SUPPLY FAN/FURNACE: FLUE GAS FROM HEATING COIL SHALL BE POWER VENTED.
4. SUPPLY FAN/FURNACE: WEATHERHOOD WITH ALUMINUM MESH.
5. SUPPLY FAN/FURNACE: 5 YEAR HEAT EXCHANGER WARRANTY.
6. SUPPLY FAN/FURNACE CONTROLS: INTEGRAL HEATER CONTROLS WITH BAS INTERLOCK FOR PERMISSIVE ON/OFF AND LOCAL SWITCH INTERLOCK FOR CONTROL FROM KITCHEN HOOD SWITCH. FURNACE CONTROLS SHALL BE PROGRAMMED FOR 64°F LAT, WITH A LOCKOUT FOR O/A TEMPERATURES ABOVE THE LAT SETPOINT. COORDINATE WITH DIV.25 AND DIV.26 FOR CONTROLS AND SWITCH INTERLOCKS.
7. TWO POINT POWER CONNECTION: ONE FOR EXHAUST FAN AND ONE FOR INTAKE/SUPPLY FAN.
8. INTERLOCK FAN(S) WITH ASSOCIATED COOKING HOOD
9. INTERLOCK FAN WITH SWITCH ON KITCHEN HOOD.
10. UNIT TO BE PROVIDED WITH GALVANIZED STEEL FAN PACK EXTENSION/COMBINATION CURB.
11. REFER TO WRITTEN SPECS FOR ADDITIONAL REQUIREMENTS.

## MECHANICAL RENO KEYED NOTES

1. TIE-IN NEW DUCTWORK TO EXISTING DUCTWORK AT WALL PENETRATION.
2. CONNECT NEW AIR DEVICE AND TAP TO EXISTING E/A TRUNK DUCT.
3. REWORK EXISTING EXHAUST AND SUPPLY DUCTWORK FROM EXISTING KITCHEN HOOD UP TO FAN, AS REQUIRED, WITH NEW TRANSITIONS AND SUPPLY AIR DUCTWORK OFFSETS TO MATE WITH NEW FAN CURB.
4. EXISTING ELECTRIC DUCT HEATER TO BE RETAINED FOR RE-INSTALLATION IN RENOVATION PHASE.
5. NEW DRYER VENT DUCT AND VENT CAP.
6. TEMP. KITCHEN – CEILING MOUNTED CABINET EXHAUST FAN.
7. TEMP. KITCHEN – 24"X24" SIDE WALL GRILLE. SURFACE MOUNT OPTIONAL. AUXILIARY FRAME. TITUS CT-700.
8. RECONFIGURE DUCTWORK TO CONNECT TO NEW DISHMACHINE HOOD OUTLETS. REF. KITCHEN CONSULTANT DRAWINGS FOR EXACT DIMENSIONS OF DUCT CONNECTIONS.
9. CONDENSATE EXHAUST DUCT UP THROUGH ROOF TO NEW EXHAUST FAN SET ON NEW ROOF CURB. REUSE EXISTING ROOF PENETRATION.

## MECHANICAL DEMO KEYED NOTES

1. DEMOLISH EXISTING AIR DEVICE, BRANCH DUCT, DAMPER AND TAP BACK TO TRUNK DUCT. CAP AND SEAL RESULTING OPENING.
2. EXISTING E/A TRUNK DUCT TO REMAIN.
3. DISCONNECT EXISTING S/A AND E/A DUCTWORK SERVING KITCHEN HOODS FROM FAN ASSEMBLY ON ROOF. DEMOLISH SUPPLY AND EXHAUST FAN PLENUM ASSEMBLY SERVING KITCHEN HOODS, ALONG WITH CURB. NEW CURB TO BE PROVIDED AND INSTALLED AS PART OF RENOVATION.
4. DEMOLISH ALL EXISTING AIR DEVICES, DUCTWORK, AND DUCTWORK ACCESSORIES SERVING KITCHEN AREA BACK TO MECH. ROOM WALL PENETRATION.
5. EXISTING ELECTRIC DUCT HEATER TO BE RETAINED FOR RE-INSTALLATION IN RENOVATION PHASE.
6. REFURBISH EXISTING KITCHEN HOOD. REFER TO "KITCHEN HOOD REFURBISHMENT NOTES".
7. DEMOLISH AND REPLACE EXISTING DRYER EXHAUST DUCT AND FLUE VENT CAP.
8. DEMOLISH EXISTING CONDENSATE HOOD, ASSOCIATED DUCTWORK, AND ROOF EXHAUST FAN.

## EXHAUST FAN SCHEDULE

| MARK | EF-TK | EF-CF | EF-14 |
|---|---|---|---|
| SERVES | TEMPORARY KITCHEN | COOLER/FREEZER | DISH WASHER |
| TYPE | CEILING CABINET | INLINE FAN | ROOF UPBLAST |
| DRIVE | DIRECT | DIRECT | DIRECT |
| SPEED CONTROL | INTEGRAL SPEED CONTROLLER | CONSTANT | CONSTANT |
| CFM | 1055 | 1000 | 1200 |
| EXT. S.P. (IN. W.G.) | 0.3 | 0.35 | 0.60 |
| IMP. SIZE (IN.) | 8.0 | 13.5 | |
| HORSEPOWER (WATTS) | 1/3 HP | 1/6 HP | 1/6 HP |
| VOLTAGE | 120V/1-PHASE | 120V/1-PHASE | 120V/1-PHASE |
| MANUFACTURER | COOK | COOK | COOK |
| MODEL | GC-862 | 1355QN10D | CUE-140-VG |
| SONES (MAX.) | 15.0 | 15.0 | 15.0 |
| NOTES | 1 THRU 4 | 1 THRU 4 | 1 THRU 4 |

NOTES
1. STATIC PRESSURE SHOWN IS EXTERNAL TO THE UNIT. MANUFACTURER SHALL ADD DAMPER AND ACCESSORY LOSSES TO THIS VALUE BEFORE SELECTING FAN. FANS SHALL BE CAPABLE OF 120% OF THE SCHEDULED CFM CAPACITY.
2. INTEGRAL DISCONNECT SWITCH.
3. RUBBER IN-SHEAR ISOLATORS.
4. REFER TO WRITTEN SPECS FOR ADDITIONAL REQUIREMENTS.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD.
SUGAR LAND, TX 77479

SEAL




ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

KITCHEN AREA MECHANICAL PLANS
S-M1.01

STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM (713) 300-6092 | TEXAS ENG. FIRM REG. NO. F-018332-0 | 1300 W. SAM HOUSTON PARKWAY N., SUITE 121, HOUSTON, TX 77043
2025 ALL RIGHTS RESERVED

## MECHANICAL SYMBOL SCHEDULE

| | |
|---|---|
| CWS | CONDENSER WATER SUPPLY |
| CWR | CONDENSER WATER RETURN |
| CHS | CHILLED WATER SUPPLY |
| CHR | CHILLED WATER RETURN |
| HWS | HEATING WATER SUPPLY |
| HWR | HEATING WATER RETURN |
| RS | REFRIGERANT SUPPLY |
| RR | REFRIGERANT RETURN |
| D | CONDENSATE LINE |
| | PETE'S PLUG |
| | ISOLATION VALVE |
| | ELECTRONIC CONTROL VALVE |
| | BUTTERFLY VALVE |
| | BALL VALVE |
| | UNION OR FLANGE |
| | STRAINER |
| | AUTOMATIC AIR VENT |
| T | LOCAL CONTROL THERMOSTAT |
| T | TEMPERATURE SENSOR |
| H | HUMIDITY SENSOR |
| FD | FIRE DAMPER |
| SD | SMOKE DAMPER |
| FSD | FIRE/SMOKE COMBINATION DAMPER |
| MD | MOTORIZED DAMPER |
| C | CARBON MONOXIDE SENSOR |
| C | CARBON DIOXIDE SENSOR |
| | SUPPLY AIR DIFFUSER |
| | RETURN AIR GRILLE |
| | EXHAUST GRILLE |
| RA | RETURN AIR OPENING IN WALL |
| VD | VOLUME DAMPERS |
| | DUCT ELEVATION CHANGE |
| | 90° DUCT ELBOW WITH TURNING VANES |
| | FLEXIBLE DUCT |
| M | DAMPER MOTOR |
| T | TEMPERATURE TRANSMITTER |
| FS | FLOW SWITCH |
| P | DIFFERENTIAL PRESSURE SENSOR |
| SD | DUCT SMOKE DETECTOR |
| PS | STATIC PRESSURE SENSOR |
| PH | STATIC PRESSURE SENSOR HI-LIMIT |
| | ACCESS PANEL |

| | |
|---|---|
| A.P. | ACCESS PANEL |
| AHU | AIR HANDLING UNIT |
| B | BOILER |
| CH | CHILLER |
| CHP | CHILLED WATER PUMP |
| CVT | CONSTANT VOLUME TERMINAL |
| DH | DEHUMIDIFIER |
| E/A | EXHAUST AIR |
| EF | EXHAUST FAN |
| F&B | FACE & BYPASS |
| FF | FLY FAN |
| HDT | HORIZONTAL DRAW THROUGH |
| HWP | HOT WATER PUMP |
| KEF | KITCHEN EXHAUST FAN |
| KSF | KITCHEN SUPPLY FAN |
| O/A | OUTSIDE AIR |
| OBD | OPPOSED-BLADES DAMPER |
| PT | PRE-TREAT |
| R/A | RETURN AIR |
| RAHU | ROOF-MOUNTED AIR HANDLING UNIT |
| S/A | SUPPLY AIR |
| SA | SOUND ATTENUATOR |
| SF | SUPPLY FAN |
| SPD | SPILTER DAMPER |
| SZ | SINGLE ZONE |
| VAV | VARIABLE AIR VOLUME |
| VB | VAV BOX |
| VD | VOLUME DAMPER |
| VDT | VERTICAL DRAW THROUGH |
| VFD | VARIABLE FREQUENCY DRIVE |
| WH | WATER HEATER |
| ⌀ | DESIGNATION FOR "ROUND" |
| ⌀ | DESIGNATION FOR "OVAL" |

## GENERAL MECHANICAL NOTES


1. REFER TO WRITTEN SPECIFICATIONS FOR ADDITIONAL INFORMATION.
2. COORDINATE INSTALLATION OF EQUIPMENT AND PIPING WITH THE ELECTRICAL CONTRACTOR TO INSURE NEC CLEARANCE (42 INCHES) IN FRONT OF ALL ELECTRICAL PANELS. DO NOT INSTALL DUCTWORK OR WATER PIPING OVER THE TOP OF ELECTRICAL PANELS SEE DETAIL 1/M2.01.
3. DUCT SIZES SHOWN ARE NET FREE AIR PASSAGE DIMENSIONS, DUCTS ARE NOT LINED, BUT ARE EXTERNALLY INSULATED. RUNOUTS TO CEILING OUTLETS SHALL BE EXTERNALLY INSULATED GALVANIZED SHEET METAL WITH SPIN-IN V.D. AT TRUNK TAPS, SEE DETAIL 1 & 2/M2.01.
4. REFER TO ARCHITECTURAL REFLECTED CEILING DRAWINGS FOR EXACT LOCATIONS OF CEILING OUTLETS IN RELATION TO OTHER CEILING ENTITIES. OUTLETS MUST BE COMPATIBLE WITH THE CEILING TYPES FOR THE VARIOUS AREAS.
5. IN AREAS WHERE SUPPLY AIR ENTERS CEILING CAVITY THRU RETURN AIR GRILLES AND FREE RETURNS TO AHU'S VIA CEILING CAVITY, PROVIDE RETURN AIR OPENING IN WALL-TO-DECK ABOVE CEILING THAT BLOCK PATH, REFER TO ARCHITECTURAL DRAWINGS. RETURN AIR ELBOWS SHALL BE SIZED AT 1 SQ. FT PER 400 CFM SUPPLY AIR.
6. ARRANGE PIPING CONNECTIONS TO ALL EQUIPMENT TO ALLOW EASY REMOVAL OF EQUIPMENT, SUB-ASSEMBLIES, COILS, FANS, MOTORS, FILTERS, ACCESS PANELS, ETC... PROVIDE UNIONS, FLANGES AND VALVES AT CONNECTIONS. PROVIDE AND INSTALL VICTAULIC JOINTS AT COILS, REF. SPECIFICATIONS. PLACE STOP VALVES ON SYSTEM SIDE OF REMOVABLE PIPE SECTIONS.
7. CONTRACTOR SHALL FIELD MEASURE STRUCTURAL ELEMENTS AND COORDINATE EQUIPMENT, PIPING AND DUCT ROUTING TO FIT EXISTING CONSTRUCTION. PROVIDE OFFSETS, BOOTS FOR ENVELOP OBSTRUCTIONS THAT CANNOT BE AVOIDED. CONSTRUCTION SHALL BE PER SMACNA FIGURE 2-10.

## AIR DEVICE SCHEDULE

| MARK | DESCRIPTION |
|---|---|
| A | CEILING DIFFUSER – 24" X 24" FACE, PATTERN TYPE, STEEL CONSTRUCTION, OBD/RADIATION DAMPER, WHITE FINISH, U.L. LISTED PRICE SCD |
| B | CEILING RETURN GRILLE – 24" X 24" PERFORATED FACE, STEEL CONSTRUCTION, RADIATION DAMPER, WHITE FINISH, U.L. LISTED PRICE PDFR |
| C | CEILING EXHAUST GRILLE – 24" X 24" PERFORATED FACE, STEEL CONST., OBD/RADIATION DAMPER, WHITE FINISH, NECK SIZE SHOWN, U.L. LISTED PRICE PDDR |

NOTES:

1. REFER TO ARCHITECTURAL REFLECTED CEILING PLAN TO VERIFY CEILING TYPES FOR AIR DEVICES.
2. ALL CEILINGS ARE FIRE RATED PER U.L. LISTINGS ON ARCHITECTURAL DRAWINGS. PROVIDE FIRE PROTECTION FOR ALL CEILING DEVICES PER DETAIL 13/M-17 AND SPECIFICATIONS.





### 6 KITCHEN UPBLAST EXHAUST FAN DETAIL

NO SCALE

NOTES

1. ARCHITECTURAL ROOF CURB INSTALLATION REQUIREMENTS SHALL SUPERCEDE THIS DETAIL.
2. INSTALL SHEETMETAL COVERING OVER WOOD BLOCKING IN THE AIRSTREAM OR OPEN TO THE CEILING CAVITY.





### 4 EXTERNALLY INSULATED DUCT SUPPORT DETAIL

NO SCALE

NOTES:

1. ROUND MEDIUM PRESSURE DUCT MAY BE SUPPORTED WITH DUCT STRAPS.
2. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.





### 2 DUCTWORK DETAIL

NO SCALE

NOTES:

1. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.





### 5 AIR DEVICE DETAIL

NO SCALE

NOTES:

1. RADIATION DAMPER SHALL ONLY BE PROVIDED IN CEILING DEVICES INSTALLED IN RATED CEILING ASSEMBLIES. REFER TO ARCHITECTURAL REFLECTED CEILING PLAN TO DETERMINE WHICH, IF ANY, CEILINGS ARE RATED.
2. REFER TO SPECIFICATIONS OF FOR ADDITIONAL INFORMATION AND REQUIREMENTS.




| TAP SIZE | ROD SIZE | DAMPER THICKNESS |
|---|---|---|
| UP TO 10" | 1/4" | 20 GA |
| OVER 10" | 3/8" | 18 GA |


HARDWARE MANUFACTURERS SHALL BE VENTLOCK, AMERICAN ELGEN, YOUNG AND DURO-DYNE.

### 3 DUCT TAP CONNECTION DETAIL

NO SCALE

NOTES:

1. DELETE CONICAL SECTION IF TOO LARGE FOR THE DUCT.
2. REFER TO SPECIFICATIONS OF FOR ADDITIONAL INFORMATION AND REQUIREMENTS.




### 1 MECHANICAL - ELECTRICAL COORDINATION DETAIL

NO SCALE

NOTES:

1. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD.
SUGAR LAND, TX 77479

SEAL

STATE OF TEXAS
TYLER W. HERRING
106052
LICENSED PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

MECHANICAL NOTES AND DETAILS
S-M2.01


STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM (713) 305-6282 | TEXAS ENG. FIRM REG. NO. F-018537-00


2025 ALL RIGHTS RESERVED


1300 W. SAM HOUSTON PARKWAY N., SUITE 175, HOUSTON, TX 77043





## 5 RESIDENTIAL CLOTHES DRYER FLUE VENT

NO SCALE

NOTES:

1. VENT TERMINATION AT WALL FOR STACKABLE WASHER/DRYER SHALL BE AT 60" AFF.
2. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.





## 4 SUPPLY/EXHAUST KITCHEN PLENUM DETAIL

NO SCALE

NOTES:

1. xxxxx





## 3 ROOF EXHAUST FAN AND VENT DETAIL

NO SCALE


NOTES:

1. NO WOOD BLOCKING SHALL BE LEFT EXPOSED IN THE CEILING PLENUM. COVER ALL EXPOSED WOOD WITH 1/2" SHEETROCK OR 20 GAUGE GALVANIZED SHEETMETAL.
2. ROOF VENT WILL NOT HAVE FAN/MOTOR ASSEMBLY, DISCONNECT SWITCH OR OBD.
3. ARCHITECTURAL ROOF CURB INSTALLATION REQUIREMENTS SHALL SUPERCEDE THIS DETAIL WHERE APPLICABLE.
4. ALL FANS SCHEDULED TO BE PROVIDED WITH 140MPH WIND RATING, INCLUDING FACTORY PROVIDED CURB. CURB INSTALLATION SHALL FOLLOW MANUFACTURER'S REQUIREMENTS FOR SECURING TO ROOF AND EQUIPMENT WHERE IT DIFFERS FROM THE DETAIL.
5. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.




## 2 INLINE EXHAUST FAN DETAIL

NO SCALE




## 1 CABINET EXHAUST FAN

NO SCALE

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD.
SUGAR LAND, TX 77479

SEAL

STATE OF TEXAS
TYLER W. HERRING
106052
LICENSED PROFESSIONAL ENGINEER
07.18.2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

MECHANICAL DETAILS (CONT'D.)

S-M2.02

STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM | (713) 300-4080
TEXAS ENG. FIRM REG. NO. F-018337-00
2025, ALL RIGHTS RESERVED
1300 W. SAM HOUSTON PARKWAY S., SUITE 125, HOUSTON, TX 77042

# ELECTRICAL AND LOW VOLTAGE LEGEND AND SYMBOLS

- A — TYPE 'A' LIGHT FIXTURE
- LIGHT FIXTURE WITH EMERGENCY BACKUP
- EXIT SIGN/EXIT SIGN WITH DIRECTIONAL ARROW
- EMERGENCY EGRESS LIGHT FIXTURE
- WALL MOUNTED FIXTURE OR SCONCE
- CEILING DOWNLIGHT OR CYLINDER
- WALL PACK FIXTURE
- INV — LIGHTING INVERTER

- $, $^{3}$, $^{4}$ — 20A, 277V TOGGLE/3-WAY/4-WAY SWITCH
- $^{P}$ — 20A, 277V MOMENTARY 3-POSITION TOGGLE SWITCH
- $^{K}$ — 20A, 277V, MOMENTARY 3-POSITION KEY SWITCH
- $^{2}$, $^{3}$, $^{4}$ — 20A, 277V MAINTAINED 2-POSITION/3-WAY/4-WAY KEY SWITCH
- $^{LT}$ — 20A, 277V TOGGLE SWITCH W/ INTEGRAL NIGHT LIGHT
- $^{MP}$ — MOTOR RATED ON/OFF SWITCH, MP W/ PILOT LIGHT (SWITCH RATING SHALL BE ≥ UPSTREAM OCPD & VOLTAGE)
- DPST$ — DOUBLE POLE SINGLE THROW (DPST) SWITCH WITH RED PILOT LIGHT.
- TDR — TIMER SWITCH

## NETWORK LIGHTING CONTROLS

- MB — MULTIBUTTON LOW VOLTAGE LIGHTING SWITCH PROVIDE NUMBER OF BUTTONS INDICATED IN SINGLE PLATE.
- MD — MULTIPLE DIMMER SWITCHES PROVIDE NUMBER OF SWITCHES INDICATED IN SINGLE PLATE.
- MK — MULTIPLE KEY TYPE SWITCHES PROVIDE NUMBER OF SWITCHES INDICATED IN SINGLE PLATE.
- VDC — WALL SENSOR SWITCH
- $D — 20A, 277V, STANDALONE DIMMER SWITCH (DISPLAY CABINET)
- OCC — 360° CEILING SENSOR
- OCW — 180° CEILING SENSOR
- OCC — CEILING SENSOR
- OC — WALL MOUNT SENSOR
- PCO — DAYLIGHT PHOTOSENSOR
- RC / RCK — LIGHTING ROOM CONTROLLER/POWER PACK
- ELR — EMERGENCY LIGHTING RELAY/CONTROL UNIT
- PLC — PLUG LOAD CONTROLLER

- 20A, 125V SIMPLEX/DUPLEX/QUAD RECEPTACLE
- GFI — 20A, 125V DUPLEX RECEPTACLE WITH GFCI PROTECTION
- GFI WP — 20A, 125V DUPLEX RECEPTACLE WITH GFCI PROTECTION AND WEATHERPROOF COVER.
- GFI — REMOTE GFCI DEVICE, REF SPECS AND EDF GFI DETAIL.
- USB-A — 20A, 125V DUPLEX/QUAD RECEPTACLE W/ USB-A PORTS PROVIDE 2-5A PORTS PER DEVICE — HUBBELL USB20A5
- IG — 20A, 125V SIMPLEX/DUPLEX/QUAD IG/COMPUTER RECEPTACLE
- GFI IG — 20A, 125V, IG/COMPUTER DUPLEX RECEPTACLE WITH GFCI
- PLUG LOAD CONTROLLED DUPLEX
- NEMA IEC CS — NEMA/IEC/CS NUMBERED POWER OUTLET MATCH PROVIDED EQUIPMENT CONNECTION OR CIRCUIT.
- TV IG — 20A, 125V IG DUPLEX RECEPTACLE AT PROJECTOR, TV, OR INTERACTIVE MEDIA LOCATION.
- LOW VOLTAGE OUTLET
- CEILING MOUNTED RECEPTACLE
- CEILING MOUNTED LOW VOLTAGE OUTLET
- SINGLE SERVICE FLOOR BOX WITH DUPLEX/QUAD REC
- SINGLE SERVICE FLOOR BOX WITH DUPLEX/QUAD IG REC
- SINGLE SERVICE LOW VOLTAGE FLOOR BOXES
- MULTI SERVICE FLOOR BOX WITH QUAD/QUAD IG REC
- CR — CORD REEL
- DC — DROP CORD
- EPO — EMERGENCY POWER OFF (EPO) SWITCH
- PB — PUSH BUTTON
- SP — TELEPOWER POLE

- J — J-BOX
- CEILING MOUNTED J-BOX
- CA — J-BOX FOR ACCESS CONTROL DEVICE
- HD — JUNCTION BOX AND FINAL CONNECTION TO HAND DRYER BY DIVISION 26.
- HDWR — JUNCTION BOX AND FINAL CONNECTION TO ELECTRIFIED DOOR HARDWARE BY DIVISION 26.
- HEAT — JUNCTION BOX AND FINAL CONNECTION TO HEAT TRACE EQUIPMENT BY DIVISION 26.
- WC — JUNCTION BOX AND FINAL CONNECTION TO POWERED PLUMBING EQUIPMENT BY DIVISION 26.
- SF — JUNCTION BOX AND FINAL CONNECTION TO SYSTEM FURNITURE BY DIVISION 26.

- CONTACTOR
- NON-FUSED DISCONNECT SWITCH
- NON-FUSED DOUBLE THROW DISCONNECT
- FUSED DISCONNECT SWITCH
- DISCONNECT/CB WITH SHUNT TRIP
- ENCLOSED CIRCUIT BREAKER
- MOTOR STARTER 'VFD' INDICATES VARIABLE FREQUENCY DRIVE MOTOR STARTER
- MOTOR STARTER WITH INTEGRAL DISCONNECT
- MOTOR
- TC — TIME CLOCK

- ELECTRICAL PANELBOARD
- ELECTRICAL METER
- SPD — TVSS OR SPD
- GANN — GENERATOR REMOTE ANNUNCIATOR

- LOW VOLTAGE CABLING PATHWAY, REF. SPECIFICATIONS

## KITCHEN SYMBOL LEGEND

- LOAD CENTER, BY FOOD SERVICE PROVIDE UNDERGROUND CONDUIT STUBBED UP AT LOAD CENTER LOCATION PER SUBMITTAL SHOP DRAWINGS.
- P — POINT OF SALE EQUIPMENT, BY FOOD SERVICE. PROVIDE UNDERGROUND CONDUIT STUBBED UP POS LOCATION PER SUBMITTAL SHOP DRAWINGS.
- F — REMOTE FIRE PULL, REFERENCE INSTALLATION DETAIL
- B — BELL/BUZZER WITH 120V TO LOW VOLTAGE TRANSFORMER
- D — DROP CORD
- DB — DOORBELL BUTTON
- V — CEILING STROBE FOR ENTRAPMENT ALARM
- V CLR/FRZR — WALL STROBE FOR ENTRAPMENT ALARM

## COORDINATION SYMBOL LEGEND

- DDC — HVAC CONTROL PANEL. REQUIRES POWER AND DATA CONNECTIONS WITHIN CABINET COOR EXACT LOCATION AND REQUIREMENTS WITH CONTROLS CONTRACTOR PRIOR TO ROUGH-IN.
- SD — SMOKE DAMPER
- FSD — FIRE/SMOKE COMBINATION DAMPER
- M / MD — MOTORIZED DAMPER

## SITE PLAN

- UTILITY POLE
- POLE MOUNTED TRANSFORMER BANK
- SITE POLE LIGHT
- UGE — FLUSH IN GRADE ELECTRICAL PULL BOX
- LV UG — FLUSH IN GRADE, LOW VOLTAGE HAND HOLE
- CONCRETE BOLLARD
- (X)PP — POWER POLE
- (X)SP — SERVICE POLE OR RACK
- (X)XP — XFMR POLE
- (X)LVP — LOW VOLTAGE POLE
- (X)TP — TRANSITION POLE
- OHP — OVERHEAD POWER WIRING
- 480V — 480V OVERHEAD POWER WIRING
- UGP — UNDERGROUND PRIMARY ELECTRICAL
- UGS — UNDERGROUND SECONDARY ELECTRICAL
- UGE — UNDERGROUND EMERGENCY ELECTRICAL

## DIVISION 28 LEGENDS

### FIRE ALARM

- F — FIRE ALARM PULL STATION W/ STOPPER II
- F / S — WALL FIRE ALARM AUDIO/VISUAL DEVICE
- WP-S — OUTDOOR WEATHERPROOF FIRE AUDIO/VISUAL DEVICE
- H — WALL FIRE ALARM AUDIO DEVICE
- V — WALL FIRE ALARM VISUAL DEVICE
- H/S — CEILING FIRE ALARM AUDIO/VISUAL DEVICE
- S — CEILING FIRE ALARM AUDIO DEVICE
- V — CEILING FIRE ALARM VISUAL DEVICE
- DUCT SMOKE DETECTOR
- I / S — CEILING SMOKE DETECTOR
- H — CEILING HEAT DETECTOR
- CO — CEILING CARBON MONOXIDE DETECTOR
- S/CO — CEILING COMBINATION SMOKE/CARBON MONOXIDE DETECTOR
- FR — FIRE ALARM RELAY FOR STAGE SOUND RACK OVERRIDE
- BEAM SMOKE DETECTOR
- FANN — FIRE ALARM REMOTE ANNUNCIATOR OR LOCAL OPERATOR'S CONSOLE
- FACP — FIRE ALARM CONTROL PANEL
- FAPS — FIRE ALARM POWER SUPPLY/AMPLIFIER

- G — INDICATES DEVICE WITH PROTECTIVE GUARD
- WG — INDICATES DEVICE WITH WIRE GUARD
- HC — INDICATES DEVICE RATED FOR HAZARDOUS CONDITIONS
- SD — SMOKE DAMPER
- FSD — FIRE/SMOKE COMBINATION DAMPER

## MULTI-SERVICE FLOOR BOX NOTES

FLOOR POWER AND LOW VOLTAGE

PROVIDE HEAVY-DUTY MULTI-GANG FLUSH IN GRADE OR FIRE RATED POKE-THRU OUTLET WITH HEAVY DUTY METAL HINGED COVER WITH CABLE EXIT SLOT.
FLOOR BOX MUST BE RATED FOR INSTALLATION IN GRADE.

FOR EACH FLOOR BOX PROVIDE:
1. PROVIDE:
   - 1.A. ONE QUAD OR TWO DUPLEX RECEPTACLES.
   - 1.B. PROVIDE IG RECEPTACLES WHERE SHOWN.
   - 1.C. POWER CONNECTION TO TABLE (WHERE SHOWN)
2. BLANK STAINLESS STEEL COVER FOR UN-USED GANGS.
3. PROVIDE ONE 3/4"C UNDERGROUND CONDUIT FOR POWER.
4. PROVIDE ONE 1"C UNDERGROUND CONDUIT WITH WATERPROOF INNER DUCT FOR DATA.
5. PROVIDE ONE 1"C UNDERGROUND CONDUIT WITH WATERPROOF INNER DUCT FOR LOW VOLTAGE CABLING
6. PROVIDE DIVIDERS TO MAINTAIN SEPARATION BETWEEN SERVICES.

UNDERGROUND CONDUITS MUST BE WATER TIGHT TO PREVENT MOISTURE ENTERING CONDUITS.
DO NOT COMBINE CONDUIT FOR POWER & LOW VOLTAGE.

REFERENCE FLOOR PLANS AND SPECIFICATIONS FOR QUANTITY OF DATA DROPS AND ADDITIONAL INFORMATION.

COORDINATE WITH ARCHITECT TO PROVIDE COVER/RING TO MATCH FLOOR MATERIAL AND SUBMIT COVER FINISH FOR ARCHITECT TO SELECT PRIOR TO ORDERING.

## GENERAL NOTES / TAGS

| | |
|---|---|
| +18" | INDICATES DEVICES AT +18" AFF |
| +42" | INDICATES DEVICES AT +42" AFF |
| +96" | INDICATES DEVICES AT +96" AFF |
| +12 FT | INDICATES DEVICES AT +12 FT AFF, ETC. |
| * | INDICATES DEVICES ABOVE COUNTER, REF ARCH |
| CLG | INDICATES DEVICES AT CEILING |
| PMR | INDICATES PEDESTAL MOUNTED DEVICE, REF PMR DETAIL |
| TV | INDICATES DEVICES AT TELEVISION/DISPLAY LOCATION |
| IM | INDICATES DEVICES AT INTERACTIVE MEDIA LOCATION |
| PROJ | INDICATES DEVICES AT PROJECTOR LOCATION |
| S | INDICATES SURFACE MOUNTED DEVICE |
| IEC | INDICATES IEC POWER OUTLET |
| NEMA | INDICATES NEMA NUMBERED POWER OUTLET |
| GFI | INDICATES GROUND FAULT INTERRUPT (GFI) PROTECTION |
| WP | INDICATES WEATHERPROOF DEVICES |
| GFI WP | INDICATES GFI PROTECTED WEATHERPROOF DEVICE |
| G | INDICATES DEVICE WITH PROTECTIVE GUARD |
| WG | INDICATES DEVICE WITH WIRE GUARD |
| 3R | INDICATES NEMA 3R RATED DEVICE |
| 4XSS | INDICATES NEMA 4XSS RATED DEVICE |
| EM | INDICATES DEVICE ON EM/STANDBY POWER |
| VFD | INDICATES VARIABLE FREQUENCY DRIVE (VFD) |
| E | EXISTING DEVICES TO REMAIN |
| D | EXISTING DEVICES TO BE DEMO/REMOVED |
| R | EXISTING DEVICES TO BE RELOCATED |
| REP | EXISTING DEVICES TO BE REPLACED |
| | (X) = (E) FOR EXISTING |
| | (X) = (D) FOR DEMO |
| | (X) = (R) FOR RELOCATION |
| | (X) = (N) FOR NEW |

- HOMERUN TO CIRCUIT NOTED

1. RECEPTACLES AND DATA OUTLETS SHALL BE MOUNTED AT +18" AFF UNLESS NOTED ON THE DRAWINGS.
2. REF. SPECIFICATIONS FOR MOUNTING HEIGHT OF OTHER DEVICES.
3. ELECTRICAL RECEPTACLES, TELEPHONES, ETC... ARE SHOWN FOR GENERAL LOCATION. HEIGHTS ARE NOTED SO THE ESTIMATOR WILL KNOW WHETHER THEY ARE ABOVE OR BELOW COUNTERS. PRIOR TO INSTALLATION, REVIEW THE ARCHITECTURAL DRAWINGS AND SPECIFICATIONS. IN THE EVENT OF CONFLICT, THE ARCHITECT'S LOCATION WILL GENERALLY PREVAIL BUT SHOULD BE CLARIFIED BY RFI. PROVIDE DEVICES SHOWN ON THE ELECTRICAL DRAWING EVEN IF NOT SHOWN ON ARCHITECTURAL DRAWINGS.
4. COORDINATE POWER AND DATA WITH THE FURNITURE SUPPLIER PRIOR TO ROUGH-IN. AT CASEWORK WITH KNEE SPACE, MOUNT RECEPTACLES AND DATA OUTLETS IN KNEE SPACE. COORDINATE WITH ARCHITECT AND FURNITURE SUPPLIER TO ENSURE THAT PROTECTIVE GROMMETS ARE PROVIDED IN THE COUNTER.
4. ALL DEVICES SHOWN AT THE SAME LOCATION AND ELEVATION SHALL BE GROUPED TOGETHER AND SPACED 2 INCHES BETWEEN BOXES.
5. PROVIDE SS COVER PLATE FOR ALL EMPTY JBOX.
6. ALL NON-LOCKING 125V AND 250V, 15A AND 20A RECEPTACLES SHALL BE TAMPER RESISTANT TYPE.


ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |


S

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD.
SUGAR LAND, TX 77479

SEAL

STATE OF TEXAS — GEORGE L. STANTON — 38582 — REGISTERED — PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL AND FIRE ALARM SCHEDULES
s-E.000


STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM (713) 305-6266


TEXAS ENG. FIRM REG. NO. F-13932 | © 2025 ALL RIGHTS RESERVED


12999 W. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77040

PROVIDE CONDUIT & SLEEVES THRU FIRE WALLS, WALLS AND FLOORS FOR LOW VOLTAGE CABLING WIRING, ETC.

ALL CONDUIT & J-BOXES FOR LOW VOLTAGE CABLING SHALL BE PROVIDED AND INSTALLED BY THE ELECTRICAL CONTRACTOR. ALL LOW VOLTAGE CABLING IN WALLS, EXPOSED AREAS AND ABOVE INACCESSIBLE CEILINGS SHALL REQUIRE CONDUIT AND J-BOXES. REFERENCE SPECIFICATIONS AND TECHNOLOGY DOCUMENTS FOR ADDITIONAL INFORMATION/REQUIREMENTS.

PULL BOXES AND BELOW GRADE CONDUIT FOR LOW VOLTAGE CABLING, WIRING, ETC. BY ELEC CONTRACTOR.

## FIRE ALARM SYSTEM DESCRIPTION AND SEQUENCE OF OPERATION

1. FIRE ALARM SYSTEM SHALL BE DESIGNED TO MEET NFPA REQUIREMENTS AS WELL AS CITY AND NATIONAL BUILDING CODES. PROVIDE COMPLETE FIRE ALARM SYSTEM, DEVICES AND WIRING.
2. INSTALL FIRE ALARM CONTROL PANEL IN RECEPTION AREA. INSTALL REMOTE POWER SUPPLY PANELS IN MECHANICAL/ELECTRICAL ROOMS.
3. FIRE ALARM PANEL, POWER SUPPLIES, DEVICES, ETC. SHALL BE MANUFACTURED BY THE SAME MANUFACTURER AS THE FIRE ALARM CONTROL PANEL.
4. FIRE ALARM REMOTE POWER SUPPLIES AND PANELS SHALL BE LOCATED IN MECHANICAL OR ELECTRICAL ROOMS ONLY. DO NOT LOCATE IN STORAGE ROOMS, DATA CLOSETS OR FINISHED SPACES.
4. PROVIDE AUDIBLE, INTELLIGIBLE AND VISUAL ALARM COVERAGE OF THE AREA OF RENOVATION AS REQUIRED BY CODE.
5. PROVIDE SMOKE DETECTORS AT EACH FIRE ALARM PANEL, REMOTE TRANSPONDER PANEL, BOOSTER PANEL AND REMOTE ANNUNCIATOR PER NFPA 72.
6. IN ADDITION TO THE SPECIFIED FIRE ALARM EQUIPMENT, THE FIRE ALARM CONTRACTOR SHALL PROVIDE
   6.A. SURGE PROTECTORS FOR ALL NEW 120V POWER CONNECTIONS TO FIRE ALARM EQUIPMENT.
   6.B. SURGE PROTECTORS FOR ALL SIGNALING LINE CIRCUITS (SLC), NOTIFICATION CIRCUITS AND INITIATING CIRCUITS CONNECTED TO THE FIRE ALARM CONTROL PANEL WHICH LEAVE THE BUILDING.
7. SHOULD ANY DETECTOR, MONITOR OR PULL STATION ACTIVATE, ALL SPEAKERS SHALL SOUND AND STROBES FLASH. AIR HANDLING EQUIPMENT SHALL BE DEACTIVATED. AN ALARM SIGNAL SHALL BE SENT TO A REMOTE LOCATION VIA AUTOMATIC DIALER. ALSO, DE-ENERGIZE SUPPLY FANS, EXHAUST FANS AND OTHER AIR CIRCULATING DEVICES IF 2000 CFM OR OVER, SERVING THE AREA IN ALARM.
8. ALL LOW VOLTAGE WIRING SHALL BE FPLP RATED WIRE, WITH MINIMUM WIRE SIZE PER SPECIFICATIONS.
   8.A. PLENUM RATED CABLE ABOVE ACCESSIBLE CEILING SHALL BE SUPPORTED BY J-HOOKS, SPACED AT FOUR (4) FEET ON CENTER.
   8.B. INSTALL FIRE ALARM CABLES IN CONDUIT FOR AREAS WITHOUT CEILING OR ABOVE INACCESSIBLE CEILINGS.
   8.C. EXPOSED CONDUIT IN FINISHED SPACES SHALL BE ALLOWED WHERE NO OTHER OPTION EXISTS AND ONLY WITH PRIOR WRITTEN APPROVAL BY THE OWNER. ALL EXPOSED CONDUIT SHALL BE PAINTED TO MATCH.
   8.D. ALL CABLING THROUGH WALLS, FIRE WALLS AND FLOORS SHALL BE INSTALLED IN SLEEVES WITH PROTECTIVE BUSHINGS ON BOTH ENDS.
9. FIRE ALARM SYSTEM SHALL BE MONITORED BY A UL LISTED CENTRAL RECEIVING STATION.
10. INTERLOCK LIGHTING CONTROL PANELS WITH FIRE ALARM SYSTEM TO ENABLE ALL LIGHTING UPON ACTIVATION.
11. REFER TO THE WRITTEN SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.

## FIRE ALARM SYSTEM NOTES

1. GENERAL CONTRACTOR SHALL COORDINATE WITH ELECTRICAL AND FIRE ALARM SUBCONTRACTOR FOR LOCATIONS OF REMOTE POWER SUPPLIES. FIRE ALARM POWER SUPPLIES ARE NOT SHOWN ON THIS DRAWING AND SHALL BE LOCATED BY FIRE ALARM SUBCONTRACTOR IN ORDER TO ACCOMMODATE HIS FIRE ALARM SYSTEM BATTERY AND VOLTAGE DROP CALCULATIONS PER MANUFACTURER'S RECOMMENDATION & NFPA REQUIREMENTS. ELECTRICAL CONTRACTOR SHALL INCLUDE ADDITIONAL DEDICATED 120V CIRCUITS IN BASE BID TO SERVE FIRE ALARM POWER SUPPLIES IN DIFFERENT AREAS. PROVIDE 2–12 +12G, 3/4"C AND SPARE 20A/1P CB(S) IN LOCAL LIFE SAFETY EMERGENCY 120V PANELS TO SERVE FIRE ALARM REMOTE POWER SUPPLIES.
2. FIRE ALARM CONTRACTOR IS RESPONSIBLE FOR DESIGN AND FOR FINAL CORRECT LOCATION OF DEVICES TO RELIEVE NUISANCE ALARMS, SUCH AS INSTALLING A HEAT DETECTOR IN FRONT OF AN OVEN WHICH WILL RELEASE STEAM, THUS POTENTIALLY SETTING OFF THE ALARM. ALSO, THE CONTRACTOR IS RESPONSIBLE FOR DETECTORS REQUIRED BY CODE EVEN IF NOT SHOWN ON DRAWING, LIKE A CLOSET. IF THERE IS UNCERTAINTY, BRING UP DURING THE BID PROCESS AND THEY WILL BE ADDRESSED DURING THE BIDDING PROCESS.
3. FIELD VERIFY ENVIRONMENTAL ISSUES THAT CAN ADVERSELY AFFECT OPERATION OF SMOKE DETECTORS. DO NOT LOCATE NEAR AIR FLOW DEVICES LEADING TO PREMATURE BUILD UP OF DUST CAUSING NUISANCE TROUBLE SIGNALS. DEVICE RELOCATION OR TYPE CHANGE WILL BE COVERED UNDER WARRANTY.

## FIRE ALARM SCOPE OF WORK

1. THERE IS AN EXISTING FIRE ALARM SYSTEM IN EACH BUILDING.
   1.A. TEST THE EXISTING SYSTEM PRIOR TO BEGINNING DEMO. NOTE ANY FAULTS OR TROUBLES AND PROVIDE A WRITTEN REPORT TO THE OWNER.
   1.B. EXPAND THE EXISTING SYSTEM AS REQUIRED TO INTEGRATE THE NEW DEVICES IN THE AREA OF RENOVATION.
2. PROVIDE WIRING AND DEVICES AS INDICATED TO PROVIDE COMPLETE AUDIBLE, INTELLIGIBLE AND VISUAL ALARM COVERAGE OF RENOVATED AREAS AS REQUIRED BY CODE.
   2.A. PROVIDE SMOKE DETECTOR COVERAGE OF ALL STORAGE ROOMS AND ADDITIONALLY AS SHOWN ON THE DRAWINGS.
   2.B. PROVIDE HEAT DETECTOR COVERAGE OF THE KITCHEN, CUSTODIAL ROOMS, AND ADDITIONALLY AS SHOWN ON THE DRAWINGS.
   2.C. PROVIDE DUCT MOUNTED DETECTORS AT EACH NEW AIR HANDLING UNIT SUPPLY AND RETURN CONNECTION EXCEEDING 2000 CFM. IF FREE AIR RETURN, PROVIDE FREE AIR DETECTOR COVERAGE OF THE RETURN AIR OPENINGS TO THE MECHANICAL ROOM. ENSURE AIR FLOW CANNOT PREVENT OPERATION OF THE DETECTORS AND PROVIDE ADEQUATE CLEARANCE PER NFPA 72.
   2.D. CONTROL RELAYS SHALL BE LOCATED WITHIN 3 FT OF THE CONTROLLED CIRCUIT OR APPLIANCE.
3. PROVIDE SMOKE DETECTORS AT EACH NEW FIRE ALARM PANEL, REMOTE TRANSPONDER PANEL, BOOSTER PANEL AND REMOTE ANNUNCIATOR PER NFPA 72.
4. PROVIDE LED REMOTE ALARM WITH ENGRAVED STAINLESS STEEL PLATE WHERE DUCT DETECTORS ARE NOT LOCATED IN MECHANICAL ROOM, LOCATED ABOVE CEILINGS OR WHERE MOUNTED TOO HIGH OR VIEW IS BLOCKED BY DUCTWORK IN MECHANICAL ROOM.
   4.A. REMOTE LED LIGHT INDICATOR FOR DUCT SMOKE DETECTORS SHALL BE MOUNTED FLUSH IN CEILING OR MOUNTED IN WALL AT +7'FT.
   4.B. STAINLESS STEEL PLATE SHALL BE ENGRAVED WITH THE DUCT SMOKE DETECTOR AS–BUILT IDENTIFICATION NUMBER.
5. REFER TO THE WRITTEN SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.

## SPARES

1. THE FIRE ALARM CONTRACTOR SHALL INCLUDE IN HIS BID THE COST TO PROVIDE AND INSTALL THE ADDITIONAL SPARE PARTS AND ASSOCIATED CABLING PER THE SPECIFICATIONS. SPARES SHALL BE INSTALLED AS INSTRUCTED BY THE OWNER. UNINSTALLED DEVICES SHALL BE DELIVERED TO THE OWNER AS ATTIC STOCK.

## GENERAL RENOVATION AND REMODELING NOTES

1. READ ALL MEP AND ARCH. DRAWINGS TO IDENTIFY AREAS OF RENOVATION AND SCOPE OF WORK.
2. ALL RENOVATION AND DEMOLITION WORK SHALL NOT AFFECT AREAS NOT INCLUDED IN THE AREAS OF WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE CONTINUITY OF ALL SERVICES (POWER, TELEPHONE, FIRE ALARM, DATA, SECURITY, ETC.) IN NON–DEMOLITION/RENOVATION AREAS. ALL SERVICES SHALL BE MAINTAINED AT ALL TIMES.
3. ALL OUTAGES AFFECTING NON–DEMOLITION/RENOVATION AREAS SHALL BE SCHEDULED WITH THE OWNER WITH A MINIMUM 2 WEEKS ADVANCE NOTICE. OUTAGES SHALL BE COORDINATED WITH OTHER TRADES TO MINIMIZE THE QUANTITY AND IMPACT ON BUILDING OPERATION.
4. THIS ELECTRICAL DRAWING ONLY SHOWS SOME EXISTING ELECTRICAL PANELS, DEVICES AND LIGHT FIXTURES IN AREAS OF RENOVATION. ALL OTHER ELECTRICAL EQUIPMENT, WIRING DEVICES, LOW VOLTAGE SYSTEMS, J–BOXES AND CONDUITS SHALL BE LOCATED AND FIELD VERIFIED BY CONTRACTOR.
5. CONTRACTOR SHALL FIELD VERIFY AND MARK UP THE FOLLOWINGS IN AREAS OF RENOVATION:
   5.A. EXISTING DATA, AUDIO, VIDEO, SPEAKERS AND OTHER LOW VOLTAGE OUTLETS AND DEVICES.
   5.B. EXISTING CEILING MOUNTED PROJECTORS.
   5.C. EXISTING SECURITY, CCTV, ACCESS CONTROL DEVICES.
   5.D. EXISTING FIRE ALARM DEVICES.
   5.E. EXISTING WIRELESS ACCESS POINTS AND GRID LABELING.
   5.F. EXISTING LIGHT FIXTURES AND SWITCHES.
   5.G. EXISTING ELECTRICAL DEVICES, J–BOXES, CONDUIT, WIRING, WIRING SUPPORTS, ETC.
   5.H. EXISTING ELECTRICAL SWITCHGEAR.
   5.I. EXISTING CONTROL PANELS AND CONTROL CIRCUITS.
   5.J. EXISTING HANGER WIRE FROM CONC. CEILING.
6. ALL REMOVED DEVICES SHALL BE OFFERED TO THE OWNER AS SALVAGE.
7. ALL EXISTING DEVICES SHALL BE REINSTALLED IN NEW CEILINGS AT SAME LOCATION EXCEPT WHERE SHOWN TO BE NEW.
8. CONDUIT/WIRE NOT TO BE REUSED SHALL BE REMOVED ALL THE WAY BACK TO THE UPSTREAM EQUIPMENT.
   8.A. PROVIDE ADDITIONAL SUPPORTS FOR EXISTING CONDUIT/WIRE TO REMAIN TO MEET CURRENT CODE REQUIREMENTS.
9. ANY MATERIAL THAT HAS SALVAGE VALUE SHALL BE OFFERED TO THE OWNER, AND IF ACCEPTED, DELIVERED TO HIS WAREHOUSE. IF NOT ACCEPTED IT SHALL BE PROPERLY DISPOSED OF WITH THE OTHER CONSTRUCTION DEBRIS.
10. RELOCATE CONDUIT AS NECESSARY TO ALLOW NEW OR MODIFIED CONSTRUCTION. REPAIR EXISTING ELECTRICAL SYSTEMS DAMAGED BY CONSTRUCTION ACTIVITES.
11. WHERE PARTIAL CIRCUITS OR SYSTEMS ARE TO BE REUSED, ENSURE THAT THEY REMAIN ACTIVE. WHERE EXISTING EQUIPMENT IS RELOCATED OR REPLACED WITH NEW, MODIFY, EXTEND AND RELOCATE EXISTING CIRCUIT TO CONNECT TO EQUIPMENT, UNLESS SHOWN TO HAVE NEW CIRCUIT.
12. WHERE AUXILIARY SYSTEMS SUCH AS SECURITY, DATA, SOUND, ETC. INTERFACE WITH EXISTING EQUIPMENT THAT IS REPLACED OR MODIFIED (MECHANICAL, ELECTRICAL OR PLUMBING), DISCONNECT AND RECONNECT THESE SYSTEMS.
13. WHERE NEW CIRCUIT BREAKERS ARE TO BE INSTALLED IN EXISTING PANELS OR SWITCHBOARD, VERIFY THAT THE CIRCUIT BREAKER WILL FIT IN THE ALLOTTED SPACE. PROVIDE NEMA 1 ENCLOSURE ADJACENT TO PANEL & WIRE CONNECT TO BUSSING IF THERE IS INSUFFICIENT SPACE.
14. WHERE PARTIAL CIRCUITS OR SYSTEMS ARE TO BE REUSED, ENSURE THAT THEY REMAIN ACTIVE. WHERE EXISTING EQUIPMENT IS RELOCATED OR REPLACED WITH NEW, MODIFY, EXTEND AND RELOCATE EXISTING CIRCUIT TO CONNECT TO EQUIPMENT, UNLESS SHOWN TO HAVE NEW CIRCUIT.
15. WHEN REPLACING LIGHTS AND CEILINGS, ENSURE THAT EXISTING DATA, TELEVISION AND PA CABLES TO REMAIN CONTINUE TO MEET THE CURRENT STANDARDS. FOR DATA CABLES, THIS IS THE IEEE 802.1. FOR TELEVISION AND PA CABLE, A FOUR INCH DISTANCE IS NEEDED FROM ALL LIGHT FIXTURES. NEW DROP LOCATION SHOULD BE WITHIN THREE FEET OF POWER OUTLET.
16. PAINT NEW AND EXISTING EXPOSED RACEWAY IN AREAS OF RENOVATION TO MATCH FINISHES.
17. ANY DAMAGE TO EXISTING BUILDING, ELECTRICAL EQUIPMENT, WIRING DEVICES, CONDUIT, WIRING, ETC. SHALL BE REPLACED BY THE CONTRACTOR AT NO COST TO THE OWNER. ALL MATERIALS USED FOR THE REPLACEMENT MUST MEET RENOVATION PROJECT STANDARDS.
18. INTERESTED CONTRACTORS MUST VISIT THE SITE PRIOR TO BIDDING TO BECOME FAMILIAR WITH THE PROJECT REQUIREMENTS AND EXISTING CONDITIONS AND SHALL INCLUDE IN THEIR PROPOSALS COSTS TO REPAIR, RELOCATE, MODIFY AND REMOVE EXISTING ELEMENTS AS REQUIRED TO COMPLETE INSTALLATION OF ALL SYSTEMS SHOWN ON THESE DRAWINGS.
19. SEE DRAWINGS FOR ADDITIONAL REQUIREMENTS.

## ELEC REQUIREMENTS FOR BUILDING RENOVATION

1. ELECTRICAL CONTRACTOR SHALL BEGIN FIELD VERIFYING ALL EXISTING BRANCH CIRCUITS FOR EXISTING AREAS TO BE RENOVATED IMMEDIATELY AFTER THE CONTRACT IS ISSUED.
2. ELECTRICAL CONTRACTOR SHALL FIELD VERIFY EXISTING CIRCUITS WITH OWNER'S MAINTENANCE PERSONNEL AFTER NORMAL BUILDING HOURS AS REQUIRED.
3. ELECTRICAL CONTRACTOR SHALL INCLUDE COST RELATED TO FIELD VERIFY EXISTING CIRCUITS IN BASE PROPOSAL.
4. FIND AND RECORD ALL EXISTING DEVICES IN CEILINGS, WALLS AND CASEWORK IN AREAS TO BE RENOVATED. PROVIDE A COPY OF THE FIELD VERIFIED DEVICE DRAWINGS TO OWNER PRIOR TO BEGINNING WORK.
5. ALL EXISTING DEVICES TO REMAIN SHALL BE REINSTALLED IN NEW CEILINGS AND WALLS EXCEPT WHERE INDICATED TO BE REMOVED/RELOCATED/REPLACED.
6. EXISTING DEVICES IN WALLS TO BE FURRED OUT OR RECEIVE NEW SURFACE TREATMENT SHALL REMAIN. EXTEND JBOX TO NEW WALL SURFACE AND RECONNECT TO EXISTING CIRCUITS. EXTEND WIRING/CABLING FROM NEAREST ACCESSIBLE POINT AS NECESSARY.
7. REINSTALL ALL DEVICES NOT SHOWN TO BE REMOVED.
8. EXISTING LIGHT FIXTURES SHALL REMAIN EXCEPT WHERE SHOWN AS NEW. EXTEND EXIST CONDUIT AND WIRE DOWN TO NEW LIGHT FIXTURES, REFERENCE SPECIFICATIONS FOR ADDITIONAL INFORMATION.
9. ALL EXISTING EXIT SIGNS SHALL BE REINSTALLED AND RECONNECTED TO EXISTING CIRCUITS EXCEPT IN CORRIDORS AND AREAS OF RENOVATION SHOWING NEW.
10. ALL NEW DEVICES IN EXISTING WALLS IN FINISHED SPACES SHALL BE INSTALLED FLUSH MOUNTED, NO EXPOSED CONDUIT OR WIREMOLD ALLOWED. CUT EXISTING WALLS AND PATCH/REPAIR TO MATCH EXISTING AS REQUIRED.
    10.1. DEVICES/CONDUIT IN CUSTODIAL, MECHANICAL AND ELECTRICAL ROOMS MAY BE EXPOSED AND SURFACE MOUNTED.
11. PROVIDE NEW DIRECTORY FOR ALL EXISTING AND NEW PANELS SHOWING FIELD VERIFIED CIRCUITS.
12. ANY FEEDER AND BRANCH CIRCUIT NOT TO BE REUSED SHALL BE REMOVED COMPLETELY UP TO CB IN EXISTING PANEL.
13. ANY CIRCUIT OR PARTIAL CIRCUIT TO BE REUSED SHALL REMAIN ACTIVE.

## GENERAL EQUIPMENT ELECTRICAL NOTE

THE ELECTRICAL DESIGN HAS BEEN COORDINATED FOR SPACE, INSTALLATION AND ELECTRICAL REQUIREMENTS WITH EQUIPMENT THAT IS SCHEDULED BY OTHER DIVISIONS. THE REQUIREMENTS FOR OTHER EQUIPMENT AND MODELS FROM ACCEPTABLE MANUFACTURERS HAVE NOT BEEN VERIFIED OR COORDINATED. THE GENERAL CONTRACTOR SHALL VERIFY THESE REQUIREMENTS PRIOR TO USING OTHER EQUIPMENT IN HIS BID AND INCLUDE ANY ADDITIONAL COSTS FOR INSTALLATION OF THE EQUIPMENT. THIS INCLUDES GENERAL CONSTRUCTION AND MEP COSTS.

ELECTRICAL CONTRACTOR SHALL COORDINATE WITH OWNER/OTHER TRADES FOR EXACT ELECTRICAL REQUIREMENTS OF EQUIPMENT PRIOR TO ORDERING CB(S). FIELD VERIFY EQUIPMENT NAMEPLATE RATINGS AND EQUIPMENT CONNECTION LOCATIONS WITH OTHER TRADES PRIOR TO ROUGH–IN.

TYPICAL OF HVAC EQUIPMENT, SHOP EQUIPMENT, KITCHEN EQUIPMENT, ELECTRIC ROLLUP DOORS, ETC.

## GENERAL ELECTRICAL NOTES

1. REFER TO THE WRITTEN SPECIFICATIONS FOR ADDITIONAL INFORMATION.
2. INSTALL SYSTEMS IN ACCORDANCE WITH THE NATIONAL ELECTRIC CODE.
3. PROVIDE LIGHT FIXTURE FIRE PROTECTION AND CONDUIT FIRE SEALING TO MAINTAIN FIRE RATING OF WALLS AND CEILINGS PER ARCHITECT'S SCHEDULE. REF. SPECIFICATIONS AND ARCH. DRAWINGS FOR ADDITIONAL INFORMATION.
4. ELECTRICAL RECEPTACLES, TELEPHONES, ETC... ARE SHOWN FOR GENERAL LOCATION. HEIGHTS ARE NOTED SO THE ESTIMATOR WILL KNOW WHETHER THEY ARE ABOVE OR BELOW COUNTERS. PRIOR TO INSTALLATION, REVIEW THE ARCHITECTURAL DRAWINGS AND SPECIFICATIONS. IN THE EVENT OF CONFLICT, THE ARCHITECT'S LOCATION WILL GENERALLY PREVAIL BUT SHOULD BE CLARIFIED BY RFI. PROVIDE DEVICES SHOWN ON THE ELECTRICAL DRAWING EVEN IF NOT SHOWN ON ARCHITECTURAL DRAWINGS.
5. COORDINATE POWER AND DATA WITH THE FURNITURE SUPPLIER PRIOR TO ROUGH–IN. AT CASEWORK WITH WIRE SPACE, MOUNT RECEPTACLES AND DATA OUTLETS IN KNEE SPACE. COORDINATE WITH ARCHITECT AND FURNITURE SUPPLIER TO ENSURE THAT PROTECTIVE GROMMETS ARE PROVIDED IN THE COUNTER.
6. DO NOT INSTALL ELECTRICAL PANELS AND TRANSFORMERS UNTIL 1/4" SCALE DRAWINGS SHOWING LOCATION OF THIS EQUIPMENT RELATIVE TO MECHANICAL/PLUMBING EQUIPMENT, DUCTWORK AND PIPING IS SUBMITTED AND APPROVED. NEC CODE CLEARANCE MUST BE MAINTAINED.
7. ELECTRICAL EQUIPMENT HAS BEEN COORDINATED WITH PIPING AND DUCTWORK. DO NOT RELOCATE PANELS WITHOUT PRIOR APPROVAL.
8. ELECTRICAL DEVICES IN FIRE RATED WALLS SHALL BE A MINIMUM OF 24" AWAY FROM DEVICES ON THE OPPOSITE SIDE OF THE WALL TO MAINTAIN FIRE RATING.
9. MINIMUM SIZE CONDUIT FOR POWER SHALL BE 3/4", MIN. SIZE FLEX CONDUIT MAY BE 1/2". MINIMUM SIZE CONDUIT FOR DATA SHALL BE 1"C. DO NOT COMBINE CONDUIT FOR DATA.
10. MAX. LENGTH FOR FLEX CONDUIT SHALL BE 6 FT. ALL FLEX CONDUIT SHALL BE LISTED FOR GROUNDING.
11. LIGHT FIXTURE WHIPS MAY BE MIN. 1/2" FLEX CONDUIT WITH MIN. #12 WIRE. LIGHT FIXTURE WHIPS SHALL BE NO MORE THAN 6 FT LONG.
12. PROVIDE GREEN GROUND WIRE WITH ALL CIRCUITS SIZED PER NEC. BOND GREEN GROUND WIRE TO EACH END OF CONDUIT.
13. GROUND TRANSFORMER SECONDARIES TO BUILDING STEEL AND GROUND ROD. PROVIDE CONDUIT TO PROTECT GROUNDING CONDUCTOR AND BOND EACH END OF CONDUIT TO GROUNDING SYSTEM. MIN. SIZE OF CONDUIT FOR GROUND WIRE SHALL BE 3/4"C.
14. PROVIDE J–BOXES, CONDUIT AND SLEEVES THRU ALL FIRE WALLS FOR DATA, TELEPHONE, SECURITY, FIRE ALARM AND SOUND SYSTEMS WIRINGS, ETC. SEE SPECIFICATIONS.
15. PROVIDE PULL BOXES, JUNCTION BOXES, WIRING TROUGHS AND CABINETS WHEREVER REQUIRED FOR PROPER INSTALLATION OF VARIOUS ELECTRICAL SYSTEMS.
16. WHERE PORTIONS OF INTERIOR RACEWAY SYSTEM ARE EXPOSED TO WIDELY DIFFERENT TEMPERATURES, PROVIDE AIR SEALING PER NEC TO PREVENT CIRCULATION OF AIR FROM WARMER TO A COOLER SECTION.
17. ALL WIRING SHALL BE 600 VOLT, SOFT DRAWN ANNEALED COPPER, 98% CONDUCTIVITY, CONTINUOUS FROM OUTLET TO OUTLET. MINIMUM WIRE SIZE #12. ALL WIRE SHALL BE STRANDED TYPE THHN OR THWN–2 (WET RATED FOR 90° C). ALL WIRES SHALL BE COLOR CODED WITH SAME COLOR CONNECTED TO SAME UNGROUNDED PHASE THROUGHOUT THE INSTALLATION.
18. ALL ELECTRICAL WIRING SHALL BE INSTALLED IN CONDUIT. NO SURFACE MOUNTED WIREMOLD SHALL BE ALLOWED IN FINISHED SPACES. MC CABLE SHALL BE ALLOWED INSIDE EXIST STUD WALLS OR CHASE WALLS.
19. PROVIDE AND INSTALL FINAL CONNECTIONS TO ALL EQUIPMENT PROVIDED BY OTHER TRADES AND/OR FURNISHED BY OWNER INCLUDING ALL NECESSARY CONDUIT, CORDS, PLUGS, WHIPS, HARDWIRING, ETC. IN PARTICULAR CONFIRM CONNECTION REQUIREMENTS WITH DELIVERED EQUIPMENT PRIOR TO ROUGH–IN.
20. ALL MATERIAL MUST BE NEW AND OF GOOD QUALITY AND SHALL BEAR THE STAMP OF APPROVAL OF THE UNDERWRITERS' LABORATORIES, INC. (U.L.).

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD.
SUGAR LAND, TX 77479

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING


ELECTRICAL AND FIRE ALARM NOTES

s-E.001


STANTON ENGINEERING GROUP
INFO@STANTON–ENG.COM | (713) 360–6080


TEXAS ENG. FIRM REG. NO. F–01853 | © 2025 ALL RIGHTS RESERVED


1200 W. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77043





SYMBOL: ▽

## 1 TYPICAL DATA OUTLETS

NO SCALE

NOTES:
1. PROVIDE DEEP 4 11/16" X 4 11/16" X 2 1/8", 2-GANG BACK BOX FOR ALL DATA OUTLETS.
   1.A. PROVIDE SINGLE GANG MUDRING FOR DATA OUTLETS WITH 1-4 DROPS.
   1.B. PROVIDE PULL STRING IN ALL LOW VOLTAGE CONDUITS.
2. LOW VOLTAGE CABLING AND DEVICES BY DIVISION 27.
3. REFERENCE TECHNOLOGY DRAWINGS FOR ADDITIONAL INFORMATION.





SYMBOL: ⊕ SYMBOL: ⊕

## 2 TYPICAL POWER & DATA OUTLET DETAIL

NO SCALE

NOTES:
1. LOCATE DEVICES GROUPED TOGETHER AS CLOSELY TOGETHER AS POSSIBLE.
   1.A. USE CADDY TSGB16, RBS16 OR SIMILAR MOUNTING BAR IN SHEETROCK WALLS.




SYMBOL: ⊕ SYMBOL: ⊕ SYMBOL: ⊕USB SYMBOL: ⊕GFI

## 3 TYPICAL ELECTRICAL DEVICES

NO SCALE

NOTES:
1. ALL DEVICES SHALL BE COLOR CODED PER SPECIFICATIONS WITH 302/304 STAINLESS STEEL, STANDARD SIZE, FACEPLATES.
2. ONLY SELECT RECEPTACLES ARE SHOWN HERE. PROVIDE SIMILAR LABELS ON ALL SWITCHES, NEMA POWER OUTLETS, ETC.
3. PROVIDE LABEL WITH RED TEXT READING "EMERGENCY" FOR DEVICES ON GENERATOR FED CIRCUITS.
4. PROVIDE TYPEWRITTEN OR PREMADE CIRCUIT LABELS INDICATING THE ELECTRICAL CIRCUIT ON:
   4.A. INSTALLED WIRING AT EACH SPLICE POINT
   4.B. EACH J-BOX ABOVE CEILING WITH WIRING INSTALLED OR MODIFIED AS PART OF THIS PROJECT.
   4.C. AFFIXED TO THE FRONT OF EACH NEW AND EXISTING DEVICE FACEPLATE IN THE AREA OF RENOVATION.
        CIRCUIT LABEL
        A. XX = PANEL DESIGNATION
        B. ## = AS-BUILT CIRCUIT DESIGNATION

XX-##

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD.
SUGAR LAND, TX 77479

SEAL




07.18.2025


MWA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL
DEVICE DETAILS

s-E.010


STANTON ENGINEERING GROUP
INFORMATION ONLY | TEXAS ENG. FIRM REG NO. F-18332-10
2025 ALL RIGHTS RESERVED
(713) 305-6080 | 1300 W. SAM HOUSTON PARKWAY N., SUITE 121, HOUSTON, TX 77043




## 10 MECHANICAL - ELECTRICAL COORDINATION DETAIL


NO SCALE

**COORDINATE WITH OTHER TRADES TO ENSURE NO PIPING AND DUCTWORK ABOVE ELECTRICAL EQUIPMENT AS SHOWN. PROVIDE WORKING CLEARANCE IN FRONT OF STARTERS, DISCONNECTS, PANELS, XFMRS AND ADDITIONALLY PER CODE.**




## 11 CONDUIT ROOF PENETRATION DETAIL

NO SCALE





## 7 EDF GFI PROTECTION DETAIL

NO SCALE

NOTES:


1. MODIFY EXISTING WALL AS NEEDED TO INSTALL NEW RECEPTACLE AND REMOTE GFI TEST SWITCH. PATCH/REPAIR WALL AS NEEDED TO MATCH EXISTING.
2. WIRE NEW RECEPTACLE DOWNSTREAM OF REMOTE GFI TEST SWITCH.
3. REMOTE GFI TEST SWITCH SHALL BE A DEAD FRONT GFI DEVICE TO BE INSTALLED FLUSH MOUNTED IN WALL WITH EDF SERVED AND PROVIDE GFI PROTECTION FOR THE RECEPTACLE LOCATED WITHIN THE EDF HOUSING.
4. GFI TEST SWITCH SHALL BE READILY ACCESSIBLE PER NEC 210.8.
5. COORDINATE RECEPTACLE LOCATION(S) WITHIN EDF HOUSINGS WITH MANUFACTURER'S INSTALLATION INSTRUCTIONS.




## 12 ROOF AND CANOPY CONDUIT SUPPORT DETAIL

NO SCALE

1. COORDINATE WITH ARCHITECTURAL DRAWINGS, DETAILS, SPECIFICATIONS AND OTHER TRADES.





## 13 CANOPY LIGHT MOUNTING DETAIL TYPE 1

NO SCALE

NOTES:

1. MOUNTING PLATES SHALL BE WELDED TO CANOPY TO MOUNT LIGHT FIXTURES.
2. FOR FIXTURES WITH END CONDUIT ATTACHMENTS ALL CANOPY PENETRATIONS SHALL BE MADE OFF CENTER FROM THE FIXTURE WIRING ENTRY POINT AND SHALL HAVE WEATHERTIGHT SEALING. (SHOWN HERE)
3. CANOPY PENETRATIONS ABOVE FIXTURES SHALL BE PERMITTED ONLY WHERE THE SUPPLIED FIXTURE HAS NO END CONDUIT ATTACHMENTS.
4. CONDUIT SHALL BE SEALED BOTH ABOVE AND BELOW THE CANOPY PENETRATION AND AGAIN AT THE FIXTURE ENTRY POINT TO PREVENT WATER FROM ENTERING THE LIGHTING FIXTURE.
5. CANOPY PENETRATIONS SHALL BE MADE AS CLOSE TO CONDUIT ENTRY PENETRATION POINT AS POSSIBLE AND CONDUIT SHALL BE ROUTED TO MINIMIZE EXPOSED CONDUIT.





## 8 TRANSFORMER CONNECTION AND GROUNDING DETAIL

NO SCALE


NOTES:

1. INSTALL GROUND ROD ADJACENT TO TRANSFORMER AND SEAL PENETRATION AROUND GROUND ROD.
2. WHERE AN ISOLATED GROUND IS PROVIDED MAKE THE CONNECTION AT THE TRANSFORMER AND RUN DIRECTLY TO THE ISOLATED GROUND BAR IN THE PANELBOARD. DO NOT DEFINE THE ISOLATED GROUND AT THE PANELBOARD.
3. FINAL CONNECTIONS TO TRANSFORMERS SHALL BE MADE IN FLEXIBLE CONDUIT. PROVIDE LIQUID TIGHT CONSTRUCTION AND FITTINGS IN WET, DAMP OR OUTSIDE AREAS EXCEPT WHERE LOCATED IN AIR HANDLING ROOMS. REFERENCE SPECIFICATIONS FOR ADDITIONAL INFORMATION.





## 9 PIGTAIL WIRING DETAIL FOR ELECTRICAL DEVICE

NO SCALE





## 1 CONDUIT/J-BOX DETAIL FOR LIGHT FIXTURES IN LAY-IN CEILING

NO SCALE




## 2 FIXTURE SUPPORT DETAIL

NO SCALE





## 3 TRAPEZE MOUNTED CONDUIT DETAIL

NO SCALE

NOTES:

1. ALL SUPPORT DEVICES SHALL BE UL LISTED AND NEC APPROVED.
2. REFER TO NEC FOR CONDUIT SUPPORT SPACING.





## 4 WALL MOUNTED CONDUITS

NO SCALE

NOTES:

1. ALL SUPPORT DEVICES SHALL BE UL LISTED AND NEC APPROVED.
2. REFER TO NEC FOR CONDUIT SUPPORT SPACING.





## 5 FIREWALL PENETRATION DETAIL

NO SCALE

NOTES:

1. FIRE RATING OF COMPLETED FIREPROOFED ASSEMBLY SHALL BE EQUAL OR EXCEED RATING OF WALL.




## 6 GROUNDING BUSHING WIRING DETAIL

NO SCALE

NOTE:

1. PROVIDE AND INSTALL GROUNDING BUSHINGS FOR DISCONNECT SWITCHES, PANELS AND TRANSFORMERS.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

# S

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD.
SUGAR LAND, TX 77479

SEAL




07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL DETAILS

s-E.011

STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM (713) 300-6060
TEXAS ENG. FIRM REG. NO. F-018332 © 2025 ALL RIGHTS RESERVED
1300 W. SAM HOUSTON PARKWAY S., SUITE 121, HOUSTON, TX 77042




## 5 TYPICAL BRANCH CIRCUIT PANEL LABELING DETAIL

NO SCALE

NOTES:

1. LAYOUT OF PANELBOARD, INCLUDING LOCATIONS OF NAMEPLATES, CIRCUIT DIRECTORY, AND OTHER LABELING IS SHOWN FOR REFERENCE ONLY, FIELD LOCATE AS NEEDED BASED ON TRUE EQUIPMENT LAYOUT AND DIMENSIONS.
2. REFERENCE OWNER'S DESIGN GUIDELINES FOR ADDITIONAL LABELING REQUIREMENTS.

(1) PROVIDE LAMACOID NAMEPLATE WITH 5/16" LETTERS SHOWING PANEL NAME, AMPERAGE RATING, VOLTAGE, AND FROM WHERE POWER IS DERIVED. ATTACH WITH MASTIC AND TWO SCREWS. COORDINATE TO GIVE SAME NAME AS PANEL SCHEDULE. IF USED AS MAIN SERVICE PANEL, PROVIDE SHORT CIRCUIT AVAILABLE AND RATING INFORMATION.

(2) PROVIDE PERMANENT ARC FAULT WARNING LABEL.


(3) FOR ALL NEW ELECTRICAL EQUIPMENT, PROVIDE PERMANENTLY AFFIXED LABEL STATING FAULT CURRENT AT THE TIME OF INSTALLATION AND CALCULATION. THE LABEL SHALL BE MINIMUM 2" X 3" IN SIZE, AND INCLUDE THE DATE OF THE CALCULATION. REFERENCE ELECTRICAL DRAWINGS AND EQUIPMENT SHORT CIRCUIT ANALYSIS TABLE. ATTACH WITH MASTIC AND TWO SCREWS.

(4) PROVIDE INFORMATION PER INDUSTRY STANDARDS, BUT SHALL INCLUDE VOLTAGE, PHASE, BUS AMPERAGE, AND SHORT CIRCUIT RATING

(5) FOR EACH CIRCUIT PROVIDE PERMANENT LABEL INDICATING CIRCUIT BREAKER NUMBER, NUMBER SHALL MATCH CIRCUIT DIRECTORY.

(6) CIRCUIT DIRECTORY TO BE COMPLETED AT END OF JOB, TYPEWRITTEN, STATING EQUIPMENT OR ROOMS SERVED BY CIRCUIT. EVEN CIRCUIT ON RIGHT SIDE OF CARD, ODD ON LEFT. PROVIDE LAMINATED DIRECTORY FOR EXTERIOR OR WET LOCATIONS.

(7) PROVIDE PERMANENT LABEL INDICATING COLOR CODING OF PHASE CONDUCTORS BASED ON VOLTAGE USING BUILDING COLOR SCHEME AS IDENTIFIED IN THE OWNER'S DESIGN GUIDELINES.




## 1 TYPICAL DISCONNECT, STARTER, & CONTACTOR LABELING DETAIL

NO SCALE

NOTES:

1. LOCATIONS OF NAMEPLATES SHOWN FOR REFERENCE ONLY, FIELD LOCATE AS NEEDED BASED ON TRUE EQUIPMENT LAYOUT AND DIMENSIONS. REFERENCE OWNER'S DESIGN GUIDELINES FOR ADDITIONAL LABELING REQUIREMENTS.

(1) PROVIDE AN ENGRAVED NAMEPLATE SHOWING LOAD SERVED, EQUIPMENT VOLTAGE, AND CIRCUIT NUMBER MATCHING AS-BUILT CONDITIONS.

(2) PROVIDE AN ENGRAVED NAMEPLATE SHOWING LOADS SERVED, VOLTAGES, AND CIRCUIT NUMBERS MATCHING AS-BUILT CONDITIONS FOR ALL CONTACTOR CIRCUITS. LOADS SERVED SHALL BE "LIGHTING", "FAN", "RECEPTACLES", "PUMP", "WATER HEATER", OR SIMILAR DESCRIPTIVE NOTE.

**DISHWASHER**
**480V, 3PH, 3 WIRE**
**FROM HK-2/4/6**

## 2 DISCONNECT LABELING

NO SCALE

NOTES:

1. PROVIDE LABEL ON EACH DISCONNECT AND FUSED SWITCH.
   1.1. FOR DISCONNECTS AND FUSED SWITCHES REPLACE "PANEL P1NA" WITH THE LOAD SERVED.
   1.2. REFER TO OWNER'S STANDARDS FOR ADDITIONAL LABEL REQUIREMENTS.
2. PROVIDE LABEL ON ELECTRICAL PANEL AND TRANSFORMER.
   2.1. REPLACE "PANEL P1NA" WITH THE PANEL OR TRANSFORMER NAME BEING LABELED.
3. REPLACE "400A FUSED SWITCH" WITH UPSTREAM SOURCE OR CONNECTION.
   3.1. IF FED FROM A XFMR REPLACE "400A FUSED SWITCH" WITH "XFMR XX" WHERE XX IS THE FIELD VERIFIED XFMR NAME.
4. REPLACE VOLTAGE CONFIGURATION TO MATCH THE EQUIPMENT BEING LABELED.
5. REFERENCE FLOOR PLANS FOR EQUIPMENT LOCATIONS.

**⚠ WARNING**

**Arc Flash and Shock Hazard**
**Appropriate PPE Required**


| FLASH PROTECTION | | SHOCK PROTECTION | |
|---|---|---|---|
| Incident Energy at: | 18 in | Shock Risk When Cover is Removed | 480 VAC |
| Min. Arc Rating: | 0.45 cal/cm² | Limited Approach | 42 in |
| Arc Flash Boundary: | 10 in | Restricted Approach | 12 in |
| PPE: Per NFPA 70E 2015 | 1 | Equipment Name: **PANEL HA** Prot Dev: 225/3 CB from Panel DA | |

## 3 TYPICAL ARC FLASH LABEL DETAIL

NO SCALE

NOTES:

1. VALUES AND NAMES SHOWN HERE ARE FOR REFERENCE ONLY, MODIFY TO REFLECT PROJECT'S ARC FLASH STUDY VALUES AND EQUIPMENT NAMES.
2. IF MIN. ARC RATING IS OVER 40CAL/CM² MODIFY "WARNING" TEXT TO READ "DANGER" AND PROVIDE RED SHADING IN LIEU OF ORANGE SHOWN.




## 4 TYPICAL TRANSFORMER LABELING DETAIL

NO SCALE

NOTES:

1. LOCATIONS OF NAMEPLATES SHOWN FOR REFERENCE ONLY, FIELD LOCATE AS NEEDED BASED ON TRUE EQUIPMENT LAYOUT AND DIMENSIONS.

(1) PROVIDE AN ENGRAVED NAMEPLATE SHOWING EQUIPMENT NAME, RATING, VOLTAGE, SOURCE.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD.
SUGAR LAND, TX 77479

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL DETAILS

s-E.012



STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM (713) 305-6080


TEXAS ENG. FIRM REG. NO. F-18332-00 2025 ALL RIGHTS RESERVED


12999 W. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77040

## KITCHEN AREA ELECTRICAL NOTES

1. REFER TO KITCHEN CONSULTANTS "FS" DRAWINGS FOR ADDITIONAL REQUIREMENTS PARTICULARLY NOTING MOUNTING HEIGHTS OF EQUIPMENT OUTLETS AND JUNCTION BOXES, AND WHETHER SERVICE IS FROM WALL, FLOOR OR OVERHEAD.
2. SOME RECEPTACLES SHALL BE MOUNTED HORIZONTALLY, REFER TO KITCHEN CONSULTANTS "FS" DRAWINGS.
3. FOR DEVICES WITH SERVICE FROM FLOOR, RUN UNDERGROUND CONDUIT FROM DEVICES TO NEAREST COLUMN OR WALL THEN TURN CONDUIT UP AND RUN CONDUIT IN CEILING CAVITY.
4. LIGHT SWITCHES AND RECEPTACLES NOT SERVING A SPECIFIC PIECE OF EQUIPMENT SHALL BE MOUNTED AT ADA HEIGHTS.
5. CONNECTION TYPE SHOWN ON KITCHEN ELECTRICAL FLOOR PLAN IS FOR BIDDING PURPOSES, COORDINATE WITH KITCHEN EQUIPMENT SUPPLIER FOR FINAL CONNECTIONS:
   - 5.A. OBTAIN WIRING INSTRUCTIONS FOR EACH PIECE OF EQUIPMENT FROM EQUIPMENT SUPPLIER PRIOR TO ORDERING WIRING DEVICES AND ROUGH-IN.
   - 5.B. IF EQUIPMENT REQUIRES CORD AND PLUG CONNECTION, CONTRACTOR SHALL PROVIDE NEMA POWER CORD, PLUG, AND RECEPTACLES PER MANUFACTURER'S INSTRUCTION.
   - 5.C. IF EQUIPMENT REQUIRES JUNCTION BOX AND/OR DISCONNECT SWITCH, CONTRACTOR SHALL PROVIDE JUNCTION BOX AND DISCONNECT SWITCH AND CONNECT EQUIPMENT WITH SEALTITE FLEXIBLE CONDUIT.
6. ALL DISCONNECT SWITCHES IN THE KITCHEN AREA SHALL BE NEMA 4XSS STAINLESS STEEL.
7. WHERE PORTIONS OF INTERIOR RACEWAY SYSTEM ARE EXPOSED TO WIDELY DIFFERENT TEMPERATURES, PROVIDE AIR SEALING PER NEC TO PREVENT CIRCULATION OF AIR FROM WARMER TO A COOLER SECTION.
8. FLEXIBLE CONDUIT IN KITCHENS, FOOD PRODUCTION SPLASH ZONES AND WASH DOWN AREAS, FOOD PROCESSING, AND SIMILAR AREAS SHALL BE LIQUID TIGHT CONSTRUCTION INCORPORATING A BACTERIAL GROWTH INHIBITING PVC JACKET THAT MAY BE CLEANED WITHOUT DEGREDATION TO THE JACKET BLEACHING ELEMENTS AND APPROVED FITTINGS FOR WET LOCATION.
   - 8.A. AFC SZ TYPE LFMC OR EQUAL BY KAF-TECH.
9. INTERLOCK KITCHEN EXHAUST HOOD FIRE SYSTEM WITH FIRE ALARM SYSTEM.
10. PROVIDE RELAYS AND INTERLOCK KITCHEN HOOD FANS WITH FIRE ALARM SYSTEM. ACTUATION OF ANY ALARM INITIATING DEVICE SHALL DE-ENERGIZE KITCHEN HOOD FANS.
11. ALL GFI RECEPTACLES IN KITCHEN SHALL BE PASS & SEYMOUR MODEL 2097TRWR-XX TO EXCEED UL943 VOLTAGE SURGE REQUIREMENTS.





### 4 FIRE PROTECTION SYSTEM DETAIL

NO SCALE

NOTES:

1. ANSUL MODEL R-120 FIRE PROTECTION SYSTEM AND TANK(S)
2. ELECTRICAL CONTRACTOR TO FURNISH AND INSTALL POWER DISCONNECT DEVICES FOR ALL EQUIPMENT BELOW THE HOOD, SHUTTING OFF ALL SERVICE, INCLUDING CONTROL VOLTAGE, UPON ACTIVATION OF THE FIRE PROTECTION SYSTEM.
3. MICRO-SWITCH FURNISHED WITH SYSTEM TO BE INTERWIRED TO THE SHUT-OFF DEVICES FOR THE COOKING EQUIPMENT BY THE ELECTRICAL CONTRACTOR.
4. ELECTRICAL CONTRACTOR TO FURNISH AND INSTALL AN OCTAGON SHAPED HANDY BOX FOR THE PULL STATION AT 54" ABOVE THE FLOOR WITH 1/2" CONDUIT FROM THE TOP OF THE BOX TO 6" ABOVE THE CEILING.
5. GAS SHUT-OFF VALVE FURNISHED WITH THE SYSTEM (IF REQUIRED) TO BE INSTALLED IN THE GAS LINE SERVING THE COOKING EQUIPMENT BY THE PLUMBING CONTRACTOR. VERIFY SIZE OF GAS LINE.
6. ALL EXPOSED PIPEWORK TO BE STAINLESS STEEL OR CHROME WHERE EXPOSED.
7. VERIFY LOCATION OF REMOTE MANUAL PULL STATION.
8. UNIT MUST BE PLACED WITHIN EASY ACCESS OF EXIT DOOR.





### 5 KITCHEN HOOD FAN CONTROL SCHEMATIC

NO SCALE

NOTES:

1. THE FANS SHALL BE WIRED SO THAT ONE LOCAL SWITCH TURNS ON ASSOCIATED SUPPLY AND EXHAUST FANS.
2. IF THE FIRE ALARM IS IN ALARM, A FIRE ALARM CONTROL CONTACT SHALL CAUSE THE SUPPLY FAN TO STOP AND THE EXHAUST FAN TO START, EVEN IF THE CONTROL SWITCH IS "OFF".
3. SCHEMATIC IS DIAGRAMMATIC. PROVIDE INTERLOCK WIRING BASED ON EQUIPMENT PROVIDED AND FAN VOLTAGE TO IMPLEMENT THE SEQUENCE SPECIFIED.
4. COORDINATE BETWEEN FIRE ALARM CONTRACTOR, CONTROLS CONTRACTOR AND ELECTRICAL CONTRACTOR TO PROVIDE A COMPLETE INSTALLATION.
5. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.





### 1 GAS VALVE DETAIL

NO SCALE

NOTES:

1. GAS VALVE HOUSINGS ARE NOT SHOWN ON THE ELECTRICAL DRAWING. GC AND ELECTRICAL CONTRACTOR SHALL COORDINATE SIZE AND LOCATION OF GAS VALVE HOUSINGS.
2. SEE FOOD SERVICE CONSULTANT'S DRAWINGS ADDITIONAL INFORMATION AND REQUIREMENTS.
3. PROVIDE MINIMUM 3/4"C AS SHOWN ON THIS DETAIL.





### 2 RECESSED FIRE PULL DETAILS

NO SCALE

NOTES:

1. VERIFY LOCATION OF REMOTE MANUAL PULL STATION.
   - 1.A. MANUAL PULL STATION MUST BE PLACED WITHIN EASY ACCESS OF EXIT DOOR.
   - 1.B. MANUAL PULL STATION MUST BE PLACED NO LESS THAN 4 FEET AWAY FROM KITCHEN HOOD BUT WITHIN A MAXIMUM OF 20 FEET FROM THE KITCHEN HOOD.




### 3 TYPICAL PEDESTAL MOUNTED DEVICE

NO SCALE

NOTES:

1. ALL FACEPLATES SHALL BE STAINLESS STEEL.
2. PEDESTAL BOX PROVIDED BY DIVISION 26.
   - 2.A. A STANDARD DUPLEX INSTALLATION IS SHOWN FOR REFERENCE. PROVIDE SIMILAR INSTALLATION FOR QUAD RECEPTACLES, GFI RECEPTACLES, DATA OUTLETS, NEMA POWER OUTLETS, ETC.
   - 2.B. ALL PEDESTAL BOXES TO BE DOUBLE FACED WITH ONE BLANK FACE FOR FUTURE GROWTH. 2-GANG PEDESTALS WITH ONE BLANK FACE FOR QUAD RECEPTACLE LOCATIONS.
   - 2.C. PEDESTAL BOXES TO BE SIZED BY DIVISION 26 TO PROVIDE SCHEDULED DEVICES ON A SINGLE FACE AND SUFFICIENT DEPTH FOR BACK TO BACK DEVICES ON DOUBLE FACED PEDESTALS.
   - 2.D. BASIS OF DESIGN:
     - 2.D.A. 1-GANG ELECTRICAL DEVICES: LEGRAND LBP2 OR WATER SAVER E400SA-WS
     - 2.D.B. 1-GANG LOW VOLTAGE DEVICES: LEGRAND LBP2 OR WATER SAVER E400SA-WS
     - 2.D.C. 2-GANG ELECTRICAL DEVICES: WATER SAVER E600SA-WS
     - 2.D.D. 2-GANG LOW VOLTAGE DEVICES: WATER SAVER E600SA-WS
3. INSTALLATION REQUIREMENTS:
   - 3.A. STUB UP CONDUIT ABOVE FLOOR TO PEDESTAL BOX CONNECTION LOCATION.
   - 3.B. GROUT GAP BETWEEN FINISHED FLOOR AND BOTTOM OF PEDESTAL BOX.
   - 3.C. PROVIDE TRANSITION PIECE TO CONTINUE FINISHED FLOOR TO BOTTOM EDGE OF SERVICE FITTING AND CONCEAL GROUT. TRANSITION PIECE TO MATCH ARCHITECT'S FINISH SCHEDULE.
   - 3.D. PEDESTAL BOX TO BE INSTALLED SQUARE TO THE FINISHED FLOOR.
4. PROVIDE TYPEWRITTEN OR PREMADE CIRCUIT LABELS ON INSTALLED WIRING AT EACH DEVICE AND SPLICE POINT.
5. PROVIDE TYPEWRITTEN LABEL AFFIXED TO THE FRONT OF EACH DEVICE FACEPLATE INDICATING ELECTRICAL CIRCUIT.

XX-## CIRCUIT LABEL

- A. XX = PANEL DESIGNATION
- B. ## = AS-BUILT CIRCUIT DESIGNATION

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD.
SUGAR LAND, TX 77479

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL KITCHEN DETAILS

s-E.013


STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM (713) 305-6080


TEXAS ENG FIRM REG NO. F-019332 © 2025 ALL RIGHTS RESERVED


12999 W. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77040

LIGHTING SYSTEM FUNCTIONAL TESTING AND DOCUMENTATION NOTES:

1. PRIOR TO PASSING FINAL INSPECTION, THE CONTRACTOR SHALL PERFORM FUNCTIONAL TESTING IN THE PRESENCE OF THE REGISTERED DESIGN PROFESSIONAL, THE OWNER AND/OR THEIR AGENT. THE FUNCTIONAL TESTING SHALL BE AS REQUIRED BY SECTION C408.3.1 OF THE 2021 IECC.
   1.A. THE FUNCTIONAL TESTING SHALL PROVIDE EVIDENCE THAT THE LIGHTING CONTROL SYSTEMS, INCLUDING BOTH HARDWARE AND SOFTWARE, ARE CALIBRATED, ADJUSTED, PROGRAMMED AND IN PROPER WORKING CONDITION IN ACCORDANCE WITH THE CONSTRUCTION DOCUMENTS AND MANUFACTURER'S INSTRUCTIONS.
   1.B. THE FUNCTIONAL TESTING SHALL BE IN ACCORDANCE WITH SECTIONS C408.3.1.1 AND C408.3.1.2 OF THE 2021 IECC FOR THE APPLICABLE CONTROL TYPE.
   1.C. A WRITTEN REPORT SHALL BE GENERATED DOCUMENTING THE FUNCTIONAL TESTING RESULTS IN ACCORDANCE WITH THE 2015 IECC REQUIREMENTS.
2. ALL LIGHTING CONTROLS O&M MANUALS, AS-BUILTS, TESTING REPORTS AND DOCUMENTATION RELATED TO THE LIGHTING CONTROL SYSTEM SHALL BE PROVIDED IN THEIR FINAL AND APPROVED FORM WITHIN 60 DAYS OF THE CERTIFICATE OF OCCUPANCY. ALL DOCUMENTS CERTIFYING THAT THE INSTALLED LIGHTING CONTROLS MEET DOCUMENTED PERFORMANCE CRITERIA OF SECTION C405 OF THE 2021 IECC SHALL BE INCLUDED IN THE O&M MANUALS.
3. ALL DOCUMENTS FROM ITEMS #1 AND #2 ABOVE SHALL BE COMBINED AND PROVIDED TO THE OWNER WITHIN 90 DAYS FROM THE DATE OF RECEIPT OF THE CERTIFICATE OF OCCUPANCY.

# LIGHT FIXTURE SCHEDULE

## EXTERIOR LIGHT FIXTURE SCHEDULE

| | | | |
|---|---|---|---|
| RECESSED 6" DOWNLIGHT WET LOCATION | D5<br>D5Y | 6" DIAMETER RECESSED LED DOWNLIGHT, SPECULAR CLEAR REFLECTOR, MEDIUM (56') BEAM DISTRIBUTION, 1000 LUMENS, 4000K COLOR TEMPERATURE, 120-277V MULTIVOLT INPUT, 1% 0-10V DIMMING DRIVER.<br>LIGHTOLIER 6R-N / C6L-10-9-40-M-Z10-U / C6-R-DL-CC | 9W |
| RECESSED 6" DOWNLIGHT WET LOCATION | D6<br>D6Y | 6" DIAMETER RECESSED LED DOWNLIGHT, SPECULAR CLEAR REFLECTOR, MEDIUM (56') BEAM DISTRIBUTION, 2000 LUMENS, 4000K COLOR TEMPERATURE, 120-277V MULTIVOLT INPUT, 1% 0-10V DIMMING DRIVER.<br>LIGHTOLIER 6R-N / C6L-20-9-40-M-Z10-U / C6-R-DL-CC | 22W |
| SURFACE CANOPY SQUARE LED | WC1<br>WC1X<br>WC1Y | 9" SQUARE SURFACE LED CANOPY LIGHT, 4000K COLOR TEMPERATURE, 3500 LUMENS, 120-277V MULTIVOLT INPUT, DARK BRONZE FINISH.<br>EELP VR7-T-28L-QT-40K (EBLED9W) | 28W |
| EXTERIOR WALL PACK | WP1<br>WP1X<br>WP1Y | 7" WDE WALL MOUNTED LED, 4000K COLOR TEMPERATURE, 5000 LUMENS, TYPE 3 DISTRIBUTION, 120-277 MULTIVOLT INPUT, WET LOCATION, 10KV KA SURGE PROTECTION.<br>REFER TO ARCH FOR MOUNTING HEIGHT.<br>FINISH TO BE SELECTED BY ARCHITECT FROM ALL AVAILABLE FINISHES.<br>GARDCO GEOFORM SMALL GWS-A04-740-UNV-XX FINISH (EM) | 34W |
| EXTERIOR WALL PACK | WP2<br>WP2X<br>WP2Y | 12" WDE WALL MOUNTED LED, 4000K COLOR TEMPERATURE, 8500 LUMENS, TYPE 3 DISTRIBUTION, 120-277 MULTIVOLT INPUT, WET LOCATION. REFER TO ARCH FOR MOUNTING HEIGHT.<br>REFER TO ARCH FOR MOUNTING HEIGHT.<br>FINISH TO BE SELECTED BY ARCHITECT FROM ALL AVAILABLE FINISHES.<br>GARDCO GEOFORM MEDIUM GWM-A11-740-T3M-UNV-XX FINISH (REMOTE EM BATTERY) | 52W |
| EXTERIOR WALL PACK | WP3<br>WP3X<br>WP3Y | 17" WDE WALL MOUNTED LED, 4000K COLOR TEMPERATURE, 12500 LUMENS, TYPE 3 DISTRIBUTION, 120-277 MULTIVOLT INPUT, WET LOCATION. REFER TO ARCH FOR MOUNTING HEIGHT.<br>REFER TO ARCH FOR MOUNTING HEIGHT.<br>FINISH TO BE SELECTED BY ARCHITECT FROM ALL AVAILABLE FINISHES.<br>GARDCO GEOFORM MEDIUM GWM-A14-740-T3M-UNV-XX FINISH (REMOTE EM BATTERY) | 77W |

1. LIGHT FIXTURE CATALOG NUMBERS AND DESCRIPTIONS ARE SCHEDULED FOR ESTABLISHING QUALITY, APPEARANCE AND PERFORMANCE OF THE FIXTURES. EXACT CATALOG NUMBERS DESCRIBING MOUNTING CONDITIONS AND REQUIREMENT RELATED TO TRIM FOR ALL FIXTURES SHALL BE CONFIRMED (BY THE ELECTRICAL CONTRACTOR) WITH THE ROOM FINISH SCHEDULE AND REFLECTED CEILING PLANS ON THE ARCHITECTURAL PLANS PRIOR TO BIDDING AND SUBMITTING LIGHT FIXTURES. PROVIDE DRY WALL KIT AS REQUIRED.
2. ALL 'X', 'Y', AND 'Z' TYPE FIXTURES SHALL HAVE EMERGENCY POWER BACKUP. EMERGENCY POWER SOURCES SHALL MONITOR POWER UPSTREAM OF THE LIGHTING CONTROLS TO SEE IF POWER IS LOST. BATTERY PACKS AND INVERTERS SHALL BE CAPABLE OF POWERING THE DESIGNATED FIXTURE(S) WITH AN OUTPUT OF 1400 LUMENS FOR A MINIMUM OF 90-MINUTES. PROVIDE REMOTE BATTERY PACKS OR INVERTERS AS NECESSARY. EMERGENCY LIGHTS SHALL OPERATE ONLY UPON LOSS OF POWER; ALSO, PROVIDE AND WIRE TEST SWITCH AND LED INDICATOR LIGHT FOR EMERGENCY BATTERY. SEE WIRING INSTRUCTION SUPPLIED BY EMERGENCY BATTERY MANUFACTURER.
   2.A. 'X' TYPE FIXTURES (AX, ETC.) HAVE EMERGENCY GENERATOR POWER LIGHTING TRANSFER DEVICES.
   2.B. 'Y' TYPE FIXTURES (MY, ETC.) HAVE INDIVIDUAL 90-MINUTE EMERGENCY BATTERY POWER.
   2.C. 'Z' TYPE FIXTURES (GTZ, ETC.) HAVE 90-MINUTE INVERTER EMERGENCY BATTERY POWER.
3. PROVIDE BASE COVER FOR ALL LIGHT POLES.
4. ALL EXTERIOR FIXTURES SHALL BE WET RATED WITH COLD WEATHER BALLASTS AND BATTERY PACKS.
5. PROVIDE SPARE FIXTURES AND EMERGENCY DEVICES PER SPECIFICATIONS.
6. WHERE FIXTURE FINISHES ARE INDICATED TO BE SELECTED BY ARCHITECT THE CONTRACTOR SHALL INCLUDE IN THEIR BID ALL AVAILABLE FINISHES. SUBMIT COMPLETE FIXTURE FINISH OPTIONS AS PART OF THE LIGHTING SUBMITTAL PACKAGE.
7. EQUAL BY PHILIPS (CW LIGHTING), COOPER (PUTTERMAN SCHAROK), AND LITHONIA (LESCO) SHALL BE ACCEPTABLE.

## INTERIOR LIGHT FIXTURE SCHEDULE

| APPLICATION | TYPE | DESCRIPTION | WATTS |
|---|---|---|---|
| 1X4 RECESSED LAY-IN CEILING SELECTABLE CCT & LUMENS | A1<br>A1X<br>A1Y | 2X4 RECESSED LED, SMOOTH FROSTED ACRYLIC LENS, EXTRUDED ALUMINUM FRAME, WHITE FINISH, LAY-IN CEILING, 6000 LUMENS, 4000K COLOR TEMPERATURE, 120-347V MULTIVOLT INPUT, 5% 0-10V DIMMING.<br>SET FIELD SELECTABLE SWITCHES TO NEUTRAL WHITE (4000K) AND HIGH (47W).<br>DAYBRITE 2SBP3550L8CS-4-UNJ-DIM | 47W |
| 1X4 RECESSED LAY-IN CEILING SELECTABLE CCT & LUMENS | B1<br>B1X<br>B1Y | 1X4 RECESSED LED, SMOOTH FROSTED ACRYLIC LENS, EXTRUDED ALUMINUM FRAME, WHITE FINISH, LAY-IN CEILING, 4500 LUMENS, 4000K COLOR TEMPERATURE, 120-347V MULTIVOLT INPUT, 5% 0-10V DIMMING.<br>SET FIELD SELECTABLE SWITCHES TO NEUTRAL WHITE (4000K) AND HIGH (36W).<br>DAYBRITE 1SBP3040L8CS-4-UNJ-DIM | 36W |
| 2X2 RECESSED LAY-IN CEILING SELECTABLE CCT & LUMENS | B2<br>B2X<br>B2Y | 2X2 RECESSED LED, SMOOTH FROSTED ACRYLIC LENS, EXTRUDED ALUMINUM FRAME, WHITE FINISH, LAY-IN CEILING, 4250 LUMENS, 4000K COLOR TEMPERATURE, 120-347V MULTIVOLT INPUT, 5% 0-10V DIMMING.<br>SET FIELD SELECTABLE SWITCHES TO NEUTRAL WHITE (4000K) AND HIGH (36W).<br>DAYBRITE 2SBP3040L8CS-2-UNJ-DIM | 39W |
| 4FT STRIP LED MECHANICAL & STORAGE ROOMS | C<br>CX<br>CY | 4 FOOT STRIP LED, STEEL HOUSING, FROSTED ACRYLIC LENS, 4000 LUMENS, 3500K COLOR TEMPERATURE, CHAIN HANGING SET, WIRE GUARD, 120-277V MULTIVOLT INPUT, 0-10V DIMMING DRIVER. PROVIDE CHAIN HANGING SET AND WIREGUARD IN MECHANICAL ROOMS AND AREAS WITHOUT CEILINGS.<br>SET FIELD SELECTABLE SWITCHES TO NEUTRAL WHITE (4000K) AND HIGH (36W).<br>DAYBRITE SDS-4-2448L-8CST-UNV-DIM | 30W |
| RECESSED 6" DOWNLIGHT | D1<br>D1X<br>D1Y | 6" DIAMETER RECESSED LED DOWNLIGHT, MATTE WHITE FINISH, WIDE (76') BEAM DISTRIBUTION, 1000 LUMENS, 4000K COLOR TEMPERATURE, 120-277V MULTIVOLT INPUT, 1% 0-10V DIMMING DRIVER.<br>LIGHTOLIER 6R-N / C6L-10-9-40-W-Z10-U / C6-R-DL-WH | 9W |
| RECESSED 6" DOWNLIGHT | D2<br>D2X<br>D2Y | 6" DIAMETER RECESSED LED DOWNLIGHT, MATTE WHITE FINISH, WIDE (76') BEAM DISTRIBUTION, 2000 LUMENS, 4000K COLOR TEMPERATURE, 120-277V MULTIVOLT INPUT, 1% 0-10V DIMMING DRIVER.<br>LIGHTOLIER 6R-N / C6L-20-9-40-W-Z10-U / C6-R-DL-WH | 22W |
| EXIT SIGN | XB<br>XS<br>XD | DIE CAST ALUMINUM LED EXIT LIGHT, RED LETTERS, MATTE BLACK HOUSING W/ BRUSHED ALUMINUM FACE, UNIVERSAL ARROWS, 120/277 VOLT DUAL INPUT, 90 MINUTE EMERGENCY BATTERY. VERIFY LETTER AND FACE COLOR WITH OWNER/ARCHITECT PRIOR TO ORDERING.<br>XS=SINGLE FACE, XD=DOUBLE FACE, XB=BACK MOUNTED<br>PHILIPS CHLORIDE ER55L-3-R<br>SURELITES CX7-1/2-R<br>LITHONIA LQC-1/2-R-EL N | 5W |
| EXIT SIGN INTEGRAL BATTERY INTEGRAL EM LIGHT BAR | YB<br>YS<br>YD | THERMOPLASTIC LED EXIT LIGHT WITH INTEGRAL EM LIGHT, RED LETTERS, WHITE HOUSING W/ WHITE FACE, UNIVERSAL ARROWS, 120-277 MULTIVOLT INPUT, 90 MINUTE EMERGENCY BATTERY. VERIFY LETTER AND FACE WITH OWNER/ARCHETICT PRIOR TO ORDERING.<br>YS=SINGLE FACE, YD=DOUBLE FACE, YB=BACK MOUNTED<br>SIGNTEX CLP-BB-U-R-W-DG | 5W |
| TWIN HEAD EM LIGHT INTEGRAL BATTERY WET LOCATION | YT1 | TWIN HEAD EM LIGHT, INJECTION-MOLDED THERMOPLASTIC WHITE HOUSING, GASKETED CLEAR POLYCARBONATE COVER, LED LAMPS, 90-MINUTE EMERGENCY BATTERY.<br>CHLORIDE TPU-W-N-LM7-W | 7W |

# LIGHTING CONTROL SEQUENCE OF OPERATIONS

| ROOM TYPE | AUTO ON | MANUAL ON (VACANCY) | AUTO OFF (20 MIN MAX) | PARTIAL OFF AT NORMAL HOURS | AUTO ON AFTER HOURS | AUTO OFF AFTER HOURS (20 MIN MAX) | TIME ON | TIME OFF | ASTRONOMIC OR PHOTOCELL ON/OFF | AUTO STEP CONTROL WITH OFF | AUTO CONTINUOUS DIM WITH OFF | MANUAL BI-LEVEL REDUCTION CONTROL | MANUAL CONTINUOUS DIM CONTROL | MANUAL ON/OFF SWITCH | MANUAL DIMMER SWITCH | DISPLAY, ACCENT, TASK CONTROL | PLUG LOAD CONTROL | SEQUENCE OF OPERATION |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | OCCUPANCY SENSOR | | | | | | TIME SWITCH/SCHEDULING | | | DAYLIGHT CONTROL | | LIGHT REDUCTION | | MANUAL CONTROL | | | | |
| Kitchen/Serving | | | | | | | • | • | | | | • | | • | | | | LOCAL ON/OFF CONTROLS, LOCAL CONTROLS MAY OVERRIDE BUILDING SCHEDULE AND TURN ALL LIGHTS ON FOR MAXIMUM 2HRS. NETWORK LIGHTING CONTROLS ROOM CONTROLLER CONNECTED TO BUILDING CONTROLS; ON/OFF BASED ON BUILDING SCHEDULE, AFTER HOURS ON/OFF BASED ON OCCUPANCY, COORDINATE SCHEDULING WITH OWNER. WHERE ≥150W IN DAYLIGHT AREA, USE CONTINUOUS DIMMING DAYLIGHTING CONTROL. |
| Restrooms | 100% | | 20 MIN | | | | | | | | | | | • | | | | AUTO ON 100%, AUTO OFF BY LOCAL OCCUPANCY SENSOR. LOCAL ON/OFF CONTROLS ONLY, NO FULLY NETWORKED SYSTEM. |
| Custodial rooms | | • | 20 MIN | | | | | | | | | | | • | • | | | MANUAL ON, AUTO OFF BY LOCAL OCCUPANCY SENSOR. LOCAL ON/OFF CONTROLS ONLY, NO FULLY NETWORKED SYSTEM. |
| Storage rooms | 50% | | 20 MIN | | | | | | | | | | | • | • | | | AUTO ON 50%, AUTO OFF BY LOCAL OCCUPANCY SENSOR. LOCAL ON/OFF/DIMMING CONTROLS ONLY, NO FULLY NETWORKED SYSTEM. |
| Private Offices | 50% | | 20 MIN | | | | | | | | | | | • | • | | • | AUTO ON 50%, AUTO OFF BY LOCAL OCCUPANCY SENSOR. LOCAL ON/OFF/DIMMING CONTROLS ONLY, NO FULLY NETWORKED SYSTEM. |
| Corridors | | | | | 100% | 20 MIN | • | • | | | | | | • | | | | LOCAL ON/OFF CONTROLS, LOCAL CONTROLS MAY OVERRIDE BUILDING SCHEDULE AND TURN ALL LIGHTS ON FOR MAXIMUM 2HRS. NETWORK LIGHTING CONTROLS ROOM CONTROLLER CONNECTED TO BUILDING CONTROLS; ON/OFF BASED ON BUILDING SCHEDULE, AFTER HOURS ON/OFF BASED ON OCCUPANCY, COORDINATE SCHEDULING WITH OWNER. WHERE ≥150W IN DAYLIGHT AREA, USE CONTINUOUS DIMMING DAYLIGHTING CONTROL. |
| Electrical Rooms | | | | | | | | | | | | | | • | | | | MANUAL ON/OFF; LOCAL CONTROL DEVICE NOT TIED TO LVLCS. |
| Building Facade/Landscape | | | | | | | • | • | | | | | | | | | | CONNECTED TO BUILDING CONTROLS THROUGH LIGHTING CONTACTOR; ON/OFF BASED ON BUILDING SCHEDULE. |

1. DIMMER SWITCHES SHALL ACTIVATE PRESET ALL ON LIGHTING LEVEL WHEN PRESSED IN THE UP POSITION. LIGHTING LEVELS MAY BE RAISED/LOWERED BY HOLDING THE DIMMER PADDLE. WHEN PRESSED IN THE DOWN POSITION ALL LIGHTS SHALL SMOOTHLY DIM TO OFF.
2. AT LEAST 50 PERCENT OF ALL 125V, 15- AND 20-AMP RECEPTACLES INSTALLED IN ENCLOSED OFFICES, CONFERENCE ROOMS, ROOMS USED PRIMARILY FOR COPY OR PRINT FUNCTIONS, BREAKROOMS, CLASSROOMS AND INDIVIDUAL WORKSTATIONS, INCLUDING THOSE INSTALLED IN MODULAR PARTITIONS AND MODULE OFFICE WORKSTATION SYSTEMS SHALL HAVE PLUG LOAD CONTROL PER IECC 2021 C405.11.

# LIGHTING CONTACTOR SCHEDULE

**CONTACTOR CT1**

| POLE | DESCRIPTION | NORMAL CKT | EM CKT | CONTROL ZONE | CONTACTOR LOCATION | CONTACTOR TYPE |
|---|---|---|---|---|---|---|
| CT1-1 | KITCHEN/SERVING AREA - ZONE 'a' | HK-3 | - | Kitchen-a | CENTRAL PLANT | MAGNETICALLY HELD |
| CT1-2 | SPARE | | | Kitchen-a | CENTRAL PLANT | MAGNETICALLY HELD |
| CT1-3 | SPARE | | | Kitchen-a | CENTRAL PLANT | MAGNETICALLY HELD |

**CONTACTOR CT2**

| | | | | | | |
|---|---|---|---|---|---|---|
| CT2-1 | KITCHEN/SERVING AREA - ZONE 'b' | HK-3 | - | Kitchen-b | CENTRAL PLANT | MAGNETICALLY HELD |
| CT2-2 | SPARE | | | Kitchen-b | CENTRAL PLANT | MAGNETICALLY HELD |
| CT2-3 | SPARE | | | Kitchen-b | CENTRAL PLANT | MAGNETICALLY HELD |

**CONTACTOR CT3**

| | | | | | | |
|---|---|---|---|---|---|---|
| CT3-1 | KITCHEN SOFFIT/CANOPY LTS | HK-5 | - | Exterior | CENTRAL PLANT | MAGNETICALLY HELD |
| CT3-2 | | | | Exterior | CENTRAL PLANT | MAGNETICALLY HELD |
| CT3-3 | | | | Exterior | CENTRAL PLANT | MAGNETICALLY HELD |

1. REFERENCE TYPICAL LIGHTING CONTACTOR WIRING DIAGRAM.
2. EMERGENCY AND NORMAL ZONES WITHIN THE KITCHEN/SERVING SHALL HAVE SEPARATE CONTROLS TO ALLOW FOR LIGHTING REDUCTION CONTROL.
3. LIGHTING CONTACTORS SHALL BE DIN RAIL MOUNTED, MAGNETICALLY HELD TYPE WITH THREE WIRE CONTROL BY THE BAS.
   3.A. PROVIDE CABINET AT EACH LOCATION TO MOUNT ALL CONTACTORS IN A SINGLE ENCLOSURE. ENCLOSURE SIZED BY DIVISION 26.
   3.B. PROVIDE SEPARATE HOA SWITCHES IN THE FRONT COVER OF THE ENCLOSURE WIRED TO CONTROL THE FOLLOWING ZONES SEPARATELY.
      3.B.1. INTERIOR LIGHTING (ALL INTERIOR LIGHTING GROUPS)
      3.B.2. EXTERIOR LIGHTING (ALL EXTERIOR LIGHTING GROUPS)
      3.B.3. HOA SWITCH SHALL PASS THE BAS SIGNALS IN AUTO MODE, DISENGAGE ALL CONTACTORS IN THE OFF POSITION, AND ENGAGE ALL THE CONTACTORS IN THE ON POSITION.
   3.C. SPARE CAPACITY:
      3.C.1. PROVIDE MINIMUM TWO (2) SPARE POLE ON EACH COMBINED TYPE CONTACTOR FOR FUTURE USE.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD.
SUGAR LAND, TX 77479

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

LIGHTING SCHEDULES

s-E.060


STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM (713) 303-6080 | TEXAS ENG. FIRM REG. NO. F-018332 | 1300 W. SAM HOUSTON PARKWAY S., SUITE 121, HOUSTON, TX 77042

© 2025 ALL RIGHTS RESERVED

## ELECTRICAL KEYED NOTES

GENERAL NOTES:

- CUT WALLS AS REQUIRED TO FLUSH MOUNT NEW DEVICES IN EXISTING WALLS. PATCH/REPAIR WALLS TO MATCH.

LIGHTING RENOVATION NOTES:

A. KITCHEN LIGHTS TO BE CONTROLLED BY LOCAL MOMENTARY SWITCHES AND BAS. LIGHTING CONTACTOR LOCATIONS SHOWN SCHEMATICALLY ONLY. LOCATE LIGHTING CONTACTOR ENCLOSURE IN THE ADJACENT CENTRAL PLANT SPACE, FIELD VERIFY. REFERENCE LIGHTING CONTROL DETAIL. TYPICAL.
   LEFT SWITCH SHALL CONTROL ZONE 'a' NORMAL POWER LIGHTING FIXTURES.
   RIGHT SWITCH SHALL CONTROL ZONE 'b' EMERGENCY LIGHTING FIXTURES.


B. PROVIDE PLUG LOAD CONTROLS TIED TO THE LIGHTING IN OFFICE SPACES.

C. WIRE EXIT SIGNS UPSTREAM OF LIGHTING CONTROLS. TYPICAL.

D. EXTERIOR LIGHTS TO BE CONTROLLED BY BAS. LIGHTING CONTACTOR LOCATIONS SHOWN SCHEMATICALLY ONLY. LOCATE LIGHTING CONTACTOR ENCLOSURE IN THE ADJACENT CENTRAL PLANT SPACE, FIELD VERIFY. REFERENCE LIGHTING CONTROL DETAIL. TYPICAL.

E. AFTER REMOVAL OF THE TEMPORARY KITCHEN, PROVIDE NEW EXIT SIGN AT ORIGINAL LOCATION AND RECONNECT TO EXISTING CAFETERIAL LIGHTING CIRCUIT.

F. PATCH/REPAIR EXTERIOR SOFFIT TO ACCOMMODATE NEW SURFACE MOUNTED FIXTURES.




1 **LIGHTING RENOVATION PLAN**
SCALE: 1/4" = 1'- 0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD.
SUGAR LAND, TX 77479

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING


LIGHTING FLOOR PLANS

s-E.100


STANTON ENGINEERING GROUP
INFORMATION@SEGROUP.COM (713) 300-6060


TEXAS ENG. FIRM REG. NO. F-018332 | © 2025 ALL RIGHTS RESERVED


1300 W. SAM HOUSTON PARKWAY S., SUITE 121, HOUSTON, TX 77042




## 1 ELECTRICAL RENOVATION PLAN

SCALE: 1/4" = 1'- 0"

## ELECTRICAL KEYED NOTES

GENERAL NOTES:

- CUT WALLS AS REQUIRED TO FLUSH MOUNT NEW DEVICES IN EXISTING WALLS. PATCH/REPAIR WALLS TO MATCH.

ELECTRICAL RENOVATION NOTES:

A. CONNECT NEW FREEZER/COOLER AND CONDENSER TO EXISTING STANDBY GENERATOR.

B. PROVIDE ILLUMINATED PUSH BUTTON IN COOLER AND FREEZER. WHEN PRESSED RED STROBE DEVICES IN KITCHEN AND CAFETERIA SHALL ACTIVATE. TYPICAL.

C. PROVIDE HORN/STROBE DEVICE TIED TO PUSH BUTTONS IN FREEZER/COOLER.
(EDWARDS 860 SERIES OR EQUAL).

D. PROVIDE NEW DOORBELL BUTTON AT RECEIVING DOOR. DOORBELL BUTTON SHALL BE THE CLOSEST DEVICE TO THE DOOR FRAME.

E. PROVIDE NEW VIBRATING BUZZER TIED TO DOORBELL BUTTON AT RECEIVING DOOR. BUZZER TO BE WALL MOUNTED JUST BELOW THE CEILING.

F. PROVIDE NEW ELECTRICAL DEVICES MATCHING NEW KITCHEN EQUIPMENT AND ROOM LAYOUTS. REFERENCE FOOD SERVICE DRAWINGS. TYPICAL.

G. PROVIDE ROUGH-IN FOR LOW VOLTAGE DEVICES. REFERENCE TECHNOLOGY DRAWINGS, TYPICAL.

H. POWER AND DATA ROUGH-IN FOR KITCHEN MENU BOARD.

I. POWER AND DATA ROUGH-IN FOR POINT OF SALE (POS) LOCATION.

J. PROVIDE DROP CORD RECEPTACLE WITH HUBBELL KELLEMS LIQUIDTIGHT GRIPS FOR STRAIN RELIEF, TYPICAL OF ALL.

K. PROVIDE J-BOXES AND CONDUIT FOR REMOTE FIRE PULLS, SEE FOOD SERVICE DETAIL DRAWING FOR REQUIREMENTS, TYPICAL

L. WIRE ANSUL SYSTEM TO HOOD EQUIPMENT CONTROL CONTRACTOR. UPON ANSUL SYSTEM ACTIVATION ALL POWER TO EQUIPMENT BENEATH THE HOODS SHALL BE DEACTIVATED. MOUNT CONTACTOR CABINET(S) JUST BELOW THE CEILING.

M. PROVIDE SEPARATE SWITCHES TO TURN ON HOOD LIGHTS AND FANS. WIRE HOOD TEMP SENSOR AHEAD OF HOOD LIGHT SWITCH. USE 120V CIRCUIT TO CONTROL HOOD FANS THROUGH EXISTING STARTER. PROVIDE CONTROLS TRANSFORMER AS REQUIRED TO MATCH STARTER CONTROL INPUT VOLTAGE. TYPICAL.

N. PROVIDE PLUG LOAD CONTROLS TIED TO THE LIGHTING IN OFFICE SPACES.

O. INTERCONNECT DISH MACHINE TO VENT CONTROL. INTERCONNECT TABLE LIMIT SWITCH TO DISHMACHINE.

P. EXISTING MECHANICAL EQUIPMENT TO BE REPLACED. CONNECT TO CIRCUIT AS SHOWN. RECONNECT TO EXISTING STARTER/CONTACTORS, FIELD VERIFY.

Q. SAWCUT FLOOR TO INSTALL NEW PEDESTAL MOUNTED DEVICE BENEATH NEW SERVING LINES, DO NOT REUSE EXISTING STUB UPS OR DEVICES. POUR BACK SLAB AND PROVIDE NEW FINISHES, REFERENCE ARCHITECTURAL.

R. REFERENCE EDF GFI PROTECTION DETAIL FOR INSTALLATION REQUIREMENTS, TYPICAL.

S. WIRE MICRO SWITCH IN DOOR FRAME TO AIR SCREEN. COOR W/ FOOD SERVICE CONTRACTOR PRIOR TO ROUGH-IN. LOCATE LOCAL MOTOR RATED SWITCH ABOVE CEILING ADJACENT TO THE AIR SCREEN.

COOLER/FREEZER NOTES:

1. PROVIDE SEALING FOR CONDUIT IN COOLER AND FREEZER. WHERE PORTIONS OF INTERIOR RACEWAY SYSTEM ARE EXPOSED TO WIDELY DIFFERENT TEMPERATURES, CIRCULATION OF AIR FROM WARMER TO A COLDER SECTION SHALL BE PREVENTED PER N.E.C. ARTICLE 300.7 (A).
2. PROVIDE GROUND-FAULT PROTECTION OF EQUIPMENT FOR ELECTRIC HEAT TRACING AND HEATING PANELS IN THE FREEZER PER N.E.C. ARTICLE 427.22.
3. ELECTRICAL CONTRACTOR SHALL PROVIDE LIQUID TIGHT CONDUIT AND WIRING FOR LIGHT FIXTURES AND LIGHT SWITCHES IN WALK-IN COOLER AND FREEZER, SEE FOODSERVICE CONSULTANT'S DRAWINGS.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD.
SUGAR LAND, TX 77479

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL FLOOR PLANS

s-E.200

STANTON ENGINEERING GROUP
INFORMATION@SEGHOU.COM (713) 300-8256
TEXAS ENG. FIRM REG. NO. F-01833210
©2025 ALL RIGHTS RESERVED
12800 W. SAM HOUSTON PARKWAY N., SUITE 121, HOUSTON, TX 77040




**1** **FIRE ALARM RENOVATION PLAN**
SCALE: 1/4" = 1'- 0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

**S**

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD.
SUGAR LAND, TX 77479

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING


FIRE ALARM FLOOR PLANS

s-E.300


STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM (713) 300-6082


TEXAS ENG. FIRM REG. NO. F-018332 | © 2021 ALL RIGHTS RESERVED


13300 W. SAM HOUSTON PARKWAY S., SUITE 121, HOUSTON, TX 77043




## 1 PARTIAL ELECTRICAL RISER

NO SCALE

NOTES:
1. FIELD VERIFY ALL EXISTING ELECTRICAL PANELS AND FEEDERS SHOWN ON DRAWINGS.
2. REF ELECTRICAL FLOOR PLANS FOR PANEL LOCATIONS.
3. ALL OUTAGES SHALL BE SCHEDULED/CONFIRMED IN WRITING WITH THE OWNER A MINIMUM OF TWO WEEKS PRIOR TO ANY OUTAGE.
4. AT THE END OF THE PROJECT PROVIDE A NEW TYPEWRITTEN PANEL SCHEDULE USING BUILDING ROOM NUMBERS FOR ALL PANELS WITH CIRCUITS ADDED, REMOVED, OR MODIFIED AS PART OF THE PROJECT.
5. REFERENCE PANEL SCHEDULES AND SHORT CIRCUIT TABLE FOR AIC AND SCCR VALUES.

### NEW KITCHEN PANEL — KITCHEN

**PANEL HK** — 225A MLO, 480Y/277V, 3ϕ, 4 WIRE — AVAILABLE FAULT: SCCR & AIC: 20,250A / 25,000A — MOUNTING: RECESSED, STAINLESS STEEL COVER

| NOTES | EQUIP. NO. | LOAD | DESCRIPTION | WIRE | CB | CKT | A | B | C | CKT | CB | WIRE | DESCRIPTION | LOAD | EQUIP. NO. | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 6 | | 376 | KITCHEN ROOM LIGHTS | 3–12 | 20/1 | 1 | ■ | | | 2 | 15/3 | 3–12 | ESF–1 | 4986 | | |
| 7 | | 1095 | KITCHEN LIGHTS | 3–12 | 20/1 | 3 | | ■ | | 4 | – | +12G | ( 1.5HP / 1.5HP ) | – | | |
| | | 84 | KITCHEN SOFFIT LIGHTS | 3–12 | 20/1 | 5 | | | ■ | 6 | – | 3/4"C | – | – | | |
| | | | SPARE | | 20/1 | 7 | ■ | | | 8 | 15/3 | 3–12 | ESF–2 | 4986 | | |
| | | | SPARE | | 20/1 | 9 | | ■ | | 10 | – | +12G | ( 1.5HP / 1.5HP ) | – | | |
| | | | SPARE | | 20/1 | 11 | | | ■ | 12 | – | 3/4"C | – | – | | |
| | | | SPARE | | 20/1 | 13 | ■ | | | 14 | | | SPACE | | | |
| | | | SPARE | | 20/1 | 15 | | ■ | | 16 | | | SPACE | | | |
| | | | SPARE | | 20/1 | 17 | | | ■ | 18 | | | SPACE | | | |
| | | | SPARE | | 20/1 | 19 | ■ | | | 20 | | | SPACE | | | |
| | | | SPARE | | 20/1 | 21 | | ■ | | 22 | | | SPACE | | | |
| | | | SPACE | | | 23 | | | ■ | 24 | | | SPACE | | | |
| | | | SPACE | | | 25 | ■ | | | 26 | | | SPACE | | | |
| | | | SPACE | | | 27 | | ■ | | 28 | | | SPACE | | | |
| | | | SPACE | | | 29 | | | ■ | 30 | | | SPACE | | | |
| | | | SPACE | | | 31 | ■ | | | 32 | | | SPACE | | | |
| | | | SPACE | | | 33 | | ■ | | 34 | | | SPACE | | | |
| | | | SPACE | | | 35 | | | ■ | 36 | | | SPACE | | | |
| | | | SPACE | | | 37 | ■ | | | 38 | 70/3 | 3–6 | DISHMACHINE | 42963 | E250 | |
| | | | SPACE | | | 39 | | ■ | | 40 | – | +8G | – | – | | |
| | | | SPACE | | | 41 | | | ■ | 42 | – | 3/4"C | – | – | | |

TOTAL LOAD @ 100% = 54490VA — TOTAL LOAD @ 100% = 66A — TOTAL LOAD @ 125% = 82A

### NEW KITCHEN PANEL — KITCHEN

**PANEL LK** — 225A MLO, 208Y/120V, 3ϕ, 4 WIRE — AVAILABLE FAULT: SCCR & AIC: <10,000A / 10,000A — MOUNTING: RECESSED, STAINLESS STEEL COVER

| NOTES | EQUIP. NO. | LOAD | DESCRIPTION | WIRE | CB | CKT | A | B | C | CKT | CB | WIRE | DESCRIPTION | LOAD | EQUIP. NO. | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E10 | 640 | 3 REC – RR/STOR/CUST & BELL | 3–12 | 20/1 | 1 | ■ | | | 2 | 20/1 | 3–12 | 1 REC – KITCHEN | 180 | E10 | |
| | E110 | 1920 | WASHING MACHINE | 3–12 | 20/1 | 3 | | ■ | | 4 | 20/1 | 3–12 | 1 REC – KITCHEN | 180 | E10 | |
| | E110A | 5000 | DRYER | 2–10 | 30/2GFI | 5 | | | ■ | 6 | 20/1 | 3–12 | 1 REC – KITCHEN | 180 | E10 | |
| | E151 | – | – | +10N+10G | 3/4"C | 7 | ■ | | | 8 | 20/2 | 2–10 | HEATED CABINET | 3224 | E187 | |
| | | 540 | 3 REC – OFFICE | 3–12 | 20/1 | 9 | | ■ | | 10 | 3/4"C | +10G | – | – | | |
| | E10 | 540 | 3 REC – KITCHEN | 3–12 | 20/1 | 11 | | | ■ | 12 | 20/2 | 2–10 | HEATED CABINET | 3224 | E187 | |
| | E10 | 360 | 2 REC – SERVING LINE | 3–12 | 20/1 | 13 | ■ | | | 14 | 3/4"C | +10G | – | – | | |
| | E10 | 360 | 2 REC – SERVING LINE | 3–12 | 20/1 | 15 | | ■ | | 16 | 20/3 | 3–12 | DISPOSER | 3960 | E123 | |
| | | 1000 | 2 EDF – CAFETERIA | 3–12 | 20/1 | 17 | | | ■ | 18 | – | +12G | ( 3 HP ) | – | | |
| | E615 | 500 | 2 MENU BOARDS | 3–12 | 20/1 | 19 | ■ | | | 20 | – | 3/4"C | – | – | | |
| | E209 | 960 | MILK COOLER | 3–12 | 20/1 | 21 | | ■ | | 22 | 20/1 | 3–12 | AIR SCREEN | 612 | E101 | |
| | E201A | 5824 | HOT FOOD COUNTER | 2–8 | 35/2 | 23 | | | ■ | 24 | 15/1 | 3–12 | EF–CF ( 1/6HP ) | 528 | | |
| | | – | – | +10G | 3/4"C | 25 | ■ | | | 26 | 15/1 | 3–12 | EF–14 ( 1/6HP ) | 528 | | |
| | E201B | 1920 | COLD FOOD COUNTER | 3–12 | 20/1 | 27 | | ■ | | 28 | 20/1 | 3–12 | EF–2 ( 1/6HP ) | 528 | | |
| | E214 | 360 | CASH REGISTERS | 3–12 | 20/1 | 29 | | | ■ | 30 | 20/1 | | SPARE | | | |
| | E201B | 1920 | COLD FOOD COUNTER | 3–12 | 20/1 | 31 | ■ | | | 32 | 20/1 | | SPARE | | | |
| | E201A | 5824 | HOT FOOD COUNTER | 2–8 | 35/2 | 33 | | ■ | | 34 | 20/1 | | SPARE | | | |
| | | – | – | +10G | 3/4"C | 35 | | | ■ | 36 | 20/1 | | SPARE | | | |
| | E209 | 960 | MILK COOLER | 3–12 | 20/1 | 37 | ■ | | | 38 | 20/1 | | SPARE | | | |
| | | 360 | 2 REC – CAFETERIA | 3–12 | 20/1 | 39 | | ■ | | 40 | 20/1 | | SPARE | | | |
| | | | SPARE | | 20/1 | 41 | | | ■ | 42 | 20/1 | | SPARE | | | |
| | E153/E153M | 250 | HOOD LTS & SENSOR | 3–12 | 20/1 | 43 | ■ | | | 44 | 20/1GFI | 3–12 | DROP CORD | 180 | E129 | |
| | E153/E153M | 250 | HOOD LTS & SENSOR | 3–12 | 20/1 | 45 | | ■ | | 46 | 20/1GFI | 3–12 | DROP CORD | 180 | E129 | |
| 8 | E161 | 720 | CONVECTION OVEN | 3–12 | 20/1GFI | 47 | | | ■ | 48 | 20/1GFI | 3–12 | MOBILE PROOFER | 1800 | E139A | |
| 8 | E161 | 720 | CONVECTION OVEN | 3–12 | 20/1GFI | 49 | ■ | | | 50 | 20/1GFI | 3–12 | 20QT MIXER | 960 | E125 | |
| 8 | E161 | 720 | CONVECTION OVEN | 3–12 | 20/1GFI | 51 | | ■ | | 52 | 20/1GFI | 3–12 | DROP CORD | 180 | E129 | |
| 8 | E161 | 720 | CONVECTION OVEN | 3–12 | 20/1GFI | 53 | | | ■ | 54 | 20/1GFI | 3–12 | DROP CORD | 180 | E129 | |
| 8 | E163 | 600 | TILT BRAISING PAN | 3–12 | 20/1 | 55 | ■ | | | 56 | 20/1GFI | 3–12 | DROP CORD | 180 | E129 | |
| 8 | E172 | 3120 | COMBI OVEN | 2–12 | 20/2 | 57 | | ■ | | 58 | 20/1GFI | 3–12 | DROP CORD | 180 | E129 | |
| | | – | – | +12G | 3/4"C | 59 | | | ■ | 60 | 20/1 | 3–12 | EXISTING CIRCUIT | 500 | | 5 |
| 8 | E172 | 3120 | COMBI OVEN | 2–12 | 20/2 | 61 | ■ | | | 62 | 20/2 | 2–12 | EXISTING CIRCUIT | 1000 | | 5 |
| | | – | – | +12G | 3/4"C | 63 | | ■ | | 64 | – | +12N+12G | – | – | | 5 |
| | | 250 | EXISTING CIRCUIT | 3–12 | 20/1 | 65 | | | ■ | 66 | 20/2 | 2–12 | EXISTING CIRCUIT | 1000 | | 5 |
| 9 | E161 | 0 | TEMP LOAD CENTER | 4–3 | 100/3 | 67 | ■ | | | 68 | – | +12N+12G | – | – | | 5 |
| | | – | – | +8G | – | 69 | | ■ | | 70 | 30/2 | 2–10 | EXISTING CIRCUIT | 3000 | | 5 |
| | | – | – | 1.25"C | – | 71 | | | ■ | 72 | – | +10N+10G | – | – | | |

TOTAL LOAD @ 100% = 61942VA — TOTAL LOAD @ 100% = 172A — TOTAL LOAD @ 65% = 112A

### KITCHEN HOOD CONTACTOR SCHEDULE

**HOOD 1**

| POLE | DESCRIPTION | NORMAL CKT | EM CKT | CONTROL ZONE | EQUIPMENT LOCATION | CONTACTOR TYPE |
|---|---|---|---|---|---|---|
| CK1–1 | CONVECTION OVEN | LK–47 | – | HOOD 1 | KITCHEN | ELECTRICALLY HELD – NO |
| CK1–2 | CONVECTION OVEN | LK–49 | – | HOOD 1 | KITCHEN | ELECTRICALLY HELD – NO |
| CK1–3 | CONVECTION OVEN | LK–51 | – | HOOD 1 | KITCHEN | ELECTRICALLY HELD – NO |
| CK1–4 | CONVECTION OVEN | LK–53 | – | HOOD 1 | KITCHEN | ELECTRICALLY HELD – NO |
| CK1–5 | SPARE | | | | | ELECTRICALLY HELD – NO |
| CK1–6 | SPARE | | | | | ELECTRICALLY HELD – NO |
| CK1–7 | SPARE | | | | | ELECTRICALLY HELD – NO |
| CK1–8 | SPARE | | | | | ELECTRICALLY HELD – NO |

**HOOD 2**

| POLE | DESCRIPTION | NORMAL CKT | EM CKT | CONTROL ZONE | EQUIPMENT LOCATION | CONTACTOR TYPE |
|---|---|---|---|---|---|---|
| CK2–1 | TILT BRAISING PAN | LK–55 | – | HOOD 2 | KITCHEN | ELECTRICALLY HELD – NO |
| CK2–2 | COMBI–OVEN | LK–57/59 | – | HOOD 2 | KITCHEN | ELECTRICALLY HELD – NO |
| CK2–3 | ( 2–POLE ) | – | – | – | – | ELECTRICALLY HELD – NO |
| CK2–4 | COMBI–OVEN | LK–61/63 | – | HOOD 2 | KITCHEN | ELECTRICALLY HELD – NO |
| CK2–5 | ( 2–POLE ) | – | – | – | – | ELECTRICALLY HELD – NO |
| CK2–6 | SPARE | | | | | ELECTRICALLY HELD – NO |
| CK2–7 | SPARE | | | | | ELECTRICALLY HELD – NO |
| CK2–8 | SPARE | | | | | ELECTRICALLY HELD – NO |

1. REFERENCE FLOOR PLANS FOR EQUIPMENT LOCATIONS AND ADDITIONAL INFORMATION.
2. EACH KITCHEN HOOD CONTACTOR HALL BE CONTROLLED ON/OFF BY THE APPROPRIATE HOOD ANSUL SYSTEM. WHEN ACTIVATED ALL POWER WITHIN THE COOKING HOOD SHALL BE DE–ENERGIZED.

### EXIST GE SWITCHBOARD — CENTRAL PLANT

**(E)SWBD MSB** — 1600A MCB, 480Y/277V, 3ϕ, 4 WIRE — AVAILABLE FAULT: SCCR & AIC: 37,000A / 100,000A — FREE STANDING

| NOTES | CIRCUIT | DESCRIPTION | CB | FEEDER SIZE | AMPS |
|---|---|---|---|---|---|
| | 1 | EXTENDED DAY PANEL H | 200/3 | EXIST FEEDER | |
| | 2 | PFCC | 200/3 | EXIST FEEDER | |
| | 3 | EXIST DISTRIBUTION PANEL DA | 400/3 | EXIST FEEDER | 275A |
| | 4 | EXIST DISTRIBUTION PANEL DB | 400/3 | EXIST FEEDER | |
| | 5 | EXIST DISTRIBUTION PANEL AC | 800/3 | EXIST FEEDER | |
| | 6 | EXIST DISTRIBUTION PANEL DC | 400/3 | EXIST FEEDER | |
| 2,3 | 7 | NEW PANEL HK | 225/3 | 4–4/0 +4G, 2.5"C | 66A |
| | 8 | XFMR TLCAB | 125/3 | EXIST FEEDER | |
| | 9 | SPD | 60/3 | EXIST FEEDER | |
| | | | | TOTAL LOAD @ 100% = | 275A |
| | | | | TOTAL LOAD @ 125% = | 344A |

1. THE EXISTING 2000A FEEDER IS SUFFICIENT FOR THE REVISED LOAD.
2. UPDATE PANEL SCHEDULE TO MATCH REVISED EQUIPMENT DESCRIPTION.

### EXIST WESTINGHOUSE PANELBOARD — STORAGE ROOM

**(E)PANEL DA** — 400A MLO, 480Y/277V, 3ϕ, 4 WIRE — AVAILABLE FAULT: SCCR & AIC: 27,000A / 35,000A — MOUNTING: SURFACE

| NOTES | LOAD | DESCRIPTION | WIRE | CB | CKT | A | B | C | CKT | CB | WIRE | DESCRIPTION | LOAD | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | 9150 | AHU #2 | EXIST | 20/3 | 1 | ■ | | | 2 | 60/3 | EXIST | DUCT HEATER 3 | 39000 | |
| | – | – | – | – | 3 | | ■ | | 4 | – | – | ( STAGE ) | – | |
| | – | – | – | – | 5 | | | ■ | 6 | – | – | – | – | |
| | 2300 | LIGHTS CAFETORIUM RMS | EXIST | 20/1 | 7 | ■ | | | 8 | 20/1 | EXIST | LTS KITCHEN | | 2 |
| | 3000 | LIGHTS CAFETORIUM | EXIST | 20/1 | 9 | | ■ | | 10 | 20/1 | EXIST | LIGHTS CAFETORIUM RMS | 3000 | |
| | 4500 | HWH MECH RM 029 | EXIST | 25/1 | 11 | | | ■ | 12 | 70/3 | 3–6 | TEMP KITCHEN PANEL LTK | 37918 | 4 |
| | | SPACE | | | 13 | ■ | | | 14 | – | +8G | – | – | |
| | | SPACE | | | 15 | | ■ | | 16 | – | 3/4"C | – | – | |
| | | SPACE | | | 17 | | | ■ | 18 | | | SPACE | | |
| | | SPACE | | | 19 | ■ | | | 20 | | | SPACE | | |
| | | SPACE | | | 21 | | ■ | | 22 | | | SPACE | | |
| | | SPACE | | | 23 | | | ■ | 24 | | | SPACE | | |
| | 130000 | PANEL PA | EXIST | 225/3 | 25 | ■ | | | 26 | – | – | – | – | |
| | – | ( SUBFEED BREAKER ) | – | – | 27 | | ■ | | 28 | – | – | – | – | |
| | – | – | – | – | 29 | | | ■ | 30 | – | – | – | – | |

TOTAL LOAD @ 100% = 228868VA — TOTAL LOAD @ 100% = 275A — TOTAL LOAD @ 125% = 344A

1. THE EXISTING 400A FEEDER IS SUFFICIENT FOR THE REVISED LOAD.
2. UPDATE PANEL SCHEDULE TO MATCH REVISED EQUIPMENT DESCRIPTION.

### EXIST EM STANDBY PANELBOARD — STORAGE ROOM

**(E)PANEL ELA** — 60A MCB, 208Y/120V, 3ϕ, 4 WIRE — AVAILABLE FAULT: SCCR & AIC: <10,000A / 10,000A — MOUNTING: SURFACE

| NOTES | EQUIP. NO. | LOAD | DESCRIPTION | WIRE | CB | CKT | A | B | C | CKT | CB | WIRE | DESCRIPTION | LOAD | EQUIP. NO. | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | 250 | FACP | EXIST | 20/1 | 1 | ■ | | | 2 | 20/1 | 3–12 | REFRIGERATOR | 864 | E188 | 3 |
| | | 250 | FACP | EXIST | 20/1 | 3 | | ■ | | 4 | 20/1 | 3–12 | REFRIGERATOR | 864 | E188 | 3 |
| | | 250 | FACP | EXIST | 20/1 | 5 | | | ■ | 6 | 20/1 | 3–12 | ICE MACHINE | 1428 | E109 | 3 |
| | | 250 | FACP | EXIST | 20/1 | 7 | ■ | | | 8 | 20/1 | 3–12 | HOOD ANSUL SYSTEMS | 240 | E151 | 4 |
| | | 250 | PA SYSTEM | EXIST | 20/1 | 9 | | ■ | | 10 | 25/3 | 3–10 | REFRIGERATION SYSTEM | 6192 | E103 | 4 |
| | | 250 | SECURITY PANEL | EXIST | 20/1 | 11 | | | ■ | 12 | – | +10G | – | – | | |
| | | 120 | GEN BATTERY CHARGER | EXIST | 20/1 | 13 | ■ | | | 14 | – | 3/4"C | – | – | | |
| | | 1000 | GEN COOLANT HEATER | EXIST | 20/1 | 15 | | ■ | | 16 | 20/1EGF | 3–12 | COOLER DOOR HEATER/LTS | 600 | E102A | 4 |
| | | 300 | GEN HEATER | EXIST | 20/1 | 17 | | | ■ | 18 | 20/1EGF | 3–12 | FREEZER DOOR HEATER/LTS | 600 | E102A | 4 |
| | | 180 | GEN RECEPTACLE | EXIST | 20/1 | 19 | ■ | | | 20 | 20/1EGF | 3–12 | FREEZER DRAIN LINE HEATER | 600 | E103F | 4 |
| 3 | E102B | 600 | COOLER TEMP. ALARM | 3–12 | 20/1 | 21 | | ■ | | 22 | 20/2 | 2–10 | FREEZER COIL | 1893 | E103C | 4 |
| 3 | E102C | 600 | COOLER/FRZR PRESSURE PORT | 3–12 | 20/1 | 23 | | | ■ | 24 | – | +10G | – | – | | |
| 3 | E102E | 120 | PANIC ALARM BUTTONS | 3–12 | 20/1 | 25 | ■ | | | 26 | 30/3 | EXIST | SPD | 50 | | |
| 3 | E103D | 216 | COOLER COIL | 3–12 | 20/1 | 27 | | ■ | | 28 | – | – | – | – | | |
| 3 | E102B | 600 | FREEZER TEMP. ALARM | 3–12 | 20/1 | 29 | | | ■ | 30 | – | – | – | – | | |

TOTAL LOAD @ 100% = 18567VA — TOTAL LOAD @ 100% = 52A — NEC DIVERSIFIED LOAD = 56A

1. THE EXISTING 60A FEEDER IS SUFFICIENT FOR THE REVISED LOAD.
2. UPDATE PANEL SCHEDULE TO MATCH REVISED EQUIPMENT DESCRIPTION.

GENERAL PANEL REQUIREMENTS:
A. REF ELECTRICAL FLOOR PLANS FOR PANEL LOCATIONS.
B. FIELD VERIFY EXISTING CIRCUITS PRIOR TO BEGINNING WORK.
C. ALL OUTAGES SHALL BE SCHEDULED AND CONFIRMED IN WRITING WITH THE OWNER A MINIMUM OF TWO WEEKS PRIOR TO ANY OUTAGE.
D. AT THE END OF THE PROJECT PROVIDE A NEW TYPEWRITTEN PANEL SCHEDULE USING BUILDING ROOM NUMBERS FOR ALL PANELS WITH CIRCUITS ADDED, REMOVED, OR MODIFIED AS PART OF THE PROJECT.

PANEL NOTES:
1. REVISE/REWORK WIRING/CONDUIT AS REQUIRED TO ADD/REMOVE DEVICES FROM EXISTING CIRCUIT.
2. EXISTING CIRCUIT TO BE DEMO.
3. REUSE EXISTING SPARE CB AND WIRE NEW CIRCUIT.
4. PROVIDE NEW CB & WIRE NEW CIRCUIT.
5. IDENTIFY ANY CIRCUITS OR PARTIAL CIRCUITS THAT EXTEND BEYOND THE AREA OF RENOVATION. PROVIDE TEMPORARY FEED TO MAINTAIN ALL CIRCUITS SERVING ELEMENTS/SPACES NOT TO BE REMOVED DURING CONSTRUCTION. RECONNECT EXISTING CIRCUITS/DEVICES TO REMAIN TO TEMPORARY KITCHEN PANEL ONCE AVAILABLE USING CB(S) PROVIDED. ALL PARTIAL CIRCUITS SHALL REMAIN AND REMAIN ACTIVE BOTH DURING AND AFTER CONSTRUCTION.
6. KITCHEN LIGHTS TO BE DUAL ZONES WIRED THROUGH LIGHTING CONTACTORS AND CONTROLLED ON/OFF BY THE BAS AND LOCAL LIGHTING SWITCHES.
7. EXTERIOR LIGHTS TO BE WIRED THROUGH LIGHTING CONTACTOR AND CONTROLLED ON/OFF BY THE BAS.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD.
SUGAR LAND, TX 77479

SEAL

STATE OF TEXAS — GEORGE L. STANTON — 38582 — REGISTERED PROFESSIONAL ENGINEER
07.18.2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL SCHEMATIC

s-E.400

STANTON ENGINEERING GROUP
INFO@STANTON–ENGR.COM (713) 300–4082
TEXAS ENGINEERING FIRM REG NO. F–018332 | 2021 ALL RIGHTS RESERVED
13999 W. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77040

## PLUMBING SYMBOLS LEGEND

| | | | |
|---|---|---|---|
| ——— | SANITARY WASTE BELOW SLAB | SAN. | SANITARY |
| ——— | SANITARY WASTE ABOVE SLAB | CW | DOMESTIC COLD WATER |
| —— V. —— | VENT PIPING ABOVE SLAB | HW | DOMESTIC HOT WATER |
| — — — — | VENT PIPING | WC | WATER CLOSET |
| —— G —— | GAS PIPING, 4–8oz | UR | URINAL |
| —— G5 —— | GAS PIPING, 5LB | LAV | LAVATORY |
| —·—·— | DOMESTIC COLD WATER PIPING | SK | SINK |
| —·—·—·— | DOMESTIC HOT WATER PIPING | EDF | ELECTRIC DRINKING FOUNTAIN |
| —— D —— | DRAIN/RELIEF VENT PIPING | WH | WALL HYDRANT |
| —⋈— | STOP VALVE | HB | HOSEBIBB |
| 2CO | DOUBLE SAN. CLEANOUT (2–WAY) | CP | HOT WATER CIRCULATOR PUMP |
| CO | SANITARY SEWER CLEANOUT | FD | FLOOR DRAIN |
| WCO | WALL CLEANOUT | FSINK | FLOOR SINK |
| EXIST. | EXISTING | | |
| (R) | REMOVE (DEMOLISH) | | |
| (D) | DEMOLISH (REMOVE) | | |
| (E) | EXISTING – NO WORK | | |

## PLUMBING FIXTURE NOTES

1. ALL FIXTURES SHALL MEET WATER CONSERVATION PERFORMANCE STANDARDS MANDATED BY SENATE BILL 587. ALL FIXTURES SHALL HAVE FLOW RESTRICTION DEVICES (DRINKING FOUNTAINS SHALL BE SELF–CLOSING) TO COMPLY WITH THESE REQUIREMENTS.
2. ALL FIXTURES SHALL HAVE CONTROLS REQUIRING OPERATING FORCE NO GREATER THAN FIVE (5) POUNDS.
3. FOR LAVATORIES AND SINKS, ALL FAUCETS SHALL BE NO–LEAD SOLID BRASS, MEETING ALL REQUIREMENTS OF ANSI/NSF 61, SECTION 9 AND CERTIFIED AS SUCH. ALSO, INSTALL SYMMONS 7–210 MIXING VALVE ON HOT WATER SUPPLY SIDE OF ALL FAUCETS UNLESS HIGH TEMPERATURE LIMIT IS PROVIDED WITH FAUCET. MAXIMUM WATER TEMPERATURE FOR ALL FAUCETS THAT DELIVER HOT OR TEPID WATER SHALL BE 110°F. ALL METERING FAUCETS SHALL HAVE A MINIMUM TEN (10) SECONDS OF WATER FLOW, AND, INSTALL TRUEBRO HANDI LAV–GUARD VANDAL–PROOF INSULATION KITS OVER P–TRAP, SUPPLIES, STOPS AND ALL SHARP EDGES FOR ALL SINKS AND LAVATORIES (TRAP WRAP FROM BROCAR OR PROWRAP FROM McGUIRE SHALL BE ACCEPTABLE).
4. ALL PLUMBING FIXTURES REFERENCED AS "ADA", "TAS" OR "HANDICAP COMPLIANT" SHALL MEET ALL REQUIREMENTS OF THE ADA AND THE TEXAS ACCESSIBILITY STANDARDS. IT SHALL BE THE PLUMBING CONTRACTORS RESPONSIBILITY TO MEET THESE REQUIREMENTS.
5. IN MANY CASES, FIXTURES WITH THE SAME PLUMBING DESIGNATION HAVE DIFFERENT INSTALLATION HEIGHTS – REFERENCE ARCHITECTURAL DRAWINGS FOR ALL INSTALLATION HEIGHTS AND HANDICAP FIXTURE DESIGNATIONS. FIXTURES DESIGNATED AS ADULT HANDICAP SHALL MEET ALL REQUIREMENTS OF THE ADA. FIXTURES DESIGNATED AS CHILD HANDICAP SHALL MEET ALL REQUIREMENTS OF THE TEXAS ACCESSIBILITY STANDARDS FOR THE APPROPRIATE CHILDREN'S AGE GROUP (REF. ARCH. DWGS. AND SPECIFICATIONS).

## PLUMBING MATERIALS

SANITARY WASTE AND VENT

BELOW SLAB/GRADE: SCHEDULE 40, DWV PVC

ABOVE SLAB: STANDARD WEIGHT, CAST IRON, NO–HUB PIPING.

STORM DRAIN PIPING

BELOW SLAB/GRADE: SCHEDULE 40, DWV PVC

ABOVE SLAB, 8" AND UNDER: STANDARD WEIGHT, CAST IRON, NO–HUB PIPING.

ABOVE SLAB, 10" AND ABOVE: SERVICE WEIGHT, CAST IRON, BELL & SPIGOT.

NATURAL GAS

BELOW GRADE (OUTSIDE): YELLOW POLYETHYLENE PIPE WITH COATED STEEL RISER AND TRACER WIRE.

ABOVE SLAB: SCHEDULE 40 BLACK STEEL. PIPING 2.5" AND LARGER SHALL BE WELDED. PIPING 2" AND SMALLER SHALL HAVE SCREWED FITTINGS.

DOMESTIC WATER

INTERIOR: TYPE L COPPER WITH SOLDER TYPE WROUGHT COPPER FITTINGS, MADE UP WITH LEAD–FREE SOLDER.

EXTERIOR: TYPE K COPPER WITH SWEAT FITTINGS AND LEAD–FREE SOLDER. BEYOND 5 FEET FROM BUILDING, SCHEDULE 40 PVC.

## FIRE SPRINKLER SYSTEM NOTES


1. THE EXISTING FIRE SPRINKLER SYSTEM SHALL BE MODIFIED AND/OR EXPANDED TO COVER THE AREA OF RENOVATION IN ENTIRETY. ALL NEW AND REVISED PIPING SHALL BE ENGINEERED AND INSTALLED BY A LICENSED FIRE SPRINKLER CONTRACTOR.
2. REFERENCE THE SPECIFICATIONS, DIVISION 21, FOR MORE INFORMATION.

## GENERAL PLUMBING NOTES

1. SEE ARCHITECTURAL DRAWINGS AND SPECIFICATIONS FOR ADDITIONAL WORK DESCRIPTION. SEE THIS SHEET (P4.00) FOR PLUMBING SYMBOLS LEGEND.
2. COORDINATE PLUMBING SYSTEMS INSTALLATION WITH ARCHITECTURAL, STRUCTURAL, HVAC SYSTEMS, ELECTRICAL SYSTEMS, CONDUITS, ETC.... OFFSET PIPING AS REQUIRED TO PROVIDE A FUNCTIONING SYSTEM WITH ADEQUATE SPACE FOR SERVICING AND REPAIRS.
3. MAKE CONNECTIONS OF NEW PIPE SYSTEMS IN TO EXISTING PIPE SYSTEMS WITH THREADED OR SWEAT JOINTS. PROVIDE ELECTROLYSIS ISOLATING UNIONS AT CONNECTION OF DISSIMILAR MATERIALS. REFERENCE THE SPECIFICATIONS.
4. SITE SERVICES ARE SHOWN FOR REFERENCE ONLY. PLUMBING CONTRACTOR SHALL REFERENCE CIVIL DRAWINGS, INCLUDING LOCATIONS OF SERVICES, SIZES OF PIPES, FLOWLINE ELEVATIONS, ETC..
5. DO NOT INSTALL PLUMBING PIPING OVER ANY ELECTRICAL EQUIPMENT. REFERENCE ELECTRICAL DRAWINGS FOR LOCATIONS OF ELECTRICAL EQUIPMENT AND COORDINATE WITH ELECTRICAL SUBCONTRACTORS ACCORDINGLY. SEE DETAIL 2/MEP1. THIS INCLUDES FIRE SPRINKLER PIPING.
6. ALL PIPES THROUGH WALLS OR FLOORS SHALL BE SLEEVED AND SEALED PER DETAIL 5/P4.02. FIRE CAULK WHERE REQUIRED. THIS INCLUDES ALL WALLS, INTERIOR AND EXTERIOR. THIS INCLUDES FIRE SPRINKLER PIPING.
7. ALL CLEANOUTS SHALL BE CONNECTED TO SANITARY LINES USING WYES AND/OR LONG RADIUS ELLS. SANITARY TEES ARE NOT ACCEPTABLE. 2" MINIMUM SIZE. ALL WALL CLEAN OUTS IN VERTICAL RISERS, OR BANKS OF FIXTURES SHALL BE INSTALLED 4" ABOVE THE FLOOD RIM LEVEL OF THE LOWEST CONNECTED FIXTURE AND A MINIMUM OF 24" AFF.
8. ALL WASTE AND VENT PIPING BELOW SLAB SHALL BE 2" MINIMUM.
9. LOCATE PLUMBING VENTS THROUGH ROOF NOT NEARER THAN SIX (6) FEET AWAY FROM EDGE OF BUILDING AND TEN (10) FEET AWAY FROM ANY FRESH AIR INTAKES. OFFSET VENT PIPING, AS REQUIRED, IN CEILING SPACE BETWEEN CEILING AND ROOF TO MEET THESE REQUIREMENTS. SEE DETAIL 3/P4.02.
10. ALL DOMESTIC WATER PIPING (CW, HW AND HWR) SHALL BE INSULATED PER THE WRITTEN SPECIFICATIONS.
11. TOP OF FLOOR DRAINS IN MECHANICAL, AHU AND BOILER ROOMS SHALL BE SET 1–1/2" BELOW FINISHED FLOOR SURFACE. CONCRETE FLOOR SHALL BE SLOPED TO DRAIN, REFERENCE ARCHITECTURAL DRAWINGS. IN ALL OTHER LOCATIONS, FLOOR DRAINS SHALL BE SET FLUSH WITH FINISHED FLOOR, TAKING INTO ACCOUNT ANY FLOOR SLOPE OR FLOOR FINISH (TILE, TERRAZZO, ETC.) AS SHOWN ON ARCHITECTURAL DRAWINGS.
12. PROVIDE AN ISOLATING VALVE AT EACH WATER TAP OFF HOT AND COLD WATER MAINS TO ALLOW FOR SERVICING. VALVE SHALL BE BALL VALVE IF PIPE SIZE IS 2" OR LESS AND GATE VALVE OR BUTTERFLY VALVE IF LARGER THAN 2". SEE WRITTEN SPECIFICATIONS. VALVES SHALL BE EASILY ACCESSIBLE. PROVIDE 18" X 18", FIRE–RATED, STAINLESS STEEL ACCESS PANELS WITH HINGED, CYLINDRICAL LOCK DOORS WHERE VALVES ARE INSTALLED ABOVE INACCESSIBLE CEILINGS OR IN WALL CHASES (MIFAB MODEL MPFR–SS–C). BALL VALVES AND BUTTERFLY VALVES INSTALLED ABOVE CEILINGS SHALL BE INSTALLED SUCH THAT HANDLE IS ON BOTTOM OF PIPE. ISOLATING WATER VALVES ABOVE CEILINGS SHALL BE INSTALLED NO MORE THAN 24" ABOVE CEILING. VALVES ABOVE INACCESSIBLE CEILINGS SHALL BE INSTALLED WITHIN REASONABLE REACH OF CEILING MOUNTED ACCESS PANEL.
13. WATER HAMMER ARRESTERS SHALL BE INSTALLED IN ADDITION TO AIR CHAMBERS PER THE RISER DIAGRAMS. SEE SPECIFICATIONS.
14. MECHANICALLY CLEAN ALL WASTE LINES WITH ROTARY MACHINE TO PROVE FREE FLOWING, SEE SPECIFICATIONS.
15. PROVIDE VENTED SLEEVE (2 PIPE SIZES LARGER THAN GAS PIPE UNLESS NOTED OTHERWISE) FOR ALL GAS PIPING IN GROUND BELOW PAVING OR SIDEWALKS AND INSIDE BUILDING IN WALLS AND IN UNVENTILATED CEILING SPACES, SEE SPECIFICATIONS.
16. GAS PIPING SHALL BE 1/2" MINIMUM. TAP GAS PIPING ON TOP OR SIDES ONLY. DO NOT INSTALL VALVES IN CEILING PLENUM OR IN ANY INACCESSIBLE LOCATION. ALL GAS VALVES SHALL BE EASILY ACCESSIBLE. REFER TO DETAIL 9/P4.01 FOR TYPICAL GAS CONNECTION INSTALLATION. REFER TO DETAIL 8/P4.02 FOR TYPICAL PRV INSTALLATION.
17. CENTER WALL HYDRANTS IN BRICK PATTERN OF EXTERIOR WALLS, REFERENCE THE ARCHITECTURAL DRAWINGS AND SPECIFICATIONS.
18. ALL REFRIGERATORS WITH ICE MAKERS, COMMERCIAL TYPE COFFEE MAKERS, ICE MAKERS, COFFEE VENDING MACHINES AND OTHER ITEMS PROVIDED THAT REQUIRE A WATER CONNECTION SHALL HAVE A CW VALVE BOX, "VBOX", INSTALLED TO ALLOW EASY ACCESS AND REMOVAL OF MACHINE. ALSO, INSTALL IN–LINE FILTER IN WATER CONNECTION.
19. REFER TO CIVIL DRAWINGS FOR SITE SANITARY, SITE STORM SEWER, FIRE SERVICE AND DOMESTIC WATER SERVICE. PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR ALL PIPING INSIDE BUILDING TO OUTSIDE LOCATIONS SHOWN ON PLUMBING DRAWINGS. PLUMBING CONTRACTOR SHALL INCLUDE COST OF FINAL TIE–INS TO SITE SERVICES.
20. PER THE DRAWINGS, ALL DRAINS (FLOOR DRAINS, FLOOR SINKS, HUB DRAINS, KITCHEN DRAINS, SHOWER DRAINS, ETC.) SHALL BE VENTED AND TRAP PRIMED – NO EXCEPTIONS. TRAP PRIMING SHALL BE ACCOMPLISHED USING WATER CLOSET FLUSH VALVE TRAP PRIMING DEVICES OR PROSET SYSTEMS TRAP GUARD SEWER GAS EMISSION PROTECTION, AS SHOWN ON DRAWINGS. REFERENCE PLUMBING FLOOR PLANS AND RISER DIAGRAMS.
21. ALL PIPING LOCATED ON ROOF (GAS PIPING) SHALL BE INSTALLED ON ROOF PIPE SUPPORTS PER DETAIL 10/P4.02, 6–FOOT ON CENTER. INSTALL ROOF PIPE JACK PER DETAIL 9/P4.02 FOR ALL PIPING THROUGH ROOF.
22. COORDINATE LOCATIONS OF ALL ROOF DRAINS AND OVERFLOW ROOF DRAINS WITH ARCHITECTURAL DRAWINGS.
23. FOR COMBINATION WASTE AND VENT SYSTEMS (WHERE APPLICABLE ON DRAWINGS), DRAIN P–TRAPS SHALL BE SIZE OF PIPE SHOWN ON DRAWINGS (I.E. TWO PIPE SIZES LARGER THAN DRAIN SIZE). FOR EXAMPLE, A 4" FLOOR DRAIN SHALL HAVE A 6" P–TRAP.
24. FOR ALL PLUMBING FIXTURES, IF COPPER PIPING IS STUBBED THROUGH WALL FOR DRAIN CONNECTION, INSTALL MARVEL FITTING AT DRAIN CONNECTION FOR EASE OF SERVICING AND REPAIRS. COPPER DRAIN PIPING WILL ONLY BE ALLOWED FOR DIRECT/STRAIGHT STUB–OUT OF FIXTURE DRAIN PIPING THROUGH WALL.
25. DO NOT INSTALL ANY PIPING BENEATH CVT OR VAV BOXES. THIS INCLUDES FIRE SPRINKLER PIPING.
26. WHERE UNDERGROUND VENT PIPE SIZE IS NOT NOTATED, VENT SHALL BE 2" DIAMETER.
27. WHERE UNDERGROUND SANITARY PIPE SIZE IS NOT NOTATED, REFER TO THE RISER DIAGRAMS FOR SIZE. NOT BELOW GRADE SANITARY PIPE SHALL BE SMALLER THAN 2". NO SANITARY LINE OR P–TRAP FOR A DRAIN/FIXTURE SHALL BE SMALLER THAN THE FIXTURE CONNECTION SIZE SHOWN ON THE DRAIN/FIXTURE SCHEDULE.
28. WHERE ABOVE GROUND VENT PIPE SIZE IS NOT NOTATED, REFER TO THE RISER DIAGRAMS FOR VENT SIZE.
29. WHERE CW/HW PIPING SIZE TO THE FIXTURE IS NOT SHOWN ON THE FLOOR PLAN, REFER TO THE RISER DIAGRAMS FOR CW/HW PIPE SIZE. NO PIPING TO FIXTURE SHALL BE SMALLER THAN THE FIXTURE CONNECTION SIZE SHOWN ON THE FIXTURE SCHEDULE.
30. TO INSTALL NEW PLUMBING SYSTEMS BELOW EXISTING CONCRETE SLABS, FIRST PLUMBING CONTRACTOR SHALL LAY OUT CUT. THEN, DEMOLITION CONTRACTOR SHALL SAW CUT SLAB TO CONTROL CRACKING AND REMOVE ALL CONCRETE. PLUMBING CONTRACTOR SHALL THEN EXCAVATE FILL TO PROPER SLOPE, INSTALL NEW PIPING SYSTEMS AS REQUIRED, THEN BACKFILL AND COMPACT TO PROPER DENSITY. THE CONCRETE CONTRACTOR SHALL THEN INSTALL NEW SIX (6) MIL POLYETHYLENE VAPOR BARRIER AND SEAL, INSTALL NEW REINFORCING STEEL AND WELD ON TO EXISTING, THEN RE–POUR CONCRETE TO NEW LEVEL. DO NOT CUT THROUGH GRADE BEAMS WITHOUT APPROVAL FROM THE STRUCTURAL ENGINEER. SEE ARCHITECTURAL AND STRUCTURAL DRAWINGS AND SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.
31. ALL ABANDONED FIXTURES, DRAINS AND PIPING (INCLUDING PIPING ABANDONED IN THE PAST) IN AREAS WHERE WORK IS BEING DONE SHALL BE COMPLETELY REMOVED FROM BUILDING (INCLUDING PIPING BELOW SLAB/GRADE – UNLESS SHOWN OTHERWISE ON DRAWINGS). EXISTING WATER PIPING SHALL BE CAPPED AT EXISTING WATER MAIN TAPS AND ALL ABANDONED PIPING REMOVED. ABANDONED VENT PIPING SHALL BE COMPLETELY REMOVED, INCLUDING EXISTING VTR'S NOT RE–USED. PATCH AS REQUIRED. ONLY ACTIVE PIPING, FIXTURES AND DRAINS SHALL REMAIN IN BUILDING WHERE WORK IS BEING DONE.

## GAS PRV SCHEDULE

| MARK | PRV–K |
|---|---|
| LOCATION | MECH. YARD |
| SERVES | KITCHEN |
| GAS LOAD | 585 CFH |
| DISTANCE FROM METER | 150 FT |
| DISTANCE TO LAST OUTLET | 200 FT |
| INLET (SIZE/PRESSURE) | 1" / 5 PSI |
| OUTLET (SIZE/PRESSURE) | 2" / 7–12 IN WC |




### 4 GAS PRESSURE REGULATOR DETAIL (PRV)

NO SCALE

NOTES:
1. GAS REGULATOR SHALL BE ANSI Z21.80 CERTIFIED FOR LINE PRESSURE REGULATION BETWEEN THE SERVICE REGULATOR AND CONNECTED EQUIPMENT.
2. ALL GAS REGULATORS WITH INLET PRESSURE ABOVE 2 PSI SHALL BE EQUIPPED WITH A FACTORY INSTALLED OVERPRESSURE PROTECTION DEVICE, AS PART OF THE ANSI Z21.80 CERTIFICATION.
3. GAS REGULATOR SHALL BE EQUIPPED WITH A VENT LIMITING DEVICE, SIZED IN ACCORDANCE WITH THE REGULATOR OUTLET PRESSURE.
4. ALL REGULATORS INSTALLED OUTDOORS SHALL BE RATED FOR OUTDOOR INSTALLATION.
5. BASIS OF DESIGN IN THE MAXITROL 325–L SERIES OF REGULATORS

## PLUMBING DRAINS, CLEANOUTS AND HYDRANTS


| MARK | MIN. CONNECTION SIZES (IN.) SAN | VENT | CW | HW | DESCRIPTION/SPECIFICATION FOR FIXTURE OR EQUIPMENT |
|---|---|---|---|---|---|
| FD | 4 | 2 | 1/2 | – | TOILET FLOOR DRAIN – TWO–PIECE CAST IRON WITH SEEPAGE FLANGE, REVERSIBLE CLAMPING COLLAR, 1/2" TRAP PRIMER TAP, 6" SQUARE, NICKEL BRONZE HISTRAINER AND SECURITY SCREWS JR SMITH MODEL 2005–03–K06PB–P050–U. |
| FD2 | 4 | 2 | 1/2 | – | EQUIPMENT FLOOR DRAIN – CAST IRON, MEDIUM DEPTH DRAIN WITH FLANGE, CLAMPING DEVICE, SEEPAGE OPENINGS, DUCTILE IRON TRUE–FIT SEDIMENT BUCKET WITH 12" STAINLESS STEEL RIM LESS GRATE, 1/2" TRAP PRIMER TAP ZURN MODEL ZS–540–U–P DRAIN SHALL BE DESIGNED SUCH THAT GRATE CANNOT BE INSTALLED WITHOUT SEDIMENT BUCKET. |
| FD3 | 4 | 2 | 1/2 | – | GRATED MECHANICAL ROOM FLOOR DRAIN – CAST IRON WITH FLANGE, SEEPAGE OPENINGS, 9" HEAVY–DUTY DUCTILE IRON GRATE WITH STAINLESS STEEL VENEER, CLAMPING DEVICE AND 1/2" TRAP PRIMER TAP ZURN MODEL ZS–550–C–P |
| FD4 | 4 | 2 | 1/2 | – | CANWASH FLOOR DRAIN – ALL GALVANIZED CAST IRON, MEDIUM DEPTH DRAIN WITH FLANGE, CLAMPING DEVICE, SEEPAGE OPENINGS, GALVANIZED SUR–SET SEDIMENT BUCKET WITH 12" GALVANIZED DUCTILE IRON RIM AND GRATE, 1/2" TRAP PRIMER TAP ZURN MODEL ZS–540–P–G–HD. DRAIN SHALL BE DESIGNED SUCH THAT GRATE CANNOT BE INSTALLED WITHOUT SEDIMENT BUCKET. |
| FD5 | 4 | 2 | 1/2 | – | KITCHEN FLOOR DRAINS SHALL BE SIMILAR EXCEPT WITH 7" SQUARE, BRONZE GRATE JR SMITH MODEL 2005–03–K07PB–P050–U PROVIDE 4" DIAMETER STAINLESS STEEL FUNNEL WHERE SHOWN ON DRAWINGS. REFERENCE KITCHEN CONNECTION SCHEDULE ON PLUMBING RENOVATION FLOOR PLAN SHEET. |
| FS KITCHEN FS | 4 | 2 | 1/2 | – | FLOOR SINK – CAST IRON, 8" DEEP SUMP, A.R.E. INTERIOR, INTEGRAL FLANGE FOR SUPPORT, CLAMPING DEVICE WHERE VAPOR BARRIER IS INSTALLED BETWEEN SLAB AND CONCRETE BEDDING FOR FLOOR, ALUMINUM SECONDARY DOME STRAINER AND 12" SQUARE HEAVY DUTY STAINLESS STEEL TRACTOR DUTY FRAME WITH 3/4–TRACTOR GRATE AND 1/2" TRAP PRIMER TAP JR SMITH MODEL 3150Y–04–C–13. |
| CO | VARIES | – | – | – | FLOOR CLEANOUT – ADJUSTABLE EXTENSION HOUSING, CAST IRON FERRULE WITH FULL–LINE–SIZE BRASS PLUG (UP TO 4"), 5" DIAMETER STAINLESS STEEL ACCESS COVER WITH VANDAL–PROOF SCREW, ROUND FRAME AND TOP LOAD RATING COMPATIBLE WITH FLOOR TYPE (REFERENCE ARCHITECTURAL DRAWINGS FOR FLOOR TYPES) ZURN MODEL ZS–1400–VP. PROVIDE CARPET FRANGE FOR CARPETED AREAS (CARPET MARKER SHALL NOT BE ACCEPTABLE) AND TERRAZZO RECESS FOR TERRAZZO FLOORS.<br>OUTDOOR CLEANOUT – SAME AS TYPE "CO" EXCEPT WITH HEAVY–DUTY NICKEL BRONZE TOP ZURN MODEL ZN–1400–HD–VP. INSTALL 18" X 18" X 6" THICK CONCRETE PAD AROUND EACH OUTDOOR CLEANOUT. |
| WCO | VARIES | – | – | – | WALL CLEANOUT – CAST IRON FERRULE WITH COUNTERSUNK HEAD (FULL–LINE–SIZE PVC PLUG UP TO 4") MI–FAB MODEL CMSD. ACCESS COVER SHALL BE 8" SQUARE, SURFACE MOUNT, FLUSH INSTALLATION, 16–GAUGE STAINLESS STEEL ACCESS DOOR WITH FLANGED FRAME AND VANDAL–PROOF OPTION MI–FAB MODEL UA–SS–VP. ACID WASTE CLEANOUT (AWCO) SHALL BE SAME EXCEPT ACID WASTE PIPING.<br>INSIDE CABINETWORK WHERE CLEANOUT IS NOT VISIBLE, ACCESS PANEL MAY BE ROUND STAINLESS STEEL TYPE WITH VANDAL–PROOF CENTER SCREW MI–FAB MODEL C1450–RD–3–6. |
| 2CO | 4 | – | – | – | DOUBLE CLEANOUTS – SAME AS OUTDOOR CLEANOUTS. INSTALLED FOR TWO–WAY RODDING. SINGLE CLEANOUT WITH 2–WAY FITTING IS NOT ACCEPTABLE, PROVIDE TWO SEPARATE CLEANOUTS. INSTALL 18" X 18" X 6" THICK CONCRETE PAD AROUND EACH OUTDOOR CLEANOUT. |
| HB | – | – | 3/4 | – | HOSEBIBB – 3/4" HOSE THREAD, INTEGRAL VACUUM BREAKER SPOUT, ROUGH CHROME FINISH WITH REMOVABLE KEYED HANDLE, WALL FLANGE CHICAGO MODEL 952. |
| WH | – | – | 3/4 | – | RESTROOM WALL HYDRANT – NARROW WALL, WARM CLIMATE TYPE HOSE BOX, QUARTER–TURN WHEEL HANDLE, ASSE APPROVED ANTI–SIPHON INTEGRAL VACUUM BREAKER AND DUAL CHECK VALVE, 3/4" STRAIGHT INLET HOSE CONNECTION, CAST STAINLESS STEEL HYDRANT BOX, FLUSH MOUNTED 16–GAUGE STAINLESS STEEL FRAME AND 180° DROP DOWN DOOR WITH KEY LOCK AND WALL CLAMP JR SMITH MODEL 5518 |
| WH2 | – | – | 3/4 | – | EXTERIOR WALL HYDRANT – NON–FREEZE HOSE BOX, QUARTER–TURN WHEEL HANDLE, ASSE APPROVED ANTI–SIPHON INTEGRAL VACUUM BREAKER AND DUAL CHECK VALVE, 3/4" STRAIGHT INLET HOSE CONNECTION, CAST STAINLESS STEEL HYDRANT BOX, FLUSH MOUNTED 16–GAUGE STAINLESS STEEL FRAME AND 180° DROP DOWN DOOR WITH KEY LOCK AND WALL CLAMP JR SMITH MODEL 5519 |
| WH3 | – | – | 3/4 | 3/4 | CANWASH WALL HYDRANT – NON–FREEZE HOSE BOX WITH STRAIGHT INLET CONNECTION, HOT AND COLD MIXING, REMOVABLE KEYED HANDLE, ASSE APPROVED ANTI–SIPHON INTEGRAL BACKFLOW PREVENTER WITH 3/4" HOSE CONNECTION, HEAVY DUTY BRASS CASING, POLISHED BRONZE HYDRANT BOX WITH HINGED COVER, "WATER" CAST ON COVER, DRIP LIP AND WALL CLAMP J.R. SMITH MODEL 5560–QT–WC–H–W–PB. |
| WBOX | 2 | 2 | 3/4 | 3/4 | CLOTHES WASHER DRAIN/VALVE BOX – HEAVY–GAUGE GALVANIZED STEEL CONSTRUCTION, RECESSED IN WALL, VALVE AND DRAIN CONNECTIONS, WATTS DUO–CLOZ VALVE GUY GRAY MODEL WB–200. |

## PLUMBING FIXTURES AND EQUIPMENT

| MARK | MIN. CONNECTION SIZES (IN.) SAN | VENT | CW | HW | DESCRIPTION/SPECIFICATION |
|---|---|---|---|---|---|
| WC | 4 | 2 | 1 | – | WATER CLOSET – WALL MOUNTED, WHITE VITREOUS CHINA, SIPHON JET ACTION, 1.28 GPF, ELONGATED BOWL, TOP SPUD, ADA/TAS COMPLIANT, AMERICAN STANDARD AFWALL: SLOAN ROYAL 111–1.28 FLUSH VALVE WITH VANDAL–PROOF FREE–SPINNING TOP CAP, 1.28 GPF, VANDAL–PROOF STOP AND ADA/TAS COMPLIANT LEVER ACTUATOR WITH LEVER INSTALLED ON LEFT SIDE (FOR FIXTURES DESIGNATED AS "HANDICAP"), INSTALL LEVER ON "WIDE–SIDE" OF TOILET STALL); BEMIS 1655–SS/C EXTRA HEAVY DUTY, WHITE, OPEN FRONT SEAT LESS COVER WITH SELF–SUSTAINING, STAINLESS STEEL CHECK HINGE; AND, FLOOR MOUNTED CARRIER. |
| LV | 1–1/4 | 1–1/4 | 1/2 | 1/2 | LAVATORY GOOSENECK FAUCET – WALL HUNG, WHITE VITREOUS CHINA, FRONT OVERFLOW, SELF–DRAINING DECK AREA, 21" X 18", ADA/TAS COMPLIANT AMERICAN STANDARD LUCERNE 0355.012; DECK MOUNTED FAUCET, 4" CENTERS, FIXED, CHROME PLATED, 5.25" GOOSENECK SPOUT, PRESSURE COMPENSATING LAMINAR FLOW NON–AERATING 0.5 GPM OUTLET, 4" WRISTBLADE HANDLES, REPLACEABLE COMPRESSION CARTRIDGES, CHICAGO 895–317GN2AE72ABCP; CHROME PLATED, 17–GAUGE CAST BRASS GRID DRAIN WITH WHEELCHAIR OFFSET FITTING; CHROME PLATED, 17–GAUGE CAST BRASS P–TRAP WITH CLEANOUT PLUG; CHROME PLATED, CAST BRASS, LOOSE KEY ANGLE STOP WITH CHROME PLATED COPPER RISER; TRUEBRO HANDI LAV–GUARD VANDAL–PROOF, WHITE INSULATION KITS; AND, FLOOR MOUNTED, CONCEALED ARMS CARRIER. PROVIDE ASSE 1070 LISTED MIXING VALVE, LEONARD 170–LF OR EQUAL (MUST BE CAPABLE OF ADJUSTMENT ABOVE 130°F). |
| LV2 | 1–1/4 | 1–1/4 | 1/2 | 1/2 | LAVATORY – WALL HUNG, WHITE VITREOUS CHINA, FRONT OVERFLOW, SELF–DRAINING DECK AREA, 21" X 18", ADA/TAS COMPLIANT AMERICAN STANDARD LUCERNE 0355.012; CHROME PLATED, ALL CAST BRASS CONSTRUCTION, ADA/TAS COMPLIANT, VANDAL–PROOF FAUCET WITH 4" WRIST BLADE HANDLES, COMPRESSION STYLE CARTRIDGES, CHROME DECK PLATE, VANDAL–PROOF AERATOR, COPPER SUPPLIES AND CERTIFIED FOR MEETING ALL REQUIREMENTS OF NSF 61 SECTION 9 CHICAGO MARATHON MODEL 802–E70–317ABCP; CHROME PLATED, 17–GAUGE CAST BRASS GRID DRAIN WITH WHEELCHAIR OFFSET FITTING; CHROME PLATED, 17–GAUGE CAST BRASS P–TRAP WITH CLEANOUT PLUG; CHROME PLATED, CAST BRASS, LOOSE KEY ANGLE STOP WITH CHROME PLATED COPPER RISER; TRUEBRO HANDI LAV–GUARD VANDAL–PROOF, WHITE INSULATION KITS; AND, FLOOR MOUNTED, CONCEALED ARMS CARRIER. PROVIDE ASSE 1070 LISTED MIXING VALVE, LEONARD 170–LF OR EQUAL (MUST BE CAPABLE OF ADJUSTMENT ABOVE 130°F). |
| EDF | 1–1/2 | 1–1/2 | 1/2 | – | BI–LEVEL ELECTRIC DRINKING FOUNTAINS WITH BOTTLE FILLER – WALL MOUNTED, ALL STAINLESS STEEL, ADA AND TAS COMPLIANT FOR ALL AGES, 8 GPH AT ARI STANDARDS, 2–STREAM ALL METAL BUBBLER FITTING WITH VANDAL–RESISTANT KIT AND FRONT PUSH BUTTON ACTUATION, PUSH BUTTON ACTIVATED BOTTLE FILLER WITH 1.1GPM FILL RATE AND ANTI–MICROBIAL COATING, INTEGRAL WATER FILTER, LEAD–FREE (CERTIFIED FOR MEETING ALL REQUIREMENTS OF NSF 61 SECTION 9), REFRIGERANT HFC–134a, MAINTENANCE ACCESS PANEL, HALSEY–TAYLOR MODEL HTHBHVR8EC WITH CHROME PLATED, 17–GAUGE CAST BRASS P–TRAP WITH CLEANOUT PLUG; CHROME PLATED, CAST BRASS, LOOSE KEY ANGLE STOP WITH CHROME PLATED COPPER RISER; FLOOR MOUNTED CHAIR CARRIER; AND, STAINLESS STEEL ADA APRON FOR LOCATIONS REQUIRED BY ADA OR TAS. |
| MB | 3 | 2 | 3/4 | 3/4 | MOP BASIN – 24" X 24" X 12" DEEP TERRAZZO, TWO (2) STAINLESS STEEL SPLASH CATCHER PANELS, 8" DROP FRONT WITH STAINLESS STEEL CAP, CAST BRASS DRAIN WITH STAINLESS STEEL STRAINER STERN WILLIAMS HILOW MODEL HI1800–BP; FAUCET SHALL BE POLISHED CHROME PLATED SERVICE SINK TYPE WITH VACUUM BREAKER, INTEGRAL SUPPLY CHECK STOPS, SPOUT WITH PAIL HOOK, HOSE END AND TOP BRACE CHICAGO MODEL 897–CCF (INSTALL BACKING/BRACING INSIDE WALL TO SUPPORT FAUCET AND TOP BRACE). |
| LP–1 | 3 | 2 | 3/4 | 3/4 | LAVATORY PUMP – FACTORY BUILT, LIFT PUMP FOR GRAY WATER WASTE, TOP ACCESS TO INTERNAL 1/6HP PUMP AND FLOAT SWITCH, 1.5" TOP AND SIDE INLETS, 1.5" TOP OUTLET, INTEGRAL CHECK VALVE AT BOTTOM INLET CONNECTIONS, 9FT POWER CORD WITH GROUNDED PLUG;<br>LIBERTY PUMPS MODEL 406 |

## KITCHEN PLUMBING CONNECTION SCHEDULE


| MARK | DESCRIPTION |
|---|---|
| P5 | 3/4" CW AND 3/4" HW – IN WALL, 36" AFF, TO MOP BASIN ("MB") FAUCET. REFERENCE PLUMBING FIXTURE SCHEDULE. |
| P6 | 3" DRAIN IN FLOOR FOR MOP BASIN ("MB") DRAIN. REFERENCE PLUMBING FIXTURE SCHEDULE. |
| P7 | 3/4" CW AND 3/4" HW – IN WALL, 18" AFF, TO HOSE BIBB. |
| P10 | FLOOR DRAIN – 3" OUTLET; FLUSH WITH FLOOR; TWO–PIECE CAST IRON WITH SEEPAGE FLANGE, REVERSIBLE CLAMPING COLLAR, 7" SQUARE HEAVY–DUTY POLISHED BRONZE GRATE, 1/2" TRAP PRIMER TAP, AND TRAP SEAL DEVICE (MODEL 2692) JR SMITH MODEL 2005–03–K07PB–P050–U. |
| P11C | 1/2" CW AND 1/2" HW – IN WALL, FOR HAND LAVATORY WITH FOOT CONTROLS ("LV"). REFERENCE PLUMBING FIXTURE SCHEDULE. |
| P11D | 2" DRAIN – IN WALL, FOR HAND LAVATORY WITH FOOT CONTROLS ("LV"). REFERENCE PLUMBING FIXTURE SCHEDULE. |
| P12 | FLOOR SINK – 4" OUTLET; FLUSH WITH FLOOR; CAST IRON, 8" DEEP SUMP, A.R.E. INTERIOR, INTEGRAL FLANGE FOR SUPPORT, CLAMPING DEVICE WHERE VAPOR BARRIER IS INSTALLED BETWEEN SLAB AND CONCRETE BEDDING FOR FLOOR, ALUMINUM SECONDARY DOME STRAINER AND 12" SQUARE HEAVY DUTY NICKEL BRONZE FRAME WITH 3/4–TRAC




## 13 FLUSH VALVE TRAP PRIMING TUBE DETAIL

NO SCALE


MI-FAB MODEL MI-702-MOD FLUSH VALVE TRAP PRIMER, OR EQUAL




## 13 GAS PIPING WALL-TO-ROOF TRANSITION DETAIL

NO SCALE

| TANKLESS WATER HEATER SCHED. | | |
|---|---|---|
| MARK | IEWH-1 | |
| SERVES | LAVATORY | |
| LOCATION | BELOW COUNTER | |
| HEATER KW | 1.8 KW | |
| TEMP RISE (@ 0.5 GPM) | 25°F | |
| VOLTAGE/PHASE | 120V/1PH | |
| EEMAX MODEL | SPEX1812T | |





## 11 TANKLESS WATER HEATER

NO SCALE

NOTES:

1. LOCATION OF VALVE AND PIPING SHALL NOT INTERFERE WITH ANY ADA/HANDICAP KNEE-SPACE CLEARANCE REQUIREMENTS.
2. ALL PIPING SHALL BE CHROME PLATED CAST BRASS AND SHALL BE INSULATED BY TRUEBRO HANDI LAV-GUARD INSULATION KITS. INSULATION KITS SHALL COVER P-TRAP, MIXING VALVE, WATER STOPS, PIPING AND ALL SHARP EDGES (ONLY WHERE CABINETWORK KNEESPACE SCREEN NOT PROVIDED).
3. ALL CW AND HW CONNECTIONS SHALL HAVE COMPRESSION TYPE FITTINGS.
4. FURNISH & INSTALL 0.5-GPM AERATOR ON FAUCET COMPATIBLE WITH TANKLESS EWH REQUIREMENTS.
5. WATER HEATER SHALL HAVE INTEGRAL ASSE-1070 COMPLIANT TEMPERED MIXING VALVE.





## 10 ELECTRONIC TRAP PRIMING MANIFOLD DETAIL (TP)

NO SCALE

NOTES:

1. REFERENCE SCHEDULE ON SHEET P3.00





## 14 GAS PIPING ROOF SUPPORT DETAIL

NO SCALE

NOTES:


1. GAS PIPING SUPPORT SHALL BE PORTABLE PIPE HANGERS, INC. MODEL PP10-R. PIPING SHALL BE INSTALLED 12" ABOVE FINISHED ROOF. PROVIDE 18" X 18" CAREY TREAD-TYPE MATERIAL BENEATH EACH PIPE SUPPORT.
2. FIELD LOCATE ROOF STRUCTURAL SUPPORTS AND PLACE BASE OF PIPE SUPPORT OVER ROOF SUPPORTS ONLY. PROVIDE BASE OF ADEQUATE LENGTH TO SPAN ROOF JOIST TO PREVENT SUPPORTS SETTING ON ROOF DECK ONLY.
3. INSTALL SIX (6) FOOT-ON-CENTERS.
4. PIPE SUPPORT MANUFACTURER'S REPRESENTATIVE SHALL PERSONALLY INSPECT INSTALLATIONS OF PIPE SUPPORTS AND MAKE CORRECTIONS AND HEIGHT ADJUSTMENTS TO INSTALLATIONS, AS REQUIRED, DURING INSPECTION.




## 9 ROOF PIPE JACK DETAIL

NO SCALE


NOTE: COORDINATE WITH ARCHITECTURAL DRAWINGS, DETAILS AND SPECIFICATIONS.




## 8 SAMPLE TEST WELL DETAIL (STW)


NO SCALE

NOTES:




## 7 TYPICAL GAS CONNECTION


NO SCALE




## 6 HOT WATER BALANCING STATION


NO SCALE

PROVIDE AT EACH JUNCTION OF BRANCH HOT WATER RETURN LOOPS TO MAIN CIRCULATING HOT WATER LINE, SEE PLUMBING PLANS.




## 5 WALL PENETRATION DETAIL


NO SCALE




## 4 PVC-TO-CAST IRON INSTALLATION DETAIL

NO SCALE


MISSION TRANSITION COUPLING DESIGNED AND CERTIFIED FOR THIS SPECIFIC APPLICATION SHALL BE ACCEPTABLE IN LIEU OF HUSKY COUPLING IN THIS DETAIL.




## 3 ROOF VENT DETAIL

NO SCALE

COORDINATE WITH ARCHITECTURAL DRAWINGS AND SPECIFICATIONS.





## 2 MIXING VALVE DETAIL

NO SCALE

NOTES

1. UNDERCOUNTER MIXING VALVE SHALL BE MOUNTED ON WALL IN FIXTURE KNEE-SPACE. LOCATION OF VALVE AND PIPING SHALL NOT INTERFERE WITH ANY ADA/HANDICAP KNEE-SPACE CLEARANCE REQUIREMENTS.
2. ALL PIPING SHALL BE CHROME PLATED CAST BRASS AND SHALL BE INSULATED BY TRUEBRO HANDI LAV-GUARD INSULATION KITS. INSULATION KITS SHALL COVER P-TRAP, MIXING VALVE, WATER STOPS, PIPING AND ALL SHARP EDGES (ONLY WHERE CABINETWORK KNEESPACE SCREEN NOT PROVIDED).
3. ALL CW AND HW CONNECTIONS SHALL HAVE COMPRESSION TYPE FITTINGS.
4. FOR ABOVE CEILING INSTALLATION, VALVE SHALL BE INSTALLED IN AN EASILY/READILY ACCESSIBLE LOCATION. SEE KITCHEN PLUMBING CONNECTION SCHEDULE FOR REQUIRED KITCHEN LOCATIONS.
5. LAVATORY MIXING VALVES SHALL HAVE AN OUTPUT ADJUSTMENT RANGE UP TO OR ABOVE 130°F.
   SINK MIXING VALVES SHALL HAVE AN OUTPUT ADJUSTMENT RANGE UP TO OR ABOVE 140°F.




## 1 MECHANICAL - ELECTRICAL COORDINATION DETAIL

NO SCALE

DO NOT INSTALL ANY PIPING BENEATH CVT BOXES. DO NOT INSTALL ANY PIPING (EXCEPT FIRE SPRINKLER PIPING AND OTHER PIPES SHOWN SPECIFICALLY ON THE PLUMBING FLOOR PLANS) OVER COMPUTER CLASSROOMS, BOOKROOMS, IDF/MDF/SERVER ROOMS OR OTHER ROOMS NOTED ON THE PLUMBING FLOOR PLANS.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD.
SUGAR LAND, TX 77479

SEAL

STATE OF TEXAS — INTERIM REVIEW — 07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING


PLUMBING SCHEDULES & DETAILS

s-P0.02

PRELIMINARY
NOT FOR CONSTRUCTION OR BIDDING PURPOSES


STANTON ENGINEERING GROUP
INFORMATION-CHECKER (713) 300-60982
TEXAS ENG. FIRM REG NO. F-019332 | 1300 W. SAM HOUSTON PARKWAY N., SUITE 121, HOUSTON, TX 77043


2025 ALL RIGHTS RESERVED





**EYED NOTES**

PLACE OF EXISTING.
ING SANITARY BELOW
LAB TO MATCH EXISTING.
4 PLACE OF EXISTING
P-TRAP. TIE BACK
ARY BELOW SLAB AND
CH EXISTING.
AIR FURNACE ON ROOF
H NEW OF SIMILAR SIZE
NECT AND RECONNECT
E WITH NEW RIGID GAS
WITH DIV.23 FOR ALL

## 2 FIRE SPRINKLER - FDC RELOCATION

SCALE: 1/4" = 1'- 0"




## 1 PLUMBING RENOVATION FLOOR PLAN

SCALE: 1/4" = 1'- 0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

**S**

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT

SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD.
SUGAR LAND, TX 77479

SEAL




ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

PLUMBING FLOOR PLAN

**s-P1.01**

STANTON ENGINEERING GROUP
INFORMATION-DESIGN (713) 300-4080
TEXAS ENG. FIRM REG. NO. F-01853210
2021 ALL RIGHTS RESERVED
1200 N. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77043

# TECHNOLOGY SYMBOLS & LEGEND

## VOICE SYMBOLS

| | |
|---|---|
| | SINGLE VOICE OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| X | VOICE OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |
| | SINGLE VOICE OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED. |
| X | VOICE OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED, X = NUMBER OF CABLE TERMINATIONS PER LOCATION AS INDICATED. |
| | POWER/COMMUNICATIONS POLE WITH A SINGLE VOICE OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| X | POWER/COMMUNICATIONS POLE WITH X = NUMBER OF VOICE OUTLETS, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| | SINGLE VOICE OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE-THRU AS SPECIFIED. |
| X | VOICE OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE -THRU AS SPECIFIED WITH X = NUMBER OF VOICE TERMINATIONS PER LOCATION. |
| W | SINGLE VOICE OUTLET FOR WALL-MOUNTED PHONE, CABLE TYPE AS SPECIFIED, MOUNTED +52-INCHES A.F.F. UNLESS OTHERWISE NOTED. |

## VOICE/DATA SYMBOLS

| | |
|---|---|
| | SINGLE VOICE & SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| X Y | VOICE & DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. X = NUMBER OF VOICE TERMINATIONS , Y = NUMBER OF DATA TERMINATIONS PER LOCATION. |
| | SINGLE VOICE & SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED. |
| X Y | VOICE & DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED, X = NUMBER OF VOICE OUTLETS AND Y = NUMBER OF DATA OUTLETS PER LOCATION AS INDICATED. |
| | POWER/COMMUNICATIONS POLE WITH A SINGLE VOICE OUTLET AND SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| X Y | POWER/COMMUNICATIONS POLE WITH X = NUMBER OF VOICE TERMINATIONS, Y = NUMBER OF DATA TERMINATIONS, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| | SINGLE VOICE OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE-THRU AS SPECIFIED. |
| X Y | VOICE OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE -THRU AS SPECIFIED WITH X = NUMBER OF VOICE TERMINATIONS, Y = NUMBER OF DATA TERMINATIONS PER LOCATION. |

## DATA SYMBOLS

| | |
|---|---|
| | SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| X | DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |
| | SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED. |
| X | DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED, X = NUMBER OF CABLE TERMINATIONS PER LOCATION AS INDICATED. |
| | POWER/COMMUNICATIONS POLE WITH A SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| X | POWER/COMMUNICATIONS POLE WITH X = NUMBER OF DATA OUTLETS, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| | SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE-THRU AS SPECIFIED. |
| X | DATA OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE -THRU AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |
| W | SINGLE DATA OUTLET FOR WALL-MOUNTED IP PHONE, CABLE TYPE AS SPECIFIED, MOUNTED +52-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| X | DATA CABLE FOR COMPUTER ON WHEELS, CABLE TYPE AS SPECIFIED MOUNTED + 18-INCHES A.F.F UNLESS OTHERWISE NOTED. X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |
| X | DATA CABLE FOR CEILING MOUNTED WIRELESS ACCESS POINT, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A GREEN ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. |
| X | DATA CABLE FOR CEILING MOUNTED VIDEO SURVEILLANCE CAMERA, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A ORANGE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. REFER TO SECURITY DRAWINGS PRIOR TO INSTALLATION. |
| | DATA CABLE FOR CEILING MOUNTED PROJECTOR, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A BLUE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. REFER TO AUDIO/VISUAL DRAWINGS PRIOR TO INSTALLATION. |
| X | DATA CABLE FOR CEILING MOUNTED AUDIO/VISUAL EQUIPMENT ENCLOSURE, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A BLUE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. REFER TO AUDIO/VISUAL DRAWINGS PRIOR TO INSTALLATION. |
| X | DATA CABLE FOR WALL MOUNTED PROJECTOR, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A BLUE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. REFER TO AUDIO/VISUAL DRAWINGS PRIOR TO INSTALLATION. |

## FIBER OPTIC SYMBOLS

| | |
|---|---|
| | SINGLE FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| X | FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |
| | SINGLE FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED. |
| X | FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED, X = NUMBER OF CABLE TERMINATIONS PER LOCATION AS INDICATED. |
| | POWER/COMMUNICATIONS POLE WITH A SINGLE FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| X | POWER/COMMUNICATIONS POLE WITH X = NUMBER OF FIBER OPTIC OUTLETS, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| | SINGLE FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE-THRU AS SPECIFIED. |
| X | FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE -THRU AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |

## DATA SYMBOLS, CONT.

| | |
|---|---|
| X CAME | DATA CABLE FOR EXTERIOR WALL MOUNTED VIDEO SURVEILLANCE CAMERA, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A ORANGE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW, REFER TO SECURITY DRAWINGS PRIOR TO INSTALLATION. |
| X CAMW | DATA CABLE FOR INTERIOR WALL MOUNTED SURVEILLANCE CAMERA, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A ORANGE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. |
| X CAME | DATA CABLE FOR EXTERIOR WALL MOUNTED SURVEILLANCE CAMERA, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A ORANGE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. |
| X WAPW | DATA CABLE FOR INTERIOR WALL MOUNTED WIRELESS ACCESS POINT, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A GREEN ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. |
| X WAPE | DATA CABLE FOR EXTERIOR WALL MOUNTED WIRELESS ACCESS POINT, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A GREEN ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. |

## ROUGH-IN & MISC. SYMBOLS

| | |
|---|---|
| R | ROUGH-IN LOCATION, INFRASTRUCTURE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| R | ROUGH-IN LOCATION, INFRASTRUCTURE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED. |
| R | POWER POLE WITH ROUGH-IN LOCATION, INFRASTRUCTURE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| R | ROUGH-IN LOCATION. TERMINATED IN FLOOR BOX/POKE-THRU AS SPECIFIED. |
| WAP | WIRELESS ACCESS POINT. EQUIPMENT AS SPECIFIED. |

## CABLE PLANT & RISER DIAGRAM

| | |
|---|---|
| | MAINTENANCE HOLE, SIZE & TYPE AS SPECIFIED. |
| | PULLBOX, SIZE AND TYPE AS SPECIFIED. |
| UGC | DIRECT BURIED COMMUNICATIONS, CABLE TYPE AS SPECIFIED. |
| AER | AERIAL COMMUNICATIONS, CABLE TYPE AS SPECIFIED. |
| | CONDUIT, SIZE AND TYPE AS SPECIFIED. |

## GENERAL SYMBOLS

| | |
|---|---|
| # SHEET — DRAWING TITLE SCALE: SCALE | DRAWING TITLE CALLOUT, # = DETAIL NUMBER. |
| # SHEET | DETAIL CALLOUT, # = DETAIL NUMBER. |
| # SHEET | SECTION CALLOUT, # = DETAIL NUMBER. |
| SHEET # | ELEVATION CALLOUT, # = DETAIL NUMBER. |
| # | KEYED NOTE, # = KEYED NOTE NUMBER. |
| # | REVISION TRIANGLE, # = REVISION NUMBER (PER SHEET). |
| TR (IDF XXX) | INDICATES TELECOMMUNICATIONS REGION |

## ABBREVIATIONS

| | |
|---|---|
| A.F.F. | ABOVE FINISHED FLOOR |
| A.F.G. | ABOVE FINISHED GRADE |
| AER | AERIAL |
| DEMARC | DEMARCATION POINT |
| EMT | ELECTRIC METALLIC TUBE |
| F.O.C. | FIBER OPTIC CABLE |
| GIP | GALVANIZED IRON PIPE |
| HE | PAINTERCOM HEAD-END |
| IMC | INTERMEDIATE METAL CONDUIT |
| ISP | INSIDE CABLE PLANT |
| IDF | INTERMEDIATE DISTRIBUTION FRAME |
| MDF | MAIN DISTRIBUTION FRAME |
| MH | MAINTENANCE HOLE |
| MM | MULTIMODE |
| OSP | OUTSIDE CABLE PLANT |
| PB | PULLBOX |
| PR | PAIR |
| PVC | POLYVINYL CHLORIDE |
| RSC | RIGID STEEL CONDUIT |
| SM | SINGLE MODE |
| SP | SERVICE PROVIDER |
| STP | SHIELDED TWISTED PAIR |
| TB | TERMINAL BLOCK |
| TR | TELECOMMUNICATION REGION |
| UGC | UNDERGROUND COMMUNICATION |
| UON | UNLESS OTHERWISE NOTED |
| UTP | UNSHIELDED TWISTED PAIR |

## NOTES

1. CONTRACTOR SHALL REVIEW DRAWINGS AND SPECIFICATIONS THAT MAKE UP THE CONTRACT DOCUMENTS AND COMPLETE ALL WORK INCLUDED THEREIN.
2. SCALE OF TECHNOLOGY DRAWINGS IS PROVIDED FOR REFERENCE ONLY. CONTRACTOR SHALL BE RESPONSIBLE FOR PROPER CABLE LENGTHS, SIZE OF PATHWAYS, DIMENSIONS, ETC.
3. TECHNOLOGY DRAWINGS SHALL BE USED TO COMPLEMENT THE WRITTEN SPECIFICATIONS.
4. ANY DISCREPANCY OR CONFLICT WITHIN OR BETWEEN THE DRAWINGS AND SPECIFICATIONS SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT/DESIGN CONSULTANT'S. DISCREPANCIES OR CONFLICTS NOT BROUGHT TO THE ATTENTION OF THE ARCHITECT/DESIGN CONSULTANT AND SUBSEQUENTLY CLARIFIED DURING THE BIDDING OF THE PROJECT WILL BE DEEMED TO HAVE BEEN BID OR PROPOSED IN THE MORE COSTLY OR DIFFICULT MANNER, AND THE BETTER QUALITY OR GREATER QUANTITY OF WORK SHALL BE PROVIDED BY THE CONTRACTOR IN ACCORDANCE WITH THE ARCHITECT'S/DESIGN CONSULTANT'S INTERPRETATION.

## INDEX OF DRAWINGS


s-T000 TECHNOLOGY SYMBOLS & LEGEND
s-TD201 TECHNOLOGY DEMOLITION FLOOR PLAN
s-T200 TECHNOLOGY COMPOSITE FLOOR PLAN
s-T201 TECHNOLOGY NEW/RENOVATION KITCHEN PLAN
s-T202 TECHNOLOGY TEMPORARY KITCHEN FLOOR PLAN
s-T300 TECHNOLOGY ENLARGED VIEWS
s-T400 TECHNOLOGY TYPICAL DETAILS
s-T401 TECHNOLOGY TYPICAL DETAILS
s-T500 TECHNOLOGY TYPICAL DETAILS


ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD
SUGAR LAND, TX 774

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD


07/18/2025


ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY SYMBOLS & LEGEND

SHEET NO.
s-T000




1 TECHNOLOGY COMPOSITE FLOOR PLAN
s-T200 1/16" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

# S

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD
SUGAR LAND, TX 774

SEAL


REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD
07/18/2025

ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY COMPOSITE FLOOR PLAN

SHEET NO.
s-T200




1 s-T201 TECHNOLOGY NEW/RENOVATION KITCHEN PLAN
1/4" = 1'-0"

**TECHNOLOGY FLOOR PLANS GENRAL NOTES:**

1. THE TECHNOLOGY REGION / WIRING BOUNDARIES ARE IDENTIFIED ON THE OVERALL SHEETS ONLY AND NOT ON THE ENLARGED SHEETS. CONTRACTOR SHALL REFER TO THE OVERALL SHEETS FOR ALL TECHNOLOGY REGIONS / WIRING BOUNDARIES.
2. ALL CONDUIT PATHWAYS, ROUGH-INS, BACKBOXES, FLOOR BOXES, CONDUIT SLEEVES, ETC. INDICATED ON THE TECHNOLOGY DRAWINGS ARE TO BE PROVIDED AND INSTALLED BY DIVISION 26.
3. ALL POWER INDICATED ON THE TECHNOLOGY DRAWINGS IS TO BE PROVIDED AND INSTALLED BY DIVISION 26.
4. CONTRACTOR SHALL RESTORE ALL PENETRATIONS PROVIDED THROUGH FIRE RATED WALLS/STRUCTURES FOR TECHNOLOGY CABLING BACK TO THE ORIGINAL RATING.
5. CONTRACTOR SHALL RESTORE ALL PENETRATIONS PROVIDED THROUGH NON-RATED WALLS/STRUCTURES FOR TECHNOLOGY CABLING FOR SOUND TO REDUCE NOISE TRAVELING THROUGH PENETRATIONS.
6. TECHNOLOGY CABLING SHALL BE ROUTED IN SEPARATE PATHWAYS IN J-HOOKS, CONDUITS, CONDUIT SLEEVES, CORES, ETC. THROUGHOUT THE ENTIRE PATHWAY. DIFFERENT MEDIA TYPES (DATA, VIDEO, SECURITY, ETC.) SHALL NOT SHARE THE SAME J-HOOK, CONDUIT, CONDUIT SLEEVE, CORE, ETC.
7. UNLESS NOTED OTHERWISE, ALL CONDUITS FOR TECHNOLOGY DEVICES SHALL ROUTE FROM THE DEVICE LOCATION AND TERMINATE ABOVE AN ACCESSIBLE CEILING (AN OPEN CEILING OR CLOUD TYPE CEILING IS NOT CONSIDERED AN ACCESSIBLE CEILING) IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF A MAIN CORRIDOR OR NEAREST MDF/IDF. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF / IDF ROOM TO MINIMIZE THE CABLE LENGTH ENSURING CABLE LENGTH DOES NOT EXCEED 275 FEET.
8. UNLESS NOTED OTHERWISE ALL CONDUITS SHALL BE HOMERUN FROM THE DEVICE LOCATION AND NO DAISY CHAINING OF DEVICES/ ROUGH-INS SHALL BE ALLOWED.
9. CONDUIT SEGMENTS SHALL BE NO MORE THAN 100-FEET IN LENGTH WITH NO MORE THAN THE EQUIVALENT OF (2) 90 DEGREE BENDS BETWEEN PULLING POINTS.
10. CONDUITS SHALL MAINTAIN A BEND RADIUS OF 6 TIMES THE DIAMETER OF THE CONDUIT FOR CONDUITS 2-INCHES OR SMALLER AND 10 TIMES THE DIAMETER OF THE CONDUIT FOR CONDUITS GREATER THAN 2-INCHES.
11. ALL CONDUITS SHALL HAVE A PULL STRING INSTALLED FOR PULLING OF CABLE. CLEARLY LABEL AS "PULL STRING" INDICATING OPPOSITE END LOCATION.
12. ALL SPARE CONDUITS OR CONDUITS FILLED WITH LESS THAN THE MAXIMUM ALLOWED FILL RATIO SHALL HAVE A PULL STRING INSTALLED AND LEFT FOR FUTURE PULLING OF CABLE. CLEARLY LABEL AS "PULL STRING" INDICATING OPPOSITE END LOCATION.
13. EQUIPMENT NOT RELATED TO THE SUPPORT OF THE TELECOMMUNICATIONS ROOM (E.G., PIPING, DUCTWORK, PNEUMATIC TUBING) SHALL NOT BE INSTALLED IN, PASS THROUGH, OR ENTER THE TELECOMMUNICATIONS ROOM.
14. ALL CONDUITS FOR TECHNOLOGY DEVICES SHALL ROUTE FROM THE DEVICE LOCATION AND TERMINATE ABOVE A LAY-IN TYPE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE A LAY- IN TYPE CEILING TO PREVENT THE CABLES FROM BEING EXPOSED, THE CONDUIT SHALL ROUTE TO THE NEAREST LAY-IN TYPE CEILING OFF A MAIN CORRIDOR OR NEAREST MDF/IDF. THE CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE MAIN CORRIDOR OR NEAREST MDF/IDF TO MINIMIZE THE CABLE LENGTH ENSURING THE CABLE LENGTH DOES NOT EXCEED 275 FEET. CONDUIT, CONNECTIONS, J-BOXES, SUSPENSION, ANCHORAGES, AND OTHER CONDUIT COMPONENTS EXPOSED TO VIEW IN PUBLIC SPACES SHALL BE ROUTED AND INSTALLED CAREFULLY TO MINIMIZE VISUAL IMPACT AND SHALL BE FULLY PAINTED TO MATCH UNLESS NOTED OTHERWISE.
15. CONDUIT(S) INSTALLED IN-SLAB OR UNDER-SLAB TO FLOOR BOXES, POKE-THURS, AND TO WORKAREA OUTLETS, ETC. SHALL BE INSTALLED WITH WET RATED CABLE(S).
16. NO GRID WIRE SHALL BE UTILIZED FOR SUPPORTS ONLY USE SOLID SUPPORTS (CLIPS, ALL-THREAD, ANCHORS, ETC.).

**TECHNOLOGY PLAN KEYED NOTES**

**NOT ALL KEYED BELOW APPLY TO THIS SHEET**

1. DATA CABLE FOR CONTRACTOR FURNISHED / CONTRACTOR INSTALLED MENU BOARD. REFERENCE ARCHITECTURAL AND FOOD SERVICE DRAWINGS FOR MOUNTING HEIGHT AND ADDITIONAL INFORMATION. BUILDING POWER ADJACENT TO DATA RECEPTACLE IS REQUIRED.
2. INDOOR / OUTDOOR RATED DATA CABLE FOR POINT OF SALE LOCATION. PROVIDE (1) 1-INCH CONDUIT FOR DATA TO THE WALL BEHIND POINT OF SALE LOCATION AND UP WALL TO ABOVE ACCESSIBLE CEILING. CONDUITS SHALL TERMINATE INSIDE A DOUBLE GANG BOX THAT IS SECURED TO THE POINT OF SALE LOCATION. REFER TO FOOD SERVICE / KITCHEN DRAWINGS FOR EXACT LOCATION AND CONDUIT ROUGH-IN REQUIREMENTS.
3. DATA CABLE FOR TEMPERATURE MONITORING OF FREEZER COOLER. REFER TO FOOD SERVICE / KITCHEN DRAWINGS FOR EXACT LOCATION AND CONDUIT ROUGH-IN REQUIREMENTS AND TERMINATION POINT AND CONNECTIVITY NEEDS IN FREEZER / COOLER CONTROL UNIT.
4. DATA CABLE FOR TEMPORARY POINT OF SALES CASH REGISTER. COORDINATE WITH OWNER, ARCHITECT, AND CONSULTANT FOR ROUTING OF CABLES TO POINT OF SALE CASH REGISTER PRIOR TO INSTALLATION

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

# S

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD
SUGAR LAND, TX 774

SEAL

BICSI Jason Gonzalez Jr BICSI ID # 364970 Expires 12-31-25 RCDD


07/18/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY NEW/RENOVATION KITCHEN PLAN

SHEET NO.
s-T201




1 TECHNOLOGY TEMPORARY KITCHEN FLOOR PLAN
s-T202 1/4" = 1'-0"

**TECHNOLOGY FLOOR PLANS GENRAL NOTES:**

1. THE TECHNOLOGY REGION / WIRING BOUNDARIES ARE IDENTIFIED ON THE OVERALL SHEETS ONLY AND NOT ON THE ENLARGED SHEETS. CONTRACTOR SHALL REFER TO THE OVERALL SHEETS FOR ALL TECHNOLOGY REGIONS / WIRING BOUNDARIES.
2. ALL CONDUIT PATHWAYS, ROUGH-INS, BACKBOXES, FLOOR BOXES, CONDUIT SLEEVES, ETC. INDICATED ON THE TECHNOLOGY DRAWINGS ARE TO BE PROVIDED AND INSTALLED BY DIVISION 26.
3. ALL POWER INDICATED ON THE TECHNOLOGY DRAWINGS IS TO BE PROVIDED AND INSTALLED BY DIVISION 26.
4. CONTRACTOR SHALL RESTORE ALL PENETRATIONS PROVIDED THROUGH FIRE RATED WALLS/STRUCTURES FOR TECHNOLOGY CABLING BACK TO THE ORIGINAL RATING.
5. CONTRACTOR SHALL RESTORE ALL PENETRATIONS PROVIDED THROUGH NON-RATED WALLS/STRUCTURES FOR TECHNOLOGY CABLING FOR SOUND TO REDUCE NOISE TRAVELING THROUGH PENETRATIONS.
6. TECHNOLOGY CABLING SHALL BE ROUTED IN SEPARATE PATHWAYS IN J-HOOKS, CONDUITS, CONDUIT SLEEVES, CORES, ETC. THROUGHOUT THE ENTIRE PATHWAY. DIFFERENT MEDIA TYPES (DATA, VIDEO, SECURITY, ETC.) SHALL NOT SHARE THE SAME J-HOOK, CONDUIT, CONDUIT SLEEVE, CORE, ETC.
7. UNLESS NOTED OTHERWISE, ALL CONDUITS FOR TECHNOLOGY DEVICES SHALL ROUTE FROM THE DEVICE LOCATION AND TERMINATE ABOVE AN ACCESSIBLE CEILING (AN OPEN CEILING OR CLOUD TYPE CEILING IS NOT CONSIDERED AN ACCESSIBLE CEILING) IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF A MAIN CORRIDOR OR NEAREST MDF/IDF. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF / IDF ROOM TO MINIMIZE THE CABLE LENGTH ENSURING CABLE LENGTH DOES NOT EXCEED 275 FEET.
8. UNLESS NOTED OTHERWISE ALL CONDUITS SHALL BE HOMERUN FROM THE DEVICE LOCATION AND NO DAISY CHAINING OF DEVICES/ ROUGH-INS SHALL BE ALLOWED.
9. CONDUIT SEGMENTS SHALL BE NO MORE THAN 100-FEET IN LENGTH WITH NO MORE THAN THE EQUIVALENT OF (2) 90 DEGREE BENDS BETWEEN PULLING POINTS.
10. CONDUITS SHALL MAINTAIN A BEND RADIUS OF 6 TIMES THE DIAMETER OF THE CONDUIT FOR CONDUITS 2-INCHES OR SMALLER AND 10 TIMES THE DIAMETER OF THE CONDUIT FOR CONDUITS GREATER THAN 2-INCHES.
11. ALL CONDUITS SHALL HAVE A PULL STRING INSTALLED FOR PULLING OF CABLE. CLEARLY LABEL AS "PULL STRING" INDICATING OPPOSITE END LOCATION.
12. ALL SPARE CONDUITS OR CONDUITS FILLED WITH LESS THAN THE MAXIMUM ALLOWED FILL RATIO SHALL HAVE A PULL STRING INSTALLED AND LEFT FOR FUTURE PULLING OF CABLE. CLEARLY LABEL AS "PULL STRING" INDICATING OPPOSITE END LOCATION.
13. EQUIPMENT NOT RELATED TO THE SUPPORT OF THE TELECOMMUNICATIONS ROOM (E.G., PIPING, DUCTWORK, PNEUMATIC TUBING) SHALL NOT BE INSTALLED IN, PASS THROUGH, OR ENTER THE TELECOMMUNICATIONS ROOM.
14. ALL CONDUITS FOR TECHNOLOGY DEVICES SHALL ROUTE FROM THE DEVICE LOCATION AND TERMINATE ABOVE A LAY-IN TYPE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE A LAY- IN TYPE CEILING TO PREVENT THE CABLES FROM BEING EXPOSED, THE CONDUIT SHALL ROUTE TO THE NEAREST LAY-IN TYPE CEILING OFF A MAIN CORRIDOR OR NEAREST MDF/IDF. THE CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE MAIN CORRIDOR OR NEAREST MDF/IDF TO MINIMIZE THE CABLE LENGTH ENSURING THE CABLE LENGTH DOES NOT EXCEED 275 FEET. CONDUIT, CONNECTIONS, J-BOXES, SUSPENSION, ANCHORAGES, AND OTHER CONDUIT COMPONENTS EXPOSED TO VIEW IN PUBLIC SPACES SHALL BE ROUTED AND INSTALLED CAREFULLY TO MINIMIZE VISUAL IMPACT AND SHALL BE FULLY PAINTED TO MATCH UNLESS NOTED OTHERWISE.
15. CONDUIT(S) INSTALLED IN-SLAB OR UNDER-SLAB TO FLOOR BOXES, POKE-THURS, AND TO WORKAREA OUTLETS, ETC. SHALL BE INSTALLED WITH WET RATED CABLE(S).
16. NO GRID WIRE SHALL BE UTILIZED FOR SUPPORTS ONLY USE SOLID SUPPORTS (CLIPS, ALL-THREAD, ANCHORS, ETC.).

**TECHNOLOGY PLAN KEYED NOTES**

**NOT ALL KEYED BELOW APPLY TO THIS SHEET**

1. DATA CABLE FOR CONTRACTOR FURNISHED / CONTRACTOR INSTALLED MENU BOARD. REFERENCE ARCHITECTURAL AND FOOD SERVICE DRAWINGS FOR MOUNTING HEIGHT AND ADDITIONAL INFORMATION. BUILDING POWER ADJACENT TO DATA RECEPTACLE IS REQUIRED.
2. INDOOR / OUTDOOR RATED DATA CABLE FOR POINT OF SALE LOCATION. PROVIDE (1) 1-INCH CONDUIT FOR DATA TO THE WALL BEHIND POINT OF SALE LOCATION AND UP WALL TO ABOVE ACCESSIBLE CEILING. CONDUITS SHALL TERMINATE INSIDE A DOUBLE GANG BOX THAT IS SECURED TO THE POINT OF SALE LOCATION. REFER TO FOOD SERVICE / KITCHEN DRAWINGS FOR EXACT LOCATION AND CONDUIT ROUGH-IN REQUIREMENTS.
3. DATA CABLE FOR TEMPERATURE MONITORING OF FREEZER COOLER. REFER TO FOOD SERVICE / KITCHEN DRAWINGS FOR EXACT LOCATION AND CONDUIT ROUGH-IN REQUIREMENTS AND TERMINATION POINT AND CONNECTIVITY NEEDS IN FREEZER / COOLER CONTROL UNIT.
4. DATA CABLE FOR TEMPORARY POINT OF SALES CASH REGISTER. COORDINATE WITH OWNER, ARCHITECT, AND CONSULTANT FOR ROUTING OF CABLES TO POINT OF SALE CASH REGISTER PRIOR TO INSTALLATION

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD
SUGAR LAND, TX 774

SEAL

CERTIFIED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD

07/18/2025

MWA ARCHITECTS

ARCHITECTS
AND PLANNING
CONSULTANTS

11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY TEMPORARY KITCHEN FLOOR PLAN


SHEET NO.
s-T202

REMOVE EXISTING CABLING THAT IS CURRENTLY TERMINATED IN KITCHEN DEMOLTION AREA FROM RACK. UTILZE PORT MADE AVAIBLE FROM DEMOLITION FOR NEW CABLING TO BE INSTALLED TO RENOVATION CABLING OUTLETS

RACK 1 PATCH PANEL RE: 2/T300



1/T300 REAR OF EXISTING IDF RACK SYSETM
NTS



ISNTALL NEW WAP CABLING TO OPEN PORTS ON THIS PATCH PANEL

PROVIDE NEW PATCH PANEL FOR CAMERAS

2/T300 RACK 1 PATCH PANEL CLOSEUP
NTS

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD
SUGAR LAND, TX 774

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD

07/18/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING


TECHNOLOGY ENLARGED VIEWS

SHEET NO.
s-T300

NOTE TO CONTRACTOR:

UNLESS OTHERWISE NOTED, LOW VOLTAGE CABLING SHALL BE INSTALLED WITHIN 6-INCHES OF THE CEILING AND ACCESSIBLE BY A TECHNICIAN ON A STANDARD A-FRAME LADDER.

CONTRACTOR SHALL MAINTAIN AT LEAST 6-INCHES OF SEPRATION BETWEEN CABLING BUNDLES AND MECHANICAL DUCTWORKS, EQUIPMENT, PIPIING OR OTHER SYSTEMS IN THE CEILING PLENUM.





KEYED NOTES:

1. J-HOOK WITH RETAINER CLIP ABOVE ACCESSIBLE CEILING (BY DIV 27).
2. DATA CABLE ABOVE ACCESSIBLE CEILING (BY DIV 27).
3. A/V CABLE ABOVE ACCESSIBLE CEILING (BY DIV 27).
4. SECURITY CABLE ABOVE ACCESSIBLE CEILING (BY DIV 28).
5. SPARE J-HOOK (BY DIV 27).

## 1 T400 TYPICAL J-HOOK CABLE PATHWAY

SCALE: N.T.S.





KEYED NOTES:

1. SCHEDULED FLOOR OR DECK.
2. CONDUIT SLEEVE (BY DIV 26).
3. NYLON BUSHING (BY DIV 26).

## 2 T400 TYPICAL CONDUIT SLEEVE THROUGH FLOOR OR DECK DETAIL

SCALE: N.T.S.





KEYED NOTES:

1. SCHEDULED WALL.
2. SCHEDULED CEILING.
3. CONDUIT SLEEVE (BY DIV 26).
4. NYLON BUSHING (BY DIV 26).

## 3 T400 TYPICAL CONDUIT SLEEVE GOING THROUGH WALL

SCALE: N.T.S.





KEYED NOTES:

1. SCHEDULED WALL.
2. SCHEDULED CEILING.
3. SCHEDULED DECK ABOVE.
4. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX WITH DOUBLE GANG PLASTER RING (BY DIV 26).
5. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH. (BY DIV 26).

## 4 T400 TYPICAL TECHNOLOGY CONDUIT ROUGH-IN

SCALE: N.T.S.





KEYED NOTES:

1. SCHEDULED STUD.
2. SCHEDULED WALL.
3. J-HOOK WITH RETAINER CLIP ABOVE ACCESSIBLE CEILING (BY DIV 27).
4. DATA CABLE ABOVE ACCESSIBLE CEILING (BY DIV 27).
5. 20 FOOT SERVICE LOOP ABOVE ACCESSIBLE CEILING NEATLY COILED AND SECURED TO J-HOOK (BY DIV 27).
6. SURFACE MOUNT BOX ABOVE ACCESSIBLE CEILING SECURED TO BUILDING STRUCTURE (BY DIV 27).
7. DATA INSTER (BY DIV 27).

## 5 T400 TYPICAL ABOVE CEILING SINGLE DATA OUTLET (WALL MOUNTED)

SCALE: N.T.S.





KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH PHONE STUDS (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. CABLE AS SPECIFIED (BY DIV 27).

## 6 T400 TYPICAL WALL PHONE OUTLET CONFIGURATION

SCALE: N.T.S.





KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH DESIGNATION IN WINDOW (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. CABLE AS SPECIFIED (BY DIV 27).
7. ELECTRICAL RECEPTACLE, GANG BOX AND CONDUIT SHOWN FOR REFERENCE ONLY (REFER TO DIV 26).

## 7 T400 TYPICAL DUAL DATA OUTLET CONFIGURATION

SCALE: N.T.S.





KEYED NOTES:

1. 4 11/16-INCH X 4 11/16-INCH X 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. DOUBLE GANG PLASTER RING (BY DIV 26).
4. SURFACE MOUNT BOX INSIDE THE 4 11/16-INCH X 4 11/16-INCH X 2 1/8-INCH DOUBLE GANG BOX (BY DIV 27).
5. RJ-45 INSERT (BY DIV 27).

## 8 T400 TYPICAL WALL-MOUNTED WIRELESS ACCESS POINT

SCALE: N.T.S.




KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH DESIGNATION IN WINDOW (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. BLANK INSERT (BY DIV 27).
7. CABLE AS SPECIFIED (BY DIV 27).
8. ELECTRICAL RECEPTACLE, GANG BOX AND CONDUIT SHOWN FOR REFERENCE ONLY (REFER TO DIV 26).

## 9 T400 TYPICAL THREE DATA OUTLET CONFIGURATION

SCALE: N.T.S.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD
SUGAR LAND, TX 774

SEAL

RECOGNIZED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD


07/18/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY TYPICAL DETAILS

SHEET NO.
s-T400





KEYED NOTES:

1. ALL THREAD TO BUILDING STRUCTURE (BY DIV. 27)
2. SCHEDULING CEILING
3. IN-PLENUM CEILING BRACKET PN 49223-CBC ATTACHED TO ALL THREAD (BY DIV. 27)
4. SURFACE MOUNT BOX ABOVE ACCESSIBLE CEILING SECURED TO BRACKET (BY DIV. 27)
5. DATA CABLE (BY DIV. 27)
6. DATA INSERT (BY DIV. 27)

## 1 T401 TYPICAL ABOVE CEILING DATA OUTLET

SCALE: N.T.S.





KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH DESIGNATION IN WINDOW (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. CABLE AS SPECIFIED (BY DIV 27).
7. ELECTRICAL RECEPTACLE, GANG BOX AND CONDUIT SHOWN FOR REFERENCE ONLY (REFER TO DIV 26). ELECTRICAL RECEPTACLE TO BE INSTALLED AT 36" A.F.F AND ADJACENT TO COW / SECONDARY TEACHING OUTLET LOCATION.

## 2 T401 TYPICAL COW / SECONDARY TEACHER'S DATA OUTLET CONFIGURATION

SCALE: N.T.S.





KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH DESIGNATION IN WINDOW (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. BLANK INSERT (BY DIV 27).
7. CABLE AS SPECIFIED (BY DIV 27).
8. ELECTRICAL RECEPTACLE, GANG BOX AND CONDUIT SHOWN FOR REFERENCE ONLY (REFER TO DIV 26).

## 3 T401 TYPICAL THREE DATA OUTLET CONFIGURATION

SCALE: N.T.S.




KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH DESIGNATION IN WINDOW (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. CABLE AS SPECIFIED (BY DIV 27).
7. ELECTRICAL RECEPTACLE, GANG BOX AND CONDUIT SHOWN FOR REFERENCE ONLY (REFER TO DIV 26).

## 4 T401 TYPICAL FOUR DATA OUTLET CONFIGURATION


SCALE: N.T.S.

| TBB/GE CONDUCTOR SIZING | |
|---|---|
| LENGTH IN LINEAR M (FT) | SIZE (AWG) |
| LESS THAN 4 (13) | 6 |
| 4 - 6 (14-20) | 4 |
| 6 - 8 (21 - 26) | 3 |
| 8 - 10 (27 - 33) | 2 |
| 10 - 13 (34 - 41) | 1 |
| 13 - 16 (42 - 52) | 1/0 |
| 16 - 20 (53 - 66) | 2/0 |
| 20 - 26 (67 - 84) | 3/0 |
| 26 - 32 (85 - 105) | 4/0 |
| 32 - 38 (106 - 125) | 250 kcmil |
| 38 - 46 (126 - 150) | 300 kcmil |
| 46 - 53 (151 - 175) | 350 kcmil |
| 53 - 76 (176 - 250) | 500 kcmil |
| 76 - 91 (251 - 300) | 600 kcmil |
| GREATER THAN 91 (301) | 750 kcmil |

ROUTE THE TBB TO EACH TGB IN AS STRAIGHT A PATH AS POSSIBLE. THE TBB SHOULD BE INSTALLED AS A CONTINUOUS CONDUCTOR, AVOIDING SPLICES WHERE POSSIBLE.

## 5 T401 TBB CONDUCTOR SIZING

SCALE: N.T.S.





1. TELECOMMUNICATIONS MAIN GROUNDING BUS BAR (PBB)(BY DIV. 27)
2. TELECOMMUNICATIONS GROUNDING BUS BAR (SBB)(BY DIV 27)
3. TELECOMMUNICATIONS BONDING CONDUCTOR (TBC). REFER TO CONDUCTOR SIZING CHART FOR EXACT SIZE REQUIREMENTS (BY DIV 27)
4. CONNECT TO GROUNDED BUILDING STEEL WHEN EXPOSED IN ROOM.
5. TELECOMMUNICATIONS BONDING BACKBONE (TBB). REFER TO CONDUCTOR SIZING CHART FOR EXACT SIZE REQUIREMENTS (BY DIV 26)
6. TELECOMMUNICATIONS BONDING CONDUCTOR (TBC). BY ELECTRICAL CONTRACTOR.REFER TO CONDUCTOR SIZING CHART FOR EXACT SIZE REQUIREMENTS.
7. GROUNDING EQUALIZER CONDUCTOR (GEC)(BY DIV 26)
8. BOUND WITH GROUDING COLLARS TO EACH CONTINUOUS CONDUIT THAT ENTERS THE TELECOM ROOM. (BY DIV 26).
9. BOND TO EACH ACCESS CONTROL PANEL AND OTHER SECURITY PANELS IN HE TELECOM ROOM. (BY DIV 27)

## 6 T401 TYPICAL GROUNDING DIAGRAM

SCALE: N.T.S.

System No. W-L-3218
F Ratings - 1, 2, 3 and 4 Hr (See Items 1 and 3)
T Ratings - 3/4 and 1 Hr (See Item 3)
L Rating At Ambient - Less Than 1, 1.3, 4 or 7 CFM (See Item 3)
L Rating At 400 F - Less Than 1, 2 or 3 CFM (See Item 3)




Section A-A

1. Wall Assembly - The 1, 2, 3 or 4 hr fire-rated gypsum board/stud wall assembly shall be constructed of the materials and in the manner described within the individual U300, U400 or V400 Series Wall and Partition Designs in the UL Fire Resistance Directory and shall incorporate the following construction features:

   A. Studs - Wall framing shall consist of either wood studs or steel channel studs. Wood studs to consist of nom 2 by 4 in. (51 by 102 mm) lumber spaced max 16 in. (406 mm) OC. Steel studs to be min 3-1/2 in. (89 mm) wide and spaced max 24 in. (610 mm) OC.

   B. Gypsum Board* - Thickness, type, number of layers and fasteners as specified in the individual Wall and Partition Design. Opening in gypsum board to be max 1/4 in. (6 mm) larger then width and height dimensions of firestop device(s).

   The hourly F Rating of the firestop system is dependent upon the hourly rating of the wall in which it is installed.

2. Firestop Device* - One, two, three, four or seven firestop device modules ganged together. Each firestop device module consists of a 3 by 3 by 10-1/2 in. (76 by 76 by 267 mm) long galv steel tube with an intumescent material lining. Firestop device modules to be installed in accordance with the accompanying installation instructions. The space between the firestop device module(s) and the periphery of the opening shall be min 0 in. ( 0 mm, point contact) to max 1/8 in. (3.2 mm). In round openings, the space between the firestop device and the periphery of the opening shall be min 0 in. (point contact) to max 1/2 in. (13 mm). Firestop device module(s) secured in place by means of steel wall plates installed with gasketing material supplied with product. Steel wall plates installed on both sides of wall and secured to each device by means of steel set screws provided with device. Each four- and seven-gang steel wall plate shall be fastened to the studs with steel screws sized to extend through the gypsum board layers and penetrate 1/2 in. (13 mm) into the framing member. Each firestop device module is to be installed with ends projecting an equal distance beyond each surface of the wall assembly.

   As an alternate, the four- and seven-gang steel wall plates may be installed directly against the studs for walls having 16 and 24 in. (406 and 610 mm) center-to-center stud spacing, respectively, prior to installation of the gypsum board layers. The steel wall plates shall be secured to the stud by means of steel screws. After installation of the steel wall plates and firestop device modules, the gypsum board shall be installed as specified in the individual U300 or U400 Design with a maximum 1/8 in. (3.2 mm) gap between the firestop device module and the cutout in the gypsum board. Gap between the firestop device module and the cutout in the gypsum board may be filled with gypsum joint compound or fill material (Item 4).

   SPECIFIED TECHNOLOGIES INC - EZ PATH Series 33 Fire Rated Pathway

2A. Firestop Device* - Extension Module - (Optional, Not Shown) - Module attached to ends of 3 by 3 by 10-1/2 in. (76 by 76 by 267 mm) long firestop device (Item 3) to increase its length to facilitate installation in thicker walls. Each module consists of a 3 by 3 by 6 in. (76 by 76 by 152 mm) long galv steel tube with an intumescent material lining. Extension module to be installed in accordance with the accompanying installation instructions. When module is used, firestop device (Item 2) and extension module(s) secured in place by means of steel wall plates installed with gasketing material supplied with product. Steel wall plates installed on both sides of wall and secured to each device or extension module(s) by means of steel set screws provided with wall plates. Firestop device and extension module(s) assembly to be installed with ends projecting an equal distance beyond each surface of the wall assembly.

   SPECIFIED TECHNOLOGIES INC - EZ PATH Extension

3. Cables - Within the loading area for each firestop device module, the cables may represent a 0 to 100 percent visual fill. Cable fill to be distributed at a uniform height across the width of the firestop device module. Cables to be rigidly supported on both sides of the wall assembly. Any combination of the following types of cables may be used:

   A. Max 400 pair No. 24 AWG (or smaller) copper conductor telecommunication cable with polyvinyl chloride (PVC) jacketing and insulation.
   B. Max 350 kcmil single copper conductor power cable with XLPE jacket and insulation
   C. Max 7/C No. 12 AWG copper conductor control cable with PVC or XLPE jacket and insulation.
   D. Max 3/C No. 10 AWG metal clad or armored cable with steel or aluminum jacket.
   E. Max 3/C No. 8 AWG NM cable (Romex) with PVC insulation and jacket.
   F. Max four pair No. 22 AWG (or smaller) copper conductor data cable with PVC or plenum rated jacketing and insulation.
   G. Max RG/U coaxial cable with fluorinated ethylene insulation and jacketing.
   H. Fiber optic cable with PVC or polyethylene (PE) jacket and insulation having a max diam of 5/8 in. (16 mm).
   I. Optical Fiber Raceway+ - Max 1-1/2 in. (38 mm) diam (or smaller) optical fiber raceway ("innerduct") formed of either PVC or polyvinylidene fluoride (PVDF) with optical fiber cable fill. Raceways installed in accordance with the National Electrical Code (NFPA 70).

   When the hourly rating of the wall assembly is 1 hr, the T Rating is 3/4 hr. When the hourly fire rating of the wall assembly is greater than 1 hr, the T Rating is 3/4 hr when Item 3A, 3B, 3C, 3D or 3E is used. Otherwise the T Rating is 1 hr. When Item 3A, 3B, 3C, 3D or 3E is used, the maximum F Rating is 2 hr. When max 200 pair No. 24 AWG telecommunication cable is used or when Item 3F, 3G, 3H or 3I is used, the maximum F Rating is 4 hr.

   The L Rating for each empty firestop device module is less than 1 cfm at ambient and at 400F. When Item 3A is used, the L Rating for each firestop device module with 100 percent visual fill is 4 cfm at ambient and 3 cfm at 400F. When Item 3F is used, the L Rating for each firestop device module with 100 percent visual fill is 1.3 cfm at ambient and 1 cfm at 400F. When Item 3G or 3H is used, the L Rating for each firestop device module with 100 percent visual fill is 7 cfm at ambient and 2 cfm at 400F.

4. Fill, Void or Cavity Material* - Sealant or Putty - (Not Shown) - As an alternate to gypsum joint compound, the gap between the firestop device module and the cutout in the gypsum board may be sealed with fill material on each side of the wall assembly when four- and seven-gang steel wall plates are installed directly against the wood or steel studs.

   SPECIFIED TECHNOLOGIES INC - SpecSeal Series SSS Sealant, SpecSeal LCI Sealant, SpecSeal Putty

   *Bearing the UL Classification Mark

## 7 T401 TYPICAL STI EZ-PATH SLEEVE DETAIL

SCALE: N.T.S.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD
SUGAR LAND, TX 774

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 12-31-25
RCDD


07/18/2025



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY TYPICAL DETAILS

SHEET NO.
s-T401









1 T500 TYPICAL HORIZONTAL DATA CABLE LABELING SCHEME


SCALE: N.T.S.





2 T500 TYPICAL FIBER BACKBONE LABELING SCHEME

SCALE: N.T.S.




3 T500 TYPICAL COPPER BACKBONE LABELING SCHEME

SCALE: N.T.S.




4 T500 ABOVE ASSESSIBLE CEILING LABELING SCHEME

SCALE: N.T.S.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SETTLERS WAY ELEMENTARY SCHOOL
3015 SETTLERS WAY BLVD
SUGAR LAND, TX 774

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Jason Gonzalez Jr
BICSI ID # 364970
EXPIRES 03-31-25
RCDD

07/18/2025

MWA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY TYPICAL DETAILS

SHEET NO.
s-T500

## AUDIO/VISUAL MULTIMEDIA LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| A## V## | WALL AV ROUGH-IN DETAIL |
| A## V## | CEILING AV ROUGH-IN DETAIL |
| A## V## | FLOOR AV ROUGH-IN DETAIL |
| IWB IWB | INTERACTIVE WHITE BOARD - WALL - CEILING |
| PJ PJ | MULTIMEDIA PROJECTOR |
| FP# FP# | MULTIMEDIA FLAT PANEL DISPLAY |
| S S | LOUDSPEAKER, WALL MOUNTED AND CEILING MOUNTED RESPECTIVELY - # INDICATES TYPE |
| CP# | CONTROL PANEL |
| TP# | TOUCH PANEL |
| M | MICROPHONE, CEILING MOUNTED - # INDICATES TYPE |
| VC | VOLUME CONTROL |
| WB | WALL BOX ENCLOSURE |
| D1 A1 | D1 = DIGITAL SINGLE SIDED CLOCK / A1 = ANALOG SINGLE SIDED CLOCK |
| D2 A2 | D2 = DIGITAL DOUBLE SIDED CLOCK / A2 = ANALOG DOUBLE SIDED CLOCK |
| ENC | CEILING AV ENCLOSURE |
| C C | PRESENTATION CAMERA - CEILING - WALL MOUNTED |

## PREMISE SECURITY LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| CR | CARD READER |
| CR M | CARD READER MULLION |
| KP | INTRUSION DETECTION KEYPAD |
| IC | INTERCOM (1 DATA CABLE) |
| IC MS | INTERCOM MASTER STATION (1 DATA CABLE) |
| PB | PANIC/DURESS BUTTON |
| LD | LOCK DOWN BUTTON |
| MD | MOTION DETECTOR |
| GB | ACCOUSTICAL GLASS BREAK SENSOR |
| BM | BIOMETRIC READER |
| RX | REQUEST TO EXIT - SURFACE PIR |
| KS | KEY SWITCH |
| LA | LOCAL ALARM SOUNDER |
| RG | RED/GREEN INDICATOR LIGHT |
| DB | DOORBELL |
| DH | MAGNETIC DOOR HOLD |
| DR | DOOR RELEASE |
| RX | REQUEST TO EXIT - INTEGRAL TO DOOR HARDWARE |
| DC | DOOR CONTACT / MONITOR |
| ES EL EH | ELECTRIFIED STRIKE - ELECTRIFIED LATCH - ELECTRIFIED HARDWARE (REFER TO SCHEDULES) |
| C C | STANDARD IP SURVEILLANCE CAMERA, (1) CABLE |
| C C C | 180° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° FISHEYE LENS CAMERA |
| IR | IR ILLUMINATOR |

## STRUCTURED CABLING LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF DATA CABLE(S)/JACK(S) |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) |
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| W | WALL MOUNT PHONE (1 CABLE/JACK) |
| W | WALL MOUNT PHONE, SURFACE MOUNT (1 CABLE/JACK) |
| # | FLOOR MOUNTED OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| #/# | FLOOR MOUNTED OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| # | CEILING MOUNTED DATA OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) |
| AP# | CEILING MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| AP# | WALL MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| | CABLING SLEEVE(S) |
| | TYPICAL LADDER RACK |
| | TYPICAL CABLE TRAY, BASKET STYLE |

## GENERAL ANNOTATION LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| MER | MAIN EQUIPMENT ROOM |
| TR | TELECOMMUNICATION ROOM |
| MDF | MAIN DISTRIBUTION FRAME |
| IDF | INTERMEDIATE DISTRIBUTION FRAME |
| ETR | EXISTING TO REMAIN |
| PBO | PROVIDED BY OTHERS |
| AFF | ABOVE FINISHED FLOOR |
| AFG | ABOVE FINISHED GRADE |
| AC | ABOVE COUNTER |
| EC | ELECTRICAL CONTRACTOR |
| PSC | PREMISE SECURITY CONTRACTOR |
| SCC | STRUCTURAL CABLING CONTRACTOR |
| AVC | AV/MULTIMEDIA CONTRACTOR |
| UNO | UNLESS NOTED OTHERWISE |
| ACS | ACCESS CONTROL SYSTEM |
| VSS | VIDEO SURVEILLANCE SYSTEM |

## TECHNOLOGY - GENERAL NOTES

1. EACH KEYNOTE MAY NOT BE UTILIZED ON EVERY SHEET.
2. ALL CONDUIT MEASUREMENTS REFER TO STANDARD CONDUIT TRADE SIZES.
3. ALL CABLES SHALL BE CONCEALED.
4. EACH CONTRACTOR SHALL PROVIDE AND INSTALL ALL NECESSARY SLEEVES, WHETHER OR NOT SPECIFICALLY NOTED ON PROJECT DRAWINGS. ALL SLEEVES SHALL BE 2" UNLESS NOTED OTHERWISE ON THE DRAWINGS. CABLE FILL PERCENTAGE SHALL COMPLY WITH NEC.
5. DEVICE LOCATIONS ARE APPROXIMATE. CONTRACTOR SHALL REVIEW CONDITIONS AND COORDINATE WITH OTHER TRADES AS NECESSARY FOR EXACT PLACEMENT.

## TECHNOLOGY SYMBOLS LEGEND

NOT ALL SYMBOLS ARE USED

- AV WALL ROUGH-IN WITH DATA
- KEYNOTE
- Proposed Camera Direction SURVEILLANCE CAMERA
- Camera Schedule Number (Floor #-Camera #) Camera (N)ew, (E)xisting Rough-in, (D)emo
- Proposed Camera Direction PTZ CAMERA
- PTZ
- Proposed Camera Direction FIXED SURVEILLANCE CAMERA
- 360°/MULTI-SENSOR FIXED SURVEILLANCE CAMERA OR FISHEYE LENS CAMERA
- Approximate view of lens
- Lens View Angle
- 360°/MULTI-SENSOR FIXED SURVEILLANCE CAMERA OR FISHEYE LENS CAMERA
- Lens size
- MICROPHONE WITH AUDIO LINKED TO CAMERA
- CARD READER LINKED TO CAMERA
- SYMBOL TAG — (#) = DIFFERENT TYPES OF CARD READERS: M = MULLION; W = WIRELESS (Proprietary); Wi = Wi-Fi (802.11); POE = POWER OVER ETHERNET
- SYMBOL TAG — (#) = DIFFERENT TYPES OF CARD READERS: TS = TOUCHSCREEN; PU = PUSH BUTTON
- TOP = DETAIL NUMBER; DETAIL REFERENCE; BOTTOM = SHEET NUMBER
- NORTH ARROW
- SHEET NUMBER; SECTION MARKER; DETAIL NUMBER
- DIRECTION OF ELEVATION; ELEVATION MARKER; SHEET NUMBER; DETAIL NUMBER
- DIRECTION OF ELEVATION; SHEET NUMBER; DIRECTION OF ELEVATION; DETAIL NUMBER
- BAR IS ONE INCH ON ORIGINAL DRAWING. IF NOT ONE INCH ON THIS DRAWING ADJUST SCALES ACCORDINGLY

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Settlers Way Elementary School
3015 Settlers Way Blvd, Sugar Land, TX 77479

SEAL

BICSI CERTIFIED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 258657
EXPIRES 10-31-27
RCDD

07-18-25


MVA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY - TITLE SHEET

s-TN000

**DEMO KEYNOTES**

1. REMOVE, AND PROTECT DURING CONSTRUCTION, INSTALL IN EXISTING LOCATION AFTER NEW ACT GRID IS IN PLACE.
2. DEVICES IN ACT ARE TO BE REMOVED AND PROTECTED DURING CONSTRUCTION AND REINSTALLED IN THE SAME LOCATION AFTER THE NEW CEILING GRID IS IN PLACE. DECIVES INCLUDE: SPEAKERS, ACCESS POINTS AND INTRUSION MOTION DETECTORS.
3. EXISTING CARD READER, DOOR CONTACT, & REX (REQUEST TO EXIT) TO BE DEMOLISHED, REMOVE DEVICES AND PROTECT WIREING.




1 SETTLERS WAY - DEMO PLAN
SCALE: 3/16" = 1'-0"

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Settlers Way Elementary School
3015 Settlers Way Blvd, Sugar Land, TX 77479

SEAL

BICSI REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 295857
EXPIRES 12-31-27

07-18-25



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Settlers Way ES - DEMO

s-TN.001

## TECHNOLOGY KEYNOTES

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.




1 BACKGROUND S (SETTLER'S WAY ES)
SCALE: 1" = 20'-0"

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Settlers Way Elementary School
3015 Settlers Way Blvd, Sugar Land, TX 77479

SEAL

BICSI REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 384683
EXPIRES 12-31-27
07-18-25



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Settlers Way ES - OVERALL

s-TN.100

## TECHNOLOGY KEYNOTES

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.




1 SETTLERS WAY - KITCHEN PLAN
SCALE: 3/16" = 1'-0"

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Settlers Way Elementary School
3015 Settlers Way Blvd, Sugar Land, TX 77479

SEAL

BICSI REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 395857
EXPIRES 12-31-27

07-18-25



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Settlers Way ES - KITCHEN


s-TN.101

**GENERAL NOTE**


1. FACE PLATE DETAIL FOR OUTLET CONFIGURATION PURPOSES ONLY. CONTRACTOR TO SELECT TYPE OF FACE PLATE TO MATCH CONNECTIVITY HARDWARE, FLOOR BOX AND/OR MODULAR FURNITURE OPENING.





1 DATA ROUGH-IN DETAILS
SCALE: NS




2 TYPICAL CABLING SLEEVE
SCALE: NTS




3 PANDUIT J-HOOK DETAIL
SCALE: NTS




4 LABELING & CABLING SCHEMES
SCALE: NTS




5 CABLE PATHWAY CROSS SECTION
SCALE: NTS




6 DROPPED CEILING MOUNTING DETAIL
SCALE: NS




7 I-JOIST MOUNTING DETAIL
SCALE: NS




8 BAR JOIST MOUNTING DETAIL
SCALE: NS

| CAMERA TYPE | MANUFACTURER | MODEL NUMBER | GENERAL DESCRIPTION |
|---|---|---|---|
| C1 | iPro | WV-S8574L | 4x4K (33MP) EXTERIOR MULTI-SENSOR - PARKING LOTS, STADIUM |
| C2 | iPro | WV-S8544L | 4x4MP (16MP) EXTERIOR MULTI-SENSOR - BUILDING PERIMETER |
| C3 | iPro | WV-S25500-V3LN | 5MP EXTERIOR VANDAL DOME |
| C4 | iPro | WV-S22500-V3L | 5MP INTERIOR VANDAL DOME - CORR., COMMON, SPED |
| C5 | iPro | WV-S4156A | 5MP 360 (FISHEYE) - STAIRWELLS |

9 CAMERA SCHEDULE
SCALE: NTS

| Symbol | Purpose | Size | Mount | Backbox | Notes |
|---|---|---|---|---|---|
| FP1 | Digital Signage/Menu Boards | +49" | Ceiling Pole | N/A | Data and Power Outlets on ceiling |

10 DISPLAY SCHEDULE
SCALE: NTS

TRUENORTH
A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Settlers Way Elementary School
3015 Settlers Way Blvd, Sugar Land, TX 77479

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256687
EXPIRES 12-31-27

07-18-25



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Settlers Way ES - DETAILS


s-TN.500

GENERAL NOTES:


1. REFER TO SECURITY SCHEDULE AND WRITTEN SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
2. ALL MOUNTING DETAILS ARE REFERENCE FOR ALL FIXED DOME, 180°, 360°, PTZ, AND "BULLET/BOX" CAMERAS.





1 TYPICAL CAMERA INSTALLATION SECTION DETAIL
SCALE: NS




6 WALL MOUNTED CAMERA DETAIL
SCALE: NS




4 TILE BRIDGE DETAIL
SCALE: NS





5 CEILING MOUNTED CAMERA DETAIL
SCALE: NS


ACCESS CONROL DETAILS AND GENERAL NOTES:

1. CONDUIT ROUGH-IN IS A GUIDE FOR WHAT WILL BE REQUIRED FOR EACH DOOR. AS DOOR COMPONENTS CHANGE, EXACT CONDUIT LOCATION WILL ALSO NEED TO BE ADJUSTED.


2. PROTECT EXISTING-TO-REMAIN ACCESS CONTROL DEVICES AND CABLE THROUGHOUT RENOVATION WORK. IF CABLE AND/OR DEVICES ARE DAMAGED, SECURITY CONTRACTOR TO REPLACE WITH NEW.




1 ACCESS CONTROL - WIRING DETAIL - EXIT DEVICE W/ BUILT-IN REX
SCALE: NTS




2 ACCESS CONTROL - STEEL/HOLLOW METAL DOOR.
SCALE: NTS




KP PB LD

3 ROUGH-IN DETAILS: KP, PB, LD
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Settlers Way Elementary School
3015 Settlers Way Blvd, Sugar Land, TX 77479

SEAL





07-18-25


MVA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING
AND
PERMITTING
TECHNOLOGY - Settlers Way
ES - SECURITY DETAILS

s-TN.600




6 CEILING MOUNT DISPLAY - A/V ROUGH-IN DETAIL
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

S

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Settlers Way Elementary School
3015 Settlers Way Blvd, Sugar Land, TX 77479

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Pena
BICSI ID # 295857
EXPIRES 12-31-27

07-18-25

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Settlers Way ES - AV DETAILS

s-TN.700

# FBISD BP013 KITCHEN RENOVATIONS ES

## SIENNA CROSSING ELEMENTARY SCHOOL
10011 STEEP BANK TRCE, MISSOURI CITY, TX 77459

| Sheet List Table | |
|---|---|
| Sheet Number | Sheet Title |
| School: t-Sienna Crossing ES | |
| t-A.000 | COVER AND INDEX |
| t-A00-01 | GENERAL NOTES AND ABBREVIATIONS |
| t-A.201 | FLOOR PLAN |
| t-A.301 | KITCHEN PLAN |
| t-A.401 | REFLECTED CEILING PLAN |
| t-A.501 | FINISH FLOOR PLAN |
| t-E.200 | ELECTRICAL PLAN AND SCHEDULES |
| t-TN-000 | TECHNOLOGY - INDEX SHEET |
| t-TN-100 | TECHNOLOGY - OVERALL |
| t-TN-101 | TECHNOLOGY - KITCHEN |
| t-TN-500 | TECHNOLOGY - DETAILS |
| t-TN-600 | TECHNOLOGY - SECURITY DETAILS |




FORT BEND INDEPENDENT SCHOOL DISTRICT

## FORT BEND INDEPENDENT SCHOOL DISTRICT

### ADMINISTRATION

| | |
|---|---|
| DR. MARCELL SMITH | SUPERINTENDENT OF FBISD |
| DR. ANDRIA SCHUR, Ed.D. | CHIEF OF SCHOOLS |

### BOARD OF TRUSTEES

| | |
|---|---|
| KRISTIN K. TASSIN | PRESIDENT |
| RICK GARCIA | VICE PRESIDENT |
| DAVID HAMILTON | SECRETARY |
| ANGIE HANAN | BOARD MEMBER |
| ADAM SCHOOF | BOARD MEMBER |
| DR. SHIRLEY ROSE-GILLIAM | BOARD MEMBER |
| SONYA JONES | BOARD MEMBER |

### PROJECT DESIGN TEAM

PROGRAM MANAGEMENT
FBISD 2023 Bond Team
2323 Texas Parkway
Missouri City, TX 77489
Phone Number: 281-327-5481

ARCHITECT
MWA Architects
11767 Katy Freeway, Suite 430
Houston, Texas 77079
Phone Number: 713-782-8188

FOOD SERVICE
Food Design Professionals
26215 Oak Ridge Drive
The Woodlands, Texas 77380
Phone Number: 281-350-2323

MEP ENGINEERS
Stanton Engineering Group
1300 W. Sam Houston Pkwy South, Suite 121
Houston, Texas 77042
Phone Number: 713-300-9292

STRUCTURAL ENGINEER
Stanley Spurling & Hamilton
3301 Edloe Street, Suite 200
Houston, Texas 77027
Phone Number: 713-776-9433

ISSUED FOR BIDDING AND PERMITTING - JULY 18, 2025

t

PART 1 - GENERAL

1.1 GENERAL DEMOLITION NOTES

A. VERIFY EXISTING SITE AND BUILDING CONDITIONS IN FIELD PRIOR TO BIDDING. NOTIFY ARCHITECT OF ANY DISCREPANCIES PRIOR TO BIDDING.

B. CONTRACTOR SHALL COORDINATE WITH OWNER THE SALVAGE OF ITEMS, FURNITURE AND EQUIPMENT INDICATED TO BE REMOVED.

C. CLAIMS FOR ADDITIONAL COST OR TIME DUE TO EXISTING CONDITIONS THAT COULD HAVE BEEN REASONABLY ANTICIPATED DURING A SITE VISIT BY THE CONTRACTOR PRIOR TO BIDDING WILL NOT BE APPROVED.

D. PROTECT EXISTING FINISHES SHOWN TO REMAIN DURING CONSTRUCTION TO PREVENT DAMAGE. REPAIR OR REPLACE DAMAGED MATERIALS AND FINISHES TO MATCH EXISTING AT NO ADDITIONAL COST TO FORT BEND ISD (OWNER).

E. EXISTING AREAS REQUIRING MINOR DEMOLITION OR REPAIR FOR EXECUTION OF WORK SHALL BE REPAIRED TO MATCH EXISTING ADJACENT MATERIALS, UNLESS NOTED OTHERWISE.

F. DO NOT DAMAGE CASEWORK AND EQUIPMENT NOT DESIGNATED TO BE REMOVED OR RELOCATED.EXISTING CASEWORK SHALL REMAIN THE PROPERTY OF THE OWNER.

G. CONTRACTOR TO VERIFY LOCATION OF ELEC. SWITCHES, OUTLETS, GRILLES, CLEAN-OUTS, COVER PLATES, ACCESS DOORS, AND OTHER EQUIPMENT AND DEVICES THAT MAY CONFLICT WITH THE RENOVATION AND NEW CONSTRUCTION OF WALLS, FLOORS, AND CEILINGS PRIOR TO COMMENCEMENT OF WORK. CONTRACTOR SHALL LIKEWISE CONFIRM THAT ELECTRICAL CONDUIT ROUTING SHALL BE CONCEALED WITHIN WALLS. NOTIFY ARCHITECT IF WALL THICKNESS WILL NOT ALLOW FOR CONCEALMENT.

H. REMOVE ANY EXISTING CORNER GUARDS IN THE KITCHEN AREA.

I. PRIOR TO EXECUTION OF DEMOLITION WORK, SCHEDULE A WALK-THROUGH WITH OWNER AND ARCHITECT TO CONFIRM SCOPE OF WORK AND TO REVIEW EXISTING CONDITIONS.

J. EXISTING FLOOR FINISHES AND ACOUSTIC CEILING TILE TO BE REMOVED THROUGHOUT.

K. REFER TO MEP DRAWINGS FOR DEMOLITION AND ALTERATION OF UTILITIES.

L. AT ALL EXISTING WALLS REQUIRING DEMOLITION TO INSTALL NEW PIPING BEHIND SINKS, CUT AND PATCH WALLS AS REQUIRED TO MATCH ADJACENT SURFACE.

M. CLEAN AND PREPARE SUBFLOOR FOR INSTALLATION OF NEW FLOOR FINISH.

N. DEMOLITION ACTIVITIES SHALL BE PERFORMED AS TO PRODUCE MINIMAL DISTURBANCE TO EXISTING FACILITY OCCUPANTS. MINIMIZE EXCESSIVE AND PROLONGED NOISE LEVELS AND DUST.

O. ASBESTOS-CONTAINING MATERIALS. REFER TO SPECIFICATION 02 26 23 FOR ASBESTOS INFORMATION APPLICABLE TO KITCHEN AREAS. FORT BEND ISD HAS RETAINED A SEPARATE ENVIRONMENTAL CONSULTANT FOR THE REMOVAL OF ASBESTOS. GC TO COORDINATE WITH ENVIRONMENTAL CONSULTANT TO CARRY OUT ASBESTOS ABATEMENT FOR ALL AFFECTED KITCHEN AREAS.

1.2 FLOOR PLAN GENERAL NOTES

A. FIELD VERIFY EXISTING CONDITIONS PRIOR TO GENERATING SHOP DRAWINGS AND FABRICATION OF EQUIPMENT.
B. FLOOR FINISH CHANGES SHALL OCCUR AT THE CENTERLINE OF DOORS UNLESS NOTED OTHERWISE. FLOOR FINISH CHANGES SHALL HAVE THRESHOLDS OR REDUCERS STRIPS.
C. DOORS THAT ARE TO BE REPLACED AND INSTALLED IN EXISTING FRAMES SHALL BE MACHINED FOR HARDWARE DIMENSIONS AT EXISTING FRAMES, CONTRACTOR SHALL FIELD VERIFY FRAME CONDITIONS AND DIMENSIONS.
D. CONTRACTOR TO PROVIDE SHEET METAL REINFORCING STRAP AS REQUIRED FOR MOUNTING OF ALL GRAB BARS, CABINETS, MIRRORS, SHELVING, ETC.
E. SAW CUT AND REMOVE EXISTING SLAB AND FLOOR FINISHES AS REQUIRED TO INSTALL NEW PLUMBING LINES, FLOOR DRAINS, PLUMBING FIXTURES, OR ELECTRICAL ITEMS. SPLICE NEW REINFORCING BARS DOWELED INTO EXISTING CONCRETE, AND PROVIDE NEW VAPOR RETARDER AND WATERSTOPS, AND PATCH W/ 3000 PSI CONCRETE AFTER INSTALLATION OF UTILITIES AND FIXTURES. PREPARE CONCRETE TO RECEIVE NEW FINISH.
F. COORDINATE HOUSEKEEPING PAD DIMENSIONS AND LOCATIONS WITH EQUIPMENT TO BE INSTALLED. HOUSEKEEPING PADS SHALL BE A MIN. OF 4" THICK REINF. W/ #3 BARS AT 15" O.C. BOTH WAYS. PROVIDE 1" BY 45-DEGREE CHAMFERED EDGES.

1.3 COMPLETE PERFORMANCE

L. THE CONTRACTOR SHALL FURNISH AND INSTALL ALL ITEMS SPECIFIED HEREIN AND AS INDICATED ON THE DRAWINGS. THE CONTRACTOR SHALL ALSO FURNISH AND INSTALL ALL ITEMS NECESSARY TO MAKE THE SYSTEMS FUNCTION WHICH MAY BE REASONABLY IMPLIED AS ESSENTIAL, WHETHER MENTIONED IN THE CONTRACT DOCUMENTS OR NOT.

M. WORK SHALL BE EXECUTED IN STRICT ACCORDANCE WITH THE BEST PRACTICE OF THE TRADES IN A THOROUGH, SUBSTANTIAL AND WORKMANLIKE MANNER BY COMPETENT WORKMEN.

1.4 SITE FAMILIARIZATION

A. GENERAL: BECOME FAMILIAR WITH THE DRAWINGS AND SPECIFICATIONS, EXAMINE THE PREMISES, AND UNDERSTAND THE CONDITIONS UNDER WHICH THE CONTRACT SHALL BE PERFORMED, PRIOR TO SUBMITTING A BID.

B. SITE: BE INFORMED OF THE SITE CONDITIONS, VERIFY LOCATIONS OF NEW AND EXISTING EQUIPMENT, AND DETERMINE EXACT REQUIREMENTS FOR CONNECTIONS.

C. COORDINATION: TENDER OF A PROPOSAL FOR THIS PROJECT INFERS THAT THE CONTRACTOR HAS VISITED THE SITE AND HAS BECOME FAMILIAR WITH THE DRAWINGS, SPECIFICATIONS, AND SITE CONDITIONS AND HAS INCLUDED IN HIS PROPOSAL ALL WORK NECESSARY TO PROPERLY INSTALL COMPLETE AND FUNCTIONING SYSTEMS ON THE PROJECT. FAILURE TO COMPLY WITH THIS REQUIREMENT SHALL NOT BE CONSIDERED JUSTIFICATION FOR THE OMISSION OR FAULTY INSTALLATION OF ANY WORK COVERED BY THE CONTRACT DOCUMENTS.

1.5 CODES AND STANDARDS

A. GENERAL: ALL WORK SHALL COMPLY WITH THE MOST RECENTLY REVISED VERSIONS OF ALL APPLICABLE LAWS, RULES, REGULATIONS AND ORDINANCES OF ALL FEDERAL, STATE AND LOCAL AUTHORITIES AND APPLICABLE UTILITIES. NONE OF THE TERMS OR PROVISIONS OF THIS SPECIFICATION SHALL BE CONSTRUED AS WAIVING ANY PART OF THE LAWS, RULES, REGULATIONS OR REQUIREMENTS OF THESE AUTHORITIES.

B. CONFLICT: IN THE EVENT OF CONFLICT BETWEEN THE CONTRACT DOCUMENTS AND THE LOCAL ENFORCING AUTHORITY, THE LATTER SHALL RULE. ANY MODIFICATIONS RESULTING THEREFROM SHALL BE MADE WITHOUT ANY ADDITIONAL COST TO THE OWNER OR ARCHITECT. THIS CONTRACTOR SHALL REPORT ANY SUCH MODIFICATIONS TO THE ARCHITECT AND SECURE HIS APPROVAL PRIOR TO PROCEEDING WITH THE WORK.

C. PRECEDENCE: WHERE CONTRACT DOCUMENT REQUIREMENTS EXCEED THE REQUIREMENTS OF THE CODES AND STANDARDS, THE CONTRACT DOCUMENTS SHALL TAKE PRECEDENCE PROVIDED THEY ARE NOT IN CONFLICT WITH THOSE CODES AND STANDARDS.

D. APPROVAL LABELS: ALL ITEMS OF EQUIPMENT AND ALL MATERIALS FOR WHICH APPROVED STANDARDS HAVE BEEN ESTABLISHED BY UNDERWRITERS' LABORATORIES, INC. (UL), FACTORY MUTUAL (FM), CERTIFIED BALLAST MANUFACTURER (CBM), ELECTRICAL TESTING LABORATORY (ETL), NATIONAL MANUFACTURERS ASSOCIATION (NEMA), AMERICAN STANDARD CODES, ASME, AGA, AMCA, ASA, ANSI, ASHRAE, AND ARI SHALL BE SO APPROVED AND SHALL BEAR APPROVAL LABELS ATTESTING TO SAME.

1.6 DRAWINGS AND SPECIFICATIONS

A. DRAWINGS: THE SET OF ORIGINAL DRAWINGS HAS BEEN MODIFIED AND INDICATE APPROXIMATE EXISTING LOCATIONS OF THE FLOOR FINISH ITEMS. ALL ITEMS ARE SHOWN APPROXIMATELY TO SCALE. FIELD VERIFY CONDITIONS.

B. SPECIFICATIONS: THE SPECIFICATIONS ARE INTENDED TO SUPPLEMENT THE DRAWINGS AND IT IS NOT IN THE SCOPE OF THE SPECIFICATIONS TO MENTION ANY PART OF THE WORK THAT THE DRAWINGS ARE COMPETENT TO FULLY EXPLAIN. CONVERSELY, ANY PART OF THE WORK THAT THE SPECIFICATIONS ARE COMPETENT TO FULLY EXPLAIN MAY NOT BE MENTIONED ON THE DRAWINGS. DRAWINGS AND SPECIFICATIONS ARE COMPLIMENTARY/SUPPLEMENTARY DOCUMENTS TO EACH OTHER.

C. DISAGREEMENT: DISAGREEMENT BETWEEN THE DRAWINGS AND SPECIFICATIONS OR WITHIN THE DRAWINGS OR SPECIFICATIONS SHALL BE ESTIMATED AND/OR BID USING THE BETTER QUALITY OR GREATER QUANTITY OF MATERIAL OR INSTALLATION, AND A CLARIFICATION REQUEST FOR INFORMATION SHALL BE MADE TO THE ARCHITECT IN A TIMELY MANNER AFTER THE PROJECT IS UNDER CONTRACT.

1.7 DISCREPANCIES

A. CLARIFICATION: CLARIFICATION OF SIGNIFICANT COST MATTERS SHALL BE OBTAINED BEFORE SUBMITTING A PROPOSAL FOR THE WORK AS TO DISCREPANCIES OR OMISSIONS FROM THE CONTRACT DOCUMENTS OR QUESTIONS AS TO THE INTENT THEREOF.

B. INTERPRETATIONS: SHOULD ANY DOUBT OR QUESTION ARISE RESPECTING THE TRUE MEANING OF DRAWINGS OR SPECIFICATIONS, REFERENCE SHALL BE MADE TO THE ARCHITECT, WHOSE WRITTEN DECISION SHALL BE FINAL AND CONCLUSIVE. NO ALLEGED STATEMENT BY THE ARCHITECT WILL BE ACCEPTED AS AN EXCUSE FOR NON-COMPLIANCE OR INFERIOR WORK.

C. CONTRACTOR AGREEMENT: CONSIDERATION WILL NOT BE GRANTED FOR MISUNDERSTANDING OF THE AMOUNT OF WORK TO BE PERFORMED. TENDER OF A PROPOSAL CONVEYS FULL CONTRACTOR AGREEMENT OF THE ITEMS AND CONDITIONS SPECIFIED, SHOWN, SCHEDULED, OR REQUIRED BY THE NATURE OF THE PROJECT, AND ALL COSTS ARE INCLUDED IN THE PROPOSAL.

1.8 REQUESTS FOR INFORMATION (RFI)

A. GENERAL: SUBMIT ALL CONTRACTOR REQUESTS FOR INFORMATION (RFI) IN WRITING TO THE ARCHITECT FOR RESPONSE. SUBMIT RFI ON A STANDARD FORM THAT HAS A SPACE FOR THE REQUESTED INFORMATION AND THE ARCHITECT'S RESPONSE.
B. SOLUTION PROPOSAL: IN GENERAL, THE CONTRACTOR SHALL PROPOSE SOLUTIONS TO IDENTIFY PROBLEMS FOR REVIEW AND APPROVAL OF THE ARCHITECT. THE RFI SHALL INCLUDE HAND SKETCHES, MARKED DRAWING PRINTS, EQUIPMENT CUTSHEETS, DRAWING AND SPECIFICATION REFERENCES, AND ANY OTHER BACK-UP INFORMATION, ETC., AS REQUIRED TO SUFFICIENTLY EXPLAIN THE PROBLEM AND PROPOSED SOLUTION.

1.9 QUALITY ASSURANCE

A. GENERAL: MATERIALS AND EQUIPMENT SHALL BE NEW, OF BEST GRADE AND QUALITY, AND STANDARD PRODUCTS OF REPUTABLE MANUFACTURERS REGULARLY ENGAGED IN THE PRODUCTION OF SUCH MATERIALS AND EQUIPMENT.
B. WORKMANSHIP: WORK SHALL BE EXECUTED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE BEST PRACTICE OF THE TRADES IN A THOROUGH, SUBSTANTIAL, WORKMANLIKE MANNER BY COMPETENT WORKMEN, PRESENTING A NEAT APPEARANCE WHEN COMPLETED.
C. JUDGMENT: IN ALL CASES, THE ARCHITECT SHALL BE THE SOLE JUDGE OF THE QUALITY AND EQUIVALENCE OF MANUFACTURERS, PRODUCTS, MATERIALS, AND METHODS.
D. MANUFACTURERS/PRODUCTS/MATERIALS/METHODS: MANUFACTURERS, PRODUCTS, MATERIALS, AND METHODS DESCRIBED IN THE VARIOUS SECTIONS OF THE SPECIFICATIONS AND INDICATED ON THE DRAWINGS ARE INTENDED TO ESTABLISH A STANDARD OF QUALITY ONLY. IT IS NOT THE INTENTION OF THE ARCHITECT TO DISCRIMINATE AGAINST ANY MANUFACTURER, PRODUCT, MATERIAL, OR METHOD THAT IS EQUAL TO THE STANDARDS AS INDICATED AND/OR SPECIFIED, NOR IS IT INTENDED TO PRECLUDE OPEN, COMPETITIVE BIDDING. THE FACT THAT A SPECIFIC MANUFACTURER IS LISTED AS AN ACCEPTABLE MANUFACTURER SHALL NOT BE INTERPRETED TO MEAN THAT THE MANUFACTURER'S STANDARD PRODUCT WILL MEET THE REQUIREMENTS OF THE PROJECT DESIGN, SPECIFICATIONS, AND SPACE CONSTRAINTS.
    1. WHEREVER A DEFINITE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS SPECIFIED AND THERE IS NOT A STATEMENT THAT ANOTHER MANUFACTURER, PRODUCT, MATERIAL, OR METHOD WILL BE ACCEPTABLE, IT IS THE INTENTION OF THE ARCHITECT THAT THE SPECIFIED MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS THE ONLY ONE THAT SHALL BE USED WITHOUT PRIOR APPROVAL.
    2. WHEREVER A DEFINITE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS SPECIFIED AS "NO SUBSTITUTE", IT IS THE INTENTION OF THE ARCHITECT THAT THE LISTED ITEM IS THE ONLY ONE ACCEPTABLE.
E. COORDINATION: WHERE EQUIPMENT IS USED ON THE PROJECT, IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR OR SUBCONTRACTOR INVOLVED TO VERIFY THAT THE EQUIPMENT WILL FIT IN THE SPACE AVAILABLE, INCLUDING ALL REQUIRED CODE AND MAINTENANCE CLEARANCES, AND TO COORDINATE ALL EQUIPMENT REQUIREMENTS AND PROVISIONS WITH THE SYSTEM DESIGN, ALL AFFECTED DIVISIONS, AND ALL OTHER CONTRACTORS. WHERE THE USE OF ALTERNATE OR SUBSTITUTE MATERIALS AFFECTS THE COST OF PROVISIONS MADE BY OTHER CONTRACTORS, THE CONTRACTOR PROVIDING THE ALTERNATE OR SUBSTITUTE SHALL BE RESPONSIBLE FOR THE OTHER CONTRACTOR'S COST ADJUSTMENT. THERE SHALL BE NO ADDITIONAL COST TO THE OWNER OR ARCHITECT DUE TO THE USE OR ACCEPTANCE OF ANY ALTERNATE OR SUBSTITUTE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD.

1.10 PRIOR APPROVAL

A. SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES: THE CONTRACTOR'S SUBMITTAL AND ARCHITECT'S ACCEPTANCE OF SHOP DRAWINGS, PRODUCT DATA, OR SAMPLES THAT RELATE TO CONSTRUCTION ACTIVITIES NOT COMPLYING WITH THE CONTRACT DOCUMENTS DOES NOT CONSTITUTE AN ACCEPTABLE OR VALID REQUEST FOR SUBSTITUTION, NOR DOES IT CONSTITUTE APPROVAL.

1.11 COORDINATION

A. BY SUBMITTING SHOP DRAWINGS ON THE PROJECT, THIS CONTRACTOR IS INDICATING THAT ALL NECESSARY COORDINATION HAS BEEN COMPLETED AND THAT THE SYSTEMS, PRODUCTS AND EQUIPMENT SUBMITTED CAN BE INSTALLED IN THE BUILDING AND WILL OPERATE AS SPECIFIED AND INTENDED, IN FULL COORDINATION WITH ALL OTHER DISCIPLINES.

1.12 SHOP DRAWINGS AND SUBMITTALS

A. GENERAL: AFTER THE CONTRACT IS AWARDED BUT PRIOR TO PROCEEDING WITH THE WORK REQUIRING SHOP DRAWING REVIEW, THE CONTRACTOR SHALL OBTAIN COMPLETE SHOP DRAWINGS AND PRODUCT DATA FROM THE MANUFACTURERS, SUPPLIERS, VENDORS, AND SUB- CONTRACTORS FOR ALL MATERIALS AND EQUIPMENT SPECIFIED HEREIN, AND MAKE FORMAL SUBMISSION TO THE ARCHITECT. A MINIMUM PERIOD OF TWO (2) WEEKS SHOULD BE ALLOWED IN THE CONSTRUCTION SCHEDULE EXCLUSIVE OF TRAVEL TIME FOR THE ARCHITECTS REVIEW.

B. CERTIFICATION: EACH CONTRACTOR RESPONSIBLE FOR THE WORK SHALL REVIEW AND CERTIFY THE SHOP DRAWING, SUBMITTAL AND/OR PRODUCT DATA TO BE IN FULL COMPLIANCE WITH THE REQUIREMENTS OF THE CONTRACT DOCUMENTS.

C. THE ARCHITECTS REVIEW OF SHOP DRAWINGS AND SUBMITTAL DATA SHALL NOT RELIEVE THE CONTRACTOR OF THE RESPONSIBILITY FOR DIMENSIONS OR ERRORS THAT MAY BE CONTAINED THEREIN, OR FOR DEVIATIONS FROM ANY REQUIREMENTS OF THE CONTRACT DOCUMENTS. IT SHALL BE CLEARLY UNDERSTOOD THAT THE ARCHITECTS NOTING SOME ERRORS BUT OVERLOOKING SOME OTHERS DOES NOT GRANT THE CONTRACTOR PERMISSION TO PROCEED IN ERROR. REGARDLESS OF ANY INFORMATION CONTAINED IN THE SHOP DRAWING OR PRODUCT DATA, THE CONTRACT DOCUMENTS SHALL GOVERN THE WORK AND ARE NEITHER WAIVED NOR SUPERSEDED IN ANY WAY BY THE REVIEW OF SHOP DRAWINGS, PRODUCT DATA AND SAMPLES.

1.13 EXECUTION AND COORDINATION OF WORK

A. MANUFACTURER'S RECOMMENDATIONS: WITH EXCEPTIONS AS SPECIFIED AND/OR INDICATED ON THE DRAWINGS OR IN THE SPECIFICATIONS, APPLY, INSTALL, ERECT, USE, CLEAN, AND CONDITION, MANUFACTURED ARTICLES, MATERIALS, AND EQUIPMENT PER MANUFACTURER'S CURRENT PRINTED RECOMMENDATIONS. KEEP COPIES OF SUCH PRINTED RECOMMENDATIONS AT JOB SITE AND MAKE THEM AVAILABLE AS REQUIRED.

1.14 SUPERVISION

A. A COMPETENT SUPERINTENDENT APPROVED BY THE ARCHITECT, SHALL BE KEPT BY THE CONTRACTOR AT THE BUILDING TO RECEIVE INSTRUCTIONS AND TO ACT FOR THE CONTRACTOR. ONCE THE SUPERINTENDENT HAS BEEN APPROVED, NO CHANGE SHALL BE MADE WITHOUT APPROVAL OF ARCHITECT. REPRESENTATIVES OF THE OWNER, ARCHITECT SHALL HAVE THE RIGHT TO OBSERVE THE WORK AT ANY TIME. THE CONTRACTOR SHALL HAVE A REPRESENTATIVE AVAILABLE WHEN HIS WORK IS BEING OBSERVED AND HE SHALL GIVE ASSISTANCE AS MAY BE REQUIRED TO THE ARCHITECT'S REPRESENTATIVE.

B. THE PROJECT SHALL BE CONSTRUCTED BY EMPLOYEES OF THE CONTRACTOR OR BY WORKERS UNDER HIS SUPERVISION. ANY SUBCONTRACTORS EMPLOYED BY THE CONTRACTOR SHALL BE APPROVED BY THE OWNER'S REPRESENTATIVE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL EQUIPMENT, MATERIAL AND WORK PERFORMED BY ANY SUBCONTRACTOR.

1.15 STORAGE AND PROTECTION OF MATERIALS

A. THE CONTRACTOR SHALL PROPERLY STORE ALL MATERIAL AND EQUIPMENT AT THE JOBSITE AND PROTECT IT FROM THE ELEMENTS AND FROM DAMAGE. ANY EQUIPMENT DAMAGED DUE TO IMPROPER PROTECTION SHALL BE REPLACED BY THE CONTRACTOR AT HIS EXPENSE.

B. THE CONTRACTOR SHALL PROTECT THE WORK, EQUIPMENT, AND MATERIAL OF ALL OTHER TRADES FROM DAMAGE BY HIS WORK OR OTHER WORKMEN, AND SHALL MAKE GOOD ALL DAMAGE THUS CAUSED.

C. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL WORK, MATERIALS, AND EQUIPMENT UNTIL FINALLY INSPECTED, TESTED, AND ACCEPTED. PROTECT WORK AGAINST THEFT, INJURY OR DAMAGE; AND CAREFULLY STORE MATERIAL AND EQUIPMENT RECEIVED ON SITE WHICH ARE NOT IMMEDIATELY INSTALLED. CLOSE OPEN ENDS OF WORK WITH TEMPORARY COVERS OR PLUGS DURING CONSTRUCTION TO PREVENT ENTRY OF OBSTRUCTING MATERIAL. THE CONTRACTOR SHALL COVER AND PROTECT IN AN ACCEPTABLE MANNER TO THE OWNER, EXISTING REMAINING EQUIPMENT AND MATERIALS.

D. IF ANY MATERIAL OR EQUIPMENT IS RECEIVED PRIOR TO THE TIME IT IS REQUIRED, THE CONTRACTOR SHALL BE RESPONSIBLE FOR ITS PROPER STORAGE AND PROTECTION UNTIL SUCH TIME AS IT MAY BE REQUIRED. THE CONTRACTOR SHALL PAY FOR ALL COSTS OF DEMURRAGE OR STORAGE.

1.16 DRAYAGE AND HAULING

A. THE CONTRACTOR SHALL KEEP THE JOBSITE FREE FROM THE ACCUMULATION OF TRASH AND CONSTRUCTION DEBRIS, REGARDLESS OF WHICH SUBCONTRACTOR MAY BE RESPONSIBLE.

1.17 CUTTING AND PATCHING

A. WHERE IT BECOMES NECESSARY TO CUT THROUGH ANY WALL, FLOOR OR CEILING TO PERMIT THE INSTALLATION OF ANY WORK, OR TO REPAIR ANY DEFECTS THAT MAY APPEAR, THE CUTTING SHALL BE PERFORMED UNDER THE SUPERVISION OF THE GENERAL CONTRACTOR. INFORM THE OWNER'S REPRESENTATIVE BEFORE ANY WORK COMMENCES. NO STRUCTURAL MEMBER SHALL BE ALTERED WITHOUT THE WRITTEN PERMISSION OF THE ARCHITECT.

B. VERIFICATION: SHOULD A QUESTION ARISE REGARDING THE ACCEPTABLE LEVEL OF NOISE OR VIBRATION IN A PARTICULAR SPACE OR PIECE OF EQUIPMENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING THE SERVICES OF AN APPROVED ACOUSTICAL CONSULTANT TO DETERMINE ACTUAL NOISE/VIBRATION CONDITIONS.

01 GENERAL NOTES

| | |
|---|---|
| SEQUENCE OF CONSTRUCTION (AS OF 01/27/2025) Schools will be renovated in groups as shown. These groups contain two or three major kitchen renovations and some cafeteria/miscellaneous renovations. This sequencing is critical for FBISD food service to provide the uninterrupted meal services to their schools. | |
| GROUPING 1 | AUSTIN PARKWAY ES + SUGAR MILL ES, kitchen renovations. *Plus: COMMON WEALTH ES, CONERSTONE ES misc. renovations.* |
| GROUPING 2 | SETTLERS WAY ES + PALMER ES kitchen renovations. *Plus: SULLIVAN ES, SIENNA CROSSING ES, HERITAGE ROSE ES misc. renovations* |
| GROUPING 3 | HUNTER'S GLEN ES + HIGHLANDS ES + PECAN GROVE ES kitchen renovations. *Plus: RIDGEGATE ES, DULLES ES misc. renovations.* |

03 PROJECT SCHEDULE

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SIENNA CROSSING ELEMENTARY SCHOOL
10011 STEEP BANK TRACE
MISSOURI CITY, TX 77459

SEAL

REGISTERED ARCHITECT
MICHAEL W. ANDERSON
22651
STATE OF TEXAS

7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

GENERAL NOTES AND ABBREVIATIONS

A00-01

SCOPE OF WORK: SECURITY CAMERAS OVER SERVING LINES.
RENOVATE, RECONFIGURE, AND EXPAND EXISTING CAFETERIA.

**ADOPTED CODES WITH AMMENDMENTS OF CITY OF MISSOURI CITY, TX**

- 2021 INTERNATIONAL BUILDING CODE
- 2021 INTERNATIONAL RESIDENTIAL CODE
- 2021 INTERNATIONAL PLUMBING CODE
- 2021 INTERNATIONAL MECHANICAL CODE
- 2023 NATIONAL ELECTRIC CODE NFPA 70
- 2021 INTERNATIONAL ENERGY CONSERVATION CODE
- 2021 INTERNATIONAL FUEL GAS CODE
- 2021 INTERNATIONAL FIRE CODE

**INTERIOR WALL AND CEILING FINISH REQUIREMENTS BY OCCUPANCY:**

**SPRINKLERED**

| | |
|---|---|
| INTERIOR EXIT STAIRWAYS AND RAMPS AND EXIT PASSAGEWAYS | B |
| CORRIDORS AND ENCLOSURE FOR EXIT ACCESS STAIRWAYS AND RAMPS | C |
| ROOMS AND ENCLOSED SPACES | C |

**FLOORING SHALL BE CLASS II**

**2021 INTERNATIONAL EXISTING BUILDING CODE**

301.3.1 PRESCRIPTIVE COMPLIANCE METHOD. REPAIRS, ALTERATIONS, ADDITIONS AND CHANGES OF OCCUPANCY COMPLYING WITH CHAPTER FIVE OF THIS CODE IN BUILDINGS COMPLYING WITH THE INTERNATIONAL FIRE CODE SHALL BE CONSIDERED IN COMPLIANCE WITH THE PROVISIONS OF THIS CODE.

302.3 EXISTING MATERIALS. MATERIALS ALREADY IN USE IN A BUILDING IN COMPLIANCE WITH REQUIREMENTS OR APPROVALS IN EFFECT AT THE TIME OF THEIR ERECTION OR INSTALLATION SHALL BE PERMITTED TO REMAIN IN USE UNLESS DETERMINED BY THE BUILDING OFFICIAL TO BE UNSAFE .

302.4 NEW AND REPLACEMENT MATERIALS. EXCEPT AS OTHERWISE REQUIRED OR PERMITTED BY THIS CODE, MATERIALS PERMITTED BY THE APPLICABLE CODE FOR NEW CONSTRUCTION SHALL BE USED. LIKE MATERIALS SHALL BE PERMITTED FOR REPAIRS AND ALTERATIONS, PROVIDED THAT NO UNSAFE CONDITION IS CREATED. HAZARDOUS MATERIALS SHALL NOT BE USED WHERE THE CODE FOR NEW CONSTRUCTION WOULD NOT PERMIT THEIR USE IN BUILDINGS OF SIMILAR OCCUPANCY, PURPOSE AND LOCATION.

**ALTERATION - LEVEL 1** INCLUDE THE REMOVAL AND REPLACEMENT OR THE COVERING OF EXISTING MATERIALS, ELEMENTS, EQUIPMENT, OR FIXTURES USING NEW MATERIALS, ELEMENTS, EQUIPMENT, OR FIXTURES THAT SERVE THE SAME PURPOSE.

**ALTERATION - LEVEL 2** INCLUDE THE ADDITION OR ELIMINATION OF ANY DOOR OR WINDOW, THE RECONFIGURATION OR EXTENSION OF ANY SYSTEM, OR THE INSTALLATION OF ANY ADDITIONAL EQUIPMENT, AND SHALL APPLY WHERE THE WORK IS EQUAL TO OR LESS THAN 50% OF THE BUILDING AREA.

THIS BUILDING'S CONSTRUCTION IS TYPE IIB.

THIS BUILDING'S OCCUPANCY IS E.


THIS BUILDING'S IS SPRINKLERED.

THERE WILL NOT BE ANY MODIFACATIONS TO THE HOOD SYSTEMS IN THE KITCHENS BEYOND REPLACEMENT OF MOTOR FOR LIKE KIND IF NEEDED.

THE BUILDING WILL NOT HAVE ADDITIONAL SQUARE FOOTAGE AS PART OF THE WORK.

NEW CONSTRUCTION ELEMENTS, COMPONENTS, SYSTEMS AND SPACES SHALL COMPLY WITH THE REQUIREMENTS OF THE INTERNATIONAL BUILDING CODES

# 2 CODE ANALYSIS




# 1 OVERALL FLOOR PLAN

SCALE: 1/16" = 1'-0"

| PHASING CHART FOR ALL SCHOOLS | | |
|---|---|---|
| PHASE 1 | | |
| **SCHOOLS** | **FREEZER START DATE :** | **FREEZER END DATE :** |
| ***AUSTIN PARKWAY ES*** | 11/7/2025 | 5/13/2026 |
| SUGAR MILL ES | | |
| COMMONWEALTH ES | | |
| CONERSTONE ES | | |
| PHASE 2 | | |
| SETTLERS WAY ES | 5/29/2026 | 10/28/2026 |
| PALMER ES | | |
| SULLIVAN ES | | |
| SIENNA CROSSING ES | | |
| HERITAGE ROSE ES | | |
| **PHASE 3** | | |
| HUNTERS GLEN ES | 3/19/2027 | 3/19/2027 |
| PECAN GROVE ES | | |
| HIGHLANDS ES | | |
| DULLES ES | | |

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

t

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SIENNA CROSSING ELEMENTARY SCHOOL
10011 STEEP BANK TRACE
MISSOURI CITY, TX 77459

SEAL
R. RICHARD ARCHITECT
REGISTERED
23201
STATE OF TEXAS
7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

OVERALL FLOOR PLAN

t-A.201

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\T-Sienna Crossing ES\t-A.201 FLOOR PLAN.dwg Jul 23, 2025 - 4:53pm

DOOR SCHEDULE

| DOOR # | DOOR WIDTH | DOOR HEIGHT | DOOR TYPE | DOOR MATERIAL | DOOR FINISH | FIRE RATING | FRAME THICKNESS | FRAME FINISH | DETAILS SILL | DETAILS JAMB | DETAILS HEAD | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| A1 | - | | - | - | - | - | - | - | - | - | - | REFERENCE ONLY - NO WORK THIS DOOR. |
| A2 | - | | - | - | - | - | - | - | - | - | - | REFERENCE ONLY - NO WORK THIS DOOR. |
| A3 | - | | - | - | - | - | - | - | - | - | - | REFERENCE ONLY - NO WORK THIS DOOR. |
| A4 | 3'-0" | X ___" | — | S.C. WOOD | S.C. WOOD | NR | 4 7/8"* | ALUM | | | | REPLACE EXISTING WITH SOLID DOOR WITHOUT LITES |
| A5 | PR. 3'-0" | X ___" | —— | S.C. WOOD | S.C. WOOD | NR | 4 7/8"* | ALUM | | | | REPLACE EXISTING WITH SOLID DOOR WITHOUT LITES |
| A6 | - | | - | - | - | - | - | - | - | - | - | REFERENCE ONLY - NO WORK THIS DOOR. |
| A7 | - | | - | - | - | - | - | - | - | - | - | REFERENCE ONLY - NO WORK THIS DOOR. |
| A8 | - | | - | - | - | - | - | - | - | - | - | REFERENCE ONLY - NO WORK THIS DOOR. |

## 2 DOOR SCHEDULE

## FLOOR PLAN - GENERAL NOTES

1. REFER TO SHEET FOR GENERAL NOTES. GENERAL NOTES APPLY TO ALL SCHOOL KITCHENS.
2. REFER TO SHEET FOR PARTITION TYPES.
3. EXIXSTING EXPOSED CONDUITS AND DATA CABLING IN WIREMOLD TO BE ROUTED INSIDE WALLS (EXCEPT AT WAREWASH AREA BELOW TABLE HEIGHT AND DRY STORAGE ROOMS). PATCH AND REPAIR AS REQUIRED TO ACHIEVE SMOOTH CLEAN WALL SURFACE.

## PARTITION LEGEND

- EXISTING CMU PARTITION
- NEW CMU SCHEDULED PARTITION
- EXISTING METAL PARTITION
- NEW FRAMED SCHEDULED PARTITION

REFER TO SHEET FOR PARTITION TYPES

## FLOOR PLAN - KEYED NOTES

(NOT ALL NOTES USED ON EACH SHEET)

01 PROVIDE NEW MOP SINK UTILITY SHELF
RE: PLUMBING FOR MOP SINK
RE: SPEC 10 28 00 FOR UTILITY SHELF

02 REMOVE, STORE & REPLACE WALL MOUNTED FIRE EXTINGUISHER

03 PROVIDE NEW WALL MOUNTED FIRE EXTINGUISHER
RE: SPEC SECTIONS 10 44 13

04 PROVIDE NEW LOCKERS
RE: SPEC 10 51 13.

05 PROVIDE WASHER AND DRYER
RE: SPEC 11 45 20

06 REMOVE, PROTECT & REINSTALL WALL MOUNTED CLOCK.

07 PROVIDE CONDENSING UNIT
FOR WALK-IN COOLER/FREEZER
RE: MECHANICAL AND SPEC 11 40 00


08 PROVIDE POWER AND DATA FOR MENU BOARD.
RE: ELECTRICAL, TECHNOLOGY DRAWINGS & FOOD SERVICE.

09 PROVIDE P-LAM SHELVING
REFER TO DETAIL FOR BRACKET SUPPORT

10 FURNITURE & NON FOOD SVE EQUIPMENT RETURN TO OWNER FOI STORAGE

11 INSPECT & SREVICE TOLLING COUNTER DOORS. RETURN TO LIKE NEW CONDITION.

## 3 FLOOR PLAN NOTES




## 1 KITCHEN PLAN

SCALE: 1/4" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

t

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SIENNA CROSSING ELEMENTARY SCHOOL
10011 STEEP BANK TRACE
MISSOURI CITY, TX 77459

SEAL
REGISTERED ARCHITECT
MICHAEL W. WILLIAMS
22651
STATE OF TEXAS
7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

KITCHEN PLAN

t-A.301

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\T-Sienna Crossing ES\t-A.301 KITCHEN PLAN.dwg Jul 23, 2025 - 4:53pm




---- RCP PLAN
SCALE: 1/4" = 1'-0" XREF

## RCP - GENERAL NOTES

1. CEILING GRID SHALL BE INSTALLED TO MATCH EXISTING GRID'S POINT OF OR THIS WILL REDUCE NEED TO RE-LOCATE ABOVE CEILING DUCTS, SPRINKLER AND OTHER SUPPORT SYSTEMS.
2. REFER TO SHEET A00-01 FOR GENERAL NOTES. GENERAL NOTES APPLY TO SEVEN SCHOOL KITCHEN REMODELS.
3. LIGHTING LEVELS SHOULD BE 50 FC IN PREPARATION AREAS, WARE WASH A SERVING LINES, OR MEET MINIMUM HEALTH CODE LEVELS, WHICHEVER ITS SEE MEP PLANS
4. REPLACE HVAC DEVICES. REPLACE LIGHTING WITH 24"x24" LED LAY IN LIGH SCHEDULED IN ELECTRICAL PLANS.
5. REFER TO MECHANICAL, ELECTRICAL SHEETS FOR DEVICE SCHEDULES.

## RCP - NUMBERED NOTES

01 PROVIDE 30"x30" MIN. ACCESS HATCH IN SOFFIT CENTERED ON MOTOR.

02 AFTER LOWERING THE NEW POWER RETRACTION SYSTEM. REPAIR AND PAINT SOFFITS AND SIDWALLS OF FURR TO MATCH EXISTING.

---- RCP NOTES
SCALE: 1/4" = 1'-0" XREF

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT

SEAL
REGISTERED ARCHITECT
ROBERT A. WEBB
22453
STATE OF TEXAS
7/15/2025



MWA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

REFLECTED CEILING PLAN

T-A.401

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\t-A.401 REFLECTED CEILING PLAN.dwg Jul 23, 2025 - 4:53pm





1 FINISH PLAN
SCALE:3/16"=1'-0"

PAINT COLOR SCHEDULE
UNLESS OTHERWISE INDICATED FIELD COLOR IS PT-1 (SW 7014 EIDER WHITE)
SW 7014 EIDER WHITE (EPOXY PAINT)

WALL TILE
CERAMIC WALL TILE (WT-1)
REFER TO TILE PATTERN AT SERVING AND RESTROOM
FIELD WALL TILE: DALTILE RITTENHOUSE SQUARE K175 BISCUIT (3X6)

A — PROVIDE ROOM SIGN TO REPLACE EXISTING. SEE LAYOUT FOR TYPE A OR TYPE B SIGN LOCATIONS.


2 FINISH FLOOR LEGEND




TYPE A
ROOM SIGNAGE - FIXED NAMES


TYPE B
KITCHEN RESTROOM SIGNAGE

3 ROOM SIGNAGE





WALL TILE PATTERN - RESTROOM

4 WALL TILE PATTERN




5 CAFETERIA SIDE OF WALL (NEW CONSTRUCTION)
SCALE: 3/16 = 1'-0"




6 GYM SIDE OF WALL (NEW CONSTRUCTION)
SCALE: 3/16" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

t

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT

SEAL
REGISTERED ARCHITECT
ROBERT A. NAVARRO
22653
STATE OF TEXAS
7/15/2025


ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

FINISH FLOOR PLAN

t-A.501

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\T-Sienna Crossing ES\t-A.501 FINISH FLOOR PLAN.dwg Jul 23, 2025 - 4:54pm

## SYMBOL LEGEND


| | |
|---|---|
| | SIMPLEX/DUPLEX/QUAD – 5361/2 REC |
| GFI | DUPLEX W/ GFCI PROTECTION–P&S 2097 |
| | J–BOX |
| | CEILING MOUNTED J–BOX |
| | MOTOR |
| | HEAVY DUTY, NON–FUSED DISCONNECT. MIN RATING OF CIRCUIT OCPD/VOLTAGE. |
| | ELECTRICAL PANEL |
| | HOMERUN TO CIRCUIT NOTED |
| E | EXISTING DEVICES TO REMAIN |
| R | EXISTING DEVICES TO BE RELOCATED |
| D | EXISTING DEVICES TO BE DEMO/REMOVED |
| REP | EXISTING DEVICES TO BE REPLACED |
| S | INDICATES SURFACE MOUNTED |
| SR | INDICATES SURFACE RACEWAY |
| + | INDICATES ABOVE COUNTER DEVICE |
| + | INDICATES DEVICE AT +30–60" |
| ++ | INDICATES DEVICE AT +80–96" |
| CLG | INDICATES DEVICES MOUNTED IN CEILING |
| WP | INDICATES WEATHERPROOF COVER |
| 3R | INDICATES 3R RATED DEVICE |
| (E)LA–X | CONNECT(ED) TO EXIST CIRCUIT LA–X |
| (D)LA–X | DEMO PORTION OF EXIST CIRCUIT LA–X |
| (N)LA–X | CONNECT(ED) TO NEW CIRCUIT LA–X |

GENERAL ELECTRICAL NOTES:

1. INSTALL SYSTEM IN ACCORDANCE WITH THE NATIONAL ELECTRIC CODE AS ADOPTED BY THE LOCAL AUTHORITY HAVING JURISDICTION INCLUDING ALL AMENDMENTS.
2. PROVIDE CONDUIT FOR ALL DEVICES INSTALLED IN WALLS.
   - 2.A. 3/4"C FOR POWER AND 1"C FOR LOW VOLTAGE/DATA UNLESS NOTED OTHERWISE.
   - 2.B. PROVIDE PROTECTIVE BUSHING ON END OF ALL LOW VOLTAGE CONDUITS.
   - 2.C. ALL ELECTRICAL HOMERUNS SHALL BE IN CONDUIT, MIN 3/4"C.
   - 2.D. USE INSULATED THROAT FITTINGS FOR CONNECTIONS TO HOUSINGS, BOXES, ENCLOSURES, ETC.
   - 2.E. MAX LENGTH FOR FLEX CONDUIT SHALL BE 6FT AND MIN. SIZE SHALL BE 1/2". ALL FLEX CONDUIT SHALL BE LISTED FOR GROUNDING.
3. CONDUIT TYPES:
   - 3.A. INSIDE BUILDINGS: GALVANIZED STEEL EMT.
     - 3.A.A. ALL LOW VOLTAGE CABLING SHALL BE INSTALLED IN CONDUIT IN EXPOSED CEILING AREAS. ROUTE TO NEAREST ACCESSIBLE CEILING WITH CONTINUOUS PATHWAYS TO LOW VOLTAGE SOURCE/DEVICE.
     - 3.A.B. ALL LOW VOLTAGE CABLING SHALL BE INSTALLED IN CONDUIT ABOVE INACCESSIBLE CEILINGS. ROUTE TO NEAREST ACCESSIBLE CEILING WITH CONTINUOUS PATHWAYS TO LOW VOLTAGE SOURCE/DEVICE.
   - 3.B. NO MC CABLE SHALL BE ALLOWED.
   - 3.C. PROVIDE FLEXIBLE CONNECTIONS TO MOTORS, PUMPS, TRANSFORMERS, OR SIMILAR EQUIPMENT.
4. PROVIDE GALVANIZED STEEL, ONE–PIECE CONSTRUCTION, OUTLET BOXES IN ALL CASES SUITABLE FOR INTENDED USE.
   - 4.A. BOXES OUTSIDE SHALL BE STEEL NEMA 3 TYPE.
   - 4.B. PROVIDE CEILING BRACKET TO SUPPORT CEILING MOUNTED DEVICES FROM CEILING TEES.
5. 20 AMP, SINGLE PHASE BRANCH CIRCUITS SERVING LIGHTING AND GENERAL RECEPTACLES MAY BE GROUPED IN A SINGLE RACEWAY PROVIDED A NEUTRAL CONDUCTOR IS INSTALLED FOR EACH CIRCUIT REQUIRING A NEUTRAL.
   - 5.A. DO NOT INSTALL MORE THAN FOUR CURRENT CARRYING CONDUCTORS IN A CONDUIT EXCEPT SIX #12 OR #10 CURRENT CARRYING CONDUCTORS MAY BE INSTALLED IN 3/4" OR LARGER CONDUIT FOR 20A CIRCUITS.
   - 5.B. DO NOT INSTALL 480/277 VOLT CONDUCTORS IN THE SAME CONDUIT WITH 240/208/120 VOLT CONDUCTORS.
   - 5.C. DO NOT COMBINE NEUTRALS. PROVIDE DEDICATED NEUTRALS FOR EACH BRANCH CIRCUIT.
   - 5.D. MULTIPLE DEVICES ON A CIRCUIT SUCH AS RECEPTACLES SHALL BE WIRED WITH A PIGTAIL SO THE DEVICE DOES NOT PROVIDE THE CONTINUITY PATH. FEED THROUGH CONNECTIONS FOR GFCI RECEPTACLES SHALL NOT BE USED FOR PROTECTION OF DOWNSTREAM DEVICES.
6. PROVIDE GREEN GROUND WIRE WITH ALL CIRCUITS SIZED PER NEC. BOND GREEN GROUND WIRE TO EACH END OF CONDUIT.
7. PROVIDE J–BOXES, CONDUIT AND SLEEVES THRU ALL FIRE WALLS FOR DATA, TELEPHONE, SECURITY, FIRE ALARM, SOUND SYSTEM, LOW VOLTAGE WIRING, ETC. PROVIDE PROTECTIVE BUSHINGS ON ENDS OF ALL LOW VOLTAGE CONDUITS.
8. PROVIDE PULL BOXES, JUNCTION BOXES, WIRING TROUGHS AND CABINETS WHEREVER REQUIRED FOR PROPER INSTALLATION OF VARIOUS ELECTRICAL SYSTEMS. ALL JUNCTION/PULL BOXES INSTALLED ABOVE ACCESSIBLE CEILINGS SHALL BE MOUNTED SO THAT THE ACCESS PANEL IS NO HIGHER THAN 18" ABOVE THE CEILING.
9. PROVIDE CIRCUIT LABELS IN PERMANENT MARKER ON ALL NEW AND EXISTING J–BOX COVERS UTILIZED IN THE AREA OF RENOVATION.
10. PROVIDE CIRCUIT LABEL ON ALL ABOVE CEILING J–BOXES, EQUIPMENT, ETC. IDENTIFYING THE CIRCUITS CONTAINED/CONNECTED.
11. ALL WIRING SHALL BE 600 VOLT, SOFT DRAWN ANNEALED COPPER, 98% CONDUCTIVITY, CONTINUOUS FROM OUTLET TO OUTLET. MINIMUM WIRE SIZE #12.
    - 11.A. TYPICAL BUILDING WIRE SHALL BE STRANDED TYPE THHN, THWN–2 (WET RATED FOR 90°C), OR XHHW–2. MINIMUM WIRE SIZE SHALL BE #12.
    - 11.B. ALL BUILDING WIRE SHALL BE COLOR CODED WITH THE SAME COLOR CONNECTED TO THE SAME UNGROUNDED PHASE THROUGHOUT THE INSTALLATION MATCHING THE EXISTING BUILDING COLOR CODE SCHEME.
12. WHERE PORTIONS OF INTERIOR RACEWAY SYSTEM ARE EXPOSED TO WIDELY DIFFERENT TEMPERATURES, PROVIDE AIR SEAL PER NEC TO PREVENT CIRCULATION OF AIR FROM WARMER TO COOLER SECTIONS.
13. DRAWINGS, SCHEDULES, NOTES, AND DETAILS ARE INTENDED TO BE COMPLIMENTARY. ANY WORK DESCRIBED IN ANY OF THEM, WILL BE WORK REQUIRED UNDER THIS CONTRACT. WHERE THERE IS A CONFLICT BETWEEN DIFFERENT PORTIONS OF THE DESIGN DOCUMENTS IT SHALL BE CLARIFIED BY RFI. BARRING CLARIFICATION PRIOR TO BIDDING THE MOST EXPENSIVE OPTION SHALL BE INCLUDED AND CLARIFICATION SHALL BE MADE DURING CONSTRUCTION.
14. SHOULD ANY WORK REQUIRED BY THE DRAWINGS AND SPECIFICATIONS BE IN VIOLATION OF ANY FEDERAL, STATE, COUNTY OR CITY LAWS, ORDINANCE OR REGULATION, THOSE LAWS AND REGULATIONS SHALL PREVAIL, AND SHALL BE COMPLIED WITH BY THE CONTRACTOR AS A PART OF THIS WORK WITH NO EXTRA COMPENSATION.
15. ALL MATERIAL MUST BE NEW AND OF GOOD QUALITY AND SHALL BEAR THE STAMP OF APPROVAL OF THE UNDERWRITERS' LABORATORIES, INC. (U.L.).


GENERAL RENOVATION AND REMODELING NOTES:

1. THESE ELECTRICAL DRAWINGS ONLY SHOW SOME EXISTING ELECTRICAL PANELS, DEVICES AND LIGHT FIXTURES IN AREAS OF RENOVATION. ALL OTHER ELECTRICAL EQUIPMENT, WIRING DEVICES, LOW VOLTAGE SYSTEMS, J–BOXES AND CONDUITS SHALL BE LOCATED AND FIELD VERIFIED BY CONTRACTOR.
2. ALL REMOVED DEVICES SHALL BE OFFERED TO THE OWNER AS SALVAGE.
3. RELOCATE CONDUIT AS NECESSARY TO ALLOW NEW OR MODIFIED CONSTRUCTION. RESUPPORT EXISTING CABLING/CONDUIT TO REMAIN TO MEET CURRENTLY ADOPTED CODE REQUIREMENTS. REMOVE ALL ABANDONED CONDUIT AND WIRE. REPAIR EXISTING ELECTRICAL SYSTEMS DAMAGED BY CONSTRUCTION ACTIVITIES.
4. ANY DAMAGE TO EXISTING BUILDING, ELECTRICAL EQUIPMENT, WIRING DEVICES, CONDUIT, WIRING, ETC. SHALL BE REPLACED BY THE CONTRACTOR AT NO COST TO THE OWNER. ALL MATERIALS USED FOR THE REPLACEMENT MUST MEET RENOVATION PROJECT STANDARDS.
5. ELECTRICAL CONTRACTOR SHALL BEGIN FIELD VERIFYING ALL EXISTING BRANCH CIRCUITS FOR EXISTING AREAS TO BE RENOVATED IMMEDIATELY AFTER THE CONTRACT IS ISSUED.
6. ELECTRICAL CONTRACTOR SHALL FIELD VERIFY EXISTING CIRCUITS WITH OWNER'S MAINTENANCE PERSONNEL AFTER NORMAL BUILDING HOURS AS REQUIRED.
7. ANY CIRCUIT OR PATCH, CIRCUIT TO REMAIN OR BE REUSED SHALL REMAIN ACTIVE.
8. ELECTRICAL CONTRACTOR SHALL INCLUDE COST RELATED TO FIELD VERIFY EXISTING CIRCUITS IN BASE PROPOSAL.
9. FIND AND RECORD ALL EXISTING DEVICES IN CEILINGS, WALLS AND CASEWORK IN AREAS TO BE RENOVATED. PROVIDE A COPY OF THE FIELD VERIFIED DEVICE DRAWINGS TO OWNER PRIOR TO BEGINNING WORK.
10. AT THE END OF THE PROJECT, PROVIDE A NEW TYPEWRITTEN AS–BUILT PANEL SCHEDULE FOR ALL PANELS WITH CIRCUITS ADDED, REMOVED, OR MODIFIED AS PART OF THE PROJECT USING BUILDING ROOM NUMBERS.




## 2 OVERALL FLOOR PLAN

SCALE: 1" = 50'– 0"





## 3 PARTIAL ELECTRICAL RISER - SULLIVAN CROSSING ES

NO SCALE

NOTES:

1. FIELD VERIFY ALL EXISTING ELECTRICAL PANELS AND FEEDERS SHOWN ON DRAWINGS.
2. REF ELECTRICAL FLOOR PLANS FOR PANEL LOCATIONS.
3. ALL OUTAGES SHALL BE SCHEDULED/CONFIRMED IN WRITING WITH THE OWNER A MINIMUM OF TWO WEEKS PRIOR TO ANY OUTAGE.
4. AT THE END OF THE PROJECT PROVIDE A NEW TYPEWRITTEN PANEL SCHEDULE USING BUILDING ROOM NUMBERS FOR ALL PANELS WITH CIRCUITS ADDED, REMOVED, OR MODIFIED AS PART OF THE PROJECT.
5. REFERENCE PANEL SCHEDULES AND SHORT CIRCUIT TABLE FOR AIC AND SCCR VALUES.




## 1 ELECTRICAL RENOVATION PLAN

SCALE: 1/8" = 1'– 0"

| ISSUE: | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SIENNA CROSSING ELEMENTARY SCHOOL
10011 STEEP BANK TRACE
MISSOURI CITY, TX 77459

SEAL




MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL FLOOR PLAN & SCHEDULES

t-E.200

STANTON ENGINEERING GROUP
INFORMATION PROVIDED | TEXAS ENGINEERING FIRM REG. NO. F–12360 | © 2025 ALL RIGHTS RESERVED
(713) 300–60360 | 13999 W. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77040

## AUDIO/VISUAL MULTIMEDIA LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| A## V## | WALL AV ROUGH-IN DETAIL |
| A## V## | CEILING AV ROUGH-IN DETAIL |
| A## V## | FLOOR AV ROUGH-IN DETAIL |
| IWB IWB | INTERACTIVE WHITE BOARD - WALL - CEILING |
| PJ PJ | MULTIMEDIA PROJECTOR |
| FP# FP# | MULTIMEDIA FLAT PANEL DISPLAY |
| S S | LOUDSPEAKER, WALL MOUNTED AND CEILING MOUNTED RESPECTIVELY - # INDICATES TYPE |
| CP# | CONTROL PANEL |
| TP# | TOUCH PANEL |
| M | MICROPHONE, CEILING MOUNTED - # INDICATES TYPE |
| VC | VOLUME CONTROL |
| WB | WALL BOX ENCLOSURE |
| D1 A1 | D1 = DIGITAL SINGLE SIDED CLOCK / A1 = ANALOG SINGLE SIDED CLOCK |
| D2 A2 | D2 = DIGITAL DOUBLE SIDED CLOCK / A2 = ANALOG DOUBLE SIDED CLOCK |
| ENC | CEILING AV ENCLOSURE |
| C C | PRESENTATION CAMERA - CEILING - WALL MOUNTED |

## PREMISE SECURITY LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| CR | CARD READER |
| CR M | CARD READER MULLION |
| KP | INTRUSION DETECTION KEYPAD |
| IC | INTERCOM (1 DATA CABLE) |
| IC MS | INTERCOM MASTER STATION (1 DATA CABLE) |
| PB | PANIC/DURESS BUTTON |
| LD | LOCK DOWN BUTTON |
| MD | MOTION DETECTOR |
| GB | ACCOUSTICAL GLASS BREAK SENSOR |
| BM | BIOMETRIC READER |
| RX | REQUEST TO EXIT - SURFACE PIR |
| KS | KEY SWITCH |
| LA | LOCAL ALARM SOUNDER |
| RG | RED/GREEN INDICATOR LIGHT |
| DB | DOORBELL |
| DH | MAGNETIC DOOR HOLD |
| DR | DOOR RELEASE |
| RX | REQUEST TO EXIT - INTEGRAL TO DOOR HARDWARE |
| DC | DOOR CONTACT / MONITOR |
| ES EL EH | ELECTRIFIED STRIKE - ELECTRIFIED LATCH - ELECTRIFIED HARDWARE (REFER TO SCHEDULES) |
| C C | STANDARD IP SURVEILLANCE CAMERA, (1) CABLE |
| C C | 180° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° FISHEYE LENS CAMERA |
| IR | IR ILLUMINATOR |

## STRUCTURED CABLING LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF DATA CABLE(S)/JACK(S) |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) |
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| W | WALL MOUNT PHONE (1 CABLE/JACK) |
| W | WALL MOUNT PHONE, SURFACE MOUNT (1 CABLE/JACK) |
| # | FLOOR MOUNTED OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| #/# | FLOOR MOUNTED OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| # | CEILING MOUNTED DATA OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) |
| AP# | CEILING MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| AP# | WALL MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| | CABLING SLEEVE(S) |
| | TYPICAL LADDER RACK |
| | TYPICAL CABLE TRAY, BASKET STYLE |

## GENERAL ANNOTATION LEGEND


| SYMBOL | DESCRIPTION |
|---|---|
| MER | MAIN EQUIPMENT ROOM |
| TR | TELECOMMUNICATION ROOM |
| MDF | MAIN DISTRIBUTION FRAME |
| IDF | INTERMEDIATE DISTRIBUTION FRAME |
| ETR | EXISTING TO REMAIN |
| PBO | PROVIDED BY OTHERS |
| AFF | ABOVE FINISHED FLOOR |
| AFG | ABOVE FINISHED GRADE |
| AC | ABOVE COUNTER |
| EC | ELECTRICAL CONTRACTOR |
| PSC | PREMISE SECURITY CONTRACTOR |
| SCC | STRUCTURAL CABLING CONTRACTOR |
| AVC | AV/MULTIMEDIA CONTRACTOR |
| UNO | UNLESS NOTED OTHERWISE |
| ACS | ACCESS CONTROL SYSTEM |
| VSS | VIDEO SURVEILLANCE SYSTEM |

## TECHNOLOGY - GENERAL NOTES

1. EACH KEYNOTE MAY NOT BE UTILIZED ON EVERY SHEET.
2. ALL CONDUIT MEASUREMENTS REFER TO STANDARD CONDUIT TRADE SIZES.
3. ALL CABLES SHALL BE CONCEALED.
4. EACH CONTRACTOR SHALL PROVIDE AND INSTALL ALL NECESSARY SLEEVES, WHETHER OR NOT SPECIFICALLY NOTED ON PROJECT DRAWINGS. ALL SLEEVES SHALL BE 2" UNLESS NOTED OTHERWISE ON THE DRAWINGS. CABLE FILL PERCENTAGE SHALL COMPLY WITH NEC.
5. DEVICE LOCATIONS ARE APPROXIMATE. CONTRACTOR SHALL REVIEW CONDITIONS AND COORDINATE WITH OTHER TRADES AS NECESSARY FOR EXACT PLACEMENT.

## TECHNOLOGY SYMBOLS LEGEND

NOT ALL SYMBOLS ARE USED




TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

t

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Sienna Crossing Elementary School
10011 Steep Bank Trce, Missouri City, TX 77459

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 295857
EXPIRES 12-31-27

07-18-25


MVA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY - TITLE SHEET

t-TN000

## TECHNOLOGY KEYNOTES

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.




1 BACKGROUND T (SIENNA CROSSING ES)
SCALE: 1" = 20'-0"

TRUENORTH A PWY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

t

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Sienna Crossing Elementary School
10011 Steep Bank Trce, Missouri City, TX 77459

SEAL

BICSI REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256557
EXPIRES 12-31-27

07-18-25


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY - Sienna Crossing ES - OVERALL

t-TN.100

## TECHNOLOGY KEYNOTES

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.




2 SIENNA CROSSING - REFLECTED CEILING PLAN
SCALE: 3/16" = 1'-0"

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

t

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Sienna Crossing Elementary School
10011 Steep Bank Trce, Missouri City, TX 77459

SEAL

BICSI REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 258657
EXPIRES 12-31-27
ecpd

07-18-25


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY - Sienna Crossing ES - KITCHEN

t-TN.101

**GENERAL NOTE**


1. FACE PLATE DETAIL FOR OUTLET CONFIGURATION PURPOSES ONLY. CONTRACTOR TO SELECT TYPE OF FACE PLATE TO MATCH CONNECTIVITY HARDWARE, FLOOR BOX AND/OR MODULAR FURNITURE OPENING.









## 1 DATA ROUGH-IN DETAILS
SCALE: NS





## 2 TYPICAL CABLING SLEEVE
SCALE: NTS





## 3 PANDUIT J-HOOK DETAIL
SCALE: NTS





## 4 LABELING & CABLING SCHEMES
SCALE: NTS





## 5 CABLE PATHWAY CROSS SECTION
SCALE: NTS




## 6 DROPPED CEILING MOUNTING DETAIL
SCALE: NS




## 7 I-JOIST MOUNTING DETAIL
SCALE: NS




## 8 BAR JOIST MOUNTING DETAIL
SCALE: NS

| CAMERA TYPE | MANUFACTURER | MODEL NUMBER | GENERAL DESCRIPTION |
|---|---|---|---|
| C1 | iPro | WV-S8574L | 4x4K (33MP) EXTERIOR MULTI-SENSOR - PARKING LOTS, STADIUM |
| C2 | iPro | WV-S8544L | 4x4MP (16MP) EXTERIOR MULTI-SENSOR - BUILDING PERIMETER |
| C3 | iPro | WV-S25500-V3LN | 5MP EXTERIOR VANDAL DOME |
| C4 | iPro | WV-S22500-V3L | 5MP INTERIOR VANDAL DOME - CORR., COMMON, SPED |
| C5 | iPro | WV-S4156A | 5MP 360 (FISHEYE) - STAIRWELLS |

## 9 CAMERA SCHEDULE
SCALE: NTS

| Symbol | Purpose | Size | Mount | Backbox | Notes |
|---|---|---|---|---|---|
| FP1 | Digital Signage/Menu Boards | +49" | Ceiling Pole | N/A | Data and Power Outlets on ceiling |

## 10 DISPLAY SCHEDULE
SCALE: NTS

TRUENORTH A PWY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

t

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Sienna Crossing Elementary School
10011 Steep Bank Trce, Missouri City, TX 77459

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256557
EXPIRES 12-31-27

07-18-25


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY - Sienna Crossing ES - DETAILS


t-TN.500

GENERAL NOTES:


1. REFER TO SECURITY SCHEDULE AND WRITTEN SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
2. ALL MOUNTING DETAILS ARE REFERENCE FOR ALL FIXED DOME, 180°, 360°, PTZ, AND "BULLET/BOX" CAMERAS.





1 TYPICAL CAMERA INSTALLATION SECTION DETAIL
SCALE: NS




6 WALL MOUNTED CAMERA DETAIL
SCALE: NS




4 TILE BRIDGE DETAIL
SCALE: NS





5 CEILING MOUNTED CAMERA DETAIL
SCALE: NS


ACCESS CONROL DETAILS AND GENERAL NOTES:

1. CONDUIT ROUGH-IN IS A GUIDE FOR WHAT WILL BE REQUIRED FOR EACH DOOR. AS DOOR COMPONENTS CHANGE, EXACT CONDUIT LOCATION WILL ALSO NEED TO BE ADJUSTED.


2. PROTECT EXISTING-TO-REMAIN ACCESS CONTROL DEVICES AND CABLE THROUGHOUT RENOVATION WORK. IF CABLE AND/OR DEVICES ARE DAMAGED, SECURITY CONTRACTOR TO REPLACE WITH NEW.




1 ACCESS CONTROL - WIRING DETAIL - EXIT DEVICE W/ BUILT-IN REX
SCALE: NTS




2 ACCESS CONTROL - STEEL/HOLLOW METAL DOOR.
SCALE: NTS




KP PB LD

3 ROUGH-IN DETAILS: KP, PB, LD
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

t

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Sienna Crossing Elementary School
10011 Steep Bank Trce, Missouri City, TX 77459

SEAL

BICSI REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 384683
EXPIRES 12-31-27

07-18-25


MVA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING
AND
PERMITTING

TECHNOLOGY - Sienna Crossing ES - SECURITY DETAILS

t-TN.600

# FBISD BP013 KITCHEN RENOVATIONS ES

## SUGAR MILL ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD, SUGAR LAND, TX 77498

FORT BEND INDEPENDENT SCHOOL DISTRICT

FORT BEND INDEPENDENT SCHOOL DISTRICT

## ADMINISTRATION

| | |
|---|---|
| DR. MARCELL SMITH | SUPERINTENDENT OF FBISD |
| DR. ANDRIA SCHUR, Ed.D. | CHIEF OF SCHOOLS |

## BOARD OF TRUSTEES

| | |
|---|---|
| KRISTIN K. TASSIN | PRESIDENT |
| RICK GARCIA | VICE PRESIDENT |
| DAVID HAMILTON | SECRETARY |
| ANGIE HANAN | BOARD MEMBER |
| ADAM SCHOOF | BOARD MEMBER |
| DR. SHIRLEY ROSE-GILLIAM | BOARD MEMBER |
| SONYA JONES | BOARD MEMBER |

## PROJECT DESIGN TEAM


**PROGRAM MANAGEMENT**
FBISD 2023 Bond Team
2323 Texas Parkway
Missouri City, TX 77489
Phone Number: 281-327-5481

**ARCHITECT**
MWA Architects
11767 Katy Freeway, Suite 430
Houston, Texas 77079
Phone Number: 713-782-8188

**FOOD SERVICE**
Food Design Professionals
26215 Oak Ridge Drive
The Woodlands, Texas 77380
Phone Number: 281-350-2323

**MEP ENGINEERS**
Stanton Engineering Group
1300 W. Sam Houston Pkwy South, Suite 121
Houston, Texas 77042
Phone Number: 713-300-9292

**STRUCTURAL ENGINEER**
Stanley Spurling & Hamilton
3301 Edloe Street, Suite 200
Houston, Texas 77027
Phone Number: 713-776-9433


| Sheet List Table | |
|---|---|
| Sheet Number | Sheet Title |
| School: u-Sugar Mill ES | |
| u-A.000 | COVER AND INDEX |
| u-A00-01 | GENERAL NOTES AND ABBREVIATIONS |
| u-A.D.101 | DEMO PLAN |
| u-D.101-2 | REFERENCE PHOTOS FLOOR PLAN |
| u-D.101-3 | DEMO PLAN PHOTOS |
| u-ED.100 | ELECTRICAL DEMO AND TEMP PLANS |
| u-PD1.01 | PLUMBING DEMOLITION FLOOR PLAN |
| u-TD201 | TECHNOLOGY DEMOLITION FLOOR PLAN |
| u-A.101 | SITE PLAN |
| u-A.200 | SLAB DIMENSION CONTROL PLAN |
| u-A.201 | FLOOR PLAN |
| u-A.301 | KITCHEN PLAN |
| u-A.302 | TEMPORARY KITCHEN LAYOUT |
| u-A.401 | REFLECTED CEILING PLAN |
| u-A.501 | FINISH FLOOR PLAN |
| u-A.502 | PARTITION SCHEDULE |
| u-S1 | KITCHEN PLAN |
| u-S2 | SECTIONS AND TYPICAL DETAILS |
| u-C1.0 | GRADING & PAVING PLAN |
| u-QF1 | FS GENERAL COORDINATION NOTES |
| u-QF1.0 | FS EQUIPMENT PLAN |
| u-QF1.1 | FS FACILITY MODEL |
| u-QF1.2 | FS EQUIPMENT MODEL |
| u-QF1.3 | QF SPECIAL CONDITIONS & MECHANICAL PLAN |
| u-QF1.4 | FS PLUMBING PLAN |
| u-QF1.5 | FS ELECTRICAL PLAN |
| u-QF1.6 | FS CONDENSING UNITS |
| u-QF1.7 | FS WALK-INS |
| U-QF2.0 | FS TEMPORARY SERVING |
| u-M1.01 | MECHANICAL PLANS |
| M2.01 | KITCHEN MECHANICAL DETAILS |
| u-M2.02 | MECHANICAL DETAILS |
| E.000 | ELECTRICAL AND FIRE ALARM SCHEDULES |
| E.001 | ELECTRICAL AND FIRE ALARM NOTES |
| E.010 | ELECTRICAL DEVICE DETAILS |
| E.011 | ELECTRICAL DETAILS |
| E.012 | ELECTRICAL DETAILS |
| E.013 | ELECTRICAL KITCHEN DETAILS |
| E.060 | LIGHTING SCHEDULES |
| u-E.100 | LIGHTING FLOOR PLAN |
| u-E.200 | ELECTRICAL FLOOR PLAN |
| u-E.300 | FIRE ALARM FLOOR PLANS |
| u-E.400 | ELECTRICAL SCHEMATIC |
| u-P0.01 | PLUMBING NOTES AND SCHEDULES |
| u-P0.02 | PLUMBING SCHEDULES & DETAILS |
| u-P1.01 | PLUMBING FLOOR PLAN |
| u-P1.02 | PLUMBING FLOOR PLAN - TEMPORARY KITCHEN |
| u-T000 | TECHNOLOGY SYMBOLS & LEGEND |
| u-T200 | TECHNOLOGY COMPOSITE FLOOR PLAN |
| u-T201 | TECHNOLOGY NEW_RENOVATION KITCHEN PLAN |
| u-T202 | TECHNOLOGY TEMPORARY KITCHEN PLAN |
| u-T300 | TECHNOLOGY ENLARGED VIEWS |
| u-T400 | TECHNOLOGY TYPICAL DETAILS |
| u-T401 | TECHNOLOGY TYPICAL DETAILS |
| u-T500 | TECHNOLOGY TYPICAL DETAILS |
| u-TN-000 | TECHNOLOGY - INDEX SHEET |
| u-TN-001 | TECHNOLOGY - KITCHEN DEMOLITION |
| u-TN-100 | TECHNOLOGY - OVERALL |
| u-TN-101 | TECHNOLOGY - KITCHEN |
| u-TN-500 | TECHNOLOGY - DETAILS |
| u-TN-600 | TECHNOLOGY - SECURITY DETAILS |
| u-TN-700 | TECHNOLOGY - AV DETAILS |

REGISTERED ARCHITECT MIKE ANAGNOS 22651 STATE OF TEXAS

18 JULY 2025

ISSUED FOR PERMIT AND BIDDING - JULY 18, 2025

u

PART 1 - GENERAL

1.1 GENERAL DEMOLITION NOTES

A. VERIFY EXISTING SITE AND BUILDING CONDITIONS IN FIELD PRIOR TO BIDDING. NOTIFY ARCHITECT OF ANY DISCREPANCIES PRIOR TO BIDDING.

B. CONTRACTOR SHALL COORDINATE WITH OWNER THE SALVAGE OF ITEMS, FURNITURE AND EQUIPMENT INDICATED TO BE REMOVED.

C. CLAIMS FOR ADDITIONAL COST OR TIME DUE TO EXISTING CONDITIONS THAT COULD HAVE BEEN REASONABLY ANTICIPATED DURING A SITE VISIT BY THE CONTRACTOR PRIOR TO BIDDING WILL NOT BE APPROVED.

D. PROTECT EXISTING FINISHES SHOWN TO REMAIN DURING CONSTRUCTION TO PREVENT DAMAGE. REPAIR OR REPLACE DAMAGED MATERIALS AND FINISHES TO MATCH EXISTING AT NO ADDITIONAL COST TO FORT BEND ISD (OWNER).

E. EXISTING AREAS REQUIRING MINOR DEMOLITION OR REPAIR FOR EXECUTION OF WORK SHALL BE REPAIRED TO MATCH EXISTING ADJACENT MATERIALS, UNLESS NOTED OTHERWISE.

F. DO NOT DAMAGE CASEWORK AND EQUIPMENT NOT DESIGNATED TO BE REMOVED OR RELOCATED.EXISTING CASEWORK SHALL REMAIN THE PROPERTY OF THE OWNER.

G. CONTRACTOR TO VERIFY LOCATION OF ELEC. SWITCHES, OUTLETS, GRILLES, CLEAN-OUTS, COVER PLATES, ACCESS DOORS, AND OTHER EQUIPMENT AND DEVICES THAT MAY CONFLICT WITH THE RENOVATION AND NEW CONSTRUCTION OF WALLS, FLOORS, AND CEILINGS PRIOR TO COMMENCEMENT OF WORK. CONTRACTOR SHALL LIKEWISE CONFIRM THAT ELECTRICAL CONDUIT ROUTING SHALL BE CONCEALED WITHIN WALLS. NOTIFY ARCHITECT IF WALL THICKNESS WILL NOT ALLOW FOR CONCEALMENT.

H. REMOVE ANY EXISTING CORNER GUARDS IN THE KITCHEN AREA.

I. PRIOR TO EXECUTION OF DEMOLITION WORK, SCHEDULE A WALK-THROUGH WITH OWNER AND ARCHITECT TO CONFIRM SCOPE OF WORK AND TO REVIEW EXISTING CONDITIONS.

J. EXISTING FLOOR FINISHES AND ACOUSTIC CEILING TILE TO BE REMOVED THROUGHOUT.

K. REFER TO MEP DRAWINGS FOR DEMOLITION AND ALTERATION OF UTILITIES.

L. AT ALL EXISTING WALLS REQUIRING DEMOLITION TO INSTALL NEW PIPING BEHIND SINKS, CUT AND PATCH WALLS AS REQUIRED TO MATCH ADJACENT SURFACE.

M. CLEAN AND PREPARE SUBFLOOR FOR INSTALLATION OF NEW FLOOR FINISH.

N. DEMOLITION ACTIVITIES SHALL BE PERFORMED AS TO PRODUCE MINIMAL DISTURBANCE TO EXISTING FACILITY OCCUPANTS. MINIMIZE EXCESSIVE AND PROLONGED NOISE LEVELS AND DUST.

O. ASBESTOS-CONTAINING MATERIALS. REFER TO SPECIFICATION 02 26 23 FOR ASBESTOS INFORMATION APPLICABLE TO KITCHEN AREAS. FORT BEND ISD HAS RETAINED A SEPARATE ENVIRONMENTAL CONSULTANT FOR THE REMOVAL OF ASBESTOS. GC TO COORDINATE WITH ENVIRONMENTAL CONSULTANT TO CARRY OUT ASBESTOS ABATEMENT FOR ALL AFFECTED KITCHEN AREAS.

1.2 FLOOR PLAN GENERAL NOTES

A. FIELD VERIFY EXISTING CONDITIONS PRIOR TO GENERATING SHOP DRAWINGS AND FABRICATION OF EQUIPMENT.

B. FLOOR FINISH CHANGES SHALL OCCUR AT THE CENTERLINE OF DOORS UNLESS NOTED OTHERWISE. FLOOR FINISH CHANGES SHALL HAVE THRESHOLDS OR REDUCERS STRIPS.

C. DOORS THAT ARE TO BE REPLACED AND INSTALLED IN EXISTING FRAMES SHALL BE MACHINED FOR HARDWARE DIMENSIONS AT EXISTING FRAMES, CONTRACTOR SHALL FIELD VERIFY FRAME CONDITIONS AND DIMENSIONS.

D. CONTRACTOR TO PROVIDE SHEET METAL REINFORCING STRAP AS REQUIRED FOR MOUNTING OF ALL GRAB BARS, CABINETS, MIRRORS, SHELVING, ETC.

E. SAW CUT AND REMOVE EXISTING SLAB AND FLOOR FINISHES AS REQUIRED TO INSTALL NEW PLUMBING LINES, FLOOR DRAINS, PLUMBING FIXTURES, OR ELECTRICAL ITEMS. SPLICE NEW REINFORCING BARS DOWELED INTO EXISTING CONCRETE, AND PROVIDE NEW VAPOR RETARDER AND WATERSTOPS, AND PATCH W/ 3000 PSI CONCRETE AFTER INSTALLATION OF UTILITIES AND FIXTURES. PREPARE CONCRETE TO RECEIVE NEW FINISH.

F. COORDINATE HOUSEKEEPING PAD DIMENSIONS AND LOCATIONS WITH EQUIPMENT TO BE INSTALLED. HOUSEKEEPING PADS SHALL BE A MIN. OF 4" THICK REINF. W/ #3 BARS AT 15" O.C. BOTH WAYS. PROVIDE 1" BY 45-DEGREE CHAMFERED EDGES.

1.3 COMPLETE PERFORMANCE

L. THE CONTRACTOR SHALL FURNISH AND INSTALL ALL ITEMS SPECIFIED HEREIN AND AS INDICATED ON THE DRAWINGS. THE CONTRACTOR SHALL ALSO FURNISH AND INSTALL ALL ITEMS NECESSARY TO MAKE THE SYSTEMS FUNCTION WHICH MAY BE REASONABLY IMPLIED AS ESSENTIAL, WHETHER MENTIONED IN THE CONTRACT DOCUMENTS OR NOT.

M. WORK SHALL BE EXECUTED IN STRICT ACCORDANCE WITH THE BEST PRACTICE OF THE TRADES IN A THOROUGH, SUBSTANTIAL AND WORKMANLIKE MANNER BY COMPETENT WORKMEN.

1.4 SITE FAMILIARIZATION

A. GENERAL: BECOME FAMILIAR WITH THE DRAWINGS AND SPECIFICATIONS, EXAMINE THE PREMISES, AND UNDERSTAND THE CONDITIONS UNDER WHICH THE CONTRACT SHALL BE PERFORMED, PRIOR TO SUBMITTING A BID.

B. SITE: BE INFORMED OF THE SITE CONDITIONS, VERIFY LOCATIONS OF NEW AND EXISTING EQUIPMENT, AND DETERMINE EXACT REQUIREMENTS FOR CONNECTIONS.

C. COORDINATION: TENDER OF A PROPOSAL FOR THIS PROJECT INFERS THAT THE CONTRACTOR HAS VISITED THE SITE AND HAS BECOME FAMILIAR WITH THE DRAWINGS, SPECIFICATIONS, AND SITE CONDITIONS AND HAS INCLUDED IN HIS PROPOSAL ALL WORK NECESSARY TO PROPERLY INSTALL COMPLETE AND FUNCTIONING SYSTEMS ON THE PROJECT. FAILURE TO COMPLY WITH THIS REQUIREMENT SHALL NOT BE CONSIDERED JUSTIFICATION FOR THE OMISSION OR FAULTY INSTALLATION OF ANY WORK COVERED BY THE CONTRACT DOCUMENTS.

1.5 CODES AND STANDARDS

A. GENERAL: ALL WORK SHALL COMPLY WITH THE MOST RECENTLY REVISED VERSIONS OF ALL APPLICABLE LAWS, RULES, REGULATIONS AND ORDINANCES OF ALL FEDERAL, STATE AND LOCAL AUTHORITIES AND APPLICABLE UTILITIES. NONE OF THE TERMS OR PROVISIONS OF THIS SPECIFICATION SHALL BE CONSTRUED AS WAIVING ANY PART OF THE LAWS, RULES, REGULATIONS OR REQUIREMENTS OF THESE AUTHORITIES.

B. CONFLICT: IN THE EVENT OF CONFLICT BETWEEN THE CONTRACT DOCUMENTS AND THE LOCAL ENFORCING AUTHORITY, THE LATTER SHALL RULE. ANY MODIFICATIONS RESULTING THEREFROM SHALL BE MADE WITHOUT ANY ADDITIONAL COST TO THE OWNER OR ARCHITECT. THIS CONTRACTOR SHALL REPORT ANY SUCH MODIFICATIONS TO THE ARCHITECT AND SECURE HIS APPROVAL PRIOR TO PROCEEDING WITH THE WORK.

C. PRECEDENCE: WHERE CONTRACT DOCUMENT REQUIREMENTS EXCEED THE REQUIREMENTS OF THE CODES AND STANDARDS, THE CONTRACT DOCUMENTS SHALL TAKE PRECEDENCE PROVIDED THEY ARE NOT IN CONFLICT WITH THOSE CODES AND STANDARDS.

D. APPROVAL LABELS: ALL ITEMS OF EQUIPMENT AND ALL MATERIALS FOR WHICH APPROVED STANDARDS HAVE BEEN ESTABLISHED BY UNDERWRITERS' LABORATORIES, INC. (UL), FACTORY MUTUAL (FM), CERTIFIED BALLAST MANUFACTURER (CBM), ELECTRICAL TESTING LABORATORY (ETL), NATIONAL MANUFACTURERS ASSOCIATION (NEMA), AMERICAN STANDARD CODES, ASME, AGA, AMCA, ASA, ANSI, ASHRAE, AND ARI SHALL BE SO APPROVED AND SHALL BEAR APPROVAL LABELS ATTESTING TO SAME.

1.6 DRAWINGS AND SPECIFICATIONS

A. DRAWINGS: THE SET OF ORIGINAL DRAWINGS HAS BEEN MODIFIED AND INDICATE APPROXIMATE EXISTING LOCATIONS OF THE FLOOR FINISH ITEMS. ALL ITEMS ARE SHOWN APPROXIMATELY TO SCALE. FIELD VERIFY CONDITIONS.

B. SPECIFICATIONS: THE SPECIFICATIONS ARE INTENDED TO SUPPLEMENT THE DRAWINGS AND IT IS NOT IN THE SCOPE OF THE SPECIFICATIONS TO MENTION ANY PART OF THE WORK THAT THE DRAWINGS ARE COMPETENT TO FULLY EXPLAIN. CONVERSELY, ANY PART OF THE WORK THAT THE SPECIFICATIONS ARE COMPETENT TO FULLY EXPLAIN MAY NOT BE MENTIONED ON THE DRAWINGS. DRAWINGS AND SPECIFICATIONS ARE COMPLIMENTARY/SUPPLEMENTARY DOCUMENTS TO EACH OTHER.

C. DISAGREEMENT: DISAGREEMENT BETWEEN THE DRAWINGS AND SPECIFICATIONS OR WITHIN THE DRAWINGS OR SPECIFICATIONS SHALL BE ESTIMATED AND/OR BID USING THE BETTER QUALITY OR GREATER QUANTITY OF MATERIAL OR INSTALLATION, AND A CLARIFICATION REQUEST FOR INFORMATION SHALL BE MADE TO THE ARCHITECT IN A TIMELY MANNER AFTER THE PROJECT IS UNDER CONTRACT.

1.7 DISCREPANCIES

A. CLARIFICATION: CLARIFICATION OF SIGNIFICANT COST MATTERS SHALL BE OBTAINED BEFORE SUBMITTING A PROPOSAL FOR THE WORK AS TO DISCREPANCIES OR OMISSIONS FROM THE CONTRACT DOCUMENTS OR QUESTIONS AS TO THE INTENT THEREOF.

B. INTERPRETATIONS: SHOULD ANY DOUBT OR QUESTION ARISE RESPECTING THE TRUE MEANING OF DRAWINGS OR SPECIFICATIONS, REFERENCE SHALL BE MADE TO THE ARCHITECT, WHOSE WRITTEN DECISION SHALL BE FINAL AND CONCLUSIVE. NO ALLEGED STATEMENT BY THE ARCHITECT WILL BE ACCEPTED AS AN EXCUSE FOR NON-COMPLIANCE OR INFERIOR WORK.

C. CONTRACTOR AGREEMENT: CONSIDERATION WILL NOT BE GRANTED FOR MISUNDERSTANDING OF THE AMOUNT OF WORK TO BE PERFORMED. TENDER OF A PROPOSAL CONVEYS FULL CONTRACTOR AGREEMENT OF THE ITEMS AND CONDITIONS SPECIFIED, SHOWN, SCHEDULED, OR REQUIRED BY THE NATURE OF THE PROJECT, AND ALL COSTS ARE INCLUDED IN THE PROPOSAL.

1.8 REQUESTS FOR INFORMATION (RFI)

A. GENERAL: SUBMIT ALL CONTRACTOR REQUESTS FOR INFORMATION (RFI) IN WRITING TO THE ARCHITECT FOR RESPONSE. SUBMIT RFI ON A STANDARD FORM THAT HAS A SPACE FOR THE REQUESTED INFORMATION AND THE ARCHITECT'S RESPONSE.

B. SOLUTION PROPOSAL: IN GENERAL, THE CONTRACTOR SHALL PROPOSE SOLUTIONS TO IDENTIFY PROBLEMS FOR REVIEW AND APPROVAL OF THE ARCHITECT. THE RFI SHALL INCLUDE HAND SKETCHES, MARKED DRAWING PRINTS, EQUIPMENT CUTSHEETS, DRAWING AND SPECIFICATION REFERENCES, AND ANY OTHER BACK-UP INFORMATION, ETC., AS REQUIRED TO SUFFICIENTLY EXPLAIN THE PROBLEM AND PROPOSED SOLUTION.

1.9 QUALITY ASSURANCE

A. GENERAL: MATERIALS AND EQUIPMENT SHALL BE NEW, OF BEST GRADE AND QUALITY, AND STANDARD PRODUCTS OF REPUTABLE MANUFACTURERS REGULARLY ENGAGED IN THE PRODUCTION OF SUCH MATERIALS AND EQUIPMENT.

B. WORKMANSHIP: WORK SHALL BE EXECUTED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE BEST PRACTICE OF THE TRADES IN A THOROUGH, SUBSTANTIAL, WORKMANLIKE MANNER BY COMPETENT WORKMEN, PRESENTING A NEAT APPEARANCE WHEN COMPLETED.

C. JUDGMENT: IN ALL CASES, THE ARCHITECT SHALL BE THE SOLE JUDGE OF THE QUALITY AND EQUIVALENCE OF MANUFACTURERS, PRODUCTS, MATERIALS, AND METHODS.

D. MANUFACTURERS/PRODUCTS/MATERIALS/METHODS: MANUFACTURERS, PRODUCTS, MATERIALS, AND METHODS DESCRIBED IN THE VARIOUS SECTIONS OF THE SPECIFICATIONS AND INDICATED ON THE DRAWINGS ARE INTENDED TO ESTABLISH A STANDARD OF QUALITY ONLY. IT IS NOT THE INTENTION OF THE ARCHITECT TO DISCRIMINATE AGAINST ANY MANUFACTURER, PRODUCT, MATERIAL, OR METHOD THAT IS EQUAL TO THE STANDARDS AS INDICATED AND/OR SPECIFIED, NOR IS IT INTENDED TO PRECLUDE OPEN, COMPETITIVE BIDDING. THE FACT THAT A SPECIFIC MANUFACTURER IS LISTED AS AN ACCEPTABLE MANUFACTURER SHALL NOT BE INTERPRETED TO MEAN THAT THE MANUFACTURER'S STANDARD PRODUCT WILL MEET THE REQUIREMENTS OF THE PROJECT DESIGN, SPECIFICATIONS, AND SPACE CONSTRAINTS.

1. WHEREVER A DEFINITE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS SPECIFIED AND THERE IS NOT A STATEMENT THAT ANOTHER MANUFACTURER, PRODUCT, MATERIAL, OR METHOD WILL BE ACCEPTABLE, IT IS THE INTENTION OF THE ARCHITECT THAT THE SPECIFIED MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS THE ONLY ONE THAT SHALL BE USED WITHOUT PRIOR APPROVAL.
2. WHEREVER A DEFINITE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS SPECIFIED AS "NO SUBSTITUTE", IT IS THE INTENTION OF THE ARCHITECT THAT THE LISTED ITEM IS THE ONLY ONE ACCEPTABLE.

E. COORDINATION: WHERE EQUIPMENT IS USED ON THE PROJECT, IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR OR SUBCONTRACTOR INVOLVED TO VERIFY THAT THE EQUIPMENT WILL FIT IN THE SPACE AVAILABLE, INCLUDING ALL REQUIRED CODE AND MAINTENANCE CLEARANCES, AND TO COORDINATE ALL EQUIPMENT REQUIREMENTS AND PROVISIONS WITH THE SYSTEM DESIGN, ALL AFFECTED DIVISIONS, AND ALL OTHER CONTRACTORS. WHERE THE USE OF ALTERNATE OR SUBSTITUTE MATERIALS AFFECTS THE COST OF PROVISIONS MADE BY OTHER CONTRACTORS, THE CONTRACTOR PROVIDING THE ALTERNATE OR SUBSTITUTE SHALL BE RESPONSIBLE FOR THE OTHER CONTRACTOR'S COST ADJUSTMENT. THERE SHALL BE NO ADDITIONAL COST TO THE OWNER OR ARCHITECT DUE TO THE USE OR ACCEPTANCE OF ANY ALTERNATE OR SUBSTITUTE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD.

1.10 PRIOR APPROVAL

A. SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES: THE CONTRACTOR'S SUBMITTAL AND ARCHITECT'S ACCEPTANCE OF SHOP DRAWINGS, PRODUCT DATA, OR SAMPLES THAT RELATE TO CONSTRUCTION ACTIVITIES NOT COMPLYING WITH THE CONTRACT DOCUMENTS DOES NOT CONSTITUTE AN ACCEPTABLE OR VALID REQUEST FOR SUBSTITUTION, NOR DOES IT CONSTITUTE APPROVAL.

1.11 COORDINATION

A. BY SUBMITTING SHOP DRAWINGS ON THE PROJECT, THIS CONTRACTOR IS INDICATING THAT ALL NECESSARY COORDINATION HAS BEEN COMPLETED AND THAT THE SYSTEMS, PRODUCTS AND EQUIPMENT SUBMITTED CAN BE INSTALLED IN THE BUILDING AND WILL OPERATE AS SPECIFIED AND INTENDED, IN FULL COORDINATION WITH ALL OTHER DISCIPLINES.

1.12 SHOP DRAWINGS AND SUBMITTALS

A. GENERAL: AFTER THE CONTRACT IS AWARDED BUT PRIOR TO PROCEEDING WITH THE WORK REQUIRING SHOP DRAWING REVIEW, THE CONTRACTOR SHALL OBTAIN COMPLETE SHOP DRAWINGS AND PRODUCT DATA FROM THE MANUFACTURERS, SUPPLIERS, VENDORS, AND SUB- CONTRACTORS FOR ALL MATERIALS AND EQUIPMENT SPECIFIED HEREIN, AND MAKE FORMAL SUBMISSION TO THE ARCHITECT. A MINIMUM PERIOD OF TWO (2) WEEKS SHOULD BE ALLOWED IN THE CONSTRUCTION SCHEDULE EXCLUSIVE OF TRAVEL TIME FOR THE ARCHITECTS REVIEW.

B. CERTIFICATION: EACH CONTRACTOR RESPONSIBLE FOR THE WORK SHALL REVIEW AND CERTIFY THE SHOP DRAWING, SUBMITTAL AND/OR PRODUCT DATA TO BE IN FULL COMPLIANCE WITH THE REQUIREMENTS OF THE CONTRACT DOCUMENTS.

C. THE ARCHITECTS REVIEW OF SHOP DRAWINGS AND SUBMITTAL DATA SHALL NOT RELIEVE THE CONTRACTOR OF THE RESPONSIBILITY FOR DIMENSIONS OR ERRORS THAT MAY BE CONTAINED THEREIN, OR FOR DEVIATIONS FROM ANY REQUIREMENTS OF THE CONTRACT DOCUMENTS. IT SHALL BE CLEARLY UNDERSTOOD THAT THE ARCHITECTS NOTING SOME ERRORS BUT OVERLOOKING SOME OTHERS DOES NOT GRANT THE CONTRACTOR PERMISSION TO PROCEED IN ERROR. REGARDLESS OF ANY INFORMATION CONTAINED IN THE SHOP DRAWING OR PRODUCT DATA, THE CONTRACT DOCUMENTS SHALL GOVERN THE WORK AND ARE NEITHER WAIVED NOR SUPERSEDED IN ANY WAY BY THE REVIEW OF SHOP DRAWINGS, PRODUCT DATA AND SAMPLES.

1.13 EXECUTION AND COORDINATION OF WORK

A. MANUFACTURER'S RECOMMENDATIONS: WITH EXCEPTIONS AS SPECIFIED AND/OR INDICATED ON THE DRAWINGS OR IN THE SPECIFICATIONS, APPLY, INSTALL, ERECT, USE, CLEAN, AND CONDITION, MANUFACTURED ARTICLES, MATERIALS, AND EQUIPMENT PER MANUFACTURER'S CURRENT PRINTED RECOMMENDATIONS. KEEP COPIES OF SUCH PRINTED RECOMMENDATIONS AT JOB SITE AND MAKE THEM AVAILABLE AS REQUIRED.

1.14 SUPERVISION

A. A COMPETENT SUPERINTENDENT APPROVED BY THE ARCHITECT, SHALL BE KEPT BY THE CONTRACTOR AT THE BUILDING TO RECEIVE INSTRUCTIONS AND TO ACT FOR THE CONTRACTOR. ONCE THE SUPERINTENDENT HAS BEEN APPROVED, NO CHANGE SHALL BE MADE WITHOUT APPROVAL OF ARCHITECT. REPRESENTATIVES OF THE OWNER, ARCHITECT SHALL HAVE THE RIGHT TO OBSERVE THE WORK AT ANY TIME. THE CONTRACTOR SHALL HAVE A REPRESENTATIVE AVAILABLE WHEN HIS WORK IS BEING OBSERVED AND HE SHALL GIVE ASSISTANCE AS MAY BE REQUIRED TO THE ARCHITECT'S REPRESENTATIVE.

B. THE PROJECT SHALL BE CONSTRUCTED BY EMPLOYEES OF THE CONTRACTOR OR BY WORKERS UNDER HIS SUPERVISION. ANY SUBCONTRACTORS EMPLOYED BY THE CONTRACTOR SHALL BE APPROVED BY THE OWNER'S REPRESENTATIVE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL EQUIPMENT, MATERIAL AND WORK PERFORMED BY ANY SUBCONTRACTOR.

1.15 STORAGE AND PROTECTION OF MATERIALS

A. THE CONTRACTOR SHALL PROPERLY STORE ALL MATERIAL AND EQUIPMENT AT THE JOBSITE AND PROTECT IT FROM THE ELEMENTS AND FROM DAMAGE. ANY EQUIPMENT DAMAGED DUE TO IMPROPER PROTECTION SHALL BE REPLACED BY THE CONTRACTOR AT HIS EXPENSE.

B. THE CONTRACTOR SHALL PROTECT THE WORK, EQUIPMENT, AND MATERIAL OF ALL OTHER TRADES FROM DAMAGE BY HIS WORK OR OTHER WORKMEN, AND SHALL MAKE GOOD ALL DAMAGE THUS CAUSED.

C. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL WORK, MATERIALS, AND EQUIPMENT UNTIL FINALLY INSPECTED, TESTED, AND ACCEPTED; PROTECT WORK AGAINST THEFT, INJURY OR DAMAGE; AND CAREFULLY STORE MATERIAL AND EQUIPMENT RECEIVED ON SITE WHICH ARE NOT IMMEDIATELY INSTALLED. CLOSE OPEN ENDS OF WORK WITH TEMPORARY COVERS OR PLUGS DURING CONSTRUCTION TO PREVENT ENTRY OF OBSTRUCTING MATERIAL. THE CONTRACTOR SHALL COVER AND PROTECT IN AN ACCEPTABLE MANNER TO THE OWNER, EXISTING REMAINING EQUIPMENT AND MATERIALS.

D. IF ANY MATERIAL OR EQUIPMENT IS RECEIVED PRIOR TO THE TIME IT IS REQUIRED, THE CONTRACTOR SHALL BE RESPONSIBLE FOR ITS PROPER STORAGE AND PROTECTION UNTIL SUCH TIME AS IT MAY BE REQUIRED. THE CONTRACTOR SHALL PAY FOR ALL COSTS OF DEMURRAGE OR STORAGE.

1.16 DRAYAGE AND HAULING


A. THE CONTRACTOR SHALL KEEP THE JOBSITE FREE FROM THE ACCUMULATION OF TRASH AND CONSTRUCTION DEBRIS, REGARDLESS OF WHICH SUBCONTRACTOR MAY BE RESPONSIBLE.

1.17 CUTTING AND PATCHING


A. WHERE IT BECOMES NECESSARY TO CUT THROUGH ANY WALL, FLOOR OR CEILING TO PERMIT THE INSTALLATION OF ANY WORK, OR TO REPAIR ANY DEFECTS THAT MAY APPEAR, THE CUTTING SHALL BE PERFORMED UNDER THE SUPERVISION OF THE GENERAL CONTRACTOR. INFORM THE OWNER'S REPRESENTATIVE BEFORE ANY WORK COMMENCES. NO STRUCTURAL MEMBER SHALL BE ALTERED WITHOUT THE WRITTEN PERMISSION OF THE ARCHITECT.

B. VERIFICATION: SHOULD A QUESTION ARISE REGARDING THE ACCEPTABLE LEVEL OF NOISE OR VIBRATION IN A PARTICULAR SPACE OR PIECE OF EQUIPMENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING THE SERVICES OF AN APPROVED ACOUSTICAL CONSULTANT TO DETERMINE ACTUAL NOISE/VIBRATION CONDITIONS.


## 01 GENERAL NOTES





## 21 EXTERIOR DOOR SILL
SCALE: 6" = 1'-0" XREF





## 22 DOOR JAMB
SCALE: 6" = 1'-0" XREF





## 23 WINDOW HEAD
SCALE: 6" = 1'-0" XREF





## 24 DOOR WINDOW HEAD
SCALE: 6" = 1'-0" XREF




## 15 WINDOW JAMB AT WALL
SCALE: ################





## 16 DOOR HEAD
SCALE: 6" = 1'-0" XREF





## 17 WINDOW SILL
SCALE: 6" = 1'-0" XREF





## 18 DOOR SILL
SCALE: 6" = 1'-0" XREF





## 09 WINDOW CORNER
SCALE: ################




## 10 DOOR STRIKE JAMB
SCALE: ################





## 11 DOOR HINGE JAMB
SCALE: ################





## 12 WINDOW MULLION
SCALE: ################

| | |
|---|---|
| SEQUENCE OF CONSTRUCTION (AS OF 01/27/2025). Schools will be renovated in groups as shown. These groups contain two or three major kitchen renovations and some cafeteria/miscellaneous renovations. This sequencing is critical for FBISD food service to provide the uninterrupted meal services to their schools. | |
| GROUPING 1 | AUSTIN PARKWAY ES + SUGAR MILL ES, kitchen renovations. *Plus: COMMON WEALTH ES, CONERSTONE ES misc. renovations.* |
| GROUPING 2 | SETTLERS WAY ES + PALMER ES kitchen renovations. *Plus: SULLIVAN ES, SIENNA CROSSING ES, HERITAGE ROSE ES misc. renovations* |
| GROUPING 3 | HUNTER'S GLEN ES + HIGHLANDS ES + PECAN GROVE ES kitchen renovations. *Plus: RIDGEGATE ES, DULLES ES misc. renovations.* |

## 03 PROJECT SCHEDULE




## 04 EXTERIOR DOOR HEAD JAMB
SCALE: 6" = 1'-0" XREF




## 06 WINDOW JAMB
SCALE: 6" = 1'-0" XREF

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

u

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILLS ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD
SUGAR LAND, TX 77498

SEAL
REGISTERED ARCHITECT
NOLAN WILSON
23953
STATE OF TEXAS
7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

GENERAL NOTES AND ABBREVIATIONS

A00-01

## GENERAL DEMOLITION NOTES
(NOT ALL NOTES USED ON EACH SHEET)

1. REFER TO SHEET A00-01 FOR DEMOLITION GENERAL NOTES. THESE NOTES APPLY TO ALL SCHOOL KITCHENS.
2. COORDINATE EXTENT OF SAW CUTTING AREAS WITH NEW RECESSED SLAB FOR COOLER/FREEZER LAYOUTS, NEW SERVICE ENTRANCE FLOOR AND EXISTING KITCHEN LAYOUTS THAT REMAIN. SEE STRUCTURAL DRAWINGS AND SLAB DIMENSION CONTROL PLANS FOR ADDITIONAL SCOPE.
3. REMOVE PROTECT AND REINSTALL ALL EXISTING SURFACE MOUNTED FIRE EXTINGUISHERS (TYPES ABC AND K) AT ALL KITCHENS.
4. SAWCUT AND RE-LOCATE EXPOSED CONDUITS AND WIREMOLD TO INSIDE OF WALLS. PATCH AND PAINT. EXCEPTION: WAREWASH AREA BELOW TABLE HEIGHT AND DRY STORAGE ROOMS.
5. CONTRACTOR TO RELOCATE EXISTING KITCHEN EQUIPMENT AND OFFICE FURNITURE TO TEMPORARY KITCHEN LAYOUT AS REQUESTED BY KITCHEN MANAGER. ALSO THAT THE IT EQUIPMENT IS PROTECTED DURING RENOVATIONS. ALL EXISTING EQUIPMENT SHALL BE RETURNED TO OWNER.
6. EXISTING TACKBOARDS TO BE REMOVED BY OWNER.
7. IF PRESENT, EXISTING SAFE IN EACH KITCHEN TO BE TEMPORARILY REMOVED DURING RENOVATION AND REINSTALLED IN KITCHEN AREA.
8. ORIGIN POINT OF EXISTING CEILING GRID SHALL BE IDENTIFIED. NEW CEILING WILL BE INSTALLED (AS MUCH AS POSSIBLE) AT THE SAME ORIGIN POINT SO THAT SPRINKLER SYSTEM PIPING CAN REMAIN UNCHANGED.
9. ABOVE-CEILING INFRASTRUCTURE SHALL REMAIN UNDISTURBED AS MUCH AS IS POSSIBLE. CEILING DEVICES ARE TO BE REMOVED FROM EXISTING GRID/TILE THEN DURING RE-INSTALATION OF CEILING DEVICES SHALL BE LOCATED AS CLOSE TO ORIGINAL LOCATION AS POSSIBLE INTO THE NEW GRID/TILE. PROTECT AND STORE EXISTING INFRASTRUCTURE (CABLING, ELECTRICAL POWER, PIPING) DURING CONSTRUCTION.
10. EXISTING HOOD IN WAREWASH AND (2) HOODS IN PRODUCTION AREA ARE TO BE CLEANED, INSPECTED, SERVICED AND REFURBISHED TO A LIKE NEW CONDITION. THEY ARE TO REMAIN IN PLACE.

## KEYED DEMOLITION NOTES
(NOT ALL NOTES USED ON EACH SHEET)

1. REMOVE EXISTING THINSET SYNTHETIC TERRAZZO FLOOR AND TERRAZZO COVE BASE MATERIAL IF ANY EXISTS THROUGHTOUT KITCHEN AREA. CLEAN AND PREPARE SUBFLOOR TO RECEIVE NEW FLOOR. RE: FINISH PLAN FOR NEW FLOOR FINISH MATERIAL.
2. REMOVE EXISTING QUARRY TILE FLOORING AND BASE. CLEAN AND PREPARE SUBFLOOR TO RECEIVE NEW FLOORING. RE: FINISH SCHEDULE FOR NEW FLOOR FINISH MATERIAL.
3. CEILING DEVICES: REMOVE SMOKE DETECTORS, STROBES, EXIT SIGNAGE, MOTION DETECTORS AND CEILING SPEAKERS. PROTECT AND RE-INSTALL AFTER FINISHES ARE APPLIED.
4. REMOVE EXISTING LOCKERS. PROTECT AND RE-INSTALL AFTER FINISHES APPLIED.
5. REMOVE EXISTING WASHER AND DRYER. VERIFY WITH FBISD FOR RELOCATION TO WAREHOUSE.
6. TEMPORARILY REMOVE EXISTING WALL MOUNTED CLOCK AND STORE FOR REINSTALLATION AFTER WALL RECEIVED NEW FINSH.
7. REMOVE EXISTING WALK-IN COOLER/FREEZER AND CONDENSING UNIT LOCATED IN ADJACENT SPACE. MITIGATE ANY MOLD FOUND.
8. REMOVE EXISTING DOOR AND PROTECT EXISTING FRAME TO REMAIN
9. REMOVE EXISTING DOOR AND FRAME, PROTECT FRAME AND OR DOOR IF IT IS SCHEDULED TO REMAIN.
10. REMOVE PARTIAL EXISTING CMU PARTITION FOR NEW DOOR OPENING
11. INSPECT EXISTING WAREWASH COUNTER DOOR AND S.S. PASS-THRU WINDOW CHUTE. REPAIR REPLACE DAMAGED COMPONENTS. CLEAN, LUBRICATE AND RE-INSTALL.
12. EXISTING CARD READER ACCESS TO REMAIN
13. EXISTING WINDOW TO REMAIN
14. REMOVE EXISTING KITCHEN EQUIPMENT THROUGHOUT KITCHEN INCLUDING WALK-IN COOLER / FREEZER AND CONDENSING UNIT LOCATED IN ADJACENT ROOM OR OUTSIDE OF THE BUILDING. VERIFY WITH OWNER FOR RELOCATION TO WAREHOUSE. SOME EQUIPMENT IS TO BE RE-USED IN TEMPORARY SERVING LINES. SEE ALSO GENERAL DEMOLITION NOTE 6.
15. REMOVE EXISTING FRP AND PREP FOR NEW TILE FINISH.
16. COORDINATE REMOVAL AND STORAGE OF ANY EXISTING FURNITURE ITEMS WITH OWNER. SEE ALSO GENERAL DEMOLITION NOTE 5.
17. REMOVE EXISTING SOAP AND PAPER TOWEL DISPENSER AND RETURN TO OWNER
18. EXISTING WALL MOUNTED ACCESSORIES SIGNS, DISPLAY BOARDS, AND MATS TO BE REMOVED BY FORT BEND ISD (VERIFY EQUIPMENT - IF ANY).
19. REMOVE EXISTING SURFACE MOUNTED FIRE EXTINGUISHER. RE-INSTALL AFTER NEW FINISH APPLIED.
20. REMOVE EXISTING ACOUSTIC CEILING TILE CEILNG SYSTEM AND LIGHT FIXTURES, HVAC DEVICES, SENSORS, ETC. THROUGHTOUT RENOVATED AREAS. PREP FOR NEW SUSPENDED CEILING. EXISTING SPRINKLE SYSTEM TO REMAIN AS-IS UNLESS ROOM CONFIGURATION HAS CHANGED IN NEW DESIGN. PROTECT RECESSED SPRINKLER HEADS AND - RE-INSTALL IN NEW CEILING.
21. REMOVE EXISTING CASEWORK/SHELVING
22. EXISTING CERAMIC WALL TILE TO REMAIN. PROTECT FROM DAMAAGE.
23. REMOVE EXISTING COAT HANGER / ROD / SHELF
24. REMOVE EXISTING PLUMBING FIXTURES IN RESTROOMS. RE: PLUMBING FOR NEW FIXTURES.
25. REMOVE EXISTING UTILITY SINK. RE: PLUMBING FOR NEW PLUMBING FIXTURES.
26. REMOVE EXISTING MOP HOLDER. REPLACE WITH NEW UNIT AS SPECIFIED.
27. REMOVE EXISTING WALL MOUNTED CLEANING SOLUTION DISPENSER (BY FBISD VENDOR)
28. HOOD TO REMAIN - SEE GENERAL DEMOLITION NOTE 10.
29. HOOD TO REMAIN - SEE GENERAL DEMOLITION NOTE 10.
30. REMOVE FLOORING IN THIS AREA FOR NOTE 1.
31. REMOVE CARTIDGE FILTER AND WATER PURTICATION CABNET


## DEMOLITION LEGEND

- EXISTING PARTITION TO REMAIN
- REMOVE EXISTING PARTITION
- EXISTING CMU PARTITION
- REMOVE DOOR AND FRAME TO REMAIN
- REMOVE EXISTING DOOR AND FRAME
- EXISTING PLUMBING FIXTURES (WATER CLOSET, HAND LAVATORY, AND MOP SINK TO BE REMOVED. RE: PLUMBING DRAWINGS.
- EXISTING ACOUSTIC CEILING TILE AND GRID TO BE REMOVED. RE: ELECTRICAL DRAWINGS.
- SPRINKLER HEAD (RECESSED)
- CLOCK
- CEILING MOUNTED SPEAKERS


# 3 DEMOLITION NOTES

## OLD FLOOR LEGEND

OLD QUARRY TILE
(1,562 SF)




1 DEMOLITION FLOOR PLAN
SCALE: 1/4" = 1'-0"




2 DEMOLITION REFLECTED CEILING PLAN
SCALE: 1/4" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

u

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT

SUGAR MILLS ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD
SUGAR LAND, TX 77498

SEAL
REGISTERED ARCHITECT
MICHAEL W. ANDERSON
22651
STATE OF TEXAS
7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

DEMO PLAN

u-D.101

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\U-Sugar Mill ESIu-A D.101 DEMO PLAN.dwg Jul 23, 2025 - 4:57pm


PHOTO D1


PHOTO D2




PHOTO D3




PHOTO D4



PHOTO D5




PHOTO D6



PHOTO D7


PHOTO D8



PHOTO D9



PHOTO D10



PHOTO D11



PHOTO D12




PHOTO D13



PHOTO D14



PHOTO D15




PHOTO D16




PHOTO D17



PHOTO D18



PHOTO D19



PHOTO D20

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

u

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILL ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD,
SUGAR LAND, TX 77498

SEAL

REGISTERED ARCHITECT
ROBERT M. WEIR
22601
STATE OF TEXAS

7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
DEMO PLAN PHOTOS
u-D.101-2

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\U-Sugar Mill ES\u-D.101-2 REFERENCE PHOTOS FLOOR PLAN.dwg Jul 23, 2025 - 4:57pm




PHOTO D21



PHOTO D22




PHOTO D23


PHOTO D24




PHOTO D25



PHOTO D26



PHOTO D27



PHOTO D28




PHOTO D29


PHOTO D30

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\U-Sugar Mill ES\u-D.101-3 DEMO PLAN PHOTOS.dwg Jul 23, 2025 - 4:57pm

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

u

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILL ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD,
SUGAR LAND, TX 77498

SEAL

REGISTERED ARCHITECT
ROY A. MENDOZA
23651
STATE OF TEXAS

7/15/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

DEMO PLAN PHOTOS

u-D.101-3

## NEW PANEL

## TEMP KITCHEN

**PANEL LTK**


150A MCB
208Y/120V, 3ϕ, 4 WIRE

AVAILABLE FAULT: <10,000A
SCCR & AIC: 10,000A

MOUNTING: SURFACE


| NOTES | EQUIP. NO. | LOAD | DESCRIPTION | WIRE | CB | CKT | A | B | C | CKT | CB | WIRE | DESCRIPTION | LOAD | EQUIP. NO. | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E810 | 2766 | HOT WELLS | 2–12 | 20/2GFI | 1 | ■ | | | 2 | 20/1 | 3–12 | TRANSPORT CART | 1920 | E806 | |
| | | – | – | +12G | – | 3 | | ■ | | 4 | 20/1 | 3–12 | TRANSPORT CART | 1920 | E806 | |
| | E810A | 1643 | HOT WELLS | 2–12 | 20/2GFI | 5 | | | ■ | 6 | 20/1 | 3–12 | TRANSPORT CART | 1920 | E806 | |
| | | – | – | +12G | – | 7 | ■ | | | 8 | 20/1 | 3–12 | TRANSPORT CART | 1920 | E806 | |
| | E810B | 600 | COLD PAN | 3–12 | 20/1GFI | 9 | | ■ | | 10 | 20/1 | 3–12 | 2 REC | 360 | E800A | |
| | E810C | 1200 | BEVERAGE | 3–12 | 20/1GFI | 11 | | | ■ | 12 | 20/1 | 3–12 | 2 REC – DESK | 360 | E800B | |
| | E810C | 1200 | BEVERAGE | 3–12 | 20/1GFI | 13 | ■ | | | 14 | 20/1 | 3–12 | 2 REC | 360 | E800A | |
| | E811 | 180 | CASH REGISTER | 3–12 | 20/1GFI | 15 | | ■ | | 16 | 20/1 | 3–12 | 3 REC | 360 | E800A | |
| | E810B | 600 | COLD PAN | 3–12 | 20/1GFI | 17 | | | ■ | 18 | 20/1 | 3–12 | TEMP. KITCHEN LTS/FAN | 566 | | |
| | E810A | 1643 | HOT WELLS | 2–12 | 20/2GFI | 19 | ■ | | | 20 | 20/1 | | SPARE | | | |
| | | – | – | +12G | – | 21 | | ■ | | 22 | 20/1 | | SPARE | | | |
| | E810 | 2766 | HOT WELLS | 2–12 | 20/2GFI | 23 | | | ■ | 24 | 20/1 | | SPARE | | | |
| | | – | – | +12G | – | 25 | ■ | | | 26 | 20/1 | | SPARE | | | |
| | E808 | 1622 | HEATED CABINET | 2–12 | 20/2 | 27 | | ■ | | 28 | 20/1 | | SPARE | | | |
| | | – | – | +12N+12G | – | 29 | | | ■ | 30 | 20/1 | 3–12 | EXISTING CIRCUIT | 500 | | 3 |
| | E809 | 984 | REFRIGERATOR | 3–12 | 20/1 | 31 | ■ | | | 32 | 20/1 | 3–12 | EXISTING CIRCUIT | 500 | | 3 |
| | E808 | 1622 | HEATED CABINET | 2–12 | 20/2 | 33 | | ■ | | 34 | 15/2 | 2–12 | EXISTING CIRCUIT | 1000 | | 3 |
| | | – | – | +12N+12G | – | 35 | | | ■ | 36 | – | +12N+12G | – | – | | |
| | E809 | 984 | REFRIGERATOR | 3–12 | 20/1 | 37 | ■ | | | 38 | 20/2 | 2–12 | EXISTING CIRCUIT | 1000 | | 3 |
| | | | SPARE | | 20/1 | 39 | | ■ | | 40 | – | +12N+12G | – | – | | |
| | | | SPARE | | 20/1 | 41 | | | ■ | 42 | 50/2 | 2–8 | EXISTING CIRCUIT | 5000 | | 3 |
| | | | SPARE | | 20/1 | 43 | ■ | | | 44 | – | +8N+10G | – | – | | |
| | | | TOTAL LOAD @ 100% = 35498VA | | | | | | | | TOTAL LOAD @ 100% = 99A | | | | | |

1. REF. KITCHEN CONSULTANT'S "FCS" DRAWINGS FOR KITCHEN EQUIPMENT NUMBERS.
2. A DEMAND FACTOR PERCENT OF 65% HAS BEEN APPLIED TO THE KITCHEN EQUIPMENT LOAD PURSUANT TO NEC 220–20 AND NEC TABLE 220–20.
3. IDENTIFY ANY CIRCUITS OR PARTIAL CIRCUITS THAT EXTEND BEYOND THE AREA OF RENOVATION. PROVIDE TEMPORARY FEED TO MAINTAIN ALL CIRCUITS SERVING ELEMENTS/SPACES NOT TO BE REMOVED DURING CONSTRUCTION. RECONNECT EXISTING CIRCUITS/DEVICES TO REMAIN TO TEMPORARY KITCHEN PANEL ONCE AVAILABLE USING CB(S) PROVIDED. ALL PARTIAL CIRCUITS SHALL REMAIN AND REMAIN ACTIVE BOTH DURING AND AFTER CONSTRUCTION.





## T1 TEMPORARY KITCHEN - LIGHTING PLAN

SCALE: 1/4" = 1'– 0"




## T2 TEMPORARY KITCHEN - ELECTRICAL PLAN

SCALE: 1/4" = 1'– 0"




## 1 DEMOLITION FLOOR PLAN

SCALE: 1/8" = 1'– 0"

## ELECTRICAL KEYED NOTES

GENERAL NOTES:

- CUT WALLS AS REQUIRED TO FLUSH MOUNT NEW DEVICES IN EXISTING WALLS. PATCH/REPAIR WALLS TO MATCH.

DEMOLITION NOTES:

A. EXISTING STANDBY GENERATOR PANEL TO REMAIN.

B. EXISTING KITCHEN PANELS TO BE REPLACED WITH NEW. MODIFY EXISTING WALLS TO MATCH NEW PANEL LAYOUTS AND DIMENSIONS.

C. EXISTING LIGHTING FIXTURES AND CEILING DEVICES TO BE REMOVED THROUGHOUT.

D. EXISTING WALK–IN COOLER/FREEZER AND ASSOCIATED EQUIPMENT TO BE REMOVED.

E. EXISTING WALL ELECTRICAL DEVICES TO BE REMOVED. EXISTING J–BOXES MAY BE REUSED WHERE NEW DEVICES ARE TO BE INSTALLED AT THE SAME LOCATIONS.

F. EXISTING ELECTRICAL DEVICES TO BE REMOVED.

G. NEW 208Y/120V PANEL AND TRANSFORMER FOR TEMPORARY KITCHEN TO BE INSTALLED PRIOR TO DEMOLITION. PANEL AND TRANSFORMER TO BE REMOVED AT END OF KITCHEN RENOVATION AND TURNED OVER TO THE DISTRICT. INSTALL TRANSFORMER ON PREMADE FIBERCRETE PAD AND WAFFLE TYPE VIBRATION ISOLATION PADS. DO NOT PROVIDE A POURED IN PLACE CONCRETE PAD AT THIS LOCATION.

H. PROVIDE RECEPTACLES AND LIGHT FIXTURES FOR TEMPORARY KITCHEN DURING RENOVATION. ALL TEMPORARY DEVICES AND EQUIPMENT TO BE REMOVED AT END OF KITCHEN RENOVATION AND OFFERED TO THE OWNER AS SALVAGE.

I. CONDUITS ROUTED FROM TEMPORARY KITCHEN WALL AND BENEATH SERVING LINE. PROVIDE MULTICHANNEL ROLLOVER CABLE PROTECTOR FOR EXPOSED CONDUITS NOT UNDER THE SERVING LINE. ALL CONDUITS UNDER THE SERVING LINE SHALL BE SECURED TO/ROUTED ON TOP OF UNISTRUT AND NOT DIRECTLY ON THE FLOOR. DO NOT ANCHOR UNISTRUT TO THE EXISTING FLOORING. COORDINATE POWER AND DATA OUTLET LOCATIONS WITH OTHER TRADES.

J. REMOVE EXISTING LIGHT FIXTURES ABOVE NEW KITCHEN EXTENSION. MODIFY EXISTING WIRING TO MAINTAIN REMAINING FIXTURE OPERATION.

K. HARDWIRE KITCHEN EQUIPMENT TO LOCAL ON/OFF SWITCH. TYPICAL.

L. SURFACE MOUNT FIXTURES ON TEMPORARY KITCHEN CEILING. TYPICAL.

M. WIRE TEMPORARY KITCHEN FAN TO LOCAL LIGHTING CIRCUIT AND CONTROLS. FAN SHALL BE ON/OFF WITH LIGHTS.

N. EXISTING EXTERIOR LIGHT FIXTURES TO BE REMOVED.

O. PROVIDE NEW FIRE ALARM DEVICES AS PART OF THE TEMPORARY KITCHEN BUILDOUT.

P. PROVIDE NEW TEMPORARY LIGHT FIXTURES IN THE EXISTING CAFETERIA CEILING ABOVE THE SERVING LINE. COORDINATE LOCATIONS WITH TEMPORARY SERVING LINE AND EXISTING CONDITIONS. CONNECT TO EXISTING LIGHTING CONTROLS/CIRCUIT. ALL TEMPORARY LIGHT FIXTURES SHALL BE REMOVED AT THE END OF KITCHEN RENOVATION AND OFFERED TO THE OWNER AS SALVAGE. PROVIDE REPLACEMENT CEILING TILES.

Q. PROVIDE IN–USE WEATHERPROOF COVER FOR RECEPTACLE.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

u

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILL ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD.
SUGAR LAND, TX 77498

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL DEMO AND TEMP PLANS

u-ED.100


STANTON ENGINEERING GROUP
INFO@STANTON–ENG.COM (713) 300–6282 | TEXAS ENG. FIRM REG. NO. F–018332 | 1300 W. SAM HOUSTON PARKWAY S., SUITE 121, HOUSTON, TX 77042


© 2021 ALL RIGHTS RESERVED

## DEMOLITION KEYED NOTES

D1 EXISTING CLEAN OUT SHALL BE REPLACED WITH NEW. CHIP OUT SLAB AROUND CLEANOUT TO REMOVE.

D2 EXISTING FLOOR DRAIN SHALL BE REPLACED WITH NEW, INCLUDING P-TRAP. CHIP OUT SLAB AROUND DRAIN TO REMOVE FLOOR DRAIN AND EXISTING P-TRAP.

D3 CUT AND CAP EXISTING HW/CW FOR FUTURE EXTENSION. DEMOLISH ALL PIPING WITHIN KITCHEN. DEMOLITION SHALL BE DELAYED UNTIL NEW CW MAIN AND HW PIPING LOOP IS INSTALLED IN PARALLEL. CW/HW SERVICE TO THE TEMPORARY KITCHEN SHALL BE UNINTERRUPTED DURING OCCUPIED HOURS. COORDINATE SWITCHOVER FROM EXISTING PIPING TO NEW WITH OCCUPANCY SCHEDULE.


D4 EXISTING FLOOR DRAIN TIED TO GREASE WASTE SYSTEM. DRAIN IS BEING USED FOR TEMPORARY KITCHEN INDIRECT WASTE, AND SHALL REMAIN ACTIVE DURING OCCUPIED HOURS. COORDINATE DEMOLITION AND REPLACEMENT WITH TEMPORARY KITCHEN USAGE.

D5 DEMOLISH EXISTING DRAIN A CAP BELOW SLAB.

D6 EXISTING SPACE BEING DEMOLISHED. CAP EXISTING SANITARY MAIN BELOW SLAB AND REMOVE UPSTREAM PIPING. CUT/CHIP OUT SLAB AS REQUIRED AND REPAIR TO MATCH EXISTING.

D7 TEMPORARILY CAP EXISTING SANITARY MAIN BELOW SLAB AND REMOVE UPSTREAM PIPING. CUT/CHIP OUT SLAB AS REQUIRED AND REPAIR TO MATCH EXISTING. PIPING TO BE REPLACED WITH NEW TRUNK AND ADDITIONAL DRAIN BRANCH LINES.

D8 CUT AND CAP EXISTING SANITARY MAIN BELOW GRADE FOR EXTENSION IN RENOVATION PHASE. ALL UPSTREAM PIPING SHALL BE ABANDONED IN PLACE. CAP ANY OPEN ENDS BEFORE BURIAL.




**1 PLUMBING DEMOLITION FLOOR PLAN**
SCALE: 1/4" = 1'- 0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

u

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILL ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD.
SUGAR LAND, TX 77498

SEAL

STATE OF TEXAS
TYLER W. HERRING
106052
LICENSED PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

PLUMBING DEMOLITION FLOOR PLAN
**u-PD1.01**



STANTON ENGINEERING GROUP
INFORMATION@STANTONEG.COM | (713) 300-4000


TEXAS ENG. FIRM REG. NO. F-9183 | © 2025 ALL RIGHTS RESERVED



12999 N. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77060

NUMBERED NOTES: FOR 2/a-A.101

1. COOLER RENTAL UNIT; APPROX. 8' X 10' BASIS OF DESIGN: MODEL DT810 BY POLAR LEASING REFRIGERATION RENTAL
2. INCLUDE OPTIONAL DIAMOND TREAD RAMP SUITABLE FOR WHEELED TRAFFIC
3. LOCATION SHOWN IS SUBJECT TO OWNER APPROX. LOCATION MUST NOT BLOCK DELIVERIES TO REAR DOOR. MUST BE WITH 10' OF AREA DRAIN, AND WITHIN 100' OF ELECTRICAL POWER.
4. CONTRACTOR SHALL SCAN PAVING FOR BURIED UTILITIES BEFOR CUTTING CONC.




1 SITE PLAN
SCALE: 1" = 30'-0"




2 ENLARGED SITE PLAN
SCALE: 1/16" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

u

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILLS ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD
SUGAR LAND, TX 77498

SEAL
REGISTERED ARCHITECT
ROBERT A. MEYER
23621
STATE OF TEXAS
7/15/2025



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING


SITE PLAN

u-A.101


F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\U-Sugar Mill ES\u-A.101 SITE PLAN.dwg Jul 23, 2025 - 4:58pm




10 CANOPY DETAILS
3/4" = 1'-0"




11 CANOPY PLAN
3/4" = 1'-0"





12 CANOPY SECTION
3/4" = 1'-0"

NOTES:
1. SAW CUT AND REMOVE EXISTING SLAB AND FLOOR FINISHES AS REQUIRED TO INSTALL NEW PLUMBING LINES, FLOOR DRAINS, FIXTURES, OR ELECTRICAL ITEMS.
2. SHADED AREA REPRESENTS APPROXIMATE SAWCUT AREAS NEEDED FOR PLUMBING ALTERATIONS.
3. CONTRACTOR TO DETERMINE EXTENT OF CONCRETE SLAB SAW CUTTING AS REQUIRED FOR ALL UTILITIES REQUIRED FOR THIS PROJECT.
4. SPLICE NEW REINFORCING BARS AND DOWELED INTO EXISTING CONCRETE, AND PROVIDE NEW VAPOR RETARDER AND WATERSTOPS, AND PATCH W/ 3000 PSI CONCRETE AFTER INSTALLATION OF UTILITIES AND FIXTURES.
5. PREPARE CONCRETE TO RECEIVE NEW FINISH.

HATCHED AREA REPRESENTS APPROXIMATE AREA THAT WILL NEED TO BE EXCAVATED IN ORDER TO MAKE PLUMBING ALTERATIONS OUTSIDE THE BUILDING. CONTRACTOR TO REMOVE CONCRETE WALKS, PAVING, AND EXCAVATE AS REQUIRED IN ORDER TO INSTALL NEW PLUMBING. BACK FILL AND RESTORE AFFECTED AREAS. REFER TO CIVIL DETAILS.

SAW CUT AND REMOVE EXISTING SLAB AND FLOOR FINISHES AS REQUIRED TO INSTALL NEW PLUMBING LINES, FLOOR DRAINS, FIXTURES, OR ELECTRICAL ITEMS. SPLICE NEW REINFORCING BARS AND DOWELED INTO EXISTING CONCRETE, AND PROVIDE NEW VAPOR RETARDER AND WATERSTOPS, AND PATCH W/ 3000 PSI CONCRETE AFTER INSTALLATION OF UTILITIES AND FIXTURES. PREPARE CONCRETE TO RECEIVE NEW FINISH.

SHADED AREA REPRESENTS APPROXIMATE SAWCUT AREAS NEEDED FOR PLUMBING ALTERATIONS. CONTRACTOR TO DETERMINE EXTENT OF CONCRETE SLAB SAW CUTTING AS REQUIRED FOR ALL PLUMBING REQUIRED FOR THIS PROJECT.




1 SLAB DEPRESSION PLAN
SCALE: 1/4" = 1'-0"

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\u-Sugar Mill ES\u-A 200 SLAB DIMENSION CONTROL PLAN.dwg Jul 23, 2025 - 4:59pm

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

u

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT

SUGAR MILLS ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD
SUGAR LAND, TX 77498

SEAL
REGISTERED ARCHITECT
MICHAEL K. WILLIAMS
22651
STATE OF TEXAS
7/15/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

SLAB DIMENSION CONTROL PLAN

u-A.200

SCOPE OF WORK: KITCHEN REPLACEMENT OF FLOOR, WALL, AND CEILING FINISHES, AS WELL AS, REPLACEMENT OF KITCHEN EQUIPMENT. PROVIDE ADDITIONAL KITCHEN STORAGE FOR CEP. UPGRADE TO BACK DOOR DELIVERY AREA.

**ADOPTED CODES WITH AMMENDMENTS OF CITY OF MISSOURI CITY, TX**

- 2021 INTERNATIONAL BUILDING CODE
- 2021 INTERNATIONAL RESIDENTIAL CODE
- 2021 INTERNATIONAL PLUMBING CODE
- 2021 INTERNATIONAL MECHANICAL CODE
- 2023 NATIONAL ELECTRIC CODE NFPA 70
- 2021 INTERNATIONAL ENERGY CONSERVATION CODE
- 2021 INTERNATIONAL FUEL GAS CODE
- 2021 INTERNATIONAL FIRE CODE

**INTERIOR WALL AND CEILING FINISH REQUIREMENTS BY OCCUPANCY:**

**SPRINKLERED**

| | |
|---|---|
| INTERIOR EXIT STAIRWAYS AND RAMPS AND EXIT PASSAGEWAYS | **B** |
| CORRIDORS AND ENCLOSURE FOR EXIT ACCESS STAIRWAYS AND RAMPS | **C** |
| ROOMS AND ENCLOSED SPACES | **C** |

**FLOORING SHALL BE CLASS II**

**2021 INTERNATIONAL EXISTING BUILDING CODE**

301.3.1 PRESCRIPTIVE COMPLIANCE METHOD. REPAIRS, ALTERATIONS, ADDITIONS AND CHANGES OF OCCUPANCY COMPLYING WITH CHAPTER FIVE OF THIS CODE IN BUILDINGS COMPLYING WITH THE INTERNATIONAL FIRE CODE SHALL BE CONSIDERED IN COMPLIANCE WITH THE PROVISIONS OF THIS CODE.

302.3 EXISTING MATERIALS. MATERIALS ALREADY IN USE IN A BUILDING IN COMPLIANCE WITH REQUIREMENTS OR APPROVALS IN EFFECT AT THE TIME OF THEIR ERECTION OR INSTALLATION SHALL BE PERMITTED TO REMAIN IN USE UNLESS DETERMINED BY THE BUILDING OFFICIAL TO BE UNSAFE .

302.4 NEW AND REPLACEMENT MATERIALS. EXCEPT AS OTHERWISE REQUIRED OR PERMITTED BY THIS CODE, MATERIALS PERMITTED BY THE APPLICABLE CODE FOR NEW CONSTRUCTION SHALL BE USED. LIKE MATERIALS SHALL BE PERMITTED FOR REPAIRS AND ALTERATIONS, PROVIDED THAT NO UNSAFE CONDITION IS CREATED. HAZARDOUS MATERIALS SHALL NOT BE USED WHERE THE CODE FOR NEW CONSTRUCTION WOULD NOT PERMIT THEIR USE IN BUILDINGS OF SIMILAR OCCUPANCY, PURPOSE AND LOCATION.

**ALTERATION - LEVEL 1** INCLUDE THE REMOVAL AND REPLACEMENT OR THE COVERING OF EXISTING MATERIALS, ELEMENTS, EQUIPMENT, OR FIXTURES USING NEW MATERIALS, ELEMENTS, EQUIPMENT, OR FIXTURES THAT SERVE THE SAME PURPOSE.

**ALTERATION - LEVEL 2** INCLUDE THE ADDITION OR ELIMINATION OF ANY DOOR OR WINDOW, THE RECONFIGURATION OR EXTENSION OF ANY SYSTEM, OR THE INSTALLATION OF ANY ADDITIONAL EQUIPMENT, AND SHALL APPLY WHERE THE WORK IS EQUAL TO OR LESS THAN 50% OF THE BUILDING AREA.

THIS BUILDING'S CONSTRUCTION IS TYPE IIB.

THIS BUILDING'S OCCUPANCY IS E.

THIS BUILDING'S IS SPRINKLERED.

THERE WILL NOT BE ANY MODIFACATIONS TO THE HOOD SYSTEMS IN THE KITCHENS BEYOND REPLACEMENT OF MOTOR FOR LIKE KIND IF NEEDED.


THE BUILDING WILL NOT HAVE ADDITIONAL SQUARE FOOTAGE AS PART OF THE WORK.

NEW CONSTRUCTION ELEMENTS, COMPONENTS, SYSTEMS AND SPACES SHALL COMPLY WITH THE REQUIREMENTS OF THE INTERNATIONAL BUILDING CODES

# 2 CODE ANALYSIS

## RESPONSIBILITY MATRIX

| ITEM | | | | CONTRACTOR RESPONSIBILITY | | OWNER RESPONSIBILITY | | NOTES |
|---|---|---|---|---|---|---|---|---|
| **EQUIPMENT** | **MAKE** | **MODEL** | **BASIS OF DESIGN** | FURNISHED | INSTALL | FURNISHED | INSTALL | |
| MARKERBOARD | | | MUST BE MAGNETIC; LOW GLOS, WHITE. NO GREY ALLOWED. 5' X 10' | X | X | | | |
| MOTORIZED FOLDING PARTITION | | | TOP SUPPORTED AND CONTINUOUSLY HINGED, MADE OF 3" THICK STEEL WITH FULL SOUND SEALS. THEY FEATURE AUTOMATIC FLOOR SEALS THAT DEPLOY WHEN POSITIONED. MARKERBOARD FINISHES ARE SUGGESTED FOR CLASSROOM USE. LARGE PARTITIONS SHOULD BE ELECTRONICALLY OPERATED, INTEGRATED WITH THE SCHOOL SYSTEM, AND SUPPORTED FROM THE BOTTOM IN A RECESSED MANNER. | X | X | | | |
| PAPER TOWEL DISPENSER | | | 1 PAPER TOWEL DISPENSER PER SINK | | X | X | | |
| SOAP DISPENSER | | | 1 SOAP DISPENSER PER SINK | | X | X | | |
| COMMERCIAL WASHER | GE | GTW75CPLDG | STAINLESS STEEL; ASTM A666, TYPE 304 WITH NUMBER 4 FINISH. ELECTRIC, 480 VOLTS, 40 LB CAPACITY, MINIMUM EXTRACTOR FORCE: 140 G FACTOR. | X | X | | | |
| COMMERCIAL DRYER | GE | GTD75ECPLDG | HEAVY DUTY EMBOSSED STEEL WITH ELECTROSTATICALLY APPLIED BACKED ENAMEL FINISH. | X | X | | | |
| MOP RACK | | | BROOM AND MOP HANGGERS FOR A MINIMUM OF TWELVE (12) HANGERS TO BE PROVIDED IN THE CONTRACT | X | X | | | |
| KITCHEN MENU SYSTEM DEVICE | | | RE: A-GF1.0 SF EQUIPMENT PLAN | X | X | | | REFERED TO IT DRAWINGS |
| LOCKERS | | | 12"W X 15"D, 3 TIER, 60" HIGH. 16 GA. DOOR WITH 20GA. BODY | X | X | | | |
| MIRROR | | | TOP EDGE 74 INCHES (1880 MM) MINIMUM ABOVE THE FINISH FLOOR OR GROUND & BOTTOM EDGE OF THE REFLECTING SURFACE 40 INCHES (1015 MM) MAXIMUM | X | X | | | |
| GRAB BARS | | | AS REQUIRED BY ADA | X | X | | | |
| HOOKS | | | J-HOOKS | X | X | | | |
| TIME CLOCK | KRONOS | | EXISTING UNIT | | X | | | COORDINATE HEIGHT, DATA, POWER AND ROUGH-IN REQUIREMENTS WITH FBISD IT. REMOVE, PROTECT & REINSTALL EXISITING TIME CLOCK. |
| **KITCHEN OFFICE FURNITURE** | | | | | | | | |
| AUSTIN PARKWAY ES | | | | | | X | X | |
| PECAN GROVE ES | | | | | | X | X | |
| SETTLERS WAY ES | | | | | | X | X | |
| SUGAR MILL ES | | | | | | X | X | |
| HIGHLANDS ES | | | | | | X | X | |
| PALMER ES | | | | | | X | X | |
| HUNTERS GLEN ES | | | | | | X | X | |




## 1 OVERALL FLOOR PLAN

SCALE: 1/16" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

u

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT

SUGAR MILLS ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD
SUGAR LAND, TX 77498

SEAL

REGISTERED ARCHITECT
MICHAEL K. WILLIAMS
22651
STATE OF TEXAS

7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING


OVERALL FLOOR PLAN

u-A.201

F:\2022\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\U-Sugar Mill ES\u-A.201 FLOOR PLAN.dwg, Jul 23, 2025 - 4:59pm

## DOOR SCHEDULE

| DOOR # | DOOR WIDTH | DOOR HEIGHT | DOOR TYPE | DOOR MATERIAL | DOOR FINISH | FIRE RATING | FRAME THICKNESS | FRAME FINISH | KEY | HARDWARE | DETAILS | | | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | | SILL | JAMB | HEAD | |
| A005 | 3'-0" | X 7'-0" | SF4 | SOLID CORE | P LAM | NR | 4 1/2" | ANOD AL | | 103 | | 22/A00-01 | 16/A00-01 | |
| A006 | 3'-0" | X 7'-0" | SF4 | SOLID CORE | P LAM | NR | 4 1/2" | ANOD AL | | 501 | | 22/A00-01 | 16/A00-01 | |
| A007 | 3'-0" | X 7'-0" | SF4 | SOLID CORE | P LAM | NR | 4 1/2" | ANOD AL | | 341 | | 22/A00-01 | 16/A00-01 | |
| A008 | 3'-0" | X 7'-0" | SF4 | SOLID CORE | P LAM | NR | 4 1/2" | ANOD AL | | 501C | | 22/A00-01 | 16/A00-01 | |
| A012 | 4'-0" | X 7'-0" | HM1 | H.M. | PAINT | NR | 6" | PAINT HM | | 715V | 21/A00-01 | 04/A00-01 | 04/A00-01 | |
| 109A | 3'-0" | X 7'-0" | SF4 | SOLID CORE | P LAM | NR | 4 1/2" | ANOD AL | | 501H | | 22/A00-01 | 16/A00-01 | |
| 109B | 3'-0" | X 7'-0" | SF1 | ALUM/GLASS | ANOD AL | NR | 4 1/2" | ANOD AL | | C201AH | 18/A00-01 | 10&11/A00-01 | 23&24/A00-01 | CARD READER, CLOSER, BUZZER |
| 109C | 3'-0" | X 7'-0" | SF1 | ALUM/GLASS | ANOD AL | NR | 4 1/2" | ANOD AL | | C201AH | 18/A00-01 | 10&11/A00-01 | 23&24/A00-01 | CARD READER, CLOSER, BUZZER |
| 109D | 3'-0" | X 7'-0" | SF4 | SOLID CORE | P LAM | NR | 4 1/2" | ANOD AL | | 501H | | 22/A00-01 | 16/A00-01 | |




NEW DOOR AND FRAME HOLLOW METAL DOOR NEW H.M. FRAME

NEW DOOR AND FRAME HOLLOW METAL DOOR NEW H.M. FRAME

NEW DOOR AND FRAME S. C. WOOD DOOR ALUM. FRAME

NEW DOOR AND FRAME ALUM/GLASS ALUM. FRAME

## 2 DOOR SCHEDULE

## FLOOR PLAN - GENERAL NOTES

1. REFER TO SHEET FOR GENERAL NOTES. GENERAL NOTES APPLY TO ALL SCHOOL KITCHENS.
2. REFER TO SHEET FOR PARTITION TYPES.
3. EXIXSTING EXPOSED CONDUITS AND DATA CABLING IN WIREMOLD TO BE ROUTED INSIDE WALLS (EXCEPT AT WAREWASH AREA BELOW TABLE HEIGHT AND DRY STORAGE ROOMS). PATCH AND REPAIR AS REQUIRED TO ACHIEVE SMOOTH CLEAN WALL SURFACE.

## PARTITION LEGEND

- EXISTING CMU PARTITION
- NEW CMU SCHEDULED PARTITION
- EXISTING METAL PARTITION
- NEW FRAMED SCHEDULED PARTITION

## 3 FLOOR PLAN NOTES

## FLOOR PLAN - KEYED NOTES

(NOT ALL NOTES USED ON EACH SHEET)

01 PROVIDE NEW MOP SINK UTILITY SHELF
RE: PLUMBING FOR MOP SINK
RE: SPEC 10 28 00 FOR UTILITY SHELF

02 REMOVE, STORE & REPLACE WALL MOUNTED FIRE EXTINGUISHER

03 PROVIDE NEW WALL MOUNTED FIRE EXTINGUISHER
RE: SPEC SECTIONS 10 44 13

04 PROVIDE NEW LOCKERS
RE: SPEC 10 51 13.

05 PROVIDE WASHER AND DRYER
RE: SPEC 11 45 20

06 REMOVE, PROTECT & REINSTALL WALL MOUNTED CLOCK.

07 PROVIDE CONDENSING UNIT
FOR WALK-IN COOLER/FREEZER
RE: MECHANICAL AND SPEC 11 40 00


08 PROVIDE POWER AND DATA FOR MENU BOARD.
RE: ELECTRICAL, TECHNOLOGY DRAWINGS & FOOD SE

09 PROVIDE P-LAM SHELVING
REFER TO DETAIL FOR BRACKET SUPPORT

10 FURNITURE & NON FOOD SVE EQUIPMENT RETURN TO STORAGE


11 INSPECT & SREVICE TOLLING COUNTER DOORS. RETU NEW CONDITION.

12 COMMERCIAL CLOSED WASHER 40LB CAPACITY.
COMMERCIAL CLOSED DRYER 55LB CAPACITY.
BASIS OF DESIGN: WASHER; SPEED QUEEN SYN040
DRYER; SPEED QUEEN ST055.
REFER TO ELECTRICAL & PLUMBING FOR CONNECTION












## 1 KITCHEN PLAN

SCALE: 1/4" = 1'-0"





## 4 MAKERBOARD ELEVATION

SCALE: 1/2"=1'-0"




## 5 RAMP @ REAR DOOR

SCALE: 3/16"=1'-0"




## A

SCALE: 1/2"=1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

u

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILLS ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD
SUGAR LAND, TX 77498

SEAL

REGISTERED ARCHITECT
KOTY A. WILLIAMS
42651
STATE OF TEXAS

7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

KITCHEN PLAN

u-A.301

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\U-Sugar Mill ES\u-A 301 KITCHEN PLAN.dwg Jul 30, 2025 - 10:36am

## TEMPORARY KITCHEN FLOOR PLAN KEYED NOTES 05/A-A03-02

01 PROVIDE & INSTALL 555 SF OF RAM BOARD TO PROTECT EXISTING FLOORING. REMOVE AFTER CONSTRUCTION IS COMPLETE. CONTRACTOR MUST REPAIR FLOORING DAMAGED DURING CONSTRUCTION.

02 PROVIDE SCHEDULED PARTITIONS. BUILD PARTITIONS ON TOP OF RAM BOARD. DO NOT ATTACH PARTITIONS TO FLOOR.


03 ATTACH PARTITIONS TO EXISTING WALL. REPAIR WALL TO MATCH EXISTING AFTER CONSTRUCTION IS COMPLETE.

## TEMPORARY KITCHEN RCP KEYED NOTES 03/A-A03-02

04 ALL NEW SCHEDULED PARTITIONS AND CEILINGS FOR TEMPORARY STORAGE LAYOUT TO BE EPOXY PAINTED SW 7014 EIDER WHITE WITH SPECIFIED 4" RUBBER BASE. REMOVE WHEN CONSTRUCTION IS COMPLETED.


05 MOUNT TEMPORARY FLUORESCENT LIGHTS TO TEMPORARY CEILING.

## 3 KEYED NOTES





## 4 TEMPORARY LAYOUT SECTION

SCALE: 1"=1'-0"




## 1 TEMPORARY KITCHEN RCP

SCALE: 1/4" = 1'-0"




## 2 TEMPORARY KITCHEN FLOOR PLAN

SCALE: 1/4" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

u

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT

SUGAR MILLS ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD
SUGAR LAND, TX 77498

SEAL

REGISTERED ARCHITECT
MICHAEL W. ALLEN
#22651
STATE OF TEXAS

7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING


TEMPORARY KITCHEN LAYOUT
u-A.302

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\U-Sugar Mill ES\u-A.302 TEMPORARY KITCHEN LAYOUT.dwg Jul 23, 2025 - 5:00pm

## RCP - GENERAL NOTES


1. CEILING GRID SHALL BE INSTALLED TO MATCH EXISTING GRID'S POINT OF ORIGIN. THIS WILL REDUCE NEED TO RE-LOCATE ABOVE CEILING DUCTS, SPRINKLER PIPING AND OTHER SUPPORT SYSTEMS.
2. REFER TO SHEET A00-01 FOR GENERAL NOTES. GENERAL NOTES APPLY TO ALL SEVEN SCHOOL KITCHEN REMODELS.
3. LIGHTING LEVELS SHOULD BE 50 FC IN PREPARATION AREAS, WARE WASH AND SERVING LINES, OR MEET MINIMUM HEALTH CODE LEVELS, WHICHEVER ITS GREATER. SEE MEP PLANS
4. REPLACE HVAC DEVICES. REPLACE LIGHTING WITH 24"x24" LED LAY IN LIGHT AS SCHEDULED IN ELECTRICAL PLANS.
5. REFER TO MECHANICAL, ELECTRICAL SHEETS FOR DEVICE SCHEDULES.

## 2 RCP GENERAL NOTES




## 1 REFLECTED CEILING PLAN

SCALE: 1/4" = 1'-0"




## 3 FOOD SERVICE AREA ELEVATION

SCALE: 3/16" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

u

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILLS ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD
SUGAR LAND, TX 77498

SEAL

REGISTERED ARCHITECT
MELVIN WILLIAMS
#2651
STATE OF TEXAS

7/15/2025

MWA ARCHITECTS

ARCHITECTS AND PLANNING CONSULTANTS

11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25

DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING


REFLECTED CEILING PLAN

u-A.401


F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\U-Sugar Mill ES\u-A.401 REFLECTED CEILING PLAN.dwg Jul 23, 2025 - 5:01pm





## 12 MOPSINK ELEVATIONS
SCALE: 1/4"=1'-0"




## 11 LOCKER HOUSEKEEPING PAD
SCALE: 3"=1'-0"




### TYPE A
ROOM SIGNAGE - FIXED NAMES




### TYPE B
KITCHEN RESTROOM SIGNAGE

## 4 ROOM SIGNAGE
SCALE: 6"=1'-0"


### PAINT COLOR SCHEDULE
UNLESS OTHERWISE INDICATED FIELD COLOR IS PT-1 (SW 7014 EIDER WHITE)

SW 7014 EIDER WHITE (EPOXY PAINT)


### WALL TILE
CERAMIC WALL TILE (WT-1)
REFER TO TILE PATTERN AT SERVING AND RESTROOM
FIELD WALL TILE: DALTILE RITTENHOUSE SQUARE K175 BISCUIT (3X6)

A — PROVIDE ROOM SIGN TO REPLACE EXISTING. SEE LAYOUT FOR TYPE A OR TYPE B SIGN LOCATIONS.

## 2 FLOOR FINISH LEGEND





## 5 FLOOR TRANSITION THRESHOLD
SCALE: 3"=1'-0"





## 1 FINISH FLOOR PLAN
SCALE: 1/4" = 1'-0"

ALL FINISHED NOT DENOTED IN DRAWINGS SHALL BE SELECTED DURING THE SUBMITTAL PROCESS





## 7 RR ELEVATIONS
SCALE: 1/4"=1'-0"





WALL TILE PATTERN - RESTROOM


## 3 WALL TILE PATTERN
SCALE: 1/4"=1'-0"




## 8 UTILITY ELEVATIONS
SCALE: 1/4"=1'-0"




## 9 STOREFRONT ELEVATIONS
SCALE: 1/4"=1'-0"




## 10 STOREFRONT SECTION
SCALE: 1/2"=1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

u

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILLS ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD
SUGAR LAND, TX 77498

SEAL
REGISTERED ARCHITECT
ANGIE MAGUIRE
42651
STATE OF TEXAS
7/15/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

FINISH FLOOR PLAN

u-A.501

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\U-Sugar Mill ES\u-A.501 FINISH FLOOR PLAN.dwg Jul 28, 2025 - 6:02pm

1. AT WALLS THAT TERMINATE ABOVE CEILING, CONTRACTOR MAY CONTINUE METAL STUD FRAMED WALLS TO UNDERSIDE OF METAL DECK AND OMIT DIAGONAL BRACING IF HEIGHT DOES NOT EXCEED LIMITING HEIGHT OF METAL STUD AS INDICATED ON CHART BELOW.

2. PROVIDE INTERMEDIATE BRACING AT ALL PARTITIONS THAT EXCEED LIMITING HEIGHT OF METAL STUDS AS INDICATED ON CHART BELOW.

3. ALL BRACING SHALL BE AT STUD POINTS.


CMU PARTITION NOTES:

1. MATCH EXISTING CMU COURSING (TYP.):
   BRIARGATE ES (4" CMU STARTER COURSE)
   LAKE OLYMPIA MS (4" CMU STARTER COURSE)
   MISSION BEND ES (8" CMU STARTER COURSE)
   RIDGEMONT ES (8" CMU STARTER COURSE)
   TOWNEWEST ES (8" CMU STARTER COURSE)
2. PROVIDE CMU LINTELS FOR ALL OPENINGS IN INTERIOR CMU PARTITIONS. COORDINATE WITH STRUCTURAL.
3. PROVIDE A 3/4" SPACE BETWEEN TOP OF CMU AND STRUCTURE/DECK FOR POTENTIAL DEFLECTION. SEAL WITH APPROPRIATE CAULK.
4. REFER TO FINISH SCHEDULES FOR CERAMIC TILE LOCATIONS.


GYPSUM WALLBOARD PARTITION NOTES:

1. ALL METAL STUDS PARTITIONS ARE 25 GAUGE METAL STUDS AT 16" O.C. UNLESS OTHERWISE NOTED. IF THE LIMITING HEIGHT FOR A PARTITION TYPE IS EXCEEDED, INCREASE SIZE AND/OR GAUGE OF METAL STUDS AS INDICATED ON "LIMITING HEIGHT OF METAL STUDS" TABLE. NOTIFY THE ARCHITECT PRIOR TO INSTALLATION.


| LIMITING HEIGHT OF METAL STUDS | | | |
|---|---|---|---|
| STUD SIZE | SPACING | 25 GA | 20 GA. |
| 2-1/2" | 16" | 11'-3" | 12'-10" |
| 3-5/8" | 16" | 14'-4" | 16'-5" |
| 6" | 16" | 19'-9" | 24'-6" |





PARTITION A
SCALE: 1-1/2" = 1'-0"




PARTITION B1
SCALE: 1-1/2" = 1'-0"




PARTITION B2
SCALE: 1-1/2" = 1'-0"




PARTITION B3
SCALE: 1-1/2" = 1'-0"




PARTITION B4
SCALE: 1-1/2" = 1'-0"




PARTITION B5
SCALE: 1-1/2" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |

u

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILLS ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD
SUGAR LAND, TX 77498

SEAL

FOR
INTERIM REVIEW
AND NOT INTENDED FOR CONSTRUCTION, BIDDING OR PERMIT PURPOSES.


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 05/23/25

PARTITION SCHEDULE

u-A.502

## GENERAL NOTES


1. ALL CONCRETE SHALL TEST 4000 PSI AT 28 DAYS.
2. ALL CONCRETE REINFORCING BARS SHALL CONFORM TO ASTM A615 GRADE 60.
3. DETAILING AND FABRICATION OF CONCRETE REINFORCEMENT AND ACCESSORIES SHALL BE IN ACCORDANCE WITH ACI-315 LATEST EDITION.
4. LAP ALL CONTINUOUS REINFORCING BARS 50 DIAMETERS AT SPLICES, TEES, AND CORNERS.
5. THE USE OF HEAT TO FACILITATE THE BENDING OF REINFORCING BARS WILL NOT BE PERMITTED.
6. NO ENGINEERING DRAWING MAY BE REPRODUCED FOR USE AS SHOP DRAWINGS.
7. CONTRACTOR SHALL COORDINATE ALL LOCATIONS OF ALL ANCHOR BOLTS AND OPENINGS FOR MECHANICAL, PIPING, AND ELECTRICAL EQUIPMENT WITH THE RESPECTIVE ENGINEERING AND VENDOR DRAWINGS.

## SLAB NOTE

4" CONC. SLAB ON 10 MIL POLY FILM ON 2" MAX. SAND FILL. REINFORCE WITH #3 @ 15"c.c. E.W. IN CENTER OF SLAB. FOR SUBGRADE PREPARATION REFER TO GEOTECHNICAL INVESTIGATION BY PARADIGM CONSULTANTS, INC. REPORT NUMBER 24-1067, DATED DEC. 2024.

## SLAB SIDEWALK SLAB NOTE

4" CONC. SLAB ON 2" MAX. SAND FILL. REINF. W/ #3 @ 18"c.c. IN CENTER OF SLAB.




## FOUNDATION PLAN

SCALE: 1/4"=1'-0"

## FIELD VERIFICATION NOTE

1. CONTRACTOR SHALL VERIFY ALL DIMENSIONS PRIOR TO FABRICATION OR CONSTRUCTION.
2. CONTRACTOR SHALL VERIFY AND NOTIFY ENGINEER OF EXISTING CONDITIONS IN NEED OF REVIEW AND POSSIBLE MODIFICATION PRIOR TO FABRICATION.

ISSUE:

| | |
|---|---|
| 03/07/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILLS ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD
SUGAR LAND, TX 77498


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079






*July 17, 2025*


STANLEY SPURLING & HAMILTON, INC.
Consulting Engineering Services
T.B.P.E. Registration # F-000175
www.sshinc.net
50 Years
3301 Edloe Street, Suite 200 Houston, Texas 77027 Tel 713-776-9433
E-MAIL: info@sshinc.net | 0002-0256



PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

KITCHEN PLAN


S1





1 SECTION
SCALE: 3/4"=1'-0"





2 SECTION
SCALE: 3/4"=1'-0"




3 SECTION
SCALE: 3/4"=1'-0"




4 SECTION
SCALE: 3/4"=1'-0"




## MIN. REBAR LAP SCHEDULE FOR f'm = 1,500 psi

| BAR SIZE | 6" CMU | 8" CMU | 10" CMU | 12" CMU |
|---|---|---|---|---|
| #3 | 12" | 12" | 12" | 12" |
| #4 | 20" | 15" | 12" | 12" |
| #5 | 32" | 23" | 18" | 15" |
| #6 | 54" | 43" | 34" | 28" |
| #7 | NA | 60" | 46" | 38" |
| #8 | NA | 72" | 71" | 57" |
| #9 | NA | NA | 82" | 74" |

## CONCRETE MASONRY NOTES

1. CONCRETE MASONRY UNITS AND CONSTRUCTION TO BE PER "NATIONAL CONCRETE MASONRY ASSOCIATION" RECOMMENDATIONS (WHERE NOT COVERED BY THE LOCAL BUILDING CODE).
2. ALL MASONRY GROUT TO BE PER TABLE 1 (THIS SHEET); ALL MORTAR PER TABLE 2 (THIS SHEET).
3. FILL CELLS WITH GROUT AT VERTICAL REINFORCEMENT.
4. CAST-IN-ANCHORS EMBEDDED IN CONCRETE MASONRY SHALL EXTEND BEYOND REINFORCING 1" MIN.
5. COMPRESSIVE STRENGTH OF MASONRY SHALL BE 1500 PSI AT 28 DAYS.
6. CMU SHALL BE PLACED IN A RUNNING BOND PATTERN UNLESS SPECIFICALLY NOTED OTHERWISE ON THE PLANS.
7. CONTROL JOINTS SHALL HAVE NO HORIZONTAL REINFORCING THROUGH THE JOINT AND VERTICAL REINFORCING ON BOTH SIDES OF JOINT. CONTROL JOINTS SHALL BE UNGROUTED WITH A BACKER ROD AND SEALANT ON BOTH SIDES OF WALL.
8. BOND BEAMS AND REINFORCING SHALL BE CONTINUOUS AT CONTROL JOINT WITH BACKER ROD AND SEALANT CONTINUOUS WITH JOINT.

## CONCRETE BLOCK LINTEL SCHEDULE

| WALL THICKNESS \ MAXIMUM SPAN | 4'-6" | 9'-0" |
|---|---|---|
| 4" | GROUT 1 COURSE 1~#4 CONT. | #3 STIRRUPS @ 16" c.c. GROUT 2 COURSES 1~#4 CONT. |
| 6" 8" & 12" | GROUT 1 COURSE 2~#5 CONT. | #3 STIRRUPS @ 16" c.c. GROUT 2 COURSES 2~#5 CONT. TOP & BOT. |

## TABLE 1. GROUT PROPORTIONS BY VOLUME

| TYPE | PARTS BY VOLUME OF PORTLAND CEMENT OR PORTLAND BLAST-FURNACE SLAG CEMENT | PARTS BY VOLUME OF HYDRATED LIME OR LIME PUTTY | AGGREGATE MEASURED IN DAMP, LOOSE CONDITION | |
|---|---|---|---|---|
| | | | FINE | COARSE |
| FINE GROUT (<4" WIDE CAVITY) | 1 | 0 TO 1/10 | 2¼ TO 3 TIMES THE SUM OF THE VOLUMES OF THE CEMENTITIOUS MATERIAL | |
| COARSE GROUT (>4" WIDE CAVITY) | 1 | 0 TO 1/10 | 2¼ TO 3 TIMES THE SUM OF THE VOLUMES OF THE CEMENTITIOUS MATERIAL | 1 TO 2 TIMES THE SUM OF THE VOLUMES OF THE CEMENTITIOUS MATERIAL |

## TABLE 2. MORTAR PROPORTIONS BY VOLUME

| MATERIAL | TYPE | PORTLAND CEMENT OR BLENDED CEMENT | MASONRY CEMENT | HYDRATED LIME OR LIME PUTTY | AGGREGATE RATIO (MEASURE IN DAMP, LOOSE CONDITION) |
|---|---|---|---|---|---|
| CEMENT LIME | S | 1 | .... | OVER ¼ TO ½ | NOT LESS THAN 2¼ & NOT MORE THAN 3 TIMES THE SUM OF THE SEPARATE VOLUMES OF CEMENTITIOUS MATERIALS |
| MASONRY/ CEMENT | S | 1/2 | 1 | .... | |


**NOTE: CONTROL JOINTS SHALL BE LOCATED AT THE FOLLOWING**

1. AT ALL CHANGES IN WALL HEIGHT.
2. AT ALL CHANGES IN WALL THICKNESS SUCH AS CHASES, COLUMNS OR PILASTERS.
3. AT (ABOVE) MOVEMENT JOINTS IN FOUNDATIONS AND FLOORS.
4. AT (BELOW) MOVEMENT JOINTS IN ROOFS AND FLOORS THAT BEAR ON A WALL.
5. ADJACENT TO CORNERS OF WALLS OR INTERSECTIONS WITHIN A DISTANCE OF ONE-HALF THE NORMAL CONTROL JOINT SPACING.
6. CONTROL JOINTS SHALL BE SPACED NO MORE THAN 25'-0" APART.
7. DO NOT PLACE CONTROL JOINT ABOVE OR BELOW OPENINGS.
8. CONTRACTOR SHALL PROVIDE A CONTROL JOINT PLAN PRIOR TO FABRICATION OR CONSTRUCTION.

## LOOSE LINTEL SCHEDULE

| SPAN | LINTEL | SPAN | LINTEL |
|---|---|---|---|
| 0' TO 6' | L3½x3½x¼ | 8' TO 9' | L5x3½x5/16 |
| 6' TO 7' | L4x3½"x¼ | 9' TO 10' | L6x3½x5/16 |
| 7' TO 8' | L4x3½x5/16 | 10' TO 12' | L7x4x⅜ |

LOOSE LINTEL MIN. BEARING OF 8".




CONTRACTOR SHALL COVER ALL EXPOSED REBAR DURING CONSTRUCTION.

## TYPICAL ELEVATION OF CONCRETE MASONRY WALL AND NOTES

SCALE: N.T.S.

## TYPICAL REBAR CAP DETAIL

SCALE: N.T.S.

ISSUE:

| | |
|---|---|
| 03/07/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILLS ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD
SUGAR LAND, TX 77498


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING


SECTIONS AND TYPICAL DETAILS


S2




*July 17, 2025*


STANLEY SPURLING & HAMILTON, INC.
50 Years
Consulting Engineering Services
T.B.P.E. Registration # F-000175
www.sshinc.net
3301 Edloe Street, Suite 200 Houston, Texas 77027 Tel 713-776-9433
E-MAIL: info@sshinc.net | 0002-0256




# ENLARGEMENT SCOPE

## EXISTING INVERT TABLE

#2567
SANITARY MANHOLE RIM=81.80' 6"WP(N&S)FL=77.75'

#1903
SANITARY MANHOLE RIM=81.45' 6"PVC(N&W)FL=77.88'

#1904
STORM MANHOLE RIM=78.72' UNABLE TO VERIFY SIZE, BXC(N/W&SE)=68.41'

#1902
CURB INLET W/STM MH TOP=78.73' GT=77.51' 24"RCP(NE)FL=70.63'

#1901
STORM MANHOLE RIM=78.38' UNABLE TO VERIFY SIZE, BXC(N/W&SE)=68.15'

#1900
CURB INLET W/STM MH TOP=78.62' GT=77.46' 24"RCP(SW)FL=70.86'

#1897
CURB INLET W/STM MH TOP=78.42' GT=77.23' 24"RCP(SW)FL=71.31'

#1714
STORM MANHOLE RIM=78.24' UNABLE TO VERIFY SIZE, BXC(N/W&SE)=68.12'

#1703
CURB INLET W/STM MH TOP=78.67' GT=77.47' 24"RCP(SW)FL=70.97' 24"RCP(NE)FL=73.63'

#1701
STORM MANHOLE RIM=79.43' 24"RCP(SE)FL=74.02' 24"RCP(SW)FL=74.68' 24"RCP(SE)FL=73.71'

#1788
CURB INLET W/STM MH TOP=78.94' GT=78.04' 24"RCP(NE)FL=70.72'

#1793
STORM MANHOLE RIM=78.34' UNABLE TO VERIFY SIZE, BXC(NW&SE)=67.87'

#1894
STORM MANHOLE TOP=78.93' GT=77.93' 24"RCP(SW)FL=70.52'

#1695
STORM MANHOLE RIM=79.93' 24"RCP(N)FL=73.28' 24"RCP(SE)FL=73.28'

#1681
CURB INLET T/C=80.06' 18"RCP(N/W&SW)FL=74.75' 24"RCP(SE)FL=74.67'

#1697
CURB INLET T/C=79.86' 24"RCP(N/W)FL=74.50' 24"RCP(NE)FL=74.47' 12"PVC(SE)FL=75.09'

#1082
GRATE INLET GRATE=79.80' 12"PVC(NW)FL=75.25'

#2586
GRATE INLET GRATE=78.80' 12"HDPE(SE)=77.53' 18"RP(W)=74.65' 4"PVC(W)FL=78.00' 10"PVC(W)FL=75.18' 18"RCP(NE)FL=74.88'

#2755
GRATE INLET GRATE=80.60' 18"RCP(W)FL=75.22' 18"RCP(SE)FL=76.35' 4"PVC(NW)FL=79.05'

#2711
GRATE INLET TOP=81.73' VERTICAL PVC FL=78.33'


#2764
GRATE INLET TOP=80.99' UNABLE TO INVERT VERTICAL PVC FL; LID WARPED SHUT

| Curve Table | | | | | |
|---|---|---|---|---|---|
| Curve | Length | Radius | Delta | Chd Direction | Chd Length |


## EXISTING LINETYPE TABLE

- = ADJOINER LINE
- = BOUNDARY LINE
- = EASEMENT LINE
- = CURB AND GUTTER LINE
- = EDGE OF RAIL
- = EDGE OF BRICK
- = EDGE OF CONCRETE
- = EDGE OF ASPHALT
- = EDGE OF GRAVEL
- = FENCE (BARBED-WIRE)
- = FENCE (CHAIN-LINK)
- = FENCE (WOOD)
- = FENCE (WROUGHT-IRON)
- = GRADE BREAK
- = HIGH BANK
- OH = OVERHEAD ELECTRIC
- = PAVING STRIPES
- = STORM LINE CULVERT
- = TOE SLOPE
- = TREE LINE
- UGE = UNDERGROUND ELECTRIC LINE
- GAS = UNDERGROUND GAS LINE
- FO = UNDERGROUND FIBER OPTIC LINE
- TEL = UNDERGROUND TELEPHONE LINE
- STM = UNDERGROUND STORM LINE
- RLS = UNDERGROUND STORM LINE (REV)
- SAN = UNDERGROUND SANITARY LINE
- VAS = UNDERGROUND SANITARY LINE (REV)
- WL = UNDERGROUND WATER LINE

# SUGAR MILL ELEMENTARY SCHOOL




2 NO SCALE SWING GATE DETAIL




7" CONCRETE PAVEMENT
SCALE: N.T.S.

| LEGEND | | |
|---|---|---|
| DESCRIPTION | EXISTING | NEW |
| PROPERTY LINE | | |
| STORM SEWER LINE | | |
| SANITARY SEWER LINE | | |
| WATER LINE | | |
| GAS LINE | | |
| STORM SEWER INLET | □ | ■ |
| MANHOLE | ○ | ● |
| FIRE HYDRANT | ⊹ | |
| CONTOUR LINE | 85 | 93 |
| SPOT ELEVATION | 79.9 | TC 50.00 TOP OF CURB<br>TP 45.00 TOP OF PAVEMENT |
| SPOT ELEVATION | | TP 40.00 TOP OF PAVEMENT |
| SPOT ELEVATION | | TW 35.90 TOP OF WALK |
| SPOT ELEVATION | | EL 35.00 TOP OF GROUND |
| SPOT ELEVATION | | TW 50.00 TOP OF WALK<br>TP 45.00 TOP OF PAVEMENT |
| DRAINAGE FLOW | | ⇒ |
| EXTREME EVENT FLOW | | ⇨ |
| DRAINAGE DIVIDE | | |
| DRAINAGE AREA | | 0.05 AC |
| FENCE | | —o—o— |

## PAVEMENT NOTES

1. ALL PAVING SLOPES FROM SPOT ELEVATION TO SPOT ELEVATION AND SHALL BE UNIFORM AND CONSTANT.
2. PAVEMENT GRADES IN HANDICAP PARKING, LOADING/UNLOADING AREAS SHALL BE SLOPED AT 2.0% OR LESS.
3. ALL RAMPS DESIGNATED AS HANDICAP RAMPS SHALL BE SLOPED AT 8.33% (MAX)
4. CONCRETE PAVEMENT SHALL BE MINIMUM 3500 PSI AT 28 DAYS WITH A MINIMUM FLEXURAL STRENGTH OF 600 PSI AT 28 DAYS.
5. CONCRETE PAVEMENT SHALL HAVE A BROOM FINISH SURFACE BY DRAWING A FINE HAIR BROOM ACROSS CONCRETE SURFACE PERPENDICULAR TO LINE OF TRAFFIC.
6. CONCRETE SHALL BE CURED BY PROTECTING IT AGAINST LOSS OF MOISTURE, RAPID TEMPERATURE CHANGE, FOR AT LEAST 3 DAYS AFTER PLACEMENT. A LIQUID MEMBRANE-FORMING COMPOUND SHALL BE UNIFORMLY SPRAYED ON ALL EXPOSED SURFACES.

## PAVEMENT JOINTS

CONTRACTOR SHALL SUBMIT A CONCRETE JOINT LAYOUT PLAN FOR APPROVAL PRIOR TO PLACING CONCRETE PAVEMENT.

STATE OF TEXAS
F. H. RADFORD, III
61636
LICENSED PROFESSIONAL ENGINEER
07/18/2024


STANLEY SPURLING & HAMILTON, INC.
Consulting Engineering Services
T.B.P.E. Registration # F-000175
www.sshinc.net
3301 Edloe Street, Suite 200 Houston, Texas 77027 Tel 713-776-9433
E-MAIL: info@sshinc.net
0002-0255


SCALE: _____ DGN. BY: _____
DATE: _____ DWN. BY: _____
JOB NO. _____ DWG. NO. _____

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | 100% CD PKG. |

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT

SUGAR MILL ELEMENTARY SCHOOL
13707 Jess Pirtle Blvd, Sugar Land, TX 77498

SEAL

FOR
INTERIM REVIEW
AND NOT INTENDED FOR CONSTRUCTION, BIDDING OR PERMIT PURPOSES.


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 05/23/25

GRADING & PAVING PLAN

C1.0

Q:\0000\0002\0002-0255\CIVIL DWGS\C1.0 - GRADING AND SITE PLAN.dwg, Jul 15, 2025 - 1:47pm

# REFER TO FOODSERVICE DESIGN PROFESSIONALS SPECIFICATIONS AND SUBSEQUENT SHEETS FOR ADDITIONAL COORDINATION INFORMATION

**EXISTING EQUIPMENT NOTES (IF EXISTING EQUIPMENT IS PROVIDED IN THIS PROJECT):**

1. EXISTING EQUIPMENT NOT SCHEDULED FOR RE-USE TO BE RELOCATED BY THE K.E.C. COORDINATE WITH OWNER FOR NEW LOCATION.
2. ALL UTILITIES NOT SCHEDULED FOR RE-USE TO BE CAPPED & COVERED BY REQUIRED DISCIPLINE.
3. K.E.C. TO VERIFY ALL EXISTING UTILITY LOCATIONS & COORDINATE WITH ALL EQUIPMENT AS REQUIRED.

8 EXISTING EQUIPMENT NOTES
NOT TO SCALE

**ARCHITECT TO VERIFY/COORDINATE THE AESTHETIC OPTIONS BELOW (FOOD SERVICE COLOR, MATERIAL, OR SIGNAGE SELECTIONS) IF THESE ITEMS ARE PROVIDED IN THIS PROJECT:**

1. COUNTERTOPS: STONE (STAINLESS STEEL IS PROVIDED UNLESS OTHERWISE SPECIFIED).
2. TRAY SLIDES: CORIAN OR STONE (STAINLESS STEEL IS PROVIDED UNLESS OTHERWISE SPECIFIED).
3. COUNTER FRONTS: CERAMIC TILE, 3 FORM, OR PLASTIC LAMINATE.
4. SNEEZE GUARDS: STONE INSETS.
5. GENERAL COLOR, MATERIAL AND GRAPHIC SELECTIONS:
   - A. DISPLAY AIR SCREEN MERCHANDISERS - COLOR SELECTION: POWDER COAT OR PLASTIC LAMINATE (S/S IS PROVIDED UNLESS OTHERWISE SPECIFIED).
   - B. BAKERY DISPLAY CASES - COLOR SELECTION: POWDER COAT OR PLASTIC LAMINATE (S/S IS PROVIDED UNLESS OTHERWISE SPECIFIED).
   - C. PASS THRU OR REACH IN HOLDING CABINETS - COLOR SELECTION: POWDER COAT (MFG.: TRUE) OR PLASTIC LAMINATE (MFG.: TRAULSEN) (S/S IS PROVIDED UNLESS OTHERWISE SPECIFIED).
   - D. HANGING HEAT LAMPS - TRACK AND FIXTURE COLOR SELECTION.
   - E. HEATED MERCHANDISERS.
   - F. PORTABLE GUIDE RAILS - STANCHION AND BELT COLOR SELECTION.
   - G. POPCORN MACHINE - SIGNAGE SELECTION.
   - H. BOTTLE COOLER - SIGNAGE SELECTION.
   - I. GRAPHICS PACKAGE INFORMATION.
   - J. HOT FOOD WELL COVERS.
6. ARCHITECT TO VERIFY/COORDINATE THE FINISHES BELOW:
   - A. WALLS: CERAMIC TILE, FLAT FRP, OR MOLDED FRP (SMOOTH, IMPERVIOUS, AND EASILY CLEANABLE AS APPROVED BY LOCAL JURISDICTION).
   - B. CEILINGS: REMOVABLE VINYL FACE TILE (SMOOTH, IMPERVIOUS, AND EASILY CLEANABLE AS APPROVED BY LOCAL JURISDICTION).
   - C. FLOORS: TILE, EPOXY, OR RUBBERIZED FLOORING SYSTEM (SMOOTH, IMPERVIOUS, EASILY CLEANABLE AND SLIP RESISTANT AS APPROVED BY LOCAL JURISDICTION) (COORDINATE FLOOR TILE TRANSITION AT SERVING LINES).
   - D. FLOORS: WALK-IN ASSEMBLY - EXTEND KITCHEN FLOOR FLUSH INTO WALK-IN ASSEMBLY WITH COVED BASE.
   - E. FURR DOWNS ABOVE SERVING COUNTERS.

5 ARCHITECTURAL COORDINATION NOTES
NOT TO SCALE

**CRITICAL NOTES:**

1. CONTRACTOR MUST COORDINATE AND VERIFY ALL DIMENSIONS WITH FOOD SERVICE EQUIPMENT SHOP DRAWINGS AND MANUFACTURER'S DATA. DIMENSIONS SHOWN ARE FOR DESIGN AND BIDDING PURPOSES ONLY.
2. WALK-IN ASSEMBLY DOORS MUST BE LEFT OPEN WHILE INTERIOR CONCRETE FLOOR CURES.
3. INSTALL PROTECTIVE COVER ON WALK-IN ASSEMBLY WALL PANELS BEFORE INSTALLING CONCRETE FLOORS AND CURBS.
4. REFER TO GENERAL SPECS - DIVISION 27 TO PROVIDE CONDUIT, DATA, AND INTERCONNECT THE PANIC ALARM INSIDE FREEZER TO THE BUILDING AUTOMATION SYSTEM FOR NOTIFICATION TO DISTRICT PERSONNEL IN THE EVENT OF STAFF ENTRAPMENT.
5. PIPING AND DRAINAGE SYSTEMS (SANITARY AND GREASE-LADEN). SYSTEMS MUST BE CLEANED AND FLUSHED BEFORE THE FINAL CONNECTION WITH FOOD SERVICE EQUIPMENT - CRITICAL (DIV. 22).

7 CRITICAL NOTES
NOT TO SCALE

**DIVISION 26 (ELECTRICAL) IS RESPONSIBLE FOR BUT NOT LIMITED TO:**

1. **DO NOT ROUGH IN FROM FDP DRAWINGS. REFER TO THE KITCHEN EQUIPMENT CONTRACTOR'S DIMENSIONED SHOP DRAWINGS. DIMENSIONS INDICATED ARE TO BE VERIFIED BY KITCHEN EQUIPMENT CONTRACTOR AND ADJUSTED AS REQUIRED BY EQUIPMENT AND FIELD CONDITIONS.**
2. SECTION 11 40 00 TO VERIFY UTILITY REQUIREMENTS OF ANY EXISTING EQUIPMENT.
3. ALL CONNECTIONS SHALL BE MADE FOLLOWING LOCAL CODES AND NATIONAL STANDARDS, EXCEPT WHERE PLANS AND SPECIFICATIONS EXCEED THOSE CODES AND STANDARDS.
4. VERIFY ALL ELECTRICAL REQUIREMENTS WITH ENGINEERING DRAWINGS.
5. ROUGH-IN AND FINAL CONNECTION OF ELECTRICAL SYSTEMS TO FOOD SERVICE EQUIPMENT, WALK-IN ASSEMBLIES, AND BETWEEN COMPONENTS (INCLUDING MATERIALS AND LABOR). ACCESSORIES PROVIDED LOOSE WITH FOOD SERVICE EQUIPMENT BY SECTION 11 40 00 TO BE FIELD INSTALLED BY DIVISION 26.
6. EMPTY EMT CONDUIT WITH PULL-WIRE AND WIDE-SWEEP BENDS FOR REFRIGERANT PIPING TO REMOTE FOOD SERVICE EQUIPMENT REFRIGERATION SYSTEMS.
7. EMPTY EMT CONDUIT WITH PULL-WIRE AND WIDE-SWEEP BENDS FOR INTERCONNECT CABLES BETWEEN LAN AND POS TERMINALS, CHANGE-MAKERS, PRE-CHECK UNITS, PRINTERS, CPUS, ETC. DIVISION 26 TO VERIFY WHERE THE CONDUIT IS TO RUN FOR POS SYSTEM (I.E., MANAGER'S OFFICE OR IDF ROOM).
8. EMPTY EMT CONDUIT WITH PULL-WIRE AND WIDE-SWEEP BENDS FOR FIRE SUPPRESSION SYSTEMS. INTERCONNECT FIRE PROTECTION SYSTEM TO PANEL BOX SHUNT TRIPS AND BUILDING ALARM.
9. WALK-IN LIGHT FIXTURE INSTALLATION (PROVIDED LOOSE BY SECTION 11 40 00) (IF WALK-IN IS PROVIDED IN THIS PROJECT).
10. TABLE LIMIT SWITCH INSTALLATION (PROVIDED LOOSE BY SECTION 11 40 00) (IF DISHMACHINE IS PROVIDED IN THIS PROJECT).
11. ELECTRICAL MATERIALS AND DEVICES (SHUNT-TRIP BREAKERS, SURGE PROTECTORS, LIGHTING CONTROL DEVICES, CONDUIT, WIRE, ETC.).
12. SWITCHES AND STAINLESS STEEL DISCONNECTS AS REQUIRED (PROVIDE, LOCATE, AND INSTALL – TO BE IN AN ACCESSIBLE LOCATION).
13. CHARGING STATIONS FOR FORKLIFTS, PALLET STACKERS, AND PALLET JACKS (SIZE, PROVIDE, LOCATE, AND INSTALL) (IF EQUIPMENT IS PROVIDED IN THIS PROJECT).
14. INTERCONNECTION BETWEEN CONDENSATE FAN AND DISHMACHINE CONTROL PANEL (IF EQUIPMENT IS PROVIDED IN THIS PROJECT).
15. INTERCONNECTION BETWEEN EXHAUST HOOD FANS AND SWITCH (IF EQUIPMENT IS PROVIDED IN THIS PROJECT).
16. INTERCONNECTION BETWEEN EXHAUST HOOD LIGHTS AND SWITCH (IF EQUIPMENT IS PROVIDED IN THIS PROJECT).
17. DOOR HEATERS, LIGHTS, COILS, AND PRESSURE RELIEF PORTS PRE-WIRED TO JUNCTION BOX AT TOP OF WALK-IN ASSEMBLIES (IF EQUIPMENT IS PROVIDED IN THIS PROJECT) PROVIDED BY SECTION 11 40 00. FINAL CONNECTION BY DIV. 26.
18. IF ANY ELECTRICAL ACCESSORIES, FITTINGS, AND CORD/PLUGS ARE PROVIDED LOOSE WITH EQUIPMENT BY 11 40 00, DIV.26 IS TO ATTACH TO EQUIPMENT AND PROVIDE FINAL CONNECTION.
19. PROVIDE WATERPROOF RECEPTACLES IN WET AREAS.
20. ALL ELECTRICAL CONNECTIONS BENEATH EXHAUST HOODS (IF EQUIPMENT IS PROVIDED IN THIS PROJECT) TO EXTEND TO SHUNT TRIP BREAKERS WITH ELECTRICAL PANEL BOX FOR SHUTDOWN DURING FIRE MODE.
21. RECEPTACLES ARE TO BE PRE-WIRED TO THE JUNCTION BOX OR LOAD CENTER FOR FINAL CONNECTION BY DIVISION 26.
22. ALL ELECTRICAL LIGHTING, POWER, AND DISTRIBUTION SYSTEMS.
23. DO NOT INTERCONNECT MORE THAN THREE (3) CONVENIENCE OUTLETS ON ONE (1) BREAKER.
24. OTHER THAN CONVENIENCE OUTLETS, ALL ELECTRICAL CONNECTIONS SHOWN ON FOOD SERVICE PLANS ARE DEDICATED BREAKERS.
25. DOORBELL AT RECEIVING DOOR (PROVIDE AND INSTALL – TO BE AUDIBLE THROUGHOUT KITCHEN, OFFICE, AND DRY STORAGE ROOM).
26. ADEQUATE LIGHTING AT RECEIVING DOOR.
27. PROVIDE AND INSTALL TWO EMERGENCY STROBE BEACONS THAT INTERCONNECT TO PANIC ALARM IN WALK-IN FREEZER. ONE (1) IN KITCHEN ABOVE WALK-IN FREEZER DOOR ONE (1) IN CAFETORIUM (IF WALK-IN IS PROVIDED IN THIS PROJECT). REFER TO GENERAL SPECIFICATIONS FOR ADDITIONAL DETAILS.
28. DEDICATED CIRCUIT FOR HEATED DRAIN LINE CONNECTION IN WALK-IN FREEZER AT EACH COIL (IF WALK-IN IS PROVIDED IN THIS PROJECT).

**NOTE: ELECTRICAL CONNECTIONS INDICATED ARE THOSE REQUIRED FOR THE FOOD SERVICE EQUIPMENT AND THOSE REQUIRED FOR SUPPORT EQUIPMENT FURNISHED BY DIVISION 26. FOR ADDITIONAL REQUIREMENTS, REFER TO THE ELECTRICAL ENGINEER'S DRAWINGS.**

6 ELECTRICAL COORDINATION NOTES
NOT TO SCALE

**DIVISION 22 (PLUMBING) RESPONSIBLE FOR BUT NOT LIMITED TO:**

1. **DO NOT ROUGH-IN FROM FDP DRAWINGS. REFER TO THE KITCHEN EQUIPMENT CONTRACTOR'S DIMENSIONED SHOP DRAWINGS. DIMENSIONS INDICATED ARE TO BE VERIFIED BY KITCHEN EQUIPMENT CONTRACTOR AND ADJUSTED AS REQUIRED BY EQUIPMENT AND/OR FIELD CONDITIONS.**
2. SECTION 11 40 00 TO VERIFY UTILITY REQUIREMENTS OF ANY EXISTING EQUIPMENT.
3. ALL CONNECTIONS SHALL BE MADE IN ACCORDANCE WITH LOCAL CODES AND NATIONAL STANDARDS, EXCEPT WHERE PLANS AND SPECIFICATIONS EXCEED THOSE CODES AND STANDARDS.
4. VERIFY ALL PLUMBING REQUIREMENTS WITH ENGINEERING DRAWINGS.
5. EMPTY PVC CONDUIT WITH WIDE-SWEEP BENDS FOR REFRIGERANT PIPING TO BEVERAGE LINES, CO2 LINES, AND REMOTE FOOD SERVICE EQUIPMENT REFRIGERATION SYSTEMS.
6. ROUGH-IN AND FINAL PLUMBING CONNECTIONS TO FOOD SERVICE EQUIPMENT AND BETWEEN COMPONENTS (INCLUDING MATERIALS AND LABOR). ACCESSORIES PROVIDED LOOSE WITH FOOD SERVICE EQUIPMENT BY SECTION 11 40 00 TO BE FIELD INSTALLED BY DIVISION 22. THIS INCLUDES BUT IS NOT LIMITED TO INSTALLATION OF ALL FAUCETS (WATER FILL FAUCETS, PRE-RINSE FAUCETS, ETC.), HOSES, GAS DISCONNECTS, AND DRAINS FROM EQUIPMENT POINT OF CONNECTION TO BUILDING PLUMBING SYSTEMS. ALL DRAIN LINES ARE PROVIDED AND INSTALLED BY DIV. 22.
7. KITCHEN EQUIPMENT CONTRACTOR IS RESPONSIBLE FOR PROVIDING ALL FAUCETS (WATER FILL FAUCETS, PRE-RINSE FAUCETS, ETC.), DRAIN FITTINGS, MIXING VALVES, CONTROL VALVES, WATER PRESSURE REGULATORS, VACUUM BREAKERS, AND ALL ACCESSORIES FOR EQUIPMENT SPECIFIED UNDER 11 40 00. DIVISION 22 IS RESPONSIBLE FOR INSTALLATION.
8. INDIRECT DRAIN LINE RUNS FROM EQUIPMENT TO NEAREST DRAIN OR FLOOR SINK. LINES TO BE TYPE 'K' COPPER.
9. IF ANY PLUMBING ACCESSORIES OR FITTINGS ARE PROVIDED LOOSE WITH EQUIPMENT BY 11 40 00, DIV. 22 IS TO ATTACH TO EQUIPMENT AND PROVIDE FINAL CONNECTION.
10. GAS SUPPLY SYSTEMS WITH ALL COMPONENTS AND FITTINGS AS REQUIRED FOR A COMPLETE SYSTEM.
11. WATER SUPPLY SYSTEMS WITH ALL COMPONENTS AND FITTINGS AS REQUIRED FOR A COMPLETE SYSTEM.
12. COMPRESSED AIR SYSTEMS WITH ALL COMPONENTS AND FITTINGS AS REQUIRED FOR A COMPLETE SYSTEM (IF REQUIRED FOR THIS PROJECT).
13. PIPING AND DRAINAGE SYSTEMS (SANITARY AND GREASE-LADEN). SYSTEMS MUST BE CLEANED AND FLUSHED BEFORE THE FINAL CONNECTION WITH FOOD SERVICE EQUIPMENT - CRITICAL.
14. FLOOR SINKS (PROVIDE AND INSTALL). FLANGE AND GRATES TO BE FLUSH WITH FINISHED FLOOR.
15. FLOOR DRAINS (PROVIDE AND INSTALL). FLANGE AND GRATES TO BE FLUSH WITH FINISHED FLOOR.
16. TRENCH DRAINS (PROVIDE AND INSTALL). TRENCH LINERS PROVIDED BY 11 40 00. FLANGE AND LINERS TO BE FLUSH WITH FINISHED FLOOR.
17. GREASE TRAPS AS REQUIRED. VERIFY WITH LOCAL CODES TO BYPASS OR PIPE THRU GREASE TRAP AND/OR INTERCEPTOR.
18. P-TRAPS AS REQUIRED (INCLUDING ALL DISPOSERS).
19. INTERCONNECT WATER THRU WATER FILTER (FILTER PROVIDED BY 11 40 00 UNLESS OTHERWISE SPECIFIED) TO EQUIPMENT.
20. GAS QUICK DISCONNECT INSTALLATION (QUICK DISCONNECT PROVIDED BY 11 40 00).
21. SAFETY RESTRAINT CABLE INSTALLATION (SAFETY RESTRAINT CABLE PROVIDED BY 11 40 00).
22. SPECIFIED COUPLINGS AND PIPING TO ALL EQUIPMENT FURNISHED BY 11 40 00.
23. AIR COMPRESSORS (IF REQUIRED FOR THIS PROJECT) (SIZE, PROVIDE, AND INSTALL, UNLESS OTHERWISE SPECIFIED).
24. WATER SOFTENERS (IF REQUIRED FOR THIS PROJECT) (SIZE, PROVIDE, AND INSTALL, UNLESS OTHERWISE SPECIFIED).
25. PRESSURE BOILERS (IF REQUIRED FOR THIS PROJECT) (SIZE, PROVIDE, AND INSTALL, UNLESS OTHERWISE SPECIFIED).
26. HAND SINKS (PROVIDE (UNLESS OTHERWISE SPECIFIED) AND INSTALL). PROVIDE HOT WATER TEMPERING VALVE IF REQUIRED. WATER TEMPERATURE TO BE AT LEAST 100 DEGREES AND FLOW FOR AT LEAST 20 SECONDS.
27. ICE BIN DRAIN INSULATION (IF ICE MACHINE IS PROVIDED IN THIS PROJECT) (PROVIDE AND INSTALL).
28. UNIONS AT DISPOSER SOLENOID VALVES (IF DISPOSER IS PROVIDED IN THIS PROJECT) (PROVIDE AND INSTALL).
29. BACK FLOW PREVENTION AS REQUIRED (PROVIDE AND INSTALL - INCLUDING ALL DISPOSERS). BACK- SIPHONAGE SHALL BE INSTALLED AT ALL FIXTURES AND EQUIPMENT WHERE BACKFLOW AND/OR BACK-SIPHONAGE MAY OCCUR AND WHERE A MINIMUM AIR GAP CANNOT BE PROVIDED BETWEEN THE WATER TO THE FIXTURE OR EQUIPMENT AT ITS FLOOD/LEVEL RIM. VACUUM BREAKERS, WHEN FURNISHED WITH EQUIPMENT, SHALL OVERRIDE THE ABOVE, IF ACCEPTABLE WITH APPLICABLE CODES. DIVISION 22 RESPONSIBLE FOR VERIFYING REQUIREMENT WITH LOCAL CODES.
30. JANITOR SINK WITH FAUCET (PROVIDE AND INSTALL).
31. FREEZE PROOF HYDRANT AT EXTERIOR OF BUILDING BY RECEIVING DOOR (PROVIDE AND INSTALL).
32. REVERSE OSMOSIS SYSTEMS (SIZE, PROVIDE (UNLESS OTHERWISE SPECIFIED), LOCATE AND INSTALL).
33. ALL PIPING WITHIN COUNTER BODY OR UNDER FABRICATED COUNTERS TO BE RUN TO A CONNECTION POINT BELOW COUNTER BODY BY SECTION 11 40 00. FINAL CONNECTION BY DIVISION 22.
34. EXHAUST HOOD CONDENSATE DRAIN CONNECTIONS (IF EXHAUST HOOD IS PROVIDED IN THIS PROJECT) (PROVIDE AND INSTALL).
35. INTERCONNECTION OF 1/2" CW TO PRE-RINSE AND DISPOSERS CONE/BODY INLETS PIPED THROUGH SOLENOID AND VACUUM BREAKER (IF DISPOSER IS PROVIDED IN THIS PROJECT).
36. FIRE SYSTEM PIPING. EXPOSED PIPING TO BE CHROME PLATED.
37. PIPE 1/2" COLD WATER TO SWIRL INLETS AT DISPOSERS (IF DISPOSER IS PROVIDED IN THIS PROJECT).
38. WATER TREATMENT FOR ICE BUILDERS (NON-CHLORINATED WATER WITH A PH LEVEL OF 10 OR HIGHER) AND ANY DRAINS AND OVERFLOWS. PIPING FROM ICE BUILDERS TO TUMBLE CHILLERS BY DIV. 23 (IF ICE BUILDERS AND TUMBLE CHILLERS ARE PROVIDED IN THIS PROJECT).

**NOTE: WATER AND DRAIN CONNECTIONS INDICATED ARE THOSE REQUIRED FOR THE FOOD SERVICE EQUIPMENT AND THOSE REQUIRED FOR SUPPORT EQUIPMENT FURNISHED BY DIVISION 22. FOR ADDITIONAL WATER AND DRAIN REQUIREMENTS REFER TO MECHANICAL DRAWINGS.**

**NOTE: REFER TO ELECTRICAL/MECHANICAL DRAWINGS FOR REQUIREMENTS OF EXHAUST FANS AND MAKE-UP AIR HANDLERS AND LOCATION OF AN INTERLOCK AND START/STOP CONTROLS TO BE LOCATED WITHIN FOOD SERVICE AREA BY DIVISION 26.**

4 PLUMBING COORDINATION NOTES
NOT TO SCALE

**DIVISION 23 (MECHANICAL) RESPONSIBLE FOR BUT NOT LIMITED TO:**

1. **DO NOT ROUGH-IN FROM FDP DRAWINGS. REFER TO THE KITCHEN EQUIPMENT CONTRACTOR'S DIMENSIONED SHOP DRAWINGS. DIMENSIONS INDICATED ARE TO BE VERIFIED BY KITCHEN EQUIPMENT CONTRACTOR AND ADJUSTED AS REQUIRED BY EQUIPMENT AND/OR FIELD CONDITIONS.**
2. SECTION 11 40 00 TO VERIFY UTILITY REQUIREMENTS OF ANY EXISTING EQUIPMENT.
3. ALL CONNECTIONS SHALL BE MADE FOLLOWING LOCAL CODES AND NATIONAL STANDARDS, EXCEPT WHERE PLANS AND SPECIFICATIONS EXCEED THOSE CODES AND STANDARDS.
4. VERIFY ALL MECHANICAL REQUIREMENTS WITH ENGINEERING DRAWINGS.
5. EMPTY EMT CONDUIT WITH PULL-WIRE AND WIDE-SWEEP BENDS FOR REFRIGERANT PIPING TO REMOTE FOOD SERVICE EQUIPMENT REFRIGERATION SYSTEMS.
6. ROUGH-IN AND FINAL CONNECTION OF MECHANICAL SYSTEMS TO FOOD SERVICE EQUIPMENT, WALK-IN ASSEMBLIES, AND BETWEEN COMPONENTS (INCLUDING MATERIALS AND LABOR).
7. TESTING AND BALANCING FOR ROOMS AND EXHAUST HOODS TO BE PERFORMED BY MECHANICAL CONTRACTOR. BALANCE REPORT FOR FOOD SERVICE EXHAUST HOODS TO BE PROVIDED TO FOODSERVICE DESIGN PROFESSIONALS (FDP) IMMEDIATELY UPON COMPLETION (SEND TO HOUSTON.SUBMITTAL@FDP.ORG FOR HOUSTON OFFICE AND DALLAS.SUBMITTAL@FDP.ORG FOR DALLAS OFFICE) AND MUST BE SUBMITTED WITH O&M MANUALS.
8. EXHAUST HOODS, CONDENSATE HOODS, FIRE SUPPRESSION SYSTEMS, CONNECTIONS AND CONTROLS (PROVIDE AND INSTALL – *UNLESS OTHERWISE SPECIFIED*). PROVIDE TEMPERED AIR AT ALL SUPPLY DUCTS.
   - A. IF EXHAUST/CONDENSATE HOODS AND FIRE SUPPRESSION SYSTEMS ARE SPECIFIED UNDER SECTION 11 40 00, DIVISION 23 IS RESPONSIBLE FOR ALL EXHAUST AND CONDENSATE HOOD CONNECTIONS (PROVIDE AND INSTALL).
9. VFD SYSTEM AND CONTROLLERS, WHEN REQUIRED BY CODE (PROVIDE AND INSTALL).
10. PROVIDE AND INSTALL ALL VENTILATION (DIRECT OR INDIRECT), AIR CONDITIONING AND HEATING SYSTEMS (UNLESS OTHERWISE SPECIFIED).
11. COORDINATE SUPPLY AND RETURN DUCTS ABOVE SERVING COUNTERS OR OPEN-AIR REFRIGERATED MERCHANDISERS. NO COLD AIR TO BLOW DIRECTLY ON HOT FOOD COUNTERS.
12. COORDINATE SUPPLY AND RETURN DUCTS AWAY FROM EQUIPMENT WITH TOP MOUNTED REFRIGERATION. NO COLD AIR TO BLOW DIRECTLY ON COMPRESSORS.
13. MECHANICAL CONTRACTOR TO LOCATE TEMPERATURE MONITORS WITHIN RETURN DUCTS.
14. CIRCULATING AIR ABOVE WALK-IN ASSEMBLIES (PROVIDE AND INSTALL).
15. CIRCULATING AIR ABOVE AND IN AIR GAPS AT WAREHOUSE COLD STORAGE ASSEMBLIES (PROVIDE AND INSTALL).
16. WATER CHILLERS AS REQUIRED (IF EQUIPMENT IS PROVIDED IN THIS PROJECT) (PROVIDE, SIZE AND LOCATE).
17. PIPING FROM ICE BUILDERS TO TUMBLE CHILLERS (IF EQUIPMENT IS PROVIDED IN THIS PROJECT) (PROVIDE, SIZE AND LOCATE).

3 MECHANICAL COORDINATION NOTES
NOT TO SCALE

**GENERAL CONTRACTOR RESPONSIBLE FOR BUT NOT LIMITED TO:**

1. ANY WALL PENETRATION REQUIRED FOR FOOD SERVICE EQUIPMENT UTILITIES. ESCUTCHEON PLATES OR S/S SLEEVES TO BE PROVIDED AND INSTALLED AS NEEDED.
2. BULK FREEZER VENTILATION PIPE (IF BULK FREEZER IS PROVIDED IN THIS PROJECT) (PROVIDE AND INSTALL, UNLESS OTHERWISE SPECIFIED).
3. CORE DRILLING FOR GUIDE RAILS (IF GUIDE RAILS ARE PROVIDED IN THIS PROJECT).
4. REFRIGERATION ROOF CURBS / ROOF JACK (IF REFRIGERATION SYSTEM IS PROVIDED IN THIS PROJECT AND LOCATED ON ROOF).
5. INTERIOR BOLLARDS (IF REQUIRED FOR THIS PROJECT) – TO BE EPOXY PAINTED PER LOCAL CODES (PROVIDE AND INSTALL).
6. FURNISH AND INSTALL 3/4" PLYWOOD BLOCKING IN THE WALL FOR MOUNTING EQUIPMENT FURNISHED BY SECTION 11 40 00 AS REQUIRED.
7. WALK-IN DEPRESSIONS (TO BE DEAD LEVEL) AND SAND LEVELING BED (IF WALK-IN IS PROVIDED IN THIS PROJECT AND RECESS IS SHOWN).
8. STRUCTURAL BRACING FOR BULK WALK-IN CEILING PANELS IF REQUIRED.
9. MENU SYSTEM VIDEO MONITORS IN SERVERY (UNLESS OTHERWISE SPECIFIED).
10. STRUCTURAL BRACING FOR MENU SYSTEM VIDEO MONITORS IF REQUIRED.
11. INTERIOR/EXTERIOR REFRIGERATION PENETRATIONS AND SLEEVES AT BUILDING PENETRATIONS.
12. DOORSCOPE VIEWER (PEEPHOLE) WITH WIDE VIEWING ANGLE AT RECEIVING DOOR.
13. CANOPY AT RECEIVING DOOR. COORDINATE HEIGHT WITH THE HEIGHT OF RECEIVING DOOR (8') AND THE MOUNTING HEIGHT OF AIR SCREEN ABOVE THE DOOR.
14. SOAP AND TOWEL DISPENSER PROVIDED BY OWNER. G.C. RESPONSIBLE FOR INSTALLATION.
15. WASHER AND DRYER (PROVIDE AND INSTALL, UNLESS OTHERWISE SPECIFIED).
16. DWARF WALL AT EXPOSED FRONT/ENDS OF CAFETERIA SERVING COUNTERS WITH FINISH AS SELECTED BY ARCHITECT (IF REQUIRED IN THIS PROJECT).

2 GENERAL CONTRACTOR COORDINATION NOTES
NOT TO SCALE

**HEALTH DEPARTMENT REQUIREMENTS (VERIFY WITH LOCAL JURISDICTIONS):**

1. FLOORS: VERIFY WITH DIVISION 9. FLOORS TO BE SMOOTH, IMPERVIOUS, EASILY CLEANABLE AND SLIP RESISTANT.
2. WALLS: VERIFY WITH ARCHITECTURAL DOCUMENTS. WALLS TO BE SMOOTH, IMPERVIOUS, AND EASILY CLEANABLE.
3. CEILING: LAY-IN TILES. CEILING TILES TO BE SMOOTH, IMPERVIOUS, AND EASILY CLEANABLE.
4. EMPLOYEE TOILET: TO BE LOCATED OFF MAIN CORRIDOR AND ADJACENT TO MAIN KITCHEN. RESTROOM MUST HAVE A VESTIBULE AND NOT OPEN TO KITCHEN / PREP AREAS. TOILETS TO BE WELL VENTILATED.
5. LAVATORIES: WALL HUNG LAVATORIES LOCATED WITHIN ALL FUNCTIONAL WORKING AREAS.
6. UTENSIL CLEANING/SANITIZING: ACCOMPLISHED IN UTENSIL WASH AREA WITH (3) 2'-0" x 2'-2" x 15" MINIMUM DEEP SINKS AND WAREWASH MACHINE.
7. MECHANICAL CLEANING/SANITIZING OF TABLEWARE: ACCOMPLISHED BY WAREWASH MACHINE.
8. STOREROOMS: AMPLE DAILY STORAGE PROVIDED IN ENCLOSED STORE ROOMS. STORE ROOMS TO BE VENTILATED AND MAINTAIN PROPER TEMPERATURE.
9. WATER HEATER: LOCATED IN THE MECHANICAL ROOM ADJACENT TO KITCHEN. TO BE SIZED TO PROVIDE AMPLE WATER TO MAINTAIN PROPER WATER TEMPERATURE THROUGHOUT HOURS OF OPERATION.
10. GREASE TRAP: LOCATED AT EXTERIOR OF BUILDING. REFER TO ENGINEER'S DRAWINGS.
11. FOOD SERVICE EQUIPMENT: ALL FLOOR-MOUNTED EQUIPMENT IS TO BE SEALED TO THE FLOOR TO PROVIDE AN EASILY CLEANABLE SURFACE AND PREVENT SEEPAGE. EQUIPMENT NOT MOUNTED TO THE FLOOR IS TO BE WALL MOUNTED ON WALL CARRIERS, OR ELEVATED ON LEGS TO PROVIDE AT LEAST A SIX-INCH CLEARANCE BETWEEN FLOOR AND EQUIPMENT.
12. MOP SINK: LOCATED IN JANITOR CLOSET OFF MAIN KITCHEN CORRIDOR, AND LOCATED IN CLOSE PROXIMITY TO THE SERVERY WAREWASH AREA.
13. EXHAUST HOODS: EXHAUST HOODS PROVIDED OVER COOKING EQUIPMENT WITH LIQUID CHEMICAL ANSUL FIRE EXTINGUISHING SYSTEM.
14. LIGHTING AND PROTECTIVE SHIELDING: RECESSED CEILING-MOUNTED FLUORESCENT LIGHT FIXTURES FITTED WITH CLEAR LEXAN DIFFUSERS.
15. GARBAGE AND REFUSE: CENTRAL TRASH COLLECTION PROVIDED FOR BUILDING LOCATED NEAR RECEIVING AREA ON SMOOTH CONCRETE SURFACE.
16. POISONOUS AND TOXIC MATERIAL STORAGE: LOCATED IN RESPECTIVE JANITOR CLOSETS WITH LOCKING HARDWARE.

1 HEALTH DEPARTMENT COORDINATION NOTES
NOT TO SCALE

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT

SUGAR MILLS ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD
SUGAR LAND, TX 77498

SEAL

FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025 APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 48854119 ON: 07/18/2025



ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

FS GENERAL COORDINATION NOTES

U-QF0.0

| FOOD SERVICE DRAWING INDEX | |
|---|---|
| FDP SHEET NUMBER | FDP SHEET NAME |
| U-QF0.0 | FS GENERAL COORDINATION NOTES |
| U-QF1.0 | FS EQUIPMENT PLAN |
| U-QF1.1 | FS FACILITY MODEL |
| U-QF1.2 | FS EQUIPMENT MODEL |
| U-QF1.3 | FS SPECIAL CONDITIONS & MECHANICAL PLAN |
| U-QF1.4 | FS PLUMBING PLAN |
| U-QF1.5 | FS ELECTRICAL PLAN |
| U-QF1.6 | FS CONDENSING UNITS |
| U-QF1.7 | FS WALK-INS |
| U-QF1.8 | FS SERVING COUNTERS |
| U-QF1.9 | FS SERVING COUNTERS |
| U-QF2.0 | FS DEMO PLAN |
| U-QF2.1 | FS TEMPORARY SERVING |
| U-QF3.1 | FS ELEVATIONS |
| U-QF4.1 | FS SECTIONS & DETAILS |
| U-QF4.2 | FS DETAILS |
| U-QF4.3 | FS DETAILS |




1 FOOD SERVICE EQUIPMENT PLAN
1/4" = 1'-0"

| FOOD SERVICE EQUIPMENT SCHEDULE | | | | | |
|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR GENERAL CONTRACTOR & HEALTH DEPARTMENT COORDINATION NOTES | | | | | |
| FDP ITEM | FDP QTY | FDP DESCRIPTION | FDP REMARKS | MANUFACTURER | MODEL |
| 101 | 1 | AIR SCREEN | | MARS | STD248-1UA-OB |
| 102 | 1 | COLD STORAGE ASSEMBLY | | AMERICAN PANEL | |
| 103 | 1 | COLD STORAGE REFRIGERATION SYSTEM | | | |
| 104 | 2 | COLD STORAGE SHELVING | | METRO | METROMAX Q |
| 107 | 1 | DRY STORAGE SHELVING | | METRO | METROMAX Q |
| 108 | 1 | CAN RACK | | NEW AGE | 1250CK |
| 109 | 1 | ICE MACHINE W/ BIN | | MANITOWOC | UYF0310A |
| 110 | 1 | CLOTHES WASHER | | WHIRLPOOL | RESIDENTIAL |
| 110A | 1 | CLOTHES DRYER | | WHIRLPOOL | RESIDENTIAL |
| 111W | 1 | WALL MOUNTED OVERSHELF | | CUSTOM FABRICATED | |
| 122 | 1 | TWO COMPARTMENT SINK WITHOUT DISPOSER | | CUSTOM FABRICATED | |
| 123 | 1 | DISPOSER - 3HP | | SALVAJOR | 300-CA-18-ASRR-LD |
| 125 | 1 | 20 QT. MIXER W/STAND | | HOBART | HL200 |
| 128 | 4 | UTILITY CART | | LAKESIDE | 522 |
| 129 | 3 | WORKTABLE W/S.BAR UT.RACK | | CUSTOM FABRICATED | |
| 138 | 4 | PAN RACK | | CRES COR | 207-UA-13A |
| 139 | 1 | INSUL MOBILE PROOFER | | CRES COR | H-137-WSUA-12D |
| 151 | 2 | FIRE PROTECTION SYSTEM | | ANSUL | R102 |
| 152 | 1 | EXHAUST HOOD | EXISTING | | |
| 153 | 1 | EXHAUST HOOD | EXISTING | | |
| 161 | 2 | CONVECTION OVEN | | BLODGETT | DFG-200 DBL |
| 165 | 1 | TWO BURNER RANGE | | VULCAN | V2B18B |
| 172 | 1 | COMBI OVEN | | RATIONAL | ICP 6-FULL/6-FULL N/G |
| 186 | 2 | PASS-THRU HEATED CABINET-1DR | | TRAULSEN | AHF132WP |
| 188 | 2 | PASS-THRU REFRIGERATOR-1DR | | TRAULSEN | AHT132WPUT |
| 201M.1 | 1 | SERVING COUNTER-MODULAR | | COUNTERCRAFT | SCOL-408-MOD |
| 214 | 2 | CASH REGISTER | OWNER FURNISHED | | |
| 249 | 1 | THREE COMPARTMENT SINK NO DISPOSER | | CUSTOM FABRICATED | |
| 250 | 1 | DISHMACHINE | | HOBART | CL44-BAS |
| 254 | 2 | SOILED & CLEAN DISHTABLE | | CUSTOM FABRICATED | |
| 255 | 2 | MOBILE DRYING RACK | | METRO | PR48VX3 |
| 260 | 4 | HAND SINK | FURNISHED & INSTALLED BY DIV. 22 | | |
| 614 | 1 | FILL FAUCET | | T&S | B-0610 |
| 615 | 2 | MENU MONITOR | BY OWNER | | |
| 800 | 1 | 15 GAL. BRAISING PAN | | GROEN | BPM-15GA |
| 801 | 1 | S/S CORNER GUARDS | LOCATED ON EVERY EXPOSED CORNER THROUGHOUT KITCHEN | CUSTOM FABRICATED | |
| 802 | 1 | WALL BUMPERS | LOCATED ON ALL EXPOSED BUILDING WALLS | PAWLING | MD-1 |
| 803 | 1 | WATER SOFTENER | | HOBART | WS-40 |
| 804 | 4 | S/S SPLASH GUARDS | | CUSTOM FABRICATED | |

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILLS ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD
SUGAR LAND, TX 77498


SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
7/15/2025 APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 48854119 ON: 07/18/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS EQUIPMENT PLAN

U-QF1.0

ISOMETRIC VIEWS WITHIN THIS DRAWING ARE NOT TO SCALE AND ARE PROVIDED FOR REFERENCE PURPOSES ONLY. ISOMETRIC VIEWS ARE NOT INTENDED FOR REGULATORY APPROVAL, PERMITTING, NOR CONSTRUCTION. REFER TO FLOOR PLANS AND DETAILS FOR SPECIFIC PROJECT INFORMATION.



1 FS FACILITY MODEL

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILLS ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD
SUGAR LAND, TX 77498

SEAL

FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025 APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 48854119 ON: 07/18/2025

ARCHITECTS


ARCHITECTS
AND PLANNING
CONSULTANTS

11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS FACILITY MODEL

U-QF1.1

ISOMETRIC VIEWS WITHIN THIS DRAWING ARE NOT TO SCALE AND ARE PROVIDED FOR REFERENCE PURPOSES ONLY. ISOMETRIC VIEWS ARE NOT INTENDED FOR REGULATORY APPROVAL, PERMITTING, NOR CONSTRUCTION. REFER TO FLOOR PLANS AND DETAILS FOR SPECIFIC PROJECT INFORMATION.



1 FS EQUIPMENT MODEL

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILLS ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD
SUGAR LAND, TX 77498

SEAL

FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
FCSI
468854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025 THESE ITEMS ON THIS SHEET PREPARED BY OR UNDER MY SUPERVISION MELISSA MOORE, FCSI NO. 468854119 ON: 07/18/2025


ARCHITECTS

ARCHITECTS
AND PLANNING
CONSULTANTS


11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS EQUIPMENT MODEL

U-QF1.2


| FOOD SERVICE MECHANICAL SCHEDULE | | | | | | |
|---|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR MECHANICAL COORDINATION NOTES | | | | | | |
| FDP NO. | FDP QTY | FDP TYPE | FDP SIZE | FDP LOC | FDP CFM | FDP S.P. |
| M101 | 1 | EXHAUST | 4" X 16" | | 400 | 0.30" |
| M102 | 1 | EXHAUST | 4" X 16" | | 800 | 0.30" |
| M103 | 1 | DRYER VENT | 6" DIA. | | --- | --- |

NOTE:
SECTION 11 40 00 TO COORDINATE FINAL LOCATION AND SIZE OF WALL BLOCKING.





5 WALL BLOCKING DETAIL
NOT TO SCALE


NOTE:
SECTION 11 40 00 TO COORDINATE FINAL LOCATION OF ALL TRENCH LINERS WITH EQUIPMENT POUR PATH.





6 TRENCH LINER DETAIL
NOT TO SCALE




1 FOOD SERVICE SPECIAL CONDITIONS PLAN
1/4" = 1'-0"





3 COLD STORAGE ASSEMBLY ENCLOSURE PANEL DETAIL
NOT TO SCALE




COLD STORAGE ASSEMBLY REFRIGERATION SYSTEM GROUND MOUNT 4" PLATFORM DETAIL
4 NOT TO SCALE

SLAB TO BE MODIFIED AS REQUIRED TO ALLOW FOR A 4 1/2" DEPRESSION SLAB. PROVIDE NEW LEVEL CONCRETE PAD FOR COLD STORAGE ASSEMBLY.




WALL SECTION @ EXTERIOR DOOR

2 COLD STORAGE ASSEMBLY 4 1/2" DEPRESSION DETAIL
NOT TO SCALE

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILLS ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD
SUGAR LAND, TX 77498

SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
FCSI
48054119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO: 48054119 ON: 07/18/2025


ARCHITECTS

ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS SPECIAL CONDITIONS & MECHANICAL PLAN

U-QF1.3

| FOOD SERVICE PLUMBING SCHEDULE | | | | | | |
|---|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR PLUMBING COORDINATION NOTES | | | | | | |
| FDP PNO | FDP PSIZE | FDP PCONN | FDP PSERVICE TO | FDP PLOC | FDP PAFF | FDP PREMARKS |
| P5 | 3/4" | H & C WATER | JANITOR SINK | WALL | 48" | JANITOR SINK BY PLUMBER |
| P6 | 4" | FLOOR DRAIN | JANITOR SINK | FLOOR | VERIFY | JANITOR SINK BY PLUMBER |
| P7 | 3/4" | H & C WATER | HOSE BIBB | WALL | 18" | BTC |
| P10 | VERIFY | FLOOR DRAIN | GENERAL AREA DRAIN | FLOOR | VERIFY | --- |
| P11C | 1/2" | H & C WATER | FAUCET | WALL | 18" | FURNISHED & INSTALLED BY DIV. 22 |
| P11D | 1 1/2" | DIRECT DRAIN | HAND SINK | WALL | 15" | FURNISHED & INSTALLED BY DIV. 22 |
| P12 | VERIFY | FLOOR DRAIN | EQUIP. DRAIN | FLOOR | VERIFY | NO SLOPE |
| P15 | 4" | FLOOR DRAIN | FUNNEL FLOOR DRAIN | FLOOR | 0" | --- |
| P109 | 3/4" | COLD WATER | WATER/ ICE | WALL | 60" | BTC |
| P109A | 12" SQ. | FLOOR SINK | ICE MACHINE | FLOOR | 0" | FULL GRATE |
| P110 | 3/4" | H & C WATER | CLOTHES WASHER | WALL | 48" | BTC; VALVE BOX |
| P110A | 2" | INDIRECT DRAIN | CLOTHES WASHER | WALL | 48" | VALVE BOX |
| P122 | 3/4" | H & C WATER | FAUCET | WALL | 13" | BTC |
| P122A | 12" SQ. | FLOOR SINK | SINK | FLOOR | 0" | 3/4 GRATE |
| P123 | 3/4" | H & C WATER | FAUCET / DISPOSER | WALL | 13" | BTC |
| P123A | 2" | DIRECT DRAIN | DISPOSER | WALL | 10" | BTC |
| P161 | (2)3/4" | NATURAL GAS | CONVECTION OVEN | WALL | 18"/36" | BTC - 60 MBTU/HR EACH |
| P163A | 3/4" | NATURAL GAS | TILT BRAISING PAN | WALL | 18" | BTC - 65 MBTU/HR |
| P163B | 3/4" | H & C WATER | TILT BRAISING PAN | WALL | 36" | BTC |
| P165 | 1" | NATURAL GAS | RANGE | WALL | 18" | BTC - 70 MBTU/HR |
| P172 | (2)3/4" | COLD WATER | COMBI OVEN | WALL | 24"/48" | BTC - INTERCONNECT THRU FILTERS |
| P172A | 3/4" | COLD WATER | COMBI OVEN | WALL | 48" | BTC |
| P172B | 12"SQ. | FLOOR SINK | EQUIPMENT | FLOOR | 0" | 3/4 GRATE |
| P172C | (2)3/4" | NATURAL GAS | COMBI OVEN | WALL | 18"/36" | BTC: 105 MBTU/HR EACH |
| P172D | 3/4" | COLD WATER | COMBI OVEN | WALL | 66" | BTC; INTERCONNECT TO P172 |
| P172E | 3/4" | COLD WATER | COMBI OVEN WATER FILTER | WALL | 66" | BTC |
| P249 | 3/4" | H & C WATER | FAUCET | WALL | 13" | BTC |
| P249A | 12" SQ. | FLOOR SINK | SINK | FLOOR | 0" | THREE QUARTER GRATE |
| P250 | 12" SQ. | FLOOR SINK | BOOSTER / DISHMACHINE | FLOOR | 18" | BTC |
| P250A | 3/4" | HOT WATER | DISHMACHINE | WALL | 18" | EXT. THRU W.FILTER TO BOOSTER / DISH MACHINE - 140DEG.MIN. |
| P250B | 3/4" | COLD WATER | DISHMACHINE | WALL | 18" | BTC |
| P614 | 1/2" | H & C WATER | FILL FAUCET | WALL | 42" | BTC |
| P800 | 12" SQ. | FLOOR SINK | EQUIPMENT | FLOOR | 0" | 3/4 GRATE |




1 FOOD SERVICE PLUMBING PLAN
1/4" = 1'-0"

SECTION 11 40 00 TO PROVIDE LOOSE WITH FOOD SERVICE EQUIPMENT. INSTALLATION BY DIV. 22 & 26.


- (A) VACUUM BREAKER
- (B) DISPOSER
- (C) TIME DELAY
- (D) CONTROL PANEL
- (E) SOLENOID VALVE

DIVISION 22 TO PROVIDE AND INSTALL


- (F) 1/2" CW INLET
- (G) FLOW CONTROL
- (H) 1/2" CW
- (I) 2" DRAIN LINE WITH P-TRAP & Y ADAPTOR
- (J) 1-1/2" TAILPIECE
- (K) GATE VALVE
- (L) 1/2" CW SUPPLY
- (M) SHOCK STOP
- (N) RPZ BACK FLOW PREVENTOR

DIVISION 26 TO PROVIDE AND INSTALL


- (O) POWER SUPPLY





6 DISPOSER WITH VACUUM BREAKER DETAIL
NOT TO SCALE





7 EXHAUST HOOD - GAS LINE ROUTING DETAIL
NOT TO SCALE




3 GAS DISCONNECT DETAIL
NOT TO SCALE




5 DRAIN PIPING FASTENER DETAIL
NOT TO SCALE




8 WAREWASH - PERFORATED OVER SHELF DETAIL
NOT TO SCALE

| | | | | | |
|---|---|---|---|---|---|
| HW | HOT WATER | FFD | FUNNEL FLOOR DRAIN | | |
| CW | COLD WATER | EVC | EXHAUST VENT CONNECTION | | |
| HTW | 180 F HOT WATER | SVC | SUPPLY VENT CONNECTION | | |
| | CHILLED WATER | FR | DIRECT-CONNECTED FLUE RISER | | |
| W | DIRECT WASTE | PS | PIPE SLEEVE | | |
| IW | INDIRECT WASTE | | COMPRESSED AIR | | |
| | GAS SUPPLY | | CO2 | | |
| | STEAM SUPPLY | AFF | ABOVE FINISHED FLOOR | | |
| CR | CONDENSATE RETURN | BTC | BRANCH TO CONN. ON EQUIP | | |
| DR | DRAIN | DFA | DROP FROM ABOVE | | |
| FD | FLOOR DRAIN | CLG | CEILING | | |
| FST | FLOOR SINK 3/4 GRATE | | | | |
| FSH | FLOOR SINK 3/4 GRATE | | | | |

2 PLUMBING SYMBOLS
NOT TO SCALE

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FDP
FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILLS ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD
SUGAR LAND, TX 77498

SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
FCSI 48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 48854119 ON: 07/18/2025



ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS PLUMBING PLAN


U-QF1.4


| FOOD SERVICE ELECTRICAL SCHEDULE | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR ELECTRICAL COORDINATION NOTES | | | | | | | | |
| FDP ENO | FDP ECONN | FDP ELOAD | FDP EVOLT | FDP EPH | FDP ESERVICE TO | FDP ELOC | FDP EAFF | FDP EREMARKS |
| E10 | DR | 16.0A | 120 | 1 | CONVENIENCE | WALL | 24" | MOUNT HORIZONTAL |
| E13 | WPR | 16.0A | 120 | 1 | CONVENIENCE | WALL | 24" | MOUNT HORIZONTAL |
| E15 | JB | --- | --- | --- | FIRE PROT. SYSTEM | WALL | 48" | RECESSED EMPTY CONDUIT FOR FIRE PULL |
| E101 | JB | 5.1A | 120 | 1 | AIR SCREEN | WALL | 82" | BTC; MAGNETIC REED SWITCH ON DOOR JAMB & DOOR |
| E102A | JB | 16.0A | 120 | 1 | DOOR HEATER/LIGHTS | CLG | DFA | BTC |
| E102B | JB | 5.0A | 120 | 1 | TEMP. ALARM | CLG | DFA | BTC |
| E102C | JB | 5.0A | 120 | 1 | PRESSURE RELIEF PORT | CLG | DFA | BTC |
| E102E | JB | 10.0A | 120 | 1 | PANIC ALARM BUTTON | CLG | DFA | BTC-INTERCONNECT TO STROBE LIGHT/HORN ABOVE FREEZER DOOR AND IN CAFETORIUM |
| E103 | JB/DS | 21.9A | 208 | 3 | REFRIGERATION SYSTEM | VERIFY | VERIFY | BTC |
| E103C | JB | 9.1A | 208 | 1 | FREEZER COIL | CLG | DFA | BTC |
| E103D | JB | 1.8A | 120 | 1 | COOLER COIL | CLG | DFA | BTC |
| E103E | JB | --- | --- | --- | DATA CONNECTION | CLG | DFA | BTC; RUN TO NEAREST IDF / MDF ROOM |
| E103F | JB | 16.0A | 120 | 1 | DRAIN LINE HEATER | CLG | DFA | BTC; DEDICATED CIRCUIT |
| E109 | DR | 11.9A | 120 | 1 | ICE MACHINE | WALL | 60" | --- |
| E110 | DR | 16.0A | 120 | 1 | CLOTHES WASHER | WALL | 48" | -- |
| E110A | SR | 30.0A | 208 | 1 | CLOTHES DRYER | WALL | 48" | VERIFY NEMA PLUG RECEPTACLE |

| FOOD SERVICE ELECTRICAL SCHEDULE | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| REFER TO SHEET QF1 FOR ELECTRICAL COORDINATION NOTES | | | | | | | | |
| FDP ENO | FDP ECONN | FDP ELOAD | FDP EVOLT | FDP EPH | FDP ESERVICE TO | FDP ELOC | FDP EAFF | FDP EREMARKS |
| E123 | JB | 3.0HP | 208 | 3 | DISPOSER | WALL | 24" | BTC; CONNECT THRU C.P. TO DISPOSER |
| E129 | DCR | 16.0A | 120 | 1 | TABLE RECEPTACLE | CLG | 84" | TWISTLOCK PLUG & RECEPTACLE |
| E139 | DCR | 15.0A | 120 | 1 | INSUL. MOBILE PROOFER | CEILING | DFA | -- |
| E151 | JB | 1.0A | 120 | 1 | FIRE PROT. SYSTEM | CLG | DFA | BTC; RE: NOTE #4, #6, #9 & #11 |
| E161 | (2)DR | 6.0A EA. | 120 | 1 | CONVECTION OVEN | WALL | 24"/48" | SHUNT TRIP BREAKER |
| E163 | DR | 5.0A | 120 | 1 | TILT BRAISING PAN | WALL | 24" | SHUNT TRIP BREAKER |
| E172 | (2)JB | 15.0A EA. | 208 | 1 | COMBI OVEN | WALL | 24"/48" | BTC- SHUNT TRIP BREAKER |
| E187 | JB | 15.5A | 120/208 | 1 | HEATED CABINET | WALL | 96" | BTC; MOUNT ON KITCHEN SIDE |
| E188 | JB | 7.2A | 120 | 1 | REFRIGERATOR | WALL | 96" | BTC; MOUNT ON KITCHEN SIDE-OMIT PLUG, UNIT TO BE HARDWIRED |
| E201A | PMR | 28.0A | 208 | 1 | HOT FOOD COUNTER | FLOOR | 4.5" | BTC |
| E201B | PMR | 16.0A | 120 | 1 | COLD FOOD COUNTER | FLR | 4.5" | --- |
| E209 | PMR | 8.0A | 120 | 1 | DROP FRONT MILK COOLER-8 CASE | FLR | 4.5" | --- |
| E214 | PMR | 16.0A | 120 | 1 | CASH REGISTER | FLR | 4.5" | DEDICATED CIRCUIT |
| E214A | CS | --- | --- | --- | POS | FLOOR | 6" | BTC; CONDUIT W/DATA LINE TO RUN TO MANAGER'S OFFICE OR IDF ROOM-VERIFY |
| E250 | JB/DS-JB | 51.7A | 480 | 3 | DISHMACHINE | WALL | 66" | BTC; EXTEND FROM JB/DS AT NEAREST WALL |
| E615 | DR | 5.0A | 120 | 1 | VIDEO / DATA SYSTEM | CLG | VERIFY | PROVIDE DCO AT VIDEO LOCATION |
| E615A | JB | --- | --- | --- | VIDEO / DATA SYSTEM | CLG | VERIFY | PROVIDE JB AT DATA LOCATION |





1 FOOD SERVICE ELECTRICAL PLAN
1/4" = 1'-0"





6 COLD STORAGE ASSEMBLY ENTRAPMENT PANIC ALARM DETAIL
NOT TO SCALE





3 PEDESTAL MOUNTED RECEPTACLE DETAIL
NOT TO SCALE




| | |
|---|---|
| A | S/S ENCLOSURE W/AGENT TANK AND NITROGEN CARTRIDGE |
| B | DUCT NOZZLE(S) |
| C | PLENUM NOZZLE(S) |
| D | SURFACE PROTECTION NOZZLE(S) |
| E | FUSIBLE LINK(S) |
| F | (2) WIRES FROM FIRE SYSTEM TO SHUNT TRIP BREAKERS FOR SHUT DOWN OF ELECTRICAL CONNECTIONS LOCATED BENEATH EXHAUST HOOD DURING FIRE MODE |
| G | REMOTE FIRE PULL |
| H | GAS VALVE |
| I | GAS SUPPLY (AS REQUIRED) |

4 FIRE PROTECTION SYSTEM TYPICAL DETAIL
NOT TO SCALE




5 FIRE PROTECTION SYSTEM RECESSED FIRE PULL DETAIL
NOT TO SCALE

| | | | | | |
|---|---|---|---|---|---|
| | SCR | CONDUIT STUB BTC ON RECEPT FURNISH WITH EQUIPMENT | | CC | CONDUIT FOR COMPUTER CABLES |
| • | CS | CONDUIT STUB UP/OUT FOR DIRECT CONNECTION | | BTC | BRANCH TO CONNECTION ON EQUIPMENT |
| | DR | DUPLEX RECEPTACLE | | WPR | WATERPROOF RECEPTACLE (SPRING COVER) |
| | SR | SINGLE PURPOSE RECEPTACLE-1PH | / | FPB | FIRE PROTECTION BUZZER |
| | SR | SINGLE PURPOSE RECPTACLE-3PH | | BSC | BEVERAGE SYSTEM CONDUIT |
| | FR | FLUSH FLOOR RECEPTACLE | | DFA | DROP FROM ABOVE |
| | PMR | PEDESTAL MOUNTED RECEPTACLE | | AFF | ABOVE FINISH FLOOR |
| | DCR | DROP CORD RECEPTACLE | | CS/JB | JUNCTION BOX ON PEDESTAL |
| | JB | JUNCTION BOX ON CEILING | | SW | SWITCH |
| | JB | JUNCTION BOX IN WALL | | D | DATA |
| | JB/DS | JUNCTION BOX WITH DISCONNECT BY DIV.26 | | | |

2 ELECTRICAL SYMBOLS
NOT TO SCALE

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILLS ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD
SUGAR LAND, TX 77498


SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
THIS DOCUMENT APPEARING ON THIS SEAL IS AUTHORIZED BY MELISSA MOORE ON 7/15/2025 48854119 ON: 07182025


ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS ELECTRICAL PLAN

U-QF1.5

**MODEL NO. ZS1-02Z-CT3-EST OUTDOOR AIR COOLED REFRIGERATION SYSTEM**
**ITEM NO. 103**




NOTE:
- CRANKCASE HEATERS
- FAN CYCLING SWITCHES
- 24" STANDS & STAINLESS STEEL SKIRTING TO BE SHIPPED LOOSE FOR FIELD INSTALLATION
- DOOR SENSOR FOR EACH WALK-IN
- REFRIGERANT DETECTION SYSTEM
- CHECK VALVE (SHIPPED LOOSE)
- SHUT OFF VALVE (SHIPPED LOOSE)

RACK WEIGHT: 600 LBS.

## ENGINEERING SUMMARY

**POWER SUPPLY: 208-230/60/3**
**CONNECTED LOAD: 21.8 AMPS**

**MOPD: 30 AMP**
**MINIMUM CIRCUIT AMPACITY: 24.1**

| SYSTEM | FIXTURES ITEM # | DESCRIPTION | TEMP °F FIXT. | TEMP °F SUCT. | REQ'D FIXTURE BTU/H | REFRIG. R- | CONDENSING UNIT: COMPRESSOR MODEL NO. | H.P. | RATING @ 60 HZ RLA | V | PH | BTU CAP @ AMB °F 110 | TYPE | REC. CAP. (lbs) | CONDENSER | EVAPORATOR COILS ITEM # | MODEL NO. | QTY | FAN MOTORS @ 60 HZ RLA | V | PH | HEATERS @ 60 HZ RLA | V | PH | DEFR. TYPE | DEFROST CONTROLLER TYPE | CONTROLLER QTY | ACCESSORIES TSTAT | SOL. VALVE | EXP. VLV. | REFRIGERANT LINE SIZES (IN) SUCT. | SUCT. LINE RISER | LIQUID | LINE RUN (FT) | TYPE | TOTAL SYSTEM LOAD |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| A | 102 | WALK-IN COOLER | 35 | 25 | 8506 | 454A | YS11KAE | | 11.2 | 208 | 3 | 11700 | Z | 14.0 | L1R | - | BEL0095 | 1 | 1.8 | 115 | 1 | | | | O.C. | ECOSMART | 1 | F | F | EF | 5/8 | 5/8 | 3/8 | 100 | M | 11.2 |
| B | 102 | WALK-IN FREEZER | -10 | -20 | 7607 | 454A | YF07KSE | | 10.6 | 208 | 3 | 7610 | Z | 14.0 | L1R | - | BEL0080 | 1 | 1.0 | 208 | 1 | 9.1 | 208 | 1 | ELEC | ECOSMART | 1 | F | F | EF | 7/8 | 7/8 | 3/8 | 100 | M | 10.6 |

ALL EVAPORATOR COILS WILL REQUIRE A HOUSE POWER SUPPLY

c UL us LISTED

NOTE:
IT IS THE INSTALLING CONTRACTORS RESPONSIBILITY TO FOLLOW ALL APPLICABLE CODES AND CURRENT REFRIGERATION INDUSTRY STANDARDS AND PRACTICES WHEN DETERMINING LINE SIZES, AND INSTALLING AND STARTING UP RDT EQUIPMENT.


COMPRESSOR TYPE
Z SCROLL

DEFROST TYPE
O.C. OFF CYCLE
ELEC ELECTRIC

LINE TYPE
M MAIN - UP TO 100'


EVAPORATOR ACCESSORIES
EF EEV FACTORY EQUIPPED ON EVAP
F FACTORY EQUIPPED ON EVAP

### PLANVIEW/ CLEARANCE REQUIREMENTS





NOTE: MINIMUM CLEARANCE REQUIRED FOR PROPER OPERATION
NOTE: ROOF CURB OR GROUND PAD CAN BE SAME SIZE AS OUTDOOR UNIT

### SUCTION LINE VERTICAL RISE DETAIL




- Install trap every transition from horizontal to vertical.
- Insulate suction lines with 3/4" wall Armaflex insulation.
- All joints brazed with minimum 15% silver content brazing rod.
- Install "P" trap on suction line every 15' vertical rise.
- Not to exceed 45' vertically over all.
- *If compressor is above the evaporator, Install inverted trap on top of the rise to prevent oil from seeping down when fixture(s) is turned off.

### EVAPORATOR DETAILS - MODEL BEL




| AIR DEFROST Size | DIMENSIONS A | B | C | D | CONNECTIONS (Inches) Coil Inlet | Suction | Drain | Approx. Net Wt. Lbs. | ELECTRICAL DATA Qty. Motors | EC Motor Fan Amps |
|---|---|---|---|---|---|---|---|---|---|---|
| | Inches | Inches | Inches | Inches | | | | | | |
| 095 | 45-1/2 | 33-1/4 | - | - | 1/2 OD | 5/8 OD | 3/4 MPT | 51 | 2 | 1.8 |

| ELECTRIC DEFROST | DIMENSIONS A | B | C | D | CONNECTIONS (Inches) Coil Inlet | Suction | Drain | Approx. Net Wt. Lbs. | ELECTRICAL DATA Qty. Motors | EC Motor Fan Amps | Heater Amps as wired for 115V | 208-230/60/1 | 208-230/60/3 | 460/60/3 |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Inches | Inches | Inches | Inches | | | | Lbs. | | | | | | |
| 080 | 45-1/2 | 33-1/4 | - | - | 1/2 OD | 5/8 OD | 3/4 MPT | 54 | 2 | 1.0 | 9.1 | 5.7 | 4.6 | |

### ZS SERIES ENGINEERING SPECIFICATIONS

Multi compressor, outdoor, air cooled. The refrigeration package shall be a pre-engineered and factory-assembled unit, trade name "ZS", as manufactured by Refrigeration Design Technologies, 1808 FM Road 66, P.O. Box 622, Waxahachie, Texas 75168. Phone: (972) 937-3215; Fax: (972) 937-0970.

1. Air-Cooled Refrigeration System
The RDT UL Listed "Air-Cooled" Refrigeration system shall be housed in a weather-protected compact powder coated steel frame. The entire housing shall be brushed stainless steel. The unit shall include an air-cooled aluminum fin copper tube condenser designed to operate at 15 degrees TD. The exterior housing shall feature stainless steel one piece louvers. Lifting points shall be integrated in the framing component. Condenser fan motors shall be mounted within the enclosure. The condenser intake surface shall be protected with stainless steel expanded metal guard to protect against vandalism and hail damage.

Each unit shall be equipped with a ball-bearing fan motor, suction filter, sight glass, liquid filter/drier, liquid line inlet and outlet valve, defrost cycle and high pressure super-hose connections. Each unit shall be equipped with fan cycling controls and/or head pressure regulator where required for low ambient conditions.

Condensing unit shall contain scroll, hermetic, semi-hermetic, and/or discus type compressor(s) assembled to operate with the refrigerant specified for both medium and low temperature applications.

2. Evaporator Coils
A. Evaporator coils shall be direct expansion type fabricated of copper tubes with aluminum fins.
B. All evaporator coils shall be provided with solenoid valve, thermostatic or electronic expansion valve and thermostat.

3. Pre-Piping
All refrigerant lines shall be extended to outside of the housing in a neat and orderly manner. All tubing shall be securely supported and anchored with non-corrosive coated clamps.

All joints must be brazed, not soldered.

All piping and controls shall be factory pressure-tested with dry nitrogen.

4. Control Panel
The package shall have a factory-mounted and pre-wired control panel, with main disconnect (non fused) where required, circuit breakers, contactors wired for single point power connection.

General Information
Contractors shall verify all dimensions onsite and coordinate with other trades.

General contractor shall prepare the platform, curbed openings and weatherproofing the unit after installation.

Refrigeration Contractor
All copper tubing to be refrigerant grade. A.C.R. or type "L".

Brazing should be used for all refrigerant piping. Silver solder or soft solder is not acceptable.

All piping to be pressure tested with nitrogen at 300 psi. After the condensing unit and coil have been connected the balance of the system shall be leak tested with the valves open at 200 psi.

The complete system shall be evacuated with a vacuum pump. Each unit should be charged tested and adjusted to assure operation.

Contractor should provide and install the drain-line heater in freezer. Heater shall be connected by electrical contractor. Seal all penetrations through the walk-in units with foam.

Electrical Contractor
Electrical contractor to provide power for refrigeration package and connect control and defrost system as called for in the wiring diagram.


Electrical contractor to connect drain-line heater in the freezer.

All electrical wiring and installation shall be in accordance with the wiring diagram and local codes. Seal all penetrations through the walk-in units with foam.

Plumbing Contractor
Plumbing contractor to provide copper drain lines for walk-in refrigerator and freezer, pitched 1/4" per foot of run. Trap drain-line outside of refrigerated space to avoid entrance of warm, moist air.


All plumbing installation shall be in accordance with local codes.

### EVAPORATOR MOUNTING DETAIL (TYPICAL)




| COIL MODEL | DISTANCE FROM WALL |
|---|---|
| BEL | 1-1/3"H |
| BEM/BEH | 1/2 * W |

### EVAPORATOR PLACEMENT & CLEARANCE REQUIREMENTS LOW PROFILE EVAPORATOR COILS (I.E. - BEL)





SINGLE EVAPORATOR

### WIRING DIAGRAM - ECOSMART - AKEA1AE DEMAND DEFROST W/KE2 DOOR SWITCH FOR WALK-IN COOLER WITH ONE COIL 115/60/1

*REFERENCE ENGINEERING SUMMARY FOR COIL AMP DRAW.

| SYS | DESCRIPTION | VOLTAGE |
|---|---|---|
| A | WALK-IN COOLER | 115/1 |





FACTORY WIRING ———
FIELD WIRING - - - - - -

### WIRING DIAGRAM - ECOSMART - AKEB1EE DEMAND DEFROST W/KE2 DOOR SWITCH FOR WALK-IN FREEZER WITH ONE COIL 208-230/60/1

*REFERENCE ENGINEERING SUMMARY FOR COIL AMP DRAW.

| SYS | DESCRIPTION | VOLTAGE |
|---|---|---|
| B | WALK-IN FREEZER | 208/1 |




FACTORY WIRING ———
FIELD WIRING - - - - - -

**APPROVAL STATUS**

THIS DRAWING REPRESENTS OUR UNDERSTANDING OF THE SPECIFICATIONS. PLEASE REVIEW IT CAREFULLY FOR ACCURACY. CLEARLY AND IN DETAIL NOTE CHANGES REQUIRED.

MARK APPROPRIATE BOX, SIGN, AND DATE BELOW.

☐ APPROVED FOR FABRICATION NO CHANGES
☐ APPROVED FOR FABRICATION WITH CHANGES NOTED
☐ REVISE AND RE-SUBMIT DRAWING

BY: _____ DATE: _____

**NOTICE**

THIS DRAWING BEING AN INSTRUMENT OF SERVICE IS AND WILL REMAIN PROPERTY OF REFRIGERATION DESIGN TECHNOLOGIES AND CANNOT BE USED WITHOUT WRITTEN AUTHORIZATION.

| No. | Revision/Issue | Date |
|---|---|---|
| 0 | ORIGINAL ISSUE | 10-3-24 |
| 1 | CHANGED TO A2L EQUIPMENT | 7-16-25 |


REFRIGERATION DESIGN TECHNOLOGIES
1808 FM Road 66 / P.O. Box 622
Waxahachie, Texas
(800) 736-9518
www.rdtonline.com


Consultant:
Foodservice Design Professionals, LLC
The Woodlands, TX

Dealer
-
-

**Sugar Mill Elementary School**
**Fort Bend ISD**

Project No: 31085
Designed By: E. Milligan
Drawn By: A. Rodriguez
Sheet 1.1 of sheets

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS


FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILLS ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD
SUGAR LAND, TX 77498


SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
46854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025 APPROVING ENGINEER
THIS ITEM WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 46854119 ON: 07/18/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS CONDENSING UNITS

U-QF1.6






COOLER DOOR ELEVATION





DOOR ELECTRICAL CONNECTION




TRIM ANGLE
DETAIL #3





PANEL MOUNTED ELECTRICAL CONNECTION





SECTION E – E

SECTION K – K


American Panel's walk–in floor panels with AmeriTuff structural support are designed to withstand uniformly distributed stationary loads of 15,000 lbs. per square foot. American Panel's warranty does not cover damage caused by pallet jacks, forklifts or any other form of heavy–duty rolling traffic. A concrete wearing floor must be installed on top of the AmeriTuff walk–in floor panels for those rolling applications.




TRIM ANGLE
DETAIL #2




CLOSURE PANEL ABOVE WALK–IN DETAIL #4E




DETAIL "A" WAINSCOT AT INTERIOR CORNER

ITEM #102 WALK–IN COOLER/FREEZER

~SPECIFICATIONS~

BOX HEIGHT:
FREEZER – 10'–2" OVERALL (7'–6 1/4" INTERIOR)
COOLER – 10'–2" OVERALL (7'–6 1/4" INTERIOR)

CONSTRUCTION:
FOAMED IN PLACE
NSF LISTED, STANDARD NO. 7

INSULATION:
4" URETHANE, FINISHED PANEL
UL CLASSIFIED FLAME SPREAD 20
CORE SMOKE DEVELOPED 250

INSTALLATION:
INDOOR

FLOOR: (SEE DETAILS)
FREEZER – STANDARD W/AMERITUFF STRUCTURAL FLOOR
(1/8" INTEGRAL DIAMOND ALUMINUM TREAD PLATE, 3/4" MARINE PLYWOOD UNDERLAYMENT, FIBERGLASS GRATING SUPPORT)
COOLER – STANDARD W/36" DEEP INTERIOR RAMP & AMERITUFF STRUCTURAL FLOOR
(1/8" INTEGRAL DIAMOND ALUMINUM TREAD PLATE, 3/4" MARINE PLYWOOD UNDERLAYMENT, FIBERGLASS GRATING SUPPORT)

DOOR HARDWARE & ACCESSORIES: (EACH DOOR)
SMOOTH POLISHED DOOR HARDWARE
POWER TO BE STUBBED OUT CEILING PANEL
DRY CONTACT LEADS TO BE STUBBED OUT CEILING PANEL IN A SEPARATE STUB OUT
DEADBOLT HANDLE W/KEYED CYLINDER LOCK, PADLOCK
PROVISION & QUARTER TURN INSIDE RELEASE (EXTERIOR DOOR ONLY)
1/8" STAINLESS STEEL THRESHOLD COVER PLATE
14 GA STAINLESS STEEL SUB THRESHOLD
FRAME HEATER WIRE
HYDRAULIC DOOR CLOSER
IC+ WALK–IN DOOR CONTROLLER AND ALARM SYSTEM INCLUDING:
INTEGRATED LIGHT SWITCH WITH AUTOMATIC LIGHT OFF AND 3–WAY & 4–WAY CAPABILITY
TEMPERATURE MONITOR AND LOGGER WITH HIGH TEMP. AND LOW TEMP. VISUAL AND AUDIO ALARM
F OR C TEMPERATURE SELECTION
INTEGRATED DRY CONTACT FOR ALARM SIGNALING & POWER FAILURE (1A @ 24VAC, 1A @ 30VDC)
DOOR AND WINDOW HEATER CONTROL (WHEN SO EQUIPPED)
HACCP PREVIEW VIA ONBOARD LCD SCREEN
HACCP DOWNLOAD VIA USB
WIFI CONNECTIVITY (INTERNET ENABLED WIFI NETWORK NEEDED)
BATTERY BACKUP
TEMPERATURE ALARM NOTIFICATION VIA EMAIL &/OR EMAIL TO SMS TEXT MESSAGES
POWER FAILURE NOTIFICATION VIA EMAIL &/OR EMAIL TO SMS TEXT MESSAGES
(FOR THIS FEATURE TO WORK THE LOCAL WIFI NETWORK MUST BE POWER PROTECTED AND WORKING AT THE TIME OF POWER FAILURE EVENT)
AUTOMATIC AND ON DEMAND TRANSMISSION OF HACCP DATA VIA EMAIL
ADAPTIVE SETTINGS
MOMENTARY BACK–TO–BACK LIGHT SWITCH W/PILOT
25' AIR TEMPERATURE PROBE
25' SECOND PROBE (EXTENDED) FOR MONITORING THE TEMPERATURE AT A SECOND LOCATION OR FOR MONITORING A SECOND CABINET
DOOR SWITCH TO ENABLE DOOR AJAR ALARM, DOOR AJAR NOTIFICATION VIA EMAIL &/OR EMAIL TO SMS TEXT MESSAGES, AND AUTOMATIC LIGHTS ON WHEN DOOR OPENS
PANIC ALARM WITH ILLUMINATED PANIC BUTTON, ALARM BUZZER WITH LED, & NOTIFICATION VIA EMAIL &/OR EMAIL TO SMS TEXT MESSAGES (1–COOLER, 2–FREEZER)
KASON SCREW–IN VAPOR PROOF LIGHT FIXTURE
W/8.5 WATT SYLVANIA LED BULB & GLOBE
CCI CLEAR VU SWINGING DOOR
3 – KASON #1346 ADJUSTABLE SPRING LOADED HINGES
HEATED VISION WINDOW (14" x 24")
1/8" DIAMOND ALUMINUM TREAD PLATE KICKPLATES @ 36" HIGH I/S & O/S DOOR & FRAME
KASON 1826 INTELLO–VENT WITH LIGHTS (FREEZER DOOR ONLY) – FIELD INTERCONNECTION REQUIRED

PANEL MOUNTED ACCESSORIES: (SHIPPED LOOSE)
1 – KASON 1826 INTELLO–VENT WITH LIGHTS – FIELD INTERCONNECTION REQUIRED (FOAMED IN PANEL – PER PLAN) (COOLER ONLY)
2 – PCS. TRIM ANGLE – 18 GA STAINLESS STEEL, #3 FINISH
CLOSURE PANEL TO AN EXISTING CEILING (PER PLAN) ← VERIFY LENGTH
18 GA STAINLESS STEEL, #3 FINISH
2 – 48" (1810LC) LED LIGHT FIXTURE(S) @ 40W EACH (LIGHTS TO BE INSTALLED PERPENDICULAR TO COILS)
1/8" DIAMOND ALUMINUM TREAD PLATE WAINSCOT @ 36" HIGH (EXPOSED EXTERIOR ONLY)
1 – 1/8" DIAMOND ALUMINUM TREAD PLATE CORNER GUARD(S) @ 36" HIGH
ALUMINUM COVED BASE MOLDING (COMPLETE INTERIOR ONLY)
ROOF SUPPORT ANGLE W/BEAUTY TRIM
2 – BAKELITE LABEL(S) (BLACK) ("FREEZER", "COOLER")
1 – BAKELITE LABEL (YELLOW W/BLACK LETTERING) ("VACUUM PRESSURE RELIEF")
6 MIL POLYETHYLENE VAPOR BARRIER
5 – BELL BOX(ES) & COVER PLATE(S)
2 – DOOR STOP(S)
2 – EDWARDS 880 SERIES STROBE BEACONS
1 – EMERGENCY PRESSURE RELEASE

METAL FINISHES:
INTERIOR & EXTERIOR DOOR & FRAME – 18 GA STAINLESS STEEL, #3 FINISH
INTERIOR WALLS & CEILING – WHITE .040 STUCCO ALUMINUM
EXPOSED EXTERIOR – 20 GA STAINLESS STEEL, #3 FINISH
UNEXPOSED EXTERIOR – 26 GA STUCCO ACRYLUME
EXTERIOR FLOOR – 26 GA STUCCO ACRYLUME
EXTERIOR ROOF – 26 GA STUCCO ACRYLUME
INTERIOR FLOOR – AMERITUFF STRUCTURAL FLOOR
(1/8" INTEGRAL DIAMOND ALUMINUM TREAD PLATE, 3/4" MARINE PLYWOOD UNDERLAYMENT, FIBERGLASS GRATING SUPPORT)

REFRIGERATION: BY OTHERS

NOTE: THE LARGEST DOOR PANEL ON THIS JOB IS 57.5" x 114.5".
NOTE: THE LARGEST ROOF/FLOOR PANEL ON THIS JOB IS 46.5" x 129". CUSTOMER IS TO VERIFY THAT THIS PANEL SIZE WILL NOT CONFLICT WITH ANY JOB SITE RESTRICTIONS.
NOTE: CUSTOMER IS TO VERIFY ALL DIMENSIONS, SECTIONS, DETAILS AND SPECIFICATIONS.
NOTE: MAXIMUM LIGHT CIRCUIT LOAD IS 1200W 120VAC TUNGSTEN, 5A 120VAC ELECTRONIC BALLAST. FOR HIGHER LOADS ADDITIONAL LIGHT FIXTURES MUST BE CONTROLLED VIA RELAY (BY OTHERS).

| ELECTRICAL DATA |
|---|
| ⏚ = POINT OF ELECTRICAL CONNECTIONS. |
| WALK–IN DOORS: 115v/1⌀ – 350w* |
| PANEL MOUNTED ACC: 115v/1⌀ – 23w (EACH VENT) |

*NOTE: ADD WATTAGE FOR EACH ADDITIONAL LIGHT FIXTURE IN ACCESSORIES.

| INSULATION R–VALUES | | |
|---|---|---|
| PANEL TYPE | COOLER | FREEZER |
| 4" WALLS, ROOFS | R–29 | R–32 |
| 5" WALLS, ROOFS | R–36 | R–40 |
| FLOORS | R–25 | R–28 |
| DOORS | R–32 | |

| COOLER DOOR | |
|---|---|
| DOOR FRAME KWH/DAY | 2.424 |

| FREEZER DOOR | |
|---|---|
| DOOR FRAME KWH/DAY | 4.392 |

| WALK–IN PANEL | | |
|---|---|---|
| R–8967 | | |
| BUILDING UNITS | R–8967 | 37X2 |
| USA | | |
| SURFACE BURNING CHARACTERISTICS | | |
| MATERIAL DETAILS | "FLAME SPREAD" | "SMOKE DEVELOPED" |
| ALUMINUM PANELS, PAINTED OR UNPAINTED, 5" OR LESS | 15 | 350 |
| *GALVANIZED STEEL OR STAINLESS STEEL PANELS, PAINTED OR UNPAINTED, 5" OR LESS* | 10 | 400 TO 500 |
| CORE MATERIAL, 6" THICK | 20 | 250 |

AMERICAN PANEL WALK–IN COOLERS AND FREEZERS COMPLY WITH THE 2021 INTERNATIONAL ENERGY CONSERVATION CODE (IECC), SECTION C403.11

THIS AMERICAN PANEL WALK–IN WILL BE MANUFACTURED TO UL & NSF REQUIREMENTS. AMERICAN PANEL ACCEPTS NO LIABILITY FOR LOCAL CODE REQUIREMENTS OF WHICH AMERICAN PANEL HAS NOT BEEN MADE AWARE OF IN WRITING PRIOR TO FABRICATION.

☐ APPROVED SIGNATURE
☐ APPROVED AS NOTED PRINT NAME
☐ REVISE & RESUBMIT DATE

1) Please verify that door swing and location are correct.
2) If this walk–in is to be installed in a depression, or quarry tile is to be applied to the interior, depression depths or tile thickness must be specified to insure proper door height.
3) All site preparation, floor or slab construction, plumbing, electrical connections (including control wiring) by others.
4) ⏚ Electrical: 115–60–1 required above latch side of each door, through ceiling, to operate frame heater and light.
5) Special note to General Contractor and his Sub Contractor for quarry tile or concrete wearing floors: the sheet metal panel facings may be susceptible to staining due to excessive moisture created by hydration of concrete type materials. Therefore, it is absolutely necessary that each room be properly ventilated. Also note that special precautions must be taken when using muriatic acid due to effects hydrochloric acid fumes have on aluminum and stainless steel.
6) This drawing and information contained herein are the exclusive property of American Panel Corporation. It shall be returned to American Panel Corporation upon demand and shall not be reproduced in whole or part, disclosed to anyone else, or used without the written consent of American Panel Corporation.

| REV. | DATE | DESCRIPTION | REV. BY | CKD BY |
|---|---|---|---|---|
| A | 1/22/25 | REVISED LAYOUT, SPECS; ADDED DETAIL | DH | WQ |

American Panel — AMERICAN PANEL CORPORATION, 5800 S.E. 78th St. Ocala, Florida 34472, Ph. (352) 245–7055 Fax (352) 245–0726

CUSTOMER: FOODSERVICE DESIGN PROFESSIONALS
PROJECT: SUGAR MILL ES–FBISD – FORT BEND, TX
DATE: 10/09/24 | DRAWN BY: JG/TR | P.O.#:
SCALE: 3/8"=1'–0" | PROPOSAL#: FP0213269 | JOB#: | SHEET 1 of 1

ALL DIMENSIONS MUST BE FIELD VERIFIED PRIOR TO FABRICATION AND INSTALLATION

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS


FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILLS ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD
SUGAR LAND, TX 77498

SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL — MELISSA MOORE — FCSI — 46854119 — PROFESSIONAL MEMBER
Melissa Moore
7/15/2025
DOCUMENTS APPEARING ON THIS SEAL WERE AUTHORIZED BY MELISSA MOORE, FCSI NO. 46854119 ON: 07/18/2025


ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS WALK-INS

U-QF1.7





1 CC1 ITEM #1 PLAN

SCALE: 1/2" = 1'-0"





4 CC1 ITEM #1 SECTION VIEW

SCALE: 1/2" = 1'-0"





8 CC1 ITEM #1 CONTROL PANEL LAYOUT

SCALE: 1 1/2" = 1'-0"





2 CC1 ITEM #1 FRONT ELEVATION

SCALE: 1/2" = 1'-0"




11 CC1 ITEM #1 3D PERSPECTIVE

SCALE:




3 CC1 ITEM #1 REAR ELEVATION

SCALE: 1/2" = 1'-0"



12 CC1 ITEM #1 3D PERSPECTIVE 2

SCALE:




13 CC1 ELECTRICAL SCHEDULE

CASHIER COUNTER




10 CC1 ELECTRICAL SCHEDULE

HOT FOOD COUNTER #1
(TWO (2) REQUIRED)




15 CC1 ELECTRICAL SCHEDULE

HOT/FROST COUNTER
(TWO (2) REQUIRED)

EQUIPMENT BY OTHERS

COUNTERCRAFT LAYOUTS, MEPS, AND LOAD CENTERS ARE BASED ON SPECIFIED MANUFACTURERS AND MODELS AS OUTLINED IN THE SPECIFICATIONS IN THE CONTRACT DOCUMENTS. COUNTERCRAFT MUST BE NOTIFIED OF ANY CHANGES TO THE CONTRACT DOCUMENTS IN A TIMELY MANNER.

| NO | REVISIONS | DATE | BY |
|---|---|---|---|
| 1 | PRICING SET-DWG | 10/07/2024 | MAX |
| 2 | REVISIONS | 11/26/2024 | MAX |
| 3 | | | |
| 4 | | | |
| 5 | | | |
| 6 | | | |
| 7 | | | |
| 8 | | | |
| 9 | | | |

ANOTHER QUALITY PRODUCT FROM
CounterCraft
7007 STEARNS HOUSTON,TEXAS 77021
(713) 747-3611

PROJECT: FBISD Bond Package 013
FOOD SERVICE CONSULTANT: FOODSERVICE DESIGN PROFESSIONALS
PROJECT NO. -
DATE: 11/26/2024
SCALE: As indicated
DRAWN BY: MAX.C
CHECKED BY: E.S
SHEET NO.: CC1
OF SHEET

**ISSUE:**

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FOODSERVICE DESIGN PROFESSIONALS


FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILLS ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD
SUGAR LAND, TX 77498

SEAL
FOODSERVICE CONSULTANTS SOCIETY INTERNATIONAL
MELISSA MOORE
FCSI 48854119
PROFESSIONAL MEMBER
Melissa Moore
7/15/2025 APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MELISSA MOORE, FCSI NO. 48854119 ON: 07/15/2025

MWA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING
FS SERVING COUNTERS


U-QF1.8




## 3 MECHANICAL ROOF FLOOR PLAN

SCALE: 1/8" = 1'-0"


NORTH




## 2 RENO MECHANICAL FLOOR PLAN - KITCHEN AREA

SCALE: 1/8" = 1'-0"

NORTH




## 1 DEMO MECHANICAL FLOOR PLAN - KITCHEN AREA

SCALE: 1/8" = 1'-0"

NORTH

## AIR DEVICE SCHEDULE

| MARK | DESCRIPTION |
|---|---|
| A | CEILING DIFFUSER – 24" X 24" FACE, PATTERN TYPE, STEEL CONSTRUCTION, OBD/RADIATION DAMPER, WHITE FINISH, U.L LISTED PRICE SCD A1–12" X 12" |
| B | CEILING RETURN GRILLE – 24" X 24" PERFORATED FACE, STEEL CONSTRUCTION, RADIATION DAMPER, WHITE FINISH, U.L. LISTED PRICE PDRR B1–12" X 12" |
| C | CEILING EXHAUST GRILLE – 24" X 24" PERFORATED FACE, STEEL CONST., OBD/RADIATION DAMPER, WHITE FINISH, NECK SIZE SHOWN, U.L. LISTED PRICE PDDR C1–12" X 12" |

NOTES:

1. REFER TO ARCHITECTURAL REFLECTED CEILING PLAN TO VERIFY CEILING TYPES FOR AIR DEVICES.

## KITCHEN HOOD REFURBISHMENT NOTES

HOOD REFURBISHMENT FOR KITCHEN HOODS (QUANTITY 2):

- STEAM WASH AND DEEP CLEAN STAINLESS STEEL HOOD ASSEMBLY, CASING, AND SUPPLY GRILLES WHERE APPLICABLE.
- REPLACE GREASE FILTER RACKS.
- CLEAN EXISTING MAKE-UP AIR AND GREASE EXHAUST DUCT.
- RELAMP EXISTING LIGHT FIXTURES WITH NEW 4000K BULBS LISTED FOR USE IN AN ENCLOSED KITCHEN HOOD FIXTURE.
- COORDINATE WITH DIVISION 11 FOR REPLACEMENT OF ANSUL FIRE SUPPRESSION SYSTEM.
- HOOD ASSEMBLIES SHALL BE CLEANED TO MEET THE STANDARDS ESTABLISHED IN NFPA STANDARD 96.

## KITCHEN HOOD EXHAUST & MAKE-UP AIR UNIT SCHEDULE

| | |
|---|---|
| MARK | ESF-1,2 |
| SERVES | KITCHEN HOOD-1 & 2 |
| SUPPLY SECTION | |
| TYPE | INDIRECT GAS-FIRED MAKE-UP AIR UNIT |
| DRIVE | DIRECT |
| SPEED CONTROL | VFD |
| SUPPLY CFM | 2250 |
| EXT. S.P. (IN. W.G.) | 0.375 |
| HORSEPOWER (WATTS) | 1-1/2 HP |
| VOLTAGE | 480V/3-PHASE |
| UNIT MCA | 4.6 A |
| UNIT MOCP | 15 A |
| HEATING MEDIUM | NATURAL GAS |
| INPUT/OUTPUT (MBH) | 150.0/121.5 |
| TURNDOWN RATIO | 4:1 |
| MANUFACTURER | GREENHECK |
| MODEL | IGX-P109-H12-MF-E |
| EXHAUST SECTION | |
| TYPE | UPBLAST BELT DRIVE CENTRIFUGAL |
| EXHAUST CFM | 3600 |
| EXT. S.P. (IN. W.G.) | 0.75 |
| HORSEPOWER (WATTS) | 1-1/2 HP |
| VOLTAGE | 480V/3-PHASE |
| UNIT MCA | 3.75 A |
| UNIT MOCP | 15 A |
| MANUFACTURER | GREENHECK |
| EXHAUST FAN MODEL | CUBE-200-15 |

NOTES

1. EXHAUST FAN: PROVIDE FAN WITH PRE-FABRICATED ROOF CURB ADAPTER, VENTED CURB EXTENSION, HINGING KIT, HEAT BAFFLE, DRAIN CONNECTION, GREASE TRAP, AND DISCONNECT SWITCH. FANS SHALL BE UL LISTED FOR USE WITH TYPE 1 GREASE HOOD.
2. EXHAUST FAN: PROVIDE NEW MOTOR STARTER, SIZED FOR EXHAUST FAN MOTOR AND INSTALLED IN PLACE OF EXISTING. REFERENCE THE SPECIFICATIONS FOR STARTER REQUIREMENTS. COORDINATE WITH DIV.25 FOR RE-TERMINATION OF PERMISSIVE ON/OFF CONTROL. COORDINATE WITH DIV.26 FOR RE-TERMINATION OF LOCAL HOOD SWITCH INTERLOCK FOR START/STOP CONTROL.
3. SUPPLY FAN/FURNACE: FLUE GAS FROM HEATING COIL SHALL BE POWER VENTED.
4. SUPPLY FAN/FURNACE: WEATHERHOOD WITH ALUMINUM MESH.
5. SUPPLY FAN/FURNACE: 5 YEAR HEAT EXCHANGER WARRANTY.
6. SUPPLY FAN/FURNACE CONTROLS: INTEGRAL HEATER CONTROLS WITH BAS INTERLOCK FOR PERMISSIVE ON/OFF AND LOCAL SWITCH INTERLOCK FOR CONTROL FROM KITCHEN HOOD SWITCH. FURNACE CONTROLS SHALL BE PROGRAMMED FOR 64°F LAT, WITH A LOCKOUT FOR O/A TEMPERATURES ABOVE THE LAT SETPOINT. COORDINATE WITH DIV.25 AND DIV.26 FOR CONTROLS AND SWITCH INTERLOCKS.
7. TWO POINT POWER CONNECTION: ONE FOR EXHAUST FAN AND ONE FOR INTAKE/SUPPLY FAN.
8. INTERLOCK FAN(S) WITH ASSOCIATED COOKING HOOD
9. INTERLOCK FAN WITH SWITCH ON KITCHEN HOOD.
10. UNIT TO BE PROVIDED WITH GALVANIZED STEEL FAN PACK EXTENSION/COMBINATION CURB.
11. REFER TO WRITTEN SPECS FOR ADDITIONAL REQUIREMENTS.

## MECHANICAL RENO KEYED NOTES

1. TIE-IN NEW DUCTWORK TO EXISTING DUCTWORK AT WALL PENETRATION.
2. CONNECT NEW AIR DEVICE AND TAP TO EXISTING E/A TRUNK DUCT.
3. REWORK EXISTING EXHAUST AND SUPPLY DUCTWORK FROM EXISTING KITCHEN HOOD UP TO FAN, AS REQUIRED, WITH NEW TRANSITIONS AND SUPPLY AIR DUCTWORK OFFSETS TO MATE WITH NEW FAN CURB.
4. EXISTING ELECTRIC DUCT HEATER TO BE RETAINED FOR RE-INSTALLATION IN RENOVATION PHASE.
5. NEW DRYER VENT DUCT AND VENT CAP.
6. TEMP. KITCHEN – CEILING MOUNTED CABINET EXHAUST FAN.
7. TEMP. KITCHEN – 24"X24" SIDE WALL GRILLE. SURFACE MOUNT OPTIONAL. AUXILIARY FRAME. TITUS CT-700.
8. RECONFIGURE DUCTWORK TO CONNECT TO NEW DISHMACHINE HOOD OUTLETS. REF. KITCHEN CONSULTANT DRAWINGS FOR EXACT DIMENSIONS OF DUCT CONNECTIONS.
9. CONDENSATE EXHAUST DUCT UP THROUGH ROOF TO NEW EXHAUST FAN SET ON NEW ROOF CURB. REUSE EXISTING ROOF PENETRATION.

## EXHAUST FAN SCHEDULE

| MARK | EF-TK | EF-CF | EF-14 |
|---|---|---|---|
| SERVES | TEMPORARY KITCHEN | COOLER/FREEZER | DISH WASHER |
| TYPE | CEILING CABINET | INLINE FAN | ROOF UPBLAST |
| DRIVE | DIRECT | DIRECT | DIRECT |
| SPEED CONTROL | INTEGRAL SPEED CONTROLLER | CONSTANT | CONSTANT |
| CFM | 1055 | 1000 | 1200 |
| EXT. S.P. (IN. W.G.) | 0.3 | 0.35 | 0.60 |
| IMP. SIZE (IN.) | 8.0 | 13.5 | |
| HORSEPOWER (WATTS) | 1/3 HP | 1/6 HP | 1/6 HP |
| VOLTAGE | 120V/1-PHASE | 120V/1-PHASE | 120V/1-PHASE |
| MANUFACTURER | COOK | COOK | COOK |
| MODEL | GC-862 | 13SSDN10D | CUE-140-VG |
| SONES (MAX.) | 15.0 | 15.0 | 15.0 |
| NOTES | 1 THRU 4 | 1 THRU 4 | 1 THRU 4 |

NOTES

1. STATIC PRESSURE SHOWN IS EXTERNAL TO THE UNIT. MANUFACTURER SHALL ADD DAMPER AND ACCESSORY LOSSES TO THIS VALUE BEFORE SELECTING FAN. FANS SHALL BE CAPABLE OF 120% OF THE SCHEDULED CFM CAPACITY.
2. INTEGRAL DISCONNECT SWITCH.
3. RUBBER IN-SHEAR ISOLATORS.
4. REFER TO WRITTEN SPECS FOR ADDITIONAL REQUIREMENTS.

## MECHANICAL DEMO KEYED NOTES

1. DEMOLISH EXISTING AIR DEVICE, BRANCH DUCT, DAMPER AND TAP BACK TO TRUNK DUCT. CAP AND SEAL RESULTING OPENING.
2. EXISTING E/A TRUNK DUCT TO REMAIN.
3. DISCONNECT EXISTING S/A AND E/A DUCTWORK SERVING KITCHEN HOODS FROM FAN ASSEMBLY ON ROOF. DEMOLISH SUPPLY AND EXHAUST FAN PLENUM ASSEMBLY SERVING KITCHEN HOODS, ALONG WITH CURB. NEW CURB TO BE PROVIDED AND INSTALLED AS PART OF RENOVATION.
4. DEMOLISH ALL EXISTING AIR DEVICES, DUCTWORK, AND DUCTWORK ACCESSORIES SERVING KITCHEN AREA BACK TO MECH. ROOM WALL PENETRATION.
5. EXISTING ELECTRIC DUCT HEATER TO BE RETAINED FOR RE-INSTALLATION IN RENOVATION PHASE.
6. REFURBISH EXISTING KITCHEN HOOD. REFER TO "KITCHEN HOOD REFURBISHMENT NOTES".
7. DEMOLISH AND REPLACE EXISTING DRYER EXHAUST DUCT AND FLUE VENT CAP.
8. DEMOLISH EXISTING CONDENSATE HOOD, ASSOCIATED DUCTWORK, AND ROOF EXHAUST FAN.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

u

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILL ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD.
SUGAR LAND, TX 77498

SEAL

STATE OF TEXAS
TYLER W. HERRING
106052
LICENSED PROFESSIONAL ENGINEER
07.18.2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

KITCHEN AREA MECHANICAL PLANS
U-M1.01

STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM (713) 300-4050
TEXAS ENGINEERING FIRM REGISTRATION NO. F-01833
© 2025 ALL RIGHTS RESERVED
1300 W. SAM HOUSTON PARKWAY N., SUITE 121, HOUSTON, TX 77043

## MECHANICAL SYMBOL SCHEDULE

| | |
|---|---|
| CWS | CONDENSER WATER SUPPLY |
| CWR | CONDENSER WATER RETURN |
| CHS | CHILLED WATER SUPPLY |
| CHR | CHILLED WATER RETURN |
| HWS | HEATING WATER SUPPLY |
| HWR | HEATING WATER RETURN |
| RS | REFRIGERANT SUPPLY |
| RR | REFRIGERANT RETURN |
| D | CONDENSATE LINE |
| | PETE'S PLUG |
| | ISOLATION VALVE |
| | ELECTRONIC CONTROL VALVE |
| | BUTTERFLY VALVE |
| | BALL VALVE |
| | UNION OR FLANGE |
| | STRAINER |
| | AUTOMATIC AIR VENT |
| T | LOCAL CONTROL THERMOSTAT |
| T | TEMPERATURE SENSOR |
| H | HUMIDITY SENSOR |
| FD | FIRE DAMPER |
| SD | SMOKE DAMPER |
| FSD | FIRE/SMOKE COMBINATION DAMPER |
| MD | MOTORIZED DAMPER |
| C | CARBON MONOXIDE SENSOR |
| C | CARBON DIOXIDE SENSOR |
| | SUPPLY AIR DIFFUSER |
| | RETURN AIR GRILLE |
| | EXHAUST GRILLE |
| RA | RETURN AIR OPENING IN WALL |
| VD | VOLUME DAMPERS |
| | DUCT ELEVATION CHANGE |
| | 90° DUCT ELBOW WITH TURNING VANES |
| | FLEXIBLE DUCT |
| M | DAMPER MOTOR |
| T | TEMPERATURE TRANSMITTER |
| FS | FLOW SWITCH |
| P | DIFFERENTIAL PRESSURE SENSOR |
| SD | DUCT SMOKE DETECTOR |
| PS | STATIC PRESSURE SENSOR |
| PH | STATIC PRESSURE SENSOR HI-LIMIT |
| | ACCESS PANEL |

| | |
|---|---|
| A.P. | ACCESS PANEL |
| AHU | AIR HANDLING UNIT |
| B | BOILER |
| CH | CHILLER |
| CHP | CHILLED WATER PUMP |
| CVT | CONSTANT VOLUME TERMINAL |
| DH | DEHUMIDIFIER |
| E/A | EXHAUST AIR |
| EF | EXHAUST FAN |
| F&B | FACE & BYPASS |
| FF | FLY FAN |
| HDT | HORIZONTAL DRAW THROUGH |
| HWP | HOT WATER PUMP |
| KEF | KITCHEN EXHAUST FAN |
| KSF | KITCHEN SUPPLY FAN |
| O/A | OUTSIDE AIR |
| OBD | OPPOSED-BLADES DAMPER |
| PT | PRE-TREAT |
| R/A | RETURN AIR |
| RAHU | ROOF-MOUNTED AIR HANDLING UNIT |
| S/A | SUPPLY AIR |
| SA | SOUND ATTENUATOR |
| SF | SUPPLY FAN |
| SPD | SPILTER DAMPER |
| SZ | SINGLE ZONE |
| VAV | VARIABLE AIR VOLUME |
| VB | VAV BOX |
| VD | VOLUME DAMPER |
| VDT | VERTICAL DRAW THROUGH |
| VFD | VARIABLE FREQUENCY DRIVE |
| WH | WATER HEATER |
| ⌀ | DESIGNATION FOR "ROUND" |
| ⌀ | DESIGNATION FOR "OVAL" |

## GENERAL MECHANICAL NOTES


1. REFER TO WRITTEN SPECIFICATIONS FOR ADDITIONAL INFORMATION.
2. COORDINATE INSTALLATION OF EQUIPMENT AND PIPING WITH THE ELECTRICAL CONTRACTOR TO INSURE NEC CLEARANCE (42 INCHES) IN FRONT OF ALL ELECTRICAL PANELS. DO NOT INSTALL DUCTWORK OR WATER PIPING OVER THE TOP OF ELECTRICAL PANELS SEE DETAIL 1/M2.01.
3. DUCT SIZES SHOWN ARE NET FREE AIR PASSAGE DIMENSIONS, DUCTS ARE NOT LINED, BUT ARE EXTERNALLY INSULATED. RUNOUTS TO CEILING OUTLETS SHALL BE EXTERNALLY INSULATED GALVANIZED SHEET METAL WITH SPIN-IN V.D. AT TRUNK TAPS, SEE DETAIL 1 & 2/M2.01.
4. REFER TO ARCHITECTURAL REFLECTED CEILING DRAWINGS FOR EXACT LOCATIONS OF CEILING OUTLETS IN RELATION TO OTHER CEILING ENTITIES. OUTLETS MUST BE COMPATIBLE WITH THE CEILING TYPES FOR THE VARIOUS AREAS.
5. IN AREAS WHERE SUPPLY AIR ENTERS CEILING CAVITY THRU RETURN AIR GRILLES AND FREE RETURNS TO AHU'S VIA CEILING CAVITY, PROVIDE RETURN AIR OPENING IN WALL-TO-DECK ABOVE CEILING THAT BLOCK PATH, REFER TO ARCHITECTURAL DRAWINGS. RETURN AIR ELBOWS SHALL BE SIZED AT 1 SQ. FT PER 400 CFM SUPPLY AIR.
6. ARRANGE PIPING CONNECTIONS TO ALL EQUIPMENT TO ALLOW EASY REMOVAL OF EQUIPMENT, SUB-ASSEMBLIES, COILS, FANS, MOTORS, FILTERS, ACCESS PANELS, ETC... PROVIDE UNIONS, FLANGES AND VALVES AT CONNECTIONS. PROVIDE AND INSTALL VICTAULIC JOINTS AT COILS, REF. SPECIFICATIONS. PLACE STOP VALVES ON SYSTEM SIDE OF REMOVABLE PIPE SECTIONS.
7. CONTRACTOR SHALL FIELD MEASURE STRUCTURAL ELEMENTS AND COORDINATE EQUIPMENT, PIPING AND DUCT ROUTING TO FIT EXISTING CONSTRUCTION. PROVIDE OFFSETS, BOOTS FOR ENVELOP OBSTRUCTIONS THAT CANNOT BE AVOIDED. CONSTRUCTION SHALL BE PER SMACNA FIGURE 2-10.

## AIR DEVICE SCHEDULE

| MARK | DESCRIPTION |
|---|---|
| A | CEILING DIFFUSER – 24" X 24" FACE, PATTERN TYPE, STEEL CONSTRUCTION, OBD/RADIATION DAMPER, WHITE FINISH, U.L. LISTED PRICE SCD |
| B | CEILING RETURN GRILLE – 24" X 24" PERFORATED FACE, STEEL CONSTRUCTION, RADIATION DAMPER, WHITE FINISH, U.L. LISTED PRICE PDFR |
| C | CEILING EXHAUST GRILLE – 24" X 24" PERFORATED FACE, STEEL CONST., OBD/RADIATION DAMPER, WHITE FINISH, NECK SIZE SHOWN, U.L. LISTED PRICE PDDR |

NOTES:

1. REFER TO ARCHITECTURAL REFLECTED CEILING PLAN TO VERIFY CEILING TYPES FOR AIR DEVICES.
2. ALL CEILINGS ARE FIRE RATED PER U.L. LISTINGS ON ARCHITECTURAL DRAWINGS. PROVIDE FIRE PROTECTION FOR ALL CEILING DEVICES PER DETAIL 13/M-17 AND SPECIFICATIONS.





### 6 KITCHEN UPBLAST EXHAUST FAN DETAIL

NO SCALE

NOTES

1. ARCHITECTURAL ROOF CURB INSTALLATION REQUIREMENTS SHALL SUPERCEDE THIS DETAIL.
2. INSTALL SHEETMETAL COVERING OVER WOOD BLOCKING IN THE AIRSTREAM OR OPEN TO THE CEILING CAVITY.





### 4 EXTERNALLY INSULATED DUCT SUPPORT DETAIL

NO SCALE

NOTES:

1. ROUND MEDIUM PRESSURE DUCT MAY BE SUPPORTED WITH DUCT STRAPS.
2. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.





### 2 DUCTWORK DETAIL

NO SCALE

NOTES:

1. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.





### 5 AIR DEVICE DETAIL

NO SCALE

NOTES:

1. RADIATION DAMPER SHALL ONLY BE PROVIDED IN CEILING DEVICES INSTALLED IN RATED CEILING ASSEMBLIES. REFER TO ARCHITECTURAL REFLECTED CEILING PLAN TO DETERMINE WHICH, IF ANY, CEILINGS ARE RATED.
2. REFER TO SPECIFICATIONS OF FOR ADDITIONAL INFORMATION AND REQUIREMENTS.




| TAP SIZE | ROD SIZE | DAMPER THICKNESS |
|---|---|---|
| UP TO 10" | 1/4" | 20 GA |
| OVER 10" | 3/8" | 18 GA |


HARDWARE MANUFACTURERS SHALL BE VENTLOCK, AMERICAN ELGEN, YOUNG AND DURO-DYNE.

### 3 DUCT TAP CONNECTION DETAIL

NO SCALE

NOTES:

1. DELETE CONICAL SECTION IF TOO LARGE FOR THE DUCT.
2. REFER TO SPECIFICATIONS OF FOR ADDITIONAL INFORMATION AND REQUIREMENTS.




### 1 MECHANICAL - ELECTRICAL COORDINATION DETAIL

NO SCALE

NOTES:

1. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

u

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILL ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD.
SUGAR LAND, TX 77498

SEAL

STATE OF TEXAS
TYLER W. HERRING
106052
LICENSED PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING


MECHANICAL NOTES AND DETAILS

U-M2.01


STANTON ENGINEERING GROUP
INFORMATION-DESIGN (713) 305-6282 | TEXAS ENG. FIRM REG. NO. F-018537-00


2025, ALL RIGHTS RESERVED


1300 W. SAM HOUSTON PARKWAY N., SUITE 175, HOUSTON, TX 77043





## 5 RESIDENTIAL CLOTHES DRYER FLUE VENT

NO SCALE

NOTES:

1. VENT TERMINATION AT WALL FOR STACKABLE WASHER/DRYER SHALL BE AT 60" AFF.
2. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.





## 4 SUPPLY/EXHAUST KITCHEN PLENUM DETAIL

NO SCALE

NOTES:

1. xxxxx





## 3 ROOF EXHAUST FAN AND VENT DETAIL

NO SCALE


NOTES:

1. NO WOOD BLOCKING SHALL BE LEFT EXPOSED IN THE CEILING PLENUM. COVER ALL EXPOSED WOOD WITH 1/2" SHEETROCK OR 20 GAUGE GALVANIZED SHEETMETAL.
2. ROOF VENT WILL NOT HAVE FAN/MOTOR ASSEMBLY, DISCONNECT SWITCH OR OBD.
3. ARCHITECTURAL ROOF CURB INSTALLATION REQUIREMENTS SHALL SUPERCEDE THIS DETAIL WHERE APPLICABLE.
4. ALL FANS SCHEDULED TO BE PROVIDED WITH 140MPH WIND RATING, INCLUDING FACTORY PROVIDED CURB. CURB INSTALLATION SHALL FOLLOW MANUFACTURER'S REQUIREMENTS FOR SECURING TO ROOF AND EQUIPMENT WHERE IT DIFFERS FROM THE DETAIL.
5. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.




## 2 INLINE EXHAUST FAN DETAIL

NO SCALE




## 1 CABINET EXHAUST FAN

NO SCALE

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

U

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT

SUGAR MILL ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD.
SUGAR LAND, TX 77498

SEAL

STATE OF TEXAS
TYLER W. HERRING
106052
LICENSED PROFESSIONAL ENGINEER
07.18.2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

MECHANICAL DETAILS (CONT'D.)

U-M2.02

STANTON ENGINEERING GROUP
INFORMATION@STANTONENG.COM (713) 300-9262
TEXAS ENG. FIRM REG. NO. F-018332 © 2025 ALL RIGHTS RESERVED
1300 W. SAM HOUSTON PARKWAY S., SUITE 121, HOUSTON, TX 77042

# ELECTRICAL AND LOW VOLTAGE LEGEND AND SYMBOLS

- A — TYPE 'A' LIGHT FIXTURE
- LIGHT FIXTURE WITH EMERGENCY BACKUP
- EXIT SIGN/EXIT SIGN WITH DIRECTIONAL ARROW
- EMERGENCY EGRESS LIGHT FIXTURE
- WALL MOUNTED FIXTURE OR SCONCE
- CEILING DOWNLIGHT OR CYLINDER
- WALL PACK FIXTURE
- INV — LIGHTING INVERTER

- $S^1/S^3/S^4$ — 20A, 277V TOGGLE/3-WAY/4-WAY SWITCH
- $S^2$ — 20A, 277V MOMENTARY 3-POSITION TOGGLE SWITCH
- $S^2$ — 20A, 277V, MOMENTARY 3-POSITION KEY SWITCH
- $S^1/S^3/S^4$ — 20A, 277V MAINTAINED 2-POSITION/3-WAY/4-WAY KEY SWITCH
- $S^{LT}$ — 20A, 277V TOGGLE SWITCH W/ INTEGRAL NIGHT LIGHT
- $S^{MP}$ — MOTOR RATED ON/OFF SWITCH, MP W/ PILOT LIGHT (SWITCH RATING SHALL BE ≥ UPSTREAM OCPD & VOLTAGE)
- DPST $ — DOUBLE POLE SINGLE THROW (DPST) SWITCH WITH RED PILOT LIGHT.
- TDR — TIMER SWITCH

## NETWORK LIGHTING CONTROLS

- MB — MULTIBUTTON LOW VOLTAGE LIGHTING SWITCH PROVIDE NUMBER OF BUTTONS INDICATED IN SINGLE PLATE.
- MD — MULTIPLE DIMMER SWITCHES PROVIDE NUMBER OF SWITCHES INDICATED IN SINGLE PLATE.
- MK — MULTIPLE KEY TYPE SWITCHES PROVIDE NUMBER OF SWITCHES INDICATED IN SINGLE PLATE.
- VSC — WALL SENSOR SWITCH
- $D — 20A, 277V, STANDALONE DIMMER SWITCH (DISPLAY CABINET)
- OCC — 360° CEILING SENSOR
- OCC — 180° CEILING SENSOR
- OCC — CEILING SENSOR
- OC — WALL MOUNT SENSOR
- PCO — DAYLIGHT PHOTOSENSOR
- RC / RCK — LIGHTING ROOM CONTROLLER/POWER PACK
- ELR — EMERGENCY LIGHTING RELAY/CONTROL UNIT
- PLC — PLUG LOAD CONTROLLER

- 20A, 125V SIMPLEX/DUPLEX/QUAD RECEPTACLE
- GFI — 20A, 125V DUPLEX RECEPTACLE WITH GFCI PROTECTION
- GFI WP — 20A, 125V DUPLEX RECEPTACLE WITH GFCI PROTECTION AND WEATHERPROOF COVER.
- GFI — REMOTE GFCI DEVICE, REF SPECS AND EDF GFI DETAIL.
- USB-A — 20A, 125V DUPLEX/QUAD RECEPTACLE W/ USB-A PORTS PROVIDE 2-5A PORTS PER DEVICE — HUBBELL USB20A5
- IG — 20A, 125V SIMPLEX/DUPLEX/QUAD IG/COMPUTER RECEPTACLE
- GFI IG — 20A, 125V, IG/COMPUTER DUPLEX RECEPTACLE WITH GFCI
- PLUG LOAD CONTROLLED DUPLEX
- NEMA IEC CS — NEMA/IEC/CS NUMBERED POWER OUTLET MATCH PROVIDED EQUIPMENT CONNECTION OR CIRCUIT.
- TV IG — 20A, 125V IG DUPLEX RECEPTACLE AT PROJECTOR, TV, OR INTERACTIVE MEDIA LOCATION.
- LOW VOLTAGE OUTLET
- CEILING MOUNTED RECEPTACLE
- CEILING MOUNTED LOW VOLTAGE OUTLET
- SINGLE SERVICE FLOOR BOX WITH DUPLEX/QUAD REC
- SINGLE SERVICE FLOOR BOX WITH DUPLEX/QUAD IG REC
- SINGLE SERVICE LOW VOLTAGE FLOOR BOXES
- MULTI SERVICE FLOOR BOX WITH QUAD/QUAD IG REC
- CR — CORD REEL
- DROP CORD
- EPO — EMERGENCY POWER OFF (EPO) SWITCH
- PB — PUSH BUTTON
- SP — TELEPOWER POLE

- J — J-BOX
- CEILING MOUNTED J-BOX
- CA — J-BOX FOR ACCESS CONTROL DEVICE
- HD — JUNCTION BOX AND FINAL CONNECTION TO HAND DRYER BY DIVISION 26.
- HDWR — JUNCTION BOX AND FINAL CONNECTION TO ELECTRIFIED DOOR HARDWARE BY DIVISION 26.
- HEAT — JUNCTION BOX AND FINAL CONNECTION TO HEAT TRACE EQUIPMENT BY DIVISION 26.
- WC — JUNCTION BOX AND FINAL CONNECTION TO POWERED PLUMBING EQUIPMENT BY DIVISION 26.
- SF — JUNCTION BOX AND FINAL CONNECTION TO SYSTEM FURNITURE BY DIVISION 26.

- CONTACTOR
- NON-FUSED DISCONNECT SWITCH
- NON-FUSED DOUBLE THROW DISCONNECT
- FUSED DISCONNECT SWITCH
- DISCONNECT/CB WITH SHUNT TRIP
- CB — ENCLOSED CIRCUIT BREAKER
- MOTOR STARTER 'VFD' INDICATES VARIABLE FREQUENCY DRIVE MOTOR STARTER
- MOTOR STARTER WITH INTEGRAL DISCONNECT
- MOTOR
- TC — TIME CLOCK

- ELECTRICAL PANELBOARD
- ELECTRICAL METER
- SPS — TVSS OR SPD
- GANN — GENERATOR REMOTE ANNUNCIATOR

- LOW VOLTAGE CABLING PATHWAY, REF. SPECIFICATIONS

## KITCHEN SYMBOL LEGEND

- LOAD CENTER, BY FOOD SERVICE PROVIDE UNDERGROUND CONDUIT STUBBED UP AT LOAD CENTER LOCATION PER SUBMITTAL SHOP DRAWINGS.
- P — POINT OF SALE EQUIPMENT, BY FOOD SERVICE. PROVIDE UNDERGROUND CONDUIT STUBBED UP POS LOCATION PER SUBMITTAL SHOP DRAWINGS.
- F — REMOTE FIRE PULL, REFERENCE INSTALLATION DETAIL
- B — BELL/BUZZER WITH 120V TO LOW VOLTAGE TRANSFORMER
- D — DROP CORD
- DB — DOORBELL BUTTON
- V — CEILING STROBE FOR ENTRAPMENT ALARM
- V CLR/FRZR — WALL STROBE FOR ENTRAPMENT ALARM

## COORDINATION SYMBOL LEGEND

- DDC — HVAC CONTROL PANEL. REQUIRES POWER AND DATA CONNECTIONS WITHIN CABINET COOR EXACT LOCATION AND REQUIREMENTS WITH CONTROLS CONTRACTOR PRIOR TO ROUGH-IN.
- SD — SMOKE DAMPER
- FSD — FIRE/SMOKE COMBINATION DAMPER
- M / MD — MOTORIZED DAMPER

## SITE PLAN

- UTILITY POLE
- POLE MOUNTED TRANSFORMER BANK
- SITE POLE LIGHT
- UGE — FLUSH IN GRADE ELECTRICAL PULL BOX
- LV UG — FLUSH IN GRADE, LOW VOLTAGE HAND HOLE
- CONCRETE BOLLARD
- (X)PP — POWER POLE
- (X)SP — SERVICE POLE OR RACK
- (X)XP — XFMR POLE
- (X)LVP — LOW VOLTAGE POLE
- (X)TP — TRANSITION POLE
- OHP — OVERHEAD POWER WIRING
- 480V — 480V OVERHEAD POWER WIRING
- UGP — UNDERGROUND PRIMARY ELECTRICAL
- UGS — UNDERGROUND SECONDARY ELECTRICAL
- UGE — UNDERGROUND EMERGENCY ELECTRICAL

## DIVISION 28 LEGENDS

### FIRE ALARM

- F — FIRE ALARM PULL STATION W/ STOPPER II
- F / S — WALL FIRE ALARM AUDIO/VISUAL DEVICE
- WP-S — OUTDOOR WEATHERPROOF FIRE AUDIO/VISUAL DEVICE
- H — WALL FIRE ALARM AUDIO DEVICE
- V — WALL FIRE ALARM VISUAL DEVICE
- H/S — CEILING FIRE ALARM AUDIO/VISUAL DEVICE
- S — CEILING FIRE ALARM AUDIO DEVICE
- V — CEILING FIRE ALARM VISUAL DEVICE
- DH / DV — DUCT SMOKE DETECTOR
- I / S — CEILING SMOKE DETECTOR
- H — CEILING HEAT DETECTOR
- CO — CEILING CARBON MONOXIDE DETECTOR
- S/CO — CEILING COMBINATION SMOKE/CARBON MONOXIDE DETECTOR
- FR — FIRE ALARM RELAY FOR STAGE SOUND RACK OVERRIDE
- BS — BEAM SMOKE DETECTOR
- FANN — FIRE ALARM REMOTE ANNUNCIATOR OR LOCAL OPERATOR'S CONSOLE
- FACP — FIRE ALARM CONTROL PANEL
- FAPS — FIRE ALARM POWER SUPPLY/AMPLIFIER

- G — INDICATES DEVICE WITH PROTECTIVE GUARD
- WG — INDICATES DEVICE WITH WIRE GUARD
- HC — INDICATES DEVICE RATED FOR HAZARDOUS CONDITIONS
- SD — SMOKE DAMPER
- FSD — FIRE/SMOKE COMBINATION DAMPER

## MULTI-SERVICE FLOOR BOX NOTES

FLOOR POWER AND LOW VOLTAGE

PROVIDE HEAVY-DUTY MULTI-GANG FLUSH IN GRADE OR FIRE RATED POKE-THRU OUTLET WITH HEAVY DUTY METAL HINGED COVER WITH CABLE EXIT SLOT.
FLOOR BOX MUST BE RATED FOR INSTALLATION IN GRADE.

FOR EACH FLOOR BOX PROVIDE:
1. PROVIDE:
   - 1.A. ONE QUAD OR TWO DUPLEX RECEPTACLES.
   - 1.B. PROVIDE IG RECEPTACLES WHERE SHOWN.
   - 1.C. POWER CONNECTION TO TABLE (WHERE SHOWN)
2. BLANK STAINLESS STEEL COVER FOR UN-USED GANGS.
3. PROVIDE ONE 3/4"C UNDERGROUND CONDUIT FOR POWER.
4. PROVIDE ONE 1"C UNDERGROUND CONDUIT WITH WATERPROOF INNER DUCT FOR DATA.
5. PROVIDE ONE 1"C UNDERGROUND CONDUIT WITH WATERPROOF INNER DUCT FOR LOW VOLTAGE CABLING
6. PROVIDE DIVIDERS TO MAINTAIN SEPARATION BETWEEN SERVICES.

UNDERGROUND CONDUITS MUST BE WATER TIGHT TO PREVENT MOISTURE ENTERING CONDUITS.
DO NOT COMBINE CONDUIT FOR POWER & LOW VOLTAGE.

REFERENCE FLOOR PLANS AND SPECIFICATIONS FOR QUANTITY OF DATA DROPS AND ADDITIONAL INFORMATION.

COORDINATE WITH ARCHITECT TO PROVIDE COVER/RING TO MATCH FLOOR MATERIAL AND SUBMIT COVER FINISH FOR ARCHITECT TO SELECT PRIOR TO ORDERING.

## GENERAL NOTES / TAGS

| | |
|---|---|
| +18" | INDICATES DEVICES AT +18" AFF |
| +42" | INDICATES DEVICES AT +42" AFF |
| +96" | INDICATES DEVICES AT +96" AFF |
| +12 FT | INDICATES DEVICES AT +12 FT AFF, ETC. |
| * | INDICATES DEVICES ABOVE COUNTER, REF ARCH |
| CLG | INDICATES DEVICES AT CEILING |
| PMR | INDICATES PEDESTAL MOUNTED DEVICE, REF PMR DETAIL |
| TV | INDICATES DEVICES AT TELEVISION/DISPLAY LOCATION |
| IM | INDICATES DEVICES AT INTERACTIVE MEDIA LOCATION |
| PROJ | INDICATES DEVICES AT PROJECTOR LOCATION |
| S | INDICATES SURFACE MOUNTED DEVICE |
| IEC | INDICATES IEC POWER OUTLET |
| NEMA | INDICATES NEMA NUMBERED POWER OUTLET |
| GFI | INDICATES GROUND FAULT INTERRUPT (GFI) PROTECTION |
| WP | INDICATES WEATHERPROOF DEVICES |
| GFI WP | INDICATES GFI PROTECTED WEATHERPROOF DEVICE |
| G | INDICATES DEVICE WITH PROTECTIVE GUARD |
| WG | INDICATES DEVICE WITH WIRE GUARD |
| 3R | INDICATES NEMA 3R RATED DEVICE |
| 4XSS | INDICATES NEMA 4XSS RATED DEVICE |
| EM | INDICATES DEVICE ON EM/STANDBY POWER |
| VFD | INDICATES VARIABLE FREQUENCY DRIVE (VFD) |
| E | EXISTING DEVICES TO REMAIN |
| D | EXISTING DEVICES TO BE DEMO/REMOVED |
| R | EXISTING DEVICES TO BE RELOCATED |
| REP | EXISTING DEVICES TO BE REPLACED |
| | (X) = (E) FOR EXISTING |
| | (X) = (D) FOR DEMO |
| | (X) = (R) FOR RELOCATION |
| | (X) = (N) FOR NEW |

- HOMERUN TO CIRCUIT NOTED

1. RECEPTACLES AND DATA OUTLETS SHALL BE MOUNTED AT +18" AFF UNLESS NOTED ON THE DRAWINGS.
2. REF. SPECIFICATIONS FOR MOUNTING HEIGHT OF OTHER DEVICES.
3. ELECTRICAL RECEPTACLES, TELEPHONES, ETC... ARE SHOWN FOR GENERAL LOCATION. HEIGHTS ARE NOTED SO THE ESTIMATOR WILL KNOW WHETHER THEY ARE ABOVE OR BELOW COUNTERS. PRIOR TO INSTALLATION, REVIEW THE ARCHITECTURAL DRAWINGS AND SPECIFICATIONS. IN THE EVENT OF CONFLICT, THE ARCHITECT'S LOCATION WILL GENERALLY PREVAIL BUT SHOULD BE CLARIFIED BY RFI. PROVIDE DEVICES SHOWN ON THE ELECTRICAL DRAWING EVEN IF NOT SHOWN ON ARCHITECTURAL DRAWINGS.
4. COORDINATE POWER AND DATA WITH THE FURNITURE SUPPLIER PRIOR TO ROUGH-IN. AT CASEWORK WITH KNEE SPACE, MOUNT RECEPTACLES AND DATA OUTLETS IN KNEE SPACE. COORDINATE WITH ARCHITECT AND FURNITURE SUPPLIER TO ENSURE THAT PROTECTIVE GROMMETS ARE PROVIDED IN THE COUNTER.
4. ALL DEVICES SHOWN AT THE SAME LOCATION AND ELEVATION SHALL BE GROUPED TOGETHER AND SPACED 2 INCHES BETWEEN BOXES.
5. PROVIDE SS COVER PLATE FOR ALL EMPTY JBOX.
6. ALL NON-LOCKING 125V AND 250V, 15A AND 20A RECEPTACLES SHALL BE TAMPER RESISTANT TYPE.


ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |


u

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILL ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD.
SUGAR LAND, TX 77498

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER

07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL AND FIRE ALARM SCHEDULES
u-E.000


STANTON ENGINEERING GROUP
INFO@STANTONENG.COM (713) 365-6082


TEXAS ENG. FIRM REG NO. F-018330 | © 2025 ALL RIGHTS RESERVED


12808 W. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77064

PROVIDE CONDUIT & SLEEVES THRU FIRE WALLS, WALLS AND FLOORS FOR LOW VOLTAGE CABLING WIRING, ETC.

ALL CONDUIT & J-BOXES FOR LOW VOLTAGE CABLING SHALL BE PROVIDED AND INSTALLED BY THE ELECTRICAL CONTRACTOR. ALL LOW VOLTAGE CABLING IN WALLS, EXPOSED AREAS AND ABOVE INACCESSIBLE CEILINGS SHALL REQUIRE CONDUIT AND J-BOXES. REFERENCE SPECIFICATIONS AND TECHNOLOGY DOCUMENTS FOR ADDITIONAL INFORMATION/REQUIREMENTS.

PULL BOXES AND BELOW GRADE CONDUIT FOR LOW VOLTAGE CABLING, WIRING, ETC. BY ELEC CONTRACTOR.

## FIRE ALARM SYSTEM DESCRIPTION AND SEQUENCE OF OPERATION

1. FIRE ALARM SYSTEM SHALL BE DESIGNED TO MEET NFPA REQUIREMENTS AS WELL AS CITY AND NATIONAL BUILDING CODES. PROVIDE COMPLETE FIRE ALARM SYSTEM, DEVICES AND WIRING.
2. INSTALL FIRE ALARM CONTROL PANEL IN RECEPTION AREA. INSTALL REMOTE POWER SUPPLY PANELS IN MECHANICAL/ELECTRICAL ROOMS.
3. FIRE ALARM PANEL, POWER SUPPLIES, DEVICES, ETC. SHALL BE MANUFACTURED BY THE SAME MANUFACTURER AS THE FIRE ALARM CONTROL PANEL.
4. FIRE ALARM REMOTE POWER SUPPLIES AND PANELS SHALL BE LOCATED IN MECHANICAL OR ELECTRICAL ROOMS ONLY. DO NOT LOCATE IN STORAGE ROOMS, DATA CLOSETS OR FINISHED SPACES.
4. PROVIDE AUDIBLE, INTELLIGIBLE AND VISUAL ALARM COVERAGE OF THE AREA OF RENOVATION AS REQUIRED BY CODE.
5. PROVIDE SMOKE DETECTORS AT EACH FIRE ALARM PANEL, REMOTE TRANSPONDER PANEL, BOOSTER PANEL AND REMOTE ANNUNCIATOR PER NFPA 72.
6. IN ADDITION TO THE SPECIFIED FIRE ALARM EQUIPMENT, THE FIRE ALARM CONTRACTOR SHALL PROVIDE
   6.A. SURGE PROTECTORS FOR ALL NEW 120V POWER CONNECTIONS TO FIRE ALARM EQUIPMENT.
   6.B. SURGE PROTECTORS FOR ALL SIGNALING LINE CIRCUITS (SLC), NOTIFICATION CIRCUITS AND INITIATING CIRCUITS CONNECTED TO THE FIRE ALARM CONTROL PANEL WHICH LEAVE THE BUILDING.
7. SHOULD ANY DETECTOR, MONITOR OR PULL STATION ACTIVATE, ALL SPEAKERS SHALL SOUND AND STROBES FLASH. AIR HANDLING EQUIPMENT SHALL BE DEACTIVATED. AN ALARM SIGNAL SHALL BE SENT TO A REMOTE LOCATION VIA AUTOMATIC DIALER. ALSO, DE-ENERGIZE SUPPLY FANS, EXHAUST FANS AND OTHER AIR CIRCULATING DEVICES IF 2000 CFM OR OVER, SERVING THE AREA IN ALARM.
8. ALL LOW VOLTAGE WIRING SHALL BE FPLP RATED WIRE, WITH MINIMUM WIRE SIZE PER SPECIFICATIONS.
   8.A. PLENUM RATED CABLE ABOVE ACCESSIBLE CEILING SHALL BE SUPPORTED BY J-HOOKS, SPACED AT FOUR (4) FEET ON CENTER.
   8.B. INSTALL FIRE ALARM CABLES IN CONDUIT FOR AREAS WITHOUT CEILING OR ABOVE INACCESSIBLE CEILINGS.
   8.C. EXPOSED CONDUIT IN FINISHED SPACES SHALL BE ALLOWED WHERE NO OTHER OPTION EXISTS AND ONLY WITH PRIOR WRITTEN APPROVAL BY THE OWNER. ALL EXPOSED CONDUIT SHALL BE PAINTED TO MATCH.
   8.D. ALL CABLING THROUGH WALLS, FIRE WALLS AND FLOORS SHALL BE INSTALLED IN SLEEVES WITH PROTECTIVE BUSHINGS ON BOTH ENDS.
9. FIRE ALARM SYSTEM SHALL BE MONITORED BY A UL LISTED CENTRAL RECEIVING STATION.
10. INTERLOCK LIGHTING CONTROL PANELS WITH FIRE ALARM SYSTEM TO ENABLE ALL LIGHTING UPON ACTIVATION.
11. REFER TO THE WRITTEN SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.

## FIRE ALARM SYSTEM NOTES

1. GENERAL CONTRACTOR SHALL COORDINATE WITH ELECTRICAL AND FIRE ALARM SUBCONTRACTOR FOR LOCATIONS OF REMOTE POWER SUPPLIES. FIRE ALARM POWER SUPPLIES ARE NOT SHOWN ON THIS DRAWING AND SHALL BE LOCATED BY FIRE ALARM SUBCONTRACTOR IN ORDER TO ACCOMMODATE HIS FIRE ALARM SYSTEM BATTERY AND VOLTAGE DROP CALCULATIONS PER MANUFACTURER'S RECOMMENDATION & NFPA REQUIREMENTS. ELECTRICAL CONTRACTOR SHALL INCLUDE ADDITIONAL DEDICATED 120V CIRCUITS IN BASE BID TO SERVE FIRE ALARM POWER SUPPLIES IN DIFFERENT AREAS. PROVIDE 2–12 +12G, 3/4"C AND SPARE 20A/1P CB(S) IN LOCAL LIFE SAFETY EMERGENCY 120V PANELS TO SERVE FIRE ALARM REMOTE POWER SUPPLIES.
2. FIRE ALARM CONTRACTOR IS RESPONSIBLE FOR DESIGN AND FOR FINAL CORRECT LOCATION OF DEVICES TO RELIEVE NUISANCE ALARMS, SUCH AS INSTALLING A HEAT DETECTOR IN FRONT OF AN OVEN WHICH WILL RELEASE STEAM, THUS POTENTIALLY SETTING OFF THE ALARM. ALSO, THE CONTRACTOR IS RESPONSIBLE FOR DETECTORS REQUIRED BY CODE EVEN IF NOT SHOWN ON DRAWING, LIKE A CLOSET. IF THERE IS UNCERTAINTY, BRING UP DURING THE BID PROCESS AND THEY WILL BE ADDRESSED DURING THE BIDDING PROCESS.
3. FIELD VERIFY ENVIRONMENTAL ISSUES THAT CAN ADVERSELY AFFECT OPERATION OF SMOKE DETECTORS. DO NOT LOCATE NEAR AIR FLOW DEVICES LEADING TO PREMATURE BUILD UP OF DUST CAUSING NUISANCE TROUBLE SIGNALS. DEVICE RELOCATION OR TYPE CHANGE WILL BE COVERED UNDER WARRANTY.

## FIRE ALARM SCOPE OF WORK

1. THERE IS AN EXISTING FIRE ALARM SYSTEM IN EACH BUILDING.
   1.A. TEST THE EXISTING SYSTEM PRIOR TO BEGINNING DEMO. NOTE ANY FAULTS OR TROUBLES AND PROVIDE A WRITTEN REPORT TO THE OWNER.
   1.B. EXPAND THE EXISTING SYSTEM AS REQUIRED TO INTEGRATE THE NEW DEVICES IN THE AREA OF RENOVATION.
2. PROVIDE WIRING AND DEVICES AS INDICATED TO PROVIDE COMPLETE AUDIBLE, INTELLIGIBLE AND VISUAL ALARM COVERAGE OF RENOVATED AREAS AS REQUIRED BY CODE.
   2.A. PROVIDE SMOKE DETECTOR COVERAGE OF ALL STORAGE ROOMS AND ADDITIONALLY AS SHOWN ON THE DRAWINGS.
   2.B. PROVIDE HEAT DETECTOR COVERAGE OF THE KITCHEN, CUSTODIAL ROOMS, AND ADDITIONALLY AS SHOWN ON THE DRAWINGS.
   2.C. PROVIDE DUCT MOUNTED DETECTORS AT EACH NEW AIR HANDLING UNIT SUPPLY AND RETURN CONNECTION EXCEEDING 2000 CFM. IF FREE AIR RETURN, PROVIDE FREE AIR DETECTOR COVERAGE OF THE RETURN AIR OPENINGS TO THE MECHANICAL ROOM. ENSURE AIR FLOW CANNOT PREVENT OPERATION OF THE DETECTORS AND PROVIDE ADEQUATE CLEARANCE PER NFPA 72.
   2.D. CONTROL RELAYS SHALL BE LOCATED WITHIN 3 FT OF THE CONTROLLED CIRCUIT OR APPLIANCE.
3. PROVIDE SMOKE DETECTORS AT EACH NEW FIRE ALARM PANEL, REMOTE TRANSPONDER PANEL, BOOSTER PANEL AND REMOTE ANNUNCIATOR PER NFPA 72.
4. PROVIDE LED REMOTE ALARM WITH ENGRAVED STAINLESS STEEL PLATE WHERE DUCT DETECTORS ARE NOT LOCATED IN MECHANICAL ROOM, LOCATED ABOVE CEILINGS OR WHERE MOUNTED TOO HIGH OR VIEW IS BLOCKED BY DUCTWORK IN MECHANICAL ROOM.
   4.A. REMOTE LED LIGHT INDICATOR FOR DUCT SMOKE DETECTORS SHALL BE MOUNTED FLUSH IN CEILING OR MOUNTED IN WALL AT +7'FT.
   4.B. STAINLESS STEEL PLATE SHALL BE ENGRAVED WITH THE DUCT SMOKE DETECTOR AS–BUILT IDENTIFICATION NUMBER.
5. REFER TO THE WRITTEN SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.

## SPARES

1. THE FIRE ALARM CONTRACTOR SHALL INCLUDE IN HIS BID THE COST TO PROVIDE AND INSTALL THE ADDITIONAL SPARE PARTS AND ASSOCIATED CABLING PER THE SPECIFICATIONS. SPARES SHALL BE INSTALLED AS INSTRUCTED BY THE OWNER. UNINSTALLED DEVICES SHALL BE DELIVERED TO THE OWNER AS ATTIC STOCK.

## GENERAL RENOVATION AND REMODELING NOTES

1. READ ALL MEP AND ARCH. DRAWINGS TO IDENTIFY AREAS OF RENOVATION AND SCOPE OF WORK.
2. ALL RENOVATION AND DEMOLITION WORK SHALL NOT AFFECT AREAS NOT INCLUDED IN THE AREAS OF WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE CONTINUITY OF ALL SERVICES (POWER, TELEPHONE, FIRE ALARM, DATA, SECURITY, ETC.) IN NON–DEMOLITION/RENOVATION AREAS. ALL SERVICES SHALL BE MAINTAINED AT ALL TIMES.
3. ALL OUTAGES AFFECTING NON–DEMOLITION/RENOVATION AREAS SHALL BE SCHEDULED WITH THE OWNER WITH A MINIMUM 2 WEEKS ADVANCE NOTICE. OUTAGES SHALL BE COORDINATED WITH OTHER TRADES TO MINIMIZE THE QUANTITY AND IMPACT ON BUILDING OPERATION.
4. THIS ELECTRICAL DRAWING ONLY SHOWS SOME EXISTING ELECTRICAL PANELS, DEVICES AND LIGHT FIXTURES IN AREAS OF RENOVATION. ALL OTHER ELECTRICAL EQUIPMENT, WIRING DEVICES, LOW VOLTAGE SYSTEMS, J–BOXES AND CONDUITS SHALL BE LOCATED AND FIELD VERIFIED BY CONTRACTOR.
5. CONTRACTOR SHALL FIELD VERIFY AND MARK UP THE FOLLOWINGS IN AREAS OF RENOVATION:
   5.A. EXISTING DATA, AUDIO, VIDEO, SPEAKERS AND OTHER LOW VOLTAGE OUTLETS AND DEVICES.
   5.B. EXISTING CEILING MOUNTED PROJECTORS.
   5.C. EXISTING SECURITY, CCTV, ACCESS CONTROL DEVICES.
   5.D. EXISTING FIRE ALARM DEVICES.
   5.E. EXISTING WIRELESS ACCESS POINTS AND GRID LABELING.
   5.F. EXISTING LIGHT FIXTURES AND SWITCHES.
   5.G. EXISTING ELECTRICAL DEVICES, J–BOXES, CONDUIT, WIRING, WIRING SUPPORTS, ETC.
   5.H. EXISTING ELECTRICAL SWITCHGEAR.
   5.I. EXISTING CONTROL PANELS AND CONTROL CIRCUITS.
   5.J. EXISTING HANGER WIRE FROM CONC. CEILING.
6. ALL REMOVED DEVICES SHALL BE OFFERED TO THE OWNER AS SALVAGE.
7. ALL EXISTING DEVICES SHALL BE REINSTALLED IN NEW CEILINGS AT SAME LOCATION EXCEPT WHERE SHOWN TO BE NEW.
8. CONDUIT/WIRE NOT TO BE REUSED SHALL BE REMOVED ALL THE WAY BACK TO THE UPSTREAM EQUIPMENT.
   8.A. PROVIDE ADDITIONAL SUPPORTS FOR EXISTING CONDUIT/WIRE TO REMAIN TO MEET CURRENT CODE REQUIREMENTS.
9. ANY MATERIAL THAT HAS SALVAGE VALUE SHALL BE OFFERED TO THE OWNER, AND IF ACCEPTED, DELIVERED TO HIS WAREHOUSE. IF NOT ACCEPTED IT SHALL BE PROPERLY DISPOSED OF WITH THE OTHER CONSTRUCTION DEBRIS.
10. RELOCATE CONDUIT AS NECESSARY TO ALLOW NEW OR MODIFIED CONSTRUCTION. REPAIR EXISTING ELECTRICAL SYSTEMS DAMAGED BY CONSTRUCTION ACTIVITES.
11. WHERE PARTIAL CIRCUITS OR SYSTEMS ARE TO BE REUSED, ENSURE THAT THEY REMAIN ACTIVE. WHERE EXISTING EQUIPMENT IS RELOCATED OR REPLACED WITH NEW, MODIFY, EXTEND AND RELOCATE EXISTING CIRCUIT TO CONNECT TO EQUIPMENT, UNLESS SHOWN TO HAVE NEW CIRCUIT.
12. WHERE AUXILIARY SYSTEMS SUCH AS SECURITY, DATA, SOUND, ETC. INTERFACE WITH EXISTING EQUIPMENT THAT IS REPLACED OR MODIFIED (MECHANICAL, ELECTRICAL OR PLUMBING), DISCONNECT AND RECONNECT THESE SYSTEMS.
13. WHERE NEW CIRCUIT BREAKERS ARE TO BE INSTALLED IN EXISTING PANELS OR SWITCHBOARD, VERIFY THAT THE CIRCUIT BREAKER WILL FIT IN THE ALLOTTED SPACE. PROVIDE NEMA 1 ENCLOSURE ADJACENT TO PANEL & WIRE CONNECT TO BUSSING IF THERE IS INSUFFICIENT SPACE.
14. WHERE PARTIAL CIRCUITS OR SYSTEMS ARE TO BE REUSED, ENSURE THAT THEY REMAIN ACTIVE. WHERE EXISTING EQUIPMENT IS RELOCATED OR REPLACED WITH NEW, MODIFY, EXTEND AND RELOCATE EXISTING CIRCUIT TO CONNECT TO EQUIPMENT, UNLESS SHOWN TO HAVE NEW CIRCUIT.
15. WHEN REPLACING LIGHTS AND CEILINGS, ENSURE THAT EXISTING DATA, TELEVISION AND PA CABLES TO REMAIN CONTINUE TO MEET THE CURRENT STANDARDS. FOR DATA CABLES, THIS IS THE IEEE 802.1. FOR TELEVISION AND PA CABLE, A FOUR INCH DISTANCE IS NEEDED FROM ALL LIGHT FIXTURES. NEW DROP LOCATION SHOULD BE WITHIN THREE FEET OF POWER OUTLET.
16. PAINT NEW AND EXISTING EXPOSED RACEWAY IN AREAS OF RENOVATION TO MATCH FINISHES.
17. ANY DAMAGE TO EXISTING BUILDING, ELECTRICAL EQUIPMENT, WIRING DEVICES, CONDUIT, WIRING, ETC. SHALL BE REPLACED BY THE CONTRACTOR AT NO COST TO THE OWNER. ALL MATERIALS USED FOR THE REPLACEMENT MUST MEET RENOVATION PROJECT STANDARDS.
18. INTERESTED CONTRACTORS MUST VISIT THE SITE PRIOR TO BIDDING TO BECOME FAMILIAR WITH THE PROJECT REQUIREMENTS AND EXISTING CONDITIONS AND SHALL INCLUDE IN THEIR PROPOSALS COSTS TO REPAIR, RELOCATE, MODIFY AND REMOVE EXISTING ELEMENTS AS REQUIRED TO COMPLETE INSTALLATION OF ALL SYSTEMS SHOWN ON THESE DRAWINGS.
19. SEE DRAWINGS FOR ADDITIONAL REQUIREMENTS.

## ELEC REQUIREMENTS FOR BUILDING RENOVATION

1. ELECTRICAL CONTRACTOR SHALL BEGIN FIELD VERIFYING ALL EXISTING BRANCH CIRCUITS FOR EXISTING AREAS TO BE RENOVATED IMMEDIATELY AFTER THE CONTRACT IS ISSUED.
2. ELECTRICAL CONTRACTOR SHALL FIELD VERIFY EXISTING CIRCUITS WITH OWNER'S MAINTENANCE PERSONNEL AFTER NORMAL BUILDING HOURS AS REQUIRED.
3. ELECTRICAL CONTRACTOR SHALL INCLUDE COST RELATED TO FIELD VERIFY EXISTING CIRCUITS IN BASE PROPOSAL.
4. FIND AND RECORD ALL EXISTING DEVICES IN CEILINGS, WALLS AND CASEWORK IN AREAS TO BE RENOVATED. PROVIDE A COPY OF THE FIELD VERIFIED DEVICE DRAWINGS TO OWNER PRIOR TO BEGINNING WORK.
5. ALL EXISTING DEVICES TO REMAIN SHALL BE REINSTALLED IN NEW CEILINGS AND WALLS EXCEPT WHERE INDICATED TO BE REMOVED/RELOCATED/REPLACED.
6. EXISTING DEVICES IN WALLS TO BE FURRED OUT OR RECEIVE NEW SURFACE TREATMENT SHALL REMAIN. EXTEND JBOX TO NEW WALL SURFACE AND RECONNECT TO EXISTING CIRCUITS. EXTEND WIRING/CABLING FROM NEAREST ACCESSIBLE POINT AS NECESSARY.
7. REINSTALL ALL DEVICES NOT SHOWN TO BE REMOVED.
8. EXISTING LIGHT FIXTURES SHALL REMAIN EXCEPT WHERE SHOWN AS NEW. EXTEND EXIST CONDUIT AND WIRE DOWN TO NEW LIGHT FIXTURES, REFERENCE SPECIFICATIONS FOR ADDITIONAL INFORMATION.
9. ALL EXISTING EXIT SIGNS SHALL BE REINSTALLED AND RECONNECTED TO EXISTING CIRCUITS EXCEPT IN CORRIDORS AND AREAS OF RENOVATION SHOWING NEW.
10. ALL NEW DEVICES IN EXISTING WALLS IN FINISHED SPACES SHALL BE INSTALLED FLUSH MOUNTED, NO EXPOSED CONDUIT OR WIREMOLD ALLOWED. CUT EXISTING WALLS AND PATCH/REPAIR TO MATCH EXISTING AS REQUIRED.
    10.1. DEVICES/CONDUIT IN CUSTODIAL, MECHANICAL AND ELECTRICAL ROOMS MAY BE EXPOSED AND SURFACE MOUNTED.
11. PROVIDE NEW DIRECTORY FOR ALL EXISTING AND NEW PANELS SHOWING FIELD VERIFIED CIRCUITS.
12. ANY FEEDER AND BRANCH CIRCUIT NOT TO BE REUSED SHALL BE REMOVED COMPLETELY UP TO CB IN EXISTING PANEL.
13. ANY CIRCUIT OR PARTIAL CIRCUIT TO BE REUSED SHALL REMAIN ACTIVE.

## GENERAL EQUIPMENT ELECTRICAL NOTE

THE ELECTRICAL DESIGN HAS BEEN COORDINATED FOR SPACE, INSTALLATION AND ELECTRICAL REQUIREMENTS WITH EQUIPMENT THAT IS SCHEDULED BY OTHER DIVISIONS. THE REQUIREMENTS FOR OTHER EQUIPMENT AND MODELS FROM ACCEPTABLE MANUFACTURERS HAVE NOT BEEN VERIFIED OR COORDINATED. THE GENERAL CONTRACTOR SHALL VERIFY THESE REQUIREMENTS PRIOR TO USING OTHER EQUIPMENT IN HIS BID AND INCLUDE ANY ADDITIONAL COSTS FOR INSTALLATION OF THE EQUIPMENT. THIS INCLUDES GENERAL CONSTRUCTION AND MEP COSTS.

ELECTRICAL CONTRACTOR SHALL COORDINATE WITH OWNER/OTHER TRADES FOR EXACT ELECTRICAL REQUIREMENTS OF EQUIPMENT PRIOR TO ORDERING CB(S). FIELD VERIFY EQUIPMENT NAMEPLATE RATINGS AND EQUIPMENT CONNECTION LOCATIONS WITH OTHER TRADES PRIOR TO ROUGH–IN.

TYPICAL OF HVAC EQUIPMENT, SHOP EQUIPMENT, KITCHEN EQUIPMENT, ELECTRIC ROLLUP DOORS, ETC.

## GENERAL ELECTRICAL NOTES

1. REFER TO THE WRITTEN SPECIFICATIONS FOR ADDITIONAL INFORMATION.
2. INSTALL SYSTEMS IN ACCORDANCE WITH THE NATIONAL ELECTRIC CODE.
3. PROVIDE LIGHT FIXTURE FIRE PROTECTION AND CONDUIT FIRE SEALING TO MAINTAIN FIRE RATING OF WALLS AND CEILINGS PER ARCHITECT'S SCHEDULE. REF. SPECIFICATIONS AND ARCH. DRAWINGS FOR ADDITIONAL INFORMATION.
4. ELECTRICAL RECEPTACLES, TELEPHONES, ETC... ARE SHOWN FOR GENERAL LOCATION. HEIGHTS ARE NOTED SO THE ESTIMATOR WILL KNOW WHETHER THEY ARE ABOVE OR BELOW COUNTERS. PRIOR TO INSTALLATION, REVIEW THE ARCHITECTURAL DRAWINGS AND SPECIFICATIONS. IN THE EVENT OF CONFLICT, THE ARCHITECT'S LOCATION WILL GENERALLY PREVAIL BUT SHOULD BE CLARIFIED BY RFI. PROVIDE DEVICES SHOWN ON THE ELECTRICAL DRAWING EVEN IF NOT SHOWN ON ARCHITECTURAL DRAWINGS.
5. COORDINATE POWER AND DATA WITH THE FURNITURE SUPPLIER PRIOR TO ROUGH–IN. AT CASEWORK WITH KNEE SPACE, MOUNT RECEPTACLES AND DATA OUTLETS IN KNEE SPACE. COORDINATE WITH ARCHITECT AND FURNITURE SUPPLIER TO ENSURE THAT PROTECTIVE GROMMETS ARE PROVIDED IN THE COUNTER.
6. DO NOT INSTALL ELECTRICAL PANELS AND TRANSFORMERS UNTIL 1/4" SCALE DRAWINGS SHOWING LOCATION OF THIS EQUIPMENT RELATIVE TO MECHANICAL/PLUMBING EQUIPMENT, DUCTWORK AND PIPING IS SUBMITTED AND APPROVED. NEC CODE CLEARANCE MUST BE MAINTAINED.
7. ELECTRICAL EQUIPMENT HAS BEEN COORDINATED WITH PIPING AND DUCTWORK. DO NOT RELOCATE PANELS WITHOUT PRIOR APPROVAL.
8. ELECTRICAL DEVICES IN FIRE RATED WALLS SHALL BE A MINIMUM OF 24" AWAY FROM DEVICES ON THE OPPOSITE SIDE OF THE WALL TO MAINTAIN FIRE RATING.
9. MINIMUM SIZE CONDUIT FOR POWER SHALL BE 3/4", MIN. SIZE FLEX CONDUIT MAY BE 1/2". MINIMUM SIZE CONDUIT FOR DATA SHALL BE 1"C. DO NOT COMBINE CONDUIT FOR DATA.
10. MAX. LENGTH FOR FLEX CONDUIT SHALL BE 6 FT. ALL FLEX CONDUIT SHALL BE LISTED FOR GROUNDING.
11. LIGHT FIXTURE WHIPS MAY BE MIN. 1/2" FLEX CONDUIT WITH MIN. #12 WIRE. LIGHT FIXTURE WHIPS SHALL BE NO MORE THAN 6 FT LONG.
12. PROVIDE GREEN GROUND WIRE WITH ALL CIRCUITS SIZED PER NEC. BOND GREEN GROUND WIRE TO EACH END OF CONDUIT.
13. GROUND TRANSFORMER SECONDARIES TO BUILDING STEEL AND GROUND ROD. PROVIDE CONDUIT TO PROTECT GROUNDING CONDUCTOR AND BOND EACH END OF CONDUIT TO GROUNDING SYSTEM. MIN. SIZE OF CONDUIT FOR GROUND WIRE SHALL BE 3/4"C.
14. PROVIDE J–BOXES, CONDUIT AND SLEEVES THRU ALL FIRE WALLS FOR DATA, TELEPHONE, SECURITY, FIRE ALARM AND SOUND SYSTEMS WIRINGS, ETC. SEE SPECIFICATIONS.
15. PROVIDE PULL BOXES, JUNCTION BOXES, WIRING TROUGHS AND CABINETS WHEREVER REQUIRED FOR PROPER INSTALLATION OF VARIOUS ELECTRICAL SYSTEMS.
16. WHERE PORTIONS OF INTERIOR RACEWAY SYSTEM ARE EXPOSED TO WIDELY DIFFERENT TEMPERATURES, PROVIDE AIR SEALING PER NEC TO PREVENT CIRCULATION OF AIR FROM WARMER TO A COOLER SECTION.
17. ALL WIRING SHALL BE 600 VOLT, SOFT DRAWN ANNEALED COPPER, 98% CONDUCTIVITY, CONTINUOUS FROM OUTLET TO OUTLET. MINIMUM WIRE SIZE #12. ALL WIRE SHALL BE STRANDED TYPE THHN OR THWN–2 (WET RATED FOR 90° C). ALL WIRES SHALL BE COLOR CODED WITH SAME COLOR CONNECTED TO SAME UNGROUNDED PHASE THROUGHOUT THE INSTALLATION.
18. ALL ELECTRICAL WIRING SHALL BE INSTALLED IN CONDUIT. NO SURFACE MOUNTED WIREMOLD SHALL BE ALLOWED IN FINISHED SPACES. MC CABLE SHALL BE ALLOWED INSIDE EXIST STUD WALLS OR CHASE WALLS.
19. PROVIDE AND INSTALL FINAL CONNECTIONS TO ALL EQUIPMENT PROVIDED BY OTHER TRADES AND/OR FURNISHED BY OWNER INCLUDING ALL NECESSARY CONDUIT, CORDS, PLUGS, WHIPS, HARDWIRING, ETC. IN PARTICULAR CONFIRM CONNECTION REQUIREMENTS WITH DELIVERED EQUIPMENT PRIOR TO ROUGH–IN.
20. ALL MATERIAL MUST BE NEW AND OF GOOD QUALITY AND SHALL BEAR THE STAMP OF APPROVAL OF THE UNDERWRITERS' LABORATORIES, INC. (U.L.).

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

u

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILL ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD.
SUGAR LAND, TX 77498

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
LICENSED
PROFESSIONAL ENGINEER

07.18.2025

MWA ARCHITECTS

ARCHITECTS
AND PLANNING
CONSULTANTS

11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL AND FIRE ALARM NOTES

u-E.001

STANTON ENGINEERING GROUP

INFO@STANTON–ENG.COM | (713) 360–4080 | TEXAS ENG. FIRM REG. NO. F–01853 | © 2025 ALL RIGHTS RESERVED
12999 W. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77064





SYMBOL: ▽

## 1 TYPICAL DATA OUTLETS

NO SCALE

NOTES:
1. PROVIDE DEEP 4 11/16" X 4 11/16" X 2 1/8", 2-GANG BACK BOX FOR ALL DATA OUTLETS.
   1.A. PROVIDE SINGLE GANG MUDRING FOR DATA OUTLETS WITH 1-4 DROPS.
   1.B. PROVIDE PULL STRING IN ALL LOW VOLTAGE CONDUITS.
2. LOW VOLTAGE CABLING AND DEVICES BY DIVISION 27.
3. REFERENCE TECHNOLOGY DRAWINGS FOR ADDITIONAL INFORMATION.





SYMBOL: ⏚ SYMBOL: ⏚

## 2 TYPICAL POWER & DATA OUTLET DETAIL

NO SCALE

NOTES:
1. LOCATE DEVICES GROUPED TOGETHER AS CLOSELY TOGETHER AS POSSIBLE.
   1.A. USE CADDY TSGB16, RBS16 OR SIMILAR MOUNTING BAR IN SHEETROCK WALLS.




SYMBOL: ⏚ SYMBOL: ⏚ SYMBOL: ⏚USB SYMBOL: ⏚GFI

## 3 TYPICAL ELECTRICAL DEVICES

NO SCALE

NOTES:
1. ALL DEVICES SHALL BE COLOR CODED PER SPECIFICATIONS WITH 302/304 STAINLESS STEEL, STANDARD SIZE, FACEPLATES.
2. ONLY SELECT RECEPTACLES ARE SHOWN HERE. PROVIDE SIMILAR LABELS ON ALL SWITCHES, NEMA POWER OUTLETS, ETC.
3. PROVIDE LABEL WITH RED TEXT READING "EMERGENCY" FOR DEVICES ON GENERATOR FED CIRCUITS.
4. PROVIDE TYPEWRITTEN OR PREMADE CIRCUIT LABELS INDICATING THE ELECTRICAL CIRCUIT ON:
   4.A. INSTALLED WIRING AT EACH SPLICE POINT
   4.B. EACH J-BOX ABOVE CEILING WITH WIRING INSTALLED OR MODIFIED AS PART OF THIS PROJECT.
   4.C. AFFIXED TO THE FRONT OF EACH NEW AND EXISTING DEVICE FACEPLATE IN THE AREA OF RENOVATION.
        CIRCUIT LABEL
   XX-## A. XX = PANEL DESIGNATION
        B. ## = AS-BUILT CIRCUIT DESIGNATION

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

u

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILL ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD.
SUGAR LAND, TX 77498

SEAL




07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL DEVICE DETAILS

u-E.010


STANTON ENGINEERING GROUP
INFORMATION - ENGINEER (713) 360-4636
TEXAS ENGINEERING FIRM REGISTRATION NO. F-619332 | 2025 ALL RIGHTS RESERVED
1300 W. SAM HOUSTON PARKWAY N., SUITE 121, HOUSTON, TX 77043




## 10 MECHANICAL - ELECTRICAL COORDINATION DETAIL

NO SCALE

**COORDINATE WITH OTHER TRADES TO ENSURE NO PIPING AND DUCTWORK ABOVE ELECTRICAL EQUIPMENT AS SHOWN. PROVIDE WORKING CLEARANCE IN FRONT OF STARTERS, DISCONNECTS, PANELS, XFMRS AND ADDITIONALLY PER CODE.**




## 11 CONDUIT ROOF PENETRATION DETAIL


NO SCALE




## 12 ROOF AND CANOPY CONDUIT SUPPORT DETAIL

NO SCALE

1. COORDINATE WITH ARCHITECTURAL DRAWINGS, DETAILS, SPECIFICATIONS AND OTHER TRADES.





## 13 CANOPY LIGHT MOUNTING DETAIL TYPE 1

NO SCALE

NOTES:

1. MOUNTING PLATES SHALL BE WELDED TO CANOPY TO MOUNT LIGHT FIXTURES.
2. FOR FIXTURES WITH END CONDUIT ATTACHMENTS ALL CANOPY PENETRATIONS SHALL BE MADE OFF CENTER FROM THE FIXTURE WIRING ENTRY POINT AND SHALL HAVE WEATHERTIGHT SEALING. (SHOWN HERE)
3. CANOPY PENETRATIONS ABOVE FIXTURES SHALL BE PERMITTED ONLY WHERE THE SUPPLIED FIXTURE HAS NO END CONDUIT ATTACHMENTS.
4. CONDUIT SHALL BE SEALED BOTH ABOVE AND BELOW THE CANOPY PENETRATION AND AGAIN AT THE FIXTURE ENTRY POINT TO PREVENT WATER FROM ENTERING THE LIGHTING FIXTURE.
5. CANOPY PENETRATIONS SHALL BE MADE AS CLOSE TO CONDUIT ENTRY PENETRATION POINT AS POSSIBLE AND CONDUIT SHALL BE ROUTED TO MINIMIZE EXPOSED CONDUIT.





## 7 EDF GFI PROTECTION DETAIL

NO SCALE

NOTES:

1. MODIFY EXISTING WALL AS NEEDED TO INSTALL NEW RECEPTACLE AND REMOTE GFI TEST SWITCH. PATCH/REPAIR WALL AS NEEDED TO MATCH EXISTING.
2. WIRE NEW RECEPTACLE DOWNSTREAM OF REMOTE GFI TEST SWITCH.
3. REMOTE GFI TEST SWITCH SHALL BE A DEAD FRONT GFI DEVICE TO BE INSTALLED FLUSH MOUNTED IN WALL WITH EDF SERVED AND PROVIDE GFI PROTECTION FOR THE RECEPTACLE LOCATED WITHIN THE EDF HOUSING.
4. GFI TEST SWITCH SHALL BE READILY ACCESSIBLE PER NEC 210.8.
5. COORDINATE RECEPTACLE LOCATION(S) WITHIN EDF HOUSINGS WITH MANUFACTURER'S INSTALLATION INSTRUCTIONS.





## 8 TRANSFORMER CONNECTION AND GROUNDING DETAIL

NO SCALE


NOTES:

1. INSTALL GROUND ROD ADJACENT TO TRANSFORMER AND SEAL PENETRATION AROUND GROUND ROD.
2. WHERE AN ISOLATED GROUND IS PROVIDED MAKE THE CONNECTION AT THE TRANSFORMER AND RUN DIRECTLY TO THE ISOLATED GROUND BAR IN THE PANELBOARD. DO NOT DEFINE THE ISOLATED GROUND AT THE PANELBOARD.
3. FINAL CONNECTIONS TO TRANSFORMERS SHALL BE MADE IN FLEXIBLE CONDUIT. PROVIDE LIQUID TIGHT CONSTRUCTION AND FITTINGS IN WET, DAMP OR OUTSIDE AREAS EXCEPT WHERE LOCATED IN AIR HANDLING ROOMS. REFERENCE SPECIFICATIONS FOR ADDITIONAL INFORMATION.





## 9 PIGTAIL WIRING DETAIL FOR ELECTRICAL DEVICE

NO SCALE





## 1 CONDUIT/J-BOX DETAIL FOR LIGHT FIXTURES IN LAY-IN CEILING

NO SCALE




## 2 FIXTURE SUPPORT DETAIL

NO SCALE





## 3 TRAPEZE MOUNTED CONDUIT DETAIL

NO SCALE

NOTES:

1. ALL SUPPORT DEVICES SHALL BE UL LISTED AND NEC APPROVED.
2. REFER TO NEC FOR CONDUIT SUPPORT SPACING.





## 4 WALL MOUNTED CONDUITS

NO SCALE

NOTES:

1. ALL SUPPORT DEVICES SHALL BE UL LISTED AND NEC APPROVED.
2. REFER TO NEC FOR CONDUIT SUPPORT SPACING.





## 5 FIREWALL PENETRATION DETAIL

NO SCALE

NOTES:

1. FIRE RATING OF COMPLETED FIREPROOFED ASSEMBLY SHALL BE EQUAL OR EXCEED RATING OF WALL.




## 6 GROUNDING BUSHING WIRING DETAIL

NO SCALE

NOTE:

1. PROVIDE AND INSTALL GROUNDING BUSHINGS FOR DISCONNECT SWITCHES, PANELS AND TRANSFORMERS.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

u

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILL ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD.
SUGAR LAND, TX 77498

SEAL




07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL DETAILS

u-E.011

STANTON ENGINEERING GROUP
INFORMATION-DESIGN
C*(713)-360-4080
TEXAS ENG. FIRM REGI NO. F-018532 | TBPE NO. F-018532 | 2025 ALL RIGHTS RESERVED
12800 W. LITTLE YORK ROAD, SUITE 125, HOUSTON, TX 77041




## 5 TYPICAL BRANCH CIRCUIT PANEL LABELING DETAIL

NO SCALE

NOTES:

1. LAYOUT OF PANELBOARD, INCLUDING LOCATIONS OF NAMEPLATES, CIRCUIT DIRECTORY, AND OTHER LABELING IS SHOWN FOR REFERENCE ONLY, FIELD LOCATE AS NEEDED BASED ON TRUE EQUIPMENT LAYOUT AND DIMENSIONS.
2. REFERENCE OWNER'S DESIGN GUIDELINES FOR ADDITIONAL LABELING REQUIREMENTS.

(1) PROVIDE LAMACOID NAMEPLATE WITH 5/16" LETTERS SHOWING PANEL NAME, AMPERAGE RATING, VOLTAGE, AND FROM WHERE POWER IS DERIVED. ATTACH WITH MASTIC AND TWO SCREWS. COORDINATE TO GIVE SAME NAME AS PANEL SCHEDULE. IF USED AS MAIN SERVICE PANEL, PROVIDE SHORT CIRCUIT AVAILABLE AND RATING INFORMATION.

(2) PROVIDE PERMANENT ARC FAULT WARNING LABEL.


(3) FOR ALL NEW ELECTRICAL EQUIPMENT, PROVIDE PERMANENTLY AFFIXED LABEL STATING FAULT CURRENT AT THE TIME OF INSTALLATION AND CALCULATION. THE LABEL SHALL BE MINIMUM 2" X 3" IN SIZE, AND INCLUDE THE DATE OF THE CALCULATION. REFERENCE ELECTRICAL DRAWINGS AND EQUIPMENT SHORT CIRCUIT ANALYSIS TABLE. ATTACH WITH MASTIC AND TWO SCREWS.

(4) PROVIDE INFORMATION PER INDUSTRY STANDARDS, BUT SHALL INCLUDE VOLTAGE, PHASE, BUS AMPERAGE, AND SHORT CIRCUIT RATING

(5) FOR EACH CIRCUIT PROVIDE PERMANENT LABEL INDICATING CIRCUIT BREAKER NUMBER, NUMBER SHALL MATCH CIRCUIT DIRECTORY.

(6) CIRCUIT DIRECTORY TO BE COMPLETED AT END OF JOB, TYPEWRITTEN, STATING EQUIPMENT OR ROOMS SERVED BY CIRCUIT. EVEN CIRCUIT ON RIGHT SIDE OF CARD, ODD ON LEFT. PROVIDE LAMINATED DIRECTORY FOR EXTERIOR OR WET LOCATIONS.

(7) PROVIDE PERMANENT LABEL INDICATING COLOR CODING OF PHASE CONDUCTORS BASED ON VOLTAGE USING BUILDING COLOR SCHEME AS IDENTIFIED IN THE OWNER'S DESIGN GUIDELINES.




## 1 TYPICAL DISCONNECT, STARTER, & CONTACTOR LABELING DETAIL

NO SCALE

NOTES:

1. LOCATIONS OF NAMEPLATES SHOWN FOR REFERENCE ONLY, FIELD LOCATE AS NEEDED BASED ON TRUE EQUIPMENT LAYOUT AND DIMENSIONS. REFERENCE OWNER'S DESIGN GUIDELINES FOR ADDITIONAL LABELING REQUIREMENTS.

(1) PROVIDE AN ENGRAVED NAMEPLATE SHOWING LOAD SERVED, EQUIPMENT VOLTAGE, AND CIRCUIT NUMBER MATCHING AS-BUILT CONDITIONS.

(2) PROVIDE AN ENGRAVED NAMEPLATE SHOWING LOADS SERVED, VOLTAGES, AND CIRCUIT NUMBERS MATCHING AS-BUILT CONDITIONS FOR ALL CONTACTOR CIRCUITS. LOADS SERVED SHALL BE "LIGHTING", "FAN", "RECEPTACLES", "PUMP", "WATER HEATER", OR SIMILAR DESCRIPTIVE NOTE.

**DISHWASHER**
**480V, 3PH, 3 WIRE**
**FROM HK-2/4/6**

## 2 DISCONNECT LABELING

NO SCALE

NOTES:

1. PROVIDE LABEL ON EACH DISCONNECT AND FUSED SWITCH.
   1.1. FOR DISCONNECTS AND FUSED SWITCHES REPLACE "PANEL P1NA" WITH THE LOAD SERVED.
   1.2. REFER TO OWNER'S STANDARDS FOR ADDITIONAL LABEL REQUIREMENTS.
2. PROVIDE LABEL ON ELECTRICAL PANEL AND TRANSFORMER.
   2.1. REPLACE "PANEL P1NA" WITH THE PANEL OR TRANSFORMER NAME BEING LABELED.
3. REPLACE "400A FUSED SWITCH" WITH UPSTREAM SOURCE OR CONNECTION.
   3.1. IF FED FROM A XFMR REPLACE "400A FUSED SWITCH" WITH "XFMR XX" WHERE XX IS THE FIELD VERIFIED XFMR NAME.
4. REPLACE VOLTAGE CONFIGURATION TO MATCH THE EQUIPMENT BEING LABELED.
5. REFERENCE FLOOR PLANS FOR EQUIPMENT LOCATIONS.

**⚠ WARNING**

**Arc Flash and Shock Hazard**
**Appropriate PPE Required**


| FLASH PROTECTION | | SHOCK PROTECTION | |
|---|---|---|---|
| Incident Energy at: | 16 in | Shock Risk When Cover is Removed | 480 VAC |
| Min. Arc Rating: | 0.45 cal/cm² | Limited Approach | 42 in |
| Arc Flash Boundary: | 10 in | Restricted Approach: | 12 in |
| PPE: Per NFPA 70E 2015 | 1 | Equipment Name: **PANEL HA** Prot Dev: 225/3 CB from Panel DA | |

## 3 TYPICAL ARC FLASH LABEL DETAIL

NO SCALE

NOTES:

1. VALUES AND NAMES SHOWN HERE ARE FOR REFERENCE ONLY, MODIFY TO REFLECT PROJECT'S ARC FLASH STUDY VALUES AND EQUIPMENT NAMES.
2. IF MIN. ARC RATING IS OVER 40CAL/CM² MODIFY "WARNING" TEXT TO READ "DANGER" AND PROVIDE RED SHADING IN LIEU OF ORANGE SHOWN.




## 4 TYPICAL TRANSFORMER LABELING DETAIL

NO SCALE

NOTES:

1. LOCATIONS OF NAMEPLATES SHOWN FOR REFERENCE ONLY, FIELD LOCATE AS NEEDED BASED ON TRUE EQUIPMENT LAYOUT AND DIMENSIONS.

(1) PROVIDE AN ENGRAVED NAMEPLATE SHOWING EQUIPMENT NAME, RATING, VOLTAGE, SOURCE.


ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

u

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILL ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD.
SUGAR LAND, TX 77498

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL DETAILS


u-E.012

STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM (713) 303-6080 | TEXAS ENG. FIRM REG. NO. F-018332 | 1300 W. SAM HOUSTON PARKWAY S., SUITE 121, HOUSTON, TX 77042

© 2025 ALL RIGHTS RESERVED

## KITCHEN AREA ELECTRICAL NOTES

1. REFER TO KITCHEN CONSULTANTS "FS" DRAWINGS FOR ADDITIONAL REQUIREMENTS PARTICULARLY NOTING MOUNTING HEIGHTS OF EQUIPMENT OUTLETS AND JUNCTION BOXES, AND WHETHER SERVICE IS FROM WALL, FLOOR OR OVERHEAD.
2. SOME RECEPTACLES SHALL BE MOUNTED HORIZONTALLY, REFER TO KITCHEN CONSULTANTS "FS" DRAWINGS.
3. FOR DEVICES WITH SERVICE FROM FLOOR, RUN UNDERGROUND CONDUIT FROM DEVICES TO NEAREST COLUMN OR WALL THEN TURN CONDUIT UP AND RUN CONDUIT IN CEILING CAVITY.
4. LIGHT SWITCHES AND RECEPTACLES NOT SERVING A SPECIFIC PIECE OF EQUIPMENT SHALL BE MOUNTED AT ADA HEIGHTS.
5. CONNECTION TYPE SHOWN ON KITCHEN ELECTRICAL FLOOR PLAN IS FOR BIDDING PURPOSES, COORDINATE WITH KITCHEN EQUIPMENT SUPPLIER FOR FINAL CONNECTIONS:
   - 5.A. OBTAIN WIRING INSTRUCTIONS FOR EACH PIECE OF EQUIPMENT FROM EQUIPMENT SUPPLIER PRIOR TO ORDERING WIRING DEVICES AND ROUGH-IN.
   - 5.B. IF EQUIPMENT REQUIRES CORD AND PLUG CONNECTION, CONTRACTOR SHALL PROVIDE NEMA POWER CORD, PLUG, AND RECEPTACLES PER MANUFACTURER'S INSTRUCTION.
   - 5.C. IF EQUIPMENT REQUIRES JUNCTION BOX AND/OR DISCONNECT SWITCH, CONTRACTOR SHALL PROVIDE JUNCTION BOX AND DISCONNECT SWITCH AND CONNECT EQUIPMENT WITH SEALTITE FLEXIBLE CONDUIT.
6. ALL DISCONNECT SWITCHES IN THE KITCHEN AREA SHALL BE NEMA 4XSS STAINLESS STEEL.
7. WHERE PORTIONS OF INTERIOR RACEWAY SYSTEM ARE EXPOSED TO WIDELY DIFFERENT TEMPERATURES, PROVIDE AIR SEALING PER NEC TO PREVENT CIRCULATION OF AIR FROM WARMER TO A COOLER SECTION.
8. FLEXIBLE CONDUIT IN KITCHENS, FOOD PRODUCTION SPLASH ZONES AND WASH DOWN AREAS, FOOD PROCESSING, AND SIMILAR AREAS SHALL BE LIQUID TIGHT CONSTRUCTION INCORPORATING A BACTERIAL GROWTH INHIBITING PVC JACKET THAT MAY BE CLEANED WITHOUT DEGREDATION TO THE JACKET BLEACHING ELEMENTS AND APPROVED FITTINGS FOR WET LOCATION.
   - 8.A. AFC SZ TYPE LFMC OR EQUAL BY KAF-TECH.
9. INTERLOCK KITCHEN EXHAUST HOOD FIRE SYSTEM WITH FIRE ALARM SYSTEM.
10. PROVIDE RELAYS AND INTERLOCK KITCHEN HOOD FANS WITH FIRE ALARM SYSTEM. ACTUATION OF ANY ALARM INITIATING DEVICE SHALL DE-ENERGIZE KITCHEN HOOD FANS.
11. ALL GFI RECEPTACLES IN KITCHEN SHALL BE PASS & SEYMOUR MODEL 2097TRWR-XX TO EXCEED UL943 VOLTAGE SURGE REQUIREMENTS.





## 4 FIRE PROTECTION SYSTEM DETAIL

NO SCALE

NOTES:

1. ANSUL MODEL R-120 FIRE PROTECTION SYSTEM AND TANK(S)
2. ELECTRICAL CONTRACTOR TO FURNISH AND INSTALL POWER DISCONNECT DEVICES FOR ALL EQUIPMENT BELOW THE HOOD, SHUTTING OFF ALL SERVICE, INCLUDING CONTROL VOLTAGE, UPON ACTIVATION OF THE FIRE PROTECTION SYSTEM.
3. MICRO-SWITCH FURNISHED WITH SYSTEM TO BE INTERWIRED TO THE SHUT-OFF DEVICES FOR THE COOKING EQUIPMENT BY THE ELECTRICAL CONTRACTOR.
4. ELECTRICAL CONTRACTOR TO FURNISH AND INSTALL AN OCTAGON SHAPED HANDY BOX FOR THE PULL STATION AT 54" ABOVE THE FLOOR WITH 1/2" CONDUIT FROM THE TOP OF THE BOX TO 6" ABOVE THE CEILING.
5. GAS SHUT-OFF VALVE FURNISHED WITH THE SYSTEM (IF REQUIRED) TO BE INSTALLED IN THE GAS LINE SERVING THE COOKING EQUIPMENT BY THE PLUMBING CONTRACTOR. VERIFY SIZE OF GAS LINE.
6. ALL EXPOSED PIPEWORK TO BE STAINLESS STEEL OR CHROME WHERE EXPOSED.
7. VERIFY LOCATION OF REMOTE MANUAL PULL STATION.
8. UNIT MUST BE PLACED WITHIN EASY ACCESS OF EXIT DOOR.





## 5 KITCHEN HOOD FAN CONTROL SCHEMATIC

NO SCALE

NOTES:

1. THE FANS SHALL BE WIRED SO THAT ONE LOCAL SWITCH TURNS ON ASSOCIATED SUPPLY AND EXHAUST FANS.
2. IF THE FIRE ALARM IS IN ALARM, A FIRE ALARM CONTROL CONTACT SHALL CAUSE THE SUPPLY FAN TO STOP AND THE EXHAUST FAN TO START, EVEN IF THE CONTROL SWITCH IS "OFF".
3. SCHEMATIC IS DIAGRAMMATIC. PROVIDE INTERLOCK WIRING BASED ON EQUIPMENT PROVIDED AND FAN VOLTAGE TO IMPLEMENT THE SEQUENCE SPECIFIED.
4. COORDINATE BETWEEN FIRE ALARM CONTRACTOR, CONTROLS CONTRACTOR AND ELECTRICAL CONTRACTOR TO PROVIDE A COMPLETE INSTALLATION.
5. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.





## 1 GAS VALVE DETAIL

NO SCALE

NOTES:

1. GAS VALVE HOUSINGS ARE NOT SHOWN ON THE ELECTRICAL DRAWING. GC AND ELECTRICAL CONTRACTOR SHALL COORDINATE SIZE AND LOCATION OF GAS VALVE HOUSINGS.
2. SEE FOOD SERVICE CONSULTANT'S DRAWINGS ADDITIONAL INFORMATION AND REQUIREMENTS.
3. PROVIDE MINIMUM 3/4"C AS SHOWN ON THIS DETAIL.





## 2 RECESSED FIRE PULL DETAILS

NO SCALE

NOTES:

1. VERIFY LOCATION OF REMOTE MANUAL PULL STATION.
   - 1.A. MANUAL PULL STATION MUST BE PLACED WITHIN EASY ACCESS OF EXIT DOOR.
   - 1.B. MANUAL PULL STATION MUST BE PLACED NO LESS THAN 4 FEET AWAY FROM KITCHEN HOOD BUT WITHIN A MAXIMUM OF 20 FEET FROM THE KITCHEN HOOD.




## 3 TYPICAL PEDESTAL MOUNTED DEVICE

NO SCALE

NOTES:

1. ALL FACEPLATES SHALL BE STAINLESS STEEL.
2. PEDESTAL BOX PROVIDED BY DIVISION 26.
   - 2.A. A STANDARD DUPLEX INSTALLATION IS SHOWN FOR REFERENCE, PROVIDE SIMILAR INSTALLATION FOR QUAD RECEPTACLES, GFI RECEPTACLES, DATA OUTLETS, NEMA POWER OUTLETS, ETC.
   - 2.B. ALL PEDESTAL BOXES TO BE DOUBLE FACED WITH ONE BLANK FACE FOR FUTURE GROWTH. 2-GANG PEDESTALS WITH ONE BLANK FACE FOR QUAD RECEPTACLE LOCATIONS.
   - 2.C. PEDESTAL BOXES TO BE SIZED BY DIVISION 26 TO PROVIDE SCHEDULED DEVICES ON A SINGLE FACE AND SUFFICIENT DEPTH FOR BACK TO BACK DEVICES ON DOUBLE FACED PEDESTALS.
   - 2.D. BASIS OF DESIGN:
     - 2.D.A. 1-GANG ELECTRICAL DEVICES: LEGRAND LBP2 OR WATER SAVER E400SA-WS
     - 2.D.B. 1-GANG LOW VOLTAGE DEVICES: LEGRAND LBP2 OR WATER SAVER E400SA-WS
     - 2.D.C. 2-GANG ELECTRICAL DEVICES: WATER SAVER E600SA-WS
     - 2.D.D. 2-GANG LOW VOLTAGE DEVICES: WATER SAVER E600SA-WS
3. INSTALLATION REQUIREMENTS:
   - 3.A. STUB UP CONDUIT ABOVE FLOOR TO PEDESTAL BOX CONNECTION LOCATION.
   - 3.B. GROUT GAP BETWEEN FINISHED FLOOR AND BOTTOM OF PEDESTAL BOX.
   - 3.C. PROVIDE TRANSITION PIECE TO CONTINUE FINISHED FLOOR TO BOTTOM EDGE OF SERVICE FITTING AND CONCEAL GROUT. TRANSITION PIECE TO MATCH ARCHITECT'S FINISH SCHEDULE.
   - 3.D. PEDESTAL BOX TO BE INSTALLED SQUARE TO THE FINISHED FLOOR.
4. PROVIDE TYPEWRITTEN OR PREMADE CIRCUIT LABELS ON INSTALLED WIRING AT EACH DEVICE AND SPLICE POINT.
5. PROVIDE TYPEWRITTEN LABEL AFFIXED TO THE FRONT OF EACH DEVICE FACEPLATE INDICATING ELECTRICAL CIRCUIT.

CIRCUIT LABEL

XX-## 
- A. XX = PANEL DESIGNATION
- B. ## = AS-BUILT CIRCUIT DESIGNATION

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

u

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILL ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD.
SUGAR LAND, TX 77498

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL
KITCHEN DETAILS

u-E.013

STANTON ENGINEERING GROUP
INFORMATION@SEGROUP.COM | (713) 305-4080
TEXAS ENG. FIRM REG. NO. F-018332 | © 2025 ALL RIGHTS RESERVED
12999 W. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77092

LIGHTING SYSTEM FUNCTIONAL TESTING AND DOCUMENTATION NOTES:

1. PRIOR TO PASSING FINAL INSPECTION, THE CONTRACTOR SHALL PERFORM FUNCTIONAL TESTING IN THE PRESENCE OF THE REGISTERED DESIGN PROFESSIONAL, THE OWNER AND/OR THEIR AGENT. THE FUNCTIONAL TESTING SHALL BE AS REQUIRED BY SECTION C408.3.1 OF THE 2021 IECC.
   1.A. THE FUNCTIONAL TESTING SHALL PROVIDE EVIDENCE THAT THE LIGHTING CONTROL SYSTEMS, INCLUDING BOTH HARDWARE AND SOFTWARE, ARE CALIBRATED, ADJUSTED, PROGRAMMED AND IN PROPER WORKING CONDITION IN ACCORDANCE WITH THE CONSTRUCTION DOCUMENTS AND MANUFACTURER'S INSTRUCTIONS.
   1.B. THE FUNCTIONAL TESTING SHALL BE IN ACCORDANCE WITH SECTIONS C408.3.1.1 AND C408.3.1.2 OF THE 2021 IECC FOR THE APPLICABLE CONTROL TYPE.
   1.C. A WRITTEN REPORT SHALL BE GENERATED DOCUMENTING THE FUNCTIONAL TESTING RESULTS IN ACCORDANCE WITH THE 2015 IECC REQUIREMENTS.
2. ALL LIGHTING CONTROLS O&M MANUALS, AS-BUILTS, TESTING REPORTS AND DOCUMENTATION RELATED TO THE LIGHTING CONTROL SYSTEM SHALL BE PROVIDED IN THEIR FINAL AND APPROVED FORM WITHIN 60 DAYS OF THE CERTIFICATE OF OCCUPANCY. ALL DOCUMENTS CERTIFYING THAT THE INSTALLED LIGHTING CONTROLS MEET DOCUMENTED PERFORMANCE CRITERIA OF SECTION C405 OF THE 2021 IECC SHALL BE INCLUDED IN THE O&M MANUALS.
3. ALL DOCUMENTS FROM ITEMS #1 AND #2 ABOVE SHALL BE COMBINED AND PROVIDED TO THE OWNER WITHIN 90 DAYS FROM THE DATE OF RECEIPT OF THE CERTIFICATE OF OCCUPANCY.

# LIGHT FIXTURE SCHEDULE

## EXTERIOR LIGHT FIXTURE SCHEDULE

| | | | |
|---|---|---|---|
| RECESSED 6" DOWNLIGHT WET LOCATION | D5<br>D5Y | 6" DIAMETER RECESSED LED DOWNLIGHT, SPECULAR CLEAR REFLECTOR, MEDIUM (56') BEAM DISTRIBUTION, 1000 LUMENS, 4000K COLOR TEMPERATURE, 120-277V MULTIVOLT INPUT, 1% 0-10V DIMMING DRIVER.<br>LIGHTOLIER 6R-N / C6L-10-9-40-M-Z10-U / C6-R-DL-CC | 9W |
| RECESSED 6" DOWNLIGHT WET LOCATION | D6<br>D6Y | 6" DIAMETER RECESSED LED DOWNLIGHT, SPECULAR CLEAR REFLECTOR, MEDIUM (56') BEAM DISTRIBUTION, 2000 LUMENS, 4000K COLOR TEMPERATURE, 120-277V MULTIVOLT INPUT, 1% 0-10V DIMMING DRIVER.<br>LIGHTOLIER 6R-N / C6L-20-9-40-M-Z10-U / C6-R-DL-CC | 22W |
| SURFACE CANOPY SQUARE LED | WC1<br>WC1X<br>WC1Y | 9" SQUARE SURFACE LED CANOPY LIGHT, 4000K COLOR TEMPERATURE, 3500 LUMENS, 120-277V MULTIVOLT INPUT, DARK BRONZE FINISH.<br>EELP VR7-T-28L-QT-40K (EBLED9W) | 28W |
| EXTERIOR WALL PACK | WP1<br>WP1X<br>WP1Y | 7" WDE WALL MOUNTED LED, 4000K COLOR TEMPERATURE, 5000 LUMENS, TYPE 3 DISTRIBUTION, 120-277 MULTIVOLT INPUT, WET LOCATION, 10KV KA SURGE PROTECTION.<br>REFER TO ARCH FOR MOUNTING HEIGHT.<br>FINISH TO BE SELECTED BY ARCHITECT FROM ALL AVAILABLE FINISHES.<br>GARDCO GEOFORM SMALL GWS-A04-740-UNV-XX FINISH (EM) | 34W |
| EXTERIOR WALL PACK | WP2<br>WP2X<br>WP2Y | 12" WDE WALL MOUNTED LED, 4000K COLOR TEMPERATURE, 8500 LUMENS, TYPE 3 DISTRIBUTION, 120-277 MULTIVOLT INPUT, WET LOCATION. REFER TO ARCH FOR MOUNTING HEIGHT.<br>REFER TO ARCH FOR MOUNTING HEIGHT.<br>FINISH TO BE SELECTED BY ARCHITECT FROM ALL AVAILABLE FINISHES.<br>GARDCO GEOFORM MEDIUM GWM-A11-740-T3M-UNV-XX FINISH (REMOTE EM BATTERY) | 52W |
| EXTERIOR WALL PACK | WP3<br>WP3X<br>WP3Y | 17" WDE WALL MOUNTED LED, 4000K COLOR TEMPERATURE, 12500 LUMENS, TYPE 3 DISTRIBUTION, 120-277 MULTIVOLT INPUT, WET LOCATION. REFER TO ARCH FOR MOUNTING HEIGHT.<br>REFER TO ARCH FOR MOUNTING HEIGHT.<br>FINISH TO BE SELECTED BY ARCHITECT FROM ALL AVAILABLE FINISHES.<br>GARDCO GEOFORM MEDIUM GWM-A14-740-T3M-UNV-XX FINISH (REMOTE EM BATTERY) | 77W |

1. LIGHT FIXTURE CATALOG NUMBERS AND DESCRIPTIONS ARE SCHEDULED FOR ESTABLISHING QUALITY, APPEARANCE AND PERFORMANCE OF THE FIXTURES. EXACT CATALOG NUMBERS DESCRIBING MOUNTING CONDITIONS AND REQUIREMENT RELATED TO TRIM FOR ALL FIXTURES SHALL BE CONFIRMED (BY THE ELECTRICAL CONTRACTOR) WITH THE ROOM FINISH SCHEDULE AND REFLECTED CEILING PLANS ON THE ARCHITECTURAL PLANS PRIOR TO BIDDING AND SUBMITTING LIGHT FIXTURES. PROVIDE DRY WALL KIT AS REQUIRED.
2. ALL 'X', 'Y', AND 'Z' TYPE FIXTURES SHALL HAVE EMERGENCY POWER BACKUP. EMERGENCY POWER SOURCES SHALL MONITOR POWER UPSTREAM OF THE LIGHTING CONTROLS TO SEE IF POWER IS LOST. BATTERY PACKS AND INVERTERS SHALL BE CAPABLE OF POWERING THE DESIGNATED FIXTURE(S) WITH AN OUTPUT OF 1400 LUMENS FOR A MINIMUM OF 90-MINUTES. PROVIDE REMOTE BATTERY PACKS OR INVERTERS AS NECESSARY. EMERGENCY LIGHTS SHALL OPERATE ONLY UPON LOSS OF POWER; ALSO, PROVIDE AND WIRE TEST SWITCH AND LED INDICATOR LIGHT FOR EMERGENCY BATTERY. SEE WIRING INSTRUCTION SUPPLIED BY EMERGENCY BATTERY MANUFACTURER.
   2.A. 'X' TYPE FIXTURES (AX, ETC.) HAVE EMERGENCY GENERATOR POWER LIGHTING TRANSFER DEVICES.
   2.B. 'Y' TYPE FIXTURES (MY, ETC.) HAVE INDIVIDUAL 90-MINUTE EMERGENCY BATTERY POWER.
   2.C. 'Z' TYPE FIXTURES (GTZ, ETC.) HAVE 90-MINUTE INVERTER EMERGENCY BATTERY POWER.
3. PROVIDE BASE COVER FOR ALL LIGHT POLES.
4. ALL EXTERIOR FIXTURES SHALL BE WET RATED WITH COLD WEATHER BALLASTS AND BATTERY PACKS.
5. PROVIDE SPARE FIXTURES AND EMERGENCY DEVICES PER SPECIFICATIONS.
6. WHERE FIXTURE FINISHES ARE INDICATED TO BE SELECTED BY ARCHITECT THE CONTRACTOR SHALL INCLUDE IN THEIR BID ALL AVAILABLE FINISHES. SUBMIT COMPLETE FIXTURE FINISH OPTIONS AS PART OF THE LIGHTING SUBMITTAL PACKAGE.
7. EQUAL BY PHILIPS (CW LIGHTING), COOPER (PUTTERMAN SCHAROK), AND LITHONIA (LESCO) SHALL BE ACCEPTABLE.

## INTERIOR LIGHT FIXTURE SCHEDULE

| APPLICATION | TYPE | DESCRIPTION | WATTS |
|---|---|---|---|
| 1X4 RECESSED LAY-IN CEILING SELECTABLE CCT & LUMENS | A1<br>A1X<br>A1Y | 2X4 RECESSED LED, SMOOTH FROSTED ACRYLIC LENS, EXTRUDED ALUMINUM FRAME, WHITE FINISH, LAY-IN CEILING, 6000 LUMENS, 4000K COLOR TEMPERATURE, 120-347V MULTIVOLT INPUT, 5% 0-10V DIMMING.<br>SET FIELD SELECTABLE SWITCHES TO NEUTRAL WHITE (4000K) AND HIGH (47W).<br>DAYBRITE 2SBP3550L8CS-4-UNJ-DIM | 47W |
| 1X4 RECESSED LAY-IN CEILING SELECTABLE CCT & LUMENS | B1<br>B1X<br>B1Y | 1X4 RECESSED LED, SMOOTH FROSTED ACRYLIC LENS, EXTRUDED ALUMINUM FRAME, WHITE FINISH, LAY-IN CEILING, 4500 LUMENS, 4000K COLOR TEMPERATURE, 120-347V MULTIVOLT INPUT, 5% 0-10V DIMMING.<br>SET FIELD SELECTABLE SWITCHES TO NEUTRAL WHITE (4000K) AND HIGH (36W).<br>DAYBRITE 1SBP3040L8CS-4-UNJ-DIM | 36W |
| 2X2 RECESSED LAY-IN CEILING SELECTABLE CCT & LUMENS | B2<br>B2X<br>B2Y | 2X2 RECESSED LED, SMOOTH FROSTED ACRYLIC LENS, EXTRUDED ALUMINUM FRAME, WHITE FINISH, LAY-IN CEILING, 4250 LUMENS, 4000K COLOR TEMPERATURE, 120-347V MULTIVOLT INPUT, 5% 0-10V DIMMING.<br>SET FIELD SELECTABLE SWITCHES TO NEUTRAL WHITE (4000K) AND HIGH (36W).<br>DAYBRITE 2SBP3040L8CS-2-UNJ-DIM | 39W |
| 4FT STRIP LED MECHANICAL & STORAGE ROOMS | C<br>CX<br>CY | 4 FOOT STRIP LED, STEEL HOUSING, FROSTED ACRYLIC LENS, 4000 LUMENS, 3500K COLOR TEMPERATURE, CHAIN HANGING SET, WIRE GUARD, 120-277V MULTIVOLT INPUT, 0-10V DIMMING DRIVER. PROVIDE CHAIN HANGING SET AND WIREGUARD IN MECHANICAL ROOMS AND AREAS WITHOUT CEILINGS.<br>SET FIELD SELECTABLE SWITCHES TO NEUTRAL WHITE (4000K) AND HIGH (36W).<br>DAYBRITE SDS-4-2448L-8CST-UNV-DIM | 30W |
| RECESSED 6" DOWNLIGHT | D1<br>D1X<br>D1Y | 6" DIAMETER RECESSED LED DOWNLIGHT, MATTE WHITE FINISH, WIDE (76') BEAM DISTRIBUTION, 1000 LUMENS, 4000K COLOR TEMPERATURE, 120-277V MULTIVOLT INPUT, 1% 0-10V DIMMING DRIVER.<br>LIGHTOLIER 6R-N / C6L-10-9-40-W-Z10-U / C6-R-DL-WH | 9W |
| RECESSED 6" DOWNLIGHT | D2<br>D2X<br>D2Y | 6" DIAMETER RECESSED LED DOWNLIGHT, MATTE WHITE FINISH, WIDE (76') BEAM DISTRIBUTION, 2000 LUMENS, 4000K COLOR TEMPERATURE, 120-277V MULTIVOLT INPUT, 1% 0-10V DIMMING DRIVER.<br>LIGHTOLIER 6R-N / C6L-20-9-40-W-Z10-U / C6-R-DL-WH | 22W |
| EXIT SIGN | XB<br>XS<br>XD | DIE CAST ALUMINUM LED EXIT LIGHT, RED LETTERS, MATTE BLACK HOUSING W/ BRUSHED ALUMINUM FACE, UNIVERSAL ARROWS, 120/277 VOLT DUAL INPUT, 90 MINUTE EMERGENCY BATTERY. VERIFY LETTER AND FACE COLOR WITH OWNER/ARCHITECT PRIOR TO ORDERING.<br>XS=SINGLE FACE, XD=DOUBLE FACE, XB=BACK MOUNTED<br>PHILIPS CHLORIDE ER55L-3-R<br>SURELITES CX7-1/2-R<br>LITHONIA LQC-1/2-R-EL N | 5W |
| EXIT SIGN INTEGRAL BATTERY INTEGRAL EM LIGHT BAR | YB<br>YS<br>YD | THERMOPLASTIC LED EXIT LIGHT WITH INTEGRAL EM LIGHT, RED LETTERS, WHITE HOUSING W/ WHITE FACE, UNIVERSAL ARROWS, 120-277 MULTIVOLT INPUT, 90 MINUTE EMERGENCY BATTERY. VERIFY LETTER AND FACE WITH OWNER/ARCHETICT PRIOR TO ORDERING.<br>YS=SINGLE FACE, YD=DOUBLE FACE, YB=BACK MOUNTED<br>SIGNTEX CLP-BB-U-R-W-DG | 5W |
| TWIN HEAD EM LIGHT INTEGRAL BATTERY WET LOCATION | YT1 | TWIN HEAD EM LIGHT, INJECTION-MOLDED THERMOPLASTIC WHITE HOUSING, GASKETED CLEAR POLYCARBONATE COVER, LED LAMPS, 90-MINUTE EMERGENCY BATTERY.<br>CHLORIDE TPU-W-N-LM7-W | 7W |

# LIGHTING CONTROL SEQUENCE OF OPERATIONS

| ROOM TYPE | AUTO ON | MANUAL ON (VACANCY) | AUTO OFF (20 MIN MAX) | PARTIAL OFF AT NORMAL HOURS | AUTO ON AFTER HOURS | AUTO OFF AFTER HOURS (20 MIN MAX) | TIME ON | TIME OFF | ASTRONOMIC OR PHOTOCELL ON/OFF | AUTO STEP CONTROL WITH OFF | AUTO CONTINUOUS DIM WITH OFF | MANUAL BI-LEVEL REDUCTION CONTROL | MANUAL CONTINUOUS DIM CONTROL | MANUAL ON/OFF SWITCH | MANUAL DIMMER SWITCH | DISPLAY, ACCENT, TASK CONTROL | PLUG LOAD CONTROL | SEQUENCE OF OPERATION |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | OCCUPANCY SENSOR | | | | | | TIME SWITCH/SCHEDULING | | | DAYLIGHT CONTROL | | LIGHT REDUCTION | | MANUAL CONTROL | | | | |
| Kitchen/Serving | | | | | | | • | • | | | | • | | • | | | | LOCAL ON/OFF CONTROLS, LOCAL CONTROLS MAY OVERRIDE BUILDING SCHEDULE AND TURN ALL LIGHTS ON FOR MAXIMUM 2HRS. NETWORK LIGHTING CONTROLS ROOM CONTROLLER CONNECTED TO BUILDING CONTROLS; ON/OFF BASED ON BUILDING SCHEDULE, AFTER HOURS ON/OFF BASED ON OCCUPANCY, COORDINATE SCHEDULING WITH OWNER. WHERE ≥150W IN DAYLIGHT AREA, USE CONTINUOUS DIMMING DAYLIGHTING CONTROL. |
| Restrooms | 100% | | 20 MIN | | | | | | | | | | | • | | | | AUTO ON 100%, AUTO OFF BY LOCAL OCCUPANCY SENSOR. LOCAL ON/OFF CONTROLS ONLY, NO FULLY NETWORKED SYSTEM. |
| Custodial rooms | | • | 20 MIN | | | | | | | | | | | • | • | | | MANUAL ON, AUTO OFF BY LOCAL OCCUPANCY SENSOR. LOCAL ON/OFF CONTROLS ONLY, NO FULLY NETWORKED SYSTEM. |
| Storage rooms | 50% | | 20 MIN | | | | | | | | | | | • | • | | | AUTO ON 50%, AUTO OFF BY LOCAL OCCUPANCY SENSOR. LOCAL ON/OFF/DIMMING CONTROLS ONLY, NO FULLY NETWORKED SYSTEM. |
| Private Offices | 50% | | 20 MIN | | | | | | | | | | | • | • | | • | AUTO ON 50%, AUTO OFF BY LOCAL OCCUPANCY SENSOR. LOCAL ON/OFF/DIMMING CONTROLS ONLY, NO FULLY NETWORKED SYSTEM. |
| Corridors | | | | | 100% | 20 MIN | • | • | | | | | | • | | | | LOCAL ON/OFF CONTROLS, LOCAL CONTROLS MAY OVERRIDE BUILDING SCHEDULE AND TURN ALL LIGHTS ON FOR MAXIMUM 2HRS. NETWORK LIGHTING CONTROLS ROOM CONTROLLER CONNECTED TO BUILDING CONTROLS; ON/OFF BASED ON BUILDING SCHEDULE, AFTER HOURS ON/OFF BASED ON OCCUPANCY, COORDINATE SCHEDULING WITH OWNER. WHERE ≥150W IN DAYLIGHT AREA, USE CONTINUOUS DIMMING DAYLIGHTING CONTROL. |
| Electrical Rooms | | | | | | | | | | | | | | • | | | | MANUAL ON/OFF; LOCAL CONTROL DEVICE NOT TIED TO LVLCS. |
| Building Facade/Landscape | | | | | | | • | • | | | | | | | | | | CONNECTED TO BUILDING CONTROLS THROUGH LIGHTING CONTACTOR; ON/OFF BASED ON BUILDING SCHEDULE. |

1. DIMMER SWITCHES SHALL ACTIVATE PRESET ALL ON LIGHTING LEVEL WHEN PRESSED IN THE UP POSITION. LIGHTING LEVELS MAY BE RAISED/LOWERED BY HOLDING THE DIMMER PADDLE. WHEN PRESSED IN THE DOWN POSITION ALL LIGHTS SHALL SMOOTHLY DIM TO OFF.
2. AT LEAST 50 PERCENT OF ALL 125V, 15- AND 20-AMP RECEPTACLES INSTALLED IN ENCLOSED OFFICES, CONFERENCE ROOMS, ROOMS USED PRIMARILY FOR COPY OR PRINT FUNCTIONS, BREAKROOMS, CLASSROOMS AND INDIVIDUAL WORKSTATIONS, INCLUDING THOSE INSTALLED IN MODULAR PARTITIONS AND MODULE OFFICE WORKSTATION SYSTEMS SHALL HAVE PLUG LOAD CONTROL PER IECC 2021 C405.11.

# LIGHTING CONTACTOR SCHEDULE

**CONTACTOR CT1**

| POLE | DESCRIPTION | NORMAL CKT | EM CKT | CONTROL ZONE | CONTACTOR LOCATION | CONTACTOR TYPE |
|---|---|---|---|---|---|---|
| CT1-1 | KITCHEN/SERVING AREA - ZONE 'a' | HK-3 | - | Kitchen-a | CENTRAL PLANT | MAGNETICALLY HELD |
| CT1-2 | SPARE | | | Kitchen-a | CENTRAL PLANT | MAGNETICALLY HELD |
| CT1-3 | SPARE | | | Kitchen-a | CENTRAL PLANT | MAGNETICALLY HELD |

**CONTACTOR CT2**

| | | | | | | |
|---|---|---|---|---|---|---|
| CT2-1 | KITCHEN/SERVING AREA - ZONE 'b' | HK-3 | - | Kitchen-b | CENTRAL PLANT | MAGNETICALLY HELD |
| CT2-2 | SPARE | | | Kitchen-b | CENTRAL PLANT | MAGNETICALLY HELD |
| CT2-3 | SPARE | | | Kitchen-b | CENTRAL PLANT | MAGNETICALLY HELD |

**CONTACTOR CT3**

| | | | | | | |
|---|---|---|---|---|---|---|
| CT3-1 | KITCHEN SOFFIT/CANOPY LTS | HK-5 | - | Exterior | CENTRAL PLANT | MAGNETICALLY HELD |
| CT3-2 | | | | Exterior | CENTRAL PLANT | MAGNETICALLY HELD |
| CT3-3 | | | | Exterior | CENTRAL PLANT | MAGNETICALLY HELD |

1. REFERENCE TYPICAL LIGHTING CONTACTOR WIRING DIAGRAM.
2. EMERGENCY AND NORMAL ZONES WITHIN THE KITCHEN/SERVING SHALL HAVE SEPARATE CONTROLS TO ALLOW FOR LIGHTING REDUCTION CONTROL.
3. LIGHTING CONTACTORS SHALL BE DIN RAIL MOUNTED, MAGNETICALLY HELD TYPE WITH THREE WIRE CONTROL BY THE BAS.
   3.A. PROVIDE CABINET AT EACH LOCATION TO MOUNT ALL CONTACTORS IN A SINGLE ENCLOSURE. ENCLOSURE SIZED BY DIVISION 26.
   3.B. PROVIDE SEPARATE HOA SWITCHES IN THE FRONT COVER OF THE ENCLOSURE WIRED TO CONTROL THE FOLLOWING ZONES SEPARATELY.
      3.B.1. INTERIOR LIGHTING (ALL INTERIOR LIGHTING GROUPS)
      3.B.2. EXTERIOR LIGHTING (ALL EXTERIOR LIGHTING GROUPS)
      3.B.3. HOA SWITCH SHALL PASS THE BAS SIGNALS IN AUTO MODE, DISENGAGE ALL CONTACTORS IN THE OFF POSITION, AND ENGAGE ALL THE CONTACTORS IN THE ON POSITION.
   3.C. SPARE CAPACITY:
      3.C.1. PROVIDE MINIMUM TWO (2) SPARE POLE ON EACH COMBINED TYPE CONTACTOR FOR FUTURE USE.

STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM (713) 303-6080 | TEXAS ENG. FIRM REG. NO. F-018332 | © 2025 ALL RIGHTS RESERVED | 1300 W. SAM HOUSTON PARKWAY S., SUITE 121, HOUSTON, TX 77042

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

u

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILL ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD.
SUGAR LAND, TX 77498

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

LIGHTING SCHEDULES

u-E.060

## ELECTRICAL KEYED NOTES

GENERAL NOTES:

- CUT WALLS AS REQUIRED TO FLUSH MOUNT NEW DEVICES IN EXISTING WALLS. PATCH/REPAIR WALLS TO MATCH.

LIGHTING RENOVATION NOTES:

A. KITCHEN LIGHTS TO BE CONTROLLED BY LOCAL MOMENTARY SWITCHES AND BAS. LIGHTING CONTACTOR LOCATIONS SHOWN SCHEMATICALLY ONLY. LOCATE LIGHTING CONTACTOR ENCLOSURE IN THE ADJACENT CENTRAL PLANT SPACE, FIELD VERIFY. REFERENCE LIGHTING CONTROL DETAIL. TYPICAL.
   LEFT SWITCH SHALL CONTROL ZONE 'a' NORMAL POWER LIGHTING FIXTURES.
   RIGHT SWITCH SHALL CONTROL ZONE 'b' EMERGENCY LIGHTING FIXTURES.


B. PROVIDE PLUG LOAD CONTROLS TIED TO THE LIGHTING IN OFFICE SPACES.

C. WIRE EXIT SIGNS UPSTREAM OF LIGHTING CONTROLS. TYPICAL.

D. EXTERIOR LIGHTS TO BE CONTROLLED BY BAS. LIGHTING CONTACTOR LOCATIONS SHOWN SCHEMATICALLY ONLY. LOCATE LIGHTING CONTACTOR ENCLOSURE IN THE ADJACENT CENTRAL PLANT SPACE, FIELD VERIFY. REFERENCE LIGHTING CONTROL DETAIL. TYPICAL.

E. AFTER REMOVAL OF THE TEMPORARY KITCHEN, PROVIDE NEW EXIT SIGN AT ORIGINAL LOCATION AND RECONNECT TO EXISTING CAFETERIAL LIGHTING CIRCUIT.

F. PATCH/REPAIR EXTERIOR SOFFIT TO ACCOMMODATE NEW SURFACE MOUNTED FIXTURES.




**1 LIGHTING RENOVATION PLAN**
SCALE: 1/4" = 1'- 0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

u

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILL ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD.
SUGAR LAND, TX 77498

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING


LIGHTING FLOOR PLANS

u-E.100


STANTON ENGINEERING GROUP
INFORMATION-TECHNOLOGY (713) 300-60360


TEXAS ENGINEERING FIRM REG. NO.F-12343 © 2025 ALL RIGHTS RESERVED


12000 W. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77043




## 1 ELECTRICAL RENOVATION PLAN

SCALE: 1/4" = 1'- 0"

## ELECTRICAL KEYED NOTES

GENERAL NOTES:

- CUT WALLS AS REQUIRED TO FLUSH MOUNT NEW DEVICES IN EXISTING WALLS. PATCH/REPAIR WALLS TO MATCH.

ELECTRICAL RENOVATION NOTES:

A. CONNECT NEW FREEZER/COOLER AND CONDENSER TO EXISTING STANDBY GENERATOR.

B. PROVIDE ILLUMINATED PUSH BUTTON IN COOLER AND FREEZER. WHEN PRESSED RED STROBE DEVICES IN KITCHEN AND CAFETERIA SHALL ACTIVATE. TYPICAL.

C. PROVIDE HORN/STROBE DEVICE TIED TO PUSH BUTTONS IN FREEZER/COOLER.
(EDWARDS 860 SERIES OR EQUAL).

D. PROVIDE NEW DOORBELL BUTTON AT RECEIVING DOOR. DOORBELL BUTTON SHALL BE THE CLOSEST DEVICE TO THE DOOR FRAME.

E. PROVIDE NEW VIBRATING BUZZER TIED TO DOORBELL BUTTON AT RECEIVING DOOR. BUZZER TO BE WALL MOUNTED JUST BELOW THE CEILING.

F. PROVIDE NEW ELECTRICAL DEVICES MATCHING NEW KITCHEN EQUIPMENT AND ROOM LAYOUTS. REFERENCE FOOD SERVICE DRAWINGS. TYPICAL.

G. PROVIDE ROUGH-IN FOR LOW VOLTAGE DEVICES. REFERENCE TECHNOLOGY DRAWINGS, TYPICAL.

H. POWER AND DATA ROUGH-IN FOR KITCHEN MENU BOARD.

I. POWER AND DATA ROUGH-IN FOR POINT OF SALE (POS) LOCATION.

J. PROVIDE DROP CORD RECEPTACLE WITH HUBBELL KELLEMS LIQUIDTIGHT GRIPS FOR STRAIN RELIEF, TYPICAL OF ALL.

K. PROVIDE J-BOXES AND CONDUIT FOR REMOTE FIRE PULLS, SEE FOOD SERVICE DETAIL DRAWING FOR REQUIREMENTS, TYPICAL

L. WIRE ANSUL SYSTEM TO HOOD EQUIPMENT CONTROL CONTRACTOR. UPON ANSUL SYSTEM ACTIVATION ALL POWER TO EQUIPMENT BENEATH THE HOODS SHALL BE DEACTIVATED. MOUNT CONTACTOR CABINET(S) JUST BELOW THE CEILING.

M. PROVIDE SEPARATE SWITCHES TO TURN ON HOOD LIGHTS AND FANS. WIRE HOOD TEMP SENSOR AHEAD OF HOOD LIGHT SWITCH. USE 120V CIRCUIT TO CONTROL HOOD FANS THROUGH EXISTING STARTER. PROVIDE CONTROLS TRANSFORMER AS REQUIRED TO MATCH STARTER CONTROL INPUT VOLTAGE. TYPICAL.

N. PROVIDE PLUG LOAD CONTROLS TIED TO THE LIGHTING IN OFFICE SPACES.

O. INTERCONNECT DISH MACHINE TO VENT CONTROL. INTERCONNECT TABLE LIMIT SWITCH TO DISHMACHINE.

P. EXISTING MECHANICAL EQUIPMENT TO BE REPLACED. CONNECT TO CIRCUIT AS SHOWN. RECONNECT TO EXISTING STARTER/CONTACTORS, FIELD VERIFY.

Q. SAWCUT FLOOR TO INSTALL NEW PEDESTAL MOUNTED DEVICE BENEATH NEW SERVING LINES, DO NOT REUSE EXISTING STUB UPS OR DEVICES. POUR BACK SLAB AND PROVIDE NEW FINISHES, REFERENCE ARCHITECTURAL.

R. REFERENCE EDF GFI PROTECTION DETAIL FOR INSTALLATION REQUIREMENTS, TYPICAL.

S. WIRE MICRO SWITCH IN DOOR FRAME TO AIR SCREEN. COOR W/ FOOD SERVICE CONTRACTOR PRIOR TO ROUGH-IN. LOCATE LOCAL MOTOR RATED SWITCH ABOVE CEILING ADJACENT TO THE AIR SCREEN.

COOLER/FREEZER NOTES:

1. PROVIDE SEALING FOR CONDUIT IN COOLER AND FREEZER. WHERE PORTIONS OF INTERIOR RACEWAY SYSTEM ARE EXPOSED TO WIDELY DIFFERENT TEMPERATURES, CIRCULATION OF AIR FROM WARMER TO A COLDER SECTION SHALL BE PREVENTED PER N.E.C. ARTICLE 300.7 (A).
2. PROVIDE GROUND-FAULT PROTECTION OF EQUIPMENT FOR ELECTRIC HEAT TRACING AND HEATING PANELS IN THE FREEZER PER N.E.C. ARTICLE 427.22.
3. ELECTRICAL CONTRACTOR SHALL PROVIDE LIQUID TIGHT CONDUIT AND WIRING FOR LIGHT FIXTURES AND LIGHT SWITCHES IN WALK-IN COOLER AND FREEZER, SEE FOODSERVICE CONSULTANT'S DRAWINGS.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

u

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILL ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD.
SUGAR LAND, TX 77498

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
LICENSED
PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING


ELECTRICAL FLOOR PLANS

u-E.200


STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM (713) 300-6082


TEXAS ENG. FIRM REG. NO. F-13933 | © 2025 ALL RIGHTS RESERVED


12800 W. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77065




**1 FIRE ALARM RENOVATION PLAN**
SCALE: 1/4" = 1'- 0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

u

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILL ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD.
SUGAR LAND, TX 77498

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

FIRE ALARM FLOOR PLANS

u-E.300

STANTON ENGINEERING GROUP
INFO@STANTON-ENG.COM (713) 300-6080 | TEXAS ENGINEERING FIRM REGISTRATION NO. F-018332 | 1300 W. SAM HOUSTON PARKWAY S., SUITE 121, HOUSTON, TX 77042
© ALL RIGHTS RESERVED




## 1 PARTIAL ELECTRICAL RISER

NO SCALE

NOTES:
1. FIELD VERIFY ALL EXISTING ELECTRICAL PANELS AND FEEDERS SHOWN ON DRAWINGS.
2. REF ELECTRICAL FLOOR PLANS FOR PANEL LOCATIONS.
3. ALL OUTAGES SHALL BE SCHEDULED/CONFIRMED IN WRITING WITH THE OWNER A MINIMUM OF TWO WEEKS PRIOR TO ANY OUTAGE.
4. AT THE END OF THE PROJECT PROVIDE A NEW TYPEWRITTEN PANEL SCHEDULE USING BUILDING ROOM NUMBERS FOR ALL PANELS WITH CIRCUITS ADDED, REMOVED, OR MODIFIED AS PART OF THE PROJECT.
5. REFERENCE PANEL SCHEDULES AND SHORT CIRCUIT TABLE FOR AIC AND SCCR VALUES.

## NEW KITCHEN PANEL — KITCHEN

**PANEL HK** — 225A MLO, 480Y/277V, 3ϕ, 4 WIRE — AVAILABLE FAULT: 20,250A — SCCR & AIC: 25,000A — MOUNTING: RECESSED — STAINLESS STEEL COVER

| NOTES | EQUIP. NO. | LOAD | DESCRIPTION | WIRE | CB | CKT | A | B | C | CKT | CB | WIRE | DESCRIPTION | LOAD | EQUIP. NO. | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 6 | | 376 | KITCHEN ROOM LIGHTS | 3–12 | 20/1 | 1 | | | | 2 | 15/3 | 3–12 | ESF–1 | 4986 | | |
| 7 | | 1095 | KITCHEN LIGHTS | 3–12 | 20/1 | 3 | | | | 4 | – | +12G | ( 1.5HP / 1.5HP ) | – | | |
| | | 84 | KITCHEN SOFFIT LIGHTS | 3–12 | 20/1 | 5 | | | | 6 | – | 3/4"C | – | – | | |
| | | | SPARE | | 20/1 | 7 | | | | 8 | 15/3 | 3–12 | ESF–2 | 4986 | | |
| | | | SPARE | | 20/1 | 9 | | | | 10 | – | +12G | ( 1.5HP / 1.5HP ) | – | | |
| | | | SPARE | | 20/1 | 11 | | | | 12 | – | 3/4"C | – | – | | |
| | | | SPARE | | 20/1 | 13 | | | | 14 | | | SPACE | | | |
| | | | SPARE | | 20/1 | 15 | | | | 16 | | | SPACE | | | |
| | | | SPARE | | 20/1 | 17 | | | | 18 | | | SPACE | | | |
| | | | SPARE | | 20/1 | 19 | | | | 20 | | | SPACE | | | |
| | | | SPARE | | 20/1 | 21 | | | | 22 | | | SPACE | | | |
| | | | SPACE | | | 23 | | | | 24 | | | SPACE | | | |
| | | | SPACE | | | 25 | | | | 26 | | | SPACE | | | |
| | | | SPACE | | | 27 | | | | 28 | | | SPACE | | | |
| | | | SPACE | | | 29 | | | | 30 | | | SPACE | | | |
| | | | SPACE | | | 31 | | | | 32 | | | SPACE | | | |
| | | | SPACE | | | 33 | | | | 34 | | | SPACE | | | |
| | | | SPACE | | | 35 | | | | 36 | | | SPACE | | | |
| | | | SPACE | | | 37 | | | | 38 | 70/3 | 3–6 | DISHMACHINE | 42963 | E250 | |
| | | | SPACE | | | 39 | | | | 40 | – | +8G | – | – | | |
| | | | SPACE | | | 41 | | | | 42 | – | 3/4"C | – | – | | |
| | | TOTAL LOAD ❶ 100% = | 54490VA | | | TOTAL LOAD ❶ 100% = | | | | 66A | | | TOTAL LOAD ❶ 125% = | 82A | | |

## NEW KITCHEN PANEL — KITCHEN

**PANEL LK** — 225A MLO, 208Y/120V, 3ϕ, 4 WIRE — AVAILABLE FAULT: <10,000A — SCCR & AIC: 10,000A — MOUNTING: RECESSED — STAINLESS STEEL COVER

| NOTES | EQUIP. NO. | LOAD | DESCRIPTION | WIRE | CB | CKT | A | B | C | CKT | CB | WIRE | DESCRIPTION | LOAD | EQUIP. NO. | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | E10 | 640 | 3 REC – RR/STOR/CUST & BELL | 3–12 | 20/1 | 1 | | | | 2 | 20/1 | 3–12 | 1 REC – KITCHEN | 180 | E10 | |
| | E110 | 1920 | WASHING MACHINE | 3–12 | 20/1 | 3 | | | | 4 | 20/1 | 3–12 | 1 REC – KITCHEN | 180 | E10 | |
| | E110A | 5000 | DRYER | 2–10 | 30/2GFI | 5 | | | | 6 | 20/1 | 3–12 | 1 REC – KITCHEN | 180 | E10 | |
| | E151 | – | – | +10N+10G | 3/4"C | 7 | | | | 8 | 20/2 | 2–10 | HEATED CABINET | 3224 | E187 | |
| | | 540 | 3 REC – OFFICE | 3–12 | 20/1 | 9 | | | | 10 | 3/4"C | +10G | – | – | | |
| | E10 | 540 | 3 REC – KITCHEN | 3–12 | 20/1 | 11 | | | | 12 | 20/2 | 2–10 | HEATED CABINET | 3224 | E187 | |
| | E10 | 360 | 2 REC – SERVING LINE | 3–12 | 20/1 | 13 | | | | 14 | 3/4"C | +10G | – | – | | |
| | E10 | 360 | 2 REC – SERVING LINE | 3–12 | 20/1 | 15 | | | | 16 | 20/3 | 3–12 | DISPOSER | 3960 | E123 | |
| | | 1000 | 2 EDF – CAFETERIA | 3–12 | 20/1 | 17 | | | | 18 | – | +12G | ( 3 HP ) | – | | |
| | E615 | 500 | 2 MENU BOARDS | 3–12 | 20/1 | 19 | | | | 20 | – | 3/4"C | – | – | | |
| | E209 | 960 | MILK COOLER | 3–12 | 20/1 | 21 | | | | 22 | 20/1 | 3–12 | AIR SCREEN | 612 | E101 | |
| | E201A | 5824 | HOT FOOD COUNTER | 2–8 | 35/2 | 23 | | | | 24 | 15/1 | 3–12 | EF–CF ( 1/6HP ) | 528 | | |
| | | – | – | +10G | 3/4"C | 25 | | | | 26 | 15/1 | 3–12 | EF–14 ( 1/6HP ) | 528 | | |
| | E201B | 1920 | COLD FOOD COUNTER | 3–12 | 20/1 | 27 | | | | 28 | 20/1 | 3–12 | EF–2 ( 1/6HP ) | 528 | | |
| | E214 | 360 | CASH REGISTERS | 3–12 | 20/1 | 29 | | | | 30 | 20/1 | | SPARE | | | |
| | E201B | 1920 | COLD FOOD COUNTER | 3–12 | 20/1 | 31 | | | | 32 | 20/1 | | SPARE | | | |
| | E201A | 5824 | HOT FOOD COUNTER | 2–8 | 35/2 | 33 | | | | 34 | 20/1 | | SPARE | | | |
| | | – | – | +10G | 3/4"C | 35 | | | | 36 | 20/1 | | SPARE | | | |
| | E209 | 960 | MILK COOLER | 3–12 | 20/1 | 37 | | | | 38 | 20/1 | | SPARE | | | |
| | | 360 | 2 REC – CAFETERIA | 3–12 | 20/1 | 39 | | | | 40 | 20/1 | | SPARE | | | |
| | | | SPARE | | 20/1 | 41 | | | | 42 | 20/1 | | SPARE | | | |
| | E153/E153M | 250 | HOOD LTS & SENSOR | 3–12 | 20/1 | 43 | | | | 44 | 20/1GFI | 3–12 | DROP CORD | 180 | E129 | |
| | E153/E153M | 250 | HOOD LTS & SENSOR | 3–12 | 20/1 | 45 | | | | 46 | 20/1GFI | 3–12 | DROP CORD | 180 | E129 | |
| 8 | E161 | 720 | CONVECTION OVEN | 3–12 | 20/1GFI | 47 | | | | 48 | 20/1GFI | 3–12 | MOBILE PROOFER | 1800 | E139A | |
| 8 | E161 | 720 | CONVECTION OVEN | 3–12 | 20/1GFI | 49 | | | | 50 | 20/1GFI | 3–12 | 20QT MIXER | 960 | E125 | |
| 8 | E161 | 720 | CONVECTION OVEN | 3–12 | 20/1GFI | 51 | | | | 52 | 20/1GFI | 3–12 | DROP CORD | 180 | E129 | |
| 8 | E161 | 720 | CONVECTION OVEN | 3–12 | 20/1GFI | 53 | | | | 54 | 20/1GFI | 3–12 | DROP CORD | 180 | E129 | |
| 8 | E163 | 600 | TILT BRAISING PAN | 3–12 | 20/1 | 55 | | | | 56 | 20/1GFI | 3–12 | DROP CORD | 180 | E129 | |
| 8 | E172 | 3120 | COMBI OVEN | 2–12 | 20/2 | 57 | | | | 58 | 20/1GFI | 3–12 | DROP CORD | 180 | E129 | |
| | | – | – | +12G | 3/4"C | 59 | | | | 60 | 20/1 | 3–12 | EXISTING CIRCUIT | 500 | | 5 |
| 8 | E172 | 3120 | COMBI OVEN | 2–12 | 20/2 | 61 | | | | 62 | 20/2 | 2–12 | EXISTING CIRCUIT | 1000 | | 5 |
| | | – | – | +12G | 3/4"C | 63 | | | | 64 | – | +12N+12G | – | – | | 5 |
| | | 250 | EXISTING CIRCUIT | 3–12 | 20/1 | 65 | | | | 66 | 20/2 | 2–12 | EXISTING CIRCUIT | 1000 | | 5 |
| 9 | | 0 | TEMP LOAD CENTER | 4–3 | 100/3 | 67 | | | | 68 | – | +12N+12G | – | – | | 5 |
| | | – | – | +8G | – | 69 | | | | 70 | 30/2 | 2–10 | EXISTING CIRCUIT | 3000 | | 5 |
| | | – | – | 1.25"C | – | 71 | | | | 72 | – | +10N+10G | – | – | | |
| | | TOTAL LOAD ❶ 100% = | 61942VA | | | TOTAL LOAD ❶ 100% = | | | | 172A | | | TOTAL LOAD ❶ 65% = | 112A | | |

## KITCHEN HOOD CONTACTOR SCHEDULE

**HOOD 1**

| POLE | DESCRIPTION | NORMAL CKT | EM CKT | CONTROL ZONE | EQUIPMENT LOCATION | CONTACTOR TYPE |
|---|---|---|---|---|---|---|
| CK1–1 | CONVECTION OVEN | LK–47 | – | HOOD 1 | KITCHEN | ELECTRICALLY HELD – NO |
| CK1–2 | CONVECTION OVEN | LK–49 | – | HOOD 1 | KITCHEN | ELECTRICALLY HELD – NO |
| CK1–3 | CONVECTION OVEN | LK–51 | – | HOOD 1 | KITCHEN | ELECTRICALLY HELD – NO |
| CK1–4 | CONVECTION OVEN | LK–53 | – | HOOD 1 | KITCHEN | ELECTRICALLY HELD – NO |
| CK1–5 | SPARE | | | | | ELECTRICALLY HELD – NO |
| CK1–6 | SPARE | | | | | ELECTRICALLY HELD – NO |
| CK1–7 | SPARE | | | | | ELECTRICALLY HELD – NO |
| CK1–8 | SPARE | | | | | ELECTRICALLY HELD – NO |

**HOOD 2**

| POLE | DESCRIPTION | NORMAL CKT | EM CKT | CONTROL ZONE | EQUIPMENT LOCATION | CONTACTOR TYPE |
|---|---|---|---|---|---|---|
| CK2–1 | TILT BRAISING PAN | LK–55 | – | HOOD 2 | KITCHEN | ELECTRICALLY HELD – NO |
| CK2–2 | COMBI–OVEN | LK–57/59 | – | HOOD 2 | KITCHEN | ELECTRICALLY HELD – NO |
| CK2–3 | ( 2–POLE ) | – | – | – | – | ELECTRICALLY HELD – NO |
| CK2–4 | COMBI–OVEN | LK–61/63 | – | HOOD 2 | KITCHEN | ELECTRICALLY HELD – NO |
| CK2–5 | ( 2–POLE ) | – | – | – | – | ELECTRICALLY HELD – NO |
| CK2–6 | SPARE | | | | | ELECTRICALLY HELD – NO |
| CK2–7 | SPARE | | | | | ELECTRICALLY HELD – NO |
| CK2–8 | SPARE | | | | | ELECTRICALLY HELD – NO |

1. REFERENCE FLOOR PLANS FOR EQUIPMENT LOCATIONS AND ADDITIONAL INFORMATION.
2. EACH KITCHEN HOOD CONTACTOR HALL BE CONTROLLED ON/OFF BY THE APPROPRIATE HOOD ANSUL SYSTEM. WHEN ACTIVATED ALL POWER WITHIN THE COOKING HOOD SHALL BE DE–ENERGIZED.

## EXIST GE SWITCHBOARD — CENTRAL PLANT

**(E)SWBD MM** — 2000A MCB, 480Y/277V, 3ϕ, 4 WIRE — AVAILABLE FAULT: 37,000A — SCCR & AIC: 100,000A — FREE STANDING

| NOTES | CIRCUIT | DESCRIPTION | CB | FEEDER SIZE | AMPS |
|---|---|---|---|---|---|
| | 1 | EXIST PANEL H | 225/3 | EXIST FEEDER | |
| | 2 | EXIST ATS | 70/3 | EXIST FEEDER | 29A |
| | 3 | EXIST DISTRIBUTION PANEL DB | 400/3 | EXIST FEEDER | |
| | 4 | EXIST DISTRIBUTION PANEL DA | 400/3 | EXIST FEEDER | 274A |
| | 5 | EXIST DISTRIBUTION PANEL AC | 800/3 | EXIST FEEDER | |
| | 6 | EXIST DISTRIBUTION PANEL DC | 400/3 | EXIST FEEDER | |
| 2,3 | 7 | NEW PANEL HK | 225/3 | 4–4/0 +4G, 2.5"C | 66A |
| | 8 | XFMR TLCAB | 125/3 | EXIST FEEDER | |
| | 9 | SPD | 60/3 | EXIST FEEDER | |
| | | | | TOTAL LOAD ❶ 100% = | 302A |
| | | | | TOTAL LOAD ❶ 125% = | 378A |

1. THE EXISTING 2000A FEEDER IS SUFFICIENT FOR THE REVISED LOAD.
2. UPDATE PANEL SCHEDULE TO MATCH REVISED EQUIPMENT DESCRIPTION.

## EXIST WESTINGHOUSE PANELBOARD

**(E)PANEL DA** — 400A MLO, 480Y/277V, 3ϕ, 4 WIRE — AVAILABLE FAULT: 27,000A — SCCR & AIC: 35,000A — MOUNTING: SURFACE

| NOTES | LOAD | DESCRIPTION | WIRE | CB | CKT | A | B | C | CKT | CB | WIRE | DESCRIPTION | LOAD | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | 9150 | AHU #2 | EXIST | 20/3 | 1 | | | | 2 | 60/3 | EXIST | DUCT HEATER 2 | 39000 | |
| | – | – | – | – | 3 | | | | 4 | – | – | ( STAGE ) | – | |
| | – | – | – | – | 5 | | | | 6 | – | – | – | – | |
| 2 | | KITCHEN LTS | EXIST | 20/1 | 7 | | | | 8 | 20/1 | EXIST | EXIST CIRCUIT | 3000 | |
| | 3000 | CAFETERIA LTS | EXIST | 20/1 | 9 | | | | 10 | 70/3 | 3–6 | TEMP KITCHEN PANEL LTK | 37918 | 4 |
| | 2300 | CUSTODIAN LTS | EXIST | 20/1 | 11 | | | | 12 | – | +8G | – | – | |
| | 3000 | STAGE/RR/STOR LTS | EXIST | 20/1 | 13 | | | | 14 | – | 3/4"C | – | – | |
| | | SPACE | | | 15 | | | | 16 | | | SPACE | | |
| | | SPACE | | | 17 | | | | 18 | | | SPACE | | |
| | | SPACE | | | 19 | | | | 20 | | | SPACE | | |
| | | SPACE | | | 21 | | | | 22 | | | SPACE | | |
| | | SPACE | | | 23 | | | | 24 | | | SPACE | | |
| | 130000 | PANEL PA | EXIST | 225/3 | 25 | | | | 26 | – | – | – | – | |
| | – | ( SUBFEED BREAKER ) | – | – | 27 | | | | 28 | – | – | – | – | |
| | – | – | – | – | 29 | | | | 30 | – | – | – | – | |
| | | TOTAL LOAD ❶ 100% = | 227368VA | | | TOTAL LOAD ❶ 100% = | | | | 274A | | | TOTAL LOAD ❶ 125% = | 342A |

1. THE EXISTING 400A FEEDER IS SUFFICIENT FOR THE REVISED LOAD.
2. UPDATE PANEL SCHEDULE TO MATCH REVISED EQUIPMENT DESCRIPTION.

## EXIST EM STANDBY PANELBOARD — CENTRAL PLANT

**(E)PANEL EL** — 100A MCB, 208Y/120V, 3ϕ, 4 WIRE — AVAILABLE FAULT: <10,000A — SCCR & AIC: 10,000A — MOUNTING: SURFACE

| NOTES | EQUIP. NO. | LOAD | DESCRIPTION | WIRE | CB | CKT | A | B | C | CKT | CB | WIRE | DESCRIPTION | LOAD | EQUIP. NO. | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | 500 | PA SYSTEM | EXIST | 20/1 | 1 | | | | 2 | 20/1 | EXIST | F/A RPS | 250 | | |
| | | 250 | SECURITY SYSTEM | EXIST | 20/1 | 3 | | | | 4 | 20/1 | EXIST | F/A RPS | 250 | | |
| | | 250 | FACP | EXIST | 20/1 | 5 | | | | 6 | 20/1 | EXIST | F/A RPS | 250 | | |
| | | 250 | F/A RPS | EXIST | 20/1 | 7 | | | | 8 | 20/1 | EXIST | F/A RPS | 250 | | |
| | | 250 | F/A RPS | EXIST | 20/1 | 9 | | | | 10 | 20/1 | EXIST | F/A RPS | 250 | | |
| | | | EXIST SPARE | | 20/1 | 11 | | | | 12 | 20/1 | | EXIST SPARE | | | |
| | | | EXIST SPARE | | 20/1 | 13 | | | | 14 | 20/1 | | EXIST SPARE | | | |
| 3 | E188 | 864 | REFRIGERATOR | 3–12 | 20/1 | 15 | | | | 16 | 25/3 | 3–10 | REFRIGERATION SYSTEM | 6192 | E103 | 4 |
| 3 | E188 | 864 | REFRIGERATOR | 3–12 | 20/1 | 17 | | | | 18 | – | +10G | – | – | | |
| 3 | E109 | 1428 | ICE MACHINE | 3–12 | 20/1 | 19 | | | | 20 | – | 3/4"C | – | – | | |
| 3 | E151 | 240 | HOOD ANSUL SYSTEMS | 3–12 | 20/1 | 21 | | | | 22 | 20/1EGF | 3–12 | COOLER DOOR HEATER/LTS | 600 | E102A | 4 |
| 3 | E102B | 600 | COOLER TEMP. ALARM | 3–12 | 20/1 | 23 | | | | 24 | 20/1EGF | 3–12 | FREEZER DOOR HEATER/LTS | 600 | E102A | 4 |
| 3 | E102C | 600 | COOLER PRESSURE PORT | 3–12 | 20/1 | 25 | | | | 26 | 20/1EGF | 3–12 | FREEZER DRAIN LINE HEATER | 600 | E103F | 4 |
| 3 | E102E | 120 | PANIC ALARM BUTTONS | 3–12 | 20/1 | 27 | | | | 28 | 20/2 | 2–10 | FREEZER COIL | 1893 | E103C | 4 |
| 3 | E103D | 216 | COOLER COIL | 3–12 | 20/1 | 29 | | | | 30 | – | +10G | – | – | | |
| 3 | E102B | 600 | FREEZER TEMP. ALARM | 3–12 | 20/1 | 31 | | | | 32 | 20/1 | | EXIST SPARE | | | |
| 3 | E102C | 600 | FREEZER PRESSURE PORT | 3–12 | 20/1 | 33 | | | | 34 | 20/1 | | EXIST SPARE | | | |
| | | 300 | GENERATOR ANTI COND HTR | EXIST | 20/1 | 35 | | | | 36 | 20/1 | | EXIST SPARE | | | |
| | | 250 | GENERATOR BATTERY CHRGR | EXIST | 20/1 | 37 | | | | 38 | 30/3 | EXIST | SPD | 50 | | |
| | | 4500 | GEN JACKET HTR | EXIST | 30/2 | 39 | | | | 40 | – | – | – | – | | |
| | | – | – | – | – | 41 | | | | 42 | – | – | – | – | | |
| | | TOTAL LOAD ❶ 100% = | 23867VA | | | TOTAL LOAD ❶ 100% = | | | | 66A | | | TOTAL LOAD ❶ 125% = | 83A | | |

1. THE EXISTING 100A FEEDER IS SUFFICIENT FOR THE REVISED LOAD.
2. UPDATE PANEL SCHEDULE TO MATCH REVISED EQUIPMENT DESCRIPTION.

GENERAL PANEL REQUIREMENTS:
A. REF ELECTRICAL FLOOR PLANS FOR PANEL LOCATIONS.
B. FIELD VERIFY EXISTING CIRCUITS PRIOR TO BEGINNING WORK.
C. ALL OUTAGES SHALL BE SCHEDULED AND CONFIRMED IN WRITING WITH THE OWNER A MINIMUM OF TWO WEEKS PRIOR TO ANY OUTAGE.
D. AT THE END OF THE PROJECT PROVIDE A NEW TYPEWRITTEN PANEL SCHEDULE USING BUILDING ROOM NUMBERS FOR ALL PANELS WITH CIRCUITS ADDED, REMOVED, OR MODIFIED AS PART OF THE PROJECT.

PANEL NOTES:
1. REVISE/REWORK WIRING/CONDUIT AS REQUIRED TO ADD/REMOVE DEVICES FROM EXISTING CIRCUIT.
2. EXISTING CIRCUIT TO BE DEMO.
3. REUSE EXISTING SPARE CB AND WIRE NEW CIRCUIT.
4. PROVIDE NEW CB & WIRE NEW CIRCUIT.
5. IDENTIFY ANY CIRCUITS OR PARTIAL CIRCUITS THAT EXTEND BEYOND THE AREA OF RENOVATION. PROVIDE TEMPORARY FEED TO MAINTAIN ALL CIRCUITS SERVING ELEMENTS/SPACES NOT TO BE REMOVED DURING CONSTRUCTION. RECONNECT EXISTING CIRCUITS/DEVICES TO REMAIN TO TEMPORARY KITCHEN PANEL ONCE AVAILABLE USING CB(S) PROVIDED. ALL PARTIAL CIRCUITS SHALL REMAIN AND REMAIN ACTIVE BOTH DURING AND AFTER CONSTRUCTION.
6. KITCHEN LIGHTS TO BE DUAL ZONES WIRED THROUGH LIGHTING CONTACTORS AND CONTROLLED ON/OFF BY THE BAS AND LOCAL LIGHTING SWITCHES.
7. EXTERIOR LIGHTS TO BE WIRED THROUGH LIGHTING CONTACTOR AND CONTROLLED ON/OFF BY THE BAS.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

u

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILL ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD.
SUGAR LAND, TX 77498

SEAL

STATE OF TEXAS — GEORGE L. STANTON — 38582 — REGISTERED PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL SCHEMATIC

u-E.400


STANTON ENGINEERING GROUP
INFORMATION–EXCELLENCE (713) 300–6080 | TEXAS ENG. FIRM REG. NO. F–23332 | 1300 W. SAM HOUSTON PARKWAY S., SUITE 125, HOUSTON, TX 77042

©2025 ALL RIGHTS RESERVED

## PLUMBING SYMBOLS LEGEND

| | | | |
|---|---|---|---|
| ——————— | SANITARY WASTE BELOW SLAB | SAN. | SANITARY |
| ——— | SANITARY WASTE ABOVE SLAB | CW | DOMESTIC COLD WATER |
| —— V. —— | VENT PIPING ABOVE SLAB | HW | DOMESTIC HOT WATER |
| — — — — | VENT PIPING | WC | WATER CLOSET |
| —— G —— | GAS PIPING, 4-8oz | UR | URINAL |
| —— G5 —— | GAS PIPING, 5LB | LAV | LAVATORY |
| —·—·— | DOMESTIC COLD WATER PIPING | SK | SINK |
| —··—··— | DOMESTIC HOT WATER PIPING | EDF | ELECTRIC DRINKING FOUNTAIN |
| —— D —— | DRAIN/RELIEF VENT PIPING | WH | WALL HYDRANT |
| ——⋈—— | STOP VALVE | HB | HOSEBIBB |
| 2CO | DOUBLE SAN. CLEANOUT (2-WAY) | CP | HOT WATER CIRCULATOR PUMP |
| CO | SANITARY SEWER CLEANOUT | FD | FLOOR DRAIN |
| WCO | WALL CLEANOUT | FSINK | FLOOR SINK |
| EXIST. | EXISTING | | |
| (R) | REMOVE (DEMOLISH) | | |
| (D) | DEMOLISH (REMOVE) | | |
| (E) | EXISTING — NO WORK | | |

## PLUMBING FIXTURE NOTES

1. ALL FIXTURES SHALL MEET WATER CONSERVATION PERFORMANCE STANDARDS MANDATED BY SENATE BILL 587. ALL FIXTURES SHALL HAVE FLOW RESTRICTION DEVICES (DRINKING FOUNTAINS SHALL BE SELF-CLOSING) TO COMPLY WITH THESE REQUIREMENTS.
2. ALL FIXTURES SHALL HAVE CONTROLS REQUIRING OPERATING FORCE NO GREATER THAN FIVE (5) POUNDS.
3. FOR LAVATORIES AND SINKS, ALL FAUCETS SHALL BE NO-LEAD SOLID BRASS, MEETING ALL REQUIREMENTS OF ANSI/NSF 61, SECTION 9 AND CERTIFIED AS SUCH. ALSO, INSTALL SYMMONS 7-210 MIXING VALVE ON HOT WATER SUPPLY SIDE OF ALL FAUCETS UNLESS HIGH TEMPERATURE LIMIT IS PROVIDED WITH FAUCET. MAXIMUM WATER TEMPERATURE FOR ALL FAUCETS THAT DELIVER HOT OR TEPID WATER SHALL BE 110°F. ALL METERING FAUCETS SHALL HAVE A MINIMUM TEN (10) SECONDS OF WATER FLOW, AND, INSTALL TRUEBRO HANDI LAV-GUARD VANDAL-PROOF INSULATION KITS OVER P-TRAP, SUPPLIES, STOPS AND ALL SHARP EDGES FOR ALL SINKS AND LAVATORIES (TRAP WRAP FROM BROCAR OR PROWRAP FROM McGUIRE SHALL BE ACCEPTABLE).
4. ALL PLUMBING FIXTURES REFERENCED AS "ADA", "TAS" OR "HANDICAP COMPLIANT" SHALL MEET ALL REQUIREMENTS OF THE ADA AND THE TEXAS ACCESSIBILITY STANDARDS. IT SHALL BE THE PLUMBING CONTRACTORS RESPONSIBILITY TO MEET THESE REQUIREMENTS.
5. IN MANY CASES, FIXTURES WITH THE SAME PLUMBING DESIGNATION HAVE DIFFERENT INSTALLATION HEIGHTS — REFERENCE ARCHITECTURAL DRAWINGS FOR ALL INSTALLATION HEIGHTS AND HANDICAP FIXTURE DESIGNATIONS. FIXTURES DESIGNATED AS ADULT HANDICAP SHALL MEET ALL REQUIREMENTS OF THE ADA. FIXTURES DESIGNATED AS CHILD HANDICAP SHALL MEET ALL REQUIREMENTS OF THE TEXAS ACCESSIBILITY STANDARDS FOR THE APPROPRIATE CHILDREN'S AGE GROUP (REF. ARCH. DWGS. AND SPECIFICATIONS).

## PLUMBING MATERIALS

SANITARY WASTE AND VENT

BELOW SLAB/GRADE: SCHEDULE 40, DWV PVC

ABOVE SLAB: STANDARD WEIGHT, CAST IRON, NO-HUB PIPING.

STORM DRAIN PIPING

BELOW SLAB/GRADE: SCHEDULE 40, DWV PVC

ABOVE SLAB, 8" AND UNDER: STANDARD WEIGHT, CAST IRON, NO-HUB PIPING.

ABOVE SLAB, 10" AND ABOVE: SERVICE WEIGHT, CAST IRON, BELL & SPIGOT.

NATURAL GAS

BELOW GRADE (OUTSIDE): YELLOW POLYETHYLENE PIPE WITH COATED STEEL RISER AND TRACER WIRE.

ABOVE SLAB: SCHEDULE 40 BLACK STEEL. PIPING 2.5" AND LARGER SHALL BE WELDED. PIPING 2" AND SMALLER SHALL HAVE SCREWED FITTINGS.

DOMESTIC WATER

INTERIOR: TYPE L COPPER WITH SOLDER TYPE WROUGHT COPPER FITTINGS, MADE UP WITH LEAD-FREE SOLDER.

EXTERIOR: TYPE K COPPER WITH SWEAT FITTINGS AND LEAD-FREE SOLDER. BEYOND 5 FEET FROM BUILDING, SCHEDULE 40 PVC.

## FIRE SPRINKLER SYSTEM NOTES


1. THE EXISTING FIRE SPRINKLER SYSTEM SHALL BE MODIFIED AND/OR EXPANDED TO COVER THE AREA OF RENOVATION IN ENTIRETY. ALL NEW AND REVISED PIPING SHALL BE ENGINEERED AND INSTALLED BY A LICENSED FIRE SPRINKLER CONTRACTOR.
2. REFERENCE THE SPECIFICATIONS, DIVISION 21, FOR MORE INFORMATION.

## GENERAL PLUMBING NOTES

1. SEE ARCHITECTURAL DRAWINGS AND SPECIFICATIONS FOR ADDITIONAL WORK DESCRIPTION. SEE THIS SHEET (P4.00) FOR PLUMBING SYMBOLS LEGEND.
2. COORDINATE PLUMBING SYSTEMS INSTALLATION WITH ARCHITECTURAL, STRUCTURAL, HVAC SYSTEMS, ELECTRICAL SYSTEMS, CONDUITS, ETC.... OFFSET PIPING AS REQUIRED TO PROVIDE A FUNCTIONING SYSTEM WITH ADEQUATE SPACE FOR SERVICING AND REPAIRS.
3. MAKE CONNECTIONS OF NEW PIPE SYSTEMS IN TO EXISTING PIPE SYSTEMS WITH THREADED OR SWEAT JOINTS. PROVIDE ELECTROLYSIS ISOLATING UNIONS AT CONNECTION OF DISSIMILAR MATERIALS. REFERENCE THE SPECIFICATIONS.
4. SITE SERVICES ARE SHOWN FOR REFERENCE ONLY. PLUMBING CONTRACTOR SHALL REFERENCE CIVIL DRAWINGS, INCLUDING LOCATIONS OF SERVICES, SIZES OF PIPES, FLOWLINE ELEVATIONS, ETC..
5. DO NOT INSTALL PLUMBING PIPING OVER ANY ELECTRICAL EQUIPMENT. REFERENCE ELECTRICAL DRAWINGS FOR LOCATIONS OF ELECTRICAL EQUIPMENT AND COORDINATE WITH ELECTRICAL SUBCONTRACTORS ACCORDINGLY. SEE DETAIL 2/MEP1. THIS INCLUDES FIRE SPRINKLER PIPING.
6. ALL PIPES THROUGH WALLS OR FLOORS SHALL BE SLEEVED AND SEALED PER DETAIL 5/P4.02. FIRE CAULK WHERE REQUIRED. THIS INCLUDES ALL WALLS, INTERIOR AND EXTERIOR. THIS INCLUDES FIRE SPRINKLER PIPING.
7. ALL CLEANOUTS SHALL BE CONNECTED TO SANITARY LINES USING WYES AND/OR LONG RADIUS ELLS. SANITARY TEES ARE NOT ACCEPTABLE. 2" MINIMUM SIZE. ALL WALL CLEAN OUTS IN VERTICAL RISERS, OR BANKS OF FIXTURES SHALL BE INSTALLED 4" ABOVE THE FLOOD RIM LEVEL OF THE LOWEST CONNECTED FIXTURE AND A MINIMUM OF 24" AFF.
8. ALL WASTE AND VENT PIPING BELOW SLAB SHALL BE 2" MINIMUM.
9. LOCATE PLUMBING VENTS THROUGH ROOF NOT NEARER THAN SIX (6) FEET AWAY FROM EDGE OF BUILDING AND TEN (10) FEET AWAY FROM ANY FRESH AIR INTAKES. OFFSET VENT PIPING, AS REQUIRED, IN CEILING SPACE BETWEEN CEILING AND ROOF TO MEET THESE REQUIREMENTS. SEE DETAIL 3/P4.02.
10. ALL DOMESTIC WATER PIPING (CW, HW AND HWR) SHALL BE INSULATED PER THE WRITTEN SPECIFICATIONS.
11. TOP OF FLOOR DRAINS IN MECHANICAL, AHU AND BOILER ROOMS SHALL BE SET 1-1/2" BELOW FINISHED FLOOR SURFACE. CONCRETE FLOOR SHALL BE SLOPED TO DRAIN, REFERENCE ARCHITECTURAL DRAWINGS. IN ALL OTHER LOCATIONS, FLOOR DRAINS SHALL BE SET FLUSH WITH FINISHED FLOOR, TAKING INTO ACCOUNT ANY FLOOR SLOPE OR FLOOR FINISH (TILE, TERRAZZO, ETC.) AS SHOWN ON ARCHITECTURAL DRAWINGS.
12. PROVIDE AN ISOLATING VALVE AT EACH WATER TAP OFF HOT AND COLD WATER MAINS TO ALLOW FOR SERVICING. VALVE SHALL BE BALL VALVE IF PIPE SIZE IS 2" OR LESS AND GATE VALVE OR BUTTERFLY VALVE IF LARGER THAN 2". SEE WRITTEN SPECIFICATIONS. VALVES SHALL BE EASILY ACCESSIBLE. PROVIDE 18" X 18", FIRE-RATED, STAINLESS STEEL ACCESS PANELS WITH HINGED, SECURITY LOCKING DOORS WHERE VALVES ARE INSTALLED ABOVE INACCESSIBLE CEILINGS OR IN WALL CHASES (MIFAB MODEL MPFR-SS-C). BALL VALVES AND BUTTERFLY VALVES INSTALLED ABOVE CEILINGS SHALL BE INSTALLED SUCH THAT HANDLE IS ON BOTTOM OF PIPE. ISOLATING WATER VALVES ABOVE CEILINGS SHALL BE INSTALLED NO MORE THAN 24" ABOVE CEILING. VALVES ABOVE INACCESSIBLE CEILINGS SHALL BE INSTALLED WITHIN REASONABLE REACH OF CEILING MOUNTED ACCESS PANEL.
13. WATER HAMMER ARRESTERS SHALL BE INSTALLED IN ADDITION TO AIR CHAMBERS PER THE RISER DIAGRAMS. SEE SPECIFICATIONS.
14. MECHANICALLY CLEAN ALL WASTE LINES WITH ROTARY MACHINE TO PROVE FREE FLOWING, SEE SPECIFICATIONS.
15. PROVIDE VENTED SLEEVE (2 PIPE SIZES LARGER THAN GAS PIPE UNLESS NOTED OTHERWISE) FOR ALL GAS PIPING IN GROUND BELOW PAVING OR SIDEWALKS AND INSIDE BUILDING IN WALLS AND IN UNVENTILATED CEILING SPACES, SEE SPECIFICATIONS.
16. GAS PIPING SHALL BE 1/2" MINIMUM. TAP GAS PIPING ON TOP OR SIDES ONLY. DO NOT INSTALL VALVES IN CEILING PLENUM OR IN ANY INACCESSIBLE LOCATION. ALL GAS VALVES SHALL BE EASILY ACCESSIBLE. REFER TO DETAIL 9/P4.01 FOR TYPICAL GAS CONNECTION INSTALLATION. REFER TO DETAIL 8/P4.02 FOR TYPICAL PRV INSTALLATION.
17. CENTER WALL HYDRANTS IN BRICK PATTERN OF EXTERIOR WALLS, REFERENCE THE ARCHITECTURAL DRAWINGS AND SPECIFICATIONS.
18. ALL REFRIGERATORS WITH ICE MAKERS, COMMERCIAL TYPE COFFEE MAKERS, ICE MAKERS, COFFEE VENDING MACHINES AND OTHER ITEMS REQUIRED IN OTHERS THAT REQUIRE A WATER CONNECTION SHALL HAVE A CW VALVE BOX, "VBOX", INSTALLED TO ALLOW EASY ACCESS AND REMOVAL OF MACHINE. ALSO, INSTALL IN-LINE FILTER IN WATER CONNECTION.
19. REFER TO CIVIL DRAWINGS FOR SITE SANITARY, SITE STORM SEWER, FIRE SERVICE AND DOMESTIC WATER SERVICE. PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR ALL PIPING INSIDE BUILDING TO OUTSIDE LOCATIONS SHOWN ON PLUMBING DRAWINGS. PLUMBING CONTRACTOR SHALL INCLUDE COST OF FINAL TIE-INS TO SITE SERVICES.
20. PER THE DRAWINGS, ALL DRAINS (FLOOR DRAINS, FLOOR SINKS, HUB DRAINS, KITCHEN DRAINS, SHOWER DRAINS, ETC.) SHALL BE VENTED AND TRAP PRIMED — NO EXCEPTIONS. TRAP PRIMING SHALL BE ACCOMPLISHED USING WATER CLOSET FLUSH VALVE TRAP PRIMING DEVICES OR PROSET SYSTEMS TRAP GUARD SEWER GAS EMISSION PROTECTION, AS SHOWN ON DRAWINGS. REFERENCE PLUMBING FLOOR PLANS AND RISER DIAGRAMS.
21. ALL PIPING LOCATED ON ROOF (GAS PIPING) SHALL BE INSTALLED ON ROOF PIPE SUPPORTS PER DETAIL 10/P4.02, 6-FOOT ON CENTER. INSTALL ROOF PIPE JACK PER DETAIL 9/P4.02 FOR ALL PIPING THROUGH ROOF.
22. COORDINATE LOCATIONS OF ALL ROOF DRAINS AND OVERFLOW ROOF DRAINS WITH ARCHITECTURAL DRAWINGS.
23. FOR COMBINATION WASTE AND VENT SYSTEMS (WHERE APPLICABLE ON DRAWINGS), DRAIN P-TRAPS SHALL BE SIZE OF PIPE SHOWN ON DRAWINGS (I.E. TWO PIPE SIZES LARGER THAN DRAIN SIZE). FOR EXAMPLE, A 4" FLOOR DRAIN SHALL HAVE A 6" P-TRAP.
24. FOR ALL PLUMBING FIXTURES, IF COPPER PIPING IS STUBBED THROUGH WALL FOR DRAIN CONNECTION, INSTALL MARVEL FITTING AT DRAIN CONNECTION FOR EASE OF SERVICING AND REPAIRS. COPPER DRAIN PIPING WILL ONLY BE ALLOWED FOR DIRECT/STRAIGHT STUB-OUT OF FIXTURE DRAIN PIPING THROUGH WALL.
25. DO NOT INSTALL ANY PIPING BENEATH CVT OR VAV BOXES. THIS INCLUDES FIRE SPRINKLER PIPING.
26. WHERE UNDERGROUND VENT PIPE SIZE IS NOT NOTATED, VENT SHALL BE 2" DIAMETER.
27. WHERE UNDERGROUND SANITARY PIPE SIZE IS NOT NOTATED, REFER TO THE RISER DIAGRAMS FOR SIZE. NOT BELOW GRADE SANITARY PIPE SHALL BE SMALLER THAN 2". NO SANITARY LINE OR P-TRAP FOR A DRAIN/FIXTURE SHALL BE SMALLER THAN THE FIXTURE CONNECTION SIZE SHOWN ON THE DRAIN/FIXTURE SCHEDULE.
28. WHERE ABOVE GROUND VENT PIPE SIZE IS NOT NOTATED, REFER TO THE RISER DIAGRAMS FOR VENT SIZE.
29. WHERE CW/HW PIPING SIZE TO THE FIXTURE IS NOT SHOWN ON THE FLOOR PLAN, REFER TO THE RISER DIAGRAMS FOR CW/HW PIPE SIZE. NO PIPING TO FIXTURE SHALL BE SMALLER THAN THE FIXTURE CONNECTION SIZE SHOWN ON THE FIXTURE SCHEDULE.
30. TO INSTALL NEW PLUMBING SYSTEMS BELOW EXISTING CONCRETE SLABS, FIRST PLUMBING CONTRACTOR SHALL LAY OUT CUT. THEN, DEMOLITION CONTRACTOR SHALL SAW CUT SLAB TO CONTROL CRACKING AND REMOVE ALL CONCRETE. PLUMBING CONTRACTOR SHALL THEN EXCAVATE FILL TO PROPER SLOPE, INSTALL NEW PIPING SYSTEMS AS REQUIRED, THEN BACKFILL AND COMPACT TO PROPER DENSITY. THE CONCRETE CONTRACTOR SHALL THEN INSTALL NEW SIX (6) MIL POLYETHYLENE VAPOR BARRIER AND SEAL, INSTALL NEW REINFORCING STEEL AND WELD ON TO EXISTING, THEN RE-POUR CONCRETE TO NEW LEVEL. DO NOT CUT THROUGH GRADE BEAMS WITHOUT APPROVAL FROM THE STRUCTURAL ENGINEER. SEE ARCHITECTURAL AND STRUCTURAL DRAWINGS AND SPECIFICATIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.
31. ALL ABANDONED FIXTURES, DRAINS AND PIPING (INCLUDING PIPING ABANDONED IN THE PAST) IN AREAS WHERE WORK IS BEING DONE SHALL BE COMPLETELY REMOVED FROM BUILDING (INCLUDING PIPING BELOW SLAB/GRADE — UNLESS SHOWN OTHERWISE ON DRAWINGS). EXISTING WATER PIPING SHALL BE CAPPED AT EXISTING WATER MAIN TAPS AND ALL ABANDONED PIPING REMOVED. ABANDONED VENT PIPING SHALL BE COMPLETELY REMOVED, INCLUDING EXISTING VTR'S NOT RE-USED. PATCH AS REQUIRED. ONLY ACTIVE PIPING, FIXTURES AND DRAINS SHALL REMAIN IN BUILDING WHERE WORK IS BEING DONE.

## GAS PRV SCHEDULE

| MARK | PRV-K |
|---|---|
| LOCATION | MECH. YARD |
| SERVES | KITCHEN |
| GAS LOAD | 585 CFH |
| DISTANCE FROM METER | 150 FT |
| DISTANCE TO LAST OUTLET | 200 FT |
| INLET (SIZE/PRESSURE) | 1" / 5 PSI |
| OUTLET (SIZE/PRESSURE) | 2" / 7-12 IN WC |




### 4 GAS PRESSURE REGULATOR DETAIL (PRV)

NO SCALE

NOTES:
1. GAS REGULATOR SHALL BE ANSI Z21.80 CERTIFIED FOR LINE PRESSURE REGULATION BETWEEN THE SERVICE REGULATOR AND CONNECTED EQUIPMENT.
2. ALL GAS REGULATORS WITH INLET PRESSURE ABOVE 2 PSI SHALL BE EQUIPPED WITH A FACTORY INSTALLED OVERPRESSURE PROTECTION DEVICE, AS PART OF THE ANSI Z21.80 CERTIFICATION.
3. GAS REGULATOR SHALL BE EQUIPPED WITH A VENT LIMITING DEVICE, SIZED IN ACCORDANCE WITH THE REGULATOR OUTLET PRESSURE.
4. ALL REGULATORS INSTALLED OUTDOORS SHALL BE RATED FOR OUTDOOR INSTALLATION.
5. BASIS OF DESIGN IN THE MAXITROL 325-L SERIES OF REGULATORS

## PLUMBING DRAINS, CLEANOUTS AND HYDRANTS


| MARK | MIN. CONNECTION SIZES (IN.) SAN | VENT | CW | HW | DESCRIPTION/SPECIFICATION FOR FIXTURE OR EQUIPMENT |
|---|---|---|---|---|---|
| FD | 4 | 2 | 1/2 | – | TOILET FLOOR DRAIN — TWO-PIECE CAST IRON WITH SEEPAGE FLANGE, REVERSIBLE CLAMPING COLLAR, 1/2" TRAP PRIMER TAP, 6" SQUARE, NICKEL BRONZE HSTRAINER AND SECURITY SCREWS JR SMITH MODEL 2005-03-K06PB-P050-U. |
| FD2 | 4 | 2 | 1/2 | – | EQUIPMENT FLOOR DRAIN — CAST IRON, MEDIUM DEPTH DRAIN WITH FLANGE, CLAMPING DEVICE, SEEPAGE OPENINGS, DUCTILE IRON TRUE-FIT SEDIMENT BUCKET WITH 12" STAINLESS STEEL RIM LESS GRATE, 1/2" TRAP PRIMER TAP ZURN MODEL ZS-540-U-P DRAIN SHALL BE DESIGNED SUCH THAT GRATE CANNOT BE INSTALLED WITHOUT SEDIMENT BUCKET. |
| FD3 | 4 | 2 | 1/2 | – | GRATED MECHANICAL ROOM FLOOR DRAIN — CAST IRON WITH FLANGE, SEEPAGE OPENINGS, 9" HEAVY-DUTY DUCTILE IRON GRATE WITH STAINLESS STEEL VENEER, CLAMPING DEVICE AND 1/2" TRAP PRIMER TAP ZURN MODEL ZS-550-C-P |
| FD4 | 4 | 2 | 1/2 | – | CANWASH FLOOR DRAIN — ALL GALVANIZED CAST IRON, MEDIUM DEPTH DRAIN WITH FLANGE, CLAMPING DEVICE, SEEPAGE OPENINGS, GALVANIZED SUR-SET SEDIMENT BUCKET WITH 12" GALVANIZED DUCTILE IRON RIM AND GRATE, 1/2" TRAP PRIMER TAP ZURN MODEL ZS-540-P-G-HD. DRAIN SHALL BE DESIGNED SUCH THAT GRATE CANNOT BE INSTALLED WITHOUT SEDIMENT BUCKET. |
| FD5 | 4 | 2 | 1/2 | – | KITCHEN FLOOR DRAINS SHALL BE SIMILAR EXCEPT WITH 7" SQUARE, BRONZE GRATE JR SMITH MODEL 2005-03-K07PB-P050-U PROVIDE 4" DIAMETER STAINLESS STEEL FUNNEL WHERE SHOWN ON DRAWINGS. REFERENCE KITCHEN CONNECTION SCHEDULE ON PLUMBING RENOVATION FLOOR PLAN SHEET. |
| FS KITCHEN FS | 4 | 2 | 1/2 | – | FLOOR SINK — CAST IRON, 8" DEEP SUMP, A.R.E. INTERIOR, INTEGRAL FLANGE FOR SUPPORT, CLAMPING DEVICE WHERE VAPOR BARRIER IS INSTALLED BETWEEN SLAB AND CONCRETE BEDDING FOR FLOOR, ALUMINUM SECONDARY DOME STRAINER AND 12" SQUARE HEAVY DUTY STAINLESS STEEL TRACTOR DUTY FRAME WITH 3/4-TRACTOR GRATE AND 1/2" TRAP PRIMER TAP JR SMITH MODEL 3150Y-04-C-13. |
| CO | VARIES | – | – | – | FLOOR CLEANOUT — ADJUSTABLE EXTENSION HOUSING, CAST IRON FERRULE WITH FULL-LINE-SIZE BRASS PLUG (UP TO 4"), 5" DIAMETER STAINLESS STEEL ACCESS COVER WITH VANDAL-PROOF SCREW, ROUND NICKEL BRONZE FRAME AND TOP (NOT COMPATIBLE WITH FLOOR TYPE (REFERENCE ARCHITECTURAL DRAWINGS FOR FLOOR TYPES)) ZURN MODEL ZS-1400-VP. PROVIDE CARPET FLANGE FOR CARPETED AREAS (CARPET MARKER SHALL NOT BE ACCEPTABLE) AND TERRAZZO RECESS FOR TERRAZZO FLOORS.<br>OUTDOOR CLEANOUT — SAME AS TYPE "CO" EXCEPT WITH HEAVY-DUTY NICKEL BRONZE TOP ZURN MODEL ZN-1400-HD-VP. INSTALL 18" X 18" X 6" THICK CONCRETE PAD AROUND EACH OUTDOOR CLEANOUT. |
| WCO | VARIES | – | – | – | WALL CLEANOUT — CAST IRON FERRULE WITH COUNTERSUNK HEAD (FULL-LINE-SIZE PVC PLUG UP TO 4") MIFAB MODEL C1400. ACCESS COVER SHALL BE 8" SQUARE, SURFACE MOUNT, FLUSH INSTALLATION, 16-GAUGE STAINLESS STEEL ACCESS DOOR WITH FLANGED FRAME AND VANDAL-PROOF OPTION MI-FAB MODEL UA-SS-VP. ACID WASTE CLEANOUT (AWCO) SHALL BE SAME EXCEPT ACID WASTE PIPING.<br>INSIDE CABINETWORK WHERE CLEANOUT IS NOT VISIBLE, ACCESS PANEL MAY BE ROUND STAINLESS STEEL TYPE WITH VANDAL-PROOF CENTER SCREW MI-FAB MODEL C1450-RD-3-6. |
| 2CO | 4 | – | – | – | DOUBLE CLEANOUTS — SAME AS OUTDOOR CLEANOUTS. INSTALLED FOR TWO-WAY RODDING. SINGLE CLEANOUT WITH 2-WAY FITTING IS NOT ACCEPTABLE, PROVIDE TWO SEPARATE CLEANOUTS. INSTALL 18" X 18" X 6" THICK CONCRETE PAD AROUND EACH OUTDOOR CLEANOUT. |
| HB | – | – | 3/4 | – | HOSEBIBB — 3/4" HOSE THREAD, INTEGRAL VACUUM BREAKER SPOUT, ROUGH CHROME FINISH WITH REMOVABLE KEYED HANDLE, WALL FLANGE CHICAGO MODEL 952. |
| WH | – | – | 3/4 | – | RESTROOM WALL HYDRANT — NARROW WALL, WARM CLIMATE TYPE HOSE BOX, QUARTER-TURN WHEEL HANDLE, ASSE APPROVED ANTI-SIPHON INTEGRAL VACUUM BREAKER AND DUAL CHECK VALVE, 3/4" STRAIGHT INLET HOSE CONNECTION, CAST STAINLESS STEEL HYDRANT BOX, FLUSH MOUNTED 16-GAUGE STAINLESS STEEL FRAME AND 180° DROP DOWN DOOR WITH KEY LOCK AND WALL CLAMP JR SMITH MODEL 5518 |
| WH2 | – | – | 3/4 | – | EXTERIOR WALL HYDRANT — NON-FREEZE HOSE BOX, QUARTER-TURN WHEEL HANDLE, ASSE APPROVED ANTI-SIPHON INTEGRAL VACUUM BREAKER AND DUAL CHECK VALVE, 3/4" STRAIGHT INLET HOSE CONNECTION, CAST STAINLESS STEEL HYDRANT BOX, FLUSH MOUNTED 16-GAUGE STAINLESS STEEL FRAME AND 180° DROP DOWN DOOR WITH KEY LOCK AND WALL CLAMP JR SMITH MODEL 5519 |
| WH3 | – | – | 3/4 | 3/4 | CANWASH WALL HYDRANT — NON-FREEZE HOSE BOX WITH STRAIGHT INLET CONNECTION, HOT AND COLD MIXING, REMOVABLE KEYED HANDLE, ASSE APPROVED ANTI-SIPHON INTEGRAL BACKFLOW PREVENTER WITH 3/4" HOSE CONNECTION, HEAVY DUTY BRASS CASING, POLISHED BRONZE HYDRANT BOX WITH HINGED COVER, "WATER" CAST ON COVER, DRIP LIP AND WALL CLAMP J.R. SMITH MODEL 5560-QT-WC-H-W-PB. |
| WBOX | 2 | 2 | 3/4 | 3/4 | CLOTHES WASHER DRAIN/VALVE BOX — HEAVY-GAUGE GALVANIZED STEEL CONSTRUCTION, RECESSED IN WALL, VALVE AND DRAIN CONNECTIONS, WATTS DUO-CLOZ VALVE GUY GRAY MODEL WB-200. |

## PLUMBING FIXTURES AND EQUIPMENT

| MARK | MIN. CONNECTION SIZES (IN.) SAN | VENT | CW | HW | DESCRIPTION/SPECIFICATION |
|---|---|---|---|---|---|
| WC | 4 | 2 | 1 | – | WATER CLOSET — WALL MOUNTED, WHITE VITREOUS CHINA, SIPHON JET ACTION, 1.28 GPF, ELONGATED BOWL, TOP SPUD, ADA/TAS COMPLIANT, AMERICAN STANDARD AFWALL: SLOAN ROYAL 111-1.28 FLUSH VALVE WITH VANDAL-PROOF FREE-SPINNING TOP CAP, 1.28 GPF, VANDAL-PROOF STOP AND ADA/TAS COMPLIANT LEVER ACTUATOR WITH LEVER INSTALLED ON LEFT SIDE (FOR FIXTURES DESIGNATED AS "HANDICAP"), INSTALL LEVER ON "WIDE-SIDE" OF TOILET STALL); BEMIS 1655-SS/C EXTRA HEAVY DUTY, WHITE, OPEN FRONT SEAT LESS COVER WITH SELF-SUSTAINING, STAINLESS STEEL CHECK HINGE; AND, FLOOR MOUNTED CARRIER. |
| LV | 1-1/4 | 1-1/4 | 1/2 | 1/2 | LAVATORY GOOSENECK FAUCET — WALL HUNG, WHITE VITREOUS CHINA, FRONT OVERFLOW, SELF-DRAINING DECK AREA, 21" X 18", ADA/TAS COMPLIANT AMERICAN STANDARD LUCERNE 0355.012; DECK MOUNTED FAUCET, 4" CENTERS, FIXED, CHROME PLATED, 5.25" GOOSENECK SPOUT, PRESSURE COMPENSATING LAMINAR FLOW NON-AERATING 0.5 GPM OUTLET, 4" WRISTBLADE HANDLES, INTERCHANGEABLE COMPRESSION CARTRIDGES, CHICAGO 895-317GNAE72ABCP; CHROME PLATED, 17-GAUGE CAST BRASS GRID DRAIN WITH WHEELCHAIR OFFSET FITTING; CHROME PLATED, 17-GAUGE CAST BRASS P-TRAP WITH CLEANOUT PLUG; CHROME PLATED, CAST BRASS, LOOSE KEY ANGLE STOP WITH CHROME PLATED COPPER RISER; TRUEBRO HANDI LAV-GUARD VANDAL-PROOF, WHITE INSULATION KITS; AND, FLOOR MOUNTED, CONCEALED ARMS CARRIER. PROVIDE ASSE 1070 LISTED MIXING VALVE, LEONARD 170-LF OR EQUAL (MUST BE CAPABLE OF ADJUSTMENT ABOVE 130°F). |
| LV2 | 1-1/4 | 1-1/4 | 1/2 | 1/2 | LAVATORY — WALL HUNG, WHITE VITREOUS CHINA, FRONT OVERFLOW, SELF-DRAINING DECK AREA, 21" X 18", ADA/TAS COMPLIANT AMERICAN STANDARD LUCERNE 0355.012; CHROME PLATED, ALL CAST BRASS CONSTRUCTION, ADA/TAS COMPLIANT, VANDAL-PROOF FAUCET WITH 4" WRIST BLADE HANDLES, COMPRESSION STYLE CARTRIDGES, CHROME DECK PLATE, VANDAL-PROOF AERATOR, COPPER SUPPLIES AND CERTIFIED FOR MEETING ALL REQUIREMENTS OF NSF 61 SECTION 9 CHICAGO MARATHON MODEL 802-E70-317ABCP; CHROME PLATED, 17-GAUGE CAST BRASS GRID DRAIN WITH WHEELCHAIR OFFSET FITTING; CHROME PLATED, 17-GAUGE CAST BRASS P-TRAP WITH CLEANOUT PLUG; CHROME PLATED, CAST BRASS, LOOSE KEY ANGLE STOP WITH CHROME PLATED COPPER RISER; TRUEBRO HANDI LAV-GUARD VANDAL-PROOF, WHITE INSULATION KITS; AND, FLOOR MOUNTED, CONCEALED ARMS CARRIER. PROVIDE ASSE 1070 LISTED MIXING VALVE, LEONARD 170-LF OR EQUAL (MUST BE CAPABLE OF ADJUSTMENT ABOVE 130°F). |
| EDF | 1-1/2 | 1-1/2 | 1/2 | – | BI-LEVEL ELECTRIC DRINKING FOUNTAINS WITH BOTTLE FILLER — WALL MOUNTED, ALL STAINLESS STEEL, ADA AND TAS COMPLIANT FOR ALL AGES, 8 GPH AT ARI STANDARDS, 2-STREAM ALL METAL BUBBLER FITTING WITH VANDAL-RESISTANT KIT AND FRONT PUSH BUTTON ACTUATION, PUSH BUTTON ACTIVATED BOTTLE FILLER WITH 1.1GPM FILL RATE AND ANTI-MICROBIAL COATING, INTEGRAL WATER FILTER, LEAD-FREE (CERTIFIED FOR MEETING ALL REQUIREMENTS OF NSF 61 SECTION 9), REFRIGERANT HFC-134a, MAINTENANCE ACCESS PANEL, HALSEY-TAYLOR MODEL HTHBWVR8BL; CHROME PLATED, 17-GAUGE CAST BRASS P-TRAP WITH CLEANOUT PLUG; CHROME PLATED, CAST BRASS, LOOSE KEY ANGLE STOP WITH CHROME PLATED COPPER RISER; FLOOR MOUNTED CHAIR CARRIER; AND, STAINLESS STEEL ADA APRON FOR LOCATIONS REQUIRED BY ADA OR TAS. |
| MB | 3 | 2 | 3/4 | 3/4 | MOP BASIN — 24" X 24" X 12" DEEP TERRAZZO, TWO (2) STAINLESS STEEL SPLASH CATCHER PANELS, 8" DROP FRONT WITH STAINLESS STEEL CAP, CAST BRASS DRAIN WITH STAINLESS STEEL STRAINER STERN WILLIAMS HILOW MODEL HI-1800-BP; FAUCET SHALL BE POLISHED CHROME PLATED SERVICE SINK TYPE WITH VACUUM BREAKER, INTEGRAL SUPPLY CHECK STOPS, SPOUT WITH PAIL HOOK, HOSE END AND TOP BRACE CHICAGO MODEL 897-CCF (INSTALL BACKING/BRACING INSIDE WALL TO SUPPORT FAUCET AND TOP BRACE). |
| LP-1 | 3 | 2 | 3/4 | 3/4 | LAVATORY PUMP — FACTORY BUILT, LIFT PUMP FOR GRAY WATER WASTE, TOP ACCESS TO INTERNAL 1/6HP PUMP AND FLOAT SWITCH, 1.5" TOP AND SIDE INLETS, 1.5" TOP OUTLET, INTEGRAL CHECK VALVE AT BOTTOM INLET CONNECTIONS, 9FT POWER CORD WITH GROUNDED PLUG;<br>LIBERTY PUMPS MODEL 406 |

## KITCHEN PLUMBING CONNECTION SCHEDULE


| MARK | DESCRIPTION |
|---|---|
| P5 | 3/4" CW AND 3/4" HW — IN WALL, 36" AFF, TO MOP BASIN ("MB") FAUCET. REFERENCE PLUMBING FIXTURE SCHEDULE. |
| P6 | 3" DRAIN IN FLOOR FOR MOP BASIN ("MB") DRAIN. REFERENCE PLUMBING FIXTURE SCHEDULE. |
| P7 | 3/4" CW AND 3/4" HW — IN WALL, 18" AFF, TO HOSE BIBB. |
| P10 | FLOOR DRAIN — 3" OUTLET; FLUSH WITH FLOOR; TWO-PIECE CAST IRON WITH SEEPAGE FLANGE, REVERSIBLE CLAMPING COLLAR, 7" SQUARE HEAVY-DUTY POLISHED BRONZE GRATE, 1/2" TRAP PRIMER TAP, AND TRAP SEAL DEVICE (MODEL 2692) JR SMITH MODEL 2005-03-K07PB-P050-U. |
| P11C | 1/2" CW AND 1/2" HW — IN WALL, FOR HAND LAVATORY WITH FOOT CONTROLS ("LV"). REFERENCE PLUMBING FIXTURE SCHEDULE. |
| P11D | 2" DRAIN — IN WALL, FOR HAND LAVATORY WITH FOOT CONTROLS ("LV"). REFERENCE PLUMBING FIXTURE SCHEDULE. |
| P12 | FLOOR SINK — 4" OUTLET; FLUSH WITH FLOOR; CAST IRON, 8" DEEP SUMP, A.R.E. INTERIOR, INTEGRAL FLANGE FOR SUPPORT, CLAMPING DEVICE WHERE VAPOR BARRIER IS INSTALLED BETWEEN SLAB AND CONCRETE BEDDING FOR FLOOR, ALUMINUM SECONDARY DOME STRAINER AND 12" SQUARE HEAVY DUTY NICKEL BRONZE FRA




## 13 FLUSH VALVE TRAP PRIMING TUBE DETAIL

NO SCALE

MI-FAB MODEL MI-702-MOD FLUSH VALVE TRAP PRIMER, OR EQUAL





## 14 GAS PIPING ROOF SUPPORT DETAIL

NO SCALE

NOTES:


1. GAS PIPING SUPPORT SHALL BE PORTABLE PIPE HANGERS, INC. MODEL PP10-R. PIPING SHALL BE INSTALLED 12" ABOVE FINISHED ROOF. PROVIDE 18" X 18" CAREY TREAD-TYPE MATERIAL BENEATH EACH PIPE SUPPORT.
2. FIELD LOCATE ROOF STRUCTURAL SUPPORTS AND PLACE BASE OF PIPE SUPPORT OVER ROOF SUPPORTS ONLY. PROVIDE BASE OF ADEQUATE LENGTH TO SPAN ROOF JOIST TO PREVENT SUPPORTS SETTING ON ROOF DECK ONLY.
3. INSTALL SIX (6) FOOT-ON-CENTERS.
4. PIPE SUPPORT MANUFACTURER'S REPRESENTATIVE SHALL PERSONALLY INSPECT INSTALLATIONS OF PIPE SUPPORTS AND MAKE CORRECTIONS AND HEIGHT ADJUSTMENTS TO INSTALLATIONS, AS REQUIRED, DURING INSPECTION.




## 9 ROOF PIPE JACK DETAIL

NO SCALE


NOTE: COORDINATE WITH ARCHITECTURAL DRAWINGS, DETAILS AND SPECIFICATIONS.




## 13 GAS PIPING WALL-TO-ROOF TRANSITION DETAIL

NO SCALE

| TANKLESS WATER HEATER SCHED. | | |
|---|---|---|
| MARK | IEWH-1 | |
| SERVES | LAVATORY | |
| LOCATION | BELOW COUNTER | |
| HEATER KW | 1.8 KW | |
| TEMP RISE (@ 0.5 GPM) | 25°F | |
| VOLTAGE/PHASE | 120V/1PH | |
| EEMAX MODEL | SPEX1812T | |





## 11 TANKLESS WATER HEATER

NO SCALE

NOTES:

1. LOCATION OF VALVE AND PIPING SHALL NOT INTERFERE WITH ANY ADA/HANDICAP KNEE-SPACE CLEARANCE REQUIREMENTS.
2. ALL PIPING SHALL BE CHROME PLATED CAST BRASS AND SHALL BE INSULATED BY TRUEBRO HANDI LAV-GUARD INSULATION KITS. INSULATION KITS SHALL COVER P-TRAP, MIXING VALVE, WATER STOPS, PIPING AND ALL SHARP EDGES (ONLY WHERE CABINETWORK KNEESPACE SCREEN NOT PROVIDED).
3. ALL CW AND HW CONNECTIONS SHALL HAVE COMPRESSION TYPE FITTINGS.
4. FURNISH & INSTALL 0.5-GPM AERATOR ON FAUCET COMPATIBLE WITH TANKLESS EWH REQUIREMENTS.
5. WATER HEATER SHALL HAVE INTEGRAL ASSE-1070 COMPLIANT TEMPERED MIXING VALVE.





## 10 ELECTRONIC TRAP PRIMING MANIFOLD DETAIL (TP)

NO SCALE

NOTES:


1. REFERENCE SCHEDULE ON SHEET P3.00




## 8 SAMPLE TEST WELL DETAIL (STW)


NO SCALE

NOTES:




## 7 TYPICAL GAS CONNECTION


NO SCALE




## 6 HOT WATER BALANCING STATION


NO SCALE

PROVIDE AT EACH JUNCTION OF BRANCH HOT WATER RETURN LOOPS TO MAIN CIRCULATING HOT WATER LINE, SEE PLUMBING PLANS.




## 5 WALL PENETRATION DETAIL


NO SCALE




## 4 PVC-TO-CAST IRON INSTALLATION DETAIL

NO SCALE


MISSION TRANSITION COUPLING DESIGNED AND CERTIFIED FOR THIS SPECIFIC APPLICATION SHALL BE ACCEPTABLE IN LIEU OF HUSKY COUPLING IN THIS DETAIL.




## 3 ROOF VENT DETAIL

NO SCALE

COORDINATE WITH ARCHITECTURAL DRAWINGS AND SPECIFICATIONS.





## 2 MIXING VALVE DETAIL

NO SCALE

NOTES

1. UNDERCOUNTER MIXING VALVE SHALL BE MOUNTED ON WALL IN FIXTURE KNEE-SPACE. LOCATION OF VALVE AND PIPING SHALL NOT INTERFERE WITH ANY ADA/HANDICAP KNEE-SPACE CLEARANCE REQUIREMENTS.
2. ALL PIPING SHALL BE CHROME PLATED CAST BRASS AND SHALL BE INSULATED BY TRUEBRO HANDI LAV-GUARD INSULATION KITS. INSULATION KITS SHALL COVER P-TRAP, MIXING VALVE, WATER STOPS, PIPING AND ALL SHARP EDGES (ONLY WHERE CABINETWORK KNEESPACE SCREEN NOT PROVIDED).
3. ALL CW AND HW CONNECTIONS SHALL HAVE COMPRESSION TYPE FITTINGS.
4. FOR ABOVE CEILING INSTALLATION, VALVE SHALL BE INSTALLED IN AN EASILY/READILY ACCESSIBLE LOCATION. SEE KITCHEN PLUMBING CONNECTION SCHEDULE FOR REQUIRED KITCHEN LOCATIONS.
5. LAVATORY MIXING VALVES SHALL HAVE AN OUTPUT ADJUSTMENT RANGE UP TO OR ABOVE 130°F.
   SINK MIXING VALVES SHALL HAVE AN OUTPUT ADJUSTMENT RANGE UP TO OR ABOVE 140°F.




## 1 MECHANICAL - ELECTRICAL COORDINATION DETAIL

NO SCALE

DO NOT INSTALL ANY PIPING BENEATH CVT BOXES. DO NOT INSTALL ANY PIPING (EXCEPT FIRE SPRINKLER PIPING AND OTHER PIPES SHOWN SPECIFICALLY ON THE PLUMBING FLOOR PLANS) OVER COMPUTER CLASSROOMS, BOOKROOMS, IDF/MDF/SERVER ROOMS OR OTHER ROOMS NOTED ON THE PLUMBING FLOOR PLANS.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT

SEAL

STATE OF TEXAS
INTERIM REVIEW
THIS DOCUMENT IS RELEASED FOR THE PURPOSE OF INTERIM REVIEW UNDER THE AUTHORITY OF TODD A. STANTON, P.E. TEXAS REGISTRATION NO. 108243 ON 07.18.2025 IT IS NOT TO BE USED FOR BIDDING OR CONSTRUCTION PURPOSES.
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING


PLUMBING SCHEDULES & DETAILS

**u-P0.02**

PRELIMINARY
NOT FOR CONSTRUCTION OR BIDDING PURPOSES


STANTON ENGINEERING GROUP
INFORMATION-CHECKED | TEXAS ENG. FIRM REG. NO. F-01833 | (713) 300-6080 | 1300 W. SAM HOUSTON PARKWAY S., SUITE 121, HOUSTON, TX 77042

© ALL RIGHTS RESERVED




**2 FIRE SPRINKLER - FDC RELOCATION**
SCALE: 1/4" = 1'- 0"

**EYED NOTES**
PLACE OF EXISTING.
ING SANITARY BELOW
LAB TO MATCH EXISTING.
N PLACE OF EXISTING
P-TRAP. TIE BACK
ARY BELOW SLAB AND
TCH EXISTING.
AIR FURNACE ON ROOF
H NEW OF SIMILAR SIZE
NECT AND RECONNECT
E WITH NEW RIGID GAS
WITH DIV.23 FOR ALL




**1 PLUMBING RENOVATION FLOOR PLAN**
SCALE: 1/4" = 1'- 0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

u

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT

SUGAR MILL ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD.
SUGAR LAND, TX 77498

SEAL

STATE OF TEXAS
TYLER W. HERRING
106052
LICENSED
PROFESSIONAL ENGINEER
07.18.2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING


PLUMBING FLOOR PLAN

**u-P1.01**


STANTON ENGINEERING GROUP
INFORMATION: (713) 300-4080 | TEXAS ENG. FIRM REG. NO. F-01853210


2021 ALL RIGHTS RESERVED


1200 N. SAM HOUSTON PARKWAY N., SUITE 121, HOUSTON, TX 77043




600
Student Dining


## 2 PLUMBING TEMPORARY KITCHEN PLAN - POST DEMO

SCALE: 1/4" = 1'-0"

NOTES:

1. AFTER DEMOLITION OF EXISTING KITCHEN AND DURING CONSTRUCTION OF NEW KITCHEN, EXISTING TEMPORARY KITCHEN SHALL REMAIN ACTIVE.
2. ALL SANITARY, CW AND HW CONNECTIONS SHALL REMAIN ACTIVE DURING ALL TIMES WHEN TEMPORARY KITCHEN IS ACTIVE.
3. UPON COMPLETION OF NEW KITCHEN, EXISTING TEMPORARY KITCHEN SHALL BE DEMOLISHED AND ALL TEMPORARILY UTILITIES SHALL BE REMOVED AND TEMPORARY WATER TAPS CAPPED AT MAIN LINE TAP.
4. ALL DEMOLISHED LAVATORIES AND FAUCETS SHALL BE PERMITTED TO BE RELOCATED ACROSS TEMPORARY KITCHENS WITHIN THE PROJECT BASED ON AVAILABILITY/PROJECT PHASING SCHEDULE. AT THE END OF THE PROJECT, REMOVE FIXTURES AND OFFER TO OWNER AS SALVAGE. IF NOT ACCEPTED, ALL FIXTURES SHALL BE DISPOSED OF BY THE CONTRACTOR.

NORTH




600
Student Dining

## 1 PLUMBING TEMPORARY KITCHEN PLAN - PRE DEMO

SCALE: 1/4" = 1'-0"

NOTES:

1. BEFORE DEMOLITION OF THE EXISTING KITCHEN BEGINS, INSTALL ALL NEW PLUMBING FIXTURES AND UTILITIES FOR TEMPORARY KITCHEN.

NORTH

STANTON ENGINEERING GROUP
INFORMATION - ENGINEER (713) 300-4080
TEXAS ENG. FIRM REG. NO. F-01833 | © 2025 ALL RIGHTS RESERVED
1300 W. SAM HOUSTON PARKWAY N., SUITE 121, HOUSTON, TX 77043

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

u

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILL ELEMENTARY SCHOOL
13707 JESS PIRTLE BLVD.
SUGAR LAND, TX 77498

SEAL

STATE OF TEXAS
TYLER W. HERRING
106052
LICENSED
ARCHITECT
07.18.2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

PLUMBING FLOOR PLAN - TEMP KITCHEN

u-P1.02

# TECHNOLOGY SYMBOLS & LEGEND

## VOICE SYMBOLS

| | |
|---|---|
| | SINGLE VOICE OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| X | VOICE OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |
| | SINGLE VOICE OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED. |
| X | VOICE OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED, X = NUMBER OF CABLE TERMINATIONS PER LOCATION AS INDICATED. |
| | POWER/COMMUNICATIONS POLE WITH A SINGLE VOICE OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| X | POWER/COMMUNICATIONS POLE WITH X = NUMBER OF VOICE OUTLETS, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| | SINGLE VOICE OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE-THRU AS SPECIFIED. |
| X | VOICE OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE -THRU AS SPECIFIED WITH X = NUMBER OF VOICE TERMINATIONS PER LOCATION. |
| W | SINGLE VOICE OUTLET FOR WALL-MOUNTED PHONE, CABLE TYPE AS SPECIFIED, MOUNTED +52-INCHES A.F.F. UNLESS OTHERWISE NOTED. |

## VOICE/DATA SYMBOLS

| | |
|---|---|
| | SINGLE VOICE & SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| X Y | VOICE & DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. X = NUMBER OF VOICE TERMINATIONS , Y = NUMBER OF DATA TERMINATIONS PER LOCATION. |
| | SINGLE VOICE & SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED. |
| X Y | VOICE & DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED, X = NUMBER OF VOICE OUTLETS AND Y = NUMBER OF DATA OUTLETS PER LOCATION AS INDICATED. |
| | POWER/COMMUNICATIONS POLE WITH A SINGLE VOICE OUTLET AND SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| X Y | POWER/COMMUNICATIONS POLE WITH X = NUMBER OF VOICE TERMINATIONS, Y = NUMBER OF DATA TERMINATIONS, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| | SINGLE VOICE OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE-THRU AS SPECIFIED. |
| X Y | VOICE OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE -THRU AS SPECIFIED WITH X = NUMBER OF VOICE TERMINATIONS, Y = NUMBER OF DATA TERMINATIONS PER LOCATION. |

## DATA SYMBOLS

| | |
|---|---|
| | SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| X | DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |
| | SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED. |
| X | DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED, X = NUMBER OF CABLE TERMINATIONS PER LOCATION AS INDICATED. |
| | POWER/COMMUNICATIONS POLE WITH A SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| X | POWER/COMMUNICATIONS POLE WITH X = NUMBER OF DATA OUTLETS, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| | SINGLE DATA OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE-THRU AS SPECIFIED. |
| X | DATA OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE -THRU AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |
| W | SINGLE DATA OUTLET FOR WALL-MOUNTED IP PHONE, CABLE TYPE AS SPECIFIED, MOUNTED +52-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| X | DATA CABLE FOR COMPUTER ON WHEELS, CABLE TYPE AS SPECIFIED MOUNTED + 18-INCHES A.F.F UNLESS OTHERWISE NOTED. X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |
| X | DATA CABLE FOR CEILING MOUNTED WIRELESS ACCESS POINT, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A GREEN ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. |
| X | DATA CABLE FOR CEILING MOUNTED VIDEO SURVEILLANCE CAMERA, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A ORANGE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. REFER TO SECURITY DRAWINGS PRIOR TO INSTALLATION. |
| | DATA CABLE FOR CEILING MOUNTED PROJECTOR, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A BLUE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. REFER TO AUDIO/VISUAL DRAWINGS PRIOR TO INSTALLATION. |
| X | DATA CABLE FOR CEILING MOUNTED AUDIO/VISUAL EQUIPMENT ENCLOSURE, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A BLUE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. REFER TO AUDIO/VISUAL DRAWINGS PRIOR TO INSTALLATION. |
| X | DATA CABLE FOR WALL MOUNTED PROJECTOR, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A BLUE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. REFER TO AUDIO/VISUAL DRAWINGS PRIOR TO INSTALLATION. |

## FIBER OPTIC SYMBOLS

| | |
|---|---|
| | SINGLE FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| X | FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |
| | SINGLE FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED. |
| X | FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED, X = NUMBER OF CABLE TERMINATIONS PER LOCATION AS INDICATED. |
| | POWER/COMMUNICATIONS POLE WITH A SINGLE FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| X | POWER/COMMUNICATIONS POLE WITH X = NUMBER OF FIBER OPTIC OUTLETS, CABLE TYPE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| | SINGLE FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE-THRU AS SPECIFIED. |
| X | FIBER OPTIC OUTLET, CABLE TYPE AS SPECIFIED, TERMINATED IN FLOOR BOX/POKE -THRU AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION. |

## DATA SYMBOLS, CONT.

| | |
|---|---|
| X CAME | DATA CABLE FOR EXTERIOR WALL MOUNTED VIDEO SURVEILLANCE CAMERA, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A ORANGE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW, REFER TO SECURITY DRAWINGS PRIOR TO INSTALLATION. |
| X CAMW | DATA CABLE FOR INTERIOR WALL MOUNTED SURVEILLANCE CAMERA, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A ORANGE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. |
| X CAME | DATA CABLE FOR EXTERIOR WALL MOUNTED SURVEILLANCE CAMERA, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A ORANGE ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. |
| X WAPW | DATA CABLE FOR INTERIOR WALL MOUNTED WIRELESS ACCESS POINT, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A GREEN ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. |
| X WAPE | DATA CABLE FOR EXTERIOR WALL MOUNTED WIRELESS ACCESS POINT, CABLE TYPE AS SPECIFIED WITH X = NUMBER OF CABLE TERMINATIONS PER LOCATION WITH 20-FEET OF SLACK NEATLY COILED AND STORED ON J-HOOK ABOVE ACCESSIBLE CEILING. PLACE A GREEN ADHESIVE DOT AND LABEL MIRRORING THE LABEL ON THE SURFACE MOUNTED BOX ON THE CEILING GRID DIRECTLY BELOW. |

## ROUGH-IN & MISC. SYMBOLS

| | |
|---|---|
| R | ROUGH-IN LOCATION, INFRASTRUCTURE AS SPECIFIED, MOUNTED +18-INCHES A.F.F. UNLESS OTHERWISE NOTED. |
| R | ROUGH-IN LOCATION, INFRASTRUCTURE AS SPECIFIED, MOUNTED +6-INCHES ABOVE COUNTER OR BACKSPLASH UNLESS OTHERWISE NOTED. |
| R | POWER POLE WITH ROUGH-IN LOCATION, INFRASTRUCTURE AS SPECIFIED, MOUNTED AT 18" A.F.F. UNLESS OTHERWISE NOTED. |
| R | ROUGH-IN LOCATION. TERMINATED IN FLOOR BOX/POKE-THRU AS SPECIFIED. |
| WAP | WIRELESS ACCESS POINT. EQUIPMENT AS SPECIFIED. |

## CABLE PLANT & RISER DIAGRAM

| | |
|---|---|
| | MAINTENANCE HOLE, SIZE & TYPE AS SPECIFIED. |
| | PULLBOX, SIZE AND TYPE AS SPECIFIED. |
| UGC | DIRECT BURIED COMMUNICATIONS, CABLE TYPE AS SPECIFIED. |
| AER | AERIAL COMMUNICATIONS, CABLE TYPE AS SPECIFIED. |
| | CONDUIT, SIZE AND TYPE AS SPECIFIED. |

## GENERAL SYMBOLS

| | |
|---|---|
| # SHEET — DRAWING TITLE SCALE: SCALE | DRAWING TITLE CALLOUT, # = DETAIL NUMBER. |
| # SHEET | DETAIL CALLOUT, # = DETAIL NUMBER. |
| # SHEET | SECTION CALLOUT, # = DETAIL NUMBER. |
| SHEET # | ELEVATION CALLOUT, # = DETAIL NUMBER. |
| # | KEYED NOTE, # = KEYED NOTE NUMBER. |
| # | REVISION TRIANGLE, # = REVISION NUMBER (PER SHEET). |
| TR (IDF XXX) | INDICATES TELECOMMUNICATIONS REGION |

## ABBREVIATIONS

| | |
|---|---|
| A.F.F. | ABOVE FINISHED FLOOR |
| A.F.G. | ABOVE FINISHED GRADE |
| AER | AERIAL |
| DEMARC | DEMARCATION POINT |
| EMT | ELECTRIC METALLIC TUBE |
| F.O.C. | FIBER OPTIC CABLE |
| GIP | GALVANIZED IRON PIPE |
| HE | PAINTERCOM HEAD-END |
| IMC | INTERMEDIATE METAL CONDUIT |
| ISP | INSIDE CABLE PLANT |
| IDF | INTERMEDIATE DISTRIBUTION FRAME |
| MDF | MAIN DISTRIBUTION FRAME |
| MH | MAINTENANCE HOLE |
| MM | MULTIMODE |
| OSP | OUTSIDE CABLE PLANT |
| PB | PULLBOX |
| PR | PAIR |
| PVC | POLYVINYL CHLORIDE |
| RSC | RIGID STEEL CONDUIT |
| SM | SINGLE MODE |
| SP | SERVICE PROVIDER |
| STP | SHIELDED TWISTED PAIR |
| TB | TERMINAL BLOCK |
| TR | TELECOMMUNICATION REGION |
| UGC | UNDERGROUND COMMUNICATION |
| UON | UNLESS OTHERWISE NOTED |
| UTP | UNSHIELDED TWISTED PAIR |

## NOTES

1. CONTRACTOR SHALL REVIEW DRAWINGS AND SPECIFICATIONS THAT MAKE UP THE CONTRACT DOCUMENTS AND COMPLETE ALL WORK INCLUDED THEREIN.
2. SCALE OF TECHNOLOGY DRAWINGS IS PROVIDED FOR REFERENCE ONLY. CONTRACTOR SHALL BE RESPONSIBLE FOR PROPER CABLE LENGTHS, SIZE OF PATHWAYS, DIMENSIONS, ETC.
3. TECHNOLOGY DRAWINGS SHALL BE USED TO COMPLEMENT THE WRITTEN SPECIFICATIONS.
4. ANY DISCREPANCY OR CONFLICT WITHIN OR BETWEEN THE DRAWINGS AND SPECIFICATIONS SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT/DESIGN CONSULTANT'S. DISCREPANCIES OR CONFLICTS NOT BROUGHT TO THE ATTENTION OF THE ARCHITECT/DESIGN CONSULTANT AND SUBSEQUENTLY CLARIFIED DURING THE BIDDING OF THE PROJECT WILL BE DEEMED TO HAVE BEEN BID OR PROPOSED IN THE MORE COSTLY OR DIFFICULT MANNER, AND THE BETTER QUALITY OR GREATER QUANTITY OF WORK SHALL BE PROVIDED BY THE CONTRACTOR IN ACCORDANCE WITH THE ARCHITECT'S/DESIGN CONSULTANT'S INTERPRETATION.

## INDEX OF DRAWINGS


| | |
|---|---|
| T000 | TECHNOLOGY SYMBOLS & LEGEND |
| T0201 | TECHNOLOGY DEMOLITION FLOOR PLAN |
| T200 | TECHNOLOGY COMPOSITE FLOOR PLAN |
| T201 | TECHNOLOGY NEW/RENOVATION KITCHEN PLAN |
| T202 | TECHNOLOGY TEMPORARY KITCHEN PLAN |
| T300 | TECHNOLOGY ENLARGED VIEWS |
| T400 | TECHNOLOGY TYPICAL DETAILS |
| T401 | TECHNOLOGY TYPICAL DETAILS |
| T500 | TECHNOLOGY TYPICAL DETAILS |


ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILL ELEMENTARY SCHOOL
3707 JESS PIRTLE BLVD.
SUGAR LAND, TX 77498

SEAL

FOR
INTERIM REVIEW
AND NOT INTENDED
FOR CONSTRUCTION,
BIDDING OR PERMIT
PURPOSES.


ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 05/16/25

TECHNOLOGY SYMBOLS & LEGEND

SHEET NO.
T000

ISSUE:
12/05/2024 DD PACKAGE
03/11/2025 50% CD PKG.
05/16/2025 90% CD PKG.

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILL ELEMENTARY SCHOOL
3707 JESS PIRTLE BLVD.
SUGAR LAND, TX 77498


SEAL

FOR
INTERIM REVIEW
NOT INTENDED FOR CONSTRUCTION, BIDDING OR PERMIT PURPOSES.



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 05/16/25

TECHNOLOGY COMPOSITE FLOOR PLAN
SHEET NO.
T200




1 T200 TECHNOLOGY COMPOSITE FLOOR PLAN
1/16" = 1'-0"




1 / T201 TECHNOLOGY NEW/RENOVATION KITCHEN PLAN
1/4" = 1'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |

**TECHNOLOGY FLOOR PLANS GENERAL NOTES:**

1. THE TECHNOLOGY REGION / WIRING BOUNDARIES ARE IDENTIFIED ON THE OVERALL SHEETS ONLY AND NOT ON THE ENLARGED SHEETS. CONTRACTOR SHALL REFER TO THE OVERALL SHEETS FOR ALL TECHNOLOGY REGIONS / WIRING BOUNDARIES.
2. ALL CONDUIT PATHWAYS, ROUGH-INS, BACKBOXES, FLOOR BOXES, CONDUIT SLEEVES, ETC. INDICATED ON THE TECHNOLOGY DRAWINGS ARE TO BE PROVIDED AND INSTALLED BY DIVISION 26.
3. ALL POWER INDICATED ON THE TECHNOLOGY DRAWINGS IS TO BE PROVIDED AND INSTALLED BY DIVISION 26.
4. CONTRACTOR SHALL RESTORE ALL PENETRATIONS PROVIDED THROUGH FIRE RATED WALLS/STRUCTURES FOR TECHNOLOGY CABLING BACK TO THE ORIGINAL RATING.
5. CONTRACTOR SHALL RESTORE ALL PENETRATIONS PROVIDED THROUGH NON-RATED WALLS/STRUCTURES FOR TECHNOLOGY CABLING FOR SOUND TO REDUCE NOISE TRAVELING THROUGH PENETRATIONS.
6. TECHNOLOGY CABLING SHALL BE ROUTED IN SEPARATE PATHWAYS IN J-HOOKS, CONDUITS, CONDUIT SLEEVES, CORES, ETC. THROUGHOUT THE ENTIRE PATHWAY. DIFFERENT MEDIA TYPES (DATA, VIDEO, SECURITY, ETC.) SHALL NOT SHARE THE SAME J-HOOK, CONDUIT, CONDUIT SLEEVE, CORE, ETC.
7. UNLESS NOTED OTHERWISE, ALL CONDUITS FOR TECHNOLOGY DEVICES SHALL ROUTE FROM THE DEVICE LOCATION AND TERMINATE ABOVE AN ACCESSIBLE CEILING (AN OPEN CEILING OR CLOUD TYPE CEILING IS NOT CONSIDERED AN ACCESSIBLE CEILING) IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF A MAIN CORRIDOR OR NEAREST MDF/IDF. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF / IDF ROOM TO MINIMIZE THE CABLE LENGTH ENSURING CABLE LENGTH DOES NOT EXCEED 275 FEET.
8. UNLESS NOTED OTHERWISE ALL CONDUITS SHALL BE HOMERUN FROM THE DEVICE LOCATION AND NO DAISY CHAINING OF DEVICES / ROUGH-INS SHALL BE ALLOWED.
9. CONDUIT SEGMENTS SHALL BE NO MORE THAN 100-FEET IN LENGTH WITH NO MORE THAN THE EQUIVALENT OF (2) 90 DEGREE BENDS BETWEEN PULLING POINTS.
10. CONDUITS SHALL MAINTAIN A BEND RADIUS OF 6 TIMES THE DIAMETER OF THE CONDUIT FOR CONDUITS 2-INCHES OR SMALLER AND 10 TIMES THE DIAMETER OF THE CONDUIT FOR CONDUITS GREATER THAN 2-INCHES.
11. ALL CONDUITS SHALL HAVE A PULL STRING INSTALLED FOR PULLING OF CABLE. CLEARLY LABEL AS "PULL STRING" INDICATING OPPOSITE END LOCATION.
12. ALL SPARE CONDUITS OR CONDUITS FILLED WITH LESS THAN THE MAXIMUM ALLOWED FILL RATIO SHALL HAVE A PULL STRING INSTALLED AND LEFT FOR FUTURE PULLING OF CABLE. CLEARLY LABEL AS "PULL STRING" INDICATING OPPOSITE END LOCATION.
13. EQUIPMENT NOT RELATED TO THE SUPPORT OF THE TELECOMMUNICATIONS ROOM (E.G., PIPING, DUCTWORK, PNEUMATIC TUBING) SHALL NOT BE INSTALLED IN, PASS THROUGH, OR ENTER THE TELECOMMUNICATIONS ROOM.
14. ALL CONDUITS FOR TECHNOLOGY DEVICES SHALL ROUTE FROM THE DEVICE LOCATION AND TERMINATE ABOVE AN ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE IN TYPE CEILING TO PREVENT THE CABLES FROM BEING EXPOSED, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE IN TYPE CEILING OFF A MAIN CORRIDOR OR NEAREST MDF/IDF. THE CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE MAIN CORRIDOR OR NEAREST MDF/IDF TO MINIMIZE THE CABLE LENGTH ENSURING THE CABLE LENGTH DOES NOT EXCEED 275 FEET. CONDUIT, CONNECTIONS, J-BOXES, SUSPENSION, AND ANY OTHER CONDUIT COMPONENTS EXPOSED TO VIEW IN PUBLIC SPACES SHALL BE ROUTED AND INSTALLED CAREFULLY TO MINIMIZE VISUAL IMPACT AND SHALL BE FULLY PAINTED TO MATCH UNLESS NOTED OTHERWISE.
15. CONDUIT(S) INSTALLED IN-SLAB OR UNDER-SLAB TO FLOOR BOXES, POKE-THURS, AND TO WORKAREA OUTLETS, ETC. SHALL BE INSTALLED WITH WET RATED CABLE(S).
16. NO GRID WIRE SHALL BE UTILIZED FOR SUPPORT. ONLY USE SOLID SUPPORTS (CLIPS, ALL-THREAD, ANCHORS, ETC.).

## TECHNOLOGY PLAN KEYED NOTES

NOT ALL KEYED BELOW APPLY TO THIS SHEET

1. DATA CABLE FOR OWNER FURNISHED / OWNER INSTALLED MENU BOARD. REFERENCE ARCHITECTURAL AND FOOD SERVICE DRAWINGS FOR MOUNTING HEIGHT AND ADDITIONAL INFORMATION. BUILDING POWER ADJACENT TO DATA RECEPTACLE IS REQUIRED.1.DATA CABLE FOR OWNER FURNISHED / OWNER INSTALLED MENU BOARD. REFERENCE ARCHITECTURAL AND FOOD SERVICE DRAWINGS FOR MOUNTING HEIGHT AND ADDITIONAL INFORMATION. BUILDING POWER ADJACENT TO DATA RECEPTACLE IS REQUIRED.
2. INDOOR / OUTDOOR RATED DATA CABLE FOR POINT OF SALE LOCATION. PROVIDE (1) 1-INCH CONDUIT FOR DATA TO THE WALL BEHIND POINT OF SALE LOCATION AND UP WALL TO ABOVE ACCESSIBLE CEILING. CONDUITS SHALL TERMINATE INSIDE A DOUBLE GANG BOX THAT IS SECURED TO THE POINT OF SALE LOCATION. REFER TO FOOD SERVICE / KITCHEN DRAWINGS FOR EXACT LOCATION AND CONDUIT ROUGH-IN REQUIREMENTS.
3. DATA CABLE FOR TEMPERATURE MONITORING OF FREEZER COOLER. REFER TO FOOD SERVICE / KITCHEN DRAWINGS FOR EXACT LOCATION AND CONDUIT ROUGH-IN REQUIREMENTS AND TERMINATION POINT AND CONNECTIVITY NEEDS IN FREEZER / COOLER CONTROL UNIT.
4. DATA CABLE FOR TEMPORARY POINT OF SALES CASH REGISTER. COORDINATE WITH OWNER, ARCHITECT, AND CONSULTANT FOR ROUTING OF CABLES TO POINT OF SALE CASH REGISTER PRIOR TO INSTALLATION

FBISD 2024 - 33 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILL ELEMENTARY SCHOOL
3707 JESS PIRTLE BLVD.
SUGAR LAND, TX 77498


EVIEW
NDED
CTION,
ERMIT
S.

ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 05/16/25

TECHNOLOGY
NEW/RENOVATION KITCHEN
PLAN

SHEET NO.
T201




1 T202 TECHNOLOGY TEMPORARY KITCHEN FLOOR PLAN
1/4" = 1'-0"

**TECHNOLOGY FLOOR PLANS GENERAL NOTES:**

1. THE TECHNOLOGY REGION / WIRING BOUNDARIES ARE IDENTIFIED ON THE OVERALL SHEETS ONLY AND NOT ON THE ENLARGED SHEETS. CONTRACTOR SHALL REFER TO THE OVERALL SHEETS FOR ALL TECHNOLOGY REGIONS / WIRING BOUNDARIES.
2. ALL CONDUIT PATHWAYS, ROUGH-INS, BACKBOXES, FLOOR BOXES, CONDUIT SLEEVES, ETC. INDICATED ON THE TECHNOLOGY DRAWINGS ARE TO BE PROVIDED AND INSTALLED BY DIVISION 26.
3. ALL POWER INDICATED ON THE TECHNOLOGY DRAWINGS IS TO BE PROVIDED AND INSTALLED BY DIVISION 26.
4. CONTRACTOR SHALL RESTORE ALL PENETRATIONS PROVIDED THROUGH FIRE RATED WALLS/STRUCTURES FOR TECHNOLOGY CABLING BACK TO THE ORIGINAL RATING.
5. CONTRACTOR SHALL RESTORE ALL PENETRATIONS PROVIDED THROUGH NON-RATED WALLS/STRUCTURES FOR TECHNOLOGY CABLING FOR SOUND TO REDUCE NOISE TRAVELING THROUGH PENETRATIONS.
6. TECHNOLOGY CABLING SHALL BE ROUTED IN SEPARATE PATHWAYS IN J-HOOKS, CONDUITS, CONDUIT SLEEVES, CORES, ETC. THROUGHOUT THE ENTIRE PATHWAY. DIFFERENT MEDIA TYPES (DATA, VIDEO, SECURITY, ETC.) SHALL NOT SHARE THE SAME J-HOOK, CONDUIT, CONDUIT SLEEVE, CORE, ETC.
7. UNLESS NOTED OTHERWISE, ALL CONDUITS FOR TECHNOLOGY DEVICES SHALL ROUTE FROM THE DEVICE LOCATION AND TERMINATE ABOVE AN ACCESSIBLE CEILING (AN OPEN CEILING OR CLOUD TYPE CEILING IS NOT CONSIDERED AN ACCESSIBLE CEILING) IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF A MAIN CORRIDOR OR NEAREST MDF/IDF. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF / IDF ROOM TO MINIMIZE THE CABLE LENGTH ENSURING CABLE LENGTH DOES NOT EXCEED 275 FEET.
8. UNLESS NOTED OTHERWISE ALL CONDUITS SHALL BE HOMERUN FROM THE DEVICE LOCATION AND NO DAISY CHAINING OF DEVICES / ROUGH-INS SHALL BE ALLOWED.
9. CONDUIT SEGMENTS SHALL BE NO MORE THAN 100-FEET IN LENGTH WITH NO MORE THAN THE EQUIVALENT OF (2) 90 DEGREE BENDS BETWEEN PULLING POINTS.
10. CONDUITS SHALL MAINTAIN A BEND RADIUS OF 6 TIMES THE DIAMETER OF THE CONDUIT FOR CONDUITS 2-INCHES OR SMALLER AND 10 TIMES THE DIAMETER OF THE CONDUIT FOR CONDUITS GREATER THAN 2-INCHES.
11. ALL CONDUITS SHALL HAVE A PULL STRING INSTALLED FOR PULLING OF CABLE. CLEARLY LABEL AS "PULL STRING" INDICATING OPPOSITE END LOCATION.
12. ALL SPARE CONDUITS OR CONDUITS FILLED WITH LESS THAN THE MAXIMUM ALLOWED FILL RATIO SHALL HAVE A PULL STRING INSTALLED AND LEFT FOR FUTURE PULLING OF CABLE. CLEARLY LABEL AS "PULL STRING" INDICATING OPPOSITE END LOCATION.
13. EQUIPMENT NOT RELATED TO THE SUPPORT OF THE TELECOMMUNICATIONS ROOM (E.G., PIPING, DUCTWORK, PNEUMATIC TUBING) SHALL NOT BE INSTALLED IN, PASS THROUGH, OR ENTER THE TELECOMMUNICATIONS ROOM.
14. ALL CONDUITS FOR TECHNOLOGY DEVICES SHALL ROUTE FROM THE DEVICE LOCATION AND TERMINATE ABOVE A LAY- IN TYPE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE A LAY-IN TYPE CEILING TO PREVENT THE CABLES FROM BEING EXPOSED, THE CONDUIT SHALL ROUTE TO THE NEAREST LAY-IN TYPE CEILING OFF A MAIN CORRIDOR OR NEAREST MDF/IDF. THE CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE MAIN CORRIDOR OR NEAREST MDF/IDF TO MINIMIZE THE CABLE LENGTH ENSURING THE CABLE LENGTH DOES NOT EXCEED 275 FEET. CONDUIT, CONNECTIONS, J-BOXES, SUSPENSION, ANCHORAGES, AND OTHER CONDUIT COMPONENTS EXPOSED TO VIEW IN PUBLIC SPACES SHALL BE ROUTED AND INSTALLED CAREFULLY TO MINIMIZE VISUAL IMPACT AND SHALL BE FULLY PAINTED TO MATCH UNLESS NOTED OTHERWISE.
15. CONDUIT(S) INSTALLED IN-SLAB OR UNDER-SLAB TO FLOOR BOXES, POKE-THURS, AND TO WORKAREA OUTLETS, ETC. SHALL BE INSTALLED WITH WET RATED CABLE(S).
16. NO GRID WIRE SHALL BE UTILIZED FOR SUPPORTS ONLY USE SOLID SUPPORTS (CLIPS, ALL-THREAD, ANCHORS, ETC.).

**TECHNOLOGY PLAN KEYED NOTES**

NOT ALL KEYED BELOW APPLY TO THIS SHEET

(1) DATA CABLE FOR OWNER FURNISHED / OWNER INSTALLED MENU BOARD. REFERENCE ARCHITECTURAL AND FOOD SERVICE DRAWINGS FOR MOUNTING HEIGHT AND ADDITIONAL INFORMATION. BUILDING POWER ADJACENT TO DATA RECEPTACLE IS REQUIRED.1.DATA CABLE FOR OWNER FURNISHED / OWNER INSTALLED MENU BOARD. REFERENCE ARCHITECTURAL AND FOOD SERVICE DRAWINGS FOR MOUNTING HEIGHT AND ADDITIONAL INFORMATION. BUILDING POWER ADJACENT TO DATA RECEPTACLE IS REQUIRED.

(2) INDOOR / OUTDOOR RATED DATA CABLE FOR POINT OF SALE LOCATION. PROVIDE (1) 1-INCH CONDUIT FOR DATA TO THE WALL BEHIND POINT OF SALE LOCATION AND UP WALL TO ABOVE ACCESSIBLE CEILING. CONDUITS SHALL TERMINATE INSIDE A DOUBLE GANG BOX THAT IS SECURED TO THE POINT OF SALE LOCATION. REFER TO FOOD SERVICE / KITCHEN DRAWINGS FOR EXACT LOCATION AND CONDUIT ROUGH-IN REQUIREMENTS.

(3) DATA CABLE FOR TEMPERATURE MONITORING OF FREEZER COOLER. REFER TO FOOD SERVICE / KITCHEN DRAWINGS FOR EXACT LOCATION AND CONDUIT ROUGH-IN REQUIREMENTS AND TERMINATION POINT AND CONNECTIVITY NEEDS IN FREEZER / COOLER CONTROL UNIT.

(4) DATA CABLE FOR TEMPORARY POINT OF SALES CASH REGISTER. COORDINATE WITH OWNER, ARCHITECT, AND CONSULTANT FOR ROUTING OF CABLES TO POINT OF SALE CASH REGISTER PRIOR TO INSTALLATION

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILL ELEMENTARY SCHOOL
3707 JESS PIRTLE BLVD.
SUGAR LAND, TX 77498

SEAL


FOR
INTERIM REVIEW
AND NOT INTENDED FOR CONSTRUCTION, BIDDING OR PERMIT PURPOSES.

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 05/16/25

TECHNOLOGY TEMPORARY KITCHEN PLAN

SHEET NO.
T202




1 / T300 SUGAR MILL ES EXISTING IDF RACK
NTS

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILL ELEMENTARY SCHOOL
3707 JESS PIRTLE BLVD.
SUGAR LAND, TX 77498

SEAL

FOR
INTERIM REVIEW
AND NOT INTENDED
FOR CONSTRUCTION,
BIDDING OR PERMIT
PURPOSES.

ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 05/16/25


TECHNOLOGY ENLARGED VIEWS

SHEET NO.
T300

NOTE TO CONTRACTOR:

UNLESS OTHERWISE NOTED, LOW VOLTAGE CABLING SHALL BE INSTALLED WITHIN 6-INCHES OF THE CEILING AND ACCESSIBLE BY A TECHNICIAN ON A STANDARD A-FRAME LADDER.

CONTRACTOR SHALL MAINTAIN AT LEAST 6-INCHES OF SEPRATION BETWEEN CABLING BUNDLES AND MECHANICAL DUCTWORKS, EQUIPMENT, PIPIING OR OTHER SYSTEMS IN THE CEILING PLENUM.





KEYED NOTES:

1. J-HOOK WITH RETAINER CLIP ABOVE ACCESSIBLE CEILING (BY DIV 27).
2. DATA CABLE ABOVE ACCESSIBLE CEILING (BY DIV 27).
3. A/V CABLE ABOVE ACCESSIBLE CEILING (BY DIV 27).
4. SECURITY CABLE ABOVE ACCESSIBLE CEILING (BY DIV 28).
5. SPARE J-HOOK (BY DIV 27).

## 1 T400 TYPICAL J-HOOK CABLE PATHWAY

SCALE: N.T.S.





KEYED NOTES:

1. SCHEDULED FLOOR OR DECK.
2. CONDUIT SLEEVE (BY DIV 26).
3. NYLON BUSHING (BY DIV 26).

## 2 T400 TYPICAL CONDUIT SLEEVE THROUGH FLOOR OR DECK DETAIL

SCALE: N.T.S.





KEYED NOTES:

1. SCHEDULED WALL.
2. SCHEDULED CEILING.
3. CONDUIT SLEEVE (BY DIV 26).
4. NYLON BUSHING (BY DIV 26).

## 3 T400 TYPICAL CONDUIT SLEEVE GOING THROUGH WALL

SCALE: N.T.S.





KEYED NOTES:

1. SCHEDULED WALL.
2. SCHEDULED CEILING.
3. SCHEDULED DECK ABOVE.
4. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX WITH DOUBLE GANG PLASTER RING (BY DIV 26).
5. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH. (BY DIV 26).

## 4 T400 TYPICAL TECHNOLOGY CONDUIT ROUGH-IN

SCALE: N.T.S.





KEYED NOTES:

1. SCHEDULED STUD.
2. SCHEDULED WALL.
3. J-HOOK WITH RETAINER CLIP ABOVE ACCESSIBLE CEILING (BY DIV 27).
4. DATA CABLE ABOVE ACCESSIBLE CEILING (BY DIV 27).
5. 20 FOOT SERVICE LOOP ABOVE ACCESSIBLE CEILING NEATLY COILED AND SECURED TO J-HOOK (BY DIV 27).
6. SURFACE MOUNT BOX ABOVE ACCESSIBLE CEILING SECURED TO BUILDING STRUCTURE (BY DIV 27).
7. DATA INSERT (BY DIV 27).

## 5 T400 TYPICAL ABOVE CEILING SINGLE DATA OUTLET (WALL MOUNTED)

SCALE: N.T.S.





KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH PHONE STUDS (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. CABLE AS SPECIFIED (BY DIV 27).

## 6 T400 TYPICAL WALL PHONE OUTLET CONFIGURATION

SCALE: N.T.S.





KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH DESIGNATION IN WINDOW (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. CABLE AS SPECIFIED (BY DIV 27).
7. ELECTRICAL RECEPTACLE, GANG BOX AND CONDUIT SHOWN FOR REFERENCE ONLY (REFER TO DIV 26).

## 7 T400 TYPICAL DUAL DATA OUTLET CONFIGURATION

SCALE: N.T.S.





KEYED NOTES:

1. 4 11/16-INCH X 4 11/16-INCH X 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. DOUBLE GANG PLASTER RING (BY DIV 26).
4. SURFACE MOUNT BOX INSIDE THE 4 11/16-INCH X 4 11/16-INCH X 2 1/8-INCH DOUBLE GANG BOX (BY DIV 27).
5. RJ-45 INSERT (BY DIV 27).

## 8 T400 TYPICAL WALL-MOUNTED WIRELESS ACCESS POINT

SCALE: N.T.S.




KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH DESIGNATION IN WINDOW (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. BLANK INSERT (BY DIV 27).
7. CABLE AS SPECIFIED (BY DIV 27).
8. ELECTRICAL RECEPTACLE, GANG BOX AND CONDUIT SHOWN FOR REFERENCE ONLY (REFER TO DIV 26).

## 9 T400 TYPICAL THREE DATA OUTLET CONFIGURATION

SCALE: N.T.S.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILL ELEMENTARY SCHOOL
3707 JESS PIRTLE BLVD.
SUGAR LAND, TX 77498

SEAL


FOR
INTERIM REVIEW
AND NOT INTENDED FOR CONSTRUCTION, BIDDING OR PERMIT PURPOSES.


ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 05/16/25

TECHNOLOGY TYPICAL DETAILS

SHEET NO.
T400





KEYED NOTES:

1. ALL THREAD TO BUILDING STRUCTURE (BY DIV. 27)
2. SCHEDULING CEILING
3. IN-PLENUM CEILING BRACKET PN 49223-CBC ATTACHED TO ALL THREAD (BY DIV. 27)
4. SURFACE MOUNT BOX ABOVE ACCESSIBLE CEILING SECURED TO BRACKET (BY DIV. 27)
5. DATA CABLE (BY DIV. 27)
6. DATA INSERT (BY DIV. 27)

## 1 T401 TYPICAL ABOVE CEILING DATA OUTLET

SCALE: N.T.S.





KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH DESIGNATION IN WINDOW (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. CABLE AS SPECIFIED (BY DIV 27).
7. ELECTRICAL RECEPTACLE, GANG BOX AND CONDUIT SHOWN FOR REFERENCE ONLY (REFER TO DIV 26).

## 2 T401 TYPICAL COW DATA OUTLET CONFIGURATION

SCALE: N.T.S.





KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH DESIGNATION IN WINDOW (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. BLANK INSERT (BY DIV 27).
7. CABLE AS SPECIFIED (BY DIV 27).
8. ELECTRICAL RECEPTACLE, GANG BOX AND CONDUIT SHOWN FOR REFERENCE ONLY (REFER TO DIV 26).

## 3 T401 TYPICAL THREE DATA OUTLET CONFIGURATION

SCALE: N.T.S.




KEYED NOTES:

1. 4 11/16-INCH x 4 11/16-INCH x 2 1/8-INCH RECESSED DOUBLE GANG BOX (BY DIV 26).
2. 1-INCH EMT CONDUIT FROM DOUBLE GANG BOX WITH 200 LBS PULL STRING AND NYLON BUSHING STUBBED OUT ABOVE ACCESSIBLE CEILING IN THE SAME ROOM WHERE THE DEVICE IS LOCATED. IF THE ROOM WHERE THE DEVICE IS LOCATED DOES NOT HAVE AN ACCESSIBLE CEILING, THE CONDUIT SHALL ROUTE TO THE NEAREST ACCESSIBLE CEILING OFF OF A MAIN CORRIDOR. CONDUIT PATHWAY SHALL TAKE THE SHORTEST ROUTE TO THE APPLICABLE MDF/IDF ROOM TO MINIMIZE THE CABLE LENGTH (BY DIV 26).
3. SINGLE GANG REDUCER RING (BY DIV 26).
4. SINGLE GANG WALL PLATE WITH DESIGNATION IN WINDOW (BY DIV 27).
5. DATA INSERT (BY DIV 27).
6. CABLE AS SPECIFIED (BY DIV 27).
7. ELECTRICAL RECEPTACLE, GANG BOX AND CONDUIT SHOWN FOR REFERENCE ONLY (REFER TO DIV 26).

## 4 T401 TYPICAL FOUR DATA OUTLET CONFIGURATION


SCALE: N.T.S.

| TBB/GE CONDUCTOR SIZING | |
|---|---|
| LENGTH IN LINEAR M (FT) | SIZE (AWG) |
| LESS THAN 4 (13) | 6 |
| 4 - 6 (14-20) | 4 |
| 6 - 8 (21 - 26) | 3 |
| 8 - 10 (27 - 33) | 2 |
| 10 - 13 (34 - 41) | 1 |
| 13 - 16 (42 - 52) | 1/0 |
| 16 - 20 (53 - 66) | 2/0 |
| 20 - 26 (67 - 84) | 3/0 |
| 26 - 32 (85 - 105) | 4/0 |
| 32 - 38 (106 - 125) | 250 kcmil |
| 38 - 46 (126 - 150) | 300 kcmil |
| 46 - 53 (151 - 175) | 350 kcmil |
| 53 - 76 (176 - 250) | 500 kcmil |
| 76 - 91 (251 - 300) | 600 kcmil |
| GREATER THAN 91 (301) | 750 kcmil |

ROUTE THE TBB TO EACH TGB IN AS STRAIGHT A PATH AS POSSIBLE. THE TBB SHOULD BE INSTALLED AS A CONTINUOUS CONDUCTOR, AVOIDING SPLICES WHERE POSSIBLE.

## 5 T401 TBB CONDUCTOR SIZING

SCALE: N.T.S.





1. TELECOMMUNICATIONS MAIN GROUNDING BUS BAR (PBB)(BY DIV. 27)
2. TELECOMMUNICATIONS GROUNDING BUS BAR (SBB)(BY DIV 27)
3. TELECOMMUNICATIONS BONDING CONDUCTOR (TBC). REFER TO CONDUCTOR SIZING CHART FOR EXACT SIZE REQUIREMENTS (BY DIV 27)
4. CONNECT TO GROUNDED BUILDING STEEL WHEN EXPOSED IN ROOM.
5. TELECOMMUNICATIONS BONDING BACKBONE (TBB). REFER TO CONDUCTOR SIZING CHART FOR EXACT SIZE REQUIREMENTS (BY DIV 26)
6. TELECOMMUNICATIONS BONDING CONDUCTOR (TBC). BY ELECTRICAL CONTRACTOR.REFER TO CONDUCTOR SIZING CHART FOR EXACT SIZE REQUIREMENTS.
7. GROUNDING EQUALIZER CONDUCTOR (GEC)(BY DIV 26)
8. BOUND WITH GROUDING COLLARS TO EACH CONTINUOUS CONDUIT THAT ENTERS THE TELECOM ROOM. (BY DIV 26).
9. BOND TO EACH ACCESS CONTROL PANEL AND OTHER SECURITY PANELS IN HE TELECOM ROOM. (BY DIV 27)

## 6 T401 TYPICAL GROUNDING DIAGRAM

SCALE: N.T.S.

System No. W-L-3218
F Ratings - 1, 2, 3 and 4 Hr (See Items 1 and 3)
T Ratings - 3/4 and 1 Hr (See Item 3)
L Rating At Ambient - Less Than 1, 1.3, 4 or 7 CFM (See Item 3)
L Rating At 400 F - Less Than 1, 2 or 3 CFM (See Item 3)




**Section A-A**

1. Wall Assembly - The 1, 2, 3 or 4 hr fire-rated gypsum board/stud wall assembly shall be constructed of the materials and in the manner described within the individual U300, U400 or V400 Series Wall and Partition Designs in the UL Fire Resistance Directory and shall incorporate the following construction features:
   A. Studs - Wall framing shall consist of either wood studs or steel channel studs. Wood studs to consist of nom 2 by 4 in. (51 by 102 mm) lumber spaced max 16 in. (406 mm) OC. Steel studs to be min 3-1/2 in. (89 mm) wide and spaced max 24 in. (610 mm) OC.
   B. Gypsum Board* - Thickness, type, number of layers and fasteners as specified in the individual Wall and Partition Design. Opening in gypsum board to be max 1/4 in. (6 mm) larger then width and height dimensions of firestop device(s).

   The hourly F Rating of the firestop system is dependent upon the hourly rating of the wall in which it is installed.
2. Firestop Device* - One, two, three, four or seven firestop device modules ganged together. Each firestop device module consists of a 3 by 3 by 10-1/2 in. (76 by 76 by 267 mm) long galv steel tube with an intumescent material lining. Firestop device modules to be installed in accordance with the accompanying installation instructions. The space between the firestop device module(s) and the periphery of the opening shall be min 0 in. ( 0 mm, point contact) to max 1/8 in. (3.2 mm). In round openings, the space between the firestop device and the periphery of the opening shall be min 0 in. (point contact) to max 1/2 in. (13 mm). Firestop device module(s) secured in place by means of steel wall plates installed with gasketing material supplied with product. Steel wall plates installed on both sides of wall and secured to each device by means of steel set screws provided with device. Each four- and seven-gang steel wall plate shall be fastened to the studs with steel screws sized to extend through the gypsum board layers and penetrate 1/2 in. (13 mm) into the framing member. Each firestop device module is to be installed with ends projecting an equal distance beyond each surface of the wall assembly.

   As an alternate, the four- and seven-gang steel wall plates may be installed directly against the studs for walls having 16 and 24 in. (406 and 610 mm) center-to-center stud spacing, respectively, prior to installation of the gypsum board layers. The steel wall plates shall be secured to the stud by means of steel screws. After installation of the steel wall plates and firestop device modules, the gypsum board shall be installed as specified in the individual U300 or U400 Design with a maximum 1/8 in. (3.2 mm) gap between the firestop device module and the cutout in the gypsum board. Gap between the firestop device module and the cutout in the gypsum board may be filled with gypsum joint compound or fill material (Item 4).

   SPECIFIED TECHNOLOGIES INC - EZ PATH Series 33 Fire Rated Pathway

2A. Firestop Device* - Extension Module - (Optional, Not Shown) - Module attached to ends of 3 by 3 by 10-1/2 in. (76 by 76 by 267 mm) long firestop device (Item 3) to increase its length to facilitate installation in thicker walls. Each module consists of a 3 by 3 by 6 in. (76 by 76 by 152 mm) long galv steel tube with an intumescent material lining. Extension module to be installed in accordance with the accompanying installation instructions. When module is used, firestop device (Item 2) and extension module(s) secured in place by means of steel wall plates installed with gasketing material supplied with product. Steel wall plates installed on both sides of wall and secured to each device or extension module(s) by means of steel set screws provided with wall plates. Firestop device and extension module(s) assembly to be installed with ends projecting an equal distance beyond each surface of the wall assembly.

   SPECIFIED TECHNOLOGIES INC - EZ PATH Extension

3. Cables - Within the loading area for each firestop device module, the cables may represent a 0 to 100 percent visual fill. Cable fill to be distributed at a uniform height across the width of the firestop device module. Cables to be rigidly supported on both sides of the wall assembly. Any combination of the following types of cables may be used:
   A. Max 400 pair No. 24 AWG (or smaller) copper conductor telecommunication cable with polyvinyl chloride (PVC) jacketing and insulation.
   B. Max 350 kcmil single copper conductor power cable with XLPE jacket and insulation
   C. Max 7/C No. 12 AWG copper conductor control cable with PVC or XLPE jacket and insulation.
   D. Max 3/C No. 10 AWG metal clad or armored cable with steel or aluminum jacket.
   E. Max 3/C No. 8 AWG NM cable (Romex) with PVC insulation and jacket.
   F. Max four pair No. 22 AWG (or smaller) copper conductor data cable with PVC or plenum rated jacketing and insulation.
   G. Max RG/U coaxial cable with fluorinated ethylene insulation and jacketing.
   H. Fiber optic cable with PVC or polyethylene (PE) jacket and insulation having a max diam of 5/8 in. (16 mm).
   I. Optical Fiber Raceway+ - Max 1-1/2 in. (38 mm) diam (or smaller) optical fiber raceway ("innerduct") formed of either PVC or polyvinylidene fluoride (PVDF) with optical fiber cable fill. Raceways installed in accordance with the National Electrical Code (NFPA 70).

   When the hourly rating of the wall assembly is 1 hr, the T Rating is 3/4 hr. When the hourly fire rating of the wall assembly is greater than 1 hr, the T Rating is 3/4 hr when Item 3A, 3B, 3C, 3D or 3E is used. Otherwise the T Rating is 1 hr. When Item 3A, 3B, 3C, 3D or 3E is used, the maximum F Rating is 2 hr. When max 200 pair No. 24 AWG telecommunication cable is used or when Item 3F, 3G, 3H or 3I is used, the maximum F Rating is 4 hr.

   The L Rating for each empty firestop device module is less than 1 cfm at ambient and at 400F. When Item 3A is used, the L Rating for each firestop device module with 100 percent visual fill is 4 cfm at ambient and 3 cfm at 400F. When Item 3F is used, the L Rating for each firestop device module with 100 percent visual fill is 1.3 cfm at ambient and 1 cfm at 400F. When Item 3G or 3H is used, the L Rating for each firestop device module with 100 percent visual fill is 7 cfm at ambient and 2 cfm at 400F.
4. Fill, Void or Cavity Material* - Sealant or Putty - (Not Shown) - As an alternate to gypsum joint compound, the gap between the firestop device module and the cutout in the gypsum board may be sealed with fill material on each side of the wall assembly when four- and seven-gang steel wall plates are installed directly against the wood or steel studs.

   SPECIFIED TECHNOLOGIES INC - SpecSeal Series SSS Sealant, SpecSeal LCI Sealant, SpecSeal Putty

   *Bearing the UL Classification Mark

## 7 T401 TYPICAL STI EZ-PATH SLEEVE DETAIL

SCALE: N.T.S.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILL ELEMENTARY SCHOOL
3707 JESS PIRTLE BLVD.
SUGAR LAND, TX 77498

SEAL


FOR
INTERIM REVIEW
AND NOT INTENDED FOR CONSTRUCTION, BIDDING OR PERMIT PURPOSES.



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 05/16/25

TECHNOLOGY TYPICAL DETAILS

SHEET NO.
T401









1 T500 TYPICAL HORIZONTAL DATA CABLE LABELING SCHEME


SCALE: N.T.S.





2 T500 TYPICAL FIBER BACKBONE LABELING SCHEME

SCALE: N.T.S.




3 T500 TYPICAL COPPER BACKBONE LABELING SCHEME

SCALE: N.T.S.




4 T500 ABOVE ASSESSIBLE CEILING LABELING SCHEME

SCALE: N.T.S.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/16/2025 | 90% CD PKG. |

FBISD PKG 13 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SUGAR MILL ELEMENTARY SCHOOL
3707 JESS PIRTLE BLVD.
SUGAR LAND, TX 77498

SEAL

FOR
INTERIM REVIEW
AND NOT INTENDED
FOR CONSTRUCTION,
BIDDING OR PERMIT
PURPOSES.

MWA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 05/16/25

TECHNOLOGY TYPICAL
DETAILS

SHEET NO.
T500

## AUDIO/VISUAL MULTIMEDIA LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| A## V## | WALL AV ROUGH-IN DETAIL |
| A## V## | CEILING AV ROUGH-IN DETAIL |
| A## V## | FLOOR AV ROUGH-IN DETAIL |
| IWB IWB | INTERACTIVE WHITE BOARD - WALL - CEILING |
| PJ PJ | MULTIMEDIA PROJECTOR |
| FP# FP# | MULTIMEDIA FLAT PANEL DISPLAY |
| S S | LOUDSPEAKER, WALL MOUNTED AND CEILING MOUNTED RESPECTIVELY - # INDICATES TYPE |
| CP# | CONTROL PANEL |
| TP# | TOUCH PANEL |
| M | MICROPHONE, CEILING MOUNTED - # INDICATES TYPE |
| VC | VOLUME CONTROL |
| WB | WALL BOX ENCLOSURE |
| D1 A1 | D1 = DIGITAL SINGLE SIDED CLOCK / A1 = ANALOG SINGLE SIDED CLOCK |
| D2 A2 | D2 = DIGITAL DOUBLE SIDED CLOCK / A2 = ANALOG DOUBLE SIDED CLOCK |
| ENC | CEILING AV ENCLOSURE |
| C C | PRESENTATION CAMERA - CEILING - WALL MOUNTED |

## PREMISE SECURITY LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| CR | CARD READER |
| CR M | CARD READER MULLION |
| KP | INTRUSION DETECTION KEYPAD |
| IC | INTERCOM (1 DATA CABLE) |
| IC MS | INTERCOM MASTER STATION (1 DATA CABLE) |
| PB | PANIC/DURESS BUTTON |
| LD | LOCK DOWN BUTTON |
| MD | MOTION DETECTOR |
| GB | ACCOUSTICAL GLASS BREAK SENSOR |
| BM | BIOMETRIC READER |
| RX | REQUEST TO EXIT - SURFACE PIR |
| KS | KEY SWITCH |
| LA | LOCAL ALARM SOUNDER |
| RG | RED/GREEN INDICATOR LIGHT |
| DB | DOORBELL |
| DH | MAGNETIC DOOR HOLD |
| DR | DOOR RELEASE |
| RX | REQUEST TO EXIT - INTEGRAL TO DOOR HARDWARE |
| DC | DOOR CONTACT / MONITOR |
| ES EL EH | ELECTRIFIED STRIKE - ELECTRIFIED LATCH - ELECTRIFIED HARDWARE (REFER TO SCHEDULES) |
| C C | STANDARD IP SURVEILLANCE CAMERA, (1) CABLE |
| C C C | 180° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° FISHEYE LENS CAMERA |
| IR | IR ILLUMINATOR |

## STRUCTURED CABLING LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF DATA CABLE(S)/JACK(S) |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) |
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| W | WALL MOUNT PHONE (1 CABLE/JACK) |
| W | WALL MOUNT PHONE, SURFACE MOUNT (1 CABLE/JACK) |
| # | FLOOR MOUNTED OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| #/# | FLOOR MOUNTED OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| # | CEILING MOUNTED DATA OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) |
| AP# | CEILING MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| AP# | WALL MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| | CABLING SLEEVE(S) |
| | TYPICAL LADDER RACK |
| | TYPICAL CABLE TRAY, BASKET STYLE |

## GENERAL ANNOTATION LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| MER | MAIN EQUIPMENT ROOM |
| TR | TELECOMMUNICATION ROOM |
| MDF | MAIN DISTRIBUTION FRAME |
| IDF | INTERMEDIATE DISTRIBUTION FRAME |
| ETR | EXISTING TO REMAIN |
| PBO | PROVIDED BY OTHERS |
| AFF | ABOVE FINISHED FLOOR |
| AFG | ABOVE FINISHED GRADE |
| AC | ABOVE COUNTER |
| EC | ELECTRICAL CONTRACTOR |
| PSC | PREMISE SECURITY CONTRACTOR |
| SCC | STRUCTURAL CABLING CONTRACTOR |
| AVC | AV/MULTIMEDIA CONTRACTOR |
| UNO | UNLESS NOTED OTHERWISE |
| ACS | ACCESS CONTROL SYSTEM |
| VSS | VIDEO SURVEILLANCE SYSTEM |

## TECHNOLOGY - GENERAL NOTES

1. EACH KEYNOTE MAY NOT BE UTILIZED ON EVERY SHEET.
2. ALL CONDUIT MEASUREMENTS REFER TO STANDARD CONDUIT TRADE SIZES.
3. ALL CABLES SHALL BE CONCEALED.
4. EACH CONTRACTOR SHALL PROVIDE AND INSTALL ALL NECESSARY SLEEVES, WHETHER OR NOT SPECIFICALLY NOTED ON PROJECT DRAWINGS. ALL SLEEVES SHALL BE 2" UNLESS NOTED OTHERWISE ON THE DRAWINGS. CABLE FILL PERCENTAGE SHALL COMPLY WITH NEC.
5. DEVICE LOCATIONS ARE APPROXIMATE. CONTRACTOR SHALL REVIEW CONDITIONS AND COORDINATE WITH OTHER TRADES AS NECESSARY FOR EXACT PLACEMENT.

## TECHNOLOGY SYMBOLS LEGEND

NOT ALL SYMBOLS ARE USED

- A## V## — AV WALL ROUGH-IN WITH DATA
- # — KEYNOTE
- C — Proposed Camera Direction — SURVEILLANCE CAMERA
- #-## — Camera Schedule Number (Floor #-Camera #) — Camera (N)ew, (E)xisting Rough-in, (D)emo
- C — Proposed Camera Direction — PTZ CAMERA
- #-## — PTZ
- C — Proposed Camera Direction — FIXED SURVEILLANCE CAMERA
- #-##
- C — 360°/MULTI-SENSOR FIXED SURVEILLANCE CAMERA OR FISHEYE LENS CAMERA
- Approximate view of lens
- Lens View Angle
- ##° — #mm — C — 360°/MULTI-SENSOR FIXED SURVEILLANCE CAMERA OR FISHEYE LENS CAMERA
- Lens size
- C M — MICROPHONE WITH AUDIO LINKED TO CAMERA
- C CR — CARD READER LINKED TO CAMERA
- SYMBOL TAG — CR # — (#) = DIFFERENT TYPES OF CARD READERS: M = MULLION; W = WIRELESS (Proprietary); Wi = Wi-Fi (802.11); POE = POWER OVER ETHERNET
- SYMBOL TAG — KP # — (#) = DIFFERENT TYPES OF CARD READERS: TS = TOUCHSCREEN; PU = PUSH BUTTON
- TOP = DETAIL NUMBER
- # / #### — DETAIL REFERENCE
- BOTTOM = SHEET NUMBER
- NORTH ARROW
- SHEET NUMBER
- # / #### — SECTION MARKER
- DETAIL NUMBER
- DIRECTION OF ELEVATION
- # / #### — ELEVATION MARKER
- SHEET NUMBER
- DETAIL NUMBER
- DIRECTION OF ELEVATION
- SHEET NUMBER
- # / #### — DIRECTION OF ELEVATION
- DETAIL NUMBER
- BAR IS ONE INCH ON ORIGINAL DRAWING. IF NOT ONE INCH ON THIS DRAWING ADJUST SCALES ACCORDINGLY

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

u

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Sugar Mill Elementary School
13707 Jess Pirtle Blvd, Sugar Land, TX 77498

SEAL

BICSI Registered Communications Distribution Designer
Bicsi
Brian C Porter
BICSI ID # 258557
EXPIRES 10-31-27
RCDD

07-18-25


MVA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY - TITLE SHEET

u-TN000

**DEMO KEYNOTES**

1. REMOVE, AND PROTECT DURING CONSTRUCTION, INSTALL IN EXISTING LOCATION AFTER NEW ACT GRID IS IN PLACE.
2. DEVICES IN ACT ARE TO BE REMOVED AND PROTECTED DURING CONSTRUCTION AND REINSTALLED IN THE SAME LOCATION AFTER THE NEW CEILING GRID IS IN PLACE. DECIVES INCLUDE: SPEAKERS, ACCESS POINTS AND INTRUSION MOTION DETECTORS.
3. EXISTING CARD READER, DOOR CONTACT, & REX (REQUEST TO EXIT) TO BE DEMOLISHED, REMOVE DEVICES AND PROTECT WIREING.




1 SUGAR MILL - DEMO PLAN
SCALE: 3/16" = 1'-0"

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

u

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Sugar Mill Elementary School
13707 Jess Pirtle Blvd, Sugar Land, TX 77498

SEAL




07-18-25



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Sugar Mill ES - DEMO

u-TN.001

## TECHNOLOGY KEYNOTES

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.




1 BACKGROUND 1 (SUGAR MILL)
SCALE: 1" = 20'-0"

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

u

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Sugar Mill Elementary School
13707 Jess Pirtle Blvd, Sugar Land, TX 77498

SEAL

BICSI REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256557
EXPIRES 12-31-27

07-18-25

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Sugar Mill ES - OVERALL

u-TN.100




1 SUGAR MILL - KITCHEN PLAN
SCALE: 3/16" = 1'-0"

**TECHNOLOGY KEYNOTES**

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

u

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Sugar Mill Elementary School
13707 Jess Pirtle Blvd, Sugar Land, TX 77498

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 254557
EXPIRES 12-31-27
RCDD

07-18-25


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Sugar Mill ES - KITCHEN

u-TN.101


TRUENORTH A PMY COMPANY

**GENERAL NOTE**


1. FACE PLATE DETAIL FOR OUTLET CONFIGURATION PURPOSES ONLY. CONTRACTOR TO SELECT TYPE OF FACE PLATE TO MATCH CONNECTIVITY HARDWARE, FLOOR BOX AND/OR MODULAR FURNITURE OPENING.





## 1 DATA ROUGH-IN DETAILS
SCALE: NS





## 2 TYPICAL CABLING SLEEVE
SCALE: NTS





## 3 PANDUIT J-HOOK DETAIL
SCALE: NTS





## 4 LABELING & CABLING SCHEMES
SCALE: NTS





## 5 CABLE PATHWAY CROSS SECTION
SCALE: NTS




## 6 DROPPED CEILING MOUNTING DETAIL
SCALE: NS




## 7 I-JOIST MOUNTING DETAIL
SCALE: NS




## 8 BAR JOIST MOUNTING DETAIL
SCALE: NS

| CAMERA TYPE | MANUFACTURER | MODEL NUMBER | GENERAL DESCRIPTION |
|---|---|---|---|
| C1 | iPro | WV-S8574L | 4x4K (33MP) EXTERIOR MULTI-SENSOR - PARKING LOTS, STADIUM |
| C2 | iPro | WV-S8544L | 4x4MP (16MP) EXTERIOR MULTI-SENSOR - BUILDING PERIMETER |
| C3 | iPro | WV-S25500-V3LN | 5MP EXTERIOR VANDAL DOME |
| C4 | iPro | WV-S22500-V3L | 5MP INTERIOR VANDAL DOME - CORR., COMMON, SPED |
| C5 | iPro | WV-S4156A | 5MP 360 (FISHEYE) - STAIRWELLS |

## 9 CAMERA SCHEDULE
SCALE: NTS

| Symbol | Purpose | Size | Mount | Backbox | Notes |
|---|---|---|---|---|---|
| FP1 | Digital Signage/Menu Boards | +49" | Ceiling Pole | N/A | Data and Power Outlets on ceiling |

## 10 DISPLAY SCHEDULE
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

u

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Sugar Mill Elementary School
13707 Jess Pirtle Blvd, Sugar Land, TX 77498

SEAL

BICSI REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256557
EXPIRES 12-31-27

07-18-25



MVA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Sugar Mill ES - DETAILS


u-TN.500

GENERAL NOTES:


1. REFER TO SECURITY SCHEDULE AND WRITTEN SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
2. ALL MOUNTING DETAILS ARE REFERENCE FOR ALL FIXED DOME, 180°, 360°, PTZ, AND "BULLET/BOX" CAMERAS.





1 TYPICAL CAMERA INSTALLATION SECTION DETAIL
SCALE: NS




6 WALL MOUNTED CAMERA DETAIL
SCALE: NS




4 TILE BRIDGE DETAIL
SCALE: NS





5 CEILING MOUNTED CAMERA DETAIL
SCALE: NS


ACCESS CONROL DETAILS AND GENERAL NOTES:

1. CONDUIT ROUGH-IN IS A GUIDE FOR WHAT WILL BE REQUIRED FOR EACH DOOR. AS DOOR COMPONENTS CHANGE, EXACT CONDUIT LOCATION WILL ALSO NEED TO BE ADJUSTED.


2. PROTECT EXISTING-TO-REMAIN ACCESS CONTROL DEVICES AND CABLE THROUGHOUT RENOVATION WORK. IF CABLE AND/OR DEVICES ARE DAMAGED, SECURITY CONTRACTOR TO REPLACE WITH NEW.




1 ACCESS CONTROL - WIRING DETAIL - EXIT DEVICE W/ BUILT-IN REX
SCALE: NTS




2 ACCESS CONTROL - STEEL/HOLLOW METAL DOOR.
SCALE: NTS




KP PB LD

3 ROUGH-IN DETAILS: KP, PB, LD
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

u

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Sugar Mill Elementary School
13707 Jess Pirtle Blvd, Sugar Land, TX 77498

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 254657
EXPIRES 12-31-27
RCDD


07-18-25


MVA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING
AND
PERMITTING

TECHNOLOGY - Sugar Mill ES
- SECURITY DETAILS

u-TN.600




6 CEILING MOUNT DISPLAY - A/V ROUGH-IN DETAIL
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

u

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Sugar Mill Elementary School
13707 Jess Pirtle Blvd, Sugar Land, TX 77498

SEAL




07-18-25

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Sugar Mill ES - AV DETAILS

u-TN.700

# FBISD BP013 KITCHEN RENOVATIONS ES

| Sheet List Table | |
|---|---|
| Sheet Number | Sheet Title |
| School: v-Sullivan ES | |
| v-A.000 | COVER AND INDEX |
| v-A00-01 | GENERAL NOTES AND ABBREVIATIONS |
| v-D.101 | REFERENCE PHOTOS PLAN |
| v-A.101 | SITE PLAN |
| v-A.201 | OVERALL FLOOR PLAN |
| v-A.301 | CAFETERIA PLAN |
| v-A.501 | FINISH FLOOR PLAN |
| v-E.000 | ELECTRICAL AND FIRE ALARM SCHEDULES |
| v-E.001 | ELECTRICAL AND FIRE ALARM NOTES |
| v-E.200 | ELECTRICAL FLOOR PLAN & SCHEDULE |
| V-TN-000 | TECHNOLOGY - INDEX SHEET |
| V-TN-100 | TECHNOLOGY - OVERALL |
| V-TN-101 | TECHNOLOGY - KITCHEN |
| V-TN-500 | TECHNOLOGY - DETAILS |
| V-TN-600 | TECHNOLOGY - SECURITY DETAILS |




FORT BEND INDEPENDENT SCHOOL DISTRICT

ANNE SULLIVAN ELEMENTARY SCHOOL
17828 WINDING WATERS LN, SUGAR LAND, TX 77479

## ADMINISTRATION

| | |
|---|---|
| DR. MARCELL SMITH | SUPERINTENDENT OF FBISD |
| DR. ANDRIA SCHUR, Ed.D. | CHIEF OF SCHOOLS |

## BOARD OF TRUSTEES

| | |
|---|---|
| KRISTIN K. TASSIN | PRESIDENT |
| RICK GARCIA | VICE PRESIDENT |
| DAVID HAMILTON | SECRETARY |
| ANGIE HANAN | BOARD MEMBER |
| ADAM SCHOOF | BOARD MEMBER |
| DR. SHIRLEY ROSE-GILLIAM | BOARD MEMBER |
| SONYA JONES | BOARD MEMBER |

## PROJECT DESIGN TEAM

PROGRAM MANAGEMENT
FBISD 2023 Bond Team
2323 Texas Parkway
Missouri City, TX 77489
Phone Number: 281-327-5481

ARCHITECT
MWA Architects
11767 Katy Freeway, Suite 430
Houston, Texas 77079
Phone Number: 713-782-8188

FOOD SERVICE
Food Design Professionals
26215 Oak Ridge Drive
The Woodlands, Texas 77380
Phone Number: 281-350-2323

MEP ENGINEERS
Stanton Engineering Group
1300 W. Sam Houston Pkwy South, Suite 121
Houston, Texas 77042
Phone Number: 713-300-9292

STRUCTURAL ENGINEER
Stanley Spurling & Hamilton
3301 Edloe Street, Suite 200
Houston, Texas 77027
Phone Number: 713-776-9433

ISSUED FOR BIDDING AND PERMITTING - JULY 18, 2025

V

PART 1 - GENERAL

1.1 GENERAL DEMOLITION NOTES

A. VERIFY EXISTING SITE AND BUILDING CONDITIONS IN FIELD PRIOR TO BIDDING. NOTIFY ARCHITECT OF ANY DISCREPANCIES PRIOR TO BIDDING.

B. CONTRACTOR SHALL COORDINATE WITH OWNER THE SALVAGE OF ITEMS, FURNITURE AND EQUIPMENT INDICATED TO BE REMOVED.

C. CLAIMS FOR ADDITIONAL COST OR TIME DUE TO EXISTING CONDITIONS THAT COULD HAVE BEEN REASONABLY ANTICIPATED DURING A SITE VISIT BY THE CONTRACTOR PRIOR TO BIDDING WILL NOT BE APPROVED.

D. PROTECT EXISTING FINISHES SHOWN TO REMAIN DURING CONSTRUCTION TO PREVENT DAMAGE. REPAIR OR REPLACE DAMAGED MATERIALS AND FINISHES TO MATCH EXISTING AT NO ADDITIONAL COST TO FORT BEND ISD (OWNER).

E. EXISTING AREAS REQUIRING MINOR DEMOLITION OR REPAIR FOR EXECUTION OF WORK SHALL BE REPAIRED TO MATCH EXISTING ADJACENT MATERIALS, UNLESS NOTED OTHERWISE.

F. DO NOT DAMAGE CASEWORK AND EQUIPMENT NOT DESIGNATED TO BE REMOVED OR RELOCATED.EXISTING CASEWORK SHALL REMAIN THE PROPERTY OF THE OWNER.

G. CONTRACTOR TO VERIFY LOCATION OF ELEC. SWITCHES, OUTLETS, GRILLES, CLEAN-OUTS, COVER PLATES, ACCESS DOORS, AND OTHER EQUIPMENT AND DEVICES THAT MAY CONFLICT WITH THE RENOVATION AND NEW CONSTRUCTION OF WALLS, FLOORS, AND CEILINGS PRIOR TO COMMENCEMENT OF WORK. CONTRACTOR SHALL LIKEWISE CONFIRM THAT ELECTRICAL CONDUIT ROUTING SHALL BE CONCEALED WITHIN WALLS. NOTIFY ARCHITECT IF WALL THICKNESS WILL NOT ALLOW FOR CONCEALMENT.

H. REMOVE ANY EXISTING CORNER GUARDS IN THE KITCHEN AREA.

I. PRIOR TO EXECUTION OF DEMOLITION WORK, SCHEDULE A WALK-THROUGH WITH OWNER AND ARCHITECT TO CONFIRM SCOPE OF WORK AND TO REVIEW EXISTING CONDITIONS.

J. EXISTING FLOOR FINISHES AND ACOUSTIC CEILING TILE TO BE REMOVED THROUGHOUT.

K. REFER TO MEP DRAWINGS FOR DEMOLITION AND ALTERATION OF UTILITIES.

L. AT ALL EXISTING WALLS REQUIRING DEMOLITION TO INSTALL NEW PIPING BEHIND SINKS, CUT AND PATCH WALLS AS REQUIRED TO MATCH ADJACENT SURFACE.

M. CLEAN AND PREPARE SUBFLOOR FOR INSTALLATION OF NEW FLOOR FINISH.

N. DEMOLITION ACTIVITIES SHALL BE PERFORMED AS TO PRODUCE MINIMAL DISTURBANCE TO EXISTING FACILITY OCCUPANTS. MINIMIZE EXCESSIVE AND PROLONGED NOISE LEVELS AND DUST.

O. ASBESTOS-CONTAINING MATERIALS. REFER TO SPECIFICATION 02 26 23 FOR ASBESTOS INFORMATION APPLICABLE TO KITCHEN AREAS. FORT BEND ISD HAS RETAINED A SEPARATE ENVIRONMENTAL CONSULTANT FOR THE REMOVAL OF ASBESTOS. GC TO COORDINATE WITH ENVIRONMENTAL CONSULTANT TO CARRY OUT ASBESTOS ABATEMENT FOR ALL AFFECTED KITCHEN AREAS.

1.2 FLOOR PLAN GENERAL NOTES

A. FIELD VERIFY EXISTING CONDITIONS PRIOR TO GENERATING SHOP DRAWINGS AND FABRICATION OF EQUIPMENT.
B. FLOOR FINISH CHANGES SHALL OCCUR AT THE CENTERLINE OF DOORS UNLESS NOTED OTHERWISE. FLOOR FINISH CHANGES SHALL HAVE THRESHOLDS OR REDUCERS STRIPS.
C. DOORS THAT ARE TO BE REPLACED AND INSTALLED IN EXISTING FRAMES SHALL BE MACHINED FOR HARDWARE DIMENSIONS AT EXISTING FRAMES, CONTRACTOR SHALL FIELD VERIFY FRAME CONDITIONS AND DIMENSIONS.
D. CONTRACTOR TO PROVIDE SHEET METAL REINFORCING STRAP AS REQUIRED FOR MOUNTING OF ALL GRAB BARS, CABINETS, MIRRORS, SHELVING, ETC.
E. SAW CUT AND REMOVE EXISTING SLAB AND FLOOR FINISHES AS REQUIRED TO INSTALL NEW PLUMBING LINES, FLOOR DRAINS, PLUMBING FIXTURES, OR ELECTRICAL ITEMS. SPLICE NEW REINFORCING BARS DOWELED INTO EXISTING CONCRETE, AND PROVIDE NEW VAPOR RETARDER AND WATERSTOPS, AND PATCH W/ 3000 PSI CONCRETE AFTER INSTALLATION OF UTILITIES AND FIXTURES. PREPARE CONCRETE TO RECEIVE NEW FINISH.
F. COORDINATE HOUSEKEEPING PAD DIMENSIONS AND LOCATIONS WITH EQUIPMENT TO BE INSTALLED. HOUSEKEEPING PADS SHALL BE A MIN. OF 4" THICK REINF. W/ #3 BARS AT 15" O.C. BOTH WAYS. PROVIDE 1" BY 45-DEGREE CHAMFERED EDGES.

1.3 COMPLETE PERFORMANCE

L. THE CONTRACTOR SHALL FURNISH AND INSTALL ALL ITEMS SPECIFIED HEREIN AND AS INDICATED ON THE DRAWINGS. THE CONTRACTOR SHALL ALSO FURNISH AND INSTALL ALL ITEMS NECESSARY TO MAKE THE SYSTEMS FUNCTION WHICH MAY BE REASONABLY IMPLIED AS ESSENTIAL, WHETHER MENTIONED IN THE CONTRACT DOCUMENTS OR NOT.

M. WORK SHALL BE EXECUTED IN STRICT ACCORDANCE WITH THE BEST PRACTICE OF THE TRADES IN A THOROUGH, SUBSTANTIAL AND WORKMANLIKE MANNER BY COMPETENT WORKMEN.

1.4 SITE FAMILIARIZATION

A. GENERAL: BECOME FAMILIAR WITH THE DRAWINGS AND SPECIFICATIONS, EXAMINE THE PREMISES, AND UNDERSTAND THE CONDITIONS UNDER WHICH THE CONTRACT SHALL BE PERFORMED, PRIOR TO SUBMITTING A BID.

B. SITE: BE INFORMED OF THE SITE CONDITIONS, VERIFY LOCATIONS OF NEW AND EXISTING EQUIPMENT, AND DETERMINE EXACT REQUIREMENTS FOR CONNECTIONS.

C. COORDINATION: TENDER OF A PROPOSAL FOR THIS PROJECT INFERS THAT THE CONTRACTOR HAS VISITED THE SITE AND HAS BECOME FAMILIAR WITH THE DRAWINGS, SPECIFICATIONS, AND SITE CONDITIONS AND HAS INCLUDED IN HIS PROPOSAL ALL WORK NECESSARY TO PROPERLY INSTALL COMPLETE AND FUNCTIONING SYSTEMS ON THE PROJECT. FAILURE TO COMPLY WITH THIS REQUIREMENT SHALL NOT BE CONSIDERED JUSTIFICATION FOR THE OMISSION OR FAULTY INSTALLATION OF ANY WORK COVERED BY THE CONTRACT DOCUMENTS.

1.5 CODES AND STANDARDS

A. GENERAL: ALL WORK SHALL COMPLY WITH THE MOST RECENTLY REVISED VERSIONS OF ALL APPLICABLE LAWS, RULES, REGULATIONS AND ORDINANCES OF ALL FEDERAL, STATE AND LOCAL AUTHORITIES AND APPLICABLE UTILITIES. NONE OF THE TERMS OR PROVISIONS OF THIS SPECIFICATION SHALL BE CONSTRUED AS WAIVING ANY PART OF THE LAWS, RULES, REGULATIONS OR REQUIREMENTS OF THESE AUTHORITIES.

B. CONFLICT: IN THE EVENT OF CONFLICT BETWEEN THE CONTRACT DOCUMENTS AND THE LOCAL ENFORCING AUTHORITY, THE LATTER SHALL RULE. ANY MODIFICATIONS RESULTING THEREFROM SHALL BE MADE WITHOUT ANY ADDITIONAL COST TO THE OWNER OR ARCHITECT. THIS CONTRACTOR SHALL REPORT ANY SUCH MODIFICATIONS TO THE ARCHITECT AND SECURE HIS APPROVAL PRIOR TO PROCEEDING WITH THE WORK.

C. PRECEDENCE: WHERE CONTRACT DOCUMENT REQUIREMENTS EXCEED THE REQUIREMENTS OF THE CODES AND STANDARDS, THE CONTRACT DOCUMENTS SHALL TAKE PRECEDENCE PROVIDED THEY ARE NOT IN CONFLICT WITH THOSE CODES AND STANDARDS.

D. APPROVAL LABELS: ALL ITEMS OF EQUIPMENT AND ALL MATERIALS FOR WHICH APPROVED STANDARDS HAVE BEEN ESTABLISHED BY UNDERWRITERS' LABORATORIES, INC. (UL), FACTORY MUTUAL (FM), CERTIFIED BALLAST MANUFACTURER (CBM), ELECTRICAL TESTING LABORATORY (ETL), NATIONAL MANUFACTURERS ASSOCIATION (NEMA), AMERICAN STANDARD CODES. ASME, AGA, AMCA, ASA, ANSI, ASHRAE, AND ARI SHALL BE SO APPROVED AND SHALL BEAR APPROVAL LABELS ATTESTING TO SAME.

1.6 DRAWINGS AND SPECIFICATIONS

A. DRAWINGS: THE SET OF ORIGINAL DRAWINGS HAS BEEN MODIFIED AND INDICATE APPROXIMATE EXISTING LOCATIONS OF THE FLOOR FINISH ITEMS. ALL ITEMS ARE SHOWN APPROXIMATELY TO SCALE. FIELD VERIFY CONDITIONS.

B. SPECIFICATIONS: THE SPECIFICATIONS ARE INTENDED TO SUPPLEMENT THE DRAWINGS AND IT IS NOT IN THE SCOPE OF THE SPECIFICATIONS TO MENTION ANY PART OF THE WORK THAT THE DRAWINGS ARE COMPETENT TO FULLY EXPLAIN. CONVERSELY, ANY PART OF THE WORK THAT THE SPECIFICATIONS ARE COMPETENT TO FULLY EXPLAIN MAY NOT BE MENTIONED ON THE DRAWINGS. DRAWINGS AND SPECIFICATIONS ARE COMPLIMENTARY/SUPPLEMENTARY DOCUMENTS TO EACH OTHER.

C. DISAGREEMENT: DISAGREEMENT BETWEEN THE DRAWINGS AND SPECIFICATIONS OR WITHIN THE DRAWINGS OR SPECIFICATIONS SHALL BE ESTIMATED AND/OR BID USING THE BETTER QUALITY OR GREATER QUANTITY OF MATERIAL OR INSTALLATION, AND A CLARIFICATION REQUEST FOR INFORMATION SHALL BE MADE TO THE ARCHITECT IN A TIMELY MANNER AFTER THE PROJECT IS UNDER CONTRACT.

1.7 DISCREPANCIES

A. CLARIFICATION: CLARIFICATION OF SIGNIFICANT COST MATTERS SHALL BE OBTAINED BEFORE SUBMITTING A PROPOSAL FOR THE WORK AS TO DISCREPANCIES OR OMISSIONS FROM THE CONTRACT DOCUMENTS OR QUESTIONS AS TO THE INTENT THEREOF.

B. INTERPRETATIONS: SHOULD ANY DOUBT OR QUESTION ARISE RESPECTING THE TRUE MEANING OF DRAWINGS OR SPECIFICATIONS, REFERENCE SHALL BE MADE TO THE ARCHITECT, WHOSE WRITTEN DECISION SHALL BE FINAL AND CONCLUSIVE. NO ALLEGED STATEMENT BY THE ARCHITECT WILL BE ACCEPTED AS AN EXCUSE FOR NON-COMPLIANCE OR INFERIOR WORK.

C. CONTRACTOR AGREEMENT: CONSIDERATION WILL NOT BE GRANTED FOR MISUNDERSTANDING OF THE AMOUNT OF WORK TO BE PERFORMED. TENDER OF A PROPOSAL CONVEYS FULL CONTRACTOR AGREEMENT OF THE ITEMS AND CONDITIONS SPECIFIED, SHOWN, SCHEDULED, OR REQUIRED BY THE NATURE OF THE PROJECT, AND ALL COSTS ARE INCLUDED IN THE PROPOSAL.

1.8 REQUESTS FOR INFORMATION (RFI)

A. GENERAL: SUBMIT ALL CONTRACTOR REQUESTS FOR INFORMATION (RFI) IN WRITING TO THE ARCHITECT FOR RESPONSE. SUBMIT RFI ON A STANDARD FORM THAT HAS A SPACE FOR THE REQUESTED INFORMATION AND THE ARCHITECT'S RESPONSE.
B. SOLUTION PROPOSAL: IN GENERAL, THE CONTRACTOR SHALL PROPOSE SOLUTIONS TO IDENTIFY PROBLEMS FOR REVIEW AND APPROVAL OF THE ARCHITECT. THE RFI SHALL INCLUDE HAND SKETCHES, MARKED DRAWING PRINTS, EQUIPMENT CUTSHEETS, DRAWING AND SPECIFICATION REFERENCES, AND ANY OTHER BACK-UP INFORMATION, ETC., AS REQUIRED TO SUFFICIENTLY EXPLAIN THE PROBLEM AND PROPOSED SOLUTION.

1.9 QUALITY ASSURANCE

A. GENERAL: MATERIALS AND EQUIPMENT SHALL BE NEW, OF BEST GRADE AND QUALITY, AND STANDARD PRODUCTS OF REPUTABLE MANUFACTURERS REGULARLY ENGAGED IN THE PRODUCTION OF SUCH MATERIALS AND EQUIPMENT.
B. WORKMANSHIP: WORK SHALL BE EXECUTED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE BEST PRACTICE OF THE TRADES IN A THOROUGH, SUBSTANTIAL, WORKMANLIKE MANNER BY COMPETENT WORKMEN, PRESENTING A NEAT APPEARANCE WHEN COMPLETED.
C. JUDGMENT: IN ALL CASES, THE ARCHITECT SHALL BE THE SOLE JUDGE OF THE QUALITY AND EQUIVALENCE OF MANUFACTURERS, PRODUCTS, MATERIALS, AND METHODS.
D. MANUFACTURERS/PRODUCTS/MATERIALS/METHODS: MANUFACTURERS, PRODUCTS, MATERIALS, AND METHODS DESCRIBED IN THE VARIOUS SECTIONS OF THE SPECIFICATIONS AND INDICATED ON THE DRAWINGS ARE INTENDED TO ESTABLISH A STANDARD OF QUALITY ONLY. IT IS NOT THE INTENTION OF THE ARCHITECT TO DISCRIMINATE AGAINST ANY MANUFACTURER, PRODUCT, MATERIAL, OR METHOD THAT IS EQUAL TO THE STANDARDS AS INDICATED AND/OR SPECIFIED, NOR IS IT INTENDED TO PRECLUDE OPEN, COMPETITIVE BIDDING. THE FACT THAT A SPECIFIC MANUFACTURER IS LISTED AS AN ACCEPTABLE MANUFACTURER SHALL NOT BE INTERPRETED TO MEAN THAT THE MANUFACTURER'S STANDARD PRODUCT WILL MEET THE REQUIREMENTS OF THE PROJECT DESIGN, SPECIFICATIONS, AND SPACE CONSTRAINTS.
    1. WHEREVER A DEFINITE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS SPECIFIED AND THERE IS NOT A STATEMENT THAT ANOTHER MANUFACTURER, PRODUCT, MATERIAL, OR METHOD WILL BE ACCEPTABLE, IT IS THE INTENTION OF THE ARCHITECT THAT THE SPECIFIED MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS THE ONLY ONE THAT SHALL BE USED WITHOUT PRIOR APPROVAL.
    2. WHEREVER A DEFINITE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD IS SPECIFIED AS "NO SUBSTITUTE", IT IS THE INTENTION OF THE ARCHITECT THAT THE LISTED ITEM IS THE ONLY ONE ACCEPTABLE.
E. COORDINATION: WHERE EQUIPMENT IS USED ON THE PROJECT, IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR OR SUBCONTRACTOR INVOLVED TO VERIFY THAT THE EQUIPMENT WILL FIT IN THE SPACE AVAILABLE, INCLUDING ALL REQUIRED CODE AND MAINTENANCE CLEARANCES, AND TO COORDINATE ALL EQUIPMENT REQUIREMENTS AND PROVISIONS WITH THE SYSTEM DESIGN, ALL AFFECTED DIVISIONS, AND ALL OTHER CONTRACTORS. WHERE THE USE OF ALTERNATE OR SUBSTITUTE MATERIALS AFFECTS THE COST OF PROVISIONS MADE BY OTHER CONTRACTORS, THE CONTRACTOR PROVIDING THE ALTERNATE OR SUBSTITUTE SHALL BE RESPONSIBLE FOR THE OTHER CONTRACTOR'S COST ADJUSTMENT. THERE SHALL BE NO ADDITIONAL COST TO THE OWNER OR ARCHITECT DUE TO THE USE OR ACCEPTANCE OF ANY ALTERNATE OR SUBSTITUTE MANUFACTURER, PRODUCT, MATERIAL, OR METHOD.

1.10 PRIOR APPROVAL

A. SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES: THE CONTRACTOR'S SUBMITTAL AND ARCHITECT'S ACCEPTANCE OF SHOP DRAWINGS, PRODUCT DATA, OR SAMPLES THAT RELATE TO CONSTRUCTION ACTIVITIES NOT COMPLYING WITH THE CONTRACT DOCUMENTS DOES NOT CONSTITUTE AN ACCEPTABLE OR VALID REQUEST FOR SUBSTITUTION, NOR DOES IT CONSTITUTE APPROVAL.

1.11 COORDINATION

A. BY SUBMITTING SHOP DRAWINGS ON THE PROJECT, THIS CONTRACTOR IS INDICATING THAT ALL NECESSARY COORDINATION HAS BEEN COMPLETED AND THAT THE SYSTEMS, PRODUCTS AND EQUIPMENT SUBMITTED CAN BE INSTALLED IN THE BUILDING AND WILL OPERATE AS SPECIFIED AND INTENDED, IN FULL COORDINATION WITH ALL OTHER DISCIPLINES.

1.12 SHOP DRAWINGS AND SUBMITTALS

A. GENERAL: AFTER THE CONTRACT IS AWARDED BUT PRIOR TO PROCEEDING WITH THE WORK REQUIRING SHOP DRAWING REVIEW, THE CONTRACTOR SHALL OBTAIN COMPLETE SHOP DRAWINGS AND PRODUCT DATA FROM THE MANUFACTURERS, SUPPLIERS, VENDORS, AND SUB- CONTRACTORS FOR ALL MATERIALS AND EQUIPMENT SPECIFIED HEREIN, AND MAKE FORMAL SUBMISSION TO THE ARCHITECT. A MINIMUM PERIOD OF TWO (2) WEEKS SHOULD BE ALLOWED IN THE CONSTRUCTION SCHEDULE EXCLUSIVE OF TRAVEL TIME FOR THE ARCHITECTS REVIEW.
B. CERTIFICATION: EACH CONTRACTOR RESPONSIBLE FOR THE WORK SHALL REVIEW AND CERTIFY THE SHOP DRAWING, SUBMITTAL AND/OR PRODUCT DATA TO BE IN FULL COMPLIANCE WITH THE REQUIREMENTS OF THE CONTRACT DOCUMENTS.
C. THE ARCHITECTS REVIEW OF SHOP DRAWINGS AND SUBMITTAL DATA SHALL NOT RELIEVE THE CONTRACTOR OF THE RESPONSIBILITY FOR DIMENSIONS OR ERRORS THAT MAY BE CONTAINED THEREIN, OR FOR DEVIATIONS FROM ANY REQUIREMENTS OF THE CONTRACT DOCUMENTS. IT SHALL BE CLEARLY UNDERSTOOD THAT THE ARCHITECTS NOTING SOME ERRORS BUT OVERLOOKING SOME OTHERS DOES NOT GRANT THE CONTRACTOR PERMISSION TO PROCEED IN ERROR. REGARDLESS OF ANY INFORMATION CONTAINED IN THE SHOP DRAWING OR PRODUCT DATA, THE CONTRACT DOCUMENTS SHALL GOVERN THE WORK AND ARE NEITHER WAIVED NOR SUPERSEDED IN ANY WAY BY THE REVIEW OF SHOP DRAWINGS, PRODUCT DATA AND SAMPLES.

1.13 EXECUTION AND COORDINATION OF WORK

A. MANUFACTURER'S RECOMMENDATIONS: WITH EXCEPTIONS AS SPECIFIED AND/OR INDICATED ON THE DRAWINGS OR IN THE SPECIFICATIONS, APPLY, INSTALL, ERECT, USE, CLEAN, AND CONDITION, MANUFACTURED ARTICLES, MATERIALS, AND EQUIPMENT PER MANUFACTURER'S CURRENT PRINTED RECOMMENDATIONS. KEEP COPIES OF SUCH PRINTED RECOMMENDATIONS AT JOB SITE AND MAKE THEM AVAILABLE AS REQUIRED.

1.14 SUPERVISION

A. A COMPETENT SUPERINTENDENT APPROVED BY THE ARCHITECT, SHALL BE KEPT BY THE CONTRACTOR AT THE BUILDING TO RECEIVE INSTRUCTIONS AND TO ACT FOR THE CONTRACTOR. ONCE THE SUPERINTENDENT HAS BEEN APPROVED, NO CHANGE SHALL BE MADE WITHOUT APPROVAL OF ARCHITECT. REPRESENTATIVES OF THE OWNER, ARCHITECT SHALL HAVE THE RIGHT TO OBSERVE THE WORK AT ANY TIME. THE CONTRACTOR SHALL HAVE A REPRESENTATIVE AVAILABLE WHEN HIS WORK IS BEING OBSERVED AND HE SHALL GIVE ASSISTANCE AS MAY BE REQUIRED TO THE ARCHITECT'S REPRESENTATIVE.
B. THE PROJECT SHALL BE CONSTRUCTED BY EMPLOYEES OF THE CONTRACTOR OR BY WORKERS UNDER HIS SUPERVISION. ANY SUBCONTRACTORS EMPLOYED BY THE CONTRACTOR SHALL BE APPROVED BY THE OWNER'S REPRESENTATIVE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL EQUIPMENT, MATERIAL AND WORK PERFORMED BY ANY SUBCONTRACTOR.

1.15 STORAGE AND PROTECTION OF MATERIALS

A. THE CONTRACTOR SHALL PROPERLY STORE ALL MATERIAL AND EQUIPMENT AT THE JOBSITE AND PROTECT IT FROM THE ELEMENTS AND FROM DAMAGE. ANY EQUIPMENT DAMAGED DUE TO IMPROPER PROTECTION SHALL BE REPLACED BY THE CONTRACTOR AT HIS EXPENSE.
B. THE CONTRACTOR SHALL PROTECT THE WORK, EQUIPMENT, AND MATERIAL OF ALL OTHER TRADES FROM DAMAGE BY HIS WORK OR OTHER WORKMEN, AND SHALL MAKE GOOD ALL DAMAGE THUS CAUSED.
C. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL WORK, MATERIALS, AND EQUIPMENT UNTIL FINALLY INSPECTED, TESTED, AND ACCEPTED; PROTECT WORK AGAINST THEFT, INJURY OR DAMAGE; AND CAREFULLY STORE MATERIAL AND EQUIPMENT RECEIVED ON SITE WHICH ARE NOT IMMEDIATELY INSTALLED. CLOSE OPEN ENDS OF WORK WITH TEMPORARY COVERS OR PLUGS DURING CONSTRUCTION TO PREVENT ENTRY OF OBSTRUCTING MATERIAL. THE CONTRACTOR SHALL COVER AND PROTECT IN AN ACCEPTABLE MANNER TO THE OWNER, EXISTING REMAINING EQUIPMENT AND MATERIALS.
D. IF ANY MATERIAL OR EQUIPMENT IS RECEIVED PRIOR TO THE TIME IT IS REQUIRED, THE CONTRACTOR SHALL BE RESPONSIBLE FOR ITS PROPER STORAGE AND PROTECTION UNTIL SUCH TIME AS IT MAY BE REQUIRED. THE CONTRACTOR SHALL PAY FOR ALL COSTS OF DEMURRAGE OR STORAGE.

1.16 DRAYAGE AND HAULING

A. THE CONTRACTOR SHALL KEEP THE JOBSITE FREE FROM THE ACCUMULATION OF TRASH AND CONSTRUCTION DEBRIS, REGARDLESS OF WHICH SUBCONTRACTOR MAY BE RESPONSIBLE.

1.17 CUTTING AND PATCHING

A. WHERE IT BECOMES NECESSARY TO CUT THROUGH ANY WALL, FLOOR OR CEILING TO PERMIT THE INSTALLATION OF ANY WORK, OR TO REPAIR ANY DEFECTS THAT MAY APPEAR, THE CUTTING SHALL BE PERFORMED UNDER THE SUPERVISION OF THE GENERAL CONTRACTOR. INFORM THE OWNER'S REPRESENTATIVE BEFORE ANY WORK COMMENCES. NO STRUCTURAL MEMBER SHALL BE ALTERED WITHOUT THE WRITTEN PERMISSION OF THE ARCHITECT.
B. VERIFICATION: SHOULD A QUESTION ARISE REGARDING THE ACCEPTABLE LEVEL OF NOISE OR VIBRATION IN A PARTICULAR SPACE OR PIECE OF EQUIPMENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING THE SERVICES OF AN APPROVED ACOUSTICAL CONSULTANT TO DETERMINE ACTUAL NOISE/VIBRATION CONDITIONS.

01 GENERAL NOTES

SEQUENCE OF CONSTRUCTION (AS OF 01/27/2025) Schools will be renovated in groups as shown. These groups contain two or three major kitchen renovations and some cafeteria/miscellaneous renovations. This sequencing is critical for FBISD food service to provide the uninterrupted meal services to their schools.

| | |
|---|---|
| GROUPING 1 | AUSTIN PARKWAY ES + SUGAR MILL ES, kitchen renovations. *Plus: COMMON WEALTH ES, CONERSTONE ES misc. renovations.* |
| GROUPING 2 | SETTLERS WAY ES + PALMER ES kitchen renovations. *Plus: SULLIVAN ES, SIENNA CROSSING ES, HERITAGE ROSE ES misc. renovations* |
| GROUPING 3 | HUNTER'S GLEN ES + HIGHLANDS ES + PECAN GROVE ES kitchen renovations. *Plus: RIDGEGATE ES, DULLES ES misc. renovations.* |

03 PROJECT SCHEDULE

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\A00-01 GENERAL NOTES AND ABBREVIATIONS.dwg, Jul 23, 2025 - 5:09pm

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

V

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SULLIVAN ELEMENTARY SCHOOL
17828 WINDING WATERS LANE
SUGAR LAND, TX 77479

SEAL

REGISTERED ARCHITECT
ROBERT E. HOWARD
22651
STATE OF TEXAS

7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

GENERAL NOTES AND ABBREVIATIONS

A00-01




PHOTO D1




PHOTO D2




PHOTO D3




PHOTO D4





PHOTO D5




1 DEMOLITION REFERENCE AND PHOTOS FLOOR PLAN
SCALE: 1/8" = 1'-0"

## DEMOLITION FLOOR PLAN - KEYED NOTES

01 REPAIR BROKEN WOOD NOSINGS / RISERS ON STEPS LEADING TO STAGE AREA. MATCH SPECIES AND FINISH. APPROX. 20 LF WILL BE REPLACED.

02 REMOVE EXISTING MOVEABLE PANELS AND TRACK AND DISCARD.
- a. REMOVE EXISTING SOFFIT FRAMING AND FINISH TO THE EXTENT REQUIRED TO IN INSTALL A NEW POWERED MOVEABLE PANEL SYSTEM.
- b. APPROX. 7" - 10" IN HEIGHT WILL BE LOST.
- c. EXISTING BEAM SHALL REMAIN IN PLACE WHERE POSSIBLE. LOWER THE BLOCKING TO THIS NEW HEIGHT AND ATTACH NEW TRACK AND POWER ACTUATION SYSTEM.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

V

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SULLIVAN ELEMENTARY SCHOOL
17828 WINDING WATERS LANE
SUGAR LAND, TX 77479


SEAL
REGISTERED ARCHITECT
KIM A. MCKINNEY
22651
STATE OF TEXAS
7/15/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

REFERENCE PHOTOS FLOOR PLAN
v-D.101

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWG\SD\drawings\v-Sullivan ES\v-D.101 REFERENCE PHOTOS PLAN.dwg Jul 23, 2025 - 5:10pm




| PHASING CHART FOR ALL SCHOOLS | | |
|---|---|---|
| PHASE 1 | | |
| **SCHOOLS** | **FREEZER START DATE :** | **FREEZER END DATE :** |
| ***AUSTIN PARKWAY ES*** | | |
| SUGAR MILL ES | 11/7/2025 | 5/13/2026 |
| COMMONWEALTH ES | | |
| CONERSTONE ES | | |
| PHASE 2 | | |
| SETTLERS WAY ES | | |
| PALMER ES | | |
| SULLIVAN ES | 5/29/2026 | 10/28/2026 |
| SIENNA CROSSING ES | | |
| HERITAGE ROSE ES | | |
| **PHASE 3** | | |
| HUNTERS GLEN ES | | |
| PECAN GROVE ES | 3/19/2027 | 3/19/2027 |
| HIGHLANDS ES | | |
| DULLES ES | | |

1 SITE PLAN
SCALE: 1" = 30'-0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

V

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SULLIVAN ELEMENTARY SCHOOL
17828 WINDING WATERS LANE
SUGAR LAND, TX 77479

SEAL
REGISTERED ARCHITECT
MOHAMMAD A. MOMIN
22651
STATE OF TEXAS
7/15/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

SITE PLAN

v-A.101

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\V-Sullivan ES\v-A 101 SITE PLAN.dwg Jul 23, 2025 - 5:16pm




1 OVERALL FLOOR PLAN
SCALE: 1/16" = 1'-0"

SCOPE OF WORK: SECURITY CAMERAS OVER SERVING LINES.
RENOVATE, CONFIGURE AND EXPAND EXISTING CAFETERIA.

**FORT BEND COUNTY BUILDING CODES:**

2021 INTERNATIONAL FIRE CODE

**INTERIOR WALL AND CEILING FINISH REQUIREMENTS BY OCCUPANCY:**

**SPRINKLERED**

| | |
|---|---|
| INTERIOR EXIT STAIRWAYS AND RAMPS AND EXIT PASSAGEWAYS | B |
| CORRIDORS AND ENCLOSURE FOR EXIT ACCESS STAIRWAYS AND RAMPS | C |
| ROOMS AND ENCLOSED SPACES | C |

**FLOORING SHALL BE CLASS II**

**2021 INTERNATIONAL EXISTING BUILDING CODE**

301.3.1 PRESCRIPTIVE COMPLIANCE METHOD. REPAIRS, ALTERATIONS, ADDITIONS AND CHANGES OF OCCUPANCY COMPLYING WITH CHAPTER FIVE OF THIS CODE IN BUILDINGS COMPLYING WITH THE INTERNATIONAL FIRE CODE SHALL BE CONSIDERED IN COMPLIANCE WITH THE PROVISIONS OF THIS CODE.

302.3 EXISTING MATERIALS. MATERIALS ALREADY IN USE IN A BUILDING IN COMPLIANCE WITH REQUIREMENTS OR APPROVALS IN EFFECT AT THE TIME OF THEIR ERECTION OR INSTALLATION SHALL BE PERMITTED TO REMAIN IN USE UNLESS DETERMINED BY THE BUILDING OFFICIAL TO BE UNSAFE .

302.4 NEW AND REPLACEMENT MATERIALS. EXCEPT AS OTHERWISE REQUIRED OR PERMITTED BY THIS CODE, MATERIALS PERMITTED BY THE APPLICABLE CODE FOR NEW CONSTRUCTION SHALL BE USED. LIKE MATERIALS SHALL BE PERMITTED FOR REPAIRS AND ALTERATIONS, PROVIDED THAT NO UNSAFE CONDITION IS CREATED. HAZARDOUS MATERIALS SHALL NOT BE USED WHERE THE CODE FOR NEW CONSTRUCTION WOULD NOT PERMIT THEIR USE IN BUILDINGS OF SIMILAR OCCUPANCY, PURPOSE AND LOCATION.

SECTION 402 ADDITIONS.

402.1 GENERAL. ADDITIONS TO ANY BUILDING OR STRUCTURE SHALL COMPLY WITH THE REQUIREMENTS OF THE INTERNATIONAL BUILDING CODE FOR NEW CONSTRUCTION. ALTERATIONS TO THE EXISTING BUILDING OR STRUCTURE SHALL BE MADE TO ENSURE THAT THE EXISTING OR STRUCTURE TOGETHER WITH THE ADDITION ARE NO LESS CONFORMING TO THE PROVISIONS OF THE INTERNATIONAL BUILDING CODE THAN THE EXISTING BUILDING OR STRUCTURE WAS PRIOR TO THE ADDITION. AN EXISTING BUILDING TOGETHER WITH ITS ADDITIONS SHALL COMPLY WITH THE HEIGHT AND AREA PROVISIONS OF CHAPTER FIVE OF THE INTERNATIONAL BUILDING CODE.

402.3 EXISTING STRUCTURAL ELEMENTS CARRYING GRAVITY LOAD. ANY EXISTING GRAVITY LOAD-CARRYING STRUCTURAL ELEMENT FOR WHICH AN ADDITION AND ITS RELATED ALTERATIONS CAUSE AN INCREASE IN DESIGN GRAVITY LOAD OF MORE THAN FIVE PERCENT SHALL BE STRENGTHENED, SUPPLEMENTED, REPLACED OR OTHERWISE ALTERED AS NEEDED TO CARRY THE INCREASED GRAVITY LOAD REQUIRED BY THE INTERNATIONAL BUILDING CODE FOR NEW STRUCTURES. ANY EXISTING GRAVITY LOAD-CARRYING STRUCTURAL ELEMENT WHOSE GRAVITY LOAD-CARRYING CAPACITY IS DECREASED SHALL BE CONSIDERED AN ALTERED ELEMENT SUBJECT SUBJECTED TO THE REQUIREMENTS OF SECTION 403.3. ANY EXISTING ELEMENT THAT WILL FORM PART OF THE LATERAL LOAD PATH FOR ANY PART OF THE ADDITION SHALL BE CONSIDERED AN EXISTING LATERAL LOAD-CARRYING STRUCTURAL ELEMENT SUBJECT SUBJECTED TO THE REQUIREMENTS OF SECTION 402.4.

402.3.1 DESIGN LIVE LOAD. WHERE THE ADDITION DOES NOT RESULT IN INCREASED DESIGN LIVE LOAD, EXISTING GRAVITY LOAD-CARRYING STRUCTURAL ELEMENTS SHALL BE PERMITTED TO BE EVALUATED AND DESIGNED FOR LIVE LOADS APPROVED PRIOR TO THE ADDITION. IF THE APPROVED LIVE LOAD IS LESS THAN THAT REQUIRED BY SECTION 1607 OF THE INTERNATIONAL BUILDING CODE, THE AREA DESIGNATED FOR THE NONCONFORMING LIVE LOAD SHALL BE POSTED WITH PLACARDS OF APPROVED DESIGN INDICATING THE APPROVED LIVE LOAD. WHERE THE ADDITION DOES NOT RESULT IN INCREASED DESIGN LIVE LOAD, THE LIVE LOAD REQUIRED BY SECTION 1607 OF THE INTERNATIONAL BUILDING CODE SHALL BE USED.

402.4 EXISTING STRUCTURAL ELEMENTS CARRYING LATERAL LOADS. WHERE THE ADDITION IS STRUCTURALLY INDEPENDENT OF THE EXISTING STRUCTURE, EXISTING LATERAL LOAD-CARRYING STRUCTURAL ELEMENTS SHALL BE PERMITTED TO REMAIN UNALTERED. WHERE THE ADDITION IS NOT STRUCTURALLY INDEPENDENT OF THE EXISTING STRUCTURE, THE EXISTING STRUCTURE AND ITS ADDITION ACTING TOGETHER AS A SINGLE STRUCTURE SHALL BE SHOWN TO MEET THE REQUIREMENTS OF SECTION 1609 AND 1613 OF THE INTERNATIONAL BUILDING CODE. FOR PURPOSES OF THIS SECTION, COMPLIANCE WITH ASCE 41,USING A TIER 3 PROCEDURE AND THE TWO-LEVEL PERFORMANCE OBJECTIVE IN TABLE 301.1.4.1 FOR THE APPLICABLE RISK CATEGORY, SHALL BE DEEMED TO MEET THE REQUIREMENTS OF SECTION 1613.

403.1 GENERAL. ALTERATIONS TO ANY BUILDING OR STRUCTURE SHALL COMPLY WITH THE REQUIREMENTS OF THE INTERNATIONAL BUILDING CODE FOR NEW CONSTRUCTION. ALTERATIONS SHALL BE SUCH THAT THE EXISTING BUILDING OR STRUCTURE IS NO LESS CONFORMING TO THE PROVISIONS OF THE INTERNATIONAL BUILDING CODE THAN THE EXISTING BUILDING OR STRUCTURE WAS PRIOR TO THE ALTERATION.

403.3 EXISTING STRUCTURAL ELEMENTS CARRYING GRAVITY LOAD. ANY EXISTING GRAVITY LOAD-CARRYING STRUCTURAL ELEMENT FOR WHICH AN ALTERATIONS CAUSE AN INCREASE IN DESIGN GRAVITY LOAD OF MORE THAN FIVE PERCENT SHALL BE STRENGTHENED, SUPPLEMENTED, REPLACED OR OTHERWISE ALTERED AS NEEDED TO CARRY THE INCREASED GRAVITY LOAD REQUIRED BY THE INTERNATIONAL BUILDING CODE FOR NEW STRUCTURES. ANY EXISTING GRAVITY LOAD-CARRYING STRUCTURAL ELEMENT WHOSE GRAVITY LOAD-CARRYING CAPACITY IS DECREASED AS PART OF THE ALTERATION SHALL BE SHOWN TO HAVE THE CAPACITY TO RESIST THE APPLICABLE DESIGN GRAVITY LOADS REQUIRED BY THE INTERNATIONAL BUILDING CODE FOR NEW STRUCTURES.

403.3.1 DESIGN LIVE LOAD. WHERE THE ALTERATION DOES NOT RESULT IN INCREASED DESIGN LIVE LOAD, EXISTING GRAVITY LOAD-CARRYING STRUCTURAL ELEMENTS SHALL BE PERMITTED TO BE EVALUATED AND DESIGNED FOR LIVE LOADS APPROVED PRIOR TO THE ALTERATION. IF THE APPROVED LIVE LOAD IS LESS THAN THAT REQUIRED BY SECTION 1607 OF THE INTERNATIONAL BUILDING CODE, THE AREA DESIGNATED FOR THE NONCONFORMING LIVE LOAD SHALL BE POSTED WITH PLACARDS OF APPROVED DESIGN INDICATING THE APPROVED LIVE LOAD. WHERE THE ALTERATION DOES NOT RESULT IN INCREASED DESIGN LIVE LOAD, THE LIVE LOAD REQUIRED BY SECTION 1607 OF THE INTERNATIONAL BUILDING CODE SHALL BE USED.

403.4 EXISTING STRUCTURAL ELEMENTS CARRYING LATERAL LOADS. WHERE THE ALTERATION IS STRUCTURALLY INDEPENDENT OF THE EXISTING STRUCTURE, EXISTING LATERAL LOAD-CARRYING STRUCTURAL ELEMENTS SHALL BE PERMITTED TO REMAIN UNALTERED. WHERE THE ALTERATION IS NOT STRUCTURALLY INDEPENDENT OF THE EXISTING STRUCTURE, THE EXISTING STRUCTURE AND ITS ADDITION ACTING TOGETHER AS A SINGLE STRUCTURE SHALL BE SHOWN TO MEET THE REQUIREMENTS OF SECTION 1609 AND 1613 OF THE INTERNATIONAL BUILDING CODE. FOR PURPOSES OF THIS SECTION, COMPLIANCE WITH ASCE 41,USING A TIER 3 PROCEDURE AND THE TWO-LEVEL PERFORMANCE OBJECTIVE IN TABLE 301.1.4.1 FOR THE APPLICABLE RISK CATEGORY, SHALL BE DEEMED TO MEET THE REQUIREMENTS OF SECTION 1613 OF THE INTERNATIONAL BUILDING CODE.

**ALTERATION - LEVEL 1** INCLUDE THE REMOVAL AND REPLACEMENT OR THE COVERING OF EXISTING MATERIALS, ELEMENTS, EQUIPMENT, OR FIXTURES USING NEW MATERIALS, ELEMENTS, EQUIPMENT, OR FIXTURES THAT SERVE THE SAME PURPOSE.

**ALTERATION - LEVEL 2** INCLUDE THE ADDITION OR ELIMINATION OF ANY DOOR OR WINDOW, THE RECONFIGURATION OR EXTENSION OF ANY SYSTEM, OR THE INSTALLATION OF ANY ADDITIONAL EQUIPMENT, AND SHALL APPLY WHERE THE WORK IS EQUAL TO OR LESS THAN 50% OF THE BUILDING AREA.

THIS BUILDING'S CONSTRUCTION IS TYPE IIB.

THIS BUILDING'S OCCUPANCY IS E.

THIS BUILDING'S IS SPRINKLERED.

THERE WILL NOT BE ANY MODIFACATIONS TO THE HOOD SYSTEMS IN THE KITCHENS BEYOND REPLACEMENT OF MOTOR FOR LIKE KIND IF NEEDED.

THE BUILDING WILL NOT HAVE ADDITIONAL SQUARE FOOTAGE AS PART OF THE WORK.

NEW CONSTRUCTION ELEMENTS, COMPONENTS, SYSTEMS AND SPACES SHALL COMPLY WITH THE REQUIREMENTS OF THE INTERNATIONAL BUILDING CODES

2 CODE ANALYSIS

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

V

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT

SULLIVAN ELEMENTARY SCHOOL
17828 WINDING WATERS LANE
SUGAR LAND, TX 77479

SEAL

REGISTERED ARCHITECT
ROBERT A. MEYER
22451
STATE OF TEXAS

7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

OVERALL FLOOR PLAN

v-A.201

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\V-Sullivan ES\v-A.201 OVERALL FLOOR PLAN.dwg Jul 23, 2025 - 5:10pm




## 1 CAFETERIA FLOOR PLAN

SCALE: 1/8" = 1'-0"

## FLOOR PLAN - GENERAL NOTES

1. REFER TO SHEET A00-01 FOR GENERAL NOTES. GENERAL NOTES APPLY TO ALL SCHOOLS.
2. SULLIVAN HAS NO KITCHEN WORK SCHEDULED IN THIS PROJECT. THE CAFETERIA AND STAGE AREAS, WITH SOME SMALL AREA (250 SF) OF EXTERIOR PAINTING WILL BE REQUIRED. SEE FLOOR PLAN AND FINISH PLAN..

## FLOOR PLAN - KEYED NOTES


01 REPAIR BROKEN WOOD NOSINGS / RISERS ON STEPS LEADING TO STAGE AREA. MATCH SPECIES AND FINISH. APPROX. 20 LF WILL BE REPLACED.

02 REMOVE EXISTING TRACK, PANELS, AND A PORTION OF THE HEAD AND SOFFIT SIDEWALLS.

03 EXTERIOR PAINTING REQUIRED FOR APPROX. 250 SF OF STUCCO WALL SURFACE.


04 INSTALL NEW POWERED MOVEABLE PARTITION SYSTEM.
- a. THE NEW PANEL WILL BE LOWER TO ACCOMODATE DRIVE AND TRACK MECHANISMS PLACED IN THE EXSITING SOFFIT
- b. 208/230V 3PH 60 HZ. 1 HP MOTOR SHALL BE INSTALLED ABOVE EXISTING STACK SPACE. CONFIRM THIS SIZE WITH MANUFACTURER.
- c. RUN POWER FROM NEAREST AVAILABLE POWER PANEL - SEE ELECTRICAL.

## 3 FLOOR PLAN NOTES





## 4 SECTION AT FOLDING PARTITION

SCALE: 1-1/2" = 1'-0"




## 5 CAFETERIA SIDE OF WALL (NEW CONSTRUCTION)

SCALE: 3/16 = 1'-0"




## 6 GYM SIDE OF WALL (NEW CONSTRUCTION)

SCALE: 3/16" = 1'-0"

F:\2023\23-35 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\V-Sullivan ES\v-A.301 CAFETERIA PLAN.dwg, Jul 23, 2025, 5:10pm

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

V

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SULLIVAN ELEMENTARY SCHOOL
17828 WINDING WATERS LANE
SUGAR LAND, TX 77479


SEAL
REGISTERED ARCHITECT
STATE OF TEXAS
22651
7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

CAFETERIA PLAN

v-A.301




1 FINISH FLOOR PLAN
SCALE: 1/8" = 1'-0"

## PAINT COLOR SCHEDULE

UNLESS OTHERWISE INDICATED FIELD COLOR IS PT-1 TO MATCH EXISTING COLOR AND SHEEN.

FOR PRICING, USE
SW 7014 EIDER WHITE, INTERIOR/EXTERIOR PAINT
FOR ACCENT COLORS, SUBMIT SELECTION SAMPLES TO EXISTING ACCENT COLORS.

## WALL PAINT FINISH LEGEND

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

V

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SULLIVAN ELEMENTARY SCHOOL
17828 WINDING WATERS LANE
SUGAR LAND, TX 77479

SEAL
REGISTERED ARCHITECT
MICHAEL A. WEAVER
#26651
STATE OF TEXAS
7/15/2025


MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

FINISH FLOOR PLAN

v-A.501

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings\V-Sullivan ES\v-A.501 FINISH FLOOR PLAN.dwg Jul 23, 2025 - 5:11pm




## 2 OVERALL FLOOR PLAN

SCALE: 1" = 60'- 0"

## SYMBOL LEGEND

| | |
|---|---|
| ⓓ/ⓓ/ⓓ: | SIMPLEX/DUPLEX/QUAD – 5361/2 REC |
| GFI ⓓ | DUPLEX W/ GFCI PROTECTION–P&S 2097 |
| J | J–BOX |
| | CEILING MOUNTED J–BOX |
| M | MOTOR |
| | HEAVY DUTY, NON–FUSED DISCONNECT. MIN RATING OF CIRCUIT OCPD/VOLTAGE. |
| | ELECTRICAL PANEL |
| | HOMERUN TO CIRCUIT NOTED |
| E | EXISTING DEVICES TO REMAIN |
| R | EXISTING DEVICES TO BE RELOCATED |
| D | EXISTING DEVICES TO BE DEMO/REMOVED |
| RDP | EXISTING DEVICES TO BE REPLACED |
| S | INDICATES SURFACE MOUNTED |
| SR | INDICATES SURFACE RACEWAY |
| * | INDICATES ABOVE COUNTER DEVICE |
| + | INDICATES DEVICE AT +30–60" |
| ++ | INDICATES DEVICE AT +80–96" |
| CLG | INDICATES DEVICES MOUNTED IN CEILING |
| WP | INDICATES WEATHERPROOF COVER |
| 3R | INDICATES 3R RATED DEVICE |
| (E)LA–X | CONNECT(ED) TO EXIST CIRCUIT LA–X |
| (D)LA–X | DEMO PORTION OF EXIST CIRCUIT LA–X |
| (N)LA–X | CONNECT(ED) TO NEW CIRCUIT LA–X |

GENERAL ELECTRICAL NOTES:

1. INSTALL SYSTEM IN ACCORDANCE WITH THE NATIONAL ELECTRIC CODE AS ADOPTED BY THE LOCAL AUTHORITY HAVING JURISDICTION INCLUDING ALL AMENDMENTS.
2. PROVIDE CONDUIT FOR ALL DEVICES INSTALLED IN WALLS.
   - 2.A. 3/4"C. FOR POWER AND 1"C. FOR LOW VOLTAGE/DATA UNLESS NOTED OTHERWISE.
   - 2.B. PROVIDE PROTECTIVE BUSHING ON END OF ALL LOW VOLTAGE CONDUITS.
   - 2.C. ALL ELECTRICAL HOMERUNS SHALL BE IN CONDUIT, MIN 3/4"C.
   - 2.D. USE INSULATED THROAT FITTINGS FOR CONNECTIONS TO HOUSINGS, BOXES, ENCLOSURES, ETC.
   - 2.E. MAX LENGTH FOR FLEX CONDUIT SHALL BE 6FT AND MIN. SIZE SHALL BE 1/2". ALL FLEX CONDUIT SHALL BE LISTED FOR GROUNDING.
3. CONDUIT TYPES:
   - 3.A. INSIDE BUILDINGS: GALVANIZED STEEL EMT.
     - 3.A.A. ALL LOW VOLTAGE CABLING SHALL BE INSTALLED IN CONDUIT IN EXPOSED CEILING AREAS. ROUTE TO NEAREST ACCESSIBLE CEILING WITH CONTINUOUS PATHWAYS TO LOW VOLTAGE SOURCE/DEVICE.
     - 3.A.B. ALL LOW VOLTAGE CABLING SHALL BE INSTALLED IN CONDUIT ABOVE INACCESSIBLE CEILINGS. ROUTE TO NEAREST ACCESSIBLE CEILING WITH CONTINUOUS PATHWAYS TO LOW VOLTAGE SOURCE/DEVICE.
   - 3.B. NO MC CABLE SHALL BE ALLOWED.
   - 3.C. PROVIDE FLEXIBLE CONNECTIONS TO MOTORS, PUMPS, TRANSFORMERS, OR SIMILAR EQUIPMENT.
4. PROVIDE GALVANIZED STEEL, ONE–PIECE CONSTRUCTION, OUTLET BOXES IN ALL CASES SUITABLE FOR INTENDED USE.
   - 4.A. BOXES OUTSIDE SHALL BE STEEL, NEMA 3 TYPE.
   - 4.B. PROVIDE CEILING BRACKET TO SUPPORT CEILING MOUNTED DEVICES FROM CEILING TEES.
5. 20 AMP. SINGLE PHASE BRANCH CIRCUITS SERVING LIGHTING AND GENERAL RECEPTACLES MAY BE GROUPED IN A SINGLE RACEWAY PROVIDED A NEUTRAL CONDUCTOR IS INSTALLED FOR EACH CIRCUIT REQUIRING A NEUTRAL.
   - 5.A. DO NOT INSTALL MORE THAN FOUR CURRENT CARRYING CONDUCTORS IN A CONDUIT EXCEPT SIX #12 OR #10 CURRENT CARRYING CONDUCTORS MAY BE INSTALLED IN 3/4" OR LARGER CONDUIT FOR 20A CIRCUITS.
   - 5.B. DO NOT INSTALL 480/277 VOLT CONDUCTORS IN THE SAME CONDUIT WITH 240/208/120 VOLT CONDUCTORS.
   - 5.C. DO NOT COMBINE NEUTRALS. PROVIDE DEDICATED NEUTRALS FOR EACH BRANCH CIRCUIT.
   - 5.D. MULTIPLE DEVICES ON A CIRCUIT SUCH AS RECEPTACLES SHALL BE WIRED WITH A PIGTAIL SO THE DEVICE DOES NOT PROVIDE THE CONTINUITY PATH. FEED THROUGH CONNECTIONS FOR GFCI RECEPTACLES SHALL NOT BE USED FOR PROTECTION OF DOWNSTREAM DEVICES.
6. PROVIDE GREEN GROUND WIRE WITH ALL CIRCUITS SIZED PER NEC. BOND GREEN GROUND WIRE TO EACH END OF CONDUIT.
7. PROVIDE J–BOXES, CONDUIT AND SLEEVES THRU ALL FIRE WALLS FOR DATA, TELEPHONE, SECURITY, FIRE ALARM, SOUND SYSTEM, LOW VOLTAGE WIRING, ETC. PROVIDE PROTECTIVE BUSHINGS ON ENDS OF ALL LOW VOLTAGE CONDUITS.
8. PROVIDE PULL BOXES, JUNCTION BOXES, WIRING TROUGHS AND CABINETS WHEREVER REQUIRED FOR PROPER INSTALLATION OF VARIOUS ELECTRICAL SYSTEMS. ALL JUNCTION/PULL BOXES INSTALLED ABOVE ACCESSIBLE CEILINGS SHALL BE MOUNTED SO THAT THE ACCESS PANEL IS NO HIGHER THAN 18" ABOVE THE CEILING.
9. PROVIDE CIRCUIT LABELS IN PERMANENT MARKER ON ALL NEW AND EXISTING J–BOX COVERS UTILIZED IN THE AREA OF RENOVATION.
10. PROVIDE CIRCUIT LABEL ON ALL ABOVE CEILING J–BOXES, EQUIPMENT, ETC. IDENTIFYING THE CIRCUITS CONTAINED/CONNECTED.
11. ALL WIRING SHALL BE 600 VOLT, SOFT DRAWN ANNEALED COPPER, 98% CONDUCTIVITY, CONTINUOUS FROM OUTLET TO OUTLET. MINIMUM WIRE SIZE #12.
    - 11.A. TYPICAL BUILDING WIRE SHALL BE STRANDED TYPE THHN, THWN–2 (WET RATED FOR 90?C), OR XHHW–2. MINIMUM WIRE SIZE SHALL BE #12.
    - 11.B. ALL BUILDING WIRE SHALL BE COLOR CODED WITH THE SAME COLOR CONNECTED TO THE SAME UNGROUNDED PHASE THROUGHOUT THE INSTALLATION MATCHING THE EXISTING BUILDING COLOR CODE SCHEME.
12. WHERE PORTIONS OF INTERIOR RACEWAY SYSTEM ARE EXPOSED TO WIDELY DIFFERENT TEMPERATURES, PROVIDE AIR SEAL PER NEC TO PREVENT CIRCULATION OF AIR FROM WARMER TO COOLER SECTIONS.
13. DRAWINGS, SCHEDULES, NOTES, AND DETAILS ARE INTENDED TO BE COMPLIMENTARY. ANY WORK DESCRIBED IN ANY OF THEM, WILL BE WORK REQUIRED UNDER THIS CONTRACT. WHERE THERE IS A CONFLICT BETWEEN DIFFERENT PORTIONS OF THE DESIGN DOCUMENTS IT SHALL BE CLARIFIED BY RFI. BIDDING CLARIFICATION PRIOR TO BIDDING THE MOST EXPENSIVE OPTION SHALL BE INCLUDED AND CLARIFICATION SHALL BE MADE DURING CONSTRUCTION.
14. SHOULD ANY WORK REQUIRED BY THE DRAWINGS AND SPECIFICATIONS BE IN VIOLATION OF ANY FEDERAL, STATE, COUNTY OR CITY LAWS, ORDINANCE OR REGULATION, THOSE LAWS AND REGULATIONS SHALL PREVAIL, AND SHALL BE COMPLIED WITH BY THE CONTRACTOR AS A PART OF THIS WORK WITH NO EXTRA COMPENSATION.
15. ALL MATERIAL MUST BE NEW AND OF GOOD QUALITY AND SHALL BEAR THE STAMP OF APPROVAL OF THE UNDERWRITERS' LABORATORIES, INC. (U.L.).

GENERAL RENOVATION AND REMODELING NOTES:

1. THESE ELECTRICAL DRAWINGS ONLY SHOW SOME EXISTING ELECTRICAL PANELS, DEVICES AND LIGHT FIXTURES IN AREAS OF RENOVATION. ALL OTHER ELECTRICAL EQUIPMENT, WIRING DEVICES, LOW VOLTAGE SYSTEMS, J–BOXES AND CONDUITS SHALL BE LOCATED AND FIELD VERIFIED BY CONTRACTOR.
2. ALL REMOVED DEVICES SHALL BE OFFERED TO THE OWNER AS SALVAGE.
3. RELOCATE CONDUIT AS NECESSARY TO ALLOW NEW OR MODIFIED CONSTRUCTION. RESUPPORT EXISTING CABLING/CONDUIT TO REMAIN TO MEET CURRENTLY ADOPTED CODE REQUIREMENTS. REMOVE ALL ABANDONED CONDUIT AND WIRE. REPAIR EXISTING ELECTRICAL SYSTEMS DAMAGED BY CONSTRUCTION ACTIVITIES.
4. ANY DAMAGE TO EXISTING BUILDING, ELECTRICAL EQUIPMENT, WIRING DEVICES, CONDUIT, WIRING, ETC. SHALL BE REPLACED BY THE CONTRACTOR AT NO COST TO THE OWNER. ALL MATERIALS USED FOR THE REPLACEMENT MUST MEET RENOVATION PROJECT STANDARDS.
5. ELECTRICAL CONTRACTOR SHALL BEGIN FIELD VERIFYING ALL EXISTING BRANCH CIRCUITS FOR EXISTING AREAS TO BE RENOVATED IMMEDIATELY AFTER THE CONTRACT IS ISSUED.
6. ELECTRICAL CONTRACTOR SHALL FIELD VERIFY EXISTING CIRCUITS WITH OWNER'S MAINTENANCE PERSONNEL AFTER NORMAL BUILDING HOURS AS REQUIRED.
7. ANY CIRCUIT OR PARTIAL CIRCUIT TO REMAIN OR BE REUSED SHALL REMAIN ACTIVE.
8. ELECTRICAL CONTRACTOR SHALL INCLUDE COST RELATED TO FIELD VERIFY EXISTING CIRCUITS IN BASE PROPOSAL.
9. FIND AND RECORD ALL EXISTING DEVICES IN CEILINGS, WALLS AND CASEWORK IN AREAS TO BE RENOVATED. PROVIDE A COPY OF THE FIELD VERIFIED DEVICE DRAWINGS TO OWNER PRIOR TO BEGINNING WORK.
10. AT THE END OF THE PROJECT PROVIDE A NEW TYPEWRITTEN AS–BUILT PANEL SCHEDULE FOR ALL PANELS WITH CIRCUITS ADDED, REMOVED, OR MODIFIED AS PART OF THE PROJECT USING BUILDING ROOM NUMBERS.





## 3 PARTIAL ELECTRICAL RISER - SULLIVAN ELEMENTARY

NO SCALE

NOTES:

1. FIELD VERIFY ALL EXISTING ELECTRICAL PANELS AND FEEDERS SHOWN ON DRAWINGS.
2. REF ELECTRICAL FLOOR PLANS FOR PANEL LOCATIONS.
3. ALL OUTAGES SHALL BE SCHEDULED/CONFIRMED IN WRITING WITH THE OWNER A MINIMUM OF TWO WEEKS PRIOR TO ANY OUTAGE.
4. AT THE END OF THE PROJECT PROVIDE A NEW TYPEWRITTEN PANEL SCHEDULE USING BUILDING ROOM NUMBERS FOR ALL PANELS WITH CIRCUITS ADDED, REMOVED, OR MODIFIED AS PART OF THE PROJECT.
5. REFERENCE PANEL SCHEDULES AND SHORT CIRCUIT TABLE FOR AIC AND SCCR VALUES.




## 1 ELECTRICAL RENOVATION PLAN

SCALE: 1/8" = 1'- 0"

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

V

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
SULLIVAN ELEMENTARY SCHOOL
17828 WINDING WATERS LANE
SUGAR LAND, TX 77479

SEAL

STATE OF TEXAS · GEORGE L. STANTON · 38582 · REGISTERED · PROFESSIONAL ENGINEER
07.18.2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL FLOOR PLAN & SCHEDULES

v-E.200

STANTON ENGINEERING GROUP
INFO@STANTON-ENGR.COM (713) 300-6080
TEXAS ENG. FIRM REG NO. F-23337 © 2025 ALL RIGHTS RESERVED
1300 W. SAM HOUSTON PARKWAY S., SUITE 125, HOUSTON, TX 77042

## AUDIO/VISUAL MULTIMEDIA LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| A## V## | WALL AV ROUGH-IN DETAIL |
| A## V## | CEILING AV ROUGH-IN DETAIL |
| A## V## | FLOOR AV ROUGH-IN DETAIL |
| IWB IWB | INTERACTIVE WHITE BOARD - WALL - CEILING |
| PJ PJ | MULTIMEDIA PROJECTOR |
| FP# FP# | MULTIMEDIA FLAT PANEL DISPLAY |
| S S | LOUDSPEAKER, WALL MOUNTED AND CEILING MOUNTED RESPECTIVELY - # INDICATES TYPE |
| CP# | CONTROL PANEL |
| TP# | TOUCH PANEL |
| M | MICROPHONE, CEILING MOUNTED - # INDICATES TYPE |
| VC | VOLUME CONTROL |
| WB | WALL BOX ENCLOSURE |
| D1 A1 | D1 = DIGITAL SINGLE SIDED CLOCK / A1 = ANALOG SINGLE SIDED CLOCK |
| D2 A2 | D2 = DIGITAL DOUBLE SIDED CLOCK / A2 = ANALOG DOUBLE SIDED CLOCK |
| ENC | CEILING AV ENCLOSURE |
| C C | PRESENTATION CAMERA - CEILING - WALL MOUNTED |

## PREMISE SECURITY LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| CR | CARD READER |
| CR M | CARD READER MULLION |
| KP | INTRUSION DETECTION KEYPAD |
| IC | INTERCOM (1 DATA CABLE) |
| IC MS | INTERCOM MASTER STATION (1 DATA CABLE) |
| PB | PANIC/DURESS BUTTON |
| LD | LOCK DOWN BUTTON |
| MD | MOTION DETECTOR |
| GB | ACCOUSTICAL GLASS BREAK SENSOR |
| BM | BIOMETRIC READER |
| RX | REQUEST TO EXIT - SURFACE PIR |
| KS | KEY SWITCH |
| LA | LOCAL ALARM SOUNDER |
| RG | RED/GREEN INDICATOR LIGHT |
| DB | DOORBELL |
| DH | MAGNETIC DOOR HOLD |
| DR | DOOR RELEASE |
| RX | REQUEST TO EXIT - INTEGRAL TO DOOR HARDWARE |
| DC | DOOR CONTACT / MONITOR |
| ES EL EH | ELECTRIFIED STRIKE - ELECTRIFIED LATCH - ELECTRIFIED HARDWARE (REFER TO SCHEDULES) |
| C C | STANDARD IP SURVEILLANCE CAMERA, (1) CABLE |
| C C C | 180° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° FISHEYE LENS CAMERA |
| IR | IR ILLUMINATOR |

## STRUCTURED CABLING LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF DATA CABLE(S)/JACK(S) |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) |
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| W | WALL MOUNT PHONE (1 CABLE/JACK) |
| W | WALL MOUNT PHONE, SURFACE MOUNT (1 CABLE/JACK) |
| # | FLOOR MOUNTED OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| #/# | FLOOR MOUNTED OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| # | CEILING MOUNTED DATA OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) |
| AP# | CEILING MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| AP# | WALL MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| | CABLING SLEEVE(S) |
| | TYPICAL LADDER RACK |
| | TYPICAL CABLE TRAY, BASKET STYLE |

## GENERAL ANNOTATION LEGEND


| SYMBOL | DESCRIPTION |
|---|---|
| MER | MAIN EQUIPMENT ROOM |
| TR | TELECOMMUNICATION ROOM |
| MDF | MAIN DISTRIBUTION FRAME |
| IDF | INTERMEDIATE DISTRIBUTION FRAME |
| ETR | EXISTING TO REMAIN |
| PBO | PROVIDED BY OTHERS |
| AFF | ABOVE FINISHED FLOOR |
| AFG | ABOVE FINISHED GRADE |
| AC | ABOVE COUNTER |
| EC | ELECTRICAL CONTRACTOR |
| PSC | PREMISE SECURITY CONTRACTOR |
| SCC | STRUCTURAL CABLING CONTRACTOR |
| AVC | AV/MULTIMEDIA CONTRACTOR |
| UNO | UNLESS NOTED OTHERWISE |
| ACS | ACCESS CONTROL SYSTEM |
| VSS | VIDEO SURVEILLANCE SYSTEM |

## TECHNOLOGY - GENERAL NOTES

1. EACH KEYNOTE MAY NOT BE UTILIZED ON EVERY SHEET.
2. ALL CONDUIT MEASUREMENTS REFER TO STANDARD CONDUIT TRADE SIZES.
3. ALL CABLES SHALL BE CONCEALED.
4. EACH CONTRACTOR SHALL PROVIDE AND INSTALL ALL NECESSARY SLEEVES, WHETHER OR NOT SPECIFICALLY NOTED ON PROJECT DRAWINGS. ALL SLEEVES SHALL BE 2" UNLESS NOTED OTHERWISE ON THE DRAWINGS. CABLE FILL PERCENTAGE SHALL COMPLY WITH NEC.
5. DEVICE LOCATIONS ARE APPROXIMATE. CONTRACTOR SHALL REVIEW CONDITIONS AND COORDINATE WITH OTHER TRADES AS NECESSARY FOR EXACT PLACEMENT.

## TECHNOLOGY SYMBOLS LEGEND

NOT ALL SYMBOLS ARE USED




TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

V

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Sullivan Elementary School
17828 Winding Waters Ln, Sugar Land, TX 77479

SEAL




07-18-25

MVA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY - TITLE SHEET

v-TN000

## TECHNOLOGY KEYNOTES

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.




1 BACKGROUND V (SULLIVAN ES)
SCALE: 1" = 20'-0"

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

V

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Sullivan Elementary School
17828 Winding Waters Ln, Sugar Land, TX 77479

SEAL


REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256657
EXPIRES 12-31-27
RCDD

07-18-25

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Sullivan ES - OVERALL

v-TN.100




1 SULLIVAN - REFLECTED CEILING PLAN
SCALE: 3/16" = 1'-0"

**TECHNOLOGY KEYNOTES**

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

V

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Sullivan Elementary School
17828 Winding Waters Ln, Sugar Land, TX 77479

SEAL

BICSI REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256657
EXPIRES 12-31-27
RCDD

07-18-25

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Sullivan ES - KITCHEN

v-TN.101


TRUENORTH A PMY COMPANY

**GENERAL NOTE**


1. FACE PLATE DETAIL FOR OUTLET CONFIGURATION PURPOSES ONLY. CONTRACTOR TO SELECT TYPE OF FACE PLATE TO MATCH CONNECTIVITY HARDWARE, FLOOR BOX AND/OR MODULAR FURNITURE OPENING.





1 DATA ROUGH-IN DETAILS
SCALE: NS




2 TYPICAL CABLING SLEEVE
SCALE: NTS




3 PANDUIT J-HOOK DETAIL
SCALE: NTS




4 LABELING & CABLING SCHEMES
SCALE: NTS




5 CABLE PATHWAY CROSS SECTION
SCALE: NTS




6 DROPPED CEILING MOUNTING DETAIL
SCALE: NS




7 I-JOIST MOUNTING DETAIL
SCALE: NS




8 BAR JOIST MOUNTING DETAIL
SCALE: NS

| CAMERA TYPE | MANUFACTURER | MODEL NUMBER | GENERAL DESCRIPTION |
|---|---|---|---|
| C1 | iPro | WV-S8574L | 4x4K (33MP) EXTERIOR MULTI-SENSOR - PARKING LOTS, STADIUM |
| C2 | iPro | WV-S8544L | 4x4MP (16MP) EXTERIOR MULTI-SENSOR - BUILDING PERIMETER |
| C3 | iPro | WV-S25500-V3LN | 5MP EXTERIOR VANDAL DOME |
| C4 | iPro | WV-S22500-V3L | 5MP INTERIOR VANDAL DOME - CORR., COMMON, SPED |
| C5 | iPro | WV-S4156A | 5MP 360 (FISHEYE) - STAIRWELLS |

9 CAMERA SCHEDULE
SCALE: NTS

| Symbol | Purpose | Size | Mount | Backbox | Notes |
|---|---|---|---|---|---|
| FP1 | Digital Signage/Menu Boards | +49" | Ceiling Pole | N/A | Data and Power Outlets on ceiling |

10 DISPLAY SCHEDULE
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

V

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Sullivan Elementary School
17828 Winding Waters Ln, Sugar Land, TX 77479

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256687
EXPIRES 12-31-27

07-18-25



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - Sullivan ES - DETAILS


v-TN.500

GENERAL NOTES:


1. REFER TO SECURITY SCHEDULE AND WRITTEN SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
2. ALL MOUNTING DETAILS ARE REFERENCE FOR ALL FIXED DOME, 180°, 360°, PTZ, AND "BULLET/BOX" CAMERAS.





1 TYPICAL CAMERA INSTALLATION SECTION DETAIL
SCALE: NS




6 WALL MOUNTED CAMERA DETAIL
SCALE: NS




4 TILE BRIDGE DETAIL
SCALE: NS





5 CEILING MOUNTED CAMERA DETAIL
SCALE: NS


ACCESS CONROL DETAILS AND GENERAL NOTES:

1. CONDUIT ROUGH-IN IS A GUIDE FOR WHAT WILL BE REQUIRED FOR EACH DOOR. AS DOOR COMPONENTS CHANGE, EXACT CONDUIT LOCATION WILL ALSO NEED TO BE ADJUSTED.


2. PROTECT EXISTING-TO-REMAIN ACCESS CONTROL DEVICES AND CABLE THROUGHOUT RENOVATION WORK. IF CABLE AND/OR DEVICES ARE DAMAGED, SECURITY CONTRACTOR TO REPLACE WITH NEW.




1 ACCESS CONTROL - WIRING DETAIL - EXIT DEVICE W/ BUILT-IN REX
SCALE: NTS




2 ACCESS CONTROL - STEEL/HOLLOW METAL DOOR.
SCALE: NTS




KP PB LD

3 ROUGH-IN DETAILS: KP, PB, LD
SCALE: NTS

TRUENORTH A PMT COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

V

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Sullivan Elementary School
17828 Winding Waters Ln, Sugar Land, TX 77479

SEAL

REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256857
EXPIRES 12-31-27

07-18-25


MVA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING
AND
PERMITTING
TECHNOLOGY - Sullivan ES - SECURITY DETAILS

v-TN.600

# FBISD BP013 KITCHEN RENOVATIONS ES

| Sheet List Table | |
|---|---|
| Sheet Number | Sheet Title |
| School: w-TOWNEWEST ES | |
| W-A.000 | COVER AND INDEX |
| w-TN-000 | TECHNOLOGY - INDEX SHEET |
| w-TN-100 | TECHNOLOGY - OVERALL |
| w-TN-101 | TECHNOLOGY - KITCHEN |
| w-TN-501 | TECHNOLOGY - DETAILS |
| w-TN-600 | TECHNOLOGY - SECURITY DETAILS |




FORT BEND INDEPENDENT SCHOOL DISTRICT 2023 BOND

ISSUED FOR PERMIT AND BIDDING - JULY 18, 2025

## FORT BEND INDEPENDENT SCHOOL DISTRICT

TOWNEWEST ELEMENTARY SCHOOL
13927 OLD RICHMOND ROAD, SUGAR LAND, TX 77498

## ADMINISTRATION

| | |
|---|---|
| DR. MARCELL SMITH | SUPERINTENDENT OF FBISD |
| DR. ANDRIA SCHUR, Ed.D. | CHIEF OF SCHOOLS |

## BOARD OF TRUSTEES

| | |
|---|---|
| KRISTIN K. TASSIN | PRESIDENT |
| RICK GARCIA | VICE PRESIDENT |
| DAVID HAMILTON | SECRETARY |
| ANGIE HANAN | BOARD MEMBER |
| ADAM SCHOOF | BOARD MEMBER |
| DR. SHIRLEY ROSE-GILLIAM | BOARD MEMBER |
| SONYA JONES | BOARD MEMBER |

## PROJECT DESIGN TEAM

PROGRAM MANAGEMENT
FBISD 2023 Bond Team
2323 Texas Parkway
Missouri City, TX 77489
Phone Number: 281-327-5481

ARCHITECT
MWA Architects
11767 Katy Freeway, Suite 430
Houston, Texas 77079
Phone Number: 713-782-8188

FOOD SERVICE
Food Design Professionals
26215 Oak Ridge Drive
The Woodlands, Texas 77380
Phone Number: 281-350-2323

MEP ENGINEERS
Stanton Engineering Group
1300 W. Sam Houston Pkwy South, Suite 121
Houston, Texas 77042
Phone Number: 713-300-9292

STRUCTURAL ENGINEER
Stanley Spurling & Hamilton
3301 Edloe Street, Suite 200
Houston, Texas 77027
Phone Number: 713-776-9433

W

## AUDIO/VISUAL MULTIMEDIA LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| A## V## | WALL AV ROUGH-IN DETAIL |
| A## V## | CEILING AV ROUGH-IN DETAIL |
| A## V## | FLOOR AV ROUGH-IN DETAIL |
| IWB IWB | INTERACTIVE WHITE BOARD - WALL - CEILING |
| PJ PJ | MULTIMEDIA PROJECTOR |
| FP# FP# | MULTIMEDIA FLAT PANEL DISPLAY |
| S S | LOUDSPEAKER, WALL MOUNTED AND CEILING MOUNTED RESPECTIVELY - # INDICATES TYPE |
| CP# | CONTROL PANEL |
| TP# | TOUCH PANEL |
| M | MICROPHONE, CEILING MOUNTED - # INDICATES TYPE |
| VC | VOLUME CONTROL |
| WB | WALL BOX ENCLOSURE |
| D1 A1 | D1 = DIGITAL SINGLE SIDED CLOCK / A1 = ANALOG SINGLE SIDED CLOCK |
| D2 A2 | D2 = DIGITAL DOUBLE SIDED CLOCK / A2 = ANALOG DOUBLE SIDED CLOCK |
| ENC | CEILING AV ENCLOSURE |
| C C | PRESENTATION CAMERA - CEILING - WALL MOUNTED |

## PREMISE SECURITY LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| CR | CARD READER |
| CR M | CARD READER MULLION |
| KP | INTRUSION DETECTION KEYPAD |
| IC | INTERCOM (1 DATA CABLE) |
| IC MS | INTERCOM MASTER STATION (1 DATA CABLE) |
| PB | PANIC/DURESS BUTTON |
| LD | LOCK DOWN BUTTON |
| MD | MOTION DETECTOR |
| GB | ACCOUSTICAL GLASS BREAK SENSOR |
| BM | BIOMETRIC READER |
| RX | REQUEST TO EXIT - SURFACE PIR |
| KS | KEY SWITCH |
| LA | LOCAL ALARM SOUNDER |
| RG | RED/GREEN INDICATOR LIGHT |
| DB | DOORBELL |
| DH | MAGNETIC DOOR HOLD |
| DR | DOOR RELEASE |
| RX | REQUEST TO EXIT - INTEGRAL TO DOOR HARDWARE |
| DC | DOOR CONTACT / MONITOR |
| ES EL EH | ELECTRIFIED STRIKE - ELECTRIFIED LATCH - ELECTRIFIED HARDWARE (REFER TO SCHEDULES) |
| C C | STANDARD IP SURVEILLANCE CAMERA, (1) CABLE |
| C C C | 180° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° MULTI-IMAGER IP SURVEILLANCE CAMERA, (1) CABLE |
| C | 360° FISHEYE LENS CAMERA |
| IR | IR ILLUMINATOR |

## STRUCTURED CABLING LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF DATA CABLE(S)/JACK(S) |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) |
| # | TELECOMMUNICATIONS OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| #/# | TELECOMMUNICATIONS OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S), SURFACE MOUNT |
| W | WALL MOUNT PHONE (1 CABLE/JACK) |
| W | WALL MOUNT PHONE, SURFACE MOUNT (1 CABLE/JACK) |
| # | FLOOR MOUNTED OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| #/# | FLOOR MOUNTED OUTLET, #/# = NUMBER OF VOICE CABLE(S)/JACK(S) AND NUMBER OF DATA CABLE(S)/JACK(S) (FLOOR BOX BY E.C.) |
| # | CEILING MOUNTED DATA OUTLET, # =NUMBER OF VOICE/DATA CABLE(S)/JACK(S) |
| AP# | CEILING MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| AP# | WALL MOUNTED OUTLET FOR WIRELESS ACCESS POINT #=NUMBER OF CABLE(S)/JACK(S) |
| | CABLING SLEEVE(S) |
| | TYPICAL LADDER RACK |
| | TYPICAL CABLE TRAY, BASKET STYLE |

## GENERAL ANNOTATION LEGEND

| SYMBOL | DESCRIPTION |
|---|---|
| MER | MAIN EQUIPMENT ROOM |
| TR | TELECOMMUNICATION ROOM |
| MDF | MAIN DISTRIBUTION FRAME |
| IDF | INTERMEDIATE DISTRIBUTION FRAME |
| ETR | EXISTING TO REMAIN |
| PBO | PROVIDED BY OTHERS |
| AFF | ABOVE FINISHED FLOOR |
| AFG | ABOVE FINISHED GRADE |
| AC | ABOVE COUNTER |
| EC | ELECTRICAL CONTRACTOR |
| PSC | PREMISE SECURITY CONTRACTOR |
| SCC | STRUCTURAL CABLING CONTRACTOR |
| AVC | AV/MULTIMEDIA CONTRACTOR |
| UNO | UNLESS NOTED OTHERWISE |
| ACS | ACCESS CONTROL SYSTEM |
| VSS | VIDEO SURVEILLANCE SYSTEM |

## TECHNOLOGY - GENERAL NOTES

1. EACH KEYNOTE MAY NOT BE UTILIZED ON EVERY SHEET.
2. ALL CONDUIT MEASUREMENTS REFER TO STANDARD CONDUIT TRADE SIZES.
3. ALL CABLES SHALL BE CONCEALED.
4. EACH CONTRACTOR SHALL PROVIDE AND INSTALL ALL NECESSARY SLEEVES, WHETHER OR NOT SPECIFICALLY NOTED ON PROJECT DRAWINGS. ALL SLEEVES SHALL BE 2" UNLESS NOTED OTHERWISE ON THE DRAWINGS. CABLE FILL PERCENTAGE SHALL COMPLY WITH NEC.
5. DEVICE LOCATIONS ARE APPROXIMATE. CONTRACTOR SHALL REVIEW CONDITIONS AND COORDINATE WITH OTHER TRADES AS NECESSARY FOR EXACT PLACEMENT.

## TECHNOLOGY SYMBOLS LEGEND

NOT ALL SYMBOLS ARE USED

- AV WALL ROUGH-IN WITH DATA
- KEYNOTE
- Proposed Camera Direction
  SURVEILLANCE CAMERA
  Camera Schedule Number (Floor #-Camera #)
  Camera (N)ew, (E)xisting Rough-in, (D)emo
- Proposed Camera Direction
  PTZ CAMERA
  PTZ
- Proposed Camera Direction
  FIXED SURVEILLANCE CAMERA
- 360°/MULTI-SENSOR FIXED SURVEILLANCE CAMERA OR FISHEYE LENS CAMERA
- Approximate view of lens
  Lens View Angle
  360°/MULTI-SENSOR FIXED SURVEILLANCE CAMERA OR FISHEYE LENS CAMERA
  Lens size
- MICROPHONE WITH AUDIO LINKED TO CAMERA
- CARD READER LINKED TO CAMERA
- SYMBOL TAG
  (#) = DIFFERENT TYPES OF CARD READERS:
  M = MULLION
  W = WIRELESS (Proprietary)
  Wi = Wi-Fi (802.11)
  POE = POWER OVER ETHERNET
- SYMBOL TAG
  (#) = DIFFERENT TYPES OF CARD READERS:
  TS = TOUCHSCREEN
  PU = PUSH BUTTON
- TOP = DETAIL NUMBER
  DETAIL REFERENCE
  BOTTOM = SHEET NUMBER
- NORTH ARROW
- SHEET NUMBER
  SECTION MARKER
  DETAIL NUMBER
- DIRECTION OF ELEVATION
  ELEVATION MARKER
  SHEET NUMBER
  DETAIL NUMBER
- DIRECTION OF ELEVATION
  SHEET NUMBER
  DIRECTION OF ELEVATION
  DETAIL NUMBER
- BAR IS ONE INCH ON ORIGINAL DRAWING. IF NOT ONE INCH ON THIS DRAWING ADJUST SCALES ACCORDINGLY

TRUENORTH
A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

W

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Townewest Elementary School
13927 Old Richmond Rd West, Sugar Land, TX 77498

SEAL

Bicsi
Brian C Porter
BICSI ID # 258657
EXPIRES 10-31-27
NCCD

07-18-25


MVA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY - TITLE SHEET

w-TN000

## TECHNOLOGY KEYNOTES

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.




1 BACKGROUND W (TOWNEWEST ES)
SCALE: 1" = 20'-0"

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

W

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Townewest Elementary School
13927 Old Richmond Rd West, Sugar Land, TX 77498

SEAL


BICSI REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256557
EXPIRES 12-31-27

07-18-25



MVA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - TOWNEWEST ES - OVERALL

w-TN.100




1 TOWNEWEST - KITCHEN PLAN
SCALE: 3/16" = 1'-0"




2 TOWNEWEST - REFLECTED CEILING PLAN
SCALE: 3/16" = 1'-0"

**TECHNOLOGY KEYNOTES**

1. IDF WILL REQUIRE ADDITIONAL HARDWARE TO SUPPORT THE ADDED CAMERA CABLES.
2. CONTRACTOR TO VERIFY WEITHER ADDITIONAL HARDWARE WILL BE NEEDED TO SUPPORT ADDITIONAL CAMAERA CABLES.
3. CONTRACTOR TO COORDINATE FINAL DEVICE LOCATION AND POSITIONING WITH FBISD.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

W

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Townewest Elementary School
13927 Old Richmond Rd West, Sugar Land, TX 77498

SEAL




07-18-25

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING
TECHNOLOGY - TOWNEWEST ES - KITCHEN

w-TN.101


TRUENORTH A PMY COMPANY

**GENERAL NOTE**


1. FACE PLATE DETAIL FOR OUTLET CONFIGURATION PURPOSES ONLY. CONTRACTOR TO SELECT TYPE OF FACE PLATE TO MATCH CONNECTIVITY HARDWARE, FLOOR BOX AND/OR MODULAR FURNITURE OPENING.





1 DATA ROUGH-IN DETAILS
SCALE: NS





2 TYPICAL CABLING SLEEVE
SCALE: NTS





3 PANDUIT J-HOOK DETAIL
SCALE: NTS





4 LABELING & CABLING SCHEMES
SCALE: NTS





5 CABLE PATHWAY CROSS SECTION
SCALE: NTS




6 DROPPED CEILING MOUNTING DETAIL
SCALE: NS




7 I-JOIST MOUNTING DETAIL
SCALE: NS




8 BAR JOIST MOUNTING DETAIL
SCALE: NS

| CAMERA TYPE | MANUFACTURER | MODEL NUMBER | GENERAL DESCRIPTION |
|---|---|---|---|
| C1 | iPro | WV-S8574L | 4x4K (33MP) EXTERIOR MULTI-SENSOR - PARKING LOTS, STADIUM |
| C2 | iPro | WV-S8544L | 4x4MP (16MP) EXTERIOR MULTI-SENSOR - BUILDING PERIMETER |
| C3 | iPro | WV-S25500-V3LN | 5MP EXTERIOR VANDAL DOME |
| C4 | iPro | WV-S22500-V3L | 5MP INTERIOR VANDAL DOME - CORR., COMMON, SPED |
| C5 | iPro | WV-S4156A | 5MP 360 (FISHEYE) - STAIRWELLS |

9 CAMERA SCHEDULE
SCALE: NTS

| Symbol | Purpose | Size | Mount | Backbox | Notes |
|---|---|---|---|---|---|
| FP1 | Digital Signage/Menu Boards | +49" | Ceiling Pole | N/A | Data and Power Outlets on ceiling |

10 DISPLAY SCHEDULE
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

W

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Townewest Elementary School
13927 Old Richmond Rd West, Sugar Land, TX 77498

SEAL

BICSI REGISTERED COMMUNICATIONS DISTRIBUTION DESIGNER
Bicsi
Brian C Porter
BICSI ID # 256557
EXPIRES 12-31-27
RCDD

07-18-25


ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079



PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING AND PERMITTING

TECHNOLOGY - TOWNEWEST ES - DETAILS


w-TN.500

GENERAL NOTES:


1. REFER TO SECURITY SCHEDULE AND WRITTEN SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
2. ALL MOUNTING DETAILS ARE REFERENCE FOR ALL FIXED DOME, 180°, 360°, PTZ, AND "BULLET/BOX" CAMERAS.





1 TYPICAL CAMERA INSTALLATION SECTION DETAIL
SCALE: NS




6 WALL MOUNTED CAMERA DETAIL
SCALE: NS




4 TILE BRIDGE DETAIL
SCALE: NS





5 CEILING MOUNTED CAMERA DETAIL
SCALE: NS


ACCESS CONROL DETAILS AND GENERAL NOTES:

1. CONDUIT ROUGH-IN IS A GUIDE FOR WHAT WILL BE REQUIRED FOR EACH DOOR. AS DOOR COMPONENTS CHANGE, EXACT CONDUIT LOCATION WILL ALSO NEED TO BE ADJUSTED.


2. PROTECT EXISTING-TO-REMAIN ACCESS CONTROL DEVICES AND CABLE THROUGHOUT RENOVATION WORK. IF CABLE AND/OR DEVICES ARE DAMAGED, SECURITY CONTRACTOR TO REPLACE WITH NEW.




1 ACCESS CONTROL - WIRING DETAIL - EXIT DEVICE W/ BUILT-IN REX
SCALE: NTS




2 ACCESS CONTROL - STEEL/HOLLOW METAL DOOR.
SCALE: NTS




KP PB LD

3 ROUGH-IN DETAILS: KP, PB, LD
SCALE: NTS

TRUENORTH A PMY COMPANY

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

W

FORT BEND BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
Townewest Elementary School
13927 Old Richmond Rd West, Sugar Land, TX 77498

SEAL




07-18-25


MWA ARCHITECTS
ARCHITECTS
AND PLANNING
CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07-18-25
ISSUED FOR BIDDING
AND
PERMITTING
TECHNOLOGY -
TOWNEWEST ES - SECURITY
DETAILS
w-TN.600

# FBISD BP013 KITCHEN RENOVATIONS ES

| Sheet List Table | |
|---|---|
| Sheet Number | Sheet Title |
| School: aa-First Colony MS | |
| aa-A.00 | COVER AND INDEX |
| aa-A.101 | TEMPORARY COOKING LOCATION SITE PLAN |
| aa-E.200 | ELECTRICAL FLOOR PLAN & SCHEDULES |




FORT BEND INDEPENDENT SCHOOL DISTRICT

FIRST COLONY ELEMENTARY SCHOOL
2720 PLANTERS STREET, SUGAR LAND, TX 77479

## ADMINISTRATION

| | |
|---|---|
| DR. MARCELL SMITH | SUPERINTENDENT OF FBISD |
| DR. ANDRIA SCHUR, Ed.D. | CHIEF OF SCHOOLS |

## BOARD OF TRUSTEES

| | |
|---|---|
| KRISTIN K. TASSIN | PRESIDENT |
| RICK GARCIA | VICE PRESIDENT |
| DAVID HAMILTON | SECRETARY |
| ANGIE HANAN | BOARD MEMBER |
| ADAM SCHOOF | BOARD MEMBER |
| DR. SHIRLEY ROSE-GILLIAM | BOARD MEMBER |
| SONYA JONES | BOARD MEMBER |

## PROJECT DESIGN TEAM

PROGRAM MANAGEMENT
FBISD 2023 Bond Team
2323 Texas Parkway
Missouri City, TX 77489
Phone Number: 281-327-5481

ARCHITECT
MWA Architects
11767 Katy Freeway, Suite 430
Houston, Texas 77079
Phone Number: 713-782-8188


FOOD SERVICE
Food Design Professionals
26215 Oak Ridge Drive
The Woodlands, Texas 77380
Phone Number: 281-350-2323

MEP ENGINEERS
Stanton Engineering Group
1300 W. Sam Houston Pkwy South, Suite 121
Houston, Texas 77042
Phone Number: 713-300-9292


STRUCTURAL ENGINEER
Stanley Spurling & Hamilton
3301 Edloe Street, Suite 200
Houston, Texas 77027
Phone Number: 713-776-9433

ISSUED FOR PERMIT AND BIDDING - JULY 18, 2025

aa




2 SCHEMATIC LAYOUT





NOTES:
1. ALL TO BE GALV. & PAINTED SAFETY YELLOW
2. PROVIDE PLAN & DETAILS IN SUBMITTAL FOR LOCATION AND ARCH. APPROVAL
3. MOUNT BOLLARD PLUMB.

3 BOLLARD
SCALE: 1- 1/2"=1'-0"

PROPOSED TEMPORARY FREEZER LOCATION. CONFFIRM WITH ARCH. BEFORE INSTALLING

APPROX. LOCATION OF NEAREST ELECTRICAL ROOM OR ELECTRICAL PANEL RE: ELEC SHEETS.




1 SITE PLAN
SCALE: 1"=30'-0"

GENERAL NOTES:
- A. TEMPARAY RENTAL FREEZER, CONTRACTOR FURNISHED & CONTRACTOR INSTALLED. COORDINATE W/ ARCHITECT FOR PROCUREMENT, DELIVERY AND CONNECTION TO POWER CANENSATE DISCHARGE. BASIS OF DESIGN SHALL BE POLAR LEASING DT180 (OTHER MODLES TO BE ACCEPTED WITH ARCHITECT APPROVAL)
- B. CONTRACTOR SHALL FURNISH ELECT. REQUIREMENTS: MIN. 30A, 220V, AS MINIMUM PRICING. SEE ELECTRICAL FOR ADDITIONAL IFORMATION.
- C. LOCATED UNIT WITHIN 100' (APPROX.) OF EXISTING ELECTRICAL ROOM.
- D. INSTALL 1" CONDENSATE DRAIN, CONNECT TO UNIT AS PER PROVIDER INSTRUCTS. KEEP DRAIN LINE AWAY FROM TRAFFIC AREAS. DISCHARGE AS PER PLUMBING DRAWINGS A LOCAL CODES.
- E. PROVIDE EIGHT 4'/ 48" ABV. PAVING BOLT-DOWN TEMPORARY BOLLARDS AROUND UNIT. PATCH HOLES UPON REMOVAL.
- F. SUBMIT LOCATION PLAN IN SUBMITTAL FOR LACATION APPROVAL BY ARCHITECTS.
- G. LOCATE UNIT IN AREA THAT:
  - G.1. HAS BEEN APPROVED INSURMITTAL
  - G.2. WITHIN 100' OF ELECT. CONNECTION
  - G.3. WILL NOT BLOCK WATER FLOW
  - G.4. AWAY FROM EXISTING AREAS SUBJECT TO STANDING WATER

| PHASING CHART FOR ALL SCHOOLS | | |
|---|---|---|
| PHASE 1 | | |
| ***SCHOOLS*** | **FREEZER START DATE :** | **FREEZER END DATE :** |
| ***FIRST COLONY MS*** | | |
| LAKEVIEW ES | 11/7/2025 | EST. END DATE IS 5/13/2026 BUT ALL SCHOOLS BEING SERVED MUST BE SUBSTATIALLY COMPLETE |
| PHASE 2 | | |
| ***FIRST COLONY MS*** | | |
| LAKE OLYMPIA MS | 5/29/2026 | EST. END DATE IS 10/28/2026 BUT ALL SCHOOLS BEING SERVED MUST BE SUBSTATIALLY COMPLETE |
| **PHASE 3** | | |
| MARSHAL HS | | |
| TRAVIS HS | 3/19/2027 | EST. END DATE IS 3/19/2027 BUT ALL SCHOOLS BEING SERVED MUST BE SUBSTATIALLY COMPLETE |
| DULLES HS | | |

NOTES:
1. FREEZER SHALL STAY IN OPERATION UNTIL ALL SCHOOLS BEING SERVED FROM THIS LOCATION HAVE ACHIVED SUBSTANTIAL COMPLETION

THIS SCHOOL WILL SUPPLY FOOD SERVICES DURING PHASE 1 & 2

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

aa

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
FIRST COLONY MIDDLE SCHOOL
3225 AUSTIN PARKWAY
SUGAR LAND, TX 77479

SEAL
REGISTERED ARCHITECT
KEITH ALEXANDER
#22657
STATE OF TEXAS
7/15/2025



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

TEMPORARY COOKING LOCATION SITE PLAN

aa-A.101

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings_TEMPORARY COOKING SITES\FirstColonyMiddleSchoolSitePlan.dwg, Jul 28, 2025 - 4:20pm




## 2 OVERALL FLOOR PLAN - FIRST COLONY MS

SCALE: 1" = 50'- 0"

## SYMBOL LEGEND

| | |
|---|---|
| ⓢⓓⓠ | SIMPLEX/DUPLEX/QUAD – 5361/2 REC |
| GFI | DUPLEX W/ GFCI PROTECTION–P&S 2097 |
| J | J–BOX |
| | CEILING MOUNTED J–BOX |
| M | MOTOR |
| | HEAVY DUTY, NON–FUSED DISCONNECT. MIN RATING OF CIRCUIT OCPD/VOLTAGE. |
| | ELECTRICAL PANEL |
| | HOMERUN TO CIRCUIT NOTED |
| E | EXISTING DEVICES TO REMAIN |
| R | EXISTING DEVICES TO BE RELOCATED |
| D | EXISTING DEVICES TO BE DEMO/REMOVED |
| REP | EXISTING DEVICES TO BE REPLACED |
| S | INDICATES SURFACE MOUNTED |
| SR | INDICATES SURFACE RACEWAY |
| ^ | INDICATES ABOVE COUNTER DEVICE |
| + | INDICATES DEVICE AT +30–60" |
| ++ | INDICATES DEVICE AT +80–96" |
| CLG | INDICATES DEVICES MOUNTED IN CEILING |
| WP | INDICATES WEATHERPROOF COVER |
| 3R | INDICATES 3R RATED DEVICE |
| (E)LA–X | CONNECT(ED) TO EXIST CIRCUIT LA–X |
| (D)LA–X | DEMO PORTION OF EXIST CIRCUIT LA–X |
| (N)LA–X | CONNECT(ED) TO NEW CIRCUIT LA–X |

GENERAL ELECTRICAL NOTES:

1. INSTALL SYSTEM IN ACCORDANCE WITH THE NATIONAL ELECTRIC CODE AS ADOPTED BY THE LOCAL AUTHORITY HAVING JURISDICTION INCLUDING ALL AMENDMENTS.
2. PROVIDE CONDUIT FOR ALL DEVICES INSTALLED IN WALLS.
   - 2.A. 3/4"C FOR POWER AND 1"C FOR LOW VOLTAGE/DATA UNLESS NOTED OTHERWISE.
   - 2.B. PROVIDE PROTECTIVE BUSHING ON END OF ALL LOW VOLTAGE CONDUITS.
   - 2.C. ALL ELECTRICAL HOMERUNS SHALL BE IN CONDUIT, MIN 3/4"C.
   - 2.D. USE INSULATED THROAT FITTINGS FOR CONNECTIONS TO HOUSINGS, BOXES, ENCLOSURES, ETC.
   - 2.E. MAX LENGTH FOR FLEX CONDUIT SHALL BE 6FT AND MIN. SIZE SHALL BE 1/2". ALL FLEX CONDUIT SHALL BE LISTED FOR GROUNDING.
3. CONDUIT TYPES:
   - 3.A. INSIDE BUILDINGS: GALVANIZED STEEL EMT.
     - 3.A.A. ALL LOW VOLTAGE CABLING SHALL BE INSTALLED IN CONDUIT IN EXPOSED CEILING AREAS. ROUTE TO NEAREST ACCESSIBLE CEILING WITH CONTINUOUS PATHWAYS TO LOW VOLTAGE SOURCE/DEVICE.
     - 3.A.B. ALL LOW VOLTAGE CABLING SHALL BE INSTALLED IN CONDUIT ABOVE INACCESSIBLE CEILINGS. ROUTE TO NEAREST ACCESSIBLE CEILING WITH CONTINUOUS PATHWAYS TO LOW VOLTAGE SOURCE/DEVICE.
   - 3.B. NO MC CABLE SHALL BE ALLOWED.
   - 3.C. PROVIDE FLEXIBLE CONNECTIONS TO MOTORS, PUMPS, TRANSFORMERS, OR SIMILAR EQUIPMENT.
4. PROVIDE GALVANIZED STEEL, ONE–PIECE CONSTRUCTION, OUTLET BOXES IN ALL CASES SUITABLE FOR INTENDED USE.
   - 4.A. BOXES OUTSIDE SHALL BE STEEL, NEMA 3 TYPE.
   - 4.B. PROVIDE CEILING BRACKET TO SUPPORT CEILING MOUNTED DEVICES FROM CEILING TEES.
5. 20 AMP, SINGLE PHASE BRANCH CIRCUITS SERVING LIGHTING AND GENERAL RECEPTACLES MAY BE GROUPED IN A SINGLE RACEWAY PROVIDED A NEUTRAL CONDUCTOR IS INSTALLED FOR EACH CIRCUIT REQUIRING A NEUTRAL.
   - 5.A. DO NOT INSTALL MORE THAN FOUR CURRENT CARRYING CONDUCTORS IN A CONDUIT EXCEPT SIX #12 OR #10 CURRENT CARRYING CONDUCTORS MAY BE INSTALLED IN 3/4" OR LARGER CONDUIT FOR 20A CIRCUITS.
   - 5.B. DO NOT INSTALL 400/277 VOLT CONDUCTORS IN THE SAME CONDUIT WITH 240/208/120 VOLT CONDUCTORS.
   - 5.C. DO NOT COMBINE NEUTRALS. PROVIDE DEDICATED NEUTRALS FOR EACH BRANCH CIRCUIT.
   - 5.D. MULTIPLE DEVICES ON A CIRCUIT SUCH AS RECEPTACLES SHALL BE WIRED WITH A PIGTAIL SO THE DEVICE DOES NOT PROMBE THE CONTINUITY PATH. FEED THROUGH CONNECTIONS FOR GFCI RECEPTACLES SHALL NOT BE USED FOR PROTECTION OF DOWNSTREAM DEVICES.
6. PROVIDE GREEN GROUND WIRE WITH ALL CIRCUITS SIZED PER NEC. BOND GREEN GROUND WIRE TO EACH END OF CONDUIT.
7. PROVIDE J–BOXES, CONDUIT AND SLEEVES THRU ALL FIRE WALLS FOR DATA, TELEPHONE, SECURITY, FIRE ALARM, SOUND SYSTEM, LOW VOLTAGE WIRING, ETC. PROVIDE PROTECTIVE BUSHINGS ON ENDS OF ALL LOW VOLTAGE CONDUITS.
8. PROVIDE PULL BOXES, JUNCTION BOXES, WIRING TROUGHS AND CABINETS WHEREVER REQUIRED FOR PROPER INSTALLATION OF VARIOUS ELECTRICAL SYSTEMS. ALL JUNCTION/PULL BOXES INSTALLED ABOVE ACCESSIBLE CEILINGS SHALL BE MOUNTED SO THAT THE ACCESS PANEL IS NO HIGHER THAN 18" ABOVE THE CEILING.
9. PROVIDE CIRCUIT LABELS IN PERMANENT MARKER ON ALL NEW AND EXISTING J–BOX COVERS UTILIZED IN THE AREA OF RENOVATION.
10. PROVIDE CIRCUIT LABEL ON ALL ABOVE CEILING J–BOXES, EQUIPMENT, ETC. IDENTIFYING THE CIRCUITS CONTAINED/CONNECTED.
11. ALL WIRING SHALL BE 600 VOLT, SOFT DRAWN ANNEALED COPPER, 98% CONDUCTIVITY, CONTINUOUS FROM OUTLET TO OUTLET. MINIMUM WIRE SIZE #12.
    - 11.A. TYPICAL BUILDING WIRE SHALL BE STRANDED TYPE THHN, THWN–2 (WET RATED FOR 90°C), OR XHHW–2. MINIMUM WIRE SIZE SHALL BE #12.
    - 11.B. ALL BUILDING WIRE SHALL BE COLOR CODED WITH THE SAME COLOR CONNECTED TO THE SAME UNGROUNDED PHASE THROUGHOUT THE INSTALLATION MATCHING THE EXISTING BUILDING COLOR CODE SCHEME.
12. WHERE PORTIONS OF INTERIOR RACEWAY SYSTEM ARE EXPOSED TO WIDELY DIFFERENT TEMPERATURES, PROVIDE AIR SEAL PER NEC TO PREVENT CIRCULATION OF AIR FROM WARMER TO COOLER SECTIONS.
13. DRAWINGS, SCHEDULES, NOTES, AND DETAILS ARE INTENDED TO BE COMPLIMENTARY. ANY WORK DESCRIBED IN ANY OF THEM, WILL BE WORK REQUIRED UNDER THIS CONTRACT. WHERE THERE IS A CONFLICT BETWEEN DIFFERENT PORTIONS OF THE DESIGN DOCUMENTS IT SHALL BE CLARIFIED BY RFI, BARRING CLARIFICATION PRIOR TO BIDDING THE MOST EXPENSIVE OPTION SHALL BE INCLUDED AND CLARIFICATION SHALL BE MADE DURING CONSTRUCTION.
14. SHOULD ANY WORK REQUIRED BY THE DRAWINGS AND SPECIFICATIONS BE IN VIOLATION OF ANY FEDERAL, STATE, COUNTY OR CITY LAWS, ORDINANCE OR REGULATION, THOSE LAWS AND REGULATIONS SHALL PREVAIL, AND SHALL BE COMPLIED WITH BY THE CONTRACTOR AS A PART OF THIS WORK WITH NO EXTRA COMPENSATION.
15. ALL MATERIAL MUST BE NEW AND OF GOOD QUALITY AND SHALL BEAR THE STAMP OF APPROVAL OF THE UNDERWRITERS' LABORATORIES, INC. (U.L.).

GENERAL RENOVATION AND REMODELING NOTES:

1. THESE ELECTRICAL DRAWINGS ONLY SHOW SOME EXISTING ELECTRICAL PANELS, DEVICES AND LIGHT FIXTURES IN AREAS OF RENOVATION. ALL OTHER ELECTRICAL EQUIPMENT, WIRING DEVICES, LOW VOLTAGE SYSTEMS, J–BOXES AND CONDUITS SHALL BE LOCATED AND FIELD VERIFIED BY CONTRACTOR.
2. ALL REMOVED DEVICES SHALL BE OFFERED TO THE OWNER AS SALVAGE.
3. RELOCATE CONDUIT AS NECESSARY TO ALLOW NEW OR MODIFIED CONSTRUCTION. RESUPPORT EXISTING CABLING/CONDUIT TO REMAIN TO MEET CURRENTLY ADOPTED CODE REQUIREMENTS. REMOVE ALL ABANDONED CONDUIT AND WIRE. REPAIR EXISTING ELECTRICAL SYSTEMS DAMAGED BY CONSTRUCTION ACTIVITIES.
4. ANY DAMAGE TO EXISTING BUILDING, ELECTRICAL EQUIPMENT, WIRING DEVICES, CONDUIT, WIRING, ETC. SHALL BE REPLACED BY THE CONTRACTOR AT NO COST TO THE OWNER. ALL MATERIALS USED FOR THE REPLACEMENT MUST MEET RENOVATION PROJECT STANDARDS.
5. ELECTRICAL CONTRACTOR SHALL BEGIN FIELD VERIFYING ALL EXISTING BRANCH CIRCUITS FOR EXISTING AREAS TO BE RENOVATED IMMEDIATELY AFTER THE CONTRACT IS ISSUED.
6. ELECTRICAL CONTRACTOR SHALL FIELD VERIFY EXISTING CIRCUITS WITH OWNER'S MAINTENANCE PERSONNEL AFTER NORMAL BUILDING HOURS AS REQUIRED.
7. ANY CIRCUIT OR PARTIAL CIRCUIT TO REMAIN OR BE REUSED SHALL REMAIN ACTIVE.
8. ELECTRICAL CONTRACTOR SHALL INCLUDE COST RELATED TO FIELD VERIFY EXISTING CIRCUITS IN BASE PROPOSAL.
9. FIND AND RECORD ALL EXISTING DEVICES IN CEILINGS, WALLS AND CASEWORK IN AREAS TO BE RENOVATED. PROVIDE A COPY OF THE FIELD VERIFIED DEVICE DRAWINGS TO OWNER PRIOR TO BEGINNING WORK.
10. AT THE END OF THE PROJECT, PROVIDE A NEW TYPEWRITTEN AS–BUILT PANEL SCHEDULE FOR ALL PANELS WITH CIRCUITS ADDED, REMOVED, OR MODIFIED AS PART OF THE PROJECT USING BUILDING ROOM NUMBERS.


## EXIST TO REMAIN

**PANEL EL** — 80A MCB, 208Y/120V, 3ø, 4 WIRE — MOUNTING: SURFACE — AVAILABLE FAULT: SCCR & AIC:

| | LOAD | DESCRIPTION | ROOM | WIRE | CB | CKT | A | B | C | CKT | CB | ROOM | DESCRIPTION | WIRE | LOAD |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | 500 | INTRUSION DETECTION | | EXIST | 20/1 | 1 | | | | 2 | | | SPACE | | |
| | 500 | FIRE ALARM | | EXIST | 20/1 | 3 | | | | 4 | | | SPACE | | |
| | 500 | PA SYSTEM | | EXIST | 20/1 | 5 | | | | 6 | 60/2 | EXIST | SPD | | 1 |
| | 1000 | 120 FOR GENERATOR | | EXIST | 20/1 | 7 | | | | 8 | – | | – | | |
| | | EXIST SPARE | | | 20/1 | 9 | | | | 10 | | | SPACE | | |
| | | EXIST SPARE | | | 20/1 | 11 | | | | 12 | | | SPACE | | |
| | | EXIST SPARE | | | 20/1 | 13 | | | | 14 | | | SPACE | | |
| | | EXIST SPARE | | | 20/1 | 15 | | | | 16 | | | SPACE | | |
| | | EXIST SPARE | | | 20/1 | 17 | | | | 18 | | | SPACE | | |
| | | EXIST SPARE | | | 20/1 | 19 | | | | 20 | 30/3 | EXIST | SPD | | 1 |
| | | EXIST SPARE | | | 20/1 | 21 | | | | 22 | – | | – | | |
| | | EXIST SPARE | | | 20/1 | 23 | | | | 24 | – | | – | | |
| NOTE 1 | 3100 | FOOD STORAGE UNIT | | 3–10 | 30/3 | 25 | | | | 26 | | | SPACE | | |
| | – | – | | +10N+10G | – | 27 | | | | 28 | | | SPACE | | |
| | 180 | NEW DUPLEX REC | | 3/4"C | – | 29 | | | | 30 | | | SPACE | | |

TOTAL LOAD @ 100% = 5782VA — TOTAL LOAD @ 100% = 16A — TOTAL LOAD @ 125% = 20A

1. PROVIDE NEW CB & WIRE NEW CIRCUIT.





## 3 FIRST COLONY MS PARTIAL ELECTRICAL RISER

NO SCALE

NOTES:

1. ALL PANELS, TRANSFORMER, SWITCHBOARD AND TRANSFER SWITCH ARE EXISTING. ADD 30/3 CB TO PANEL XXX AND EXTEND 3–10+10N+10G, 3/4"C TO NEW FUSED SWITCH.




## 1 ELECTRICAL RENOVATION PLAN - FIRST COLONY MS

SCALE: 1/8" = 1'– 0"

STANTON ENGINEERING GROUP
INFORMATION@STANTONEG.COM (713) 300–6080 | TEXAS ENG. FIRM REG NO. F–018332 | © 2025 ALL RIGHTS RESERVED | 1300 W. SAM HOUSTON PARKWAY N., SUITE 121, HOUSTON, TX 77043

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

aa

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
FIRST COLONY MIDDLE SCHOOL
3225 AUSTIN PARKWAY
SUGAR LAND, TX 77049

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL FLOOR PLAN & SCHEDULES

aa-E.200

# FBISD BP013 KITCHEN RENOVATIONS ES

| Sheet List Table | |
|---|---|
| Sheet Number | Sheet Title |
| School: bb-Lakeview ES | |
| bb-A.000 | COVER AND INDEX |
| bb-A.101 | TEMPORARY COOKING LOCATION SITE PLAN |
| bb-E.200 | ELECTRICAL FLOOR PLAN & SCHEDULES |




FORT BEND INDEPENDENT SCHOOL DISTRICT

LAKEVIEW ELEMENTARY SCHOOL
314 LIKEVIEW DRIVE, SUGAR LAND, TX 77498

## ADMINISTRATION

| | |
|---|---|
| DR. MARCELL SMITH | SUPERINTENDENT OF FBISD |
| DR. ANDRIA SCHUR, Ed.D. | CHIEF OF SCHOOLS |

## BOARD OF TRUSTEES

| | |
|---|---|
| KRISTIN K. TASSIN | PRESIDENT |
| RICK GARCIA | VICE PRESIDENT |
| DAVID HAMILTON | SECRETARY |
| ANGIE HANAN | BOARD MEMBER |
| ADAM SCHOOF | BOARD MEMBER |
| DR. SHIRLEY ROSE-GILLIAM | BOARD MEMBER |
| SONYA JONES | BOARD MEMBER |

## PROJECT DESIGN TEAM

PROGRAM MANAGEMENT
FBISD 2023 Bond Team
2323 Texas Parkway
Missouri City, TX 77489
Phone Number: 281-327-5481

ARCHITECT
MWA Architects
11767 Katy Freeway, Suite 430
Houston, Texas 77079
Phone Number: 713-782-8188


FOOD SERVICE
Food Design Professionals
26215 Oak Ridge Drive
The Woodlands, Texas 77380
Phone Number: 281-350-2323

MEP ENGINEERS
Stanton Engineering Group
1300 W. Sam Houston Pkwy South, Suite 121
Houston, Texas 77042
Phone Number: 713-300-9292


STRUCTURAL ENGINEER
Stanley Spurling & Hamilton
3301 Edloe Street, Suite 200
Houston, Texas 77027
Phone Number: 713-776-9433

ISSUED FOR PERMIT AND BIDDING - JULY 18, 2025

bb




2 SCHEMATIC LAYOUT




NOTES:
1. ALL TO BE GALV. & PAINTED SAFETY YELLOW
2. PROVIDE PLAN & DETAILS IN SUBMITIDAL FOR LOCATION AND ARCH. APPROVAL
3. MOUNT BOLLARD PLIMB.

3 BOLLARD
SCALE: 1- 1/2"=1'-0"




1 SITE PLAN
SCALE: 1"=30'-0"

GENERAL NOTES:
A. TEMPARAY RENTAL FREEZER, CONTRACTOR FURNISHED & CONTRACTOR INSTALLED. COORDINATE W/ ARCHITECT FOR PROCUREMENT, DELIVERY AND CONNECTION TO POWER CANENSATE DISCHARGE. BASIS OF DESIGN SHALL BE POLAR LEASING DT180 (OTHER MODLES TO BE ACCEPTED WITH ARCHITECT APPROVAL)
B. CONTRACTOR SHALL FURNISH ELECT. REQUIREMENTS: MIN. 30A, 220V, AS MINIMUM PRICING. SEE ELECTRICAL FOR ADDITIONAL IFORMATION.
C. LOCATED UNIT WITHIN 100' (APPROX.) OF EXISTING ELECTRICAL ROOM.
D. INSTALL 1" CONDENSATE DRAIN, CONNECT TO UNIT AS PER PROVIDER INSTRUCTS. KEEP DRAIN LINE AWAY FROM TRAFFIC AREAS. DISCHARGE AS PER PLUMBING DRAWINGS A LOCAL CODES.
E. PROVIDE EIGHT 4'/ 48" ABV. PAVING BOLT-DOWN TEMPORARY BOLLARDS AROUND UNIT. PATCH HOLES UPON REMOVAL.
F. SUBMIT LOCATION PLAN IN SUBMITTAL FOR LACATION APPROVAL BY ARCHITECTS.
G. LOCATE UNIT IN AREA THAT:
G.1. HAS BEEN APPROVED INSURMITTAL
G.2. WITHIN 100' OF ELECT. CONNECTION
G.3. WILL NOT BLOCK WATER FLOW
G.4. AWAY FROM EXISTING AREAS SUBJECT TO STANDING WATER

| PHASING CHART FOR ALL SCHOOLS | | |
|---|---|---|
| PHASE 1 | | |
| SCHOOLS | FREEZER START DATE : | FREEZER END DATE : |
| FIRST COLONY MS<br>*LAKEVIEW ES* | 11/7/2025 | EST. END DATE IS 5/13/2026 BUT ALL SCHOOLS BEING SERVED MUST BE SUBSTATIAILLY COMPLETE |
| PHASE 2 | | |
| FIRST COLONY MS<br>LAKE OLYMPIA MS | 5/29/2026 | EST. END DATE IS 10/28/2026 BUT ALL SCHOOLS BEING SERVED MUST BE SUBSTATIAILLY COMPLETE |
| PHASE 3 | | |
| MARSHAL HS<br>TRAVIS HS<br>DULLES HS | 3/19/2027 | EST. END DATE IS 3/19/2027 BUT ALL SCHOOLS BEING SERVED MUST BE SUBSTATIAILLY COMPLETE |

NOTES:
1. FREEZER SHALL STAY IN OPERATION UNTIL ALL SCHOOLS BEING SERVED FROM THIS LOCATION HAVE ACHIVED SUBSTANTIAL COMPLETION

THIS SCHOOL WILL SUPPLY FOOD SERVICES DURING PHASE 1

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

bb

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
LAKEVIEW ELEMENTARY SCHOOL
314 LAKEVIEW DR
SUGAR LAND, TX 77498

SEAL
REGISTERED ARCHITECT
NOEL ALEJANDRO
22651
STATE OF TEXAS
7/15/2025


WA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

TEMPORARY COOKING LOCATION SITE PLAN

bb-A.101

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings_TEMPORARY COOKING SITES\Lakeview\Elementary\SchoolSitePlan.dwg Jul 28, 2025 - 4:22pm




## 2 OVERALL FLOOR PLAN - LAKEVIEW ES

SCALE: 1" = 50'- 0"

## SYMBOL LEGEND


| | |
|---|---|
| ⏚/⏚/⏚ | SIMPLEX/DUPLEX/QUAD – 5361/2 REC |
| GFI | DUPLEX W/ GFCI PROTECTION–P&S 2097 |
| J | J–BOX |
| | CEILING MOUNTED J–BOX |
| | MOTOR |
| | HEAVY DUTY, NON–FUSED DISCONNECT. MIN RATING OF CIRCUIT OCPD/VOLTAGE. |
| | ELECTRICAL PANEL |
| | HOMERUN TO CIRCUIT NOTED |
| E | EXISTING DEVICES TO REMAIN |
| R | EXISTING DEVICES TO BE RELOCATED |
| D | EXISTING DEVICES TO BE DEMO/REMOVED |
| REP | EXISTING DEVICES TO BE REPLACED |
| S | INDICATES SURFACE MOUNTED |
| SR | INDICATES SURFACE RACEWAY |
| + | INDICATES ABOVE COUNTER DEVICE |
| + | INDICATES DEVICE AT +30–60" |
| ++ | INDICATES DEVICE AT +80–96" |
| CLG | INDICATES DEVICES MOUNTED IN CEILING |
| WP | INDICATES WEATHERPROOF COVER |
| 3R | INDICATES 3R RATED DEVICE |
| (E)LA–X | CONNECT(ED) TO EXIST CIRCUIT LA–X |
| (D)LA–X | DEMO PORTION OF EXIST CIRCUIT LA–X |
| (N)LA–X | CONNECT(ED) TO NEW CIRCUIT LA–X |

GENERAL ELECTRICAL NOTES:

1. INSTALL SYSTEM IN ACCORDANCE WITH THE NATIONAL ELECTRIC CODE AS ADOPTED BY THE LOCAL AUTHORITY HAVING JURISDICTION INCLUDING ALL AMENDMENTS.
2. PROVIDE CONDUIT FOR ALL DEVICES INSTALLED IN WALLS.
   - 2.A. 3/4"C FOR POWER AND 1"C FOR LOW VOLTAGE/DATA UNLESS NOTED OTHERWISE.
   - 2.B. PROVIDE PROTECTIVE BUSHING ON END OF ALL LOW VOLTAGE CONDUITS.
   - 2.C. ALL ELECTRICAL HOMERUNS SHALL BE IN CONDUIT, MIN 3/4"C.
   - 2.D. USE INSULATED THROAT FITTINGS FOR CONNECTIONS TO HOUSINGS, BOXES, ENCLOSURES, ETC.
   - 2.E. MAX LENGTH FOR FLEX CONDUIT SHALL BE 6FT AND MIN. SIZE SHALL BE 1/2". ALL FLEX CONDUIT SHALL BE LISTED FOR GROUNDING.
3. CONDUIT TYPES:
   - 3.A. INSIDE BUILDINGS: GALVANIZED STEEL EMT.
     - 3.A.A. ALL LOW VOLTAGE CABLING SHALL BE INSTALLED IN CONDUIT IN EXPOSED CEILING AREAS. ROUTE TO NEAREST ACCESSIBLE CEILING WITH CONTINUOUS PATHWAYS TO LOW VOLTAGE SOURCE/DEVICE.
     - 3.A.B. ALL LOW VOLTAGE CABLING SHALL BE INSTALLED IN CONDUIT ABOVE INACCESSIBLE CEILINGS. ROUTE TO NEAREST ACCESSIBLE CEILING WITH CONTINUOUS PATHWAYS TO LOW VOLTAGE SOURCE/DEVICE.
   - 3.B. NO MC CABLE SHALL BE ALLOWED.
   - 3.C. PROVIDE FLEXIBLE CONNECTIONS TO MOTORS, PUMPS, TRANSFORMERS, OR SIMILAR EQUIPMENT.
4. PROVIDE GALVANIZED STEEL, ONE–PIECE CONSTRUCTION, OUTLET BOXES IN ALL CASES SUITABLE FOR INTENDED USE.
   - 4.A. BOXES OUTSIDE SHALL BE STEEL NEMA 3 TYPE.
   - 4.B. PROVIDE CEILING BRACKET TO SUPPORT CEILING MOUNTED DEVICES FROM CEILING TEES.
5. 20 AMP, SINGLE PHASE BRANCH CIRCUITS SERVING LIGHTING AND GENERAL RECEPTACLES MAY BE GROUPED IN A SINGLE RACEWAY PROVIDED A NEUTRAL CONDUCTOR IS INSTALLED FOR EACH CIRCUIT REQUIRING A NEUTRAL.
   - 5.A. DO NOT INSTALL MORE THAN FOUR CURRENT CARRYING CONDUCTORS IN A CONDUIT EXCEPT SIX #12 OR #10 CURRENT CARRYING CONDUCTORS MAY BE INSTALLED IN 3/4" OR LARGER CONDUIT FOR 20A CIRCUITS.
   - 5.B. DO NOT INSTALL 480/277 VOLT CONDUCTORS IN THE SAME CONDUIT WITH 240/208/120 VOLT CONDUCTORS.
   - 5.C. DO NOT COMBINE NEUTRALS. PROVIDE DEDICATED NEUTRALS FOR EACH BRANCH CIRCUIT.
   - 5.D. MULTIPLE DEVICES ON A CIRCUIT SUCH AS RECEPTACLES SHALL BE WIRED WITH A PIGTAIL SO THE DEVICE DOES NOT PREMBE THE CONTINUITY PATH. FEED THROUGH CONNECTIONS FOR GFCI RECEPTACLES SHALL NOT BE USED FOR PROTECTION OF DOWNSTREAM DEVICES.
6. PROVIDE GREEN GROUND WIRE WITH ALL CIRCUITS SIZED PER NEC. BOND GREEN GROUND WIRE TO EACH END OF CONDUIT.
7. PROVIDE J–BOXES, CONDUIT AND SLEEVES THRU ALL FIRE WALLS FOR DATA, TELEPHONE, SECURITY, FIRE ALARM, SOUND SYSTEM, LOW VOLTAGE WIRING, ETC. PROVIDE PROTECTIVE BUSHINGS ON ENDS OF ALL LOW VOLTAGE CONDUITS.
8. PROVIDE PULL BOXES, JUNCTION BOXES, WIRING TROUGHS AND CABINETS WHEREVER REQUIRED FOR PROPER INSTALLATION OF VARIOUS ELECTRICAL SYSTEMS. ALL JUNCTION/PULL BOXES INSTALLED ABOVE ACCESSIBLE CEILINGS SHALL BE MOUNTED SO THAT THE ACCESS PANEL IS NO HIGHER THAN 18" ABOVE THE CEILING.
9. PROVIDE CIRCUIT LABELS IN PERMANENT MARKER ON ALL NEW AND EXISTING J–BOX COVERS UTILIZED IN THE AREA OF RENOVATION.
10. PROVIDE CIRCUIT LABEL ON ALL ABOVE CEILING J–BOXES, EQUIPMENT, ETC. IDENTIFYING THE CIRCUITS CONTAINED/CONNECTED.
11. ALL WIRING SHALL BE 600 VOLT, SOFT DRAWN ANNEALED COPPER, 98% CONDUCTIVITY, CONTINUOUS FROM OUTLET TO OUTLET. MINIMUM WIRE SIZE #12.
    - 11.A TYPICAL BUILDING WIRE SHALL BE STRANDED TYPE THHN, THWN–2 (WET RATED FOR 90ºC), OR XHHW–2. MINIMUM WIRE SIZE SHALL BE #12.
    - 11.B ALL BUILDING WIRE SHALL BE COLOR CODED WITH THE SAME COLOR CONNECTED TO THE SAME UNGROUNDED PHASE THROUGHOUT THE INSTALLATION MATCHING THE EXISTING BUILDING COLOR CODE SCHEME.
12. WHERE PORTIONS OF INTERIOR RACEWAY SYSTEM ARE EXPOSED TO WIDELY DIFFERENT TEMPERATURES, PROVIDE AIR SEAL PER NEC TO PREVENT CIRCULATION OF AIR FROM WARMER TO COOLER SECTIONS.
13. DRAWINGS, SCHEDULES, NOTES, AND DETAILS ARE INTENDED TO BE COMPLIMENTARY. ANY WORK DESCRIBED IN ANY OF THEM, WILL BE WORK REQUIRED UNDER THIS CONTRACT. WHERE THERE IS A CONFLICT BETWEEN DIFFERENT PORTIONS OF THE DESIGN DOCUMENTS IT SHALL BE CLARIFIED BY RFI, BARRING CLARIFICATION PRIOR TO BIDDING THE MOST EXPENSIVE OPTION SHALL BE INCLUDED AND CLARIFICATION SHALL BE MADE DURING CONSTRUCTION.
14. SHOULD ANY WORK REQUIRED BY THE DRAWINGS AND SPECIFICATIONS BE IN VIOLATION OF ANY FEDERAL, STATE, COUNTY OR CITY LAWS, ORDINANCE OR REGULATION, THOSE LAWS AND REGULATIONS SHALL PREVAIL, AND SHALL BE COMPLIED WITH BY THE CONTRACTOR AS A PART OF THIS WORK WITH NO EXTRA COMPENSATION.
15. ALL MATERIAL MUST BE NEW AND OF GOOD QUALITY AND SHALL BEAR THE STAMP OF APPROVAL OF THE UNDERWRITERS' LABORATORIES, INC. (U.L.).

GENERAL RENOVATION AND REMODELING NOTES:

1. THESE ELECTRICAL DRAWINGS ONLY SHOW SOME EXISTING ELECTRICAL PANELS, DEVICES AND LIGHT FIXTURES IN AREAS OF RENOVATION. ALL OTHER ELECTRICAL EQUIPMENT, WIRING DEVICES, LOW VOLTAGE SYSTEMS, J–BOXES AND CONDUITS SHALL BE LOCATED AND FIELD VERIFIED BY CONTRACTOR.
2. ALL REMOVED DEVICES SHALL BE OFFERED TO THE OWNER AS SALVAGE.
3. RELOCATE CONDUIT AS NECESSARY TO ALLOW NEW OR MODIFIED CONSTRUCTION. RESUPPORT EXISTING CABLING/CONDUIT TO REMAIN TO MEET CURRENTLY ADOPTED CODE REQUIREMENTS. REMOVE ALL ABANDONED CONDUIT AND WIRE. REPAIR EXISTING ELECTRICAL SYSTEMS DAMAGED BY CONSTRUCTION ACTIVITIES.
4. ANY DAMAGE TO EXISTING BUILDING, ELECTRICAL EQUIPMENT, WIRING DEVICES, CONDUIT, WIRING, ETC. SHALL BE REPLACED BY THE CONTRACTOR AT NO COST TO THE OWNER. ALL MATERIALS USED FOR THE REPLACEMENT MUST MEET RENOVATION PROJECT STANDARDS.
5. ELECTRICAL CONTRACTOR SHALL BEGIN FIELD VERIFYING ALL EXISTING BRANCH CIRCUITS FOR EXISTING AREAS TO BE RENOVATED IMMEDIATELY AFTER THE CONTRACT IS ISSUED.
6. ELECTRICAL CONTRACTOR SHALL FIELD VERIFY EXISTING CIRCUITS WITH OWNER'S MAINTENANCE PERSONNEL AFTER NORMAL BUILDING HOURS AS REQUIRED.
7. ANY CIRCUIT OR PARTIAL CIRCUIT TO REMAIN OR BE REUSED SHALL REMAIN ACTIVE.
8. ELECTRICAL CONTRACTOR SHALL INCLUDE COST RELATED TO FIELD VERIFY EXISTING CIRCUITS IN BASE PROPOSAL.
9. FIND AND RECORD ALL EXISTING DEVICES IN CEILINGS, WALLS AND CASEWORK IN AREAS TO BE RENOVATED. PROVIDE A COPY OF THE FIELD VERIFIED DEVICE DRAWINGS TO OWNER PRIOR TO BEGINNING WORK.
10. AT THE END OF THE PROJECT, PROVIDE A NEW TYPEWRITTEN AS–BUILT PANEL SCHEDULE FOR ALL PANELS WITH CIRCUITS ADDED, REMOVED, OR MODIFIED AS PART OF THE PROJECT USING BUILDING ROOM NUMBERS.




## 1 ELECTRICAL RENOVATION PLAN - LAKEVIEW ES


SCALE: 1/8" = 1'- 0"

## EXISTING TO REMAIN

**PANEL EGP1E** — 150A MCB, 208Y/120V, 3ϕ, 4 WIRE — MOUNTING: SURFACE — DOOR–IN–DOOR HINGE TO BOX — AVAILABLE FAULT: SCCR & AIC:

| LOAD | DESCRIPTION | WIRE | CB | CKT | A B C | CKT | CB | WIRE | DESCRIPTION | LOAD | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 6000 | E103 REFRIGERATION SYS | EXIST | 40/3 | 1 | | 2 | 20/1 | EXIST | E102C PRESS RELIEF | 50 | |
| – | – | EXIST | – | 3 | | 4 | 20/1 | EXIST | E102C PRESS RELIEF | 50 | |
| – | – | EXIST | – | 5 | | 6 | 20/2 | EXIST | E103C FREEZER COIL | 500 | |
| 500 | E103D COOLER COIL | EXIST | 20/1 | 7 | | 8 | – | – | – | – | |
| 500 | TF–1 B118 | EXIST | 20/1 | 9 | | 10 | 20/1 | EXIST | E102B TEMP ALARM | 100 | |
| 200 | E102B TEMP ALARM B116 | EXIST | 20/1 | 11 | | 12 | 20/1 | EXIST | E102 DOOR HTR/LTS | 500 | |
| 500 | E102 DOOR HTR/LTS | EXIST | 20/1 | 13 | | 14 | 20/1 | EXIST | IDF REC C113 | 800 | |
| | SPACE | | | 15 | | 16 | 30/1 | EXIST | IDF RACK C113 | 1800 | |
| 800 | IDF RACK C113 | EXIST | 30/1 | 17 | | 18 | | | SPACE | | |
| | SPACE | | | 19 | | 20 | 20/1 | EXIST | IDF REC C113 | 800 | |
| 1800 | IDF RACK C113 | EXIST | 30/1 | 21 | | 22 | 20/1 | EXIST | IDF INTRUSION C113 | 100 | |
| 800 | IDF RACK C113 | EXIST | 20/1 | 23 | | 24 | 20/1 | EXIST | IDF ACCESS CTRL C113 | 100 | |
| 50 | LIGHTING CONTACTOR | EXIST | 20/1 | 25 | | 26 | 20/1 | EXIST | OSX SECURITY ACCESS | 300 | |
| 540 | REC MECH B129,B130,131 | EXIST | 20/1 | 27 | | 28 | 20/1 | EXIST | UNIFY PANEL AREA D | 500 | |
| 800 | IDF C113 | EXIST | 20/1 | 29 | | 30 | 20/1 | EXIST | F/A PANEL AREA E C111 | 500 | |
| 800 | IDF C113 | EXIST | 20/1 | 31 | | 32 | 20/1 | | EXIST SPARE | | |
| | SPACE | | | 33 | | 34 | | | SPACE | | |
| | EXIST SPARE | | 30/1 | 35 | | 36 | 20/1 | | EXIST SPARE | | |
| | EXIST SPARE | | 20/1 | 37 | | 38 | 20/1 | EXIST | F/A PUMP | 500 | |
| | SPACE | | | 39 | | 40 | 20/1 | EXIST | F/A PUMP | 500 | |
| | SPACE | | | 41 | | 42 | | | SPACE | | |
| | SPACE | | | 43 | | 44 | | | SPACE | | |
| | SPACE | | | 45 | | 46 | | | SPACE | | |
| | SPACE | | | 47 | | 48 | | | SPACE | | |
| | SPD | EXIST | 30/3 | 49 | | 50 | 30/3 | 3–10 | FOOD STORAGE UNIT | 3100 | NOTE 1 |
| | – | – | – | 51 | | 52 | – | +10N+10G | – | – | |
| | – | – | – | 53 | | 54 | – | 3/4"C | NEW DUPLEX REC | 180 | |
| TOTAL LOAD ❂ 100% = 23670VA | | | | | TOTAL LOAD ❂ 100% = 66A | | | | TOTAL LOAD ❂ 125% = | 82A | |

1. PROVIDE NEW CB & WIRE NEW CIRCUIT.




## 3 LAKEVIEW ES PARTIAL ELECTRICAL RISER

NO SCALE

NOTES:

1. ALL PANELS, TRANSFORMER, SWITCHBOARD AND TRANSFER SWITCH ARE EXISTING. ADD 30/3 CB TO PANEL EGP1E AND EXTEND 3–10+10N+10G, 3/4"C TO NEW FUSED SWITCH.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

bb

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT

LAKEVIEW ELEMENTARY SCHOOL
314 LAKEVIEW DR
SUGAR LAND, TX 77498

SEAL

STATE OF TEXAS — GEORGE L. STANTON — 38582 — REGISTERED PROFESSIONAL ENGINEER

07.18.2025

MWA ARCHITECTS

ARCHITECTS AND PLANNING CONSULTANTS

11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL FLOOR PLAN & SCHEDULES

bb-E.200

STANTON ENGINEERING GROUP

INFO@STANTON–ENG.COM (713) 300–6282 | TEXAS ENG. FIRM REG. NO. F–018332 | © 2021 ALL RIGHTS RESERVED | 1300 W. SAM HOUSTON PARKWAY S., SUITE 121, HOUSTON, TX 77042

# FBISD BP013 KITCHEN RENOVATIONS ES

| Sheet List Table | |
|---|---|
| Sheet Number | Sheet Title |
| School: cc-Lake Olympia MS | |
| cc-A.00 | COVER AND INDEX |
| cc-A.101 | TEMPORARY COOKING LOCATION SITE PLAN |
| cc-E.200 | ELECTRICAL FLOOR PLAN & SCHEDULES |




FORT BEND INDEPENDENT SCHOOL DISTRICT

LAKE OLYMPIA ELEMENTARY SCHOOL
3100 LAKE OLYMPIA DRIVE, SUGAR LAND, TX 77498

## ADMINISTRATION

| | |
|---|---|
| DR. MARCELL SMITH | SUPERINTENDENT OF FBISD |
| DR. ANDRIA SCHUR, Ed.D. | CHIEF OF SCHOOLS |

## BOARD OF TRUSTEES

| | |
|---|---|
| KRISTIN K. TASSIN | PRESIDENT |
| RICK GARCIA | VICE PRESIDENT |
| DAVID HAMILTON | SECRETARY |
| ANGIE HANAN | BOARD MEMBER |
| ADAM SCHOOF | BOARD MEMBER |
| DR. SHIRLEY ROSE-GILLIAM | BOARD MEMBER |
| SONYA JONES | BOARD MEMBER |

## PROJECT DESIGN TEAM

PROGRAM MANAGEMENT
FBISD 2023 Bond Team
2323 Texas Parkway
Missouri City, TX 77489
Phone Number: 281-327-5481

ARCHITECT
MWA Architects
11767 Katy Freeway, Suite 430
Houston, Texas 77079
Phone Number: 713-782-8188


FOOD SERVICE
Food Design Professionals
26215 Oak Ridge Drive
The Woodlands, Texas 77380
Phone Number: 281-350-2323

MEP ENGINEERS
Stanton Engineering Group
1300 W. Sam Houston Pkwy South, Suite 121
Houston, Texas 77042
Phone Number: 713-300-9292


STRUCTURAL ENGINEER
Stanley Spurling & Hamilton
3301 Edloe Street, Suite 200
Houston, Texas 77027
Phone Number: 713-776-9433

ISSUED FOR PERMIT AND BIDDING - JULY 18, 2025

CC





## 2 SCHEMATIC LAYOUT




NOTES:
1. ALL TO BE GALV. & PAINTED SAFETY YELLOW
2. PROVIDE PLAN & DETAILS IN SUBMITIDAL FOR LOCATION AND ARCH. APPROVAL
3. MOUNT BOLLARD PLIMB.

## 3 BOLLARD
SCALE: 1- 1/2"=1'-0"




## 1 SITE PLAN
SCALE: 1"=10'-0"

GENERAL NOTES:
- A. TEMPARAY RENTAL FREEZER, CONTRACTOR FURNISHED & CONTRACTOR INSTALLED. COORDINATE W/ ARCHITECT FOR PROCUREMENT, DELIVERY AND CONNECTION TO POWER CANENSATE DISCHARGE. BASIS OF DESIGN SHALL BE POLAR LEASING DT180 (OTHER MODLES TO BE ACCEPTED WITH ARCHITECT APPROVAL)
- B. CONTRACTOR SHALL FURNISH ELECT. REQUIREMENTS: MIN. 30A, 220V. AS MINIMUM PRICING. SEE ELECTRICAL FOR ADDITIONAL IFORMATION.
- C. LOCATED UNIT WITHIN 100' (APPROX.) OF EXISTING ELECTRICAL ROOM.
- D. INSTALL 1" CONDENSATE DRAIN, CONNECT TO UNIT AS PER PROVIDER INSTRUCTS. KEEP DRAIN LINE AWAY FROM TRAFFIC AREAS. DISCHARGE AS PER PLUMBING DRAWINGS A LOCAL CODES.
- E. PROVIDE EIGHT 4'/ 48" ABV. PAVING BOLT-DOWN TEMPORARY BOLLARDS AROUND UNIT. PATCH HOLES UPON REMOVAL.
- F. SUBMIT LOCATION PLAN IN SUBMITTAL FOR LACATION APPROVAL BY ARCHITECTS.
- G. LOCATE UNIT IN AREA THAT:
  - G.1. HAS BEEN APPROVED INSURMITTAL
  - G.2. WITHIN 100' OF ELECT. CONNECTION
  - G.3. WILL NOT BLOCK WATER FLOW
  - G.4. AWAY FROM EXISTING AREAS SUBJECT TO STANDING WATER

| PHASING CHART FOR ALL SCHOOLS | | |
|---|---|---|
| PHASE 1 | | |
| **SCHOOLS** | **FREEZER START DATE :** | **FREEZER END DATE :** |
| ***FIRST COLONY MS*** | 11/7/2025 | EST. END DATE IS 5/13/2026 BUT ALL SCHOOLS BEING SERVED MUST BE SUBSTATIALLY COMPLETE |
| LAKEVIEW ES | | |
| **PHASE 2** | | |
| FIRST COLONY MS | 5/29/2026 | EST. END DATE IS 10/28/2026 BUT ALL SCHOOLS BEING SERVED MUST BE SUBSTATIALLY COMPLETE |
| ***LAKE OLYMPIA MS*** | | |
| PHASE 3 | | |
| MARSHAL HS | 3/19/2027 | EST. END DATE IS 3/19/2027 BUT ALL SCHOOLS BEING SERVED MUST BE SUBSTATIALLY COMPLETE |
| TRAVIS HS | | |
| DULLES HS | | |

NOTES:
1. FREEZER SHALL STAY IN OPERATION UNTIL ALL SCHOOLS BEING SERVED FROM THIS LOCATION HAVE ACHIVED SUBSTANTIAL COMPLETION

THIS SCHOOL WILL SUPPLY FOOD SERVICES DURING PHASE 2

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

CC

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
LAKE OLYMPIA MIDDLE SCHOOL
3100 LAKE OLYMPIA PARKWAY
MISSOURI CITY, TX 77459

SEAL
REGISTERED ARCHITECT
PAUL A. MAYER
22651
STATE OF TEXAS
7/15/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

TEMPORARY COOKING LOCATION SITE PLAN

cc-A.101

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings_TEMPORARY COOKING SITES\LakeOlympiaMiddleSchoolSitePlan.dwg Jul 28, 2025 - 4:26pm




## 2 OVERALL FLOOR PLAN - LAKE OLYMPIA MS

SCALE: 1" = 50'- 0"

## SYMBOL LEGEND

| | |
|---|---|
| ⊕/⊕/⊕ | SIMPLEX/DUPLEX/QUAD – 5361/2 REC |
| GFI | DUPLEX W/ GFCI PROTECTION–P&S 2097 |
| J | J–BOX |
| | CEILING MOUNTED J–BOX |
| M | MOTOR |
| | HEAVY DUTY, NON–FUSED DISCONNECT. MIN RATING OF CIRCUIT OCPD/VOLTAGE. |
| | ELECTRICAL PANEL |
| | HOMERUN TO CIRCUIT NOTED |
| E | EXISTING DEVICES TO REMAIN |
| R | EXISTING DEVICES TO BE RELOCATED |
| D | EXISTING DEVICES TO BE DEMO/REMOVED |
| RDP | EXISTING DEVICES TO BE REPLACED |
| S | INDICATES SURFACE MOUNTED |
| SR | INDICATES SURFACE RACEWAY |
| ^ | INDICATES ABOVE COUNTER DEVICE |
| + | INDICATES DEVICE AT +30–60" |
| ++ | INDICATES DEVICE AT +80–96" |
| CLG | INDICATES DEVICES MOUNTED IN CEILING |
| WP | INDICATES WEATHERPROOF COVER |
| 3R | INDICATES 3R RATED DEVICE |
| (E)LA–X | CONNECT(ED) TO EXIST CIRCUIT LA–X |
| (D)LA–X | DEMO PORTION OF EXIST CIRCUIT LA–X |
| (N)LA–X | CONNECT(ED) TO NEW CIRCUIT LA–X |

**GENERAL ELECTRICAL NOTES:**

1. INSTALL SYSTEM IN ACCORDANCE WITH THE NATIONAL ELECTRIC CODE AS ADOPTED BY THE LOCAL AUTHORITY HAVING JURISDICTION INCLUDING ALL AMENDMENTS.
2. PROVIDE CONDUIT FOR ALL DEVICES INSTALLED IN WALLS.
   - 2.A. 3/4"C FOR POWER AND 1"C FOR LOW VOLTAGE/DATA UNLESS NOTED OTHERWISE.
   - 2.B. PROVIDE PROTECTIVE BUSHING ON END OF ALL LOW VOLTAGE CONDUITS.
   - 2.C. ALL ELECTRICAL HOMERUNS SHALL BE IN CONDUIT, MIN 3/4"C.
   - 2.D. USE INSULATED THROAT FITTINGS FOR CONNECTIONS TO HOUSINGS, BOXES, ENCLOSURES, ETC.
   - 2.E. MAX LENGTH FOR FLEX CONDUIT SHALL BE 6FT AND MIN. SIZE SHALL BE 1/2". ALL FLEX CONDUIT SHALL BE LISTED FOR GROUNDING.
3. CONDUIT TYPES:
   - 3.A. INSIDE BUILDINGS: GALVANIZED STEEL EMT.
     - 3.A.A. ALL LOW VOLTAGE CABLING SHALL BE INSTALLED IN CONDUIT IN EXPOSED CEILING AREAS. ROUTE TO NEAREST ACCESSIBLE CEILING WITH CONTINUOUS PATHWAYS TO LOW VOLTAGE SOURCE/DEVICE.
     - 3.A.B. ALL LOW VOLTAGE CABLING SHALL BE INSTALLED IN CONDUIT ABOVE INACCESSIBLE CEILINGS. ROUTE TO NEAREST ACCESSIBLE CEILING WITH CONTINUOUS PATHWAYS TO LOW VOLTAGE SOURCE/DEVICE.
   - 3.B. NO MC CABLE SHALL BE ALLOWED.
   - 3.C. PROVIDE FLEXIBLE CONNECTIONS TO MOTORS, PUMPS, TRANSFORMERS, OR SIMILAR EQUIPMENT.
4. PROVIDE GALVANIZED STEEL, ONE–PIECE CONSTRUCTION, OUTLET BOXES IN ALL CASES SUITABLE FOR INTENDED USE.
   - 4.A. BOXES OUTSIDE SHALL BE STEEL NEMA 3 TYPE.
   - 4.B. PROVIDE CEILING BRACKET TO SUPPORT CEILING MOUNTED DEVICES FROM CEILING TEES.
5. 20 AMP, SINGLE PHASE BRANCH CIRCUITS SERVING LIGHTING AND GENERAL RECEPTACLES MAY BE GROUPED IN A SINGLE RACEWAY PROVIDED A NEUTRAL CONDUCTOR IS INSTALLED FOR EACH CIRCUIT REQUIRING A NEUTRAL.
   - 5.A. DO NOT INSTALL MORE THAN FOUR CURRENT CARRYING CONDUCTORS IN A CONDUIT EXCEPT SIX #12 OR #10 CURRENT CARRYING CONDUCTORS MAY BE INSTALLED IN 3/4" OR LARGER CONDUIT FOR 20A CIRCUITS.
   - 5.B. DO NOT INSTALL 480/277 VOLT CONDUCTORS IN THE SAME CONDUIT WITH 240/208/120 VOLT CONDUCTORS.
   - 5.C. DO NOT COMBINE NEUTRALS. PROVIDE DEDICATED NEUTRALS FOR EACH BRANCH CIRCUIT.
   - 5.D. MULTIPLE DEVICES ON A CIRCUIT SUCH AS RECEPTACLES SHALL BE WIRED WITH A PIGTAIL SO THE DEVICE DOES NOT PROMOTE THE CONTINUITY PATH. FEED THROUGH CONNECTIONS FOR GFCI RECEPTACLES SHALL NOT BE USED FOR PROTECTION OF DOWNSTREAM DEVICES.
6. PROVIDE GREEN GROUND WIRE WITH ALL CIRCUITS SIZED PER NEC. BOND GREEN GROUND WIRE TO EACH END OF CONDUIT.
7. PROVIDE J–BOXES, CONDUIT AND SLEEVES THRU ALL FIRE WALLS FOR DATA, TELEPHONE, SECURITY, FIRE ALARM, SOUND SYSTEM, LOW VOLTAGE WIRING, ETC. PROVIDE PROTECTIVE BUSHINGS ON ENDS OF ALL LOW VOLTAGE CONDUITS.
8. PROVIDE PULL BOXES, JUNCTION BOXES, WIRING TROUGHS AND CABINETS WHEREVER REQUIRED FOR PROPER INSTALLATION OF VARIOUS ELECTRICAL SYSTEMS. ALL JUNCTION/PULL BOXES INSTALLED ABOVE ACCESSIBLE CEILINGS SHALL BE MOUNTED SO THAT THE ACCESS PANEL IS NO HIGHER THAN 18" ABOVE THE CEILING.
9. PROVIDE CIRCUIT LABELS IN PERMANENT MARKER ON ALL NEW AND EXISTING J–BOX COVERS UTILIZED IN THE AREA OF RENOVATION.
10. PROVIDE CIRCUIT LABEL ON ALL ABOVE CEILING J–BOXES, EQUIPMENT, ETC. IDENTIFYING THE CIRCUITS CONTAINED/CONNECTED.
11. ALL WIRING SHALL BE 600 VOLT, SOFT DRAWN ANNEALED COPPER, 98% CONDUCTIVITY, CONTINUOUS FROM OUTLET TO OUTLET. MINIMUM WIRE SIZE #12.
    - 11.A TYPICAL BUILDING WIRE SHALL BE STRANDED TYPE THHN, THWN–2 (WET RATED FOR 90°C), OR XHHW–2. MINIMUM WIRE SIZE SHALL BE #12.
    - 11.B ALL BUILDING WIRE SHALL BE COLOR CODED WITH THE SAME COLOR CONNECTED TO THE SAME UNGROUNDED PHASE THROUGHOUT THE INSTALLATION MATCHING THE EXISTING BUILDING COLOR CODE SCHEME.
12. WHERE PORTIONS OF INTERIOR RACEWAY SYSTEM ARE EXPOSED TO WIDELY DIFFERENT TEMPERATURES, PROVIDE AIR SEAL PER NEC TO PREVENT CIRCULATION OF AIR FROM WARMER TO COOLER SECTIONS.
13. DRAWINGS, SCHEDULES, NOTES, AND DETAILS ARE INTENDED TO BE COMPLIMENTARY. ANY WORK DESCRIBED IN ANY OF THEM, WILL BE WORK REQUIRED UNDER THIS CONTRACT. WHERE THERE IS A CONFLICT BETWEEN DIFFERENT PORTIONS OF THE DESIGN DOCUMENTS IT SHALL BE CLARIFIED BY RFI, BARRING CLARIFICATION PRIOR TO BIDDING THE MOST EXPENSIVE OPTION SHALL BE INCLUDED AND CLARIFICATION SHALL BE MADE DURING CONSTRUCTION.
14. SHOULD ANY WORK REQUIRED BY THE DRAWINGS AND SPECIFICATIONS BE IN VIOLATION OF ANY FEDERAL, STATE, COUNTY OR CITY LAWS, ORDINANCE OR REGULATION, THOSE LAWS AND REGULATIONS SHALL PREVAIL, AND SHALL BE COMPLIED WITH BY THE CONTRACTOR AS A PART OF THIS WORK WITH NO EXTRA COMPENSATION.
15. ALL MATERIAL MUST BE NEW AND OF GOOD QUALITY AND SHALL BEAR THE STAMP OF APPROVAL OF THE UNDERWRITERS' LABORATORIES, INC. (U.L.).

**GENERAL RENOVATION AND REMODELING NOTES:**

1. THESE ELECTRICAL DRAWINGS ONLY SHOW SOME EXISTING ELECTRICAL PANELS, DEVICES AND LIGHT FIXTURES IN AREAS OF RENOVATION. ALL OTHER ELECTRICAL EQUIPMENT, WIRING DEVICES, LOW VOLTAGE SYSTEMS, J–BOXES AND CONDUITS SHALL BE LOCATED AND FIELD VERIFIED BY CONTRACTOR.
2. ALL REMOVED DEVICES SHALL BE OFFERED TO THE OWNER AS SALVAGE.
3. RELOCATE CONDUIT AS NECESSARY TO ALLOW NEW OR MODIFIED CONSTRUCTION. RESUPPORT EXISTING CABLING/CONDUIT TO REMAIN TO MEET CURRENTLY ADOPTED CODE REQUIREMENTS. REMOVE ALL ABANDONED CONDUIT AND WIRE. REPAIR EXISTING ELECTRICAL SYSTEMS DAMAGED BY CONSTRUCTION ACTIVITIES.
4. ANY DAMAGE TO EXISTING BUILDING, ELECTRICAL EQUIPMENT, WIRING DEVICES, CONDUIT, WIRING, ETC. SHALL BE REPLACED BY THE CONTRACTOR AT NO COST TO THE OWNER. ALL MATERIALS USED FOR THE REPLACEMENT MUST MEET RENOVATION PROJECT STANDARDS.
5. ELECTRICAL CONTRACTOR SHALL BEGIN FIELD VERIFYING ALL EXISTING BRANCH CIRCUITS FOR EXISTING AREAS TO BE RENOVATED IMMEDIATELY AFTER THE CONTRACT IS ISSUED.
6. ELECTRICAL CONTRACTOR SHALL FIELD VERIFY EXISTING CIRCUITS WITH OWNER'S MAINTENANCE PERSONNEL AFTER NORMAL BUILDING HOURS AS REQUIRED.
7. ANY CIRCUIT OR PARTIAL CIRCUIT TO REMAIN OR BE REUSED SHALL REMAIN ACTIVE.
8. ELECTRICAL CONTRACTOR SHALL INCLUDE COST RELATED TO FIELD VERIFY EXISTING CIRCUITS IN BASE PROPOSAL.
9. FIND AND RECORD ALL EXISTING DEVICES IN CEILINGS, WALLS AND CASEWORK IN AREAS TO BE RENOVATED. PROVIDE A COPY OF THE FIELD VERIFIED DEVICE DRAWINGS TO OWNER PRIOR TO BEGINNING WORK.
10. AT THE END OF THE PROJECT, PROVIDE A NEW TYPEWRITTEN AS–BUILT PANEL SCHEDULE FOR ALL PANELS WITH CIRCUITS ADDED, REMOVED, OR MODIFIED AS PART OF THE PROJECT USING BUILDING ROOM NUMBERS.




## 1 ELECTRICAL RENOVATION PLAN - LAKE OLYMPIA MS


SCALE: 1/8" = 1'- 0"

**EXIST TO REMAIN**

**PANEL ELA** — 150A MCB, 208Y/120V, 3ø, 4 WIRE — MOUNTING: SURFACE — AVAILABLE FAULT: SCCR & AIC:

| | LOAD | DESCRIPTION | ROOM | WIRE | CB | CKT | A B C | CKT | CB | WIRE | DESCRIPTION | ROOM | LOAD |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | 500 | BOILER 1 PUMPS | | EXIST | 20/1 | 1 | | 2 | 20/3 | EXIST | REFRIGERATION RACK | | 4000 |
| | 500 | BOILER 2 PUMPS | | EXIST | 20/1 | 3 | | 4 | – | – | – | | – |
| | | EXIST SPARE | | EXIST | 20/1 | 5 | | 6 | – | – | – | | – |
| | 1500 | FREEZER COIL | | EXIST | 20/3 | 7 | | 8 | 20/3 | EXIST | COOLER COIL | | 4000 |
| | – | – | | – | – | 9 | | 10 | – | – | – | | – |
| | – | – | | – | – | 11 | | 12 | – | – | – | | – |
| | | EXIST SPARE | | | 20/1 | 13 | | 14 | 20/1 | | EXIST SPARE | | |
| | 500 | COOLER & FREEZER LTS | | EXIST | 20/1 | 15 | | 16 | 20/1 | EXIST | CONDENSATE DRAIN SYS | | 500 |
| | 500 | KIT FIRE SYSTEM | | EXIST | 20/1 | 17 | | 18 | 20/1 | EXIST | EXIST SPARE | | |
| | | EXIST SPARE | | | 20/1 | 19 | | 20 | 100/3 | EXIST | TRANSFORMER T–7 | | 15000 |
| | 500 | BOILER 2 | | EXIST | 20/1 | 21 | | 22 | – | – | – | | – |
| | 500 | BOILER 1 | | EXIST | 20/1 | 23 | | 24 | – | – | – | | – |
| NOTE 2 | 500 | EXIST CKT | | EXIST | 20/1 | 25 | | 26 | 60/3 | | EXIST SPARE | | |
| NOTE 1 | 3100 | FOOD STORAGE UNIT | | 2–10 | 30/2 | 27 | | 28 | – | | – | | |
| | – | – | | +10N+10G | 3/4"C | 29 | | 30 | – | | – | | |
| | TOTAL LOAD ❂ 100% = 31600VA | | | | | TOTAL LOAD ❂ 100% = 88A | | | | | TOTAL LOAD ❂ 125% = 110A | | |

1. PROVIDE NEW CB & WIRE NEW CIRCUIT.
2. RELOCATE 20/1 CB IN CKT 27 TO CKT 25 TO ALLOW INSTALLATION OF NEW 30/2P CIRCUIT BREAKER.




## 3 LAKE OLYMPIA MS PARTIAL ELECTRICAL RISER

NO SCALE

NOTES:

1. ALL PANELS, TRANSFORMERS, SWITCHBOARD AND TRANSFER SWITCH ARE EXISTING. ADD 30/2 CB TO PANEL ELA AND EXTEND 3–10+10N+10G, 3/4"C TO NEW FUSED SWITCH.
2. RELOCATE ONE EXISTING CIRCUIT IN PANEL ELA TO ALLOW FOR TWO POLE CIRCUIT BREAKER.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

CC

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT

LAKE OLYMPIA MIDDLE SCHOOL
3100 LAKE OLYMPIA PARKWAY
MISSOURI CITY, TX 77459

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
LICENSED
PROFESSIONAL ENGINEER
07.18.2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL FLOOR PLAN & SCHEDULES

cc-E.200

STANTON ENGINEERING GROUP
INFORMATION@STANTONENGR.COM (713) 300–6080
TEXAS ENG. FIRM REG. NO. F–01853(14) 2025 ALL RIGHTS RESERVED
12999 W. SAM HOUSTON PARKWAY S., SUITE 125, HOUSTON, TX 77072

# FBISD BP013 KITCHEN RENOVATIONS ES

| Sheet List Table | |
|---|---|
| Sheet Number | Sheet Title |
| School: dd-Marshall HS | |
| ds-A.000 | COVER AND INDEX |
| ds-A.101 | TEMPORARY COOKING LOCATION SITE PLAN |
| ds-E.200 | ELECTRICAL FLOOR PLAN & SCHEDULES |




FORT BEND INDEPENDENT SCHOOL DISTRICT

THURGOOD MARSHALL HIGH SCHOOL
1220 BUFFALO RUN, MISSOURI CITY, TX 77489

## ADMINISTRATION

| | |
|---|---|
| DR. MARCELL SMITH | SUPERINTENDENT OF FBISD |
| DR. ANDRIA SCHUR, Ed.D. | CHIEF OF SCHOOLS |

## BOARD OF TRUSTEES

| | |
|---|---|
| KRISTIN K. TASSIN | PRESIDENT |
| RICK GARCIA | VICE PRESIDENT |
| DAVID HAMILTON | SECRETARY |
| ANGIE HANAN | BOARD MEMBER |
| ADAM SCHOOF | BOARD MEMBER |
| DR. SHIRLEY ROSE-GILLIAM | BOARD MEMBER |
| SONYA JONES | BOARD MEMBER |

## PROJECT DESIGN TEAM

PROGRAM MANAGEMENT
FBISD 2023 Bond Team
2323 Texas Parkway
Missouri City, TX 77489
Phone Number: 281-327-5481

ARCHITECT
MWA Architects
11767 Katy Freeway, Suite 430
Houston, Texas 77079
Phone Number: 713-782-8188


FOOD SERVICE
Food Design Professionals
26215 Oak Ridge Drive
The Woodlands, Texas 77380
Phone Number: 281-350-2323

MEP ENGINEERS
Stanton Engineering Group
1300 W. Sam Houston Pkwy South, Suite 121
Houston, Texas 77042
Phone Number: 713-300-9292

STRUCTURAL ENGINEER
Stanley Spurling & Hamilton
3301 Edloe Street, Suite 200
Houston, Texas 77027
Phone Number: 713-776-9433


ISSUED FOR PERMIT AND BIDDING - JULY 18, 2025

dd




## 2 SCHEMATIC LAYOUT

PROPOSED TEMPORARY FREEZER LOCATION. CONFFIRM WITH ARCH. BEFORE INSTALLING




NOTES:
1. ALL TO BE GALV. & PAINTED SAFETY YELLOW
2. PROVIDE PLAN & DETAILS IN SUBMITIDAL FOR LOCATION AND ARCH. APPROVAL
3. MOUNT BOLLARD PLIMB.

## 3 BOLLARD
SCALE: 1- 1/2"=1'-0"

APPROX. LOCATION OF NEAREST ELECTRICAL ROOM OR ELECTRICAL PANEL RE: ELEC SHEETS.



## 1 SITE PLAN
SCALE: 1"=30'-0"

THIS SCHOOL WILL SUPPLY FOOD SERVICES DURING PHASE 3

GENERAL NOTES:
- A. TEMPARAY RENTAL FREEZER, CONTRACTOR FURNISHED & CONTRACTOR INSTALLED. COORDINATE W/ ARCHITECT FOR PROCUREMENT, DELIVERY AND CONNECTION TO POWER CANENSATE DISCHARGE. BASIS OF DESIGN SHALL BE POLAR LEASING DT180 (OTHER MODLES TO BE ACCEPTED WITH ARCHITECT APPROVAL)
- B. CONTRACTOR SHALL FURNISH ELECT. REQUIREMENTS: MIN. 30A, 220V, AS MINIMUM PRICING. SEE ELECTRICAL FOR ADDITIONAL IFORMATION.
- C. LOCATED UNIT WITHIN 100' (APPROX.) OF EXISTING ELECTRICAL ROOM.
- D. INSTALL 1" CONDENSATE DRAIN, CONNECT TO UNIT AS PER PROVIDER INSTRUCTS. KEEP DRAIN LINE AWAY FROM TRAFFIC AREAS. DISCHARGE AS PER PLUMBING DRAWINGS A LOCAL CODES.
- E. PROVIDE EIGHT 4'/ 48" ABV. PAVING BOLT-DOWN TEMPORARY BOLLARDS AROUND UNIT. PATCH HOLES UPON REMOVAL.
- F. SUBMIT LOCATION PLAN IN SUBMITTAL FOR LACATION APPROVAL BY ARCHITECTS.
- G. LOCATE UNIT IN AREA THAT:
  - G.1. HAS BEEN APPROVED INSURMITTAL
  - G.2. WITHIN 100' OF ELECT. CONNECTION
  - G.3. WILL NOT BLOCK WATER FLOW
  - G.4. AWAY FROM EXISTING AREAS SUBJECT TO STANDING WATER

| PHASING CHART FOR ALL SCHOOLS | | |
|---|---|---|
| PHASE 1 | | |
| SCHOOLS | FREEZER START DATE : | FREEZER END DATE : |
| FIRST COLONY MS | 3/19/2025 | EST. END DATE IS 5/13/2026 BUT ALL SCHOOLS BEING SERVED MUST BE SUBSTATIALLY COMPLETE |
| LAKEVIEW ES | | |
| PHASE 2 | | |
| FIRST COLONY MS | 5/13/2026 | EST. END DATE IS 10/28/2026 BUT ALL SCHOOLS BEING SERVED MUST BE SUBSTATIALLY COMPLETE |
| LAKE OLYMPIA MS | | |
| PHASE 3 | | |
| *MARSHAL HS* | 3/19/2027 | EST. END DATE IS 3/19/2027 BUT ALL SCHOOLS BEING SERVED MUST BE SUBSTATIALLY COMPLETE |
| TRAVIS HS | | |
| DULLES HS | | |

NOTES:
1. FREEZER SHALL STAY IN OPERATION UNTIL ALL SCHOOLS BEING SERVED FROM THIS LOCATION HAVE ACHIVED SUBSTANTIAL COMPLETION

Creenshot 2025-06-16 133508.p

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

dd

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
THURGOOD MARSHALL HIGH SCHOOL
1220 BUFFALO RUN
MISSOUR CITY, TX 77489

SEAL




7/15/2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

TEMPORARY COOKING LOCATION SITE PLAN

dd-A.101

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings_TEMPORARY COOKING SITES\ThurgoodMarshallHighSchoolSitePlan.dwg Jul 28, 2025 - 4:27pm




## 2 OVERALL FLOOR PLAN - THURGOOD MARSHALL HS

SCALE: 1" = 100'- 0"

## SYMBOL LEGEND

- SIMPLEX/DUPLEX/QUAD – 5361/2 REC
- GFI DUPLEX W/ GFCI PROTECTION–P&S 2097
- J J–BOX
- CEILING MOUNTED J–BOX
- MOTOR
- HEAVY DUTY, NON–FUSED DISCONNECT. MIN RATING OF CIRCUIT OCPD/VOLTAGE.
- ELECTRICAL PANEL
- HOMERUN TO CIRCUIT NOTED

| | |
|---|---|
| E | EXISTING DEVICES TO REMAIN |
| R | EXISTING DEVICES TO BE RELOCATED |
| D | EXISTING DEVICES TO BE DEMO/REMOVED |
| RDP | EXISTING DEVICES TO BE REPLACED |
| S | INDICATES SURFACE MOUNTED |
| SR | INDICATES SURFACE RACEWAY |
| * | INDICATES ABOVE COUNTER DEVICE |
| + | INDICATES DEVICE AT +30–60" |
| ++ | INDICATES DEVICE AT +80–96" |
| CLG | INDICATES DEVICES MOUNTED IN CEILING |
| WP | INDICATES WEATHERPROOF COVER |
| 3R | INDICATES 3R RATED DEVICE |
| (E)La–X | CONNECT(ED) TO EXIST CIRCUIT LA–X |
| (D)La–X | DEMO PORTION OF EXIST CIRCUIT LA–X |
| (N)La–X | CONNECT(ED) TO NEW CIRCUIT LA–X |

GENERAL ELECTRICAL NOTES:

1. INSTALL SYSTEM IN ACCORDANCE WITH THE NATIONAL ELECTRIC CODE AS ADOPTED BY THE LOCAL AUTHORITY HAVING JURISDICTION INCLUDING ALL AMENDMENTS.
2. PROVIDE CONDUIT FOR ALL DEVICES INSTALLED IN WALLS.
   - 2.A. 3/4"C FOR POWER AND 1"C FOR LOW VOLTAGE/DATA UNLESS NOTED OTHERWISE.
   - 2.B. PROVIDE PROTECTIVE BUSHING ON END OF ALL LOW VOLTAGE CONDUITS.
   - 2.C. ALL ELECTRICAL HOMERUNS SHALL BE IN CONDUIT, MIN 3/4"C.
   - 2.D. USE INSULATED THROAT FITTINGS FOR CONNECTIONS TO HOUSINGS, BOXES, ENCLOSURES, ETC.
   - 2.E. MAX LENGTH FOR FLEX CONDUIT SHALL BE 6FT AND MIN. SIZE SHALL BE 1/2". ALL FLEX CONDUIT SHALL BE LISTED FOR GROUNDING.
3. CONDUIT TYPES:
   - 3.A. INSIDE BUILDINGS: GALVANIZED STEEL EMT.
     - 3.A.A. ALL LOW VOLTAGE CABLING SHALL BE INSTALLED IN CONDUIT IN EXPOSED CEILING AREAS. ROUTE TO NEAREST ACCESSIBLE CEILING WITH CONTINUOUS PATHWAYS TO LOW VOLTAGE SOURCE/DEVICE.
     - 3.A.B. ALL LOW VOLTAGE CABLING SHALL BE INSTALLED IN CONDUIT ABOVE INACCESSIBLE CEILINGS. ROUTE TO NEAREST ACCESSIBLE CEILING WITH CONTINUOUS PATHWAYS TO LOW VOLTAGE SOURCE/DEVICE.
   - 3.B. NO MC CABLE SHALL BE ALLOWED.
   - 3.C. PROVIDE FLEXIBLE CONNECTIONS TO MOTORS, PUMPS, TRANSFORMERS, OR SIMILAR EQUIPMENT.
4. PROVIDE GALVANIZED STEEL, ONE–PIECE CONSTRUCTION, OUTLET BOXES IN ALL CASES SUITABLE FOR INTENDED USE.
   - 4.A. BOXES OUTSIDE SHALL BE STEEL NEMA 3 TYPE.
   - 4.B. PROVIDE CEILING BRACKET TO SUPPORT CEILING MOUNTED DEVICES FROM CEILING TEES.
5. 20 AMP, SINGLE PHASE BRANCH CIRCUITS SERVING LIGHTING AND GENERAL RECEPTACLES MAY BE GROUPED IN A SINGLE RACEWAY PROVIDED A NEUTRAL CONDUCTOR IS INSTALLED FOR EACH CIRCUIT REQUIRING A NEUTRAL.
   - 5.A. DO NOT INSTALL MORE THAN FOUR CURRENT CARRYING CONDUCTORS IN A CONDUIT EXCEPT SIX #12 OR #10 CURRENT CARRYING CONDUCTORS MAY BE INSTALLED IN 3/4" OR LARGER CONDUIT FOR 20A CIRCUITS.
   - 5.B. DO NOT INSTALL 480/277 VOLT CONDUCTORS IN THE SAME CONDUIT WITH 240/208/120 VOLT CONDUCTORS.
   - 5.C. DO NOT COMBINE NEUTRALS. PROVIDE DEDICATED NEUTRALS FOR EACH BRANCH CIRCUIT.
   - 5.D. MULTIPLE DEVICES ON A CIRCUIT SUCH AS RECEPTACLES SHALL BE WIRED WITH A PIGTAIL SO THE DEVICE DOES NOT PREMBE THE CONTINUITY PATH. FEED THROUGH CONNECTIONS FOR GFCI RECEPTACLES SHALL NOT BE USED FOR PROTECTION OF DOWNSTREAM DEVICES.
6. PROVIDE GREEN GROUND WIRE WITH ALL CIRCUITS SIZED PER NEC. BOND GREEN GROUND WIRE TO EACH END OF CONDUIT.
7. PROVIDE J–BOXES, CONDUIT AND SLEEVES THRU ALL FIRE WALLS FOR DATA, TELEPHONE, SECURITY, FIRE ALARM, SOUND SYSTEM, LOW VOLTAGE WIRING, ETC. PROVIDE PROTECTIVE BUSHINGS ON ENDS OF ALL LOW VOLTAGE CONDUITS.
8. PROVIDE PULL BOXES, JUNCTION BOXES, WIRING TROUGHS AND CABINETS WHEREVER REQUIRED FOR PROPER INSTALLATION OF VARIOUS ELECTRICAL SYSTEMS. ALL JUNCTION/PULL BOXES INSTALLED ABOVE ACCESSIBLE CEILINGS SHALL BE MOUNTED SO THAT THE ACCESS PANEL IS NO HIGHER THAN 18" ABOVE THE CEILING.
9. PROVIDE CIRCUIT LABELS IN PERMANENT MARKER ON ALL NEW AND EXISTING J–BOX COVERS UTILIZED IN THE AREA OF RENOVATION.
10. PROVIDE CIRCUIT LABEL ON ALL ABOVE CEILING J–BOXES, EQUIPMENT, ETC. IDENTIFYING THE CIRCUITS CONTAINED/CONNECTED.
11. ALL WIRING SHALL BE 600 VOLT, SOFT DRAWN ANNEALED COPPER, 98% CONDUCTIVITY, CONTINUOUS FROM OUTLET TO OUTLET. MINIMUM WIRE SIZE #12.
    - 11.A. TYPICAL BUILDING WIRE SHALL BE STRANDED TYPE THHN, THWN–2 (WET RATED FOR 90°C), OR XHHW–2. MINIMUM WIRE SIZE SHALL BE #12.
    - 11.B. ALL BUILDING WIRE SHALL BE COLOR CODED WITH THE SAME COLOR CONNECTED TO THE SAME UNGROUNDED PHASE THROUGHOUT THE INSTALLATION MATCHING THE EXISTING BUILDING COLOR CODE SCHEME.
12. WHERE PORTIONS OF INTERIOR RACEWAY SYSTEM ARE EXPOSED TO WIDELY DIFFERENT TEMPERATURES, PROVIDE AIR SEAL PER NEC TO PREVENT CIRCULATION OF AIR FROM WARMER TO COOLER SECTIONS.
13. DRAWINGS, SCHEDULES, NOTES, AND DETAILS ARE INTENDED TO BE COMPLIMENTARY. ANY WORK DESCRIBED IN ANY OF THEM, WILL BE WORK REQUIRED UNDER THIS CONTRACT. WHERE THERE IS A CONFLICT BETWEEN DIFFERENT PORTIONS OF THE DESIGN DOCUMENTS IT SHALL BE CLARIFIED BY RFI, BARRING CLARIFICATION PRIOR TO BIDDING THE MOST EXPENSIVE OPTION SHALL BE INCLUDED AND CLARIFICATION SHALL BE MADE DURING CONSTRUCTION.
14. SHOULD ANY WORK REQUIRED BY THE DRAWINGS AND SPECIFICATIONS BE IN VIOLATION OF ANY FEDERAL, STATE, COUNTY OR CITY LAWS, ORDINANCE OR REGULATION, THOSE LAWS AND REGULATIONS SHALL PREVAIL, AND SHALL BE COMPLIED WITH BY THE CONTRACTOR AS A PART OF THIS WORK WITH NO EXTRA COMPENSATION.
15. ALL MATERIAL MUST BE NEW AND OF GOOD QUALITY AND SHALL BEAR THE STAMP OF APPROVAL OF THE UNDERWRITERS' LABORATORIES, INC. (U.L.).

GENERAL RENOVATION AND REMODELING NOTES:

1. THESE ELECTRICAL DRAWINGS ONLY SHOW SOME EXISTING ELECTRICAL PANELS, DEVICES AND LIGHT FIXTURES IN AREAS OF RENOVATION. ALL OTHER ELECTRICAL EQUIPMENT, WIRING DEVICES, LOW VOLTAGE SYSTEMS, J–BOXES AND CONDUITS SHALL BE LOCATED AND FIELD VERIFIED BY CONTRACTOR.
2. ALL REMOVED DEVICES SHALL BE OFFERED TO THE OWNER AS SALVAGE.
3. RELOCATE CONDUIT AS NECESSARY TO ALLOW NEW OR MODIFIED CONSTRUCTION. RESUPPORT EXISTING CABLING/CONDUIT TO REMAIN TO MEET CURRENTLY ADOPTED CODE REQUIREMENTS. REMOVE ALL ABANDONED CONDUIT AND WIRE. REPAIR EXISTING ELECTRICAL SYSTEMS DAMAGED BY CONSTRUCTION ACTIVITIES.
4. ANY DAMAGE TO EXISTING BUILDING, ELECTRICAL EQUIPMENT, WIRING DEVICES, CONDUIT, WIRING, ETC. SHALL BE REPLACED BY THE CONTRACTOR AT NO COST TO THE OWNER. ALL MATERIALS USED FOR THE REPLACEMENT MUST MEET RENOVATION PROJECT STANDARDS.
5. ELECTRICAL CONTRACTOR SHALL BEGIN FIELD VERIFYING ALL EXISTING BRANCH CIRCUITS FOR EXISTING AREAS TO BE RENOVATED IMMEDIATELY AFTER THE CONTRACT IS ISSUED.
6. ELECTRICAL CONTRACTOR SHALL FIELD VERIFY EXISTING CIRCUITS WITH OWNER'S MAINTENANCE PERSONNEL AFTER NORMAL BUILDING HOURS AS REQUIRED.
7. ANY CIRCUIT OR PARTIAL CIRCUIT TO REMAIN OR BE REUSED SHALL REMAIN ACTIVE.
8. ELECTRICAL CONTRACTOR SHALL INCLUDE COST RELATED TO FIELD VERIFY EXISTING CIRCUITS IN BASE PROPOSAL.
9. FIND AND RECORD ALL EXISTING DEVICES IN CEILINGS, WALLS AND CASEWORK IN AREAS TO BE RENOVATED. PROVIDE A COPY OF THE FIELD VERIFIED DEVICE DRAWINGS TO OWNER PRIOR TO BEGINNING WORK.
10. AT THE END OF THE PROJECT, PROVIDE A NEW TYPEWRITTEN AS–BUILT PANEL SCHEDULE FOR ALL PANELS WITH CIRCUITS ADDED, REMOVED, OR MODIFIED AS PART OF THE PROJECT USING BUILDING ROOM NUMBERS.




## 1 ELECTRICAL RENOVATION PLAN - THURGOOD MARSHALL HS

SCALE: 1/8" = 1'- 0"


### EXIST TO REMAIN

**PANEL EC** — 225A MLO, 208Y/120V, 3ø, 4 WIRE — MOUNTING: SURFACE — AVAILABLE FAULT: SCCR & AIC:

| LOAD | DESCRIPTION | ROOM | WIRE | CB | CKT | A | B | C | CKT | CB | WIRE | DESCRIPTION | ROOM | LOAD | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 500 | FIRE ALARM PANEL | | EXIST | 20/1 | 1 | | | | 2 | 60/3 | EXIST | REFRIGERATION RACK | | 10000 | |
| 500 | TELEPHONE T3 | | EXIST | 20/1 | 3 | | | | 4 | – | – | – | | – | |
| 500 | TELEPHONE T3 | | EXIST | 20/1 | 5 | | | | 6 | – | – | – | | – | |
| 500 | TELEPHONE T3 | | EXIST | 20/1 | 7 | | | | 8 | 30/1 | EXIST | KITCHEN REFRIG | | 1200 | |
| 500 | MAIN SOUND SYSTEM T3 | | EXIST | 20/1 | 9 | | | | 10 | 30/1 | EXIST | KITCHEN REFRIG | | 1200 | |
| 500 | PRO GYM SOUND SYSTEM | | EXIST | 20/1 | 11 | | | | 12 | 30/1 | EXIST | KITCHEN REFRIG | | 1200 | |
| 500 | AUX GYM SOUND SYSTEM | | EXIST | 20/1 | 13 | | | | 14 | 30/1 | EXIST | KITCHEN REFRIG | | 1200 | |
| 500 | SECURITY PANEL M210 | | EXIST | 20/1 | 15 | | | | 16 | 30/3 | 3–10 | FOOD STORAGE UNIT | | 3100 | NOTE 1 |
| 500 | SECURITY MONITOR M210 | | EXIST | 20/1 | 17 | | | | 18 | – | +10N+10G | – | | – | |
| 800 | BATTERY CHARGER M10 | | EXIST | 20/1 | 19 | | | | 20 | – | 3/4"C | NEW DUPLEX REC | | 180 | |
| 1200 | AUDITORIUM LTS SEATING | | EXIST | 20/1 | 21 | | | | 22 | | | SPACE | | | |
| 1200 | AUDITORIUM LTS SEATING | | EXIST | 20/1 | 23 | | | | 24 | | | SPACE | | | |
| 1200 | AUDITORIUM LTS SEATING | | EXIST | 20/1 | 25 | | | | 26 | | | SPACE | | | |
| 500 | COMMONS AMP | | EXIST | 20/1 | 27 | | | | 28 | | | SPACE | | | |
| 200 | SMOKE LOUVERS, S STRT | | EXIST | 20/1 | 29 | | | | 30 | | | SPACE | | | |
| 200 | SMOKE LOUVERS, S STRT | | EXIST | 20/1 | 31 | | | | 32 | | | SPACE | | | |
| 500 | VOICE EVAC AUDITORIUM | | EXIST | 20/1 | 33 | | | | 34 | | | SPACE | | | |
| 500 | VOICE EVAC GYM | | EXIST | 20/1 | 35 | | | | 36 | | | SPACE | | | |
| | SPACE | | | 20/1 | 37 | | | | 38 | | | SPACE | | | |
| | SPACE | | | 20/1 | 39 | | | | 40 | | | SPACE | | | |
| | SPACE | | | 20/1 | 41 | | | | 42 | | | SPACE | | | |
| TOTAL LOAD @ 100% = 28880VA | | | | | TOTAL LOAD @ 100% = 80A | | | | | | | TOTAL LOAD @ 125% = | | 100A | |

1. PROVIDE NEW CB & WIRE NEW CIRCUIT.

INSTALL 2–25A FUSES IN NEMA 3R FUSED SWITCH TO SERVE FOOD STORAGE UNIT AND A 20A FUSE IN THIRD PHASE TO FEED DUPLEX RECEPTACLE. WIRING TO STORAGE UNIT SHALL BE 2–10 +10N + 10G, 3/4" IN SEALTITE FLEX CONDUIT. WIRING TO NEW 20A DUPLEX RECEPTACLE SHALL BE 2–10 + 10G IN 3/4" RIGID CONDUIT OR SEALTITE. MOUNT RECEPTACLE IN NEMA 3R ALUMINUM JUNCTION BOX WITH WET LOCATION COVER, 6" BELOW FS.




## 1 MARSHALL HS PARTIAL ELECTRICAL RISER

NO SCALE

NOTES:

1. ALL PANELS, TRANSFORMER, SWTCHBOARD AND TRANSFER SWITCH ARE EXISTING. ADD 30/3 CB TO PANEL XXX AND EXTEND 3–10+10N+10G, 3/4"C TO NEW FUSED SWITCH.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

dd

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
THURGOOD MARSHALL HIGH SCHOOL
1220 BUFFALO RUN
MISSOURI CITY, TX 77489

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL FLOOR PLAN & SCHEDULES

dd-E.200

STANTON ENGINEERING GROUP
INFORMATION–ENGINEER (713) 300–6080
TEXAS ENG. FIRM REG. NO. F–01853 | 10810 W. SAM HOUSTON PARKWAY N., SUITE 125, HOUSTON, TX 77064
© 2025 ALL RIGHTS RESERVED

# FBISD BP013 KITCHEN RENOVATIONS ES

| Sheet List Table | |
|---|---|
| Sheet Number | Sheet Title |
| School: ee-Travis HS | |
| ee-A.000 | COVER AND INDEX |
| ee-A.101 | TEMPORARY COOKING LOCATION SITE PLAN |
| ee-E.200 | ELECTRICAL FLOOR PLAN & SCHEDULES |




FORT BEND INDEPENDENT SCHOOL DISTRICT

WILLIAM B. TRAVIS HIGH SCHOOL
11111 HARLEM ROAD, RICHMOND, TX 77406

## ADMINISTRATION

| | |
|---|---|
| DR. MARCELL SMITH | SUPERINTENDENT OF FBISD |
| DR. ANDRIA SCHUR, Ed.D. | CHIEF OF SCHOOLS |

## BOARD OF TRUSTEES

| | |
|---|---|
| KRISTIN K. TASSIN | PRESIDENT |
| RICK GARCIA | VICE PRESIDENT |
| DAVID HAMILTON | SECRETARY |
| ANGIE HANAN | BOARD MEMBER |
| ADAM SCHOOF | BOARD MEMBER |
| DR. SHIRLEY ROSE-GILLIAM | BOARD MEMBER |
| SONYA JONES | BOARD MEMBER |

## PROJECT DESIGN TEAM

PROGRAM MANAGEMENT
FBISD 2023 Bond Team
2323 Texas Parkway
Missouri City, TX 77489
Phone Number: 281-327-5481

ARCHITECT
MWA Architects
11767 Katy Freeway, Suite 430
Houston, Texas 77079
Phone Number: 713-782-8188

FOOD SERVICE
Food Design Professionals
26215 Oak Ridge Drive
The Woodlands, Texas 77380
Phone Number: 281-350-2323

MEP ENGINEERS
Stanton Engineering Group
1300 W. Sam Houston Pkwy South, Suite 121
Houston, Texas 77042
Phone Number: 713-300-9292


STRUCTURAL ENGINEER
Stanley Spurling & Hamilton
3301 Edloe Street, Suite 200
Houston, Texas 77027
Phone Number: 713-776-9433


ISSUED FOR PERMIT AND BIDDING - JULY 18, 2025

C:\Users\Atorres\OneDrive - MWA Architects\Pictures\Screens

APPROX. LOCATION OF NEAREST ELECTRICAL ROOM OR ELECTRICAL PANEL RE: ELEC SHEETS.


PROPOSED TEMPORARY FREEZER LOCATION. CONFFIRM WITH ARCH. BEFORE INSTALLING






NOTES:
1. ALL TO BE GALV. & PAINTED SAFETY YELLOW
2. PROVIDE PLAN & DETAILS IN SUBMITTIDAL FOR LOCATION AND ARCH. APPROVAL
3. MOUNT BOLLARD PLIMB.

## 3 BOLLARD
SCALE: 1- 1/2"=1'-0"




## 2 SCHEMATIC LAYOUT

## 1 SITE PLAN
SCALE: 1"=30'-0"

GENERAL NOTES:
- A. TEMPARAY RENTAL FREEZER, CONTRACTOR FURNISHED & CONTRACTOR INSTALLED. COORDINATE W/ ARCHITECT FOR PROCUREMENT, DELIVERY AND CONNECTION TO POWER CANENSATE DISCHARGE. BASIS OF DESIGN SHALL BE POLAR LEASING DT180 (OTHER MODLES TO BE ACCEPTED WITH ARCHITECT APPROVAL)
- B. CONTRACTOR SHALL FURNISH ELECT. REQUIREMENTS: MIN. 30A, 220V, AS MINIMUM PRICING. SEE ELECTRICAL FOR ADDITIONAL IFORMATION.
- C. LOCATED UNIT WITHIN 100' (APPROX.) OF EXISTING ELECTRICAL ROOM.
- D. INSTALL 1" CONDENSATE DRAIN, CONNECT TO UNIT AS PER PROVIDER INSTRUCTS. KEEP DRAIN LINE AWAY FROM TRAFFIC AREAS. DISCHARGE AS PER PLUMBING DRAWINGS A LOCAL CODES.
- E. PROVIDE EIGHT 4'/ 48" ABV. PAVING BOLT-DOWN TEMPORARY BOLLARDS AROUND UNIT. PATCH HOLES UPON REMOVAL.
- F. SUBMIT LOCATION PLAN IN SUBMITTAL FOR LACATION APPROVAL BY ARCHITECTS.
- G. LOCATE UNIT IN AREA THAT:
  - G.1. HAS BEEN APPROVED INSURMITTAL
  - G.2. WITHIN 100' OF ELECT. CONNECTION
  - G.3. WILL NOT BLOCK WATER FLOW
  - G.4. AWAY FROM EXISTING AREAS SUBJECT TO STANDING WATER

THIS SCHOOL WILL SUPPLY FOOD SERVICES DURING PHASE 3

| PHASING CHART FOR ALL SCHOOLS | | |
|---|---|---|
| PHASE 1 | | |
| **SCHOOLS** | **FREEZER START DATE :** | **FREEZER END DATE :** |
| FIRST COLONY MS | 11/7/2025 | EST. END DATE IS 5/13/2026 BUT ALL SCHOOLS BEING SERVED MUST BE SUBSTATIALLY COMPLETE |
| LAKEVIEW ES | | |
| PHASE 2 | | |
| FIRST COLONY MS | 5/29/2026 | EST. END DATE IS 10/28/2026 BUT ALL SCHOOLS BEING SERVED MUST BE SUBSTATIALLY COMPLETE |
| LAKE OLYMPIA MS | | |
| **PHASE 3** | | |
| MARSHAL HS | 3/19/2027 | EST. END DATE IS 3/19/2027 BUT ALL SCHOOLS BEING SERVED MUST BE SUBSTATIALLY COMPLETE |
| ***TRAVIS HS*** | | |
| DULLES HS | | |

NOTES:
1. FREEZER SHALL STAY IN OPERATION UNTIL ALL SCHOOLS BEING SERVED FROM THIS LOCATION HAVE ACHIVED SUBSTANTIAL COMPLETION

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

ee

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
TRAVIS HIGH SCHOOL
11111 HARLEM RD
RICHMOND, TX 77406

SEAL
REGISTERED ARCHITECT
ANDREW J. TORRES
22651
STATE OF TEXAS
7/15/2025



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

TEMPORARY COOKING LOCATION SITE PLAN

ee-A.101

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings_TEMPORARY COOKING SITES\Travis\HighSchoolSitePlan.dwg Jul 28, 2025 - 4:29pm




## 2 OVERALL FLOOR PLAN - TRAVIS HS

SCALE: 1" = 100'- 0"

## SYMBOL LEGEND

| | |
|---|---|
| ⊕ ⊕ ⊕ ⊕ | SIMPLEX/DUPLEX/QUAD – 5361/2 REC |
| GFI | DUPLEX W/ GFCI PROTECTION–P&S 2097 |
| J | J–BOX |
| | CEILING MOUNTED J–BOX |
| M | MOTOR |
| | HEAVY DUTY, NON–FUSED DISCONNECT. MIN RATING OF CIRCUIT OCPD/VOLTAGE. |
| | ELECTRICAL PANEL |
| | HOMERUN TO CIRCUIT NOTED |
| E | EXISTING DEVICES TO REMAIN |
| R | EXISTING DEVICES TO BE RELOCATED |
| D | EXISTING DEVICES TO BE DEMO/REMOVED |
| REP | EXISTING DEVICES TO BE REPLACED |
| S | INDICATES SURFACE MOUNTED |
| SR | INDICATES SURFACE RACEWAY |
| + | INDICATES ABOVE COUNTER DEVICE |
| + | INDICATES DEVICE AT +30–60" |
| ++ | INDICATES DEVICE AT +80–96" |
| CLG | INDICATES DEVICES MOUNTED IN CEILING |
| WP | INDICATES WEATHERPROOF COVER |
| 3R | INDICATES 3R RATED DEVICE |
| (E)LA–X | CONNECT(ED) TO EXIST CIRCUIT LA–X |
| (D)LA–X | DEMO PORTION OF EXIST CIRCUIT LA–X |
| (N)LA–X | CONNECT(ED) TO NEW CIRCUIT LA–X |

GENERAL ELECTRICAL NOTES:

1. INSTALL SYSTEM IN ACCORDANCE WITH THE NATIONAL ELECTRIC CODE AS ADOPTED BY THE LOCAL AUTHORITY HAVING JURISDICTION INCLUDING ALL AMENDMENTS.
2. PROVIDE CONDUIT FOR ALL DEVICES INSTALLED IN WALLS.
   - 2.A. 3/4"C FOR POWER AND 1"C FOR LOW VOLTAGE/DATA UNLESS NOTED OTHERWISE.
   - 2.B. PROVIDE PROTECTIVE BUSHING ON END OF ALL LOW VOLTAGE CONDUITS.
   - 2.C. ALL ELECTRICAL HOMERUNS SHALL BE IN CONDUIT, MIN 3/4"C.
   - 2.D. USE INSULATED THROAT FITTINGS FOR CONNECTIONS TO HOUSINGS, BOXES, ENCLOSURES, ETC.
   - 2.E. MAX LENGTH FOR FLEX CONDUIT SHALL BE 6FT AND MIN. SIZE SHALL BE 1/2". ALL FLEX CONDUIT SHALL BE LISTED FOR GROUNDING.
3. CONDUIT TYPES:
   - 3.A. INSIDE BUILDINGS: GALVANIZED STEEL EMT.
     - 3.A.A. ALL LOW VOLTAGE CABLING SHALL BE INSTALLED IN CONDUIT IN EXPOSED CEILING AREAS. ROUTE TO NEAREST ACCESSIBLE CEILING WITH CONTINUOUS PATHWAYS TO LOW VOLTAGE SOURCE/DEVICE.
     - 3.A.B. ALL LOW VOLTAGE CABLING SHALL BE INSTALLED IN CONDUIT ABOVE INACCESSIBLE CEILINGS. ROUTE TO NEAREST ACCESSIBLE CEILING WITH CONTINUOUS PATHWAYS TO LOW VOLTAGE SOURCE/DEVICE.
   - 3.B. NO MC CABLE SHALL BE ALLOWED.
   - 3.C. PROVIDE FLEXIBLE CONNECTIONS TO MOTORS, PUMPS, TRANSFORMERS, OR SIMILAR EQUIPMENT.
4. PROVIDE GALVANIZED STEEL, ONE–PIECE CONSTRUCTION, OUTLET BOXES IN ALL CASES SUITABLE FOR INTENDED USE.
   - 4.A. BOXES OUTSIDE SHALL BE STEEL NEMA 3 TYPE.
   - 4.B. PROVIDE CEILING BRACKET TO SUPPORT CEILING MOUNTED DEVICES FROM CEILING TEES.
5. 20 AMP, SINGLE PHASE BRANCH CIRCUITS SERVING LIGHTING AND GENERAL RECEPTACLES MAY BE GROUPED IN A SINGLE RACEWAY PROVIDED A NEUTRAL CONDUCTOR IS INSTALLED FOR EACH CIRCUIT REQUIRING A NEUTRAL.
   - 5.A. DO NOT INSTALL MORE THAN FOUR CURRENT CARRYING CONDUCTORS IN A CONDUIT EXCEPT SIX #12 OR #10 CURRENT CARRYING CONDUCTORS MAY BE INSTALLED IN 3/4" OR LARGER CONDUIT FOR 20A CIRCUITS.
   - 5.B. DO NOT INSTALL 480/277 VOLT CONDUCTORS IN THE SAME CONDUIT WITH 240/208/120 VOLT CONDUCTORS.
   - 5.C. DO NOT COMBINE NEUTRALS. PROVIDE DEDICATED NEUTRALS FOR EACH BRANCH CIRCUIT.
   - 5.D. MULTIPLE DEVICES ON A CIRCUIT SUCH AS RECEPTACLES SHALL BE WIRED WITH A PIGTAIL SO THE DEVICE DOES NOT PREMBE THE CONTINUITY PATH. FEED THROUGH CONNECTIONS FOR GFCI RECEPTACLES SHALL NOT BE USED FOR PROTECTION OF DOWNSTREAM DEVICES.
6. PROVIDE GREEN GROUND WIRE WITH ALL CIRCUITS SIZED PER NEC. BOND GREEN GROUND WIRE TO EACH END OF CONDUIT.
7. PROVIDE J–BOXES, CONDUIT AND SLEEVES THRU ALL FIRE WALLS FOR DATA, TELEPHONE, SECURITY, FIRE ALARM, SOUND SYSTEM, LOW VOLTAGE WIRING, ETC. PROVIDE PROTECTIVE BUSHINGS ON ENDS OF ALL LOW VOLTAGE CONDUITS.
8. PROVIDE PULL BOXES, JUNCTION BOXES, WIRING TROUGHS AND CABINETS WHEREVER REQUIRED FOR PROPER INSTALLATION OF VARIOUS ELECTRICAL SYSTEMS. ALL JUNCTION/PULL BOXES INSTALLED ABOVE ACCESSIBLE CEILINGS SHALL BE MOUNTED SO THAT THE ACCESS PANEL IS NO HIGHER THAN 18" ABOVE THE CEILING.
9. PROVIDE CIRCUIT LABELS IN PERMANENT MARKER ON ALL NEW AND EXISTING J–BOX COVERS UTILIZED IN THE AREA OF RENOVATION.
10. PROVIDE CIRCUIT LABEL ON ALL ABOVE CEILING J–BOXES, EQUIPMENT, ETC. IDENTIFYING THE CIRCUITS CONTAINED/CONNECTED.
11. ALL WIRING SHALL BE 600 VOLT, SOFT DRAWN ANNEALED COPPER, 98% CONDUCTIVITY, CONTINUOUS FROM OUTLET TO OUTLET. MINIMUM WIRE SIZE #12.
    - 11.A. TYPICAL BUILDING WIRE SHALL BE STRANDED TYPE THHN, THWN–2 (WET RATED FOR 90°C), OR XHHW–2. MINIMUM WIRE SIZE SHALL BE #12.
    - 11.B. ALL BUILDING WIRE SHALL BE COLOR CODED WITH THE SAME COLOR CONNECTED TO THE SAME UNGROUNDED PHASE THROUGHOUT THE INSTALLATION MATCHING THE EXISTING BUILDING COLOR CODE SCHEME.
12. WHERE PORTIONS OF INTERIOR RACEWAY SYSTEM ARE EXPOSED TO WIDELY DIFFERENT TEMPERATURES, PROVIDE AIR SEAL PER NEC TO PREVENT CIRCULATION OF AIR FROM WARMER TO COOLER SECTIONS.
13. DRAWINGS, SCHEDULES, NOTES, AND DETAILS ARE INTENDED TO BE COMPLIMENTARY. ANY WORK DESCRIBED IN ANY OF THEM, WILL BE WORK REQUIRED UNDER THIS CONTRACT. WHERE THERE IS A CONFLICT BETWEEN DIFFERENT PORTIONS OF THE DESIGN DOCUMENTS IT SHALL BE CLARIFIED BY RFI, BARRING CLARIFICATION PRIOR TO BIDDING THE MOST EXPENSIVE OPTION SHALL BE INCLUDED AND CLARIFICATION SHALL BE MADE DURING CONSTRUCTION.
14. SHOULD ANY WORK REQUIRED BY THE DRAWINGS AND SPECIFICATIONS BE IN VIOLATION OF ANY FEDERAL, STATE, COUNTY OR CITY LAWS, ORDINANCE OR REGULATION, THOSE LAWS AND REGULATIONS SHALL PREVAIL, AND SHALL BE COMPLIED WITH BY THE CONTRACTOR AS A PART OF THIS WORK WITH NO EXTRA COMPENSATION.
15. ALL MATERIAL MUST BE NEW AND OF GOOD QUALITY AND SHALL BEAR THE STAMP OF APPROVAL OF THE UNDERWRITERS' LABORATORIES, INC. (U.L.).

GENERAL RENOVATION AND REMODELING NOTES:

1. THESE ELECTRICAL DRAWINGS ONLY SHOW SOME EXISTING ELECTRICAL PANELS, DEVICES AND LIGHT FIXTURES IN AREAS OF RENOVATION. ALL OTHER ELECTRICAL EQUIPMENT, WIRING DEVICES, LOW VOLTAGE SYSTEMS, J–BOXES AND CONDUITS SHALL BE LOCATED AND FIELD VERIFIED BY CONTRACTOR.
2. ALL REMOVED DEVICES SHALL BE OFFERED TO THE OWNER AS SALVAGE.
3. RELOCATE CONDUIT AS NECESSARY TO ALLOW NEW OR MODIFIED CONSTRUCTION. RESUPPORT EXISTING CABLING/CONDUIT TO REMAIN TO MEET CURRENTLY ADOPTED CODE REQUIREMENTS. REMOVE ALL ABANDONED CONDUIT AND WIRE. REPAIR EXISTING ELECTRICAL SYSTEMS DAMAGED BY CONSTRUCTION ACTIVITIES.
4. ANY DAMAGE TO EXISTING BUILDING, ELECTRICAL EQUIPMENT, WIRING DEVICES, CONDUIT, WIRING, ETC. SHALL BE REPLACED BY THE CONTRACTOR AT NO COST TO THE OWNER. ALL MATERIALS USED FOR THE REPLACEMENT MUST MEET RENOVATION PROJECT STANDARDS.
5. ELECTRICAL CONTRACTOR SHALL BEGIN FIELD VERIFYING ALL EXISTING BRANCH CIRCUITS FOR EXISTING AREAS TO BE RENOVATED IMMEDIATELY AFTER THE CONTRACT IS ISSUED.
6. ELECTRICAL CONTRACTOR SHALL FIELD VERIFY EXISTING CIRCUITS WITH OWNER'S MAINTENANCE PERSONNEL AFTER NORMAL BUILDING HOURS AS REQUIRED.
7. ANY CIRCUIT OR PARTIAL CIRCUIT TO REMAIN OR BE REUSED SHALL REMAIN ACTIVE.
8. ELECTRICAL CONTRACTOR SHALL INCLUDE COST RELATED TO FIELD VERIFY EXISTING CIRCUITS IN BASE PROPOSAL.
9. FIND AND RECORD ALL EXISTING DEVICES IN CEILINGS, WALLS AND CASEWORK IN AREAS TO BE RENOVATED. PROVIDE A COPY OF THE FIELD VERIFIED DEVICE DRAWINGS TO OWNER PRIOR TO BEGINNING WORK.
10. AT THE END OF THE PROJECT, PROVIDE A NEW TYPEWRITTEN AS–BUILT PANEL SCHEDULE FOR ALL PANELS WITH CIRCUITS ADDED, REMOVED, OR MODIFIED AS PART OF THE PROJECT USING BUILDING ROOM NUMBERS.




## 1 ELECTRICAL RENOVATION PLAN - TRAVIS HS

SCALE: 1/8" = 1'- 0"


### EXIST TO REMAIN

**PANEL ELC** — 80A MCB, 208Y/120V, 3Φ, 4 WIRE — MOUNTING: SURFACE — AVAILABLE FAULT: SCCR & AIC:

| LOAD | DESCRIPTION | ROOM | WIRE | CB | CKT | A B C | CKT | CB | WIRE | DESCRIPTION | ROOM | LOAD |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 500 | FIRE ALARM PANEL | | EXIST | 20/1 | 1 | | 2 | 50/3 | EXIST | REFRIGERATION | | 10000 |
| | SPARE | | | 20/1 | 3 | | 4 | – | EXIST | RACK | | – |
| 500 | TELEPHONE | | EXIST | 20/1 | 5 | | 6 | – | EXIST | – | | – |
| | SPARE | | | 30/1 | 7 | | 8 | 20/1 | | SPARE | | |
| | SPARE | | | 30/1 | 9 | | 10 | 20/1 | | SPARE | | |
| | SPARE | | | 20/1 | 11 | | 12 | 20/1 | | SPARE | | |
| | SPARE | | | 20/1 | 13 | | 14 | 20/1 | | SPARE | | |
| 1000 | AUDITORIUM LIGHTS | | EXIST | 20/1 | 15 | | 16 | 20/1 | | SPARE | | |
| 1000 | AUDITORIUM LIGHTS | | EXIST | 20/1 | 17 | | 18 | 20/1 | | SPARE | | |
| | SPARE | | | 20/1 | 19 | | 20 | | | SPACE | | |
| 500 | CLINIC RECEPTACLE | | EXIST | 20/1 | 21 | | 22 | | | SPACE | | |
| 500 | CLINIC RECEPTACLE | | EXIST | 20/1 | 23 | | 24 | | | SPACE | | |
| NOTE 1 3100 | FOOD STORAGE UNIT | | 3–10 | 30/3 | 25 | | 26 | | | SPACE | | |
| – | – | | +10N+10G | – | 27 | | 28 | | | SPACE | | |
| 180 | NEW DUPLEX REC | | 3/4"C | – | 29 | | 30 | | | SPACE | | |

TOTAL LOAD @ 100% = 17280VA — TOTAL LOAD @ 100% = 48A — TOTAL LOAD @ 125% = 60A

1. PROVIDE NEW CB & WIRE NEW CIRCUIT.




## 3 TRAVIS HS PARTIAL ELECTRICAL RISER

NO SCALE

NOTES:

1. ALL PANELS, TRANSFORMER, SWITCHBOARD AND TRANSFER SWITCH ARE EXISTING. ADD 30/3 CB TO PANEL ELC AND EXTEND 3–10+10N+10G, 3/4"C TO NEW FUSED SWITCH.

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

ee

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
TRAVIS HIGH SCHOOL
11111 HARLEM RD
RICHMOND, TX 77406

SEAL




MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL FLOOR PLAN & SCHEDULES

ee-E.200

STANTON ENGINEERING GROUP
INFO@STANTON–ENG.COM (713) 300–6080
TEXAS ENG. FIRM REG. NO. F–01853 | 1200 N. SAM HOUSTON PKWY E., SUITE 125, HOUSTON, TX 77060
© 2025 ALL RIGHTS RESERVED

# FBISD BP013 KITCHEN RENOVATIONS ES

| Sheet List Table | |
|---|---|
| Sheet Number | Sheet Title |
| School: ff-Dulles HS | |
| ff-A.000 | COVER AND INDEX |
| ff-A.101 | TEMPORARY COOKING LOCATION SITE PLAN |
| ff-E.200 | ELECTRICAL FLOOR PLAN & SCHEDULES |

REGISTERED ARCHITECT
MICHAEL MAGUIRE
22651
STATE OF TEXAS
18 July 2025

ISSUED FOR PERMIT AND BIDDING - JULY 18, 2025

FORT BEND INDEPENDENT SCHOOL DISTRICT

DULLES HIGH SCHOOL
550 DULLES AVE., SUGAR LAND, TX 77478

## ADMINISTRATION

| | |
|---|---|
| DR. MARCELL SMITH | SUPERINTENDENT OF FBISD |
| DR. ANDRIA SCHUR, Ed.D. | CHIEF OF SCHOOLS |

## BOARD OF TRUSTEES

| | |
|---|---|
| KRISTIN K. TASSIN | PRESIDENT |
| RICK GARCIA | VICE PRESIDENT |
| DAVID HAMILTON | SECRETARY |
| ANGIE HANAN | BOARD MEMBER |
| ADAM SCHOOF | BOARD MEMBER |
| DR. SHIRLEY ROSE-GILLIAM | BOARD MEMBER |
| SONYA JONES | BOARD MEMBER |

## PROJECT DESIGN TEAM

PROGRAM MANAGEMENT
FBISD 2023 Bond Team
2323 Texas Parkway
Missouri City, TX 77489
Phone Number: 281-327-5481

ARCHITECT
MWA Architects
11767 Katy Freeway, Suite 430
Houston, Texas 77079
Phone Number: 713-782-8188


FOOD SERVICE
Food Design Professionals
26215 Oak Ridge Drive
The Woodlands, Texas 77380
Phone Number: 281-350-2323

MEP ENGINEERS
Stanton Engineering Group
1300 W. Sam Houston Pkwy South, Suite 121
Houston, Texas 77042
Phone Number: 713-300-9292


STRUCTURAL ENGINEER
Stanley Spurling & Hamilton
3301 Edloe Street, Suite 200
Houston, Texas 77027
Phone Number: 713-776-9433

APPROX. LOCATION OF NEAREST ELECTRICAL ROOM OR ELECTRICAL PANEL RE: ELEC SHEETS.

PROPOSED TEMPORARY FREEZER LOCATION. CONFFIRM WITH ARCH. BEFORE INSTALLING




2 SCHEMATIC LAYOUT




NOTES:
1. ALL TO BE GALV. & PAINTED SAFETY YELLOW
2. PROVIDE PLAN & DETAILS IN SUBMITIDAL FOR LOCATION AND ARCH. APPROVAL
3. MOUNT BOLLARD PLIMB.

3 BOLLARD
SCALE: 1- 1/2"=1'-0"



GENERAL NOTES:
- A. TEMPARAY RENTAL FREEZER, CONTRACTOR FURNISHED & CONTRACTOR INSTALLED. COORDINATE W/ ARCHITECT FOR PROCUREMENT, DELIVERY AND CONNECTION TO POWER CANENSATE DISCHARGE. BASIS OF DESIGN SHALL BE POLAR (LEASING DT180 (OTHER MODLES TO BE ACCEPTED WITH ARCHITECT APPROVAL)
- B. CONTRACTOR SHALL FURNISH ELECT. REQUIREMENTS: MIN. 30A, 220V, AS MINIMUM PRICING. SEE ELECTRICAL FOR ADDITIONAL IFORMATION.
- C. LOCATED UNIT WITHIN 100' (APPROX.) OF EXISTING ELECTRICAL ROOM.
- D. INSTALL 1" CONDENSATE DRAIN, CONNECT TO UNIT AS PER PROVIDER INSTRUCTS. KEEP DRAIN LINE AWAY FROM TRAFFIC AREAS. DISCHARGE AS PER PLUMBING DRAWINGS A LOCAL CODES.
- E. PROVIDE EIGHT 4'/ 48" ABV. PAVING BOLT-DOWN TEMPORARY BOLLARDS AROUND UNIT. PATCH HOLES UPON REMOVAL.
- F. SUBMIT LOCATION PLAN IN SUBMITTAL FOR LACATION APPROVAL BY ARCHITECTS.
- G. LOCATE UNIT IN AREA THAT:
  - G.1. HAS BEEN APPROVED INSURMITTAL
  - G.2. WITHIN 100' OF ELECT. CONNECTION
  - G.3. WILL NOT BLOCK WATER FLOW
  - G.4. AWAY FROM EXISTING AREAS SUBJECT TO STANDING WATER

1 SITE PLAN
SCALE: 1"=30'-0"

THIS SCHOOL WILL SUPPLY FOOD SERVICES DURING PHASE 3

| PHASING CHART FOR ALL SCHOOLS | | |
|---|---|---|
| PHASE 1 | | |
| **SCHOOLS** | **FREEZER START DATE :** | **FREEZER END DATE :** |
| FIRST COLONY MS<br>LAKEVIEW ES | 11/7/2025 | EST. END DATE IS 5/13/2026 BUT ALL SCHOOLS BEING SERVED MUST BE SUBSTATIALLY COMPLETE |
| PHASE 2 | | |
| FIRST COLONY MS<br>LAKE OLYMPIA MS | 5/29/2026 | EST. END DATE IS 10/28/2026 BUT ALL SCHOOLS BEING SERVED MUST BE SUBSTATIALLY COMPLETE |
| **PHASE 3** | | |
| MARSHAL HS<br>TRAVIS HS<br>***DULLES HS*** | 3/19/2027 | EST. END DATE IS 3/19/2027 BUT ALL SCHOOLS BEING SERVED MUST BE SUBSTATIALLY COMPLETE |

NOTES:
1. FREEZER SHALL STAY IN OPERATION UNTIL ALL SCHOOLS BEING SERVED FROM THIS LOCATION HAVE ACHIVED SUBSTANTIAL COMPLETION

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

ff

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT
DULLES HIGH SCHOOL
550 DULLES AVE
SUGAR LAND, TX 77478

SEAL
REGISTERED ARCHITECT
ROBERT A. MEYER
22651
STATE OF TEXAS
7/15/2025



MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079


PROJ. NO.: 23-25
DATE: 07/18/25
ISSUED FOR BIDDING AND PERMITTING

TEMPORARY COOKING LOCATION SITE PLAN

ff-A.101

F:\2023\23-25 FBISD Package 13 Kitchen Renovations\DWGS\Drawings_TEMPORARY COOKING SITES\DullesHighSchoolSitePlan.dwg Jul 28, 2025 - 4:31pm




## 2 OVERALL FLOOR PLAN - DULLES HS

SCALE: 1" = 100'- 0"

## SYMBOL LEGEND


| | |
|---|---|
| ⓓⓓⓓ | SIMPLEX/DUPLEX/QUAD – 5361/2 REC |
| GFI | DUPLEX W/ GFCI PROTECTION-P&S 2097 |
| J | J-BOX |
| | CEILING MOUNTED J-BOX |
| M | MOTOR |
| | HEAVY DUTY, NON-FUSED DISCONNECT. MIN RATING OF CIRCUIT OCPD/VOLTAGE. |
| | ELECTRICAL PANEL |
| | HOMERUN TO CIRCUIT NOTED |
| E | EXISTING DEVICES TO REMAIN |
| R | EXISTING DEVICES TO BE RELOCATED |
| D | EXISTING DEVICES TO BE DEMO/REMOVED |
| RDP | EXISTING DEVICES TO BE REPLACED |
| S | INDICATES SURFACE MOUNTED |
| SR | INDICATES SURFACE RACEWAY |
| ^ | INDICATES ABOVE COUNTER DEVICE |
| + | INDICATES DEVICE AT +30-60" |
| ++ | INDICATES DEVICE AT +80-96" |
| CLG | INDICATES DEVICES MOUNTED IN CEILING |
| WP | INDICATES WEATHERPROOF COVER |
| 3R | INDICATES 3R RATED DEVICE |
| (E)LA-X | CONNECT(ED) TO EXIST CIRCUIT LA-X |
| (D)LA-X | DEMO PORTION OF EXIST CIRCUIT LA-X |
| (N)LA-X | CONNECT(ED) TO NEW CIRCUIT LA-X |

GENERAL ELECTRICAL NOTES:

1. INSTALL SYSTEM IN ACCORDANCE WITH THE NATIONAL ELECTRIC CODE AS ADOPTED BY THE LOCAL AUTHORITY HAVING JURISDICTION INCLUDING ALL AMENDMENTS.
2. PROVIDE CONDUIT FOR ALL DEVICES INSTALLED IN WALLS.
   - 2.A. 3/4"C FOR POWER AND 1"C FOR LOW VOLTAGE/DATA UNLESS NOTED OTHERWISE.
   - 2.B. PROVIDE PROTECTIVE BUSHING ON END OF ALL LOW VOLTAGE CONDUITS.
   - 2.C. ALL ELECTRICAL HOMERUNS SHALL BE IN CONDUIT, MIN 3/4"C.
   - 2.D. USE INSULATED THROAT FITTINGS FOR CONNECTIONS TO HOUSINGS, BOXES, ENCLOSURES, ETC.
   - 2.E. MAX LENGTH FOR FLEX CONDUIT SHALL BE 6FT AND MIN. SIZE SHALL BE 1/2". ALL FLEX CONDUIT SHALL BE LISTED FOR GROUNDING.
3. CONDUIT TYPES:
   - 3.A. INSIDE BUILDINGS: GALVANIZED STEEL EMT.
     - 3.A.A. ALL LOW VOLTAGE CABLING SHALL BE INSTALLED IN CONDUIT IN EXPOSED CEILING AREAS. ROUTE TO NEAREST ACCESSIBLE CEILING WITH CONTINUOUS PATHWAYS TO LOW VOLTAGE SOURCE/DEVICE.
     - 3.A.B. ALL LOW VOLTAGE CABLING SHALL BE INSTALLED IN CONDUIT ABOVE INACCESSIBLE CEILINGS. ROUTE TO NEAREST ACCESSIBLE CEILING WITH CONTINUOUS PATHWAYS TO LOW VOLTAGE SOURCE/DEVICE.
   - 3.B. NO MC CABLE SHALL BE ALLOWED.
   - 3.C. PROVIDE FLEXIBLE CONNECTIONS TO MOTORS, PUMPS, TRANSFORMERS, OR SIMILAR EQUIPMENT.
4. PROVIDE GALVANIZED STEEL, ONE-PIECE CONSTRUCTION, OUTLET BOXES IN ALL CASES SUITABLE FOR INTENDED USE.
   - 4.A. BOXES OUTSIDE SHALL BE STEEL NEMA 3 TYPE.
   - 4.B. PROVIDE CEILING BRACKET TO SUPPORT CEILING MOUNTED DEVICES FROM CEILING TEES.
5. 20 AMP, SINGLE PHASE BRANCH CIRCUITS SERVING LIGHTING AND GENERAL RECEPTACLES MAY BE GROUPED IN A SINGLE RACEWAY PROVIDED A NEUTRAL CONDUCTOR IS INSTALLED FOR EACH CIRCUIT REQUIRING A NEUTRAL.
   - 5.A. DO NOT INSTALL MORE THAN FOUR CURRENT CARRYING CONDUCTORS IN A CONDUIT EXCEPT SIX #12 OR #10 CURRENT CARRYING CONDUCTORS MAY BE INSTALLED IN 3/4" OR LARGER CONDUIT FOR 20A CIRCUITS.
   - 5.B. DO NOT INSTALL 480/277 VOLT CONDUCTORS IN THE SAME CONDUIT WITH 240/208/120 VOLT CONDUCTORS.
   - 5.C. DO NOT COMBINE NEUTRALS. PROVIDE DEDICATED NEUTRALS FOR EACH BRANCH CIRCUIT.
   - 5.D. MULTIPLE DEVICES ON A CIRCUIT SUCH AS RECEPTACLES SHALL BE WIRED WITH A PIGTAIL SO THE DEVICE DOES NOT PREMBE THE CONTINUITY PATH. FEED THROUGH CONNECTIONS FOR GFCI RECEPTACLES SHALL NOT BE USED FOR PROTECTION OF DOWNSTREAM DEVICES.
6. PROVIDE GREEN GROUND WIRE WITH ALL CIRCUITS SIZED PER NEC. BOND GREEN GROUND WIRE TO EACH END OF CONDUIT.
7. PROVIDE J-BOXES, CONDUIT AND SLEEVES THRU ALL FIRE WALLS FOR DATA, TELEPHONE, SECURITY, FIRE ALARM, SOUND SYSTEM, LOW VOLTAGE WIRING, ETC. PROVIDE PROTECTIVE BUSHINGS ON ENDS OF ALL LOW VOLTAGE CONDUITS.
8. PROVIDE PULL BOXES, JUNCTION BOXES, WIRING TROUGHS AND CABINETS WHEREVER REQUIRED FOR PROPER INSTALLATION OF VARIOUS ELECTRICAL SYSTEMS. ALL JUNCTION/PULL BOXES INSTALLED ABOVE ACCESSIBLE CEILINGS SHALL BE MOUNTED SO THAT THE ACCESS PANEL IS NO HIGHER THAN 18" ABOVE THE CEILING.
9. PROVIDE CIRCUIT LABELS IN PERMANENT MARKER ON ALL NEW AND EXISTING J-BOX COVERS UTILIZED IN THE AREA OF RENOVATION.
10. PROVIDE CIRCUIT LABEL ON ALL ABOVE CEILING J-BOXES, EQUIPMENT, ETC. IDENTIFYING THE CIRCUITS CONTAINED/CONNECTED.
11. ALL WIRING SHALL BE 600 VOLT, SOFT DRAWN ANNEALED COPPER, 98% CONDUCTIVITY, CONTINUOUS FROM OUTLET TO OUTLET. MINIMUM WIRE SIZE #12.
    - 11.A. TYPICAL BUILDING WIRE SHALL BE STRANDED TYPE THHN, THWN-2 (WET RATED FOR 90°C), OR XHHW-2. MINIMUM WIRE SIZE SHALL BE #12.
    - 11.B. ALL BUILDING WIRE SHALL BE COLOR CODED WITH THE SAME COLOR CONNECTED TO THE SAME UNGROUNDED PHASE THROUGHOUT THE INSTALLATION MATCHING THE EXISTING BUILDING COLOR CODE SCHEME.
12. WHERE PORTIONS OF INTERIOR RACEWAY SYSTEM ARE EXPOSED TO WIDELY DIFFERENT TEMPERATURES, PROVIDE AIR SEAL PER NEC TO PREVENT CIRCULATION OF AIR FROM WARMER TO COOLER SECTIONS.
13. DRAWINGS, SCHEDULES, NOTES, AND DETAILS ARE INTENDED TO BE COMPLIMENTARY. ANY WORK DESCRIBED IN ANY OF THEM, WILL BE WORK REQUIRED UNDER THIS CONTRACT. WHERE THERE IS A CONFLICT BETWEEN DIFFERENT PORTIONS OF THE DESIGN DOCUMENTS IT SHALL BE CLARIFIED BY RFI, BARRING CLARIFICATION PRIOR TO BIDDING THE MOST EXPENSIVE OPTION SHALL BE INCLUDED AND CLARIFICATION SHALL BE MADE DURING CONSTRUCTION.
14. SHOULD ANY WORK REQUIRED BY THE DRAWINGS AND SPECIFICATIONS BE IN VIOLATION OF ANY FEDERAL, STATE, COUNTY OR CITY LAWS, ORDINANCE OR REGULATION, THOSE LAWS AND REGULATIONS SHALL PREVAIL, AND SHALL BE COMPLIED WITH BY THE CONTRACTOR AS A PART OF THIS WORK WITH NO EXTRA COMPENSATION.
15. ALL MATERIAL MUST BE NEW AND OF GOOD QUALITY AND SHALL BEAR THE STAMP OF APPROVAL OF THE UNDERWRITERS' LABORATORIES, INC. (U.L.).

GENERAL RENOVATION AND REMODELING NOTES:

1. THESE ELECTRICAL DRAWINGS ONLY SHOW SOME EXISTING ELECTRICAL PANELS, DEVICES AND LIGHT FIXTURES IN AREAS OF RENOVATION. ALL OTHER ELECTRICAL EQUIPMENT, WIRING DEVICES, LOW VOLTAGE SYSTEMS, J-BOXES AND CONDUITS SHALL BE LOCATED AND FIELD VERIFIED BY CONTRACTOR.
2. ALL REMOVED DEVICES SHALL BE OFFERED TO THE OWNER AS SALVAGE.
3. RELOCATE CONDUIT AS NECESSARY TO ALLOW NEW OR MODIFIED CONSTRUCTION. RESUPPORT EXISTING CABLING/CONDUIT TO REMAIN TO MEET CURRENTLY ADOPTED CODE REQUIREMENTS. REMOVE ALL ABANDONED CONDUIT AND WIRE. REPAIR EXISTING ELECTRICAL SYSTEMS DAMAGED BY CONSTRUCTION ACTIVITIES.
4. ANY DAMAGE TO EXISTING BUILDING, ELECTRICAL EQUIPMENT, WIRING DEVICES, CONDUIT, WIRING, ETC. SHALL BE REPLACED BY THE CONTRACTOR AT NO COST TO THE OWNER. ALL MATERIALS USED FOR THE REPLACEMENT MUST MEET RENOVATION PROJECT STANDARDS.
5. ELECTRICAL CONTRACTOR SHALL BEGIN FIELD VERIFYING ALL EXISTING BRANCH CIRCUITS FOR EXISTING AREAS TO BE RENOVATED IMMEDIATELY AFTER THE CONTRACT IS ISSUED.
6. ELECTRICAL CONTRACTOR SHALL FIELD VERIFY EXISTING CIRCUITS WITH OWNER'S MAINTENANCE PERSONNEL AFTER NORMAL BUILDING HOURS AS REQUIRED.
7. ANY CIRCUIT OR PARTIAL CIRCUIT TO REMAIN OR BE REUSED SHALL REMAIN ACTIVE.
8. ELECTRICAL CONTRACTOR SHALL INCLUDE COST RELATED TO FIELD VERIFY EXISTING CIRCUITS IN BASE PROPOSAL.
9. FIND AND RECORD ALL EXISTING DEVICES IN CEILINGS, WALLS AND CASEWORK IN AREAS TO BE RENOVATED. PROVIDE A COPY OF THE FIELD VERIFIED DEVICE DRAWINGS TO OWNER PRIOR TO BEGINNING WORK.
10. AT THE END OF THE PROJECT, PROVIDE A NEW TYPEWRITTEN AS-BUILT PANEL SCHEDULE FOR ALL PANELS WITH CIRCUITS ADDED, REMOVED, OR MODIFIED AS PART OF THE PROJECT USING BUILDING ROOM NUMBERS.




## 1 ELECTRICAL RENOVATION PLAN - DULLES HS

SCALE: 1/8" = 1'- 0"

## EXISTING TO REMAIN


**PANEL LQ-2** — 225A MLO, 208Y/120V, 3ϕ, 4 WIRE — MOUNTING: RECESSED — AVAILABLE FAULT: SCCR & AIC:

| LOAD | DESCRIPTION | WIRE | CB | CKT | A | B | C | CKT | CB | WIRE | DESCRIPTION | LOAD |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 500 | EXIST CIRCUIT | EXIST | 20/1 | 1 | | | | 2 | 70/3 | EXIST | REFRIGERATION RACK | 10000 |
| 500 | EXIST CIRCUIT | EXIST | 20/1 | 3 | | | | 4 | – | – | – | – |
| 800 | REC'S AND HOOD LIGHT | EXIST | 20/1 | 5 | | | | 6 | – | – | – | – |
| 800 | REC'S AND HOOD LIGHT | EXIST | 20/1 | 7 | | | | 8 | 20/3 | EXIST | DISPOSER | 800 |
| 540 | RECEPTACLES | EXIST | 20/1 | 9 | | | | 10 | – | – | – | – |
| 300 | FREEZE/COOLER LTS | EXIST | 20/1 | 11 | | | | 12 | – | – | – | – |
| 300 | FREEZER/COOLER LTS | EXIST | 20/1 | 13 | | | | 14 | 20/1 | EXIST | EXIST CKT | 500 |
| 300 | FREEZER/COOLER LTS | EXIST | 20/1 | 15 | | | | 16 | 30/3 | EXIST | EXIST CKT | 1200 |
| 3000 | DRYER | EXIST | 40/2 | 17 | | | | 18 | – | – | – | – |
| – | – | – | – | 19 | | | | 20 | – | – | – | – |
| 800 | WASHING MACHINE | EXIST | 20/1 | 21 | | | | 22 | 20/1 | EXIST | EXIST CKT | 500 |
| 1200 | ICE MAKER | EXIST | 30/2 | 23 | | | | 24 | 20/1 | EXIST | EXIST CKT | 500 |
| – | – | – | – | 25 | | | | 26 | 20/1 | EXIST | EXIST CKT | 500 |
| 100 | CLOCK | EXIST | 20/1 | 27 | | | | 28 | 20/1 | EXIST | EXIST CKT | 500 |
| 540 | MANAGERS OFFICE RECS | EXIST | 20/1 | 29 | | | | 30 | 20/1 | EXIST | VENDING MACHINE | 500 |
| 500 | PREP RM FLOOR REC | EXIST | 20/1 | 31 | | | | 32 | 20/1 | EXIST | VENDING MACHINE | 500 |
| | SPARE | | 20/1 | 33 | | | | 34 | 20/1 | EXIST | VENDING MACHINE | 500 |
| | SPARE | | 20/1 | 35 | | | | 36 | 20/1 | EXIST | VENDING MACHINE | 500 |
| | SPARE | | 20/1 | 37 | | | | 38 | 20/1 | EXIST | VENDING MACHINE | 500 |
| | SPARE | | 20/1 | 39 | | | | 40 | 20/1 | EXIST | VENDING MACHINE | 500 |
| | SPARE | | 20/1 | 41 | | | | 42 | 20/1 | EXIST | VENDING MACHINE | 500 |

**2ND SECTION** — 225A MLO, 208Y/120V, 3ϕ, 4 WIRE — MOUNTING: RECESSED — AVAILABLE FAULT: SCCR & AIC:

| LOAD | DESCRIPTION | WIRE | CB | CKT | A | B | C | CKT | CB | WIRE | DESCRIPTION | LOAD |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 8000 | HOT FOOD UNIT | EXIST | 35/3 | 1 | | | | 2 | 35/3 | EXIST | HOT FOOD UNIT | 8000 |
| – | – | – | – | 3 | | | | 4 | – | – | – | – |
| – | – | – | – | 5 | | | | 6 | – | – | – | – |
| | EXIST SPARE | EXIST | 20/1 | 7 | | | | 8 | 20/1 | EXIST | EXIST SPARE | |
| | EXIST SPARE | EXIST | 20/1 | 9 | | | | 10 | 20/1 | EXIST | ROLL UP DOOR | 500 |
| 500 | E2 REC | EXIST | 20/1 | 11 | | | | 12 | 20/1 | EXIST | ROLL UP DOOR | 500 |
| | SPACE | | | 13 | | | | 14 | 20/1 | EXIST | ROLL UP DOOR | 500 |
| 500 | HWCP-2 | EXIST | 20/1 | 15 | | | | 16 | 20/1 | EXIST | ROLL UP DOOR | 500 |
| 500 | HWCP-1 | EXIST | 20/1 | 17 | | | | 18 | 20/1 | EXIST | ROLL UP DOOR | 500 |
| 500 | GWH-2 | EXIST | 20/1 | 19 | | | | 20 | 20/1 | EXIST | ROLL UP DOOR | 500 |
| 400 | MENU BOARD | EXIST | 20/1 | 21 | | | | 22 | 20/1 | EXIST | ROLL UP DOOR | 500 |
| | SPACE | | | 23 | | | | 24 | | | SPACE | |
| | EXIST SPARE | EXIST | 20/1 | 25 | | | | 26 | | | SPACE | |
| | EXIST SPARE | EXIST | 20/1 | 27 | | | | 28 | | | SPACE | |
| 740 | REC'S & MENU BOARD | EXIST | 20/1 | 29 | | | | 30 | | | SPACE | |
| | SPACE | | | 31 | | | | 32 | | | SPACE | |
| | SPACE | | | 33 | | | | 34 | | | SPACE | |
| | SPACE | | | 35 | | | | 36 | | | SPACE | |
| NOTE 1 3100 | FOOD STORAGE UNIT | 3–10 | 30/3 | 37 | | | | 38 | | | SPACE | |
| – | – | +10N+10G | – | 39 | | | | 40 | | | SPACE | |
| 180 | DUPLEX REC | 3/4"C | – | 41 | | | | 42 | | | SPACE | |
| TOTAL LOAD @ 100% = 54100VA | | | | TOTAL LOAD @ 100% = 150A | | | | | | | TOTAL LOAD @ 125% = 188A | |

1. PROVIDE NEW CB & WIRE NEW CIRCUIT.




## 3 DULLES HS PARTIAL ELECTRICAL RISER

NO SCALE

NOTES:

1. ALL PANELS, TRANSFORMER AND SWITCHBOARD ARE EXISTING. ADD 30/3 CB TO PANEL LQ2 AND EXTEND 3-10+10N+10G, 3/4"C TO NEW FUSED SWITCH.
2. THERE IS NO AVAILABLE EMERGENCY POWER AT THIS SCHOOL

ISSUE:

| | |
|---|---|
| 12/05/2024 | DD PACKAGE |
| 03/11/2025 | 50% CD PKG. |
| 05/23/2025 | 90% CD PKG. |
| 07/18/2025 | ISSUED FOR BIDDING AND PERMITTING |

FBISD BP 013 KITCHEN RENOVATIONS
FORT BEND INDEPENDENT SCHOOL DISTRICT

DULLES HIGH SCHOOL
550 DULLES AVE
SUGAR LAND, TX 77478

SEAL

STATE OF TEXAS
GEORGE L. STANTON
38582
REGISTERED
PROFESSIONAL ENGINEER
07.18.2025

MWA ARCHITECTS
ARCHITECTS AND PLANNING CONSULTANTS
11767 KATY FREEWAY, SUITE 430
HOUSTON, TEXAS 77079

PROJ. NO.: 23-25
DATE: 07/18/2025
ISSUED FOR BIDDING AND PERMITTING

ELECTRICAL FLOOR PLAN & SCHEDULES

ff-E.200

STANTON ENGINEERING GROUP
INFORMATION - (346)254-7000 (713) 300-4050
TEXAS ENGINEERING FIRM REGISTRATION NO. F-01833
1300 W. SAM HOUSTON PARKWAY S., SUITE 121, HOUSTON, TX 77042
ALL RIGHTS RESERVED